**Pacific Northwest
National Laboratory**

Operated by Battelle for the
U.S. Department of Energy

RECEIVED

MAR 31 1999

051

**Borehole Data Package for 1998
Wells Installed at Single-Shell Tank
Waste Management Area TX-TY**

D. G. Horton
F. N. Hodges

March 1999

Prepared for the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or Battelle Memorial Institute.

PACIFIC NORTHWEST NATIONAL LABORATORY

operated by

BATTELLE

for the

UNITED STATES DEPARTMENT OF ENERGY

under Contract DE-AC06-76RLO 1830

Printed in the United States of America

**Available to DOE and DOE contractors from the
Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831;
prices available from (615) 576-8401.**

**Available to the public from the National Technical Information Service,
U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161**

This document was printed on recycled paper.

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, make any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

**Borehole Data Package for 1998 Wells
Installed at Single-Shell Tank Waste
Management Area TX-TY**

D. G. Horton
F. N. Hodges

March 1999

Prepared for
the U.S. Department of Energy
under Contract DE-AC06-76RLO 1830

Pacific Northwest National Laboratory
Richland, Washington 99352

Acknowledgment

The analyses of particle size distribution, moisture content, pH, electrical conductivity, cation exchange capacity, and alkalinity were done in the Applied Geology and Geochemistry Group laboratory, Pacific Northwest National Laboratory, Richland, Washington. The work was supervised by Jeff Serne. His laboratory also produced the 1:1 water:sediment extracts for major cation and anion analyses. The cation analyses were done at the Chemical Analysis Laboratory at the University of Georgia in Athens, Georgia. The anion analyses were done in the Pacific Northwest National Laboratory interfacial geochemistry laboratory. Mr. Serne provided interpretations of all the physical and chemical data from sediment samples, and those interpretations are incorporated into this report. His contribution is very much appreciated.

Contents

Acknowledgment.....	iii
1.0 Introduction.....	1
2.0 Well 299-W10-26	1
2.1 Drilling and Sampling.....	1
2.2 Well Completion.....	3
2.3 Well Development and Pump Installation	4
3.0 Well 299-W14-13	4
3.1 Drilling and Sampling.....	4
3.2 Well Completion.....	5
3.3 Well Development and Pump Installation	6
4.0 Well 299-W14-14	6
4.1 Drilling and Sampling.....	6
4.2 Well Completion.....	7
4.3 Well Development and Pump Installation	8
5.0 Well 299-W15-40	8
5.1 Drilling and Sampling.....	8
5.2 Well Completion.....	9
5.3 Well Development and Pump Installation	9
6.0 References.....	10
Appendix A - Well Construction and Completion Documentation.....	A.1
Appendix B - Physical and Chemical Properties Data	B.1
Appendix C - Geophysical Logs	C.1
Appendix D - Groundwater Analytical Data	D.1

Figure

1	Map of Waste Management Area TX-TY and Locations of Wells in the Groundwater Monitoring Network	2
---	---	---

Table

1	Survey Data for New Wells at Waste Management Area TX-TY	4
---	--	---

1.0 Introduction

Four new Resource Conservation and Recovery Act (RCRA) groundwater monitoring wells were installed at the single-shell tank farm Waste Management Area (WMA) TX-TY during August through November of 1998 in fulfillment of Tri-Party Agreement (Ecology 1996) milestone M-24-38. The wells are 299-W10-26, 299-W14-13, 299-W14-14, and 299-W15-40. Well 299-W10-26 is located outside the east fence of the TY tank farm and replaces downgradient well 299-W10-18; well 299-W14-13 is located along the east fence near the northeast corner of the TX tank farm and replaces downgradient well 299-W14-12; well 299-W14-14 is located outside the east fence in the south half of the TX tank farm and is a new downgradient well; and well 299-W15-40 is located on the west side of the TX tank farm and is a new upgradient well. The locations of all wells in the monitoring network are shown on Figure 1.

The groundwater monitoring plan for WMA TX-TY (Caggiano and Goodwin 1991) describes the hydrogeology of the 200 West Area and WMA TX-TY. An Interim Change Notice to the groundwater monitoring plan provides justification for the new wells. The new wells were constructed to the specifications and requirements described in Washington Administrative Code (WAC) 173-160 and WAC 173-303.

This document compiles information on the drilling and construction, well development, pump installation, groundwater sampling, and sediment testing applicable to wells 299-W10-26, 299-W14-13, 299-W14-14, and 299-W15-40. Appendix A contains the geologist's log, the Well Construction Summary Report, and Well Summary Sheet (as-built diagram); Appendix B contains results of laboratory analyses of particle size distribution, pH, conductivity, calcium carbonate content, major cation and anion concentrations from 1:1 water:sediment extracts, and moisture content; Appendix C contains geophysical logs; and Appendix D contains the analytical results from groundwater samples obtained during well construction. Aquifer tests (slug tests) were performed on all the new wells after well completions. Results of the aquifer tests will be reported elsewhere. Additional documentation concerning well construction is on file with Bechtel Hanford, Inc., Richland, Washington.

English units are used in this report because they are used by drillers to measure and report depths and well construction details. The conversion is made by multiplying feet by 0.3048 to obtain meters or multiplying inches by 2.54 to obtain centimeters.

2.0 Well 299-W10-26

2.1 Drilling and Sampling

Well 299-W10-26 was drilled using an air rotary rig. The well was drilled to a total depth of 262 ft below ground surface (bgs) during August 1998. Temporary 8 5/8-in.-outside-diameter, carbon steel casing was used from ground surface to total depth. Static water level was 216.8 ft bgs on August 25, 1998.

~/home/d3j394/arcwork/tfarmextend.map-0925-98

Figure 1. Map of Waste Management Area TX-TY and Locations of Wells in the Groundwater Monitoring Network

Sediments encountered during drilling were predominantly sand, gravelly sand, sandy gravel, and gravel of the Hanford formation from the surface to about 89 ft bgs; Plio-Pleistocene silty sands and sands with varying caliche content from 89 to ~127 ft bgs (depths based on geophysical log correlation); and sands, silty sands, and silty, sandy gravels of the Ringold Formation from 127 to 262 ft bgs (total depth). A geologist's log is included in Appendix A.

Grab samples for analysis of particle size distribution, pH, conductivity, major cations and anions, and moisture content were collected at 25 and 69 ft bgs. The shallower sample is a coarse gravel and the deeper sample is a sand. The sample from 25 ft depth has a slightly higher water extract pH, and the sample from 69 ft depth has a higher electrical conductivity.

The analysis of 1:1 water:sediment extracts show that the 25-ft sample is enriched in sodium compared to the 69-ft sample and that the 69-ft sample may be contaminated with nitrate. All laboratory results are in Appendix B. Sediment samples also were collected for geologic description and archive at approximately 5-ft intervals throughout the borehole.

The borehole and drill cuttings were monitored regularly for organic vapors and radionuclide contaminants. No contamination was found.

The well was logged using high resolution, spectral gamma-ray instrumentation on August 22, 1998. No man-made radionuclides were detected. The geophysical logs are in Appendix C.

2.2 Well Completion

The permanent casing and screen were installed in well 299-W10-26 in August 1998. A 4-in.-inner-diameter, stainless steel, wire wrap (0.01 in. slot) screen was set from 252.13 to 217.04 ft bgs. The permanent casing is 4-in.-inner-diameter, stainless steel from 217.04 ft bgs to 2.1 ft above ground surface. The bottom of the screen has a 4-in. end cap.

The sand pack is 20 to 40 mesh silica sand from 262.0 to 211.0 ft bgs. The annular seal is 0.25 in. bentonite pellets from 211.0 to 204.5 ft bgs; 3/8 in. bentonite chips from 204.5 to 10.5 ft bgs; and Portland cement 10.5 ft to the surface. A 4 ft by 4 ft by 6 in. concrete pad was placed around the well at the surface. A protective casing with locking cap, four protective steel posts, and a brass marker stamped with the well number were set into the concrete. The Well Construction Summary Report and the Well Summary Sheet (as-built) are included in Appendix A.

Well 299-W10-26 has an asymmetrical well completion. The outer, protective casing was placed against one side of the permanent casing. This required alteration of the pump landing plate.

The vertical and horizontal coordinates of the well were surveyed in December 1998. The horizontal position of the well was determined by global positioning system observations referenced to horizontal control stations established by the U.S. Army Corps of Engineers. The coordinates are Washington

Coordinate System, South Zone, NAD83/91 datum. Vertical datum is NAVD 1988 and is based on existing bench marks established by the U.S. Army Corps of Engineers. Survey data are included in Table 1.

Table 1. Survey Data for New Wells at Waste Management Area TX-TY

Well Name	Easting (m)	Northing (m)	Elevation (m)	
299-W10-26	566,843.3955	136,400.594	205.4515	Center of Casing
	566,843.397	136,400.927	204.6729	"X" on Casing Brass Cap
299-W14-13	566,901.7175	136,282.3745	205.1050	Center of Casing
	566,901.721	136,282.708	204.3462	"X" on Casing Brass Cap
299-W14-14	566,898.386	136,181.048	205.4321	Center of Casing
	566,898.3875	136,181.3305	204.6213	"X" on Casing Brass Cap
299-W15-40	566,652.5015	136,204.9705	205.8242	Center of Casing
	566,652.494	136,205.292	205.0601	"X" on Casing Brass Cap

2.3 Well Development and Pump Installation

Well 299-W10-26 was developed on September 17, 1998. A temporary, 2 hp submersible pump was used to remove approximately 700 gal of formation water from the well at 9 gal/min. The final turbidity was 3.15 NTU.

A dedicated Hydrostar sampling pump was installed in well 299-W10-26 on October 20, 1998. The sampling pump intake is at 231.5 ft depth relative to the brass cap (see Table 1) or about 14.7 ft below the water table.

3.0 Well 299-W14-13

3.1 Drilling and Sampling

Well 299-W14-13 was drilled using an air rotary rig to a total depth of 262 ft bgs during August 1998. Temporary 8 5/8-in.-outside-diameter, carbon steel casing was used from ground surface to total depth. Static water level was 215.8 ft bgs on August 31, 1998.

Sediments encountered during drilling were predominantly sand with some sandy gravel of the Hanford formation from the surface to about 88 ft bgs; Plio-Pleistocene sand and sandy gravel with some caliche from about 88 to 126 ft bgs (depths based on geophysical log correlation); and Ringold Formation Unit E sandy gravel from 126 ft to total depth (262 ft bgs). The geologist's log is in Appendix A.

Grab samples were collected at 25 ft and 69 ft bgs for measurement of particle size distribution, pH, conductivity, moisture content, and major cation and anion concentrations. The shallower sample is coarse gravel and the deeper sample is sand. The sand has a slightly higher electrical conductivity and a higher moisture content. Analytical data are in Appendix B. Sediment samples also were collected for geologic description and archive at approximately 5-ft intervals throughout the borehole.

The chemical extract data from the two samples suggest that the sediment column at this location shows signs of leachable sodium over that expected for most natural Hanford sediments. The monovalent to divalent cation ratio is dominated by sodium whereas most natural Hanford sediments are dominated by calcium. The sample from 69 ft depth also contains leachable nitrate and fluoride; neither anion shows up in the shallower sample.

The borehole and drill cuttings were monitored regularly for organic vapors and radionuclide contaminants. Carbon tetrachloride was detected at 1 ppm at about 88 ft bgs. No other contamination was noted.

The well was logged with high resolution, spectral gamma-ray instrumentation on August 28, 1998. Cesium-137 was identified at 4.75 ft bgs with an activity of 1 pCi/g; cobalt-60 was identified between 90 and 96 and between 110 and 112 ft bgs with a maximum activity of 0.29 pCi/g at 90 ft bgs; and europium-154 was identified between 90 and 92 ft bgs with a maximum activity of 1.7 pCi/g at 92 ft depth. The geophysical logs are in Appendix C.

3.2 Well Completion

The permanent casing and screen were installed in well 299-W14-13 in August 1998. A 4-in.-inner-diameter, stainless steel, wire wrap (0.01 in. slot) screen was set from 251.73 to 216.62 ft bgs. The permanent casing is 4-in.-inner-diameter stainless steel from 216.62 ft bgs to 2.1 ft above ground surface. Centralizers were placed at the top and bottom of the screen and every 40 ft from the screen to the surface. The bottom of the screen has a 4-in. end cap.

The filter pack is 20 to 40 mesh silica sand from 261.7 to 206.4 ft bgs. The annular seal is 0.25 in. bentonite pellets from 206.4 to 195.1 ft bgs; medium bentonite chips from 195.1 to 9.6 ft bgs; and Portland cement 9.6 ft to the surface. A 4 ft by 4 ft by 6 in. concrete pad was placed around the well at the surface. A protective casing with locking cap, four protective steel posts, and a brass marker stamped with the well number were set into the concrete. The Well Construction Summary Report and the Well Summary Sheet (as-built) are included in Appendix A.

The vertical and horizontal coordinates of the well were surveyed in December 1998. The horizontal position of the well was determined by global positioning system observations referenced to horizontal

control stations established by the U.S. Army Corps of Engineers. The coordinates are Washington Coordinate System, South Zone, NAD83/91 datum. Vertical datum is NAVD 1988 and is based on existing bench marks established by the U.S. Army Corps of Engineers. Survey data are included in Table 1.

3.3 Well Development and Pump Installation

Well 299-W14-13 was developed on September 17, 1998. A temporary, 2 hp submersible pump was used to remove approximately 500 gal of formation water at 8 gal/min and 200 gal of formation water at 7 gal/min. The final turbidity was 2.08 NTU.

A dedicated Hydrostar sampling pump was installed in well 299-W14-13 on October 22, 1998. The sampling pump intake is at 231.40 ft depth relative to the brass cap (see Table 1) or about 15 ft below the water table.

4.0 Well 299-W14-14

4.1 Drilling and Sampling

Well 299-W14-14 was drilled in October and November 1998 using a cable tool rig and temporary, 12-in. carbon steel casing to 20 ft bgs then air rotary and 8 5/8-in. temporary casing to a total depth of 443 ft bgs. Static water level was 217.42 ft bgs on November 14, 1998.

Sediments encountered during drilling were predominantly sand and sandy gravel of the Hanford formation from the surface to 93 ft bgs; Plio-Pleistocene silty sand with caliche from 93 to about 124 ft bgs (depths from geophysical log correlation); and sandy gravel and gravelly sand of the Ringold Formation Unit E from about 124 ft to total depth (443 ft bgs). The Ringold Formation lower mud unit, consisting of silty clay and silt with some gravel, was found between 402 and 438 ft bgs. A geologist's log is included in Appendix A.

Two grab samples were collected at 25 ft and 69 ft bgs for measurement of particle size distribution and two grab samples were collected from 185 ft and 196 ft bgs for analysis of residual contaminants remaining from a declining water table. Two split spoon samples were collected between 86 to 88 ft and between 93 to 95 ft bgs (100% recovery for both samples) for measurement of hydraulic properties. The only analyses completed to date are particle size distribution on the two shallowest samples. The sediment at 25 ft depth is coarse gravel and the sediment at 69 ft depth is sand. Particle size distribution data are in Appendix B. Sediment samples also were collected for geologic description and archive at approximately 5-ft intervals throughout the entire borehole.

Five groundwater samples were collected at 265, 315, 348, 402, and 442 ft bgs during well construction. Analytical results from the samples are in Appendix D.

The borehole and drill cuttings were monitored regularly for organic vapors and radionuclide contaminants. No contamination was noted.

The well was logged on November 7, 1998, with high resolution, spectral gamma-ray instrumentation (35% HPGe detector) at 200 sec/ft from the surface to 442 ft bgs and at 60 sec/ft from 70 to 130, 200 to 240 and 325 to 442 ft bgs. Cesium-137 was identified from 4 to 7 ft depth with a maximum activity of 7 pCi/g. The well was also logged with a sodium iodide detector from 0 to 344 ft bgs on October 30, 1998. A moisture log was obtained on October 28, 1998 from 19 to 217 ft bgs. All geophysical logs are in Appendix C.

4.2 Well Completion

The permanent casing and screen were installed in well 299-W14-14 in November 1998. A 4-in.-inner-diameter, stainless steel, wire wrap (10 slot) screen was set from 252.3 to 216.98 ft bgs. The permanent casing is 4-in.-inner-diameter stainless steel from 216.98 ft bgs to 2.0 ft above ground surface. Centralizers were placed at the top and bottom of the screen and every 40 ft from the screen to the surface. The bottom of the screen has a 4-in. end cap.

The borehole was filled with silica sand (8-16 and 10-20 mesh) from 443 ft to 438.8 ft bgs, cement grout from 438.8 to 326.6 ft bgs, and silica sand (4-10, 6-9, 8-12, 8-16, and 10-20 mesh) from 326.6 to 257.3 ft bgs. The filter pack is 20 to 40 mesh silica sand from 257.3 to 203.8 ft bgs. The annular seal is 3/8 in. bentonite pellets from 203.8 to 202.3 ft bgs; 3/8 in. bentonite chunks from 202.3 to 9.3 ft bgs; and cement grout from 9.3 ft bgs to the surface. A protective carbon steel casing with a locking cap extends to 3.06 ft above the surface. A 4 ft by 4 ft by 6 in. concrete pad was placed around the well at the surface with four protective steel posts set into the concrete. A brass marker stamped with the well number was placed into the concrete. The Well Construction Summary Report and the Well Summary Sheet (as-built) are included in Appendix A.

The vertical and horizontal coordinates of the well were surveyed in December 1998. The horizontal position of the well was determined by global positioning system observations referenced to horizontal control stations established by the U.S. Army Corps of Engineers. The coordinates are Washington Coordinate System, South Zone, NAD83/91 datum. Vertical datum is NAVD 1988 and is based on existing bench marks established by the U.S. Army Corps of Engineers. Survey data are included in Table 1.

4.3 Well Development and Pump Installation

Well 299-W14-14 was developed on November 13, 1998. A temporary, 2 hp submersible pump was used to remove approximately 1,700 gal of formation water from the well at 6 gal/min. Turbidity was 4.55 NTU.

A dedicated Hydrostar sampling pump was installed in well 299-W14-14 on November 13, 1998. The sampling pump intake is at 231.50 ft depth relative to the brass cap (see Table 1) or about 14 ft below the water table.

5.0 Well 299-W15-40

5.1 Drilling and Sampling

Well 299-W15-40 was drilled in August and September 1998. The well was started with a cable tool rig and drive barrel using 9-in.-outside-diameter temporary, carbon steel casing from the surface to 125.5 ft bgs. The 9-in. casing was then removed and the hole redrilled with air rotary and 8 5/8-in.-outside-diameter casing to 262.4 ft bgs. About 300 gal of water were added to the borehole at 262 ft bgs to keep fine grained sediment out of the casing. Static water level was 218.08 ft bgs on September 10, 1998.

Sediments encountered during drilling were predominantly sandy gravel and sand of the Hanford formation from the surface to about 98 ft bgs; Plio-Pleistocene silty sand and gravelly, silty sand from 98 to 132 ft bgs (depths from geophysical log correlation); and Ringold Formation Unit E silty sand and silty, sandy gravels from 132 to 262 ft bgs (total depth). A geologist's log is included in Appendix A.

Grab samples were collected at approximately 5-ft intervals from the surface to 125 ft depth for analysis of physical and chemical properties (pH, conductivity, cation exchange capacity, calcium carbonate content, extractable major cations and anions, and moisture contents). Two split spoon samples were collected at 98 ft and 105 ft depths for measurement of hydraulic properties; those measurements have not been done to date. Particle size distributions were determined for samples from 25 ft and 69 ft depths. The sample from 25 ft depth is gravel and the sample from 69 ft depth is sand. Sediment samples also were collected for geologic description and archive at approximately 5-ft intervals throughout the entire borehole.

The 1:1 water:sediment extract data show some high leachable salt at 40 ft bgs and high nitrate concentrations in the samples from 40, 55, 68, 100, 115, 120, and 125 ft depths. There is also a zone between 30 and 40 ft bgs where sulfate is high. Finally, sodium is enriched in zones between 10 and 15 ft bgs and at 90 ft bgs. The zones of high leachable salts, high leachable sodium, nitrate, and sulfate do not seem to correlate. This may indicate natural heterogeneity although the influence of past waste disposal cannot be eliminated.

The borehole and drill cuttings were monitored regularly for organic vapors and radionuclide contaminants. No contamination was noted.

The well was logged from 0 to 125 ft bgs on August 28, 1998, using a high resolution, spectral gamma-ray instrumentation and neutron moisture instrumentation. The well was logged a second time on September 4, 1998, using the same tools from 105 to 262 ft bgs (220 ft depth for the moisture log). No man-made radionuclides were detected. All geophysical logs are in Appendix C.

5.2 Well Completion

The permanent casing and screen were installed in well 299-W15-40 in September 1998. A 4-in.-inner-diameter, stainless steel, wire wrap (0.01 in. slot) screen was set from 253.08 to 217.95 ft bgs. The permanent casing is 4-in.-inner-diameter stainless steel and was set from 217.95 ft bgs to 2.0 ft above ground surface. Centralizers were placed at the top and bottom of the screen and every 40 ft from the screen to the surface. The bottom of the screen has a 4-in. end cap.

Silica sand (20 to 40 mesh) was placed around the permanent casing and screen from 262.4 to 208.3 ft bgs. The annular seal was constructed of 1/4 in. bentonite pellets from 208.3 to 195.4 ft bgs, medium bentonite chips from 195.4 to 10.1 ft bgs, and Portland cement from 10.1 ft to the surface. The well has a protective carbon steel casing with a locking cap. A 4 ft by 4 ft by 6 in. concrete pad was placed around the well at the surface with four protective steel posts set into the concrete. A brass marker stamped with the well number was placed into the concrete. The Well Construction Summary Report and the Well Summary Sheet (as-built) are included in Appendix A.

The vertical and horizontal coordinates of the well were surveyed in December 1998. The horizontal position of the well was determined by global positioning system observations referenced to horizontal control stations established by the U.S. Army Corps of Engineers. The coordinates are Washington Coordinate System, South Zone, NAD83/91 datum. Vertical datum is NAVD 1988 and is based on existing bench marks established by the U.S. Army Corps of Engineers. Survey data are included in Table 1.

5.3 Well Development and Pump Installation

Well 299-W15-40 was developed on September 16, 1998. A temporary, 2 hp submersible pump was used to remove approximately 2,000 gal of formation water from the well at 6 gal/min. The final turbidity was 4.2 NTU.

A dedicated Hydrostar sampling pump was installed in well 299-W15-40 on October 19, 1998. The sampling pump intake is at 231.45 ft depth relative to the brass cap (see Table 1) or about 13 ft below the water table.

6.0 References

Caggiano, J. A., and S. M. Goodwin. 1991. *Interim Status Groundwater Monitoring Plan for the Single-Shell Tanks*. WHC-SD-EN-AP-012, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

Ecology - Washington State Department of Ecology, U.S. Environmental Protection Agency, and U.S. Department of Energy. 1996. *Hanford Federal Facility Agreement and Consent Order*. Document No. 89-10, Rev. 4 (The Tri-Party Agreement), Ecology, Olympia, Washington.

RCRA - Resource Conservation and Recovery Act. 1976. Public Law 94-580, as amended, 90 Stat. 2795, 42 USC 6901 et seq.

WAC 173-160, Washington Administrative Code. *Minimum Standards for Construction and Maintenance of Wells*. Olympia, Washington.

WAC 173-303, Washington Administrative Code. *Dangerous Waste Regulations*. Olympia, Washington.

Appendix A

Well Construction and Completion Documentation

<div style="float: right; font-weight: bold; font-size: 1.2em;">0502396</div> WELL CONSTRUCTION SUMMARY REPORT				Start Date: <u>8/19/98</u> Finish Date: <u>8/25/98</u> Page <u>1</u> of <u>1</u>			
Specification No.: <u>0200X-SP-V0001</u>		Rev. No.: <u> </u>		Well Name: <u>B 048</u>			
ECNs: <u>NA</u>		Approximate Location: <u>25' E of 24-LTY Tank Farm, 200W</u>					
Project: <u>RCRA Drilling 1998</u>		Other Companies: <u>CH2M Hill</u>					
Drilling Company: <u>Layne Christensen</u>		Geologist(s): <u>D.C. Weekes</u> <u>L. Walker</u>					
Driller: <u>W. Franklin</u>		Temp. Well No.: <u>299-W10-26</u>					
TEMPORARY CASING AND DRILL DEPTH			DRILLING METHOD/HOLE DIAMETER				
*Size/Grade/Lbs. Per Ft.	Interval	Shoe O.D./I.D.	Auger:	Diameter From <u> </u> to <u> </u>			
<u>CS/FJ</u>	<u>0' - 262.2'</u>	<u>8 5/8" / 8"</u>	Cable Tool:	Diameter From <u> </u> to <u> </u>			
			Air Rotary: ☒ (ODEX)	Diameter From <u>0'</u> to <u>262'</u>			
			A.R. w/Sonic:	Diameter From <u> </u> to <u> </u>			
				Diameter From <u> </u> to <u> </u>			
				Diameter From <u> </u> to <u> </u>			
*Indicate Welded (W) - Flush Joint (FJ) Coupled (C) & Thread Design			Diameter From <u> </u> to <u> </u>				
			Drilling Fluid: <u>Air</u>				
Total Drilled Depth: <u>262'</u>		Hole Dia @ TD: <u>9 1/2"</u>		Total Amt. Of Water Added During Drilling: <u> </u>			
Well Straightness Test Results: <u>NA</u>		Static Water Level: <u>216.80'</u>		Date: <u>8-25-98</u>			
GEOPHYSICAL LOGGING							
Sondes (type)	Interval	Date	Sondes (type)	Interval	Date		
<u>Spectral KUT</u>	<u>0' - 262'</u>	<u>8-22-98</u>					
COMPLETED WELL							
Size/WL/Material	Depth	Thread	Slot Size	Type	Interval Annual Seal/Filter Pack	Volume	Mesh Size
<u>4" ID SS</u>	<u>+2.1 - 217.04'</u>	<u>FJ</u>	<u>NA</u>	<u>Portland Cement</u>	<u>0' - 10.5'</u>	<u>6.425 ft³</u>	<u>NA</u>
<u>4" ID SS wire wrap</u>	<u>217.04' - 252.13'</u>	<u>FJ</u>	<u>0.010-in</u>	<u>Bentonite chips</u>	<u>10.5' - 204.5'</u>	<u>62.79 ft³</u>	<u>3/8"</u>
<u>4" ID SS</u>	<u>252.13' - 252.45'</u>	<u>FJ</u>	<u>NA</u>	<u>Bentonite Pellets</u>	<u>204.5' - 211.0'</u>	<u>1.86 ft³</u>	<u>1/4"</u>
				<u>Silica Sand</u>	<u>211.0' - 262.0'</u>	<u>27.16 ft³</u>	<u>20-40</u>
OTHER ACTIVITIES							
Aquifer Test:		Date:		Well Abandoned:		Yes: ☐ No: ☒ Date: <u> </u>	
Description:				Description:			
WELL SURVEY DATA							
Date:				Protective Casing Elevation:			
Washington State Plane Coordinates:				Brass Cap Elevation:			
COMMENTS/REMARKS							
<u>CS = Carbon steel, SS = stainless steel; Volume calc: cement = 1.285 x 5 = 6.425 ft³</u> <u>Bentonite chips = 0.69 x 91 = 62.79 ft³; Bentonite Pellets = 0.62 x 3 = 1.86 ft³</u> <u>20-40 Silica Sand = 1.12 x 24.25 = 27.16 ft³</u>							
Reported By: <u>L.D. Walker</u>				Reported By: <u>E.L. RAUSE</u>			
Title: <u>Geologist</u>		Date: <u>8-25-98</u>		Title: <u>FIELD ENGINEER</u>		Date: <u>8/26/98</u>	
Signature: <u>L.D. Walker</u>				Signature: <u>E.L. Rause</u>			

BHI-EE-181 (12/97)

WELL SUMMARY SHEET				Page <u>1</u> of <u>2</u>	
				Date: <u>8/15/98</u>	
Well ID: <u>B8548</u>		Well Name: <u>299-W10-26</u>			
Location: <u>15' East of 241-TY Tank Farm, 200W</u>		Project: <u>RCRA Drilling 1998</u>			
Prepared By: <u>L.D. Walker</u>	Date: <u>8-25-98</u>	Reviewed By: <u>EDWARD RAJAN</u>	Date: <u>09/15/98</u>		
Signature: <u>L.D. Walker</u>		Signature: <u>Edward Rajan</u>			
CONSTRUCTION DATA		Depth in Feet	GEOLOGIC/HYDROLOGIC DATA		
Description	Diagram		Graphic Log	Lithologic Description	
Portland Cement: 0'-10.5'		0		0'-4': Back Fill	
				4'-9': Sand	
				9'-22': Gravel	
		25		22'-42.5': Sandy Gravel	
Bentonite Chips:					
10.5'-204.5'		50		42.5'-64': Sand	
				64'-89': Gravelly Sand	
4 1/2" OD (4" ID) type 304 stainless steel casing:		75		89'-102': Silty Sand	
+2.1'-217.04'				-calcareous	
				(97'-100' caliche)	
		100		(108'-110' caliche)	
				102'-108': Sand	
				108'-114': Silty Sand	
				114'-116': Sand	
		116'-124': Silty Sand			
	125	124'-127': Sand			
		127'-159': Silty Sandy Gravel			

WELL SUMMARY SHEET				8-25-98 Page <u>1</u> of <u>2</u> Date: <u>8-15-98</u>
Well ID: <u>B8548</u>		Well Name: <u>299-W10-26</u>		
Location: <u>15' East of 241-TY Tank Farm, 200W</u>		Project: <u>RCRA Drilling 1998</u>		
Prepared By: <u>L.D. Walker</u>	Date: <u>8-25-98</u>	Reviewed By: <u>EDWARD RAFFERTY</u>	Date: <u>9/5/98</u>	
Signature: <u>L.D. Walker</u>		Signature: <u>Edward Rafferty</u>		
CONSTRUCTION DATA		Depth in Feet	GEOLOGIC/HYDROLOGIC DATA	
Description	Diagram		Graphic Log	Lithologic Description
		150		(152'-156': lg cobbles)
				159'-161': Gravelly Sand
				161'-205': Sandy Gravel
Bentonite Pellets: 204.5' - 211.0'		200		
20-40 mesh Silica Sand: 211.0' - 262.0'		225		205'-262': Silty Sandy Gravel
4 1/2" OD (4" ID) type 304 ss continuous wire wrap 0.010-in. slot screen: 217.04' - 252.13'		250		Water Level = 216.80' (8-25-98)
Bottom of 4 1/2" OD (4" ID) type 304 ss endcap at 252.45'		275		TD = 262 ft.
9 1/2" borehole to 262'				
8 5/8" OD carbon steel casing to 262.2' + all temp. casing removed from ground				
Depths are measured from ground surface				

Boring or Well No. 299-W10-26/B8548

Sheet 1 of 4

Project RCRA Drilling 1998

Prepared By DC Weekes DC Weekes
(Sign/Print Name)

Date 8/20/98

Reviewed By Edward C. Rife / EDWARD C. RIFE Date 08/28/98
(Sign/Print Name)

အ.ကုလ.ဝေ. ၁၅.၂၃၇

BOREHOLE LOG				Boring or Well No. 299-W10-26/B8548	
				Sheet <u>2</u> of <u>4</u>	
Location <u>~15. ft E. of 241-TY Tank Farm</u>			Project <u>RCRA Drilling 1998</u>		
Prepared By <u>LD Walker / L.D. Walker</u> Date <u>8-20-98</u> <small>(Sign/Print Name)</small>			Reviewed By <u>Edward R. Ruff / EDWARD RUFF</u> Date <u>08/28/98</u> <small>(Sign/Print Name)</small>		

Depth	Sample		Graphic Log	Sample Description <small>Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl</small>	Comments <small>Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level</small>
	Type and No.	Blows or Recovery			
80					8" olex bit, 9 1/4" bore hole 8 5/8" OD Temp CS casing
90				89'-102': Silty Sand (m S) (70% sand, 30% silt); sand 20% fn, 80% v. fn; 10YR 6/4 (lt vel. brn); sl moist, well to med sorted, tr mica, strong HCl rxn (calcareous)	Drilling smooth, 10 ft/12 min.
100				97'-100': 10% gravel (med-fn peb) tr caliche to 102 ft.	Drilling indicates probable caliche 97-100'
				102'-108': Sand (S); (tr gravel, 95% sand, 5% silt) sand 10% cse, 60% med, 30% fn-v. fn; mineralogy as above 108-114': Silty Sand-as above	102-108' drilling faster 108'- caliche to 110'
110				114'-116': Sand (S); (tr gravel, 90% sand, 10% silt, 10YR 6/2	OVM, LEL < detect.
120				116'-124': Silty Sand (m S) (5% gravel, 60% sand, 35% silt); gravel med-v. fn peb; sand 20% v. cse, 40% cse, 30% med, 10% fn-v. fn, 10YR 4/2 dry, poorly sorted, gravel sub-round, sand sub-angular, gravel and sand 60% basalt; silt has strong rxn HCl	RCT survey: B, X < detect.
130				124'-127': Sand (S); (5% gravel, 95% sand); sand 10% v. cse, 80% cse, 10% med-v. fn, 50% basalt, 40% qtz, 10% other. Sub-angular	
140				127'-159': Silty Sandy Gravel (mSG); gravel 50%, sand 40%, silt 10% ; gravel 10% v. cse-cse peb, 50% med, 40% fn-v. fn; sand 10% v. cse, 80% cse, 10% med-v. fn; 60% basalt, 35% qtz 5% other; weak HCl rxn; max particle ~50mm	150': qtz content up; basalt content down to ~35%
150					152'-156': drilling indicates lg. cobbles

3-RCRA-382 (01/93)

Boring or Well No. 299-W10-26/88548

Sheet 4 of 4

Project RCRA Drilling 1998

Prepared By DCubekees DCubekees Date 8/21/98
(Sign/Print Name)

Reviewed By Edward R. Lerner Date 08/28/98
(Sign/Print Name)

[illegible]

A-6000-382 (01/93)

WELL CONSTRUCTION SUMMARY REPORT				Start Date <u>8-26-98</u> Finish Date <u>8-31-98</u> Page 1 of 1																																																					
Specification No. <u>2200Y-SP-10001</u> Rev. No. <u>1</u>			Well No. <u>88549</u> Temp. Well No. <u>299-W14-13</u>																																																						
ECNs: <u>NA</u> Project: <u>RCRA Drilling 1998</u> Drilling Company: <u>Layne Christensen</u> Driller: <u>W. Franklin</u>			Approximate Location: <u>intersect. of Comden & 22nd, 200W</u> Other Companies: <u>Rechtel, CH2M Hill</u> Geologist (s): <u>E. R. Ruse</u> <u>L. Walker</u>																																																						
Temporary Casing and Drill Depth			Drilling Method/Hole Diameter																																																						
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 30%;">*Size/Grade/Lbs per Ft.</th> <th style="width: 30%;">Interval</th> <th style="width: 40%;">Shoe O.D./I.D.</th> </tr> </thead> <tbody> <tr> <td><u>CS/FJ</u></td> <td><u>0 - 262'</u></td> <td><u>8 5/8" / 8"</u></td> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>			*Size/Grade/Lbs per Ft.	Interval	Shoe O.D./I.D.	<u>CS/FJ</u>	<u>0 - 262'</u>	<u>8 5/8" / 8"</u>																<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 30%;">Auger:</th> <th style="width: 30%;">Dia. From</th> <th style="width: 40%;">to</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td>Cable Tool:</td> <td>Dia. From</td> <td>to</td> </tr> <tr> <td>Air Rotary: <u>✓ (Odex)</u></td> <td>Dia. From <u>0</u></td> <td>to <u>262 Ft.</u></td> </tr> <tr> <td>A.R. w/Sonic:</td> <td>Dia. From</td> <td>to</td> </tr> <tr> <td> </td> <td>Dia. From</td> <td>to</td> </tr> <tr> <td> </td> <td>Dia. From</td> <td>to</td> </tr> <tr> <td> </td> <td>Dia. From</td> <td>to</td> </tr> </tbody> </table>			Auger:	Dia. From	to				Cable Tool:	Dia. From	to	Air Rotary: <u>✓ (Odex)</u>	Dia. From <u>0</u>	to <u>262 Ft.</u>	A.R. w/Sonic:	Dia. From	to		Dia. From	to		Dia. From	to		Dia. From	to							
*Size/Grade/Lbs per Ft.	Interval	Shoe O.D./I.D.																																																							
<u>CS/FJ</u>	<u>0 - 262'</u>	<u>8 5/8" / 8"</u>																																																							
Auger:	Dia. From	to																																																							
Cable Tool:	Dia. From	to																																																							
Air Rotary: <u>✓ (Odex)</u>	Dia. From <u>0</u>	to <u>262 Ft.</u>																																																							
A.R. w/Sonic:	Dia. From	to																																																							
	Dia. From	to																																																							
	Dia. From	to																																																							
	Dia. From	to																																																							
*Indicate Welded (W) - Flush Joint (FJ) - Coupled (C) & Thread Design			Drilling Fluid: <u>Air</u> Total Amt. of Water Added During Drilling: <u> </u> Static Water Level: <u>215.8 Ft.</u> Date: <u>8-31-98</u>																																																						
Total Drilled Depth <u>262 Ft.</u> Hole Dia. @ TD <u>9 1/2"</u> Well Straightness Test Result <u>NA</u>																																																									
Geophysical Logging																																																									
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 30%;">Sondes (type)</th> <th style="width: 30%;">Interval</th> <th style="width: 40%;">Date</th> </tr> </thead> <tbody> <tr> <td><u>Spectral KUT</u></td> <td><u>0' - 254'</u></td> <td><u>8-28-98</u></td> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>			Sondes (type)	Interval	Date	<u>Spectral KUT</u>	<u>0' - 254'</u>	<u>8-28-98</u>										<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 30%;">Sondes (type)</th> <th style="width: 30%;">Interval</th> <th style="width: 40%;">Date</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>			Sondes (type)	Interval	Date																																		
Sondes (type)	Interval	Date																																																							
<u>Spectral KUT</u>	<u>0' - 254'</u>	<u>8-28-98</u>																																																							
Sondes (type)	Interval	Date																																																							
Completed Well																																																									
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 20%;">Size/Wt./Material</th> <th style="width: 20%;">Depth</th> <th style="width: 20%;">Thread</th> <th style="width: 40%;">Slot Size</th> </tr> </thead> <tbody> <tr> <td><u>4" ID SS</u></td> <td><u>+2.1 - 216.62'</u></td> <td><u>FJ</u></td> <td><u>NA</u></td> </tr> <tr> <td><u>4" ID SS wirewrap</u></td> <td><u>216.62' - 251.73'</u></td> <td><u>FJ</u></td> <td><u>0.010" in</u></td> </tr> <tr> <td><u>4" ID SS</u></td> <td><u>251.73' - 252.05'</u></td> <td><u>FJ</u></td> <td><u>NA</u></td> </tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>				Size/Wt./Material	Depth	Thread	Slot Size	<u>4" ID SS</u>	<u>+2.1 - 216.62'</u>	<u>FJ</u>	<u>NA</u>	<u>4" ID SS wirewrap</u>	<u>216.62' - 251.73'</u>	<u>FJ</u>	<u>0.010" in</u>	<u>4" ID SS</u>	<u>251.73' - 252.05'</u>	<u>FJ</u>	<u>NA</u>									<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 20%;">Type</th> <th style="width: 20%;">Interval</th> <th style="width: 20%;">Volume</th> <th style="width: 40%;">Mesh Size</th> </tr> </thead> <tbody> <tr> <td colspan="4" style="text-align: center;">Annular Seal/Filter Pack</td> </tr> <tr> <td><u>Portland Cement</u></td> <td><u>0 - 9.6'</u></td> <td><u>6.43 ft³</u></td> <td><u>NA</u></td> </tr> <tr> <td><u>Bentonite Chips</u></td> <td><u>9.6' - 205.5'</u></td> <td><u>195.1</u></td> <td><u>52.79 ft³ medium</u></td> </tr> <tr> <td><u>Bentonite Pellets</u></td> <td><u>195.5' - 206.4'</u></td> <td><u>3.1 ft³</u></td> <td><u>1/4"</u></td> </tr> <tr> <td><u>Silica Sand</u></td> <td><u>206.4' - 261.7'</u></td> <td><u>29.12 ft³</u></td> <td><u>20-40</u></td> </tr> <tr> <td colspan="4"><u>→ Correction LW 9-4-98</u></td> </tr> </tbody> </table>		Type	Interval	Volume	Mesh Size	Annular Seal/Filter Pack				<u>Portland Cement</u>	<u>0 - 9.6'</u>	<u>6.43 ft³</u>	<u>NA</u>	<u>Bentonite Chips</u>	<u>9.6' - 205.5'</u>	<u>195.1</u>	<u>52.79 ft³ medium</u>	<u>Bentonite Pellets</u>	<u>195.5' - 206.4'</u>	<u>3.1 ft³</u>	<u>1/4"</u>	<u>Silica Sand</u>	<u>206.4' - 261.7'</u>	<u>29.12 ft³</u>	<u>20-40</u>	<u>→ Correction LW 9-4-98</u>			
Size/Wt./Material	Depth	Thread	Slot Size																																																						
<u>4" ID SS</u>	<u>+2.1 - 216.62'</u>	<u>FJ</u>	<u>NA</u>																																																						
<u>4" ID SS wirewrap</u>	<u>216.62' - 251.73'</u>	<u>FJ</u>	<u>0.010" in</u>																																																						
<u>4" ID SS</u>	<u>251.73' - 252.05'</u>	<u>FJ</u>	<u>NA</u>																																																						
Type	Interval	Volume	Mesh Size																																																						
Annular Seal/Filter Pack																																																									
<u>Portland Cement</u>	<u>0 - 9.6'</u>	<u>6.43 ft³</u>	<u>NA</u>																																																						
<u>Bentonite Chips</u>	<u>9.6' - 205.5'</u>	<u>195.1</u>	<u>52.79 ft³ medium</u>																																																						
<u>Bentonite Pellets</u>	<u>195.5' - 206.4'</u>	<u>3.1 ft³</u>	<u>1/4"</u>																																																						
<u>Silica Sand</u>	<u>206.4' - 261.7'</u>	<u>29.12 ft³</u>	<u>20-40</u>																																																						
<u>→ Correction LW 9-4-98</u>																																																									
Other Activities																																																									
Aquifer Test: _____ Date: _____ Description: _____			Well Abandoned: Y ☐ N ☒ Date: _____ Description: _____																																																						
Well Survey Data																																																									
Date: _____ Washington State Plane Coordinates: _____			Protective Casing Elevation: _____ Brass Cap Elevation: _____																																																						
Comments/Remarks: <u>CS = carbon steel, SS = stainless steel; Volume calc: cement = 1.285 x 4 = 5.14 ft³</u> <u>Bentonite chips = 0.69 x 76.5 = 52.79 ft³; Bentonite pellets = 0.62 x 5 = 3.1 ft³</u> <u>20-40 silica sand = 1.12 x 26 = 29.12 ft³</u>																																																									
Reported By: <u>L.D. Walker</u> Title: <u>Geologist</u> Signature: <u>[Signature]</u> Date: <u>08/31/98</u>			Reported By: <u>E.C. Ruse</u> Title: <u>FIELD ENGINEER (BNI)</u> Signature: <u>[Signature]</u> Date: <u>09/15/98</u>																																																						

0502443

WELL SUMMARY SHEET

Page 1 of 2

Date: 8-26-98

Well ID: B8549

Well Name: 299-W14-13

Location: intersection of Camden Ave & 22nd St. 200 W

Project: RCRA Drilling 1998

Prepared By: L. D. Walker

Date: 8-28-98

Reviewed By: E.C. RoFuge

Date: 09/15/08

Signature: T.D. Walker

Signature: *E. C. Loper*

CONSTRUCTION DATA

GEOLOGIC/HYDROLOGIC DATA

Depth in
Feet

Graphic Log

Lithologic Description

Description

Diagram

Portland Cement: 0'-9.6'

0'-4': Construction Fill

4'-14': Sand

14'-33': Sandy Gravel

Bentonite chips:

9.6' - 195.1'

33'-95': Sand

4 1/2" OD (4" ID) type 304
stainless steel casing:
+2.1' - 216.62'

95'-98': Sand, s/calcareous

98'-101': Caliche

101'-112': Sandy Gravel
sl calcareous

112'-125': Sand

125'-163': Silty Sandy Gravel

WELL SUMMARY SHEET				Page <u>2</u> of <u>2</u>	
				Date: <u>8-28-98</u>	
Well ID: <u>B8549</u>		Well Name: <u>299-W14-13</u>			
Location: <u>intersect. of Camden Ave. and 22nd St, 200W</u>		Project: <u>RCRA Drilling, 1998</u>			
Prepared By: <u>L.D. Walker</u>	Date: <u>8-28-98</u>	Reviewed By: <u>E.C. Baker</u>	Date: <u>9/15/98</u>		
Signature: <u>L.D. Walker</u>		Signature: <u>E.C. Baker</u>			
CONSTRUCTION DATA		Depth in Feet	GEOLOGIC/HYDROLOGIC DATA		
Description	Diagram		Graphic Log	Lithologic Description	
		150			
Bentonite Pellets:					
195.1' - 206.4'					
20-40 mesh Silica Sand:					
206.4' - 261.7'					
4 1/2" OD (4" ID) type 304 SS					
continuous wire wrap 0.010-in					
slot screen: 216.62' - 251.73'					
Bottom of 4 1/2" OD (4" ID) type					
304 SS endcap at 252.05'					
9 1/2" borehole to 262'					
8 5/8" OD carbon steel casing					
to 262' - All temp. casing					
removed from the ground					
Depths are measured from ground surface.		275			

BOREHOLE LOG				Boring or Well No. <u>299-W14-13 / B8549</u>	
				Sheet <u>1</u> of <u>4</u>	
Location <u>intersection of Camden Ave & 22nd St, 200W</u>			Project <u>RCRA Drilling 1998</u>		
Prepared By <u>L.D. Walker</u> Date <u>8-26-98</u> <small>(Sign/Print Name)</small>			Reviewed By <u>Edward Rabin</u> Date <u>09/15/98</u> <small>(Sign/Print Name)</small>		

Depth (<u>0</u>)	Sample		Graphic Log	Sample Description	Comments
	Type and No.	Blows or Recovery		Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
				0' - 4': Silty Sandy Gravel (msG) Construction Fill	8" Odex bit / 9 1/2" borehole 8 5/8" OD (8" ID) CS casing
10				4' - 14': Sand (S); 95% sand, 5% silt; Sand tr med, 50% F _n , 50% v. F _n ; 10 YR 5/2 (gr. brn); sl moist well sorted, sub angular, weak rxn HCl.	
20				14' - 33': Sandy Gravel (sG) 60% gravel, 40% sand, tr silt.	16' - 18': drilling indicates large cobbles
	Grab #1			v. F _n ; sand 40% v. cse, 30% cse, 30% med. v. F _n ; 10 YR 5/1 (gray), sl moist, mod sorted; gravel sub-round to sub-ang,	B, X < detectable 21': drilling indicates decrease in gravel size
30	Sieve analysis 25'-26'			gravel and sand 70% basalt, 30% qtz and granitics. Max size lg. cobble - in 16'-18' area.	Collect grab sample for sieve analysis 25'-26' Drill rate increases at 33'
40				33' - 95': Sand (S). Sand 95% silt 5%. Sand is tr v. cse, 20% cse, 40% med, 30% F _n , 10% v. F _n ; tr thin layers siltier areas.	
50				10 YR 6/2 (lt. brownish gray); moist; mod. sorted; sub angular; 25% basalt, 70% qtz, 5% other, tr mica; max size 2 mm; no rxn HCl.	Drill rate: 10 ft / 5 min
60					
70	Grab #2				69' - 70': collect grab sample for sieve analysis number 2
	Sieve analysis 69'-70'				
					End shift 8/26/98

A-6000-382 (01/93)

BOREHOLE LOG

Boring or Well No. 299-WY-B/6Sheet 2 of 4Location INTERSECTION OF CAMDEN AVE & 22ND ST. Project RCA Drilling 1998Prepared By Edward Rafus/EDWARD RAFFUS Date 08/27/98 Reviewed By L.D. Walker Date 9-16-98
(Sign/Print Name) (Sign/Print Name)

Depth (<u>80</u>)	Sample		Graphic Log	Sample Description Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Comments Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
	Type and No.	Blows or Recovery			
90				95-98 - SAND (s) to GRAVEL, 60% slightly HCL rxn. SAND - MOD SPT 10 ft 6/5 (H. B. H. H.)	8" DEX bit / 9 1/2" borehole 8 1/2" OD (8" ID) cc casing OUM LEL Ldet CO Ldet CL 14 - 1.0 ppm
100				98-101 - CARICHE, STRONG HCL rxn (CALCAREOUS)	
110				101-112 - SANDY GRAVEL, 60% SAND, 35% GRAVEL 5% silt MOD HCL rxn, SAND - MOD SCTED, SOME GRANITIC MAT.	
120				112-125 SAND (s) to GRAVEL SAND - 10% ccs, 40% med, 50% Fgr, some mica flakes	2125.0 slow + DRILL RATE APPROX. 30 min. COBBLES AND GRAVELS
130				125-143 silt SANDY GRAVEL (MSG); GRAVEL 60% SAND 30% silt 10% GRAVEL 20% V.C.S - Ccs per, 50% med - 30% Fgr, SAND 20% ccs 60% MED gr, 20% Fgr WEAK HCL rxn,	DRILL RATE ≈ 10 1/2 hr
140					
150					

A-6000-382 101/931

BOREHOLE LOG				Boring or Well No. <u>299-W14-13</u>	
				Sheet <u>3</u> of <u>4</u>	
Location <u>INTERSECTION of CAMDEN AVE & 20th ST.</u>			Project <u>RCCA Drilling 1998</u>		
Prepared By <u>Edmund Ruffin / Edmund Ruffin</u> Date <u>08/27/98</u> <small>(Sign/Print Name)</small>			Reviewed By <u>RD Walker / L.D. Walker</u> Date <u>9-16-98</u> <small>(Sign/Print Name)</small>		

Depth	Sample		Graphic Log	Sample Description	Comments
	Type and No.	Blows or Recovery			
(160)					
170			163-310	163-310 SANDY GRAVEL (SG) GRAVEL 65% SAND, 30% SILT 5% GRAVEL - 50% V.C.P. PER. 30% M LSE, 20% FCS, SAND (30% V.C.P. PER.) LSE 40% M.G.P., 30% F-VF GR. Fairly SORT, MICACEOUS, & FELOSAR	8" ODEX bit / 9 1/2" box hole 8 1/2" x 20 (8" T.O.) L.S. CASING TIME - 2 NET 00 & 00.4 166-20.00
180					
190					
200					
210				210-225 1/4 SANDY GRAVEL (SG) GRAVEL 55% SAND 40% SILT 5% TR. F.F. MICA, biotite, GRAVELS 30% V.C.P. - CRS PER. 20% MED, 40% FCS, SAND 20% CRS GR. 30% MED GR, 20% FGR, 2% VF GR. PRO-WELL SCT., FELOSAR, NO XIN HCL	DRILL RATE 10 FT / 30 MIN
220					
230					

A-6000-382 (01/93)

Boring or Well No. 299-W14-13

Sheet 4 of 4

Project RCS Drilling 1988

Reviewed By L.D. Walker Date 9-16-98
(Sign/Print Name)

[illegible]

A-6000-382 (01/93)

WELL CONSTRUCTION SUMMARY REPORT

Start Date: 10/8/98

Finish Date: 11/13/98

Page 1 of 1

Specification No.: 0200X-SP-1001 Rev. No.: 1 Well Name: B 8547 Temp. Well No.: 299-W14-14

ECNs: NA Approximate Location: East of Tank Farm

Project: RCRA GW Drilling, 1998 Other Companies: CH2M Hill

Drilling Company: Layne - Christensen Geologist(s): J.M. Faurate

Driller: M.W. Waspir, Randy Thompson L.D. Walker

TEMPORARY CASING AND DRILL DEPTH

DRILLING METHOD/HOLE DIAMETER

*Size/Grade/Lbs. Per Ft.	Interval	Shoe O.D./I.D.	Auger:	Diameter From	to
12" Carbon Steel (W)	0 - 19.88	1.1' / 1.0'	Cable Tool: 12"	Diameter From 0'	to 20.0'
Carbon Steel 85 1/8" / 8" FJ	0 - 442.5	85 1/8" / 75 1/8"	Air Rotary: Tubex 8" 9 1/8"	Diameter From 20	to 443
			A.R. w/Sonic:	Diameter From	to
				Diameter From	to
				Diameter From	to

*Indicate Welded (W) - Flush Joint (FJ) Coupled (C) & Thread Design

Diameter From to

Drilling Fluid: Air

Total Drilled Depth: 443 Hole Dia @ TD: 9 1/8" Total Amt. Of Water Added During Drilling:

Well Straightness Test Results: Static Water Level: 217.42 bgs Date: 11/14/98

GEOPHYSICAL LOGGING

Sondes (type)	Interval	Date	Sondes (type)	Interval	Date
RLS Spectral KUT	0' - 344'	10/29/98			
Neutron	20' - 210'	10/31/98			
RLS Spectral KUT	225 - 443	11/07/98			

COMPLETED WELL

Size/Wt./Material	Depth	Thread	Slot Size	Type	Interval Annual Seal/Filter Pack	Volume	Mesh Size
4" ID Stainless end cap				Colorado Silica Sand	443 - 438.8	3 bags	8-16
4" ID SS304 wire wrap SS				Cement Grout	438.8 - 326.6	42 bags	10-20
4" ID SS304 SS riser				Colorado Silica Sand	326.6 - 257.3	122.5 bags	N/A
				Colorado Silica Sand (Filter Pack)	257.3 - 203.8	50 bags	*see Comments
3/8" Bentonite Pellets	203.8 - 202.3	25 bags	3/8"	Bentonite Chunks	202.3 - 9.3	127 bags	20-40

OTHER ACTIVITIES

Aquifer Test:	Date:	Well Abandoned:	Yes:	No:	Date:
Description:		Description:			

WELL SURVEY DATA

Date:	Protective Casing Elevation:
Washington State Plane Coordinates:	Brass Cap Elevation:

COMMENTS/REMARKS

* Sand consisted of 4-10, 6-10, 6-9, 8-12, 8-16 and 10-20 mesh, plus 6-12 to fill the void.

Reported By: J.M. Faurate	Reported By: E.C. Ruffe
Title: Geologist	Title: Field Engineer
Signature: J.M. Faurate	Signature: E.C. Ruffe
Date: 11/16/98	Date: 11/18/98

WELL SUMMARY SHEET				Page <u>1</u> of <u>2</u>
			Date: <u>11/6/98</u>	
Well ID: <u>B8547</u>		Well Name: <u>299-W14-14</u>		
Location: <u>50' E. of 241-TX Tank Farm / 200W</u>		Project: <u>RCRA Drilling 1998</u>		
Prepared By: <u>L.D. Walker / J.M. Faurote</u>	Date: <u>11/6/98</u>	Reviewed By: <u>E.C. Rofers</u>	Date: <u>11/18/98</u>	
Signature: <u>[Signature]</u>		Signature: <u>[Signature]</u>		
CONSTRUCTION DATA		Depth in Feet	GEOLOGIC/HYDROLOGIC DATA	
Description	Diagram		Graphic Log	Lithologic Description
<i>Depths are below ground surface</i>				
Protective casing is 3.0' above ground		0		0'-4.5': Backfill (gravel, sand)
Cement Grout 0'-9.3'				4.5'-7': Silty Gravelly SAND
Stainless stickup is: 2.0'				7'-14.5': Silty SAND
12" ID Bore 0-19.88'				14.5'-16.5': Silty Sandy GRAVEL
medium Bentonite chunks				16.5'-33': Sandy GRAVEL
9.3'-202.3		50		33'-86.5': SAND
4 1/2" OD (4" ID) Type 304 Stainless				
steel riser: +2.0-216.98		100		86.5'-93.5': SAND
				(tr caliche at 86')
				93.5'-123': Silty SAND
				(caliche 108'-110')
Centralizers at top and bottom				123'-145': Sandy GRAVEL
of screen, then every 40'				
up hole.		150		145'-165': Sandy GRAVEL
				165'-209': Sandy GRAVEL
		200		
3/8 Bentonite Pellets 202.3-203.8				209'-217': Gravelly SAND
Filter Pack: Colorado Silica Sand,				
20-40 mesh 203.8'-257.3'				
SS 304 Screen 35', 10 slot		217'-278':		
SS 304 end cap 0.32	250	Silty Sandy GRAVEL		
(216.98'-252.30)				
257.3-326.6 Colorado		Water Table 217.4 ft, 11-14-98		
Silica Sand (4-10, 6-9, 8-12,				
8-16, 10-20,)				

Page <u>4</u> ² of <u>2</u>
Date: <u>11/6/98</u>

BHI-EE-189 (12/97)

BOREHOLE LOG

Boring or Well No.

899-W14-14

Sheet

1

of

6

Location East of 241-TX Tank farm / 200 WProject RCRA Drilling 1998 (cy)Prepared By J.M. Fawcote
(Sign/Print Name)Date 10/8/98Reviewed By EC Rapp / E.C. Ruffe
(Sign/Print Name)Date 11/8/98

Depth (0)	Sample		Graphic Log	Sample Description Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Comments Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
	Type and No.	Blows or Recovery			
10	cd 2, 3 cd 3, 4 cd 4, 5 cd 5, 6 cd 6, 7 cd 7, 8 cd 8, 9 cd 9, 10			0-4.5' Predominantly fill, is a gravelly sand (80% sand, 20% gravel) 4.5-7 m-dk bn, silty sand, silty gravelly sand mgs. 10-20% st, 60% to 70% sand. no rxn to HCl, it is moist, and appears to be the original soil/dirt horizon. becomes silty sand (40-60% basalt, poorly sorted, sub-angular, 7.5YR 5/3)	L, B are < detect. 10.5' End Shift 10/8/98 Driller says change at ~13' - but not shown in dirt
20	cd 10, 11 cd 11, 12 cd 12, 13 cd 13, 14 cd 14, 15 cd 15, 16 cd 16, 17 cd 17, 18 cd 18, 19 cd 19, 20 cd 20, 21 cd 21, 22 cd 22, 23 cd 23, 24 cd 24, 25 cd 25, 26 cd 26, 27 cd 27, 28 cd 28, 29 cd 29, 30 cd 30, 31 cd 31, 32 cd 32, 33 cd 33, 34 cd 34, 35 cd 35, 36 cd 36, 37 cd 37, 38 cd 38, 39 cd 39, 40 cd 40, 41 cd 41, 42 cd 42, 43 cd 43, 44 cd 44, 45 cd 45, 46 cd 46, 47 cd 47, 48 cd 48, 49 cd 49, 50 cd 50, 51 cd 51, 52 cd 52, 53 cd 53, 54 cd 54, 55 cd 55, 56 cd 56, 57 cd 57, 58 cd 58, 59 cd 59, 60 cd 60, 61 cd 61, 62 cd 62, 63 cd 63, 64 cd 64, 65 cd 65, 66 cd 66, 67 cd 67, 68 cd 68, 69 cd 69, 70 cd 70, 71 cd 71, 72 cd 72, 73 cd 73, 74 cd 74, 75 cd 75, 76 cd 76, 77 cd 77, 78 cd 78, 79 cd 79, 80 cd 80, 81 cd 81, 82 cd 82, 83 cd 83, 84 cd 84, 85 cd 85, 86 cd 86, 87 cd 87, 88 cd 88, 89 cd 89, 90 cd 90, 91 cd 91, 92 cd 92, 93 cd 93, 94 cd 94, 95 cd 95, 96 cd 96, 97 cd 97, 98 cd 98, 99 cd 99, 100 cd 100, 101 cd 101, 102 cd 102, 103 cd 103, 104 cd 104, 105 cd 105, 106 cd 106, 107 cd 107, 108 cd 108, 109 cd 109, 110 cd 110, 111 cd 111, 112 cd 112, 113 cd 113, 114 cd 114, 115 cd 115, 116 cd 116, 117 cd 117, 118 cd 118, 119 cd 119, 120 cd 120, 121 cd 121, 122 cd 122, 123 cd 123, 124 cd 124, 125 cd 125, 126 cd 126, 127 cd 127, 128 cd 128, 129 cd 129, 130 cd 130, 131 cd 131, 132 cd 132, 133 cd 133, 134 cd 134, 135 cd 135, 136 cd 136, 137 cd 137, 138 cd 138, 139 cd 139, 140 cd 140, 141 cd 141, 142 cd 142, 143 cd 143, 144 cd 144, 145 cd 145, 146 cd 146, 147 cd 147, 148 cd 148, 149 cd 149, 150 cd 150, 151 cd 151, 152 cd 152, 153 cd 153, 154 cd 154, 155 cd 155, 156 cd 156, 157 cd 157, 158 cd 158, 159 cd 159, 160 cd 160, 161 cd 161, 162 cd 162, 163 cd 163, 164 cd 164, 165 cd 165, 166 cd 166, 167 cd 167, 168 cd 168, 169 cd 169, 170 cd 170, 171 cd 171, 172 cd 172, 173 cd 173, 174 cd 174, 175 cd 175, 176 cd 176, 177 cd 177, 178 cd 178, 179 cd 179, 180 cd 180, 181 cd 181, 182 cd 182, 183 cd 183, 184 cd 184, 185 cd 185, 186 cd 186, 187 cd 187, 188 cd 188, 189 cd 189, 190 cd 190, 191 cd 191, 192 cd 192, 193 cd 193, 194 cd 194, 195 cd 195, 196 cd 196, 197 cd 197, 198 cd 198, 199 cd 199, 200 cd 200, 201 cd 201, 202 cd 202, 203 cd 203, 204 cd 204, 205 cd 205, 206 cd 206, 207 cd 207, 208 cd 208, 209 cd 209, 210 cd 210, 211 cd 211, 212 cd 212, 213 cd 213, 214 cd 214, 215 cd 215, 216 cd 216, 217 cd 217, 218 cd 218, 219 cd 219, 220 cd 220, 221 cd 221, 222 cd 222, 223 cd 223, 224 cd 224, 225 cd 225, 226 cd 226, 227 cd 227, 228 cd 228, 229 cd 229, 230 cd 230, 231 cd 231, 232 cd 232, 233 cd 233, 234 cd 234, 235 cd 235, 236 cd 236, 237 cd 237, 238 cd 238, 239 cd 239, 240 cd 240, 241 cd 241, 242 cd 242, 243 cd 243, 244 cd 244, 245 cd 245, 246 cd 246, 247 cd 247, 248 cd 248, 249 cd 249, 250 cd 250, 251 cd 251, 252 cd 252, 253 cd 253, 254 cd 254, 255 cd 255, 256 cd 256, 257 cd 257, 258 cd 258, 259 cd 259, 260 cd 260, 261 cd 261, 262 cd 262, 263 cd 263, 264 cd 264, 265 cd 265, 266 cd 266, 267 cd 267, 268 cd 268, 269 cd 269, 270 cd 270, 271 cd 271, 272 cd 272, 273 cd 273, 274 cd 274, 275 cd 275, 276 cd 276, 277 cd 277, 278 cd 278, 279 cd 279, 280 cd 280, 281 cd 281, 282 cd 282, 283 cd 283, 284 cd 284, 285 cd 285, 286 cd 286, 287 cd 287, 288 cd 288, 289 cd 289, 290 cd 290, 291 cd 291, 292 cd 292, 293 cd 293, 294 cd 294, 295 cd 295, 296 cd 296, 297 cd 297, 298 cd 298, 299 cd 299, 300 cd 300, 301 cd 301, 302 cd 302, 303 cd 303, 304 cd 304, 305 cd 305, 306 cd 306, 307 cd 307, 308 cd 308, 309 cd 309, 310 cd 310, 311 cd 311, 312 cd 312, 313 cd 313, 314 cd 314, 315 cd 315, 316 cd 316, 317 cd 317, 318 cd 318, 319 cd 319, 320 cd 320, 321 cd 321, 322 cd 322, 323 cd 323, 324 cd 324, 325 cd 325, 326 cd 326, 327 cd 327, 328 cd 328, 329 cd 329, 330 cd 330, 331 cd 331, 332 cd 332, 333 cd 333, 334 cd 334, 335 cd 335, 336 cd 336, 337 cd 337, 338 cd 338, 339 cd 339, 340 cd 340, 341 cd 341, 342 cd 342, 343 cd 343, 344 cd 344, 345 cd 345, 346 cd 346, 347 cd 347, 348 cd 348, 349 cd 349, 350 cd 350, 351 cd 351, 352 cd 352, 353 cd 353, 354 cd 354, 355 cd 355, 356 cd 356, 357 cd 357, 358 cd 358, 359 cd 359, 360 cd 360, 361 cd 361, 362 cd 362, 363 cd 363, 364 cd 364, 365 cd 365, 366 cd 366, 367 cd 367, 368 cd 368, 369 cd 369, 370 cd 370, 371 cd 371, 372 cd 372, 373 cd 373, 374 cd 374, 375 cd 375, 376 cd 376, 377 cd 377, 378 cd 378, 379 cd 379, 380 cd 380, 381 cd 381, 382 cd 382, 383 cd 383, 384 cd 384, 385 cd 385, 386 cd 386, 387 cd 387, 388 cd 388, 389 cd 389, 390 cd 390, 391 cd 391, 392 cd 392, 393 cd 393, 394 cd 394, 395 cd 395, 396 cd 396, 397 cd 397, 398 cd 398, 399 cd 399, 400 cd 400, 401 cd 401, 402 cd 402, 403 cd 403, 404 cd 404, 405 cd 405, 406 cd 406, 407 cd 407, 408 cd 408, 409 cd 409, 410 cd 410, 411 cd 411, 412 cd 412, 413 cd 413, 414 cd 414, 415 cd 415, 416 cd 416, 417 cd 417, 418 cd 418, 419 cd 419, 420 cd 420, 421 cd 421, 422 cd 422, 423 cd 423, 424 cd 424, 425 cd 425, 426 cd 426, 427 cd 427, 428 cd 428, 429 cd 429, 430 cd 430, 431 cd 431, 432 cd 432, 433 cd 433, 434 cd 434, 435 cd 435, 436 cd 436, 437 cd 437, 438 cd 438, 439 cd 439, 440 cd 440, 441 cd 441, 442 cd 442, 443 cd 443, 444 cd 444, 445 cd 445, 446 cd 446, 447 cd 447, 448 cd 448, 449 cd 449, 450 cd 450, 451 cd 451, 452 cd 452, 453 cd 453, 454 cd 454, 455 cd 455, 456 cd 456, 457 cd 457, 458 cd 458, 459 cd 459, 460 cd 460, 461 cd 461, 462 cd 462, 463 cd 463, 464 cd 464, 465 cd 465, 466 cd 466, 467 cd 467, 468 cd 468, 469 cd 469, 470 cd 470, 471 cd 471, 472 cd 472, 473 cd 473, 474 cd 474, 475 cd 475, 476 cd 476, 477 cd 477, 478 cd 478, 479 cd 479, 480 cd 480, 481 cd 481, 482 cd 482, 483 cd 483, 484 cd 484, 485 cd 485, 486 cd 486, 487 cd 487, 488 cd 488, 489 cd 489, 490 cd 490, 491 cd 491, 492 cd 492, 493 cd 493, 494 cd 494, 495 cd 495, 496 cd 496, 497 cd 497, 498 cd 498, 499 cd 499, 500 cd 500, 501 cd 501, 502 cd 502, 503 cd 503, 504 cd 504, 505 cd 505, 506 cd 506, 507 cd 507, 508 cd 508, 509 cd 509, 510 cd 510, 511 cd 511, 512 cd 512, 513 cd 513, 514 cd 514, 515 cd 515, 516 cd 516, 517 cd 517, 518 cd 518, 519 cd 519, 520 cd 520, 521 cd 521, 522 cd 522, 523 cd 523, 524 cd 524, 525 cd 525, 526 cd 526, 527 cd 527, 528 cd 528, 529 cd 529, 530 cd 530, 531 cd 531, 532 cd 532, 533 cd 533, 534 cd 534, 535 cd 535, 536 cd 536, 537 cd 537, 538 cd 538, 539 cd 539, 540 cd 540, 541 cd 541, 542 cd 542, 543 cd 543, 544 cd 544, 545 cd 545, 546 cd 546, 547 cd 547, 548 cd 548, 549 cd 549, 550 cd 550, 551 cd 551, 552 cd 552, 553 cd 553, 554 cd 554, 555 cd 555, 556 cd 556, 557 cd 557, 558 cd 558, 559 cd 559, 560 cd 560, 561 cd 561, 562 cd 562, 563 cd 563, 564 cd 564, 565 cd 565, 566 cd 566, 567 cd 567, 568 cd 568, 569 cd 569, 570 cd 570, 571 cd 571, 572 cd 572, 573 cd 573, 574 cd 574, 575 cd 575, 576 cd 576, 577 cd 577, 578 cd 578, 579 cd 579, 580 cd 580, 581 cd 581, 582 cd 582, 583 cd 583, 584 cd 584, 585 cd 585, 586 cd 586, 587 cd 587, 588 cd 588, 589 cd 589, 590 cd 590, 591 cd 591, 592 cd 592, 593 cd 593, 594 cd 594, 595 cd 595, 596 cd 596, 597 cd 597, 598 cd 598, 599 cd 599, 600 cd 600, 601 cd 601, 602 cd 602, 603 cd 603, 604 cd 604, 605 cd 605, 606 cd 606, 607 cd 607, 608 cd 608, 609 cd 609, 610 cd 610, 611 cd 611, 612 cd 612, 613 cd 613, 614 cd 614, 615 cd 615, 616 cd 616, 617 cd 617, 618 cd 618, 619 cd 619, 620 cd 620, 621 cd 621, 622 cd 622, 623 cd 623, 624 cd 624, 625 cd 625, 626 cd 626, 627 cd 627, 628 cd 628, 629 cd 629, 630 cd 630, 631 cd 631, 632 cd 632, 633 cd 633, 634 cd 634, 635 cd 635, 636 cd 636, 637 cd 637, 638 cd 638, 639 cd 639, 640 cd 640, 641 cd 641, 642 cd 642, 643 cd 643, 644 cd 644, 645 cd 645, 646 cd 646, 647 cd 647, 648 cd 648, 649 cd 649, 650 cd 650, 651 cd 651, 652 cd 652, 653 cd 653, 654 cd 654, 655 cd 655, 656 cd 656, 657 cd 657, 658 cd 658, 659 cd 659, 660 cd 660, 661 cd 661, 662 cd 662, 663 cd 663, 664 cd 664, 665 cd 665, 666 cd 666, 667 cd 667, 668 cd 668, 669 cd 669, 670 cd 670, 671 cd 671, 672 cd 672, 673 cd 673, 674 cd 674, 675 cd 675, 676 cd 676, 677 cd 677, 678 cd 678, 679 cd 679, 680 cd 680, 681 cd 681, 682 cd 682, 683 cd 683, 684 cd 684, 685 cd 685, 686 cd 686, 687 cd 687, 688 cd 688, 689 cd 689, 690 cd 690, 691 cd 691, 692 cd 692, 693 cd 693, 694 cd 694, 695 cd 695, 696 cd 696, 697 cd 697, 698 cd 698, 699 cd 699, 700 cd 700, 701 cd 701, 702 cd 702, 703 cd 703, 704 cd 704, 705 cd 705, 706 cd 706, 707 cd 707, 708 cd 708, 709 cd 709, 710 cd 710, 711 cd 711, 712 cd 712, 713 cd 713, 714 cd 714, 715 cd 715, 716 cd 716, 717 cd 717, 718 cd 718, 719 cd 719, 720 cd 720, 721 cd 721, 722 cd 722, 723 cd 723, 724 cd 724, 725 cd 725, 726 cd 726, 727 cd 727, 728 cd 728, 729 cd 729, 730 cd 730, 731 cd 731, 732 cd 732, 733 cd 733, 734 cd 734, 735 cd 735, 736 cd 736, 737 cd 737, 738 cd 738, 739 cd 739, 740 cd 740, 741 cd 741, 742 cd 742, 743 cd 743, 744 cd 744, 745 cd 745, 746 cd 746, 747 cd 747, 748 cd 748, 749 cd 749, 750 cd 750, 751 cd 751, 752 cd 752, 753 cd 753, 754 cd 754, 755 cd 755, 756 cd 756, 757 cd 757, 758 cd 758, 759 cd 759, 760 cd 760, 761 cd 761, 762 cd 762, 763 cd 763, 764 cd 764, 765 cd 765, 766 cd 766, 767 cd 767, 768 cd 768, 769 cd 769, 770 cd 770, 771 cd 771, 772 cd 772, 773 cd 773, 774 cd 774, 775 cd 775, 776 cd 776, 777 cd 777, 778 cd 778, 779 cd 779, 780 cd 780, 781 cd 781, 782 cd 782, 783 cd 783, 784 cd 784, 785 cd 785, 786 cd 786, 787 cd 787, 788 cd 788, 789 cd 789, 790 cd 790, 791 cd 791, 792 cd 792, 793 cd 793, 794 cd 794, 795 cd 795, 796 cd 796, 797 cd 797, 798 cd 798, 799 cd 799, 800 cd 800, 801 cd 801, 802 cd 802, 803 cd 803, 804 cd 804, 805 cd 805, 806 cd 806, 807 cd 807, 808 cd 808, 809 cd 809, 810 cd 810, 811 cd 811, 812 cd 812, 813 cd 813, 814 cd 814, 815 cd 815, 816 cd 816, 817 cd 817, 818 cd 818, 819 cd 819, 820 cd 820, 821 cd 821, 822 cd 822, 823 cd 823, 824 cd 824, 825 cd 825, 826 cd 826, 827 cd 827, 828 cd 828, 829 cd 829, 830 cd 830, 831 cd 831, 832 cd 832, 833 cd 833, 834 cd 834, 835 cd 835, 836 cd 836, 837 cd 837, 838 cd 838, 839 cd 839, 840 cd 840, 841 cd 841, 842 cd 842, 843 cd 843, 844 cd 844, 845 cd 845, 846 cd 846, 847 cd 847, 848 cd 848, 849 cd 849, 850 cd 850, 851 cd 851, 852 cd 852, 853 cd 853, 854 cd 854, 855 cd 855, 856 cd 856, 857 cd 857, 858 cd 858, 859 cd 859, 860 cd 860, 861 cd 861, 862 cd 862, 863 cd 863, 864 cd 864, 865 cd 865, 866 cd 866, 867 cd 867, 868 cd 868, 869 cd 869, 870 cd 870, 871 cd 871, 872 cd 872, 873 cd 873, 874 cd 874, 875 cd 875, 876 cd 876, 877 cd 877, 878 cd 878, 879 cd 879, 880 cd 880, 881 cd 881, 882 cd 882, 883 cd 883, 884 cd 884, 885 cd 885, 886 cd 886, 887 cd 887, 888 cd 888, 889 cd 889, 890 cd 890, 891 cd 891, 892 cd 892, 893 cd 893, 894 cd 894, 895 cd 895, 896 cd 896, 89				

BOREHOLE LOG

Boring or Well No. 299-W14-14 / B 8547

Sheet 2 of 6

Location ~50' East of 241-TX Tank Farm/200W

Project RCRA Drilling 1998

Prepared By L.D. Walker / L.D. Walker Date 10-22-98

(Sign/Print Name)

Reviewed By EC Rafuse / EC Rafuse

(Sign/Print Name)

Date 11/18/98

Depth (ft.)	Sample		Graphic Log	Sample Description Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Comments Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
	Type and No.	Blows or Recovery			
(80)					
	Odex				8 5/8" OD, CS casing
	↓			86' : tr caliche	8" odex bit = 9 1/8" bore
	Split Spoon #1	100%		86.5' → 93.5' : Sand (S) 100% sand	
	Odex			40% cse, 50% med, 10% fn; dry	86.5' → 88.0' : split spoon
90	↓			mod sorted; sub-angular; 50% qtz,	sample #1; 100% rec.
	Split Spoon #2	100%		30% basalt, 20% felds/other; no rxn to HCl.	(W14-14SS86)
	Odex			93.5' → 123' : Silty SAND (mS)	93.0' → 95.0' : Split Spoon
				(60% sand, 40% silt, tr gravel) Sand	sample #2; 100% rec.
100				tr med, 40% fn, 60% v.fn; 10YR6/3	(W14-14SS93)
				(pale brn) sl moist, well sorted - mod	OVM, LEL < detect
				sorted; strong rxn HCl - calcareous	
				108'-110' : Fragments of caliche and	Q, B, X < detect
110				v. fn pebs; 10% basalt, 80% qtz,	
				10% other - tr mica	
				120' : still mS, slightly more sand:	
120				80% sand, 20% silt	
				123' → 145' : Sandy GRAVEL (SG)	
				(70% gravel, 30% sand, tr silt)	
130				gravel tr sm. cob, 10% v.cse peb, 30%	
				cse peb, 40% med peb, 20% fn-v.fn	
				peb, sand 40% v.cse, 50% cse, 10%	
				med - v.fn; 10YR5/1 (gray); dry;	
				poorly sorted; sub round to sub ang;	
140				50% basalt, 20% qtzite, 30% granitic	138' → 140' : drilling indicates
				and other; weak rxn to HCl on	small cobbles
				silt fraction.	
				142' → 143' : 10% silt mixed with SG	
				145' : The sand fraction changes:	
150				145' → 165' : Sandy Gravel (SG)	
				(60% gravel, 40% sand, tr silt)	
				gravel similar to above, sand 10%	
				v.cse - cse, 70% med, 20% fn; Sand	OVM, LEL < detect
				80% qtz, 20% basalt & other, weak	
				rxn HCl	

BOREHOLE LOG

Boring or Well No. 299-W14-14 / B8547

Sheet 3 of 6

Location ~50' East of 241-TX Tank Farm; 200W

Project RCRA Drilling 1998

Prepared By L.D. Walker / L.D. Walker Date 10/23/98
(Sign/Print Name)Reviewed By EL Ramez / EC Refuse Date 11/18/98
(Sign/Print Name)

Depth (Ft.)	Sample		Graphic Log	Sample Description Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Comments Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
	Type and No.	Blows or Recovery			
(160)					
	Tubex (Odex)				8 5/8" OD, CS casing
					8" Odex bit; 9 1/8" bore
170				165' → 209': Sandy GRAVEL (sG) (40% gravel, 55% sand, 5% silt) gravel tr v. cse pcb, 20% cse pcb, 50% med pcb, 30% fn-v. fn, sand 10% v. cse-cse, 50% med, 40% fn-v. fn, 10YR6/2 (lt. brn gray); sl moist; poorly sorted; sub-round - some gravel g'round; gravel 30% basalt, 30% granitic, 40% meta + other, sand 70% qtz, 10% basalt, 20% felds + other, tr mica; no rxn HCl	185' → 186': Grab sample collected for first Bath tub sample. Sample # W14-14-185
180					
190	Grab Bath tub Sample Odex				
200	Grab Bath tub Sample Odex				196' → 197': Grab sample collected for second Bath tub sample Sample # W14-14-196
210				209' → 217': Gravelly SAND (gS) (15% gravel, 85% sand, tr silt) gravel similar to above; sand 10% v. cse-cse, 40% med, 40% fn, 10% v. fn; 10YR5/3 (brn) moist; med well sorted; gravel round, sand sub-ang to sub-round; sand 70% qtz, 30% other, no rxn HCl	OVM, LEL < detect.
220				217' → 278': Silty Sandy GRAVEL (msG) (50% gravel, 40% sand, 10% silt) gravel 10% cse pcb, 30% med pcb, 50% fn pcb, 10% v. fn pcb; sand 20% v. cse-cse, 40% med, 30% fn, 10% v. fn; 10YR5/3 (brn) poorly sorted; sub round gravel, sub ang. sand; mineral as above; tr mica no rxn HCl; sed. moist to wet.	a, B, Y < detect
230					

BOREHOLE LOG				Boring or Well No. <u>299-W14-14 / B8547</u>	
				Sheet <u>4</u> of <u>4</u>	
Location <u>~50' East of 241-TX Tank Farm / 200W</u> Project <u>RCRA Drilling 1998</u>					
Prepared By <u>L.D. Walker</u> Date <u>10-24-98</u> Reviewed By <u>EC Rafter</u> Date <u>11/18/98</u> <div style="display: flex; justify-content: space-between; font-size: small;"> (Sign/Print Name) (Sign/Print Name) </div>					
Depth Ft.	Sample		Graphic Log	Sample Description	Comments
(240)	Type and No.	Blows or Recovery		Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
	Tubex (Oder)			Silty Sandy GRAVEL (msG)	8 5/8" OD cs casing
				-as above	8" Oder bit; 9 1/8" borehole
250				248' → 249': msG with iron staining	
				5YR3/3 (dk reddish brown)	
				253' → 254': iron staining	
				5YR3/3	
				→ both stained areas strong rxn HCl	
260				260' → 262': msG with iron staining	10-24-98: water sample
				5YR3/3 - dk red. brn	collected; casing shoe at 265 ft.
	Water Sample				
270				sl. silt increase	
				278' - 360': Silty Sandy GRAVEL (msG)	Drill rate: 10 ft/20 min
280				(40% gravel, 35% sand, 25% silt); gravel	
				20% cse, 40% med. pb, 40% fn - v. fn pb,	
				sand is 30% v. cse - cse, 50% med, 30%	
			fn - v. fn; 10YR4/2 (dk grayish brown),	ce, f, & < detect	
290			wet; poorly sorted; gravel round to		
			sub round, sand sub round - sub ang,		
			sand 60% qtz, 15% basalt, 25% feld/other,		
			max gravel size ~ 30 mm; when dry, silt		
			has weak rxn to HCl.	OVM, LEL < detect	
300			298': tr clay	increase water production	
				drilling smoother ~ 300'	
				308': drill rate indicates	
				increase in gravel	
310					
	Water sample			10-26-98: Second water	
				sample collected; casing	
				shoe at 315 ft.	
			FeOx common, med rxn to HCl	W.L. = 210.5'	

BOREHOLE LOG

Boring or Well No. 29A-W14-14/88547Sheet 5 of 6Location ~50' East of 241-TX Tank Farm, 200WProject RCRA Drilling 1998

Prepared By

DC Weeks
(Sign/Print Name)

Date

10/27/98

Reviewed By

EC Ruffe
(Sign/Print Name)

Date

11/18/98

Depth (ft)	Sample		Graphic Log	Sample Description Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Comments Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
	Type and No.	Blows or Recovery			
320	Tubex (Odex)				8 3/4" OD CS casing
					8" OD EX bit; 9 1/8" borehole
330				FeOx common, mod rxn to HCl to weak.	OVM, LEL < detect
340				FeOx common, weak rxn to HCl	
					α B X < detectable
					Water sample at 348' (O&H)
350				FeOx common, weak rxn to HCl	End of shift 10/27/98
					10/28/98: Worn out drive shoe
					stop drilling at 357'
					Remove 20' of 8" casing
360				360' → 402': Sandy GRAVEL (sG) (70% gravel, 30% sand, tr silt)	Spectral gamma borehole log (HPGe and NaI): 0-345'
				gravel 10% v.cse - cse peb, 50% med peb, 40% fn - v.fn; sand 20% v.cse.	also Neutron: 0-215'
				20% cse, 40% med, 20% fn - v.fn;	
370				10YR 5/2 (grayish brown), wet, poorly sorted, sub-ang to sub-round; mineralogy	11-2-98: Resume drilling.
				mixed - 20% basalt, 30% granite, 25% granitic, 25% metamorph + other;	
				no rxn to HCl	
380					
390				388': sand content increases slightly	387': drilling a bit smoother
					α, β, X < detect.

<div style="display: flex; justify-content: space-between;"> WELL CONSTRUCTION SUMMARY REPORT 0502401 </div>				Start Date: <u>8/24/98</u> Finish Date: <u>9-9-98</u> Page <u>1</u> of <u>1</u>			
Specification No.: <u>0200X-SP-10001</u> Rev. No.: <u>1</u>		Well Name: <u>299-WIS-40</u> Temp. Well No.: <u>B8550</u>		Approximate Location: <u>105' West of 241-TX Rinkway 200</u>			
ECNs: <u>NA</u>		Other Companies: <u>CH2M Hill</u>		Geologist(s): <u>DC Weekes, Km Singleton</u> <u>L.D. Walker</u>			
Project: <u>RCRA Drilling 1998</u>		Drilling Company: <u>Layne Christensen</u>					
Driller: <u>M. Wraspic</u>		TEMPORARY CASING AND DRILL DEPTH					
*Size/Grade/Lbs. Per Ft.	Interval	Shoe O.D./I.D.	Auger:	DRILLING METHOD/HOLE DIAMETER			
<u>9" OD carbon steel (FJ)</u>	<u>0' - 124.5'</u>	<u>0.80' / 0.70'</u>	Cable Tool: <u>Drive barrel</u>	Diameter From <u>0'</u> to <u>125.5'</u>			
<u>8 5/8" OD CS (FJ)</u>	<u>0' - 262.3'</u>	<u>8 5/8" / 8"</u>	Air Rotary: <u>Odex</u>	Diameter From <u>0'</u> to <u>262.4'</u>			
_____	_____	_____	A.R. w/Sonic:	Diameter From _____ to _____			
_____	_____	_____	_____	Diameter From _____ to _____			
*Indicate Welded (W) - Flush Joint (FJ) Coupled (C) & Thread Design			Diameter From _____ to _____				
Note on water added: <u>oil at total depth (262')</u> <u>to keep fine sediment out of casing.</u>							
Drilling Fluid: <u>Air</u>							
Total Drilled Depth: <u>262.4</u>		Hole Dia @ TD: <u>9 1/2"</u>		Total Amt. Of Water Added During Drilling: <u>~300 gal.</u>			
Well Straightness Test Results: <u>NA</u>		Static Water Level: <u>218.08'</u>		Date: <u>9-10-98</u>			
GEOPHYSICAL LOGGING							
Sondes (type)	Interval	Date	Sondes (type)	Interval	Date		
<u>Spectral KUT</u>	<u>0 - 125</u>	<u>8/28/98</u>	<u>Spectral KUT</u>	<u>130' - 262'</u>	<u>9/4/98</u>		
<u>Neutron</u>	<u>0 - 125</u>	<u>8/28/98</u>	<u>Neutron</u>	<u>105' - 220'</u>	<u>9/4/98</u>		
COMPLETED WELL							
Size/Wt./Material	Depth	Thread	Slot Size	Type	Interval Annual Seal/Filter Pack	Volume	Mesh Size
<u>4" ID SS</u>	<u>+2.0' - 217.95'</u>	<u>FJ</u>	<u>NA</u>	<u>Portland Cement</u>	<u>0 - 10.1'</u>	<u>11.57 ft³</u>	<u>NA</u>
<u>4" ID SS wire wrap</u>	<u>217.95' - 253.08'</u>	<u>FJ</u>	<u>0.010-in</u>	<u>Bentonite Chips</u>	<u>10.1' - 195.4'</u>	<u>80.4 ft³</u>	<u>med/fin</u>
<u>4" ID SS</u>	<u>253.08' - 253.40'</u>	<u>FJ</u>	<u>NA</u>	<u>Bentonite Pellets</u>	<u>195.4' - 208.3'</u>	<u>3.72 ft³</u>	<u>1/4"</u>
_____	_____	_____	_____	<u>Silica Sand</u>	<u>208.3' - 262.4'</u>	<u>28.0 ft³</u>	<u>20-40</u>
OTHER ACTIVITIES							
Aquifer Test:		Date:		Well Abandoned:		Yes: No: Date:	
Description:				Description:			
WELL SURVEY DATA							
Date:				Protective Casing Elevation:			
Washington State Plane Coordinates:				Brass Cap Elevation:			
COMMENTS/REMARKS							
<u>CS = carbon steel; SS = stainless steel; Volume calc: cement = 1.285 x 9 = 11.57 ft³, Bentonite chips =</u> <u>0.69 x 116 = 80.4 ft³, Bentonite pellets: 0.62 x 6 = 3.72 ft³, 20-40 silica sand =</u> <u>1.12 x 25 = 28.0 ft³</u>							
Reported By: <u>L.D. Walker</u>				Reported By: <u>E.C. Rafuse</u>			
Title: <u>Geologist</u>		Date: <u>9-10-98</u>		Title: <u>Field Engineer (BNC)</u>		Date: <u>09/15/98</u>	
Signature: <u>L.D. Walker</u>				Signature: <u>E.C. Rafuse</u>			

BHI-EE-181 (12/97)

WELL SUMMARY SHEET				Page <u>1</u> of <u> </u>	
				Date: <u>9-10-98</u>	
Well ID: <u>B8550</u>		Well Name: <u>299-WIS-40</u>			
Location: <u>105' West of 241-TX Tank Farm, 200W</u>		Project: <u>RCRA Drilling 1998</u>			
Prepared By: <u>L.D. Walker</u>	Date: <u>9-10-98</u>	Reviewed By: <u>E.C. Ruffe</u>	Date: <u>9/15/98</u>		
Signature: <u>L.D. Walker</u>		Signature: <u>E.C. Ruffe</u>			
CONSTRUCTION DATA		Depth in Feet	GEOLOGIC/HYDROLOGIC DATA		
Description	Diagram		Graphic Log	Lithologic Description	
		0		0'-1' Backfill (Silty Sandy GRAVEL)	
				1'-2' SAND	
Portland Cement: 0'-10.1'				2'-7' SAND	
				7'-67' Sandy GRAVEL	
		25			
Bentonite Chips:		50			
10.1' - 195.4'					
		75		67'-80' SAND (ve-vf)	
				80'-97' SAND (m-vf)	
4 1/2" OD (4" ID) type 304					
stainless steel casing:					
+20' - 217.95'					
		100		97'-98' SAND	
				98'-98.3' Silty Sandy GRAVEL	
				98.3'-101' Slightly Silty SAND	
				101'-107' SILT	
				107'-113.5' Silty SAND	
		125		113.5'-118' Gravelly Sandy SILT	
				118'-125' Silty Gravelly SAND	
		125'-132' Silty Sand			

WELL SUMMARY SHEET					Page 1 st of 2
					Date: 9-10-98
Well ID: B8550		Well Name: 299-W15-40			
Location: 105' West of 241-TX Tank Farm, 200W		Project: RCRA Drilling 1998			
Prepared By: L.D. Walker	Date: 9-10-98	Reviewed By: E.C. Ruffe	Date: 09/15/98		
Signature: <i>L.D. Walker</i>		Signature: <i>E.C. Ruffe</i>			
CONSTRUCTION DATA		Depth in Feet	GEOLOGIC/HYDROLOGIC DATA		
Description	Diagram		Graphic Log	Lithologic Description	
		150		132'-167': Silty Sandy Gravel	
Bentonite Pellets:					
195.4'-208.3'		175		167'-183': Sandy Gravel	
20-40 mesh Silica Sand:					
208.3'-262.4'				183'-187': Silty Sand	
4 1/2" OD (4" ID) type 304 SS		200		187'-220': Silty Sandy Gravel	
continuous wire wrap 0.010-in					
slot screen: 217.95'-253.08'					
Bottom of 4 1/2" OD (4" ID) type 304 SS endcap at 253.40'		225		220'-262': Sandy Gravel	
9 1/2" borehole to 262.4'					
8 5/8" OD carbon steel casing to 262.3' - All temp.					
casing removed from the ground	250	Water Level = 218.08' (9-10-98)			
		TD = 262.4 Ft.			
Depths are measured from ground surface	275				

BOREHOLE LOG				Boring or Well No. <u>299-WIS-40/B8550</u>	
				Sheet <u>1</u> of <u>5</u>	
Location <u>105' West of 241-Tx Tank Farm, 200W</u>		Project <u>RCRA Drilling 1998</u>			
Prepared By <u>DC Weekes</u> <small>(Sign/Print Name)</small>		Date <u>8/29/98</u>		Reviewed By <u>Edward Rahn / Emma Rahn</u> <small>(Sign/Print Name)</small> Date <u>09/15/98</u>	

Depth (ft)	Sample Type and No.	Blows or Recovery	Graphic Log	Sample Description <small>Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl</small>	Comments <small>Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level</small>
		DB		0'-1': Backfill (Silty sandy GRAVEL)	9" OD casing with
				1'-20': SAND (s), tr gr, 20% vc-c, 20% m, 40% fvf, 10% silt; 10YR 4/3 dark brown (moist), 10YR 5/3 brown (dry), moist, moderately sorted, A-SA, 50% bas, 50% other, max part 3mm, no rxn to HCl	0.80' OD shoe
10				2'-7': SAND (s), tr gr, 40% vc-c, 10% m, 40% fvf, 10% silt, same wet color as above, 10YR 5/3 brown (dry), moderately sorted, A-SA, 60% bas, 40% other, max part 3/7mm, strong rxn to HCl, moist to wet	Started 8/24/98
20				7'-67': Sandy GRAVEL (sG), 60% grav, 35% sand, 5% silt, 10YR 4/3 dark brown (moist), 10YR 6/2 light brownish gray (dry), moist, max 10" grav is 70% bas, 30% other, some have partial CaCO ₃ coatings; sand is 40% vc-c, 20% m, 40% vf-f, A-SR, 70% bas, 30% other, v poorly sorted, strong rxn to HCl	End shift 8/24/98
30				silt increased to ~10% starting at 34 ft.	End of shift 8/25/98
40					
50					
60				from 55'-67' material is moister and is more consolidated, near saturation at 67'	
70				67'-80': SAND (s), 5% vfp, 40% vc-cs, 30% ms, 20% vf-fs, 5% silt, 10YR 6/2 light brownish gray (dry), moist, moderately sorted, A-SA, overall 80% quartz, silt, other, 20% bas, max 5mm, weak rxn to HCl (strong in spots)	End of shift 8/26/98
				Occasional vfs lens	0800-0900 hrs - LFL, GUM < Detect, O ₂ = 20.7 - Breathing zone @ well head

A-6000-382 (01/93)

BOREHOLE LOG

Boring or Well No. 299W/15-40/1855CSheet 2 of 5Location 105' West of 241-TX TANK FARM, 200WProject RCRA Drilling

Prepared By

Kevin Singleton
(Sign/Print Name)Date 8-27-98

Reviewed By

Edward Rabe/Edward Rabe
(Sign/Print Name)Date 09/15/98

Depth (ft)	Sample		Graphic Log	Sample Description Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Comments Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
	Type and No.	Blows or Recovery			
80	2 1/4" H-1 moisture 1 CaCO ₃			80'-97' SAND(S), 94% SAND - 50% ms, 50% vc-vf, 3% Gravel - VF-F pebbles, 3% silt, 10% 5/16 yellowish brown, moist, well to mod sorted, A-SR 75% quartz & feld, 25% Basalt & others. max 4mm, weak rx to HCL, <1% mica Occasional very fine sand stringers/lens 2-3" thick 90% vcs, 10% other silt weak rx to acid (non plastic)	
90	2 1/4" H-1 moisture 1 CaCO ₃			Q-85 90% SAND 7% GRAVEL 3% silt otherwise same as above, max gravel 1/4" - 1/2"	S. Spoon sample ~96-98 ~97' P.P.U./Early Palouse ~140kps - LEL, OUMK Detect
100	2 1/4" H-1 moisture 1 CaCO ₃			Gravel m-vf, subroundy, @ 90' same as 80' sample except. color 10% 4/4, dark yellowish brown 70% QH 12 30% Basalt	Cu = 20.8 in breathing zone and well head. 1 archive collected from split spoon
110	split spoon	194			
110	split spoon	213			
110	Go to next page				
120				97'-98. SAND(S) as above, CaCO ₃ content increasing - Strong rx to HCL 98-98.3 Silty-Gravelly SAND SANDY GRAVEL cm s.g. 9 45% GRAVEL 35% SAND, 20% silt, Gravel 10% VF-F pebble, SAND - 60% c-vcs, 30% fms 10% other, 20% silt, 10% 7/12, light gray poorly sorted, moist, A-SR, 60% Qtz & feld Feld 40% Basalt & others, Highly cemented very strong reaction to acid, iron oxide staining 7mm max - indurated	
130				98.3-101 Slightly Silty SAND cm S - 85% SAND - 85% fine to ms, 15% other, 10% 15% silt, 10% 6/8 brownish yellow, moist, well-sorted subang- ang, 85% Quartz & feld, 15% others - Strong reaction to acid, <1% mica 101-102 i (t) (M) 95% silt, 5% VFSAND, 10% 5/14-10% 6/12 light brownish gray - yellow brown, moist, well sorted 80-90% Qtz, max size .125mm, Strong rx to HCL	
140					
150					

A-5000-382 (01/93)

BOREHOLE LOG				Boring or Well No. <u>299-W15-40/B955C</u>	
				Sheet <u>3</u> of <u>5</u>	
Location <u>105' West of 241-TX Tank Farm, xxw</u>			Project <u>RCRA Drilling</u>		
Prepared By <u>[Signature] K.M. Singler</u> Date <u>8-28-98</u>			Reviewed By <u>[Signature] Edwina Butler</u> Date <u>09/15/98</u>		
Depth (Ft)		Sample Type and No. Blows or Recovery		Sample Description Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	
		Graphic Log		Comments Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level	
120	2 lith 1m/slow 1c/cog AS ABOVE AS ABOVE	DB		<u>107'-113.5' Silty SAND (m.s); 60% VES, 40% SILT, 10YR 5/4, BROWN, moist, well sorted, A-SA, 70% Qtz & Feld, 30% other, MAX Particle 0.1mm, Strong Reaction to HCL</u> <u>abundant caliche @ 111'</u>	
125.5	AS ABOVE		TO 125.5	<u>113.5'-118' Gravely SANDY Silt (gmM), 30% GRAVEL, 30% SAND, 40% SILT, 10YR 6/4 light yellow brown moist, poorly sorted, E-A, Matrix med. CaCO₃ & 0.1% 20-25% Basalt. Gravel is mostly basalt. MAX size FP (8mm). Very strong rx to acid. Portion of sample highly indurated & cemented.</u> <u>118'-125.5' Silty Gravely SAND, 15% GRAVEL, 50% SAND (VF-FS) sand m-v; 35% silt, 10YR 5/4, Brown, moist, poorly sorted, A-SR, 70% Qtz & Feld - 30% Basalt & others, MAX size 8mm (FP). Strong RX. Caliche stringer abundant</u> <u>@ ~123' 7% GRAVEL increases to large ANG BASALT clast to 10mm.</u>	
				<u>End of shift 8/29/98</u> <u>8-31-98</u> <u>All 9" OD cs temp. casing removed from the ground. Re-drill with Odex method, temp casing 8 5/8" OD. Geo log will resume at 125 Ft - see page 4</u>	

A-6000-382 (01/93)

BOREHOLE LOG

Boring or Well No. 299-W15-40/88550

Sheet 4 of 5

Location 105' West of 241-TX Tank Farm, 200W

Project RCRA Drilling 1998

Prepared By L.D. Walker / L.D. Walker Date 9-2-98
(Sign/Print Name)Reviewed By Edmund R. / Edmund R. Date 09/15/98
(Sign/Print Name)

Depth	Sample		Graphic Log	Sample Description Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Comments Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
	Type and No.	Blows or Recovery			
(120)					
					8 7/8" OD CS casing
				125' - 132': Silty Sand (mS) (75% Sand, 25% silt, tr gravel); Sand is 20% med, 40% fn, 40% v. fn; 10YR 6/3 (pale brown); moist; med sorted, sub-angular; 70% qtz, 15% feld, 15% basalt and other, strong rxn HCl - calcareous	8" odcx bit; 9 1/2" borehole 9-2-98 Smooth drilling - no large gravel OVM, LEL < detectable
130	Air Rotary (Odcx)	NA		132' - 167': Silty Sandy Gravel (mSG) (50% gravel, 30% sand, 20% silt); gravel 20% med peb, 40% fn, 40% v. fn; sand 10% v. cse, 50% cse, 40% m-v. fn; 10YR 4/2 (dk grayish brown), moist, poorly sorted; gravel sub. round and 80% basalt, sand sub-ang, and 70% qtz, 30% other, Max cobble size ~100mm, strong rxn to HCl.	Drilling indicates tr cobbles 4-5 in. diameter.
140				150' - silt content decreasing	
150					
160					
				167' - 183': Sandy Gravel (sG) (60% gravel, 35% sand, 5% silt) gravel tr sm. cob, 10% cse-v. cse peb, 60% med peb, 30% fn-v. fn; sand 20% v. cse-cse, 30% med, 30% fn, 20% v. fn; 10YR 7/2 (lt. gray), dry, poorly sorted; gravel sub round, sand sub-ang; gravel 50% basalt, 30% qtz, 20% other sand 80% qtz, 20% basalt and other, tr mica, no rxn HCl.	End Shift 9/2/98
170				183' - 187': Silty Sand (mS) (5% gravel, 30% med, 60% sand, 35% silt) 10YR 6/2 (lt brn gray), moist	B, X < detectable
180				187' - 220': Silty Sandy Gravel (mSG) Similar to above - silt content 10%	
190					

A-6000-382 (01/93)

BOREHOLE LOG				Boring or Well No. <u>299-W15-40 / B8550</u>	
				Sheet <u>5</u> of <u>5</u>	
Location <u>105' West of 241 TX/TY Tank Farm, 200W</u>			Project <u>RCRA Drilling 1998</u>		
Prepared By <u>L.D. Walker</u> Date <u>9-3-98</u> <small>(Sign/Print Name)</small>			Reviewed By <u>Edmund R. R. / EDWARD R. R.</u> Date <u>09/15/98</u> <small>(Sign/Print Name)</small>		

Depth	Sample		Graphic Log	Sample Description	Comments
	Type and No.	Blows or Recovery		Group Name, Group Symbol, Grain Size Distribution, Soil Classification, Color, Moisture Content, Sorting, Angularity, Mineralogy, Max Particle Size, Reaction to HCl	Depth of Casing, Drilling Rate, Casing Size & Type, Bit Size, Water Level
(200)					
	Air Rotary (Olex)	NA			8 5/8" OD CS casing
					8" Olex bit - 9 1/2" borehole
					OVM, LEL < detectable
210					End shift 9-3-98
					215' - drill cuttings come up wet
220					220' - 262': Sandy Gravel (SG) (60% gravel, 35% sand, 5% silt); gravel + cse pbb, 20% med, 50% fn, 30% v. fn pbb; sand 20% v cse, 30% cse, 40% med, 10% fn-v. fn; 10YR 4/3 (brown), wet, poorly sorted, gravel sub round, sand is sub ang-sub round; gravel and sand 70% qtz and granitics, 20% basalt, 10% other; max gravel size ≈ 30 mm, no rxh to HCl.
230					
					OVM, LEL < detectable
240					
250					250' - cuttings are only moist
260					EW 9-4-98 TD = 262' below ground 262.4' surface
270					

A-6000-382 (01/93)

Appendix B

Physical and Chemical Properties Data

Appendix B

Physical and Chemical Properties Data

This appendix includes the results of laboratory testing for pH, conductivity, particle size distribution, moisture content, total inorganic carbon, and major cations and anions from 1:1 water:sediment extractions.

Moisture content was measured as weight loss after drying an aliquot of the bulk sample at 105°C for 24 h or until weight was constant for two consecutive measurements.

Total inorganic carbon was measured from an air-dried aliquot of the <2mm fraction. The sample was combusted in a total carbon analyzer at 975°C and the weight of evolved carbon dioxide was determined and converted to calcium carbonate equivalent. Reagent grade calcium carbonate was used as a standard. Instrument precision was ± 3 weight percent based on replicate measurements of reagent grade calcium carbonate.

Exchangeable cations were determined by inductively coupled plasma analysis (ICP) after exchange with an ammonium acetate solution. Twenty grams of air dried sediment were mixed with 50 mL of 1M ammonium acetate for 16 h. Electrical conductivity, pH, and major cations and anions were determined from a 1:1 water:sediment extract. The concentrations of major cations were measured with ICP, anions were determined by ion chromatography (IC), and alkalinity was measured by titration. Electrical conductivity and pH were determined from unfiltered aliquots and cations and anions from aliquots of solution filtered through 0.45 μm membranes.

Particle size analysis was done using standard sieve techniques. Samples were oven dried at 105°C for 24 h (or until weight was constant for two consecutive measurements) prior to analysis.

Table B.1. Moisture Content, pH, and Conductivity of Sediment Samples from Wells 299-W10-26, 299-W14-13, and 299-W15-40

Depth (ft)	Moisture Content (wt%)	pH	Conductivity (μ S/cm)
299-W10-26			
25-26	4.99	8.81	101 @ 22.6°C
69-70	4.88	8.61	164 @ 22.6°C
299-W14-13			
25-26	2.67	9.02	77 @ 22.5°C
69-70	5.07	9.00	204? @ 22.4°C
299-W15-40			
5	12.2	8.73	162 @ 25°C
10	3.1	8.9	126 @ 25°C
15	3.4	8.75	117 @ 25°C
20	5.3	8.63	126 @ 25°C
25	4.2	8.57	177 @ 24.9°C
30	5.2	8.54	224 @ 25.1°C
35	4.4	8.54	225 @ 25°C
40	4.8	8.51	329 @ 21.7°C
45	4.6	8.75	107 @ 21.8°C
50	5.1	8.8	105 @ 21.9°C
55	6.3	8.68	141 @ 22°C
60	7.3	8.72	117 @ 22°C
65	9.7	8.72	114 @ 22°C
68	6.3	8.74	142 @ 22.1°C
70	4.6	8.77	122 @ 22.2°C
75	5.1	8.84	96 @ 22.2°C
80	4.6	8.7	139 @ 22.2°C
85	8.4	8.76	126 @ 22.2°C
90	4.8	8.71	134 @ 22.3°C
95	4.8	8.73	127 @ 22.3°C
100	6.0	8.58	177 @ 22.4°C
110	8.6	8.64	168 @ 22.3°C
115	7.2	8.64	159 @ 22.3°C

Table B.2. Particle Size Distribution for Samples from Wells 299-W10-26, 299-W14-13, 299-W14-14, and 299-W15-40

Particle Size (mm)	Sieve	Weight of Dry Sample (g)	Weight Percent
299-W10-26—Depth 25 to 26 ft			
2	10	189.32	87
0.88	20	17.15	8.0
0.425	40	4.31	2.0
0.25	60	2.44	1.0
0.106	140	2.33	1.0
0.075	200	0.64	0
<0.075	Pan	2.45	1.0
Total		218.64	100.0
299-W10-26—Depth 69 to 70 ft			
2	10	22.24	19.0
0.88	20	21.95	18.0
0.425	40	41.81	35.0
0.25	60	18.1	15.0
0.106	140	11.04	9.0
0.075	200	1.56	1.0
>0.075	Pan	3.08	3.0
Total		119.78	100.0
299-W14-14—Depth 25 - 26 ft			
2	10	835.3	96.2
0.88	20	29.5	3.4
0.425	40	2.11	0.2
0.25	60	0.04	0.0
0.106	140	0.2	0.0
0.075	200	0.1	0.0
<0.075	Pan	0.64	0.1
Total		867.89	100.0
299-W14-14—Depth 69 - 70 ft			
2	10	6.5	2.7
0.88	20	28.95	11.9
0.425	40	87.87	36.1
0.25	60	73.63	30.2
0.106	140	32.56	13.4
0.075	200	3.94	1.6
<0.075	Pan	10.04	4.1
Total		243.49	100.0

Particle Size (mm)	Sieve	Weight of Dry Sample (g)	Weight Percent
299-W14-13—Depth 25 to 26 ft			
2	10	237.82	80.7
0.88	20	38.95	13.2
0.425	40	11.91	4.0
0.25	60	2.84	1.0
0.106	140	1.53	0.5
0.075	200	0.44	0.1
<0.075	Pan	1.25	0.4
Total		294.74	100.0
299-W14-13—Depth 69 - 70 ft			
2	10	11.14	7.2
0.88	20	20.15	13.0
0.425	40	62.71	40.6
0.25	60	40.18	26.0
0.106	140	15.94	10.3
0.075	200	1.28	0.8
<0.075	Pan	3.08	2.0
Total		154.48	100.0
299-W15-40—Depth 25 to 26 ft			
2	10	701.24	57.3
0.88	20	255.05	20.8
0.425	40	129.81	10.6
0.25	60	50.04	4.1
0.106	140	43.53	3.6
0.075	200	12.74	1.0
<0.075	Pan	31.38	2.6
Total		1223.79	100.0
299-W15-40—Depth 69 to 70 ft			
2	10	30.22	3.1
0.88	20	187.15	19.4
0.425	40	350.11	36.3
0.25	60	205.9	21.4
0.106	140	122.44	12.7
0.075	200	8.56	0.9
<0.075	Pan	59.15	6.1
Total		963.53	100.0

Table B.3. Major Cation and Anion Concentrations from Extracts of Samples from Wells 299-W10-26, 299-W14-13, and 299-W15-40

299-W10-26									
Depth (ft)	Cations (mg/L)						Total Cations (meq/L)	Monovalent Cations (%)	Divalent Cations (%)
	Ba	Ca	K	Mg	Na	Sr			
25-26	0.028	4.99	0.38	0.82	18.87	0.022	1.15	72.35	27.65
69-70	0.068	12.56	0	2.7	19.03	0.066	1.68	49.30	50.70

Depth (ft)	Total Inorganic Carbon (wt%)	Alkalinity as CaCO ₃	Anions (mg/L)				Anions (meq/L)	Electrical Balance (%)
			F	Cl	NO ₃	SO ₄		
25-26	--	36.27	0.40	1.53	<0.06	11.84	1.04	10.25
69-70	--	42.51	0.64	2.42	7.50	29.75	1.69	-0.78

299-W14-13									
Depth (ft)	Cations (mg/L)						Total Cations (meq/L)	Monovalent Cations (%)	Divalent Cations (%)
	Ba	Ca	K	Mg	Na	Sr			
25-26	0	3.32	0	0.69	12.62	0.017	0.772	71.13	28.87
69-70	0	5.59	0	1.14	43.37	0.025	2.260	83.48	16.52

Depth (ft)	Total Inorganic Carbon (wt%)	Alkalinity as CaCO ₃	Anions (mg/L)				Anions (meq/L)	Electrical Balance (%)
			F	Cl	NO ₃	SO ₄		
25-26	--	33.41	0.387	1.025	<0.06	5.261	0.827	-6.9
69-70	--	37.55	3.674	7.525	4.021	35.708	1.965	13.95

Table B.3. (contd)

299-W15-40									
Depth (ft)	Cations (mg/L)						Total Cations (meq/L)	Monovalent Cations (%)	Divalent Cations (%)
	Ba	Ca	K	Mg	Na	Sr			
5	0.08	12.74	0.00	1.27	12.54	0.14	1.29	42.28	57.72
10	0.00	1.48	0.00	0.14	15.98	0.00	0.78	89.06	10.94
15	0.03	4.12	0.00	0.33	7.16	0.01	0.54	57.16	42.84
20	0.01	7.84	0.00	0.55	6.61	0.03	0.72	39.67	60.33
25	0.06	12.43	0.00	1.24	9.92	0.05	1.16	37.33	62.67
30	0.01	16.03	0.00	1.18	13.18	0.10	1.47	38.94	61.06
35	0.01	23.82	0.28	2.36	11.64	0.16	1.90	27.03	72.97
40	0.00	33.83	1.60	6.21	12.08	0.24	2.77	20.44	79.56
45	0.03	9.33	0.00	1.79	3.80	0.05	0.78	21.18	78.82
50	0.05	8.53	1.34	1.63	4.15	0.06	0.78	27.66	72.34
55	0.00	11.80	1.30	2.43	9.90	0.08	1.25	36.99	63.01
60	0.00	9.60	4.15	1.79	3.49	0.07	0.89	29.10	70.90
65	0.04	9.78	4.81	1.87	6.18	0.06	1.04	37.82	62.18
68	0.05	12.13	6.89	2.41	10.10	0.09	1.42	43.30	56.70
70	0.15	9.70	7.13	1.93	8.10	0.07	1.18	45.26	54.74
75	0.15	9.48	4.83	1.65	8.18	0.05	1.09	43.90	56.10
80	0.00	11.63	7.78	2.35	13.23	0.07	1.55	49.97	50.03
85	0.05	11.37	5.94	2.21	8.18	0.06	1.26	40.32	59.68
90	0.00	10.78	6.20	2.52	15.00	0.06	1.56	52.06	47.94
95	0.00	10.53	5.49	2.15	9.70	0.06	1.27	44.40	55.60
100	0.00	16.73	2.63	3.69	9.48	0.10	1.62	29.60	70.40
110	0.00	16.69	1.77	3.75	15.28	0.11	1.85	38.28	61.72
115	0.00	13.97	4.17	5.59	10.53	0.13	1.72	32.74	67.26
120	0.00	14.59	0.58	6.91	8.15	0.15	1.67	22.13	77.87
125	0.00	11.04	0.00	4.54	13.01	0.09	1.49	37.93	62.07

Table B.3. (contd)

Depth (ft)	Total Inorganic Carbon (wt%)	Alkalinity as CaCO ₃	Anions (mg/L)				Anions (meq/L)	Electrical Balance (%)
			F	Cl	NO ₃	SO ₄		
5	--	48.45	0.69	2.60	3.81	11.01	1.37	-5.96
10	--	29.35	0.41	0.78	<0.06	4.92	0.73	6.15
15	--	45.26	0.26	0.61	<0.06	6.15	1.06	-64.60
20	--	31.20	0.32	0.84	<0.06	16.05	1.00	-31.84
25	--	30.16	0.22	1.38	0.98	32.48	1.35	-15.17
30	--	121.93	0.34	1.81	<0.06	46.65	3.48	-81.09
35	--	44.03	0.33	7.51	2.54	54.37	2.28	-18.32
40	--	44.43	0.33	59.20	8.33	50.07	3.75	-30.11
45	--	17.04	0.20	3.41	2.84	9.27	0.69	12.72
50	--	26.21	0.27	1.22	2.66	10.50	0.83	-7.10
55	--	20.21	0.47	1.91	6.09	19.20	0.98	24.48
60	--	29.46	0.21	1.67	3.55	12.10	0.96	-7.65
65	--	23.86	0.18	3.57	4.35	10.01	0.87	17.83
68	--	30.54	0.25	6.87	8.10	21.19	1.39	2.31
70	--	23.28	0.20	4.04	4.23	11.46	0.90	27.43
75	--	13.77	0.29	5.14	2.05	12.18	0.72	40.79
80	--	36.02	0.27	6.36	4.06	15.25	1.30	17.77
85	--	14.16	0.24	9.81	6.42	15.32	1.00	23.39
90	--	25.34	0.27	2.04	5.60	13.28	0.95	48.96
95	--	30.11	0.20	4.41	6.09	15.60	1.16	8.72
100	--	21.91	0.47	8.21	12.58	32.07	1.57	3.42
110	--	40.39	0.24	6.68	7.61	34.08	1.84	0.66
115	--	26.86	0.79	7.85	12.93	27.16	1.57	9.12
120	--	45.92	0.89	8.51	16.45	24.20	1.97	-16.76
125	--	28.03	0.69	5.48	13.95	11.85	1.22	19.80

Table B.4. Cation Exchange Capacity and CaCO₃ Content for Samples from Well 299-W15-40

Depth (ft)	Cation Exchange Capacity (meq/100 g)	Divalent Cations (%)	CaCO ₃ Content (wt%)
25	8.25	88.77	1.10
30	7.90	89.47	1.16
40	9.13	91.79	2.81
45	8.51	92.05	2.17
55	8.27	91.73	1.38
65	10.05	91.50	3.56
68	5.60	93.46	3.68
75	4.60	98.47	1.91
95	6.10	96.05	1.91
100	5.87	97.50	3.46
110	5.56	97.12	5.19
120	8.54	95.90	18.99

Appendix C

Geophysical Logs

Appendix C

Geophysical Logs

This appendix contains the borehole geophysical logs obtained from boreholes 299-W10-26, 299-W14-13, 299-W14-14, and 299-W15-40. The logs were run by Waste Management Federal Services Northwest, Inc. and log data analyses were completed by Three Rivers Scientific Company. Included with the logs are Log Header sheets, Acceptance QA Processing data, and Log Analysis Summary Reports.

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Log Header

Project: RCRA Drilling – FY1998

Well: 299 - W10 - 26

Log Type: HPGe Spectral Gamma Ray

Borehole Information

Well ID	<u>B8548</u>	Water Depth	<u>217.0</u> ft	Total Depth	<u>262.0</u> ft
Elevation Reference	<u>Ground</u>	Elevation	<u>n/a</u> ft		
Depth Reference	<u>Ground Surface</u>	Casing Stickup	<u>3.15</u> ft		
Casing Diameter	<u>8.625</u> in	Depth Interval	<u>0 to 262.0</u> ft	Thickness	<u>0.313</u> in
Casing Diameter	<u> </u> in	Depth Interval	<u> </u> ft	Thickness	<u> </u> in

Logging Information

Log Type:	HPGe Spectral Gamma Ray		
Company	Waste Management Federal Services NW		
Date/Archive File Name	Aug 22, 1998 H2W10026		
Logging Engineers	<u>J.Meisner</u>	<u>K.Reynolds</u>	
Instrument Series	RLSG3.1		
Logging Unit	RLS2		
Depth Interval	0 to 205 ft		Prefix B209
	202 to 262 ft & 90 to 100 ft		Prefix B210
Instrument Calibration Date	Sep 11, 1998		
Calibration Report	WHC-SD-EN-TI-292, Rev. 0		

Analysis Information

Company	Three Rivers Scientific
Analyst	Russ Randall
Date	December 20, 1998
Notes	<u>No man made radionuclides were detected.</u>

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 22, 1998

Borehole: 299-W10-26 (B8548)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 22, 1998

Borehole: 299-W10-26 (B8548)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 22, 1998

Borehole: 299-W10-26 (B8548)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Acceptance QA Processing

Project: RCRA Drilling - FY1998

Log Date: Aug. 22, 1998

Borehole: 299-W10-26 (B8548)

Compare Main Log & Repeat

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Log Analysis Summary Report

Project: RCRA Drilling - FY1998
Log Type: HPGe Spectral Gamma Ray

Well ID: 299-W10-26
Log Dates: Aug 22, 1998

General Notes:

Total gamma is a response to formation lithology for the entire depth logged.

The system dead-time limit was not exceeded (less than 5%) for the borehole survey.

System Performance Verify: The pre- and post-log verification was performed using coleman #2 mantle, and passed the equipment performance check. The maximum FWHM for the 583 keV gamma ray photo peak for the survey date was 2.49 keV. The maximum acceptable FWHM resolution is 3.10 keV for probe RLSG3.1 on the log date.

Repeat Interval: The repeat intervals, 90 to 100 feet and 252 to 261 feet, agrees with the main log within acceptable limits, refer to the Acceptance QA Processing plots.

Environmental Corrections: The KUT concentrations have been corrected for casing attenuation (entire well) and water inside the casing (below 217 feet) for a centralized detector configuration. No casing correction was applied to the total gamma due to Compton downscatter interference.

Radionuclides:

No man-made radionuclides were detected, However, using a factor of 4 summing technique Cs-137 was identified only at the surface to 1.5 feet and a maximum reading of 0.5 pCi/g. There are no man-made plots provided since the normal pass experiences the Cs-137 below detection threshold.

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey **Waste Management Federal Services NW**

Log Header

Project: RCRA Drilling – FY1998

Well: 299 - W14 - 13

Log Type: HPGe Spectral Gamma Ray

Borehole Information

Well ID <u>B8549</u>	Water Depth <u>193.4</u> ft	Total Depth <u>254.2</u> ft
Elevation Reference <u>Ground</u>	Elevation <u>n/a</u> ft	
Depth Reference <u>Ground Surface</u>	Casing Stickup <u>4.12</u> ft	
Casing Diameter <u>8</u> in	Depth Interval <u>0 to 253.5</u> ft	Thickness <u>0.312</u> in
Casing Diameter <u> </u> in	Depth Interval <u> </u> ft	Thickness <u> </u> in

Logging Information

Log Type	HPGe Spectral Gamma Ray	
Company	Waste Management Federal Services NW	
Date/Archive File Name	Aug 28, 1998	H2W14013
Logging Engineers	J. Meisner	Jones
Instrument Series	RLSG3.1	
Logging Unit	RLS2	
Depth Interval	0 to 200 ft	Prefix B211
	197.5 to 253 ft & 110 to 120 ft	Prefix B212
Instrument Calibration Date	Sep 11, 1998	
Calibration Report	WHC-SD-EN-TL-292, Rev. 0	

Analysis Information

Company	Three Rivers Scientific
Analyst	Russ Randall
Date	December 21, 1998
Notes	Man-made radionuclides identified are Cs-137, Co-60, and Eu-154. Cs-137 maximum observed reading is 1.0 pCi/g at 4.75 feet. Co-60 maximum observed reading is 0.27 pCi/g at 91.25 feet and Eu-154 maximum observed reading is 1.7 pCi/g at 91.75 feet.

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 28, 1998

Borehole: 299-W14-13 (B8549)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 28, 1998

Borehole: 299-W14-13 (B8549)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 28, 1998

Borehole: 299-W14-13 (B8549)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma-Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 28, 1998

Borehole: 299-W14-13 (B8549) Man-Made Radio-Isotopes of Concern

Analysis by: Three Rivers Scientific

RLS Spectral Gamma-Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 28, 1998

Borehole: 299-W14-13 (B8549) Man-Made Radio-Isotopes of Concern

Analysis by: Three Rivers Scientific

RLS Spectral Gamma-Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug. 28, 1998

Borehole: 299-W14-13 (B8549) Man-Made Radio-Isotopes of Concern

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Acceptance QA Processing

Project: RCRA Drilling - FY1998
Borehole: 299-W14-13 (B8549)

Log Date: Aug. 28, 1998
Compare Main Log & Repeat

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Log Analysis Summary Report

Project: RCRA Drilling - FY1998
Log Type: HPGe Spectral Gamma Ray

Well ID: 299-W14-13
Log Dates: Aug 28, 1998

General Notes:

Total gamma is, in general, a response to formation lithology for the entire depth logged, since the level of contamination identified is so low a concentration.

The system dead-time limit was not exceeded (less than 5%) for the borehole survey.

System Performance Verify: The pre- and post-log verification was performed using coleman #2 mantle, and passed the equipment performance check. The maximum FWHM for the 583 keV gamma ray photo peak for the survey date was 2.42 keV. The maximum acceptable FWHM resolution is 3.10 keV for probe RLSG3.1 on the log date.

Repeat Interval: The repeat intervals, 110 to 120 feet and 240 to 250 feet, agrees with the main log within acceptable limits, refer to the Acceptance QA Processing plots.

Environmental Corrections: The KUT concentrations have been corrected for casing attenuation (entire well) and water inside the casing (below 193.4 feet) for a centralized detector configuration. No casing correction was applied to the total gamma due to Compton downscatter interference.

Radionuclides:

Three man-made radionuclides were detected; and these are Cs-137, Co-60, and Eu-154. Cs-137 was identified only over a small interval centered at 4.75 feet, with a maximum reading of 1.0 pCi/g. Both Co-60 and Eu-154 were identified over a deeper interval. Co-60 was identified from 90 to 96 feet and from 110 to 112 feet, with a maximum reading of 0.29 pCi/g at 90 feet. Eu-154 was identified from 90 to 92 feet near detection threshold (based upon a summing technique identification is positive) with a maximum reading of 1.7 pCi/g at 92 feet.

Analysis by: Three Rivers Scientific

RLS Spectral Gamma-Ray Borehole Survey

Waste Management Federal Services NW

Log Header

Project: RCRA Drilling – FY1999

Well: 299 - W14 - 14

Log Type: HPGe Spectral Gamma-Ray

Borehole Information

Well ID <u>B8547</u>	Water Depth <u>217.75</u> ft	Total Depth <u>443.0</u> ft
Elevation Reference <u>Not Available</u>	Elevation <u>667 approx</u> ft	
Depth Reference <u>Ground Surface</u>	Casing Stickup <u>2.7</u> ft	
Casing Diameter <u>12</u> in	Depth Interval <u>0 to 19.4</u> ft	Thickness <u>0.39</u> in
Casing Diameter <u>8</u> in	Depth Interval <u>0 to 442.3</u> ft	Thickness <u>0.31</u> in

Logging Information

Log Type:	HPGe Spectral Gamma Ray		
Company	Waste Management Federal Services NW		
Date/Archive File Name	Nov 7, 1998 H2W14014		
Logging Engineers	<u>A. Pearson, J. Meisner</u>		
Instrument Series	RLSG3.1		
Logging Unit	RLS2		
Depth Interval	0 to 139 ft	Prefix B223	100sec/0.5ft
	135 to 270 ft	Prefix B224	100sec/0.5ft
	267 to 330 ft	Prefix B225	100sec/0.5ft
	70 to 130 ft	Prefix B226	1 ft/min
	112 to 120 ft	Prefix B226	100sec/0.5ft
	200 to 240 ft	Prefix B226	1 ft/min
	325 to 344 ft	Prefix B227	100sec/0.5ft
	325 to 442 ft	Prefix B228	1 ft/min
	400 to 442 ft	Prefix B228	100sec/0.5ft
Instrument Calibration Date	325 to 442 ft	Prefix B229	100sec/0.5ft
	Sep 11, 1998		
Calibration Report	WHC-SD-EN-TI-292, Rev. 0		

Analysis Information

Company	Three Rivers Scientific
Analyst	Randall Price
Date	Nov 17, 1998
Notes <u>Cs-137 was identified near the surface (4 to 7 ft) with a maximum concentration of 7 pCi/g.</u>	

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999

Log Date: Nov. 7, 1998

Borehole: 299-W14-14 (B8547)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

Plot_Ge1fpm_N1.jnb

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999 Log Date: Nov. 7, 1998
Borehole: 299-W14-14 (B8547) Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific
Plot_Ge1fpm_N2.jnb

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999 Log Date: Nov. 7, 1998
Borehole: 299-W14-14 (B8547) Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

Plot_Ge1fpm_N3.jnb

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999 Log Date: Nov. 7, 1998
Borehole: 299-W14-14 (B8547) Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

Plot_Ge1fpm_N4.jnb

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999

Log Date: Nov. 7, 1998

Borehole: 299-W14-14 (B8547)

Natural Radionuclides & Cs-137

Analysis by: Three Rivers Scientific

Plot_Ge100s_CsNat_1.jnb

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999

Log Date: Nov. 7, 1998

Borehole: 299-W14-14 (B8547)

Natural Radionuclides & Cs-137

Analysis by: Three Rivers Scientific

Plot_Ge100s_CsNa1_2.jnb

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999

Log Date: Nov. 7, 1998

Borehole: 299-W14-14 (B8547)

Natural Radionuclides & Cs-137

Analysis by: Three Rivers Scientific

Plot_Ge100s_CsNat1_3.jnb

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999
Borehole: 299-W14-14 (B8547)

Log Date: Nov. 7, 1998
Natural Radionuclides & Cs-137

Analysis by: Three Rivers Scientific

Plot_Ge100s_CsNat1_4.jnb

RLS Spectral Gamma-Ray Borehole Survey

Acceptance QA Processing

Project: RCRA Drilling - FY1999
Borehole: 299-W14-14 (B8547)

Log Date: Nov. 7, 1998
Compare Slow Main, Repeat,
and Fast Main

Plot_Ge100s_Ge1fpm_QC2.jnb

RLS Spectral Gamma-Ray Borehole Survey

Acceptance QA Processing

Project: RCRA Drilling - FY1999
Borehole: 299-W14-14 (B8547)

Log Date: Nov. 7, 1998
Compare Slow Main & Repeat
with Fast Main & Repeat

Plot_Ge100s_Ge1fpm_QC1.jnb

RLS Spectral Gamma-Ray Borehole Survey

Waste Management Federal Services NW

Log Analysis Summary Report

Project: RCRA Drilling - FY1999
Log Type: HPGe Spectral Gamma-Ray

Well ID: 299-W14-14
Last Log Date: Nov 7, 1998

General Notes:

Total gamma is a response to man made gamma-ray emitters and formation lithology from surface to 7 feet, and a function of formation lithology below 7 feet. The main logging speed was 100 seconds (Real Time) at 0.5 feet increments. At selected intervals (70-130, 200-240, and 325-442 ft) were logged at a faster rate of one (1) foot per minute. Comparison of the slow and fast logging speed are presented on additional plots.

Deviations in the interval from 344 to 345 feet between data sets B227 and B228 are probably the result of formation changes (borehole washout) that occurred between the two logging dates (Oct 30 and Nov 7, 1998). Consequently the decrease in gamma ray activity at 345 feet is likely not the result of lithologic changes in the subsurface.

The system dead-time limit was not exceeded (less than 5%) for the borehole survey.

System Performance Verify: The pre- and post-log verification was performed using coleman #2 mantle, and passed the equipment performance check. The maximum FWHM for the 583 keV gamma ray photo peak for the survey dates was 2.40 keV. The maximum acceptable FWHM resolution is 3.10 keV for probe RLSG3.1 on the log dates.

Repeat Interval: The repeat interval, 325-344 and 400-422 ft, agree with the main log within acceptable limits, refer to the Acceptance QA Processing plots.

Environmental Corrections: The KUT and man made radionuclide concentrations have been corrected for casing attenuation (entire well) and water inside the casing (below 217.75 ft) for a centralized detector configuration. No casing correction was applied to the total gamma due to Compton downscatter interference.

Radionuclides:

Cs-137 was identified near the surface (4 to 7 ft) with a maximum concentration of 7 pCi/g at 5 feet. No other man made radionuclides were detected.

Analysis by: Three Rivers Scientific

Nal Spectral Gamma-Ray Borehole Survey
Waste Management Federal Services NW

Log Header

Project: RCRA Drilling – FY1999

Well: 299 - W14 - 14

Log Type: Sodium-Iodide (NaI) Spectral Gamma-Ray

Borehole Information

Well ID <u>B8547</u>	Water Depth <u>217.75</u> ft	Total Depth <u>443.0</u> ft
Elevation Reference <u>Not Available</u>	Elevation <u>667 approx</u> ft	
Depth Reference <u>Ground Surface</u>	Casing Stickup <u>2.7</u> ft	
Casing Diameter <u>12</u> in	Depth Interval <u>0 to 19.4</u> ft	Thickness <u>0.39</u> in
Casing Diameter <u>8</u> in	Depth Interval <u>0 to 442.3</u> ft	Thickness <u>0.31</u> in

Logging Information

Log Type:	HPGe Spectral Gamma Ray		
Company	Waste Management Federal Services NW		
Date/Archive File Name	Oct 30, 1998	H2W14014	
Logging Engineers	<u>A. Pearson</u>		
Instrument Series	RLSG3.1		
Logging Unit	RLS2		
Depth Interval	0 to 200 ft	Prefix N270	1 ft/min
	195 to 344 ft	Prefix N271	1 ft/min
	90 to 130 ft	Prefix N271 (repeat)	
Instrument Calibration Date	Aug 5, 1998		
Calibration Report	WHC-SD-EN-TI-292, Rev. 0		

Analysis Information

Company	Three Rivers Scientific
Analyst	Randall Price
Date	Nov 17, 1998
Notes	<u>Cs-137 was identified near the surface (4 to 6 ft). Amplifier gain was adjusted to process spectra for KUT concentrations.</u>

Nal Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999

Log Date: Nov. 7, 1998

Borehole: 299-W14-14 (B8547)

Natural Radionuclides & Cs-137

Analysis by: Three Rivers Scientific

Plot_Nal_CsNat1_1.jnb

Nal Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999
 Borehole: 299-W14-14 (B8547)

Log Date: Nov. 7, 1998
 Natural Radionuclides & Cs-137

Analysis by: Three Rivers Scientific

Plot_Nal_CsNat_2.jnb

Nal Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1999
Borehole: 299-W14-14 (B8547)

Log Date: Nov. 7, 1998
Natural Radionuclides & Cs-137

Analysis by: Three Rivers Scientific

Plot_Nal_CsNat_3.jnb

NaI Spectral Gamma-Ray Borehole Survey

Waste Management Federal Services NW

Log Analysis Summary Report

Project: RCRA Drilling - FY1999 Well ID: 299-W14-14
Log Type: Sodium-Iodide (NaI) Spectral Gamma-Ray Log Date: Oct 30, 1998

General Notes:

Total gamma is a response to man made gamma-ray emitters and formation lithology from surface to 7 feet, and a function of formation lithology below 7 feet. The main spectral gamma ray log survey was a high resolution HPGe probe at 100 seconds per 0.5 foot increments. Comparison of the NaI and HPGe spectral gamma ray surveys are presented on additional plots.

The amplifier gain (coefficient to convert MCA channels to energy in keV) was adjusted to position the potassium gamma ray peak (1461 keV) in the spectra window for NaI processing. Resulting in an excellent agreement with the high resolution HPGe survey. However, excessive gain changes in two spectra (75.75 & 325.25 ft) prohibited calculation of valid KUT concentrations and the two spectra were excluded on the presentation plots

The system dead-time limit was not exceeded (less than 5%) for the borehole survey.

Repeat Interval: The repeat interval, 90-130 and 195-200 ft, shows good agreement with the main log.

Environmental Corrections: The KUT concentrations have been corrected for casing attenuation (entire well) and water inside the casing (below 217.75 ft) for a centralized detector configuration. No casing correction was applied to the total gamma due to Compton downscatter interference.

Radionuclides:

Cs-137 (661 keV) was identified near the surface (4 to 6 ft) by increased count rate in the 590 to 715 keV energy window. The energy window count rates (above 40 c/s) are shown on the results plot.

Analysis by: Three Rivers Scientific

Moisture Borehole Survey
Waste Management Federal Services NW

Log Header

Project: RCRA Drilling – FY1999

Well: 299 - W14 - 14

Log Type: Moisture

Borehole Information

Well ID <u>B8547</u>	Water Depth <u>217.75</u> ft	Total Depth <u>443.0</u> ft
Elevation Reference <u>Not Available</u>	Elevation <u>667 approx</u> ft	
Depth Reference <u>Ground Surface</u>	Casing Stickup <u>2.7</u> ft	
Casing Diameter <u>12</u> in	Depth Interval <u>0 to 19.4</u> ft	Thickness <u>0.39</u> in
Casing Diameter <u>8</u> in	Depth Interval <u>0 to 442.3</u> ft	Thickness <u>0.31</u> in

Logging Information

Log Type:	HPGe Spectral Gamma Ray	
Company	Waste Management Federal Services NW	
Date/Archive File Name	Oct 28, 1998 H2W14014	
Logging Engineers	<u>A. Pearson, J. Meisner</u>	
Instrument Series	RLSG3.1	
Logging Unit	RLS2	
Depth Interval	15 to 115 ft	Prefix MS67
	100 to 217.5 ft	Prefix MS68
	210 to 217 ft	Prefix MS68 (repeat)
	200 to 210 ft	Prefix MS69 (repeat)
Instrument Calibration Date	Dec 18, 1997	
Calibration Report	WHC-SD-EN-TI-306, Rev. 0	

Analysis Information

Company	Three Rivers Scientific
Analyst	Randall Price
Date	Nov 17, 1998
Notes <u>Calibration coefficients for 8 inch borehole applied after casing thickness correction to compute volume percent moisture.</u>	

Moisture & KUT - Survey

Waste Management Federal Services Inc., Northwest Operations

Project: RCRA Drilling - 98

Log Date : November 7, 1998

Borehole: 299-W14-14 (B8547)

Analysis by: Three Rivers Scientific

Plot_Moist_Ge100s_KUT1.jnb

Moisture & KUT - Survey

Waste Management Federal Services Inc., Northwest Operations

Project: RCRA Drilling - 98

Log Date : November 7, 1998

Borehole: 299-W14-14 (B8547)

Analysis by: Three Rivers Scientific

Plot_Moist_Ge100s_KUT2.jnb

Moisture Borehole Survey
Waste Management Federal Services NW

Log Analysis Summary Report

Project: RCRA Drilling - FY1999
Log Type: Moisture

Well ID: 299-W14-14
Log Date: Oct 28, 1998

General Notes:

The moisture log was run in the single casing interval above the water table (19 to 217 ft). The moisture (volume percent) is plotted with the HPGe survey results (total gamma and K, U, T concentrations).

System Performance Verification: The pre- and post-log verification was performed using the instrument carrier. The pre-log reading and post-log readings were identical at 755 c/s.

Repeat Interval: The repeat intervals, 100-115 and 200-217 ft, show good agreement with the main log.

Environmental Corrections: The moisture has been corrected for casing attenuation before applying the 8 inch borehole calibration coefficients.

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Log Header

Project: RCRA Drilling – FY1998

Well: 299 - W15 - 40

Log Type: HPGe Spectral Gamma Ray

Borehole Information

Well ID	<u>B8550</u>	Water Depth	<u>217</u> ft	Total Depth	<u>265.8</u> ft
Elevation Reference	<u>Ground</u>	Elevation	<u>n/a</u> ft		
Depth Reference	<u>Ground Surface</u>	Casing Stickup	<u>3.5</u> ft		
Casing Diameter	<u>8625</u> in	Depth Interval	<u>0 to 265.8</u> ft	Thickness	<u>0.3125</u> in
Casing Diameter	_____ in	Depth Interval	_____ ft	Thickness	_____ in

Logging Information

Log Type:	HPGe Spectral Gamma Ray	
Company	Waste Management Federal Services NW	
Date/Archive File Name	Sep 4, 1998	H2W15040
Logging Engineers	<u>B.Marks</u>	
Instrument Series	RLSG3.1	
Logging Unit	RLS2	
Depth Interval	0 to 124 ft	Prefix B213
	105 to 262 ft	Prefix B214
Instrument Calibration Date	Sep 11, 1998	
Calibration Report	WHC-SD-EN-TI-292, Rev. 0	

Analysis Information

Company	Three Rivers Scientific	
Analyst	Russ Randall	
Date	December 29, 1998	
Notes	<u>No man made radionuclides were detected. Evidence for radon pumping exists for the separate logging dates. (August 28 and September 4).</u>	

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998 Log Date: Aug 28 & Sep 4, 1998
Borehole: 299-W15-40 (B8550) Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug 28 & Sep 4, 1998

Borehole: 299-W15-40 (B8550)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Project: RCRA Drilling - FY1998

Log Date: Aug 28 & Sep 4, 1998

Borehole: 299-W15-40 (B8550)

Naturally Occurring Radionuclides

Analysis by: Three Rivers Scientific

RLS Spectral Gamma Ray Borehole Survey

Acceptance QA Processing

Project: RCRA Drilling - FY1998
Borehole: 299-W15-40 (B8550)

Log Date: Aug 28 & Sep 4, 1998
Compare Main Log, Repeat, & Relog

RLS Spectral Gamma Ray Borehole Survey

Waste Management Federal Services NW

Log Analysis Summary Report

Project: RCRA Drilling - FY1998
Log Type: HPGe Spectral Gamma Ray

Well ID: 299-W15-40
Log Dates: Aug 28 & Sep 4, 1998

General Notes:

Total gamma is a response to formation lithology for the entire depth logged.

The system dead-time limit was not exceeded (less than 5%) for the borehole survey.

System Performance Verify: The pre- and post-log verifications were performed using coleman #2 mantle, and passed the equipment performance check. The maximum FWHM for the 583 keV gamma ray photo peak for both survey dates was 2.44 keV. The maximum acceptable FWHM resolution is 3.10 keV for probe RLSG3.1 on the log date.

Repeat Interval: The repeated intervals also contain what is labeled as relog sections since the full logging run spanned two separate days. The 1st pass was repeated over 100 to 112 feet. The 2nd log to completion relogged from 105 to 125 feet, and then this 2nd logging pass was also repeated near the bottom from 247 to 262 feet. All repeated intervals agree within acceptable limits, refer to the Acceptance QA Processing plots. Evidence for radon pumping differences between the separate logging days is clear in the uranium repeat, and since the different levels of radon are real, the gross is also affected.

Environmental Corrections: The KUT concentrations have been corrected for casing attenuation (entire well) and water inside the casing (below 217 feet) for a centralized detector configuration. No casing correction was applied to the total gamma due to Compton downscatter interference.

Radionuclides:

No man-made radionuclides were detected, even using a factor of 4 summing technique.

Appendix D

Groundwater Analytical Data

Appendix D

Groundwater Analytical Data

This appendix contains analytical results from five groundwater samples collected from 265, 316, 348, 404, and 442 ft bgs during drilling of well 299-W14-14. Columns 6 and 7 in this appendix contain qualifiers that should be considered when using the analytical values. The definition of the qualifiers are given below.

- U Undetected at the detection limit.
- C Inorganics - blank contamination is above the practical quantitation limit.
- B Organics - compound was found in the blank (blank contamination); inorganics - result is less than the practical quantitation limit.
- J Organics - the result is estimated and less than the practical quantitation limit.
- D Adjusted dilution factor.
- E Inorganics - estimated value due to interference.
- H Hold time exceeded.

Table D.1. Groundwater Analysis of Five Samples from Well 299-W14-14

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
265 ft Depth								
Tritium	Y	10/24/98	893	pCi/L			181	259
Cesium-137	Y	10/24/98	1.64	pCi/L	U		2.08	2.08
Strontium-90	Y	10/24/98	-0.0193	pCi/L	U		0.266	0.266
Cobalt-60	Y	10/24/98	-0.819	pCi/L	U		2.68	2.68
Gross alpha	Y	10/24/98	0.503	pCi/L	U		0.636	0.639
Gross beta	Y	10/24/98	135	pCi/L			6.01	13.5
Potassium-40	Y	10/24/98	-25.4	pCi/L	U		60.5	60.5
Beryllium-7	Y	10/24/98	-5.91	pCi/L	U		31.8	31.8
Ruthenium-106	Y	10/24/98	-7.64	pCi/L	U		22.7	22.7
Cesium-134	Y	10/24/98	-2.04	pCi/L	U		2.32	2.32
Technetium-99	Y	10/24/98	554	pCi/L			13.1	72
Antimony-125	Y	10/24/98	-1.51	pCi/L	U		5.18	5.18
Europium-155	Y	10/24/98	3.55	pCi/L	U		4.75	4.75
Europium-152	Y	10/24/98	-2.38	pCi/L	U		5.5	5.5
Iodine-129	Y	10/24/98	0.042	pCi/L	U		0.304	0.304
Europium-154	Y	10/24/98	3.15	pCi/L	U		7	7
Aluminum	Y	10/24/98	20.6	µg/L	U			
Iron	Y	10/24/98	139	µg/L				
Magnesium	Y	10/24/98	22,700	µg/L				
Manganese	Y	10/24/98	36.3	µg/L				
Nickel	Y	10/24/98	10.8	µg/L	U			
Potassium	Y	10/24/98	5,410	µg/L				
Silver	Y	10/24/98	5	µg/L	U			
Sodium	Y	10/24/98	37,300	µg/L				
Strontium (elemental)	Y	10/24/98	262	µg/L				
Antimony	Y	10/24/98	33	µg/L	U			
Barium	Y	10/24/98	64.9	µg/L				
Beryllium	Y	10/24/98	0.5	µg/L	U			
Cadmium	Y	10/24/98	2.6	µg/L	U			
Chromium	Y	10/24/98	2.7	µg/L	U			
Cobalt	Y	10/24/98	2.6	µg/L	B			
Copper	Y	10/24/98	2.9	µg/L	U			
Vanadium	Y	10/24/98	15.9	µg/L				
Zinc	Y	10/24/98	40.3	µg/L				
Calcium	Y	10/24/98	66,300	µg/L				
Turbidity	Y	10/24/98	0.81	NTU				
Tritium	N	10/24/98	865	pCi/L			181	258
Cesium-137	N	10/24/98	-0.189	pCi/L	U		2.27	2.27
Strontium-90	N	10/24/98	-0.107	pCi/L	U		0.291	0.292
Cobalt-60	N	10/24/98	-0.624	pCi/L	U		1.77	1.77
1,4-Dichlorobenzene	N	10/24/98	0.17	µg/L	U			
1,2-Dichloroethane	N	10/24/98	0.12	µg/L	U			
Ethyl cyanide	N	10/24/98	1.8	µg/L	U			
4-Methyl-2-Pentanone	N	10/24/98	0.24	µg/L	U			
Toluene	N	10/24/98	0.08	µg/L	U			

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Tetrahydrofuran	N	10/24/98	1.5	µg/L	U			
Gross alpha	N	10/24/98	1.1	pCi/L	J		0.814	0.824
Gross beta	N	10/24/98	117	pCi/L			5.4	10.7
Tetrachloroethene	N	10/24/98	0.11	µg/L	U			
Xylenes (total)	N	10/24/98	0.78	µg/L	U			
Potassium-40	N	10/24/98	6.95	pCi/L	U		36.6	36.6
Beryllium-7	N	10/24/98	-11.3	pCi/L	U		38	38
Ruthenium-106	N	10/24/98	1.51	pCi/L	U		21.3	21.3
Cesium-134	N	10/24/98	-0.741	pCi/L	U		2.21	2.21
Technetium-99	N	10/24/98	556	pCi/L			13.2	72.2
Antimony-125	N	10/24/98	5.8	pCi/L	U		5.8	5.8
Europium-155	N	10/24/98	-5.93	pCi/L	U		5.59	5.59
Europium-152	N	10/24/98	-3.08	pCi/L	U		5.92	5.92
Sulfate	N	10/24/98	31.3	mg/L	D			
Iodine-129	N	10/24/98	0.177	pCi/L	U		0.315	0.315
Europium-154	N	10/24/98	3.17	pCi/L	U		7.35	7.35
cis-1,2-Dichloroethylene	N	10/24/98	0.13	µg/L	U			
trans-1,2-Dichloroethylene	N	10/24/98	0.05	µg/L	U			
Chloride	N	10/24/98	36.1	mg/L	CD			
Fluoride	N	10/24/98	0.531	mg/L				
Carbon tetrachloride	N	10/24/98	180	µg/L	D			
Acetone	N	10/24/98	0.21	µg/L	U			
Chloroform	N	10/24/98	4	µg/L	J			
1-Butanol	N	10/24/98	2.8	µg/L	U			
Benzene	N	10/24/98	0.12	µg/L	U			
1,1,1-Trichloroethane	N	10/24/98	0.13	µg/L	U			
Vinyl chloride	N	10/24/98	0.18	µg/L	U			
Methylenechloride	N	10/24/98	0.16	µg/L	U			
Carbon disulfide	N	10/24/98	0.8	µg/L	J			
1,1-Dichloroethane	N	10/24/98	0.13	µg/L	U			
2-Butanone	N	10/24/98	0.61	µg/L	U			
1,1,2-Trichloroethane	N	10/24/98	0.11	µg/L	U			
Trichloroethene	N	10/24/98	0.4	µg/L	J			
Alkalinity	N	10/24/98	87.9	mg/L				
Conductivity	N	10/24/98	687	µmhos/cm				
Nitrogen in Nitrite	N	10/24/98	0.017	mg/L	U	H		
Nitrogen in Nitrate	N	10/24/98	51	mg/L	CD	H		
pH Measurement	N	10/24/98	7.8	pH				
Total dissolved solids	N	10/24/98	573	mg/L				
Temperature	N	10/24/98	20.8	Deg C				
Total organic carbon	N	10/24/98	0.902	mg/L	B			
Turbidity	N	10/24/98	10.6	NTU				

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
316 ft Depth								
Tritium	Y	10/26/98	5,380	pCi/L			344	580
Cesium-137	Y	10/26/98	0.311	pCi/L	U		2.3	2.3
Strontium-90	Y	10/26/98	-0.0593	pCi/L	U		0.309	0.312
Cobalt-60	Y	10/26/98	0.885	pCi/L	U		2.37	2.37
Gross alpha	Y	10/26/98	0.517	pCi/L	U		0.564	0.566
Gross beta	Y	10/26/98	26.3	pCi/L			2.79	3.64
Potassium-40	Y	10/26/98	0.447	pCi/L	U		39.9	39.9
Beryllium-7	Y	10/26/98	0.0757	pCi/L	U		38.8	38.8
Ruthenium-106	Y	10/26/98	-6.45	pCi/L	U		22.2	22.2
Cesium-134	Y	10/26/98	-1.35	pCi/L	U		2.44	2.44
Technetium-99	Y	10/26/98	78.6	pCi/L			6.78	22.4
Antimony-125	Y	10/26/98	0.572	pCi/L	U		5.02	5.02
Europium-155	Y	10/26/98	-4.3	pCi/L	U		5.94	5.94
Europium-152	Y	10/26/98	-1.85	pCi/L	U		6.06	6.06
Iodine-129	Y	10/26/98	-0.0461	pCi/L	U		0.232	0.233
Europium-154	Y	10/26/98	5.74	pCi/L	U		8.17	8.17
Aluminum	Y	10/26/98	23.7	µg/L	B			
Iron	Y	10/26/98	117	µg/L				
Magnesium	Y	10/26/98	17,500	µg/L				
Manganese	Y	10/26/98	47.1	µg/L				
Nickel	Y	10/26/98	10.8	µg/L	U			
Potassium	Y	10/26/98	4,930	µg/L				
Silver	Y	10/26/98	5	µg/L	U			
Sodium	Y	10/26/98	13,100	µg/L				
Strontium (elemental)	Y	10/26/98	194	µg/L				
Antimony	Y	10/26/98	33	µg/L	U			
Barium	Y	10/26/98	43.4	µg/L				
Beryllium	Y	10/26/98	0.5	µg/L	U			
Cadmium	Y	10/26/98	2.6	µg/L	U			
Chromium	Y	10/26/98	6.3	µg/L	B			
Cobalt	Y	10/26/98	2.4	µg/L	U			
Copper	Y	10/26/98	2.9	µg/L	U			
Ruthenium-106	N	10/26/98	0.453	pCi/L	U		25.6	25.6
Beryllium-7	N	10/26/98	15.8	pCi/L	U		44.1	44.1
Potassium-40	N	10/26/98	16.6	pCi/L	U		59.9	59.9
Xylenes (total)	N	10/26/98	0.78	µg/L	U			
Tetrachloroethene	N	10/26/98	0.11	µg/L	U			
Gross beta	N	10/26/98	24.8	pCi/L			2.88	3.67
Gross alpha	N	10/26/98	1.71	pCi/L	J		0.99	1.01
Tetrahydrofuran	N	10/26/98	1.5	µg/L	U			
Toluene	N	10/26/98	0.08	µg/L	U			
4-Methyl-2-Pentanone	N	10/26/98	0.24	µg/L	U			
Ethyl cyanide	N	10/26/98	1.8	µg/L	U			
1,2-Dichloroethane	N	10/26/98	0.12	µg/L	U			
1,4-Dichlorobenzene	N	10/26/98	0.17	µg/L	U			

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Cobalt-60	N	10/26/98	0.416	pCi/L	U		2.44	2.44
Strontium-90	N	10/26/98	0.0169	pCi/L	U		0.317	0.319
Cesium-137	N	10/26/98	0.879	pCi/L	U		2.29	2.29
1,1,2-Trichloroethane	N	10/26/98	0.11	µg/L	U			
2-Butanone	N	10/26/98	0.61	µg/L	U			
1,1-Dichloroethane	N	10/26/98	0.13	µg/L	U			
Carbon disulfide	N	10/26/98	0.7	µg/L	J			
Methylenechloride	N	10/26/98	0.16	µg/L	U			
Vinyl chloride	N	10/26/98	0.18	µg/L	U			
1,1,1-Trichloroethane	N	10/26/98	0.13	µg/L	U			
Benzene	N	10/26/98	0.12	µg/L	U			
Turbidity	N	10/26/98	14.1	NTU				
Total organic carbon	N	10/26/98	1.39	mg/L				
Temperature	N	10/26/98	21.5	Deg C				
Total dissolved solids	N	10/26/98	353	mg/L				
pH Measurement	N	10/26/98	7.64	pH				
Nitrogen in Nitrate	N	10/26/98	9.35	mg/L	CD			
Nitrogen in Nitrite	N	10/26/98	0.034	mg/L	UD			
Conductivity	N	10/26/98	382	µmhos/cm				
Alkalinity	N	10/26/98	105	mg/L				
Trichloroethene	N	10/26/98	1	µg/L	J			
1-Butanol	N	10/26/98	2.8	µg/L	U			
Chloroform	N	10/26/98	4	µg/L	J			
Acetone	N	10/26/98	0.21	µg/L	U			
Carbon tetrachloride	N	10/26/98	380	µg/L	D			
Fluoride	N	10/26/98	0.322	mg/L				
Chloride	N	10/26/98	51.2	mg/L	CD			
trans-1,2-Dichloroethylene	N	10/26/98	0.05	µg/L	U			
cis-1,2-Dichloroethylene	N	10/26/98	0.13	µg/L	U			
Europium-154	N	10/26/98	-4.33	pCi/L	U		7.1	7.1
Iodine-129	N	10/26/98	0.13	pCi/L	U		0.324	0.324
Sulfate	N	10/26/98	35.5	mg/L	D			
Europium-152	N	10/26/98	-0.105	pCi/L	U		6.36	6.36
Europium-155	N	10/26/98	-2.37	pCi/L	U		5.63	5.63
Antimony-125	N	10/26/98	-0.137	pCi/L	U		6.97	6.97
Technetium-99	N	10/26/98	81.2	pCi/L			6.85	22.7
Cesium-134	N	10/26/98	-3.91	pCi/L	U		2.78	2.78
Tritium	N	10/26/98	5,750	pCi/L			354	607
Vanadium	Y	10/26/98	16.6	µg/L				
Zinc	Y	10/26/98	24.3	µg/L				
Calcium	Y	10/26/98	50,900	µg/L				
Turbidity	Y	10/26/98	0.46	NTU				

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
348 ft Depth								
Tritium	Y	10/27/98	9,010	pCi/L			433	843
Cesium-137	Y	10/27/98	-0.717	pCi/L	U		1.87	1.87
Strontium-90	Y	10/27/98	0.448	pCi/L	U		0.4	0.409
Cobalt-60	Y	10/27/98	-0.264	pCi/L	U		1.59	1.59
Gross alpha	Y	10/27/98	1.48	pCi/L	J		0.885	0.902
Gross beta	Y	10/27/98	12.6	pCi/L			2.22	2.46
Potassium-40	Y	10/27/98	-26.4	pCi/L	U		31.6	31.6
Beryllium-7	Y	10/27/98	-12.2	pCi/L	U		35.4	35.4
Ruthenium-106	Y	10/27/98	-5.64	pCi/L	U		22.6	22.6
Cesium-134	Y	10/27/98	-2.11	pCi/L	U		2.31	2.31
Technetium-99	Y	10/27/98	31.9	pCi/L			5.8	18.2
Gross beta	Y	10/27/98	13	pCi/L			2.22	2.51
Gross alpha	Y	10/27/98	0.563	pCi/L	U		0.586	0.589
Cobalt-60	Y	10/27/98	1.13	pCi/L	U		2.99	2.99
Strontium-90	Y	10/27/98	0.0837	pCi/L	U		0.351	0.352
Cesium-137	Y	10/27/98	1.75	pCi/L	U		2.44	2.44
Tritium	Y	10/27/98	8,420	pCi/L			419	799
Turbidity	N	10/27/98	15.1	NTU				
Total organic carbon	N	10/27/98	0.577	mg/L	B			
Temperature	N	10/27/98	21.4	Deg C				
Total dissolved solids	N	10/27/98	336	mg/L				
pH Measurement	N	10/27/98	7.65	pH				
Nitrogen in Nitrate	N	10/27/98	7.35	mg/L	D	H		
Nitrogen in Nitrite	N	10/27/98	0.034	mg/L	UD	H		
Conductivity	N	10/27/98	467	µmhos/cm				
Alkalinity	N	10/27/98	114	mg/L				
Trichloroethene	N	10/27/98	10	µg/L				
1,1,2-Trichloroethane	N	10/27/98	0.11	µg/L	U			
2-Butanone	N	10/27/98	0.61	µg/L	U			
1,1-Dichloroethane	N	10/27/98	0.13	µg/L	U			
Carbon disulfide	N	10/27/98	0.4	µg/L	J			
Methylenechloride	N	10/27/98	0.4	µg/L	BJ			
Vinyl chloride	N	10/27/98	0.18	µg/L	U			
1,1,1-Trichloroethane	N	10/27/98	0.13	µg/L	U			
Benzene	N	10/27/98	0.12	µg/L	U			
1-Butanol	N	10/27/98	2.8	µg/L	U			
Chloroform	N	10/27/98	9	µg/L				
Acetone	N	10/27/98	3	µg/L	BJ			
Carbon tetrachloride	N	10/27/98	920	µg/L	D			
Fluoride	N	10/27/98	0.314	mg/L				
Chloride	N	10/27/98	50.5	mg/L	CD			
trans-1,2-Dichloroethylene	N	10/27/98	0.05	µg/L	U			
cis-1,2-Dichloroethylene	N	10/27/98	0.13	µg/L	U			

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Europium-154	N	10/27/98	-6.68	pCi/L	U		7.43	7.43
Iodine-129	N	10/27/98	0.00148	pCi/L	U		0.151	0.151
Sulfate	N	10/27/98	34.1	mg/L	D			
Europium-152	N	10/27/98	1.69	pCi/L	U		5.26	5.26
Europium-155	N	10/27/98	4.99	pCi/L	U		5.28	5.28
Antimony-125	N	10/27/98	-1.43	pCi/L	U		5.41	5.41
Technetium-99	N	10/27/98	34.6	pCi/L			5.86	18.5
Cesium-134	N	10/27/98	-1.12	pCi/L	U		2.39	2.39
Ruthenium-106	N	10/27/98	-7.53	pCi/L	U		20.9	20.9
Beryllium-7	N	10/27/98	29.4	pCi/L	U		36.4	36.4
Potassium-40	N	10/27/98	-10.6	pCi/L	U		35.5	35.5
Xylenes (total)	N	10/27/98	0.78	µg/L	U			
Tetrachloroethene	N	10/27/98	0.4	µg/L	J			
Gross beta	N	10/27/98	14.2	pCi/L			2.3	2.63
Gross alpha	N	10/27/98	0.359	pCi/L	U		0.556	0.557
Tetrahydrofuran	N	10/27/98	1.5	µg/L	U			
Toluene	N	10/27/98	0.2	µg/L	J			
4-Methyl-2-Pentanone	N	10/27/98	0.24	µg/L	U			
Ethyl cyanide	N	10/27/98	1.8	µg/L	U			
1,2-Dichloroethane	N	10/27/98	0.12	µg/L	U			
1,4-Dichlorobenzene	N	10/27/98	0.17	µg/L	U			
Cobalt-60	N	10/27/98	0.672	pCi/L	U		2.16	2.16
Strontium-90	N	10/27/98	0.0343	pCi/L	U		0.292	0.292
Cesium-137	N	10/27/98	1.14	pCi/L	U		2.32	2.32
Tritium	N	10/27/98	8,800	pCi/L			429	827
Antimony-125	Y	10/27/98	1.01	pCi/L	U		4.94	4.94
Europium-155	Y	10/27/98	-1.42	pCi/L	U		4.17	4.17
Europium-152	Y	10/27/98	-4.22	pCi/L	U		4.91	4.91
Iodine-129	Y	10/27/98	0.259	pCi/L	U		0.484	0.484
Europium-154	Y	10/27/98	-1.1	pCi/L	U		3.71	3.71
Aluminum	Y	10/27/98	27	µg/L	B			
Iron	Y	10/27/98	118	µg/L				
Calcium	Y	10/27/98	51,600	µg/L				
Zinc	Y	10/27/98	43.6	µg/L				
Vanadium	Y	10/27/98	22.7	µg/L				
Copper	Y	10/27/98	2.9	µg/L	U			
Cobalt	Y	10/27/98	2.4	µg/L	U			
Chromium	Y	10/27/98	2.7	µg/L	U			
Cadmium	Y	10/27/98	2.6	µg/L	U			
Beryllium	Y	10/27/98	0.5	µg/L	U			
Barium	Y	10/27/98	53.1	µg/L				
Antimony	Y	10/27/98	33	µg/L	U			
Strontium (elemental)	Y	10/27/98	203	µg/L				
Sodium	Y	10/27/98	12,800	µg/L				
Silver	Y	10/27/98	5	µg/L	U			
Potassium	Y	10/27/98	5,580	µg/L				

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Nickel	Y	10/27/98	10.8	µg/L	U			
Manganese	Y	10/27/98	29.5	µg/L				
Magnesium	Y	10/27/98	18,100	µg/L				
Iron	Y	10/27/98	105	µg/L				
Aluminum	Y	10/27/98	20.6	µg/L	U			
Europium-154	Y	10/27/98	3.19	pCi/L	U		5.64	5.64
Iodine-129	Y	10/27/98	0.109	pCi/L	U		0.239	0.24
Europium-152	Y	10/27/98	-0.848	pCi/L	U		5.39	5.39
Europium-155	Y	10/27/98	3.98	pCi/L	U		5.55	5.55
Antimony-125	Y	10/27/98	-0.255	pCi/L	U		5.69	5.69
Technetium-99	Y	10/27/98	31.5	pCi/L			5.78	18.2
Cesium-134	Y	10/27/98	-0.238	pCi/L	U		2.4	2.4
Ruthenium-106	Y	10/27/98	-0.696	pCi/L	U		20	20
Beryllium-7	Y	10/27/98	41.6	pCi/L	U		39.8	39.8
Potassium-40	Y	10/27/98	29.4	pCi/L	U		33.1	33.1
Magnesium	Y	10/27/98	17,800	µg/L				
Manganese	Y	10/27/98	28	µg/L				
Nickel	Y	10/27/98	10.8	µg/L	U			
Potassium	Y	10/27/98	5,850	µg/L				
Silver	Y	10/27/98	5	µg/L	U			
Sodium	Y	10/27/98	12,700	µg/L				
Strontium (elemental)	Y	10/27/98	202	µg/L				
Antimony	Y	10/27/98	33	µg/L	U			
Europium-154	N	10/27/98	5.57	pCi/L	U		7.15	7.15
Iodine-129	N	10/27/98	0.0125	pCi/L	U		0.241	0.241
Sulfate	N	10/27/98	33.8	mg/L	D			
Europium-152	N	10/27/98	1.2	pCi/L	U		5.19	5.19
Europium-155	N	10/27/98	2.77	pCi/L	U		5.69	5.69
Antimony-125	N	10/27/98	0.886	pCi/L	U		5.95	5.95
Technetium-99	N	10/27/98	32.2	pCi/L			5.81	18.2
Cesium-134	N	10/27/98	-3.32	pCi/L	U		2.56	2.56
1,1,2-Trichloroethane	N	10/27/98	0.11	µg/L	U			
2-Butanone	N	10/27/98	0.61	µg/L	U			
1,1-Dichloroethane	N	10/27/98	0.13	µg/L	U			
Carbon disulfide	N	10/27/98	0.4	µg/L	J			
Methylenechloride	N	10/27/98	0.4	µg/L	BJ			
Vinyl chloride	N	10/27/98	0.18	µg/L	U			
1,1,1-Trichloroethane	N	10/27/98	0.13	µg/L	U			
Benzene	N	10/27/98	0.12	µg/L	U			
Total organic carbon	N	10/27/98	0.427	mg/L	B			
Total dissolved solids	N	10/27/98	350	mg/L				
Nitrogen in Nitrate	N	10/27/98	7.36	mg/L	D	H		
Nitrogen in Nitrite	N	10/27/98	0.034	mg/L	UD	H		
Alkalinity	N	10/27/98	109	mg/L				
Trichloroethene	N	10/27/98	10	µg/L				
1-Butanol	N	10/27/98	2.8	µg/L	U			

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Chloroform	N	10/27/98	9	µg/L				
Acetone	N	10/27/98	0.21	µg/L	U			
Carbon tetrachloride	N	10/27/98	920	µg/L	D			
Fluoride	N	10/27/98	0.352	mg/L				
Chloride	N	10/27/98	49.5	mg/L	CD			
trans-1,2-Dichloroethylene	N	10/27/98	0.05	µg/L	U			
cis-1,2-Dichloroethylene	N	10/27/98	0.13	µg/L	U			
Ruthenium-106	N	10/27/98	-3.01	pCi/L	U		20.1	20.1
Beryllium-7	N	10/27/98	16.7	pCi/L	U		36.1	36.1
Potassium-40	N	10/27/98	33.3	pCi/L	U		38.3	38.3
Xylenes (total)	N	10/27/98	0.78	µg/L	U			
Tetrachloroethene	N	10/27/98	0.5	µg/L	J			
Gross beta	N	10/27/98	13.2	pCi/L			2.2	2.52
Gross alpha	N	10/27/98	0.249	pCi/L	U		0.473	0.473
Tetrahydrofuran	N	10/27/98	1.5	µvg/L	U			
Toluene	N	10/27/98	0.2	µg/L	J			
4-Methyl-2-Pentanone	N	10/27/98	0.24	µg/L	U			
Ethyl cyanide	N	10/27/98	1.8	µg/L	U			
1,2-Dichloroethane	N	10/27/98	0.12	µg/L	U			
1,4-Dichlorobenzene	N	10/27/98	0.17	µg/L	U			
Cobalt-60	N	10/27/98	-0.885	pCi/L	U		2.43	2.43
Strontium-90	N	10/27/98	0.218	pCi/L	U		0.291	0.295
Cesium-137	N	10/27/98	0.817	pCi/L	U		2.03	2.03
Tritium	N	10/27/98	8,350	pCi/L			416	794
Barium	Y	10/27/98	53.3	µg/L				
Beryllium	Y	10/27/98	0.5	µg/L	U			
Cadmium	Y	10/27/98	2.6	µg/L	U			
Chromium	Y	10/27/98	2.7	µg/L	U			
Cobalt	Y	10/27/98	2.4	µg/L	U			
Copper	Y	10/27/98	2.9	µg/L	U			
Vanadium	Y	10/27/98	19.2	µg/L				
Zinc	Y	10/27/98	39.2	µg/L				
Calcium	Y	10/27/98	50,600	µg/L				
404 ft Depth								
Tritium	Y	11/3/98	7,180	pCi/L			387	708
Cesium-137	Y	11/3/98	0.261	pCi/L	U		2.13	2.13
Strontium-90	Y	11/3/98	0.0182	pCi/L	U		0.306	0.307
Cobalt-60	Y	11/3/98	1.54	pCi/L	U		2.34	2.34
Gross alpha	Y	11/3/98	0.424	pCi/L	U		0.537	0.539
Gross beta	Y	11/3/98	14.3	pCi/L			2.29	2.6
Turbidity	N	11/3/98	12.8	NTU				
Total organic carbon	N	11/3/98	0.36	mg/L	B			
Temperature	N	11/3/98	21.2	Deg C				

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Total dissolved solids	N	11/3/98	325	mg/L				
pH Measurement	N	11/3/98	7.62	pH				
Nitrogen in Nitrate	N	11/3/98	9.68	mg/L	D			
Nitrogen in Nitrite	N	11/3/98	0.017	mg/L	U			
Conductivity	N	11/3/98	451	µmhos/cm				
Alkalinity	N	11/3/98	108	mg/L				
Trichloroethene	N	11/3/98	10	µg/L				
1,1,2-Trichloroethane	N	11/3/98	0.11	µg/L	U			
2-Butanone	N	11/3/98	0.61	µg/L	U			
1,1-Dichloroethane	N	11/3/98	0.13	µg/L	U			
Carbon disulfide	N	11/3/98	0.15	µg/L	U			
Methylenechloride	N	11/3/98	0.16	µg/L	U			
Vinyl chloride	N	11/3/98	0.18	µg/L	U			
1,1,1-Trichloroethane	N	11/3/98	0.13	µg/L	U			
Benzene	N	11/3/98	0.12	µg/L	U			
1-Butanol	N	11/3/98	2.8	µg/L	U			
Chloroform	N	11/3/98	13	µg/L				
Acetone	N	11/3/98	0.21	µg/L	U			
Carbon tetrachloride	N	11/3/98	380	µg/L	D			
Fluoride	N	11/3/98	0.306	mg/L				
Chloride	N	11/3/98	41.9	mg/L	CD			
trans-1,2-Dichloroethylene	N	11/3/98	0.05	µg/L	U			
cis-1,2-Dichloroethylene	N	11/3/98	0.13	µg/L	U			
Europium-154	N	11/3/98	-5.74	pCi/L	U		6.74	6.74
Iodine-129	N	11/3/98	0.148	pCi/L	U		0.179	0.18
Sulfate	N	11/3/98	31.9	mg/L	D			
Europium-152	N	11/3/98	-1.96	pCi/L	U		5.7	5.7
Europium-155	N	11/3/98	8.06	pCi/L	U		5.86	5.86
Antimony-125	N	11/3/98	3.34	pCi/L	U		5.55	5.55
Technetium-99	N	11/3/98	29	pCi/L			5.73	18
Cesium-134	N	11/3/98	-2.06	pCi/L	U		2.48	2.48
Ruthenium-106	N	11/3/98	-2.75	pCi/L	U		20	20
Beryllium-7	N	11/3/98	20.7	pCi/L	U		39.2	39.2
Potassium-40	N	11/3/98	-14.2	pCi/L	U		34.5	34.5
Xylenes (total)	N	11/3/98	0.78	µg/L	U			
Tetrachloroethene	N	11/3/98	0.4	µg/L	J			
Gross beta	N	11/3/98	14.4	pCi/L			2.3	2.64
Gross alpha	N	11/3/98	-0.259	pCi/L	U		0.149	0.152
Tetrahydrofuran	N	11/3/98	1.5	µg/L	U			
Toluene	N	11/3/98	0.08	µg/L	U			
4-Methyl-2-Pentanone	N	11/3/98	0.24	µg/L	U			
Ethyl cyanide	N	11/3/98	1.8	µg/L	U			
1,2-Dichloroethane	N	11/3/98	0.12	µg/L	U			
1,4-Dichlorobenzene	N	11/3/98	0.17	µg/L	U			

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Cobalt-60	N	11/3/98	-0.622	pCi/L	U		2.74	2.74
Strontium-90	N	11/3/98	0.142	pCi/L	U		0.372	0.373
Cesium-137	N	11/3/98	0.234	pCi/L	U		2.08	2.08
Tritium	N	11/3/98	7,430	pCi/L			395	727
Potassium-40	Y	11/3/98	-3.08	pCi/L	U		41.7	41.7
Beryllium-7	Y	11/3/98	28.9	pCi/L	U		40.4	40.4
Ruthenium-106	Y	11/3/98	6.21	pCi/L	U		20.5	20.5
Cesium-134	Y	11/3/98	-3.05	pCi/L	U		2.19	2.19
Technetium-99	Y	11/3/98	29.7	pCi/L			5.75	18
Antimony-125	Y	11/3/98	0.688	pCi/L	U		6.42	6.42
Europium-155	Y	11/3/98	2.18	pCi/L	U		4.32	4.32
Europium-152	Y	11/3/98	4.91	pCi/L	U		5.87	5.87
Iodine-129	Y	11/3/98	0.338	pCi/L	U		0.341	0.343
Europium-154	Y	11/3/98	-1.4	pCi/L	U		7.59	7.59
Aluminum	Y	11/3/98	26.8	µg/L	B			
Iron	Y	11/3/98	113	µg/L				
Magnesium	Y	11/3/98	17,300	µg/L				
Manganese	Y	11/3/98	49.4	µg/L				
Nickel	Y	11/3/98	10.8	µg/L	U			
Potassium	Y	11/3/98	6,460	µg/L				
Silver	Y	11/3/98	5	µg/L	U			
Sodium	Y	11/3/98	12,900	µg/L				
Strontium (elemental)	Y	11/3/98	198	µg/L				
Antimony	Y	11/3/98	33	µg/L	U			
Barium	Y	11/3/98	54.8	µg/L				
Beryllium	Y	11/3/98	0.5	µg/L	U			
Cadmium	Y	11/3/98	2.6	µg/L	U			
Chromium	Y	11/3/98	2.7	µg/L	U			
Cobalt	Y	11/3/98	2.4	µg/L	U			
Copper	Y	11/3/98	2.9	µg/L	U			
Vanadium	Y	11/3/98	10.2	µg/L				
Zinc	Y	11/3/98	25.5	µg/L				
Calcium	Y	11/3/98	47,800	µg/L				
442 ft Depth								
Tritium	Y	11/9/98	8,460	pCi/L			420	795
Cesium-137	Y	11/9/98	0.766	pCi/L	U		2.31	2.31
Strontium-90	Y	11/9/98	-0.0127	pCi/L	U		0.216	0.216
Cobalt-60	Y	11/9/98	0.117	pCi/L	U		2.41	2.41
Gross alpha	Y	11/9/98	1.11	pCi/L	U		1.08	1.09
Gross beta	Y	11/9/98	12.9	pCi/L			2.13	2.42
Potassium-40	Y	11/9/98	18.9	pCi/L	U		47.8	47.8
Beryllium-7	Y	11/9/98	15.1	pCi/L	U		40.8	40.8
Ruthenium-106	Y	11/9/98	-3.97	pCi/L	U		26.3	26.3
Cesium-134	Y	11/9/98	1.9	pCi/L	U		2.6	2.6
Technetium-99	Y	11/9/98	33.1	pCi/L			5.84	18.4

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Antimony-125	Y	11/9/98	-0.0548	pCi/L	U		5.8	5.8
Europium-155	Y	11/9/98	1.91	pCi/L	U		5.22	5.22
Europium-152	Y	11/9/98	-0.559	pCi/L	U		6.47	6.47
Iodine-129	Y	11/9/98	0.0105	pCi/L	U		0.165	0.165
Europium-154	Y	11/9/98	0.279	pCi/L	U		7.82	7.82
Aluminum	Y	11/9/98	21.5	µg/L	B			
Iron	Y	11/9/98	126	µg/L				
Magnesium	Y	11/9/98	18,600	µg/L	C			
Manganese	Y	11/9/98	65.3	µg/L				
Nickel	Y	11/9/98	10.8	µg/L	U			
Potassium	Y	11/9/98	5,670	µg/L				
Silver	Y	11/9/98	5	µg/L	U			
Sodium	Y	11/9/98	13,900	µg/L				
Strontium (elemental)	Y	11/9/98	224	µg/L				
Antimony	Y	11/9/98	33	µg/L	U			
Barium	Y	11/9/98	77	µg/L				
Beryllium	Y	11/9/98	0.5	µg/L	U			
Cadmium	Y	11/9/98	2.6	µg/L	U			
Chromium	Y	11/9/98	2.7	µg/L	U			
Cobalt	Y	11/9/98	2.4	µg/L	U			
Copper	Y	11/9/98	2.9	µg/L	U			
Vanadium	Y	11/9/98	8.9	µg/L	B			
Zinc	Y	11/9/98	17.6	µg/L				
Calcium	Y	11/9/98	49,100	µg/L	CE			
Tritium	N	11/9/98	8,310	pCi/L			417	784
Cesium-137	N	11/9/98	-1.46	pCi/L	U		2.28	2.28
Strontium-90	N	11/9/98	0.0471	pCi/L	U		0.229	0.23
Cobalt-60	N	11/9/98	3.93	pCi/L	U		2.51	2.51
1,4-Dichlorobenzene	N	11/9/98	0.17	µg/L	U			
1,2-Dichloroethane	N	11/9/98	0.12	µg/L	U			
Ethyl cyanide	N	11/9/98	1.8	µg/L	U			
4-Methyl-2-Pentanone	N	11/9/98	0.24	µg/L	U			
Toluene	N	11/9/98	0.08	µg/L	U			
Tetrahydrofuran	N	11/9/98	1.5	µg/L	U			
Gross alpha	N	11/9/98	0.452	pCi/L	U		0.839	0.841
Gross beta	N	11/9/98	13.1	pCi/L			2.18	2.5
Tetrachloroethene	N	11/9/98	0.11	µg/L	U			
Xylenes (total)	N	11/9/98	0.78	µg/L	U			
Potassium-40	N	11/9/98	8.27	pCi/L	U		60.3	60.3
Beryllium-7	N	11/9/98	33.3	pCi/L	U		40	40
Ruthenium-106	N	11/9/98	-6.93	pCi/L	U		25.4	25.4
Cesium-134	N	11/9/98	-0.747	pCi/L	U		2.37	2.37
Technetium-99	N	11/9/98	34.5	pCi/L			5.88	18.5
Antimony-125	N	11/9/98	1.44	pCi/L	U		6.28	6.28
Europium-155	N	11/9/98	-0.643	pCi/L	U		4.5	4.5
Europium-152	N	11/9/98	-3.48	pCi/L	U		5.96	5.96

Table D.1. (contd)

Constituent	Filtered	Sample Date	Value	Analysis Units	Lab Qualifier	Review Qualifier	Counting Error	Total Analysis Error
Sulfate	N	11/9/98	33.4	mg/L	D			
Iodine-129	N	11/9/98	-0.0476	pCi/L	U		0.204	0.204
Europium-154	N	11/9/98	-6.6	pCi/L	U		7.59	7.59
cis-1,2-Dichloroethylene	N	11/9/98	0.13	µg/L	U			
trans-1,2-Dichloroethylene	N	11/9/98	0.05	µg/L	U			
Chloride	N	11/9/98	45.3	mg/L	CD			
Fluoride	N	11/9/98	0.321	mg/L				
Carbon tetrachloride	N	11/9/98	590	µg/L	D			
Acetone	N	11/9/98	0.21	µg/L	U			
Chloroform	N	11/9/98	25	µg/L				
1-Butanol	N	11/9/98	2.8	µg/L	U			
Benzene	N	11/9/98	0.12	µg/L	U			
1,1,1-Trichloroethane	N	11/9/98	0.13	µg/L	U			
Vinyl chloride	N	11/9/98	0.18	µg/L	U			
Methylenechloride	N	11/9/98	0.3	µg/L	BJ			
Carbon disulfide	N	11/9/98	0.3	µg/L	J			
1,1-Dichloroethane	N	11/9/98	0.13	µg/L	U			
2-Butanone	N	11/9/98	0.61	µg/L	U			
1,1,2-Trichloroethane	N	11/9/98	0.11	µg/L	U			
Trichloroethene	N	11/9/98	8	µg/L				
Alkalinity	N	11/9/98	108	mg/L				
Conductivity	N	11/9/98	430	µmhos/cm				
Nitrogen in Nitrite	N	11/9/98	0.034	mg/L	UD			
Nitrogen in Nitrate	N	11/9/98	9.09	mg/L	D			
pH Measurement	N	11/9/98	7.53	pH				
Total dissolved solids	N	11/9/98	328	mg/L				
Temperature	N	11/9/98	20.7	Deg C				
Total organic carbon	N	11/9/98	0.302	mg/L	B			
Turbidity	N	11/9/98	15.8	NTU				
Turbidity	Y	12/10/98	0.77	NTU				
Conductivity	N	12/10/98	534	µmhos/cm				
pH Measurement	N	12/10/98	7.68	pH				
Temperature	N	12/10/98	20	Deg C				
Turbidity	N	12/10/98	4.38	NTU				

Distribution

**No. of
Copies**

**No. of
Copies**

OFFSITE

Fluor Daniel Northwest, Inc.

T. Valero
Washington State Department of Ecology
1315 4th Avenue
Kennewick, WA 99336

F. M. Mann H0-22

Lockheed Martin Hanford Corporation

E. A. Fredenburg R1-04

ONSITE

18 Pacific Northwest National Laboratory

2 DOE, Richland Operations Office

M. J. Furman H0-12

Bechtel Hanford Company

A. J. Knepp H0-19

F. N. Hodges (5) K6-81

G. R. Holdren K6-81

D. G. Horton (2) K6-81

S. P. Luttrell K6-96

L. F. Morasch K6-86

F. A. Spane, Jr. K6-96

Information Release Office (7) K1-06