CATALYTIC MULTI-STAGE LIQUEFACTION (CMSL)

DOE/PC/92147--T2- Vol. 3

WORK PERFORMED UNDER DOE CONTRACT
NO. DE-AC22-93PC92147

FINAL REPORT

RECEIVED

FEB 07 1997

OSTI

RECEIVED
USDOE/PETC
26 DEC 10 PM 1:26
ACQUISITION & ASSISTANCE DIV.

VOLUME III

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Hydrocarbon Technologies, Inc.

1501 New York Avenue

Lawrenceville, NJ 08648

MASTER

November, 1996

CLEARED BY
PATENT COUNSEL

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, make any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

**Portions of this document may be illegible
in electronic image products. Images are
produced from the best available original
document.**

CATALYTIC MULTI-STAGE LIQUEFACTION OF COAL (CMSL)

FINAL REPORT

VOLUME III

SECTION III - DETAILED ECONOMIC EVALUATIONS

**A.G. Comolli
P. Ganguli
W.F. Karolkiewicz
Theo L.K. Lee
V.R. Pradhan
G.A. Popper
T. Smith
R.. Stalzer**

**WORK PERFORMED UNDER DOE CONTRACT
No. DE-AC22-93PC92147
October 1992 to December 1995**

**HYDROCARBON TECHNOLOGIES, INC.
1501 New York Avenue
Lawrenceville, NJ 08648**

November 1996

**CLEARED BY
PATENT COUNSEL**

VOLUME III

SECTION III - DETAILED ECONOMIC EVALUATIONS

SUMMARY

Introduction

Variables Investigated

Economic Assessment Conclusions

- RUN CMSL-2 - Run CMSL-02 Illinois Coal, Catalytic/Catalytic Mode, Solvent/Coal Ratio, Surfactant
- RUN CMSL-3 - Run CMSL-03 Wyoming Coal, Thermal/Catalytic Mode, AHM Molybdenum Additive, Interstage Separator, Synthesis Gas
- RUN CMSL-4 - Run CMSL-04 Wyoming Coal, Catalytic/Catalytic Mode, Interstage Separator, Synthesis Gas, In-line Hydrotreating
- RUN CMSL-5 - Run CMSL-05 Illinois Coal, Catalytic-Catalytic Mode, Interstage Separator, Synthesis Gas
- RUN CMSL-6 - Run CMSL-06 Wyoming Coal, Thermal/Catalytic Mode, Sulfated Fe/Mo Additive
- RUN CMSL-7 - Run CMSL-07 Wyoming Coal, Catalytic/Catalytic Mode, AHM Molybdenum Additive, Synthesis Gas, Lower Pressures
- RUN CMSL-8 - Run CMSL-08 Illinois Coal, Catalytic/Thermal Mode, Sulfated Fe/Mo Additive, Coprocessing with Plastics
- RUN CMSL-9 - Run CMSL-09 Wyoming Coal, No Extrudate Catalyst, Molyvan Molybdenum Additive and Iron Additive, Coprocessing with Plastics
- RUN CMSL-10 - Run CMSL-10 Wyoming Coal, No Extrudate Catalyst, Molyvan Molybdenum Additive and Iron Additive
- RUN CMSL-11 - Run CMSL-11 Wyoming Coal, No Extrudate Catalyst, Molyvan Molybdenum Additive and Iron Additive, Coprocessing with Municipal Plastic Waste, Elimination of Catalyst Additive Pretreater

**CATALYTIC MULTI-STAGE LIQUEFACTION OF COAL (CMSL)
FINAL REPORT**

VOLUME III

SECTION III - DETAILED ECONOMIC EVALUATIONS

TABLE OF CONTENTS

1.0	SUMMARY	1
	1.1 Introduction	1
2.0	VARIABLES INVESTIGATED	2
3.0	ECONOMIC IMPACT OF VARIABLES	3
4.0	ECONOMIC ASSESSMENT CONCLUSIONS	7

VOLUME III

SECTION III - DETAILED ECONOMIC EVALUATIONS

LIST OF TABLES

Table 3.1	Major Assumptions Used in Economic Analysis	8
Table 3.2	Economic Evaluation of Bench Unit CMSL Runs Results Black Thunder Mine Coal Operations	9
Table 3.3	Economic Evaluation of Bench Unit CMSL Runs Results Illinois No. 6 Coal Operations	10

VOLUME III

SECTION III - DETAILED ECONOMIC EVALUATIONS

LIST OF FIGURES

Figure 3.1	Blow Flow Diagram of Major Processing Areas	11
Figure 3.2	Ratio of Crude Oil Price to Product Price	12

CATALYTIC MULTI-STAGE LIQUEFACTION OF COAL (CMSL) FINAL REPORT

VOLUME III

SECTION III - DETAILS ECONOMIC EVALUATIONS

1.0 SUMMARY

1.1 Introduction

Under contract with the US Department of Energy, Hydrocarbon Technologies, Inc. has conducted a series of eleven catalytic, multi-stage, liquefaction (CMSL) bench scale runs between February, 1993, and September, 1995. The purpose of these runs was to investigate novel approaches to liquefaction relating to feedstocks, hydrogen source, improved catalysts as well as processing variables, all of which are designed to lower the cost of producing coal-derived liquid products. This report summarizes the technical assessment of these runs, and in particular the evaluation of the economic impact of the results.

Economic evaluations have been performed for a fully-integrated grass-roots commercial complex, to manufacture finished gasoline and diesel fuel. Byproducts from the complex include propane and butane, as well as elemental sulfur and anhydrous ammonia. Coal and waste plastics required in the liquefaction facility are prepared on site. Part of the hydrogen needs of the complex is manufactured by partial oxidation of unconverted liquefaction plant feed and residual oil product. Part of the fuel requirement of the complex is met by waste process gases. Natural gas is imported to meet the remainder of the fuel needs of the complex and also to satisfy the rest of the hydrogen requirements. All utility needs of the complex, including electric power, are produced on site. *Figure 3.1* shows a schematic block flow diagram of the major processing areas of the complex.

The liquefaction plant is a multi-train facility, and the feed processing capacity has been selected based on construction of maximum-sized, heavy-walled pressure liquefaction reactors. The costs and utility requirements for the liquefaction plant were factored from detailed engineering studies. Costs and operating requirements of other process facilities and off-sites were estimated using information derived from the Baseline Design Study, developed by Bechtel for DOE. The plant sizes for these evaluations was about 10,000 tons per day of coal (or coal plus plastic) producing 40-45,000 barrels per day of finished gasoline and diesel fuel products.

This study updated the 1988 HRI Commercial Plant Design with Illinois Coal¹ using the Bechtel Baseline Design Study² for cost and utility requirements of the sections outside the liquefaction plant. Plant costs and product costs are in effect those that would apply in 1991, the time of Bechtel's update of the cost bases. The criteria and financing basis for used in the economic model are essentially those outlined in Bechtel's Baseline Design. The major assumptions and bases for the economics are summarized in *Table 3.1*. A four-year construction period was assumed followed by a 25-year operating life. Capital costs, including working capital and startup costs were depreciated over a ten-year period using straight-line amortization. Feed costs and product selling prices were inflated at an annual rate of 3 per cent. Labor and staffing requirements and wage rates were developed from the Baseline Design. Catalysts and chemicals cost were calculated for each plant within the complex, as factored from the Baseline Design.

Results of the economic evaluations are present in terms of an equivalent crude oil price. The concept of the equivalent crude oil price was adapted from the Bechtel Baseline Design Study to evaluate coal-derived synthetic oil products allowing for their condition of being finished light and middle distillate products, in terms of the cost of a crude oil that would produce such products in a conventional petroleum refinery at the same cost. Analysis of published data showed a correlation between crude oil cost and product costs, depending upon the product slate and product price. For a given product slate and product cost, multiplying the product cost by the ratio gives the equivalent crude oil cost. *Figure 3.2* gives the factors that were employed to adjust the projected product costs to the equivalent crude oil price.

2.0 VARIABLES INVESTIGATED

Feedstocks for the CMSL runs have ranged from coal-only operation with bituminous and sub-bituminous coals to coal/plastics mixtures, the plastics simulating the composition of solid municipal wastes. Catalysts have included molybdenum and iron in the dispersed form. Successful use of an all-dispersed slurry catalyst system has been demonstrated, as well as employment of dispersed catalyst in combination with supported catalyst. Synthesis gas was investigated as an alternative to high purity hydrogen feed gas in liquefaction. Among the process improvements investigated were lower slurry oil to feed coal ratios, lower operating pressure, use of interstage separators, in-line hydrotreaters and pretreaters.

Table 3.2 summarizes the principal operating parameters and projected equivalent crude oil costs for the seven CMSL runs with Black Thunder Mine Wyoming sub-bituminous coal for which economic evaluations were done. *Table 3.3* is a similar summary for the three CMSL runs with Illinois No. 6 coal that were evaluated.

¹ DOE/PC/8002-Top 2, Low-Severity Catalytic Two-Stage Liquefaction Process - Illinois Coal Studies

² DOE Contract DE-AC22-90PC89857, Volume VIII Design, Capital Cost and Economics for Improved Baseline, March, 1993

Details of the economic analyses of each run are presented later in this volume. The following is a discussion of the economic effect of the major process variables investigated, namely:

1. Oil/solids ratio
2. Use of interstage separation, including reactor design modification because of lowered vapor loading
3. Use of in-line hydrotreaters
4. Co-liquefaction of plastics along with coal
5. Use of synthesis gas as reactor feed
6. Operating pressure
7. Use of dispersed catalyst
8. Use of pretreaters

The reactor design modification cited above in connection with the use of an interstage separator is a consequence of halving the vapor load in each stage by splitting the vapor feed between the stages. A limiting factor in ebullated bed reactor design is the vapor velocity in the reactor, which for a given solids feed space velocity limits the height of the reactor and the amount of coal that can be fed to the reactor. With the vapor rate halved, as with the interstage separator, the length of reactor can be doubled and the amount of coal feed to the reactor increased proportionally, which lowers the number of liquefaction trains and results in reduced investment because of the lower number of auxiliary vessels, piping, and instrumentation. The economic evaluations of the results of the individual CMSL runs assumes this modification of the basic reactor design.

3.0 ECONOMIC IMPACT OF VARIABLES

The economic impact of the operating parameters that were studied were as follows:

- * In this study with the conventional process design, the lowest projected equivalent crude oil price using Black Thunder Mine coal was \$30.4 per barrel (For Run CMSL-9 Period 5), which is \$2.2 per barrel lower than that for a reference operation (Run CMSL-4 Period 5), with Ni-Mo extrudate catalyst in both stages and with no additives. The CMSL-9 operation used 300 ppm Mo additive and no extrudate catalyst.
- * In this study with the modified process design, the lowest projected equivalent crude oil price using Black Thunder Mine coal was \$28.7 per barrel (For Run CMSL-4 Period 5, which used extrudate catalyst in both stages), which is \$3.9 per barrel lower than that for the same operation using the conventional process design. With the modified process design, the estimated equivalent crude oil prices were slightly higher for various evaluations of operations which used catalyst additives at \$29.2-\$29.8 per barrel;
- * The lowest projected equivalent crude oil cost using Illinois No. 6 coal was \$27.6 per barrel, which had interstage removal of vapors, permitting modified process design, using Ni-Mo extrudate catalyst in both stages (Run CMSL-5). This cost was \$4.0 per

barrel lower than that of reference operation without interstage separation (Run CMSL-2);

- * The lowest projected equivalent crude oil cost for coprocessing of plastics and coal was \$19.8 per barrel with 50% of a prepared plastic mixture with Black Thunder Mine coal using Mo and Fe additives and no extrudate catalyst. A similar operation with 33% of a commercially obtained plastic mixture cost had a cost of \$21.8 per barrel. A coprocessing operation with Illinois Coal had a cost of \$26.0 per barrel using only catalyst additives and a prepared catalyst mixture;
- * Interstage Vapor Separation - With interstage separation in Period 8 of Run CMSL-5 the cost was \$0.6 per barrel lower than in Period 10 of Run CMSL-2 in operations with Illinois coal (although there were differences in the coal feed and some of the operating conditions). In this case, modification of the process design taking advantage of the lower vapor rates consequent to the use of the interstage separator lowered the equivalent crude oil cost by an additional \$2.5 per barrel. In general for the other such evaluations summarized in these tables the modified process design lowered the equivalent crude oil cost by \$0.5-4.9 per barrel.
- * Use of Synthesis Gas - Using synthesis gas containing 84% Co increased the equivalent crude oil cost by \$1.5 per barrel compared to operations with high purity hydrogen (operations with Black Thunder Mine Coal in Run CMSL-4). When the synthesis gas contained 75% CO this increase was \$0.6 per barrel (Run CMSL-3). When it was assumed that the synthesis gas contained 50% CO the equivalent crude oil cost was lower by \$0.4 per barrel than with high purity hydrogen (Compare Period 7 of Run CMSL-7 with Period 5 of Run CMSL-4), although the Run CMSL-7 operation included 200 ppm Mo additive, which probably contributed to the economic advantage.
- * Lower Pressures - In the conventional design operations at a pressure of 10.3 MPa had an equivalent crude oil cost \$0.8 lower than that at a pressure of 17.2 MPa (Run CMSL-7). The lower pressure operation did use 500 ppm Mo additive compared to 200 ppm used in the higher pressure operation. With the modified process design the lower pressure cost was \$0.2 per barrel higher than the higher pressure cost.
- * Catalyst - The catalyst configuration for operations with Black Thunder Mine coal with the lowest equivalent crude oil cost for the conventional design, \$30.4 per barrel was in Run CMSL-9 with 300 ppm molybdenum additive and no extrudate catalyst, \$2.2 per barrel per lower than for the CTSL configuration of the supported catalyst in both stages of Run CMSL-4. Other configurations using additives with extrudate catalyst only in the second stage had slightly lower costs than that of the reference CTSL operation of Run CMSL-4: in Run CMSL-3 with 1500 ppm molybdenum additive the equivalent crude oil price was lower by \$0.5 per barrel; in Run CMSL-6 with 100 ppm/615 ppm of sulfated Mo/Fe additive this price was lower by \$0.7 per barrel.
- * With no supported catalyst in either stage and 5,000-10000 ppm Fe (sulfated hydrated iron oxide) dispersed catalyst additive with 100-300 ppm molybdenum additive (Molyvan) the equivalent crude oil costs were \$2.5-3.0 higher (Runs CMSL-9,

CMSL-10, and CMSL-11) than for the reference operation with extrudate catalyst in both stages. The principal reason for the increased cost was high cost of the relatively high amounts of the iron additive.

- * For operations with Illinois Coal, with a catalyst configuration of a supported catalyst in the first stage only and sulfated 100 ppm Mo/625 ppm Fe additive the equivalent crude oil cost was about \$2.1 per barrel higher than that of a reference operation with extrudate catalyst in both stages (Compare Period 6 of Run CMSL-8 with Period 4 of Run CMSL-2)
- * Plastic/Coal Coprocessing - The lowest equivalent crude oil cost indicated in this study was \$19.8 per barrel for the Coprocessing Black Thunder Mine coal with 50% of an HTI prepared mixed plastic in Run CMSL-9, with the process modification for the maximum coal rate. A comparably low cost, \$21.8 per barrel, was indicated for the operation in Run CMSL-11 using 33% of a plastic mix obtained from a commercial recycling facility. These operations were with no supported catalyst in either stage and 100-300 ppm molybdenum additive (Molyvan), and 5,000-10000 ppm Fe (sulfated hydrated iron oxide) dispersed catalyst additive which had relatively high equivalent crude oil costs in the coal only operations. These costs were \$9.4-11.5 per barrel lower than those of equivalent operations feeding coal only. When the Coprocessing used 33% HDPE as the plastic component the equivalent crude oil cost was \$4.0 per barrel lower than that of the equivalent coal-only operation (Run CMSL-9). Note that the plastics were assumed to be delivered at no cost to the liquefaction plant, although there was an allowance for preparation of the plastics for slurry preparation at the plant site.
- * Coprocessing of Illinois Coal with 25-33% of the HTI prepared plastic mix gave an equivalent crude oil cost \$4.9-6.8 per barrel lower than the equivalent coal only operation (Run CMSL-8). The catalyst configuration for this operation, sulfated 100-200 ppm Mo/625-1230 ppm Fe additive had a relatively high equivalent crude oil cost in corresponding coal-only operations. The lowest equivalent crude oil cost for these Co-processing operations was \$26.0 per barrel. Using 33% HDPE as the plastic component increased the equivalent crude oil cost by \$7.3 per barrel, which was \$3.0 per barrel higher than that of the corresponding coal-only operation.
- * Reduction of Recycle Solvent Flow - Lowering the recycle ratio from 1.06 kg/kg to 0.9 kg/kg lowered the equivalent crude oil cost by \$0.9 per barrel (Compare Periods 4 and 10 of Run CMSL-2 with Illinois No. 6 coal);
- * Use of Surfactant - With 2% surfactant this cost was increased by about \$0.2 per barrel (Compare Periods 13 and 16 of Run CMSL-2);

In addition to the specific evaluations that used the experimental results for the various CMSL runs, the following estimates were made of the effects of other process modifications:

A. In-line Hydrotreating

An in-line hydrotreater was used in eight of the eleven CMSL runs. While adding to the liquefaction plant cost, the hydrotreater substantially lowered the cost of downstream product upgrading facilities. The benefit of the in-line hydrotreater could not be evaluated from a CMSL run, but is shown in the following comparison assuming constant yields in CMSL-11 (liquefying Illinois No.6 coal and waste plastics).

	<u>Base</u>	<u>Modif'n A</u>
In-line hydrotreater use	no	yes
Supported catalyst, lb/Ton	2.7	2.7
Dispersed Iron catalyst, ppm	0	0
Dispersed Molyvan A, ppm	0	0
Liquefaction plant cost, \$MM	564.9	575.4
Product upgrading cost, \$MM	124.6	98.5
Total plant cost, \$MM	2,354	2,335
Equivalent crude oil price, \$/B	31.20	30.98

This estimate shows that the cost of an in-line hydrotreater would be about 40% as much as the savings in down-stream product upgrading costs so that the product cost would be lowered by \$0.2 per barrel.

B. Elimination of Pretreater Reactor For Activation of Dispersed Catalyst

With all-dispersed catalyst system a pretreater-reactor was used for two runs (CMSL-9 and CMSL-10) for activation of the Fe catalyst additive. The pretreater reactor was eliminate in Run CMSL-11 and the catalyst activation was effected by a preheater coil without an apparent negative impact. While comparison of these modes of activation could not be made at nearly identical operating conditions, the economic benefit of eliminating the pretreater reactor was evaluated assuming constant yields:

	<u>Base</u>	<u>Modif'n A</u>
Pretreater used	yes	no
Dispersed Iron Catalyst, ppm	5,000	5,000
Dispersed Molyvan A, ppm	100	100
Liquefaction plant cost, \$MM	588.4	551.6
Total plant cost, \$MM	2,353	2,307
Equivalent crude oil price, \$/B	31.65	31.15

Elimination of the pretreated reactor lowers the product cost by \$0.5 per barrel.

4.0 ECONOMIC ASSESSMENT CONCLUSIONS

Results of the economic evaluation of these CMSL runs have shown positive benefits from most of the variables investigated. Positive economic benefits arise from:

- lowering the oil/solids ratio in the liquefaction reactor feed
- use of an interstage separators
- use of an in-line hydrotreater
- incorporation of plastics in the liquefaction plant feed
- operation at lower liquefaction pressure
- use of dispersed catalyst, at moderate rates
- elimination of the pretreater when using dispersed catalyst

The economically detrimental variables investigated were the use of synthesis gas in place of pure hydrogen and use of surfactant with the coal feed.

TABLE 3.1**Major Assumptions Used in Economic Analysis**

DCF Rate of Return, %	15
Project Life, Years	25
Depreciation Term, Years	10
Depreciation Type	Straight-line
Construction Period, Years	4
Draw-down During Construction, %	
First Year	4
Second Year	26
Third Year	45
Fourth Year	25
Escalation During Construction, %	3
On-Stream Factor, Days/Year	
First-Year	237
Second Year	292
Thereafter	328.5
Equity, %	25
Interest Rate on Debt	8
Inflation Rate, %/year	3
Federal Income Tax Rate, %	34
Debt Life, Years	25
Interest Rate During Construction, %	8
Working Capital	
Owner's Cost, % of Capital Cost	5
Product Revenue, % Annual Cost	50
Maintenance, % of Capital Cost	1
Byproduct revenue, % of Annual Cost	10

TABLE 3.2

**Economic Evaluation of Bench Unit CMSL Runs Results
Black Thunder Mine Coal Operations**

Run CMSL Period	Base 4 5	4 12	3 5	3 12	6 17	7 7	7 11	7 19	9 5	9 29	9 38	9 41	10 9	10 18	11 10	11 16
1st Stage Catalyst	S-317	S-317	---	---	---	S-317	S-317	S-317	---	---	---	---	---	---	---	---
2nd Stage Catalyst	S-317	S-317	S-317	S-317	S-317	S-317	S-317	S-317	---	---	---	---	---	---	---	---
Additive, ppm			Mo, 1500	Mo, 1500	Mo, 100 Fe, 615	Mo, 200	Mo, 200	Mo, 500	Mo, 300	Mo, 300 Fe, 1000	Mo, 300 Fe, 1000	Mo, 300 Fe, 1000	Mo, 100 5000, Fe	Mo, 100 5000, Fe	Mo, 100 5000, Fe	Mo, 100 5000, Fe
Temperature, C																
1st Stage	400	414	399	399	437	427	427	427	444	440	448	449	441	449	450	450
2nd Stage	427	438	427	427	432	443	443	443	449	449	461	462	448	457	459	459
Solids Feed, Kg/h/M3	308	370	304	304	455	321	321	321	673	673	673	673	415	721	671	688
Pressure, MPa	17.2	17.2	17.2	17.2	17.2	17.2	13.8	10.3	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2
CO, V% (4)	0	84	0	75	0	50	50	50	0	0	0	0	0	0	0	0
Plastics, w% of solid	0	0	0	0	0	0	0	0	0	0	33 (2)	50 (1)	0	0	0	33 (3)
Interstage Separator	Yes	Yes	Yes	Yes	No	Yes	Yes	Yes	No	No	No	No	No	No	No	No
Equivalent Crude Oil Oil Price, \$/Barrel																
Conventional Design	32.62	34.17	29.68	30.27	31.94	32.25	32.20	31.46	30.39	35.02	30.97	23.57	35.56	31.58	35.10	25.69
Maximum Coal (5)	28.70	33.69	27.05	38.11		31.26	32.20	31.46	29.83	33.22	26.70	19.81	35.14	28.90	33.77	21.79

(1) Mixed, HDPE, Polystyrene, Polypropylene

(2) HDPE

(3) Monmouth Recycling Curbside Recycle Plastic

(4) Feed Gas to First Stage

(5) With Interstage Separator, Reducing Vapor Load in Each Stage, Permitting Longer Reactors and Greater Coal Feed per Reactor with Fewer Liquefaction Trains.

TABLE 3.3

**Economic Evaluation of Bench Unit CMSL Runs Results
Illinois No. 6 Coal Operations**

Run CMSL Period	2 4	2 10	2 13	2 16	5 8	5 11	5 13	8 6	8 11	8 16	8 20	8 22
1st Stage Catalyst	S-317	S-317	S-317	S-317	S-317	S-317	S-317	S-317	S-317	S-317	S-317	S-317
2nd Stage Catalyst	S-317	S-317	S-317	S-317	S-317	S-317	S-317	S-317	---	-----	-----	-----
Additive, ppm								Mo 100 Fe 615	Mo 100 Fe 615	Mo 100 Fe 615	Mo 200 Fe 1230	Mo 200 Fe 1230
Temperature, C												
1st Stage	400	400	414	413	413	413	399	432	432	432	433	433.00
2nd Stage	428	428	433	433	441	427	427	439	441	454	454	454.00
Solids Feed, Kg/h/M3	296	296	535	458	462	317	317	481	481	641	481	481.00
Pressure, MPa	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2	17.2
CO, V% (3)	0	0	0	0	0	0	0	0	0	0	0	0.00
Recycle Solv., Kg/Kg Solids	1.06	0.9	0.9	0.9	0.9	0.9	0.9	1.5	1.6	1.8	2.1	1.90
Plastics, W% of Solids	0	0	0	0	0	0	0	0	25 (1)	25 (1)	33 (1)	33 (2)
Surfactant, W%	0	0	0	0	0	0	0	0	0	0	0	0.00
Interstage Separator	No	No	No	No	Yes	Yes	Yes	No	No	No	No	No
Equivalent Crude Oil Oil Price, \$/Barrel												
Conventional Design	31.56	30.70	31.56	31.72	30.12	30.65	32.78	33.68	28.84	31.67	29.30	36.57
Maximum Coal (4)					27.64	27.99	29.77	32.84	26.62	29.12	25.95	

(1) Mixed, HDPE, Polystyrene, Polypropylene

(2) HDPE

(3) Fee Gas to First Stage

(4) With Interstage Separator, Reducing Vapor Load in Each Stage, Permitting Longer Reactors and Greater Coal Feed per Reactor with Fewer Liquefaction Trains.

BLOCK FLOW DIAGRAM OF MAJOR PROCESSING AREAS

FIGURE 3.1

FIGURE 3.2

VOLUME III

SECTION III

RUN CMSL-2

ILLINOIS NO. 6 COAL

**STUDY OF SOLVENT/COAL RATIO
SURFACTANT**

VOLUME III

SECTION III - RUN CMSL-2

TABLE OF CONTENTS

**STUDY OF SOLVENT/COAL RATIO
SURFACTANT**

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	2

VOLUME III

SECTION III - RUN CMSL-2

LIST OF TABLES

Table 3.2.1	Design Coal Feed Analysis	3
Table 3.2.2	CMSL- 2 Design Basis Comparison	4
Table 3.2.3	CMSL- 2 Overall Material Balance	5
Table 3.2.4	CMSL- 2 Plant Net Hydrogen Balance	6
Table 3.2.5	CMSL- 2 Thermal Efficiency	7
Table 3.2.6	CMSL- 2 Utilities Summary	8
Table 3.2.7	CMSL- 2 Capacities Of Process Units and Offsites	9
Table 3.2.8	CMSL- 2 Liquefaction Plant Investment Details	10
Table 3.2.9	CMSL- 2 Total Plant Investment Summary	11
Table 3.2.10	CMSL- 2 Product Cost Calculation	12
TABLE 3.2.11	CMSL- 2 Breakdown of Equivalent oil crude price - - - -	13

VOLUME III

SECTION III

TECHNICAL ASSESSMENT CMSL-2

1.0 BACKGROUND

The objective of Run 227-78 (CMSL-2) was to investigate the impact of lower solvent-to-coal ratios in the liquefaction of bituminous coal and the use of surfactant with the coal feed. The coal used for CMSL-2 was a washed Illinois #6 coal from the Burning Star Mine. The properties summarized in *Table 3.2.1*, are comparable to the Illinois #6 coal used for the earlier (1993) base case. The catalyst for the run was Shell S-317 Ni-Mo extrudates in both stages. No catalyst additives were used.

Four conditions were explored during the run: Condition 1 (Period 4), operated with 1.06 pounds of solvent per pound of coal. In Condition 2, (Period 10) the ratio was lowered to 0.9 pounds of solvent per pound of coal, with other reactor operating parameters being kept the same as in Condition 1. For Condition 3, (Period 13) the reactor space velocity was lowered and the temperature was raised with 0.9 pounds of solvent per pound of coal. Finally, in Condition 4 (Period 16), a surfactant was added using essentially the same reactor operating parameters as in Condition 3. *Table 3.2.2* summarizes the operating conditions for the four periods.

Performance and yields for each Run Condition, as derived from run data, were projected to commercial operating conditions, with continuous catalyst addition and withdrawal, using the CTSI Process Simulator. As seen from *Table 3.2.2*, the projected yields varied, showing the highest distillate production and maximum hydrogen consumption in Condition 2.

The basis for the economic comparison was essentially that reported in December, 1993. In brief, this study updated the 1988 HRI commercial plant design with coal, using the Bechtel Baseline Design Study for cost and utility requirements of the sections outside the liquefaction plant. The major assumptions and bases for the economics are summarized in the introduction to these economic analyses.

Overall material balances (*Table 3.2.3*) show that the liquids production tails off after Period 10. (*Table 3.2.4*) presents net hydrogen balances, while *Table 3.2.5* shows thermal efficiency. *Table 3.2.6* is a summary of utilities usage and *Table 3.2.7* shows the capacities of the various process units and off sites.

Liquefaction plant investment details are presented in *Table 3.2.8*. The lower oil-to-solids ratio is reflected in lower costs for pumps, fired heaters and exchangers. The cost of the other items, however, is more a function of gas yields and, in particular of the hydrogen consumption, which affects reactor size and cost. *Table 3.2.9* is a summary of the total plant investment for all the cases. The investment cost per daily barrel of liquids is almost constant, except for Periods 13 and 16, for which the liquids production falls off.

2.0 SUMMARY

The overall economics are summarized in *Table 3.2.10*. In addition to detailing annual operating costs and byproduct credits for each case, this Table presents net product costs and equivalent crude oil prices, both in dollars per barrel.

Lowering the oil-to-solids ratio reduces equivalent crude oil price by \$0.90 per barrel as seen by comparing Period 10 with Period 4. The higher cost of Periods 13 and 16 is a result of the indicated lower liquids production at the higher space velocity and temperatures used in these operations.

The use of surfactant in Period 16 does not appear to result in a process performance improvement or in an improved product yield slate. The product cost in Period 16, even excluding surfactant cost is higher than Period 13, and for this reason the use of surfactant does not appear to be economically attractive.

Table 3.2.11 summarizes the breakdown of the equivalent crude oil price, shown in *Table 3.2.10*.

3.0 CONCLUSIONS

The results of the technical assessment of CMSL-2 show that lowering the oil-to-solids ratio is economically beneficial. The liquefaction plant cost decrease due to savings in pumps, furnaces and exchangers. There appeared to be no advantage with an increase in space velocity from the base value used in Periods 4 and 10, or with the use of surfactant.

TABLE 3.2.1
DESIGN COAL FEED ANALYSIS

	<u>CMSL-2</u>	<u>Base Case</u> (December, 1993)
Coal Type	Illinois #6	Illinois #6
Mine	Burning Star	Burning Star
<u>Proximate Analysis, W% Dry Coal</u>		
Volatile Matter	38.92	37.85
Fixed Carbon	49.04	50.65
Ash	12.04	11.50
Total	100.00	100.00
<u>Ultimate Analysis, W% Dry Coal</u>		
Carbon	69.00	71.00
Hydrogen	4.24	4.80
Nitrogen	1.26	1.40
Sulfur	4.00	3.20
Oxygen (by difference)	9.46	8.00
Chlorine	0.00	0.10
Ash	12.04	11.50
Total	100.00	100.00
H/C Atomic Ratio	0.73	0.81
O/C Atomic Ratio	0.10	0.08
<u>Sulfur Forms, W% Dry Coal</u>		
Organic	2.74	2.35
Pyritic	1.25	0.84
Sulfate	0.01	0.01
Total	4.00	3.20
<u>Heating Value, BTU/lb dry coal</u>		
measured		13,181
calculated	12,208	12,927
Coal Moisture, W%	1.16	3.08

TABLE 3.2.2

CMSL - 2
DESIGN BASIS COMPARISON

	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
<u>Operating Conditions</u>				
Space Velocity, lb/hr/ft ³	18.5	18.5	33.4	28.6
<u>Recycle Solvent</u>				
Solvent/Coal, lbs/lb	1.06	0.9	0.9	0.9
Resid, W%	19	19	19	19
<u>Temperatures, F</u>				
First Stage	752	752	777	776
Second Stage	802	802	812	811
Catalyst Replacement Rate, lb/Ton	2.7	2.7	2.7	2.7
<u>Projected Process Performance</u>				
Coal Conversion, W% MAF	92.9	92.8	92.4	93.2
Resid Conversion, W% MAF	90.9	90.5	85.8	83.8
Desulfurization, W%	78.9	80.0	77.6	75.7
Denitrogenation, W%	93.3	91.7	85.8	80.1
<u>Projected Yields, W% Dry Coal</u>				
H ₂ S	3.36	3.40	3.29	3.21
NH ₃	1.40	1.40	1.31	1.23
H ₂ O	10.45	10.20	10.13	8.64
CO _x	0.10	0.13	0.29	0.38
C ₁ -C ₃	5.45	5.49	4.69	5.10
C ₄ -350 F	17.64	18.11	18.36	15.02
350-650 F	42.08	39.98	28.50	28.36
650-975 F	6.46	8.69	15.64	17.83
975 + F	1.77	2.03	5.81	8.27
Unconverted Coal	6.25	6.33	6.68	5.98
Ash	12.04	12.04	12.04	12.04
TOTAL:	106.99	107.78	106.74	106.06
C ₄ -975, W% dry coal	66.18	66.77	62.50	61.21
, W% MAF coal	75.24	75.91	71.05	69.59

TABLE 3.2.3

CMSL - 2
OVERALL MATERIAL BALANCE

	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
Coal Feed, TPSD	9800	9800	9800	9800
Natural Gas, MMSCFD	128	113	83	77
<u>Liquid Products, BPSD</u>				
Gasoline	12519	12622	11211	11031
Diesel	30404	30563	27227	26791
TOTAL:	42923	43185	38438	37822
Barrels/Ton dry coal	4.38	4.41	3.92	3.86
<u>By-products</u>				
Propane, BPSD	2148	2161	1854	2003
Butane, BPSD	1814	1857	1861	1549
Sulfur, TPSD	346	346	346	346
Ammonia, TPSD	140	140	132	125
Ash to disposal, TPSD	1196	1212	1215	1320

TABLE 3.2.4

**CMSL - 2
PLANT NET HYDROGEN BALANCE**

	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
<u>Hydrogen Consumption, MMSCFD</u>				
Liquefaction	259	288	249	224
Product Upgrading	28	0	17	31
TOTAL:	287	288	266	255
Hydrogen Consumption, SCF/B	6678	6679	6911	6732
<u>Hydrogen Production, MMSCFD</u>				
Partial Oxidation	62	68	120	126
Steam Reforming	225	220	146	129
TOTAL:	287	288	266	255

TABLE 3.2.5

CMSL - 2
THERMAL EFFICIENCY

	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
<u>Inputs, GBTU/Day</u>				
Coal	239.3	239.3	239.3	239.3
Natural Gas	116.4	102.6	75.8	69.6
Total	355.7	341.9	315.1	308.9
<u>Outputs, GBTU/Day</u>				
Gasoline	70.0	69.6	62.7	61.6
Diesel	176.5	175.5	158.0	155.4
Propane	8.3	8.3	7.1	7.7
Butane	7.9	8.1	8.1	6.8
Sulfur	3.1	3.1	3.1	3.1
Ammonia	2.7	2.7	2.6	2.4
Total	268.5	267.3	241.6	237.0
Thermal Efficiency, %	75.5	78.2	76.7	76.7

TABLE 3.2.6

**CMSL - 2
UTILITIES SUMMARY**

	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
Electric Power, MW	159	166	170	167
600 Psig Steam, Mlbs/hr	265	254	168	172
Cooling Water, Mgpm	157	156	138	137
Process Fuel, GBTU/Day	116	103	76	70
Raw Water, gpm	4,271	4,280	4,231	4,351

TABLE 3.2.7

CMSL - 2
CAPACITIES OF PROCESS UNITS AND OFFSITES

			<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
Area No.	Description	Sizing basis, Units				
100	Coal Preparation	TPSD Dry coal	9800	9800	9800	9800
200	Liquefaction	TPSD Dry coal	9800	9800	9800	9800
300	Hydrogen Manufacture					
	Partial Oxidation	MMSCFD H ₂	62	68	120	126
	Steam Reforming	MMSCFD H ₂	225	220	146	129
400	Oxygen Plant	TPSD Oxygen	777	857	1504	1575
500	Product Treating					
	Sour Water treating	gpm sour water	2681	2694	2566	2486
	Sulfur recovery	TPSD Sulfur	346	346	346	346
	Gas plant	lb/hr C ₁ -C ₃	44517	44794	38326	41666
600	Upgrading & Solids Sep'n					
	Hydrotreating	BPSD Coal liquids	42923	43185	38438	37822
	Catalytic reforming	BPSD 180-350	12519	12622	11211	11031
700	Utilities					
	Steam generation	Mlbs/hr	265	254	168	172
	Power distribution	MW	159	166	170	167
	Cooling water	MGPM	157	156	138	137
800	Tankage					
	Coal liquids	BPSD liquids	42923	43185	38438	37822
	LPG	BPSD LPG	2148	2161	1854	2003
	Waste solids handling	TPSD solids	1196	1212	1215	1320
900	General Off-Sites	TPSD Dry coal	9800	9800	9800	9800

TABLE 3.2.8

CMSL - 2
LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
<u>Major Equipment Costs, \$M</u>				
Pumps	22127	21259	21376	21448
Reactors	61594	63790	42747	43905
Fired Heaters	14651	11444	11510	11365
Exchangers	16193	16236	15496	14973
Drums & Towers	29473	29886	28425	27403
Compressors	27207	29174	26551	24762
HPU	13020	13720	12480	11610
TOTAL	184265	185509	158585	155466
<u>Plant Investment, \$MM</u>				
Materials & Equipment	333.8	336.2	287.4	281.7
Labor & Subcontracts	144.5	145.4	124.3	121.9
Indirects	120.2	121	103.4	101.4
Contingency	0	0	0	0
Total Liquefaction Plant Investment	598.5	602.6	515.1	505

TABLE 3.2.9

CMSL - 2
TOTAL PLANT INVESTMENT SUMMARY
 (Plant Investment in \$MM, 1991 US Gulf Coast basis)

Area	Name	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
100	Coal Preparation	45.5	45.5	45.5	45.5
200	Liquefaction	598.5	602.6	515.1	505
300	Hydrogen Manufacture	238.2	239.8	230	222.6
400	Oxygen Plant	36.5	39.1	58	59.9
500	Product Treating	205.6	206.3	190.5	197.6
600	Upgrading & Solids Sep'n	118.3	116.8	111.3	111.5
700	Utilities	252.4	248.6	219.9	217.7
800	Tankage	120.6	119.6	109.8	108.3
900	General Off-Sites	185.5	185.6	185.7	186.6
	Subtotal	1801.1	1803.9	1665.8	1654.7
	Fee, Contingency	408.6	409.3	377.9	375.4
	Total Plant Investment	2210	2213	2044	2030
	\$/BPD of Product	51481	51249	53169	53675

TABLE 3.2.10

CMSL - 2
PRODUCT COST CALCULATION

	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
<u>Operating Costs, \$MM/year</u>				
Coal (\$20.50/Ton)	66	66	66	66
Natural Gas (\$2.00/MMBTU)	76.45	67.4	49.78	45.72
Water (\$0.10/Mgal)	0.2	0.2	0.2	0.21
Catalysts and Chemicals	37.76	37.49	33.5	32.62
Ash Disposal (\$5.00/Ton)	1.96	1.99	2	2.17
Labor	23.07	23.07	23.07	23.07
Maintenance	20.67	20.67	20.67	20.67
Capital-Related	333.2	333.81	307.76	305.54
TOTAL:	559.31	550.63	502.98	496
<u>By-product Credits, \$MM/year</u>				
Propane (\$7.50/B)	5.29	5.32	4.57	4.93
Butane (\$14.50/B)	8.64	8.85	8.86	7.38
Sulfur (\$80/Ton)	9.1	9.11	9.09	9.09
Ammonia (\$120/Ton)	5.53	5.53	5.2	4.92
TOTAL:	28.56	28.81	27.72	26.32
Product Cost	530.75	521.82	475.26	469.68
Product Cost, \$/B	37.64	36.74	37.64	37.8
Crude Oil Equivalent Factor	0.838	0.835	0.838	0.839
Equivalent Crude Oil Price, \$/B	31.56	30.70	31.56	31.72

TABLE 3.2.11

CMSE - 2
BREAKDOWN OF EQUIVALENT OIL CRUDE PRICE

	<u>Period 4</u>	<u>Period 10</u>	<u>Period 13</u>	<u>Period 16</u>
<u>Contribution to Price, \$/B</u>				
Coal	3.92	3.88	4.38	4.46
Natural Gas	4.55	3.97	3.31	3.09
Water	0.01	0.01	0.01	0.01
Catalysts & Chemicals	2.25	2.21	2.22	2.2
Ash Disposal	0.12	0.12	0.13	0.15
Labor	1.37	1.36	1.53	1.56
Maintenance	1.23	1.22	1.37	1.4
Capital-Related	19.81	19.64	20.44	20.63
By-product Credit	-1.7	-1.69	-1.84	-1.78
Equivalent Crude Oil Price, \$/B	31.56	30.7	31.56	31.72

VOLUME III

SECTION III

RUN CMSL-3

BLACK THUNDER MINE SUB-BITUMINOUS COAL

STUDY OF INTERSTAGE SEPARATION

**SUBSTITUTION OF AHM MOLYBDENUM ADDITIVE FOR
FIRST-STAGE EXTRUDATE CATALYST**

USE OF SYNTHESIS GAS

VOLUME III

SECTION III - RUN CMSL-3

TABLE OF CONTENTS

**STUDY OF INTERSTAGE SEPARATION
SUBSTITUTION OF AHM MOLYBDENUM ADDITIVE FOR
FIRST-STAGE EXTRUDATE CATALYST**

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	3

SECTION III - RUN CMSL-3

LIST OF TABLES

Table 3.3.1	Design Coal Feed Analysis	4
Table 3.3.2	CMSL-3 Design Basis Comparison	5
Table 3.3.3	CMSL-3 Overall Material Balance	6
Table 3.3.4	CMSL-3 Plant Net Hydrogen Balance	7
Table 3.3.5	CMSL-3 Thermal Efficiency	8
Table 3.3.6	CMSL-3 Utilities Summary	9
Table 3.3.7	CMSL-3 Capacities Of Process Units And Offsites	10
Table 3.3.8	CMSL-3 Liquefaction Plant Investment Details	11
Table 3.3.9	CMSL-3 Total Plant Investment Summary (Plant Investment In \$MM, 1991 US Gulf Coast Basis)	12
Table 3.3.10	CMSL-3 Product Cost Calculation	13
Table 3.3.11	CMSL-3 Breakdown of Equivalent Crude Oil Price	14
Table 3.3.12	CMSL-3 Comparison of Cases At Maximum Reactor Throughput	15

SECTION III - RUN CMSL-3

LIST OF FIGURES

Figure 3.3.1	Effect of CO in Feed Gas	16
Figure 3.3.2	Required Reduction in H2 Plant Cost to Offset Liquefaction Plant Cost	17

VOLUME III

SECTION III

TECHNICAL ASSESSMENT CMSL-3

1.0 BACKGROUND

The primary objective of Run 227-79 (CMSL-3) was to evaluate the use of synthesis gas in the liquefaction of subbituminous coal, while at the same time substituting a dispersed ammonium heptamolybdate catalyst for the standard supported catalyst in the first-stage reactor. The run also tested the operability of an interstage separator, as a means of reducing the vapor load to the second-stage reactor.

The subbituminous coal in CMSL-3 was a Wyoming coal from the Black Thunder mine, and the properties are summarized in *Table 3.3.1*. Two major operating conditions were assessed. In the first condition (Period 5), pure hydrogen was fed to the first stage, while in the second condition (Period 10) a synthesis gas (25% hydrogen and 75% CO) was fed to the first stage. *Table 3.3.2* summarizes the Design Basis yields used for the two operating periods that were evaluated.

The basis for the economic comparison was described in the introduction, with additional updating for the Wyoming coal as reported in Bechtel's study for that coal. It should be noted that the commercial plant design coal feed rate was increased to 10,500 T/D in five liquefaction reaction trains from 9,800 T/D in four reaction trains in the bituminous coal study. The lower per-train coal capacity with subbituminous coal is due to the higher hydrogen consumption and higher gas yields with the subbituminous coal, which results in higher vapor load per reactor. With the reactors designed at the limiting vapor velocity, with subbituminous coal the reactors are necessarily shorter with less coal feed per reactor so that more reaction trains are needed.

Overall material balances are shown in *Table 3.3.3*, *Table 3.3.4* presents net hydrogen balances, while *Table 3.3.5* shows the thermal efficiency for the cases. *Table 3.3.6* is a summary of the utilities usage, and *Table 3.3.7* shows the capacities of the various process units and off sites in the cases.

The liquefaction plant investment details are presented in *Table 3.3.8*. Substituting dispersed catalyst for supported catalyst in the first-stage reactor would undoubtedly simplify the design of the reactor internals, although no reactor cost savings were taken in this comparison. However, the costs associated with adding and withdrawing the supported catalyst were reduced. Adding an interstage separator resulted in lower reactor cost due to the lower vapor load in the second stage. This combination of factors leads to roughly a 4% reduction in liquefaction plant cost. However, use of synthesis gas negates the above savings, leading to an 11% increase in liquefaction plant cost over the base case. The primary reason for the increased cost is the increased vapor load in the entire high-pressure gas-handling part of the liquefaction

plant, affecting the cost of drums, compressors, exchangers and the hydrogen purification unit (HPU). While a more detailed engineering design may disclose that the equipment costs are not quite as high as the costs shown in this prorated and factored study, there is undoubtedly a substantial cost penalty for the increased gas load resulting from a synthesis gas feed.

Carbon monoxide reacts with water to form hydrogen and carbon dioxide in the liquefaction reactor. In Run CMSL-3 this shift reaction was lower than would be obtained at thermodynamic equilibrium but supplied a part of the hydrogen required for the liquefaction reactions. The reaction is not very helpful in reducing the overall downstream vapor load, and furthermore a cost penalty is incurred because of the need to supply and vaporize water to reactor. As a final observation, while the actual CMSL run used synthesis gas to the first stage and pure hydrogen to the second stage, the commercial evaluation assumed that synthesis gas is fed to both reactor stages. It was realized that this assumption adds to the liquefaction plant cost but two levels of hydrogen purity would add to complexity of the plant.

The process alternative corresponding to the experimental CMSL-3 pattern would be to change the hydrogen plant configuration to provide syngas for the first stage, and high purity hydrogen to second stage. This would involve installing shift reactors and hydrogen purification in a portion of the gasification trains. The cost of the liquefaction plant would be lowered by 10% compared to the all syngas case, which saving is probably more than the additional costs in the hydrogen plant, with substantial savings in the utilities costs. A preliminary estimate indicates even with this modification the oil product cost using syngas only to the first stage would still be about \$0.7 per barrel higher than if all of the feed was high purity hydrogen

Table 3.3.9 is a summary of the total plant investment for all the cases. Several process steps can be eliminated when producing synthesis gas instead of pure hydrogen. These steps include shift conversion, carbon dioxide removal and final carbon monoxide removal. The cost savings due to eliminating these steps, assumed to be 25% of the total hydrogen manufacture plant cost, are substantial, but do not offset the higher liquefaction plant cost. The result is a higher cost per barrel of product when using synthesis gas.

2.0 SUMMARY

The overall economics are summarized in *Table 3.3.10*. With an interstage separator, high purity hydrogen feed to both stages, and using the 1500 ppm dispersed Mo catalyst the equivalent crude oil price is \$29.89 per barrel using the CMSL-3 yields. There was no exactly comparable operation without the interstage separator especially with regard to catalyst usage. However, this cost was the lowest calculated for any of the five CMSL runs with Black Thunder Mine coal that were evaluated (see *Table 3.1.3* above). The advantage can be considered to combine the benefits of interstage separation and the use of the catalyst additive in place of the extrudate catalyst in the first stage. In Run CMSL-6, without the interstage separator and lower amounts of catalyst additives, the equivalent crude oil price was higher by \$2.3 per barrel. In *Table 3.3.10*, the use of syngas adds \$0.6 per barrel to the equivalent crude oil price.

As noted previously, a major advantage of using an interstage separator is reducing the vapor load in the reactors which permits longer, smaller diameter reactors at a fixed coal throughput

per reactor. Realistically, it is more cost-effective to construct maximum diameter reactors and maximize the per reactor coal processing capacity and thereby reducing the number of operating liquefaction trains. *Table 3.3.12*, comparing the cases at maximum coal throughput per reactor, shows a further advantage of using interstage separators which lowers the equivalent crude oil price by \$2.2-2.60 per barrel to as low as \$27.00 per barrel.

Table 3.3.11 is a breakdown of the equivalent crude oil price shown in *Table 3.3.10*. Subsequent CMSL runs indicated that the dispersed Mo (as AHM) feed rates could be dropped considerably below the rate of 1500 ppm used in Run CMSL-2 with little change in process performance. In *Table 3.3.11*, the cost of the dispersed AHM catalyst (at \$3.00 per pound) corresponded to \$1.64 in the equivalent crude oil cost. Any reduction in the amount of Mo additive or its cost (such as Molyvan lubricant additive) would result in proportional reduction in the equivalent crude oil cost.

The economic effect of using synthesis gas in liquefaction was studied based on a 50/50 (molar) carbon monoxide/hydrogen mixture, assumed directly obtainable from the gasifier or from a reformer in a hydrogen plant. There is a substantial increase in liquefaction plant cost with increasing carbon monoxide content of the liquefaction feed gas, as shown in *Figure 3.3.2*. This increased liquefaction plant cost can be related to the required savings in the hydrogen plant cost, as shown in *Figure 3.3.2*. Thus a 50/50 feed gas would require a 32% reduction in the cost of the hydrogen plant. There is obviously a trade-off in cost, between the hydrogen manufacturing facility and the liquefaction plant which needs to be investigated in more detailed future economics studies.

3.0 CONCLUSIONS

The results of the technical assessment of CMSL-3 have shown that the use of interstage separation is cost effective. The economic benefit of ammonium heptamolybdate dispersed catalyst is marginal, depending on the catalyst cost and use rate. While feeding synthesis gas to only the first reactor stage is more economical than feeding this gas to both reactor stages, the use of synthesis gas appears uneconomic at low hydrogen content, but a more detailed engineering study is needed in this area.

TABLE 3.3.1

DESIGN COAL FEED ANALYSIS

CMSL -3

Coal Type
MineWyoming
Black ThunderProximate Analysis, W% Dry Coal

Volatile Matter	43.37
Fixed Carbon	50.36
Ash	6.27
Total	100.00

Ultimate Analysis, W% Dry Coal

Carbon	70.40
Hydrogen	3.88
Nitrogen	0.87
Sulfur	0.44
Oxygen (by difference)	18.14
Chlorine	0.00
Ash	6.27
Total	100.00

SO ₃ -free ash	5.59
H/C Atomic Ratio	0.66
O/C Atomic Ratio	0.19

Heating Value, BTU/lb dry coal calculated 11,339

Coal Moisture, W% 25.4

TABLE 3.3.2

CMSL - 3
DESIGN BASIS COMPARISON

<u>Operating Conditions</u>	<u>Period 5</u>	<u>Period 12</u>
Interstage separator	Yes	Yes
Dispersed catalyst, ppm	1500	1500
CO in feed gas, mol%	0	75
Space Velocity, lb/hr/ft ³	19	19
<u>Recycle Solvent</u>		
Solvent/Coal, lb/lb	1.2	1.2
Resid, W%	24.5	24.5
<u>Temperatures, F</u>		
First Stage	750	750
Second Stage	800	800
<u>Supported Catalyst Replacement Rate</u>		
First stage, lbs/Ton	0	0
Second stage, lb/Ton	1.35	1.35
Overall, lbs/Ton	1.35	1.35
<u>Projected Process Performance</u>		
Coal Conversion, W% MAF	89.5	92.4
Resid Conversion, W% MAF	87.2	86.9
Denitrogenation, W%	75.9	80.7
<u>Projected Yields, W% Dry Coal</u>		
H ₂ S	0.15	0.16
NH ₃	0.8	0.85
H ₂ O	12.89	11.68
CO _x	6.62	8.14
C ₁ -C ₃	6.62	6.69
C ₄ -390 F	16.29	13.6
390-500 F	11.64	9.07
500-650 F	21.61	18
650-850 F	11.97	18.23
850-975 F	1	2.13
975 + F	2.34	5.42
Unconverted Coal	9.9	7.22
Ash	5.59	5.59
Total:	107.42	106.78
C ₄ -975 F, W% dry coal	62.51	61.03
, W% MAF	66.21	64.64

TABLE 3.3.3

CMSL - 3
OVERALL MATERIAL BALANCE

	<u>Period 5</u>	<u>Period 12</u>
Coal Feed, TPSD	10,500	10,500
Natural Gas, MMSCFD	116	123
<u>Liquid Products, BPSD</u>		
Gasoline	12,520	12,128
Diesel	30,405	29,455
TOTAL:	42,925	41,583
Barrels/Ton dry coal	4.09	3.96
<u>By-products</u>		
Propane, BPSD	2,757	2,780
Butane, BPSD	1,797	1,525
Sulfur, TPSD	59	65
Ammonia, TPSD	88	93
Ash to disposal, TPSD	792	811

TABLE 3.3.4

**CMSL-3
PLANT NET HYDROGEN BALANCE**

	<u>Period 5</u>	<u>Period 12</u>
<u>Hydrogen Consumption, MMSCFD</u>		
Liquefaction	294	268
Product Upgrading	15	34
TOTAL:	309	302
Hydrogen Consumption, SCF/B	7,203	7,276
<u>Hydrogen Production, MMSCFD</u>		
Partial Oxidation	93	105
Steam Reforming	216	197
TOTAL:	309	302

TABLE 3.3.5

CMSL - 3
THERMAL EFFICIENCY

	<u>Period 5</u>	<u>Period 12</u>
<u>Inputs, GBTU/Day</u>		
Coal	238.1	238.1
Natural Gas	105.3	111.3
Total	343.4	349.4
 <u>Outputs, GBTU/Day</u>		
Gasoline	70.0	67.8
Diesel	176.5	170.9
Propane	10.6	10.7
Butane	7.8	6.6
Sulfur	0.5	0.6
Ammonia	1.7	1.8
Total	267.1	258.4
 Thermal Efficiency, %	 77.8	 74

TABLE 3.3.6

**CMSL - 3
UTILITIES SUMMARY**

	<u>Period 5</u>	<u>Period 12</u>
Electric Power, MW	194	252
600 Psig Steam, Mlbs/hr	95	115
Cooling Water, Mgpm	119	122
Process Fuel, GBTU/Day	105	111
Raw Water, gpm	2,914	3,203

TABLE 3.3.7

CMSL - 3
CAPACITIES OF PROCESS UNITS AND OFFSITES

			<u>Period 5</u>	<u>Period 12</u>
Area				
No.	Description	Sizing basis, Units		
100	Coal Preparation	TPSD Dry coal	10,500	10,500
200	Liquefaction	TPSD Dry coal	10,500	10,500
300	Hydrogen Manufacture			
	Partial Oxidation	MMSCFD H ₂	93	105
	Steam Reforming	MMSCFD H ₂	216	197
400	Oxygen Plant	TPSD Oxygen	1,166	1,317
500	Product Treating			
	Sour Water treating	gpm sour water	1,483	1,487
	Sulfur recovery	TPSD Sulfur	59	65
	Gas plant	lb/hr C ₁ -C ₃	57,925	58,538
600	Upgrading & Solids Sep'n			
	Hydrotreating	BPSD Coal liquids	42,925	41,583
	Catalytic reforming	BPSD 180-350	15,067	15,067
700	Utilities			
	Steam generation	Mlbs/hr	95	115
	Power distribution	MW	194	252
	Cooling water	MGPM	119	122
800	Tankage			
	Coal liquids	BPSD liquids	42,925	41,583
	LPG	BPSD LPG	2,757	2,780
	Waste solids handling	TPSD solids	792	811
900	General Off-Sites	TPSD Dry coal	10,500	10,500

TABLE 3.3.8

CMSL - 3
LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 5</u>	<u>Period 12</u>
<u>Major Equipment Costs, \$M</u>		
Pumps	23,974	23,978
Reactors	53,936	55,176
Fired Heaters	13,486	17,374
Exchangers	19,185	24,125
Drums & Towers	33,008	38,881
Compressors	37,014	47,530
HPU	16,449	22,711
TOTAL	197,052	229,775
<u>Plant Investment, \$MM</u>		
Materials & Equipment	357.0	416.3
Labor & Subcontracts	154.5	180.1
Indirects	128.5	149.9
Contingency	0.0	0.0
Total Liquefaction Plant Investment	640.0	746.3

TABLE 3.3.9

CMSE - 3

TOTAL PLANT INVESTMENT SUMMARY

(Plant Investment In \$MM, 1991 US Gulf Coast Basis)

		<u>Period 5</u>	<u>Period 12</u>
Area	Name		
100	Coal Preparation	200.0	200.0
200	Liquefaction	640.0	746.3
300	Hydrogen Manufacture	256.0	189.7
400	Oxygen Plant	48.6	52.9
500	Product Treating	204.4	206.3
600	Upgrading & Solids Sep'n	123.1	121.4
700	Utilities	233.3	275.7
800	Tankage	120.6	117.4
900	General Off-Sites	190.0	190.2
	Subtotal	2016.0	2099.9
	Fee, Contingency	402.7	419.5
	Total Plant Investment	2,419	2,519
	\$/BPD of Product	56,347	60,587

TABLE 3.3.10

CMSL - 3
PRODUCT COST CALCULATION

	<u>Period 5</u>	<u>Period 12</u>
<u>Operating Costs, \$MM/year</u>		
Coal (\$7.00/Ton)	24.14	24.14
Natural Gas (\$2.00/MMBTU)	69.20	73.12
Water (\$2.50/Mgal)	3.45	3.79
Catalysts and Chemicals	26.41	25.5
Dispersed Catalyst	31.04	31.04
Ash Disposal (\$5.00/Ton)	1.30	1.33
Labor	24.43	24.43
Maintenance	21.89	21.89
Capital-Related	362.70	376.03
TOTAL:	564.56	581.27
<u>By-product Credits, \$MM/year</u>		
Propane (\$12.29/Bbl)	11.13	11.23
Butanes (\$14.50/B)	8.56	7.26
Sulfur (\$52.00/Ton)	1.01	1.11
Ammonia (\$200.00/Ton)	5.78	6.14
TOTAL:	26.48	25.74
Net Product Cost, \$MM/year	538.08	555.53
Product Cost, \$/B	38.16	40.67
Crude Oil Equivalent Factor	0.841	0.852
Equivalent Crude Oil Price, \$/B	32.08	34.65

TABLE 3.3.11

CMSL - 3
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 5</u>	<u>Period 12</u>
<u>Contribution to Price, \$/B</u>		
Coal	1.44	1.51
Natural Gas	4.13	4.56
Water	0.21	0.24
Catalyst & Chemicals	1.57	1.59
Dispersed Catalyst	1.85	1.94
Ash Disposal	0.08	0.08
Labor	1.46	1.52
Maintenance	1.31	1.37
Capital Related	21.63	23.45
By-product Credit	-1.58	-1.61
Equivalent Crude Oil Price, \$/B	32.08	34.65

TABLE 3.3.12

CMSL - 3
COMPARISON OF CASES AT MAXIMUM REACTOR
THROUGHPUT

	<u>Period 5</u>	<u>Period 12</u>
Coal to liquefaction, T/D	13,250	12,250
Number of liquefaction trains	3	3
Coal, T/D/train	4,417	4,083
Product, B/D	54,117	48,482
Liquefaction Plant Cost, \$MM	671	736
Total Plant Investment, \$MM	2,762	2,699
Net Annual Operating cost, \$MM	626.62	606.98
Product Cost, \$/B	35.25	38.11
Equivalent Crude Oil Price, \$/B	29.17	32.04

Effect of CO in Feed Gas

on Liquefaction Plant Cost

FIGURE 3.3.1

Required Reduction in H2 Plant Cost to Offset Higher Liquefac'n Plant Cost

FIGURE 3.3.

VOLUME III

SECTION III

RUN CMSL-4

BLACK THUNDER MINE SUB-BITUMINOUS COAL

STUDY OF INTERSTAGE SEPARATION,

EXTRUDATE CATALYST IN BOTH STAGE

SYNTHESIS GAS TO FIRST STAGE

IN-LINE HYDROTREATING

VOLUME III

SECTION III - CMSL-4

TABLE OF CONTENTS

STUDY OF INTERSTAGE SEPARATION, EXTRUDATE CATALYST IN BOTH STAGE

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	2

VOLUME III

SECTION III - CMSL-4

LIST OF TABLES

Table 3.4.1	CMSL- 4	Design Basis Comparison	3
Table 3.4.2	CMSL - 4	Overall Material Balance	4
Table 3.4.4	CMSL - 4	Thermal Efficiency	6
Table 3.4.5	CMSL - 4	Utilities Summary	7
Table 3.4.6	CMSL - 4	Capacities Of Process Units And Offsites	8
Table 3.4.7	CMSL - 4	Liquefaction Plant Investment Details	9
Table 3.4.8	CMSL - 4	Total Plant Investment Summary (Plant Investment In \$MM, 1991 US Gulf Coast Basis)	10
Table 3.4.9	CMSL - 4	Product Cost Calculation	11
Table 3.4.10	CMSL - 4	Breakdown Of Equivalent Crude Oil Price	12
Table 3.4.11	CMSL - 4	Economic Comparison Of Cases At Maximum Reactor Throughput	13

VOLUME III

SECTION III

TECHNICAL ASSESSMENT CMSL-4

1.0 BACKGROUND

The primary objective of Run 227-81 (CMSL-4) was to evaluate the use of synthesis gas in the liquefaction of subbituminous coal using standard supported catalyst in both reactor stages. The run also tested the operability of an in-line hydrotreater as a means of reducing the downstream product upgrading requirements, in addition the run used an interstage separator.

The subbituminous coal for CMSL-4 was the same Wyoming coal from the Black Thunder Mine previously used in CMSL-3. Four operating conditions were assessed. In the first condition (Period 5), pure hydrogen was fed to both reactor stages while in the second condition (Period 10) synthesis gas containing 86% CO was fed to the first stage at the same reactor operating conditions. Temperature and space velocity were both increased for the third condition (Period 12), while in the fourth condition (Period 16) the CO content of the feed gas fell to 30% inadvertently at the same reactor conditions as in the third condition.

Overall material balances are shown in *Table 3.4.2*. *Table 3.4.3* presents net hydrogen balances, while *Table 3.4.4* shows the thermal efficiency for the cases. *Table 3.4.5* is a summary of the utilities usage, and *Table 4.6* shows the capacities of the various process units and off sites for the cases.

The details of the liquefaction plant investment are present in *Table 3.4.7*. *Table 3.4.8* is a summary of the total plant investment for all the cases. For Period 10, with synthesis gas feed, the liquefaction plant investment is 27% higher than that for the Period 5 operation, with high purity hydrogen feed only, *Table 3.4.7*. This increase is because of the greater cost of auxiliary vessels, heaters, and compressors because of the higher vapor load with synthesis gas. While the estimated cost of the hydrogen (or synthesis gas) preparation section is, lowered by 24%, this saving is less than the additional costs in the liquefaction section, so that the overall plant investment is higher by 8% when using synthesis gas feed to the liquefaction section, *Table 3.4.8*.

2.0 SUMMARY

The overall economics are summarized in *Table 3.4.9*. The equivalent crude oil price for the Period 5 Condition, with high purity hydrogen feed, is \$32.62 per barrel. For the Period 10 Condition, with syngas feed, this price was higher by \$2.60 per barrel. For the Period 12 Condition, at 20% higher space velocity with syngas, the estimated price was higher by \$1.60 per barrel than for the Period 5 Condition.

The Run CMSL-4 Period 5 projected cost is \$2.60 per barrel higher than that Projected for Period 4 of Run CMSL-3, see *Table A-2* above. The principal difference in the Run CMSL-4 operation was the use in Run CMSL-3 of 1500 ppm Mo additive with no extrudate catalyst in the first stage. With syngas feed the Run CMSL-4 costs were \$3.9-5.0 higher than that of Run CMSL-3. The greater increase cost in the syngas operations for the Run CMSL-4 reflects the reaction of CO in the syngas to CH₄ when using extrudate Catalyst and the need for more syngas feed than when using Mo additive only as in Run CMSL-3.

Table 4.4.10 summarizes the breakdown of the equivalent crude oil prices which are given in *Table 3.4.9*.

Table 3.4.11 summarizes an economic comparison when using maximum diameter, longer reactors, and fewer liquefaction trains because of the lower vapor loading afforded by the use of an interstage separator. Here, the equivalent crude oil price is \$3.90 per barrel, lower than for the conventional design case given *Table 3.4.9* when feeding high purity hydrogen only, and \$0.5-1.90 per barrel lower for the various syngas cases evaluated.

3.0 CONCLUSIONS

The use of 1500 ppm Mo additive with no first stage extrudate, as in Run CMSL-3, has lower product cost than using extrudate catalyst in both stages. Use of synthesis gas in place of high purity hydrogen has appreciably higher plant investment and product costs. This impact was greater when there was extrudate catalyst in the stage into which the syngas was fed than when a catalyst additive replaced the extrudate catalyst.

TABLE 3.4.1

CMSL - 4
DESIGN BASIS COMPARISON

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
<u>Operating Conditions</u>				
Interstage separator	yes	yes	yes	yes
In-line hydro-treater	yes	yes	yes	yes
CO in feed gas to liquefaction, %	0	86	84	30
Space Velocity, lb/hr/ft ³	19.2	19.2	23.1	23.5
<u>Recycle Solvent</u>				
Solvent/Coal, lbs/lb	1.2	1.2	1.2	1.2
Resid, W%	28.5	28.5	28.5	28.5
<u>Temperatures, F</u>				
First Stage	752	752	777	776
Second Stage	800	800	820	820
Catalyst Replacement Rate, lb/Ton	2.7	2.7	2.7	2.7
<u>Projected Process Performance</u>				
Coal Conversion, W% MAF	86.8	87.6	90.8	86.8
Resid Conversion, W% MAF	84.3	84.4	87.2	81.9
Denitrogenation, W%	80.3	73.6	84.0	81.3
<u>Projected Yields, W% Dry Coal</u>				
H ₂ S	0.19	0.13	0.25	0.22
NH ₃	0.85	0.79	0.89	0.86
H ₂ O	16.33	16.48	17.07	16.31
CO _x	1.90	2.04	2.20	2.26
C ₁ -C ₃	7.33	6.76	6.70	6.43
C ₄ -350 F	17.16	17.58	17.97	16.77
350-650 F	32.82	33.87	34.73	31.86
650-975 F	10.52	10.87	11.14	10.23
975 + F	2.36	3.02	3.40	4.63
Unconverted Coal	12.46	11.71	8.69	12.46
Ash	5.59	5.59	5.59	5.59
TOTAL:	107.52	108.83	108.63	107.62
C ₄ -975, W% dry coal	60.50	62.31	63.85	58.86
, W% MAF	64.09	66.00	67.63	62.35

TABLE 3.4.2

CMSL - 4
OVERALL MATERIAL BALANCE

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
Coal Feed, TPSD	10500	10500	10500	10500
Natural Gas, MMSCFD	116	135	146	125
<u>Liquid Products, BPSD</u>				
Gasoline	12016	12117	12491	11633
Diesel	29182	29427	30335	28252
TOTAL:	41198	41544	42826	39885
Barrels/Ton dry coal	3.92	3.96	4.08	3.8
<u>By-products</u>				
Propane, BPSD	3034	2810	2789	2670
Butane, BPSD	1874	1921	1965	1832
Sulfur, TPSD	64	63	64	63
Ammonia, TPSD	89	83	93	90
Ash to disposal, TPSD	860	838	774	843

TABLE 3.4.3

CMSE - 4
PLANT NET HYDROGEN BALANCE

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
<u>Hydrogen Consumption, MMSCFD</u>				
Liquefaction	298	333	339	302
Product Upgrading	31	0	0	19
TOTAL:	329	333	339	321
Hydrogen Consumption, SCF/B	7975	8026	7915	8050
<u>Hydrogen Production, MMSCFD</u>				
Partial Oxidation	116	119	103	139
Steam Reforming	213	214	236	182
TOTAL:	329	333	339	321

TABLE 3.4.4

**CMSL - 4
THERMAL EFFICIENCY**

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
<u>Inputs, GBTU/Day</u>				
Coal	238.1	238.1	238.1	238.1
Natural Gas	105.5	122.1	132.9	113.1
Total	343.6	360.2	371.0	351.2
<u>Outputs, GBTU/Day</u>				
Gasoline	67.2	67.7	69.8	65.0
Diesel	169.4	170.8	176.1	163.9
Propane	11.7	10.8	10.7	10.3
Butane	8.2	8.4	8.6	8.0
Sulfur	1.7	1.6	1.8	1.7
Ammonia	0.6	0.6	0.6	0.6
Total	258.8	259.9	267.6	249.5
Thermal Efficiency, %	75.3	72.2	72.1	71.1

TABLE 3.4.5

**CMSL - 4
UTILITIES SUMMARY**

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
Electric Power, MW	208	299	290	282
600 Psig Steam, Mlbs/hr	190	156	158	179
Cooling Water, Mgpm	138	132	134	133
Process Fuel, GBTU/Day	106	122	133	113
Raw Water, gpm	3,789	3,517	3,388	3,890

TABLE 3.4.6

CMSL - 4

CAPACITIES OF PROCESS UNITS AND OFFSITES

			<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
Area						
No.	Description	Sizing basis, Units				
100	Coal Preparation	TPSD Dry coal	10,500	10,500	10500	10500
200	Liquefaction	TPSD Dry coal	10,500	10,500	10500	10500
300	Hydrogen Manufacture					
	Partial Oxidation	MMSCFD H ₂	116	119	103	139
	Steam Reforming	MMSCFD H ₂	212	214	236	182
400	Oxygen Plant	TPSD Oxygen	1,455	1,496	1290	1745
500	Product Treating					
	Sour Water treating	gpm sour water	1,558	1,524	1621	1555
	Sulfur recovery	TPSD Sulfur	64	63	64	63
	Gas plant	lb/hr C1-C3	64,164	59,159	58634	56228
600	Upgrading & Solids Sep'n					
	Hydrotreating	BPSD Coal liquids	41,198	41,544	42826	39885
	Catalytic reforming	BPSD 180-350	12,016	12,117	12491	11633
700	Utilities					
	Steam generation	Mlbs/hr	190	156	158	179
	Power distribution	MW	208	299	290	282
	Cooling water	MGPM	138	132	134	133
800	Tankage					
	Coal liquids	BPSD liquids	41,198	41,544	42826	39885
	LPG	BPSD LPG	3,034	2,810	2789	2670
	Waste solids handling	TPSD solids	860	838	774	843
900	General Off-Sites	TPSD Dry coal	10,500	10,500	10500	10500

TABLE 3.4.7

CMSL - 4
LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
<u>Major Equipment Costs, \$M</u>				
Pumps	24,536	24,223	24,329	24,468
Reactors	53,582	56,593	49,183	45,965
Fired Heaters	13,604	20,060	20,561	19,458
Exchangers	19,212	26,746	26,533	25,311
Drums, Towers & Hydrotreater	38,952	50,275	49,822	47,470
Compressors	37,222	53,719	53,133	50,160
HPU	16,445	26,306	26,092	24,262
TOTAL	203,553	257,922	249,653	237,094
<u>Plant Investment, \$MM</u>				
Materials & Equipment	368.8	467.3	452.3	429.6
Labor & Subcontracts	159.6	202.2	195.7	185.9
Indirects	132.8	168.2	162.8	154.6
Contingency	0.0	0.0	0.0	0.0
Total Liquefaction Plant Investment	661.2	837.7	810.8	770.1

TABLE 3.4.8

CMSL - 4

TOTAL PLANT INVESTMENT SUMMARY
(PLANT INVESTMENT IN \$MM, 1991 US GULF COAST BASIS)

Area	Name	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
100	Coal Preparation	200.0	200.0	200.0	200.0
200	Liquefaction	661.2	837.7	810.8	770.1
300	Hydrogen Manufacture	269.4	204.1	206.1	198.9
400	Oxygen Plant	56.7	57.8	52.1	64.4
500	Product Treating	218.3	207.8	207.6	201.9
600	Upgrading & Solids Sep'n	95.7	96.6	97.0	95.2
700	Utilities	243.7	307.0	301.1	295.6
800	Tankage	116.5	117.3	120.4	113.3
900	General Off-Sites	190.7	190.5	189.8	190.5
	Subtotal	2052.2	2218.8	2184.9	2129.9
	Fee, Contingency	409.9	443.2	436.4	425.5
	Total Plant Investment	2462	2,662	2,621	2,555
	\$/BPD of Product	59763	64,077	61,208	64,069

TABLE 3.4.9

CMSL - 4
PRODUCT COST CALCULATION

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
<u>Operating Costs, \$MM/year</u>				
Coal (\$7.00/Ton)	24.14	24.14	24.14	24.14
Natural Gas (\$2.00/MMBTU)	69.29	80.22	87.33	74.32
Water (\$2.50/Mgal)	4.48	4.16	4.01	4.60
Catalysts and Chemicals	38.24	38.23	39.39	36.64
Ash Disposal (\$5.00/Ton)	1.41	1.38	1.27	1.38
Labor	24.43	24.43	24.43	24.43
Maintenance	21.89	21.89	21.89	21.89
Capital-Related	367.83	395.90	390.89	380.19
TOTAL:	551.71	590.35	593.35	567.59
<u>By-product Credits, \$MM/year</u>				
Propane (\$12.29/B)	12.25	11.35	11.26	10.78
Butane, (\$14.50/B)	8.93	9.15	9.36	8.72
Sulfur (\$52.00/Ton)	1.09	1.08	1.09	1.08
Ammonia (\$200.00/Ton)	5.86	5.45	6.14	5.93
TOTAL:	28.13	27.03	27.85	26.51
Product Cost	523.58	563.32	565.50	541.08
Product Cost, \$/B	38.69	41.28	40.20	41.30
Crude Oil Equivalent Factor	0.843	0.855	0.850	0.855
Equivalent Crude Oil Price, \$/B	32.62	35.28	34.17	35.31

TABLE 3.4.10

CMSL - 4
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
<u>Contribution to Price, \$/B</u>				
Coal	1.50	1.51	1.46	1.58
Natural Gas	4.32	5.02	5.28	4.85
Water	0.28	0.26	0.24	0.3
Catalysts & Chemicals	2.38	2.39	2.38	2.39
Ash Disposal	0.09	0.09	0.08	0.09
Labor	1.52	1.53	1.48	1.59
Maintenance	1.36	1.37	1.32	1.43
Capital-Related	22.92	24.79	23.62	24.81
By-product Credit	-1.75	-1.69	-1.68	-1.73
Equivalent Crude Oil Price, \$/B	32.62	35.28	34.17	35.31

TABLE 3.4.11

CMSL - 4
ECONOMIC COMPARISON OF CASES AT MAXIMUM REACTOR
THROUGHPUT

	<u>Period 5</u>	<u>Period 10</u>	<u>Period 12</u>	<u>Period 16</u>
Coal to Liquefaction, T/D	13,750	9,800	9,800	11,200
Number of Liquefaction Trains	3	3	3	3
Coal, T/D/train	4,583	3,267	3,267	3,733
Product, B/D	53,890	38,788	39,983	42,532
Liquefaction Plant Cost, \$MM	708	703	672	711
Total Plant Investment, \$MM	2,864	2,419	2,377	2,558
Net Annual Operating Cost, \$MM	615.43	519.82	521.95	548.97
Product Cost, \$/B	34.77	40.80	39.74	39.29
Equivalent Crude Oil Price, \$/B	28.70	34.79	33.69	33.24

VOLUME III

SECTION III

RUN CMSL-5

ILLINOIS NO. 6 COAL

STUDY OF INTERSTAGE SEPARATION,

FEED SPACE VELOCITY

**SYNTHESIS GAS FEED EXTRUDATE CATALYST IN
BOTH STAGES**

VOLUME III

SECTION III - CMSL 5

TABLE OF CONTENTS

**STUDY OF INTERSTAGE SEPARATION,
FEED SPACE VELOCITY**

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	2

SECTION III - CMSL 5

LIST OF TABLES

Table 3.5.1	Design Coal Feed Analysis	3
Table 3.5.2	CMSL - 5 Design Basis Comparison	4
Table 3.5.3	CMSL - 5 Overall Material Balance	5
Table 3.5.4	CMSL - 5 Plant Net Hydrogen Balance	6
Table 3.5.5	CMSL - 5 Thermal Efficiency	7
Table 3.5.6	CMSL - 5 Utilities Summary	8
Table 3.5.7	CMSL - 5 Capacities Of Process Units And Offsites	9
Table 3.5.8	CMSL - 5 Liquefaction Plant Investment Details	10
Table 3.5.9	CMSL - 5 Total Plant Investment Summary	11
Table 3.5.10	CMSL - 5 Product Cost Calculation	12
Table 3.5.11	CMSL - 5 Breakdown Of Equivalent Crude Oil Price	13
Table 3.5.12	CMSL - 5 Economic Comparison Of Cases At Maximum Reactor Throughput	14

VOLUME III

SECTION III

TECHNICAL ASSESSMENT - CMSL-5

1.0 BACKGROUND

The primary objective of Run 227-82 (CMSL-5) was to evaluate the use of synthesis gas in the liquefaction of bituminous coal, using standard supported catalyst in both reactor stages. The run also tested two process improvements on bituminous coal, which were previously found successful with subbituminous coal: (1) an interstage separator to reduce the vapor load to the second-stage reactor, and (2) an in-line hydrotreater to lower downstream product upgrading requirements.

The bituminous coal in CMSL-5 was an Illinois #6 coal from the Crown II Mine, having a lower ash-content than of the coal from Burning Star Mine used in CMSL-2, as shown in *Table 3.5.1*. Three operating conditions were assessed. Pure hydrogen was fed to the first stage in the first condition (Period 8) and in the second condition (Period 11), while in the third condition (Period 13) synthesis gas containing 75% was fed to the first stage. Conditions 2 and 3 were at the same temperature and space velocity. Condition 1 was at a higher temperature and higher space velocity than the other two conditions.

Overall material balances are shown in *Table 3.5.3*, illustrating the lower liquids production in CMSL-5 projected run conditions. *Table 3.5.4* presents net hydrogen balances. *Table 3.5.5* shows the thermal efficiency for the cases. *Table 3.5.6* is a summary of the utilities usage, while *Table 3.5.7* shows the capacities of the various process units and off sites.

The liquefaction plant investment details are presented in *Table 3.5.8*. Use of synthesis gas increases the liquefaction plant investment by 20%, or about the same as with subbituminous coal. *Table 3.5.8* also shows a 7% lower liquefaction plant investment in Period 8 over Period 11, owing to the lower process severity.

Table 3.5.9 is a summary of the total plant investment for all the cases. The total plant investment for Period 13 case using syngas feed is 5% higher than that of the comparable case with high purity hydrogen feed, with the decrease in hydrogen plant cost being less than the increase in the liquefaction section cost.

2.0 SUMMARY

The overall economics are summarized in *Table 3.5.10*. The equivalent crude oil price for the Period 5 operation with high purity hydrogen feed, \$30.12 per barrel is \$1.40 per barrel lower than that for an operation at a similar space velocity in Run CMSL-2. This difference is largely associated with the use on interstage separator in Run CMSL-5. From CMSL-5 projected yields, the higher reactor operating space velocity decreases the crude oil equivalent price by \$0.53 per barrel, while use of synthesis gas adds \$2.13 per barrel to the crude oil equivalent price.

Table 3.5.11 summarizes the breakdown of the equivalent crude oil price.

Table 3.5.12 shows results of the economic comparison utilizing maximum diameter reactors and fewer liquefaction trains. This comparison clearly shows the advantage of interstage separators with equivalent crude oil prices lowered by \$2.5-3.00 per barrel. The use of synthesis gas appears continues to be more costly even with the maximum per liquefaction train coal throughput.

3.0 CONCLUSIONS

The results of the technical assessment of CMSL-5 have shown that the use of an in-line hydrotreater and an interstage separator are both economically cost effective with bituminous coal. This conclusion substantiates the previous findings with subbituminous coal. Synthesis gas use increases total plant investment cost, but the overall debit is not as great as previously found with subbituminous coal. The use of a higher reactor space velocity is economically beneficial.

TABLE 3.5.1

DESIGN COAL FEED ANALYSIS

	CMSL-2	CMSL-5
Coal Type	Illinois #6	Illinois #6
Mine	Burning Star	Crown II
<u>Proximate Analysis, W% Dry Coal</u>		
Volatile Matter	38.92	41.04
Fixed Carbon	49.04	48.56
Ash	12.04	10.4
Total	100	100
<u>Ultimate Analysis, W% Dry Coal</u>		
Carbon	69.00	70.28
Hydrogen	4.24	4.73
Nitrogen	1.26	1.33
Sulfur	4.00	4.17
Oxygen (by difference)	9.46	9.09
Ash	12.04	10.4
Total	100	100
H/C Atomic ratio	0.732	0.802
O/C Atomic ratio	0.103	0.097
<u>Sulfur Forms, W% dry coal</u>		
Organic	2.74	2.86
Pyritic	1.25	1.3
Sulfate	0.01	0.01
Total	4	4.17
Heating value, BTU/lb dry coal calculated	12208	12739
Coal moisture, w%	1.16	3.98

TABLE 3.5.2

CMSL - 5
DESIGN BASIS COMPARISON

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Operating Conditions</u>			
Interstage separator	yes	yes	yes
Inline hydrotreater	yes	yes	yes
CO in feed gas to liquefaction, %	0	0	50
Space Velocity, lb/hr/ft ³	28.8	19.8	19.8
<u>Recycle Solvent</u>			
Solvent/Coal, lbs/lb	0.9	0.9	0.9
Resid, W%	30.5	30.5	30.5
<u>Temperatures, F</u>			
First Stage	775	775	750
Second Stage	825	800	800
Catalyst Replacement Rate, lb/Ton	2.7	2.7	2.7
<u>Projected Process Performance</u>			
Coal Conversion, W% MAF	96.0	95.0	96.0
Resid Conversion, W% MAF	92.9	84.8	83.7
Desulfurization, W%	98.5	96.7	97.0
Denitrogenation, W%	95.0	92.2	91.3
<u>Projected Yields, W% Dry Coal</u>			
H ₂ S	4.37	4.28	4.29
NH ₃	1.54	1.49	1.48
H ₂ O	7.53	5.68	5.24
CO _x	0.26	0.27	0.27
C ₁ -C ₃	7.38	5.12	5.65
C ₄ -350 F	16.36	12.23	13.46
350-650 F	39.59	32.36	30.14
650-975 F	11.87	20.35	20.37
975 + F	2.78	9.13	11.02
Unconverted Coal	3.58	4.48	3.58
Ash	10.40	10.40	10.40
TOTAL:	105.66	105.80	105.90
C ₄ -975, W% dry coal	67.82	64.95	63.97
, W% MAF	75.70	72.49	71.40

TABLE 3.5.3**CMSL - 5
OVERALL MATERIAL BALANCE**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
Coal Feed, TPSD	9,800	9,800	9,800
Natural Gas, MMSCFD	134	91	98
<u>Liquid Products, BPSD</u>			
Gasoline	12,949	11,761	11,488
Diesel	31,447	28,564	27,899
TOTAL:	44,396	40,325	39,387
 Barrels/Ton dry coal	 4.53	 4.11	 4.02
<u>By-products</u>			
Propane, BPSD	2,863	2,017	2,212
Butane, BPSD	1,699	1,303	1,413
Sulfur, TPSD	363	363	363
Ammonia, TPSD	151	146	145
Ash to disposal, TPSD	1,167	1,307	1,327

TABLE 3.5.4

CMSL - 5
PLANT NET HYDROGEN BALANCE

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Hydrogen Consumption, MMSCFD</u>			
Liquefaction	209	215	218
Product Upgrading	71	33	29
TOTAL:	280	248	247
Hydrogen Consumption, SCF/B	6,303	6,146	6,280
<u>Hydrogen Production, MMSCFD</u>			
Partial Oxidation	50	121	129
Steam Reforming	230	127	118
TOTAL:	280	248	247

TABLE 3.5.5**CMSL - 5
THERMAL EFFICIENCY**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Inputs, GBTU/Day</u>			
Coal	249.7	249.7	249.7
Natural Gas	121.7	82.6	89.0
Total	371.4	332.3	338.7
<u>Outputs, GBTU/Day</u>			
Gasoline	72.4	65.7	64.2
Diesel	182.6	165.7	161.9
Propane	11.0	7.8	8.5
Butane	7.4	5.7	6.2
Sulfur	3.2	3.2	3.2
Ammonia	2.9	2.8	2.8
Total	279.5	250.9	246.8
Thermal Efficiency, %	75.3	75.5	72.9

TABLE 3.5.6

**CMSL - 5
UTILITIES SUMMARY**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
Electric Power, MW	161	176	232
600 Psig Steam, Mlbs/hr	482	307	320
Cooling Water, Mgpm	202	132	171
Process Fuel, GBTU/Day	122	83	89
Raw Water, gpm	6,042	5,563	5,787

TABLE 3.5.7

CMSL - 5
CAPACITIES OF PROCESS UNITS AND OFFSITES

			<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
Area No.	Description	Sizing basis, Units			
100	Coal Preparation	TPSD Dry coal	9800	9,800	9,800
200	Liquefaction	TPSD Dry coal	9800	9,800	9,800
300	Hydrogen Manufacture				
	Partial Oxidation	MMSCFD H ₂	50	121	130
	Steam Reforming	MMSCFD H ₂	230	127	118
400	Oxygen Plant	TPSD Oxygen	629	1,518	1,625
500	Product Treating				
	Sour Water treating	gpm sour water	3078	2,956	2,955
	Sulfur recovery	TPSD Sulfur	363	363	363
	Gas plant	lb/hr C ₁ -C ₃	60237	41,805	46,174
600	Upgrading & Solids Sep'n				
	Hydrotreating	BPSD Coal liquids	44396	40,325	39,387
	Catalytic reforming	BPSD 180-350	12949	11,761	11,488
700	Utilities				
	Steam generation	Mlbs/hr	482	307	320
	Power distribution	MW	161	176	232
	Cooling water	MGPM	202	132	171
800	Tankage				
	Coal liquids	BPSD liquids	44396	40,325	39,387
	LPG	BPSD LPG	2863	2,017	2,212
	Waste solids handling	TPSD solids	1167	1,307	1,327
900	General Off-Sites	TPSD Dry coal	9800	9,800	9,800

TABLE 3.5.8

CMSL - 5
LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Major Equipment Costs, \$M</u>			
Pumps	21,718	21,909	21,738
Reactors	34,340	46,243	48,486
Fired Heaters	10,507	10,575	14,460
Exchangers	15,094	14,927	19,815
Drums & Towers	30,505	30,601	37,529
Compressors	28,846	29,147	38,974
HPU	12,922	12,321	18,747
TOTAL	153,932	165,723	199,749
<u>Plant Investment, \$MM</u>			
Materials & Equipment	278.9	300.3	361.9
Labor & Subcontracts	120.7	129.9	156.6
Indirects	100.4	108.1	130.3
Contingency	0.0	0.0	0.0
Total Liquefaction Plant Investment	500.0	538.3	648.8

TABLE 3.5.9**CMSL - 5****TOTAL PLANT INVESTMENT SUMMARY**

(Plant Investment in \$MM, 1991 US Gulf Coast basis)

Area	Name	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
100	Coal Preparation	45.5	45.5	45.5
200	Liquefaction	500.0	538.3	648.8
300	Hydrogen Manufacture	231.5	218.2	163.1
400	Oxygen Plant	31.5	58.4	61.3
500	Product Treating	243.2	202.3	212.2
600	Upgrading & Solids Sep'n	93.5	92.1	91.6
700	Utilities	350.3	276.1	291.3
800	Tankage	124.1	114.3	112.1
900	General Off-Sites	185.2	186.5	186.7
	Subtotal	1804.8	1731.7	1812.6
	Fee, Contingency	360.5	345.9	362.1
	Total Plant Investment	2,165	2,078	2,175
	\$/BPD of Product	48,772	51,521	55,214

TABLE 3.5.10

**CMSL - 5
PRODUCT COST CALCULATION**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Operating Costs, \$MM/year</u>			
Coal (\$20.50/Ton)	66.00	66.00	66.00
Natural Gas (\$2.00/MMBTU)	79.98	54.26	58.47
Water (\$0.10/Mgal)	0.29	0.26	0.27
Catalysts and Chemicals	38.74	33.05	32.65
Ash Disposal (\$5.00/Ton)	1.92	2.15	2.18
Labor	23.07	23.07	23.07
Maintenance	20.67	20.67	20.67
Capital-Related	328.00	313.66	326.72
TOTAL:	558.67	513.12	530.03
<u>By-product Credits, \$MM/year</u>			
Propane (\$7.50/B)	7.05	4.97	5.45
Butane (\$14.50/B)	8.09	6.21	6.73
Sulfur (\$80.00/Ton)	9.53	9.53	9.53
Ammonia (\$120.00/Ton)	5.95	5.76	5.72
TOTAL:	30.62	26.47	27.43
Product Cost	528.05	486.65	502.60
Product Cost, \$/B	36.21	36.74	38.84
Crude Oil Equivalent Factor	0.832	0.834	0.844
Equivalent Crude Oil Price, \$/B	30.12	30.65	32.78

TABLE 3.5.11

CMSL - 5
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Contribution to Price, \$/B</u>			
Coal	3.76	4.16	4.3
Natural Gas	4.56	3.42	3.81
Water	0.02	0.02	0.02
Catalysts & Chemicals	2.21	2.08	2.13
Ash Disposal	0.11	0.14	0.14
Labor	1.32	1.45	1.5
Maintenance	1.18	1.3	1.35
Capital-Related	18.71	19.75	21.31
By-product Credit	-1.75	-1.67	-1.79
Equivalent Crude oil price, \$/B	30.12	30.65	32.78

TABLE 3.5.12

CMSL - 5

ECONOMIC COMPARISON OF CASES AT MAXIMUM REACTOR
THROUGHPUT

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
Coal to Liquefaction, T/D	11,800	12,000	13,000
Number of Liquefaction trains	2	2	3
Coal, T/D/train	5,900	6,000	4,333
Liquid Product, B/D	53,417	49,335	52,185
Liquefaction Plant Cost, \$MM	478	533	751
Total Plant Investment, \$MM	2,357	2,300	2,616
Net Annual Operating Cost, \$MM	591.11	551.64	614.63
Product Cost, \$/B	33.69	34.04	35.85
Equivalent Crude Oil Price, \$/B	27.64	27.99	29.77

TABLE 3.5.2

CMSL - 5
DESIGN BASIS COMPARISON

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Operating Conditions</u>			
Interstage separator	yes	yes	yes
Inline hydrotreater	yes	yes	yes
CO in feed gas to liquefaction, %	0	0	50
Space Velocity, lb/hr/ft ³	28.8	19.8	19.8
<u>Recycle Solvent</u>			
Solvent/Coal, lbs/lb	0.9	0.9	0.9
Resid, W%	30.5	30.5	30.5
<u>Temperatures, F</u>			
First Stage	775	775	750
Second Stage	825	800	800
Catalyst Replacement Rate, lb/Ton	2.7	2.7	2.7
<u>Projected Process Performance</u>			
Coal Conversion, W% MAF	96.0	95.0	96.0
Resid Conversion, W% MAF	92.9	84.8	83.7
Desulfurization, W%	98.5	96.7	97.0
Denitrogenation, W%	95.0	92.2	91.3
<u>Projected Yields, W% Dry Coal</u>			
H ₂ S	4.37	4.28	4.29
NH ₃	1.54	1.49	1.48
H ₂ O	7.53	5.68	5.24
CO _x	0.26	0.27	0.27
C ₁ -C ₃	7.38	5.12	5.65
C ₄ -350 F	16.36	12.23	13.46
350-650 F	39.59	32.36	30.14
650-975 F	11.87	20.35	20.37
975 + F	2.78	9.13	11.02
Unconverted Coal	3.58	4.48	3.58
Ash	10.40	10.40	10.40
TOTAL:	105.66	105.80	105.90
C ₄ -975, W% dry coal	67.82	64.95	63.97
, W% MAF	75.70	72.49	71.40

TABLE 3.5.3

CMSL - 5
OVERALL MATERIAL BALANCE

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
Coal Feed, TPSD	9,800	9,800	9,800
Natural Gas, MMSCFD	134	91	98
<u>Liquid Products, BPSD</u>			
Gasoline	12,949	11,761	11,488
Diesel	31,447	28,564	27,899
TOTAL:	44,396	40,325	39,387
Barrels/Ton dry coal	4.53	4.11	4.02
<u>By-products</u>			
Propane, BPSD	2,863	2,017	2,212
Butane, BPSD	1,699	1,303	1,413
Sulfur, TPSD	363	363	363
Ammonia, TPSD	151	146	145
Ash to disposal, TPSD	1,167	1,307	1,327

TABLE 3.5.4

**CMSL - 5
PLANT NET HYDROGEN BALANCE**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Hydrogen Consumption, MMSCFD</u>			
Liquefaction	209	215	218
Product Upgrading	71	33	29
TOTAL:	280	248	247
Hydrogen Consumption, SCF/B	6,303	6,146	6,280
<u>Hydrogen Production, MMSCFD</u>			
Partial Oxidation	50	121	129
Steam Reforming	230	127	118
TOTAL:	280	248	247

TABLE 3.5.5

CMSL - 5
THERMAL EFFICIENCY

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Inputs, GBTU/Day</u>			
Coal	249.7	249.7	249.7
Natural Gas	121.7	82.6	89.0
Total	371.4	332.3	338.7
<u>Outputs, GBTU/Day</u>			
Gasoline	72.4	65.7	64.2
Diesel	182.6	165.7	161.9
Propane	11.0	7.8	8.5
Butane	7.4	5.7	6.2
Sulfur	3.2	3.2	3.2
Ammonia	2.9	2.8	2.8
Total	279.5	250.9	246.8
Thermal Efficiency, %	75.3	75.5	72.9

TABLE 3.5.6

**CMSL - 5
UTILITIES SUMMARY**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
Electric Power, MW	161	176	232
600 Psig Steam, Mlbs/hr	482	307	320
Cooling Water, Mgpm	202	132	171
Process Fuel, GBTU/Day	122	83	89
Raw Water, gpm	6,042	5,563	5,787

TABLE 3.5.7

CMSL - 5
CAPACITIES OF PROCESS UNITS AND OFFSITES

			<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
Area					
No.	Description	Sizing basis, Units			
100	Coal Preparation	TPSD Dry coal	9800	9,800	9,800
200	Liquefaction	TPSD Dry coal	9800	9,800	9,800
300	Hydrogen Manufacture				
	Partial Oxidation	MMSCFD H ₂	50	121	130
	Steam Reforming	MMSCFD H ₂	230	127	118
400	Oxygen Plant	TPSD Oxygen	629	1,518	1,625
500	Product Treating				
	Sour Water treating	gpm sour water	3078	2,956	2,955
	Sulfur recovery	TPSD Sulfur	363	363	363
	Gas plant	lb/hr C ₁ -C ₃	60237	41,805	46,174
600	Upgrading & Solids Sep'n				
	Hydrotreating	BPSD Coal liquids	44396	40,325	39,387
	Catalytic reforming	BPSD 180-350	12949	11,761	11,488
700	Utilities				
	Steam generation	Mlbs/hr	482	307	320
	Power distribution	MW	161	176	232
	Cooling water	MGPM	202	132	171
800	Tankage				
	Coal liquids	BPSD liquids	44396	40,325	39,387
	LPG	BPSD LPG	2863	2,017	2,212
	Waste solids handling	TPSD solids	1167	1,307	1,327
900	General Off-Sites	TPSD Dry coal	9800	9,800	9,800

TABLE 3.5.8**CMSL - 5****LIQUEFACTION PLANT INVESTMENT DETAILS**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Major Equipment Costs, \$M</u>			
Pumps	21,718	21,909	21,738
Reactors	34,340	46,243	48,486
Fired Heaters	10,507	10,575	14,460
Exchangers	15,094	14,927	19,815
Drums & Towers	30,505	30,601	37,529
Compressors	28,846	29,147	38,974
HPU	12,922	12,321	18,747
TOTAL	153,932	165,723	199,749
<u>Plant Investment, \$MM</u>			
Materials & Equipment	278.9	300.3	361.9
Labor & Subcontracts	120.7	129.9	156.6
Indirects	100.4	108.1	130.3
Contingency	0.0	0.0	0.0
Total Liquefaction Plant Investment	500.0	538.3	648.8

TABLE 3.5.9**CMSL - 5****TOTAL PLANT INVESTMENT SUMMARY**

(Plant Investment in \$MM, 1991 US Gulf Coast basis)

Area	Name	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
100	Coal Preparation	45.5	45.5	45.5
200	Liquefaction	500.0	538.3	648.8
300	Hydrogen Manufacture	231.5	218.2	163.1
400	Oxygen Plant	31.5	58.4	61.3
500	Product Treating	243.2	202.3	212.2
600	Upgrading & Solids Sep'n	93.5	92.1	91.6
700	Utilities	350.3	276.1	291.3
800	Tankage	124.1	114.3	112.1
900	General Off-Sites	185.2	186.5	186.7
	Subtotal	1804.8	1731.7	1812.6
	Fee, Contingency	360.5	345.9	362.1
	Total Plant Investment	2,165	2,078	2,175
	\$/BPD of Product	48,772	51,521	55,214

TABLE 3.5.10

**CMSL - 5
PRODUCT COST CALCULATION**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Operating Costs, \$MM/year</u>			
Coal (\$20.50/Ton)	66.00	66.00	66.00
Natural Gas (\$2.00/MMBTU)	79.98	54.26	58.47
Water (\$0.10/Mgal)	0.29	0.26	0.27
Catalysts and Chemicals	38.74	33.05	32.65
Ash Disposal (\$5.00/Ton)	1.92	2.15	2.18
Labor	23.07	23.07	23.07
Maintenance	20.67	20.67	20.67
Capital-Related	328.00	313.66	326.72
TOTAL:	558.67	513.12	530.03
<u>By-product Credits, \$MM/year</u>			
Propane (\$7.50/B)	7.05	4.97	5.45
Butane (\$14.50/B)	8.09	6.21	6.73
Sulfur (\$80.00/Ton)	9.53	9.53	9.53
Ammonia (\$120.00/Ton)	5.95	5.76	5.72
TOTAL:	30.62	26.47	27.43
Product Cost	528.05	486.65	502.60
Product Cost, \$/B	36.21	36.74	38.84
Crude Oil Equivalent Factor	0.832	0.834	0.844
Equivalent Crude Oil Price, \$/B	30.12	30.65	32.78

TABLE 3.5.11

CMSL - 5
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
<u>Contribution to Price, \$/B</u>			
Coal	3.76	4.16	4.3
Natural Gas	4.56	3.42	3.81
Water	0.02	0.02	0.02
Catalysts & Chemicals	2.21	2.08	2.13
Ash Disposal	0.11	0.14	0.14
Labor	1.32	1.45	1.5
Maintenance	1.18	1.3	1.35
Capital-Related	18.71	19.75	21.31
By-product Credit	-1.75	-1.67	-1.79
Equivalent Crude oil price, \$/B	30.12	30.65	32.78

TABLE 3.5.12**CMSL - 5****ECONOMIC COMPARISON OF CASES AT MAXIMUM REACTOR
THROUGHPUT**

	<u>Period 8</u>	<u>Period 11</u>	<u>Period 13</u>
Coal to Liquefaction, T/D	11,800	12,000	13,000
Number of Liquefaction trains	2	2	3
Coal, T/D/train	5,900	6,000	4,333
Liquid Product, B/D	53,417	49,335	52,185
Liquefaction Plant Cost, \$MM	478	533	751
Total Plant Investment, \$MM	2,357	2,300	2,616
Net Annual Operating Cost, \$MM	591.11	551.64	614.63
Product Cost, \$/B	33.69	34.04	35.85
Equivalent Crude Oil Price, \$/B	27.64	27.99	29.77

VOLUME III

SECTION III

RUN CMSL-6

BLACK THUNDER MINE COAL

**STUDY OF SUBSTITUTION OF SULFATED
IRON/MOLYBDENUM ADDITIVE FOR FIRST STAGE
EXTRUDATE CATALYST**

VOLUME III

SECTION III - RUN CMSL-6

TABLE OF CONTENTS

**STUDY OF SUBSTITUTION OF SULFATED
IRON/MOLYBDENUM ADDITIVE FOR FIRST STAGE
EXTRUDATE CATALYST**

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	3

LIST OF TABLES

Table 3.6.1	Design Coal Feed Analysis	4
Table 3.6.2	CMSL - 6 Design Basis Comparison	5
Table 3.6.3	CMSL - 6 Overall Material Balance	6
Table 3.6.4	CMSL - 6 Plant Net Hydrogen Balance	7
Table 3.6.5	CMSL - 6 Thermal Efficiency	8
Table 3.6.6	CMSL - 6 Utilities Summary	9
Table 3.6.7	CMSL - 6 Capacities Of Process Units And Offsites	10
Table 3.6.8	CMSL - 6 Liquefaction Plant Investment Details	11
Table 3.6.9	CMSL - 6 Total Plant Investment Summary	12
Table 3.6.10	CMSL - 6 Product Cost Calculation	13
Table 3.6.11	CMSL - 6 Breakdown Of Equivalent Crude Oil Price	14

VOLUME III

SECTION III

TECHNICAL ASSESSMENT - CMSL-6

1.0 BACKGROUND

The primary objective of Run 227-83 (CMSL-6) was to evaluate the substitution of a molybdenum-containing sulfated iron oxide dispersed catalyst for the standard supported catalyst in the first-stage reactor, in the liquefaction of subbituminous coal. The run continued use of an in-line hydrotreater to lower the downstream product upgrading requirements. There was no interstage separator for this run.

The subbituminous coal for CMSL-6 was a Wyoming coal from the Black Thunder mine, with a higher hydrogen content and a lower ash content than that used in CMSL-3, as seen from *Table 3.6.1*. Three major operating conditions were assessed. The first condition (Period 6) employed a low first-stage reactor operating temperature and a low solvent-to-coal ratio, with a relatively high dispersed catalyst addition rate (200 ppm Molyvan A and 1230 ppm Iron). The catalyst addition rate was halved in conditions two (Period 13) and three (Period 17), with higher temperatures and progressively higher solvent-to-coal ratios. The space velocity remained constant throughout the run.

Overall material balances are shown in *Table 3.6.3*. *Table 3.6.4* presents net hydrogen balances. It is worth noting that Period 6, with high unconverted residuum and with high gas yield requires a minimum of import natural gas for hydrogen production. *Table 3.6.5* shows the thermal efficiency for the cases. *Table 3.6.6* is a summary of the utilities usage, and *Table 3.6.7* shows the capacities of the various process units and off sites.

The liquefaction plant investment details are presented in *Table 3.6.8*. As in the technical assessment of earlier CMSL runs with dispersed catalyst, no credit was taken for saving in reactor internals, but the catalyst addition/withdrawal system cost was reduced. The savings from eliminating this almost offsets the additional cost for the in-line hydrotreater. The highest investment was for Period 17 condition with the highest oil-to-solids ratio.

Table 3.6.9 is a summary of the total plant investment for all the cases. Total plant investments for the three cases are almost the same plus or minus 2%.

2.0 SUMMARY

The overall economics are summarized in *Table 3.6.10*. Comparing Period 13 with Period 6 shows that increasing the reactor operating temperature is economically advantageous, despite the higher gas yield. With the lower dispersed catalyst rate and reactor temperatures adjusted to give the highest yield of distillates in Period 17, the lowest equivalent crude oil price was obtained, \$31.94 per barrel. *Table 6.11* summarizes the breakdown of the equivalent crude oil price.

The equivalent crude oil cost for CMSL-6, Period 17, operations was about \$0.70 per barrel lower than at of comparable operation of Run CMSL-4 where there was Ni-Mo extrudate catalyst in both stages and no catalyst additives were used. Since no interstage separator was used in Run CMSL-6, while there was one in Run CMSL-4, the costs with additives Run CMSL-6 could be lowered with such a modification. Compared to Run CMSL-3, where the catalyst additive was 1500 ppm (AHM) the equivalent crude oil price in Run CMSL-6 was higher by \$2.30 per barrel indicating that at these levels the Mo additive was more economic than sulfated iron-molybdenum additive.

An estimate was made of the economic impact of substituting the catalyst additives for first stage Ni-Mo extrudate catalyst. The following costs for the catalyst and additives were used:

Ni-Mo Extrudate	\$2.50/lb
Mo additive	\$3.00/lb Mo
Fe Additive	\$0.80/lb Fe

In the standard CTSL operation with using 2.7 lb Ni-Mo extrudate per ton coal, this extrudate cost would correspond to \$6.76 per ton coal. In the CMSL-6, Period 17 operation, using half as much extrudate catalyst and 100 ppm Mo and 615 ppm Fe additives, the extrudate cost would be \$3.38 per ton coal and the combined additives cost would be \$1.58 Per ton coal, for a combined cost of \$4.96 per ton coal. The difference of \$1.80 per ton coal corresponds to a reduction of equivalent crude oil price of \$0.38 per barrel. Another factor in such a comparison is the elimination of extrudate catalyst addition/withdrawal vessels, which it is estimated would result in a reduction in plant investment on this scale of \$9,500,000, which corresponds to a reduction of equivalent crude oil price of \$0.09 per barrel in capital related costs. Thus additives costs and usage could be increased by \$0.47 per barrel of equivalent crude oil, or \$2.20 per ton coal, to 200 ppm of Mo and 1600 ppm of Fe for the same effective catalyst costs as in the standard CTSL operation. This analyses is separate from the impact upon process performance of the change in catalyst pattern.

3.0 CONCLUSIONS

The results of CMSL-6 indicate favorable economics for the substitution of molybdenum-containing sulfated iron oxide dispersed catalyst for the standard supported catalyst in the first-stage reactor in the liquefaction of subbituminous coal. Operations at the higher reactor temperatures were economically beneficial, despite the high gas yields.

TABLE 3.6.1

DESIGN COAL FEED ANALYSIS

	CMSL -6	CMSL -3
Coal Type	Wyoming	Wyoming
Mine	Black Thunder	Black Thunder
<u>Proximate Analysis, W% Dry Coal</u>		
Volatile Matter	43.48	43.37
Fixed Carbon	50.52	50.36
Ash	6	6.27
Total	100	100
<u>Ultimate Analysis, W% Dry Coal</u>		
Carbon	69.95	70.4
Hydrogen	4.5	3.88
Nitrogen	0.89	0.87
Sulfur	0.39	0.44
Oxygen (by difference)	18.27	18.14
Chlorine	0	0
Ash	6	6.27
Total	100	100
SO ₃ -free ash	5.13	5.59
H/C Atomic Ratio	0.77	0.66
O/C Atomic Ratio	0.2	0.19
Heating Value, BTU/lb dry coal calculated	11664	11339
Coal Moisture, W%	11.47	25.4

TABLE 3.6.2

CMSL - 6
DESIGN BASIS COMPARISON

	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
<u>Operating Conditions</u>			
In-line hydrotreater	yes	yes	yes
Space Velocity, lb/hr/ft ³	28.4	28.4	28.4
<u>Recycle Solvent</u>			
Solvent/Coal, lbs/lb	1.2	1.3	1.6
Resid, W%	37.5	37.5	25.7
<u>Temperatures, F</u>			
First Stage	800	825	818
Second Stage	776	805	810
<u>Dispersed catalyst , ppm</u>			
Molyvan A	200	100	100
Iron	1230	615	615
Supported catalyst rate, lb/Ton	1.35	1.35	1.35
<u>Projected Process Performance</u>			
Coal Conversion, W% MAF	93.9	93.6	94.5
Resid Conversion, W% MAF	82.9	87.9	89.7
Denitrogenation, W%	91.0	91.2	91.8
<u>Projected Yields, W% Dry Coal</u>			
H ₂ S	0.35	0.33	0.29
NH ₃	0.98	0.99	0.99
H ₂ O	11.73	11.76	11.85
CO _x	4.45	4.74	5.92
C ₁ -C ₃	9.26	12.34	10.31
C ₄ -350 F	14.95	16.56	15.62
350-650 F	25.25	34.02	28.40
650-975 F	18.65	10.12	19.17
975 + F	10.44	5.41	4.53
Unconverted Coal	5.79	6.07	5.22
Ash	5.13	5.13	5.13
TOTAL	106.98	107.47	107.43
C ₄ -975, W% dry coal	58.85	60.70	63.19
, W% MAF	62.03	63.98	66.60

TABLE 3.6.3

CMSL - 6
OVERALL MATERIAL BALANCE

	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
Coal Feed, TPSD	10,500	10,500	10,500
Natural Gas, MMSCFD	88	124	120
<u>Liquid Products, BPSD</u>			
Gasoline	11,254	12,139	12,158
Diesel	27,278	29,422	29,480
TOTAL:	38,532	41,561	41,638
Barrels/Ton dry coal	3.67	3.96	3.97
<u>By-products</u>			
Propane, BPSD	3,472	4,616	3,699
Butane, BPSD	1,643	1,815	1,724
Sulfur, TPSD	63	60	60
Ammonia, TPSD	103	104	104
Ash to disposal, TPSD	1,017	995	916

TABLE 3.6.4

CMSL - 6
PLANT NET HYDROGEN BALANCE

	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
<u>Hydrogen Consumption, MMSCFD</u>			
Liquefaction	276	296	294
Product Upgrading	18	25	17
TOTAL:	294	321	311
Hydrogen Consumption, SCF/B	7,647	7,725	7,460
<u>Hydrogen Production, MMSCFD</u>			
Partial Oxidation	139	76	87
Steam Reforming process gases	128	170	146
Steam Reforming import gases	27	75	78
TOTAL:	294	321	311

TABLE 3.6.5

CMSL - 6
THERMAL EFFICIENCY

	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
<u>Inputs, GBTU/Day</u>			
Coal	244.5	244.5	244.5
Natural Gas	79.5	112.5	109.3
Total	324.0	357.0	353.8
 <u>Outputs, GBTU/Day</u>			
Gasoline	62.3	67.2	67.5
Diesel	157.1	169.5	170.1
Propane	13.4	17.8	14.2
Butane	7.2	7.9	7.5
Sulfur	0.6	0.5	0.5
Ammonia	2.0	2.0	2.0
Total	242.6	264.9	261.8
 Thermal Efficiency, %	74.9	74.2	74.0

TABLE 3.6.6

**CMSL - 6
UTILITIES SUMMARY**

	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
Electric Power, MW	208	205	200
600 Psig Steam, Mlbs/hr	117	292	192
Cooling Water, Mgpm	133	170	148
Process Fuel, GBTU/Day	80	113	109
Raw Water, gpm	3,993	4,656	3,952

TABLE 3.6.7

CMSL - 6
CAPACITIES OF PROCESS UNITS AND OFFSITES

Area No.	Description	Sizing basis, Units	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
100	Coal Preparation	TPSD Dry coal	10,500	10,500	10,500
200	Liquefaction	TPSD Dry coal	10,500	10,500	10,500
300	Hydrogen Manufacture				
	Partial Oxidation	MMSCFD H ₂	139	76	87
	Steam Reforming	MMSCFD H ₂	155	245	223
400	Oxygen Plant	TPSD Oxygen	1,746	952	1,095
500	Product Treating				
	Sour Water treating	gpm sour water	1,626	1,693	1,638
	Sulfur recovery	TPSD Sulfur	63	60	60
	Gas plant	lb/hr C ₁ -C ₃	81,051	107,949	90,239
600	Upgrading & Solids Sep'n				
	Hydrotreating	BPSD Coal liquids	38,532	41,561	41,638
	Catalytic reforming	BPSD 180-350	11,254	12,139	12,158
700	Utilities				
	Steam generation	Mlbs/hr	117	292	192
	Power distribution	MW	208	205	200
	Cooling water	MGPM	133	170	148
800	Tankage				
	Coal liquids	BPSD liquids	38,532	41,561	41,638
	LPG	BPSD LPG	3,472	4,616	3,699
	Waste solids handling	TPSD solids	1,017	995	916
900	General Off-Sites	TPSD Dry coal	10,500	10,500	10,500

TABLE 3.6.8

CMSL - 6
LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
<u>Major Equipment Costs, \$M</u>			
Pumps	24,499	24,790	26,487
Reactors	48,475	50,246	50,246
Fired Heaters	14,458	15,416	16,919
Exchangers	17,864	18,755	19,348
Drums, Towers & Hydrotreater	34,918	36,146	36,843
Compressors	33,483	34,462	34,374
HPU	13,236	14,427	13,931
TOTAL	186,933	194,242	198,148
<u>Plant Investment, \$MM</u>			
Materials & Equipment	338.7	351.9	359.1
Labor & Subcontracts	146.6	152.3	155.3
Indirects	121.9	126.7	129.2
Contingency	0.0	0.0	0.0
Total Liquefaction Plant Investment	607.2	630.9	643.6

TABLE 3.6.9

CMSL - 6

TOTAL PLANT INVESTMENT SUMMARY

(Plant Investment In \$MM, 1991 US Gulf Coast Basis)

CASE		<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
Area	Name			
100	Coal Preparation	200.0	200.0	200.0
200	Liquefaction	607.2	630.9	643.6
300	Hydrogen Manufacture	248.5	261.0	256.3
400	Oxygen Plant	64.4	42.1	46.5
500	Product Treating	251.8	300.7	268.7
600	Upgrading & Solids Sep'n	97.8	100.7	97.3
700	Utilities	249.4	274.1	242.5
800	Tankage	109.0	116.2	116.6
900	General Off-Sites	192.2	192.0	191.3
	Subtotal	2020.3	2117.7	2062.8
	Fee, Contingency	403.5	423.1	412.0
	Total Plant Investment	2,424	2,541	2,475
	\$/BPD of Product	62,904	61,134	59,436

TABLE 3.6.10

CMSL - 6
PRODUCT COST CALCULATION

	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
<u>Operating Costs, \$MM/year</u>			
Coal (\$7.00/Ton)	24.14	24.14	24.14
Natural Gas (\$2.00/MMBTU)	52.26	73.88	71.82
Water (\$2.50/Mgal)	4.72	5.51	4.67
Catalysts and Chemicals	23.60	23.20	27.21
Dispersed Catalyst	10.93	10.93	5.46
Ash Disposal (\$5.00/Ton)	1.67	1.63	1.50
Labor	24.43	24.43	24.43
Maintenance	21.89	21.89	21.89
Capital-Related	361.15	379.04	369.86
TOTAL:	524.79	564.65	550.98
<u>By-product Credits, \$MM/year</u>			
Propane (\$12.29/B)	14.02	18.64	14.93
Butane, (\$14.50/B)	7.83	8.65	8.21
Sulfur (\$52.00/Ton)	1.07	1.03	1.02
Ammonia (\$200.00/Ton)	6.76	6.83	6.83
TOTAL:	29.68	35.15	30.99
Product Cost	495.11	529.50	519.99
Product Cost, \$/B	39.12	38.78	38.02
Crude Oil Equivalent Factor	0.845	0.844	0.840
Equivalent Crude Oil Price, \$/B	33.06	32.72	31.94

TABLE 3.6.11

CMSL - 6
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 6</u>	<u>Period 13</u>	<u>Period 17</u>
<u>Contribution to Price, \$/B</u>			
Coal	1.61	1.49	1.48
Natural Gas	3.49	4.57	4.41
Water	0.32	0.34	0.29
Catalysts & Chemicals	1.58	1.43	1.67
Dispersed Catalyst	0.73	0.68	0.34
Ash Disposal	0.11	0.10	0.09
Labor	1.63	1.51	1.50
Maintenance	1.46	1.35	1.34
Capital-related	24.12	23.42	22.72
By-product Credit	-1.98	-2.17	-1.90
Equivalent Crude Oil Price, \$/B	33.06	32.72	31.94

VOLUME III

SECTION III

RUN CMSL-7

BLACK THUNDER MINE COAL

**EXTRUDATE CATALYST IN BOTH STAGES
200 PPM MOLYBDENUM ADDITIVE WITH COAL
SUBSTITUTION OF SYNTHESIS GAS FOR
HIGH PURITY HYDROGEN
STUDY OF IMPACT OF LIQUEFACTION PRESSURE**

VOLUME III

SECTION VII - CMSL-7

TABLE OF CONTENTS

**EXTRUDATE CATALYST IN BOTH STAGES
200 PPM MOLYBDENUM ADDITIVE WITH COAL
SUBSTITUTION OF SYNTHESIS GAS FOR
HIGH PURITY HYDROGEN
STUDY OF IMPACT OF LIQUEFACTION PRESSURE**

1.0	BACKGROUND	1
2.0	SUMMARY AND CONCLUSIONS	2

VOLUME III

SECTION VII - CMSL-7

LIST OF TABLES

Table 3.7.1	CMSL - 7 Design Basis Comparison	3
Table 3.7.2	CMSL - 7 Overall Material Balance	4
Table 3.7.3	CMSL - 7 Plant Net Hydrogen Balance	5
Table 3.7.4	CMSL - 7 Thermal Efficiency	6
Table 3.7.5	CMSL - 7 Utilities Summary	7
Table 3.7.6	CMSL - 7 Capacities Of Process Units And Offsites	8
Table 3.7.7	CMSL - 7 Liquefaction Plant Investment Details	9
Table 3.7.8	CMSL - 7 Total Plant Investment Summary (Plant Investment in \$MM, 1991 US Gulf Coast basis)	10
Table 3.7.9	CMSL - 7 Product Cost Calculation	11
Table 3.7.10	CMSL - 7 Breakdown Of Equivalent Crude Oil Price	12
Table 3.7.11	CMSL - 7 Economic Comparison Of Cases At Maximum Reactor Throughput	13

VOLUME III

SECTION III

TECHNICAL ASSESSMENT - CMSL-7

1.0 BACKGROUND

The primary objective of Run 227-84 (CMSL-7) was to evaluate the use of synthesis gas at reduced total operating pressure, in the liquefaction of subbituminous coal. In addition to the standard supported catalyst in both reactor stages, a dispersed ammonium heptamolybdate (AHM) catalyst was added to the first-stage reactor feed. An interstage separator was used, as proven successful in previous CMSL runs.

The subbituminous coal in CMSL-7 was the same Wyoming coal from the Black Thunder mine used in CMSL-6. Three major operating conditions were assessed at constant reactor temperature and space velocity, with synthesis gas throughout the run. The first condition (Period 7) was carried out at high 17.2 MPa (2500 psig) pressure with 200 ppm dispersed Molybdenum catalyst. The pressure was reduced in the second condition (Period 11), and reduced even further to 10.3 MPa in the third condition (Period 19). The dispersed catalyst remained at 200 ppm in the second condition, and was raised to 500 ppm for the third condition.

The process conditions and yields used in these projections are summarized in *Table 3.7.1*. Overall material balances are shown in *Table 3.7.2*. *Table 3.7.3* presents net Hydrogen balances, and *Table 3.7.4* shows the thermal efficiency for the cases. *Table 3.7.5* is a summary of the utilities usage, and *Table 3.7.6* shows the capacities of the various process units and off sites.

The liquefaction plant investment details are presented in *Table 3.7.7*. Reduced pressure lowered the liquefaction plant cost, primarily due to savings in reactor cost. Use of synthesis gas, however, offsets the reactor cost savings, due to the increased volume of gas required. Reduced pressure was found to be beneficial.

Table 3.7.8 is a summary of the total plant investment for all the cases. The savings in total plant investment follow those reflected in liquefaction plant savings. The investment is 5% lower for at the lowest pressure in Period 19, compared to Periods 7 and 11.

2.0 SUMMARY AND CONCLUSIONS

The overall economics are summarized in *Table 3.7.9*. *Table 3.7.10* is a breakdown of the equivalent crude oil price. The lowest pressure case for Period 19 had an equivalent crude oil price of \$31.46 per barrel, which was \$0.8 per barrel lower than that for the highest pressure case. Nominally, this resulted because of the increase in Mo catalyst additive from 200 ppm to 500 ppm, which maintained the yield of distillates. For Period 19, the reduction in the plant investment more than over-weighed the increased cost of catalyst additive.

Since an interstage separator was used in these operations, the vapor load in the liquefaction was reduced. The alternative design was to maximize the amount of coal feed per reactor by increasing reactor lengths while using a maximum diameter reactor. *Table 3.7.11* compares the three cases considering the maximum diameter reactors. Here, at the lower pressures no benefit could be derived from this consideration because necessarily greater vapor velocities, but at the highest pressure the coal throughput could be increased so that the equivalent crude oil price was lowered to \$31.26 per barrel, which is \$0.2 lower than that calculated for the lower pressure case.

These operations in Run CMSL-7, Period 7 with synthesis gas had a projected cost in the conventional design, \$0.40 per barrel lower than in comparable operation of Run CMSL-4, which also used extrudate catalyst in both stages and fed only high purity hydrogen. However, in the modified, maximum coal throughput cases, the synthesis gas operation had a equivalent crude oil price that was higher by \$1.60 per barrel than that with high purity hydrogen.

The principal conclusions are that lower operating pressure is feasible with an appropriate increase in catalyst usage and that the use of syngas in place of high purity hydrogen is probably more costly. The use of molybdenum additive in conjunction with two stages of Ni-Mo extrudate catalyst is probably of some economic advantage.

TABLE 3.7.1

CMSL - 7
DESIGN BASIS COMPARISON

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
<u>Operating Conditions</u>			
Interstage Separator	yes	yes	yes
Total pressure, psig	2,700	2,200	1,700
CO in feed gas to liquefaction, %	50	50	50
Dispersed catalyst, ppm Mo	200	200	500
Supported catalyst rate, lb/Ton	2.7	2.7	2.7
Space Velocity, lb/hr/ft ³	20.0	20.0	20.0
<u>Recycle Solvent</u>			
Solvent/Coal, lbs/lb	1.2	1.2	1.2
Resid, W%	28.3	28.3	28.3
<u>Temperatures, F</u>			
First Stage	800	800	800
Second Stage	830	830	830
<u>Projected Process Performance</u>			
Coal Conversion, W% MAF	92.6	92.1	91.3
Resid Conversion, W% MAF	91.2	87.9	89.5
Denitrogenation, W%	89.2	88.2	83.7
<u>Projected Yields, W% Dry Coal</u>			
H ₂ S	0.37	0.35	0.35
NH ₃	0.99	0.90	0.90
H ₂ O	14.88	14.81	14.90
CO _x	5.30	5.43	5.31
C ₁ -C ₃	7.89	7.61	6.96
C ₄ -350 F	22.17	21.28	21.20
350-650 F	41.29	37.05	41.22
650-975 F	0.65	2.46	1.48
975 + F	1.35	3.99	1.70
Unconverted Coal	7.02	7.49	8.25
Ash	5.13	5.13	5.13
TOTAL:	107.06	106.51	107.41
C ₄ -975, W% dry coal	64.12	60.79	63.90
, W% MAF	67.59	64.08	67.36

TABLE 3.7.2**CMSL - 7
OVERALL MATERIAL BALANCE**

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
Coal Feed, TPSD	10,500	10,500	10,500
Natural Gas, MMSCFD	175	150	163
<u>Liquid Products, BPSD</u>			
Gasoline	13,049	12,400	12,893
Diesel	31,690	30,116	31,311
TOTAL:	44,739	42,516	44,204
Barrels/Ton dry coal	4.26	4.05	4.21
<u>By-products</u>			
Propane, BPSD	3,209	3,152	3,155
Butane, BPSD	2,385	2,286	2,288
Sulfur, TPSD	68	68	68
Ammonia, TPSD	106	98	98
Ash to disposal, TPSD	713	714	714

TABLE 3.7.3**CMSL - 7
PLANT NET HYDROGEN BALANCE**

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
<u>Hydrogen Consumption, MMSCFD</u>			
Liquefaction	280	258	293
Product Upgrading	37	46	15
TOTAL:	317	304	308
Hydrogen Consumption, SCF/B	7,076	7,146	6,976
<u>Hydrogen Production, MMSCFD</u>			
Partial Oxidation	55	82	69
Steam Reforming	262	222	239
TOTAL:	317	304	308

TABLE 3.7.4
CMSL - 7
THERMAL EFFICIENCY

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
<u>Inputs, GBTU/Day</u>			
Coal	244.5	244.5	244.5
Natural Gas	159.1	136.2	148.0
Total	403.6	380.7	392.5
<u>Outputs, GBTU/Day</u>			
Gasoline	73.0	69.3	72.1
Diesel	184.0	174.8	181.8
Propane	12.3	12.1	12.1
Butane	10.4	10.0	10.0
Sulfur	0.6	0.6	0.6
Ammonia	2.0	1.9	1.9
Total	282.3	268.7	278.5
Thermal Efficiency, %	69.9	70.6	71.0

TABLE 3.7.5

**CMSL - 7
UTILITIES SUMMARY**

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
Electric Power, MW	233	209	190
600 Psig Steam, Mlbs/hr	148	88	73
Cooling Water, Mgpm	135	123	120
Process Fuel, GBTU/Day	159	136	148
Raw Water, gpm	3,058	2,956	2,642

TABLE 3.7.6

CMSL - 7

CAPACITIES OF PROCESS UNITS AND OFFSITES

Area			<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
No.	Description	Sizing basis, Units			
100	Coal Preparation	TPSD Dry coal	10500	10500	10500
200	Liquefaction	TPSD Dry coal	10500	10500	10500
300	Hydrogen Manufacture				
	Partial Oxidation	MMSCFD H ₂	55	82	69
	Steam Reforming	MMSCFD H ₂	262	222	239
400	Oxygen Plant	TPSD Oxygen	686	1031	863
500	Product Treating				
	Sour Water treating	gpm sour water	1671	1596	1607
	Sulfur recovery	TPSD Sulfur	68	68	68
	Gas plant	lb/hr C ₁ -C ₃	69038	66588	60900
600	Upgrading & Solids Sep'n				
	Hydrotreating	BPSD Coal liquids	44739	42516	44204
	Catalytic reforming	BPSD 180-350	13049	12400	12893
700	Utilities				
	Steam generation	Mlbs/hr	148	88	73
	Power distribution	MW	233	209	190
	Cooling water	MGPM	135	123	120
800	Tankage				
	Coal liquids	BPSD liquids	44739	42516	44204
	LPG	BPSD LPG	3209	3152	3155
	Waste solids handling	TPSD solids	713	714	714
900	General Off-Sites	TPSD Dry coal	10500	10500	10,500

TABLE 3.7.7

CMSL - 7
LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
Number of Reactor Trains	4	5	6
<u>Major Equipment Costs, \$M</u>			
Pumps	23,436	23,503	23,977
Reactors	48,368	42,836	34,965
Fired Heaters	24,993	21,245	23,118
Exchangers	21,839	22,168	24,482
Drums & Towers	42,583	39,760	43,541
Compressors	39,725	34,759	30,968
HPU	16,617	18,389	20,588
TOTAL	217,561	202,660	201,639
<u>Plant Investment, \$MM</u>			
Materials & Equipment	394.2	367.2	365.3
Labor & Subcontracts	170.6	158.9	158.1
Indirects	141.9	132.2	131.5
Contingency	0.0	0.0	0.0
Total Liquefaction Plant Investment	706.7	658.3	654.9

TABLE 3.7.8

CMSL - 7

TOTAL PLANT INVESTMENT SUMMARY

(Plant Investment in \$MM, 1991 US Gulf Coast basis)

Area	Name	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
100	Coal Preparation	200.0	200.0	200.0
200	Liquefaction	706.7	658.3	654.9
300	Hydrogen Manufacture	190.7	188.7	189.2
400	Oxygen Plant	33.5	44.5	39.3
500	Product Treating	229.5	224.0	212.5
600	Upgrading & Solids Sep'n	124.6	122.2	125.0
700	Utilities	263.1	246.3	230.6
800	Tankage	125.0	119.6	123.7
900	General Off-Sites	189.2	189.2	189.2
	Subtotal	2062.3	1992.8	1964.4
	Fee, Contingency	411.9	398.1	392.4
	Total Plant Investment	2,474	2,391	2,357
	\$/BPD of Product	55,303	56,235	53,316

TABLE 3.7.9

CMSL - 7
PRODUCT COST CALCULATION

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
<u>Operating Costs, \$MM/year</u>			
Coal (\$7.00/Ton)	24.14	24.14	24.14
Natural Gas (\$2.00/MMBTU)	104.39	89.49	97.25
Water (\$2.50/Mgal)	3.62	3.50	3.12
Catalysts and Chemicals	40.55	38.34	39.19
Dispersed Catalyst	4.14	4.14	10.35
Ash Disposal (\$5.00/Ton)	1.17	1.17	1.17
Labor	24.43	24.43	24.43
Maintenance	21.89	21.89	21.89
Capital-Related	371.35	358.60	354.73
TOTAL:	595.68	565.70	576.27
<u>By-product Credits, \$MM/year</u>			
Propane (\$12.29/B)	12.95	12.72	12.74
Butane, (\$14.50/B)	11.36	10.89	10.90
Sulfur (\$52.00/Ton)	1.16	1.16	1.16
Ammonia (\$200.00/Ton)	6.95	6.41	6.42
TOTAL:	32.42	31.18	31.22
Product Cost	563.26	534.52	545.05
Product Cost, \$/B	38.33	38.27	37.54
Crude Oil Equivalent Factor	0.842	0.841	0.838
Equivalent Crude Oil Price, \$/B	32.25	32.20	31.46

TABLE 3.7.10

CMSL - 7
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
<u>Contribution to Price, \$/B</u>			
Coal	1.38	1.45	1.39
Natural Gas	5.98	5.39	5.61
Water	0.21	0.21	0.18
Catalysts & Chemicals	2.32	2.31	2.26
Dispersed Catalyst	0.24	0.25	0.60
Ash Disposal	0.07	0.07	0.07
Labor	1.40	1.47	1.41
Maintenance	1.25	1.32	1.26
Capital-Related	21.26	21.60	20.48
By-product Credit	-1.86	-1.88	-1.80
Equivalent Crude Oil Price, \$/B	32.25	32.20	31.46

TABLE 3.7.11**CMSL - 7****ECONOMIC COMPARISON OF CASES AT MAXIMUM REACTOR
THROUGHPUT**

	<u>Period 7</u>	<u>Period 11</u>	<u>Period 19</u>
Coal to Liquefaction, T/D	11,800	10,500	10,500
Number of Liquefaction Trains	4	5	5
Coal, T/D/train	2,950	2,100	2,100
Product, B/D	50,254	42,516	44,204
Liquefaction Plant Cost, \$MM	780	658	655
Total Plant Investment, \$MM	2,707	2,391	2,357
Net Annual Operating Cost, \$MM	616.46	534.52	545.05
Product Cost, \$/B	37.34	38.27	37.54
Equivalent Crude Oil Price, \$/B	31.26	32.20	31.46

VOLUME III

SECTION III

RUN CMSL-8

ILLINOIS NO. 6 COAL

**COPROCESSING WITH PREPARED PLASTICS MIXES
EXTRUDATE CATALYST IN FIRST STAGE
SULFATED IRON- MOLYBDENUM ADDITIVE**

VOLUME III

SECTION III - CMSL-8

TABLE OF CONTENTS

COPROCESSING WITH PREPARED PLASTICS MIXES EXTRUDATE CATALYST IN FIRST STAGE SULFATED IRON- MOLYBDENUM ADDITIVE

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	3

VOLUME III

SECTION III - CMSL-8

LIST OF TABLES

Table 3.8.1	CMSL - 8	Feed Analysis	4
Table 3.8.2	CMSL - 8	Design Basis Comparison	5
Table 3.8.3	CMSL - 8	Overall Material Balance	6
Table 3.8.4	CMSL - 8	Plant Net Hydrogen Balance	7
Table 3.8.5	CMSL - 8	Thermal Efficiency	8
Table 3.8.6	CMSL - 8	Utilities Summary	9
Table 3.8.7	CMSL - 8	Capacities Of Process Units And Offsites	10
Table 3.8.8	CMSL - 8	Liquefaction Plant Investment Details	11
Table 3.8.9	CMSL - 8	Total Plant Investment Summary	12
Table 3.8.10	CMSL - 8	Product Cost Calculation	13
Table 3.8.11	CMSL - 8	Breakdown Of Equivalent Crude Oil Price	14
Table 3.8.12	CMSL - 8	Economic Comparison Of Cases At Maximum Reactor Throughput	15

VOLUME III
SECTION III - CMSL-8
LIST OF FIGURES

FIGURE 3.8.1	Economic Effect of Plastics Cost 16
---------------------	--

VOLUME III

SECTION III

TECHNICAL ASSESSMENT - CMSL-8

1.0 BACKGROUND

The objective of Run 227-85 (CMSL-8) was to investigate in the bench unit the coliquefaction of the primary plastics constituents of municipal solid waste together with coal. The technical feasibility of combined coal/plastics liquefaction had been demonstrated in continuous operation on the PDU-scale in an earlier DOE-sponsored run (POC-2). This CMSL-run was the initial bench-scale effort to understand and thus to optimize the effect of the major process variables in plastics/coal coliquefaction. Supported Ni-Mo catalyst was used only in the first reactor stage and dispersed catalyst (sulfated iron-Molybdenum A) was added to the first-stage feed. The run also continued use of the in-line hydrotreater.

The coal for CMSL-8 was a Crown Mine Illinois #6 bituminous coal, previously used in CMSL-5. The plastics mixture contained 50% high-density polyethylene, 35% polystyrene and 15% polyethylene terephthalate. The combined plastics content of the total feed was increased during the run, from zero initially to 33% in the final run condition. The compositions and ultimate analyses of the coal plus plastics feed for the various run conditions are shown in *Table 3.8.1*. It is noteworthy that as the run progressed, the heteroatom and ash content of the feed decreased, and the hydrogen content increased.

Five operating conditions were assessed. Condition 1 (Period 6) was with coal only. The plastics content of the total feed was increased to 25% in Condition 2 (Period 11) at substantially the same reactor operating conditions. Space velocity and temperature were increased for Condition 3 (Period 16) with the same feed composition. In Condition 4 (Period 20) the feed plastics content was increased to 33% at the same reactor temperature, but at a decreased space velocity. Finally in Condition 5 (Period 22), the plastics component was polyethylene, at the same operating conditions as in condition 4. The operating conditions are summarized in *Table 3.8.2*.

Yields and process performances for the above run conditions are summarized in *Table 3.8.2*. As expected from the feed analysis the hydrogen consumption decreased as the run progressed. Except for Period 6 (coal-only operation) the gas yield remained low. Coal-plus-plastics conversion remained high throughout the run, but residuum conversion dropped off with the introduction of the plastics components so that the distillate yield declined the run progressed. Very low distillate yield was obtained during Period 22 when high-density polyethylene was the only plastics component.

The material balances in *Table 3.8.3* show lower liquids production in the course of CMSL-8. *Table 3.8.4* presents net hydrogen balances. Since hydrogen needs decreased and liquefaction bottoms oil yields increased during the course of the run, the need for steam reforming gases decreased, allowing process gases to be used as plant fuel, and thereby minimizing the need for imported natural gas.

Table 3.8.5 shows the thermal efficiencies. *Table 3.8.6* is a summary of the utilities usage and *Table 3.8.7* shows the capacities of the various process units and off sites.

Liquefaction plant investment details are presented in *Table 3.8.8*. Equipment has been provided to dissolve plastics in the process solvent, separately from coal dissolution. Despite the added cost of this equipment, all the CMSL-8 run periods with plastic feed show lower liquefaction plant cost than the coal only case, owing to the lower reactor cost, which reflects lower vapor flow due to the reduced hydrogen consumption. The advantage of higher reactor space velocity is observed for Period 16. Liquefaction Plant investment is lowest for Period 22, but the distillate production dropped off significantly for this operation.

Comparison of the total plant investment, in *Table 3.8.9* shows the advantage of combined coal/plastics operation. Total plant investments for the various coprocessing cases are 8-27% lower than for coal only operation of Period 6. However, on the basis of investment per unit of distillate product, the coprocessing investments range from 93% (Period 11, with 25% mixed plastics) to 108% (Period 22, with 33% HDPE) than that of the Period 6, coal only operation.

2.0 SUMMARY

Economics are summarized in *Table 3.8.10*. The coprocessing operations are more economically attractive than the coal only operation, in terms of the equivalent crude oil price, except for the pure polyethylene feed case (Period 22). For Period 16, the savings in the liquefaction plant costs due to the higher reactor space velocity are offset by the decreased liquids production. *Table 3.8.11* summarizes the breakdown of the equivalent crude oil prices, shown in *Table 3.8.10*.

Table 3.8.12 shows results of the economic comparison utilizing maximum-sized reactors, assuming the use of an interstage separator, which would lower the vapor rate per stage and permit larger maximum diameter reactors and fewer liquefaction trains. This comparison clearly shows the advantage of combined coal/plastics coliquefaction. The lowest equivalent crude oil price is \$25.95 per barrel for the Period 20 operation with 33% mixed plastics at the lower space velocity. The cost is \$5.40 per barrel lower than that of the coal-only operation of Period 6.

The economic analysis in *Tables 3.8.10* and *3.8.11* assumed plastics are received at no cost. *Figure 3.8.1* shows the economic sensitivity to plastics cost based on CMSL-8 results, excluding use of pure polyethylene. The economics favor use of coal/plastics over the coal-only case below a plastics cost of over \$60/ton for Period 11, \$50/ton for Period 20, and \$30/ton for Period 15, for equivalent oil prices equal to that of the Period 6 coal-only operation.

The equivalent crude oil price for the Period 6 coal-only operation of Run CMSL-8 is \$2.10 per barrel higher than that for a similar operation in Run CMSL-2, which used extrudate catalyst in both stages with no additive. Nominally, this difference reflects inferior performance of the sulfated iron/molybdenum catalyst. However, several of the operating condition were different for the two runs. Run CMSL-8 had a higher space velocity 481 Kg/h/M3 against 296 Kg/h/M3, higher stage temperatures, 32 C and 11 C higher first and second stage temperatures,

and a higher recycle solvent rate, 1.5 kg/kg coal against 1.06 kg/kg. It is not certain that this set of conditions in Run CMSL-8 would necessarily be optimum for such coal-only operations.

3.0 CONCLUSIONS

Compared to liquefaction of coal alone, the coliquefaction of plastics and coal is economically attractive for the operating conditions demonstrated in CMSL-8. Both the capital investment and the operating costs are lower for coliquefaction compared to coal-only operation. The advantage of higher reactor space velocity is not clearly apparent from these results, due to a slight drop-off in liquids production. The high-density polyethylene feed is not as economically attractive a coliquefaction feedstock as the plastics mixture expected in commercial municipal waste and used in this run.

TABLE 3.8.1

FEED ANALYSIS, CMSL-8

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
<u>Feed Composition, W%</u>					
Coal	100.00	75.00	75.00	67.00	67.00
HDPE	0.00	12.50	12.50	16.50	33.00
Polystyrene	0.00	8.75	8.75	11.55	0.00
PET	0.00	3.75	3.75	4.95	0.00
Total	100.00	100.00	100.00	100.00	100.00
<u>Ultimate Analysis, W%</u>					
Carbon	70.28	73.64	73.64	74.72	75.23
Hydrogen	4.73	6.20	6.20	6.67	7.99
Nitrogen	1.33	1.01	1.01	0.90	0.89
Sulfur	4.17	3.13	3.13	2.80	2.81
Oxygen (by difference)	9.09	8.22	8.22	7.94	6.11
Ash	10.40	7.80	7.80	6.97	6.97
Total	100.00	100.00	100.00	100.00	100.00
H/C Atomic ratio	0.802	1.003	1.003	1.064	1.265
O/C Atomic ratio	0.097	0.084	0.084	0.080	0.061
Heating value, BTU/lb , coal + plastics					
calculated	12,739	14,181	14,181	14,643	15,690

TABLE 3.8.2

CMSL - 8
DESIGN BASIS COMPARISON

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
<u>Operating Conditions</u>					
Interstage separator	no	no	no	no	no
Inline hydrotreater	yes	yes	yes	yes	yes
Space Velocity, lb/hr/ft ³	30	30	40	30	30
<u>Recycle Solvent</u>					
Oil/solids, lbs/lb	1.5	1.6	1.8	2.1	1.9
Resid, W%	30	46	45	57	64
<u>Temperatures, F</u>					
First Stage	810	810	810	811	811
Second Stage	822	826	850	850	850
Catalyst Replacement Rate, lb/Ton	1.35	1.35	1.35	1.35	1.35
Dispersed Catalyst, ppm	100	100	100	100	100
<u>Projected Process Performance</u>					
Feed Conversion, W% MAF	96.1	95.9	95.5	95.6	95.8
Resid Conversion, W% MAF	91.3	85.4	78.4	76	62.1
Desulfurization, W%	80.3	82.7	79.0	78.8	69.9
Denitrogenation, W%	82.8	81.4	78.3	69.6	23.2
<u>Projected Yields, W% Dry Feed</u>					
H ₂ S	3.56	2.75	2.63	2.34	2.09
NH ₃	1.34	1.00	0.96	0.77	0.25
H ₂ O	8.13	6.77	6.32	5.49	4.48
CO _x	0.52	0.71	1.16	0.65	0.19
C ₁ -C ₃	10.97	8.54	7.98	6.56	4.53
C ₄ -350 F	18.34	21.87	20.80	19.39	11.36
350-650 F	34.71	29.84	19.36	26.34	17.26
650-975 F	11.06	13.61	19.28	14.8	19.46
975 + F	4.34	9.71	15.72	18.21	31.38
Unconverted Feed	3.49	3.75	4.15	4.09	3.92
Ash	10.40	7.80	7.80	6.97	6.97
TOTAL:	106.87	106.35	106.16	105.62	101.9
C ₄ -975, W% dry feed	64.11	65.32	59.43	60.54	48.08
, W% MAF	71.55	70.84	64.46	65.07	51.68

TABLE 3.8.3

CMSL - 8

OVERALL MATERIAL BALANCE

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
Coal, TPSD	9,800	7,350	7,350	6,533	6,533
Plastics, TPSD	0	2,450	2,450	3,267	3,267
Coal + Plastics Feed, TPSD	9,800	9,800	9,800	9,800	9,800
Natural Gas, MMSCFD	133	89	65	62	73
<u>Liquid Products, BPSD</u>					
Gasoline	11,884	11,702	10,048	10,513	8,012
Diesel	28,862	28,419	24,402	25,532	19,459
TOTAL:	40,746	40,121	34,450	36,045	27,471
Barrels/Ton total feed	4.16	4.09	3.52	3.68	2.80
<u>By-products</u>					
Propane, BPSD	4,097	3,099	2,607	2,127	1,604
Butane, BPSD	1,867	2,194	2,071	1,949	1,168
Sulfur, TPSD	360	270	269	238	189
Ammonia, TPSD	131	98	94	75	25
Ash to disposal, TPSD	1,128	895	920	899	876

TABLE 3.8.4

CMSL - 8

PLANT NET HYDROGEN BALANCE

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
<u>Hydrogen Consumption, MMSCFD</u>					
Liquefaction	254	234	227	207	70
Product Upgrading	35	-6	-17	-19	11
TOTAL:	289	228	210	188	81
Hydrogen Consumption, SCF/B	7,088	5,690	6,089	5,208	2,938
<u>Hydrogen Production, MMSCFD</u>					
Partial Oxidation	64	121	195	188	81
Steam Reforming	225	107	15	0	0
TOTAL:	289	228	210	188	81

TABLE 3.8.5

CMSL - 8
THERMAL EFFICIENCY

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
<u>Inputs, GBTU/Day</u>					
Coal + Plastics	249.7	277.9	277.9	287.0	307.5
Natural Gas	120.8	80.4	59.0	55.9	65.8
Total	370.5	358.3	336.9	342.9	373.3
<u>Outputs, GBTU/Day</u>					
Gasoline	66.4	65.4	56.1	58.7	44.7
Diesel	167.5	164.9	141.5	148.1	112.7
Propane	15.8	11.9	10.0	8.2	6.2
Butane	8.1	9.6	9.0	8.5	5.1
Sulfur	3.2	2.4	2.4	2.1	1.7
Ammonia	2.5	1.9	1.8	1.5	0.5
Total	263.5	256.1	220.8	227.1	170.9
Thermal Efficiency, %	71.1	71.5	65.2	66.2	45.8

TABLE 3.8.6**CMSL - 8
UTILITIES SUMMARY**

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
Electric Power, MW	184	188	209	201	122
600 Psig Steam, Mlbs/hr	503	318	227	195	315
Cooling Water, Mgpm	211	163	147	132	113
Process Fuel, GBTU/Day	121	80	59	56	66
Raw Water, gpm	6,467	5,576	5,770	5,313	4,622

TABLE 3.8.7

CMSL - 8
CAPACITIES OF PROCESS UNITS AND OFFSITES

			<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
Area							
No.	Description	Sizing basis, Units					
100	Coal Preparation	TPSD Dry coal	9800	7350	7350	6533	6533
150	Plastics Preparation	TPSD Plastics	0	2450	2450	3267	3267
200	Liquefaction	TPSD Total Feed	9800	9800	9800	9800	9800
300	Hydrogen Manufacture						
	Partial Oxidation	MMSCFD H ₂	64	121	195	188	81
	Steam Reforming	MMSCFD H ₂	225	107	15	0	0
400	Oxygen Plant	TPSD Oxygen	799	1514	2443	2352	1011
500	Product Treating						
	Sour Water Treating	gpm sour water	2776	2268	2173	2006	1466
	Sulfur Recovery	TPSD Sulfur	360	270	269	238	189
	Gas plant	lb/hr C ₁ -C ₃	89629	69760	65203	53557	37028
600	Upgrading & Sol Sep						
	Hydrotreating	BPSD Coal liquids	40746	40121	34450	36045	27471
	Catalytic Reforming	BPSD 180-350	11884	11702	10048	10513	8012
700	Utilities						
	Steam Generation	Mlbs/hr	503	318	227	195	315
	Power Distribution	MW	184	188	209	201	122
	Cooling Water	MGPM	211	163	147	132	113
800	Tankage						
	Coal Liquids	BPSD liquids	40746	40121	34450	36045	27471
	LPG	BPSD LPG	4097	3099	2607	2127	1604
	Waste Solids	TPSD solids	1128	895	920	899	876
900	General Off-Sites	TPSD total feed	9800	9800	9800	9800	9,800

TABLE 3.8.8

CMSL - 8

LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
<u>Major Equipment Costs, \$M</u>					
Pumps	24,018	24,252	25,192	26,413	25,665
Reactors	40,905	38,166	30,726	36,604	32,946
Fired Heaters	14,515	14,948	16,590	17,808	15,579
Exchangers	16,190	15,697	15,853	16,042	12,388
Drums, Towers & Hydrotreater	30,531	29,500	29,551	28,979	20,546
Compressors	29,044	28,105	27,737	26,690	17,647
HPU	11,344	10,169	9,642	8,925	4,129
TOTAL	166,547	160,837	155,291	161,461	128,900
<u>Plant Investment, \$MM</u>					
Materials & Equipment	301.8	291.4	281.4	292.5	233.5
Labor & Subcontracts	130.6	126.1	121.7	126.6	101.1
Indirects	108.6	104.9	101.3	105.3	84.1
Contingency	0.0	0.0	0.0	0.0	0.0
Total Liquefaction Plant Investment	541.0	522.4	504.4	524.4	418.7

TABLE 3.8.9

CMSL - 8
TOTAL PLANT INVESTMENT SUMMARY
(Plant Investment, \$MM, 1991 US Gulf Coast Basis)

Area	Name	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
100	Coal Preparation	45.5	36.1	36.1	32.9	32.9
150	Plastics Preparation	0.0	10.5	10.5	13.2	13.2
200	Liquefaction	541.0	522.4	504.4	524.4	418.7
300	Hydrogen Manufacture	239.8	204.8	175.1	151.9	84.1
400	Oxygen Plant	37.3	58.3	81.5	79.4	43.9
500	Product Treating	297.8	250.9	241.0	213.6	168.4
600	Upgrading & Solids Sep'n	97.3	108.2	106.1	120.2	113.6
700	Utilities	363.6	282.1	253.9	246.1	262.4
800	Tankage	115.4	113.9	100.0	103.9	82.4
900	General Off-Sites	184.9	182.7	182.9	182.7	182.5
	Subtotal	1922.6	1769.9	1691.5	1668.3	1402.1
	Fee, Contingency	384.1	353.5	337.9	333.1	280.0
	Total Plant Investment	2,307	2,123	2,029	2,001	1,682
	\$/BPD of Product	56,612	52,925	58,909	55,525	61,232

TABLE 3.8.10

CMSL - 8
PRODUCT COST CALCULATION

		<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
<u>Operating Costs, \$MM/year</u>						
Coal	(\$20.50/Ton)	66.00	49.50	49.50	44.00	44.00
Plastics	(\$0.00/Ton)	0.00	0.00	0.00	0.00	0.00
Natural Gas	(\$2.00/MMBTU)	79.34	52.80	38.73	36.72	43.23
Water	(\$0.10/Mgal)	0.31	0.26	0.27	0.25	0.22
Catalysts and Chemicals		28.31	21.49	16.62	15.59	14.58
Ash Disposal	(\$5.00/Ton)	1.85	1.47	1.51	1.48	1.44
Labor		23.07	23.07	23.07	23.07	23.07
Maintenance		20.67	20.67	20.67	20.67	20.67
Capital-Related		345.80	319.92	303.88	300.79	251.84
TOTAL:		565.35	489.18	454.25	442.57	399.05
<u>By-product Credits, \$MM/year</u>						
Propane	(\$7.50/B)	10.09	7.63	6.42	5.24	3.95
Butane	(\$14.50/B)	8.90	10.45	9.86	9.28	5.56
Sulfur	(\$80.00/Ton)	9.45	7.09	7.06	6.25	4.97
Ammonia	(\$120.00/Ton)	5.18	3.86	3.71	2.97	0.98
TOTAL:		33.62	29.03	27.05	23.74	15.46
Product Cost		531.73	460.15	427.20	418.83	383.59
Product Cost, \$/B		39.73	34.91	37.75	35.37	42.51
Crude Oil Equivalent Factor		0.848	0.826	0.839	0.828	0.860
Equivalent Crude Oil Price, \$/B		33.68	28.84	31.67	29.30	36.57

TABLE 3.8.11

CMSL - 8
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>	<u>Period 22</u>
<u>Contribution to Price, \$/B</u>					
Coal	4.18	3.10	3.67	3.08	4.20
Plastics	0.00	0.00	0.00	0.00	0.00
Natural Gas	5.03	3.31	2.87	2.57	4.12
Water	0.02	0.02	0.02	0.02	0.02
Catalysts & Chemicals	1.79	1.35	1.23	1.09	1.39
Ash Disposal	0.12	0.09	0.11	0.10	0.14
Labor	1.46	1.45	1.71	1.61	2.20
Maintenance	1.31	1.30	1.53	1.45	1.97
Capital-Related	21.90	20.05	22.53	21.04	24.01
By-product Credit	-2.13	-1.82	-2.01	-1.66	-1.47
Equivalent Crude Oil Price, \$/B	33.68	28.84	31.67	29.30	36.57

TABLE 3.8.12

CMSL - 8
ECONOMIC COMPARISON OF CASES AT MAXIMUM REACTOR
THROUGHPUT

	<u>Period 6</u>	<u>Period 11</u>	<u>Period 16</u>	<u>Period 20</u>
Total feed to Liquefaction, T/D	10,600	12,250	12,700	14,300
Number of Liquefaction trains	4	4	4	4
Total feed, T/D/train	2,650	3,063	3,175	3,575
Liquid Product, B/D	44,056	50,103	44,587	52,507
Liquefaction Plant Cost, \$MM	573	618	614	697
Total Plant Investment, \$MM	2,441	2,490	2,451	2,613
Net Annual Operating Cost, \$MM	562.99	537.01	515.53	550.73
Product Cost, \$/B	38.90	32.63	35.20	31.93
Equivalent Crude Oil Price, \$/B	32.84	26.62	29.12	25.95

Economic Effect of Plastics Cost

CMSL - 8

FIGURE 3.8.1

■ Period 11 □ Period 20 △ Period 16 × Base

VOLUME III

SECTION III

RUN CMSL-9

BLACK THUNDER MINE COAL

MOLYBDENUM (MOLYVAN) ADDITIVE

FEOOH ADDITIVE

NO EXTRUDATE CATALYST

COAL-ONLY AND COAL-PLASTICS

VOLUME III

SECTION III - CMSL-9

TABLE OF CONTENTS

**MOLYBDENUM (MOLYVAN) ADDITIVE
FEOOH ADDITIVE
NO EXTRUDATE CATALYST
COAL-ONLY AND COAL-PLASTICS**

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	3

VOLUME III

SECTION III - CMSL-9

LIST OF TABLES

Table 3.9.1	Feed Analysis	3
Table 3.9.2	Design Basis Comparison	4
Table 3.9.3	Overall Material Balance	5
Table 3.9.4	Plant Net Hydrogen Balance	6
Table 3.9.5	Thermal Efficiency	7
Table 3.9.6	Utilities Summary	8
Table 3.9.7	Capacities of Process Units and Offsites	9
Table 3.9.8	Liquefaction Plant Investment Details	10
Table 3.9.9	Total Plant Investment Summary	11
Table 3.9.10	Product Cost Calculation	12
Table 3.9.11	Breakdown of Equivalent Crude Price	13
Table 3.9.12	Economic Comparison of Cases at Maximum Reactor Throughput	14

VOLUME III

SECTION III

TECHNICAL ASSESSMENT-CMSL-9

1.0 BACKGROUND

The primary objective of Run 227-87 (CMSL-9) was to investigate the feasibility of bench-scale liquefaction in an all-dispersed catalyst multi-stage reactor system. The run demonstrated operation with coal only, as well as coliquefaction of coal plus the primary plastics constituents of municipal solid waste. A pretreatment reactor was added ahead of the two-stage liquefaction reactors, in order to assure complete activation of the dispersed catalyst. The run used an in-line hydrotreater.

The coal for CMSL-9 was a subbituminous Wyoming coal. The plastics mixture contained high-density polyethylene (40%), polystyrene (27%) and polypropylene (33%); in one condition pure polyethylene was used. The plastics content of the total feed varied from 33% to 50%. Feed compositions and ultimate analyses of the coal plus plastics feed for the various run conditions are shown in *Table 3.9.1*.

In the coal-only operations the major processing conditions were kept nearly constant but dispersed catalyst rates were assessed: molybdenum (Molyvan lubricant additive) rates of 300 ppm (Period 5, 150 ppm (Period 15), and then molybdenum of 100 ppm plus an iron catalyst at 10,000 ppm (Period 29). In the coal/plastics operations the reactor temperatures were increased from those used in the coal-only operations, but the solids feed space velocity was not changed. Three coal / plastic conditions were assessed, all with a molybdenum rate of 300 ppm and an iron rate of 10,000 ppm. The feed was 33% of the plastics mixture during Period 34, 33% of polyethylene for Period 38, and 50% of the plastics mixture for Period 41.

The operating conditions, yields and process performance are summarized in *Table 3.9.2*. In the coal only operation, as the amount of molybdenum was lowered feed conversion remained high, but the residuum conversion decreased so that the yield of distillates fell slightly. The incorporation of iron additive did not reverse this trend in residuum conversion. With 33-50% mixed plastics feed, Periods 34 and 41, residuum conversion and distillates yields were appreciably higher than during the comparable coal only operation, Period 29. With the polyethylene as the only plastic component, Period 38, the residuum conversion and distillate yield were at the levels of the coal only operation. This inferior process performance using only polyethylene was observed in Run CMSL-8.

The material balances in *Table 3.9.3* point out the lower liquids production in the course of coal-only operation and the subsequent increase in liquids production with coal/plastics operation. *Table 3.9.4* presents net hydrogen balances. *Table 3.9.5* shows the thermal efficiency for the cases. *Table 3.9.6* is a summary of the utilities usage, and *Table 3.9.7* shows the capacities of the various process units and off sites.

The liquefaction plant investment details are presented in *Table 3.9.8*. When feeding

coal/plastics mixtures, provision has been made to dissolve plastics in the process solvent separately from coal dissolution. Equipment for supported catalyst addition has been deleted. The low vapor flow rates consequent of the low hydrogen consumption for all the CMSL-9 cases has allowed use of substantially smaller reactors. The reduced cost is especially notable for the coal/plastics cases.

Comparison of the total plant investment is given in *Table 3.9.9*. In coal-only operation, the liquefaction plant savings are offset by higher costs in other plant sections, notably the utilities, so that plant investment for the CMSL-9 coal-only operation is within 1.5% of those of Run CMSL-3 (1500 ppm Mo, second stage extrudate catalyst, and Run CMSL-4 (extrudate catalyst in both stages). Plant investment for coprocessing operations with mixed plastics were 7 - 17% lower than for coal-only operation.

2.0 SUMMARY

The overall economics are summarized in *Table 3.9.10*. In the coal-only operation of Period 5, using only 300 ppm Mo additive, the cost equivalent crude oil price, \$32.46 per barrel, was only \$0.70 per barrel higher than that of Run CMSL-3 where there was extrudate catalyst in the second stage and 1500 ppm of Mo additive was used. In Run CMSL-9, when the molybdenum additive was lowered to 150 ppm, Period 15, the equivalent crude oil price increased by \$1.90 per barrel, and when 10000 ppm of Fe additive was also used the cost increased an addition \$2.80 per barrel. With 50% mixed plastics coprocessing feed, Period 41, the equivalent crude oil cost was \$11.50 per barrel lower than in the comparable coal-only operation, Period 29. With 33% polyethylene feed, the equivalent crude oil cost was higher, but still \$4.00 per barrel lower than that in the comparable coal only operation.

The breakdown of the equivalent crude oil prices, given in *Table 3.9.11*, shows how the cost of dispersed iron additive contributes to the high equivalent prices of the operations employing the additive. Its cost is the major cause of the higher cost of such coal-only operations than that using Mo additive only. Its contribution to the equivalent crude oil price, \$2.90 per barrel, could be reduced if lower amounts of the additive proved to be effective.

Table 3.9.12 is summary of the economic analysis, assuming the use of an interstage separator which would reduce the vapor load per reactor permitting longer reactors of the maximum diameter for increased coal feed per reactor and fewer liquefaction trains. Such a modification lowered the equivalent crude oil prices by \$0.5-4.30 per barrel, with the lowest price being \$19.81 per barrel for the coprocessing operation of Period 41, feeding 50% of mixed plastic.

3.0 CONCLUSIONS

Economics of an all-dispersed catalyst are comparable to those with supported catalyst. The high dispersed iron catalyst rate in CMSL-9 harms the economics. As previously demonstrated in CMSL-8, the coliquefaction of plastics and coal is economically attractive, even at the high iron rate additive used in CMSL-9.

TABLE 3.9.1

FEED ANALYSIS, CMSL-9

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
<u>Feed Composition, W%</u>						
Coal	100.00	100.00	100.00	67.00	67.00	50.00
HDPE	0.00	0.00	0.00	13.20	33.00	20.00
Polystyrene	0.00	0.00	0.00	8.91	0.00	13.50
Polypropylene	0.00	0.00	0.00	10.89	0.00	16.50
Total	100.00	100.00	100.00	100.00	100.00	100.00
<u>Ultimate Analysis, W% Dry Feed</u>						
Carbon	70.12	70.12	70.12	75.85	75.26	78.80
Hydrogen	5.11	5.11	5.11	7.55	8.14	8.81
Nitrogen	0.99	0.99	0.99	0.66	0.66	0.50
Sulfur	0.53	0.53	0.53	0.35	0.35	0.26
Oxygen (by difference)	17.50	17.50	17.50	11.74	11.74	8.75
Ash (SO3-free)	5.75	5.75	5.75	3.85	3.85	2.88
Total	100.00	100.00	100.00	100.00	100.00	100.00
H/C Atomic Ratio	0.87	0.87	0.87	1.19	1.29	1.33
O/C Atomic Ratio	0.19	0.19	0.19	0.12	0.12	0.08
<u>Heating Value, BTU/lb dry feed</u>						
calculated	11,997	11,997	11,997	14,781	15,061	16,218

TABLE 3.9.2
CMSL - 9
DESIGN BASIS COMPARISON

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
<u>Operating Conditions</u>						
Pretreater	yes	yes	yes	yes	yes	yes
Inline hydrotreater	yes	yes	yes	yes	yes	yes
Space Velocity, lb/hr/ft ³	42	42	42	42	44	42
Supported Catalyst Rate, lb/ton feed	0	0	0	0	0	0
<u>Dispersed Catalyst, ppm</u>						
Iron	300	150	10000	10000	10000	10000
Molyvan			100	300	300	300
<u>Recycle Solvent</u>						
Solvent/feed, lb/lb	1.083	1.123	1.133	1.433	1.294	1.4
Resid, W%	30	30	30	30	30	30
<u>Temperatures, F</u>						
First Stage	832841	833842	824840	839839	839861	840863
Second Stage						
<u>Projected Process Performance</u>						
Feed Conversion, W% MAF	95.8	95.2	95.4	94.4	95.5	97.0
Resid Conversion, W% MAF	91.9	89.1	87.7	92.2	78.8	88.2
Denitrogenation, W%	84.4	80.3	71.0	69.2	63.0	63.0
<u>Projected Yields, W% Dry Coal</u>						
H ₂ S	0.53	0.53	0.53	0.36	0.36	0.27
NH ₃	1.02	0.97	0.85	0.51	0.51	0.38
H ₂ O	15.16	13.17	14.86	10.46	10.46	7.13
CO _x	3.76	5.57	4.35	2.81	2.81	2.06
C ₁ -C ₃	10.91	12.04	9.17	7.42	7.42	7.29
C ₄ -390F	21.44	19.15	11.95	13.12	13.12	29.02
390-500F	12.09	14.57	15.54	10.28	10.28	11.51
500-650F	17.11	15.66	14.83	12.14	12.14	13.85
650-850F	10.17	6.75	12.36	18.25	18.25	13.23
850-975F	1.68	2.25	3.98	4.58	4.58	4.30
975+ F	3.68	5.76	7.30	16.08	16.08	8.59
Unconverted Feed	3.91	4.53	4.31	4.30	4.30	2.91
Ash	5.75	5.75	5.75	3.85	3.85	2.88
Total:	107.22	106.70	105.80	104.16	104.16	103.43
C ₄ -975 F, W% dry feed	62.50	58.38	58.66	58.37	58.37	71.91
, W% MAF	66.31	61.94	62.24	60.71	60.71	74.04

TABLE 3.9.3

CMSE - 9
OVERALL MATERIAL BALANCE

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
Coal, TPSD	10,500	10,500	10,500	7,000	7,000	5,250
Plastics, TPSD	0	0	0	3,500	3,500	5,250
Total Feed, TPSD	10,500	10,500	10,500	10,500	10,500	10,500
Natural Gas, MMSCFD	120	103	90	89	42	58
<u>Liquid Products, BPSD</u>						
Gasoline	12,329	11,421	11,370	13,837	10,851	13,540
Diesel	29,944	27,738	27,613	33,605	26,351	32,884
TOTAL:	42,273	39,159	38,983	47,442	37,202	46,424
Barrels/Ton total feed	4.03	3.73	3.71	4.52	3.54	4.42
<u>By-products</u>						
Propane, BPSD	4,517	5,084	4,174	3,931	3,323	3,587
Butane, BPSD	2,303	2,066	1,349	2,762	1,462	3,070
Sulfur, TPSD	49	49	49	32	32	24
Ammonia, TPSD	107	102	90	59	53	40
Ash to disposal, TPSD	738	792	738	542	1,286	398

TABLE 3.9.4
CMSL-9
PLANT NET HYDROGEN BALANCE

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
Hydrogen Consumption, MMSCFD						
Liquefaction	286	265	230	182	165	136
Product Upgrading	23	26	46	32	-13	15
TOTAL:	309	292	276	213	152	151
Hydrogen Consumption, SCF/B	7310	7450	7074	4490	4082	3247
Hydrogen Production, MMSCFD						
Partial Oxidation	70	94	125	91	152	135
Steam Reforming	239	198	151	122	0	16
TOTAL:	309	292	276	213	152	151

TABLE 3.9.5

CMSL-9

THERMAL EFFICIENCY.

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
Inputs, GBTU/Day						
Coal + Plastics	25.19	251.9	251.9	310.4	316.3	340.6
Natural Gas	109.1	93.4	81.3	80.9	37.8	52.8
Total	361.0	345.3	333.2	391.3	354.1	393.4
Outputs, GBTU/Day						
Gasoline	68.9	63.8	63.5	77.4	60.6	75.7
Diesel	173.8	160.9	160.2	195.1	152.9	190.9
Propane	17.4	19.6	16.1	15.1	12.8	13.8
Butane	10.0	9.0	5.9	12.0	6.4	13.4
Sulfur	0.4	0.4	0.4	0.3	0.3	0.2
Ammonia	2.1	2.0	1.7	1.1	1.0	0.8
Total	272.6	255.7	247.8	301.0	234.0	294.8
Thermal Efficiency, %	75.5	74.1	74.4	76.9	66.1	74.9

TABLE 3.9.6

**CMSL - 9
UTILITIES SUMMARY**

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
Electric Power, MW	193	199	190	162	173	157
600 Psig Steam, Mlbs/hr	257	287	132	127	159	134
Cooling Water, Mgpm	160	165	132	116	108	104
Process Fuel, GBTU/Day	109	93	81	81	38	53
Raw Water, gpm	4,287	4,879	3,963	3,497	4,362	3,987

TABLE 3.9.7

CMSL - 9
CAPACITIES OF PROCESS UNITS AND OFFSITES

No.	Description	Sizing basis, Units	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
100	Coal Preparation	TPSD Dry coal	10,500	10,500	10,500	7,000	7,000	5,250
150	Plastics Preparation	TPSD Plastics	0	0	0	3,500	3,500	5,250
200	Liquefaction	TPSD Total feed	10,500	10,500	10,500	10,500	10,500	10,500
300	H ₂ Manufacture							
	Partial Oxidation	MMSCFD H ₂	70	94	125	91	152	135
	Steam Reforming	MMSCFD H ₂	239	198	151	122	0	16
400	Oxygen Plant	TPSD Oxygen	881	1,182	1,572	1,142	1,900	1,692
500	Product Treating							
	Sour Water treating	gpm sour water	1,726	1,670	1,577	1,275	1,117	1,031
	Sulfur recovery	TPSD Sulfur	49	49	49	32	32	24
	Gas plant	lb/hr C ₁ -C ₃	95,454	105,341	80,246	71,356	64,951	63,823
600	Upgrading							
	Hydrotreating	BPSD Coal liquids	42,273	39,159	38,983	47,442	37,202	46,424
	Catalytic reforming	BPSD 180-350	12,329	11,421	11,370	13,837	10,851	13,540
700	Utilities							
	Steam generation	Mlbs/hr	257	287	132	127	159	134
	Power distribution	MW	193	199	190	162	173	157
	Cooling water	MGPM	160	165	132	116	108	104
800	Tankage							
	Coal liquids	BPSD liquids	42,273	39,159	38,983	47,442	37,202	46,424
	LPG	BPSD LPG	4,517	5,084	4,174	3,931	3,323	3,587
	Waste solids	TPSD solids	738	792	738	542	1,286	398
900	General Off-Sites	TPSD Total Feed	10,500	10,500	10,500	10,500	10,500	10,500

TABLE 3.9.8

CMSL - 9

LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
<u>Major Equipment Costs, \$M</u>						
Pumps	23,136	23,372	23,553	24,999	24,446	24,996
Reactors & Pretreaters	68,793	68,793	65,258	64,261	59,501	60,224
Fired Heaters	13,904	14,031	14,013	15,421	14,966	14,975
Exchangers	17,207	17,176	16,645	16,803	15,723	15,244
Drums, Hydrotreaters & Towers	28,344	28,157	27,245	26,611	24,861	22,343
Compressors	35,077	33,977	31,965	29,023	27,906	25,868
HPU	13,208	12,964	11,944	10,969	9,677	8,582
TOTAL	199,669	198,470	190,623	188,087	177,080	172,232
<u>Plant Investment, \$MM</u>						
Materials & Equipment	361.8	359.5	345.5	340.7	320.9	312.1
Labor & Subcontracts	156.5	155.6	149.4	147.5	138.8	135.0
Indirects	130.2	129.5	124.3	122.7	115.5	112.3
Contingency	0.0	0.0	0.0	0.0	0.0	0.0
Total Liquefaction Plant Investment	648.5	644.6	619.2	610.9	575.2	559.4

TABLE 3.9.9

CMSE - 9

TOTAL PLANT INVESTMENT SUMMARY

(Plant Investment in \$MM, 1991 US Gulf Coast basis)

Area	Name	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
100	Coal Preparation	200.0	200.0	200.0	144.6	144.6	114.9
150	Plastics Preparation	0.0	0.0	0.0	14.0	14.0	19.3
200	Liquefaction	648.5	644.6	619.2	610.9	575.2	559.4
300	Hydrogen Manufacture	253.0	245.5	236.5	194.7	130.8	140.6
400	Oxygen Plant	39.9	49.0	59.9	47.9	68.4	63.0
500	Product Treating	277.8	294.8	248.5	226.7	212.3	208.1
600	Upgrading & Solids Sep'n	93.9	92.0	92.2	103.0	100.5	103.2
700	Utilities	254.9	270.5	235.8	211.0	219.7	206.1
800	Tankage	119.0	111.5	111.1	131.4	106.7	129.0
900	General Off-Sites	189.5	190.0	189.5	187.3	194.7	185.6
	Subtotal	2076.5	2097.9	1992.7	1871.5	1766.9	1729.2
	Fee, Contingency	414.8	419.1	398.0	373.9	353.0	345.4
	Total Plant Investment	2,491	2,517	2,391	2,245	2,120	2,075
	\$/BPD of Product	58,934	64,276	61,327	47,329	56,983	44,688

TABLE 3.9.10
CMSL - 9
PRODUCT COST CALCULATION

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
<u>Operating Costs, \$MM/year</u>						
Coal (\$7.00/Ton)	24.14	24.14	24.14	16.10	16.1	12.07
Plastics (\$0.00/Ton)	0	0.00	0	0.00	0	0
Natural Gas (\$2.00/MMBTU)	71.67	61.34	53.39	53.12	24.87	34.7
Water (\$2.50/Mgal)	5.07	5.77	4.69	4.14	5.16	4.71
Catalysts and Chemicals	16.47	14.45	11.58	9.71	3.33	4.07
Dispersed Catalyst	6.21	3.10	57.26	61.40	61.4	61.4
Ash Disposal (\$5.00/Ton)	1.21	1.30	1.21	0.89	2.11	0.65
Labor	24.43	24.43	24.43	24.43	24.43	24.43
Maintenance	21.89	21.89	21.89	21.89	21.89	21.89
Capital-Related	372.49	374.47	356.74	340.78	318.05	316.45
TOTAL:	543.58	530.89	555.33	532.46	477.34	480.37
<u>By-product Credits, \$MM/year</u>						
Propane (\$12.29/Bbl)	18.24	20.53	16.85	15.87	13.42	14.48
Butanes (\$14.50/B)	10.97	9.84	6.43	13.15	6.96	14.62
Sulfur (\$52.00/Ton)	0.84	0.84	0.84	0.55	0.55	0.41
Ammonia (\$200.00/Ton)	7	6.67	5.89	3.85	3.5	2.61
TOTAL:	37.05	37.88	30.01	33.42	24.43	32.12
Net Product Cost, \$MM/year	506.53	493.01	525.32	499.04	452.91	448.25
Product Cost, \$/B	36.48	38.33	41.02	32.02	37.06	29.39
Crude Oil Equivalent Factor	0.833	0.842	0.854	0.813	0.836	0.801
Equivalent Crude Oil Price, \$/B	30.39	32.25	35.02	26.04	30.97	23.54

TABLE 3.9.11

CMSL - 9
BREAKDOWN OF EQUIVALENT CRUDE PRICE

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
<u>Contribution to Crude Price, \$/B</u>						
Coal	1.45	1.58	1.61	0.84	1.10	0.63
Plastics	0.00	0.00	0.00	0.00	0.00	0.00
Natural Gas	4.30	4.01	3.56	2.77	1.70	1.82
Water	0.30	0.38	0.31	0.22	0.35	0.25
Supported Catalyst	0.00	0.00	0.00	0.00	0.00	0.00
Dispersed Catalyst- Mo	0.37	0.20	0.14	0.32	0.42	0.33
Dispersed Catalyst - Iron	0.00	0.00	3.68	2.88	3.77	2.90
Other Catalysts & Chemicals	0.99	0.95	0.77	0.51	0.23	0.21
Ash Disposal	0.07	0.09	0.08	0.05	0.14	0.03
Labor	1.47	1.60	1.63	1.27	1.67	1.28
Maintenance	1.31	1.43	1.46	1.14	1.50	1.15
Capital-Related	22.35	24.50	23.78	17.78	21.75	16.62
By-product credit	-2.22	-2.48	-2.00	-1.74	-1.67	-1.69
Equivalent Crude Oil Price, \$/B	30.39	32.25	35.02	26.04	30.97	23.54

TABLE 3.9.12

CMSL - 9

ECONOMIC COMPARISON OF CASES AT MAXIMUM REACTOR THROUGHPUT

	<u>Period 5</u>	<u>Period 15</u>	<u>Period 29</u>	<u>Period 34</u>	<u>Period 38</u>	<u>Period 41</u>
Total Feed to liquefaction, T/D	10,700	11,000	12,100	14,700	16,300	17,100
Number of liquefaction trains	4	4	4	4	4	4
Total Feed, T/D/train	2,675	2,750	3,025	3,675	4,075	4,275
Product, B/D	43,074	41,014	44,894	66,341	57,646	75,483
Liquefaction Plant Cost, \$MM	625	633	660	750	771	726
Total Plant Investment, \$MM	2,489	2,567	2,619	2,834	2,888	2,868
Net Annual Operating cost, \$MM	508.14	504.33	579.16	636.50	619.44	627.50
Product Cost, \$/B	35.91	37.43	39.27	29.21	32.71	25.31
Equivalent Crude Oil Price, \$/B	29.83	31.35	33.22	23.38	26.70	19.81

VOLUME III

SECTION III

RUN CMSL-10

BLACK THUNDER MINE COAL

MOLYBDENUM (MOLYVAN) ADDITIVE

FEOOH ADDITIVE

NO EXTRUDATE CATALYST

VOLUME III

SECTION III - CMSL-10

TABLE OF CONTENTS

**MOLYBDENUM (MOLYVAN) ADDITIVE
FEOOH ADDITIVE
NO EXTRUDATE CATALYST**

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	2

VOLUME III

SECTION III - CMSL-10

LIST OF TABLES

Table 3.10.1	Design Basis Comparison	3
Table 3.10.2	Overall Material Balance	4
Table 3.10.3	Plant Net Hydrogen Balance	5
Table 3.10.4	Thermal Efficiency	6
Table 3.10.5	Utilities Summary	7
Table 3.10.6	Capacities of Process Units and Offsites	8
Table 3.10.7	Liquefaction Plant Investment Details	9
Table 3.10.8	Total Plant Investment Summary (Plant Investment in \$MM, 1991 US Gulf Coast)	10
Table 3.10.9	Product Cost Calculation	11
Table 3.10.10	Breakdown of Equivalent Crude Oil Price	12
Table 3.10.11	Comparison of Cases at Maximum Reactor Throughput	13

VOLUME III

SECTION III

TECHNICAL ASSESSMENT CMSL-10

1.0 BACKGROUND

The primary objective of Run 227-88 (CMSL-10) was to investigate coal-only liquefaction in an all-dispersed catalyst multi-stage reactor system. As in CMSL-9, a pretreater was added ahead of the two-stage liquefaction reactors for activation of the dispersed catalyst. The dispersed iron catalyst rate was halved and the Molybdenum rate was reduced to one-third of the rate used in CMSL-9.

The feed for CMSL-10 was the same sub-bituminous coal used in the previous CMSL run. Two conditions were evaluated for this technical assessment. In the first condition (Period 9) the space velocity and reactor temperature were about the same as in CMSL-9, while in the second condition (Period 18) both the reactor temperatures and the space velocity were increased. An in-line hydrotreater was used in addition to the pretreater mentioned above. Operating conditions, yields and process performances are summarized in *Table 3.10.1*.

Overall material balances are presented in *Table 3.10.2*. It is notable that the liquid products yield for the high space velocity operation of Period 18 is only 2% lower than that of the low space velocity operation of Period 9. *Table 3.10.3* presents net hydrogen balances and *Table 3.10.4* shows the thermal efficiency. *Table 3.10.5* is a summary of the utilities usage. The higher utilities demand for Period 9 is in large part due to the increased gas recovery unit caused by the higher gas yields for that period. *Table 3.10.6* shows the capacities of the various process units and off sites.

The liquefaction plant investment details are presented in *Table 3.10.7*. The inclusion of the pretreater is expensive and more than offsets savings incurred by eliminating the supported catalyst system. The higher hydrogen consumption and higher gas yields in Period 9 account for the increased liquefaction plant cost. The benefit of higher space velocity is clearly seen in Period 18, where the liquefaction plant cost is 19% lower than that for Period 9 using the lower space velocity.

Comparison of the total plant investment is given in *Table 3.10.8*. The Period 9 costs, with lower space velocity, are well above that of the Period 18 costs, because of the high gas yield and high hydrogen consumption.

2.0 SUMMARY

The overall economics are summarized in *Table 3.10.9*. The breakdown of the equivalent crude oil prices is given in *Table 3.10.10*. The equivalent crude oil price for the high space velocity operation of Period 18 is \$4.00 per barrel lower than that of low space velocity operation of Period 9, reflecting the lower plant cost for that case with only slightly lower liquids production. The Period 18 cost is \$3.40 per barrel lower than that of Period 29 of Run CMSL-9, an operation at about the same space velocity and about 9°C lower stage temperatures using twice the iron additive and the same amount of molybdenum additive used in Run CMSL-10. This change in cost is about twice the savings in additive costs, \$1.80 per barrel, for the Run CMSL-10 operation.

Table 3.10.11 is a summary of the economic analysis assuming the use of an interstage separator which would reduce the vapor load per reactor permitting longer reactors of the maximum diameter for increased coal feed per reactor and fewer liquefaction trains. Such a modification lowered the equivalent crude oil prices by \$2.70 per barrel for Period 18 operation at the higher space velocity to \$28.90 per barrel. This costs about the same as that for an operation with extrudate catalyst in both stages (Run CMSL-4) and \$1.80 per barrel higher than that for an operation using 1500 ppm Mo additive and extrudate catalyst in the second stage (Run CMSL-3). However, a subsequent Run CMSL-11 operation that was essentially the same as that of Run CMSL-10, Period 18, indicated appreciably higher product cost.

3.0 CONCLUSIONS

Run CMSL-10 showed an economic advantage for the higher space velocity operation. The reduction in the amount of iron additive from that used in Run CMSL-9 apparently did not cause an appreciable change in yield of distillate products so that the reduction in cost of the additive effected a lower product cost. Nominally, these operations indicated the economic feasibility of a system with only dispersed catalyst and no extrudate catalyst. Further experimental work should be directed to using lower amounts of the iron additive and reconsidering the necessity for the dispersed catalyst pretreater reactor.

TABLE 3.10.1

CMSL - 10
DESIGN BASIS COMPARISON

	<u>Period 9</u>	<u>Period 18</u>
<u>Operating Conditions</u>		
Pretreater	yes	yes
Inline hydrotreater	yes	yes
Space Velocity, lb/hr/ft ³	25.9	45.0
Supported Catalyst Rate, lb/Ton feed	0	0
<u>Dispersed catalyst, ppm</u>		
Iron	5,000	5,000
Molyvan	100	100
<u>Recycle Solvent</u>		
Solvent/feed, lb/lb	1.08	1.08
Resid, W%	34.0	42.0
<u>Temperatures, F</u>		
First Stage	825	840
Second Stage	839	854
<u>Projected Process Performance</u>		
Feed Conversion, W% MAF	94.4	96.6
Resid Conversion, W% MAF	90.1	84.4
Denitrogenation, W%	85.1	60.4
<u>Projected Yields, W% Dry Coal</u>		
H ₂ S	0.53	0.53
NH ₃	1.02	0.73
H ₂ O	10.35	9.24
CO _x	5.33	3.87
C ₁ -C ₃	15.62	10.91
C ₄ -390 F	21.27	16.49
390-500 F	11.63	11.09
500-650 F	15.70	13.68
650-850 F	9.45	13.16
850-975 F	1.54	4.01
975 + F	3.98	11.48
Unconverted Feed	5.31	3.25
Ash	5.75	5.75
Total:	107.48	104.19
C4-975, W% dry feed	59.59	58.43
, W% MAF	63.23	62.00

TABLE 3.10.2**CMSL - 10
OVERALL MATERIAL BALANCE**

	<u>Period 9</u>	<u>Period 18</u>
Coal, TPSD	10,500	10,500
Natural Gas, MMSCFD	119	96
<u>Liquid Products, BPSD</u>		
Gasoline	11,701	11,482
Diesel	28,418	27,886
TOTAL:	40,119	39,368
Barrels/Ton total feed	3.82	3.75
<u>By-products</u>		
Propane, BPSD	6,525	4,919
Butane, BPSD	2,277	1,795
Sulfur, TPSD	49	49
Ammonia, TPSD	108	76
Ash to disposal, TPSD	1,023	1,180

TABLE 3.10.3**CMSL-10
PLANT NET HYDROGEN BALANCE**

	<u>Period 9</u>	<u>Period 18</u>
<u>Hydrogen Consumption, MMSCFD</u>		
Liquefaction	296	165
Product Upgrading	12	95
TOTAL:	308	260
Hydrogen Consumption, SCF/B	7,682	6,612
<u>Hydrogen Production, MMSCFD</u>		
Partial Oxidation	58	110
Steam Reforming	250	150
TOTAL:	308	260

TABLE 3.10.4

**CMSL - 10
THERMAL EFFICIENCY**

	<u>Period 9</u>	<u>Period 18</u>
<u>Inputs, GBTU/Day</u>		
Coal	251.9	251.9
Natural Gas	108.4	87.0
Total	360.3	338.9
<u>Outputs, GBTU/Day</u>		
Gasoline	65.4	64.2
Diesel	164.9	161.8
Propane	25.1	18.9
Butane	9.9	7.8
Sulfur	0.4	0.4
Ammonia	2.1	1.5
Total	267.8	254.6
Thermal Efficiency, %	74.3	75.1

TABLE 3.10.5

**CMSL - 10
UTILITIES SUMMARY**

	<u>Period 9</u>	<u>Period 18</u>
Electric Power, MW	195	175
600 Psig Steam, Mlbs/hr	483	263
Cooling Water, Mgpm	205	152
Process Fuel, GBTU/Day	108	87
Raw Water, gpm	6,070	4,801

TABLE 3.10.6

CMSL - 10
CAPACITIES OF PROCESS UNITS AND OFFSITES

			<u>Period 9</u>	<u>Period 18</u>
Area				
No.	Description	Sizing basis, Units		
100	Coal Preparation	TPSD Dry coal	10,500	10,500
200	Liquefaction	TPSD Total feed	10,500	10,500
300	Hydrogen Manufacture			
	Partial Oxidation	MMSCFD H ₂	58	110
	Steam Reforming	MMSCFD H ₂	250	150
400	Oxygen Plant	TPSD Oxygen	731	1,379
500	Product Treating			
	Sour Water treating	gpm sour water	1,749	1,525
	Sulfur recovery	TPSD Sulfur	49	49
	Gas plant	lb/hr C ₁ -C ₃	136,684	95,463
600	Upgrading & Solids Sep'n			
	Hydrotreating	BPSD Coal liquids	40,119	39,368
	Catalytic reforming	BPSD 180-350	11,701	11,482
700	Utilities			
	Steam generation	Mlbs/hr	483	263
	Power distribution	MW	195	175
	Cooling water	MGPM	205	152
800	Tankage			
	Coal liquids	BPSD liquids	40,119	39,368
	LPG	BPSD LPG	6,525	4,919
	Waste solids handling	TPSD solids	1,023	1,180
900	General Off-Sites	TPSD Total Feed	10,500	10,500

TABLE 3.10.7

CMSL - 10
LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 9</u>	<u>Period 18</u>
<u>Major Equipment Costs, \$M</u>		
Pumps	23,128	23,289
Reactors & Pretreaters	59,730	37,972
Fired Heaters	13,980	13,545
Exchangers	17,339	15,970
Drums, Hydrotreaters & Towers	28,672	25,254
Compressors	35,623	27,978
HPU	13,395	11,121
TOTAL	191,867	155,129
<u>Plant Investment, \$MM</u>		
Materials & Equipment	347.7	281.1
Labor & Subcontracts	150.4	121.6
Indirects	125.1	101.2
Contingency	0.0	0.0
Total Liquefaction Plant Investment	623.2	503.9

TABLE 3.10.8

CMSL - 10
TOTAL PLANT INVESTMENT SUMMARY
(Plant Investment in \$MM, 1991 US Gulf Coast)

		<u>Period 9</u>	<u>Period 18</u>
Area	Name		
100	Coal Preparation	200.0	200.0
200	Liquefaction	623.2	503.9
300	Hydrogen Manufacture	250.2	226.4
400	Oxygen Plant	35.0	54.6
500	Product Treating	348.0	276.0
600	Upgrading & Solids Sep'n	94.0	98.1
700	Utilities	359.0	254.1
800	Tankage	113.9	112.0
900	General Off-Sites	192.3	193.8
	Subtotal	2215.6	1918.9
	Fee, Contingency	442.6	383.3
	Total Plant Investment	2,658	2,302
	\$/BPD of Product	66,258	58,479

TABLE 3.10.9

CMSL - 10
PRODUCT COST CALCULATION

	<u>Period 9</u>	<u>Period 18</u>
<u>Operating Costs, \$MM/year</u>		
Coal (\$7.00/Ton)	24.14	24.14
Natural Gas (\$2.00/MMBTU)	71.20	57.15
Water (\$2.50/Mgal)	7.18	5.68
Catalysts and Chemicals	17.71	11.83
Dispersed Catalyst	29.66	29.66
Ash Disposal (\$5.00/Ton)	1.68	1.94
Labor	24.43	24.43
Maintenance	21.89	21.89
Capital-Related	394.64	344.61
TOTAL:	592.53	521.33
<u>By-product Credits, \$MM/year</u>		
Propane (\$12.29/Bbl)	26.34	19.86
Butanes (\$14.50/B)	10.84	8.55
Sulfur (\$52.00/Ton)	0.84	0.84
Ammonia (\$200.00/Ton)	7.06	5.02
TOTAL:	45.08	34.27
Net Product Cost, \$MM/year	547.45	487.06
Product Cost, \$/B	41.54	37.66
Crude Oil Equivalent Factor	0.856	0.839
Equivalent Crude Oil Price, \$/B	35.56	31.58

TABLE 3.10.10

CMSL - 10
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 9</u>	<u>Period 18</u>
<u>Contribution to Price, \$/B</u>		
Coal	1.57	1.57
Natural Gas	4.62	3.71
Water	0.47	0.37
Supported Catalyst	0.00	0.00
Dispersed Catalyst- Mo	0.13	0.13
Dispersed Catalyst - Iron	1.79	1.79
Other Catalysts & Chemicals	1.15	0.77
Ash Disposal	0.11	0.13
Labor	1.59	1.58
Maintenance	1.42	1.42
Capital-Related	25.63	22.34
By-product credit	-2.93	-2.22
Equivalent Crude Oil Price, \$/B	35.56	31.58

TABLE 3.10.11

CMSL - 10
COMPARISON OF CASES AT MAXIMUM REACTOR
THROUGHPUT

	<u>Period 9</u>	<u>Period 18</u>
Total Feed to liquefaction, T/D	10,500	13,700
Number of liquefaction trains	4	4
Total Feed, T/D/train	2,625	3,425
Product, B/D	40,120	51,308
Liquefaction Plant Cost, \$MM	593	584
Total Plant Investment, \$MM	2,621	2,779
Net Annual Operating cost, \$MM	542.19	589.51
Product Cost, \$/B	41.14	34.98
Equivalent Crude Oil Price, \$/B	35.14	28.90

VOLUME III

SECTION III

RUN CMSL-11

BLACK THUNDER MINE COAL

MOLYBDENUM (MOLYVAN) ADDITIVE

FeOOH ADDITIVE

NO EXTRUDATE CATALYST

CO-PROCESSING WITH COMMERCIAL

CURBSIDE RECYCLED PLASTIC

VOLUME III

SECTION III - CMSL-11

TABLE OF CONTENTS

**MOLYBDENUM (MOLYVAN) ADDITIVE
FeOOH ADDITIVE
NO EXTRUDATE CATALYST**

**CO-PROCESSING WITH COMMERCIAL
CURBSIDE RECYCLED PLASTIC**

1.0	BACKGROUND	1
2.0	SUMMARY	2
3.0	CONCLUSIONS	3

VOLUME III

SECTION III - CMSL-11

LIST OF TABLES

Table 3.11.1	Feed Analysis, CMSL-11	3
Table 3.11.2	Design Basis Comparison	4
Table 3.11.3	Overall Material Balance	5
Table 3.11.4	Plant Net Hydrogen Balance	6
Table 3.11.5	Thermal Efficiency	7
Table 3.11.6	Utilities Summary	8
Table 3.11.7	Capacities of Process Units and Offsites	9
Table 3.11.8	Liquefaction Plant Investment Details	10
Table 3.11.9	Total Plant Investment Summary	11
Table 3.11.10	Product Cost Calculation	12
Table 3.11.11	Breakdown of Equivalent Crude Oil Price	13
Table 3.11.12	Comparison of Cases at Maximum Reactor Throughput	14

VOLUME III

SECTION III

TECHNICAL ASSESSMENT - CMSL-11

1.0 BACKGROUND

The primary objective of Run 227-89 (CMSL-11) was to investigate bench-scale liquefaction in an all-dispersed-catalyst multi-stage reactor system. The run demonstrated a coal-only operation, as well as co-liquefaction of coal with a plastic mix obtained from a commercial curbside recycling company. The pretreater reactor used in the two previous runs was eliminated and replaced by a preheater coil, but the in-line hydrotreater was retained.

The coal for CMSL-11 was the same subbituminous Wyoming coal used in the two prior CMSL runs. The plastics mixture contained high-density polyethylene (40%), polypropylene (33%) and polystyrene (27%). In coal/plastics operation, the combined plastics content of the total feed was 33%. The feed compositions and the ultimate analyses of the coal plus plastics feed for the various run conditions are shown in *Table 3.11.1*.

Two conditions were assessed in this technical evaluation, one feeding only coal (Period 10) and the other feeding with coal/plastics (Period 16). Reactor operating temperatures and space velocity were the same in both conditions. The dispersed catalyst rates were held constant through the run and were the same as in CMSL-10, namely a molybdenum rate of 100 ppm and an iron catalyst rate of 5,000 ppm.

The operating conditions, yields and process performance are summarized in *Table 3.11.2*. The gas yield in the Period 10 coal-only operation was very high, 6.1 W% higher than that in the similar coal-only operation of Run CMSL-10, Period 18, which used a catalyst pretreater reactor. In the Run CMSL-11, Period 16, coprocessing operation the gas yield was less than half that of the Run CMSL-11, Period 10, operation. The coprocessing operation of Run CMSL-11 had a hydrogen consumption that was 60% of that during the coal-only operation of the run. This difference, 2.5 W% of dry solid feed, was in part because of the higher hydrogen content, by 2.3 W%, of the coprocessing feed.

Overall material balances are shown in *Table 3.11.3* and *Table 3.11.4* presents net hydrogen balances. *Table 3.11.5* shows the thermal efficiency for the cases, while *Table 3.11.6* summarizes the utilities usage for the cases. *Table 3.11.7* shows the capacities of the various process units and off sites.

The liquefaction plant investment details are presented in *Table 3.11.8*. As in CMSL-9, when feeding coal/plastics mixtures, provisions have been made to dissolve plastics in the process solvent separately from coal dissolution.

The total plant investments are given in *Table 3.11.9*. In the coal-only operation, the liquefaction plant savings with the elimination of the dispersed catalyst pretreater are offset by higher costs in other plant sections, notably in the utilities and in the product testing, due to

the high gas yield. Operation with coal/plastics results in a considerably lower total plant investment.

2.0 SUMMARY

The overall economics are summarized in *Table 3.11.10*. The equivalent crude oil price for Period 10, coal-only, operation is \$3.50 per barrel higher than that estimated for the coal-only operation of Run CMSL-10, Period 18, which had virtually the same liquefaction reactor operating conditions, but in which there was a dispersed catalyst pretreater which was eliminated in Run CMSL-11. The difference in costs reflect the considerably higher gas yield during Run CMSL-11 operation, requiring increased hydrogen and gas purification costs. Nominally the difference indicates that the pretreater reactor is economically justified, although its apparent effect of inhibiting light gas formation should be confirmed.

The equivalent crude oil price for the coprocessing operation of Run CMSL-11 was \$9.40 per barrel lower than that of the coal-only operation of the run. This reduction in price is about the same as that estimated for the Run CMSL-9 co-processing operations which used twice as much iron additive. The breakdown of the equivalent crude oil prices is shown in *Table 3.11.1*.

Table 3.11.12 is an economic summary assuming the installation of an interstage separator which would reduce the vapor load per reactor permitting longer reactors of the maximum diameter for increased coal feed per reactor and fewer liquefaction trains. This modification lowered the equivalent crude oil prices by \$1.30 and \$3.90 per barrel, with the price for the coprocessing operation being lowered to \$21.79 per barrel.

3.0 CONCLUSIONS

The elimination of the dispersed catalyst pretreater reactor apparently increased the equivalent crude oil price significantly, but further study is required to verify the apparent inhibition of light gas formation by such a pretreater. Run CMSL-11 confirmed the improved economics for plastics/coal coprocessing operations that was shown in earlier CMSL runs. Run CMSL-11 showed that such an advantage applies when using commercially available recycled plastic mix, as well as for the prepared mixtures used in the previous CMSL coprocessing operations.

TABLE 3.11.1

FEED ANALYSIS, CMSL-11

	<u>Period 10</u>	<u>Period 16</u>
<u>Feed Composition, W %</u>		
Coal	100.00	67.00
HDPE	0.00	13.20
Polypropylene	0.00	10.90
Polystyrene	0.00	8.90
Total	100.00	100.00
<u>Ultimate Analysis, W % Dry Feed</u>		
Carbon	70.12	75.91
Hydrogen	5.11	7.43
Nitrogen	0.99	0.67
Sulfur	0.53	0.35
Oxygen (by difference)	17.50	11.72
Ash (SO ₃ -free)	5.75	3.92
Total	100.00	100.00
H/C Atomic Ratio	0.87	1.17
O/C Atomic Ratio	0.19	0.12
Heating Value, BTU/lb dry feed		
calculated	11,997	12,877

TABLE 3.11.2
CMSL - 11
DESIGN BASIS COMPARISON

	<u>Period 10</u>	<u>Period 16</u>
<u>Operating Conditions</u>		
Pretreater	no	no
Inline hydrotreater	yes	yes
Space Velocity, lb/hr/ft ³	41.9	42.9
Supported Catalyst Rate, lb/Ton feed	0	0
<u>Dispersed catalyst, ppm</u>		
Iron	5,000	5,000
Molybdenum (as Molyvan)	100	100
<u>Recycle Solvent</u>		
Solvent/feed, lb/lb	1.00	1.36
Resid, W%	33.0	32.0
<u>Temperatures, F</u>		
First Stage	842	842
Second Stage	858	858
<u>Projected Process Performance</u>		
Feed Conversion, W% MAF	95.2	95.3
Resid Conversion, W% MAF	89.2	84.1
Denitrogenation, W%	75.7	62.0
<u>Projected Yields, W% Dry Coal</u>		
H ₂ S	0.53	0.36
NH ₃	0.91	0.50
H ₂ O	7.21	9.22
CO _x	6.32	2.77
C ₁ -C ₃	16.99	8.19
C ₄ -390 F	20.27	16.05
390-500 F	11.54	9.59
500-650 F	14.26	13.98
650-850 F	10.38	18.90
850-975 F	2.25	5.13
975 + F	5.62	10.82
Unconverted Feed	4.53	4.49
Ash	5.75	3.92
Total:	106.57	103.92
C4-975 F, W% dry feed	58.71	63.65
, W% MAF	62.29	66.25

TABLE 3.11.3

CMSL - 11
OVERALL MATERIAL BALANCE

	<u>Period 10</u>	<u>Period 16</u>
Coal, TPSD	10,500	7,000
Plastics, TPSD	0	3,500
Total Feed, TPSD	10,500	10,500
Natural Gas, MMSCFD	115	56
<u>Liquid Products, BPSD</u>		
Gasoline	11,527	12,030
Diesel	27,995	29,217
TOTAL:	39,522	41,247
Barrels/Ton total feed	3.76	3.93
<u>By-products</u>		
Propane, BPSD	7,049	2,880
Butane, BPSD	2,173	1,764
Sulfur, TPSD	49	32
Ammonia, TPSD	96	53
Ash to disposal, TPSD	1,184	448

TABLE 3.11.4

**CMSL-11
PLANT NET HYDROGEN BALANCE**

	<u>Period 10</u>	<u>Period 16</u>
<u>Hydrogen Consumption, MMSCFD</u>		
Liquefaction	260	155
Product Upgrading	38	36
TOTAL:	298	191
Hydrogen Consumption, SCF/B	7,529	4,630
<u>Hydrogen Production, MMSCFD</u>		
Partial Oxidation	57	181
Steam Reforming	241	10
TOTAL:	298	191

TABLE 3.11.5

**CMSL - 11
THERMAL EFFICIENCY**

	<u>Period 10</u>	<u>Period 16</u>
<u>Inputs, GBTU/Day</u>		
Coal + Plastics	251.9	309
Natural Gas	104.8	51.2
Total	356.7	360.2
 <u>Outputs, GBTU/Day</u>		
Gasoline	64.4	67.3
Diesel	162.4	169.6
Propane	27.1	11.1
Butane	9.5	7.7
Sulfur	0.4	0.3
Ammonia	1.8	1.0
Total	265.6	257.0
 Thermal Efficiency, %	 74.5	 71.3

TABLE 3.11.6

**CMSL - 11
UTILITIES SUMMARY**

	<u>Period 10</u>	<u>Period 16</u>
Electric Power, MW	201	184
600 Psig Steam, Mlbs/hr	557	239
Cooling Water, Mgpm	217	128
Process Fuel, GBTU/Day	105	51
Raw Water, gpm	6,651	5,168

TABLE 3.11.7

CMSL - 11
CAPACITIES OF PROCESS UNITS AND OFFSITES

			<u>Period 10</u>	<u>Period 16</u>
Area				
No.	Description	Sizing basis, Units		
100	Coal Preparation	TPSD Dry coal	10,500	7,000
150	Plastics Preparation	TPSD Plastics	0	3,500
200	Liquefaction	TPSD Total feed	10,500	10,500
300	Hydrogen Manufacture			
	Partial Oxidation	MMSCFD H ₂	57	181
	Steam Reforming	MMSCFD H ₂	241	10
400	Oxygen Plant	TPSD Oxygen	710	2,262
500	Product Treating			
	Sour Water treating	gpm sour water	1,184	1,194
	Sulfur recovery	TPSD Sulfur	49	32
	Gas plant	lb/hr C ₁ -C ₃	148,698	71,671
600	Upgrading & Solids Sep'n			
	Hydrotreating	BPSD Coal liquids	39,522	41,247
	Catalytic reforming	BPSD 180-350	11,527	12,030
700	Utilities			
	Steam generation	Mlbs/hr	557	239
	Power distribution	MW	201	184
	Cooling water	MGPM	217	128
800	Tankage			
	Coal liquids	BPSD liquids	39,522	41,247
	LPG	BPSD LPG	7,049	2,880
	Waste solids handling	TPSD solids	1,184	448
900	General Off-Sites	TPSD Total Feed	10,500	10,500

TABLE 3.11.8

CMSL - 11
LIQUEFACTION PLANT INVESTMENT DETAILS

	<u>Period 10</u>	<u>Period 16</u>
<u>Major Equipment Costs, \$M</u>		
Pumps	22,407	24,506
Reactors	34,157	29,492
Fired Heaters	13,702	15,120
Exchangers	16,763	16,014
Drums, Hydrotreaters & Towers	27,461	25,188
Compressors	32,615	26,375
HPU	12,889	9,876
TOTAL	159,994	146,571
<u>Plant Investment, \$MM</u>		
Materials & Equipment	289.9	265.6
Labor & Subcontracts	125.4	114.9
Indirects	104.4	95.6
Contingency	0.0	0.0
Total Liquefaction Plant Investment	519.7	476.1

TABLE 3.11.9**CMSL - 11****TOTAL PLANT INVESTMENT SUMMARY**

(Plant Investment in \$MM, 1991 US Gulf Coast basis)

Area	Name	<u>Period 10</u>	<u>Period 16</u>
100	Coal Preparation	200.0	144.6
150	Plastics Preparation	0.0	14.0
200	Liquefaction	519.7	476.1
300	Hydrogen Manufacture	243.5	162.2
400	Oxygen Plant	34.3	77.2
500	Product Treating	366.5	226.5
600	Upgrading & Solids Sep'n	91.9	99.7
700	Utilities	387.5	240.0
800	Tankage	112.4	116.6
900	General Off-Sites	193.8	186.2
	Subtotal	2149.6	1743.1
	Fee, Contingency	429.4	348.2
	Total Plant Investment	2,579	2,091
	\$/BPD of Product	65,255	50,702

Table 3.11.10

CMSL - 11
Product Cost Calculation

	<u>Period 10</u>	<u>Period 16</u>
<u>Operating Costs, \$MM/year</u>		
Coal (\$7.00/Ton)	24.14	16.10
Plastics (0.00/Ton)	0.00	0.00
Natural Gas (\$2.00/MMBTU)	68.85	33.65
Water (\$2.50/Mgal)	7.87	6.11
Catalysts and Chemicals	17.40	4.38
Dispersed Catalyst	29.66	29.66
Ash Disposal (\$5.00/Ton)	1.95	0.74
Labor	24.43	24.43
Maintenance	21.89	21.89
Capital-Related	383.30	316.13
TOTAL:	579.49	453.09
<u>By-product Credits, \$MM/year</u>		
Propane (\$12.29/Bbl)	28.46	11.63
Butanes (\$14.50/B)	10.35	8.40
Sulfur (\$52.00/Ton)	0.84	0.55
Ammonia (\$200.00/Ton)	6.28	3.48
TOTAL:	45.93	24.06
Net Product Cost, \$MM/year	533.56	429.03
Product Cost, \$/B	41.10	31.66
Crude Oil Equivalent Factor	0.854	0.811
Equivalent Crude Oil Price, \$/B	35.10	25.69

TABLE 11.11

CMSL - 11
BREAKDOWN OF EQUIVALENT CRUDE OIL PRICE

	<u>Period 10</u>	<u>Period 16</u>
<u>Contribution to Price, \$/B</u>		
Coal	1.59	0.96
Plastics	0.00	0.00
Natural Gas	4.53	2.02
Water	0.52	0.37
Supported Catalyst	0.00	0.00
Dispersed Catalyst- Mo	0.14	0.12
Dispersed Catalyst - Iron	1.81	1.65
Other Catalysts & Chemicals	1.14	0.26
Ash Disposal	0.13	0.04
Labor	1.61	1.46
Maintenance	1.44	1.31
Capital-Related	25.21	18.93
By-product credit	-3.02	-1.44
Equivalent Crude Oil Price, \$/B	35.10	25.69

TABLE 3.11.12**CMSL - 11****COMPARISON OF CASES AT MAXIMUM REACTOR THROUGHPUT**

	<u>Period 10</u>	<u>Period 16</u>
Total Feed to liquefaction, T/D	11,400	16,200
Number of liquefaction trains	4	4
Total Feed, T/D/train	2,850	4,050
Product, B/D	42,893	63,533
Liquefaction Plant Cost, \$MM	522	619
Total Plant Investment, \$MM	2,702	2,804
Net Annual Operating cost, \$MM	560.99	573.67
Product Cost, \$/B	39.81	27.49
Equivalent Crude Oil Price, \$/B	33.77	21.79