

Stat 3

CS

OCT 11 1996

ENGINEERING DATA TRANSMITTAL

Page 1 of 1
1. EDT 615504

2. To: (Receiving Organization) Distribution		3. From: (Originating Organization) Environmental Projects		4. Related EDT No.: N/A	
5. Proj./Prog./Dept./Div.: W-457, AW Farm Tank Monitoring and Controls System		6. Cog. Engr.: D. T. Lott		7. Purchase Order No.: N/A	
8. Originator Remarks: This document is the Conceptual Design Report for Project W-457, AW Farm Tank Monitoring and Controls System.				9. Equip./Component No.: N/A	
				10. System/Bldg./Facility: 241-AW Tank Farm	
11. Receiver Remarks: THIS IS A BASELINE DOCUMENT				12. Major Assm. Dwg. No.:	
				13. Permit/Permit Application No.: N/A	
				14. Required Response Date: 6/26/96	

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Approval Designator	Reason for Transmittal	Originator Disposition	Receiver Disposition
1	WHC-SD-W457-CDR-001	All	0	Conceptual Design Report for Project W-457, AW Farm Tank Monitoring and Controls System	SQ	1	1	

16. KEY

Approval Designator (F)	Reason for Transmittal (G)	Disposition (H) & (I)
E, S, Q, D or N/A (see WHC-CM-3-5, Sec.12.7)	1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)											
(G)	(H)	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G)	(H)
1	1	Proj.Eng. D. T. Lott	<i>[Signature]</i>	11/1/96	R3-25						
1	1	Proj. Mgr. J. M. Light	<i>[Signature]</i>	11/1/96	R3-25						
1	1	Farm Cog. K. A. White	<i>[Signature]</i>	11/1/96	R3-13						
1	1	QA H. W. Henrikson	<i>[Signature]</i>	11/1/96	R3-28						
1	1	Safety M. N. Islam	<i>[Signature]</i>	6/27/96	R3-03						
1	1	Environ. B. G. Erlanson	<i>[Signature]</i>	11/1/96	W6-20						
1	1	C. C. Scaief	<i>[Signature]</i>	11/1/96	W2-01						

***DESIGN AUTHORITY**

18. Signature of EDT Originator <i>[Signature]</i> Date: 11/1/96		19. Authorized Representative Date for Receiving Organization		20. Cognizant Manager Date <i>[Signature]</i> Date: 11/1/96		21. DOE APPROVAL (if required) Ctrl. No. <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/comments <input type="checkbox"/> Disapproved w/comments	
----------------------------------------------------------------------------	--	---------------------------------------------------------------	--	-----------------------------------------------------------------------	--	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--

Conceptual Design Report for Project W-457, AW Tank Farm Monitoring and Controls System

DT Lott

P.O. Box 1970, Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-87RL10930

EDT/ECN: 615504 UC: 2030
Org Code: 8K220 Charge Code: N1763
B&R Code: EW31300010 Total Pages: 88 *82 KMB 10/10/96*

Key Words: Conceptual Design Report, AW Tank Farm, Monitoring, Controls System


Abstract: The 241-AW Tank Farm, located in the 200 East Area of the Hanford Site, contains six 1.16 Mgal double-shell tanks. The tanks are used primarily for storage of waste from facilities such as PUREX and B Plant. Tanks 102-AW and 106-AW commonly are used for staging waste concentrated by the evaporator.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: WHC/BCS Document Control Services, P.O. Box 1970, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

[Signature]
Release/Approval

10/10/96
Date



Approved for Public Release

CONCEPTUAL DESIGN REPORT

**AW TANK FARM MONITORING AND
CONTROL SYSTEM INSTALLATION**

PROJECT W-457

Prepared for

Westinghouse Hanford Company

June 1996

Subcontract WHC 380393

Prepared by

**ICF Kaiser Hanford Company
Richland, Washington**

W457CDR

CONCEPTUAL DESIGN REPORT

for

**AW TANK FARM MONITORING AND
CONTROL SYSTEM INSTALLATION
PROJECT W-457**

issued by

WESTINGHOUSE HANFORD COMPANY

for the

**U.S. Department of Energy
Richland Operations Office
Richland, Washington**

PREPARED BY: ICF Kaiser Hanford Company

June 14, 1996
Date

WESTINGHOUSE HANFORD COMPANY APPROVALS:

J.P. LMA
Responsible Manager, Projects

7/22/96
Date

[Signature]
Manager, User/Sponsor Organization

8/29/96
Date

[Signature]
Manager, Safety Organization

7/23/96
Date

J.A. Peltier by [Signature]
Manager, Quality Assurance Organization

7/22/96
Date

U.S. DEPARTMENT OF ENERGY APPROVAL:

N/A
U.S. Department of Energy
Richland Operations Office

Date

W457CDR
CONCEPTUAL DESIGN REPORT
FOR
AW TANK FARM MONITORING AND
CONTROL SYSTEM INSTALLATION
PROJECT W-457

Prepared by

ICF Kaiser Hanford Company
Richland, Washington

for

Westinghouse Hanford Company

B.M. [Signature]
Lead Engineer

6/14/96
Date

J.A. Buchanan
Technical Documents

6-13-96
Date

N/A
Safety Engineering

Date

N/A
Environmental Engineering

Date

N/A
Quality Engineering

Date

Tony L. [Signature]
Project Manager

6-14-96
Date

Westinghouse Hanford Company

D.T. [Signature]
Project Manager

6/14/96
Date

*per telecon
w/ R. W.
Matti
10/9/90*

This conceptual design report contains confidential commercial information that shall be used or duplicated only for official Government purposes, and this notice shall be affixed to any reproduction or abstract thereof. Disclosure of the confidential commercial information contained in this report outside the Government shall not be made without the advice of counsel. The restrictions contained in this notice do not apply to any data or information in this report which is not commercial information or to information generally available to the public on an unrestricted basis.

Reference: DOE Order 4700.1

**APPROVED FOR
PUBLIC RELEASE**

TABLE OF CONTENTS

I.	INTRODUCTION	1
II.	SUMMARY	2
III.	JUSTIFICATION	3
IV.	DESCRIPTION OF PROJECT SCOPE	4
	A. IMPROVEMENTS TO LAND (460)	4
	B. BUILDINGS (501)	5
	C. OTHER STRUCTURES (550)	5
	D. UTILITIES (600)	5
	E. SPECIAL EQUIPMENT AND PROCESS SYSTEMS (700)	6
	F. STANDARD EQUIPMENT (710 THROUGH 799)	6
	G. IMPROVEMENTS FOR OTHERS (800)	7
	H. DEMOLITION (810)	7
	I. OTHER PROJECT COSTS (900)	7
	J. DESIGN COMPLIANCE	7
V.	METHODS OF PERFORMANCE	8
	A. CONSTRUCTION WORK BY ONSITE CONTRACTOR (WBS 3.1)	8
	B. WORK BY OPERATING CONTRACTOR (WBS 1.0 and 4.0)	8
VI.	REQUIREMENTS AND ASSESSMENTS	9
	A. SAFEGUARDS AND SECURITY	9
	B. HEALTH AND SAFETY	9
	C. DECONTAMINATION AND DECOMMISSIONING	10
	D. MAINTENANCE AND OPERATION REQUIREMENTS	10
	E. AUTOMATED DATA PROCESSING EQUIPMENT	10
	F. QUALITY ASSURANCE/SAFETY CLASSIFICATION	11
	G. ENVIRONMENTAL COMPLIANCE	12
	H. PERMITS	13
VII.	IDENTIFICATION AND ANALYSIS OF UNCERTAINTIES	13
VIII.	REFERENCES	13

APPENDICES

- Appendix A. Work Breakdown Structure
- Appendix B. Cost Estimate Summary
- Appendix C. Conceptual Project Schedule
- Appendix D. Energy Conservation Report and Analysis
- Appendix E. Preliminary Safety Evaluation
- Appendix F. Economic Analysis and Life Cycle Cost Analysis
- Appendix G. Drawings

ABBREVIATIONS

ALARA	As Low As Reasonably Achievable
CASS	Computer Aided Surveillance System
CDR	Conceptual Design Report
Enraf	
FDC	Functional Design Criteria
FeCN	Fero Cyanide
FM	Fidelity Mutual
GCS	Gas Characterization System
MIT	Multi-functional Instrument Tree
NEC	National Electric Code
SHMS	Standard Hydrogen Monitoring Systems
TMACS	Tank Monitoring and Control System
UL	Underwriters Laboratories
USQ	Unreviewed Safety Question
WBS	Work Breakdown Structure

CONCEPTUAL DESIGN REPORT

AW TANK FARM MONITORING AND CONTROL SYSTEM INSTALLATION

PROJECT W-457

I. INTRODUCTION

The 241-AW Tank Farm, located in the 200-East Area of the Hanford Site, contains six 1.16 Mgal double-shell tanks. The tanks are used primarily for storage of waste from facilities such as PUREX and B Plant. Tanks 102-AW and 106-AW commonly are used for staging waste concentrated by the evaporator.

Evaporator personnel maintain and monitor all the 241-AW tanks on a daily basis. Two tanks within the farm recently have been identified as having potential flammable gas concerns. Tank 101-AW is currently on the Flammable Gas Watch List. Recently, Tank 104-AW was added to the Flammable Gas Watch List USQ. These classifications impose additional operating controls and monitoring of these tanks.

The process for concentrating the supernatant via the evaporator is termed an "evaporator campaign." The campaign usually lasts from one to three months depending on the waste type and level. During campaigns, supernatant is transferred through underground piping to the evaporator feed tank (Tank 241-AW-102) for concentration in the evaporator. After the evaporator treats the waste, the concentrated waste (slurry), is routed to Tank AW-106 for additional liquid removal. During evaporator campaigns and normal daily operations, many safety precautions are taken to ensure tank safety. These safety precautions are defined in tank farm operating procedures and safety documentation. The precautions predominantly involve frequent monitoring of the tank waste temperature, level, gas, and pressure using installed tank waste monitoring equipment.

The tank monitoring and control system (TMACS) was originally designed to monitor the temperature in the 24 ferrocyanide (FeCN) Watch List tanks (ref 2). TMACS provides continuous remote monitoring, alarming, and data storage of waste tank temperatures, levels and gas pressures. Since the original installation, the scope of the monitoring system has been expanded to encompass monitoring various tank farm parameters in all tank farms (200-East and 200-West Areas), including the 241-AW Tank Farm (ref 3).

The cost estimate summary and conceptual project schedule are in Appendices B and C, respectively.

II. SUMMARY

Project W-457, "AW Tank Farm Monitoring and Control System Installation," will provide systems to read and control in tank monitoring equipment remotely. Tank equipment that can be monitored by the tank monitoring and control system (TMACS) are thermocouple trees, multi-functional instrument trees (MITs), hydrogen monitoring equipment, pneumatic pressure gauges, ventilation flow, Enraf level gauges, and more. Project W-457 will install the signal conditioners and ancillary equipment required to convert the analog signal provided by the tank monitoring equipment to a digital signal suitable for interpretation by the central TMACS computer.

TMACS will provide alarm management, data storage, data trending, reporting, event logging, failure status, and graphical presentation using a hierarchy of displays that allow progression from the general to the specific. Installing TMACS will provide obvious benefits in safety and ALARA as well as reducing cost associated with manual monitoring of tank parameters.

This CDR includes information required for TMACS installation in the AW Tank Farm. The design of the AW Tank Farm installation is based on currently installed and proven designs in other tank farms.

The total estimated cost for this fiscal year 1996 General Plant Project is \$910,000. Construction costs of the project are \$740,000; other project costs are \$170,000. This estimate includes a 23% contingency.

III. JUSTIFICATION

During evaporator campaigns and normal daily operations, many safety precautions are taken to ensure waste tank integrity. These precautions predominantly involve frequent monitoring of the tank waste temperature, level, vapor space constituents, and pressure. Monitoring is performed using installed tank waste monitoring equipment.

There are several types of tank monitoring equipment installed in AW Tank Farm: pneumatic pressure gauges, standard hydrogen monitoring systems (SHMS), multi-functional instrument tree (MIT), and thermocouple trees. Additional equipment installed includes a gas characterization system (GCS), standard-D hydrogen monitoring systems on the central exhauster, and Enraf level gages.

All of the listed equipment is read and recorded locally. This requires operators to make rounds to the six tanks within the AW Tank Farm, record readings, and survey out of the tank farm. During normal operations, operators are dispatched once every shift to make rounds and record readings. During evaporator campaigns, operators are dispatched every 2 hours to make rounds and record readings.

Per DOE Order 6430.1A and Code of Federal Regulation (CFR) 10 CFR 436, an economic analysis was performed (Appendix E). The economic analysis compared the do nothing option (continue performing manual readings) versus installing TMACS in AW Tank Farm. Based on present day dollars, this analysis shows that the expense for installing TMACS will be recovered by expense savings in less than 6 years. This is based on the estimated cost for installation, operation and maintenance costs, current billing rate for operators, and

continuation of current mode of operation within the AW Tank Farm and evaporator.

Installation of TMACS will provide real-time status of parameters associated with the AW Tank Farm tanks and also will provide a means of instantaneously identifying failed equipment. Installation of TMACS will reduce tank farm activity by remotely recording waste tank parameters, and will provide ALARA benefits by reducing potential for exposure or contamination.

IV. DESCRIPTION OF PROJECT SCOPE

A. IMPROVEMENTS TO LAND (460)

Excavation will be required for buried electrical power, control, and instrumentation conduit (triple conduit). The excavation will be performed within the AW Tank Farm fence to a maximum depth of approximately 610 mm (24 in.). This will be performed following the procedure WKS 17 in WHC-CM-1-10, "Safety Manual."

Excavation for triple conduit will be made throughout the farm as shown on drawing H-2-820792. All drawings are in Appendix G. The excavation between pull boxes PB-94-5-Δ, PB-94-6-Δ, and PB-94-10-Δ and subsequent triple conduit runs and pull box placement will be provided by project W-451, "Tank Farm Gas Characteristics."

Excavation for electrical power and instrument conduit will be performed at each tank. The excavation will provide power and instrumentation conduit between the nearest pull box and the tank specific TMACS terminal box.

Further excavation for instrumentation conduit will be performed from the tank specific TMACS terminal box to the individual terminal boxes of tank instrumentation. This will be performed for three thermocouple junction

boxes, one Enraf liquid level gauge, and one tank vapor space pressure transducer cabinet [two pressure transmitters] at each tank.

Tank AW-101 will require additional excavation for power and instrumentation conduit required for MIT and hydrogen monitoring (see drawing H-2-820792).

B. BUILDINGS (501)

TMACS equipment will be provided in the existing control facility (241-AW-271) outside the AW Tank Farm north fence. The building will be provided with the electrical power and instrumentation service required for TMACS. Two electrical enclosures housing TMACS equipment will be installed in the building; the modem assembly (modems provided by others) and the communications interface unit (see drawings H-2-820793 and H-2-820801, respectively).

C. OTHER STRUCTURES (550)

The electrical enclosures in the tank farm will be supported by unistrut stands. The stands will be fabricated in the shop and then placed in the farm to maintain ALARA. Details of the support stands are shown in drawing H-2-815300.

D. UTILITIES (600)

Electrical power will be distributed to TMACS terminal boxes through underground wiring. The power wiring will be in a separate conduit than the control and instrumentation wiring.

Instrumentation wiring will be distributed to TMACS terminal boxes through underground wiring in a conduit separate from the power conduit. No control wiring will be provided by this effort. Control conduit is provided for future control expansion.

The electrical system design will conform to the National Electric Code (NEC). All electrical parts will be listed or approved by Underwriters Laboratories (UL), Fidelity Mutual (FM), or another nationally recognized testing laboratory.

Two designated telephone lines will be provided for communication between the AW Tank Farm TMACS and the master TMACS computer. The line will connect the modems located in 241-AW-271 to the TMACS central computer located in the 2750E Building. The telephone company will provide two excess modems.

E. SPECIAL EQUIPMENT AND PROCESS SYSTEMS (700)

The existing TMACS computer system will be programmed to recognize the AW Tank Farm.

The process of obtaining data from the in-tank instrumentation requires multiple electronic signal processors. The analog signal from an instrument is converted to a digital signal that is stored as a measurement in local memory. When a report is requested, the stored data is transmitted serially via an RS-485 signal that is converted to RS-232C which is suitable for transfer and interpretation by the TMACS master computer. The equipment required to do the data obtaining process will be installed at 18 thermocouple trees, 6 Enraf liquid level gauges, 12 tank vapor pressure transducers and 1 standard hydrogen monitor in the AW Tank Farm. The equipment consists of the TMACS enclosures and Acromag I/O processors installed locally at each tank.

F. STANDARD EQUIPMENT (710 THROUGH 799)

All equipment will be standard "off-the-shelf" items. Exceptions may arise with some of the instrumentation signal conversion equipment, but this is not anticipated.

G. IMPROVEMENTS FOR OTHERS (800)

Accommodations for future expansion of monitored points will be provided. These expansion points will provide standardized access for future monitoring equipment.

Conduit runs providing control capability will be at the pull boxes throughout the AW Tank Farm (see drawing H-2-820792). This will allow for future control of pumps, valves, etc. by the master TMACS computer.

Excess electrical capability also will be provided to AW Tank Farms. This will be provided in sufficient capacity to operate miscellaneous hand tools and future controls applications.

A computer terminal will be provided in the 242-A Evaporator Building to be used for in situ monitoring of tank parameters by tank farm personnel.

H. DEMOLITION (810)

The Doric Digitrend remote multiplexers in control facility 241-AW-271 that are tied to CASS will be removed. These units presently are not functional and there are no plans to repair them. However, buried CASS cables will remain.

I. OTHER PROJECT COSTS (900)

Other project costs include design finalization and project management during construction.

J. DESIGN COMPLIANCE

The design and construction of project W-457 will comply with the codes and regulations listed in the project FDC (ref 1).

V. METHODS OF PERFORMANCE

A. CONSTRUCTION WORK BY ONSITE CONTRACTOR (WBS 3.1)

Fabrication of TMACS equipment will be performed by site construction forces. Primarily, this will be fabrication of terminal boxes and stands.

Installation of the TMACS system will be performed by the onsite engineer/construction contractor. This will include excavation and backfill within the AW Tank Farm, installation of conduits and wiring, placement of terminal boxes and instruments, and termination of instrumentation and power.

The design of TMACS will utilize over the counter products to the extent practical. All items will be called out on drawings and procured using purchase requisitions by a purchasing agent. Parts that make up the design will be chosen by the responsible engineer based on its performance and physical attributes, and the requirements of the project.

B. WORK BY OPERATING CONTRACTOR (WBS 1.0 and 4.0)

The operating contractor will provide definitive design and engineering services during construction.

The operating contractor will provide overall project management support during design, procurement, and construction of this project.

The operating contractor will provide support for other project costs associated with TMACS installation.

VI. REQUIREMENTS AND ASSESSMENTS

A. SAFEGUARDS AND SECURITY

Existing safeguards and security measures will not be impacted by this project. No new measures beyond the current practices will be required.

Badging and escort requirements shall be administrated per WHC-CM-4-33, "Security Manual."

B. HEALTH AND SAFETY

Construction contractors will be required to take reasonable precautions for protection of the health and safety of their employees, subcontractors, operating contractor, and DOE personnel. This includes providing continuous access to construction areas by emergency vehicles and personnel, and ensuring that emergency evacuation routes are unobstructed.

The installation of TMACS equipment will take place in the AW Tank Farm. All installation activities will be performed in accordance with the HSRM-1, "Hanford Site Radiological Control Manual," and WHC-SD-WM-HSP-002, "Tank Farm Health and Safety Plan."

Installation will require hand excavation, routing conduit, and electrical connection to existing instrumentation. The fabrication of electrical enclosures and other equipment will be performed in shop to the extent possible for ALARA.

An Unreviewed Safety Question (USQ) screening was performed for the AW Tank Farm TMACS installation. The USQ screening determined that there would be no changes to the facility equipment or facility procedures.

C. DECONTAMINATION AND DECOMMISSIONING

All decontamination and decommissioning shall be performed in accordance with the HSRCM-1.

D. MAINTENANCE AND OPERATION REQUIREMENTS

The TMACS system maintenance requirements are known from previous installations in other tank farms. The maintenance procedures and costs associated with AW Tank Farm are assumed to be the same as those for other tank farms with TMACS. The estimated maintenance costs for the AW Tank Farm TMACS installation are \$8,000 per year.

No special tools are required for TMACS maintenance other than those regularly used by electrical maintenance personnel. The operation and maintenance costs for tank farms will decrease with the installation of TMACS due to the elimination of man-hour intensive readings required by tank farm personnel.

E. AUTOMATED DATA PROCESSING EQUIPMENT

Data processing and telecommunications equipment will be similar or identical to those used in previous TMACS installations (ref 9). The equipment has been selected carefully based on system requirements and has been successfully used in the field.

The system must be able to convert analog signals from existing in-tank instrumentation into a digital signal for computer processing. The instrumentation signals are read periodically and stored at the tank data signal converter. The data is then available, upon request, for bulk downloading to the TMACS master computer. When queued, the data stored at the tank data signal converter is transferred to a modem signal converter that formats the data for transfer to the TMACS master computer. This allows data to be organized in a historical presentation of tank parameters.

The instrumentation and processors also will provide warnings if loss of communication occurs with an instrument and will alarm if a critical tank criteria is out of established parameters. The TMACS computer system will pin-point the anomaly so corrective action can be initiated.

F. QUALITY ASSURANCE/SAFETY CLASSIFICATION

1. Quality Assurance Activities

Project activities for contractors involved in design, procurement, construction, and acceptance will be governed by 10 CFR 830.120, "Quality Assurance." Minimum project quality attributes are included in the project FDC and will be incorporated into the project specific Quality Assurance Program Plan (QAPP). The QAPP will indicate the project critical characteristics, corresponding safety classification assignments, and programmatic controlling documents. The specific technical and quality programmatic requirements, material certifications, qualification and certification of personnel, inspections, examinations and testing, and applicable quality assurance records will be established during definitive design and included in design documents. Specifications will require controls to exclude misrepresented products.

The project includes individual systems or components to an existing facility and the existing facility hazardous classification has not changed.

Independent design verification will be required. Safety significant and nonsafety significant items and services will be procured from commercially available sources unless specific exception is noted during definitive design.

2. Safety Classification

Safety classifications will be identified for those systems, components, and structures important to safety or environmental protection so that appropriate efforts will be placed on design, procurement, construction, testing, operation, maintenance, and modifications.

Safety classification criteria and methodology are defined in WHC Management Requirements and Procedures Manual, WHC-CM-4-46. Safety classifications will be determined through analysis and consequences of failure based on information contained in the project FDC and safety analysis documents. The resulting safety classifications form the basis for the Hanford design and quality assurance requirements applied to the project. Safety significant is the highest level anticipated for any element of the proposed facility.

G. ENVIRONMENTAL COMPLIANCE

All tank farm areas have been granted a cultural resource exemption based on the extensive disturbances that occurred during tank installation. This exemption includes all maintenance and new construction performed within, and extending 150 meters outside, the 18 fenced tank farm areas. All construction for the TMACS installation will be performed inside the AW Tank Farm.

All tank farm areas are covered by a blanket biological review (#95-200-073). This review determined that there would be no adverse impacts to species or habitats of concern due to projects within the 200-East and 200-West tank farm areas.

The AW Tank Farm TMACS installation is presumed to be under a categorical exclusion and NEPA documentation is not required. An

environmental checklist that shows environmental compliance has been completed (ref 11).

H. PERMITS

An excavation permit will be required for conduit runs throughout the AW Tank Farm. The permit will be obtained per procedure 503.1 in WHC-CM-8-7 (ref 12).

VII. IDENTIFICATION AND ANALYSIS OF UNCERTAINTIES

The installation of TMACS has been performed in several other tank farms in the 200-West Area. The design for installation of TMACS in the AW Tank Farm has been completed. The design and equipment used in this installation are similar, if not identical, to that used in other TMACS installations. Therefore, from a technical standpoint, no uncertainties can be identified.

VIII. REFERENCES

1. Functional Design Criteria, "AW Farm Tank Monitoring and Control System Installation," prepared by Westinghouse Hanford Company, Document No. WHC-SD-W457-FDC-001, Rev 0, 1996.
2. U.S. Congress, "Safety Measures for Waste Tanks at Hanford Nuclear Reservation," Section 3137 of National Defense Authorization Act For Fiscal Year 1991, Public Law 101-510, 1990.
3. Supporting Document, "Tank Monitor and Control System Software Configuration Management Plan," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-CSCM-019, Rev 0, 1993a.
4. U.S. Department of Energy Order 6430.1A, "General Design Criteria," 1989.

5. Code of Federal Regulations, 10 CFR 436, "Federal Energy Management and Planning Programs."
6. Manual, "Safety Manual," prepared by Westinghouse Hanford Company, Document No. WHC-CM-1-10, 1995.
7. Manual, "Hanford Site Radiological Control Manual," prepared by Westinghouse Hanford Company, Document No. HSRCM-1, Rev 2, 1994.
8. Supporting Document, "Tank Farm Health and Safety Plan," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-HSP-002, Rev. 2E, 1996.
9. Supporting Document, "TMACS System Description," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-TI-671, Rev. 0, 1995.
10. Manual, "Management Requirements and Procedures Manual," prepared by Westinghouse Hanford Company, Document No. WHC-CM-1-3, 1996.
11. Report, "Environmental Requirements Checklist for AW Farm TMACS Installation," Project W-457, prepared by Westinghouse Hanford Company, Document No. 96-POC-004, 1996.
12. Manual "Site Support Services," prepared by Westinghouse Hanford Company, Document No. WHC-CM-8-7, 1995.
13. National Fire Protection Agency NFPA 70, "National Electrical Code," 1993.
14. Manual, "Quality Assurance Manual," prepared by Westinghouse Hanford Company, Document No. WHC-CM-4-2, 1988.

15. Manual, "Standard Engineering Practices," prepared by Westinghouse Hanford Company, Document No. WHC-CM-6-1, 1993.
16. Manual, Environmental Compliance, prepared by Westinghouse Hanford Company, Document No. WHC-CM-7-5, 1993.
17. Design Criteria Source, "Preparation and Control of Engineering and Fabrication Drawings," ICF Kaiser Hanford Company Architect/Engineer Standard GG-DWG-01.
18. Design Criteria Source, "Design Loads for Facilities," ICF Kaiser Hanford Company Architect/Engineer Standard, GC-LOAD-01.
19. U.S. Department of Energy Order 4700.1, "Project Management System," March 6, 1987.
20. Waste Tank Safety Program EA (DOE/EA-0915).
21. Supporting Document, "Functional Requirements for Ferrocyanide Tank Temperature Monitoring," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-RD-013, Rev 1, 1991a.
22. Supporting Document, "Engineering Work Plan for Ferrocyanide Tank Temperature Monitoring Phase 2 and Phase 3," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-WP-116, Rev 0, 1991c.
23. Supporting Document, "Thermal Analysis of Hoffman Enclosure," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-ER-111, Rev 0, 1991d.

24. Supporting Document, "TMACS Functional Requirements," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-SFR-006, Rev 0, 1992a.
25. Supporting Document, "Tank Farm Instrumentation and Data Acquisition/Management Upgrade Plan," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-WP-132, Rev 2, 1993c.
26. Supporting Document, "TMACS and Box Support Wind/Seismic Analysis," prepared by Westinghouse Hanford Company, Document No. WHC-SD-WM-DR-010, Rev 0, WHC, 1993d.
27. Code of Federal Regulations, 10 CFR 830.120, "Quality Assurance."

APPENDIX A

Work Breakdown Structure

WORK BREAKDOWN STRUCTURE

- 1.0 ENGINEERING
 - 1.1 Definitive Design (Operating Contractor)
 - 1.2 Engineering and Inspection (Operating Contractor)
- 3.0 CONSTRUCTION
 - 3.1 Force Account Construction (Engineer/Constructor Contractor)
- 4.0 PROJECT INTEGRATION/MANAGEMENT (OPERATING CONTRACTOR)

APPENDIX B

Cost Estimate Summary

ICF KAISER HANFORD
 WESTINGHOUSE HANFORD COMPANY
 JOB NO. W-457/E62049
 FILE NO. W457CAA4

**** IEST - INTERACTIVE ESTIMATING ****
 AM TANK FARM MONITORING and CONTROL SYSTEM
 WORKING CONSTRUCTION
 DOE_R01 - PROJECT COST SUMMARY

PAGE 1 OF 7
 DATE 06/06/96 10:51:17
 BY JFR/DEA

COST CODE	DESCRIPTION	ESCALATED TOTAL COST	CONTINGENCY		TOTAL DOLLARS
			%	TOTAL	
000	ENGINEERING	76,000	15	11,000	87,000
050	CONSTRUCTION MANAGEMENT	149,000	21	32,000	181,000
706	ELECTRICAL	529,000	25	132,000	661,000
	(ADJUSTED TO MEET DOE 5100.4)	4,000		5,000	1,000
PROJECT TOTAL		750,000	23	180,000	930,000

B-1

WHC-SD-W457-CDR-001, Rev. 0

TYPE OF ESTIMATE	WORKING CONSTRUCTION	JUNE 6, 1996	REMARKS: THE PREVIOUS ESTIMATE, FILE NO. W457CAA3, HAS BEEN REVISED TO INCORPORATE ESCALATION COSTS.
ARCHITECT ENGINEER	<i>David Anderson</i> ICFKH	<i>Tracy K. Osterman</i>	
OPERATING CONTRACTOR	WHC		

(ROUNDED/ADJUSTED TO THE NEAREST " 1,000 / 10,000 " - PERCENTAGES NOT RECALCULATED TO REFLECT ROUNDING)

ICF KAISER HANFORD
 WESTINGHOUSE HANFORD COMPANY
 JOB NO. W-457/E62049
 FILE NO. W457CAA4

**** IEST - INTERACTIVE ESTIMATING ****
AW TANK FARM MONITORING and CONTROL SYSTEM
WORKING CONSTRUCTION
 DOE_R02 - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 2 OF 7
 DATE 06/06/96 10:51:20
 BY JFR/DEA

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS		
110000	WHC DEFINITIVE DESIGN	49104	0	49104	0.45	221	49325	15	7399	56724
120000	WHC ENGINEERING/INSPECTION	26040	0	26040	0.67	174	26214	15	3932	30147
	SUBTOTAL 12 ENGINEERING/INSPECTION	26040	0	26040	0.67	174	26214	15	3932	30147
	SUBTOTAL 1 ENGINEERING	75144	0	75144	0.53	395	75539	15	11331	86871
310000	GENERAL & TECHNICAL CONDITIONS	28207	0	28207	2.15	606	28813	25	7203	36017
310001	ELECTRICAL INSTALLATION	489653	0	489653	2.15	10528	500181	25	125045	625226
317710	PROJECT MANAGEMENT	66498	0	66498	1.73	1150	67648	25	16912	84561
317720	CF SUPPORT	19539	0	19539	1.73	338	19877	25	4969	24846
317730	QUALITY SUPPORT	8087	0	8087	1.73	140	8227	25	2057	10284
	SUBTOTAL 31 FA CONST-ONSITE E/C	611984	0	611984	2.09	12762	624746	25	156186	780934
	SUBTOTAL 3 CONSTRUCTION	611984	0	611984	2.09	12762	624746	25	156186	780934
400000	WHC PROJECT INTEGRATION	53092	0	53092	1.12	595	53687	15	8053	61740
	SUBTOTAL 4 PROJECT INTEGRATION	53092	0	53092	1.12	595	53687	15	8053	61740
PROJECT TOTAL		740,220	0	740,220	1.86	13,752	753,972	23	175,570	929,545

B-2

WHC-SD-W457-CDR-001, Rev. 0

KAISER ENGINEERS HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-457/E62049
FILE NO. W457CAA4

** TEST - INTERACTIVE ESTIMATING **
AW TANK FARM MONITORING and CONTROL SYSTEM
WORKING CONSTRUCTION
DOE_R03 - ESTIMATE BASIS SHEET

PAGE 3 OF 7
DATE 06/06/96 14:16:44
BY JFR/DEA

1. DOCUMENTS AND DRAWINGS

DOCUMENTS: LOI

DRAWINGS: SEE LOI LIST

2. MATERIAL PRICES

UNIT COSTS REPRESENT CURRENT PRICES FOR SPECIFIED MATERIAL.

3. LABOR RATES

A.) ICF-KH HOURLY RATES ARE BASED ON THE 1996 FISCAL YEAR BUDGET LIQUIDATION RATES AS ISSUED BY KEH FINANCE

4. GENERAL REQUIREMENTS/TECHNICAL SERVICES/OVERHEADS

A.) ONSITE CONSTRUCTION FORCES GENERAL REQUIREMENTS, TECHNICAL SERVICES AND CRAFT OVERHEAD COSTS ARE INCLUDED AS A COMPOSITE PERCENTAGE BASED ON THE ICF-KH ESTIMATING FACTOR,

5. ESCALATION

ESCALATION PERCENTAGES WERE CALCULATED FROM THE AUGUST 1994 UPDATE OF THE ECONOMIC ESCALATION PRICE CHANGE INDICES FOR DOE CONSTRUCTION PROJECTS AS PUBLISHED BY THE "OFFICE OF INFRASTRUCTURE ACQUISITION" FH-50.

6. ROUNDING

U.S. DEPARTMENT OF ENERGY - DOE ORDER 5100.4 PAGE I-32 SUBPARAGRAPH (M). REQUIRES ROUNDING OF ALL GENERAL PLANT PROJECTS (GPP'S) AND LINE ITEM (LI) COST ESTIMATES. REFERENCE: DOE 5100.4, FIGURE I-11, DATED 10-31-84.

7. REMARKS/QUALIFICATIONS

A.) NO MASK WORK ASSUMED
B.) NO CONTAMINATED SOIL WILL BE ENCOUNTERED
C.) CONSTRUCTION PERFORMED BY ICFKH FORCES.
D.) THE ESTIMATE INCLUDES COST PROVIDED BY WHC FOR ENGINEERING, DESIGN, AND MANAGEMENT SUPPORT.

B-3

ICF KAISER HANFORD
 WESTINGHOUSE HANFORD COMPANY
 JOB NO. W-457/E62049
 FILE NO. W457CAA4

** IEST - INTERACTIVE ESTIMATING **
 AW TANK FARM MONITORING and CONTROL SYSTEM
 WORKING CONSTRUCTION
 DOE_R04 - COST CODE ACCOUNT SUMMARY

PAGE 4 OF 7
 DATE 06/06/96 10:51:21
 BY JFR/DEA

COST CODE/WBS	DESCRIPTION	ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
000 ENGINEERING								
110000	WHC DEFINITIVE DESIGN	49104	0	49104	0.45	221	49325	56724
120000	WHC ENGINEERING/INSPECTION	26040	0	26040	0.67	174	26214	30147
	TOTAL 000 ENGINEERING	75144	0	75144	0.53	395	75539	86871
050 CONSTRUCTION MANAGEMENT								
317710	PROJECT MANAGEMENT	66498	0	66498	1.73	1150	67648	84561
317720	CF SUPPORT	19539	0	19539	1.73	338	19877	24846
317730	QUALITY SUPPORT	8087	0	8087	1.73	140	8227	10284
400000	WHC PROJECT INTEGRATION	53092	0	53092	1.12	595	53687	61740
	TOTAL 050 CONSTRUCTION MANAGEMENT	147216	0	147216	1.51	2223	149439	181431
706 ELECTRICAL								
310000	GENERAL & TECHNICAL CONDITIONS	28207	0	28207	2.15	606	28813	36017
310001	ELECTRICAL INSTALLATION	489653	0	489653	2.15	10528	500181	625226
	TOTAL 706 ELECTRICAL	517860	0	517860	2.15	11134	528994	661243

PROJECT TOTAL		740,220	0	740,220	1.86	13,752	753,972	929,545

B-4

ICF KAISER HANFORD
 WESTINGHOUSE HANFORD COMPANY
 JOB NO. W-457/E62049
 FILE NO. W457CAA4

** IEST - INTERACTIVE ESTIMATING **
 AW TANK FARM MONITORING and CONTROL SYSTEM
 WORKING CONSTRUCTION
 DOE_R05 - ESTIMATE SUMMARY BY CSI DIVISION

PAGE 5 OF 7
 DATE 06/06/96 10:51:23
 BY JFR/DEA

CSI DESCRIPTION	ESTIMATE SUBTOTAL	ONSITE INDIRECTS	SUB TOTAL	ESCALATION % TOTAL	SUB TOTAL	CONTINGENCY % TOTAL	TOTAL DOLLARS
ENGINEERING							
00 TECHNICAL SERVICES	75144	0	75144	0.53	395	15	86871
TOTAL ENGINEERING	75,144	0	75,144	0.53	395	15	86,871
CONSTRUCTION							
00 TECHNICAL SERVICES	53092	0	53092	1.12	595	25	61740
01 GENERAL REQUIRMENTS	122331	0	122331	1.83	2234	25	155708
16 ELECTRICAL	489653	0	489653	2.15	10528	25	625226
TOTAL CONSTRUCTION	665,076	0	665,076	2.01	13,357	24	842,674
PROJECT TOTAL							
	740,220	0	740,220	1.86	13,752	23	929,545

B-5

WHC-SD-W457-CDR-001, Rev. 0

ICF KAISER HANFORD
WESTINGHOUSE HANFORD COMPANY
JOB NO. W-457/E62049
FILE NO. W457CAA4

** TEST - INTERACTIVE ESTIMATING **
AW TANK FARM MONITORING and CONTROL SYSTEM
WORKING CONSTRUCTION
DOE_R06 - CONTINGENCY ANALYSIS BASIS SHEET

PAGE 6 OF 7
DATE 06/06/96 10:42:52
BY JFR/DEA

REFERENCE: ESTIMATE BASIS SHEET PAGE 3 OF 7
COST CODE ACCOUNT SUMMARY PAGE 4 OF 7

THE U.S. DEPARTMENT OF ENERGY - RICHLAND ORDER 5700.3 "COST ESTIMATING, ANALYSIS AND STANDARDIZATION" DATED 3-27-85, PROVIDES GUIDELINES FOR ESTIMATE CONTINGENCIES. THE GUIDELINE FOR A 'WORKING CONSTRUCTION' ESTIMATE SHOULD HAVE AN OVERALL RANGE OF 5 TO 15 %.

CONTINGENCY IS EVALUATED AT THE THIRD COST CODE LEVEL AND SUMMARIZED AT THE PRIMARY AND SECONDARY COST CODE LEVEL OF THE DETAILED COST ESTIMATE.

ENGINEERING
000 110000/120000

FIFTEEN PERCENT IS USED BASED ON POSSIBLE
UNFORSEEN FIELD CONDITIONS

AVERAGE ENGINEERING CONTINGENCY 15 %

CONSTRUCTION
050 317710/317720/317730

TWENTY FIVE PERCENT IS USED BASED ON POSSIBLE
UNFORSEEN FIELD CONDITIONS

AVERAGE CONSTRUCTION CONTINGENCY 25 %

OTHER PROJECT COST
050 400000

FIFTEEN PERCENT IS USED BASED ON POSSIBLE
UNFORSEEN FIELD CONDITIONS

AVERAGE CONSTRUCTION CONTINGENCY 15 %

AVERAGE PROJECT CONTINGENCY 23 %

B-6

WHC-SD-W457-CDR-001, Rev. 0

ICF KAISER HANFORD
 WESTINGHOUSE HANFORD COMPANY
 JOB NO. W-457/E62049
 FILE NO. W457CAA4

** IEST - INTERACTIVE ESTIMATING **
 AW TANK FARM MONITORING and CONTROL SYSTEM
 WORKING CONSTRUCTION
 DOE_R07 - OHSITE INDIRECT COSTS BY WBS

PAGE 7 OF 7
 DATE 06/06/96 10:51:24
 BY JFR/DEA

WBS	DESCRIPTION	ESTIMATE SUBTOTAL	CONTRACT %	ADMINISTRATION TOTAL	BID PACK PREP.	OTHER INDIRECTS	TOTAL INDIRECTS
-----		-----	-----	-----	-----	-----	-----
110000	WHC DEFINITIVE DESIGN	49104	0.00	0	0	0	0
120000	WHC ENGINEERING/INSPECTION	26040	0.00	0	0	0	0
310000	GENERAL & TECHNICAL CONDITIONS	28207	0.00	0	0	0	0
310001	ELECTRICAL INSTALLATION	489653	0.00	0	0	0	0
317710	PROJECT MANAGEMENT	66498	0.00	0	0	0	0
317720	CF SUPPORT	19539	0.00	0	0	0	0
317730	QUALITY SUPPORT	8087	0.00	0	0	0	0
400000	WHC PROJECT INTEGRATION	53092	0.00	0	0	0	0
PROJECT TOTAL		740.220		0	0	0	0

B-7

APPENDIX C

Conceptual Project Schedule

APPENDIX D

Energy Conservation Report and Analysis

An Energy Conservation Analysis was not performed for project W-457. The estimated power consumption for the TMACS installation in AW Tank Farm does not warrant such a report.

An Energy Conservation Report is required for new construction and retrofit projects of facilities larger than 10,000 ft², or where energy use is anticipated to be greater than 500 MBtu/yr. A conservative estimate of power consumption for the AW Tank Farm TMACS installation is 5,700 kWh/yr or less than 20 MBtu/yr. Therefore, an Energy Conservation Report is not required.

APPENDIX E

Preliminary Safety Evaluation

A USQ screening is the only preliminary safety evaluation required for project W-457. A USQ screening performed for the AW Tank Farm TMACS installation on June 28, 1994 determined that there would be no changes to the facility equipment or facility procedures.

APPENDIX F

Economic Analysis and Life Cycle Cost Analysis

SUMMARY

An economic analysis was performed to investigate the benefits of installing TMACS versus the current method of manual data gathering. The net result based on best available information was that the installation expense for TMACS would be recovered in less than 6 years.

The analysis takes into account the hourly rate for operations personnel, the time required to make readings (for normal operations and during evaporator campaigns), cost of installation of TMACS, annual operation and maintenance costs, additional electrical consumption, and a discount rate (interest and inflation) based on OMB circular A-94 guidelines. It is assumed that there is no resale value for equipment at the end of the study period.

The hourly rates for operations personnel and the time requirements were provided by WHC. This was equated into an end of year expense for manually monitoring AW Tank Farm. It was assumed that this expense disappears completely with the installation of TMACS. It was also assumed that this includes annual operation and maintenance expenses.

The TMACS installation cost is obtained from the ICF KH project cost estimate dated 2-22-96. This is the cost to complete design and installation of TMACS in the AW Tank Farm. This estimate has been updated subsequent to the release of this document. The total estimated cost did not change significantly, therefore, the economic analysis was not updated.

The TMACS maintenance cost estimates are provided by WHC. This is determined using the total TMACS budget divided by the number of tanks. It is assumed that maintenance costs will remain constant through the span of the study.

Electrical power costs are included for the additional power consumption with the TMACS equipment. The added power consumption is estimated to be a constant 650 Watts. This equates to an annual consumption of approximately 5,700 kWh. The cost of electrical power to facilities on the Hanford site is 4.6 cents per kWh.

The analysis was performed using NIST building life cycle cost software, version 4.3. This program prepares reports for comparison of alternatives using present value. The payoff time was calculated by hand using present value relations and the discount rate and present value determined by the NIST program.

The input data and results are listed on the following pages of this appendix.

AW TANK MONITORING AND CONTROL SYSTEM UPGRADE PAYBACK CALCULATION

CURRENT MANUAL RECORDING COST

NORMAL DAILY OPERATIONS (Twice each 12 hr shift.)

	DAILY MHS	RATE	TOTAL
OPERATOR	8	39	\$312
HPT	1	42	\$42
TOTAL DAILY COST	9		\$354

ANNUAL TOTAL \$95,580

EVAPORATOR CAMPAIGN (Once every 2 hours.)

	DAILY MHS	RATE	TOTAL
OPERATOR	24	39	\$936
HPT	2	42	\$84
TOTAL DAILY COST	26		\$1,020

ANNUAL TOTAL (3 MONTHS OF CAMPAIGN PER YEAR) \$91,800

TOTAL ANNUAL COST **\$187,380**

Annual total based on 3 months of evaporator campaign and 9 months normal operation

PRESENT VALUE **\$2,675,679**

Based on discount rate of 4.9%

TMACS COST

TMACS INSTALLATION COST

PROJECT W-457, DESIGN AND INSTALLATION \$840,140

TMACS MAINTENANCE COST

NUMBER OF TANKS 6

MAINTENANCE COST PER TANK \$1,213

ANNUAL OPERATION AND MAINTENANCE COST \$7,279

Maintenance cost per tank based on TMACS total operating budget and number of tanks

ELECTRICAL POWER COST **\$262**

Based on 4.6 cents per kiloWatt-hour and continuous 650 Watt consumption

PRESENT VALUE **\$947,824**

Based on discount rate of 4.9%

YEARS TO BREAK-EVEN

5.95

Based on discount rate of 4.9%

BLCC Summary for Project: AW TANK FARM TMACS INSTALLATION
Alternative: DO NOTHING

	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$0	\$0
ANNUALLY RECURRING OM&R COSTS	\$2,675,679	\$187,380
LESS: REMAINING VALUE	(\$0)	(\$0)
TOTAL LCC	\$2,675,679	\$187,380

 * N I S T B L C C : D E T A I L E D L C C A N A L Y S I S (v e r . 4 . 3 - 9 6) *

PART I - INITIAL ASSUMPTIONS AND COST DATA

 Project Name: AW TANK FARM TMACS INSTALLATION
 Project Alternative: DO NOTHING
 Run date: 02-07-1996 13:41:27
 Run type: Federal Analysis--Projects Subject to OMB A-94
 Comment:
 Input data file: DONOTHIN.DAT, last modified: 02-06-1996/11:27:30
 LCC output file: DONOTHIN.LCC, created: 02-06-1996/11:27:41
 Base Date of Study: JAN 1996
 Service Date: JAN 1996
 Study period: 25.00 years (JAN 1996 through DEC 2020)
 Discount rate: 4.9% Real (exclusive of general inflation)
 End-of-year discounting convention

INITIAL CAPITAL ASSET COSTS (NOT DISCOUNTED)

	Total Cost
TOTAL INITIAL CAPITAL ASSET COSTS	\$0

PART II - LIFE-CYCLE COST ANALYSIS
 Discount Rate = 4.9% Real (exclusive of general inflation)

PROJECT ALTERNATIVE: DO NOTHING		RUN DATE: 02-07-1996/13:41:27
	PRESENT VALUE (1996 DOLLARS)	ANNUAL VALUE (1996 DOLLARS)
CASH REQUIREMENTS AS OF SERVICE DATE	\$0	\$0
OPERATING, MAINTENANCE & REPAIR COSTS:		
ANNUALLY RECURRING COSTS (NON-ENERGY)	\$2,675,679	\$187,380
SUBTOTAL	\$2,675,679	\$187,380
RESALE VALUE OF ORIG CAPITAL COMPONENTS	\$0	\$0
RESALE VALUE OF CAPITAL REPLACEMENTS	\$0	\$0
TOTAL LIFE-CYCLE PROJECT COST	\$2,675,679	\$187,380

BLCC Summary for Project: AW TANK FARM TMACS INSTALLATION
 Alternative: INSTAL TMACS

	PRESENT VALUE	ANNUAL VALUE
INITIAL COST (AS OF SERVICE DATE)	\$840,140	\$58,836
ANNUALLY RECURRING OM&R COSTS	\$103,940	\$7,279
ENERGY COSTS	\$3,744	\$262
LESS: REMAINING VALUE	(\$0)	(\$0)
TOTAL LCC	\$947,824	\$66,377

 * N I S T B L C C : D E T A I L E D L C C A N A L Y S I S (v e r . 4 . 3 - 9 6) *

PART I - INITIAL ASSUMPTIONS AND COST DATA

Project Name: AW TANK FARM TMACS INSTALLATION
 Project Alternative: INSTAL TMACS
 Run date: 02-07-1996 13:41:56
 Run type: Federal Analysis--Projects Subject to OMB A-94
 Comment:
 Input data file: DOTMACS.DAT, last modified: 02-07-1996/09:06:54
 LCC output file: DOTMACS.LCC, created: 02-07-1996/09:06:57
 Base Date of Study: JAN 1996
 Service Date: JAN 1996
 Study period: 25.00 years (JAN 1996 through DEC 2020)
 Discount rate: 4.9% Real (exclusive of general inflation)
 End-of-year discounting convention

INITIAL CAPITAL ASSET COSTS (NOT DISCOUNTED)

	Total Cost
TOTAL INITIAL CAPITAL ASSET COSTS	\$719,312

ENERGY-RELATED COSTS

Energy Type	Units	Units/Year	Price+ (\$/Unit)	---- Annual Energy	Cost ----- Demand	Total P.V. Cost
Electricity	kWh	5,700	\$0.046	\$262	\$0	\$3,744

Price and annual cost are as of base date (not adjusted for price escalation).

PART II - LIFE-CYCLE COST ANALYSIS
 Discount Rate = 4.9% Real (exclusive of general inflation)

PROJECT ALTERNATIVE: INSTAL TMACS	RUN DATE: 02-07-1996/13:41:56	
	PRESENT VALUE (1996 DOLLARS)	ANNUAL VALUE (1996 DOLLARS)
CASH REQUIREMENTS AS OF SERVICE DATE	\$840,140	\$58,836
OPERATING, MAINTENANCE & REPAIR COSTS: ANNUALLY RECURRING COSTS (NON-ENERGY)	\$103,940	\$7,279
SUBTOTAL	\$103,940	\$7,279
ENERGY COSTS	\$3,744	\$262
RESALE VALUE OF ORIG CAPITAL COMPONENTS	\$0	\$0
RESALE VALUE OF CAPITAL REPLACEMENTS	\$0	\$0
TOTAL LIFE-CYCLE PROJECT COST	\$947,824	\$66,377

PART III - EMISSIONS SUMMARY \a

Region: US Average Source Documentation: SRP

Energy Type	Annual Emissions	Life-cycle Emissions
Electricity:		
CO2 (Kg):	5,525.3	138,134
SO2 (Kg):	41.0	485
NOx (Kg):	16.6	416
Total:		
CO2 (Kg):	5,525.3	138,134
SO2 (Kg):	41.0	485
NOx (Kg):	16.6	416

\a Based on emission factors from file USAVG.EMI

APPENDIX G

Drawings

H-2-820792,	Sh 1	TMACS AU-Tank Farm Instrm. Plan
H-2-820792,	Sh 2	TMACS AU-Tank Farm Instrm. Plan
H-2-820792,	Sh 3	TMACS AU-Tank Farm Connection Schedule
H-2-820792,	Sh 4	TMACS AU-Tank Farm Interconnection Diagram
H-2-820793,	Sh 1	TMAC-TBX-201 Modem Assembly
H-2-820793,	Sh 2	TMAC-TBX-201 Modem Wiring Diagram
H-2-820794,	Sh 1	TMAC-TBX-202 TMACS Assembly
H-2-820794,	Sh 2	TMAC-TBX-202 Wiring Diagram
H-2-820794,	Sh 3	TMAC-TBX-202 Wiring Diagram
H-2-820795,	Sh 1	TMAC-TBX-203 TMACS Assembly
H-2-820795,	Sh 2	TMAC-TBX-203 Wiring Diagram
H-2-820795,	Sh 3	TMAC-TBX-203 Wiring Diagram
H-2-820796,	Sh 1	TMAC-TBX-204 TMACS Assembly
H-2-820796,	Sh 2	TMAC-TBX-204 Wiring Diagram
H-2-820796,	Sh 3	TMAC-TBX-204 Wiring Diagram
H-2-820797,	Sh 1	TMAC-TBX-205 TMACS Assembly
H-2-820797,	Sh 2	TMAC-TBX-205 Wiring Diagram
H-2-820797,	Sh 3	TMAC-TBX-205 Wiring Diagram
H-2-820798,	Sh 1	TMAC-TBX-206 TMACS Assembly
H-2-820798,	Sh 2	TMAC-TBX-206 Wiring Diagram
H-2-820798,	Sh 3	TMAC-TBX-206 Wiring Diagram
H-2-820799,	Sh 1	TMAC-TBX-207 TMACS Assembly
H-2-820799,	Sh 2	TMAC-TBX-207 Wiring Diagram
H-2-820799,	Sh 3	TMAC-TBX-207 Wiring Diagram
H-2-820800,	Sh 1	TMAC-TBX-208 TMACS Assembly
H-2-820800,	Sh 2	TMAC-TBX-208 TMACS Wiring Diagram
H-2-820800,	Sh 3	TMAC-TBX-208 TMACS Wiring Diagram
H-2-820801,	Sh 1	Comm Interface Unit (CIU) Assembly
H-2-820801,	Sh 2	Comm Interface Unit (CIU) Assembly
H-2-820820,	Sh 1	TBX-TMACS-GEN Acromag Assemblies
H-2-820820,	Sh 2	TBX-TMACS-GEN Wiring Diagram
H-2-824669,	Sh 1	Multifunctional Instrument Tree Terminal Box Assy
H-2-824669,	Sh 2	Multifunctional Instrument Tree Term Box Wiring Diag
H-2-815300		TBX-TMACS-GEN Support Installation

QTY	REF. DES	PART/ASH NO.	DESCRIPTION	UNIT
2			INSTALLATION	
2			INSTALLATION	
3		H-2-820793-010	THAC-1BX-201 MODRM ASSEMBLY	
4		H-2-820794-010	THAC-1BX-202 THACS ASSEMBLY	
5		H-2-820795-010	THAC-1BX-203 THACS ASSEMBLY	
6		H-2-820796-010	THAC-1BX-204 THACS ASSEMBLY	
7		H-2-820797-010	THAC-1BX-205 THACS ASSEMBLY	
8		H-2-820798-010	THAC-1BX-206 THACS ASSEMBLY	
9		H-2-820799-010	THAC-1BX-207 THACS ASSEMBLY	
10		H-2-820800-010	THAC-1BX-208 THACS ASSEMBLY	
11		H-2-820801-010	THAC-1BX-209 THACS ASSEMBLY	
12		H-2-820800-010	COMM INTERACE UNIT, ASSEMBLY	
13			SEC NOTE 7	
14				
15				
16			NAMEPLATE, PLASTIC	3
17		H-2-824669-010	MIT TERMINAL BOX ASSEMBLY	1
18		H-2-824669-020	MIT CABLE ASSEMBLY	1
19			SEC NOTE 9 10	
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				

CONNECTION OF STANDARD HYDROGEN MONITORING SYSTEM (SHMS)

PAIR NO.	SIGNAL NAME	SIGNAL FUNCTION	THACS TERMINATION
182-1	3-BLK	VTP-F11-250A (-) TLDV	UB-11 (-)
182-2	2-BLK	VTP-F11-250A (-) TLDV	UB-11 (-)
182-3	3-WHT	VTP-F11-250A (-) TLDV	UB-11 (-)
182-6	2-BLK	VTP-F17-250A (-) D-10X HG	UB-10 (-)
182-7	2-WHT	VTP-F17-250A (-) D-10X HG	UB-10 (-)
182-9	1-BLK	VTP-F17-250A (-) D-1X HG	UB-9 (-)
182-10	1-WHT	VTP-F17-250A (-) D-1X HG	UB-9 (-)
182-20	SHIELD	CABLE SHIELD	NO CONNECTION
182-21	4-BLK	VTP-LT-251A HIGH HYDROGEN (C) PS-1 (-)	D/D-1A TERM 4
182-22	4-WHT	VTP-LT-251A HIGH HYDROGEN (C) PS-1 (-)	D/D-1A TERM 4
182-23	5-WHT	VTP-UT-250A TROUBLE (C) PS-1 (-)	D/D-1A TERM 6

LEGEND

TBR	TEMPERATURE ELEMENT
TE	TEMPERATURE ELEMENT
PH	PULL BOX
THACS	TANK MONITOR AND CONTROL SYSTEM
LIT	LEVEL INDICATING TRANSMITTER (C) (C)
THACS	TANK MONITOR AND CONTROL SYSTEM
WST	WASTE STORAGE TANK
MIT	MULTIFUNCTIONAL INSTRUMENT TREE

RESISTOR (SUFFIX)


USE	EXAMPLES
P	POWER THREE PHASE OR SINGLE PHASE LAMPER 600 VAC USED TO SERVE MOTORS, HEATERS OR TO PROVIDE POWER TO INSTRUMENTATION ETC. OR WIRING USED FOR CONTROL.
C	CONTROL INC CLASS 2 AND 3 CIRCUITS.
I	INSTRUMENTATION MISSE SENSITIVE WIRING, TRANSDUCERS, THERMO-Couples, RTD, ETC.

- GENERAL NOTES (UNLESS OTHERWISE SPECIFIED)
- MARK ALL WIRE RUNS WITH THEIR RESPECTIVE IDENTIFICATION NUMBERS. USE THE FULL NAME ON ALL FIELD IDENTIFICATION LABELS.
 - CONDUIT AND PULL BOX IDENTIFICATION LABELS SHALL HAVE A SUFFIX LETTER (OF, C, I) DESIGNATING ITS INTENDED USAGE. SEE EXAMPLES AND TABLE BELOW.
- EXAMPLES
- P-94-10-P CONDUIT IDENTIFICATION LABEL FOR POWER
 - P-94-10-C CONDUIT IDENTIFICATION LABEL FOR CONTROL
 - P-94-10-I PULL BOX (PB) IDENTIFICATION LABEL FOR POWER
 - I-18 USE RESISTOR SUFFIX (OF, C, I)
 - I-84 SECONDARY NUMBER OF CONDUIT OR PB
 - I-94 LAST TWO DIGITS OF CURRENT YEAR (1994)
 - PH = PREFIX DESIGNATOR FOR PULL BOX

- CONDUIT RUNS ARE SHOWN DISAGGREGATELY, FIELD ROUTE AND SUPPORT AS REQUIRED PER NEC. BURY ALL CONDUIT A MINIMUM OF 24" EXCEPT A MINIMUM OF 6" IS PERMITTED IN AREAS INACCESSIBLE TO VEHICLE TRAFFIC.
- INSTALLATION SHALL CONFORM TO THE 1993 EDITION OF THE NATIONAL ELECTRICAL CODE (NEC).
- ALL ELECTRICAL PARTS SHALL BE LISTED OR APPROVED BY UL, FM, OR ANOTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
- LIQUID TIGHT FLEXIBLE METAL CONDUIT AND APPROVED FITTINGS MAY BE USED IN LENGTHS NOT EXCEEDING THREE FEET WHERE CONDITIONS OF INSTALLATION REQUIRE FLEXIBILITY OF THE CONDUIT RUN.
- FOR I/P 12 PREPARE NAMEPLATE LABEL, P- PER HS-85-0015 TYPE 6 USING I/P 16. ATTACH TO THE FRONT OF THE DOOR WITH SILICONE ADHESIVE. THE TEXT SHALL BE AS SHOWN.

- LINE 1 USING I/P CHARACTERS: THAC-1BX-209
- LINE 2 USING I/P CHARACTERS: CDMA INTERFACE UNIT
- LINE 3 USING I/P CHARACTERS: H-2-820801, H-2-820792
- LINE 4 USING I/P CHARACTERS: H-2-820796, CMT 28
- NOTE I/P 11 ON THE SOURCE FIELD OF THE SUPPORT SYMBOL USED TO MOUNT I/P 11 USING TWO INSTALLED 1000 CHARACTERS 27-1/4" LONG. FIELD LOCATE APPROXIMATELY CENTERED BEHIND I/P 11.
- FOR I/P 17 PREPARE NAMEPLATE LABEL, A- PER HS-85-0015 TYPE 6 USING I/P 16. ATTACH IN THE LOCATION SHOWN ON H-2-824669-010 WITH SILICONE ADHESIVE. THE TEXT SHALL BE AS SHOWN.
- LINE 1 USING I/P CHARACTERS: MIT-1BX-207
- LINE 2 USING I/P CHARACTERS: H-2-824669, H-2-820792
- FOR I/P 17 PREPARE NAMEPLATE LABEL, A- PER HS-85-0015 TYPE 6 USING I/P 16. ATTACH IN THE LOCATION SHOWN ON H-2-824669-010 WITH SILICONE ADHESIVE. THE TEXT SHALL BE AS SHOWN BELOW USING 5/32" HIGH CHARACTERS.

MIT PROBE	AV-101	RIS-234
SV	TC	POS NO
1	201A	12
2	201A	13
3	201A	14
4	201A	15
5	201A	16
6	201A	17
7	201A	18
8	201A	20
9	201A	19
10	201A	21
11	211A	22
12	221A	22




FOR EACH TANK REPLACE THE FOLLOWING

TANK NO	WIRE ENCLOSURE	NARROW RANGE	WIDE RANGE	TO THACS
AV-101	VSTA-PNL-201	VST-PT-201A	VST-PT-201A	THAC-1BX-202
AV-102	VSTA-PNL-202	VST-PT-202A	VST-PT-202A	THAC-1BX-203
AV-104	VSTA-PNL-204	VST-PT-204A	VST-PT-204A	THAC-1BX-205
AV-105	VSTA-PNL-205	VST-PT-205A	VST-PT-205A	THAC-1BX-206
AV-106	VSTA-PNL-206	VST-PT-206A	VST-PT-206A	THAC-1BX-207

DETAIL 1
PARTIAL WIRING DIAG FOR TRANSMITTER ENCLOSURES
SEE H-2-70252

REV	DATE	BY	CHKD	DESCRIPTION
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				

REV	DATE	BY	CHKD	DESCRIPTION
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				



1 INSTALLATION

LOCAL NOTES:

A ON THIS SHEET THE FOLLOWING SYMBOLS REPRESENT: 01-2-70330

--- THICK LINE REPRESENTS THREE SEPARATE PARALLEL CONDUITS


□ THICK LINE BOX REPRESENTS THREE SEPARATE PULL BOXES

△ TRIANGLE REPRESENTS THE SUFFIX LETTER FOR THREE SEPARATE LABELS FOR CONDUITS OR PULL BOXES. THE SUFFIX LETTERS ARE P, C, OR I.

EXAMPLE: P-94-18-△ REPRESENTS THE FOLLOWING:
 P-94-18-P CONDUIT IDENTIFICATION LABEL FOR "POWER"
 P-94-18-C CONDUIT IDENTIFICATION LABEL FOR "CONTROL"
 P-94-18-I CONDUIT IDENTIFICATION LABEL FOR "INSTRUMENTATION"
 SEE GENERAL NOTE 1 FOR FURTHER EXPLANATION.

FOR GENERAL NOTES AND PARTS LIST SEE SH 1

DRAWING TRACEABILITY LIST		REFERENCES		DESCRIPTION		REVISIONS		U.S. DEPARTMENT OF ENERGY Ronald Operations Office Washington, Missouri Company TMACS AW-TANK FARM INSTM. PLAN	
DATE	TITLE	REF NUMBER	TITLE	NO	DESCRIPTION	BY	CHK	DATE	REV NO F 241-AW 5901 H-2-820792 0 DATE MADE 1/16/82



FOR GENERAL NOTES AND PARTS LIST SEE SH 1

NOTE:
1. COMMUNICATIONS CABLE
BLU-WHT = D
WHT-BLU = B
DRN-WHT = T
WHT-DRN = T
G-GRN = 1
G-GRN COMMUNICATION

U.S. DEPARTMENT OF ENERGY
Contract No. DE-AC05-80OR21400
Sandia National Laboratories
Livermore, California 94550


TMACS AV-TANK FARM
INTERCONNECTION DIAGRAM

DATE: 11/2/80
DRAWN BY: J. WHITE
CHECKED BY: J. WHITE
APPROVED BY: J. WHITE

FIG. NO. 1
REV. 0
H-2-820792

NO.	REV.	DATE	BY	CHKD.	DESCRIPTION
1	0	11/2/80	J. WHITE	J. WHITE	ISSUED FOR CONSTRUCTION

PROJECT: AV-TANK FARM
DRAWING: INTERCONNECTION DIAGRAM
SCALE: AS SHOWN
SHEET NO. 1 OF 1





LABEL A
TMAC-CORV-201A
RS232C TO RS485
AV FARM

7 NAMEPLATE SCHED
SEE NOTE 1 AND 7


PARTS/MATERIAL LIST					
QTY	REF. DES.	PART/DASH NO.	NOMENCLATURE/DESCRIPTION	MATERIAL/REF.	SHR
1		-010	ASSEMBLY		1
2		LDS-140	MODEM	GANDOLF	2
1		A-242016LP	ENCLOSURE, 24"x20"x16"	HOFFMAN	3
1		A-24P20AL	PANEL, 24"x16"	HOFFMAN	4
1		45CC-TTM-1	SIG. CONV. - (RS232C TO RS485)	ACROMAG	5
2			NAMEPLATE, PLASTIC	HS-B5-0015	6
AR			WIRE, 16 AVG. GRN. STRANDED	TFN COPPER	7
2	P1	DB-19604-432	CONNECTOR, MALE "D" 25 PIN	CINCH	9
2		DB-51226-1A	BACKSHELL, (FOR 1/N 9)	CINCH	10
2	RL R2	RC20G121J	RESISTOR, 120 OHM 1/2W. 5%	MIL-R-11	11
2		TBLT2	TERMINAL BLOCK, 8 TERM.	CINCH	12
5		142J-2	JUMPER (FOR 1/N 12)	CINCH	13
1			POWER STRIP, 6 OUTLETS, 120V AC, 15A WITH MASTER SV. AND CIRCUIT BREAKER		14
AR		9842	CABLE, 18 AVG. 1 PAIR, TWISTED SHLD. PAIR, STRANDED	BELDEN COPPER	15
AR		(89760)	CABLE, 24 AVG. 2 PAIR, TWISTED SHLD. PAIR, STRANDED (RED, BLK)	BELDEN COPPER	16
2			ANGLE, 1"x1"x1/4"	6061-T6 AL	17
1			PLATE, 14"x19-1/2"x1/8"	6061-T6 AL	18
1			COVER, 3"x6"x1/8"	PLEXIGLASS	19
2		HS-B-142	MARKER STRIP (FOR 1/N 12)	TRW	20
6		7220	SPACER, 1/4" HEX MALE/FEMALE 8-32 UNF. THREAD, 3/8" LONG	KEYSTONE	21
2		1471 B	SPACER, 1/4" HEX FEMALE 8-32 UNF. THREAD, 3/8" LONG	KEYSTONE	22
1		VAT-5011	MARKER, VINYL, 1/2" X 2 1/4"	T & B	23
10			SCREW, 8-32, 5/8" LONG	CS	24
8			SCREW, 8-32, 3/8" LONG	CS	25
18			WASHER, LOCK, NO. 8	CS	26
18			NUT, HEX, 8-32 UNF	CS	27
AR			CLAMP, CABLE		28
					29
					30

1 ASSEMBLY
HINGED COVER REMOVED



- GENERAL NOTES (UNLESS OTHERWISE NOTED)
- LABEL ITEM NO. 1 PER HS-B5-0015 TYPE & USING (1/N 7). TEXT SHALL CONSIST OF THE FOLLOWING:
 LINE 1 USING 1/2" CHARACTERS: FIRST LINE OF DWG. TITLE
 LINE 2 USING 1/4" CHARACTERS: "TMACS MODEM 241-AW-271"
 LINE 3 USING 1/4" CHARACTERS: DRAWING NO. PART/DASH NO.
 LINE 4 USING 1/4" CHARACTERS: "CDS-DP-206 OCT 82"
 ATTACH TO FRONT OF THE DOOR USING SILICONE ADHESIVE.
 - ELECTRICAL INSTALLATION SHALL CONFORM TO THE 1993 EDITION OF THE NATIONAL ELECTRICAL CODE.
 - ALL ELECTRICAL PARTS SHALL BE LISTED BY UL, FM OR ANOTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
 - FOR ITEM 6 SEE VENDOR INFORMATION (V1), NUMBER 22138.
 - CABLE SHIELDS ARE GROUNDED AT ONE END ONLY.
 - FIELD TO TEMPLATE MOUNTING HOLES FROM COMPONENTS AND DRILL AS REQ'D.
 - LABEL PER HS-B5-0015 TYPE, 6 WITH INFORMATION AS SHOWN USING 3/32" HIGH CHARACTERS; ATTACH USING SILICONE ADHESIVE.
 - MODEM (1/N 2) SUPPLIED BY TELEPHONE COMPANY.
 - MOUNT SHELF (1/N 18) LEAVING ROOM FOR CABLES AT REAR. POWER CORDS TO POWER STRIP (1/N 14) NOT SHOWN.
 - DIMENSIONS ARE IN INCHES:
 TOLERANCES: X = .01
 XX = .003

DESIGNER: BL. HUBBY	DATE: 1-95	U.S. DEPARTMENT OF ENERGY Advanced Operations Office Westinghouse Hanford Company TMAC-TBX-201 MODEM ASSEMBLY
ENGINEER: FAIRCHILD	DATE: 4-95	
DESIGNED BY: R. ROMINE	DATE: 4-95	
CHECKED BY: K.A. WHITE		
DWG NO. H-2-70230	TITLE: ELEC. INSTN. PLANS	REV. NO. 1 DATE 1/2/95 BY: J. W. HUBBY FOR: J. W. HUBBY CHECK: J. W. HUBBY APPROVE: J. W. HUBBY
DWG NO. H-2-81778	TITLE: TMACS DRAWING INDEX	
DWG NO. H-2-81778	TITLE: TMACS DRAWING INDEX	REV. NO. 2 DATE 1/2/95 BY: J. W. HUBBY FOR: J. W. HUBBY CHECK: J. W. HUBBY APPROVE: J. W. HUBBY
REF. NUMBER	TITLE	REV. NO. 3 DATE 1/2/95 BY: J. W. HUBBY FOR: J. W. HUBBY CHECK: J. W. HUBBY APPROVE: J. W. HUBBY
REFERENCES	TITLE	REV. NO. 4 DATE 1/2/95 BY: J. W. HUBBY FOR: J. W. HUBBY CHECK: J. W. HUBBY APPROVE: J. W. HUBBY
DRAWING TRACEABILITY LIST		REV. NO. 5 DATE 1/2/95 BY: J. W. HUBBY FOR: J. W. HUBBY CHECK: J. W. HUBBY APPROVE: J. W. HUBBY
NEXT USED ON: H-2-82072		REV. NO. 6 DATE 1/2/95 BY: J. W. HUBBY FOR: J. W. HUBBY CHECK: J. W. HUBBY APPROVE: J. W. HUBBY
CADD FILE: B20723A		REV. NO. 7 DATE 1/2/95 BY: J. W. HUBBY FOR: J. W. HUBBY CHECK: J. W. HUBBY APPROVE: J. W. HUBBY
CADD CODE: DWS-CACDR-20155		REV. NO. 8 DATE 1/2/95 BY: J. W. HUBBY FOR: J. W. HUBBY CHECK: J. W. HUBBY APPROVE: J. W. HUBBY



FOR PARTS LIST AND GENERAL NOTES SEE SHT 1

U.S. DEPARTMENT OF ENERGY
GENERAL INVESTIGATIVE DIVISION
WASHINGTON, D.C. 20545

FORM NO. 604 (REV. 11-82)
FBI

DATE: 11-2-82
BY: [Signature]
TITLE: T1-2-82079310
PROJECT: [Blank]
DRAWING NO.: [Blank]

NO.	DESCRIPTION	QTY	UNIT	REV.	DATE	BY	CHKD.	APPR.
1	RESISTORS	3	PCB	1				
2	WIRE	1	PCB	1				
3	COUPLER	1	PCB	1				
4	REFERENCE							
5	NET USED OR							
6	DRAWING TRACED/VERIFY US							
7								
8								





CHART A

MODULE LOCATOR			
SLOT NO.	UNIT A 1/N	UNIT B 1/N	DUPLICATE 1/N
0	N/A	N/A	26
1	6	6	-
2	6	6	-
3	6	6	-
4	6	6	-
5	6	6	-
6	6	6	-
7	6	6	-
8	6	6	-
9	6	6	-
10	6	6	-
11	6	6	-
12	6	7	-
13	6	7	-
14	6	-	-
15	6	-	-
16	6	7	N/A

PARTS/MATERIAL LIST

QTY	REV	REF. DES.	PART/DASH NO.	NOMENCLATURE/DESCRIPTION	UNIT	REF.	QTY
1			-010	ASSEMBLY			1
1			H-2-820920-020	ASSEMBLY, (2 ACROMAG)			2
1							3
1							4
27			4M00-210	MODULE, TC INPUT	ACROMAG		5
3			4M00-240	MODULE, DC CURRENT INPUT	ACROMAG		6
2	JL, JR		RSJ-E-R	JACK, PANEL, TC TYPE E	OMEGA		8
1	SI		DSV3-20-PG	SWITCH, SELECTOR, 20 POS.	OMEGA		10
1	SP		DSV3-16-PG	SWITCH, SELECTOR, 16 POS.	OMEGA		11
1			VLRD-1	DUPLEX COVER, W/SPRING DOOR	CROUSE-HINDS		13
							14
							15
							16
							17
							18
AR			(81760)	CABLE, 18 AWG, 1 TWISTED SHLD PAIR, STRANDED (GRN AND BLK)	ORIELBEND COPPER		19
AR				WIRE, 20 AWG, SOLID, BARE	COPPER		20
AR			(5710/2001)	WIRE, TC TYPE EX	(ALPHA)		21
							22
							23
							24
							25
1			DA75	AC OUTPUT MODULE	(ROTTER & BRUNFIELD OPTO 20VACROMAG)		26
							27
							28
							29
							30
AR			(A8285-A-C)	CABLE TIE MOUNT	(PANDUIT)		31
AR			(PLT15-C)	TIE, CABLE	(PANDUIT)		32
11				NAMEPLATE, PLASTIC	HS-B5-0015		33
							34
							35



1 ASSEMBLY
HINGED COVER REMOVED

LABEL E		LABEL F	
AV-101	RIS-206	AV-101	RIS-206
SW	TC	SW	TC
POS	NO	POS	NO
1	VST-TE-236A	1	VST-TE-246A
2	237A	12	247A
3	238A	13	248A
4	239A	14	249A
5	240A	15	250A
6	241A	16	251A
7	242A	17	252A
8	243A	18	253A
9	244A	19	-
10	245A	20	-

LABEL G	
TC	TYPE E

LABEL J	
AV-101	RIS-258
SW	TC
POS	NO
1	254A
2	255A

LABEL K	
AV-101	RIS-269
SW	TC
POS	NO
3	263A
4	264A
5	265A
6	266A
7	267A
8	268A
9	269A
10	-

LABEL A	
UNIT A	UNIT B

LABEL B	
TMAC-F-202	

LABEL C	
TMAC-RTU-200A	REMOTE TERMINAL UNIT A
AV TANK FARM	

LABEL D	
TMAC-RTU-200B	REMOTE TERMINAL UNIT B
AV TANK FARM	

1-1.5 MAX ONLY
LABEL E THRU K ONLY


33 NAMEPLATE SCHED
SEE NOTE 1 AND 8

GENERAL NOTES (UNLESS OTHERWISE NOTED)

- LABEL ITEM NO. 1 PER HS-B5-0015 TYPE 6, USING 41/N 333. TEXT SHALL CONSIST OF THE FOLLOWING:
 LINE 1 USING 1/2" CHARACTERS: FIRST LINE OF DWG TITLE
 LINE 2 USING 1/4" CHARACTERS: "TMACS 1/0 TERMINATION"
 LINE 3 USING 1/4" CHARACTERS: DRAWING NO. PART/DASH NO.
 LINE 4 USING 1/4" CHARACTERS: "EDS-DP-206 CKT 22"
 ATTACH TO FRONT OF THE DOOR USING SILICONE ADHESIVE.
- WIRING IS DIAGRAMMATICALLY SHOWN, ROUTE AND SUPPORT AS REQUIRED.
- ALL ELECTRICAL PARTS SHALL BE LISTED BY UL, FM, OR ANOTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
- USE ITEM NO. 20 FOR LUMPER.
- FOR ACROMAG PARTS SEE VENDOR INFORMATION (V.I.) NUMBER 22138.
- CABLE SHIELDS ARE GROUNDED AT ONE END ONLY.
- FIELD TO TEMPLATE MOUNTING HOLES FROM ITEMS TO BE MOUNTED AS REQ'D.
- LABEL PER HS-B5-0015 TYPE 6 WITH INFORMATION AS SHOWN USING 5/32" HIGH CHARACTERS, ATTACH USING SILICONE ADHESIVE.
- CABLE, THERMOCOUPLE EXTENSION, SINGLE PAIR, 20 AWG SOLID CONDUCTOR PER ANSIC MC 961-1973, 300 VOLT, 90 DEGREE C, ANSI COLOR CODED PVC INSULATION AND JACKET.
- BREAK ALL SHARP EDGES AND REMOVE ALL BURRS.
- DIMENSIONS ARE INCHES.
 TOLERANCES: X = ±.01
 XXXX = ±0.010
 DEGREES: ±1°





BY: BL MURRY	7-94	U.S. DEPARTMENT OF ENERGY Nuclear Operations Office Washington, D.C. 20545
CHKD: FRISCHL, B	4-95	
APP: JAMES, R	4-95	
DES: K. WHITE		
TMAC-TBX-202		
TMACS ASSEMBLY		
DWG NO: H-2-820940	REV: F 241-AV 5901	REV: H-2-820940
DRAWING TRACEABILITY LIST		REV: 1/2 161968

DWG NO.	TITLE	REV.	DATE	BY	CHKD.	APP.
H-2-81778	TMACS DRAWING INDEX					
H-2-81761	BLOCK DIAGRAM					
	REFERENCES					
	REF NUMBER	TITLE				
	REF NUMBER	TITLE				



FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

U.S. DEPARTMENT OF ENERGY National Operations Office Washington, D.C. 20545	FORM NO. 104-101 REV. 10-1988
PROJECT NO. 241-AV TASK NO. 5903 SUB-TASK NO. H-2-820794.0	REV. 2
PROJECT TITLE TASK TITLE SUB-TASK TITLE	REV. 2
PROJECT NO. 241-AV TASK NO. 5903 SUB-TASK NO. H-2-820794.0	REV. 2
PROJECT TITLE TASK TITLE SUB-TASK TITLE	REV. 2
PROJECT NO. 241-AV TASK NO. 5903 SUB-TASK NO. H-2-820794.0	REV. 2
PROJECT TITLE TASK TITLE SUB-TASK TITLE	REV. 2







DRAWING TRACKABILITY LIST		REVISED		REVISIONS		DATE		BY		CHECKED		DATE		BY	
NO.	DESCRIPTION	NO.	DESCRIPTION	NO.	DESCRIPTION	NO.	DESCRIPTION	NO.	DESCRIPTION	NO.	DESCRIPTION	NO.	DESCRIPTION	NO.	DESCRIPTION
1	ISSUED FOR CONSTRUCTION														
2	REVISIONS														
3	REVISIONS														
4	REVISIONS														
5	REVISIONS														
6	REVISIONS														
7	REVISIONS														
8	REVISIONS														
9	REVISIONS														
10	REVISIONS														

FOR GENERAL NOTES AND PARTS LIST SEE SHIT 1

QTY	REF.	DES.	PART/DASH NO.	DESCRIPTION	UNIT
1	-010	ASSEMBLY		ASSEMBLY	
2	1	ASSEMBLY	H-2-820795-020	ASSEMBLY, (2) ACRWAG	
3	2				
4	1				
5	1				
6	2		4400-210	MODULE, TC INPUT	
7	2		4400-210	MODULE, DC CURRENT INPUT	
8					
9	2	JL, 2P	RSJ-E-R	JACK, PANEL, TC TYPE E	
10					
11	1	S1	DSV3-20-PS	SWITCH SELECTOR, 20 POS.	
12					
13	1	S2	DSV3-16-PS	SWITCH SELECTOR, 16 POS.	
14					
15	1		VL8B-1	BUCK EX COVER, V/SPRING DOOR	
16					
17	14				
18	14				
19	AR	(887650)		CABLE, 18 AWG, 171STL STD (RELDCN)	
20	AR			PAIR, STRANDED GED BULKY COPPER	
21	AR			WIRE, 20 AWG, SOLID, BARE	
22	AR			WIRE, TC TYPE EX (CALPHA)	
23					
24					
25	1			DCMS	
26					
27					
28					
29					
30	AR			CABLE TIE MOUNT (GRADUIT)	
31	AR			TIE, CABLE (GRADUIT)	
32	AR			NAMEPLATE, PLASTIC	
33					
34					
35					

CHART A


SLOT NO.	UNIT A	UNIT B	UNIT C	UNIT D	UNIT E	UNIT F	UNIT G	UNIT H	UNIT I	UNIT J	UNIT K
1											
2											
3											
4											
5											
6											
7											
8											
9											
10											
11											
12											
13											
14											
15											
16											
17											
18											
19											
20											
21											
22											
23											
24											
25											
26											
27											
28											
29											
30											
31											
32											
33											
34											
35											




- GENERAL NOTES (UNLESS OTHERWISE NOTED)
- LABEL ITEM NO. 1 PER HS-85-0015 TYPE 6, USING 1/16 IN. 3X1 TEXT SHALL CONSIST OF THE FOLLOWING:
 LINE 1 USING 1/2" CHARACTERS; FIRST LINE OF DWG TITLE
 LINE 2 USING 1/4" CHARACTERS; TRIMMS I/O TERMINATION
 LINE 3 USING 1/4" CHARACTERS; DRAWING NO. PART/DASH NO.
 LINE 4 USING 1/4" CHARACTERS; DRAWING NO. PART/DASH NO. CONT 228
 - ATTACH TO FRONT OF THE DOOR USING SILICONE ADHESIVE.
 ALL ELECTRICAL PARTS SHALL BE LISTED BY U.L. OR OTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
 - USE ITEM NO. 20 FOR JUMBERS.
 - FOR ACROWAG PARTS SEE VENDOR INFORMATION CIVIL NUMBER 22198.
 - CABLE SHIELDS ARE GROUNDING AT ONE END ONLY.
 - FIELD TO TEMPLATE MOUNTING HOLES FROM ITEMS TO BE MOUNTED AS REQD.
 - LABEL PER HS-85-0015 TYPE 6 WITH INFORMATION AS SHOWN USING 5/32" HIGH CHARACTERS. ATTACH USING SILICONE ADHESIVE.
 - CABLE, THE ENCLOSURE SINGLE PAIR, 90 DEG BEND C. MUST BE SOLID CONDUCTOR PER ANSI MC 961-1975, 300 VOLT, 90 DEG BEND C. MUST BE SOLID CONDUCTOR AND JACKET.
 - BREAK ALL SHARP EDGES AND REMOVE ALL BURRS.
 - DIMENSIONS ARE IN INCHES.
 TOLERANCES: X = .010
 XXXX = .0010
 DEGREES: 30'

REV	DATE	BY	CHKD	DESCRIPTION
1	7-94	BL MERRY		
2	4-95	FRANCOIS		
3	4-95	FRANCOIS		
4	4-95	FRANCOIS		
5	4-95	FRANCOIS		
6	4-95	FRANCOIS		
7	4-95	FRANCOIS		
8	4-95	FRANCOIS		
9	4-95	FRANCOIS		
10	4-95	FRANCOIS		
11	4-95	FRANCOIS		
12	4-95	FRANCOIS		
13	4-95	FRANCOIS		
14	4-95	FRANCOIS		
15	4-95	FRANCOIS		
16	4-95	FRANCOIS		
17	4-95	FRANCOIS		
18	4-95	FRANCOIS		
19	4-95	FRANCOIS		
20	4-95	FRANCOIS		
21	4-95	FRANCOIS		
22	4-95	FRANCOIS		
23	4-95	FRANCOIS		
24	4-95	FRANCOIS		
25	4-95	FRANCOIS		
26	4-95	FRANCOIS		
27	4-95	FRANCOIS		
28	4-95	FRANCOIS		
29	4-95	FRANCOIS		
30	4-95	FRANCOIS		
31	4-95	FRANCOIS		
32	4-95	FRANCOIS		
33	4-95	FRANCOIS		

FOR GENERAL NOTES AND PARTS LIST SEE SHT 1



CONNECT RED TC WIRE (-) TO INNER RING OF TERMINALS.



SEE H-2-820795 FOR WIRE DESTINATION.

ONB VIA JAMES AND T8 HTG SCREW


DATE	BY	REVISION
7-29	W. H. MURPHY	1
4-26	W. H. MURPHY	2
4-26	W. H. MURPHY	3
4-26	W. H. MURPHY	4
4-26	W. H. MURPHY	5
4-26	W. H. MURPHY	6
4-26	W. H. MURPHY	7
4-26	W. H. MURPHY	8
4-26	W. H. MURPHY	9
4-26	W. H. MURPHY	10
4-26	W. H. MURPHY	11
4-26	W. H. MURPHY	12
4-26	W. H. MURPHY	13
4-26	W. H. MURPHY	14
4-26	W. H. MURPHY	15
4-26	W. H. MURPHY	16
4-26	W. H. MURPHY	17
4-26	W. H. MURPHY	18
4-26	W. H. MURPHY	19
4-26	W. H. MURPHY	20
4-26	W. H. MURPHY	21
4-26	W. H. MURPHY	22
4-26	W. H. MURPHY	23
4-26	W. H. MURPHY	24
4-26	W. H. MURPHY	25
4-26	W. H. MURPHY	26
4-26	W. H. MURPHY	27
4-26	W. H. MURPHY	28
4-26	W. H. MURPHY	29
4-26	W. H. MURPHY	30
4-26	W. H. MURPHY	31
4-26	W. H. MURPHY	32

U.S. GOVERNMENT OF ENERGY
Nuclear Energy Research Center
Washington, D.C. 20545



TMAC-TBX-203
WIRING DIAGRAM

FORM 500
1-2-820795

TERMINALS 1 THRU 10 RESERVED FOR
3-PAIR CABLES FROM 10-3 LEVEL CABLES



FROM
SHEET 2



FROM S1
SHEET 2

FROM TB 5
SHEET 2

FROM SA 5, TB 5
SHEET 2

FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

FORM NO.	7-54	REV.	1
TITLE	WIRING DIAGRAM		
PROJECT	THAC-TBX-203		
DATE	24-AV-5903	BY	H-2-82079510
DESIGNED BY	L. J. GARDNER		
CHECKED BY	L. J. GARDNER		
APPROVED BY	L. J. GARDNER		
U.S. DEPARTMENT OF ENERGY	Washington, D.C. 20545		

REV.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		



PARTS/MATERIAL LIST

QTY REQ	REF. DES.	PART/DASH NO.	DESCRIPTION	UNIT	ASSEMBLY
1			ASSEMBLY		
1	H-2-8080-003		ASSEMBLY, (2 ACROMAG)		
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					

GENERAL NOTES (UNLESS OTHERWISE NOTED)
 1. LABEL ITEM NO. 1 PER HS-B5-0015 TYPE 6, USING Q/IN 353. TEST SHALL CONSIST OF THE FOLLOWING:
 LINE 1 USING 1/4" CHARACTERS: FIRST LINE OF ENG TITLE
 LINE 2 USING 1/4" CHARACTERS: THICKS 1/2" TERMINATION
 LINE 3 USING 1/4" CHARACTERS: Q/IN 353, PART/DASH NO.
 LINE 4 USING 1/4" CHARACTERS: ENG-200-200, CDR
 ATTACH TO FRONT OF THE DOOR USING SILICONE ADHESIVE.
 2. WIRING IS DIAGRAMMATICALLY SHOWN, ROUTE AND SUPPORT AS REQUIRED.
 3. ALL ELECTRICAL PARTS SHALL BE LISTED BY U.L. FN. OR ANOTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
 4. USE ITEM NO. 20 FOR JAMPER.
 5. FOR ACROMAG PHOTIS SEE VENDOR INFORMATION Q/IN, NUMBER 22138.
 6. CABLE SHIELDS ARE GROUNDED AT ONE END ONLY.
 7. FIELD TO TEMPLATE MOUNTING HOLES FROM ITEMS TO BE MOUNTED AS REQ'D.
 8. LABEL PER HS-B5-0015 TYPE 6 WITH INFORMATION AS REQ'D.
 9. 5/32" HIGH CHARACTERS, ATTACH USING SILICONE ADHESIVE.
 10. CABLE, THERMO-SEALABLE EXTENSION, SINGLE PAIR, 20 AWG SOLID CONDUCTOR PER ANSI MC-961-1975, 300 VOLT, 90 DEGREE C, MUST BE COLORED PVC INSULATION AND JACKET.
 11. BREAK ALL SWAMP EDGES AND REMOVE ALL BURRS.
 12. DIMENSIONS ARE INCHES.
 TOLERANCES- X = .010
 Y = .015
 Z = .020
 R = .010
 R2 = .015
 R3 = .020

CHART A

MOUNTING LOCATOR	SLOT NO.	UNIT A	UNIT B	D/C
1	N/A	1	1	-
2	N/A	1	1	-
3	N/A	1	1	-
4	N/A	1	1	-
5	N/A	1	1	-
6	N/A	1	1	-
7	N/A	1	1	-
8	N/A	1	1	-
9	N/A	1	1	-
10	N/A	1	1	-
11	N/A	1	1	-
12	N/A	1	1	-
13	N/A	1	1	-
14	N/A	1	1	-
15	N/A	1	1	-
16	N/A	1	1	-



ASSEMBLY HINGED COVER REMOVED

1 HINGED COVER REMOVED

LABEL A
 AV-103
 HS-206
 POS
 1 230C
 2 230C
 3 230C
 4 230C
 5 230C
 6 230C
 7 230C
 8 230C
 9 230C
 10 230C

LABEL B
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C

LABEL C
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C

LABEL D
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C

LABEL E
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C

LABEL F
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C


LABEL G
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C

LABEL H
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C

LABEL I
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C



LABEL J
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C

LABEL K
 AV-103
 HS-206
 POS
 1 240C
 2 240C
 3 240C
 4 240C
 5 240C
 6 240C
 7 240C
 8 240C
 9 240C
 10 240C



NAMEPLATE SCHED
 SEE NOTE 1 AND 8

U.S. DEPARTMENT OF ENERGY	FORM NO. E-100 (REV. 8-75)	FIG. NO.	REV.
PROJECT TITLE	PROJECT NUMBER	DWG. NO.	DATE
DRAWING TITLE		SCALE	PROJ. NO.
DESIGNED BY			
CHECKED BY			
APPROVED BY			
DATE			
PROJECT NUMBER			
DRAWING NUMBER			
SCALE			
PROJECT TITLE			
PROJECT NUMBER			
DRAWING TITLE			
SCALE			
DESIGNED BY			
CHECKED BY			
APPROVED BY			
DATE			
PROJECT TITLE			
PROJECT NUMBER			
DRAWING TITLE			
SCALE			




FOR GENERAL NOTES AND PARTS LIST SEE SH1 1

DRAWING TRACEABILITY LIST		REF NUMBER	TITLE	DATE	BY	CHKD	APPD	REVISIONS	DATE	BY	CHKD	APPD	REVISIONS	DATE	BY	CHKD	APPD



DATE	BY	CHKD	APPD	REVISIONS	DATE	BY	CHKD	APPD

U.S. DEPARTMENT OF ENERGY			
Reactor Operations Office			
Westinghouse, Inservice Company			
TMAC-TBX-204			
WIRING DIAGRAM			
REV	DATE	BY	CHKD
F	241-AM	5903	H-2-820796

TERMINALS 1 THRU 16 RESERVED FOR
3-PAIR CABLES FROM UP TO 3 LEVEL GAUGES.



FROM SHEET 2



FOR GENERAL NOTES AND PARTS LIST SEE SHIT 1


DESIGNED BY	7-94	U.S. DEPARTMENT OF ENERGY
CHECKED BY	4-95	Research Operations Office
DRAWN BY	4-95	WATERGATE-DOE/ERDC/ES&C
DATE		
SCALE		
PROJECT		
UNIT		
NO.		
TITLE	WIRING DIAGRAM	
DATE	1-21-AM	5905 H-2-820796-0
BY	MS	18768
CHKD		
APP'D		
REV	NO.	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		

2 PARTS/MATERIAL LIST


QTY REQ	REF. DES	PART/DASH NO.	NOMENCLATURE/DESCRIPTION	MATERIAL/REF.	SH1	NO.
1	-010		ASSEMBLY		1	
1	M-2-820820-020		ASSEMBLY, (2 ACROMAG)		2	
1	4M0-210		MODULE, TC INPUT	ACROMAG	3	
2	4M0-240		MODULE, DC CURRENT INPUT	ACROMAG	4	
2	J1, J2	RSJ-E-R	JACK, PANEL, TC TYPE E	OMEGA	5	
1	S1	DSV3-20-PG	SWITCH, SELECTOR, 20 POS.	OMEGA	6	
1	S2	DSV3-16-PG	SWITCH, SELECTOR, 16 POS.	OMEGA	7	
1	WLRD-1		DUPLEX COVER, W/SPRING DOOR	CROUSE-HINDS	8	
					9	
					10	
					11	
					12	
					13	
					14	
					15	
					16	
					17	
					18	
AR	(8B760)		CABLE, 18 AWG, 1 TWISTED SHLD PAIR, STRANDED (RED AND BLK)	(BLENDED) COPPER	19	
AR			WIRE, 20 AWG, SOLID, BARE	COPPER	20	
AR	(S710/2001)		WIRE, TC TYPE EX	(ALPHA)	21	
					22	
					23	
					24	
1	DACS		AC OUTPUT MODULE	POTTER & BRUMFIELD (OPTO 22)(ACROMAG)	25	
					26	
					27	
					28	
					29	
AR	(ABMS-A-C)		CABLE TIE MOUNT	(PANDUIT)	30	
AR	(PLT12)-C		TIE, CABLE	(PANDUIT)	31	
					32	
					33	
					34	
					35	

CHART A

MODULE LOCATOR			
SLOT NO.	UNIT A I/N	UNIT B I/N	DI/O-A I/N
0	N/A	N/A	26
1	6	6	-
2	6	6	-
3	6	6	-
4	6	6	-
5	6	6	-
6	6	6	-
7	6	6	-
8	6	6	-
9	6	6	-
10	6	6	-
11	6	6	-
12	6	7	-
13	6	7	-
14	6	-	-
15	6	-	-
16	6	-	N/A



- GENERAL NOTES (UNLESS OTHERWISE NOTED)
- LABEL ITEM NO. 1 PER HS-BS-0015 TYPE 6, USING (1/N 33). TEXT SHALL CONSIST OF THE FOLLOWING:
 LINE 1 USING 1/2" CHARACTERS: FIRST LINE OF DWG TITLE
 LINE 2 USING 1/4" CHARACTERS: "TMACS 1/0 TERMINATION"
 LINE 3 USING 1/4" CHARACTERS: DRAWING NO. PART/DASH NO.
 LINE 4 USING 1/4" CHARACTERS: "EBS-DP-206 CKT 22"
 ATTACH TO FRONT OF THE DOOR USING SILICONE ADHESIVE.
 - WIRING IS DIAGRAMMATICALLY SHOWN, ROUTE AND SUPPORT AS REQUIRED.
 - ALL ELECTRICAL PARTS SHALL BE LISTED BY UL, FM, OR ANOTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
 - USE ITEM NO. 20 FOR JUMPER.
 - FOR ACROMAG PARTS SEE VENDOR INFORMATION (VI), NUMBER 22138.
 - CABLE SHIELDS ARE GROUNDED AT ONE END ONLY.
 - FIELD TO TEMPLATE MOUNTING HOLES FROM ITEMS TO BE MOUNTED AS REQ'D.
 - LABEL PER HS-BS-0015 TYPE 6 WITH INFORMATION AS SHOWN USING 5/32" HIGH CHARACTERS. ATTACH USING SILICONE ADHESIVE.
 - CABLE, THERMOCOUPLE EXTENSION, SINGLE PAIR, 20 AWG SOLID CONDUCTOR PER ANSI MC 96.1-1973, 300 VOLT, 90 DEGREE C, ANSI COLOR CODED PVC INSULATION AND JACKET.
 - BREAK ALL SHARP EDGES AND REMOVE ALL BURRS.
 - DIMENSIONS ARE INCHES.
 TOLERANCES: X = ±0.1
 .XXX = ±0.010
 DEGREES: ±1°



1 ASSEMBLY
HINGED COVER REMOVED

LABEL E		LABEL F		LABEL G		LABEL J		LABEL K		LABEL A	
AV-104	RIS-206	AV-104	RIS-206	TC TYPE E		AV-104	RIS-258	AV-104	RIS-269	UNIT A	UNIT B
SV	TC	SV	TC			SV	TC	SV	TC		
POS	NO	POS	NO	TC TYPE E		POS	NO	POS	NO		
1	2363	11	2460			1	2540	3	2630		
2	2370	12	2470			2	2600	4	2700		
3	2380	13	2480					5	2800		
4	2390	14	2490					6	2740		
5	2400	15	2500					7	2770		
6	2410	16	2510					8	2800		
7	2420	17	2520					9	2830		
8	2430	18	2530					10	-		
9	2440	19	-								
10	2450	20	-								


33 NAMEPLATE SCHED
SEE NOTE 1 AND 8

DWG NO.	TITLE	REV.	DATE	BY	CHKD.	APP'D.	DATE	BY	CHKD.	APP'D.
M-2-81778	TMACS DRAWING INDEX									
M-2-81761	BLOCK DIAGRAM									

Drawn by: BL MURRY 7-94
 Checked by: FAIRCHILD 4-95
 Date: 10/26/95
 U.S. DEPARTMENT OF ENERGY
 Richland Operations Office
 Washington, Maryland Company

TMACS-TBX-205
 TMACS ASSEMBLY

REV. NO. 1
 DATE 1/28/95
 BY 161958



FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

REV	NO	DATE	BY	CHKD	DESCRIPTION
1	1				ISSUED FOR CONSTRUCTION
2	2				ISSUED FOR CONSTRUCTION
3	3				ISSUED FOR CONSTRUCTION
4	4				ISSUED FOR CONSTRUCTION
5	5				ISSUED FOR CONSTRUCTION
6	6				ISSUED FOR CONSTRUCTION
7	7				ISSUED FOR CONSTRUCTION
8	8				ISSUED FOR CONSTRUCTION
9	9				ISSUED FOR CONSTRUCTION
10	10				ISSUED FOR CONSTRUCTION
11	11				ISSUED FOR CONSTRUCTION
12	12				ISSUED FOR CONSTRUCTION
13	13				ISSUED FOR CONSTRUCTION
14	14				ISSUED FOR CONSTRUCTION
15	15				ISSUED FOR CONSTRUCTION
16	16				ISSUED FOR CONSTRUCTION
17	17				ISSUED FOR CONSTRUCTION
18	18				ISSUED FOR CONSTRUCTION
19	19				ISSUED FOR CONSTRUCTION
20	20				ISSUED FOR CONSTRUCTION
21	21				ISSUED FOR CONSTRUCTION
22	22				ISSUED FOR CONSTRUCTION
23	23				ISSUED FOR CONSTRUCTION
24	24				ISSUED FOR CONSTRUCTION
25	25				ISSUED FOR CONSTRUCTION
26	26				ISSUED FOR CONSTRUCTION
27	27				ISSUED FOR CONSTRUCTION
28	28				ISSUED FOR CONSTRUCTION
29	29				ISSUED FOR CONSTRUCTION
30	30				ISSUED FOR CONSTRUCTION
31	31				ISSUED FOR CONSTRUCTION

U.S. DEPARTMENT OF ENERGY
 Federal Energy Administration
 Washington, D.C. 20545

PROJECT: WHC-SD-W457-CDR-001
 DRAWING NO: W457-2-820797-6
 SHEET: 2 OF 2

DESIGNED BY: []
 CHECKED BY: []
 APPROVED BY: []

REV	NO	DATE	BY	CHKD	DESCRIPTION
1	1				ISSUED FOR CONSTRUCTION
2	2				ISSUED FOR CONSTRUCTION
3	3				ISSUED FOR CONSTRUCTION
4	4				ISSUED FOR CONSTRUCTION
5	5				ISSUED FOR CONSTRUCTION
6	6				ISSUED FOR CONSTRUCTION
7	7				ISSUED FOR CONSTRUCTION
8	8				ISSUED FOR CONSTRUCTION
9	9				ISSUED FOR CONSTRUCTION
10	10				ISSUED FOR CONSTRUCTION
11	11				ISSUED FOR CONSTRUCTION
12	12				ISSUED FOR CONSTRUCTION
13	13				ISSUED FOR CONSTRUCTION
14	14				ISSUED FOR CONSTRUCTION
15	15				ISSUED FOR CONSTRUCTION
16	16				ISSUED FOR CONSTRUCTION
17	17				ISSUED FOR CONSTRUCTION
18	18				ISSUED FOR CONSTRUCTION
19	19				ISSUED FOR CONSTRUCTION
20	20				ISSUED FOR CONSTRUCTION
21	21				ISSUED FOR CONSTRUCTION
22	22				ISSUED FOR CONSTRUCTION
23	23				ISSUED FOR CONSTRUCTION
24	24				ISSUED FOR CONSTRUCTION
25	25				ISSUED FOR CONSTRUCTION
26	26				ISSUED FOR CONSTRUCTION
27	27				ISSUED FOR CONSTRUCTION
28	28				ISSUED FOR CONSTRUCTION
29	29				ISSUED FOR CONSTRUCTION
30	30				ISSUED FOR CONSTRUCTION
31	31				ISSUED FOR CONSTRUCTION


REV	NO	DATE	BY	CHKD	DESCRIPTION
1	1				ISSUED FOR CONSTRUCTION
2	2				ISSUED FOR CONSTRUCTION
3	3				ISSUED FOR CONSTRUCTION
4	4				ISSUED FOR CONSTRUCTION
5	5				ISSUED FOR CONSTRUCTION
6	6				ISSUED FOR CONSTRUCTION
7	7				ISSUED FOR CONSTRUCTION
8	8				ISSUED FOR CONSTRUCTION
9	9				ISSUED FOR CONSTRUCTION
10	10				ISSUED FOR CONSTRUCTION
11	11				ISSUED FOR CONSTRUCTION
12	12				ISSUED FOR CONSTRUCTION
13	13				ISSUED FOR CONSTRUCTION
14	14				ISSUED FOR CONSTRUCTION
15	15				ISSUED FOR CONSTRUCTION
16	16				ISSUED FOR CONSTRUCTION
17	17				ISSUED FOR CONSTRUCTION
18	18				ISSUED FOR CONSTRUCTION
19	19				ISSUED FOR CONSTRUCTION
20	20				ISSUED FOR CONSTRUCTION
21	21				ISSUED FOR CONSTRUCTION
22	22				ISSUED FOR CONSTRUCTION
23	23				ISSUED FOR CONSTRUCTION
24	24				ISSUED FOR CONSTRUCTION
25	25				ISSUED FOR CONSTRUCTION
26	26				ISSUED FOR CONSTRUCTION
27	27				ISSUED FOR CONSTRUCTION
28	28				ISSUED FOR CONSTRUCTION
29	29				ISSUED FOR CONSTRUCTION
30	30				ISSUED FOR CONSTRUCTION
31	31				ISSUED FOR CONSTRUCTION

U.S. DEPARTMENT OF ENERGY
 Federal Energy Administration
 Washington, D.C. 20545

PROJECT: WHC-SD-W457-CDR-001
 DRAWING NO: W457-2-820797-6
 SHEET: 2 OF 2



DESIGNED BY: []
 CHECKED BY: []
 APPROVED BY: []

TERMINALS 1 THRU 18 RESERVED FOR 3-PAIR CABLES FROM UP TO 3 LEVEL GAUGES.



FROM SHEET 2

SEC NOTE 4





CONNECT TRIP TC WIRE (-) TO INNER RING OF TERMINALS.

FROM S1 SHEET 2

FROM TB1 SHEET 2

FROM S4 L TB 5 SHEET 2



FOR GENERAL NOTES AND PARTS LIST SEE SHT 1


U.S. DEPARTMENT OF ENERGY
Contract No. EY-76-CO-87000-0001
Project: Energy Research Reactor
Workshop: Westinghouse Electric Company
Title: TMAC-TBX-205
WIRING DIAGRAM
Rev. 2-820797-6
Sheet 3 of 3

NO.	REV.	DATE	BY	CHKD.	DESCRIPTION
1					
2					
3					
4					
5					
6					
7					
8					




NO.	REV.	DATE	BY	CHKD.	DESCRIPTION
1					
2					
3					
4					
5					
6					
7					
8					

REF. NO. TITLE REF. NUMBER REFERENCES
DRAWING TRACEABILITY LIST
DRAWING NO. 820797-6
SCALE
REVISIONS

U.S. DEPARTMENT OF ENERGY
 FEDERAL BUREAU OF SURVEILLANCE
 DIVISION OF ENGINEERING
 WIRING DIAGRAM
 TMC-1-BX-206
 DRAWING TRACABILITY LIST
 SHEET 2
 PROJECT NO. 14-2-820798
 TITLE
 REFERENCE
 DRAW NO. TITLE
 DATE





TERMINALS 1 THRU 18 RESERVED FOR 3-PAIR CABLES FROM UP TO 3 LEVEL CABLES



FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

U.S. DEPARTMENT OF ENERGY	7-94
Atomic Energy Commission	4-95
Washington, D.C. 20545	4-95
PROJECT NAME	TMAC-TBX-206
PROJECT NUMBER	WIRING DIAGRAM
DATE	11-2-82
BY	182-16488
CHECKED	
APPROVED	
DESIGNED	
DRAWN	
SCALE	
SHEET NO.	1
TOTAL SHEETS	1



FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

REV	NO	DATE	BY	CHKD	APP'D	DESCRIPTION

DWG NO	TITLE	REF NUMBER	TITLE

CADFILE	B82079C	CADCODE	BDS-6-ANACD12JSS
REV		SCALE	
DATE			

DESIGNED BY	BL MURPHY	DATE	7-94
CHECKED BY	FAIRCHILD	DATE	4-95
DRAWN BY	R. NEHME	DATE	4-95
SCALE	KA WHITE		




U.S. DEPARTMENT OF ENERGY			
Richard Operations Office Washington, Norfolk Company			
TMAC-TBX-206			
WIRING DIAGRAM			
SCALE	NONE	DATE	161968
REV			

PARTS/MATERIAL LIST

QTY	REF. DES.	PART/DASH NO.	DESCRIPTION	MATERIAL/REF.	SH
1	-010	ASSEMBLY			1
1	H-2-820799-020	ASSEMBLY, C2 ACROWAG			2
4					3
6	440D-210	MODULE, TC INPUT	ACROWAG		4
7		MODULE, TC CURRENT INPUT	ACROWAG		5
8					6
9	2	JL, 22	JACK PANEL, TC TYPE E	OMEGA	7
10	1	51	SWITCH SELECTOR, 20 POS.	OMEGA	8
11	1	52	SWITCH SELECTOR, 16 POS.	OMEGA	9
12					10
13	1	VL8D-1	BURLEX COVER, V/SPRING DOOR	CROUSE-HINDS	11
14					12
15					13
16					14
17					15
18					16
19	AR	888760	CABLE, 18 AWG, 1 TWISTED SHLD (BREDND COPPER PAIR, STRANDED (RED AND BLK))	BREDND COPPER	17
20	AR		WIRE, 20 AWG, SOLID, BARE	COPPER	18
21					19
22	AR	(3710/2001)	WIRE, TC TYPE EX	CALPHAD	20
23					21
24					22
25	1	DACS	AC OUTPUT MODULE	OPTITE B BUREFIELD	23
26					24
27					25
28					26
29					27
30					28
31	AR	GABES-A-C3	CABLE TIE MOUNT	GRANDUIT	29
32	AR	(PL1101-C)	TIE, CABLE	GRANDUIT	30
33					31
34					32
35					33

CHART A

16	6	-	-	N/A
15	6	-	-	-
14	6	-	-	-
13	6	7	-	-
12	6	7	-	-
11	6	6	-	-
10	6	6	-	-
9	6	6	-	-
8	6	6	-	-
7	6	6	-	-
6	6	6	-	-
5	6	6	-	-
4	6	6	-	-
3	6	6	-	-
2	6	6	-	-
1	6	6	-	-
0	N/A	N/A	-	-



ASSEMBLY

HINGED COVER REMOVED

LABEL E

AV-106	AV-106	TC	TC
RS-206	RS-206	SV	SV
POS	POS	NO	NO
VST-TE-	VST-TE-		
1	2	3	4
2	3	4	5
3	4	5	6
4	5	6	7
5	6	7	8
6	7	8	9
7	8	9	10
8	9	10	
9	10		
10			

LABEL F


AV-106	AV-106	TC	TC
RS-206	RS-206	SV	SV
POS	POS	NO	NO
VST-TE-	VST-TE-		
1	2	3	4
2	3	4	5
3	4	5	6
4	5	6	7
5	6	7	8
6	7	8	9
7	8	9	10
8	9	10	
9	10		
10			

LABEL G

AV-106	AV-106	TC	TC
RS-206	RS-206	SV	SV
POS	POS	NO	NO
VST-TE-	VST-TE-		
1	2	3	4
2	3	4	5
3	4	5	6
4	5	6	7
5	6	7	8
6	7	8	9
7	8	9	10
8	9	10	
9	10		
10			

LABEL H

AV-106	AV-106	TC	TC
RS-206	RS-206	SV	SV
POS	POS	NO	NO
VST-TE-	VST-TE-		
1	2	3	4
2	3	4	5
3	4	5	6
4	5	6	7
5	6	7	8
6	7	8	9
7	8	9	10
8	9	10	
9	10		
10			




- GENERAL NOTES (UNLESS OTHERWISE NOTED)
- LABEL ITEM NO. 1 PER HS-85-0015 TYPE 6, USING D/W 33, TEXT SHALL CONSIST OF THE FOLLOWING:
 LINE 1 USING 1/4" CHARACTERS: FIRST LINE OF DWG TITLE
 LINE 2 USING 1/4" CHARACTERS: TMACS I/O TERMINATION
 LINE 3 USING 1/4" CHARACTERS: DRAWING NO. PART/DASH NO.
 LINE 4 USING 1/4" CHARACTERS: CBS-206 CMT 28
 - ATTACH TO FRONT OF THE DOOR USING SILICONE ADHESIVE.
 - WIRING IS DIAGRAMMATICALLY SHOWN, ROUTE AND SUPPORT AS REQUIRED.
 - ALL ELECTRICAL PARTS SHALL BE LISTED BY U.L. FR. OR ANOTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
 - USE ITEM NO. 20 FOR JUMPER.
 - FOR ACROWAG PARTS SEE VENDOR INFORMATION (V.I.) NUMBER 22138.
 - CABLE SHIELDS ARE GROUNDED AT ONE END ONLY.
 - FIELD TO TERMINAL MOUNTING HOLES FROM ITEMS TO BE MOUNTED AS REQD.
 - LABEL PER HS-85-0015 TYPE 6 WITH INFORMATION AS SHOWN USING 5/32" HIGH CHARACTERS. ATTACH USING SILICONE ADHESIVE.
 - CABLE, THE WAGO/CABLE EXTENSION SHIELD PAIR, 20 AWG SOLID CONDUCTION PER MIL MC 961-1974, 300 VOLT, 90 DEGREE C. ANSI COLOR CODES PVC INSULATION AND JACKET.
 - BREAK ALL SHARP EDGES AND REMOVE ALL BURRS.
 - DIMENSIONS ARE INCHES.
 TELEDIMENSIONS: X = 301,
 Y = 4010

NAMEPLATE SCHED

DWG NO.	TITLE	DATE	BY	CHKD
H-2-81778	TMACS DRAWING INDEX			
H-2-81761	BLOCK DIAGRAM			
H-2-82079	REFERENCES			
H-2-82078	DRAWING TRACEABILITY LIST			

U.S. DEPARTMENT OF ENERGY
 OFFICE OF NEUTRON PHYSICS
 CHEMICAL ENGINEERING DIVISION
 7-94
 BL MURPHY
 4-93
 JOHN F. ARCHILD
 4-93
 JOHN W. RICHMOND
 4-93
 JOHN W. WHITE
 4-93



SEE NOTE 4

CONNECT THIS TO WIRE (A) TO UNDER RING OF TERMINAL O 19

SEE WIRE DESTINATION

GROUND VIA JUMPER AND IS NOT SHOWN

FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

U.S. DEPARTMENT OF ENERGY
 National Laboratory Office
 Washington, D.C. 20545

THAC-TBX-207
 WIRING DIAGRAM

REV. 0
 DATE: 11-2-82
 DRAWN BY: [Name]
 CHECKED BY: [Name]
 APPROVED BY: [Name]


NO.	REV.	DATE	BY	DESCRIPTION
1	0	11-2-82	[Name]	INITIAL ISSUE

NO.	REV.	DATE	BY	DESCRIPTION
2	0	11-2-82	[Name]	INITIAL ISSUE



NO.	REV.	DATE	BY	DESCRIPTION
3	0	11-2-82	[Name]	INITIAL ISSUE

NO.	REV.	DATE	BY	DESCRIPTION
4	0	11-2-82	[Name]	INITIAL ISSUE

TERMINALS 1 THRU 18 RESERVED FOR
3-PAIR CABLES FROM UP TO 3 LEVEL GAGES.



FROM
SHEET 2



FROM TB1
SHEET 2

FROM SA & TB 5
SHEET 2


FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

DESIGNER	DATE	BY	DATE	BY	DATE
W. H. MURPHY	7-54	W. H. MURPHY	8-23	W. H. MURPHY	11-23
CHECKED	DATE	CHECKED	DATE	CHECKED	DATE
W. H. MURPHY	8-23	W. H. MURPHY	8-23	W. H. MURPHY	8-23
APPROVED	DATE	APPROVED	DATE	APPROVED	DATE
W. H. MURPHY	8-23	W. H. MURPHY	8-23	W. H. MURPHY	8-23
U.S. DEPARTMENT OF ENERGY WATERBURY RESEARCH CENTER WATERBURY, MASSACHUSETTS 01303					
TMAC-TBX-207 WIRING DIAGRAM					
NO.	DATE	BY	REVISIONS	DATE	BY
1	8-23	W. H. MURPHY	INITIAL DESIGN	8-23	W. H. MURPHY
2	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
3	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
4	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
5	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
6	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
7	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
8	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
9	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
10	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
11	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
12	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
13	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
14	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
15	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
16	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
17	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
18	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
19	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
20	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
21	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
22	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
23	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
24	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
25	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
26	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
27	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
28	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
29	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY
30	8-23	W. H. MURPHY	REVISED FOR CONSTRUCTION	8-23	W. H. MURPHY

PARTS/MATERIAL LIST					
QTY REQ'D	REF. DES.	PART/DASH NO.	NOMENCLATURE/DESCRIPTION	MATERIAL/PLT.	SHI NO.
1		-010	ASSEMBLY		1
1	H-2-820820-020		ASSEMBLY, (2 ACROMAG)		2
1	P/S-1	H-2-81764-030	ASSEMBLY, P/S		3
					4
2	JDC5		MODULE, 10-32V DC INPUT	POTTER & BRUNFIELD	5
22	4M05-210		MODULE, TC INPUT	ACROMAG	6
3	4M05-240		MODULE, DC CURRENT INPUT	ACROMAG	7
1	DACS		MODULE, AC OUTPUT	POTTER & BRUNFIELD	8
5			NAMEPLATE, PLASTIC	HS-BS-0015	9
					10
AR	(ABMS-A-C)		CABLE TIE MOUNT	(PANDUIT)	11
AR	(PLT.51-C)		TIE, CABLE	(PANDUIT)	12
AR			WIRE, 20 AVG. SOLID, BARE	COPPER	13
AR	(89760)		CABLE, 18 AVG. 1 TWISTED SHLD PAIR, STRANDED GRED AND BLK	(BELDEN) COPPER	14
AR			WIRE, 16 AVG. BLK, STRANDED	TYFFN COPPER	15
AR			WIRE, 16 AVG. WHI, STRANDED	TYFFN COPPER	16
					17
					18
					19
					20

CHART A

MODULE LOCATOR			
SLOT NO.	UNIT A 1/N	UNIT B 1/N	BI/O-A 1/N
0	N/A	N/A	8
1	6	6	5
2	6	6	3
3	6	6	-
4	6	6	-
5	6	6	-
6	6	6	-
7	6	-	-
8	6	-	-
9	6	7	-
10	6	7	-
11	6	7	-
12	6	-	-
13	6	-	-
14	6	-	-
15	6	-	-
16	6	-	N/A





1 ASSEMBLY
HINGED COVER REMOVED

9 NAMEPLATE SCHED
SEE NOTE 1 AND 6

- LABEL A
UNIT A UNIT B
- LABEL B
TMAC-F-208
- LABEL C
TMAC-RTU-208A
REMOTE TERMINAL UNIT A
AV TANK FARM
- LABEL D
TMAC-RTU-208B
REMOTE TERMINAL UNIT B
AV TANK FARM

- GENERAL NOTES (UNLESS OTHERWISE NOTED)
- LABEL ITEM NO. 1 PER HS-BS-0015 TYPE 6, USING (1/N 9). TEXT SHALL CONSIST OF THE FOLLOWING:
LINE 1 USING 3/32" CHARACTERS: FIRST LINE OF DNG TITLE
LINE 2 USING 1/4" CHARACTERS: "TMACS 1/0 TERMINATION"
LINE 3 USING 1/4" CHARACTERS: DRAWING NO. PART/DASH NO.
LINE 4 USING 1/4" CHARACTERS: "ECS-IP-206 CKT 22"
ATTACH TO FRONT OF THE DOOR USING SILICONE ADHESIVE.
 - WIRING IS DIAGRAMMATICALLY SHOWN, FIELD ROUTE AND SUPPORT AS REQUIRED.
 - ALL ELECTRICAL PARTS SHALL BE LISTED BY UL, FM, OR ANOTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
 - FOR ACROMAG PARTS SEE VENDOR INFORMATION (V1), NUMBER 22138.
 - CABLE SHIELDS ARE GROUNDED AT ONE END ONLY.
 - LABEL PER HS-BS-0015 TYPE 6 WITH INFORMATION AS SHOWN USING 5/32" HIGH CHARACTERS, ATTACH USING SILICONE ADHESIVE.
 - USE ITEM NO. 13 FOR JUMPER.

DESIGNED BY: BL MURRY 9-94 CHECKED BY: FAIRCHILD 4-95 DRAWN BY: REMINE 4-95 TITLE: KA WHITE	U.S. DEPARTMENT OF ENERGY Remote Operations Office Westinghouse Hanford Company TMACS-TBX-208 TMACS ASSEMBLY
DWG NO. H-2-81778 TITLE: TMACS DRAWING INDEX REF. NUMBER: H-2-81761 BLOCK DIAGRAM	DATE: 1/2 SHEET NO.: 1 TOTAL SHEETS: 3 DRAWN BY: REMINE CHECKED BY: FAIRCHILD APPROVED BY: [Signature]
DRAWING TRACEABILITY LIST NEXT USED ON: H-2-820778 CADFILE: B2C0800A	REVISIONS CADCODE: B2C-6-0ACD-12/1/85



FOR GENERAL NOTES AND PARTS LIST SEE SHIT 1

REV. NO.	DATE	BY	CHKD.	DESCRIPTION
1				ISSUED FOR CONSTRUCTION
2				REVISED TO CORRECT ERROR
3				REVISED TO CORRECT ERROR
4				REVISED TO CORRECT ERROR
5				REVISED TO CORRECT ERROR
6				REVISED TO CORRECT ERROR
7				REVISED TO CORRECT ERROR
8				REVISED TO CORRECT ERROR
9				REVISED TO CORRECT ERROR
10				REVISED TO CORRECT ERROR
11				REVISED TO CORRECT ERROR
12				REVISED TO CORRECT ERROR
13				REVISED TO CORRECT ERROR
14				REVISED TO CORRECT ERROR
15				REVISED TO CORRECT ERROR
16				REVISED TO CORRECT ERROR
17				REVISED TO CORRECT ERROR
18				REVISED TO CORRECT ERROR
19				REVISED TO CORRECT ERROR
20				REVISED TO CORRECT ERROR
21				REVISED TO CORRECT ERROR
22				REVISED TO CORRECT ERROR
23				REVISED TO CORRECT ERROR
24				REVISED TO CORRECT ERROR
25				REVISED TO CORRECT ERROR
26				REVISED TO CORRECT ERROR
27				REVISED TO CORRECT ERROR
28				REVISED TO CORRECT ERROR
29				REVISED TO CORRECT ERROR
30				REVISED TO CORRECT ERROR
31				REVISED TO CORRECT ERROR
32				REVISED TO CORRECT ERROR



REV. NO.	DATE	BY	CHKD.	DESCRIPTION
1				ISSUED FOR CONSTRUCTION
2				REVISED TO CORRECT ERROR
3				REVISED TO CORRECT ERROR
4				REVISED TO CORRECT ERROR
5				REVISED TO CORRECT ERROR
6				REVISED TO CORRECT ERROR
7				REVISED TO CORRECT ERROR
8				REVISED TO CORRECT ERROR
9				REVISED TO CORRECT ERROR
10				REVISED TO CORRECT ERROR
11				REVISED TO CORRECT ERROR
12				REVISED TO CORRECT ERROR
13				REVISED TO CORRECT ERROR
14				REVISED TO CORRECT ERROR
15				REVISED TO CORRECT ERROR
16				REVISED TO CORRECT ERROR
17				REVISED TO CORRECT ERROR
18				REVISED TO CORRECT ERROR
19				REVISED TO CORRECT ERROR
20				REVISED TO CORRECT ERROR
21				REVISED TO CORRECT ERROR
22				REVISED TO CORRECT ERROR
23				REVISED TO CORRECT ERROR
24				REVISED TO CORRECT ERROR
25				REVISED TO CORRECT ERROR
26				REVISED TO CORRECT ERROR
27				REVISED TO CORRECT ERROR
28				REVISED TO CORRECT ERROR
29				REVISED TO CORRECT ERROR
30				REVISED TO CORRECT ERROR
31				REVISED TO CORRECT ERROR
32				REVISED TO CORRECT ERROR

U.S. DEPARTMENT OF ENERGY
National Technical Information Office
Washington, D.C. 20540

TMAC-TBX-208
TMACS WIRING DIAGRAM


FORM NO. 617-1
MAY 1962 EDITION
GPO: 1962 O-568-000

TERMINALS 1 THRU 18 RESERVED FOR
3-PAIR CABLES FROM UP TO 3 LEVEL GAGES



WR-94-44 TO HYDROGEN MONITOR C340
V1P-200A
01-2-820798 SH L M-2-817854 SH 21

WR-94-40 TO MT-TBX-202
CONNECT SH.3 TO TB4-9
01-2-8246659



FROM TBI
SHEET 2

FROM S. & TBE
SHEET 2

FROM SHEET 2
WR-94-44

FOR GENERAL NOTES AND PARTS LIST SEE SHT 1

DATE	BY	REVISION	DESCRIPTION
9-24	REARY	1	INITIAL DESIGN
10-4	REARY	2	REVISED TO SHOW WIRING
11-22	REARY	3	REVISED TO SHOW WIRING
11-22	REARY	4	REVISED TO SHOW WIRING
11-22	REARY	5	REVISED TO SHOW WIRING
11-22	REARY	6	REVISED TO SHOW WIRING
11-22	REARY	7	REVISED TO SHOW WIRING
11-22	REARY	8	REVISED TO SHOW WIRING
11-22	REARY	9	REVISED TO SHOW WIRING
11-22	REARY	10	REVISED TO SHOW WIRING
11-22	REARY	11	REVISED TO SHOW WIRING
11-22	REARY	12	REVISED TO SHOW WIRING
11-22	REARY	13	REVISED TO SHOW WIRING
11-22	REARY	14	REVISED TO SHOW WIRING
11-22	REARY	15	REVISED TO SHOW WIRING
11-22	REARY	16	REVISED TO SHOW WIRING
11-22	REARY	17	REVISED TO SHOW WIRING
11-22	REARY	18	REVISED TO SHOW WIRING
11-22	REARY	19	REVISED TO SHOW WIRING
11-22	REARY	20	REVISED TO SHOW WIRING


U.S. DEPARTMENT OF ENERGY
Washington, D.C. 20545
U.S. GOVERNMENT PRINTING OFFICE: 1975 O-225-100

TMAC-TBX-208
TMACS WIRING DIAGRAM

FIG. NO. H-2-820800
REV. NO. H-2-820800
DATE OF REVISION 11-22-78

NO.	REV.	DATE	DESCRIPTION
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			

NO.	REV.	DATE	DESCRIPTION
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			



1 ASSEMBLY - CIU
HINGED COVER REMOVED

SWITCH SETTINGS (SETUP)

SWITCH	HOST	FUNCTION
SK1	HOST	HOST MODE
SK2	HOST	HOST MODE
SK3-1	ON	ENABLE SK3
SK3-2	OFF	BAUD RATE 2400 (RS-232-C)
SK3-3	ON	BAUD RATE 2400 (RS-232-C)
SK3-4	OFF	ODD PARITY
SK3-5	OFF	TURN AROUND DELAY (4 MS)
SK3-6	OFF	TURN AROUND DELAY (4 MS)
SK3-7	OFF	NOT SPECIFIED
SK3-8	OFF	NOT SPECIFIED

ADDRESS SWITCH SETTINGS

LOCATION	NAME	ADDRESS	SK2-4	SK2-3	SK2-2	SK2-1
241-AM-271	TMAC-TBX-108	0	OFF	OFF	OFF	OFF
241-AM-271	TMAC-TBX-200	1	OFF	OFF	OFF	ON
242-1C	TMAC-TBX-3642	2	OFF	OFF	ON	OFF
		3	OFF	OFF	ON	ON
		4	OFF	ON	OFF	OFF
		5	OFF	ON	OFF	ON
		6	OFF	ON	OFF	OFF
		7	OFF	ON	ON	ON
		8	ON	OFF	OFF	OFF
		9	ON	OFF	OFF	ON

STRAP SETTINGS

FACTORY SETTINGS NOT TO BE CHANGED	USER SELECTED		FUNCTION
	OPEN	CLOSED	
ST1			
ST2			
		ST3	WITHOUT "DCD"
ST5		ST4	2400 FIELD BAUD RATE (TT)
ST6			
ST7			
ST8			
ST9			
ST10			
ST11			
ST12			
ST13			
ST14			
ST15			
ST16			
ST17			
ST18			
ST19			
ST20			
		ST21	FIELD LINES GAIN SET AT 10
		ST22	
		ST23	
		ST24	OPEN TO DESLECT CN2 (NO MULTI-JUMPER)
		ST25	MULTI-JUMPER INSTALLED ENABLING CONNECTOR CN3
		ST26	ENABLE SK3

PARTS/MATERIAL LIST

QTY	REF. DES.	PART/DASH NO.	NOMENCLATURE/DESCRIPTION	MATERIAL/REF.	SH1	NO.
1		-010	ASSEMBLY - CIU			1
1		UNBSBU/CN3-US	COMMUNICATIONS INTERFACE UNIT	ENRAF B.V.		2
1		-020	ASSEMBLY - CIU (WITH MODEM)			3
						4
						5
1			POWER CORD, 16 AWG NEMA 5-15	(BELDEN 17461)		6
AR	AR		WIRE, 20 AWG, SOLID	COPPER		7
AR	AR		WIRE, 20 AWG, STRANDED	COPPER		8
AR	AR		CABLE, 2 TWISTED PAIR WITH OVERALL SHLD, 24 AWG STRD	(BELDEN 9842)		9
						10
1			CONNECTOR, 25 PIN PLUG, D-SUB	(CINCH DBC-25P)		11
1			CONNECTOR HOOD (FOR 1/N 11)	(CINCH DPH-B-001)		12
1			HUB, CONDUIT, 1/2"	(MYERS STA-1)		13
2			BRACKET, 3/4" X 9 1/2" X .082	AL 8081-16		14
4	7220		SPACER, 1/4" HEX MALE/FEMALE 8-32 UNC THREAD, 3/8" LONG	KEYSTONE		15
4			SCREW, 8-32 UNC-A, 1" LONG	ANY GRADE		16
12			WASHER, FLAT NO. 8	ANY GRADE		17
8			WASHER, LOCK NO. 8	ANY GRADE		18
4			NUT, HEX, 8-32 UNC-B	ANY GRADE		19
						20

- GENERAL NOTES** (UNLESS OTHERWISE NOTED)
- BOX IDENTIFICATION LABEL SHALL BE SPECIFIED BY THE DRAWING THAT INSTALLS THIS ASSEMBLY.
 - SEE VENDOR INFORMATION (M) NUMBER 31560 FOR ITEM NO. 2.
 - USE ITEM NO. 7 FOR JUMPERS.
 - VERIFY OR SET THE VOLTAGE SELECTOR SWITCH TO THE NOMINAL SUPPLY VOLTAGE. (GENERALLY THIS SETTING SHOULD BE "110" AS SUPPLIED BY THE FACTORY)
 - POSITION SWITCHES AS SHOWN IN TABLES.
 - VERIFY ALL FACTORY STRAP (ST) SETTINGS PER TABLE.
 - CONFIGURE THE USER SELECTED STRAP (ST) SETTINGS PER TABLE.
 - MODEM TO BE SUPPLIED BY TELEPHONE COMPANY.
 - ADDITIONAL FLAT WASHERS (1/N 17) OR GASKET MATERIAL MAYBE USED ON BACK SIDE OF (1/N 14) TO PREVENT SCREWS (1/N 16) FROM BOTTLING OUT.


DRAWING TRADEABILITY LIST		H-2-81778 TMACS DRAWING INDEX		1 REV PER ECH 623201		BLM	MHF	HLX	REN	WYW	
H-2-81751 TMACS BLOCK DIAGRAM		REV NUMBER		7/90		9/90	9/90	9/90	9/90	9/90	
TITLE		REFERENCES		SCALE: NONE		DATE: 1/16/98		REV: 1		PAGE: 1 OF 2	
NEXT USED ON		AS ALLOCATED		CADFILE: B20901A		CAGCODE: D05-6-0ACDZ-12-G-SS		SCALE: NONE		REV: 1	

Rev. BL MURPHY 1-95
Rev. FAIRCROFT 4-95
Rev. R. ROUMIE 4-95
Rev. KA WHITE

U.S. DEPARTMENT OF ENERGY
Richard Operations Office
Westinghouse, Hartford, Company

COMM INTERFACE UNIT
(CIU) ASSEMBLY

REV. NO. H-2-820801
REV. DATE 1/16/98




FOR GENERAL NOTES, PARTS LIST AND LEGEND SEE SH 1



REV. 7-85	REV. 8-85	REV. 8-85	REV. 8-85	REV. 8-85	REV. 8-85
BY: B. BARRY	BY: J. FARMFIELD	BY: J. FARMFIELD	BY: J. FARMFIELD	BY: J. FARMFIELD	BY: J. FARMFIELD
U.S. DEPARTMENT OF ENERGY Nuclear Operations Office Washington, D.C. 20545					
COMM INTERFACE UNIT (CIU) ASSEMBLY					
DATE: F 241-C	REV: 0	REV: 0	REV: 0	REV: 0	REV: 0
DRAWING TRACIBILITY LIST			REFERENCES		
NO.	REV.	DATE	NO.	REV.	DATE
1			1		
2			2		
3			3		
4			4		
5			5		
6			6		
7			7		
8			8		
9			9		
10			10		
11			11		
12			12		
13			13		
14			14		
15			15		
16			16		
17			17		
18			18		
19			19		
20			20		
21			21		
22			22		
23			23		
24			24		
25			25		
26			26		
27			27		
28			28		
29			29		
30			30		
31			31		
32			32		
33			33		
34			34		
35			35		
36			36		
37			37		
38			38		
39			39		
40			40		

VIEW A - A
4 PLACES

ASSEMBLY - CIU




PARTS/MATERIAL LIST					
QTY	REF. DES.	PART/DASH NO.	NOMENCLATURE/DESCRIPTION	MATERIAL/REF.	SPR. NO.
		-010	ASSEMBLY (1 ACROMAG)		1
		-020	ASSEMBLY (2 ACROMAG)		2
		-030	ASSEMBLY, CABLE		3
1	1	A-30H240MALLP	ENCLOSURE, 30"x24"x8"	HOFFMAN AL	4
1	1	H-2-81764-020	PANEL, ASSEMBLY, (115V)		5
2	1	4368-16-1	I/O SIGNAL CONT. UNIT	ACROMAG	6
1	1	210-16	I/O MOUNTING BOARD	POTTER & BRUMFIELD	7
					8
1	1	H-2-81764-040	ASSEMBLY, TERMINAL BLOCK		9
					10
AR		3580/50	CABLE, 50 CONDUCTOR	ALPHA	11
1		3425-6600	CONNECTOR, 50 CONTACTS	3M	12
1	1	5505	PLUG, WITH CORD	PANMOTOR	13
1		3415-0001	CONNECTOR, 50 CONTACTS	3M	14
1		3448-58	STRAIN RELIEF	3M	15
1		3430-2	POLARIZATION KEY	3M	16
AR	AR		WIRE, 16 AWG, BLK, STRANDED	TFFN COPPER	17
AR	AR		WIRE, 16 AWG, WHI, STRANDED	TFFN COPPER	18
AR	AR		WIRE, 16 AWG, GRN, STRANDED	TFFN COPPER	19
					20
AR	AR	(88760)	CABLE, 16 AWG, 1 PAIR, TWISTED SHLD PAIR, STRANDED (RED, BLK)	(BELDEN) COPPER	22
AR	AR		WIRE, 20 AWG, SOLID, BARE	COPPER	23
4	4		SCREW, PAN 6-32 UNC-2A, 3/8" L	ANY GRADE CS	24
10	6		SCREW, PAN 8-32 UNC-2A 3/8" L	ANY GRADE CS	25
AR	AR	ABM25-A-C	CABLE TIE MOUNT	PANDUIT	26
AR	AR	PL11.51-C	TIE, CABLE	PANDUIT	27
					28
					29
					30



- 1 ASSEMBLY HINGED COVER REMOVED
- 2 ASSEMBLY HINGED COVER REMOVED

- GENERAL NOTES (UNLESS OTHERWISE NOTED)
1. LABELS "UNIT A AND UNIT B" IDENTIFICATION SHALL BE SHOWN ON DRAWINGS THAT REFERENCE THIS DRAWING.
 2. WIRING IS DIAGRAMMATICALLY SHOWN, ROUTE AND SUPPORT AS REQUIRED.
 3. ALL ELECTRICAL PARTS SHALL BE LISTED BY UL, FM, OR ANOTHER NATIONALLY RECOGNIZED TESTING LABORATORY.
 4. FOR 1/N 6 SEE VENDOR INFORMATION (VI), NUMBER 22138.
 5. CABLE SHIELDS ARE GROUNDED AT ONE END ONLY.
 6. CONNECT THE GROUNDING SCREW ON S3 AND S4 TO THE ELECTRICAL BOX/EQUIPMENT CHASSIS USING NO. 12 AWG COPPER WIRE.

DESIGNED BY: BL MURPHY 10-94 CHECKED BY: FAIRCHILD 4-95 DRAWN BY: R. ROWINE 4-95 APPR. BY: RA WHITE		U.S. DEPARTMENT OF ENERGY Richland Operations Office Washington, Portland Company	
H-2-81778 TMACS DRAWING INDEX H-2-81781 TMACS BLOCK DIAGRAM		TBX-TMACS-GEN ACROMAG ASSEMBLIES	
DWG NO. TITLE DRAWING TRACEABILITY LIST		REVISIONS DATE BY DESCRIPTION	
REF NUMBER TITLE REFERENCES		DRAWING CODE: 60-6-0002-170-SS SCALE: 1/2" = 1" SHEET: 1 OF 2	



FOR GENERAL NOTES AND PARTS LIST SEE SHIT 1

U.S. DEPARTMENT OF ENERGY Atomic Energy Commission Washington, D.C. 20545	10-84 4-85 4-85
Author: J. RICHILLO Design: R. BOWLING Check: J.A. WHITE	10-84 4-85 4-85
TITLE TBX-TMACS-GEN WIRING DIAGRAM	
DATE 11-2-82	REV. 0
BY J. RICHILLO	CHKD. J. RICHILLO
APP. J. RICHILLO	DATE 11-2-82





NO.	REV.	DESCRIPTION	DATE
1	0	ISSUED FOR FABRICATION	11-2-82

NO.	REV.	DESCRIPTION	DATE
1	0	ISSUED FOR FABRICATION	11-2-82

PARTS/MATERIAL LIST

REF ID	REFERENCE/DESCRIPTION	PARTS/SHOP NUMBER	QUANTITY/DESCRIPTION	MATERIAL/REFERENCE	SHEET NO
1	ASSEMBLY, GENERIC TBX	-010	1	ASSEMBLY, GENERIC TBX	1
2	ASSEMBLY, CABLE	-020	1	ASSEMBLY, CABLE	2
3	ENCLOSURE, NEW 1, 11 O.D. X 11 O.D. X 11 O.D. ALUMINUM	-001	1	ENCLOSURE, NEW 1, 11 O.D. X 11 O.D. X 11 O.D. ALUMINUM	3
4	BRACKET ASSEMBLY (2 BRACKETS)	A-20NMA2	2	BRACKET ASSEMBLY (2 BRACKETS)	4
5	TERMINAL STOP	A-20T	2	TERMINAL STOP	5
6	MARKER STRIP	MS-12-141	1	MARKER STRIP	6
7	TERMINAL BLOCK, 600, 17 FT 1H SERIES	12-141	1	TERMINAL BLOCK, 600, 17 FT 1H SERIES	7
8	ROTARY SELECTOR SWITCH, 2 POLE	OSW5-30-PS	1	ROTARY SELECTOR SWITCH, 2 POLE	8
9	RESISTOR, 100 OHMS, 1/2 WATT	RS-30-R	1	RESISTOR, 100 OHMS, 1/2 WATT	9
10	CONNECTOR, THERMOCOUPLE	MTC-55-MC	1	CONNECTOR, THERMOCOUPLE	10
11	BACKSHELL, CABLE CLAMP	MTC-55-SHL	1	BACKSHELL, CABLE CLAMP	11
12	PINS, MALE CHROME (+)	MTC-CH-P	22	PINS, MALE CHROME (+)	12
13	PINS, MALE GOLD PLATED	MTC-AL-P	22	PINS, MALE GOLD PLATED	13
14	WIRE, TYPE KK	MTC-74-W	22	WIRE, TYPE KK	14
15	WIRE, TYPE KK	24K00PP	22	WIRE, TYPE KK	15
16	WIRE, TYPE KK	9153C	22	WIRE, TYPE KK	16
17	COVER, SPRING DOOR SINGLE W/OBET	WLR5-1	1	COVER, SPRING DOOR SINGLE W/OBET	17
18	NAMEPLATE, (SEE LEGEND)	MPS-I-2-7	1	NAMEPLATE, (SEE LEGEND)	18
19	TERMINAL LUG, CHROME	TLLH-2D	22	TERMINAL LUG, CHROME	19
20	TERMINAL LUG, ALUMINUM	TLLA-2C	22	TERMINAL LUG, ALUMINUM	20
21	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	21
22	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	22
23	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	23
24	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	24
25	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	25
26	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	26
27	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	27
28	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	28
29	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	29
30	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	30
31	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	31
32	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	32
33	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	33
34	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	34
35	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	35
36	SSK PAN HEAD 4-20UNC-2A X 5/8" L		24	SSK PAN HEAD 4-20UNC-2A X 5/8" L	36

- GENERAL NOTES: UNLESS OTHERWISE SPECIFIED)
 1. DIMENSIONING AND TOLERANCING PER ANSI Y14.5M-82. DIMENSIONS ARE IN INCHES
 TOLERANCES: .XX ±.01; .XXK ±.010.
 2. BREAK ALL SHARP EDGES, REMOVE ALL BURRS.
 3. INSTALLATION SHALL CONFORM WITH THE NATIONAL ELECTRICAL CODE, 1993 EDITION.
 4. PRIOR TO TERMINATING WIRE ENDS INSTALL HEAT SHRINKABLE MARKER SLEEVES ON ENDS
 OF WIRES USING BLACK STAMP MARKER WITH WIRE IDENTIFICATION PER WIRING DIAGRAM (SHEET 2).
 5. NAMEPLATES SHALL BE REMOVED IN LOCATION SHOWN USING CLEAR BUTYRATE ADHESIVE.
 6. GOOD PRACTICE TERMINALS ON TBX THROUGH TBX SHALL HAVE ITEM 25 INSTALLED ON
 TERMINAL BOARD EVEN-NUMBERED TERMINALS ON TBX THROUGH TBX SHALL HAVE ITEM
 26 INSTALLED ON TERMINAL BOARD.
 7. FIELD TO DETERMINE LENGTH PRIOR TO FABRICATION.
 8. LABELING SHALL BE SPECIFIED BY THE DRAWING THAT INSTALLS THIS ASSEMBLY.
 9. LABEL THERMOCOUPLE EXTENSION PAPER DUPLEX PARALLEL 20 AWG SOLID CONDUCTOR
 PER ANSI WG 58.1, 30 GAGE, 90 DEGREE C, RISE COLOR CODED PER IEC REGULATION.




NAMEPLATE	SIZE	LETTER	LEGEND
A	1/2" X 1 1/2"	5/32	TYPE K
B	1/2" X 1 1/2"	5/32	TB 1
C	1/2" X 1 1/2"	5/32	TB 2
D	1/2" X 1 1/2"	5/32	TB 3
E	1/2" X 1 1/2"	5/32	TB 4
F	1/2" X 1 1/2"	5/32	TB 5
G	1/2" X 1 1/2"	5/32	TB 6
H	1/2" X 1 1/2"	5/32	TB 7
J	1/2" X 1 1/2"	5/32	TB 8

U.S. DEPARTMENT OF ENERGY
 MULTIFUNCTIONAL INSTRUMENT TREE
 TERMINAL BOX ASSY
 WMC-SD-W457-CDR-001
 REV. 0
 SHEET 2 OF 2

DATE: 05/06/82
 DRAWN: J. J. WILSON
 CHECKED: J. J. WILSON
 APPROVED: J. J. WILSON

U.S. GOVERNMENT PRINTING OFFICE: 1982 O-307-001



CONNECT RED TO WIRE TO INNER RING OF TERMINALS

SEE NOTE 7


SEE NOTE 7

FOR PARTS LIST AND GENERAL NOTES, SEE SHEET 1

TERMINAL BOX WIRING DIAGRAM

U.S. DEPARTMENT OF ENERGY DOE Form 1150 (Rev. 11-1989)		PROJECT NUMBER		CONTRACT NUMBER	
MULTIFUNCTIONAL INSTRUMENT TREE		TERM BOX WIRING DIAG		HT-2-824669-0	
DATE	REV	DATE	REV	DATE	REV
01/24/90	1	01/24/90	1	01/24/90	1
01/24/90	2	01/24/90	2	01/24/90	2
01/24/90	3	01/24/90	3	01/24/90	3
01/24/90	4	01/24/90	4	01/24/90	4
01/24/90	5	01/24/90	5	01/24/90	5
01/24/90	6	01/24/90	6	01/24/90	6
01/24/90	7	01/24/90	7	01/24/90	7
01/24/90	8	01/24/90	8	01/24/90	8
01/24/90	9	01/24/90	9	01/24/90	9
01/24/90	10	01/24/90	10	01/24/90	10
01/24/90	11	01/24/90	11	01/24/90	11
01/24/90	12	01/24/90	12	01/24/90	12
01/24/90	13	01/24/90	13	01/24/90	13
01/24/90	14	01/24/90	14	01/24/90	14
01/24/90	15	01/24/90	15	01/24/90	15
01/24/90	16	01/24/90	16	01/24/90	16
01/24/90	17	01/24/90	17	01/24/90	17
01/24/90	18	01/24/90	18	01/24/90	18
01/24/90	19	01/24/90	19	01/24/90	19
01/24/90	20	01/24/90	20	01/24/90	20
01/24/90	21	01/24/90	21	01/24/90	21
01/24/90	22	01/24/90	22	01/24/90	22
01/24/90	23	01/24/90	23	01/24/90	23
01/24/90	24	01/24/90	24	01/24/90	24
01/24/90	25	01/24/90	25	01/24/90	25
01/24/90	26	01/24/90	26	01/24/90	26
01/24/90	27	01/24/90	27	01/24/90	27
01/24/90	28	01/24/90	28	01/24/90	28
01/24/90	29	01/24/90	29	01/24/90	29
01/24/90	30	01/24/90	30	01/24/90	30
01/24/90	31	01/24/90	31	01/24/90	31
01/24/90	32	01/24/90	32	01/24/90	32
01/24/90	33	01/24/90	33	01/24/90	33
01/24/90	34	01/24/90	34	01/24/90	34
01/24/90	35	01/24/90	35	01/24/90	35
01/24/90	36	01/24/90	36	01/24/90	36
01/24/90	37	01/24/90	37	01/24/90	37
01/24/90	38	01/24/90	38	01/24/90	38
01/24/90	39	01/24/90	39	01/24/90	39
01/24/90	40	01/24/90	40	01/24/90	40
01/24/90	41	01/24/90	41	01/24/90	41
01/24/90	42	01/24/90	42	01/24/90	42
01/24/90	43	01/24/90	43	01/24/90	43
01/24/90	44	01/24/90	44	01/24/90	44
01/24/90	45	01/24/90	45	01/24/90	45
01/24/90	46	01/24/90	46	01/24/90	46
01/24/90	47	01/24/90	47	01/24/90	47
01/24/90	48	01/24/90	48	01/24/90	48
01/24/90	49	01/24/90	49	01/24/90	49
01/24/90	50	01/24/90	50	01/24/90	50
01/24/90	51	01/24/90	51	01/24/90	51
01/24/90	52	01/24/90	52	01/24/90	52
01/24/90	53	01/24/90	53	01/24/90	53
01/24/90	54	01/24/90	54	01/24/90	54
01/24/90	55	01/24/90	55	01/24/90	55

QTY	REF ID	PART / DASH NO.	DESCRIPTION	UNIT
		-010	INSTALLATION - SUPPORT TMACS	SEE NOTE 5
		-020	INSTALLATION - SUPPORT BOX	SEE NOTE 5
1	H-2-B1748-010	SUPPORT, TMACS		
1	H-2-B1748-020	SUPPORT, BOX		
2	H-2-B1502-010	FOOTING, CONCRETE (48")		
2	H-2-B1502-020	FOOTING, CONCRETE (37")		
4	HHC3031500G	BOLT, 3/8-18 UNC-2A, 1 1/2 LG	UNISTRUT	
4	P 1008	NUT, 3/8-18 UNC-2B W/SPRING	UNISTRUT	
4	HLW037EG	LOCK WASHER, 3/8	UNISTRUT	
4	HP720501500G	BOLT, 1/2-13 UNC-2A, 1 1/2 LG	UNISTRUT	
4	P 1010	NUT, 1/2-13 UNC-2B W/SPRING	UNISTRUT	
4	HLW030EG	LOCK WASHER, 1/2	UNISTRUT	
4	P 1050	PLATE, FLAT 9 1/8" LG	UNISTRUT	
4	HHC3031500G	BOLT, 1/4-20 UNC-2A, 1 1/2 LG	UNISTRUT	
4	P 1008-1420	NUT, 1/4-20 UNC-2B W/SPRING	UNISTRUT	
4	HLW022EG	LOCK WASHER, 1/4	UNISTRUT	



GENERAL NOTES:(UNLESS OTHERWISE SPECIFIED)

1. ENSURE THAT THE ENCLOSURE FRONT FACES NORTH FOR THE SUN SHIELD TO HAVE MAXIMUM EFFECT.
2. PREFERABLY THE TOP OF THE CONCRETE FOOTING (L/W 17") WILL BE FLUSH WITH EXISTING GRADE OR BAIKED SLIGHTLY, OTHERWISE, AS DETERMINED IN THE FIELD, THE FOOTING CAN BE PLACED ON GRADE.
3. DIMENSION ARE IN INCHES.
4. SUPPORT STAND (L/W 1", ASSY-010) WITH SUN SHIELD IS MOUNTED FOR THE INSTALLATION OF AN ENCLOSURE BOX 30"X24"X6" WITH MOUNTING EARS (EXAMPLE: HOFFMAN P/N A-30R2406ALP).
5. SEISMIC AND WIND LOADING ANALYSIS IS DOCUMENTED IN SUPPORTING DOCUMENT WHC-SD-W457-010. ALSO ANALYZED WAS AN OPTIONAL ENCLOSURE BOX AIRBOR TANGLED TO THE BACK OF STAND.

INSTALLATION

INSTALLATION

INSTALLATION

INSTALLATION

INSTALLATION

INSTALLATION

REV	DATE	BY	CHKD	DESCRIPTION
1	10/19/89	B. MURRY	J. MATEO	ISSUE FOR CONSTRUCTION
2	4/9/93	J. MATEO	R. SCORDE	REVISED FOR TMACS-GEN
3	4/9/93	R. SCORDE	D. BORN	REVISED FOR TMACS-GEN
4	4/9/93	D. BORN		REVISED FOR TMACS-GEN
5	4/9/93			REVISED FOR TMACS-GEN
6	4/9/93			REVISED FOR TMACS-GEN
7	4/9/93			REVISED FOR TMACS-GEN
8	4/9/93			REVISED FOR TMACS-GEN
9	4/9/93			REVISED FOR TMACS-GEN
10	4/9/93			REVISED FOR TMACS-GEN
11	4/9/93			REVISED FOR TMACS-GEN
12	4/9/93			REVISED FOR TMACS-GEN
13	4/9/93			REVISED FOR TMACS-GEN
14	4/9/93			REVISED FOR TMACS-GEN
15	4/9/93			REVISED FOR TMACS-GEN
16	4/9/93			REVISED FOR TMACS-GEN
17	4/9/93			REVISED FOR TMACS-GEN
18	4/9/93			REVISED FOR TMACS-GEN
19	4/9/93			REVISED FOR TMACS-GEN
20	4/9/93			REVISED FOR TMACS-GEN
21	4/9/93			REVISED FOR TMACS-GEN
22	4/9/93			REVISED FOR TMACS-GEN
23	4/9/93			REVISED FOR TMACS-GEN
24	4/9/93			REVISED FOR TMACS-GEN
25	4/9/93			REVISED FOR TMACS-GEN
26	4/9/93			REVISED FOR TMACS-GEN
27	4/9/93			REVISED FOR TMACS-GEN
28	4/9/93			REVISED FOR TMACS-GEN
29	4/9/93			REVISED FOR TMACS-GEN
30	4/9/93			REVISED FOR TMACS-GEN
31	4/9/93			REVISED FOR TMACS-GEN
32	4/9/93			REVISED FOR TMACS-GEN
33	4/9/93			REVISED FOR TMACS-GEN
34	4/9/93			REVISED FOR TMACS-GEN
35	4/9/93			REVISED FOR TMACS-GEN
36	4/9/93			REVISED FOR TMACS-GEN