Drift-Scale Test Status Report

**Yucca Mountain Project
Lawrence Livermore National Laboratory
Livermore, California**

Drift-Scale Test Status Report

satisfying the deliverables

Second-Quarter Drift-Scale Test Report

(SP2670M4)

and

Draft Drift-Scale Test Progress Report

(SP2931M4)

by

**Stephen C. Blair
Thomas A. Buscheck
Eric Carlberg
Richard Carlson
Marc Costantino
William D. Daily
Laura D. DeLoach
Kenrick Lee
Wunan Lin
Ronald Pletcher
Abelardo L. Ramirez
Jeffery Roberts
Nina D. Rosenberg
David Ruddle
Jeffrey Wagoner**

July 1998

**Lawrence Livermore National Laboratory
Livermore, California**

DISCLAIMER

This document was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor the University of California nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or the University of California, and shall not be used for advertising or product endorsement purposes.

This report has been reproduced
directly from the best available copy.

Available to DOE and DOE contractors from the
Office of Scientific and Technical Information
P.O. Box 62, Oak Ridge, TN 37831
Prices available from (615) 576-8401, FTS 626-8401

Available to the public from the
National Technical Information Service
U.S. Department of Commerce
5285 Port Royal Rd.,
Springfield, VA 22161

This work was performed under the auspices of the U.S. Department of Energy by the Lawrence Livermore National Laboratory under contract W-7405-ENG-48 and was supported specifically by the Yucca Mountain Site Characterization Project at LLNL.

Contents

Abbreviations and Acronyms.....	xi
Acknowledgments.....	xiii
1. Introduction.....	1-1
1.1 Drift-Scale Test Layout.....	1-1
1.2 Monitoring of the DST.....	1-2
1.3 References.....	1-2
2. Temperature Measurements	2-1
2.1 Introduction	2-1
2.2 Heating in the Drift-Scale Test	2-1
2.3 Temperature Observations: December 3, 1997, to May 30, 1998.....	2-3
2.3.1 Overview of Temperature Field.....	2-3
2.3.2 Vertical Profiles Along Heater-Drift Axis.....	2-3
2.3.3 End Effects in Axial Direction	2-4
2.3.4 Vertical Cross Section at 12 m from Bulkhead.....	2-6
2.3.5 Vertical Cross Section 23 m from the Bulkhead	2-10
2.3.6 Vertical Cross Section at 39 m from Bulkhead.....	2-13
2.4 Analysis	2-14
2.5 References.....	2-15
3. Electrical Resistivity Monitoring	3-1
3.1 Introduction	3-1
3.2 Electrical Resistance Tomography.....	3-1
3.3 Description of ERT Surveys.....	3-2
3.4 Changes in Electrical Resistivity	3-3
3.5 Estimates of Saturation Change.....	3-5
3.6 Summary and Conclusions.....	3-9
3.7 References.....	3-9
4. Neutron Logging.....	4-1
4.1 Introduction	4-1
4.2 Measurement Procedures	4-2

4.3	Baseline Fraction Volume Water Contents.....	4-2
4.4	Heating Phase Neutron Data and Discussion	4-4
4.5	Summary	4-6
4.6	Future Plans.....	4-7
4.7	References	4-7
5.	Gas and Water Chemistry	5-1
5.1	Introduction	5-1
5.2	Description of Chemistry Boreholes	5-1
5.3	Methodology for Chemistry Sampling and Analysis.....	5-2
5.3.1	Discrete Gas Sampling and Analysis.....	5-2
5.3.2	Real-Time, Near-Continuous Gas Sampling and Analysis	5-2
5.3.3	SEAMIST™ Pad Sampling and Analysis.....	5-3
5.4	Results.....	5-4
5.4.1	Gas Data	5-4
5.4.2	Water Chemistry and Moisture Distribution Data.....	5-5
5.5	Tables.....	5-6
6.	Thermohydrologic Modeling.....	6-1
6.1	Introduction.....	6-1
6.2	Numerical Models and Assumptions.....	6-1
6.2.1	NUFT Numerical Simulation Code	6-1
6.2.2	Equivalent Continuum Method.....	6-2
6.2.3	Model Geometry, Boundary Conditions, and Numerical Mesh	6-2
6.2.4	Thermal-Radiative Heat Flow in Heated Drift.....	6-4
6.2.5	Heater Power.....	6-5
6.2.6	Barometric Pressure Fluctuations.....	6-6
6.2.7	Influence of Drift Ventilation.....	6-6
6.2.8	Influence of Vapor and Heat Flow Along Wing-Heater Boreholes	6-7
6.2.9	Thermal and Hydrologic Properties.....	6-7
6.3	Modeling Results	6-9
6.3.1	Simulated Temperature and Liquid-Phase Saturation	6-9
6.3.2	Comparison of Simulated and Measured Temperatures	6-11

6.3.3	Influence of Vapor Flow Along Wing-Heater Boreholes	6-13
6.3.4	Influence of Barometric Pumping.....	6-15
6.4	Conclusions and Future Work	6-17
6.5	References.....	6-17
7.	Laboratory Results	7-1
7.1	Drying and Rewetting of Intact Rocks	7-1
7.1.1	Introduction	7-1
7.1.2	Experimental Procedure.....	7-1
7.1.3	Measurement Uncertainty	7-2
7.1.4	Results and Discussion.....	7-3
7.1.5	Future Work.....	7-5
7.2	Preliminary Results on Sorptivity	7-5
7.2.1	Introduction	7-5
7.2.2	Methodology.....	7-7
7.2.3	Experiment.....	7-8
7.2.4	Results and Discussion.....	7-9
7.2.5	Summary	7-10
7.2.6	References.....	7-10
8.	Relative Humidity and Barometric Pressure	8-1
9.	Evaluation of Sensors	9-1
9.1	Failed and Suspect Sensors.....	9-1
9.2	Suggested Corrections for RTD Data	9-2
9.3	References.....	9-5

Tables

Table 2-1.	Temperature (RTD) boreholes.....	2-1
Table 5-1.	Distance of gas-sampling ports and absorbent pads (in meters) from the collar of each borehole.....	5-6
Table 5-2.	Analyses for discrete gas samples collected December 2, 1997.....	5-7
Table 5-3.	Analyses for discrete gas samples collected January 13, 1998.	5-8
Table 5-4.	Analyses for discrete gas samples collected February 19, 1998.....	5-9

Table 5-5.	Analyses for discrete gas samples collected March 25, 1998.	5-10
Table 5-6.	Analyses for discrete gas samples collected April 21, 1998.	5-12
Table 5-7.	CO ₂ (mole [volume] percent) by time, connecting drift, April 1998.	5-13
Table 5-8.	CO ₂ (mole [volume] percent) by time, heater drift, April 1998.	5-15
Table 5-9.	O ₂ (mole [volume] percent) by time, heater drift, April 1998.	5-17
Table 5-10.	O ₂ (mole [volume] percent) by time, connecting drift, April 1998.	5-19
Table 5-11.	CO ₂ (mole [volume] percent) by time, heater drift, June 1998.	5-22
Table 5-12.	CO ₂ (mole [volume] percent) by time, connecting drift, June 1998.	5-23
Table 5-13.	CO ₂ (mole [volume] percent) by time, access/observation drift, June 1998.	5-24
Table 5-14.	CO ₂ (mole [volume] percent) by time, Boreholes 54, 55, and 59, June 1998.	5-25
Table 5-15.	O ₂ (mole [volume] percent) by time, heater drift, June 1998.	5-28
Table 5-16.	O ₂ (mole [volume] percent) by time, connecting drift, June 1998.	5-29
Table 5-17.	O ₂ (mole [volume] percent) by time, Boreholes 54, 55, and 59, June 1998.	5-30
Table 5-18.	O ₂ (mole [volume] percent) by time, access/observation drift, June 1998.	5-32
Table 5-19.	Liquid water collected during gas sampling.	5-34
Table 5-20.	pH measurements.	5-34
Table 6-1.	Thermohydrologic properties of the concrete invert and fiberglass insulation.	6-4
Table 6-2.	Thermohydrologic properties of host rock (tsw34) in DST area.	6-8
Table 6-3.	Location of boreholes used for comparison of simulated and measured temperature.	6-11
Table 7-1.	Drift-Scale Test samples prepared for moisture-retention experiments.	7-3
Table 7-2.	Single-Heater Test samples prepared for moisture-retention experiments.	7-4
Table 7-3.	Sample characterization data.	7-7
Table 7-4.	Sorptivity (cm-hr ^{-1/2}) for the 20°C, 60°C, and 90°C isotherms.	7-9
Table 9-1.	RTDs suspected of malfunction.	9-1
Table 9-2.	Revised datum assignments for Borehole 80.	9-2
Table 9-3.	Revised locations for RTDs in Borehole 134.	9-3

Figures

Figure 1-1.	Configuration of the Drift-Scale Test.
Figure 1-2.	Plan view showing locations of floor and wing heaters.
Figure 1-3.	Layout of boreholes in the Drift-Scale Test.
Figure 2-1.	Configuration of temperature boreholes (RTD) in the Drift-Scale Test.
Figure 2-2.	Temperatures of radial RTD boreholes on May 30, 1998.

- Figure 2-3. Air temperatures in the heater drift, as a function of time.
- Figure 2-4. Temperatures of vertical boreholes as a function of vertical distance on February 28, 1998, and May 30, 1998.
- Figure 2-5. Temperature of vertical boreholes versus vertical distance from drift axis on May 30, 1998.
- Figure 2-6. Snapshot of the temperatures of Borehole 80, as a function of horizontal distance.
- Figure 2-7. Snapshot of the temperatures of Borehole 79, as a function of horizontal distance.
- Figure 2-8. Comparison of temperatures of Boreholes 79 and 80, as a function of horizontal distance, for February 28, 1998, and May 30, 1998.
- Figure 2-9. Snapshot of the temperatures in Boreholes 137 and 141, as a function of vertical distance.
- Figure 2-10. Temperatures of upward and downward boreholes at 12 m from the bulkhead, as a function of vertical distance, on February 28, 1998, and May 30, 1998.
- Figure 2-11. Snapshot of the temperatures of Boreholes 139 and 143, as a function of horizontal distance.
- Figure 2-12. Temperature evolution of the DST along Boreholes 139 and 143.
- Figure 2-13. Temperatures at some selected RTD locations in Borehole 139, as a function of elapsed time.
- Figure 2-14. Temperatures at some selected RTD location in Borehole 143, as a function of elapsed time.
- Figure 2-15. Snapshots of the temperatures of Boreholes 158 and 162, as a function of vertical distance.
- Figure 2-16. Snapshots of the temperatures of Boreholes 158 through 165, as a function of vertical distance, on February 28, 1998, and May 30, 1998.
- Figure 2-17. Snapshot of the temperatures in Boreholes 160 and 164, as a function of horizontal distance.
- Figure 2-18. Temperature evolution of the DST along of Boreholes 160 and 164.
- Figure 2-19. Temperature of Borehole 160.
- Figure 2-20. Temperatures at some selected RTDs of Borehole 164, as a function of elapsed time. The symbols are not exact data points; they are to identify the temperature curves.
- Figure 2-21. Snapshot of temperatures in Boreholes 170 and 173, as a function of vertical distance from the HD axis. The symbols are not exact data points; they are to identify the temperature curves.
- Figure 2-22. Snapshot of temperatures in Boreholes 170 to 175 on February 28, 1998, and May 30, 1998, as a function of vertical distance from the HD. The symbols are not exact data points; they are to identify the temperature curves.
- Figure 3-1. Perspective view showing the location and names of the ERT boreholes relative to the HD and AOD.
- Figure 3-2. Cross-section parallel to the HD showing the location of ERT boreholes.
- Figure 3-3. Two cross-sections orthogonal to the HD showing the location of ERT boreholes drilled from the AOD and selected boreholes drilled from the HD.

- Figure 3-4. Tomographs of electrical resistivity ratio along a cross-section parallel to the HD; tomographs located above the crown and below the invert of the HD are shown.
- Figure 3-5. Tomographs of electrical resistivity ratio along a cross-section that is orthogonal to the HD and near the bulkhead.
- Figure 3-6. Tomographs of electrical resistivity ratio along a cross-section that is orthogonal to the HD and near its middle, and coincident with the AOD 5 boreholes as shown in Figure 3-2 and Figure 3-3.
- Figure 3-7. Estimates of saturation change according to Model 2, along a cross-section parallel to the HD.
- Figure 3-8. Estimates of saturation change according to Model 2 along a cross-section orthogonal to the HD, near the bulkhead, and coincident with the AOD 1 boreholes shown in Figure 3-2 and Figure 3-3.
- Figure 3-9. Estimates of saturation change according to Model 2 along a cross-section orthogonal to and near the middle of the HD, and coincident with the AOD 5 boreholes.
- Figure 3-10. Estimates of saturation change according to Model 2 along a cross-section orthogonal to and near the middle of the HD, and coincident with the AOD 5 boreholes.
- Figure 3-11. Comparison of NUFT-calculated temperatures (left image) and temperatures based on interpolation of measured temperature values. The cross section shown is the same as that in Figure 3-10.
- Figure 4-1. Baseline fraction volume water content in Borehole 47 (N01).
- Figure 4-2. Baseline fraction volume water content in Borehole 48 (N02).
- Figure 4-3. Baseline fraction volume water content in Borehole 49 (N03).
- Figure 4-4. Baseline fraction volume water content in Borehole 50 (N04).
- Figure 4-5. Baseline fraction volume water content in Borehole 51 (N05).
- Figure 4-6. Baseline fraction volume water content in Borehole 64 (N06).
- Figure 4-7. Baseline fraction volume water content in Borehole 65 (N07).
- Figure 4-8. Baseline fraction volume water content in Borehole 66 (N08).
- Figure 4-9. Baseline fraction volume water content in Borehole 67 (N09).
- Figure 4-10. Baseline fraction volume water content in Borehole 68 (N10).
- Figure 4-11. Baseline fraction volume water content in Borehole 79 (N11).
- Figure 4-12. Baseline fraction volume water content in Borehole 80 (N12). The data on 8/25/97 were collected before grouting.
- Figure 4-13. Difference fraction volume water content in Borehole 47 (N01), measured on 2/17/98 and 3/16/98.
- Figure 4-14. Difference fraction volume water content in Borehole 47 (N01), measured on 4/22/98 and 5/19/98.
- Figure 4-15. Difference fraction volume water content in Borehole 48 (N02), measured on 2/18/98 and 3/16/98.
- Figure 4-16. Difference fraction volume water content in Borehole 48 (N02), measured on 4/22/98 and 5/19/98.

- Figure 4-17. Difference fraction volume water content in Borehole 49 (N03), measured on 12/19/97, 2/6/98, and 3/16/98.
- Figure 4-18. Difference fraction volume water content in Borehole 49 (N03), measured on 4/21/98 and 5/19/98.
- Figure 4-19. Difference fraction volume water content in Borehole 50 (N04), measured on 12/18/97, 2/6/98, and 3/16/98.
- Figure 4-20. Difference fraction volume water content in Borehole 50 (N04), measured on 4/21/98 and 5/19/98.
- Figure 4-21. Difference fraction volume water content in Borehole 51 (N05), measured on 2/6/98 and 3/17/98.
- Figure 4-22. Difference fraction volume water content in Borehole 51 (N05), measured on 4/21/98 and 5/19/98.
- Figure 4-23. Difference fraction volume water content in Borehole 64 (N06), measured on 2/17/98 and 3/17/98.
- Figure 4-24. Difference fraction volume water content in Borehole 64 (N06), measured on 4/20/98 and 5/18/98.
- Figure 4-25. Difference fraction volume water content in Borehole 65 (N07), measured on 2/17/98 and 3/17/98.
- Figure 4-26. Difference fraction volume water content in Borehole 65 (N07), measured on 4/20/98 and 5/18/98.
- Figure 4-27. Difference fraction volume water content in Borehole 66 (N08), measured on 12/18/97, 2/11/98, and 3/17/98.
- Figure 4-28. Difference fraction volume water content in Borehole 66 (N08), measured on 4/20/98 and 5/18/98.
- Figure 4-29. Difference fraction volume water content in Borehole 67 (N09), measured on 12/18/97, 2/11/98, and 3/18/98.
- Figure 4-30. Difference fraction volume water content in Borehole 67 (N09), measured on 4/15/98 and 5/18/98.
- Figure 4-31. Difference fraction volume water content in Borehole 68 (N10), measured on 2/11/98 and 3/16/98.
- Figure 4-32. Difference fraction volume water content in Borehole 68 (N10), measured on 4/21/98 and 5/18/98.
- Figure 4-33. Difference fraction volume water content in Borehole 79 (N11), measured on 2/29/98 and 3/12/98.
- Figure 4-34. Difference fraction volume water content in Borehole 79 (N11), measured on 4/23/98 and 5/20/98.
- Figure 4-35. Difference fraction volume water content in Borehole 80 (N12), measured on 2/18/98 and 3/12/98.
- Figure 4-36. Difference fraction volume water content in Borehole 80 (N12), measured on 4/23/98 and 5/20/98.
- Figure 5-1. Chemistry Boreholes 52–56 and 69–73.

- Figure 5-2. Percent CO₂ for discrete gas samples collected between December 1997 and April 1998. These are averaged values based on samples “D”, “E”, and “F” (in the case of boreholes gases) or averages of all the measured values for atmospheric samples collected during a particular trip.
- Figure 5-3. Gas analyses of heater-drift atmosphere, sampled during April 1998.
- Figure 5-4. Gas analyses of heater-drift atmosphere, sampled during June 1998.
- Figure 5-5. Gas analyses of connecting-drift atmosphere, sampled during April 1998.
- Figure 5-6. Gas analyses of connecting-drift atmosphere, sampled during June 1998.
- Figure 5-7. Gas analyses of Borehole 54, sampled during June 1998. O₂ and CO₂ readings appear to depend on sampling port.
- Figure 5-8. Gas analyses of Borehole 55, sampled during June 1998. Differences between the two channels measuring O₂ and CO₂ are insignificant.
- Figure 5-9. Gas analyses of hydrology Borehole 59, zone 4, sampled during June 1998. A slight trend toward higher O₂ and CO₂ values is measured over this time period.
- Figure 5-10. CO₂ analyses of hydrology Borehole 59 and nearby chemistry Borehole 54.
- Figure 5-11. Gas analyses of access/observation-drift atmosphere, sampled during June 1998. Three channels each sample and measure O₂ and CO₂ and do not display significantly different values.
- Figure 5-12. CO₂ levels observed in the heater-drift atmosphere and air-pressure readings obtained during corresponding time intervals.
- Figure 6-1. Heater and drift layout in the TH model of the Drift-Scale Test.
- Figure 6-2. Vertical cross section of the HD, showing the radiation connections in the TH model.
- Figure 6-3. Barometric-pressure history that is represented in all unheated drifts in the TH model.
- Figure 6-4. Distribution of (a) temperature and (b) liquid-phase saturation on a horizontal plane through $z = 0.4$ m, at 87 days.
- Figure 6-5. Distribution of (a) temperature and (b) liquid-phase saturation on a horizontal plane through $z = 0.4$ m, at 178 days.
- Figure 6-6. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 2.8$ m, transverse to the axis of the drift heaters, at 87 days.
- Figure 6-7. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 11.9$ m, transverse to the axis of the drift heaters, at 87 days.
- Figure 6-8. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 23.0$ m, transverse to the axis of the drift heaters, at 87 days.
- Figure 6-9. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 39.2$ m, transverse to the axis of the drift heaters, at 87 days.
- Figure 6-10. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 2.8$ m, transverse to the axis of the drift heaters, at 178 days.
- Figure 6-11. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 11.9$ m, transverse to the axis of the drift heaters, at 178 days.
- Figure 6-12. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 23.0$ m, transverse to the axis of the drift heaters, at 178 days.

- Figure 6-13. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 39.2$ m, transverse to the axis of the drift heaters, at 178 days.
- Figure 6-14. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 133 at (a) 87 days and (b) 178 days.
- Figure 6-15. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 134 at (a) 87 days and (b) 178 days.
- Figure 6-16. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 137 at (a) 87 days and (b) 178 days.
- Figure 6-17. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 141 at (a) 87 days and (b) 178 days.
- Figure 6-18. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 158 at (a) 87 days and (b) 178 days.
- Figure 6-19. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 162 at (a) 87 days and (b) 178 days.
- Figure 6-20. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 170 at (a) 87 days and (b) 178 days.
- Figure 6-21. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 173 at (a) 87 days and (b) 178 days.
- Figure 6-22. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 139 at (a) 87 days and (b) 178 days.
- Figure 6-23. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 143 at (a) 87 days and (b) 178 days.
- Figure 6-24. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 160 at (a) 87 days and (b) 178 days.
- Figure 6-25. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 164 at (a) 87 days and (b) 178 days.
- Figure 6-26. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 79 at (a) 87 days and (b) 178 days.
- Figure 6-27. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 80 at (a) 87 days and (b) 178 days.
- Figure 6-28. Profiles, for two TH models, of (a) temperature and (b) liquid-phase saturation along a horizontal line transverse to the midpoint ($y = 23.0$ m) of the HD.

- Figure 6-29. Springline temperature history (a) at the midpoint of the HD for three TH models and relative humidity (b) adjacent to heater 5 at the midpoint of the HD.
- Figure 6-30. Thermal-hydrologic conditions are given for the vicinity of the thermal bulkhead.
- Figure 7-1. Matric potential versus average saturation for 13 DST samples at 25.1°C.
- Figure 7-2. Matric potential versus average saturation for 13 DST samples at 93.7°C.
- Figure 7-3. Matric potential versus average saturation for 13 DST samples at 49.6°C.
- Figure 7-4. Matric potential versus average saturation for 11 SHT samples at 25.1°C.
- Figure 7-5. Matric potential versus average saturation for 11 SHT samples at 49.6°C.
- Figure 7-6. Matric potential versus average saturation for 11 SHT samples at 93.7°C.
- Figure 7-7. Schematic of the experimental apparatus.
- Figure 7-8. Typical response and control for the temperature and relative humidity in the sample chamber.
- Figure 7-9. Typical sample-weight versus time for an isotherm.
- Figure 7-10. Typical early time data selected for curve fitting to $w(t) = \text{Sat}^{1/2}$.
- Figure 7-11. Sorptivity coefficient vs. effective porosity for the $T = 20^\circ\text{C}$ isotherm (scatter plot).
- Figure 7-12. Sorptivity coefficient vs. temperature.
- Figure 8-1. Barometric pressure versus relative humidity for selected sensors.
- Figure 8-2. Photograph of condensation near the heater drift bulkhead.
- Figure 8-3. Location of nine thermocouples on the bulkhead inside the HD.
- Figure 8-4. Bulkhead temperature.
- Figure 8-5. Bulkhead temperature and heater drift barometric pressure.
- Figure 8-6. Bulkhead temperature at times of high and low barometric pressure.

Abbreviations and Acronyms

2-D	two-dimensional
3-D	three-dimensional
AOD	access/observation drift
CD	connecting drift
CPN	Campbell Pacific Nuclear
CRWMS M&O	Civilian Radioactive Waste Management System Management and Operating Contractor
DAS	data-acquisition system
DFM	discrete-fracture method
DKM	dual-permeability method
DST	Drift-Scale Test
DTN	data tracking number
ECM	equivalent-continuum method
ERT	electrical-resistance tomography
ESF	Exploratory Studies Facility
HD	heater drift
IC	ion chromatography
ICP	inductively coupled plasma (atomic emission spectroscopy)
ISP	Individual Software Plan
LBNL	Lawrence Berkeley National Laboratory
LBT	Large-Block Test
LLNL	Lawrence Livermore National Laboratory
NFE	near-field environment
NUFT	Nonisothermal Unsaturated-Saturated Flow and Transport
RTD	resistance–temperature device
SHT	Single-Heater Test
SMF	sample management facility
TH	thermohydrologic
THCM	thermal-hydrologic-chemical-mechanical
TSPA-VA	Total System Performance Assessment—Viability Assessment
WP	waste package
YMP	Yucca Mountain Site Characterization Project

Acknowledgments

The authors gratefully acknowledge the assistance of Pete Gaughan and Karen L. Lew in editing and preparation of the manuscript and Paul Harding for preparation of the graphics. Stephanie Wood provided assistance in preliminary data reduction, and Jeff Wagoner provided assistance with display of the DST borehole layout.

1. Introduction

by Stephen C. Blair

The Drift-Scale Test (DST) is one of the thermal tests being conducted in the Exploratory Studies Facility (ESF) at Yucca Mountain, Nevada, site of the potential repository for high-level nuclear waste. One of the DST's major objectives is to study the coupled thermal-hydrologic-chemical-mechanical (THCM) processes at the potential repository's horizon. The objectives, test design, and test layouts of the DST are included in a previous test design report (CRWMS M&O, 1996).

This report presents results and analysis of several different measurements made in the DST by researchers at Lawrence Livermore National Laboratory (LLNL) through the second quarter of the heating phase (end of May 1998). Sections 1.1 and 1.2 describe the layout of the DST and the boreholes and instrumentation used to monitor the THCM processes in the rock of associated drifts. Section 2 presents an analysis of temperature data for the test through the end of May 1998. Sections 3 and 4 present results of electrical resistance tomography and neutron logging measurements, respectively. These two sets of measurements are designed to determine the movement of moisture in the test. Results of a series of geochemical measurements made on gas and water samples are presented in Section 5. The purpose of these measurements is to monitor the chemical processes occurring in the DST. Section 6 presents results of thermohydrologic modeling analysis of the test, and Section 7 presents data collected via laboratory testing for characterization of the hydrologic properties of the rock forming the DST. A brief analysis of barometric pressure and humidity data collected through the end of May 1998 is discussed in Section 8, along with temperature data for the bulkhead. Finally, Section 9 presents an evaluation of sensors used in the DST.

1.1 Drift-Scale Test Layout

The DST is located in Alcove 5 in the ESF. Alcove 5 is 2.83 km inward from the North Portal of the ESF Main Drift, just past the southward (left) bend of the tunnel. The configuration of the DST is shown in **Figure 1-1**. This figure shows that the drifts comprising the DST are laid out in the shape of a backward "J". The shank of the J is formed by the access/observation drift (AOD). The bottom of the J is termed the connecting drift, and the hook of the J is the heater drift (HD). The AOD is oriented approximately east-west and intersects the Main Drift at approximately a right angle. This drift slopes downward, away from the Main Drift, with an inclination ranging from 11.5 to 14% below horizontal. This downward slope is designed to provide access to the middle nonlithophysal unit of the Topopah Spring Tuff. In particular, at the elevation of the DST, the overburden (rock above the drift) includes at least 10 m of middle nonlithophysal Topopah Spring tuff. The AOD is approximately 136 m long. At the end of the AOD, the connecting drift breaks out to the north for a length of approximately 40 m. At the end of the connecting drift, the HD breaks out westward. The pillar between the AOD and the HD is approximately 30 m thick. The HD consists of an 11-m-long entry, which includes a plate-loading niche, and a 47-m-long heated drift. This drift is essentially horizontal. The nominal diameter of the drifts is 5 m. The detailed configuration of the DST, including diagrams showing the drift and borehole layout, is included in the test design report (CRWMS M&O, 1996).

Figure 1-1. Configuration of the Drift-Scale Test.

The rock mass being monitored in the DST is being heated by electrical heaters placed on the invert of the HD and in horizontal wing-heater boreholes. The layout of the heaters is shown in **Figure 1-2**. Scoping model calculations have been conducted to determine heater specifications, such as power output and duration (Birkholzer and Tsang, 1997; Buscheck and Nitao, 1995; Buscheck et al., 1997). Criteria for determining the heater specifications include the maximum temperature in the drift wall, the volume of rock to be heated, and the volume of rock to be dried by heating. The heating system includes a means to control heater output in accordance with predetermined heating/cooling schedules.

Figure 1-2. Plan view showing locations of floor and wing heaters.

The heated section of the HD is nominally 47.5 m long and houses 9 floor heaters along its centerline. There are 50 wing heaters uniformly spaced in 11.5-m-deep boreholes that are drilled into the two side walls of the HD (Figure 1-2). The total heat output available for the floor and wing heaters is approximately 68 kW and 143 kW, respectively. The test design calls for four years of heating, which calculations indicate will create a drying zone around the HD extending approximately 10 m into the surrounding rock. During the heating phase, drift-wall temperatures should not exceed 200°C.

1.2 Monitoring of the DST

The coupled THCM behavior of the DST is being monitored using a wide variety of instrumentation that is deployed in a series of boreholes or mounted inside the HD, the connecting drift, and the AOD. This report describes and presents results of the subset of studies being conducted in the DST under the direction of LLNL scientists. Nearly 200 boreholes were drilled to provide for scientific monitoring of the DST. These boreholes include several suites of boreholes drilled from inside the HD, several other suites of boreholes drilled from the AOD perpendicular to the HD, and a few boreholes drilled parallel to the HD. The relative geometry of boreholes in these cross sections is shown in **Figure 1-3**. Particular subsets of boreholes used for each type of measurement are presented in each respective subsection.

Figure 1-3. Layout of boreholes in the Drift-Scale Test.

(a) plan view

(b) longitudinal cross section A-A' (looking towards the access/observation drift)

(c) cross section B-B' (perpendicular to the heater drift, looking towards the connecting drift)

The DST temperature and heater-power data from November 7, 1997, to December 3, 1997, acquired by the Data-Collection System, will be submitted to TDIF by the CRWMS M&O under data-tracking number MO9807DSTSET01.000.

1.3 References

Birkholzer, J.T., and Y.W. Tsang (1997). *Pretest Analysis of the Thermal-Hydrological Conditions of the ESF Drift Scale Test*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (SP9322M4) Berkeley, CA: Lawrence Berkeley National Laboratory. [MOL.19971201.0805]

- Buscheck, T.A., and J.J. Nitao (1995). *Thermal-Hydrological Analysis of Large-Scale Thermal Tests in the Exploratory Studies Facility at Yucca Mountain*. (UCRL-ID-121791) Livermore, CA: Lawrence Livermore National Laboratory. [MOL.19960501.0392; 223657]
- Buscheck, T.A., R.J. Shaffer, and J.J. Nitao (1997). *Pretest Thermal-Hydrological Analysis of the Drift-Scale Thermal Test at Yucca Mountain*. (SP9318M4) Livermore, CA: Lawrence Livermore National Laboratory.
- CRWMS M&O (1996). *Test Design, Plans, and Layout for the First ESF Thermal Test*. (BAB000000-01717-4600-00025, Rev. 1) Las Vegas, NV: Civilian Radioactive Waste Management System Management and Operating Contractor: TRW Environmental Safety Systems, Inc. [MOL.19970114.0166]

Reference only (scale approximate)

Figure 1-1. Configuration of the Drift-Scale Test.

Figure 1-3a. Relative geometry of boreholes, in cross sections 12, 23, and 39 m from the bulkhead (a) top view.

1. Figures

Figure 1-3c. Side view of cross section B-B' in Figure 1-3a.

2. Temperature Measurements

by Stephen C. Blair, Wunan Lin, and Dale Wilder

2.1 Introduction

This section presents temperature data collected up to and including the second quarter of Drift-Scale Test (DST) heating phase and a brief discussion of the layout of the DST and design of the temperature measurements. The overall thermal response of the rock during the reporting period is presented by discussing temperature data as a function of location and time for several of the boreholes used for temperature measurements.

2.2 Heating in the Drift-Scale Test

Heating in the DST was started on December 3, 1997, and electrical power to the heaters is being monitored and reported by one of the other participants. During the first quarter of heating, 136 kW of power was supplied to the wing heaters, and 52 kW of power was supplied to the canister (floor) heaters. Temperatures of the canister and wing heaters and of the air in the heater drift (HD) are also being monitored as is the temperature of the upper portion of the drift wall in the HD. These temperature data are reported elsewhere (SNL, 1998).

This section presents temperature data through May 30, 1998, for temperatures monitored in the rock mass and in the air in the drift. Rock-mass temperatures in the DST are being measured primarily using resistance temperature device (RTD) sensors in several boreholes. These boreholes are listed in Table 2-1, and the approximate locations of these holes are shown in **Figure 2-1**.

Table 2-1. Temperature (RTD) boreholes.

Distance from bulkhead	Borehole number	Orientation (degrees) ^a
3 m	133	0
	134	180
12 m	137	0
	138	-45
	139	-90
	140	-135
	141	180
	142	135
	143	90
	144	45
23 m	158	0
	159	-45
	160	-90

2. Temperature Measurements

Distance from bulkhead	Borehole number	Orientation (degrees) ^a
	161	–135
	162	180
	163	135
	164	90
	165	45
32 m	168	0
	169	180
39 m	170	0
	171	–45
	172	–135
	173	180
	174	135
	175	45
N/A (parallel to drift axis)	79	Parallel to the HD
	80	Parallel to the HD

^a Positive angles are measured clockwise when looking into the HD from the bulkhead (see Figure 1-3). 0° indicates a vertical borehole in the roof of the HD; 180° indicates a vertical borehole in the floor of the HD.

Figure 2-1. Configuration of temperature boreholes (RTD) in the Drift-Scale Test.

Vertical profiles of the temperature field above and below the HD axis are measured at five locations: 3, 12, 23, 32 and 39 m from the bulkhead (Figure 2-1). Temperature is also monitored in three cross sections perpendicular to the axis of the HD. These cross sections provide radial coverage of the temperature field around the HD and are located at approximately 12, 23, and 39 m from the bulkhead. Temperature in the cross sections at 12 and 23 m is being monitored using 8 boreholes and in the cross section at 39 m using 6 boreholes (Table 2-1). These holes are also shown in Figure 1-3 of this report.

Two other temperature boreholes (Boreholes 79 and 80) are also listed in Table 2-1 and shown in Figure 2-1 and Figure 1-3. These boreholes are parallel to the axis of the HD and directly above the midplane of the wing heaters on either side of the HD. These boreholes are approximately 1 m above the drift crown (Figure 2-1). The purpose of these boreholes is to monitor temperature in the region where long-term boiling is expected, assess the heterogeneity in temperature along the axis of the drift, and monitor temperatures at the ends of the heated zone for estimation of end effects.

The as-built xyz coordinates of the collar and bottom of those boreholes are provided by the Test Coordinating Office with a data-tracking number (DTN) LANE834244AQ97.001. These are further documented in deliverable SPY195M4 (Lin and Wagoner, 1998). Locations of RTDs in Borehole 134 were updated by Blair (Blair and Lin, 1998) and the updated locations are used here.

2.3 Temperature Observations: December 3, 1997, to May 30, 1998

2.3.1 Overview of Temperature Field

Heating of the DST began on December 3, 1997, and continued uninterrupted throughout the reporting period (the minor and short power interruptions did not affect the overall test). Temperature data for the radial RTD boreholes on May 30, 1998, are shown in a perspective plot in **Figure 2-2**. Borehole locations are identified by looking toward the bulkhead from a point beyond the end of the HD. This plot shows that, as expected, temperatures are highest near the drift wall and in the plane of the wing heaters. The temperature field appears to be uniform along the length of the HD and is more or less symmetric about the vertical plane along the drift axis. Temperatures at the top of the drift and along the wing heaters are well above the boiling point of water (110 to 120°C). The highest temperatures occur along one of the horizontal holes (135°C); these holes are near the wing heaters. The highest temperature gradients appear to be at the outside ends of the wing heaters.

Figure 2-2. Temperatures of radial RTD boreholes on May 30, 1998.

Air temperatures are plotted in **Figure 2-3**, which shows that air temperatures in the drift were $100^{\circ} \pm 5^{\circ}\text{C}$ after 87 days of heating and had increased to $118^{\circ} \pm 6^{\circ}\text{C}$ after 178 days of heating. The variations in temperature are caused by varying locations of the RTDs in the HD.

Figure 2-3. Air temperatures in the heater drift, as a function of time.

The symbols are not exact data points; they are to identify the temperature curves.

2.3.2 Vertical Profiles Along Heater-Drift Axis

Temperatures in vertical profiles along the drift axis are being monitored at the following distances from the bulkhead:

Borehole 133 and Borehole 134	=	3 m
Borehole 137 and Borehole 141	=	12 m
Borehole 158 and Borehole 162	=	23 m
Borehole 168 and Borehole 169	=	32 m
Borehole 170 and Borehole 173	=	39 m

At each of these distances, RTD temperature sensors have been installed along the length of one upward and one downward vertical borehole. Temperatures observed in these boreholes, after 178 days of heating, are shown in **Figure 2-4** and **Figure 2-5**.

Figure 2-4. Temperatures of vertical boreholes as a function of vertical distance on February 28, 1998, and May 30, 1998.

The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-5. Temperature of vertical boreholes versus vertical distance from drift axis on May 30, 1998.

The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-4 shows temperature as a function of vertical distance for each of these vertical boreholes. This plot shows that, as expected, temperatures were highest near the drift and declined exponentially with distance and that, at the end of May, the influence of heating in the vertical direction extended to about 16 m from the center of the drift. This is an increase of 4 m over that observed on February 28, when rock at distances greater than 12 m from the drift axis was at ambient temperature. Temperatures in the rock above the drift were greater than those below the drift. For example, in Borehole 133 and Borehole 134 on May 30, 1998, at 4 m from the center of the drift, temperatures in the rock above the drift were about 15°C higher than temperatures the same distance below the center of the drift; at 8 m from the center of the drift, the rock above the drift was 2°C warmer. The possible causes of this phenomenon include convection of the air in the HD and the fact that the invert of the HD is constructed of concrete that is about 1.2 m thick. Moreover, at the end of May, rock near the top of the drift had reached temperatures ranging from 110°C to 120°C (Boreholes 133, 137, 158, and 170 at a vertical distance of approximately 2.5 m from the axis of the HD). However, the measured temperatures show no evidence of boiling (i.e., constant temperature at the boiling point of water) in these holes. This is probably due to the fact that the zone of the rock mass in which the temperature had reached the boiling point of water was only about 1 m thick and, therefore, there was not enough water in the rock mass to sustain boiling.

Temperature variations among the five profiles appear to be small, indicating that, in this vertical plane, the rock is heating uniformly along the length of the drift between 3 and 39 m from the bulkhead. Comparison of data for the May and February dates (Figure 2-4) illustrates that temperatures have increased with time and that the relative difference between temperature profiles above and below the drift may have increased.

Figure 2-5 shows temperatures, plotted as a function of distance from the drift axis, on May 30, 1998, in these same 10 vertical boreholes. This plot more clearly delineates temperature differences between the top and bottom of the drift and shows a more uniform temperature distribution below the drift than above. To minimize temperature differences in the drift, the canister heaters were designed to have a uniform surface temperature. Again, no evidence of boiling was found, even though temperatures were well above the boiling point at the later times shown.

2.3.3 End Effects in Axial Direction

The purpose of Boreholes 79 and 80 is to provide temperature information along the axis of the drift in the regions where a boiling front is expected to develop. These boreholes also provide temperature data in the region of high thermal gradients at either end of the HD. These measurements are intended to provide constraints on model simulations of the test to identify the end effects of the HD. These boreholes were designed to be located about 3.75 m above the midpoint of the wing heaters.

Temperature data in Borehole 80, as a function of distance from the bulkhead and at several times are shown in **Figure 2-6**. This borehole is located approximately 3.75 m above the wing-heater plane and is centered over the wing heaters on the access/observation drift

(AOD) side of the HD. From December 1997 through February 1998, overall temperatures above the wing heaters rose steadily and uniformly over the entire length, except for the first and last 6 m, of the drift.

During the first two months, the temperature increases were quite uniform over the central 36 m of the drift length. There was a slight decrease around 26 to 40 m, but the maximum temperatures were about the same at either end of the drift as they were between approximately 8 and 20 m. Although temperatures continued to rise as heating continued, they were no longer symmetrical about the center of the drift. There was a notably lower temperature at the far end of the drift, and the decrease in temperature between 24 and 38 m became more dramatic. Thus, maximum temperature in February occurred at approximately 8 to 10 m from the bulkhead.

Figure 2-6. Snapshot of the temperatures of Borehole 80, as a function of horizontal distance.

The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-6 also shows that, from March through May 1998, temperatures in the region from 14 to 24 m from the bulkhead became much higher than those in the rest of the drift. In this zone, temperatures were about 8°C hotter than in the rest of the heated zone of this borehole at the end of May. The cause of this temperature anomaly is yet unclear. Possible causes include nonuniform heater power output and localized “heat pipes” to transport the heat more effectively. However, if this high temperature anomaly is caused by nonuniform heating, one would expect to have observed the phenomenon earlier, unless the nonuniform heating did not occur until March 1998. The heater power supplied in this region will be checked. Higher-than-expected temperatures were also observed in Borehole 160, which is located approximately 23 m from the bulkhead (see Section 2.3.5.2).

Moreover, heating is localized; temperatures drop rapidly in regions outside the interval containing the heaters (Figure 2-6). The steep thermal gradient on both ends of the HD is probably caused by the end effect of the heated zone. The lower temperatures (relative to other portions of the HD) at distances between 32 and 40 m may be due to the concrete liner emplaced at the far end of the HD (from 34.75 to 47.50 m from the bulkhead). The deepest point surveyed in this borehole is approximately 22 m from the bulkhead. The deeper half of this borehole deviates from its original course, but this deviation has no apparent effect on the temperature.

Figure 2-7 presents temperatures observed in Borehole 79 at a series of times as a function of distance from the bulkhead. Data for this hole are somewhat difficult to interpret due to uncertainty in the location of the sensors, because the hole curves and could not be surveyed at depths beyond approximately 10 m past the bulkhead. However, the distance of the RTDs from the borehole collar, which is approximately 11 m on the other side of the bulkhead, is known; this makes it possible to use the temperatures measured in this hole to make qualitative observations. The temperature in this borehole showed a steady increase at distances beyond 10 m from the bulkhead. This is an indication that this borehole may have sloped downward toward the heater plane at distances beyond the surveyed point. There is a smooth rise in temperature in this borehole between December 3, 1997, and February 28, 1998.

Figure 2-7. Snapshot of the temperatures of Borehole 79, as a function of horizontal distance.

The symbols are not exact data points; they are to identify the temperature curves.

However, a high-temperature region, centered at approximately 12.5 m from the bulkhead, began to develop in late March and continued to grow during April and May (Figure 2-7). The temperature data on January 30 show that the thermal gradient is constant from approximately 12 to 26 m. Because this gradient is a function of the borehole deviation, it may indicate a uniform inclination of the borehole toward the heater plane. This gradient remained constant in February and March, although the regions where it was applicable became smaller.

Interestingly, if this constant slope line were projected from the region from approximately 16 to 24 m, where it still fits the data, back to the data around 8 m, it would match those few data points. Superimposing this data trend on the April and May data shows that this anomaly has a horizontal dimension of approximately 9 m along the borehole and occurs at 7.5 to 16 m from the bulkhead. The peak temperature is approximately 15 to 17°C warmer than it is in adjacent regions on May 30, 1998.

This anomaly is quite similar to that observed in Borehole 80, but it occurs closer to the bulkhead. Similar to a preceding comment, this may indicate some type of structural (fracture) influence on the temperatures or that heater output varied on both sides of the drift. The latter would be surprising, unless the wing heaters were wired such that heaters on either side of the drift had a common controller and that the heater power varied with time. The slope of temperature versus distance from 24 m to 40 m continued to increase with time. There is no identified mechanism that would explain this, and the trend is opposite that observed in Borehole 80. The fractures in the borehole have been videotaped, and this videotaped information will be used when analyzing results.

Figure 2-8 plots temperatures on May 30 and February 28 for Boreholes 79 and 80, for the region between the connecting drift and 10 m beyond the bulkhead. On February 28, the temperatures in the two boreholes matched well, indicating a symmetric temperature field about the vertical centerline of the HD at that time. May 30 data for the two boreholes show that, between -10 m and +5 m from the bulkhead, the temperatures match well, with Borehole 80 showing temperatures 2 to 4°C higher than those of Borehole 79; beyond 6 m, however, the effect of the high-temperature region in Borehole 79 (discussed in a previous paragraph) is apparent.

Figure 2-8. Comparison of temperatures of Boreholes 79 and 80, as a function of horizontal distance, for February 28, 1998, and May 30, 1998.

2.3.4 Vertical Cross Section at 12 m from Bulkhead

2.3.4.1 Vertical and Inclined Boreholes

Figure 2-9 shows temperature in Boreholes 137 and 141 at a series of times. These boreholes are vertical upward and downward, respectively, as shown on the inset of Figure 2-9. Temperature is plotted as a function of vertical distance from the axis of the HD. The first few meters of rock above the drift is being heated faster than rock at the equivalent distance

below the drift. There is a smooth increase in temperature with time for this profile; at 12 m below and 16 m above the HD axis, rock was still at approximately ambient temperature on May 30.

Figure 2-9. Snapshot of the temperatures in Boreholes 137 and 141, as a function of vertical distance.

The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-10 shows temperatures on May 30 and February 28 for the vertical upward and downward boreholes in the 12-m cross section and for the boreholes inclined at $\pm 45^\circ$ and $\pm 135^\circ$. Temperature is plotted as a function of vertical distance from the HD axis.

Figure 2-10. Temperatures of upward and downward boreholes at 12 m from the bulkhead, as a function of vertical distance, on February 28, 1998, and May 30, 1998.

The symbols are not data points; they are to identify the temperature curves.

At 12 m from the bulkhead, the boreholes above the HD axis include Borehole 137 oriented at 0° (vertical upward) and Boreholes 138 and 144 oriented at -45° and $+45^\circ$, respectively (see Table 2-1). Data for these boreholes indicate that the temperature field above the HD in the 12-m cross section is very symmetric about a vertical plane through the axis of the HD. Temperature is highest directly above the HD, showing values of about 120°C on May 30; temperature distributions versus distance above the HD axis are identical for the two sides of the HD and are approximately 12°C lower than the temperatures directly above the drift. Note that the vertical distance of an RTD from the HD axis is the same as its distance from the collar for the vertical boreholes (Boreholes 137 and 141). For the inclined boreholes (Boreholes 138, 140, 142, and 144), however, the vertical distance is smaller than the distance from the collar. The difference in temperature indicates that regions above the wing heaters are being heated evenly but at a slightly lower rate than is the rock above the HD. Data for February 28 are also shown in Figure 2-10. Comparison of data for holes above the HD shows that, although temperature had increased, the temperature gradient in the rock had decreased somewhat. Moreover, the symmetric temperature distribution indicates that, as of May 30, the DST was successfully progressing toward the goal of developing a horizontally planar heated zone above the HD.

Boreholes below the HD axis include Borehole 141 oriented at 180° (vertical downward) and Boreholes 140 and 142 oriented at -135° and $+135^\circ$, respectively (see Table 2-1). Data for these boreholes show a very even temperature distribution in the downward direction: temperature at a given distance below the plane of the HD axis varies less than 5°C in any of the boreholes. Comparison of temperatures for May 30 and February 28 shows that, below the drift, temperature distributions were becoming more uniform and temperature gradients were decreasing as temperature increases. However, the temperature difference between Borehole 140 and Borehole 142 is greater than that between Borehole 138 and Borehole 144. This indicates that the temperature below the HD were not as symmetric as those above the HD. Data for these boreholes are consistent with data shown in Figure 2-4 and indicate that temperatures below the heater plane were lower than those at the same distance above the heaters; this difference indicates the importance of both convection and conduction as heat-transfer mechanisms.

2.3.4.2 Horizontal Boreholes

Figure 2-11, depicting temperature history for the horizontal boreholes in the 12-m cross section (Boreholes 139 and 143), shows several interesting features of the temperature in the horizontal plane:

- The temperature field was approximately symmetric about the HD up through late February, and Boreholes 139 and 143 showed indications of boiling in late February.
- The temperature field became more asymmetric after February 28. In particular, boiling persisted in Borehole 143 at least through March 30; the region involved in the apparent boiling was extended in March, and temperatures in Borehole 139 increased to about 101°C at depths of 5 m.
- A single high-temperature zone, centered at a depth of 7 m, developed in Borehole 139 during the months of March, April, and May. Peak temperatures in this zone were approximately 123°C on May 30. This zone is approximate 5 m wide. On each date, temperatures at depths of 10 to 14 m were relatively constant and about 10°C lower than the peak temperature. Temperature dropped sharply at depths of 13 to 14 m; this drop is associated with the end of outer wing heater. A slight “shelf” in the temperature values occurred at approximately 15 m depth and at a temperature of just below 100°C; this may be associated with persistent boiling at this location. Beyond 15 m, temperatures dropped off exponentially to ambient temperature at 22 m from the drift center.
- In contrast, temperature data for Borehole 143 indicate that boiling continued in this borehole at least until March 30. Subsequently, two high-temperature zones, which can be associated with the inner and outer zones of wing heaters, developed along this borehole. Moreover, these high-temperature zones were delineated by zones where temperatures dropped to boiling; these zones occur in the intervals between the drift wall and the first high-temperature zone and between the inner and outer wing heaters. The existence of these boiling zones may indicate that there is significantly more moisture present in the region around Borehole 143 than in Borehole 139. A slight shelf in the temperature values occurred at approximately 13 m depth and at a temperature just below 100°C; this may be associated with persistent boiling at this location. Beyond 13 m, temperatures dropped off exponentially to ambient temperature at 22 m from the drift center.
- Prior to February 28, temperature variations in Borehole 139 and Borehole 143 were correlated with the positions of the wing heaters. Lower temperatures were associated with the zone between the HD and inner wing heater and with the zone between the inner and outer wing heaters.
- Temperatures appear to have been higher on the south (–x or AOD) side of the HD, especially in zones influenced by the outer wing heaters. As mentioned previously, the apparent boiling phenomena indicate that the moisture content along Borehole 139 may be less than that along Borehole 143. This can also explain the greater temperatures in Borehole 139 because the thermal conductivity (2.1 W/m°K for saturated rock, and 1.6 W/m°K for dry rock) in a drier Topopah Spring tuff is less than that of a wetter rock. The presence of the AOD on this side of the HD does not appear to have influenced the temperature distribution.
- No evidence of boiling was found near the drift wall, which may indicate that drying had occurred in the first meter or so of rock around the drift wall.
- At distances beyond 14 m from the drift axis (i.e., beyond the end of the wing heaters), temperatures declined rapidly back to ambient levels.

Figure 2-11. Snapshot of the temperatures of Boreholes 139 and 143, as a function of horizontal distance.

Borehole 139 is toward the AOD.

Figure 2-12 shows data from Boreholes 139 and 143 as a surface. In this plot, the vertical axis represents temperature, and horizontal distance from the center of the drift is shown across the page. Time from the start of the test in days is shown increasing from the front to the back of the plot. This surface represents a linear interpolation of data presented in **Figure 2-11**. Temperatures shown within the drift ($-2.5 \text{ m} < x < 2.5 \text{ m}$) are not representative.

Figure 2-12. Temperature evolution of the DST along Boreholes 139 and 143.

The temperatures shown between -2.5 m and 2.5 m are an artifact of the surface rendering.

Figure 2-12 illustrates the overall symmetry of the temperature field over time. The level regions indicate that boiling occurred over some distance and/or during extended periods. This also effectively illustrates how the temperature field was becoming more asymmetric with time, with two high-temperature zones developing on the right side (Borehole 143) but only one high-temperature zone on the left (Borehole 139). Also, the boiling seemed to persist between the high-temperature peaks in Borehole 143. In addition, **Figure 2-12** illustrates the shelf at the far end of each heated zone before temperatures drop steeply to near ambient at the ends of the holes.

Figure 2-13 shows temperature data for selected RTDs in Borehole 139, plotted as a function of time from the start of the DST. RTDs 10 to 37 are located at depths associated with the extent of the wing heater, and RTDs 40 to 60 are at depths corresponding to intervals beyond the end of the wing heaters. Boiling in the borehole was clearly indicated by the constant values near 100°C for RTDs 10, 20, and 30 for the period 75 to 110 days. This behavior was expected. The suppressed temperatures shown by RTDs 35 to 42 during this same period were surprising. If heat were used to maintain a boiling pore water, one would expect less heat to conduct into adjacent regions, thus causing a change of slope, but not a decrease in temperature. These RTDs are located near the ends of the heated zone, and the drop in temperature during the time that boiling occurred along the heated zone may be associated with an increase in saturation at those locations. Increasing the saturation via influx of water would increase the heat capacity, which would, in turn, change the slope. Steam from the boiling zone might travel into a cooler region, condense, and percolate down to adjacent regions to cause a decrease in temperature.

Figure 2-13. Temperatures at some selected RTD locations in Borehole 139, as a function of elapsed time.

The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-14 shows data for Borehole 143. Boiling occurred for a longer time in this borehole, but the borehole did not exhibit the depressed temperatures at the end of the heated zone, except for a small decrease at RTD 39.

Figure 2-14. Temperatures at some selected RTD location in Borehole 143, as a function of elapsed time.

The symbols are not exact data points; they are to identify the temperature curves.

2.3.5 Vertical Cross Section 23 m from the Bulkhead

2.3.5.1 Vertical and Inclined Boreholes

Figure 2-15 shows temperature in Boreholes 158 and 162 at a series of times. These boreholes are vertical upward and downward, respectively, as shown on the inset to the figure. Temperature is plotted as a function of vertical distance from the axis of the HD. The first few meters of rock above the drift were being heated faster than was rock at the equivalent distance below the drift. This may be caused by convection in the HD and by the fact that the invert is a concrete slab about 1.2 m thick. This plot shows a smooth increase in temperature with time for this profile and also indicates that, at a vertical distance of 14 m for Borehole 162 and 16 m for Borehole 158 from the HD axis, rock was still at approximately ambient temperature on May 30.

Figure 2-15. Snapshots of the temperatures of Boreholes 158 and 162, as a function of vertical distance.

The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-16 shows temperatures, on May 30 and February 28, for the vertical upward and downward boreholes in this cross section and for the boreholes inclined at $\pm 45^\circ$ and $\pm 135^\circ$.

Figure 2-16. Snapshots of the temperatures of Boreholes 158 through 165, as a function of vertical distance, on February 28, 1998, and May 30, 1998.

The symbols are not exact data points; they are to identify the temperature curves.

Boreholes above the HD axis include Borehole 158 oriented at 0° (vertical upward) and Boreholes 159 and 165 oriented at -45° and $+45^\circ$ respectively (see Table 2-1). Data for these boreholes indicate that the temperature field above the HD in the 23-m cross section is very symmetric about a vertical plane through the axis of the HD. Temperature is highest directly above the HD, reaching values of 125°C or above near the drift wall. Temperature distributions versus distance above the HD axis are nearly identical for the two sides of the HD and are approximately 10°C lower than are the temperatures directly above the drift at the same vertical distance. Note that the vertical distances of the TRDs in Boreholes 159 and 165 are less than their distances from the collar in the borehole, whereas the vertical distance of the TRDs in Borehole 158 would be the same as their distances from the collar. This pattern is similar to that of temperatures shown in Figure 2-10 and indicates that regions above the wing heaters are being heated evenly and at a slightly lower rate than is the rock directly above the HD. Data for February 28 are also shown in Figure 2-16 ; comparison of data for boreholes above the HD shows that, although temperature has increased, the temperature

gradient in the rock has decreased somewhat. This symmetric temperature distribution indicates that, as of May 30, the DST was successfully progressing toward the goal of developing a horizontally planar heated zone above the HD.

Boreholes below the HD axis include Borehole 162 oriented at 180° (vertical downward) and Boreholes 161 and 163 oriented at -135° and +135° respectively (see Table 2-1). Data for these boreholes show an extremely even temperature distribution in the downward direction, because temperature at a given distance below the plane of the HD axis varies less than 1°C in any of the boreholes. However, the temperature difference between Borehole 161 and Borehole 163, especially on February 28, indicates that the temperature in the region below the HD is less symmetric than that above the HD. Comparison of temperatures for May 30 and February 28 shows that, below the drift, temperature distributions are becoming very uniform, and temperature gradients are decreasing slightly as temperature increases. Data for these boreholes are consistent with data shown in Figure 2-10 and indicate that temperatures below the plane of the heaters are lower than those at the same distance above, which indicates the importance of both convection and conduction as heat-transfer mechanisms. The lower temperatures below the HD may also be caused by the concrete slab in the invert of the HD. It would be reasonable to expect convection to play a stronger role above the drift than below the drift at this stage of heating.

2.3.5.2 Horizontal Boreholes

Figure 2-17 depicts temperature history for the horizontal boreholes in the 23-m cross section (Boreholes 160 and 164) and shows several interesting features of the temperature in the horizontal plane:

- Although it is not as symmetric as observed in the inclined boreholes, the temperature field is approximately symmetric about a central vertical plane. The field is more symmetric than that observed in the Boreholes 139 and 143 (see Section 2.3.4.2). Moreover, the AOD (-x) side of the field shows higher temperatures. Boiling is indicated along significant portions of Boreholes 160 and 164 in late February.
- Two zones of higher temperature are shown for each borehole (except during late February, when temperatures in both holes were relatively constant because of boiling). These temperature highs are attributed to the inner and outer segments of the wing heaters. The outer zone of high temperature has temperatures greater than those of the inner zone in each borehole. This is at least partially due to the fact that the power output of the outer wing heaters is greater than that of the inner wing heaters (1719 W for the outer wing heaters and 1145 W for the inner wing heaters).
- Temperatures in both boreholes in the region between the inner wing heater and the drift wall were near 100°C from March 30 to April 30, which indicates that boiling was occurring in this region during that time.
- Both boreholes also show temperatures near 100°C for the zone between the wing heaters, at least until March 30; this also indicates that boiling was occurring.
- Temperatures approached 135°C for a depth of 11 m in Borehole 160. These temperatures are associated with the outer wing heaters near this borehole.
- Beyond 15 m from the center of the HD, temperatures drop exponentially back to ambient. However, in late May, there was a small thermal shelf at about 100°C at 14 to 16 m in Borehole 164; this shelf indicates that boiling was occurring at this location, which is associated with the end of the wing heater.

2. Temperature Measurements

- Temperature variations are correlated with the segments of the wing heaters. Lower temperatures are associated with the zone between HD and inner segment of wing heater and with the zone between inner and outer wing heater segments.
- Temperatures are more irregular on the south ($-x$ or AOD) side (Borehole 164), primarily because of higher temperatures associated with the outer wing heaters at this location.

Figure 2-17. Snapshot of the temperatures in Boreholes 160 and 164, as a function of horizontal distance.

Borehole 160 is toward the AOD.

Figure 2-18 shows data from Boreholes 160 and 164 as a surface, in a manner similar to that in Figure 2-12. In Figure 2-18, the vertical axis represents temperature, and horizontal distance from the center of the drift is shown across the page. Time from the start of the test in days is shown increasing from the front to the back of the plot. This surface represents a linear interpolation of data presented in Figure 2-17. The notch in the high-temperature peak in Borehole 160 is an artifact of the data set.

Figure 2-18. Temperature evolution of the DST along of Boreholes 160 and 164.

The temperatures shown between -2.5 m and $+2.5$ m are artifacts of the surface rendering and are not representative.

Figure 2-18 illustrates the symmetry of the temperature field over time and the persistence of the low temperatures in the zones between heaters. The level regions indicate that boiling occurred over some distance and/or during extended periods. Also, boiling seems to have persisted between the drift wall and the first high-temperature peak in each borehole. Figure 2-18 also illustrates the shelf at the far end of Borehole 164.

Figure 2-19a shows temperature data for selected RTDs in Borehole 160, plotted as a function of time from the start of the DST. RTDs 10 to 35 are located at depths associated with the extent of the wing-heater, and RTDs 40 through 60 are at depths corresponding to intervals beyond the end of the wing heaters. Boiling in the borehole is clearly indicated by the constant temperature values near 100°C for RTDs 10, 20, 30, and 35 in various periods between 60 and 120 days. Note the gradual shift of the boiling zone with time and location; further analysis will be conducted on this observation. The lower temperatures observed at TRDs 35 through 40 in Borehole 139 (Figure 2-13) are not present in this borehole. As discussed previously, the presence of the AOD is not judged to be the reason for the differences. However, the AOD is more remote at this location than at the 12-m location because of its grade. The erratic behavior of RTD 40 is correlated with changes in barometric pressure, as shown in Figure 2-19b. The meaning of this correlation will be evaluated, and its impact on the analyses of the DST data will be assessed.

Figure 2-19. Temperature of Borehole 160.

(a) Data for selected RTDs, as a function of elapsed time. The symbols are not exact data points; they are to identify the temperature curves.

(b) Temperature at RTD 40 and barometric pressure at pressure sensor 1, as a function of elapsed time. Pressure sensor 1 is located in the HD near the bulkhead (see Section 8). The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-20 shows RTD data for Borehole 164 plotted in a similar manner. This plot shows that boiling began at approximately day 85 at RTD 10 and was continuing on May 30 at RTD 40. The temperature data for this borehole do not show the depressed temperatures at the end of the heated zone as noted for Borehole 139. The small depression shown on several of the RTDs at about day 104 is still being investigated. The flat temperature response (near 100°C) for RTD 40 after 150 days is consistent with the development of a boiling zone at the end of the outer wing heaters, as discussed previously.

Figure 2-20. Temperatures at some selected RTDs of Borehole 164, as a function of elapsed time. The symbols are not exact data points; they are to identify the temperature curves.

2.3.6 Vertical Cross Section at 39 m from Bulkhead

2.3.6.1 Vertical and Inclined Boreholes

Figure 2-21 depicts temperature in Boreholes 170 and 175 at a series of times through May 30. These boreholes are vertical upward and downward, respectively, as shown on the inset of the figure. Temperature is plotted as a function of vertical distance from the axis of the HD. This plot depicts a smooth increase in temperature with time for this profile and also shows that, at a distance from the HD axis of 15 m for Borehole 173 and 16 m for Borehole 170, rock was still at approximately ambient temperature on May 30. As shown in Figure 2-21, some of the RTDs are in the invert of the HD. This figure shows that the first few meters of rock above the drift was being heated faster than was rock at the equivalent distance below the drift. This is probably because of convection in the HD and the fact that the invert is a concrete slab about 1.2 m thick.

Figure 2-21. Snapshot of temperatures in Boreholes 170 and 173, as a function of vertical distance from the HD axis. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-22 shows temperatures, on May 30 and February 28, for the vertical upward and downward boreholes in this cross section and for the boreholes inclined at $\pm 45^\circ$ and $\pm 135^\circ$.

Figure 2-22. Snapshot of temperatures in Boreholes 170 to 175 on February 28, 1998, and May 30, 1998, as a function of vertical distance from the HD. The symbols are not exact data points; they are to identify the temperature curves.

2. Temperature Measurements

Boreholes above the HD axis include Borehole 170 oriented at 0° (vertical upward) and Boreholes 171 and 175 oriented at -45° and +45°, respectively (see Table 2-1). Data for these boreholes indicate that the temperature field above the HD in the 39-m cross section is very symmetric about a vertical plane through the axis of the HD. Temperature is highest directly above the HD; temperature distributions versus distance above the HD axis are identical for the two sides of the HD and are approximately 10°C lower than directly above the drift. Note that the vertical distances of RTDs in the inclined boreholes are less than their distances into the borehole from the collar. In the case of the vertical boreholes, the vertical distances of RTDs are the same as their distances along a borehole from the collar. This pattern of temperatures indicates that regions above the wing heaters were being heated evenly and at a lower rate than the rock above the HD. The symmetric temperature distribution indicates that, as of May 30, the DST was successfully progressing toward the goal of developing a horizontally planar heated zone above the HD.

Boreholes below the HD axis include Borehole 173 oriented at 180° (vertical downward) and Boreholes 172 and 174 oriented at -135° and +135°, respectively (see Table 2-1). Data for these boreholes show a very even temperature distribution in the downward direction because temperature at a given distance below the plane of the HD axis varies less than 1°C in any of the boreholes. Data for these boreholes are consistent with data shown in Figure 2-4 and indicate that temperatures below the plane of the heaters were lower than those at the same distance above, which indicates the importance of both convection and conduction as heat-transfer mechanisms. The temperature difference between the region above the HD and that below the HD is probably due to convection within the HD and to the fact that the invert is a concrete slab about 1.2 m thick.

2.4 Analysis

Very preliminary analyses of the measured temperatures in the DST are reported in this section. The analyses will be more mature in time and with the availability of more data. Temperature data reported here indicate that, at the end of the second quarter of heating (May 30, 1998), rock near the crown of the drift had reached a temperature of approximately 120° ± 5°C, but temperatures near the bottom of the drift (in the invert) were approximately 10°C cooler. The cooler temperatures near the bottom of the HD may be caused by convection in the HD and by the concrete slab in the invert of the HD. Temperature data also indicate that temperature variations were small along the length of the drift between 3 and 39 m from the bulkhead.

Moreover, temperatures measured in the vertical and inclined boreholes in cross sections perpendicular to the drift axis indicate that the temperature field is essentially symmetric about a vertical plane through the axis of the HD. Temperature is highest directly above the HD; temperature distributions versus distance above the HD axis are identical for the two sides of the HD and are less than 10°C lower than the temperatures directly above the drift. This pattern indicates that regions above the wing heaters are being heated evenly and at a lower rate than is the rock above the HD. However, the lower temperatures on the two sides of the HD, compared to the temperature directly above the HD, may also be caused by the fact that an RTD in an inclined borehole will have a smaller vertical distance than will an RTD in a vertical borehole when they have the same distance along the borehole from the collar. Therefore, at the same vertical distance, the RTD in an inclined borehole is further away from the collar and measures cooler temperatures than does an RTD in a vertical

borehole. This symmetric temperature distribution indicates that, as of May 30, the DST was successfully progressing toward the goal of developing a temperature field above the HD that is approximately planar in the horizontal direction.

Temperatures below the plane of the heaters were lower than those at the same distance above the heaters. This indicates the importance of both convection and conduction as heat-transfer mechanisms. The difference in temperature between rock at the top and bottom of the drift is probably caused by convection in the drift. These are useful data for guiding the numerical modeling of the test because it reflects the relative strength of air convection and radiation as heat-transfer mechanisms in affecting the boundary conditions in the HD. The differences in the temperature can also be caused by the fact that the invert of the HD is a slab of concrete about 1.2 m thick.

Temperatures in horizontal boreholes show a temperature field that is approximately symmetric, although not as symmetric as observed in the inclined boreholes. Temperature variations along some of the horizontal boreholes are correlated with the segments of the wing heaters. Lower temperatures are associated with zone between the HD and inner segment of wing heater and with the zone between inner and outer wing heater segments. Temperature appears to have been higher on the south (-x or AOD) side of the HD, especially in zones influenced by the outer wing heaters. The greater temperatures on the south side of the HD could be caused by many factors. One of them is the thermal conductivity of the rock mass. If the AOD could cause the thermal conductivity in the rock mass to decrease, relative to the north side of the HD, the temperature in the rock mass would be higher. Level temperatures at 96°C indicate boiling has occurred in significant zones. These zones begin approximately 5 m from the drift wall and extends to the end of the outer wing heater. Evidence of boiling was also found between the drift wall and the inner wing heaters.

Data for Boreholes 79 and 80 show the development of high-temperature zones that have a linear horizontal dimension of 5 to 10 m and show temperatures elevated by 8 to 10°C. The zones have developed during the second quarter of heating (March through May 1998). Possible mechanisms for this abnormally high temperature include heat-pipe effect caused by fractures in the rock mass.

2.5 References

- Blair, S.C., and W. Lin (1998). *First-Quarter Report of Temperature Measurements During the Heating Phase of the Drift-Scale Test*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (SP2640M4) Livermore, CA: Lawrence Livermore National Laboratory.
- Lin, W., and J.L. Wagoner (1998). *DST As-Built TDIF, XYZ Coordinates of the Sensors in the Drift-Scale Test*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (UCRL-ID-129591) Livermore, CA: Lawrence Livermore National Laboratory. 9 p. [MOL.19980203.0221]
- SNL (1998). *Evaluation and Comparative Analysis of the Drift-Scale Test Thermal and Thermomechanical Data: First Quarter Results*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (SP2520M4) Albuquerque, NM: Sandia National Laboratories.

Figure 2-1. Configuration (not to scale) of temperature boreholes (RTD) in the Drift-Scale Test.

2. Figures

Figure 2-2. Temperatures of radial RTD boreholes on May 30, 1998.

Figure 2-3. Air temperatures in the heater drift. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-4. Temperatures of vertical boreholes as a function of vertical distance on February 28, 1998, and May 30, 1998. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-5. Temperature of vertical boreholes versus vertical distance from drift axis on May 30, 1998. The symbols are not exact data points; they are to identify the temperature curves.

2. Figures

Figure 2-6. Snapshot of the temperatures of Borehole 80, as a function of horizontal distance. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-7. Snapshot of the temperatures of Borehole 79, as a function of horizontal distance. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-8. Comparison of temperatures of Boreholes 79 and 80, as a function of horizontal distance, for February 28, 1998, and May 30, 1998.

Figure 2-9. Snapshot of the temperatures in Boreholes 137 and 141, as a function of vertical distance. The symbols are not exact data points; they are to identify the temperature curves.

2. Figures

Figure 2-10. Temperatures of upward and downward boreholes at 12 m from the bulkhead, as a function of vertical distance, on February 28, 1998, and May 30, 1998. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-11. Snapshot of the temperatures of Boreholes 139 and 143, as a function of horizontal distance. Borehole 139 is toward the AOD.

Figure 2-12. Temperature evolution of the DST along Boreholes 139 and 143. The temperatures shown between -2.5 m and 2.5 m are an artifact of the surface rendering.

Figure 2-13. Temperature at some RTD location in Borehole 139, as a function of elapsed time. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-14. Temperature at some RTD location in Borehole 143, as a function of elapsed time. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-15. Snapshots of the temperatures of Boreholes 158 and 162, as a function of vertical distance. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-16. Snapshots of the temperatures of Boreholes 158–165, as a function of vertical distance, on February 28, 1998, and May 30, 1998. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-17. Snapshot of the temperatures in Boreholes 160 and 164, as a function of horizontal distance. Borehole 160 is toward the AOD.

Figure 2-18. Temperature evolution of the DST along of Boreholes 160 and 164. The temperatures shown between -2.5 m and +2.5 m are artifacts of the surface rendering and are not representative.

Figure 2-19a. Temperature of Borehole 160. (a) Data for selected RTDs, as a function of elapsed time. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-19b. Temperature of Borehole 160 — data for RTD 40. (b) Temperature at RTD-40 and barometric pressure at pressure sensor 1, as a function of elapsed time. Pressure sensor 1 is located in the HD near the bulkhead. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-20. Temperature at some RTDs of Borehole 164, as a function of elapsed time. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-21. Snapshot of temperatures in Boreholes 170 and 173, as a function of vertical distance from the HD axis. The symbols are not exact data points; they are to identify the temperature curves.

Figure 2-22. Snapshot of temperatures in Boreholes 170 to 175 on February 28, 1998, and May 30, 1998, as a function of vertical distance from the HD. The symbols are not exact data points; they are to identify the temperature curves.

3. Electrical Resistivity Monitoring

by Abelardo L. Ramirez and William D. Daily

3.1 Introduction

This section describes electrical resistance tomography (ERT) surveys made during the Drift-Scale Test (DST) to map the changes in moisture content caused by the heating of the rock mass. ERT is one of the several thermal, mechanical, and hydrologic measurements being used to monitor the rock-mass response during the DST. ERT is being used to monitor the behavior of liquid water, with a special interest in the movement of condensate out of the system.

Eight boreholes, containing a total of 140 ERT electrodes, were drilled above and below the heater drift (HD) to form vertical planes parallel to the drift. Four additional boreholes, containing 60 electrodes, drilled from the access/observation drift (AOD), form vertical planes at right angles to the HD. Images of resistivity change were calculated using data collected before and during the heating episode. The changes recorded show two regions of decreasing resistivity: one approximately centered around the wing heaters and another centered around the HD. These regions grow with time, and the resistivity decreases become stronger. The changes in resistivity are caused by changes in both temperature and saturation. The Waxman Smits model has been used to calculate rock saturations after accounting for temperature effects. The saturation estimates suggest that a relatively large region of drying develops around the wing heaters and grows over time; a second, smaller, drying region is developing above the crown of the HD. Some of the saturation estimates also suggest that a wetting region developed above and below the HD. The accuracy of the saturation estimates is limited due to a variety of factors discussed at the end of Section 3.5.

The perspective view in **Figure 3-1** shows the 12 boreholes drilled from the HD and the AOD. **Figure 3-2** and **Figure 3-3** show the position of 200 electrodes that are emplaced in the boreholes. These electrodes are used to conduct ERT surveys around the HD.

Figure 3-1. Perspective view showing the location and names of the ERT boreholes relative to the HD and AOD.

Figure 3-2. Cross-section parallel to the HD showing the location of ERT boreholes.

Figure 3-3. Two cross-sections orthogonal to the HD showing the location of ERT boreholes drilled from the AOD and selected boreholes drilled from the HD.

3.2 Electrical Resistance Tomography

ERT is a geophysical imaging technique that can be used to map subsurface resistivity. This technology has been successfully used to monitor a variety of subsurface processes, such as steam injection, air sparging, and contaminant spills (e.g., Daily et al., 1998; LaBrecque et al., 1996; Ramirez et al., 1997). At Yucca Mountain, ERT is used to monitor electrical

resistivity changes that develop during heater tests, including such other site-characterization tests such as the Single-Heater Test (SHT) and the Large-Block Test.

Rock-mass heating creates temperature and liquid saturation changes. These changes result in electrical resistivity changes that are readily measured. The ERT measurements consist of a series of voltage and current measurements from buried electrodes using an automated data-collection system. The data are then processed to produce electrical resistivity tomographs using state-of-the-art data-inversion algorithms. These measurements are used to calculate tomographs that show the spatial distribution of the subsurface resistivities.

To calculate the changes in the rock's electrical resistivity, a data set obtained after the start of heating is compared with a corresponding data set obtained prior to heating. One may consider subtracting, pixel by pixel, images from two tomographs representing different conditions. However, this approach could not be used because several boreholes and the HD containing metallic objects were located near the planes of interest. These objects caused large conductive anomalies and made the resistivity structure three-dimensional (3-D). 3-D inversion codes are available, but the number of boreholes available for ERT does not allow 3-D coverage of the DST block. Thus, the 3-D algorithm is not used in this work.

The inverse algorithm used is two-dimensional (2-D) and, therefore, cannot generate a model that will fit the data; thus, the code chooses a solution with a poor fit. These effects can be reduced by inverting the quantity, thus: $(R_a/R_b) \cdot R_h$. Here, R_a is the measured transfer resistance after heating started, R_b is the transfer resistance before heating, and R_h is the calculated transfer resistance for a model of uniform resistivity. This approach tends to reduce the effects of anomalies that do not change with time because they are contained in both terms R_a and R_b .

The algorithm solves both the forward and the inverse problems. The forward problem is solved using a finite-element technique that models current flow in three dimensions due to a 2-D resistivity structure. The inverse problem requires a regularized solution that minimizes an objective function. The objective of the inverse routine is to minimize the misfit between the forward-modeling data and the field data, and a stabilizing functional of the parameters. The stabilizing functional is the solution's roughness, i.e., the inverse procedure tries to find the smoothest resistivity model that fits the field data to a prescribed tolerance. Resistivity values assigned in this way to the finite-element mesh constitute the ERT image. For additional details on the 2-D algorithm, the reader is referred to Morelli and LaBrecque (1996).

Although each mesh is of a large region around the electrode arrays, only the region inside the ERT electrode array is shown in the results, because the region outside the array is poorly constrained by the data.

3.3 Description of ERT Surveys

Along the HD, ERT survey data were collected between adjacent pairs of boreholes. For example, surveys collected below the HD are collected between Boreholes 136–146, 146–167, and 167–177. A similar approach is used for surveys collected above the HD. These surveys provide information along two vertical planes (one above and one below the HD) that run parallel to the HD.

The surveys performed from boreholes drilled from the AOD provide information along two vertical planes that run orthogonal to the HD. These surveys are performed by

combining electrodes in AOD boreholes with electrodes in HD boreholes. It is advantageous that HD Boreholes 135 and 136 are close to AOD Boreholes 45 and 46, and that HD Boreholes 166 and 167 are close to AOD Boreholes 62 and 63. For these surveys, the shallowest (closest to the AOD) 10 electrodes in AOD Boreholes 45 and 46 were used in combination with the shallowest 5 electrodes (closest to the HD) in HD Boreholes 135 and 136. This approach provides better sensitivity and resolution of the rock mass on the left flank (looking toward the end of the HD) of the HD than the sensitivity and resolution that would result if only electrodes in the AOD boreholes were used.

3.4 Changes in Electrical Resistivity

Tomographs of resistivity change for the period between December 17, 1997, and March 18, 1998, are shown in **Figure 3-4**, **Figure 3-5**, and **Figure 3-6**. Figure 3-4 shows the tomographs collected along a cross-section parallel to the HD. The upper-left part of Figure 3-4 shows the changes in resistivity calculated after 84 days of heating. Most of the tomographs are yellow-green in color, indicating resistivity ratios near 1.0 (no change condition). Near the surface edge of the HD, the tomographs show resistivity ratios less than 1.0 (particularly near the crown), thereby indicating that the resistivity has decreased relative to the preheating condition. After 105 days of heating, most of the rock still shows a ratio of 1.0, but the rock near the crown and invert of the HD shows stronger resistivity decreases (ratios farther removed from 1.0). These decreases become stronger as heating time increases (lower-left and lower-right portions of Figure 3-4). Figure 2-5 shows that the temperatures above the HD are higher than the temperatures below the HD by roughly 15°C. The tomographs also indicate that the resistivity changes above the HD are stronger than those below the HD. These resistivity changes are believed to be due primarily to increases in temperature that have developed close to the walls of the HD.

Figure 3-4. Tomographs of electrical resistivity ratio along a cross-section parallel to the HD; tomographs located above the crown and below the invert of the HD are shown.

The tomographs show changes relative to the preheating (November 18, 1997) electrical resistivity distribution. A resistivity ratio equal to 1.0 indicates no change; values less than 1.0 indicate that the resistivity is decreasing relative to the baseline.

Figure 3-5. Tomographs of electrical resistivity ratio along a cross-section that is orthogonal to the HD and near the bulkhead.

Figure 3-6. Tomographs of electrical resistivity ratio along a cross-section that is orthogonal to the HD and near its middle, and coincident with the AOD 5 boreholes as shown in Figure 3-2 and Figure 3-3.

Figure 3-5 shows one of the two vertical planes at right angles to the HD; this one is located close to the bulkhead that blocks off the HD as shown in Figure 3-2 and Figure 3-3. Although the mesh consists of a large region around the electrode arrays, only the region inside the ERT electrode array is shown in the figure because the region outside the array is poorly constrained by the data. The region inside the HD is also masked because the technique does not measure rock properties in the excavated region. The tomograph sequence shows a region of resistivity decrease near the walls of the HD. The resistivity

decreases become stronger with time and they extend farther into the rock above the HD. Surprisingly, the region corresponding to the wing heaters' location (nine o'clock position relative to the HD) shows relatively weak resistivity decreases. The implications of these weak resistivity decreases are discussed in Section 3.5.

Figure 3-6 depicts resistivity-change tomographs sampling the rock mass along a second vertical plane at right angles to the HD. This figure shows tomograph planes that are coincident with the AOD 5 boreholes (refer to Figure 3-2 and Figure 3-3) and intersect the HD near its middle. The images in Figure 3-6 show resistivity decreases near the location of the wing heaters (nine o'clock position relative to the HD) and near the walls of the HD. The tomograph region corresponding to the location of the wing heaters shows an interesting sequence. On 2/25/98, this region shows a resistivity ratio of about 0.6, which means that the 2/25/98 resistivity is 0.6 times as large as the baseline resistivity. The resistivity ratio of this zone changes with time and approaches 0.9 early in June (lower-right image in Figure 3-6). Also, the zone of resistivity changes extends farther into the rock above the HD than it does below the HD.

This sequence indicates that the resistivity near the middle of the wing heaters first decreased to about 0.6, later changed in the opposite direction, and "rebounded" back to 0.9. The rebounding resistivity near the middle of the wing heaters causes an apparent "hole" to appear in the two images, shown in the bottom row of Figure 3-6.

This complicated behavior of the resistivity changes observed is primarily caused by changes in temperature and saturation. Increasing temperature tends to decrease the resistivity; decreasing saturation tends to increase the resistivity. Ramirez and Daily (1997a) show resistivity-ratio curves as a function of changing saturation and temperature. The curves indicate that when saturation remains constant and temperature increases, the resistivity ratio will drop below 1.0, because the mobility of ions in electrolytes increases with temperature and this causes a decrease in pore water resistivity. Based on those curves, we suggest that the resistivity decreases observed through February 1998 (upper-left image of Figure 3-6) are caused primarily by decreases in the resistivity of the pore water as temperature increases.

As time progresses, drying of the rock occurs. The curves in Ramirez and Daily (1997a) show that when saturation decreases and temperature remains constant, resistivity ratios will become greater than 1.0, i.e., drying of the rock would make the resistivity increase. This means that increasing temperature and decreasing saturation have opposing effects on the resistivity. The heaters in the DST are causing the rock to heat up and to dry at the same time. The curves in Ramirez and Daily (1997a) indicate when temperature increases and saturation decreases, the resistivity ratios are typically less than 1.0 so long as the saturation remains above 20%. If temperature increases and saturation drops below 20%, the resistivity ratios rebound and become greater than 1.0. We believe that the rebounding resistivity observed in the bottom row of images in Figure 3-6 is indicative of saturations below 20%.

Figure 3-4, Figure 3-5, and Figure 3-6 make it clear that resistivity decreases are the norm and, thus, that the temperature effect on pore water is dominating the resistivity changes observed for most of the rock. The exception is rock immediately adjacent to the middle portion of the wing heater boreholes, where the resistivity ratio is rebounding back towards 1.0, suggesting that the saturation there has decreased to a value near 20%.

There are both similarities and differences between the two planes orthogonal to the HD (Figure 3-5 and Figure 3-6). Both show resistivity decreases, near the HD, that extend deeper into the rock above the crown of the HD than below its invert. The decreases also become

stronger along both planes as heating time advances. Significant differences between the Figure 3-5 and Figure 3-6 results are observed in the vicinity of the wing heaters. The Figure 3-5 tomographs show much weaker decreases in resistivity near the bulkhead. Assuming that the primary factors affecting electrical resistivity are temperature and saturation, the weaker decreases by the wing heaters suggest one of the following is true:

- The rock is cooler close to the bulkhead.
- Rock saturation is decreasing faster near the bulkhead than it does near the middle of the HD, offsetting resistivity decreases caused by temperature.
- Other effects are masking the true rock response.

Temperature data in this area suggest that the first hypothesis is probably not true.

The third hypothesis may be valid if the large metallic structure making up the bulkhead (which may be electrically connected to the rock mass) is focusing the electrical current away from the rock mass. This condition would tend to create an area of low ERT sensitivity near the bulkhead. This is consistent with a previous report (Lin et al., 1998). In that report, the preheating baseline tomograph near the bulkhead indicated very low resistivity close to the HD near the location of the wing heaters. A possible root cause of this low-resistivity region could be the proximity of this part of the rock to the bulkhead metal structure. Another possible root cause is heterogeneity in the mineralogy, porosity, or water content of the rock in this region.

3.5 Estimates of Saturation Change

The resistivity changes shown in Figure 3-4, Figure 3-5, and Figure 3-6 are influenced by changes in moisture content, temperature, and ionic strength of the water. To estimate saturation, it is assumed that the dominant factors affecting resistivity changes are temperature and saturation, i.e., an increase in temperature or moisture causes a resistivity decrease. Near the heaters, there may be regions where the increasing temperature reduces resistivity, while rock drying increases resistivity. The images of resistivity change near the HD, along with the measured temperature field and what is known of initial conditions in the rock mass, are used in this section to estimate moisture change during heating. A detailed description of this approach can be found in a previous milestone report pertaining to the SHT (Ramirez and Daily, 1997b). Some of the highlights of this approach are presented here.

To estimate moisture content changes, the effects of both rock temperatures and resistivity changes measured by ERT must be taken into account. The saturation estimates shown in a previous milestone report (Ramirez and Daily, 1998) were calculated using temperature fields that were constructed by interpolating temperature measurements from throughout the DST block. Interpolation of temperature measurements made at discrete points was necessary to develop the temperature fields showing a temperature value at each tomograph pixel. The interpolations can sometimes be in error if the interpolation algorithm is not sufficiently constrained by the measured values and because the interpolation does not necessarily satisfy physical laws. (The reader can also refer to Section 4, "Neutron Logging," which describes an independent method of monitoring saturations throughout the DST block.)

Another method available to construct the temperature fields is to use a hydrothermal numerical simulator that can calculate temperatures as a function of time and space. This method was used to produce the temperature fields required to calculate the saturation ratios shown below. The hope is that this approach provides temperature fields that more closely

resemble the real fields. The simulator used is Nonisothermal Unsaturated-Saturated Flow and Transport (NUFT), which uses an equivalent continuum approach to model the hydrothermal response of the rock. The equivalent continuum approach may provide unrealistic results in situations with significant fracture flow. NUFT is described in Section 6.

The temperature estimates generated by NUFT and by the interpolation approach are unqualified; therefore, the saturation estimates are unqualified. Also, the saturation estimates are considered approximate.

A petrophysical model known as the Waxman Smits model is used to produce the saturation estimates. As indicated in Ramirez and Daily (1997b), when the Waxman Smits model is used in ratio form, it simplifies to two possible models:

- Model 1 represents the case in which the primary conduction pathway is through the water in the open pore space.
- Model 2 represents the case in which the primary conduction pathway is surface conductance within the electrical double layer that exists at the interface between the silicate matrix and pore water.

These two models bracket the range of possible relationships between saturation and resistivity. However, Model 2 exhibits a higher sensitivity to saturation change than does Model 1 for a given resistivity change. Because rock conditions are changing in space and time during heating, changes in saturation were estimated using both models. This approach should provide bounds to the domain of possible saturations that may be present. Neither of these two models accounts for changes in water resistivity caused by rock/water-chemical interactions. If such chemical reactions cause large changes in the concentration or types of ions in the water, the estimated saturation changes will be in error.

Figure 3-7 shows the saturation change estimates along the axis of the HD using Model 2. As indicated by Ramirez and Daily (1997b), Model 2 is probably closer to the real saturation changes than Model 1. For brevity, the Model 1 results are not shown; however, the technical data information form will include saturation ratios based on both models. In general, the Model 1 results show smaller changes in saturation than the Model 2 results. The Model 2 estimates in Figure 3-7 indicate that most of the rock has a saturation ratio of about 1.0 (no change relative to the baseline). These estimates suggest that some drying is occurring close to the HD and that the drying zone is growing very slowly with time. The tomographs suggest that most of the drying is occurring above the HD. The saturation ratio estimates shown in Figure 3-7 suggest that the rock showing the maximum amount of drying had lost about two-thirds of its water (saturation ratio of about 0.3) by early June 1998.

Figure 3-7. Estimates of saturation change according to Model 2, along a cross-section parallel to the HD.

The estimates show changes relative to the preheating (November 18, 1997) saturation distribution. A saturation ratio equal to 1.0 indicates no change; values less than 1.0 indicate that the saturation is decreasing relative to the baseline.

Figure 3-8 shows the saturation-change estimates for a plane perpendicular to the axis of the HD, close to the bulkhead, and coincident with the AOD 1 boreholes. **Figure 3-9** shows the saturation change estimates perpendicular to the axis of the HD, close to the middle of the HD, and coincident with the AOD 5 boreholes (shown in Figure 3-3). Figure 3-9 shows a horizontal zone of drying near the wing heaters that grows with time. Figure 3-8 shows also

shows a horizontal zone of drying near the wing heaters, but it remains relatively stable during the time period shown. The estimated saturation ratios near the wing heaters range between 0.1 and 0.2 by 6/3/98 for Figure 3-9 and are about 0.3 for Figure 3-8.

Figure 3-8. Estimates of saturation change according to Model 2 along a cross-section orthogonal to the HD, near the bulkhead, and coincident with the AOD 1 boreholes shown in Figure 3-2 and Figure 3-3.

Figure 3-9. Estimates of saturation change according to Model 2 along a cross-section orthogonal to and near the middle of the HD, and coincident with the AOD 5 boreholes.

When compared to Figure 3-8, Figure 3-9 shows a stronger zone of drying that extends beyond the zone where the wing heaters are located. As shown by the resistivity ratios in Figure 3-5 and Figure 3-6, the resistivity changes observed around the wing heaters near the bulkhead are weaker than those observed closer to the center of the HD. The petrophysical model used to provide saturation estimates interprets the weaker changes as stronger drying near the bulkhead. If the reason for the weaker resistivity changes is a “blind zone” or low-sensitivity zone caused by the metal in the bulkhead, these high drying estimates are simply due to low sensitivity to the true changes actually occurring in the rock.

On the other hand, there are reasonable physical arguments to suggest that the saturation estimates near the bulkhead may be valid. There are two reasons for expecting this ERT plane to behave differently from the AOD 5 plane:

- This plane is close to the bulkhead and to the associated access drifts. Such proximity means that there may be enhanced drying of this part of the rock mass, because it is better connected by natural and induced fractures to the ventilation system. This argument supports the fact that the saturation ratios indicate a stronger drying during the first two months of heating (discussed in Ramirez and Daily, 1998) in this image plane.
- Water was produced by one of the boreholes drilled near the bulkhead. This anecdotal evidence suggests that there may have been a small, water saturated rubble zone in this area. A small volume of pendular water in this otherwise highly resistive rock mass would image as a strong conductive anomaly, even after being drained of the bulk water at drilling. Coincidentally, a strong conductive anomaly was present in the baseline images of AOD 1 (Ramirez and Daily, 1997a) adjacent to the wing heaters. This type of anomaly might explain the unusual resistivity patterns that formed in this plane and why the anomalous moisture changes calculated from them do not look like the results from AOD 5.

As indicated previously, the temperature fields required to calculate the saturation ratios can be constructed by interpolating the measured temperature data or by using a numerical hydrothermal simulator, such as NUFT. **Figure 3-10** compares saturation estimates using temperature fields constructed by either approach. The images shown correspond to the plane which is perpendicular to the axis of the HD, and coincident with the AOD 5 boreholes. The images on the left show the saturation ratios based on the NUFT-calculated temperatures; the images on the right show the saturation ratios based on interpolated temperature measurements. A comparison of the NUFT-calculated temperatures and interpolated temperatures is shown in **Figure 3-11**.

Figure 3-10. Estimates of saturation change according to Model 2 along a cross-section orthogonal to and near the middle of the HD, and coincident with the AOD 5 boreholes.

The left column of saturation-ratio images were calculated based on temperature fields calculated by a numerical hydrothermal simulator (NUFT). The right column of images were calculated based on interpolation of measured temperature values.

Figure 3-11. Comparison of NUFT-calculated temperatures (left image) and temperatures based on interpolation of measured temperature values. The cross section shown is the same as that in Figure 3-10.

The drying regions (ratios less than 1.0) show similar saturation-ratio magnitude and shape. Also, the drying regions calculated by NUFT appear to be somewhat taller than those from interpolation for each of the dates shown. The interpolated images show regions of wetting (ratios greater than 1.0 shown by the dark purple color) above and below the HD for each of the three dates shown; the NUFT images show ratios close to 1.0 (no saturation change) in the corresponding zones. The results in Figure 3-10 suggest that wetting zones are produced only when the interpolated temperatures are used. This is an important difference because the primary objective of ERT is to track the accumulation of liquids (i.e., condensate) during the test. Figure 3-10 suggests that the ability to map liquid accumulation is strongly influenced by the accuracy of the temperature maps. At the time of writing, it is unclear which method is likely to produce the most accurate saturation ratio estimates. In the future, comparisons between the saturation estimates and independent measurements of water content in the rock mass (e.g., neutron logs, air permeability measurements) will be used to establish which approach produces the most accurate saturation ratios.

All of the saturation estimates presented are considered to be approximations. The accuracy of the saturation estimates in Figures 3-7 through 3-10 may be limited by one or more of the following factors:

- The accuracy of the temperature maps used is unknown. Errors in the temperature maps will result in erroneous saturation estimates.
- The effects of rock or water interactions on electrical resistivity are not accounted for by the Waxman Smits model. Significant changes in the number or types of ions in solution may cause resistivity changes that the model would treat as saturation changes. Data from DST water samples may be helpful in understanding this effect.
- Laboratory measurements of the electrical resistivity of welded tuff (Roberts and Lin, 1997) indicate that the Waxman Smits model underpredicts resistivity for saturations less than 20%. No saturation estimates less than 20% are present in Figures 3-7 through 3-10; this might become a limitation as drying near the heaters progresses.
- The resistivity ratios were calculated using a 2-D algorithm, whereas natural heterogeneities, such as fractures, are likely 3-D. Changes in resistivity occurring along fractures (or any other regions that do not meet the 2-D assumptions of the inversion algorithm) may be distorted.
- Several metallic objects are located near the planes of interest (e.g., bulkhead, heater canisters, steel mesh around the HD periphery). These metallic objects cause large conductive anomalies that may reduce sensitivity to resistivity changes occurring in the rock, resulting in resistivity-change tomographs that show smaller changes than those present in the rock.

- The ratio technique used to process the ERT data is an approximate technique best suited for situations of low-resistivity contrast. The presence of metallic instruments creates a high-contrast anomaly that may adversely impact the ERT-ratio tomographs.

3.6 Summary and Conclusions

ERT surveys were conducted around the HD before and after heating started. The surveys were made along a series of vertical planes, some parallel to the HD and others orthogonal to the HD. During this reporting quarter, three data sets were collected and processed after heating started. The field data was used to produce tomographs of electrical resistivity change. These tomographs primarily show electrical resistivity decreases during the course of heating. In the near vicinity of the wing heaters, some of the early resistivity decreases are becoming less pronounced, indicating that the effects of rock drying are beginning to dominate over the effects of temperature. The electrical resistivity changes have been used in combination with temperature maps of the region and a petrophysical model to calculate maps of saturation change around the HD. The saturation estimates suggest that a region of significant drying has developed near the location of the wing heaters. A less-significant drying region appears to exist above the crown and below the invert of the HD. There is also possible evidence of wetting zones developing above and below the HD.

3.7 References

- Daily, W.D., A.L. Ramirez, and R. Johnson (1998). "Electrical impedance tomography of a perchloroethylene release." *J. Environ. Eng. Geophys.* 2(3):189-201.
- LaBrecque, D.J., A.L. Ramirez, W.D. Daily, A. Binley, and S. Schima (1996). "ERT monitoring of environmental remediation processes." *Meas. Sci. Technol.* 7:375-383.
- Lin, W., R. Carlson, and D. Neubaumer (1998). *First-Quarter Report of Neutron Logging During the Heating Phase of the Drift-Scale Test*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (UCRL-ID-129592) Livermore, CA: Lawrence Livermore National Laboratory.
- Morelli, G., and D. LaBrecque (1996). "Robust scheme for ERT inverse modeling." In proceedings from *Symposium on the Application of Geophysics to Engineering and Environmental Problems*. Keystone, CO: April 28–May 2, 1996.
- Ramirez, A.L., and W.D. Daily (1997a). *Electrical Resistivity Monitoring of the Drift Scale Test in Yucca Mountain*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (UCRL-ID-129746) Livermore, CA: Lawrence Livermore National Laboratory.
- Ramirez, A.L., and W.D. Daily (1997b). *Electrical Resistivity Monitoring of the Thermomechanical Heater Test in Yucca Mountain*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (UCRL-AR-128841) Livermore, CA: Lawrence Livermore National Laboratory.
- Ramirez, A.L., and W.D. Daily (1998). *Electrical Resistivity Monitoring of the Drift Scale Test in Yucca Mountain, 2nd Quarter FY 98*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (SP2640M4) Livermore, CA: Lawrence Livermore National Laboratory. [MOL.19980512.0050]

3. Electrical Resistivity Monitoring

- Ramirez, A.L., W.D. Daily, A. Binley, D. LaBrecque, and D. Roelant (1997). "Detection of leaks in underground storage tanks using electrical resistance methods." *J. Environ. Eng. Geophys.* **1**(1):189-203.
- Roberts, J.J., and W. Lin (1997). "Electrical properties of partially saturated Topopah Spring tuff: Water distribution as a function of saturation." *Water Resources Res.* **33**(4):577-587. (Also UCRL-JC-123763, Lawrence Livermore National Laboratory, Livermore, CA) [LLNL report under MOL.19961014.0060]

Figure 3-1. Perspective view showing the location and names of the ERT boreholes relative to the Heated Drift and Access Observation Drift. A total of two hundred electrodes installed in twelve boreholes are used to sample the rockmass.

3. Figures

Figure 3-2. Cross-section parallel to the HD showing the location of ERT boreholes. Boreholes drilled from the from the HD are shown as solid lines extending above and below the HD. The locations of the electrodes within each borehole are shown by the small circles. The locations of boreholes drilled from the AOD are shown by dashed lines. The electrode spacing for the boreholes drilled from the HD is 1 m.

Figure 3-3. Two cross-sections orthogonal to the HD showing the location of ERT boreholes drilled from the AOD and selected boreholes drilled from the HD. The locations of the electrodes within each borehole are shown by the small circles. The electrode spacing is 1 m for the boreholes drilled from the HD and 2 m for the boreholes drilled from the AOD.

3. Figures

Figure 3-4. Tomographs of electrical resistivity ratio along a cross-section parallel to the HD; tomographs located above the crown and below the invert of the HD are shown. The tomographs show changes relative to the preheating (November 18, 1997) electrical resistivity distribution. A resistivity ratio equal to 1.0 indicates no change; values less than 1.0 indicate that the resistivity is decreasing relative to the baseline.

Figure 3-5. Tomographs of electrical resistivity ratio along a cross-section that is orthogonal to the HD and near the bulkhead. The tomographs show changes relative to the preheating (November 18, 1997) electrical resistivity distribution. A resistivity ratio equal to 1.0 indicates no change; values less than 1.0 indicate that the resistivity is decreasing relative to the baseline.

3. Figures

Figure 3-6. Tomographs of electrical resistivity ratio along a cross-section that is orthogonal to the HD and near its middle, and coincident with the AOD 5 boreholes as shown in Figures 3-2 and 3-3. The tomographs show changes relative to the preheating (November 18, 1997) electrical resistivity distribution. A resistivity ratio equal to 1.0 indicates no change; values less than 1.0 indicate that the resistivity is decreasing relative to the baseline.

Figure 3-7. Estimates of saturation change according to Model 2, along a cross-section parallel to the HD. The estimates show changes relative to the preheating (November 18, 1997) saturation distribution. A saturation ratio equal to 1.0 indicates no change; values less than 1.0 indicate that the saturation is decreasing relative to the baseline.

3. Figures

Figure 3-8. Estimates of saturation change according to Model 2 along a cross-section orthogonal to the HD, near the bulkhead, and coincident with the AOD 1 boreholes shown in Figures 3-2 and 3-3. The estimates show changes relative to the preheating (November 18, 1997) saturation distribution. A saturation ratio equal to 1.0 indicates no change; values less than 1.0 indicate that the saturation is decreasing relative to the baseline.

Figure 3-9. Estimates of saturation change according to Model 2 along a cross-section orthogonal to and near the middle of the HD, and coincident with the AOD 5 boreholes. The estimates show changes relative to the preheating (November 18, 1997) saturation distribution. A saturation ratio equal to 1.0 indicates no change; values less than 1.0 indicate that the saturation is decreasing relative to the baseline.

3. Figures

Figure 3-10. Estimates of saturation change according to Model 2 along a cross-section orthogonal to and near the middle of the HD, and coincident with the AOD 5 boreholes. The left hand column of saturation ratio images were calculated based on temperature fields calculated by a numerical hydrothermal simulator (NUFT). The right hand column of images were calculated based on interpolation of measured temperature values.

Figure 3-11. Comparison of NUFT calculated temperatures (left image) and temperatures based on interpolation of measured temperature values. The cross section shown is the same as that in Figure 3-10.

4. Neutron Logging

by Wunan Lin, Richard Carlson, and Dan Neubaumer

4.1 Introduction

Thermal neutron logging is a method used to determine moisture content in rocks and soils and is being used to monitor moisture content in boreholes ESF-HD-NEU-1 (N01) to ESF-HD-NEU-10 (N10) (Boreholes 47 through 51 and 64 through 68), ESF-HD-TEMP-1 (Borehole 79), and ESF-HD-TEMP-2 (Borehole 80) in the Drift-Scale Test (DST). Boreholes 79 and 80 are also identified as neutron boreholes N11 and N12, respectively, in this report.

The neutron probe contains a source of high-energy neutrons and a detector for slow (thermal) neutrons. Water present in rocks slows down the neutrons, making them detectable (because of the presence of hydrogen). Thus, higher counts (or a positive difference in counts relative to background or preheat levels) indicate higher water content (or increased water content over background). A Campbell Pacific Nuclear (CPN) model 503DR probe was used in the baseline measurements. The 3.81-cm- (1.5-in.-) diameter probe (serial number H37067677) was also used for the Single-Heater Test (SHT).

Under ambient conditions, the sampling volume has a diameter of approximately 15 cm surrounding the probe, which increases as moisture content decreases. Measurements are sensitive to the presence of elements, such as chlorine and boron, that have large neutron-capture cross-sections. Considering the counting statistics and other uncertainties, such as location of the tool, the uncertainty of the neutron logging is approximately 3% to 5% in water content. A new neutron tool made by COMPROBE, Inc. (model COMPROBE 1805DF), has been purchased for measuring the neutron counts of the rock mass during the heating and cooling phases of the DST. The COMPROBE tool is designed for operating at temperatures to 200°C. The COMPROBE tool was used to take the measurements during the heating phase; these measurements, up to May 1998 along with the baseline data, are presented in this report. The baseline data and the measurements during the heating phase up to March 1998 were also reported previously (Lin et al., 1998).

The COMPROBE tool has not yet been calibrated. However, when the COMPROBE tool was first used in the logging, its neutron counts were compared with those of the CPN probe placed at the same location in a borehole. The neutron counts of the COMPROBE tool were then normalized to those of the CPN probe. The CPN probe was calibrated to the Teflon™ liner-grout assembly of the SHT, but has not yet been calibrated to the Teflon-grout assembly of the DST. The Teflon-grout assembly in the DST is very similar, but not identical, to that in the SHT. The calibration coefficients of the CPN probe were then used to reduce the baseline neutron counts, which were measured by the CPN probe, to calculate the baseline fraction volume water contents. The CPN coefficients were also used to reduce the normalized neutron counts of the COMPROBE tool to calculate fraction volume water content measured by the COMPROBE tool. This process of reducing the COMPROBE data provides timely information about the water content in the DST during the heating phase. The calculated fraction volume water content reported in this report should be considered as preliminary and nonqualified (non-Q). When both the CPN probe and the COMPROBE tool are calibrated in the exact borehole assembly used in the DST, the neutron data will be re-analyzed, and the fraction volume water content will be recalculated.

For boreholes ESF-HD-NEU-1 through ESF-HD-NEU-10 of the DST, a Teflon™ tube was inserted into the boreholes and grouted into place. The Teflon tube permits easy insertion, placement, and removal of the tool. The CPN probe had been calibrated in the similar Teflon-grout assembly, which was used in the SHT but is not identical to that used in the boreholes. For boreholes ESF-HD-TEMP-1 (Borehole 79) and ESF-HD-TEMP-2 (Borehole 80), one resistance-temperature device (RTD) bundle was attached to the outside of the Teflon liner, and the assembly was grouted in place in the boreholes. The CPN probe had been calibrated in the Teflon-RTD-grout assembly used in the SHT and will be calibrated to a borehole assembly identical to that used in the Boreholes 79 and 80. Calibrations of the COMPROBE tool in the same assembly will also be conducted. The calibration information will be used to convert the neutron counts reported in this document into fraction volume water content.

4.2 Measurement Procedures

The following procedure describes the method of collecting the baseline neutron data of the DST. The COMPROBE continuously measures neutron counts, with a continuous, 2-sec smoothing of the counts. Standard counts, which are neutron counts when the tool is in its holder and thus independent of the influence of the rock mass to be measured, were measured and recorded immediately prior to, and subsequent to, performing measurements. The neutron probe was placed in a borehole at a specific location (depth), and the neutron count was hand-recorded in a scientific notebook; it was also recorded electronically in the device's memory. Upon completion of the test, data was downloaded to a computer, and the data values were checked against the hand-recorded values. Data were recorded at depth intervals of 10 cm in each borehole. The procedures are described in TIP-NF-31 (Lin, 1994).

In all of the boreholes, at least two measurements were conducted during the heating phase: one in February 1998 and one in March 1998. Originally, it was planned to start the in-heat measurement in the time window of December 1997 and January 1998. However, due to scheduling difficulty, only partial measurements were conducted in mid-December 1997 to detect any change of the moisture at the beginning of the heating phase. The partial measurements involved logging in some of the boreholes (49, 50, 66, and 67) at depths near the heaters. Not much change in the moisture content was detected (see Section 4.4 for details). A decision was made to start full-scale logging in February 1998 instead of in January 1998. In Borehole 50 (N04), the measurement on February 6, 1998, was repeated once to check for repeatability, as was the measurement in Borehole 67 (N09) on March 18, 1998.

4.3 Baseline Fraction Volume Water Contents

As reported previously (Lin et al., 1998), the baseline neutron logging was conducted in September, October, and November 1997. The baseline fraction volume water contents in the 12 boreholes in the DST are shown in **Figure 4-1** through **Figure 4-12**, for Boreholes ESF-HD-NEU-1 (N01) through ESF-HD-NEU-10 (N10) and ESF-HD-TEMP-1 (N11) through ESF-HD-TEMP-2 (N12), respectively. Each of these figures presents the two baseline neutron logs in the borehole. In all of these boreholes, baseline neutron logging was conducted after the Teflon liner had been grouted in place, so the water content in these boreholes is influenced by the water content in the grout. The grout had been cured prior to the baseline logging, so the grout water content was not expected to change during the test. However, if the hole experiences high temperatures then water, especially the excess water of hydration, will be driven out of the grouted hole; this could influence overall readings, because the overall

volume of water is higher in the grout. In addition to showing the baseline neutron logs in Borehole ESF-HD-TEMP-2 (N12), Figure 4-12 shows the neutron logs in this borehole before it was grouted.

Figure 4-1. Baseline fraction volume water content in Borehole 47 (N01).

Figure 4-2. Baseline fraction volume water content in Borehole 48 (N02).

Figure 4-3. Baseline fraction volume water content in Borehole 49 (N03).

Figure 4-4. Baseline fraction volume water content in Borehole 50 (N04).

Figure 4-5. Baseline fraction volume water content in Borehole 51 (N05).

Figure 4-6. Baseline fraction volume water content in Borehole 64 (N06).

Figure 4-7. Baseline fraction volume water content in Borehole 65 (N07).

Figure 4-8. Baseline fraction volume water content in Borehole 66 (N08).

Figure 4-9. Baseline fraction volume water content in Borehole 67 (N09).

Figure 4-10. Baseline fraction volume water content in Borehole 68 (N10).

Figure 4-11. Baseline fraction volume water content in Borehole 79 (N11).

Figure 4-12. Baseline fraction volume water content in Borehole 80 (N12). The data on 8/25/97 were collected before grouting.

Except for some localized spikes, which may be related to fractures, the baseline fraction volume water contents in the neutron boreholes N01 through N10 range from 0.07 to 0.15. As shown in Figure 4-1, there seems to be no grout in the deeper 12 m of Borehole 47 (N01), and the baseline fraction volume water there is only about 0.05. Figure 4-12 shows a similar situation in Borehole 80 (N12). The baseline fraction volume water contents in Boreholes 79 (N11) and 80 (N12) are greater than those in the other boreholes and range from 0.12 to 0.2. This may be at least partially due to the fact that the diameter of Boreholes 79 and 80 is 10.16 cm, and the nominal diameter of the other boreholes is 7.62 cm; therefore, the grout columns in N11 and N12 are thicker than those in the other boreholes. The relatively low fraction volume water content at the collar of most of those boreholes may be influenced by the environment outside the borehole. These boreholes will be closely watched during the logging in the heating phase of the DST. As shown in Figure 4-12, the water content in the grout has strong influence on the baseline fraction volume water content in a hole. Some of the water content is due to the excess hydration, which will change due to heating. The major portion of the fraction volume water in the grout will not change until the grout is

dehydrated. This will be taken into account in the data analyses. For Boreholes N01 through N10, the grout column is thinner than that in N12; therefore, the influence of the water in that grout will be much less.

4.4 Heating Phase Neutron Data and Discussion

The difference fraction volume water is calculated by subtracting the mean baseline fraction volume water (as shown in Figure 4-1 through Figure 4-12) from that measured during the heating phase. **Figure 4-13** through **Figure 4-36** show the difference fraction volume water content in the 12 boreholes (N01 through N12), in consecutive figures for each of the twelve neutron boreholes.

Figure 4-13. Difference fraction volume water content in Borehole 47 (N01), measured on 2/17/98 and 3/16/98.

Figure 4-14. Difference fraction volume water content in Borehole 47 (N01), measured on 4/22/98 and 5/19/98.

Figure 4-15. Difference fraction volume water content in Borehole 48 (N02), measured on 2/18/98 and 3/16/98.

Figure 4-16. Difference fraction volume water content in Borehole 48 (N02), measured on 4/22/98 and 5/19/98.

Figure 4-17. Difference fraction volume water content in Borehole 49 (N03), measured on 12/19/97, 2/6/98, and 3/16/98.

Figure 4-18. Difference fraction volume water content in Borehole 49 (N03), measured on 4/21/98 and 5/19/98.

Figure 4-19. Difference fraction volume water content in Borehole 50 (N04), measured on 12/18/97, 2/6/98, and 3/16/98.

Figure 4-20. Difference fraction volume water content in Borehole 50 (N04), measured on 4/21/98 and 5/19/98.

Figure 4-21. Difference fraction volume water content in Borehole 51 (N05), measured on 2/6/98 and 3/17/98.

Figure 4-22. Difference fraction volume water content in Borehole 51 (N05), measured on 4/21/98 and 5/19/98.

Figure 4-23. Difference fraction volume water content in Borehole 64 (N06), measured on 2/17/98 and 3/17/98.

- Figure 4-24.** Difference fraction volume water content in Borehole 64 (N06), measured on 4/20/98 and 5/18/98.
- Figure 4-25.** Difference fraction volume water content in Borehole 65 (N07), measured on 2/17/98 and 3/17/98.
- Figure 4-26.** Difference fraction volume water content in Borehole 65 (N07), measured on 4/20/98 and 5/18/98.
- Figure 4-27.** Difference fraction volume water content in Borehole 66 (N08), measured on 12/18/97, 2/11/98, and 3/17/98.
- Figure 4-28.** Difference fraction volume water content in Borehole 66 (N08), measured on 4/20/98 and 5/18/98.
- Figure 4-29.** Difference fraction volume water content in Borehole 67 (N09), measured on 12/18/97, 2/11/98, and 3/18/98.
- Figure 4-30.** Difference fraction volume water content in Borehole 67 (N09), measured on 4/15/98 and 5/18/98.
- Figure 4-31.** Difference fraction volume water content in Borehole 68 (N10), measured on 2/11/98 and 3/16/98.
- Figure 4-32.** Difference fraction volume water content in Borehole 68 (N10), measured on 4/21/98 and 5/18/98.
- Figure 4-33.** Difference fraction volume water content in Borehole 79 (N11), measured on 2/29/98 and 3/12/98.
- Figure 4-34.** Difference fraction volume water content in Borehole 79 (N11), measured on 4/23/98 and 5/20/98.
- Figure 4-35.** Difference fraction volume water content in Borehole 80 (N12), measured on 2/18/98 and 3/12/98.
- Figure 4-36.** Difference fraction volume water content in Borehole 80 (N12), measured on 4/23/98 and 5/20/98.

The difference fraction volume water contents in Boreholes 47 (N01) through 51 (N05) are shown in Figures 4-13 through 4-22. These boreholes form a fan-shaped cross-section that extends from the access/observation drift (AOD) to the heater drift (HD) at about 6.4 m from the bulkhead of the HD (CRWMS M&O, 1996). Figure 4-17 and Figure 4-19 show the results of the partial measurements mentioned in Section 4.2: that the moisture content in Boreholes 49 and 50 at depths near the heaters did not change much since the heating, except for the

appearance of some spikes of both increasing (positive) and decreasing (negative) moisture content. The spikes are localized phenomena. They may be related to the effect of fractures or other localized variations in water content. Figure 4-19 shows that the two measurements in Borehole 50 repeated well on February 6, 1998.

Figure 4-23 through Figure 4-32 show the difference fraction volume water contents in Boreholes 64 (N06) through 68 (N10), respectively. These boreholes form a fan-shaped cross-section that extends from the AOD to the HD at about 26.5 m from the bulkhead of the HD (CRWMS M&O, 1996). Figure 4-27 and Figure 4-29 show the results of the partial measurements mentioned in Section 4.2: that the moisture content in Boreholes 66 and 67 at depths near the heaters did not change much during the earlier period of heating, except for the appearance of some local variations, similar to those mentioned in preceding paragraph. Figure 4-23 and Figure 4-24 show that the water content in Borehole 64 (N06) measured in April and May 1998 seems to be slightly less than that in February and March 1998. The difference is statistically insignificant and may be just the beginning of a drying trend. Figure 4-25 and Figure 4-26 show that the water content in Borehole 65 (N07) seemed to be decreasing from February to April, but increased in May. Again, the variations were insignificant. Figure 4-27 and Figure 4-28 show that the water content in Borehole 66 (N08) had similar features as in Borehole 65. Figure 4-29 and Figure 4-30 show that a drying region has been further developed in Borehole 67 at about 18 m from the collar. The water content had decreased by about 18% in volume, and the drying region was enlarged. Among the five boreholes in this group, this borehole is located at a shortest distance from the wing heaters. The apparent drying in this part of the rock mass is consistent with the temperature data (Blair and Lin, 1998). However, Borehole 50 is located at about the same distance from the wing heaters, yet no drying is indicated (Figure 4-19 and Figure 4-20). These phenomena will be watched closely during the heating phase. Figure 4-29 also shows that the two measurements in Borehole 67 on March 18, 1998, repeated well. Figure 4-31 and Figure 4-32 show that the water content in Borehole 68 has been virtually unchanged.

Figure 4-33 and Figure 4-36 show the difference fraction volume water contents in Boreholes 79 and 80, respectively. These two boreholes are parallel to the axis of the HD and about 3.5 m above the wing heaters. A uniform drying trend had been developed in these two boreholes, and the drying rate between April and May 1998 seemed to be greater than before. Figure 4-35 and Figure 4-36 show that the moisture content in the deeper 15-m section of Borehole 80 increased relative to the outer portion of this borehole. As indicated in the baseline neutron logging (Lin et al., 1998), the deeper portion of this borehole is probably not grouted. At least part of the cause for the apparent increase in moisture content is the low baseline water content of an empty borehole, as shown in Figure 4-12. Other explanations of this apparent increase in the water content will be further investigated.

4.5 Summary

All of the baseline neutron data have been converted into fraction volume water content. Neutron measurements have been continuously conducted during the heating phase of the DST. Preliminary data indicate that, in about six months of heating, drying has occurred at certain locations near the wing heaters. Further analyses of neutron data will be conducted.

4.6 Future Plans

The DST continues in the heating phase. Neutron logging will be continued using the COMPROBE tool. Calibrations of both the COMPROBE tool and the CPN tool, in the exact Teflon-grout and Teflon-grout-RTD assemblies used in the DST, will be conducted. The baseline neutron counts and the future neutron counts during the heating phase will then be converted into fraction volume water contents. Neutron logging will continue approximately once per month.

4.7 References

- Blair, S.C., and W. Lin (1998). *First-Quarter Report of Temperature Measurements During the Heating Phase of the Drift-Scale Test*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (SP2640M4) Livermore, CA: Lawrence Livermore National Laboratory.
- CRWMS M&O (1996). *Test Design, Plans, and Layout for the First ESF Thermal Test*. (BAB000000-01717-4600-00025, Rev. 1) Las Vegas, NV: Civilian Radioactive Waste Management System Management and Operating Contractor: TRW Environmental Safety Systems, Inc. [MOL.19970114.0166]
- Lin, W. (1994). *Yucca Mountain Project Technical Implementation Plan, Neutron and Gamma (Density) Logging in Welded Tuff*. (TIP-NF-31, Rev. 1) Livermore, CA: Lawrence Livermore National Laboratory. [MOL.19941130.0025]
- Lin, W., R. Carlson, and D. Neubauber (1998). *First-Quarter Report of Neutron Logging During the Heating Phase of the Drift-Scale Test*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (UCRL-ID-129592) Livermore, CA: Lawrence Livermore National Laboratory.

Figure 4-1. Baseline fraction volume water content in Borehole #47 (N01).

Figure 4-2. Baseline fraction volume water content in Borehole #48 (N02).

4. Figures

Figure 4-3. Baseline fraction volume water content in Borehole #49 (N03).

Figure 4-4. Baseline fraction volume water content in Borehole #50 (N04).

Figure 4-5. Baseline fraction volume water content in Borehole #51 (N05).

Figure 4-6. Baseline fraction volume water content in Borehole #64 (N06).

4. Figures

Figure 4-7. Baseline fraction volume water content in Borehole #65 (N07).

Figure 4-8. Baseline fraction volume water content in Borehole #66 (N08).

Figure 4-9. Baseline fraction volume water content in Borehole #67 (N09).

Figure 4-10. Baseline fraction volume water content in Borehole #68 (N10).

4. Figures

Figure 4-11. Baseline fraction volume water content in Borehole #79 (N11).

Figure 4-12. Baseline fraction volume water content in Borehole #80 (N12).

Figure 4-13. Difference fraction volume water content in Borehole #47 (N01), measured on 2/17/98 and 3/16/98.

Figure 4-14. Difference fraction volume water content in Borehole #47 (N01), measured on 4/22/98 and 5/19/98.

4. Figures

Figure 4-15. Difference fraction volume water content in Borehole #48 (N02), measured on 2/18/98 and 3/16/98.

Figure 4-16. Difference fraction volume water content in Borehole #48 (N02), measured on 4/22/98 and 5/19/98.

Figure 4-17. Difference fraction volume water content in Borehole #49 (N03), measured on 12/19/97, 2/6/98, and 3/16/98.

Figure 4-18. Difference fraction volume water content in Borehole #49 (N03), measured on 4/21/98 and 5/19/98.

4. Figures

Figure 4-19. Difference fraction volume water content in Borehole #50 (N04), measured on 12/18/97, 2/6/98, and 3/16/98.

Figure 4-20. Difference fraction volume water content in Borehole #50 (N04), measured on 4/21/98 and 5/19/98.

Figure 4-21. Difference fraction volume water content in Borehole #51 (N05), measured on 2/6/98 and 3/17/98.

Figure 4-22. Difference fraction volume water content in Borehole #51 (N05), measured on 4/21/98 and 5/19/98.

4. Figures

Figure 4-23. Difference fraction volume water content in Hole #64 (N06), measured on 2/17/98 and 3/17/98.

Figure 4-24. Difference fraction volume water content in Borehole #64 (N06), measured on 4/20/98 and 5/18/98.

Figure 4-25. Difference fraction volume water content in Borehole #65 (N07), measured on 2/17/98 and 3/17/98.

Figure 4-26. Difference fraction volume water content in Borehole #65 (N07), measured on 4/20/98 and 5/18/98.

4. Figures

Figure 4-27. Difference fraction volume water content in Borehole #66 (N08), measured on 12/18/97, 2/11/98, and 3/17/98.

Figure 4-28. Difference fraction volume water content in Borehole #66 (N08), measured on 4/20/98 and 5/18/98.

Figure 4-29. Difference fraction volume water content in Borehole #67 (N09), measured on 12/18/97, 2/11/98, and 3/18/98.

Figure 4-30. Difference fraction volume water content in Borehole #67 (N09), measured on 4/15/98 and 5/18/98.

4. Figures

Figure 4-31. Difference fraction volume water content in Borehole #68 (N10), measured on 2/11/98 and 3/16/98.

Figure 4-32. Difference fraction volume water content in Borehole #68 (N10), measured on 4/21/98 and 5/18/98.

Figure 4-33. Difference fraction volume water content in Borehole #79 (N11), measured on 2/29/98 and 3/12/98.

Figure 4-34. Difference fraction volume water content in Borehole #79 (N11), measured on 4/23/98 and 5/20/98.

4. Figures

Figure 4-35. Difference fraction volume water content in Borehole #80 (N12), measured on 2/18/98 and 3/12/98.

Figure 4-36. Difference fraction volume water content in Borehole #80 (N12), measured on 4/23/98 and 5/20/98.

5. Gas and Water Chemistry

by Nina Rosenberg, Laura DeLoach, Marina Chiarappa, Roger Martinelli, and William Glassley

5.1 Introduction

As a consequence of heating the rock mass, complex chemical reactions between the fluids and minerals present may be expected. The chemistry studies in the Drift-Scale Test (DST) have been designed to gather geochemical information and assess the impact of thermal perturbations on gas and liquid phases present in pore spaces and fractures within the rock. Compositional changes in the pore fluids reflect dissolution and precipitation processes that implicate changes in flow paths and movement rates. By studying such chemical changes, better understanding and modeling of the nature and evolution of these rock-water interactions may be expected, and confidence may be built in models that will (of necessity) be used to predict and assess repository performance.

To assess the geochemical changes as a function of time, temperature, and position, ten chemistry boreholes have each been lined with two different sampling liner systems. Both employ SEAMIST™ liner technology (Science Engineering Associate Membrane In-situ Sampling Technology) which is an instrumentation and fluid sampler emplacement technique designed for in-situ hydrologic characterization and monitoring investigations. Gas samples and damp pads are collected from the boreholes and analyzed chemically. The gaseous phases are analyzed for the volume percent of atmospheric constituents (predominantly N₂, O₂, Ar, and CO₂). The pads are analyzed for a suite of ions typical of the total dissolved solids found in ground water samples from the vicinity of Yucca Mountain. Samples of the gas and moisture present in the heater drift atmosphere will also be collected through the plumbed ports on the bulkhead. The chemical composition of all the gases and liquids collected will be analyzed throughout the heating phase of the DST and the results will be reported as available.

5.2 Description of Chemistry Boreholes

Ten boreholes, two arrays of five boreholes each (52–56 and 69–73), are designated as chemistry boreholes (**Figure 5-1**). These boreholes were drilled from the access/observation drift (AOD) in planes that run normal to the heater drift (HD) and that are located approximately 15% and 45% of the way along the length of the drift, respectively, as measured from the bulkhead (see Figure 1-3 in the Introduction section). Each of the boreholes is about 40 m long and has been drilled at low angles directed just above or just below the heater plane. In each array, three boreholes are directed at increasingly steeper angles (< 25°) above the line of wing heaters, and two are directed at shallow angles below the wing heater plane.

Figure 5-1. Chemistry Boreholes 52–56 and 69–73.

Each chemistry borehole has been lined with two different sampling liner systems. Both employ SEAMIST™ liner technology, which uses an inverting, pneumatically deployed, tubular membrane to install sampling devices and instruments in uncased boreholes. One SEAMIST™ liner has been installed with Teflon™ tubing lines run to various depths and

ending at the collar of the hole with a port for sampling the gases originating from the rock walls. In the same hole and adjacent to this liner, a second SEAMIST™ liner has been installed with a linear array of highly absorbent pads for the collection of pore and condensate water samples. Pressurization of the gas-sampling liner to ~2 psi is designed to seal the borehole walls from the AOD atmosphere with both sampling liners in place. The liners provide ten pads for water sampling and six Teflon tubing lines for gas sampling, in three sets of two, along the length of the hole. The positions of the pads and ports within the boreholes are summarized in **Table 5-1** and shown in Figure 5-1. (In this section only, for clarity of text, tables are presented at the end, in Section 5.5.)

We have collected both gas and liquid samples. Two types of gas samples have been collected. The first type are discrete gas samples collected approximately monthly since the start of the test and analyzed at Lawrence Livermore National Laboratory (LLNL). The second type are near-continuous gas samples collected over a period of several days in April and June and analyzed in real time in the Exploratory Studies Facility (ESF). Some water was collected in a cold trap during the latter gas-sampling procedures and was volumetrically quantified and submitted for analysis. Two SEAMIST™ absorber liners have also been pulled, the pads removed for sampling, and the liners replaced; the pads have been submitted for analysis of fluids within the rock.

5.3 Methodology for Chemistry Sampling and Analysis

5.3.1 Discrete Gas Sampling and Analysis

Gas samples have been collected from the connecting drift (CD) and AOD by opening an evacuated canister to atmosphere at an appropriate location. Also, gas samples have been obtained from several of the chemistry boreholes using gas-tight syringes, which draw in gas through the Teflon tubing on the SEAMIST™ liner. Gases have similarly been collected using a syringe to sample the HD from ports in the bulkhead. The gas samples are then injected into previously-evacuated, stainless-steel vessels, which are stored and transported for later analysis. A series of gas samples are consecutively taken from the boreholes.

The sequence and volume of gas samples collected from Ports 1 and 2 (with a line volume of ~75 cc) are: A = 50 cc; B = 10 cc; C = 10 cc; D = 5 cc; E = 5 cc; and F = 10 cc. The sequence and volume of gas samples collected from Ports 3 and 4 (calculated line volume of ~43 cc) are: A = 25 cc; B = 10 cc; C = 5 cc; D = 5 cc; E = 5 cc; and F = 10 cc. The sequence and volume of gas samples collected from Ports 5 and 6 (calculated line volume of ~11 cc) are: A = 5 cc; B = 5 cc; C = 5 cc; D = 5 cc; E = 5 cc; and F = 10 cc.

All discrete gas samples are also labeled with sample management facility (SMF) identifiers and packed for transport to the gas mass spectrometry lab at LLNL. There, the collected gas samples are analyzed on a VG 30-01 gas analytical mass spectrometer for N₂, O₂, Ar, CO₂, CO, CH₄, He, and H₂. Additional gas components of molecular weight less than 160 are also identified if present above detection limits of 0.01%. Each sampling trip requires multiple gas-sampling vessels to be available, clean, and evacuated. As a consequence, samples cannot be archived nor held for additional future analyses.

5.3.2 Real-Time, Near-Continuous Gas Sampling and Analysis

In addition to the discrete gas samples, gas data are also being collected at frequent step intervals over a period of a few days. This sampling and real-time analysis is performed with a multichannel Columbus Instruments Gas Analyzer (Model 180C). Multiple gas streams are

sequentially multiplexed into the system sample pump through an expansion unit. The system sample pump dries the sample gas and then circulates the gas through each individual sensor at a constant flow and pressure. The Gas Analyzer is currently being used in the DST to measure O₂ and CO₂. CO₂ is measured by an infrared sensor and O₂ is measured by a paramagnetic sensor.

The presence of significant moisture in the HD air required the addition of a water trap, which provided an opportunity to condense and collect water. In these cases, the volume of this water is quantified, pH measured, and a sample collected for transport to LLNL for chemical analysis.

5.3.3 SEAMIST™ Pad Sampling and Analysis

When a SEAMIST™ absorber liner is removed, the pads are visually inspected for apparent moisture content and noteworthy physical variations. The pads are stored in clean, air-tight bags and sent to LLNL for chemical analysis.

Each pad is sectioned for three sets of inorganic analyses:

- **Metals or cations:** The total amount present regardless of the oxidative state is quantified via inductively coupled plasma (ICP). Samples are prepared through an acid-extraction procedure.
 - Aluminum (Al)
 - Boron (B)
 - Calcium (Ca)
 - Iron (Fe)
 - Magnesium (Mg)
 - Lithium (Li)
 - Sodium (Na)
 - Potassium (K)
 - Sulfur (S)
 - Silicon (Si)
 - Strontium (Sr)
- **Anions:** Analysis is by ion chromatography (IC). Samples are prepared by a water-extraction procedure.
 - Fluoride (F⁻)
 - Chloride (Cl⁻)
 - Bromide (Br⁻)
 - Nitrite (NO₂⁻)
 - Nitrate (NO₃⁻)
 - Phosphate (PO₄³⁻)
 - Sulfate (SO₄²⁻)
- **Carbonates:** Carbonate (CO₃²⁻) will be analyzed via an infrared analysis technique where CO₂ is liberated from the carbonate and quantified. The carbon dioxide generated by acidification of the pad material is directly proportional to the carbonate present.

5.4 Results

5.4.1 Gas Data

Gas data are reported in volume percent, exclusive of water vapor. Therefore, to determine total CO₂ or O₂ in the gas phase, these values need to be multiplied by the ratio air/(air + water vapor).

All gas data must be considered preliminary at this time because the complete quality-assurance requirements have not been satisfied. Nevertheless, all data were collected on a fully calibrated system by acceptable methods employed in gas mass-spectrometry labs or according to manufacturer specifications and are expected to be Q-pedigreed according to QARD procedures.

5.4.1.1 Discrete Gas Data

Gas sampling from the chemical study boreholes in the DST has occurred approximately monthly since the start of the test, in coordination with the air-permeability studies and tracer-gas testing conducted by Lawrence Berkeley National Laboratory (LBNL). The focus of the sampling efforts has been the chemistry boreholes that are closest to the heaters and from the gas-sampling ports in them that end nearest the heaters.

Data are reported for gas samples collected between December 1997 and April 1998 and are presented in **Table 5-2** through **Table 5-6**. CO₂ is perhaps slightly elevated with respect to atmospheric levels, which are typically around 0.03%. A plot of average CO₂ values for samples collected between December 1997 and April 1998 is shown in **Figure 5-2**. The tabulated data and the plotted graphs, however, suggest that CO₂ fluctuates with time. Although additional samples were collected in late May and early June, analyses of those samples are not yet available. No data were reported above detection limits for CO, CH₄, He, and H₂, so these components have been omitted from the tables.

Figure 5-2. Percent CO₂ for discrete gas samples collected between December 1997 and April 1998. These are averaged values based on samples “D”, “E”, and “F” (in the case of borehole gases) or averages of all the measured values for atmospheric samples collected during a particular trip.

5.4.1.2 Real-Time, Near-Continuous Gas Data

Real-time, near-continuous CO₂ and O₂ data were collected over several days in April from the HD and the CD and again in June from the HD, the CD, the AOD, and several borehole locations. Borehole locations included chemistry Boreholes 54 (ports 1, 3 and 5) and 55 (ports 1 and 3) and hydrology Borehole 59, zone 4 (close to 54-1). These data are presented in **Table 5-7** through **Table 5-18** and in **Figure 5-3** through **Figure 5-11**.

Figure 5-3. Gas analyses of heater-drift atmosphere, sampled during April 1998. In Figures 5-3 through 5-6, three channels each sample and measure O₂ and CO₂, but the differences among the channels are insignificant.

Figure 5-4. Gas analyses of heater-drift atmosphere, sampled during June 1998.

- Figure 5-5.** Gas analyses of connecting-drift atmosphere, sampled during April 1998.
- Figure 5-6.** Gas analyses of connecting-drift atmosphere, sampled during June 1998.
- Figure 5-7.** Gas analyses of Borehole 54, sampled during June 1998. O₂ and CO₂ readings appear to depend on sampling port.
- Figure 5-8.** Gas analyses of Borehole 55, sampled during June 1998. Differences between the two channels measuring O₂ and CO₂ are insignificant.
- Figure 5-9.** Gas analyses of hydrology Borehole 59, zone 4, sampled during June 1998. A slight trend toward higher O₂ and CO₂ values is measured over this time period.
- Figure 5-10.** CO₂ analyses of hydrology Borehole 59 and nearby chemistry Borehole 54.
- Figure 5-11.** Gas analyses of access/observation-drift atmosphere, sampled during June 1998. Three channels each sample and measure O₂ and CO₂ and do not display significantly different values.

These data definitively show that there is a time dependence to the CO₂ and O₂ levels measured. An initial examination of the HD atmospheric-pressure readings corresponding to the same time interval would not appear to support a direct relation (**Figure 5-12**). This is consistent with observations of occasional elevated CO₂ readings from the discrete gas samples collected on a monthly basis.

- Figure 5-12.** CO₂ levels observed in the heater-drift atmosphere and air-pressure readings obtained during corresponding time intervals.

These data also show that CO₂ levels in the HD, the CD, the AOD, and the chemistry boreholes are still not significantly different from ambient levels. Measurements for hydrology Borehole 59, zone 4, is, however, significantly elevated (~0.4–0.6%), consistent with LBNL gas measurements. This provides confidence in our analytical methods, but suggests that drift air is diluting the samples we collect from the chemistry boreholes. We are currently investigating possible leakage of the pressurized liners into the chemistry boreholes.

Table 5-19 gives the details on the water collected during the gas sampling and the temperature and relative humidity of the HD at the start of sampling, as noted from the large information display by the bulkhead. Using the temperature and humidity data available, calculations of the moisture present in the HD atmosphere were compared with the amount of water collected; these values agreed, to a rough approximation.

5.4.2 Water Chemistry and Moisture Distribution Data

To date, the absorbent liner systems used for water collection have been pulled from Boreholes 55 (April 20, 1998) and 56 (May 5, 1998). Borehole 55 contained a large amount of water and all the pads showed signs of being saturated at some point in time. All were wet during removal except for pad 6, located ~19 m down the borehole. The location is in good

agreement with neutron data from Borehole 69 (at approximately the same orientation as Borehole 55), which shows a drying region at about the same depth. Pads from Borehole 56 were also damp but not saturated, as was observed from Borehole 55. Both liners had contacted mud, and solid particulates adhered to the pads, potentially complicating the chemical analysis of the fluids.

All the water samples collected to date from gas sampling in April and June and from the SEAMIST™ pads from Borehole 55 and 56 are currently being analyzed. pH data from these samples are reported in **Table 5-20**. All pH measurements are between 7.1 and 8.6.

5.5 Tables

Table 5-1. Distance of gas-sampling ports and absorbent pads (in meters) from the collar of each borehole.

ESF-HD-CHE- sensors	Hole 52 ...CHE-1	Hole 53 ...CHE-2	Hole 54 ...CHE-3	Hole 55 ...CHE-4	Hole 56 ...CHE-5	Hole 69 ...CHE-6	Hole 70 ...CHE-7	Hole 71 ...CHE-8	Hole 72 ...CHE-9	Hole 73 ...CHE-10
ports 1, 2	none ^a	none	35.0	31.0	35.0	34.0	35.0	35.1	35.1	35.1
ports 3, 4	17.1	15.0	18.9	18.9	18.9	18.0	18.9	18.9	18.9	18.9
ports 5, 6	1.2	1.2	3.1	3.1	3.1	2.1	3.1	3.1	3.1	3.1
absorber 1	none	none	39.0	none	none	none	none	39.0	none	none
absorber 2	none	none	35.1	35.1	35.1	none	none	35.1	35.1	none
absorber 3	31.1	none	31.1	31.1	31.1	none	none	31.1	31.1	31.0
absorber 4	27.1	none	27.1	27.1	27.1	none	none	27.1	27.1	27.1
absorber 5	22.9	none	22.9	22.9	22.9	none	none	22.9	22.9	22.9
absorber 6	18.9	none	18.9	18.9	18.9	18.9	19.0	18.9	18.9	18.9
absorber 7	14.9	15.0	14.9	14.9	14.9	15.0	15.0	14.9	14.9	14.9
absorber 8	11.0	11.0	11.0	11.0	11.0	11.0	11.0	11.0	11.0	11.0
absorber 9	17.1	7.0	7.0	7.0	7.0	7.0	7.0	7.0	7.0	7.0
absorber 10	3.1	3.0	3.1	3.1	3.1	3.0	3.0	3.1	3.1	3.1

^a The designation "none" results from a shortened liner with respect to other holes; in one case (Borehole 55) the hole itself is shorter, but most cases arise from the liner being blocked from full extension.

Table 5-2. Analyses for discrete gas samples collected December 2, 1997.^a

All results are expressed in mole (volume) percent and are not corrected for water vapor.

Sample^b	Nitrogen	Oxygen	Argon	Carbon dioxide
54-1A	77.48	21.55	0.95	0.02
54-1B	76.94	22.07	0.94	0.04
54-1C	76.98	22.02	0.94	0.06
54-1D	77.38	21.65	0.92	0.05
54-1E	77.19	21.86	0.93	0.02
54-1F	77.15	21.86	0.92	0.07
54-3A	77.49	21.55	0.93	0.04
54-3B	76.92	22.11	0.92	0.05
54-3C	76.79	22.15	0.93	0.13
54-3D	77.26	21.76	0.91	0.07
54-3E	77.14	21.73	0.91	0.22
54-3F	77.52	21.50	0.91	0.07
54-5A	77.00	22.03	0.93	0.05
54-5B	76.93	22.09	0.93	0.05
54-5C	77.46	21.57	0.92	0.06
54-5D	77.21	21.82	0.92	0.05
54-5E	77.14	21.87	0.92	0.07
56-1A	77.85	21.22	0.90	0.02
56-1B	77.50	21.54	0.91	0.06
56-1C	77.64	21.39	0.91	0.06
56-1D	75.02	23.89	1.01	0.08
56-1E	77.63	21.42	0.92	0.03
56-3A	78.12	20.94	0.92	0.02
56-3B	77.43	21.59	0.91	0.07
56-3C	77.66	21.39	0.92	0.03
56-3D	77.56	21.48	0.92	0.04
56-3E	77.48	21.57	0.92	0.03
OD-1	77.36	21.65	0.92	0.06
HD-1	77.12	21.86	0.93	0.09

^a These data are preliminary because QA requirements are not complete.

Table entries for CO, CH₄, He, and H₂ have been omitted because all are reported undetectable.

^b Samples are assigned a unique descriptive tracking identifier for each trip, but are identified in tables by borehole and port.

Table 5-3. Analyses for discrete gas samples collected January 13, 1998.^a
All results are expressed in mole (volume) percent and are not corrected for water vapor.

Sample ^b	Nitrogen	Oxygen	Argon	Carbon dioxide
54-1A	76.69	22.33	0.95	0.03
54-1B	77.36	21.67	0.93	0.04
54-1C	77.04	21.99	0.93	0.04
54-1D	77.02	22.00	0.93	0.05
54-1E	76.91	22.11	0.93	0.04
54-1F	76.90	22.09	0.94	0.07
54-3A	76.86	22.15	0.93	0.06
54-3B	76.88	22.12	0.93	0.08
54-3C	77.58	21.45	0.92	0.04
54-3D	77.48	21.56	0.91	0.05
54-3E	77.37	21.66	0.92	0.06
54-3F	77.33	21.70	0.92	0.05
55-1A	77.37	21.66	0.92	0.05
55-1B	77.77	21.26	0.92	0.05
55-1C	77.73	21.31	0.91	0.05
55-1D	77.50	21.53	0.91	0.05
55-1E	77.54	21.50	0.91	0.05
55-1F	77.65	21.41	0.89	0.06
55-3A	77.43	21.60	0.91	0.06
55-3B	77.32	21.71	0.92	0.05
55-3C	77.46	21.58	0.91	0.05
55-3D	77.46	21.53	0.91	0.09
55-3E	77.34	21.69	0.91	0.06
55-3F	77.65	21.41	0.90	0.04
56-1A	77.81	21.26	0.90	0.04
56-1B	77.61	21.45	0.90	0.04
56-1C	77.31	21.72	0.92	0.06
56-1D	77.53	21.51	0.91	0.05
56-1E	77.48	21.56	0.91	0.05
56-1F	77.34	21.71	0.91	0.05
56-3A	76.73	22.30	0.92	0.06
56-3B	77.35	21.70	0.90	0.05
56-3C	77.37	21.66	0.92	0.05

Sample ^b	Nitrogen	Oxygen	Argon	Carbon dioxide
56-3D	77.09	21.93	0.92	0.06
56-3E	76.83	22.12	0.93	0.12
56-3F	77.15	21.87	0.92	0.06
HD-1	77.54	21.49	0.91	0.06
HD-2	77.46	21.56	0.92	0.06
HD-3	77.43	21.61	0.91	0.05
OD-1	77.43	21.54	0.91	0.12

^a These data are preliminary because QA requirements are not complete.

Shaded rows represent sample vessels which may have opened during transit.

Table entries for CO, CH₄, He, and H₂ have been omitted because all are reported undetectable.

^b Samples are assigned a unique descriptive tracking identifier for each trip, but are identified in tables by borehole and port.

Table 5-4. Analyses for discrete gas samples collected February 19, 1998.^a

All results are expressed in mole (volume) percent and are not corrected for water vapor.

Sample ^b	Nitrogen	Oxygen	Argon	Carbon dioxide
54-1A	77.61	21.41	0.91	0.07
54-1B	77.29	21.74	0.91	0.06
54-1C	77.20	21.84	0.91	0.05
54-1D	77.23	21.80	0.91	0.05
54-1E	77.41	21.62	0.91	0.05
54-1F	77.33	21.72	0.91	0.04
54-3A	77.68	21.34	0.93	0.05
54-3B	77.53	21.50	0.93	0.05
54-3C	77.41	21.61	0.93	0.05
54-3D	77.48	21.55	0.93	0.05
54-3E	77.43	21.59	0.93	0.05
54-3F	77.41	21.62	0.93	0.05
55-1A	77.38	21.65	0.93	0.05
55-1B	77.37	21.65	0.93	0.05
55-1C	77.38	21.65	0.92	0.05
55-1D	77.25	21.79	0.92	0.05
55-1E	77.28	21.75	0.92	0.05
55-1F	77.18	21.85	0.93	0.05
55-3A	77.22	21.81	0.93	0.04
55-3B	77.23	21.74	0.92	0.10
55-3C	77.27	21.76	0.93	0.05

5. Gas and Water Chemistry

Sample ^b	Nitrogen	Oxygen	Argon	Carbon dioxide
55-3D	77.26	21.77	0.93	0.05
55-3E	77.48	21.56	0.92	0.04
55-3F	77.35	21.69	0.92	0.05
56-3A	75.83	23.20	0.93	0.04
56-3B	76.46	22.56	0.92	0.05
56-3C	76.82	22.22	0.92	0.05
56-3D	76.89	22.09	0.92	0.10
56-3E ^c	76.82	22.18	0.93	0.06
56-3F	76.64	22.37	0.92	0.07
CD-1	76.64	22.37	0.92	0.07
HD-1	77.26	21.77	0.91	0.06
OD-1	77.25	21.76	0.92	0.07

^a These data are preliminary because the QA requirements are not complete.

^b Samples are assigned a unique descriptive tracking identifier for each trip, but are identified in tables by borehole and port.

^c 0.01 H₂ was reported for sample 56-3E; other table entries for CO, CH₄, He, and H₂ have been omitted because all are reported undetectable.

Table 5-5. Analyses for discrete gas samples collected March 25, 1998.^a

All results are expressed in mole (volume) percent and are not corrected for water vapor.

Sample ^b	Nitrogen	Oxygen	Argon	Carbon dioxide
54-1A	77.51	21.50	0.94	0.05
54-1B	77.40	21.59	0.94	0.07
54-1C	77.47	21.52	0.94	0.07
54-1D	77.52	21.46	0.94	0.07
54-1E	77.29	21.70	0.95	0.06
54-1F	77.41	21.57	0.95	0.07
54-3A	77.13	21.88	0.94	0.05
54-3B	77.08	21.93	0.94	0.05
54-3C	77.62	21.39	0.94	0.05
54-3D	77.13	21.88	0.94	0.05
54-3E	77.14	21.87	0.94	0.05
54-3F	77.12	21.90	0.94	0.05
55-1A	77.07	21.94	0.94	0.05
55-1B	77.06	21.95	0.94	0.05
55-1C	77.12	21.89	0.94	0.05
55-1D	77.10	21.90	0.94	0.05

Sample ^b	Nitrogen	Oxygen	Argon	Carbon dioxide
55-1E	77.28	21.73	0.94	0.05
55-1F	77.13	21.89	0.94	0.05
55-3A	77.04	21.97	0.94	0.04
55-3B	77.07	21.94	0.94	0.05
55-3C	77.11	21.89	0.94	0.05
55-3D	77.04	21.97	0.94	0.05
55-3E	77.08	21.93	0.94	0.05
55-3F	77.02	21.99	0.94	0.05
56-3A	77.15	21.86	0.94	0.04
56-3B	77.39	21.63	0.94	0.04
56-3C	77.28	21.73	0.94	0.05
56-3D	77.30	21.70	0.94	0.05
56-3E	77.26	21.75	0.94	0.05
56-3F	77.25	21.76	0.94	0.05
71-1A	77.33	21.68	0.95	0.04
71-1B	77.45	21.54	0.93	0.08
71-1C	77.41	21.59	0.93	0.07
71-1D	77.42	21.57	0.94	0.08
71-1E	77.38	21.61	0.94	0.07
71-1F	77.43	21.56	0.94	0.07
71-3A	77.21	21.82	0.94	0.03
71-3B	77.22	21.80	0.94	0.04
71-3C	78.09	20.91	0.95	0.04
71-3D	77.49	21.52	0.95	0.04
71-3E	77.38	21.63	0.94	0.05
71-3F	77.33	21.69	0.94	0.04
HD-1	77.47	21.51	0.94	0.09
HD-2	77.44	21.56	0.94	0.06
OD-1	77.31	21.70	0.94	0.05

^a These data are preliminary because the QA requirements are not complete.

Table entries for CO, CH₄, He, and H₂ have been omitted because all are reported undetectable.

^b Samples are assigned a unique descriptive tracking identifier for each trip, but are identified in tables by borehole and port.

Table 5-6. Analyses for discrete gas samples collected April 21, 1998.^a

All results are expressed in mole (volume) percent and are not corrected for water vapor.

Sample ^b	Nitrogen	Oxygen	Argon	Carbon dioxide
54-1A	77.41	21.60	0.93	0.07
54-1B	76.94	22.07	0.94	0.05
54-1C	77.40	21.52	0.93	0.16
54-1D	76.80	22.21	0.94	0.05
54-1E	76.91	22.09	0.93	0.07
54-1F	76.83	22.19	0.93	0.05
54-3A	77.58	21.46	0.92	0.04
54-3B	77.42	21.61	0.93	0.05
54-3C	77.34	21.67	0.93	0.06
54-3D	77.36	21.65	0.92	0.06
54-3E	77.35	21.66	0.93	0.07
54-3F	77.34	21.68	0.93	0.05
56-1A	77.83	21.19	0.92	0.06
56-1B	77.48	21.54	0.93	0.06
56-1C	77.57	21.45	0.92	0.05
56-1D	77.61	21.40	0.92	0.07
56-1E	77.64	21.39	0.92	0.05
56-1F	77.72	21.32	0.92	0.05
56-3A	76.24	22.73	0.95	0.07
56-3B	77.23	21.79	0.94	0.05
56-3C	77.30	21.72	0.93	0.06
56-3D	77.24	21.78	0.93	0.05
56-3E	77.50	21.51	0.93	0.06
56-3F	77.64	21.37	0.93	0.07
HD-1	77.50	21.52	0.93	0.06
HD-2	77.44	21.55	0.93	0.09
OD-1	77.33	21.67	0.93	0.07

^a These data are preliminary because the QA requirements are not complete.

Table entries for CO, CH₄, He, and H₂ have been omitted because all are reported undetectable.

^b Samples are assigned a unique descriptive tracking identifier for each trip, but are identified in tables by borehole and port.

Table 5-7. CO₂ (mole [volume] percent) by time, connecting drift, April 1998.

Date and time	CD-1	Date and time	CD-2	Date and time	CD-3
4/21/98 10:44	0.05	4/21/98 10:50	0.05	4/21/98 10:57	0.05
4/21/98 11:24	0.06	4/21/98 11:30	0.06	4/21/98 11:37	0.06
4/21/98 12:23	0.04	4/21/98 12:30	0.04	4/21/98 12:36	0.04
4/21/98 13:03	0.04	4/21/98 13:10	0.03	4/21/98 13:16	0.03
4/21/98 13:43	0.03	4/21/98 13:50	0.03	4/21/98 13:56	0.03
4/21/98 14:23	0.03	4/21/98 14:30	0.03	4/21/98 14:36	0.03
4/21/98 15:03	0.03	4/21/98 15:10	0.03	4/21/98 15:16	0.03
4/21/98 15:43	0.04	4/21/98 15:50	0.04	4/21/98 15:56	0.03
4/21/98 16:23	0.04	4/21/98 16:30	0.03	4/21/98 16:36	0.04
4/21/98 17:03	0.03	4/21/98 17:10	0.03	4/21/98 17:16	0.04
4/21/98 17:43	0.04	4/21/98 17:50	0.04	4/21/98 17:56	0.04
4/21/98 18:23	0.03	4/21/98 18:30	0.03	4/21/98 18:36	0.03
4/21/98 19:03	0.03	4/21/98 19:10	0.03	4/21/98 19:16	0.03
4/21/98 19:43	0.03	4/21/98 19:50	0.03	4/21/98 19:56	0.03
4/21/98 20:23	0.04	4/21/98 20:30	0.03	4/21/98 20:36	0.04
4/21/98 21:03	0.04	4/21/98 21:10	0.04	4/21/98 21:16	0.04
4/21/98 21:43	0.04	4/21/98 21:50	0.04	4/21/98 21:56	0.04
4/21/98 22:23	0.04	4/21/98 22:30	0.04	4/21/98 22:36	0.04
4/21/98 23:03	0.04	4/21/98 23:10	0.04	4/21/98 23:16	0.04
4/21/98 23:43	0.04	4/21/98 23:50	0.04	4/21/98 23:56	0.04
4/22/98 0:23	0.04	4/22/98 0:30	0.04	4/22/98 0:36	0.04
4/22/98 1:03	0.04	4/22/98 1:10	0.04	4/22/98 1:16	0.04
4/22/98 1:43	0.04	4/22/98 1:50	0.04	4/22/98 1:56	0.04
4/22/98 2:23	0.04	4/22/98 2:30	0.04	4/22/98 2:36	0.04
4/22/98 3:03	0.04	4/22/98 3:10	0.03	4/22/98 3:16	0.04
4/22/98 3:43	0.04	4/22/98 3:50	0.04	4/22/98 3:56	0.04
4/22/98 4:23	0.04	4/22/98 4:30	0.04	4/22/98 4:36	0.03
4/22/98 5:03	0.03	4/22/98 5:10	0.04	4/22/98 5:16	0.04
4/22/98 5:43	0.03	4/22/98 5:50	0.03	4/22/98 5:56	0.03
4/22/98 6:23	0.03	4/22/98 6:30	0.03	4/22/98 6:36	0.03
4/22/98 7:03	0.03	4/22/98 7:10	0.03	4/22/98 7:16	0.03
4/22/98 7:43	0.03	4/22/98 7:50	0.03	4/22/98 7:56	0.03
4/22/98 8:23	0.03	4/22/98 8:30	0.03	4/22/98 8:36	0.04
4/22/98 9:52	0.03	4/22/98 9:58	0.03	4/22/98 10:05	0.03
4/22/98 10:32	0.03	4/22/98 10:38	0.04	4/22/98 10:45	0.04

5. Gas and Water Chemistry

Date and time	CD-1	Date and time	CD-2	Date and time	CD-3
4/22/98 11:12	0.04	4/22/98 11:18	0.04	4/22/98 11:25	0.04
4/22/98 11:52	0.04	4/22/98 11:58	0.04	4/22/98 12:05	0.03
4/22/98 12:32	0.04	4/22/98 12:38	0.03	4/22/98 12:45	0.04
4/22/98 13:12	0.04	4/22/98 13:18	0.03	4/22/98 13:25	0.03
4/22/98 13:52	0.03	4/22/98 13:58	0.04	4/22/98 14:05	0.03
4/22/98 14:32	0.03	4/22/98 14:38	0.02	4/22/98 14:45	0.02
4/22/98 15:12	0.02	4/22/98 15:18	0.02	4/22/98 15:25	0.02
4/22/98 15:52	0.02	4/22/98 15:58	0.02	4/22/98 16:05	0.02
4/22/98 16:32	0.02	4/22/98 16:38	0.02	4/22/98 16:45	0.02
4/22/98 17:12	0.02	4/22/98 17:18	0.02	4/22/98 17:25	0.02
4/22/98 17:52	0.02	4/22/98 17:58	0.02	4/22/98 18:05	0.02
4/22/98 18:32	0.02	4/22/98 18:38	0.02	4/22/98 18:45	0.02
4/22/98 19:12	0.01	4/22/98 19:18	0.01	4/22/98 19:25	0.01
4/22/98 19:52	0.02	4/22/98 19:58	0.01	4/22/98 20:05	0.02
4/22/98 20:32	0.02	4/22/98 20:38	0.02	4/22/98 20:45	0.02
4/22/98 21:12	0.01	4/22/98 21:18	0.01	4/22/98 21:25	0.01
4/22/98 21:52	0.02	4/22/98 21:58	0.02	4/22/98 22:05	0.01
4/22/98 22:32	0.02	4/22/98 22:38	0.02	4/22/98 22:45	0.02
4/22/98 23:12	0.01	4/22/98 23:18	0.01	4/22/98 23:25	0.01
4/22/98 23:52	0.02	4/22/98 23:58	0.02	4/23/98 0:05	0.02
4/23/98 0:32	0.02	4/23/98 0:38	0.02	4/23/98 0:45	0.02
4/23/98 1:12	0.02	4/23/98 1:18	0.01	4/23/98 1:25	0.01
4/23/98 1:52	0.01	4/23/98 1:58	0.01	4/23/98 2:05	0.01
4/23/98 2:32	0.01	4/23/98 2:38	0.01	4/23/98 2:45	0.01
4/23/98 3:12	0.01	4/23/98 3:18	0.01	4/23/98 3:25	0.01
4/23/98 3:52	0.01	4/23/98 3:58	0.01	4/23/98 4:05	0.01
4/23/98 4:32	0.01	4/23/98 4:38	0.01	4/23/98 4:45	0.01
4/23/98 5:12	0.01	4/23/98 5:18	0.01	4/23/98 5:25	0.01
4/23/98 5:52	0.01	4/23/98 5:58	0.01	4/23/98 6:05	0.01
4/23/98 6:32	0.01	4/23/98 6:38	0.01	4/23/98 6:45	0.01
4/23/98 7:12	0.01	4/23/98 7:18	0.01	4/23/98 7:25	0.01
4/23/98 7:52	0.01	4/23/98 7:58	0.01	4/23/98 8:05	0.01
4/23/98 8:32	0.01	4/23/98 8:38	0.01	4/23/98 8:45	0.01
4/23/98 9:12	0.02	4/23/98 9:18	0.02	4/23/98 9:25	0.02
4/23/98 9:52	0.02	4/23/98 9:58	0.02	4/23/98 10:05	0.02
4/23/98 10:32	0.02	4/23/98 10:38	0.02	4/23/98 10:45	0.02

Date and time	CD-1	Date and time	CD-2	Date and time	CD-3
4/23/98 11:12	0.02	4/23/98 11:18	0.02	4/23/98 11:25	0.02
4/23/98 11:52	0.01	4/23/98 11:58	0.01	4/23/98 12:05	0.01
4/23/98 12:32	0.01	4/23/98 12:38	0.01	4/23/98 12:45	0.01

Table 5-8. CO₂ (mole [volume] percent) by time, heater drift, April 1998.

Date and time	HD-1	Date and time	HD-2	Date and time	HD-3
4/21/98 10:24	0.04	4/21/98 10:31	0.05	4/21/98 10:37	0.05
4/21/98 11:04	0.05	4/21/98 11:11	0.05	4/21/98 11:17	0.05
4/21/98 12:04	0.04	4/21/98 12:10	0.04	4/21/98 12:17	0.04
4/21/98 12:44	0.04	4/21/98 12:50	0.04	4/21/98 12:57	0.04
4/21/98 13:24	0.03	4/21/98 13:30	0.03	4/21/98 13:37	0.03
4/21/98 14:04	0.03	4/21/98 14:10	0.03	4/21/98 14:17	0.03
4/21/98 14:44	0.03	4/21/98 14:50	0.03	4/21/98 14:57	0.03
4/21/98 15:24	0.03	4/21/98 15:30	0.03	4/21/98 15:37	0.03
4/21/98 16:04	0.03	4/21/98 16:10	0.03	4/21/98 16:17	0.04
4/21/98 16:44	0.04	4/21/98 16:50	0.04	4/21/98 16:57	0.04
4/21/98 17:24	0.04	4/21/98 17:30	0.03	4/21/98 17:37	0.04
4/21/98 18:04	0.04	4/21/98 18:10	0.04	4/21/98 18:17	0.04
4/21/98 18:44	0.04	4/21/98 18:50	0.04	4/21/98 18:57	0.04
4/21/98 19:24	0.04	4/21/98 19:30	0.04	4/21/98 19:37	0.04
4/21/98 20:04	0.03	4/21/98 20:10	0.04	4/21/98 20:17	0.04
4/21/98 20:44	0.04	4/21/98 20:50	0.04	4/21/98 20:57	0.04
4/21/98 21:24	0.04	4/21/98 21:30	0.04	4/21/98 21:37	0.04
4/21/98 22:04	0.04	4/21/98 22:10	0.04	4/21/98 22:17	0.04
4/21/98 22:44	0.04	4/21/98 22:50	0.04	4/21/98 22:57	0.04
4/21/98 23:24	0.04	4/21/98 23:30	0.04	4/21/98 23:37	0.04
4/22/98 0:04	0.04	4/22/98 0:10	0.04	4/22/98 0:17	0.04
4/22/98 0:44	0.04	4/22/98 0:50	0.04	4/22/98 0:57	0.04
4/22/98 1:24	0.04	4/22/98 1:30	0.04	4/22/98 1:37	0.04
4/22/98 2:04	0.04	4/22/98 2:10	0.04	4/22/98 2:17	0.04
4/22/98 2:44	0.04	4/22/98 2:50	0.04	4/22/98 2:57	0.04
4/22/98 3:24	0.04	4/22/98 3:30	0.04	4/22/98 3:37	0.04
4/22/98 4:04	0.04	4/22/98 4:10	0.04	4/22/98 4:17	0.04
4/22/98 4:44	0.04	4/22/98 4:50	0.04	4/22/98 4:57	0.04
4/22/98 5:24	0.04	4/22/98 5:30	0.04	4/22/98 5:37	0.04
4/22/98 6:04	0.04	4/22/98 6:10	0.04	4/22/98 6:17	0.04

5. Gas and Water Chemistry

Date and time	HD-1	Date and time	HD-2	Date and time	HD-3
4/22/98 6:44	0.04	4/22/98 6:50	0.03	4/22/98 6:57	0.04
4/22/98 7:24	0.03	4/22/98 7:30	0.03	4/22/98 7:37	0.04
4/22/98 8:04	0.04	4/22/98 8:10	0.04	4/22/98 8:17	0.04
4/22/98 8:44	0.04	4/22/98 8:50	0.04	4/22/98 8:57	0.04
4/22/98 9:32	0.04	4/22/98 9:39	0.03	4/22/98 9:45	0.03
4/22/98 10:12	0.03	4/22/98 10:19	0.03	4/22/98 10:25	0.03
4/22/98 10:52	0.03	4/22/98 10:59	0.03	4/22/98 11:05	0.03
4/22/98 11:32	0.06	4/22/98 11:39	0.05	4/22/98 11:45	0.06
4/22/98 12:12	0.09	4/22/98 12:19	0.07	4/22/98 12:25	0.09
4/22/98 12:52	0.11	4/22/98 12:59	0.09	4/22/98 13:05	0.09
4/22/98 13:32	0.09	4/22/98 13:39	0.09	4/22/98 13:45	0.09
4/22/98 14:12	0.08	4/22/98 14:19	0.07	4/22/98 14:25	0.07
4/22/98 14:52	0.06	4/22/98 14:59	0.06	4/22/98 15:05	0.05
4/22/98 15:32	0.06	4/22/98 15:39	0.05	4/22/98 15:45	0.05
4/22/98 16:12	0.05	4/22/98 16:19	0.05	4/22/98 16:25	0.05
4/22/98 16:52	0.05	4/22/98 16:59	0.05	4/22/98 17:05	0.05
4/22/98 17:32	0.04	4/22/98 17:39	0.05	4/22/98 17:45	0.04
4/22/98 18:12	0.04	4/22/98 18:19	0.04	4/22/98 18:25	0.04
4/22/98 18:52	0.04	4/22/98 18:59	0.04	4/22/98 19:05	0.04
4/22/98 19:32	0.04	4/22/98 19:39	0.03	4/22/98 19:45	0.03
4/22/98 20:12	0.03	4/22/98 20:19	0.03	4/22/98 20:25	0.03
4/22/98 20:52	0.03	4/22/98 20:59	0.03	4/22/98 21:05	0.03
4/22/98 21:32	0.03	4/22/98 21:39	0.03	4/22/98 21:45	0.03
4/22/98 22:12	0.03	4/22/98 22:19	0.03	4/22/98 22:25	0.03
4/22/98 22:52	0.03	4/22/98 22:59	0.03	4/22/98 23:05	0.03
4/22/98 23:32	0.03	4/22/98 23:39	0.03	4/22/98 23:45	0.03
4/23/98 0:12	0.03	4/23/98 0:19	0.03	4/23/98 0:25	0.03
4/23/98 0:52	0.03	4/23/98 0:59	0.03	4/23/98 1:05	0.02
4/23/98 1:32	0.03	4/23/98 1:39	0.02	4/23/98 1:45	0.02
4/23/98 2:12	0.02	4/23/98 2:19	0.02	4/23/98 2:25	0.02
4/23/98 2:52	0.02	4/23/98 2:59	0.02	4/23/98 3:05	0.02
4/23/98 3:32	0.02	4/23/98 3:39	0.02	4/23/98 3:45	0.02
4/23/98 4:12	0.02	4/23/98 4:19	0.02	4/23/98 4:25	0.02
4/23/98 4:52	0.02	4/23/98 4:59	0.02	4/23/98 5:05	0.02
4/23/98 5:32	0.02	4/23/98 5:39	0.02	4/23/98 5:45	0.02
4/23/98 6:12	0.02	4/23/98 6:19	0.02	4/23/98 6:25	0.01

Date and time	HD-1	Date and time	HD-2	Date and time	HD-3
4/23/98 6:52	0.02	4/23/98 6:59	0.02	4/23/98 7:05	0.02
4/23/98 7:32	0.01	4/23/98 7:39	0.02	4/23/98 7:45	0.02
4/23/98 8:12	0.02	4/23/98 8:19	0.01	4/23/98 8:25	0.02
4/23/98 8:52	0.02	4/23/98 8:59	0.02	4/23/98 9:05	0.02
4/23/98 9:32	0.03	4/23/98 9:39	0.03	4/23/98 9:45	0.03
4/23/98 10:12	0.02	4/23/98 10:19	0.02	4/23/98 10:25	0.02
4/23/98 10:52	0.02	4/23/98 10:59	0.02	4/23/98 11:05	0.02
4/23/98 11:32	0.02	4/23/98 11:39	0.02	4/23/98 11:45	0.02
4/23/98 12:12	0.02	4/23/98 12:19	0.02	4/23/98 12:25	0.02
4/23/98 12:52	0.02	4/23/98 12:59	0.01		

Table 5-9. O₂ (mole [volume] percent) by time, heater drift, April 1998.

Date and time	HD-1	Date and time	HD-2	Date and time	HD-3
4/21/98 10:24	20.87	4/21/98 10:31	20.75	4/21/98 10:37	20.82
4/21/98 11:04	20.92	4/21/98 11:11	20.91	4/21/98 11:17	20.92
4/21/98 12:04	20.85	4/21/98 12:10	20.85	4/21/98 12:17	20.85
4/21/98 12:44	20.86	4/21/98 12:50	20.86	4/21/98 12:57	20.86
4/21/98 13:24	20.87	4/21/98 13:30	20.87	4/21/98 13:37	20.87
4/21/98 14:04	20.88	4/21/98 14:10	20.88	4/21/98 14:17	20.88
4/21/98 14:44	20.88	4/21/98 14:50	20.88	4/21/98 14:57	20.88
4/21/98 15:24	20.88	4/21/98 15:30	20.88	4/21/98 15:37	20.88
4/21/98 16:04	20.88	4/21/98 16:10	20.88	4/21/98 16:17	20.88
4/21/98 16:44	20.88	4/21/98 16:50	20.88	4/21/98 16:57	20.88
4/21/98 17:24	20.88	4/21/98 17:30	20.88	4/21/98 17:37	20.88
4/21/98 18:04	20.88	4/21/98 18:10	20.88	4/21/98 18:17	20.88
4/21/98 18:44	20.88	4/21/98 18:50	20.88	4/21/98 18:57	20.88
4/21/98 19:24	20.88	4/21/98 19:30	20.88	4/21/98 19:37	20.88
4/21/98 20:04	20.88	4/21/98 20:10	20.88	4/21/98 20:17	20.88
4/21/98 20:44	20.88	4/21/98 20:50	20.88	4/21/98 20:57	20.88
4/21/98 21:24	20.88	4/21/98 21:30	20.88	4/21/98 21:37	20.88
4/21/98 22:04	20.88	4/21/98 22:10	20.87	4/21/98 22:17	20.88
4/21/98 22:44	20.88	4/21/98 22:50	20.87	4/21/98 22:57	20.88
4/21/98 23:24	20.87	4/21/98 23:30	20.87	4/21/98 23:37	20.87
4/22/98 0:04	20.87	4/22/98 0:10	20.86	4/22/98 0:17	20.86
4/22/98 0:44	20.87	4/22/98 0:50	20.86	4/22/98 0:57	20.86
4/22/98 1:24	20.87	4/22/98 1:30	20.86	4/22/98 1:37	20.87

5. Gas and Water Chemistry

Date and time	HD-1	Date and time	HD-2	Date and time	HD-3
4/22/98 2:04	20.86	4/22/98 2:10	20.86	4/22/98 2:17	20.86
4/22/98 2:44	20.86	4/22/98 2:50	20.86	4/22/98 2:57	20.86
4/22/98 3:24	20.86	4/22/98 3:30	20.86	4/22/98 3:37	20.86
4/22/98 4:04	20.87	4/22/98 4:10	20.86	4/22/98 4:17	20.86
4/22/98 4:44	20.87	4/22/98 4:50	20.86	4/22/98 4:57	20.86
4/22/98 5:24	20.87	4/22/98 5:30	20.86	4/22/98 5:37	20.86
4/22/98 6:04	20.86	4/22/98 6:10	20.86	4/22/98 6:17	20.86
4/22/98 6:44	20.86	4/22/98 6:50	20.86	4/22/98 6:57	20.86
4/22/98 7:24	20.86	4/22/98 7:30	20.86	4/22/98 7:37	20.86
4/22/98 8:04	20.86	4/22/98 8:10	20.86	4/22/98 8:17	20.86
4/22/98 8:44	20.86	4/22/98 8:50	20.86	4/22/98 8:57	20.86
4/22/98 9:32	20.84	4/22/98 9:39	20.83	4/22/98 9:45	20.84
4/22/98 10:12	20.84	4/22/98 10:19	20.84	4/22/98 10:25	20.84
4/22/98 10:52	20.84	4/22/98 10:59	20.83	4/22/98 11:05	20.83
4/22/98 11:32	20.83	4/22/98 11:39	20.82	4/22/98 11:45	20.82
4/22/98 12:12	20.8	4/22/98 12:19	20.8	4/22/98 12:25	20.8
4/22/98 12:52	20.78	4/22/98 12:59	20.78	4/22/98 13:05	20.78
4/22/98 13:32	20.77	4/22/98 13:39	20.77	4/22/98 13:45	20.77
4/22/98 14:12	20.75	4/22/98 14:19	20.75	4/22/98 14:25	20.75
4/22/98 14:52	20.74	4/22/98 14:59	20.74	4/22/98 15:05	20.73
4/22/98 15:32	20.73	4/22/98 15:39	20.72	4/22/98 15:45	20.72
4/22/98 16:12	20.72	4/22/98 16:19	20.71	4/22/98 16:25	20.71
4/22/98 16:52	20.69	4/22/98 16:59	20.69	4/22/98 17:05	20.68
4/22/98 17:32	20.67	4/22/98 17:39	20.66	4/22/98 17:45	20.66
4/22/98 18:12	20.65	4/22/98 18:19	20.64	4/22/98 18:25	20.64
4/22/98 18:52	20.62	4/22/98 18:59	20.61	4/22/98 19:05	20.6
4/22/98 19:32	20.58	4/22/98 19:39	20.56	4/22/98 19:45	20.56
4/22/98 20:12	20.53	4/22/98 20:19	20.52	4/22/98 20:25	20.52
4/22/98 20:52	20.5	4/22/98 20:59	20.49	4/22/98 21:05	20.5
4/22/98 21:32	20.49	4/22/98 21:39	20.49	4/22/98 21:45	20.49
4/22/98 22:12	20.49	4/22/98 22:19	20.48	4/22/98 22:25	20.48
4/22/98 22:52	20.48	4/22/98 22:59	20.48	4/22/98 23:05	20.48
4/22/98 23:32	20.48	4/22/98 23:39	20.47	4/22/98 23:45	20.48
4/23/98 0:12	20.48	4/23/98 0:19	20.47	4/23/98 0:25	20.47
4/23/98 0:52	20.48	4/23/98 0:59	20.47	4/23/98 1:05	20.47
4/23/98 1:32	20.47	4/23/98 1:39	20.47	4/23/98 1:45	20.47

Date and time	HD-1	Date and time	HD-2	Date and time	HD-3
4/23/98 2:12	20.47	4/23/98 2:19	20.47	4/23/98 2:25	20.47
4/23/98 2:52	20.47	4/23/98 2:59	20.47	4/23/98 3:05	20.47
4/23/98 3:32	20.47	4/23/98 3:39	20.47	4/23/98 3:45	20.47
4/23/98 4:12	20.47	4/23/98 4:19	20.47	4/23/98 4:25	20.47
4/23/98 4:52	20.47	4/23/98 4:59	20.47	4/23/98 5:05	20.47
4/23/98 5:32	20.47	4/23/98 5:39	20.47	4/23/98 5:45	20.47
4/23/98 6:12	20.47	4/23/98 6:19	20.47	4/23/98 6:25	20.47
4/23/98 6:52	20.47	4/23/98 6:59	20.47	4/23/98 7:05	20.47
4/23/98 7:32	20.47	4/23/98 7:39	20.47	4/23/98 7:45	20.47
4/23/98 8:12	20.47	4/23/98 8:19	20.47	4/23/98 8:25	20.47
4/23/98 8:52	20.47	4/23/98 8:59	20.47	4/23/98 9:05	20.47
4/23/98 9:32	20.47	4/23/98 9:39	20.46	4/23/98 9:45	20.47
4/23/98 10:12	20.47	4/23/98 10:19	20.46	4/23/98 10:25	20.46
4/23/98 10:52	20.47	4/23/98 10:59	20.46	4/23/98 11:05	20.46
4/23/98 11:32	20.47	4/23/98 11:39	20.46	4/23/98 11:45	20.47
4/23/98 12:12	20.47	4/23/98 12:19	20.46	4/23/98 12:25	20.47
4/23/98 12:52	20.47	4/23/98 12:59	20.46		

Table 5-10. O₂ (mole [volume] percent) by time, connecting drift, April 1998.

Date and time	CD-1	Date and time	CD-2	Date and time	CD-3
4/21/98 10:44	20.89	4/21/98 10:50	20.91	4/21/98 10:57	20.91
4/21/98 11:24	20.93	4/21/98 11:30	20.93	4/21/98 11:37	20.93
4/21/98 12:23	20.86	4/21/98 12:30	20.87	4/21/98 12:36	20.87
4/21/98 13:03	20.88	4/21/98 13:10	20.88	4/21/98 13:16	20.89
4/21/98 13:43	20.89	4/21/98 13:50	20.89	4/21/98 13:56	20.89
4/21/98 14:23	20.89	4/21/98 14:30	20.89	4/21/98 14:36	20.89
4/21/98 15:03	20.89	4/21/98 15:10	20.89	4/21/98 15:16	20.89
4/21/98 15:43	20.88	4/21/98 15:50	20.88	4/21/98 15:56	20.89
4/21/98 16:23	20.89	4/21/98 16:30	20.89	4/21/98 16:36	20.89
4/21/98 17:03	20.89	4/21/98 17:10	20.89	4/21/98 17:16	20.89
4/21/98 17:43	20.89	4/21/98 17:50	20.89	4/21/98 17:56	20.89
4/21/98 18:23	20.9	4/21/98 18:30	20.9	4/21/98 18:36	20.9
4/21/98 19:03	20.9	4/21/98 19:10	20.9	4/21/98 19:16	20.9
4/21/98 19:43	20.9	4/21/98 19:50	20.89	4/21/98 19:56	20.89
4/21/98 20:23	20.89	4/21/98 20:30	20.89	4/21/98 20:36	20.89
4/21/98 21:03	20.89	4/21/98 21:10	20.89	4/21/98 21:16	20.89

5. Gas and Water Chemistry

Date and time	CD-1	Date and time	CD-2	Date and time	CD-3
4/21/98 21:43	20.89	4/21/98 21:50	20.89	4/21/98 21:56	20.89
4/21/98 22:23	20.88	4/21/98 22:30	20.88	4/21/98 22:36	20.88
4/21/98 23:03	20.88	4/21/98 23:10	20.88	4/21/98 23:16	20.88
4/21/98 23:43	20.88	4/21/98 23:50	20.88	4/21/98 23:56	20.88
4/22/98 0:23	20.88	4/22/98 0:30	20.88	4/22/98 0:36	20.88
4/22/98 1:03	20.88	4/22/98 1:10	20.88	4/22/98 1:16	20.88
4/22/98 1:43	20.88	4/22/98 1:50	20.88	4/22/98 1:56	20.88
4/22/98 2:23	20.88	4/22/98 2:30	20.87	4/22/98 2:36	20.88
4/22/98 3:03	20.88	4/22/98 3:10	20.88	4/22/98 3:16	20.88
4/22/98 3:43	20.88	4/22/98 3:50	20.87	4/22/98 3:56	20.88
4/22/98 4:23	20.88	4/22/98 4:30	20.88	4/22/98 4:36	20.88
4/22/98 5:03	20.88	4/22/98 5:10	20.88	4/22/98 5:16	20.88
4/22/98 5:43	20.88	4/22/98 5:50	20.88	4/22/98 5:56	20.88
4/22/98 6:23	20.88	4/22/98 6:30	20.88	4/22/98 6:36	20.88
4/22/98 7:03	20.88	4/22/98 7:10	20.88	4/22/98 7:16	20.88
4/22/98 7:43	20.88	4/22/98 7:50	20.88	4/22/98 7:56	20.88
4/22/98 8:23	20.88	4/22/98 8:30	20.88	4/22/98 8:36	20.88
4/22/98 9:52	20.85	4/22/98 9:58	20.85	4/22/98 10:05	20.85
4/22/98 10:32	20.85	4/22/98 10:38	20.84	4/22/98 10:45	20.84
4/22/98 11:12	20.84	4/22/98 11:18	20.83	4/22/98 11:25	20.83
4/22/98 11:52	20.83	4/22/98 11:58	20.82	4/22/98 12:05	20.82
4/22/98 12:32	20.8	4/22/98 12:38	20.8	4/22/98 12:45	20.8
4/22/98 13:12	20.79	4/22/98 13:18	20.79	4/22/98 13:25	20.79
4/22/98 13:52	20.78	4/22/98 13:58	20.77	4/22/98 14:05	20.77
4/22/98 14:32	20.77	4/22/98 14:38	20.77	4/22/98 14:45	20.77
4/22/98 15:12	20.76	4/22/98 15:18	20.75	4/22/98 15:25	20.75
4/22/98 15:52	20.74	4/22/98 15:58	20.74	4/22/98 16:05	20.74
4/22/98 16:32	20.72	4/22/98 16:38	20.72	4/22/98 16:45	20.72
4/22/98 17:12	20.71	4/22/98 17:18	20.7	4/22/98 17:25	20.7
4/22/98 17:52	20.68	4/22/98 17:58	20.68	4/22/98 18:05	20.68
4/22/98 18:32	20.66	4/22/98 18:38	20.65	4/22/98 18:45	20.65
4/22/98 19:12	20.62	4/22/98 19:18	20.61	4/22/98 19:25	20.61
4/22/98 19:52	20.58	4/22/98 19:58	20.58	4/22/98 20:05	20.56
4/22/98 20:32	20.54	4/22/98 20:38	20.53	4/22/98 20:45	20.53
4/22/98 21:12	20.52	4/22/98 21:18	20.52	4/22/98 21:25	20.52
4/22/98 21:52	20.51	4/22/98 21:58	20.5	4/22/98 22:05	20.5

Date and time	CD-1	Date and time	CD-2	Date and time	CD-3
4/22/98 22:32	20.5	4/22/98 22:38	20.49	4/22/98 22:45	20.49
4/22/98 23:12	20.5	4/22/98 23:18	20.5	4/22/98 23:25	20.5
4/22/98 23:52	20.5	4/22/98 23:58	20.49	4/23/98 0:05	20.49
4/23/98 0:32	20.49	4/23/98 0:38	20.49	4/23/98 0:45	20.5
4/23/98 1:12	20.49	4/23/98 1:18	20.49	4/23/98 1:25	20.49
4/23/98 1:52	20.49	4/23/98 1:58	20.49	4/23/98 2:05	20.49
4/23/98 2:32	20.49	4/23/98 2:38	20.49	4/23/98 2:45	20.49
4/23/98 3:12	20.49	4/23/98 3:18	20.49	4/23/98 3:25	20.49
4/23/98 3:52	20.49	4/23/98 3:58	20.49	4/23/98 4:05	20.49
4/23/98 4:32	20.49	4/23/98 4:38	20.49	4/23/98 4:45	20.49
4/23/98 5:12	20.49	4/23/98 5:18	20.49	4/23/98 5:25	20.49
4/23/98 5:52	20.49	4/23/98 5:58	20.49	4/23/98 6:05	20.49
4/23/98 6:32	20.49	4/23/98 6:38	20.49	4/23/98 6:45	20.49
4/23/98 7:12	20.49	4/23/98 7:18	20.49	4/23/98 7:25	20.49
4/23/98 7:52	20.49	4/23/98 7:58	20.49	4/23/98 8:05	20.49
4/23/98 8:32	20.49	4/23/98 8:38	20.49	4/23/98 8:45	20.49
4/23/98 9:12	20.48	4/23/98 9:18	20.48	4/23/98 9:25	20.48
4/23/98 9:52	20.48	4/23/98 9:58	20.48	4/23/98 10:05	20.48
4/23/98 10:32	20.48	4/23/98 10:38	20.48	4/23/98 10:45	20.48
4/23/98 11:12	20.47	4/23/98 11:18	20.49	4/23/98 11:25	20.48
4/23/98 11:52	20.48	4/23/98 11:58	20.49	4/23/98 12:05	20.49
4/23/98 12:32	20.48	4/23/98 12:38	20.48	4/23/98 12:45	20.48

Table 5-11. CO₂ (mole [volume] percent) by time, heater drift, June 1998.

Date and time	HD-1	Date and time	HD-2	Date and time	HD-3
6/1/98 14:56	0.04	6/1/98 15:03	0.05	6/1/98 15:10	0.05
6/1/98 15:39	0.06	6/1/98 15:46	0.06	6/1/98 15:53	0.06
6/1/98 16:22	0.07	6/1/98 16:29	0.06	6/1/98 16:36	0.06
6/1/98 17:05	0.06	6/1/98 17:12	0.06	6/1/98 17:19	0.06
6/1/98 17:48	0.06	6/1/98 17:55	0.06	6/1/98 18:02	0.06
6/1/98 18:31	0.05	6/1/98 18:38	0.05	6/1/98 18:45	0.05
6/1/98 19:14	0.05	6/1/98 19:21	0.05	6/1/98 19:28	0.05
6/1/98 19:57	0.05	6/1/98 20:04	0.05	6/1/98 20:11	0.05
6/1/98 20:40	0.05	6/1/98 20:47	0.05	6/1/98 20:54	0.06
6/1/98 21:23	0.06	6/1/98 21:30	0.06	6/1/98 21:37	0.06
6/1/98 22:06	0.06	6/1/98 22:13	0.06	6/1/98 22:20	0.06
6/1/98 22:49	0.06	6/1/98 22:56	0.06	6/1/98 23:03	0.06
6/1/98 23:32	0.06	6/1/98 23:39	0.06	6/1/98 23:46	0.06
6/2/98 0:15	0.06	6/2/98 0:22	0.05	6/2/98 0:29	0.05
6/2/98 0:58	0.05	6/2/98 1:05	0.05	6/2/98 1:12	0.05
6/2/98 1:41	0.05	6/2/98 1:48	0.05	6/2/98 1:55	0.05
6/2/98 2:24	0.05	6/2/98 2:31	0.05	6/2/98 2:38	0.05
6/2/98 3:07	0.05	6/2/98 3:14	0.05	6/2/98 3:21	0.05
6/2/98 3:50	0.05	6/2/98 3:57	0.05	6/2/98 4:04	0.05
6/2/98 4:33	0.05	6/2/98 4:40	0.05	6/2/98 4:47	0.05
6/2/98 5:16	0.05	6/2/98 5:23	0.05	6/2/98 5:30	0.05
6/2/98 5:59	0.05	6/2/98 6:06	0.05	6/2/98 6:13	0.06
6/2/98 6:42	0.05	6/2/98 6:49	0.05	6/2/98 6:56	0.05
6/2/98 7:25	0.06	6/2/98 7:32	0.06	6/2/98 7:39	0.05
6/2/98 8:08	0.05	6/2/98 8:15	0.05	6/2/98 8:22	0.05
6/2/98 8:51	0.06	6/2/98 8:58	0.07	6/2/98 9:05	0.07

Table 5-12. CO₂ (mole [volume] percent) by time, connecting drift, June 1998.

Date and time	CD-1	Date and time	CD-2	Date and time	CD-3
6/1/98 15:17	0.05	6/1/98 15:24	0.05	6/1/98 15:31	0.05
6/1/98 16:00	0.06	6/1/98 16:07	0.06	6/1/98 16:14	0.06
6/1/98 16:43	0.06	6/1/98 16:50	0.06	6/1/98 16:57	0.06
6/1/98 17:26	0.05	6/1/98 17:33	0.05	6/1/98 17:40	0.05
6/1/98 18:09	0.05	6/1/98 18:16	0.05	6/1/98 18:23	0.05
6/1/98 18:52	0.05	6/1/98 18:59	0.05	6/1/98 19:06	0.05
6/1/98 19:35	0.05	6/1/98 19:42	0.05	6/1/98 19:49	0.05
6/1/98 20:18	0.05	6/1/98 20:25	0.05	6/1/98 20:32	0.05
6/1/98 21:01	0.05	6/1/98 21:08	0.05	6/1/98 21:15	0.05
6/1/98 21:44	0.05	6/1/98 21:51	0.05	6/1/98 21:58	0.05
6/1/98 22:27	0.05	6/1/98 22:34	0.05	6/1/98 22:41	0.05
6/1/98 23:10	0.05	6/1/98 23:17	0.05	6/1/98 23:24	0.06
6/1/98 23:53	0.06	6/2/98 0:00	0.05	6/2/98 0:07	0.05
6/2/98 0:36	0.05	6/2/98 0:43	0.05	6/2/98 0:50	0.05
6/2/98 1:19	0.04	6/2/98 1:26	0.04	6/2/98 1:33	0.04
6/2/98 2:02	0.04	6/2/98 2:09	0.04	6/2/98 2:16	0.04
6/2/98 2:45	0.04	6/2/98 2:52	0.04	6/2/98 2:59	0.04
6/2/98 3:28	0.04	6/2/98 3:35	0.04	6/2/98 3:42	0.05
6/2/98 4:11	0.05	6/2/98 4:18	0.05	6/2/98 4:25	0.05
6/2/98 4:54	0.05	6/2/98 5:01	0.04	6/2/98 5:08	0.04
6/2/98 5:37	0.05	6/2/98 5:44	0.05	6/2/98 5:51	0.05
6/2/98 6:20	0.05	6/2/98 6:27	0.05	6/2/98 6:34	0.05
6/2/98 7:03	0.05	6/2/98 7:10	0.05	6/2/98 7:17	0.05
6/2/98 7:46	0.05	6/2/98 7:53	0.05	6/2/98 8:00	0.05
6/2/98 8:29	0.05	6/2/98 8:36	0.05	6/2/98 8:43	0.06
6/2/98 9:12	0.06	6/2/98 9:19	0.06	6/2/98 9:26	0.06

Table 5-13. CO₂ (mole [volume] percent) by time, access/observation drift, June 1998.

Date and time	OD-1	Date and time	OD-2	Date and time	OD-3
6/2/98 13:13	0.04	6/2/98 13:20	0.03	6/2/98 13:27	0.04
6/2/98 14:10	0.04	6/2/98 14:17	0.04	6/2/98 14:24	0.04
6/2/98 15:07	0.03	6/2/98 15:14	0.04	6/2/98 15:21	0.04
6/2/98 16:04	0.04	6/2/98 16:11	0.04	6/2/98 16:18	0.04
6/2/98 17:01	0.03	6/2/98 17:08	0.03	6/2/98 17:15	0.03
6/2/98 17:58	0.03	6/2/98 18:05	0.02	6/2/98 18:12	0.02
6/2/98 18:55	0.02	6/2/98 19:02	0.02	6/2/98 19:09	0.02
6/2/98 19:52	0.01	6/2/98 19:59	0.01	6/2/98 20:06	0.01
6/2/98 20:49	0.04	6/2/98 20:56	0.04	6/2/98 21:03	0.04
6/2/98 21:46	0.05	6/2/98 21:53	0.05	6/2/98 22:00	0.05
6/2/98 22:43	0.05	6/2/98 22:50	0.05	6/2/98 22:57	0.05
6/2/98 23:40	0.05	6/2/98 23:47	0.05	6/2/98 23:54	0.05
6/3/98 0:37	0.05	6/3/98 0:44	0.05	6/3/98 0:51	0.05
6/3/98 1:34	0.05	6/3/98 1:41	0.05	6/3/98 1:48	0.05
6/3/98 2:31	0.05	6/3/98 2:38	0.04	6/3/98 2:45	0.04
6/3/98 3:28	0.05	6/3/98 3:35	0.04	6/3/98 3:42	0.04
6/3/98 4:25	0.05	6/3/98 4:32	0.05	6/3/98 4:39	0.05
6/3/98 5:22	0.05	6/3/98 5:29	0.05	6/3/98 5:36	0.05
6/3/98 6:19	0.05	6/3/98 6:26	0.05	6/3/98 6:33	0.05
6/3/98 7:16	0.06	6/3/98 7:23	0.06	6/3/98 7:30	0.06
6/3/98 8:13	0.06	6/3/98 8:20	0.06	6/3/98 8:27	0.07
6/3/98 10:12	0.03	6/3/98 10:19	0.03	6/3/98 10:26	0.03
6/3/98 11:16	0.03	6/3/98 11:23	0.03	6/3/98 11:30	0.03
6/3/98 12:20	0.03	6/3/98 12:27	0.03	6/3/98 12:34	0.02
6/3/98 13:24	0.04	6/3/98 13:31	0.04	6/3/98 13:38	0.04
6/3/98 14:28	0.04	6/3/98 14:35	0.05	6/3/98 14:42	0.05
6/3/98 15:32	0.04	6/3/98 15:39	0.05	6/3/98 15:46	0.05
6/3/98 16:36	0.04	6/3/98 16:43	0.04	6/3/98 16:50	0.04
6/3/98 17:40	0.04	6/3/98 17:47	0.04	6/3/98 17:54	0.03
6/3/98 18:44	0.04	6/3/98 18:51	0.04	6/3/98 18:58	0.04
6/3/98 19:48	0.04	6/3/98 19:55	0.04	6/3/98 20:02	0.04
6/3/98 20:52	0.05	6/3/98 20:59	0.05	6/3/98 21:06	0.05
6/3/98 21:56	0.05	6/3/98 22:03	0.05	6/3/98 22:10	0.05
6/3/98 23:00	0.06	6/3/98 23:07	0.05	6/3/98 23:14	0.05
6/4/98 0:04	0.05	6/4/98 0:11	0.05	6/4/98 0:18	0.05

Date and time	OD-1	Date and time	OD-2	Date and time	OD-3
6/4/98 1:08	0.05	6/4/98 1:15	0.05	6/4/98 1:22	0.05
6/4/98 2:12	0.05	6/4/98 2:19	0.05	6/4/98 2:26	0.05
6/4/98 3:16	0.05	6/4/98 3:23	0.05	6/4/98 3:30	0.05
6/4/98 4:20	0.04	6/4/98 4:27	0.05	6/4/98 4:34	0.04
6/4/98 5:24	0.04	6/4/98 5:31	0.04	6/4/98 5:38	0.04
6/4/98 6:28	0.04	6/4/98 6:35	0.05	6/4/98 6:42	0.05
6/4/98 7:32	0.05	6/4/98 7:39	0.05	6/4/98 7:46	0.05
6/4/98 8:36	0.05				

Table 5-14. CO₂ (mole [volume] percent) by time, Boreholes 54, 55, and 59, June 1998.

Date and time	54-1	Date and time	54-3	Date and time	54-5
6/2/98 12:38	0.05	6/2/98 12:45	0.03	6/2/98 12:52	0.04
6/2/98 13:35	0.05	6/2/98 13:42	0.03	6/2/98 13:49	0.04
6/2/98 14:32	0.09	6/2/98 14:39	0.04	6/2/98 14:46	0.04
6/2/98 15:29	0.1	6/2/98 15:36	0.03	6/2/98 15:43	0.04
6/2/98 16:26	0.1	6/2/98 16:33	0.04	6/2/98 16:40	0.04
6/2/98 17:23	0.1	6/2/98 17:30	0.02	6/2/98 17:37	0.04
6/2/98 18:20	0.09	6/2/98 18:27	0.02	6/2/98 18:34	0.03
6/2/98 19:17	0.08	6/2/98 19:24	0.01	6/2/98 19:31	0.02
6/2/98 20:14	0.07	6/2/98 20:21	0.01	6/2/98 20:28	0.05
6/2/98 21:11	0.11	6/2/98 21:18	0.05	6/2/98 21:25	0.05
6/2/98 22:08	0.11	6/2/98 22:15	0.05	6/2/98 22:22	0.06
6/2/98 23:05	0.11	6/2/98 23:12	0.05	6/2/98 23:19	0.06
6/3/98 0:02	0.11	6/3/98 0:09	0.05	6/3/98 0:16	0.06
6/3/98 0:59	0.11	6/3/98 1:06	0.05	6/3/98 1:13	0.06
6/3/98 1:56	0.11	6/3/98 2:03	0.05	6/3/98 2:10	0.05
6/3/98 2:53	0.11	6/3/98 3:00	0.04	6/3/98 3:07	0.05
6/3/98 3:50	0.04	6/3/98 3:57	0.04	6/3/98 4:04	0.05
6/3/98 4:47	0.08	6/3/98 4:54	0.05	6/3/98 5:01	0.06
6/3/98 5:44	0.05	6/3/98 5:51	0.05	6/3/98 5:58	0.06
6/3/98 6:41	0.06	6/3/98 6:48	0.05	6/3/98 6:55	0.06
6/3/98 7:38	0.07	6/3/98 7:45	0.05	6/3/98 7:52	0.06
6/3/98 9:37	0.03	6/3/98 9:44	0.03	6/3/98 9:51	0.04
6/3/98 10:41	0.02	6/3/98 10:48	0.02	6/3/98 10:55	0.03
6/3/98 11:45	0.03	6/3/98 11:52	0.02	6/3/98 11:59	0.03
6/3/98 12:49	0.04	6/3/98 12:56	0.03	6/3/98 13:03	0.04

5. Gas and Water Chemistry

Date and time	54-1	Date and time	54-3	Date and time	54-5
6/3/98 13:53	0.04	6/3/98 14:00	0.04	6/3/98 14:07	0.05
6/3/98 14:57	0.04	6/3/98 15:04	0.04	6/3/98 15:11	0.05
6/3/98 16:01	0.04	6/3/98 16:08	0.04	6/3/98 16:15	0.05
6/3/98 17:05	0.04	6/3/98 17:12	0.03	6/3/98 17:19	0.04
6/3/98 18:09	0.04	6/3/98 18:16	0.03	6/3/98 18:23	0.04
6/3/98 19:13	0.04	6/3/98 19:20	0.04	6/3/98 19:27	0.05
6/3/98 20:17	0.04	6/3/98 20:24	0.04	6/3/98 20:31	0.05
6/3/98 21:21	0.05	6/3/98 21:28	0.05	6/3/98 21:35	0.05
6/3/98 22:25	0.05	6/3/98 22:32	0.05	6/3/98 22:39	0.06
6/3/98 23:29	0.05	6/3/98 23:36	0.05	6/3/98 23:43	0.06
6/4/98 0:33	0.05	6/4/98 0:40	0.05	6/4/98 0:47	0.05
6/4/98 1:37	0.05	6/4/98 1:44	0.05	6/4/98 1:51	0.05
6/4/98 2:41	0.05	6/4/98 2:48	0.05	6/4/98 2:55	0.05
6/4/98 3:45	0.05	6/4/98 3:52	0.05	6/4/98 3:59	0.05
6/4/98 4:49	0.05	6/4/98 4:56	0.05	6/4/98 5:03	0.05
6/4/98 5:53	0.04	6/4/98 6:00	0.04	6/4/98 6:07	0.05
6/4/98 6:57	0.05	6/4/98 7:04	0.04	6/4/98 7:11	0.05
6/4/98 8:01	0.06	6/4/98 8:08	0.05	6/4/98 8:15	0.05

Date and time	55-1	Date and time	55-3	Date and time	59-4
6/2/98 12:59	0.03	6/2/98 13:06	0.03	6/3/98 9:30	0.41
6/2/98 13:56	0.03	6/2/98 14:03	0.03	6/3/98 10:34	0.41
6/2/98 14:53	0.04	6/2/98 15:00	0.03	6/3/98 11:38	0.42
6/2/98 15:50	0.03	6/2/98 15:57	0.03	6/3/98 12:42	0.43
6/2/98 16:47	0.03	6/2/98 16:54	0.03	6/3/98 13:46	0.46
6/2/98 17:44	0.03	6/2/98 17:51	0.02	6/3/98 14:50	0.47
6/2/98 18:41	0.01	6/2/98 18:48	0.02	6/3/98 15:54	0.47
6/2/98 19:38	0.01	6/2/98 19:45	0.01	6/3/98 16:58	0.48
6/2/98 20:35	0.04	6/2/98 20:42	0.04	6/3/98 18:02	0.49
6/2/98 21:32	0.05	6/2/98 21:39	0.05	6/3/98 19:06	0.51
6/2/98 22:29	0.05	6/2/98 22:36	0.05	6/3/98 20:10	0.53
6/2/98 23:26	0.05	6/2/98 23:33	0.05	6/3/98 21:14	0.55
6/3/98 0:23	0.05	6/3/98 0:30	0.05	6/3/98 22:18	0.57
6/3/98 1:20	0.05	6/3/98 1:27	0.05	6/3/98 23:22	0.58
6/3/98 2:17	0.05	6/3/98 2:24	0.04	6/4/98 0:26	0.59
6/3/98 3:14	0.05	6/3/98 3:21	0.04	6/4/98 1:30	0.59
6/3/98 4:11	0.05	6/3/98 4:18	0.05	6/4/98 2:34	0.61

Date and time	55-1	Date and time	55-3	Date and time	59-4
6/3/98 5:08	0.05	6/3/98 5:15	0.05	6/4/98 3:38	0.61
6/3/98 6:05	0.05	6/3/98 6:12	0.05	6/4/98 4:42	0.62
6/3/98 7:02	0.06	6/3/98 7:09	0.05	6/4/98 5:46	0.62
6/3/98 7:59	0.06	6/3/98 8:06	0.05	6/4/98 6:50	0.63
6/3/98 9:58	0.03	6/3/98 10:05	0.02	6/4/98 7:54	0.64
6/3/98 11:02	0.02	6/3/98 11:09	0.02		
6/3/98 12:06	0.03	6/3/98 12:13	0.02		
6/3/98 13:10	0.03	6/3/98 13:17	0.03		
6/3/98 14:14	0.04	6/3/98 14:21	0.04		
6/3/98 15:18	0.04	6/3/98 15:25	0.04		
6/3/98 16:22	0.04	6/3/98 16:29	0.04		
6/3/98 17:26	0.04	6/3/98 17:33	0.03		
6/3/98 18:30	0.04	6/3/98 18:37	0.03		
6/3/98 19:34	0.04	6/3/98 19:41	0.04		
6/3/98 20:38	0.05	6/3/98 20:45	0.05		
6/3/98 21:42	0.05	6/3/98 21:49	0.05		
6/3/98 22:46	0.05	6/3/98 22:53	0.05		
6/3/98 23:50	0.05	6/3/98 23:57	0.05		
6/4/98 0:54	0.05	6/4/98 1:01	0.05		
6/4/98 1:58	0.05	6/4/98 2:05	0.05		
6/4/98 3:02	0.05	6/4/98 3:09	0.05		
6/4/98 4:06	0.05	6/4/98 4:13	0.05		
6/4/98 5:10	0.05	6/4/98 5:17	0.04		
6/4/98 6:14	0.05	6/4/98 6:21	0.04		
6/4/98 7:18	0.05	6/4/98 7:25	0.05		
6/4/98 8:22	0.05	6/4/98 8:29	0.05		

Table 5-15. O₂ (mole [volume] percent) by time, heater drift, June 1998.

Date and time	HD-1	Date and time	HD-2	Date and time	HD-3
6/1/98 13:36	20.85	6/1/98 13:43	20.88	6/1/98 13:50	20.87
6/1/98 14:19	20.96	6/1/98 14:26	20.97	6/1/98 15:10	20.88
6/1/98 14:56	20.86	6/1/98 15:03	20.87	6/1/98 15:53	20.91
6/1/98 15:39	20.91	6/1/98 15:46	20.91	6/1/98 16:36	20.93
6/1/98 16:22	20.92	6/1/98 16:29	20.92	6/1/98 17:19	20.94
6/1/98 17:05	20.94	6/1/98 17:12	20.93	6/1/98 18:02	20.94
6/1/98 17:48	20.94	6/1/98 17:55	20.94	6/1/98 18:45	20.94
6/1/98 18:31	20.94	6/1/98 18:38	20.94	6/1/98 19:28	20.94
6/1/98 19:14	20.94	6/1/98 19:21	20.94	6/1/98 20:11	20.94
6/1/98 19:57	20.94	6/1/98 20:04	20.94	6/1/98 20:54	20.94
6/1/98 20:40	20.94	6/1/98 20:47	20.94	6/1/98 21:37	20.94
6/1/98 21:23	20.94	6/1/98 21:30	20.94	6/1/98 22:20	20.95
6/1/98 22:06	20.95	6/1/98 22:13	20.94	6/1/98 23:03	20.95
6/1/98 22:49	20.95	6/1/98 22:56	20.94	6/1/98 23:46	20.94
6/1/98 23:32	20.95	6/1/98 23:39	20.94	6/2/98 0:29	20.95
6/2/98 0:15	20.94	6/2/98 0:22	20.94	6/2/98 1:12	20.94
6/2/98 0:58	20.94	6/2/98 1:05	20.94	6/2/98 1:55	20.95
6/2/98 1:41	20.95	6/2/98 1:48	20.94	6/2/98 2:38	20.95
6/2/98 2:24	20.95	6/2/98 2:31	20.95	6/2/98 3:21	20.95
6/2/98 3:07	20.95	6/2/98 3:14	20.95	6/2/98 4:04	20.96
6/2/98 3:50	20.96	6/2/98 3:57	20.95	6/2/98 4:47	20.95
6/2/98 4:33	20.95	6/2/98 4:40	20.95	6/2/98 5:30	20.95
6/2/98 5:16	20.95	6/2/98 5:23	20.95	6/2/98 6:13	20.95
6/2/98 5:59	20.95	6/2/98 6:06	20.95	6/2/98 6:56	20.95
6/2/98 6:42	20.95	6/2/98 6:49	20.95	6/2/98 7:39	20.95
6/2/98 7:25	20.95	6/2/98 7:32	20.95	6/2/98 8:22	20.95
6/2/98 8:08	20.95	6/2/98 8:15	20.95	6/2/98 9:05	20.95
6/2/98 8:51	20.95	6/2/98 8:58	20.95		

Table 5-16. O₂ (mole [volume] percent) by time, connecting drift, June 1998.

Date and time	CD-1	Date and time	CD-2	Date and time	CD-3
6/1/98 13:57	20.93	6/1/98 14:04	20.95	6/1/98 14:11	20.96
6/1/98 15:17	20.9	6/1/98 15:24	20.91	6/1/98 15:31	20.91
6/1/98 16:00	20.94	6/1/98 16:07	20.93	6/1/98 16:14	20.94
6/1/98 16:43	20.95	6/1/98 16:50	20.94	6/1/98 16:57	20.95
6/1/98 17:26	20.96	6/1/98 17:33	20.96	6/1/98 17:40	20.96
6/1/98 18:09	20.96	6/1/98 18:16	20.96	6/1/98 18:23	20.96
6/1/98 18:52	20.96	6/1/98 18:59	20.96	6/1/98 19:06	20.96
6/1/98 19:35	20.96	6/1/98 19:42	20.97	6/1/98 19:49	20.97
6/1/98 20:18	20.96	6/1/98 20:25	20.96	6/1/98 20:32	20.96
6/1/98 21:01	20.96	6/1/98 21:08	20.96	6/1/98 21:15	20.96
6/1/98 21:44	20.97	6/1/98 21:51	20.96	6/1/98 21:58	20.96
6/1/98 22:27	20.97	6/1/98 22:34	20.97	6/1/98 22:41	20.96
6/1/98 23:10	20.96	6/1/98 23:17	20.96	6/1/98 23:24	20.96
6/1/98 23:53	20.96	6/2/98 0:00	20.96	6/2/98 0:07	20.96
6/2/98 0:36	20.96	6/2/98 0:43	20.96	6/2/98 0:50	20.96
6/2/98 1:19	20.96	6/2/98 1:26	20.97	6/2/98 1:33	20.97
6/2/98 2:02	20.97	6/2/98 2:09	20.96	6/2/98 2:16	20.97
6/2/98 2:45	20.97	6/2/98 2:52	20.97	6/2/98 2:59	20.97
6/2/98 3:28	20.97	6/2/98 3:35	20.97	6/2/98 3:42	20.97
6/2/98 4:11	20.97	6/2/98 4:18	20.97	6/2/98 4:25	20.97
6/2/98 4:54	20.97	6/2/98 5:01	20.97	6/2/98 5:08	20.97
6/2/98 5:37	20.96	6/2/98 5:44	20.97	6/2/98 5:51	20.97
6/2/98 6:20	20.96	6/2/98 6:27	20.96	6/2/98 6:34	20.97
6/2/98 7:03	20.97	6/2/98 7:10	20.97	6/2/98 7:17	20.97
6/2/98 7:46	20.96	6/2/98 7:53	20.96	6/2/98 8:00	20.96
6/2/98 8:29	20.96	6/2/98 8:36	20.97	6/2/98 8:43	20.96
6/2/98 9:12	20.97	6/2/98 9:19	20.97	6/2/98 9:26	20.97

Table 5-17. O₂ (mole [volume] percent) by time, Boreholes 54, 55, and 59, June 1998.

Date and time	54-1	Date and time	54-3	Date and time	54-5
6/2/98 12:38	20.91	6/2/98 12:45	20.82	6/2/98 12:52	20.96
6/2/98 13:35	20.89	6/2/98 13:42	20.82	6/2/98 13:49	20.96
6/2/98 14:32	20.91	6/2/98 14:39	20.8	6/2/98 14:46	20.95
6/2/98 15:29	20.92	6/2/98 15:36	20.8	6/2/98 15:43	20.93
6/2/98 16:26	20.91	6/2/98 16:33	20.78	6/2/98 16:40	20.92
6/2/98 17:23	20.89	6/2/98 17:30	20.78	6/2/98 17:37	20.91
6/2/98 18:20	20.89	6/2/98 18:27	20.77	6/2/98 18:34	20.9
6/2/98 19:17	20.88	6/2/98 19:24	20.76	6/2/98 19:31	20.9
6/2/98 20:14	20.88	6/2/98 20:21	20.76	6/2/98 20:28	20.9
6/2/98 21:11	20.88	6/2/98 21:18	20.76	6/2/98 21:25	20.9
6/2/98 22:08	20.89	6/2/98 22:15	20.75	6/2/98 22:22	20.91
6/2/98 23:05	20.88	6/2/98 23:12	20.76	6/2/98 23:19	20.91
6/3/98 0:02	20.88	6/3/98 0:09	20.75	6/3/98 0:16	20.91
6/3/98 0:59	20.88	6/3/98 1:06	20.75	6/3/98 1:13	20.9
6/3/98 1:56	20.88	6/3/98 2:03	20.74	6/3/98 2:10	20.89
6/3/98 2:53	20.83	6/3/98 3:00	20.74	6/3/98 3:07	20.9
6/3/98 3:50	18.35	6/3/98 3:57	20.75	6/3/98 4:04	20.9
6/3/98 4:47	20.79	6/3/98 4:54	20.75	6/3/98 5:01	20.9
6/3/98 5:44	18.5	6/3/98 5:51	20.75	6/3/98 5:58	20.9
6/3/98 6:41	20.79	6/3/98 6:48	20.75	6/3/98 6:55	20.9
6/3/98 7:38	20.79	6/3/98 7:45	20.75	6/3/98 7:52	20.9
6/3/98 9:37	20.89	6/3/98 9:44	20.84	6/3/98 9:51	21
6/3/98 10:41	20.9	6/3/98 10:48	20.85	6/3/98 10:55	21
6/3/98 11:45	20.9	6/3/98 11:52	20.85	6/3/98 11:59	21
6/3/98 12:49	20.88	6/3/98 12:56	20.85	6/3/98 13:03	21
6/3/98 13:53	20.89	6/3/98 14:00	20.85	6/3/98 14:07	21.01
6/3/98 14:57	20.89	6/3/98 15:04	20.84	6/3/98 15:11	20.99
6/3/98 16:01	20.88	6/3/98 16:08	20.84	6/3/98 16:15	20.99
6/3/98 17:05	20.88	6/3/98 17:12	20.83	6/3/98 17:19	20.99
6/3/98 18:09	20.88	6/3/98 18:16	20.83	6/3/98 18:23	20.99
6/3/98 19:13	20.88	6/3/98 19:20	20.83	6/3/98 19:27	20.99
6/3/98 20:17	20.88	6/3/98 20:24	20.83	6/3/98 20:31	20.99
6/3/98 21:21	20.88	6/3/98 21:28	20.83	6/3/98 21:35	20.99
6/3/98 22:25	20.88	6/3/98 22:32	20.83	6/3/98 22:39	20.99
6/3/98 23:29	20.88	6/3/98 23:36	20.83	6/3/98 23:43	20.99

Date and time	54-1	Date and time	54-3	Date and time	54-5
6/4/98 0:33	20.88	6/4/98 0:40	20.83	6/4/98 0:47	20.99
6/4/98 1:37	20.88	6/4/98 1:44	20.83	6/4/98 1:51	20.99
6/4/98 2:41	20.88	6/4/98 2:48	20.83	6/4/98 2:55	20.99
6/4/98 3:45	20.88	6/4/98 3:52	20.83	6/4/98 3:59	20.98
6/4/98 4:49	20.88	6/4/98 4:56	20.82	6/4/98 5:03	20.98
6/4/98 5:53	20.87	6/4/98 6:00	20.82	6/4/98 6:07	20.98
6/4/98 6:57	20.87	6/4/98 7:04	20.83	6/4/98 7:11	20.97
6/4/98 8:01	20.86	6/4/98 8:08	20.82	6/4/98 8:15	20.98

Date and time	55-1	Date and time	55-3	Date and time	59-4
6/2/98 12:59	20.89	6/2/98 13:06	20.86	6/3/98 9:30	19.91
6/2/98 13:56	20.89	6/2/98 14:03	20.85	6/3/98 10:34	20.55
6/2/98 14:53	20.89	6/2/98 15:00	20.85	6/3/98 11:38	20.61
6/2/98 15:50	20.88	6/2/98 15:57	20.83	6/3/98 12:42	20.6
6/2/98 16:47	20.86	6/2/98 16:54	20.82	6/3/98 13:46	20.64
6/2/98 17:44	20.85	6/2/98 17:51	20.81	6/3/98 14:50	20.64
6/2/98 18:41	20.85	6/2/98 18:48	20.8	6/3/98 15:54	20.64
6/2/98 19:38	20.84	6/2/98 19:45	20.8	6/3/98 16:58	20.64
6/2/98 20:35	20.84	6/2/98 20:42	20.8	6/3/98 18:02	20.64
6/2/98 21:32	20.83	6/2/98 21:39	20.79	6/3/98 19:06	20.64
6/2/98 22:29	20.84	6/2/98 22:36	20.79	6/3/98 20:10	20.66
6/2/98 23:26	20.85	6/2/98 23:33	20.8	6/3/98 21:14	20.67
6/3/98 0:23	20.84	6/3/98 0:30	20.79	6/3/98 22:18	20.68
6/3/98 1:20	20.82	6/3/98 1:27	20.78	6/3/98 23:22	20.68
6/3/98 2:17	20.83	6/3/98 2:24	20.79	6/4/98 0:26	20.69
6/3/98 3:14	20.83	6/3/98 3:21	20.79	6/4/98 1:30	20.69
6/3/98 4:11	20.83	6/3/98 4:18	20.8	6/4/98 2:34	20.69
6/3/98 5:08	20.83	6/3/98 5:15	20.79	6/4/98 3:38	20.69
6/3/98 6:05	20.83	6/3/98 6:12	20.79	6/4/98 4:42	20.69
6/3/98 7:02	20.83	6/3/98 7:09	20.78	6/4/98 5:46	20.7
6/3/98 7:59	20.83	6/3/98 8:06	20.78	6/4/98 6:50	20.71
6/3/98 9:58	20.92	6/3/98 10:05	20.88	6/4/98 7:54	20.71
6/3/98 11:02	20.92	6/3/98 11:09	20.89		
6/3/98 12:06	20.94	6/3/98 12:13	20.89		
6/3/98 13:10	20.92	6/3/98 13:17	20.87		
6/3/98 14:14	20.94	6/3/98 14:21	20.89		
6/3/98 15:18	20.92	6/3/98 15:25	20.88		

5. Gas and Water Chemistry

Date and time	55-1	Date and time	55-3
6/3/98 16:22	20.92	6/3/98 16:29	20.87
6/3/98 17:26	20.91	6/3/98 17:33	20.88
6/3/98 18:30	20.92	6/3/98 18:37	20.88
6/3/98 19:34	20.92	6/3/98 19:41	20.88
6/3/98 20:38	20.91	6/3/98 20:45	20.87
6/3/98 21:42	20.91	6/3/98 21:49	20.86
6/3/98 22:46	20.91	6/3/98 22:53	20.87
6/3/98 23:50	20.91	6/3/98 23:57	20.88
6/4/98 0:54	20.91	6/4/98 1:01	20.87
6/4/98 1:58	20.91	6/4/98 2:05	20.86
6/4/98 3:02	20.9	6/4/98 3:09	20.86
6/4/98 4:06	20.91	6/4/98 4:13	20.86
6/4/98 5:10	20.9	6/4/98 5:17	20.86
6/4/98 6:14	20.9	6/4/98 6:21	20.86
6/4/98 7:18	20.9	6/4/98 7:25	20.86
6/4/98 8:22	20.91	6/4/98 8:29	20.86

Table 5-18. O₂ (mole [volume] percent) by time, access/observation drift, June 1998.

Date and time	OD-1	Date and time	OD-2	Date and time	OD-3
6/2/98 13:13	20.86	6/2/98 13:20	20.86	6/2/98 13:27	20.85
6/2/98 14:10	20.85	6/2/98 14:17	20.86	6/2/98 14:24	20.85
6/2/98 15:07	20.85	6/2/98 15:14	20.85	6/2/98 15:21	20.85
6/2/98 16:04	20.83	6/2/98 16:11	20.83	6/2/98 16:18	20.83
6/2/98 17:01	20.83	6/2/98 17:08	20.83	6/2/98 17:15	20.82
6/2/98 17:58	20.82	6/2/98 18:05	20.82	6/2/98 18:12	20.82
6/2/98 18:55	20.81	6/2/98 19:02	20.8	6/2/98 19:09	20.81
6/2/98 19:52	20.8	6/2/98 19:59	20.8	6/2/98 20:06	20.8
6/2/98 20:49	20.8	6/2/98 20:56	20.8	6/2/98 21:03	20.8
6/2/98 21:46	20.8	6/2/98 21:53	20.8	6/2/98 22:00	20.8
6/2/98 22:43	20.8	6/2/98 22:50	20.8	6/2/98 22:57	20.8
6/2/98 23:40	20.8	6/2/98 23:47	20.8	6/2/98 23:54	20.8
6/3/98 0:37	20.8	6/3/98 0:44	20.8	6/3/98 0:51	20.8
6/3/98 1:34	20.8	6/3/98 1:41	20.8	6/3/98 1:48	20.8
6/3/98 2:31	20.8	6/3/98 2:38	20.8	6/3/98 2:45	20.8
6/3/98 3:28	20.8	6/3/98 3:35	20.8	6/3/98 3:42	20.8
6/3/98 4:25	20.8	6/3/98 4:32	20.79	6/3/98 4:39	20.8

Date and time	OD-1	Date and time	OD-2	Date and time	OD-3
6/3/98 5:22	20.8	6/3/98 5:29	20.8	6/3/98 5:36	20.8
6/3/98 6:19	20.8	6/3/98 6:26	20.8	6/3/98 6:33	20.8
6/3/98 7:16	20.8	6/3/98 7:23	20.8	6/3/98 7:30	20.8
6/3/98 8:13	20.79	6/3/98 8:20	20.79	6/3/98 8:27	20.78
6/3/98 10:12	20.89	6/3/98 10:19	20.89	6/3/98 10:26	20.89
6/3/98 11:16	20.9	6/3/98 11:23	20.9	6/3/98 11:30	20.9
6/3/98 12:20	20.9	6/3/98 12:27	20.9	6/3/98 12:34	20.9
6/3/98 13:24	20.89	6/3/98 13:31	20.89	6/3/98 13:38	20.89
6/3/98 14:28	20.89	6/3/98 14:35	20.89	6/3/98 14:42	20.89
6/3/98 15:32	20.89	6/3/98 15:39	20.89	6/3/98 15:46	20.88
6/3/98 16:36	20.88	6/3/98 16:43	20.88	6/3/98 16:50	20.88
6/3/98 17:40	20.88	6/3/98 17:47	20.88	6/3/98 17:54	20.89
6/3/98 18:44	20.88	6/3/98 18:51	20.88	6/3/98 18:58	20.88
6/3/98 19:48	20.88	6/3/98 19:55	20.88	6/3/98 20:02	20.88
6/3/98 20:52	20.88	6/3/98 20:59	20.88	6/3/98 21:06	20.88
6/3/98 21:56	20.88	6/3/98 22:03	20.88	6/3/98 22:10	20.88
6/3/98 23:00	20.87	6/3/98 23:07	20.88	6/3/98 23:14	20.88
6/4/98 0:04	20.88	6/4/98 0:11	20.87	6/4/98 0:18	20.88
6/4/98 1:08	20.88	6/4/98 1:15	20.88	6/4/98 1:22	20.88
6/4/98 2:12	20.88	6/4/98 2:19	20.88	6/4/98 2:26	20.88
6/4/98 3:16	20.87	6/4/98 3:23	20.88	6/4/98 3:30	20.88
6/4/98 4:20	20.88	6/4/98 4:27	20.88	6/4/98 4:34	20.88
6/4/98 5:24	20.88	6/4/98 5:31	20.88	6/4/98 5:38	20.88
6/4/98 6:28	20.88	6/4/98 6:35	20.88	6/4/98 6:42	20.86
6/4/98 7:32	20.88	6/4/98 7:39	20.88	6/4/98 7:46	20.86
6/4/98 8:36	20.87				

Table 5-19. Liquid water collected during gas sampling.

Date	Location	Volume liquid collected (mL)	Total volume gas flow (L)	Temperature (°F)	Humidity (%)
6/2/98	54-1	30	23.1		
	54-3	0.1	23.1		
	54-5	2.0	23.1		
	55-1	0.3	23.1		
	55-3	1.0	23.1		
6/1/98	HD1	9.5	29.4	254	16.5
	HD2	9.5	29.4	254	16.5
	HD3	10	28.4	254	16.5
4/21/98	HD1	7 – 10 ^a	44.2	245	19.4
	HD2	7 – 10	44.2	245	19.4
	HD3	7 – 10	44.2	245	19.4

^a We did not collect this water.

Table 5-20. pH measurements.

Sample identification	Sample origin	Date sampled	Date analyzed	pH
Heater drift-1	Respirometer influent filter	3/24/98	3/27/98	8.52
Heater drift-2	Respirometer influent filter	3/24/98	3/27/98	8.50
Heater drift-3	Respirometer influent filter	3/24/98	3/27/98	8.51
Heater drift-1	Respirometer water trap	4/22/98	4/23/98	8.55
Heater drift-2	Respirometer water trap	4/22/98	4/23/98	8.53
Heater drift-3	Respirometer water trap	4/22/98	4/23/98	8.51
ESF-HD-CHE-5 (Borehole 56)	SEAMIST™ liner (removal)	5/5/98	5/6/98	7.12
ESF-HD-CHE-5 (56-1)	56-1 gas-sampling port line	5/5/98	5/5/98	8.0 – 8.5
Heater drift-1	Respirometer water trap	6/2/98	6/4/98	8.17
Heater drift-2	Respirometer water trap	6/2/98	6/4/98	8.20
Heater drift-3	Respirometer water trap	6/2/98	6/4/98	7.97
ESF-HD-CHE-3 (54-1)	Respirometer water trap	6/3/98	6/4/98	7.32
ESF-HD-CHE-3 (54-3)	Respirometer water trap	6/3/98	6/4/98	8.01
ESF-HD-CHE-3 (54-5)	Respirometer water trap	6/3/98	6/4/98	8.03
ESF-HD-CHE-4 (55-1)	Respirometer water trap	6/3/98	6/4/98	7.85
ESF-HD-CHE-4 (55-3)	Respirometer water trap	6/3/98	6/4/98	7.97

Figure 5-1. Chemistry Boreholes 52–56 and 69–73.

5. Figures

Figure 5-2. Percent CO₂ for discrete gas samples collected between December 1997 and April 1998. These are averaged values based on samples “D”, “E”, and “F” (in the case of boreholes gases) or averages of all the measured values for atmospheric samples collected during a particular trip.

Figure 5-3. Gas analyses of heater-drift atmosphere, sampled during April 1998. Three channels each sample and measure O_2 and CO_2 , but the differences among the channels are insignificant.

5. Figures

Figure 5-4. Gas analyses of heater-drift atmosphere, sampled during June 1998. Three channels each sample and measure O_2 and CO_2 , but the differences among the channels are insignificant.

Figure 5-5. Gas analyses of connecting-drift atmosphere, sampled during April 1998. Three channels each sample and measure O_2 and CO_2 , but the differences among the channels are insignificant.

5. Figures

Figure 5-6. Gas analyses of connecting-drift atmosphere, sampled during June 1998. Three channels each sample and measure O₂ and CO₂, but the differences among the channels are insignificant.

Figure 5-7. Gas analyses of Borehole 54, sampled during June 1998. O₂ and CO₂ readings appear to depend on sampling port.

5. Figures

Figure 5-8. Gas analyses of Borehole 55, sampled during June 1998. Differences between the two channels measuring O_2 and CO_2 are insignificant.

Figure 5-9. Gas analyses of hydrology Borehole 59, zone 4, sampled during June 1998. A slight trend toward higher O_2 and CO_2 values is measured over this time period.

Figure 5-10. CO₂ analyses of hydrology Borehole 59 and nearby chemistry Borehole 54.

Figure 5-11. Gas analyses of access/observation-drift atmosphere, sampled during June 1998. Three channels each sample and measure O_2 and CO_2 and do not display significantly different values.

5. Figures

Figure 5-12. CO₂ levels observed in the heater-drift atmosphere and air-pressure readings obtained during corresponding time intervals.

6. Thermohydrologic Modeling

by Thomas A. Buscheck and Kenrick H. Lee

6.1 Introduction

Thermohydrologic (TH) model calculations are conducted with the Nonisothermal Unsaturated-Saturated Flow and Transport (NUFT) code for the Drift-Scale Test (DST). A primary purpose for the TH-model calculations described in this section is to compare the simulated temperatures with the temperatures measured in the field during the first six months of the DST. In the process of comparing the simulated and measured temperatures, it is necessary to analyze the relationship between temperature change and (gas- and liquid-phase) moisture movement in the DST. Another important purpose for the TH-model calculations is to compare the simulated and measured relative humidity RH in the heated drift. A secondary purpose for the TH-model calculations is to scope out the possible heating schedule that will be necessary to achieve a maximum drift-wall temperature of 200°C.

The TH models of the DST described in this section are similar to the three-dimensional (3-D) TH models used in previous studies (Buscheck et al., 1997). Several significant improvements have been incorporated in the current TH models of the DST, including the following:

- A nested numerical mesh to provide much finer gridblock resolution close to the heater drift (HD) and wing-heater arrays.
- Representation of the as-built heating schedules.
- Representation of the as-built thermal bulkhead.
- Representation of the influence of drift ventilation (prior to the start of the DST) on reducing the liquid-phase saturation in the rock adjacent to the HD, plate-loading niche, and connecting drift (CD).
- Representation of the measured barometric pressure history in the unheated drifts in the DST area during the first 148 days of the test.
- Representation of preferential vapor and heat flow along the wing-heater boreholes.

The first four features are included in all TH-model calculations. The fifth feature (accounting for the influence of barometric fluctuations) is included in the base-case TH calculations, but is removed from some of the sensitivity-analysis cases to investigate the influence of barometric pumping. The last feature (representing vapor flow along the wing-heater boreholes) is included in some of the sensitivity-analysis cases.

6.2 Numerical Models and Assumptions

6.2.1 NUFT Numerical Simulation Code

All of the TH-model calculations in this study used the NUFT code (Nitao, 1995). NUFT uses the integrated-finite-difference method and simulates the transport of air, water, energy, and other species such as radionuclides. NUFT determines the spatial and temporal distribution of gas- and liquid-phase pressure, gas- and liquid-phase saturation, air-mass fraction in gas and liquid phases, water-mass fraction in gas and liquid phases, and temperature. NUFT can treat the mechanical dispersion of components. NUFT was

successfully benchmarked against the VTOUGH code (Nitao, 1988), which has been qualified for quality-affecting work, and was recently qualified for quality-affecting work, according to the individual software plan for NUFT.

6.2.2 Equivalent Continuum Method

There are three principal classes of the mathematical treatment of fracture–matrix interaction that are used in TH models. These include the equivalent (or effective) continuum method (ECM), the dual-permeability method (DKM), and the discrete-fracture method (DFM) (Hardin et al., 1998, chapter 3). Because of the computational demands of the DKM and DFM, the TH models of the DST described in this section use the ECM. It is planned to use the DKM in the TH models of the DST in the near future.

The ECM assumes that the local matrix potential (water potential plus osmotic potential) is equal in the fractures and the adjacent matrix. Local thermodynamic equilibrium is assumed between the fractures and matrix. Composite functions are derived to describe the equivalent behavior of a single continuum and to define the relations between unsaturated hydraulic conductivity and liquid-phase saturation and between matrix potential and liquid-phase saturation (Klavetter and Peters, 1986). The ECM does not treat fractures as discrete features; instead, fracture-flow effects are averaged over the whole spatial domain. The ECM involves less computational effort than do the DKM and DFM because it uses a single continuum to represent the fractures and matrix.

The assumption of local equilibrium between fractures and matrix is appropriate if the liquid-phase flux in the fractures is sufficiently small (Buscheck et al., 1991; Nitao et al., 1993). Thus, the ECM is appropriate for modeling condensate drainage during periods of quasi-steady moisture movement in thermally driven models, but may be less well suited for modeling the early stages of repository heating, when the rate of thermally driven moisture reflux will be near its peak and when condensate shedding between emplacement drifts is greatest. Because the DST was designed to develop a broad tabular boiling zone and thereby minimize condensate shedding (as discussed in Section 6.2.5), the ECM is better suited for representing TH behavior in the DST than it is for representing the early stages of TH behavior around emplacement drifts. The ECM assumptions are poorly suited for modeling the effects of transient boundary conditions (e.g., episodic infiltration events).

6.2.3 Model Geometry, Boundary Conditions, and Numerical Mesh

All of the TH-model calculations described in this section are 3-D and incorporate the entire DST area (**Figure 6-1**), including the following features:

- Heated portion of the HD, including nine in-drift heaters.
- Outer wing-heater arrays, represented with smeared-heat sources.
- Inner wing-heater arrays, represented with smeared-heat sources.
- Thermal bulkhead.
- Plate-loading niche.
- Unheated portion of the HD.
- CD.

In addition to the features included in the current DST TH model, previous calculations included the data-acquisition-system (DAS) niche and observation drift (Buscheck et al., 1997). A sensitivity study of model geometry (Buscheck et al., 1997) showed that thermal behavior around the immediate DST area is insensitive to the influence of the DAS niche and observation drift; consequently, those two features are not included in the current TH model.

Figure 6-1. Heater and drift layout in the TH model of the Drift-Scale Test.

Except for the heated portion of the HD, all drifts are held fixed at the initial temperature, gas-phase pressure, liquid-phase saturation, and relative humidity to represent the influence of drift ventilation.

As in previous DST models (Buscheck et al., 1997), the current DST TH model uses a Cartesian (xyz or ijk) coordinate system with the x direction being transverse to the HD, the y direction being parallel to the HD, and the z direction being vertical. The lateral boundaries of the models are adiabatic/no-mass-flow boundaries. The ground surface, which is 250 m above the base of the in-drift heaters, is a constant-temperature, constant-gas-phase-pressure, constant-relative-humidity boundary. The water table, which is 572.3 m below the ground surface, is a constant-temperature, constant liquid-phase-saturation, constant-gas-phase-pressure boundary. The TH models are initialized to account for the geothermal temperature gradient and pneumatostatic pressure gradient in the DST area. The initial temperature at the heater horizon is 24.2°C in the TH models. Although these boundary conditions are not appropriate for mountain-scale TH models, they are sufficiently removed from the DST area not to influence heat-driven TH behavior in the DST.

The HD is represented with a rectangular cross section (4.42 m wide by 4.42 m high). The heated portion of the HD is 47.44 m long. The lower 0.75 m of the HD is filled with a concrete invert with properties listed in **Table 6-1**. The thermal bulkhead that separates the heated and unheated portions of the HD is made of steel with fiberglass insulation and has an effective thickness of 0.07 m in the TH model. The influence of the steel on fluid flow is incorporated in the bulk permeability of the fiberglass; however, it is assumed that the steel is too thin to affect the thermal properties of the fiberglass insulation. To account for the condensation of water vapor on the bulkhead, the wet value of thermal conductivity K_{th} of the fiberglass insulation is assumed to be a factor of 10 greater than that of dry fiberglass insulation (Table 6-1). As discussed later in this section, because of the importance of heat loss through the thermal bulkhead, it is necessary to obtain measurements of K_{th} for fiberglass insulation as a function of liquid-phase saturation and to apply those measurements to future TH-model calculations.

Because of its construction, the thermal bulkhead is extremely leaky and therefore an extremely important conduit for the loss of water vapor (and its associated latent heat) from the DST area. Many of the leaks occur around the perimeter of the thermal bulkhead; however, openings such as the camera door also are significant pathways for water vapor to leave the HD. Further, binary gas-phase diffusion of air and water vapor provides a mechanism for vapor transport out of the HD and air transport into the HD. The current TH model assumes that the fiberglass insulation has zero capillarity; therefore, no van Genuchten parameters are assigned to the fiberglass insulation. Although data for capillary pressure versus liquid-phase saturation and for relative permeability versus liquid-phase saturation do not exist for fiberglass insulation, future TH-model calculations will assume various values for the van Genuchten parameters for the fiberglass insulation to attempt to better address condensate drainage that occurs through the fiberglass insulation.

Table 6-1. Thermohydrologic properties of the concrete invert and fiberglass insulation.

Property	Concrete invert	Fiberglass insulation
Permeability (m^2)	1.9×10^{-16}	1.0×10^{-10}
Porosity	0.11	0.80
van Genuchten a (1/Pa)	6.40×10^{-6}	NA
van Genuchten b (1/Pa)	1.493	NA
Residual saturation	0.01	0.01
Dry thermal conductivity ($\text{W/m}^\circ\text{K}$)	1.70	0.042
Wet thermal conductivity ($\text{W/m}^\circ\text{K}$)	1.70	0.42
Specific heat ($\text{J/kg}^\circ\text{C}$)	753	700
Grain density (kg/m^3)	2200	0.25

All nine in-drift heaters are represented in the model. The heaters are represented with a rectangular cross section (1.5 m wide by 1.5 m high). Along the axis of the drift, the first eight heaters (with the first heater being next to the bulkhead) are represented as being 5.2 m long, which includes the 0.6-m gap between the heaters. The last heater (at the far end of the HD) is represented as being 4.6 m long. The 9 heaters are suspended 0.3 m above the floor (the upper invert surface). Heat flow through the cradles supporting the heaters is ignored. Because the in-drift heaters are effectively in contact with each other in the model (whereas in the field they are separated by 0.6 m) and because K_{th} of air is so small, heater-to-heater thermal-conductive heat flow is set to zero. However, heater-to-heater thermal-radiative heat flow is accounted for in the TH model.

The TH models used the NUFT nested-mesh option to provide finer gridblock resolution in the region of the DST area experiencing strongly driven TH behavior—namely, the region where boiling, dryout, condensate drainage, and two-phase reflux occurs. The nested mesh allows for coarser gridblock resolution in the region outside the region of strongly driven TH behavior and thereby reduces the computational burden. Three finer meshes are embedded in the root mesh, referred to as Mesh 1. Mesh 2 is embedded in Mesh 1. Mesh 3, which encompasses all of the represented drifts in the DST area, is embedded in Mesh 2. Mesh 4, which encompasses an area just beyond the areal extent of the wing-heater arrays, is embedded in Mesh 3. Mesh 5, which encompasses the heated portion of the HD and thermal bulkhead, is embedded in Mesh 4. Mesh 4, which has the finest gridblock dimensions, has a typical gridblock dimension of 0.3 m in the x and z directions for the first meter of rock surrounding the HD and wing-heater arrays. The TH model has 38,210 active gridblocks.

6.2.4 Thermal-Radiative Heat Flow in Heated Drift

As in previous DST TH models (Buscheck et al., 1997), the current TH model provides a comprehensive treatment of thermo-radiative heat flow in the HD (**Figure 6-2**), with thermal radiation between all surfaces in the drift, including:

- Heater-to-heater.
- Heater-to-floor.
- Heater-to-wall.
- Heater-to-bulkhead.

- Wall-to-wall.
- Wall-to-floor.
- Bulkhead-to-floor.
- Bulkhead-to-wall.

As in previous DST models (Buscheck et al., 1997), the emissivity ϵ of the surfaces of the in-drift heaters is assumed to be 0.8; all other surfaces in the drift are assumed to be black bodies, with $\epsilon = 1.0$. The thermo-radiative heat-transfer coefficients among all surfaces in the HD are calculated using the preprocessor RADPRO, which is currently undergoing software quality assurance according to the individual software plan for RADPRO.

Figure 6-2. Vertical cross section of the HD, showing the radiation connections in the TH model.

6.2.5 Heater Power

The nine in-drift heaters are treated as discrete-heat sources that are 1.5 m wide by 1.5 m high by 5.2 m long. The wing heaters, which flank the HD, are represented as four separate heater arrays: two outer arrays and two inner arrays. Each wing-heater array is represented as a uniformly heated, smeared-heat source. The dimensions of each of the wing-heater arrays are 4.77 m (in the x or lateral direction) and 46.9 m (in the y or longitudinal direction). The outer wing-heater arrays have an areal power density that is 50% greater than that of the inner wing-heater arrays. Element failures reported in a few individual wing heaters were not included in the model.

The initial power levels of the in-drift heaters and the inner and outer wing-heater arrays assumed in the TH model closely correspond to the power histories recorded in the field. For the in-drift heaters, the initial power is 5778 W per heater; for the inner and outer wing-heater arrays, the initial areal power density is 135 W/m² and 210 W/m², respectively. These initial power levels are maintained in the TH model until the maximum drift-wall temperature approaches 200°C. The maximum drift-wall temperature occurs at the springline adjacent to the central in-drift heater (heater 5). The power level for all heaters is then uniformly reduced in the TH model to attempt to maintain a quasi-steady maximum drift-wall temperature of 200°C. The TH model was run for several trial-and-error attempts to achieve a quasi-steady maximum drift-wall temperature of 200°C (following the heatup period). The heating schedule that best achieved this goal was as follows:

- Full-power heating from 0 to 1.65 yr, with a total of 52.0 kW for the 9 in-drift heaters, 94.0 kW for the outer wing-heater arrays, and 60.5 kW for the inner wing-heater arrays.
- First ramp-down period from 1.65 to 2.25 yr, when the power for all heaters is ramped down from 100 to 73% of the initial power levels.
- Second ramp-down period from 2.25 to 4.0 yr, when the power for all heaters is ramped down from 73 to 54% of the initial power levels.
- Third ramp-down period from 4.0 to 10.0 yr, when the power for all heaters is ramped down from 54 to 0% of the initial power levels.

Early on, heater 8 had some failed elements, which caused a lower initial power of 4890 W, which was stepped up to 5778 W by about 90 days; the detailed power history of heater 8 is accounted for in the TH model.

The wing-heater operation was represented in the TH model as a smeared-heat source with an initial power output of 154.5 kW (i.e., 94.0 kW from the outer wing heaters and 60.5 kW from the inner wing heaters). This loading gave an areal power density of about 210 W/m² for the outer wing heaters and 135 W/m² for the inner wing heaters. The power modifications and rampdown schedule for the wing heaters were identical to those followed for the in-drift heaters. The wing-heater power was held constant in the TH model for the first 1.65 yr, cut back linearly to 73% of initial value over the period 1.65 to 2.25 yr, and then cut to 54% of initial value over the period 2.25 to 4.0 yr. The wing-heater power was linearly ramped down to zero from 4.0 to 10 yr, the end of the simulation period.

The purpose of using wing-heater arrays in the DST is to cause a tabular region of dryout, which maximizes the tendency for condensate to perch in the rock above the dryout zone. Maximizing the perching of condensate (and minimizing condensate shedding) will maximize the tendency for two-phase refluxing (i.e., the heat-pipe effect) to occur above the dryout zone. Approximating the 50 wing heaters with a smeared-heat source will prevent condensate from shedding between the wing heaters. Prior to the coalescence of the dryout zones surrounding each of the wing heaters, the smeared-heat-source approximation will therefore overpredict the perching of condensate above the dryout zone.

As discussed in Section 6.3.2, the simulated temperatures are higher than the measured temperatures for the outer half of the wing-heater arrays. There are several causes for this discrepancy (described in Section 6.4), the most notable of which is the uncertainty concerning the simulated versus the actual heat loss from the thermal bulkhead. Given the uncertainty about whether the current TH model accurately represents the actual heat loss from the thermal bulkhead, it is possible that the actual heating schedule required to achieve a quasi-steady maximum drift-wall temperature of 200°C will differ somewhat from the heating schedule described previously. The heating schedule described previously should be used to help guide the decisions about ramping down the heater power. Comparisons between measured and simulated temperature histories at the drift wall should be used to fine-tune the manner in which the heater power is ramped down in the field. It would be highly useful to measure the rate of water-vapor loss from the thermal bulkhead because the latent heat transported with that water vapor is the major source of heat loss from the bulkhead; the heat-loss data would be instrumental in improving the TH models so that more reliable TH-model calculations are available to help guide decisions about ramping down the heaters.

6.2.6 Barometric Pressure Fluctuations

Barometric pressure fluctuations in the drifts were incorporated into the model, based on readings from pressure transducer ESF-HD-185-HYD11-PRES-1 through April 30, 1998 (Figure 6-3). Therefore, during the first 148 days of heating, the influence of barometric pressure fluctuations was accounted for. At the time of analysis, no gas-pressure data taken after April 30 were available. For later times, a constant gas pressure of 8.912×10^4 Pa in the unheated drifts was used. This is the approximate average pressure measured in the drifts prior to heating.

Figure 6-3. Barometric-pressure history that is represented in all unheated drifts in the TH model.

6.2.7 Influence of Drift Ventilation

The base-case TH-model calculation assumes that ventilation prior to and during the start of the DST has a negligible effect on drying out the rock in the DST area; the base-case TH model also assumes an *RH* of 100% on the unheated side of the HD. However, prior to the start of the DST, all the drifts in the DST area were ventilated with air that had a much lower relative humidity *RH* than the in situ *RH* ($\approx 99\%$) in the DST area; during the DST, the drifts outside of the heated portion of the HD continue to be ventilated with relatively low *RH* air.

All of the TH-model cases assume an *RH* of 60% is maintained in all the drifts in the model for 1 yr prior to the start of the DST; after the start of the DST, an *RH* of 60% is maintained in the unheated portions of the drifts represented in the TH model. Note that this assumes that the ventilation flow rate in the DST area is large enough to result in a constant *RH* of 60% in the ventilated drifts. Future TH modeling studies will include a sensitivity study of the significance of these assumptions.

6.2.8 Influence of Vapor and Heat Flow Along Wing-Heater Boreholes

Because it is so leaky, the thermal bulkhead is an extremely important conduit for water vapor (and its associated latent heat) to leave the DST. Particularly during barometric pressure lows, water vapor that enters the HD is able to leave the HD by exiting the thermal bulkhead. The 50 wing-heater boreholes are potentially important conduits for water vapor generated during the DST to enter the HD and then to exit the HD through the thermal bulkhead. The base-case TH-model calculation neglects the influence of the transport of water vapor and latent heat from the wing-heater boreholes into the HD; therefore, the base case only considers water vapor that is able to directly enter the HD from the immediately adjacent rock.

To test the potential importance of the flow of water vapor and latent heat along the wing-heater boreholes, a case was run in which the horizontal permeability in the *x* direction (i.e., the direction parallel to the wing-heater boreholes) was increased by a factor of 1000. Although the factor of 1000 is arbitrarily chosen, it is sufficiently large to provide a good indication of the sensitivity of TH behavior to preferential vapor flow along the wing-heater boreholes. This modification was only made in the wing-heater horizon, which is extended to its intersection with the HD. If the DST TH model could explicitly represent the 50 wing-heater boreholes, it would be equivalent to introducing many fracture-like features that are orthogonal to (and intersect) the HD in the plane of the wing-heater arrays. The increased horizontal permeability in this alternative TH model is intended to represent the effect of the 50 wing-heater boreholes being preferential conduits to the flow of water vapor and latent heat into the HD.

6.2.9 Thermal and Hydrologic Properties

The TH calculations were conducted for an ambient percolation flux $q_{\text{perc}} = 3.6 \text{ mm/yr}$ and a corresponding set of hydrologic properties for the fracture and matrix continua in ECM. The hydrologic property set for the 3.6-mm/yr case (**Table 6-2**) was based on a refined, one-dimensional column-model ITOUGH inversion for borehole SD-9 (Bandurraga, 1997). The inversion was based on obtaining a liquid-phase saturation of 92% in model layer tsw34 of the unsaturated-zone site-scale flow model (Tptmn), which is the prevalent rock type in the DST area.

Table 6-2. Thermohydrologic properties of host rock (tsw34) in DST area.

Property	Host rock
Percolation flux q_{perc} (mm/yr)	3.60
Bulk permeability k_b (millidarcy)	100
Matrix permeability (m^2)	9.14×10^{-18}
Fracture permeability (m^2)	4.12×10^{-10}
Matrix porosity	0.11
Fracture porosity	2.43×10^{-4}
Matrix van Genuchten a_m (1/Pa)	1.71×10^{-6}
Matrix van Genuchten b_m	1.471
Matrix residual saturation	0.18
Fracture van Genuchten a_f (1/Pa)	2.17×10^{-5}
Fracture van Genuchten b_f	1.9685
Fracture residual saturation	1.00×10^{-2}
Initial liquid saturation	92%
Dry thermal conductivity (W/m $^{\circ}$ K)	1.67
Wet thermal conductivity (W/m $^{\circ}$ K)	2.00
Specific heat (J/kg $^{\circ}$ C)	953
Grain density (kg/m 3)	2480

For the 3.6-mm/yr case, the initial liquid-phase saturation in the model is 92 to 93% over the entire tsw34 interval; this is similar to the value reported by Bandurraga (1997). The top of the tsw34 layer is 26 m above the heater horizon, but the bottom of the tsw34 is 10 m below the heater horizon. For the 3.6-mm/yr case, the tsw33 and tsw35 layers (which overlie and underlie, respectively, the tsw34) have lower initial liquid-phase saturations than does the tsw34. Therefore, any TH perturbations that extend more than 26 m above or 10 m below the heater horizon occur in rock with slightly lower initial liquid-phase saturation. The value of thermal conductivity K_{th} in the tsw33 and tsw35 layers is different from that in the tsw34; however, these layers are too far removed from the heating horizon for the value of K_{th} to significantly affect TH behavior in the DST.

The thermal conductivity assumed in the TH model described in this chapter is the same as that used in previous DST models (Buscheck et al., 1997) and in the TH model of the Single-Heater Test (Buscheck, 1997). The dry and wet values of thermal conductivity are 1.6 W/m $^{\circ}$ K and 2.0 W/m $^{\circ}$ K, respectively.

6.3 Modeling Results

6.3.1 Simulated Temperature and Liquid-Phase Saturation

Contour plots of temperature T and liquid-phase saturation S_{liq} are shown for various planes at 87 days and 178 days. To provide a big-picture perspective of the areal extent of TH behavior in the DST, one begins with a plan view of T and S_{liq} (Figure 6-4 and Figure 6-5) for a horizontal plane located at $z = 0.4$ m, which is just above the floor of the HD. A cross-sectional view of T and S_{liq} is given for a vertical plane orthogonal to the HD axis at several axial locations, including $y = 2.8$ m, 11.9 m, 23.0 m, and 39.2 m, where $y = 0$ m corresponds to the thermal bulkhead (Figure 6-6, Figure 6-7, Figure 6-8, Figure 6-9, Figure 6-10, Figure 6-11, Figure 6-12, and Figure 6-13).

Figure 6-4. Distribution of (a) temperature and (b) liquid-phase saturation on a horizontal plane through $z = 0.4$ m, at 87 days.

The plane passes through the drift-heater horizon.

Figure 6-5. Distribution of (a) temperature and (b) liquid-phase saturation on a horizontal plane through $z = 0.4$ m, at 178 days.

The plane passes through the drift-heater horizon.

Figure 6-6. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 2.8$ m, transverse to the axis of the drift heaters, at 87 days.

Figure 6-7. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 11.9$ m, transverse to the axis of the drift heaters, at 87 days.

Figure 6-8. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 23.0$ m, transverse to the axis of the drift heaters, at 87 days.

Figure 6-9. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 39.2$ m, transverse to the axis of the drift heaters, at 87 days.

Figure 6-10. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 2.8$ m, transverse to the axis of the drift heaters, at 178 days.

Figure 6-11. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 11.9$ m, transverse to the axis of the drift heaters, at 178 days.

Figure 6-12. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 23.0$ m, transverse to the axis of the drift heaters, at 178 days.

Figure 6-13. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 39.2$ m, transverse to the axis of the drift heaters, at 178 days.

At 87 days, the predicted T and S_{liq} distributions (Figure 6-4 and Figures 6-6 through 6-9) indicate that the dryout zones surrounding the HD and wing-heater arrays have not yet coalesced. At 87 days, there are three separate superheated zones: two centered at the outer third point of the wing-heater arrays and one centered at the HD. The maximum T of about 103°C occurs at the midpoint of the DST (in the axial or y direction) and at the outer third of the wing-heat arrays (in the lateral or x direction). Distinct sub-boiling zones occur between the wing-heater arrays and the HD; these zones are indicated in Figure 6-4a and Figures 6-6a through 6-9a. The greater-than-initial S_{liq} in this region indicates condensate shedding in these areas during the early heatup stage (Figure 6-4b and Figures 6-6b through 6-9b). A pronounced increase in S_{liq} adjacent to the thermal bulkhead (Figure 6-4b) indicates the influence of preferential vapor flow and condensation and condensate drainage in that area. Increased S_{liq} in the region outside the wing-heater arrays also indicates condensate shedding around the outer edge of the wing heaters.

At 178 days, the predicted T and S_{liq} distributions (Figure 6-5 and Figures 6-10 through 6-13) indicate that the dryout zones surrounding the HD and wing-heater arrays have coalesced. At this time, a 27-m-wide superheated zone encompasses much of the wing-heater-array area, much of the rock between the wing heaters and the HD, and nearly the full length of the heated portion of the HD. However, distinct regions of condensate shedding are also evident between the wing heaters and HD at the east and west ends of the HD. In the wing-heater areas and in the rock adjacent to much of the HD, S_{liq} has been reduced to 30 to 40%, with a maximum S_{liq} of 65% along the HD wall. A distinct zone of condensate shedding is evident around the entire perimeter of the superheated zone.

The vertical and lateral extent of the dryout and superheated zones grows considerably between 87 days and 178 days (compare Figure 6-6 through Figure 6-9 with Figure 6-10 through Figure 6-13). The greatest extent of dryout occurs at the midpoint (in the axial or y direction) of the DST (compare Figure 6-12 with Figure 6-10, Figure 6-11, and Figure 6-13). At 87 days, the nominal boiling-point isotherm (96°C) in the vertical cross sections closer to the midplane of the HD, $y = 11.9$ m (Figure 6-7a), and $y = 23.0$ m (Figure 6-8a), completely enclose the HD and wing-heater arrays; for the cross sections closer to the ends of the HD, $y = 2.8$ m (Figure 6-6a) and $y = 39.2$ m (Figure 6-9a), an area of the rock between the wing heaters and the HD remains below the nominal boiling point at 87 days. At 178 days, the upper and lower contours of the nominal boiling-point isotherm are nearly horizontal for all four vertical cross sections, indicating a tabular boiling region. Other temperature isotherms are also more horizontal at 178 days than they are at 87 days. These results indicate that the wing-heater arrays have achieved the purpose of generating a broad tabular region of dryout, which maximizes the tendency for condensate to perch in the rock above the dryout zone.

6.3.2 Comparison of Simulated and Measured Temperatures

A comparison of simulated and measured temperatures T profiles at 87 days and 178 days is given for various measurement boreholes (**Figure 6-14** through **Figure 6-27**). The simulated liquid-phase saturation S_{liq} profile is also plotted along with the temperature even though field measurements of S_{liq} were not available for those locations. Each of the selected-measurement boreholes is parallel to one of the coordinate axes. This allows observation of T and S_{liq} changes along lines from the HD vertically above and below the heater horizon and horizontally out into wing-heater areas. Two of the boreholes examined are drilled from the CD, parallel to the HD axis and above the HD. **Table 6-3** summarizes the borehole locations and orientation.

Table 6-3. Location of boreholes used for comparison of simulated and measured temperature.

Each borehole is parallel to one of the three coordinate axes.

Borehole	Fixed coordinates			Axis orientation
	x	y	z	
79	9.50		3.40	y+
80	-9.60		3.20	y+
133	0.75	2.75		z+
134	0.75	2.75		z-
137	0.80	11.90		z+
141	0.80	11.90		z-
139		11.90	0.0	x-
143		11.90	0.0	x+
158	0.70	23.00		z+
160		22.80	0.11	x-
162	0.70	23.00		z-
164		22.80	0.11	x+
170	0.75	39.20		z+
173	0.75	39.20		z-

Figure 6-14. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 133 at (a) 87 days and (b) 178 days.

Figure 6-15. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 134 at (a) 87 days and (b) 178 days.

- Figure 6-16.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 137 at (a) 87 days and (b) 178 days.
- Figure 6-17.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 141 at (a) 87 days and (b) 178 days.
- Figure 6-18.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 158 at (a) 87 days and (b) 178 days.
- Figure 6-19.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 162 at (a) 87 days and (b) 178 days.
- Figure 6-20.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 170 at (a) 87 days and (b) 178 days.
- Figure 6-21.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 173 at (a) 87 days and (b) 178 days.
- Figure 6-22.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 139 at (a) 87 days and (b) 178 days.
- Figure 6-23.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 143 at (a) 87 days and (b) 178 days.
- Figure 6-24.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 160 at (a) 87 days and (b) 178 days.
- Figure 6-25.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 164 at (a) 87 days and (b) 178 days.
- Figure 6-26.** Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 79 at (a) 87 days and (b) 178 days.

Figure 6-27. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 80 at (a) 87 days and (b) 178 days.

In general, the comparison between the simulated and measured temperatures is good for the vertical boreholes (Figure 6-14 through Figure 6-21). For the horizontal boreholes (Figure 6-22 through Figure 6-27), the comparison between the simulated and measured temperatures is good in the area close to the HD; however, the simulated temperatures are higher than the measured temperatures over much of the wing-heater arrays, with the greatest discrepancy occurring over the outer half of the wing-heater arrays.

The regions for which there is good agreement between predicted and measured temperature fall into two categories:

- Regions with sub-boiling temperatures.
- The boiling and above-boiling regions that are close to the HD.

The good agreement in the sub-boiling-temperature region indicates that heat flow is dominated by heat conduction and that the assumed value of wet thermal conductivity K_{th} is reasonable. Because of the high liquid-phase saturation ($S_{liq} = 0.92$) in the sub-boiling region, the wet value of K_{th} is applicable in that region. Because the bulk permeability ($k_b = 100$ darcy) that was measured in the DST area (and which was assumed for the TH models) is much less than the threshold value of k_b for which buoyant gas-phase convection significantly affects heat flow (Buscheck and Nitao, 1994), it is likely that heat flow in the sub-boiling region is dominated by heat conduction.

The good agreement between simulated and measured temperatures in the region close to the HD indicates the following:

- Thermal radiation is adequately represented in the TH model.
- Heat flow is dominated by heat conduction, and the dry value of K_{th} is adequately represented in the TH model.

The heat flux distribution in the rock adjacent to the HD is dominated by thermal radiation in the drift (Hardin et al., 1998). The good agreement between simulated and measured temperatures in the vicinity of the HD indicates that thermal radiation is well represented in the model. As mentioned previously, k_b in the DST is too low for buoyant gas-phase convection to significantly affect heat flow. Moreover, both the simulated and vertical temperature profiles above the HD (Figures 6-14 through 6-21) do not indicate the presence of a two-phase reflux (or heat-pipe) zone above the HD; therefore, the heat-pipe effect does not significantly affect heat flow in the vicinity of the HD. Because neither of the two key mechanisms that can give rise to convective heat-flow (buoyant gas-phase convection and the heat-pipe effect) is significant in the vicinity of the HD during the first 178 days, heat flow during this period is dominated by heat conduction in that region.

The poor agreement between the simulated and measured temperatures in the outer wing-heater-array areas indicates that the TH model is overpredicting the spatial extent of dryout in that region; consequently, the simulated values of S_{liq} should be regarded as being too low in the outer wing-heater-array areas (Figures 6-22 through 6-27). The overprediction of dryout and temperature rise in the wing-heater-array areas is probably a result of a combination of effects that are not included in the TH model, the first of which is described in Section 6.3.3. The other neglected effects are summarized in Section 6.4.

6.3.3 Influence of Vapor Flow Along Wing-Heater Boreholes

For the base-case TH model (Section 6.3.2), simulated temperatures are considerably higher than the measured temperatures for the wing-heater arrays, particularly for the outer third of the wing-heater arrays. Recall that the base-case TH model does not account for the influence of vapor flow (and its associated latent heat) along the wing-heater boreholes. To assess the potential importance of vapor flow along the wing-heater holes, a sensitivity-analysis case was run where the horizontal permeability in the x direction (i.e., the direction parallel to the wing-heater boreholes) is increased by a factor of 1000. This modification is only made in the wing-heater horizon, which is extended to its intersection with the HD. If the DST TH model were to explicitly represent the 50 wing-heater boreholes, it would be equivalent to introducing many fracture-like features that are orthogonal to (and intersect) the HD in the plane of the wing-heater arrays. The increased horizontal permeability in this alternative TH model is intended to represent the effect of the 50 wing-heater boreholes being preferential conduits for the flow of water vapor and latent heat into the HD.

Discretely including all of the wing-heater boreholes in the TH model would cause the TH-model calculations to be much too computationally expensive to run on a single SUN workstation. Alternative computational approaches are required to explicitly incorporate all of the wing-heater boreholes in the TH model. One such approach, which employs massively parallel computer architecture, is currently under development at Lawrence Livermore National Laboratory (LLNL).

The influence of vapor and heat flow along the wing-heater boreholes is clearly evident at 75 days (**Figure 6-28**). Vapor flow leaving the wing-heater holes carries latent heat away from the wing-heater area, lowering the temperature; this transported latent heat increases the temperature in the rock between the wing-heater arrays and the HD. Note that the base-case TH model predicts a region of sub-boiling conditions between the wing-heater arrays and the HD, whereas the case with the breathing wing-heater holes has boiling temperatures in that region. The flow of water vapor and latent heat into the HD increases both the temperature and relative humidity *RH* in the HD (**Figure 6-29**).

Figure 6-28. Profiles, for two TH models, of (a) temperature and (b) liquid-phase saturation along a horizontal line transverse to the midpoint ($y = 23.0$ m) of the HD.

Figure 6-29. Springline temperature history (a) at the midpoint of the HD for three TH models and relative humidity (b) adjacent to heater 5 at the midpoint of the HD.

The wing-heater boreholes also have a significant effect on the liquid-phase saturation S_{liq} in the wing-heater area and on the rock between the wing-heater arrays and the HD (**Figure 6-28b**). The wing-heater boreholes facilitate additional overall dryout. Because the wing-heater boreholes relieve the gas-phase pressure P_{gas} buildup that would otherwise occur in the wing-heater arrays, boiling can occur at lower temperatures, which effectively limits the throttling of dryout.

6.3.4 Influence of Barometric Pumping

The fluctuation in relative humidity RH in the HD, particularly in the area close to the thermal bulkhead, is strongly affected by the fluctuation in barometric pressure in the DST area. Because the thermal bulkhead provides negligible resistance to gas flow, fluctuations in barometric pressure on the cold side of the thermal bulkhead are instantly transmitted to the hot side of the thermal bulkhead. Consequently, the gas-phase pressure P_{gas} history in the heated portion of the HD is essentially the same as that in the unheated portion of the HD.

Relative humidity RH is given by the relation $RH = P_{\text{gas}}(1 - X_{\text{ag}})/P_{\text{sat}}(T)$, where P_{gas} is the total gas-phase pressure, X_{ag} is the mole fraction of air of the gas phase, and $P_{\text{sat}}(T)$ is the saturated vapor pressure at the local temperature T . The primary cause for the fluctuation in RH is the fluctuation in X_{ag} in the HD. An increase in X_{ag} results in a decrease in RH . The fluctuation in X_{ag} (and RH) occurs from two effects: (1) gas-phase advection of air across the thermal bulkhead and (2) binary diffusion of air and water vapor across the thermal bulkhead.

When P_{gas} in the rock is greater than P_{gas} in the HD, water vapor is advected from the rock into the HD. Prior to the period of vigorous boiling in the rock, barometric-pressure highs can result in P_{gas} in the drift being greater than P_{gas} in the rock, thereby preventing water vapor from entering the drift. If P_{gas} in the drift is high enough, it can also cause air to be advected into the HD through the bulkhead. Even if air is not advected into the HD through the bulkhead, air can enter the drift by binary gas-phase diffusion. If the barometric pressure high causes the gas phase in the drift to be stagnant, air will rapidly diffuse into the HD through the bulkhead. If barometric pressure is low, water vapor will tend to advect into the HD from the adjacent rock; this vapor flow will then be advected out of the HD through the bulkhead; the flow of water vapor out of the HD through the bulkhead opposes the tendency for air to be diffused into the drift. Consequently, during barometric pressure lows, air is being continually displaced from the drift, thereby lowering X_{ag} and increasing RH .

Figure 6-30 shows the influence of barometric pumping on thermal-hydrologic conditions in the vicinity of the thermal bulkhead. During barometric pressure lows, water vapor exits the HD through the thermal bulkhead, transporting latent heat out of the bulkhead. During barometric pressure highs, the direction of gas through the bulkhead is reversed (compared to the direction during barometric pressure lows); therefore, water vapor and latent heat are not lost during barometric pressure highs. At all times there is a loss of heat through the thermal bulkhead resulting from heat conduction; the conductive heat loss increases as the temperature on the hot side of the bulkhead increases. However, for early time ($t < 60$ days) the heat loss out of the thermal bulkhead is small and responds weakly to changes in barometric pressure (Figure 6-30a).

For later times ($t > 60$ days), temperatures begin to exceed the nominal boiling point, substantially increasing the rate of vapor generation in the rock. Because boiling substantially increases the flow rate of water vapor leaving the bulkhead, the loss of latent heat (during barometric pressure lows) increases rapidly for $t > 60$ days. During pressure highs, because the flow of water vapor out of the bulkhead is greatly reduced or even stopped, there is much less heat loss through the bulkhead, as shown in Figure 6-30a. During pressure highs, heat conduction is the dominant mode of heat loss. Because the temperature on the hot side of the bulkhead is continually rising, the conductive heat loss through the bulkhead continually increases with time; thus, even during pressure highs, the trend over time is for increasing heat loss (as shown in Figure 6-30a).

The large contribution of latent-heat loss (during barometric pressure highs) causes the overall heat loss out of the thermal bulkhead to fluctuate widely—cyclically varying from about 4 kW to 24 kW for $t > 60$ days. Note that a heat flux of 24 kW is equivalent to half of total heater power for the nine in-drift heaters. Clearly, the heat loss out of the bulkhead plays an important role in the overall heat balance in the DST. Until efforts are made to measure the latent-heat flux out of the bulkhead, the influence of the thermal bulkhead constitutes a major modeling uncertainty for TH models of the DST. This modeling uncertainty may substantially hamper the ability to validate TH models of the DST. The latent-heat flux out of the bulkhead can be measured by allowing the water vapor to leave the bulkhead through a pipe with sufficiently large diameter (e.g., 3-in. diameter) and into a condenser where the rate of condensate-generation would be measured. Flow resistance through a 3-in. pipe would be negligibly small compared to partially sealed leaks in the thermal bulkhead; therefore, the pipe would be the preferential flow path by which the majority of water vapor would exit the thermal bulkhead.

Relative humidity RH in the drift is also seen to respond strongly to barometric pressure pumping (Figure 6-30b). For early time ($t < 60$ days) the simulated and measured RH in the HD on the hot side of the thermal bulkhead is quite good. However, for $t > 60$ days, the simulated values of RH are much greater than the measured values of RH . The causes for this discrepancy were still under investigation at the time of this report. The preliminary assessment is that the current TH model is probably overrepresenting the resistance to gas flow through the thermal bulkhead. Also, the current TH model does not have enough spatial discretization in the HD to adequately represent the influence of buoyant gas-phase convection on causing water vapor and air to segregate in the HD.

Further, the current model assumes that temperature in the unheated portion of the HD is uniform (as a result of drift ventilation). If the vertical temperature distribution in the drift on the cold side of the bulkhead were represented in the model, it is more likely that a thermally driven flow instability would be predicted, whereby cold air would enter the HD through the lower bulkhead, while hot water vapor would leave the HD through the upper bulkhead. Because the current model underrepresents buoyancy effects in the HD and through the bulkhead, the simulated vapor flow out of the bulkhead occurs in a roughly one-dimensional piston-like fashion, whereby air is displaced by water vapor out of the bulkhead. If the TH model accounted for thermally driven flow instabilities, it would allow more air to remain in the drift, thereby simulating a lower RH in the HD than is simulated by the current TH model. A pipe with a sufficiently large diameter installed in the lower region of the thermal bulkhead would serve as the primary conduit for vapor leaving the thermal bulkhead; this would tend to lessen the influence of thermally driven flow instabilities on the flow of water vapor through the thermal bulkhead.

Figure 6-30. Thermal-hydrologic conditions are given for the vicinity of the thermal bulkhead.

(a) The simulated heat flux history (of heat leaving the HD) through the thermal bulkhead is plotted. Also plotted is the measured barometric pressure history, which is assumed to apply to all unheated drifts in the TH model, including the cold side of the thermal bulkhead.

(b) Also plotted are the measured and simulated relative humidity in the HD immediately adjacent to the hot side of the thermal bulkhead.

6.4 Conclusions and Future Work

Comparisons of simulated and measured temperatures during the first six months of the DST are generally good. There is a tendency, however, to overpredict temperatures in the wing-heater-array areas, particularly in the outer third of the wing-heater arrays. There are several factors currently not considered in the base-case TH model that should decrease the tendency for this overprediction of temperature:

- Preferential vapor flow and its associated latent heat along the wing-heater boreholes will enter the HD and exit the thermal bulkhead.
- Drainage of condensate between the wing-heater boreholes will prevent much of the buildup of condensate that occurs above the wing-heater arrays at early time.
- Nonequilibrium fracture-matrix flow will allow condensate drainage to proceed much further before being imbibed by the rock matrix. Allowing condensate to drain far below the heater horizon will increase heat convection away from the immediate DST area, which will tend to lower simulated temperatures in the DST.
- More realistic representation of heat loss out of the thermal bulkhead are needed. The thermal conductivity of wet fiberglass insulation needs to be measured and incorporated in the TH model to adequately represent conductive heat loss out of the bulkhead. The current base-case model probably under-represented this loss.
- Better hydrologic properties for the concrete invert are needed. Properties for concrete that were used in the Total System Performance Assessment—Viability Assessment (TSPA-VA) seem to better account for the effect of the heat of hydration and for the influence of fractures and joints in the concrete; these properties should be incorporated in the invert.
- Representation of the concrete liner should be incorporated in the TH model along with improved hydrologic properties for concrete mentioned previously.
- Heterogeneity of fracture properties should be incorporated in the TH model to assess whether local heat pipes, small-scale buoyant gas-phase convection cells, or focused condensate drainage might occur within highly fractured zones and thereby result in regions of preferential heating or preferential cooling.

Addressing the first two items will require that the wing-heater boreholes be discretely represented in the TH model. The third item will require that DKM be used in the TH model. The enormous computational effort that would be expended if a DKM were applied to the TH model would be largely wasted if a smeared-heat-source representation of the wing-heater arrays continues to be used.

The fourth item will require laboratory measurements of dry and wet fiberglass insulation as well as the monitoring of the moisture loss out of the thermal bulkhead. The moisture loss out of the bulkhead is probably the most significant TH modeling uncertainty at this time. The fifth item may also require laboratory measurements. The fifth, sixth, and seventh items can be easily accommodated in the TH model.

6.5 References

- Bandurraga, M. (1997). "ITOUGH Inversion for Borehole SD-9." Lawrence Berkeley National Laboratory: personal communication to Buscheck, Thomas A., Lawrence Livermore National Laboratory. May 20, 1997.

- Buscheck, T.A. (1997). *Analysis of Thermal-Hydrological Behavior During the Heating Phase of the Single-Heater Test at Yucca Mountain*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (SP9266M4) Livermore, CA: Lawrence Livermore National Laboratory. [MOL.19980109.0241]
- Buscheck, T.A., and J.J. Nitao (1994). *The Impact of Buoyant Gas-Phase Flow and Heterogeneity on Thermo-Hydrological Behavior at Yucca Mountain*. (UCRL-JC-115351) Livermore, CA: Lawrence Livermore National Laboratory. [NNA.19940524.0009]
- Buscheck, T.A., J.J. Nitao, and D.A. Chesnut (1991). "The impact of episodic nonequilibrium fracture-matrix flow on geological repository performance." In proceedings from *A.N.S. FOCUS '91 Conference on Nuclear Waste Packaging*, Las Vegas, NV: September 29–October 2, 1991. (Also UCRL-JC-106759-SUM, Lawrence Livermore National Laboratory, Livermore, CA) [NNA.911231.0023; 2032525]
- Buscheck, T.A., R.J. Shaffer, and J.J. Nitao (1997). *Pretest Thermal-Hydrological Analysis of the Drift-Scale Thermal Test at Yucca Mountain*. (SP9318M4) Livermore, CA: Lawrence Livermore National Laboratory.
- Hardin, E.L., S.C. Blair, T.A. Buscheck, D.A. Chesnut, L.D. DeLoach, W.E. Glassley, J.W. Johnson, R.B. Knapp, K. Lee, A. Meike, K. Myers, J.J. Nitao, C.E. Palmer, L.L. Rogers, N.D. Rosenberg, B.E. Viani, H.F. Wang, C. Wittwer, and T.J. Wolery (1998). *Near-Field/Altered-Zone Models Report*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (UCRL-ID-129179) Livermore, CA: Lawrence Livermore National Laboratory.
- Klavetter, E.A., and R.R. Peters (1986). *Estimation of Hydrologic Properties of an Unsaturated, Fractured Rock Mass*. (SAND-84-2642) Albuquerque, NM: Sandia National Laboratories. [NNA.870317.0738; 202727]
- Nitao, J.J. (1988). *VTOUGH—An Enhanced Version of the TOUGH Code for Thermal and Hydrologic Simulation of Large-Scale Problems in Nuclear Waste Isolation*. (UCID-21954) Livermore, CA: Lawrence Livermore National Laboratory. [NNA.19900508.0040]
- Nitao, J.J. (1995). *Reference Manual for the NUFT Flow and Transport Code, Version 1.0*. Livermore, CA: Lawrence Livermore National Laboratory. (UCRL-IC-113520)
- Nitao, J.J., T.A. Buscheck, and D.A. Chesnut (1993). "Implications of episodic nonequilibrium fracture-matrix flow on repository performance." *Nucl. Tech.* **104**(3):385–402. (Also UCRL-JC-109216, Lawrence Livermore National Laboratory, Livermore, CA) [NNA.19930727.0005; 208836]

Figure 6-1. Heater and drift layout in the TH model of the Drift-Scale Test. Except for the heated portion of the HD, all drifts are held fixed at the initial temperature, gas-phase pressure, liquid-phase saturation, and relative humidity to represent the influence of drift ventilation.

Figure 6-2. Vertical cross section of the HD, showing the radiation connections in the TH model.

Figure 6-3. Barometric-pressure history that is represented in all unheated drifts in the TH model.

Figure 6-4. Distribution of (a) temperature and (b) liquid-phase saturation on a horizontal plane through $z = 0.4$ m, at 87 days. The plane passes through the drift-heater horizon.

Figure 6-5. Distribution of (a) temperature and (b) liquid-phase saturation on a horizontal plane through $z = 0.4$ m, at 178 days. The plane passes through the drift-heater horizon.

Figure 6-6. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 2.8$ m, transverse to the axis of the drift heaters, at 87 days.

Figure 6-7. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 11.9$ m, transverse to the axis of the drift heaters, at 87 days.

6. Figures

Figure 6-8. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 23.0$ m, transverse to the axis of the drift heaters, at 87 days.

Figure 6-9. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 39.2$ m, transverse to the axis of the drift heaters, at 87 days.

6. Figures

Figure 6-10. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 2.8$ m, transverse to the axis of the drift heaters, at 178 days.

Figure 6-11. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 11.9$ m, transverse to the axis of the drift heaters, at 178 days.

6. Figures

Figure 6-12. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 23.0$ m, transverse to the axis of the drift heaters, at 178 days.

Figure 6-13. Distribution of (a) temperature and (b) liquid-phase saturation on a vertical plane through $y = 39.2$ m, transverse to the axis of the drift heaters, at 178 days.

6. Figures

Figure 6-14. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 133 at (a) 87 days and (b) 178 days.

Figure 6-15. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 134 at (a) 87 days and (b) 178 days.

Figure 6-16. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 137 at (a) 87 days and (b) 178 days.

Figure 6-17. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 141 at (a) 87 days and (b) 178 days.

Figure 6-18. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 158 at (a) 87 days and (b) 178 days.

Figure 6-19. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 162 at (a) 87 days and (b) 178 days.

Figure 6-20. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 170 at (a) 87 days and (b) 178 days.

Figure 6-21. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (vertical) borehole 173 at (a) 87 days and (b) 178 days.

6. Figures

Figure 6-22. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 139 at (a) 87 days and (b) 178 days.

Figure 6-23. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 143 at (a) 87 days and (b) 178 days.

Figure 6-24. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 160 at (a) 87 days and (b) 178 days.

Figure 6-25. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 164 at (a) 87 days and (b) 178 days.

6. Figures

Figure 6-26. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 79 at (a) 87 days and (b) 178 days.

Figure 6-27. Comparison of simulated and measured temperature profiles, plotted with the simulated liquid-phase saturation profile, along (horizontal) borehole 80 at (a) 87 days and (b) 178 days.

Figure 6-28. Profiles, for two TH models, of (a) temperature and (b) liquid-phase saturation along a horizontal line transverse to the midpoint ($y = 23.0$ m) of the HD.

6. Figures

Figure 6-29. Springline temperature history (a) at the midpoint of the HD for three TH models and relative humidity (b) adjacent to heater 5 at the midpoint of the HD.

Figure 6-30. Thermal-hydrologic conditions are given for the vicinity of the thermal bulkhead. (a) The simulated heat flux history (of heat leaving the HD) through the thermal bulkhead is plotted. Also plotted is the measured barometric pressure history, which is assumed to apply to all unheated drifts in the TH model, including the cold side of the thermal bulkhead. (b) Also plotted are the measured and simulated relative humidity in the HD immediately adjacent to the hot side of the thermal bulkhead.

7. Laboratory Results

7.1 Drying and Rewetting of Intact Rocks

by Marc Costantino, Wunan Lin, Eric Carlberg, Ron Pletcher, and Jeff Roberts

7.1.1 Introduction

The primary focus of this section is measurement of moisture-retention curves of tuff as a function of temperature for drying and rewetting conditions. The section contains descriptions of experimental designs and procedures, data, observations, preliminary analyses, and future work.

Knowledge of unsaturated transport properties is critical for understanding the movement of water through the unsaturated zone. Evaluation of the performance of a potential nuclear waste repository also depends on knowledge of these properties. Moisture-retention data are important input for numerical models of moisture movement in unsaturated porous media. Also important is the effect of sample history on the moisture-retention curves and the question of significant hysteresis between wetting and drying measurements.

In this section, moisture-retention data are reported for core samples from the Drift-Scale Test (DST) and, for comparison, similar data from samples from the Single-Heater Test (SHT). The measurement of the moisture-retention curves of those core samples in the drying phase at 95°C have been completed. The moisture-retention curves at selected lower temperatures will be repeated in the next quarter to assess the effect of temperature cycling. Previous measurements of the matric potential of tuff are reported by Roberts and Lin (1994) and in the *Near-Field and Altered-Zone Environment Report, Vol. II* (Wilder, 1996).

7.1.2 Experimental Procedure

7.1.2.1 Sample Description and Preparation

Samples from the DST and the SHT from the Exploratory Studies Facility (ESF) were prepared from cores taken from the chemistry boreholes. **Table 7-1** and **Table 7-2** list the identification numbers, boreholes, depths, wet and dry densities, and porosities. Thirteen DST samples and eleven SHT samples were prepared. The samples were subcored to a diameter of between 4.4 cm and 6.1 cm and cut into disks approximately 2.5 to 3.0 mm thick. Samples with obvious large cavities and inhomogeneous inclusions were avoided. The porosity of each sample was determined by subtracting the dry density from the saturated density and dividing by the water density. The average porosity for the DST samples was $10.0 \pm 1.7\%$; for the SHT samples, it was $11.1 \pm 1.1\%$.

7.1.2.2 Calculation of Matric Potential

The matric potential is the pressure potential that arises from the interaction of water with a solid matrix (Marshall and Holmes, 1992). In tuff, it is assumed that the suction potential is equal to the matric potential. Matric potential is defined by Kelvin's Law as

$$y = b R T \ln (e/e_0)/M \quad (7-1)$$

7. Laboratory Results

where y is the matric potential in MPa, b is the density of water at the temperature of interest in g/cm^3 , R is the universal gas constant ($8.314 \text{ J}/\text{Kmol}$), T is temperature in K, e/e_0 is the relative humidity RH , and M is the molecular weight of water ($18.015 \text{ g}/\text{mole}$).

Matric potential is related to the water saturation using the RH as a parameter. The equilibrium saturation of the sample at a constant RH is measured (the “moisture-retention curve”) and plotted against the matric potential calculated using Kelvin’s law at that RH . This provides an empirical relation between the effective matric potential and the sample saturation, parameterized through RH and temperature. This effective matric potential includes the contribution of all rock properties (e.g., porosity, pore-size distribution, connectivity, chemistry) to the storage and release of water as a function of temperature and RH .

To determine the moisture-retention curve, samples were placed in the humidity chamber at a specific temperature and $\sim 20\%$ RH . Measurements began on dry samples. When the weights reached a constant value for several days (samples were weighed daily), it was assumed that equilibrium was established. When a stable weight was achieved, the RH was increased and the process repeated at the same temperature. The maximum saturations achieved at the highest RH ($\sim 98\%$) were between 30% and 40% (vide infra). A balance with a sensitivity of 0.01 mg calibrated to a traceable standard was used to weigh the samples. Saturation was calculated by comparing the samples’ weights with dry weights and taking porosity into account. The process was then repeated for the drying portion of the measurement. This cycle of measurement was repeated at different temperatures.

The following procedure was used to perform the measurements:

1. The samples were machined and the dimensions measured.
2. The samples were placed in a vacuum oven at 35°C to reach a completely dry state.
3. The samples were placed in the relative humidity chamber at 25.1°C and 20% RH .
4. When a stable weight (corresponding to a saturation) was achieved, the RH was increased to 50%. This was repeated as the RH was increased to 80%, and then to 95%.
5. The RH was decreased according to the following steps: 80%, 50%, and 20%.
6. This procedure was repeated for all samples at the next temperatures: 49.6°C and 95°C .

The SHT samples at 25.1°C had additional measurements performed, during both wetting and drying, at 35% and 65% RH .

7.1.3 Measurement Uncertainty

The uncertainties involved in the determination of the moisture-retention curves include the measurements of weights, RH , and sample size. The sample dimensions are used to determine wet and dry densities of the sample. It is estimated that the thickness of the sample can be determined to $\pm 0.01 \text{ mm}$ and diameter can be determined to $\pm 0.03 \text{ mm}$. For the samples used here, this results in an error in sample volume of $\sim \pm 0.4\%$. The uncertainty in dry weight is estimated to be $\sim 0.00002 \text{ g}$; for wet weight, it is estimated to be $\sim 0.0001 \text{ g}$. The error in the wet weight is greater than that of the dry condition because of the difficulty in achieving and maintaining saturation levels of 100% at elevated temperature. These uncertainties result in errors in dry and wet densities of $\sim 3\%$. When propagated through to porosity, the error is $\sim 1.0\%$ porosity, or $\sim 7\text{--}11\%$ of the measurement (Bevington and Robinson, 1992).

When repetitive measurements (e.g., the determination of weights at a specified *RH*) are made on samples over several days, the uncertainty in the measurement is often less than the statistical uncertainty in the mean of the measured parameter. In such cases, the error is taken as one standard deviation of the mean of the repeated measurements. The errors in saturation determined at specific temperature and *RH* vary from ~0.07 to 0.4% Sw. Thus, the relative uncertainty is between ~1% and 10%, with a 1% to 2% error most common.

The uncertainty in the *RH* is approximately $\pm 2\%$. When propagated through Eq. 7-1 to matric potential, the absolute uncertainties are fairly low, but the relative uncertainties are high at the matric potentials closest to zero.

The temperatures reported in this section are the mean temperatures recorded during the time periods of the measurements. The highest statistical uncertainty (one standard deviation) is about $\pm 0.6^\circ\text{C}$, but statistical uncertainty is generally less than $\pm 0.3^\circ\text{C}$.

7.1.4 Results and Discussion

7.1.4.1 DST Samples

The samples of the DST used in the moisture-retention-curve measurements are listed in Table 7-1. Moisture-retention curves of the DST samples are shown at temperatures of 25.1°C (**Figure 7-1**), 49.6°C (**Figure 7-2**), and 93.7°C (**Figure 7-3**). For clarity, only the average (i.e., the mean saturation and matrix potential of all samples) properties are shown. The error bars for saturation are the standard deviation from the average saturation at a matrix potential level of all samples. There is very little hysteresis observed between the wetting and drying curves. Previous measurements on similar samples showed significant hysteresis under certain conditions (Wilder, 1996). There is also very little difference between the 25.1°C and 49.6°C curves. But the data at 93.7°C show significantly less moisture retention than do the data of the lower temperature curves. For comparison, samples from USW-G4 (NTS borehole) showed a significant dependence of moisture retention on temperature (Roberts and Lin, 1994).

Table 7-1. Drift-Scale Test samples prepared for moisture-retention experiments.

Sample ID	Borehole	Depth (m)	Wet density (g/cm ³)	Dry density (g/cm ³)	Porosity
01002163-1	CHE-1	92.3 –93.2	2.371	2.286	0.0853
01002176-1	CHE-2	128.9 –129.6	2.322	2.211	0.111
01002179-1	CHE-5	39.4 –40.1	2.386	2.303	0.0831
01002189-1	CHE-6	43.4 –44.1	2.307	2.216	0.0914
01002190-1	CHE-6	63.9 – 64.6	2.375	2.292	0.0835
01002194-1	CHE-6	99.7 –100.4	2.330	2.224	0.106
01002199-2	CHE-7	51.9 – 52.6	2.301	2.174	0.127
01002200-1	CHE-7	80.0 –80.7	2.363	2.273	0.0895
01002206-2	CHE-10	15.7 –16.3	2.329	2.227	0.102
01002207-2	CHE-10	27.3 –28.0	2.400	2.311	0.0891
01002209-2	CHE-10	75.6 –76.3	2.379	2.254	0.125
01002212-1	CHE-10	91.6 –92.3	2.368	2.243	0.124
01002215-1	CHE-10	124.0–124.7	2.361	2.282	0.0796
Mean*	13 samples		2.35$\pm$0.03	2.25$\pm$0.04	0.100$\pm$0.017

* Statistical mean for 13 samples; errors represent one standard deviation for all samples collectively

7. Laboratory Results

Figure 7-1. Matric potential versus average saturation for 13 DST samples at 25.1°C.
Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-2. Matric potential versus average saturation for 13 DST samples at 93.7°C.
Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-3. Matric potential versus average saturation for 13 DST samples at 49.6°C.
Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

7.1.4.2 SHT Samples

The samples of the SHT used in the moisture-retention-curve measurements are listed in Table 7-2. Moisture-retention curves of the SHT samples at temperatures of 25.1°C, 49.6°C, and 93.7°C are shown in **Figure 7-4**, **Figure 7-5**, and **Figure 7-6**, respectively. Only the average (i.e., mean saturation and matric potential of all samples) properties are shown for clarity. The error bars for saturation are the standard deviation from the average saturation at a matric potential level of all samples. As was the case for the DST samples, neither hysteresis nor a notable temperature dependence was evident. Also, stronger temperature dependence of the moisture-retention curves is shown for the 93.7°C data than for those at the lower temperatures.

Table 7-2. Single-Heater Test samples prepared for moisture-retention experiments.

Sample ID	Borehole	Depth (m)	Wet density g/cm³)	Dry density (g/cm³)	Porosity
0047525.2	CHE-1	2.20	2.348	2.247	0.102
0047525.2A	CHE-1	2.30	2.350	2.249	0.102
0047526.2	CHE-1	4.60	2.349	2.240	0.109
0047527.2	CHE-1	8.20	2.345	2.246	0.0998
0047528.2	CHE-1	12.5	2.331	2.224	0.107
0047529.2	CHE-1	14.0	2.344	2.235	0.109
0047530.2A	CHE-2	14.8	2.294	2.167	0.127
0047531.2	CHE-2	5.00	2.332	2.222	0.111
0047533.2	CHE-2	12.7	2.290	2.156	0.135
0047534.2	CHE-2	15.2	2.331	2.229	0.103
0047535.2	CHE-2	17.6	2.314	2.195	0.119
Mean*	11 samples		2.33±0.02	2.22±0.03	0.111±0.011

* Statistical mean for 11 samples; errors represent one standard deviation for all samples collectively.

Figure 7-4. Matric potential versus average saturation for 11 SHT samples at 25.1°C.
Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-5. Matric potential versus average saturation for 11 SHT samples at 49.6°C.
Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-6. Matric potential versus average saturation for 11 SHT samples at 93.7°C.
Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

The moisture-retention curves for the SHT samples are dependent on temperature. The effect is not significant between 25°C and 50°C, but it seems to be significant between 50°C and 94°C. The effect of temperature on the moisture-retention curves is always to decrease the level of saturation at a matric potential level; this is true for both the DST and the SHT samples. The maximum saturation that can be reached in those samples depends on temperature. At 25.1°C, the maximum saturation achieved is ~30% for the DST samples and ~36% for the SHT samples. At 49.6°C, this increases to ~40% for the DST samples and to ~39% for the SHT samples. But, at 93.7°C, it decreases to about 28% for the DST samples and to about 29% for the SHT samples. These saturations are higher than those reported for USW-G4 and Large-Block Test (LBT) samples, which were ~30% saturation at the highest *RH*.

7.1.5 Future Work

The measurements are complete on both DST and SHT samples for monotonic temperature increase from 25°C to 95°C. Measurements at 25°C will be repeated to assess the effect of higher temperature excursions on the repeatability of the previous (low-temperature) measurements.

7.2 Preliminary Results on Sorptivity

by Marc Costantino and David Ruddle

7.2.1 Introduction

Water mass balance ($m_w(\mathbf{x}, t)$) in the proposed repository is a fundamental variable in a qualitative understanding the thermal-hydrologic-chemical-mechanical (THCM) response of fluids and in quantitative calculations using models of the repository (Nitao and Buscheck, 1989; Travis et al., 1984). In addition to being the simple transport of water mass as a chemical reactant in processes such as barrier material corrosion, waste-form dissolution, and hydrologic property changes, the water mass (in both liquid and vapor phases) is a significant heat-transport medium. Understanding and predicting $m_w(\mathbf{x}, t)$ requires quantitative measurements of water source and sink terms and physical properties such as the location of the fluid-vapor-phase equilibrium line, heat capacity, surface tension, fluid and vapor heat transfer, and viscosity. The accuracies of handbook values for most of these data are adequate for modeling purposes, even acknowledging errors owing to dissolved impurities.

Source and sink terms are significantly less well understood. Source terms include the following:

- Gravity- and capillary-driven transport from free-standing water at the surface
- Gravity- and capillary-driven flow through very high permeability fracture networks
- Mechanically driven flow owing to changes in water-filled porosity
- Mechanically driven flow owing to pressure gradients across water–water vapor (steam) interfaces
- Reversible chemical reactions involving water as a product

Sink terms include all of these terms (with the sign of the driving force reversed) as well as evaporation at the surface and chemical reactions with water as a reactant.

Sorptivity is a central feature of fluid transport in soils (see, for example, Jury et al., 1991), and both the experimental methodology and data analysis for sorptivity in porous rocks follow from those used in soil physics. The Richards equation (Richards, 1931) is used to describe one-dimensional flow of fluid into a partially saturated medium. Because the equation is a diffusion equation, the solution for cumulative water transport into the volume, $\mathbf{x}$, for the case of boundary conditions used in this work [a given initial, uniform saturation, $s_w(\mathbf{x}, 0)$; and an infinite liquid water source at one boundary $s_w(0, t) = 1$] is proportional to $t^{1/2}$. Zimmerman and Bodvarsson (1990) provide a useful discussion of the absorption of water into porous blocks.

This section documents experiments to measure the sorptivity in Topopah Spring tuff. These measurements are intended to provide data and a phenomenological understanding of the sorption of water into a porous tuff as part of a general investigation into the THCM response of rock to conditions similar to those in the near-field environment (NFE) of the potential nuclear-waste repository. This section contains a description of measurements of the sorptivity into dry (0% relative saturation) samples at 20°C, 60°C, and 90°C. These data provide insight into the important processes controlling fluid mass balance in fractured rocks at NFE temperature conditions, contribute to the database used in simulations of the potential repository, and provide validation and verification opportunities for computer models.

Presented are sorptivity data for 16 samples in the form of weight gain versus time. The data are interpreted using the Philip formalism (Philip, 1957), in which mass flow into a porous medium under our specific boundary and initial conditions obeys a diffusion law resulting in a square-root dependence on time for early times:

$$I(t) = SA t^{1/2}, \quad (7-2)$$

where $I(t)$ is the volume flow of water into the rock, A the area over which the boundary condition $s_w(\mathbf{x}=0, t) = 1$ occurs, and t the time. Here, $s_w(\mathbf{x}, t)$ is the relative saturation of the rock. The initial condition is $s_w(\mathbf{x}, 0) = 0$ for $\mathbf{x} > 0$. Presented are sorptivity coefficients S and a discussion of their significance to imbibition of water into dry porous rock adjacent to a fully saturated boundary at 0.1 MPa effective pore pressure.

7.2.2 Methodology

The experiment plan is to measure water uptake under the following conditions:

- In a statistically significant number of samples from several horizons relevant to the ESF
- With well-characterized initial and boundary conditions appropriate for extraction of material coefficients using analytic methods
- Along several isotherms characteristic of the NFE

7.2.2.1 Sample Preparation

Sample Source

Core material is Topopah Spring tuff from the ESF-HD-CHE chemistry boreholes in the ESF (TRW, 1997). **Table 7-3** provides the sample identification number, traceable to the Yucca Mountain Site Characterization Project (YMP) Sample Management Facility, and sample dimension data after coring and grinding. The samples are right circular cylinders, nominally 2.5 cm diameter and 2.8 cm long.

Table 7-3. Sample characterization data.

Sample	Parent borehole	Specimen ID	Type	Depth (ft)	Diam. (cm)	Length (cm)	Volume (cm ³)	Wet wt (gm)	Dry wt (gm)	Effective porosity
1	ESF-HD-CHE-1	01002159A	WCSpec	53.7	2.534	2.869	14.469	34.047	32.471	0.109
2	ESF-HD-CHE-1	01002159B	WCSpec	53.7	2.534	2.799	14.116	32.637	30.727	0.135
3	ESF-HD-CHE-1	01002164A	WCSpec	108.7	2.534	2.998	15.119	35.946	34.534	0.093
4	ESF-HD-CHE-1	01002164B	WCSpec	108.7	2.534	2.920	14.726	34.389	32.587	0.122
5	ESF-HD-CHE-2	01002169	WCSpec	58.2	2.534	2.958	14.918	35.028	33.344	0.113
6	ESF-HD-CHE-2	01002173A	WCSpec	97.5	2.534	2.932	14.787	34.433	32.737	0.115
7	ESF-HD-CHE-2	01002173B	WCSpec	97.6	2.534	2.987	15.064	35.344	33.786	0.103
8	ESF-HD-CHE-5	01002180A	WCSpec	50.5	2.535	3.001	15.146	35.937	34.562	0.091
9	ESF-HD-CHE-5	01002180B	WCSpec	50.5	2.535	3.028	15.283	36.012	34.447	0.102
10	ESF-HD-CHE-5	01002184	WCSpec	99.3	2.534	2.870	14.474	33.596	31.521	0.143
11	ESF-HD-CHE-6	01002189	WCSpec	44.0	2.533	2.922	14.724	34.786	33.389	0.095
12	ESF-HD-CHE-6	01002194	WCSpec	100.1	2.532	2.748	13.837	32.606	31.213	0.101
13	ESF-HD-CHE-7	01002199	WCSpec	52.0	2.532	2.921	14.708	34.455	32.833	0.110
14	ESF-HD-CHE-7	01002201	WCSpec	95.7	2.535	2.870	14.485	34.208	32.826	0.095
15	ESF-HD-CHE-10	01002208	WCSpec	37.9	2.533	2.785	14.034	31.060	28.482	0.184
16	ESF-HD-CHE-10	01002213	WCSpec	100.3	2.532	2.922	14.713	35.309	33.798	0.103

Sample Preparation

The original borehole cores were undercored using 1-in. diamond coring cutters and tap-water lubricant. End faces were ground flat and parallel to ± 0.05 mm. Diameters were ground circular to ± 0.01 mm. The 16 samples were air dried at room temperature, then vacuum dried at 35°C for approximately 650 hr; there was no statistically significant weight loss for the final 100 hr. These weights form the “Dry Weight” in **Table 7-4**.

As a barrier to water transport through that surface, the cylindrical surfaces of all samples (except samples #2 and #4) were coated with a thin layer of Dow Corning 3145. The top and bottom faces of the samples were not coated.

To estimate the effective porosity (i.e., the porosity that could be filled with water under conditions of room temperature and pressure), the samples were immersed in deionized water under a vacuum. The explicit assumption was made that the water gain represents 100% saturation of the sample. The weights of the samples after coating and saturation are shown as “Wet Weight” in **Table 7-3**. The effective porosity (which is less than the sample porosity because not all porosity is filled by water) was calculated using

$$\Phi = \frac{\rho_{\text{wet}} - \rho_{\text{dry}}}{\rho_{\text{water}}} = \frac{w_{\text{wet}} - w_{\text{coating}} - w_{\text{dry}}}{V \cdot \rho_{\text{water}}} \quad (7-3)$$

The effective porosity ranged from 0.091 to 0.184, with an average of 0.113 and a standard deviation of 0.024.

7.2.3 Experiment

A sorptivity measurement consists of placing one end face of the vertically oriented dry, circular-cylinder sample in contact with liquid water and exposing the opposite end face to near 100% *RH* at ambient pressure at the temperature of interest (i.e., to a water-vapor partial pressure at the water-gas-liquid phase line). For temperatures less than 100°C , this can be accomplished with a simple apparatus, shown in **Figure 7-7**. The container ideally is an isothermal surface so that the sample, liquid, and vapor are at the same temperature. Temperature and *RH* are monitored continuously using a Vaisala Model HMP 235 temperature-humidity probe with a calibration traceable to NIST primary standards. **Figure 7-8** shows typical variations in temperature and *RH* at a nominal constant temperature and the variations when the container is opened to remove the samples for weighing.

Figure 7-7. Schematic of the experimental apparatus.

Figure 7-8. Typical response and control for the temperature and relative humidity in the sample chamber.

At $t = 0$, the dry sample is placed in contact with the liquid water, with the water level not more than 1 mm above the bottom surface of the sample. At various $t > 0$, the samples are removed from the container and placed in a tray with enough water to immerse the bottoms of the samples. For each sample, droplets of free-standing water are removed by swiping lightly; the sample is then weighed and replaced in the tray. After all 16 samples are weighed, they are replaced in the container. This process takes 10 to 12 min. Samples are weighed using a Mettler Model AE240 balance, which is checked each time before weighing

with a mass having a calibration traceable to NIST primary standards. Because the weight gain is nonlinear (see **Figure 7-9**), with the highest curvature for short times, samples initially are weighed over a period of 10 to 14 days at intervals increasing from 30 min to 3 to 4 days.

To re-establish the initial, dry condition of the samples for the next isotherm, the samples are first air dried and then dried in a vacuum oven at 35°C to return the sample weight to within +0.05 gm of its initial starting weight.

7.2.4 Results and Discussion

Typical weight versus time data for an isotherm are shown in **Figure 7-9**. Early time data are plotted as a function of $t^{1/2}$, and data for fitting to a straight line are selected by eye. These data and the fitted lines are shown in **Figure 7-10**. The slope of the line for a particular sample is SA (see Eq. 7-2), the product of the sorptivity coefficient and the area across which the fluid is moving.

Figure 7-9. Typical sample-weight versus time for an isotherm.

Figure 7-10. Typical early time data selected for curve fitting to $w(t) = Sat^{1/2}$.

Sorptivity values for each sample at each of the three isotherms are given in **Table 7-4**. The sorptivity coefficients generally fall into three groups that may be distinct for $T = 20^\circ\text{C}$, but that become statistically the same for $T = 90^\circ\text{C}$. The sorptivity is not strongly correlated to sample effective porosity (**Figure 7-11**), but increases monotonically with temperature (**Figure 7-12**). The outlying behavior of Sample 15 has not yet been examined in detail, but most likely owes to the sample's high porosity and to highly permeable fracture surfaces intersecting the bottom face. All statistics are calculated after deleting Sample #15 from the data series.

Figure 7-11. Sorptivity coefficient vs. effective porosity for the $T = 20^\circ\text{C}$ isotherm (scatter plot).

Figure 7-12. Sorptivity coefficient vs. temperature.

- is the average of all coefficients except that for Sample 15. The error bar is one standard deviation.

The range of sorptivity of 0.02 to 0.09 cm-hr^{-1/2} measured in this work is significantly below the values of 0.1 to 0.8 cm-hr^{-1/2} reported by Flint et. al. (1994) on welded and nonwelded tuffs from the boreholes in the G-Tunnel facility at Yucca Mountain.

Table 7-4. Sorptivity (cm-hr^{-1/2}) for the 20°C, 60°C, and 90°C isotherms.

Sample	20°C	60°C	90°C
1	0.034	0.040	0.051
2	0.026	0.035	0.054
3	0.018	0.024	0.031
4	0.023	0.034	0.067
5	0.040	0.040	0.079
6	0.042	0.044	0.092

7. Laboratory Results

Sample	20°C	60°C	90°C
7	0.023	0.030	0.040
8	0.024	0.031	0.040
9	0.031	0.036	0.049
10	0.036	0.044	0.057
11	0.024	0.030	0.038
12	0.021	0.027	0.037
13	0.041	0.042	0.067
14	0.025	0.030	0.039
15	0.065	0.054	0.143
16	0.026	0.031	0.044

7.2.5 Summary

Sorptivity for 16 samples of Topopah Spring tuff from the chemistry boreholes ESF-HD-CHE-1, 2, 5, 6, 7, and 10 in the heated drift in the ESF was measured for 0% initial saturation along the 20°C, 60°C, and 90°C isotherms. Average values are 0.029 ± 0.008 , 0.034 ± 0.006 , and $0.052 \pm 0.017 \text{ cm-hr}^{-1/2}$, respectively, where the mean and estimated error of one standard deviation are calculated and the outlying sample 15 is excluded. The sorptivity is not strongly correlated with sample effective porosities in the range 0.09 to 0.18, but shows a significant monotonic increase with temperature.

It is planned to extend these measurements to temperatures greater than 100°C, along the water fluid-gas phase line.

7.2.6 References

- Bevington, P.R., and D.K. Robinson (1992). *Data Reduction and Error Analysis for the Physical Sciences*. San Francisco, CA: McGraw-Hill.
- Flint, A.L., L.E. Flint, and K.A. Richards (1994). "Evaluation of measurement scale using imbibition experiments in volcanic tuffs." *Soil Sci. Soc. Am. J.* **58**(1). [225906]
- Jury, W.A., W.R. Gardner, and W.H. Gardner (1991). *Soil Physics*. (5th edition) New York, NY: John Wiley and Sons.
- Marshall, T.J., and J.W. Holmes (1992). *Soil Physics*. Cambridge: Cambridge University Press.
- Nitao, J.J., and T.A. Buscheck (1989). *Movement of a Liquid Front in an Unsaturated, Fractured Porous Medium. 1. Physical Theory*. (UCRL-101005) Livermore, CA: Lawrence Livermore National Laboratory.
- Philip, J.R. (1957). "Theory of infiltration: 1. The infiltration equation and its solution." *Soil Sci.* **83**:345–357. [NNA.19910820.0012]
- Richards, L.A. (1931). "Capillary conduction of liquids through porous mediums." *Physics*. **1**:318–333.
- Roberts, J.J., and W. Lin (1994). *Hydrological Property Measurements of Topopah Spring Tuff*. (UCRL-ID-119033) Livermore, CA: Lawrence Livermore National Laboratory. [MOL.19970804.0293]

- Travis, R.B., S.W. Hodson, H.E. Nuttall, T.L. Cook, and R.S. Rundberg (1984). *Preliminary Estimates of Water Flow and Radionuclide Transport in Yucca Mountain*. (LA-UR-84-40) Los Alamos, NM: Los Alamos National Laboratory.
- TRW (1997). *Ambient Characterization of the Drift-Scale Test Block*. (BADD00000-01717-5705-000001, Rev. 1) Las Vegas, NV: TRW Environmental Safety Systems, Inc., for the U.S. Department of Energy.
- Wilder, D.G. (1996). *Near-Field and Altered-Zone Environment Report, Volume II*. (UCRL-LR-124998, Vol. II) Livermore, CA: Lawrence Livermore National Laboratory. [MOL.19961212.0121; MOL.19961212.0122]
- Zimmerman, R.W., and G.S. Bodvarsson (1990). "Adsorption of water into porous blocks of various shapes and sizes." *Water Resources Res.* **26**:2797–2806.

Figure 7-1. Matric potential versus average saturation for 13 DST samples at 25.1°C. Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-2. Matric potential versus average saturation for 13 DST samples at 93.7°C. Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-3. Matric potential versus average saturation for 13 DST samples at 49.6°C. Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-4. Matric potential versus average saturation for 11 SHT samples at 25.1°C. Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-5. Matric potential versus average saturation for 11 SHT samples at 49.6°C. Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-6. Matric potential versus average saturation for 11 SHT samples at 93.7°C. Solid line indicates the wetting curve, and dashed line indicates drying curve. Point at 100% saturation is inferred.

Figure 7-7. Schematic of the experimental apparatus.

Figure 7-8. Typical response and control for the temperature and relative humidity in the sample chamber.

Figure 7-9. Typical sample-weight versus time for an isotherm.

Figure 7-10. Typical early time data selected for curve fitting to $w(t) = \text{Sat}1/2$.

Figure 7-11. Sorptivity coefficient vs. effective porosity for the T = 20°C isotherm (scatter plot).

Figure 7-12. Sorptivity coefficient vs. temperature. • is the average of all coefficients except that for Sample 15. The error bar is one standard deviation.

8. Relative Humidity and Barometric Pressure

by Stephen C. Blair

Relative humidity (*RH*) is an important parameter in assessing the performance of waste packages (WPs) and of the overall repository. In particular, drift *RH* above 85% is considered undesirable from the point of view of WP corrosion. During the first 6 months of the Drift-Scale Test (DST), *RH* in the heater drift (HD) has been monitored using two humidity sensors located in the HD about 1 m inside the bulkhead. The humidity sensors are considered to provide only qualitative information on humidity at temperatures greater than 50°C, because calibration facilities at temperatures >50°C were unavailable prior to installation. In addition, three pressure sensors are installed in the HD, at 0.4, 24, and 47 m from the bulkhead, to monitor barometric pressure.

RH data for the two *RH* sensors, along with barometric (air) pressure, are plotted in Figure 8-1. This plot shows that, upon the start of heating, humidity (*RH*) values dropped from approximately 30% to 15%, and have varied between approximately 10% and 25% over the 178 days of heating. This figure also shows that the *RH* data are inversely correlated with the air pressure in the drift.

Figure 8-1. Barometric pressure versus relative humidity for selected sensors.

After approximately 40 days of heating, condensation was observed on various spots on the drift wall outside of the bulkhead, and a puddle formed on the concrete floor in front of the bulkhead (see **Figure 8-2**). These wet conditions near the bulkhead alternated with drier conditions.

Figure 8-2. Photograph of condensation near the heater drift bulkhead.

The pressure data plotted in Figure 8-1 also indicate that a gradient in barometric pressure has developed over time within the HD, with pressure decreasing with distance from the bulkhead into the heated drift. The magnitude of the indicated pressure gradient is 3.4 kpa (0.5 psi) along the length of the drift (approximately 47 m). This apparent pressure difference is larger than the variation in barometric pressure observed during the DST and may be due to the effect of temperature on the instrumentation and wiring used to measure the pressure. The viability of this measurement should be assessed before pursuing a physical interpretation of the data.

Thermohydrologic (TH) simulations of the DST, discussed in Section 6, show that the TH behavior is sensitive to the properties attributed to the bulkhead. Moreover, the properties of the bulkhead needed for simulation, such as permeability and thermal conductivity, are poorly known. However, bulkhead temperature is being measured at nine locations (shown in **Figure 8-3**) and temperatures observed on the bulkhead since the start of heating are shown in **Figure 8-4**. This figure shows a wide variation in temperature response on the bulkhead since the start of heating. In particular, one thermocouple (TC) is much hotter than the others. This is TC-1, which is located at the top center of the bulkhead. Temperature at this location climbed rapidly after the start of heating and reached 100°C at about day 120. Figure 8-4 also shows that temperature at this location is approximately 30°C hotter than for

TC-6, TC-7 and TC-8, which are located nearby at the upper edges of the bulkhead at approximately the 10 o'clock and 2 o'clock positions. Temperatures at these locations are increasing at a roughly linear rate.

Figure 8-3. Location of nine thermocouples on the bulkhead inside the HD.

Figure 8-4. Bulkhead temperature.

Figure 8-4 shows relatively low and stable temperatures for TC-3 and TC-5, which are located along the bottom edge of the bulkhead near the sides. Data for these sensors indicate that the lower part of the bulkhead has remained at essentially ambient temperature for the first 178 days of the test. One exception is at the middle bottom edge of the bulkhead, where the temperature began to rise after 178 days of heating. Temperatures recorded for TC-2 and TC-9 are about 10°C lower than those for TC-6 through TC-8 and are steadily increasing with time.

Figure 8-4 also shows that temperatures for TC-2 and TC-6 through TC-9 vary by as much as 20°C over a period of a few days. The variation in bulkhead temperature seems to be correlated with barometric pressure, as shown in **Figure 8-5**. Most of these correlations are 180° out of phase, but some are in phase. This will be investigated when more data are available.

Figure 8-5. Bulkhead temperature and heater drift barometric pressure.

The change in the temperature field on the bulkhead during period of high and low barometric pressure is shown in **Figure 8-6**. This figure presents contour plots of the bulkhead temperatures on April 23 and April 26, 1998, prepared by applying a kriging algorithm to temperature data collected at the time of the barometric low on April 23 and the barometric high on April 26. Figure 8-6 shows a strong gradient in temperature from top to bottom of the bulkhead and a significant shift in the location of the isotherms with changes in barometric pressure. The temperatures appear to be constant at the top center, and at the lower corners, but the central region of the bulkhead warms or cools. Figure 8-6 also shows that, on April 23, low barometric pressure produced relatively higher bulkhead temperatures, and, on April 26, high barometric pressure depressed the temperatures. Preliminary analysis indicates that this pattern is typical of the changes in bulkhead temperature that occur associated with changes in barometric pressure.

Figure 8-6. Bulkhead temperature at times of high and low barometric pressure.

During the barometric-pressure highs, the gas in the HD is likely to be largely static; thus, mass transport during this time is slow and probably dominated by the binary diffusion of air into the HD through the bulkhead. This leads to a low *RH*. During periods of changing barometric pressure, air flow will be out of the drift, increasing the influx of moist air into the drift from the drift walls and increasing the *RH*. This moist air may primarily consist of the water that is being vaporized and driven from the rock as the rock dries out. Thus, if there are changing directions of vapor flow with barometric pressure, the formation of a condensate zone might be affected (particularly during the early times while the dryout zone is located closer to the drifts). Comparisons will be made with response as the boiling front moves further from the drift. Further analysis of this behavior will provide insight into moisture

transport associated with in-drift heating and will provide information valuable for assessment of the performance of a potential repository.

As mentioned previously, the two humidity sensors are located about 1 m from the bulkhead. To monitor *RH* as a function of distance from the bulkhead, two more HumicapsTM were installed in the heated drift on June 30, 1998, at distances of approximately 4 and 8 m from the bulkhead. The placement of these additional sensors is intended to help determine the existence of a gradient in *RH* into the HD away from the bulkhead.

Figure 8-1. Barometric pressure versus relative humidity for selected sensors. Pressure transducers (Pres-1, Pres-2, and Pres-4) are located 0.4, 24, and 47 m from the bulkhead, respectively. RH sensors (Hum-1 and Hum-2) are at about 1 m from the bulkhead.

Figure 8-2. Photograph of condensation near the heater drift bulkhead.

Figure 8-3. Location of nine thermocouples on the bulkhead inside the HD.

Figure 8-4. Bulkhead temperature.

Figure 8-5. Bulkhead temperature and heater drift barometric pressure.

Figure 8-6. Bulkhead temperature at times of high and low barometric pressure.

9. Evaluation of Sensors

by Stephen C. Blair

This section presents an evaluation of RTD performance through the first quarter of heating in the DST, corrections to sensor locations for Borehole 134, and suggested changes to data-channel assignments of a portion of the RTDs in Boreholes 79 and 80.

9.1 Failed and Suspect Sensors

Approximately 1860 RTDs were emplaced in the 28 boreholes used to monitor temperature. Thirty of these sensors (listed in **Table 9-1**) had failed or were giving readings considered unreliable as of February 28, 1998, a failure rate of approximately 1.6%. The performance of these sensors continues to be monitored. Questions about the reliability of other sensors are discussed in other sections of this report.

Table 9-1. RTDs suspected of malfunction.

Borehole name	RTD	Start of malfunction	Problem—Cause
ESF-HD-80-TEMP-2	46	12/3/97	Bad—shorted
ESF-HD-133-TEMP-3	64	12/3/97	Bad—shorted
ESF-HD-138-TEMP-6	32	12/3/97	Bad—shorted
ESF-HD-138-TEMP-6	40	12/10/97	
ESF-HD-138-TEMP-6	47	2/28/98	Over—range
ESF-HD-139-TEMP-7	31	2/10/98	Over—range
ESF-HD-141-TEMP-9	36	12/3/97	Over—range
ESF-HD-141-TEMP-9	40	2/28/98	Over—range
ESF-HD-141-TEMP-9	41	1/30/98	Low
ESF-HD-143-TEMP-11	24	2/28/98	Low
ESF-HD-143-TEMP-11	40	12/3/97	Over—range
ESF-HD-143-TEMP-11	42	2/28/98	Low
ESF-HD-143-TEMP-11	67	12/3/97	Over—range
ESF-HD-144-TEMP-12	33		
ESF-HD-158-TEMP-13	7	12/3/97	Bad—shorted
ESF-HD-161-TEMP-16	64	12/3/97	Low
ESF-HD-168-TEMP-21	28	12/3/97	Low
ESF-HD-168-TEMP-21	31		Bad—shorted
ESF-HD-168-TEMP-21	40	12/3/97	Low
ESF-HD-169-TEMP-22	5	1/30/98	Over—range
ESF-HD-169-TEMP-22	22	12/3/97	Low
ESF-HD-169-TEMP-22	29	12/3/97	Low
ESF-HD-169-TEMP-22	38	12/3/97	Low

Borehole name	RTD	Start of malfunction	Problem—Cause
ESF-HD-169-TEMP-22	2	12/3/97	Low
ESF-HD-170-TEMP-23	28	12/3/97	Low
ESF-HD-171-TEMP-24	53	12/3/97	Over—range
ESF-HD-172-TEMP-25	2	2/10/98	Over—range
ESF-HD-173-TEMP-26	42	12/3/97	Low
ESF-HD-175-TEMP-28	31	12/3/97	Low
ESF-HD-175-TEMP-28	34	12/3/97	Bad—shorted

9.2 Suggested Corrections for RTD Data

Borehole 79—This borehole was designed to be parallel to the HD. Survey data of the borehole show that it is actually dipping downward, and survey points are not available beyond +10 m past the bulkhead. The increase in temperature with depth in this borehole is consistent with the borehole dipping toward the plane of the wing heaters. The exact locations of the thermocouples in this borehole are not well known, and the data cannot be properly interpreted at this writing.

The see-saw nature of the data reported for RTDs 25–58 in this borehole is unphysical and suggests that, for these sensors, pairs of data values may be switched. Thus, the values reported for pairs of RTDs from 25 through 58 should be switched (i.e., switch values for 25/26, 27/28, . . . 57/58).

Borehole 80—Data-collection system temperature data for the first 24 RTDs in Borehole 80 exhibit an unphysical see-saw pattern that suggests that pairs of sensors may be switched (i.e., the location of the RTDs is correct, but the value reported for pairs of RTDs may be switched). Thus, the value reported for RTDs 1 and 2 should be switched. A similar situation exists for pairs of RTDs from 3 and 4 through 23 and 24. Data plotted in Figure 2-6 and Figure 2-8 (in the Temperature section) have been edited to reflect such a change. **Table 9-2** presents suggested revised assignments for the first 24 RTDs in Borehole 80.

Table 9-2. Revised datum assignments for Borehole 80.

Sensor number	Recommended datum
ESF-HD-80-TEMP2-RTD-1	RTD-2
ESF-HD-80-TEMP2-RTD-2	RTD-1
ESF-HD-80-TEMP2-RTD-3	RTD-4
ESF-HD-80-TEMP2-RTD-4	RTD-3
ESF-HD-80-TEMP2-RTD-5	RTD-6
ESF-HD-80-TEMP2-RTD-6	RTD-5
ESF-HD-80-TEMP2-RTD-7	RTD-8
ESF-HD-80-TEMP2-RTD-8	RTD-7
ESF-HD-80-TEMP2-RTD-9	RTD-10
ESF-HD-80-TEMP2-RTD-10	RTD-9

Sensor number	Recommended datum
ESF-HD-80-TEMP2-RTD-11	RTD-12
ESF-HD-80-TEMP2-RTD-12	RTD-11
ESF-HD-80-TEMP2-RTD-13	RTD-14
ESF-HD-80-TEMP2-RTD-14	RTD-13
ESF-HD-80-TEMP2-RTD-15	RTD-16
ESF-HD-80-TEMP2-RTD-16	RTD-15
ESF-HD-80-TEMP2-RTD-17	RTD-18
ESF-HD-80-TEMP2-RTD-18	RTD-17
ESF-HD-80-TEMP2-RTD-19	RTD-20
ESF-HD-80-TEMP2-RTD-20	RTD-19
ESF-HD-80-TEMP2-RTD-21	RTD-22
ESF-HD-80-TEMP2-RTD-22	RTD-21
ESF-HD-80-TEMP2-RTD-23	RTD-24
ESF-HD-80-TEMP2-RTD-24	RTD-23

Borehole 134—Original data for this borehole indicated that temperatures were lower at this location than for the other four vertical downward boreholes. Examination of the notebook documenting installation indicates that the coordinates submitted in the xyz documentation (Lin and Wagoner, 1998) are in error. Revised locations of RTDs in this borehole are presented in **Table 9-3**.

Table 9-3. Revised locations for RTDs in Borehole 134.

RTD	x	y	z
ESF-HD-134-TEMP4-RTD-1	0.74	2.73	-1.85
ESF-HD-134-TEMP4-RTD-2	0.74	2.73	-2.16
ESF-HD-134-TEMP4-RTD-3	0.74	2.73	-2.48
ESF-HD-134-TEMP4-RTD-4	0.73	2.73	-2.80
ESF-HD-134-TEMP4-RTD-5	0.73	2.74	-3.11
ESF-HD-134-TEMP4-RTD-6	0.73	2.74	-3.43
ESF-HD-134-TEMP4-RTD-7	0.73	2.74	-3.74
ESF-HD-134-TEMP4-RTD-8	0.73	2.74	-4.06
ESF-HD-134-TEMP4-RTD-9	0.73	2.74	-4.37
ESF-HD-134-TEMP4-RTD-10	0.73	2.74	-4.69
ESF-HD-134-TEMP4-RTD-11	0.72	2.74	-5.01
ESF-HD-134-TEMP4-RTD-12	0.72	2.74	-5.32
ESF-HD-134-TEMP4-RTD-13	0.72	2.74	-5.64
ESF-HD-134-TEMP4-RTD-14	0.72	2.74	-5.95
ESF-HD-134-TEMP4-RTD-15	0.72	2.74	-6.27

9. Evaluation of Sensors

RTD	x	y	z
ESF-HD-134-TEMP4-RTD-16	0.72	2.74	-6.58
ESF-HD-134-TEMP4-RTD-17	0.72	2.74	-6.9
ESF-HD-134-TEMP4-RTD-18	0.71	2.75	-7.22
ESF-HD-134-TEMP4-RTD-19	0.71	2.75	-7.53
ESF-HD-134-TEMP4-RTD-20	0.71	2.75	-7.85
ESF-HD-134-TEMP4-RTD-21	0.71	2.75	-8.16
ESF-HD-134-TEMP4-RTD-22	0.71	2.75	-8.48
ESF-HD-134-TEMP4-RTD-23	0.71	2.75	-8.79
ESF-HD-134-TEMP4-RTD-24	0.70	2.75	-9.11
ESF-HD-134-TEMP4-RTD-25	0.70	2.75	-9.43
ESF-HD-134-TEMP4-RTD-26	0.70	2.75	-9.74
ESF-HD-134-TEMP4-RTD-27	0.70	2.75	-10.06
ESF-HD-134-TEMP4-RTD-28	0.70	2.75	-10.37
ESF-HD-134-TEMP4-RTD-29	0.70	2.75	-10.69
ESF-HD-134-TEMP4-RTD-30	0.70	2.75	-11.00
ESF-HD-134-TEMP4-RTD-31	0.69	2.76	-11.32
ESF-HD-134-TEMP4-RTD-32	0.69	2.76	-11.64
ESF-HD-134-TEMP4-RTD-33	0.69	2.76	-11.95
ESF-HD-134-TEMP4-RTD-34	0.69	2.76	-12.27
ESF-HD-134-TEMP4-RTD-35	0.69	2.76	-12.58
ESF-HD-134-TEMP4-RTD-36	0.69	2.76	-12.9
ESF-HD-134-TEMP4-RTD-37	0.69	2.76	-13.21
ESF-HD-134-TEMP4-RTD-38	0.68	2.76	-13.53
ESF-HD-134-TEMP4-RTD-39	0.68	2.76	-13.85
ESF-HD-134-TEMP4-RTD-40	0.68	2.76	-14.16
ESF-HD-134-TEMP4-RTD-41	0.68	2.76	-14.48
ESF-HD-134-TEMP4-RTD-42	0.68	2.76	-14.79
ESF-HD-134-TEMP4-RTD-43	0.68	2.77	-15.11
ESF-HD-134-TEMP4-RTD-44	0.67	2.77	-15.42
ESF-HD-134-TEMP4-RTD-45	0.67	2.77	-15.74
ESF-HD-134-TEMP4-RTD-46	0.67	2.77	-16.06
ESF-HD-134-TEMP4-RTD-47	0.67	2.77	-16.37
ESF-HD-134-TEMP4-RTD-48	0.67	2.77	-16.69
ESF-HD-134-TEMP4-RTD-49	0.67	2.77	-17.00
ESF-HD-134-TEMP4-RTD-50	0.67	2.77	-17.32
ESF-HD-134-TEMP4-RTD-51	0.66	2.77	-17.63

RTD	x	y	z
ESF-HD-134-TEMP4-RTD-52	0.66	2.77	-17.95
ESF-HD-134-TEMP4-RTD-53	0.66	2.77	-18.27
ESF-HD-134-TEMP4-RTD-54	0.66	2.77	-18.58
ESF-HD-134-TEMP4-RTD-55	0.66	2.77	-18.90
ESF-HD-134-TEMP4-RTD-56	0.66	2.78	-19.21
ESF-HD-134-TEMP4-RTD-57	0.66	2.78	-19.53
ESF-HD-134-TEMP4-RTD-58	0.65	2.78	-19.84
ESF-HD-134-TEMP4-RTD-59	0.65	2.78	-20.16
ESF-HD-134-TEMP4-RTD-60	0.65	2.78	-20.79
ESF-HD-134-TEMP4-RTD-61	0.65	2.78	-21.11
ESF-HD-134-TEMP4-RTD-62	0.65	2.78	-21.42
ESF-HD-134-TEMP4-RTD-63	0.65	2.78	-21.74
ESF-HD-134-TEMP4-RTD-64	0.64	2.78	-22.05
ESF-HD-134-TEMP4-RTD-65	0.64	2.78	-22.37
ESF-HD-134-TEMP4-RTD-66	0.64	2.78	-22.69

Borehole 160—Temperature sensors RTD 27 and RTD 29 (located between 10 and 11 m depth in this borehole) do not follow the overall trend of the thermal profile of the borehole. It is possible that these sensors are reversed.

9.3 References

Lin, W., and J.L. Wagoner (1998). *DST As-Built TDIF, XYZ Coordinates of the Sensors in the Drift-Scale Test*. Milestone report for the CRWMS Management and Operating Contractor, U.S. Department of Energy. (UCRL-ID-129591) Livermore, CA: Lawrence Livermore National Laboratory. 9 p. [MOL.19980203.0221]