Report Title:

DOE/BC/14990--19

Application of Reservoir Characterization and Advanced Technology to
Improve Recovery and Economics in a Lower Quality Shallow Shelf San
Andres Reservoir

Report Type:

QUARTERLY

Reporting Period Start Date: 10/01/1997 End Date: 12/31/1997

Principal Author(s): Archie R. Taylor
T. Scott Hickman
James J. Justice

40/97

RECEIVED

JUL 2 / 1998

OSTI

Report Issue Date: 01/31/1998

DOE Award No.: DE- FC22 -94BC14990 -19

Submitting
Organization(s)

OXY USA Inc.
P.O. Box 50250
Midland Tx. 79710-0250

(1)

Name & Address

T.Scott Hickman and Associates
550 West Texas Street
Suite 950
Midland, Tx. 79701

(2)

Advanced Reservoir Technologies
P.O. Box 985
Addison, Tx. 75001-0985

(3)

(4)

MASTER *th*

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

(5)

DISCLAIMER

**Portions of this document may be illegible
electronic image products. Images are
produced from the best available original
document.**

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus or product, or represents that its use would not infringe privately owned rights. Reference to any specific commercial product, process or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government of any agency thereof.

OBJECTIVES

The Class 2 Project at West Welch was designed to demonstrate the use of advanced technologies to enhance the economics of improved oil recovery (IOR) projects in lower quality Shallow Shelf Carbonate (SSC) reservoirs, resulting in recovery of additional oil that would otherwise be left in the reservoir at project abandonment. Accurate reservoir description is critical to the effective evaluation and efficient design of IOR projects in the heterogeneous SSC reservoirs. Therefore, the majority of Budget Period 1 was devoted to reservoir characterization. Technologies being demonstrated include:

1. Advanced petrophysics
2. Three-dimensional (3-D) seismic
3. Cross-well bore tomography
4. Advanced reservoir simulation
5. Carbon dioxide (CO₂) stimulation treatments
6. Hydraulic fracturing design and monitoring
7. Mobility control agents

SUMMARY OF TECHNICAL PROGRESS

West Welch Unit is one of four large waterflood units in the Welch Field in the northwestern portion of Dawson County, Texas. The Welch Field was discovered in the early 1940's and produces oil under a solution gas drive mechanism from the San Andres formation at approximately 4800 ft. The field has been under waterflood for 30 years and a significant portion has been infill-drilled on 20-ac density. A 1982-86 pilot CO₂ injection project in the offsetting South Welch Unit yielded positive results. Recent installation of a CO₂ pipeline near the field allowed the phased development of a miscible CO₂ injection project at the South Welch Unit.

The reservoir quality at the West Welch Unit is poorer than other San Andres reservoirs due to its relative position to sea level during deposition. Because of the proximity of a CO₂ source and the CO₂ operating experience that would be available from

the South Welch Unit, West Welch Unit is an ideal location for demonstrating methods for enhancing economics of IOR projects in lower quality SSC reservoirs. This Class 2 project concentrates on the efficient design of a miscible CO₂ project based on detailed reservoir characterization from advanced petrophysics, 3-D seismic interpretations and cross wellbore tomography interpretations.

During the quarter, development of the project's south expansion area was undertaken, work was continued on interpreting the crosswell seismic data and CO₂ injection into 11 wells was initiated.

3-D SEISMIC INTEGRATION

Five new wells were drilled in the south expansion area with good results. Porosity values were close to that predicted by the seismic. The wells were about 15 feet lower than expected, indicating the structure falls off quicker than anticipated but the difference is within the error bands of the surface seismic. The additional wells may be drilled for water injection if subsequent production and completion data show the pressure support is needed.

CROSS WELL SEISMIC

In the fourth quarter, ART continued work on analyzing and developing processing procedures for interwell reflection data. Much of the effort focused on overcoming the increased complexity of data recorded with fixed source and moving receivers. One-half of each interwell reflection data set had to be recorded with this configuration during the data acquisition in Phase I. Processing improvements were applied to seven of the interwell lines acquired during Phase I work, extending the processed data over the entire span from source well to receiver well. Investigation continued into the complexities of reflective data from points lying very close to either source or receiver well. Such data suffers interference from the (very strong) direct transmission wave, which arrives almost simultaneously with the reflection data at receivers near the reflecting interface. A reliable solution is required to completely image interwell reflection data originating from reflection points in close proximity to either the source or receiver well. Some progress has been made on this problem.

The dominant frequency recorded in these data sets was on the order of 600 to 700 Hz, over interwell distances characteristic of many reservoirs. This points out the potential of this type of imaging for achieving detailed reservoir characterization studies. With good data, reliable ties can be established between the imaged reflection data in depth and the depth synthetics, derived from sonic logs available from wells at the study site. Spatial wavelengths of approximately 30 ft. provide the best ties, and correspond to the dominant frequency ranges (600 - 700 Hz) obtained in the recorded data (this is a high seismic velocity regime). A considerable effort was devoted to generating synthetics and tying them to the reflection data. The experienced gained so far will greatly improve the

acquisition and processing of the monitor surveys to be carried out in Phase II of the project.

NUMERICAL SIMULATION

During the fourth quarter, CO₂ injection operations began in the field. Actual injection rates were very close to the seismic-enhanced model predicted rates during this initial injection period. These rates are based on relative permeability curves with higher residual oil saturation to waterflood than used for the base geologic model. The higher residual oil results in higher oil recovery per pore volume than for higher quality reservoirs and could offset the delayed response time from marginal reservoirs. If actual oil production matches that forecasted by the seismic-enhanced model, it would demonstrate that the lower quality reservoirs can be successfully CO₂ flooded.

An additional investigation of the effect the fracture length has on oil recovery by CO₂ was started. The results from the 3D-fracture model have shown that 400-ft fracture lengths will grow the fracture out-of-zone. Procedures to keep the fracture from growing are available, but their practicality will depend on a comparison of the effect on performance between 400-ft fractures and shorter fractures.

AREA PREPARATION AND CONSTRUCTION

CO₂ injection began October 2, 1997 into 11 of the injection wells in Area 2 of the project. The other wells scheduled for CO₂ service were kept on water injection due to unexpected low reservoir pressure. The north row of injectors have not been converted to injection, pending the results of the drilling and possible extension of injection to the new wells in the south. Average CO₂ injection rates by month were:

October	2187 mscfd
November	3780 mscfd
December	4596 mscfd

Nineteen producing wells were worked over during the quarter. Workovers included; lowering pumps, installing tubing and gas anchors, cleanouts and reperforating.

Two-inch PVC flowlines are being replaced with 3-inch fiberglass lines to reduce future gas gathering problems. Ninety percent of the lines have been replaced with the remainder to be finished in January 1998.

TECHNOLOGY TRANSFER

George Watts presented the seismic guided mapping techniques¹ to the Society of Exploration Geophysicists at a workshop in Dallas during their annual meeting and international exposition November 2-7, 1997. Archie Taylor presented the integrated well

logging methods² at the DOE-sponsored logging symposium held in Midland, November 13, 1997.

Two papers covering the simulation work were submitted to the SPE Permian Basin Oil and Gas Recovery Conference for presentation in April 1998.

REFERENCES

1. Watts, G.P., Hinterlong, G.D. et al, "Seismic Estimate of Porosity in a Permian San Andres Carbonate Reservoir, Welch Field, Dawson County, Texas," March 1996 Proceedings: Oklahoma Geological Society Workshop on Platform Carbonates of the Southern Mid-continent.
2. G. D. Hinterlong and A. R. Taylor, "Combining Flow Theory and Multiple Log Readings to Improve Permeability Calculations", November 13, 1997 Proceedings: Advanced Applications of Wireline Logging for Improved Oil Recovery Workshop.

U.S. DEPARTMENT OF ENERGY
FEDERAL ASSISTANCE MANAGEMENT SUMMARY REPORT

Other Editions are Obsolete

OMB Burden Disclosure Statement

Public reporting burden for this collection of information is estimated to average 3.38 hours per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Office of Information Resources Management, AD-244 - GTN, Paperwork Reduction Project (1910-0400), U.S. Department of Energy, 1000 Independence Avenue, S.W., Washington, DC 20585; and to the Office of Management and Budget (OMB), Paperwork Reduction Project (1910-0400), Washington, DC 20503.

1. Program/Project Identification No. E-FC22-94BC14990	2. Program/Project Title "Application of Reservoir Characterization and Advanced Technology to Improve Recovery and Economics in a Lower Quality Shallow Shelf San Andres Reservoir"	3. Reporting period 10/1/97 through 12/31/97
Name and Address XY USA Inc. O Box 50250 Midland, Tx 79710-0250		5. Program/Project Start Date 8/3/95
		6. Completion Date 9/30/2000

2. Remarks Budget period 2 tasks were separated to make tracking easier.
Project area expansion was approved for drilling up to 14 wells. 5 wells were drilled in the 4th quarter.

3. Signature of Recipient and Date

14. Signature of U.S. Department of Energy (DOE) Reviewing Representative and Date