OCT 29 1998

ENGINEERING DATA TRANSMITTAL

Page 1 of 1
1. EDT **618220**

2. To: (Receiving Organization) Tank Farms Facility Operations	3. From: (Originating Organization) SST Engineering	4. Related EDT No.: N/A
5. Proj./Prog./Dept./Div.: TWRS	6. Design Authority/ Design Agent/Cog. Engr.: DW Reberger	7. Purchase Order No.: N/A
8. Originator Remarks: This DST Emergency Pumping Guide was prepared in response to WDOE's July 8, 1998 SY Tank Farm Notice of Correction. The report is formatted similarly to the SST Emergency Pumping Guide and has a similar level of detail as the SST Guide.		9. Equip./Component No.: DST
		10. System/Bldg./Facility: AN, AP, AW, AY, AZ, SY
		11. Receiver Remarks: 11A. Design Baseline Document? ☐ Yes ☒ No
		12. Major Assm. Dwg. No.: N/A
		13. Permit/Permit Application No.: N/A
		14. Required Response Date: 28 Oct 1998

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Approval Design- nator	Reason for Trans- mittal	Origi- nator Dispo- sition	Receiv- er Dispo- sition
1	HNF-3484		0	Double-Shell Tank Emergency Pumping Guide	N/A	2	1	1

16. KEY

Approval Designator (F)	Reason for Transmittal (G)	Disposition (H) & (I)
E, S, G, D or N/A (See WHC-CM-3-5, Sec.12.7)	1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION
(See Approval Designator for required signatures)

(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN
		Design Authority				2	1	RW Reed co-author		10/27/98	74-07
		Design Agent				2	1	MH Brown co-author		10/27/98	74-07
2	1	Cog. Eng. DW Reberger		10/28/98	55-13	2	1	RE Larson SY Cog Mgr		10/27/98	74-07
2	1	Cog. Mgr. DG Baide		10/28/98	55-05	2	1	MJ Sutey		10/28/98	55-07
		QA									
		Safety									
		Env.									

18. RW Reed Signature of EDT Originator Date 10/27/98	19. RP Tank Authorized Representative Date 10/27/98	20. RE Larson Design Authority/ Cognizant Manager Date 10/27/98	21. DOE APPROVAL (if required) Ctrl. No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments
--	---	--	---

DOUBLE-SHELL TANK EMERGENCY PUMPING GUIDE

MH Brown
RW Reed

Lockheed Martin Hanford Company, Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-96RL13200

EDT/ECN: 618220 UC: 2020
Org Code: 74800 Charge Code: 106673 BC20
B&R Code: EW3130010 Total Pages: 43-44
87-11-15

Key Words: Double-Shell Tank, Emergency, Pumping, Guide, Secondary Containment, Annulus, Leak

Abstract: This Double-Shell Tank Emergency Pumping Guide provides the preplanning necessary to expeditiously remove any waste that may leak from the primary tank to the secondary tank for Hanford's 28 DSTs. The strategy is described, applicable emergency procedures are referenced, and transfer routes and pumping equipment for each tank are identified.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

Release Approval Date

Approved for Public Release

DOUBLE-SHELL TANK EMERGENCY PUMPING GUIDE

Prepared for the United States Department of Energy

Lockheed Martin Hanford Corporation
P. O. Box 1500
Richland, Washington 99352

TABLE OF CONTENTS

1	GENERAL INFORMATION	3
1.1	Purpose, Scope, and Background	3
1.2	Summary of Information Provided	3
1.3	Watch-List Tanks	4
2	EQUIPMENT DESCRIPTION	5
2.1	Primary Tank Configuration	6
2.2	Secondary Containment Configuration	7
2.3	Support Systems	7
3	PLAN OF ACTION	8
3.1	Regulatory Requirements Applicable to Leaking Double-Shell Tanks	8
3.2	General Strategy	8
3.3	Potential Leak Scenarios	9
3.3.1	Strategy for Emergency Pumping after a Minor Leak	10
3.3.2	Strategy for Emergency Pumping after a Moderate or Major Leak	11
3.4	Responsibilities	12
3.5	Major Activities	12
3.5.1	Pre-Emergency Pumping Planning Activities	12
3.5.2	Check Waste Characterization and Compatibility	12
3.5.3	Review/Prepare Safety Documentation	13
3.5.4	Ensure Equipment Readiness	13
3.6	Estimated Time To Start Pumping Tanks	13
4	REFERENCES	14

APPENDIX A - PROPOSED PRIMARY AND ALTERNATE TRANSFER ROUTES

APPENDIX B - LIST OF IMPLEMENTING PROCEDURES AND RELEVANT DRAWINGS

APPENDIX C - IDENTIFICATION AND LOCATION OF DST PUMPS AND JUMPERS THAT WOULD BE USED FOR EMERGENCY PUMPING

1 GENERAL INFORMATION

1.1 Purpose, Scope, and Background

The purpose of this plan is to provide as much preplanning as practical for pumping waste out of the annulus or secondary containment, of Double-Shell Tanks (DST). If the primary tank leaks, waste would accumulate in the secondary tank. For the purposes of this report, the terms "secondary tank" and "annulus" are used interchangeably. The preplanning will expedite emergency pumping and provide the basis for demonstrating that the leaked waste will be "removed from the secondary containment system within 24 hours, or in as timely a manner as is possible" as required by the Washington Administrative Code.

There are 177 large underground waste storage tanks in the Hanford 200 East and 200 West Areas. There are 149 single-shell tanks (SSTs), and 28 DSTs. The scope of this plan includes all 28 of the Hanford DSTs in AN, AP, AW, AY, AZ, and SY Tank Farms. The scope also includes the transfer lines, pump pits, valve pits, jumpers, transfer pumps, sump pumps, and procedures necessary to accomplish the emergency pumping.

1.2 Summary of Information Provided

This guide contains a general description of the DSTs, and discussions of the requirements, strategy, transfer routes, procedures, and equipment that will be used to expeditiously respond to a leaking DST. References to statutory requirements are included. Information for each DST about the waste transfer routes, procedures, and equipment required for the transfers are contained or referenced in the appendices. These include:

Appendix A: PROPOSED TRANSFER ROUTES.

Contains a tabulated summary description of the proposed transfer route for each DST. Routes are included for transferring the waste from the annulus back to the primary tank, and then from the primary tank to the designated receiver tank. Tank AP-104 is the designated receiver tank, and AP-103 is the alternate receiver tank, for emergency transfers from all DSTs, except from the aging waste tanks AZ-101 and AZ-102. The designated and alternate receiver tanks for emergency transfers from AZ-101 and AZ-102 are AY-101 and AY-102 respectively.

Appendix B: IMPLEMENTING PROCEDURES AND RELAVANT INFORMATION.

Contains a list of applicable transfer operating procedures and a list of Piping and Instrumentation Drawings (P&ID) for each DST farm.

Appendix C: INVENTORY AND STATUS OF REQUIRED EQUIPMENT.

Contains a list of equipment that would be used to transfer waste out of a leaking DST.

1.3 Watch-List Tanks

In response to Public Law 101-510, Section 3137, "Safety Measures for Waste Tanks at Hanford Nuclear Reservation," six DSTs are identified as Hydrogen/Flammable Gas Watch-List Tanks. The tanks are: AN-103, AN-104, AN-105, AW-101, SY-101, and SY-103. These tanks are suspected to have a significant potential for hydrogen/flammable gas generation, entrapment, and episodic release. Operating Specifications Document (OSD) OSD-T-151-00030 "Operating Specifications for Watch-List Tanks" requires that written approval must be obtained from Nuclear Safety and from DOE prior to transferring waste out of these six tanks. The OSD also requires written approval by the Secretary of Energy prior to transfer of waste into these six tanks. Because the Watch-List safety issues are a subject of ongoing research, the criteria for managing these tanks will continue to evolve. Therefore, a thorough evaluation of applicable requirements will need to be done at the time a leak is identified.

2 EQUIPMENT DESCRIPTION

Figure 1 - Typical DST Configuration

All DSTs are similar in design and each has capacity of approximately 3.8 million Liters, (L) (1 million gal.). Slight differences in the tank and ancillary equipment, however, have occurred over the years from design improvements and because of the need to accommodate variations in waste composition. Twenty-eight DSTs are located in six farms, five farms in 200 East Area and one farm in 200 West Area. DSTs consist of a carbon steel primary tank and a carbon steel secondary tank encased by a protective reinforced concrete shell. The tanks contain a mixture of liquid, sludge, and salt cake waste with both radioactive and chemically toxic hazardous constituents. Liquids exist as supernatant (liquid above solids) and interstitial liquid (liquid filling the voids between solids) in the tanks. Sludge consists primarily of solids (hydrous metal oxides) precipitated by the neutralization of acid wastes. Salt cake, generally between the supernatant and sludge, consists of the various salts formed by the evaporation of water from the waste. These waste types do not necessarily exist as distinct layers and may be intermingled to differing degrees. Some sludges and salt cakes contain interstitial liquid and are relatively soft; others may be drier and harder.

Each tank is equipped with riser pipes that penetrate the concrete dome and the top of the primary or secondary tank. The risers provide access to the primary tank and to the annulus space for waste transfer operations, equipment installation or use, and monitoring. Most risers extend above grade. However, some risers are located under covered pits (e.g., Central Pump Pits, Annulus Pump Pits).

Pits provide access from the surface to process piping and tank risers and are the points where jumper (temporary piping systems), pumps, and other equipment are

installed to establish waste transfer routes. A rigid jumper is a steel pipe that is fitted to specific wall nozzle configurations. The flexible jumpers are braided, stainless steel, flexible hose that permit connections to multiple wall nozzles.

There are three types of pumps used at TWRS to transfer waste into and out of DSTs. The types are: (1) jet pumps in combination with centrifugal pumps, with nominal capacities of 0.05 to 4.0 gpm, (2) submersible pumps, with nominal capacities of 10 to 30 gpm and (3) transfer pumps, with nominal capacities of 100 to 250 gpm.

The components of a jet pump system located within a pump pit are a centrifugal pump, flexible or rigid jumpers, a flush line, and a flow totalizer. The centrifugal pump supplies motive fluid to the submerged jet pump system. Jet pumps are used to move liquid at very low rates.

A submersible pump can be used to raise large volumes of supernatant. The pump motor is below the pump intake and is submersed in the liquid being pumped.

Transfer pumps are typically installed in a pump pit, with the motor located in the pit and the intake located in the tank waste. Transfer pumps are normally deep-well, vertical turbine pumps, where the pump intake is a rigid pipe that extends to a fixed depth in the tank waste. Some transfer pumps have a floating intake, which is a flexible jumper connected to rigid pipe that does not extend into the waste.

2.1 Primary Tank Configuration

All DSTs have a Central Pump Pit which is approximately centered over the primary tank. The primary function of the pit is to provide confinement for a possible spray leak during waste transfers and to provide radiation shielding during waste transfers. The Central Pump Pits provide for access to the tank for supernatant filling or removal, slurry distribution, and mixing. Supernatant filling is accomplished through piping or jumpers connected to the riser. For supernatant removal, Central Pump Pits are designed to hold a deep-well turbine pump and piping or jumpers. Central Pump Pits for receiver tanks that store slurry are equipped with slurry distributors. The jumpers installed in the Central Pump Pit are either rigid or flexible jumpers. Transfer pumps are normally used to remove large volumes of supernatant. Jet pumps would be used to remove interstitial liquid because the liquid drains out of the sludge interstices too slowly to employ the transfer pumps. Before a jet pump system can be used to pump interstitial liquid, a stainless steel, salt screen must be installed in the waste to prevent solids from plugging the jet intakes.

2.2 Secondary Containment Configuration

The Annulus Pump Pit is located directly above the annulus and is connected to the annulus by a riser. The pit and riser provide access for pumping out any liquids that may accumulate in the annulus. In most instances, deep-well vertical turbine pumps will be installed as needed in Annulus Pump Pits, and there is just one pump per tank farm that will be moved between the tanks within that farm. The pump is lowered into position after a riser cover is removed. A rigid or flex jumper assembly connects the pump outlet to a 51-mm (2-in) process waste line enclosed in a 102-mm (4-in) encasement. The encasement drains to the Annulus Pump Pit. The process waste line terminates at the Central Pump Pit of the tank. A jet pump could be used, to remove the small amount of liquids around the bottom of the annular space.

2.3 Support Systems

Virtually all of the equipment and support systems that would be used for emergency pumping of DSTs are existing and are in nominal serviceable condition. There may be occasions where it would be necessary or practical to use a Jet Pump to remove waste, or drainable liquid, from the annulus of a leaking DST. In that case, equipment dedicated for emergency pumping of Single-Shell Tanks (SST) would be employed. That equipment consists of a jet pump, jumper, pumping and instrumentation control skid, flammable gas monitor, and over-ground piping. The TWRS Stabilization Program stages and stores this emergency pumping equipment for SSTs in HO-64-05192. See HNF-SD-WM-AP-005 *"Single-Shell Tank Leak Emergency Pumping Guide"* for details.

3 PLAN OF ACTION

3.1 Regulatory Requirements Applicable to Leaking Double-Shell Tanks

40CFR, Part 265.193 (c)(4) Containment and detection of releases.

"...Sloped or otherwise designed or operated to drain and remove liquids resulting from leaks, spills, or precipitation. Spilled or leaked waste and accumulated precipitation must be removed from the secondary containment system within 24 hours, or in as timely a manner as is possible to prevent harm to human health or the environment, if removal of the released waste or accumulated precipitation cannot be accomplished within 24 hours."

WAC 173-303-640 (4)(iv) Tank systems.

"...Sloped or otherwise designed or operated to drain and remove liquids resulting from leaks, spills, or precipitation. Spilled or leaked waste and accumulated precipitation must be removed from the secondary containment system within twenty-four hours, or in as timely a manner as is possible to prevent harm to human health and the environment, if the owner or operator can demonstrate to the department that removal of the released waste or accumulated precipitation cannot be accomplished within twenty-four hours."

3.2 General Strategy

The general strategy for emergency pumping a leaking DST is based on several assumptions. The more significant assumptions are:

- Tank AP-104 is the designated receiver tank for all DST emergency pumping, except the AZ aging waste tanks. The designated receiver tank for aging waste will be AY-101.
- Tank AP-104 is and will be virtually empty. [NOTE: As of October 1998, Tank AP-104 contained a heel of about 30,000 gallons.]
- Waste compatibility will not be an issue that causes a delay in the pumping.
- Tank AP-103 will be the alternate receiver tank in the event that AP-104 is not available or suitable for receiving an emergency transfer. Tank AY-102 will be the alternate receiver tank for aging waste from AZ farm.
- To the maximum extent possible, existing double-contained, underground transfer lines will be used.
- Existing transfer pumps in the DST Central Pump Pits will be used to pump waste out of the primary tank.
- Existing annulus pumps in the DST farm will be used to pump waste out of the annulus back to the primary tank.
- The Saltwell Jet Pump and Emergency SST Skid may be used to remove waste from the primary and annulus.
- Leaks from SY-101 and SY-103 could be pumped to SY-102.

3.3 Potential Leak Scenarios

The regulations require removing "Spilled or leaked waste and accumulated precipitation ... from the secondary containment system within twenty-four hours, or in as timely a manner as is possible to prevent harm to human health and the environment, if the owner or operator can demonstrate to the department that removal of the released waste or accumulated precipitation cannot be accomplished within twenty-four hours." In most cases the nature of the leak will make a 24-hour response impossible.

The best strategy for emergency pumping of a specific DST to "prevent harm to human health and the environment" will depend upon the rate or size of leak from the primary tank and upon whether the tank is a Watch-List tank. For purposes of this plan, leak scenarios are divided into three classes based upon the rate of the leak. The Minor Leak is treated separately, because pumpable quantities of waste are likely to be slow to accumulate. Moderate and Major Leaks are treated together, because the emergency response to them would be the same in either case.

3.3.1 Strategy for Emergency Pumping after a Minor Leak

Scenario: Primary steel tank corrosion causes small breach. Waste dribbles into annulus and the annulus leak detection alarms. Leak rate is so slow that the dried waste will form on the side of tank. The liquid in bottom of annulus occurs very slowly that accumulation could potentially be over period of weeks or months if at all. See Figure 1 for schematic depiction of minor leak.

Figure 1. Schematic Diagram of Minor Leak

OBJECTIVE: Pump waste out of annulus within 24 hours or as timely as possible.

STRATEGY: Begin pumping primary tank contents via existing underground supernatant transfer pipelines with the existing transfer pump already installed the Central Pump Pit. In parallel, install and prepare an annulus pump, if one is not already installed, and visually inspect annulus to determine location of leak. Continue pumping the primary tank until the waste level is sufficiently below the leak path to accommodate adding the volume of waste in the annulus without rising above the leak path. When, and if, pumpable quantities of liquid accumulate in the annulus, pump annulus contents back to primary tank.

BENEFITS OF STRATEGY: For minor leaks this strategy minimizes the amount of waste that will be leaked to the annulus by using transfer pumps and pipelines already installed and serviceable to lower the waste level in the primary tank. If pumpable quantities accumulate in the annulus, they will be removed as expeditiously as possible.

Once the primary tank waste level has been lowered below the leak path, and any pumpable quantities of waste in the annulus are removed, the emergency nature of the transfers can be downgraded and a permanent resolution determined. Removing as much of the waste as possible in a non-emergency mode is more likely to prevent harm to human health or the environment, than pumping all of the tank's contents in an emergency mode.

3.3.2 Strategy for Emergency Pumping after a Moderate or Major Leak

Scenario: A moderate or major leak occurs in primary steel tank somewhere below the waste level. The waste levels in the primary tank and the secondary tank equilibrate within hours or days. See Figure 2 for schematic depiction of a moderate to major leak.

Figure 2. Schematic Diagram of Major Leak in Double-Shell Tank

OBJECTIVE: Pump waste out of annulus within 24 hours or as timely as possible.

STRATEGY: Begin pumping primary tank via existing underground supernatant transfer pipelines with the transfer pump installed in the leaking tank's Central Pump Pit. Monitor levels and material balances in primary tank to determine elevation of leak path on the sidewall or bottom of primary tank. In parallel with pumping of primary tank, install and prepare annulus pump. Monitoring and controlling the waste level in the annulus with respect to the waste level in the primary tank is important to prevent buoyant forces from floating the primary tank.

Once primary tank waste level is below the leak path, begin pumping waste from the annulus back to the primary tank via existing underground transfer lines from the Annulus Pump Pit to the Central Pump Pit. From the Central Pump Pit, the waste could be routed back to the primary tank. Since the primary tank transfer pumps have capacities equal or greater to the capacity of the annulus pumps, no additional waste will leak to the annulus.

For leaking DSTs that do not have an installed primary transfer pump, an annulus pump would be installed. The annulus pump would be used to pump waste from the annulus to the Central Pump Pit. Instead of directing the waste back to the primary tank there, the route would be jumpered through the Central Pump Pit to the same route used for transferring waste from the primary tank to the designated receiver tank.

BENEFITS OF STRATEGY: Most DSTs have primary transfer pumps installed. This strategy uses transfer pumps and pipelines already installed and serviceable so that

pumping could be initiated more quickly. The leak will be stabilized faster and the portion of the annulus above the leak path will be pumped faster by using the higher capacity primary tank transfer pump than by using the annulus pump.

The waste in the annulus would be directed back to the primary tank where it would be pumped to the designated or alternate receiver tank via the established transfer route as necessary. This approach avoids having to modify the transfer procedure, or having to set up and arrange additional equipment and jumpers. Once the location of the leak is determined and the annulus is pumped, the emergency nature of the transfer could be downgraded. The waste remaining in the non-leaking portion of the tank could be left in the tank or pumped to some other tank, depending upon the best solution under the circumstances. Removing as much of the waste as possible in a non-emergency mode is more likely to prevent harm to human health or the environment, than pumping all of the tanks contents in an emergency mode.

If the leak path is near the bottom of the tank, then this approach will result in removing waste from the annulus in the most timely manner because the highest capacity pump and transfer routes are employed.

3.4 Responsibilities

The responsibilities for various actions and activities associated with emergency pumping are detailed in the specific emergency pumping procedures. See Appendix B. Because a leaking tank may constitute both a safety issue and an environmental issue, the emergency response must be planned in cooperation with the Richland Office of the DOE (RL), and the Washington State Department of Ecology, and the Washington State Department of Health.

3.5 Major Activities

3.5.1 Pre-Emergency Pumping Planning Activities

- Hold a kick-off meeting to bring together all required participants to assign responsibilities and action items necessary to initiate pumping.
- Walk-down facility to identify needed repairs, or scheduled maintenance that may need to be accelerated.
- Review applicable operating and emergency transfer procedures and validate for specific conditions or circumstances if necessary.

3.5.2 Check Waste Characterization and Compatibility

Before waste is transferred, compatibility tests or assessments are performed on the waste in both the supply and receiver tanks to ensure that undesirable chemical

reactions do not occur. The document "Data Quality Objectives for the Waste Compatibility Program" (HNF-SD-WM-DQO-001, Rev. 0) discusses the criteria used to assess the compatibility of wastes before they are mixed. Most of the transfers discussed in this plan involve moving waste only to TK-104-AP, which contains roughly 30,000 gallons of a very dilute waste that should pose no compatibility problems.

Transfers of waste from the six DST Watch-List tanks, require special approvals per OSD-T-151-00030.

In preparation for final waste retrieval, there is an ongoing Characterization Program within TWRS to fully document the chemical and physical characteristics of the waste stored in each tank. This data will be used if available.

3.5.3 Review/Prepare Safety Documentation

All provisions of HNF-SD-WM-BIO-001, HNF-SD-WM-TSR-006 must be met during emergency pumping activities. The requirements of OSD-T-151-00030 would be met if a DST Watch-List tank is involved.

Provisions of Occupational Safety and Health procedures, Radiation Protection Procedures, and Tank Farm Health and Safety Plan, apply to all work performed. Health Physics shall assist in issuing special Radiation Work Permits as needed to safely perform the tasks required preparing pumping for the DST.

The emergency pumping procedures (See Appendix B) will be preapproved and will have unreviewed safety question (USQ) screening/determinations completed to assure that emergency pumping can be executed within the existing Authorization Basis. The USQ procedure is defined in the TWRS Administration Manual HNF-IP-0842, Volume IV, Section 5.4.

3.5.4 Ensure Equipment Readiness

Confirm proposed transfer route, destination of the waste, heat trace operability. A proposed transfer route for each tank is identified in Appendix A.

Obtain and install necessary jumpers in valve pits, if required. Ensure availability and readiness of transfer pumps.

3.6 Estimated Time To Start Pumping Tanks

Pumping of a leaking tank would begin upon establishment of a transfer route, installation of pumping equipment, as needed and validation of a transfer procedure. To the extent practical, all equipment and documentation necessary to perform emergency transfers from the primary and secondary tanks of the DSTs have been prepared ahead of time.

4 REFERENCES

40CFR, Part 265.193 (c)(4) "Containment and detection of releases."

HNH-IP-0842, TWRS Administration Manual, Volume IV, Section 5.4. "Unreviewed Safety Questions."

HNH-SD-WM-AP-005 "Single-Shell Tank Leak Emergency Pumping Guide."

HNH-SD-WM-DQO-001, Rev. 0, "Data Quality Objectives for the Waste Compatibility Program."

HNH-SD-WM-TSR-006, "Tank Waste Remediation System Technical Safety Requirements."

HNH-SD-WM-BIO-001, "Tank Waste Remediation System Basis for Interim Operation."

OSD-T-151-00030, "Operating Specifications for Watch-List Tanks."

Public Law 101-510, Section 3137, "Safety Measures for Waste Tanks at Hanford Nuclear Reservation."

Tank Farm Health & Safety Plan

WAC 173-303-640 (4)(iv) "Tank systems."

WHC-SP-1137, "Preventative Maintenance Plan for Emergency Pumping Trailers."

WHC-SD-WM-OTP-027, "Jet-Pump Jumper Pressure Test."

APPENDIX A
PROPOSED PRIMARY AND ALTERNATE TRANSFER ROUTES

HNF-3484 Rev. 0
APPENDIX A

The proposed transfer routes described below are for the emergency pumping of the primary tanks. The proposed route for emergency pumping of the annulus will be from the Annulus Pump Pit through rigid/flex jumpers to a double encased below grade pipeline back to the Central Pump Pit, and then from the Central Pump Pit back to the primary tank via the tank return. 241-AY is the only exception with the below grade pipeline tying-in to a primary tank riser. This is typical for all tanks except the AY tanks. Tanks AY-101 and AY-102 have a below grade pipeline that ties directly to a primary tank riser, which eliminates the need to go through the Central Pump Pit.

241-AN TANKS TO 241-AP-104

TK-101-AN Primary Transfer Route	
241-AN 01A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 261
241-AN-B Valve Pit	Nozzle R15 through Flex/Rigid Jumper to Nozzle R2 via E to Line SN 260
241-AZ-02B Pump Pit	Nozzle U7 through Flex Jumper to Nozzle U5 to Line SN 600
241-AX-A Valve Pit	Nozzle L16 through Flex Jumper to Nozzle L1 to Line SN 214/201
241-A-A Valve Pit	Nozzle L1 through Rigid Jumper to Nozzle L2 to Line SN 220
241-AW-A Valve Pit	Nozzle L2 through Flex/Rigid Jumper to Nozzle L1 via D to Line SN 267
241-AW-02A Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumpers to Nozzle 20 via P, M, H, & J to Line SN 614
TK 104 AP-04A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-102-AN Primary Transfer Route	
241-AN 02A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 262
241-AN-B Valve Pit	Nozzle R16 through Flex/Rigid Jumper to Nozzle R2 via E to Line SN 260
Same as 101-AN to AP-104	

HNF-3484 Rev. 0
APPENDIX A

TK-103-AN Primary Transfer Route	
241-AN 03A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 263
241-AN-B Valve Pit	Nozzle R14 through Flex/Rigid Jumper to Nozzle R2 via E to Line SN 260
Same as 101-AN to AP-104	
TK-104-AN Primary Transfer Route	
241-AN 04A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 264
241-AN-A Valve Pit	Nozzle L15 through Flex/Rigid Jumper to Nozzle L19 via D to Line SN 268
241-AN-B Valve Pit	Nozzle R19 through Rigid Jumper to Nozzle R2 to Line SN 260
Same as 101-AN to AP-104	
TK-105-AN Primary Transfer Route	
241-AN 05A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 265
241-AN-A Valve Pit	Nozzle L16 through Flex/Rigid Jumper to Nozzle L19 via D to Line SN 268
241-AN-B Valve Pit	Nozzle R19 through Rigid Jumper to Nozzle R2 to Line SN 260
Same as 101-AN to AP-104	
TK-106-AN Primary Transfer Route	
241-AN 06A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 266
241-AN-A Valve Pit	Nozzle L14 through Flex/Rigid Jumper to Nozzle L19 via D to Line SN 268
241-AN-B Valve Pit	Nozzle R19 through Rigid Jumper to Nozzle R2 to Line SN 260
Same as 101-AN to AP-104	

241-AN TANKS TO 241-AP-103

TK-101-AN Alternate Transfer Route	
241-AN 01A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 261
241-AN-B Valve Pit	Nozzle R15 through Flex/Rigid Jumper to Nozzle R2 via E to Line SN 260
241-AZ-02B Pump Pit	Nozzle U7 through Flex Jumper to Nozzle U5 to Line SN 600
241-AX-A Valve Pit	Nozzle L16 through Flex Jumper to Nozzle L1 to Line SN 214/201
241-A-A Valve Pit	Nozzle L1 through Rigid Jumper to Nozzle L2 to Line SN 220
241-AW-A Valve Pit	Nozzle L2 through Flex/Rigid Jumper to Nozzle L1 via D to Line SN 267
241-AW-02A Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumpers to Nozzle 17 via P, M, &H to Line SN 613
TK 103 AP-03A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-102-AN Alternate Transfer Route	
241-AN 02A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 262
241-AN-B Valve Pit	Nozzle R16 through Flex/Rigid Jumper to Nozzle R2 via E to Line SN 260
Same as 101-AN to AP-103	
TK-103-AN Alternate Transfer Route	
241-AN 03A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 263
241-AN-B Valve Pit	Nozzle R14 through Flex/Rigid Jumper to Nozzle R2 via E to Line SN 260
Same as 101-AN to AP-103	

HNF-3484 Rev. 0
APPENDIX A

TK-104-AN Alternate Transfer Route	
241-AN 04A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 264
241-AN-A Valve Pit	Nozzle L15 through Flex/Rigid Jumper to Nozzle L19 via D to Line SN 268
241-AN-B Valve Pit	Nozzle R19 through Rigid Jumper to Nozzle R2 to Line SN 260
Same as 101-AN to AP-103	
TK-105-AN Alternate Transfer Route	
241-AN 05A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 265
241-AN-A Valve Pit	Nozzle L16 through Flex/Rigid Jumper to Nozzle L19 via D to Line SN 268
241-AN-B Valve Pit	Nozzle R19 through Rigid Jumper to Nozzle R2 to Line SN 260
Same as 101-AN to AP-103	
TK-106-AN Alternate Transfer Route	
241-AN 06A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 266
241-AN-A Valve Pit	Nozzle L14 through Flex/Rigid Jumper to Nozzle L19 via D to Line SN 268
241-AN-B Valve Pit	Nozzle R19 through Rigid Jumper to Nozzle R2 to Line SN 260
Same as 101-AN to AP-103	

241-AP TANKS TO 241-AP-104

TK-101-AP Primary Transfer Route	
241-AP-01A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 611
241-AP Valve Pit	Nozzle 18 through to Nozzle 20 via J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-102-AP Primary Transfer Route	
241-AP 02A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 612
241-AP Valve Pit	Nozzle 19 through to Nozzle 20 to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-103-AP Primary Transfer Route	
241-AP 03A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 613
241-AP Valve Pit	Nozzle 17 through to Nozzle 20 to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-105-AP Primary Transfer Route	
241-AP 05A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 615
241-AP Valve Pit	Nozzle 24 through to Nozzle 20 via K, D, C, N, P, M, H, & J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-106-AP Primary Transfer Route	
241-AP 06A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 616
241-AP Valve Pit	Nozzle 21 through to Nozzle 20 via D, C, N, P, M, H, & J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)

HNF-3484 Rev. 0
APPENDIX A

TK-107-AP Primary Transfer Route	
241-AP 07A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 617
241-AP Valve Pit	Nozzle 23 through to Nozzle 20 via K, D, C, N, P, M, H, & J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-108-AP Primary Transfer Route	
241-AP 08A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 618
241-AP Valve Pit	Nozzle 22 through to Nozzle 20 via D, C, N, P, M, H, & J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)

241-AP TANKS TO 241-AP-103

TK-101-AP Alternate Transfer Route	
241-AP-01A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 611
241-AP Valve Pit	Nozzle 18 through to Nozzle 17 to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-102-AP Alternate Transfer Route	
241-AP-02A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 612
241-AP Valve Pit	Nozzle 19 through to Nozzle 17 via J to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-104-AP Alternate Transfer Route	
241-AP-04A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 614
241-AP Valve Pit	Nozzle 20 through to Nozzle 17 via J to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-105-AP Alternate Transfer Route	
241-AP-05A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 615
241-AP Valve Pit	Nozzle 24 through to Nozzle 17 via K, D, C, N, P, M, & H to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-106-AP Alternate Transfer Route	
241-AP-06A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 616
241-AP Valve Pit	Nozzle 21 through to Nozzle 17 via D, C, N, P, M, & H to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)

HNF-3484 Rev. 0
APPENDIX A

TK-107-AP Alternate Transfer Route	
241-AP-07A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 617
241-AP Valve Pit	Nozzle 23 through to Nozzle 17 via K, D, C, N, P, M, & H to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)
TK-108-AP Alternate Transfer Route	
241-AP-08A Pump Pit	Transfer Pump through Rigid Jumper to Nozzle A to Line SN 618
241-AP Valve Pit	Nozzle 22 through to Nozzle 17 via K, D, C, N, P, M, & H to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid jumper to Nozzle E (Tank Return)

241-AW TANKS TO 241-AP-104

TK-101-AW Primary Transfer Route	
241-AW-01A Pump Pit	Pump Nozzle through Flex /Rigid Jumper to Nozzle A to Line SN 261
214-AW-A Valve Pit	Nozzle L16 through Rigid /Flex Jumper to Nozzle L1 via D to Line SN 267
TK-102-AW-02A Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 20 via P, M, H, & J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-102-AW Primary Transfer Route	
241-AW-02E Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle D to Line SN 272
241-AW-02A Central Pump Pit	Nozzle K through Flex Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 20 via P, M, H, & J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-103-AW Primary Transfer Route	
241-AW-03A Central Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle A to Line SN 263
214-AW-A VALVE PIT	Nozzle L14 through Rigid Jumper to Nozzle L1 via D to Line SN 267
214-AW-02A Central Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 20 via P, M, H, & J to Line SN 614
241-AP-04 Central Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)

HNF-3484 Rev. 0
APPENDIX A

TK-104-AW Primary Transfer Route	
241-AW-04A Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle A to Line SN 264
214-AW-B Valve Pit	Nozzle R-14 through Rigid Jumper to Nozzle R1 via D to Line SN 268
241-AW-02A Pump Pit	Nozzle H through Rigid Jumper to Nozzle U to Line SN 610
241-AP Valve Pit	Nozzle 13 through Rigid Jumper to Nozzle 20 via N, P, M, H & J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-105-AW Primary Transfer Route	
241-AW-05A Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle A and Line SN 265
214-AW-A Valve Pit	Nozzle L15 through Rigid Jumper to Nozzle L1 to Line SN 267
214-AW-02A Central Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 20 via P, M, H, & J to Line SN614
241-AP-04 Central Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-106-AW Primary Transfer Route	
241-AW-06A Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle A to Line SN 266
214-AW-B VALVE PIT	Nozzle R-15 through Rigid Jumper to Nozzle R-1 via D to Line SN 268
214-AW-02A Central Pump Pit	Nozzle H through Rigid Jumper to Nozzle U to Line SN 610
241-AP Valve Pit	Nozzle 13 through Rigid Jumper to Nozzle 20 via N, P, M, H, & J to Line SN614
241-AP-04 Central Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)

241-AW TANKS TO 241-AP-103

TK-101-AW Alternate Transfer Route	
241-AW-01A Pump Pit	Pump Nozzle through Flex /Rigid Jumper to Nozzle A and SN 261
214-AW-A Valve Pit	Nozzle L16 through Rigid /Flex Jumper to Nozzle L1 via D to Line SN 267
TK-102-AW-02A Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 17 via P, M, & H to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-102-AW Alternate Transfer Route	
241-AW-02E Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle D to Line SN 272
241-AW-02A Central Pump Pit	Nozzle K through Flex Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 17 via P, M, & H to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-103-AW Alternate Transfer Route	
241-AW-03A Central Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle A to Line SN 263
214-AW-A VALVE PIT	Nozzle L14 through Rigid Jumper to Nozzle L1 via D to Line SN 267
214-AW-02A Central Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 17 via P, M, & H to Line SN 613
241-AP-03 Central Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)

HNF-3484 Rev. 0
APPENDIX A

TK-104-AW Alternate Transfer Route	
241-AW-04A Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle A to Line SN 264
214-AW-B Valve Pit	Nozzle R-14 through Rigid Jumper to Nozzle R1 via D to Line SN 268
241-AW-02A Pump Pit	Nozzle H through Rigid Jumper to Nozzle U to Line SN 610
241-AP Valve Pit	Nozzle 13 through Rigid Jumper to Nozzle 17 via N, P, M, & H to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-105-AW Alternate Transfer Route	
241-AW-05A Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle A and Line SN 265
214-AW-A Valve Pit	Nozzle L15 through Rigid Jumper to Nozzle L1 to Line SN 267
214-AW-02A Central Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 17 via P, M, & H to Line SN613
241-AP-03 Central Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-106-AW Alternate Transfer Route	
241-AW-06A Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle A to Line SN 266
214-AW-B VALVE PIT	Nozzle R-15 through Rigid Jumper to Nozzle R-1 via D to Line SN 268
214-AW-02A Central Pump Pit	Nozzle H through Rigid Jumper to Nozzle U to Line SN 610
241-AP Valve Pit	Nozzle 13 through Rigid Jumper to Nozzle 17 via N, P, M, & H to Line SN613
241-AP-03 Central Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)

241-AY TANKS TO 241-AP-104

TK-101-AY Primary Transfer Route	
241-AY-01D Pump Pit	Pump Nozzle through Flex Jumper to Nozzle U2 to Line SL 504
241-AY-02A Pump Pit	Nozzle U8 through Rigid Jumper to Nozzle U3 to Line SL 503
241-AY-02D Pump Pit	Nozzle U2 through Rigid Jumper to Nozzle U3 to Line SL 502
241-AX-B Valve Pit	Nozzle R16 through Flex Jumper to Nozzle R1 to Line SN 213/200
241-A-B Valve Pit	Nozzle R1 through Rigid Jumper to Nozzle R19 to Line SN 204
241-A-A Valve Pit	Nozzle L19 through Rigid Jumper to Nozzle L2 to Line SN 220
241-AW-A Valve Pit	Nozzle L2 through Flex/Rigid Jumper to Nozzle L1 via D to Line SN 267
241-AW-02A Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumpers to Nozzle 20 via P, M, H, & J to Line SN 614
TK 104 AP-04A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-102-AY Primary Transfer Route	
241-AY-02E Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle U2 to Line SN 200
241-C-106, Pit 06C	Nozzle 5 through Rigid Jumper to Tank Return
241-C-106, Pit 06A	Pump Nozzle through rigid jumper to Nozzle 9 to Line SN 100
241-AY-102, Pit 02A	Nozzle U11 through rigid jumper to Nozzle U3 to Line SL 503
241-AY-02D Pump Pit	Nozzle U2 through Rigid Jumper to Nozzle U3 to Line SN 502
Same as 101-AY to 104-AP	

241-AY TANKS TO 241-AP-103

TK-101-AY Alternate Transfer Route	
241-AY-01D Pump Pit	Pump Nozzle through Flex Jumper to Nozzle U2 to Line SL 504
214-AY-02A Pump Pit	Nozzle U8 through Rigid Jumper to Nozzle U3 to Line SL 503
241-AY-02D Pump Pit	Nozzle U2 through Rigid Jumper to Nozzle U3 to Line SL 502
241-AX-B Valve Pit	Nozzle R16 through Flex Jumper to Nozzle R1 to Line SN 213/200
241-A-B Valve Pit	Nozzle R1 through Rigid Jumper to Nozzle R19 to Line SN 204
241-A-A Valve Pit	Nozzle L19 through Rigid Jumper to Nozzle L2 to Line SN 220
241-AW-A Valve Pit	Nozzle L2 through Flex/Rigid Jumper to Nozzle L1 via D to Line SN 267
241-AW-02A Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumpers to Nozzle 17 via P, M, & H to Line SN 613
TK 104 AP-03A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-102-AY Alternate Transfer Route	
241-AY-02E Pump Pit	Pump Nozzle through Rigid Jumper to Nozzle U2 to Line SN 200
241-C-106, Pit 06C	Nozzle 5 through Rigid Jumper to Tank Return
241-C-106, Pit 06A	Pump Nozzle through rigid jumper to Nozzle 9 to Line SN 100
241-AY-102, Pit 02A	Nozzle U11 through rigid jumper to Nozzle U3 to Line SL 503
241-AY-02D Pump Pit	Nozzle U2 through Rigid Jumper to Nozzle U3 to Line SN 502
Same as 101-AY to 103-AP	

241-AZ TANKS TO 241-AY-101

TK-101-AZ Primary Transfer Route	
241-AZ-01C Pump Pit	Pump Nozzle through Flex Jumper to Nozzle U6 to Line SN 601
214-AZ-02B Pump Pit	Nozzle U6 through Flex Jumper to Nozzle U5 to Line SN 600
241-AX-A Valve Pit	Nozzle L16 through Flex Jumper to Nozzle L19 to Line SN 210
241-AX-B Valve Pit	Nozzle R19 through Flex Jumper to Nozzle R16 to Line SL 502
241-AY-02D Pump Pit	Nozzle U3 through Rigid Jumper to Nozzle U2 to Line SL 503
241-AY-02A Pump Pit	Nozzle U3 through Rigid Jumper to Nozzle U8 to Line SL 504
241-AY-01D	Nozzle U2 through Flex Jumper to the Tank Return Nozzle
TK-102-AZ Primary Transfer Route	
241-AZ-02B Pump Pit	Pump Nozzle through Flex Jumper to Nozzle U5 to Line SN 600
241-AX-A Valve Pit	Nozzle L16 through Flex Jumper to Nozzle L19 to Line SN 210
241-AX-B Valve Pit	Nozzle R19 through Flex Jumper to Nozzle R16 to Line SL 502
241-AY-02D Pump Pit	Nozzle U3 through Rigid Jumper to Nozzle U2 to Line SL 503
241-AY-02A Pump Pit	Nozzle U3 through Rigid Jumper to Nozzle U8 to Line SL 504
241-AY-01D	Nozzle U2 through Flex Jumper to the Tank Return Nozzle

241-AZ TANKS TO 241-AY-102

TK-101-AZ Alternate Transfer Route	
241-AZ-01C Pump Pit	Pump Nozzle through Flex Jumper to Nozzle U6 to Line SN 601
214-AZ-02B Pump Pit	Nozzle U6 through Flex Jumper to Nozzle U5 to Line SN 600
241-AX-A Valve Pit	Nozzle L16 through Flex Jumper to Nozzle L19 to Line SN 210
241-AX-B Valve Pit	Nozzle R19 through Flex Jumper to Nozzle R16 to Line SL 502
241-AY-02D Pump Pit	Nozzle U3 through Flex Jumper to Tank Return Nozzle
TK-102-AZ Alternate Transfer Route	
241-AZ-02B Pump Pit	Pump Nozzle through Flex Jumper to Nozzle U5 to Line SN 600
241-AX-A Valve Pit	Nozzle L16 through Flex Jumper to Nozzle L19 to Line SN 210
241-AX-B Valve Pit	Nozzle R19 through Flex Jumper to Nozzle R16 to Line SL 502
241-AY-02D Pump Pit	Nozzle U3 through Flex Jumper to Yank Return Nozzle

241-SY TANKS TO 241-AP-104

TK-101-SY Primary Transfer Route	
241-SY-101, 42" Riser # 007	Pump Nozzle through Flex Jumper to Over Ground Transfer Line
214-02A	Flex Jumper to Nozzle E (Tank Return)
TK-102-SY Primary Transfer Route	
241-SY-02A Pump Pit	Pump Nozzle through Flex Jumper to Nozzle J to Line SN 285
241-SY-A Valve Pit	Nozzle L11 through Rigid Jumper to Nozzle L12 to Line SNL 3150
244-A Lift Station	Through 6241-A Diversion Box, & 6241-V Vent Station to Nozzle P17 through Rigid Jumper to Nozzle P9 to Line SN 216
241-A-B Valve Pit	Nozzle R16 through Rigid Jumper to Nozzle R19 to Line SN 204
241-A-A Valve Pit	Nozzle L19 through Rigid/Flex Jumper to Nozzle L2 to Line SN 220
241-AW-A Valve Pit	Nozzle L2 through Rigid/Flex Jumper to Nozzle L1 via D to Line SN 267
241-AW-02A Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 20 via P, M, H, & J to Line SN 614
241-AP-04A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-103-SY Primary Transfer Route	
241-SY-03A Pump Pit	Pump Nozzle through Flex Jumper to Nozzle A to Line SN 279
241-SY-B Valve Pit	Nozzle R14 through Rigid Jumper to Nozzle R19 to Line SN 280
241-A Valve Pit	Nozzle 19 through Flex Jumper to Nozzle L16 via H to Line SN 277
241-02A Pump Pit	Nozzle A through Rigid Jumper to Nozzle G (Tank Return)

241-SY TANKS TO 241-AP-103

TK-101-SY Alternate Transfer Route	
241-SY-101, 42" Riser # 007	Pump Nozzle through Flex Jumper to Over Ground Transfer Line
241-02A	Flex Jumper to Nozzle E (Tank Return)
TK-102-SY Alternate Transfer Route	
241-SY-02A Pump Pit	Pump Nozzle through Flex Jumper to Nozzle J to Line SN 285
241-SY-A Valve Pit	Nozzle L11 through Rigid Jumper to Nozzle L12 to Line SNL 3150
244-A Lift Station	Through 6241-A Diversion Box, & 6241-V Vent Station to Nozzle P17 through Rigid Jumper to Nozzle P9 to Line SN 216
241-A-B Valve Pit	Nozzle R16 through Rigid Jumper to Nozzle R19 to Line SN 204
241-A-A Valve Pit	Nozzle L19 through Rigid/Flex Jumper to Nozzle L2 to Line SN 220
241-AW-A Valve Pit	Nozzle L2 through Rigid/Flex Jumper to Nozzle L1 via D to Line SN 267
241-AW-02A Pump Pit	Nozzle J through Rigid Jumper to Nozzle V to Line SN 609
241-AP Valve Pit	Nozzle 14 through Rigid Jumper to Nozzle 17 via P, M, & H to Line SN 613
241-AP-03A Pump Pit	Nozzle A through Rigid Jumper to Nozzle E (Tank Return)
TK-103-SY Alternate Transfer Route	
241-SY-03A Pump Pit	Pump Nozzle through Flex Jumper to Nozzle A to Line SN 279
241-SY-B Valve Pit	Nozzle R14 through Rigid Jumper to Nozzle R19 to Line SN 280
241-A Valve Pit	Nozzle 19 through Flex Jumper to Nozzle L16 via H to Line SN 277
241-02A Pump Pit	Nozzle A through Rigid Jumper to Nozzle G (Tank Return)

APPENDIX B

**LIST OF IMPLEMENTING PROCEDURES
AND RELEVANT DRAWINGS**

HNF-3484 Rev. 0
APPENDIX B

DST EMERGENCY PUMPING PROCEDURES		
TANK FARM	PROCEDURE NUMBER	PROCEDURE TITLE
AN	TO-001-181	Emergency Pumping Procedure for AN-Farm
AP	TO-001-182	Emergency Pumping Procedure for AP-Farm
AW	TO-001-183	Emergency Pumping Procedure for AW-Farm
AY	TO-001-188	Emergency Pumping Procedure for AY-Farm
AZ	TO-001-189	Emergency Pumping Procedure for AZ-Farm
SY	TO-001-184	Emergency Pumping Procedure for SY Farm

HNF-3484 Rev. 0
APPENDIX B

PIPING AND INSTRUMENT DIAGRAMS		
TANK FARM	DWG NO.	TITLE
AN	H 140020501	WASTE STORAGE TANK ANNULUS INSTM SYS WSTA O&M SYS P&ID
	H 140020601	WASTE STORAGE TANK INSTM SYSTEM WST O&MN SYSTEM P&ID
	H 140020801	WASTE TRANSFER SYSTEM-WT-O&M SYSTEM P&ID
AP	H 140020503	WASTE STORAGE TANK ANNULUS INSTM SYS WSTA O&M SYS P&ID
	H 140020603	WASTE STARAGE TANK INSTR SYSTEM WST O&M SYSTEM P&ID
	H 140020803	WASTE TRANSFER SYSTEM(WT) O&M SYSTEM P&ID
AW	H 140020502	WASTE STORAGE TANK ANNULUS INSTM SYS WSTA O&M SYS P&ID
	H 140020602	WASTE STORAGE TANK INSTM SYSTEM WST O&M SYSTEM P&ID
	H 140020803M	WASTE TRANSFER SYSTEM-WT-O&M SYSTEM P&ID
AX	H 140020609	WASTE STORAGE TANK SYSTEM(WST) O&M SYSTEM P&ID
	H 140020809	WASTE TRANSFER SYSTEM(WT) O&M SYSTEM P&ID
AY	H 020064462	PP&ID TANK 241-AY-102 ANNULUS
AZ	H 140020801	WASTE TRANSFER SYSTEM(WT) O&M SYSTEM P&ID
SY	H 140020531	WASTE STORAGE TANK ANNULUS SYSTME (WSTA) O&M SYSTEM P&ID
	H 140020631	WASTE STORAGE TANK SYSTEM(WST) O&M SYSTEM P&ID
	H 140020831	WASTE TRANSFER SYSTEM(WT) O&M SYSTEM P&ID

HNF-3484 Rev. 0
APPENDIX C

APPENDIX C

IDENTIFICATION AND LOCATION OF DST PUMPS AND JUMPERS THAT WOULD BE USED FOR EMERGENCY PUMPING

HNF-3484 Rev. 0
APPENDIX C

Facility Location	Pump Pit	Pump Use	Pump # Currently Installed	Pump Length	Fab DWG	Pump Pit Clearance **	Pump Flange to Bottom of Tank	Jumpers install for transfer	Jumper DWG	Comments
241-AN Tank Farm										
TK - 101	01A	Transfer	202P-TX1	48'-11"	H-2-91943	4'-5 3/32"	49'-9"	Yes	H-2-72026	Spare is 25 HP, 49'-03/8 long. Property # FA 25586.
	01B	Annulus	Open	46' 2 1/2"	H-2-95323	8'-2 7/32"	46'-5 1/4"	No, w/isolation blanks	H-2-72028 & H-2-72025	One Annulus pump for all of AN Tank Farm. No spare.
TK-102	02A	Transfer	65P-TX4	49'-0 1/2"	H-2-91943	4'-5 3/32"	49'-9"	Yes	H-2-72026	
	02B	Annulus	Open	46' 2 1/2"	H-2-95323	8'-2 7/32"	46'-5 1/4"	No, w/isolation blanks	H-2-72028 & H-2-72025	One Annulus pump for all of AN Tank Farm. No spare.
TK-103	03A	Transfer	202P-TX1	49'-0 3/8"	H-2-91943	4'-4 23/32"	49'-9 3/8"	No	H-2-94863	Tank is on "Watch List" due to possible Hydrogen content in tank. Pumping activity uncertain.
	03B	Annulus	Open	46' 2 1/2"	H-2-95323	8'-2 7/32"	46'-5 1/4"	No, w/isolation blanks	H-2-72028 & H-2-72025	One Annulus pump for all of AN Tank Farm. No spare.
TK-104	04A	Transfer	64P-TX4	49'-0 1/2"	H-2-91943	4'-4 23/32"	49'-9 31/64"	No	H-2-94863	Tank is on "Watch List" due to possible Hydrogen content in tank. Pumping activity uncertain.
	04B	Annulus	Open	46' 2 1/2"	H-2-95323	8'-2 7/32"	46'-5 1/4"	No, w/isolation blanks	H-2-72028 & H-2-72025	One Annulus pump for all of AN Tank Farm. No spare.
TK-105	05A	Transfer	84P-TX4/SW	49'-0 3/8"	H-2-91943	4'-4 23/32"	49'-9 31/64"	No	H-2-94863	Tank is on "Watch List" due to possible Hydrogen content in tank. Pumping activity uncertain.
	05B	Annulus	Open	46' 2 1/2"	H-2-95323	8'-2 7/32"	46'-5 1/4"	No, w/isolation blanks	H-2-72028 & H-2-72025	One Annulus pump for all of AN Tank Farm. No spare.
TK-106	06A	Transfer	2P-TX1-XCF	49'-0 3/8"	H-2-91943	4'-4 23/32"	49'-9 1/8"	No	H-2-72026	2P-TX1-XCF (20HP) pump installed 3/19/92. Spare 25 HP. Prop # FA 25592 Man. S/N 91-02165
	06B	Annulus	Open	46' 2 1/2"	H-2-95323	8'-2 7/32"	46'-5 1/4"	No, w/isolation blanks	H-2-72028 & H-2-72025	One Annulus pump for all of AN Tank Farm. No spare.
TK-107	07A	Transfer	Open	49'-0 3/8"	H-2-91943	4'-4 23/32"	49'-9 1/8"	No	H-2-72026	
	07B	Annulus	B5P-10	46' 2 1/2"	H-2-95323	8'-2 7/32"	46'-8 3/8"	No, w/isolation blanks	H-2-72028 & H-2-72025	One Annulus pump for all of AN Tank Farm. No spare.

** Pump Pit Clearance is taken from face of flange to bottom of cover block

HNF-3484 Rev. 0
APPENDIX C

Facility Location	Pump Pit	Pump Use	Pump # Currently Installed	Pump Length	Fab DWG	Pump Pit Clearance **	Pump Flange to Bottom of Tank	Jumpers install for transfer	Jumper DWG	Comments
241-AP Tank Farm										
TK - 101	01A	Transfer	1P-AP-4	33'-0" Flex/Float	H-2-91943	4'-9 13/16"	49'-5 11/16"	Yes	H-2-90725	Spare is expected to be 49'-0 3/8"
	01B	Annulus	Open	46' 2 1/2"	H-2-90576	8'-9 3/4"	46'-4 11/16"	NO, w/isolation	H-2-90729 & H-2-90726	One Annulus pump for all of AP Tank Farm. No spare.
TK-102	02B	Annulus	Open	46' 2 1/2"	H-2-90576	8'-9 3/4"	46'-4 11/16"	NO, w/isolation	H-2-90729 & H-2-90726	One Annulus pump for all of AP Tank Farm. No spare.
	02D	Transfer	1-TX-XCF	44'-7" w/screen	H-2-91943	9'-3 19/64"	44'-8 13/64"	Yes	H-2-90725	
TK-103	03A	Transfer	2P-AP-3	49'-0 3/8"	H-2-91943	4'-9 25/64"	49'-5 23/32"	Yes	H-2-90725	Spare run -in completed 11/29/89. Has Graphite bearings. 30 HP. 160 GPM at 250' TDH
	03B	Annulus	1P-AP-1	46' 2 1/2"	H-2-90576	8'-9 3/4"	46'-4 11/16"	NO, w/isolation	H-2-90729 & H-2-90726	One Annulus pump for all of AP Tank Farm. No spare.
TK-104	04A	Transfer	4P-AP-3	49'-0 3/8"	H-2-91943	4'-9 27/32"	49'-5 21/32"	Yes	H-2-90725	
	04B	Annulus	Open	46' 2 1/2"	H-2-90576	8'-9 3/4"	46'-4 11/16"	NO, w/isolation	H-2-90729 & H-2-90726	One Annulus pump for all of AP Tank Farm. No spare.
TK-105	05A	Transfer	1P-AP-3	49'-0 3/8"	H-2-91943	4'-9 13/16"	49'-5 11/16"	Yes	H-2-90725	
	05B	Annulus	Open	46' 2 1/2"	H-2-90576	8'-9 3/4"	46'-4 11/16"	NO, w/isolation	H-2-90729 & H-2-90726	One Annulus pump for all of AP Tank Farm. No spare.
TK-106	06A	Transfer	2P-AP-4	33'-0" Flex Float	H-2-91943	4'-9 53/64"	49'-5 43/64"	Yes	H-2-90725	
	06B	Annulus	Open	46' 2 1/2"	H-2-90576	8'-9 3/4"	46'-4 11/16"	NO, w/isolation	H-2-90729 & H-2-90726	One Annulus pump for all of AP Tank Farm. No spare.
TK-107	07A	Transfer	Open	49'-0 3/8"	H-2-91943	4'-9 49/64"	49'-5 47/64"	Yes	H-2-90725	
	07B	Annulus	Open	46' 2 3/8"	H-2-90576	8'-9 3/4"	46'-4 11/16"	NO, w/isolation	H-2-90729 & H-2-90726	One Annulus pump for all of AP Tank Farm. No spare.
TK-108	08A	Transfer	Open	49'-0 3/8"	H-2-91943	4'-9 45/64"	49'-5 45/64"	Yes	H-2-90725	
	08B	Annulus	Open	46' 2 1/2"	H-2-90576	8'-9 3/4"	46'-4 11/16"	NO, w/isolation blanks	H-2-90729 & H-2-90726	One Annulus pump for all of AP Tank Farm. No spare.

** Pump Pit Clearance is taken from face of flange to bottom of cover block

HNF-3484 Rev. 0
APPENDIX C

Facility Location	Pump Pit	Pump Use	Pump # Currently Installed	Pump Length	Fab DWG	Pump Pit Clearance **	Pump Flange to Bottom of Tank	Jumpers install for transfer	Jumper DWG	Comments
241-AW Tank Farm										
TK-101	01A	Transfer	BOP-TX4 (Oil Lubed)	49'-0 3/8"	H-2-91943	4'-5 21/32"	49'-5 15/32"	Yes	H-2-70445	
	01B	Annulus	Open	46'-2 1/2"	H-2-95232	8'-3 25/64"	45'-4 15/32"	No, w/isolation blanks	H-2-70451 & H-2-70444	One Annulus pump for all of AW Tank Farm. No spare.
TK-102	02B	Annulus	Open	46' 2 1/2" 33'-0"	H-2-95232	8'-3 27/64"	46'-4 13/64"	No, w/isolation blanks	H-2-70451 & H-2-70444	One Annulus pump for all of AW Tank Farm. No spare.
TK-103	03A	Transfer	1P-TX1-XCR-1	Flex Float	H-2-91943	4'-5 21/32"	49'-5 15/32"	Yes	H-2-70445	
	03B	Annulus	Open	46' 2 1/2"	H-2-95232	5'-3 3/16"	46'-4 7/16"	No, w/isolation blanks	H-2-70451 & H-2-70444	One Annulus pump for all of AW Tank Farm. No spare.
TK-104	04A	Transfer	BOP-TX4 (Oil Lubed)	49'-0 5/8"	H-2-91943	4'-5 55/64"	49'-5 45/64"	Yes	H-2-70445	
	04B	Annulus	Open	46' 2 1/2" 33'-0"	H-2-95323	8'-3 3/16"	45'-4 7/16"	No, w/isolation blanks	H-2-70451 & H-2-70444	One Annulus pump for all of AW Tank Farm. No spare.
TK-105	05A	Transfer	1P-TX1	Flex Float	H-2-91943	4'-5 11/16"	49'-5 7/16"	Yes	H-2-70445	
	05B	Annulus	Open	46' 2 1/2"	H-2-95232	8'-3 13/64"	46'-4 27/64"	No, w/isolation blanks	H-2-70451 & H-2-70444	One Annulus pump for all of AW Tank Farm. No spare.
TK-106	06A	Transfer	1P-TX1-XCR-1	49'-0 3/8"	H-2-91943	4'-5 53/64"	49'-5 19/64"	Yes	H-2-70445	
	06B	Annulus	Open	46' 2 1/2"	H-2-95323	8'-3 3/16"	46'-4 7/16"	No, w/isolation blanks	H-2-70451 & H-2-70444	One Annulus pump for all of AW Tank Farm. No spare.

** Pump Pit Clearance is taken from face of flange to bottom of cover block

HNF-3484 Rev. 0
APPENDIX C

Facility Location	Pump Plt	Pump Use	Pump #Currently Installed	Pump Length	Fab DVG	Pump Pit Clearance**	Pump Flange to Bottom of Tank	Jumpers instal for transfer	Jumper DVG	Comments
241-AY Tank Farm										
TK- 101	01B	Transfer	F64GT	Unknown		5-10 5/8"	49-0 1/8"	Yes	H-2-64421	No info available on this pump
	01D	Transfer	122P-10	47-3 3/8"	H-2-93179	5-10 5/8"	48-0 1/8"	Tes	H-2-64421	
TK-102			2B-P10						H-2-64441 & H-2-64421	One Annulus pump for all of AWTank Farm. No spare.
	01F	Annulus		46-19'16"	H-2-68424	8-3 1/2"	46-4 1/2"	No		
	02D	Transfer	57P-TX-49PTX6	47-3 3/8"	H-2-93179	5-10 5/8"	48-0 1/8"	Yes	H-2-64421	
	02E	Transfer	PO621/PO622	Adjustable	H-2-818494	5-10 5/8"	48-0 1/8"	Yes	H-2-818503	W320 Project
			Open						H-2-64441 & H-2-64421	One Annulus pump for all of AWTank Farm. No spare.
	02F	Annulus		46-19'16"	H-2-68424	8-3 1/2"	46-4 1/2"	No		
** Pump Pit Clearance is taken from face of flange to bottom of cover block										

HNF-3484 Rev. 0
APPENDIX C

Facility Location	Pump Pit	Pump Use	Pump # Currently Installed	Pump Length	Fab DWG	Pump Pit Clearance **	Pump Flange to Bottom of Tank	Jumpers install for transfer	Jumper DWG	Comments
241-AZ Tank Farm										
TK - 101	01C	Transfer	74-TX4/1P-TX5	47'-3 3/8"	H-2-93179	7'-2 49/64"	47'-11 63/64	Yes	H-2-68427	
TK-102	01F	Annulus	108P-10	46'-1 9/16"	H-2-68424	8'-3 31/64"	46'-4 21/64"	No, w/isolation blanks	H-2-68430 & H-2-68433	One Annulus pump for all of AW Tank Farm. No spare.
	02B	Transfer	Open	46'-1 9/16"	H-2-93179	7'-2 49/64"	47'-11 63/64		H-2-68427	
	02F	Annulus	Open	46'-1 9/16"	H-2-68424	8'-3 31/64"	46'-4 21/64"	No, w/isolation blanks	H-2-68430 & H-2-68433	One Annulus pump for all of AW Tank Farm. No spare.
** Pump Pit Clearance is taken from face of flange to bottom of cover block										

HNF-3484 Rev. 0
APPENDIX C

Facility Location	Pump Pit	Pump Use	Pump # Currently Installed	Pump Length	Fab DWG	Spare Pump #	Pump Pit Clearance **	Pump Flange to Bottom of Tank	Jumpers install for transfer	Jumper DWG	Comments
241-SY Tank Farm											
TK - 101	01A Riser 3A	Transfer	Open	TBD	H-2-75352 & H-2-46206		4'-5 11/16"	47'-6 9/16"	No	H-2-46215	
	01A Riser 2A	Mixer	N/A	48'-1 1/8"	H-2-821329	2 each	3'-8 1/4"	50'-2 11/16"	N/A	N/A	One of the spares is located in 400 area(FFTF), and the other is in 2101M
	01B	Annulus	Open	46'-2 1/2"	H-2-37794	No	8'-3 3/16"	46'-4 13/16"	No	H-2-68388& H-2-37800	
TK-102	02A	X-Site	SY-02A-3	33' Flex Floa	H-2-75352 & H-2-46205	1P-Sy1-102-SY	4'-5 11/16"	47'-6 9/16"	Yes	H-2-37782	
	02B	Annulus	Open	46'-2 1/2"	H-2-37794	No	8'-3 3/16"	46'-4 13/16"	No	H-2-68388& H-2-37800	
	02E	Transfer	49-PTX-4	36'-8"	?	No	8'-4 15/16"	45'-8 3/16"	Yes	H-2-37812	35 feet of the old pump broke off in tank
TK-103	03A	Transfer	116P-10	47'-0"	H-2-75352 & H-2-46206	No	4'-5 11/16"	47'-6 9/16"	No	H-2-46215	
	03B	Annulus	PTX-4	46'-2 1/2"	H-2-37794	No	8'-3 3/16"	46'-4 13/16"	No	H-2-68388& H-2-37800	This pump can be moved to the two other pit in SY farm

** Pump Pit Clearance is taken from face of flange to bottom of cover block

DISTRIBUTION SHEET

To	From	Page 1 of 1
Distribution	RW Reed	Date 28 Oct 1998
Project Title/Work Order		EDT No. 618220
HNF-3484 Rev.0, Double-Shell Tank Emergency Pumping Guide		ECN No. N/A

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
DG Baide	S5-05	X			
MH Brown	T4-07	X			
CB Bryan	S5-07	X			
BG Erlandson	R1-51	X			
JW Hunt	R2-12	X			
RE Larson	T4-07	X			
PC Miller	R1-51	X			
MA Payne	R2-58	X			
RS Popielarczyk	R2-58	X			
RE Raymond	R2-38	X			
DW Reberger (6)	S5-13	X			
RW Reed	T4-07	X			
RP Tucker	T4-07	X			
MJ Sutey	S5-07	X			