214
JUN 14 2000

ENGINEERING DATA TRANSMITTAL

Page 1 of 1
1. EDT 625321

2. To: (Receiving Organization) Distribution		3. From: (Originating Organization) Retrieval Engineering		4. Related EDT No.: N/A							
5. Proj./Prog./Dept./Div.: RPP/WFD		6. Design Authority/Design Agent/Cog. Engr.: CE Grenard, 376-3550		7. Purchase Order No.: N/A							
8. Originator Remarks: Document transmitted for approval and release.				9. Equip./Component No.: N/A							
				10. System/Bldg./Facility: Tank Farms							
11. Receiver Remarks: 11A. Design Baseline Document? ☐ Yes ☒ No				12. Major Assem. Dwg. No.: N/A							
				13. Permit/Permit Application No.: N/A							
				14. Required Response Date: June 02, 2000							
15. DATA TRANSMITTED											
(A) Item No	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev No	(E) Title or Description of Data Transmitted	(F) Approval Designer	(G) Reason for Transmittal	(H) Originator Disposition	(I) Receiver Disposition			
1	HNF-5145	---	0	High Level Waste Feed Process Control Strategy	N/A	1,2	1				
2	HNF-5146	---	0	Low Activity Waste Feed Process Control Strategy	N/A	1,2	1				
16. KEY											
Approval Designer (F) E, S, Q, D or N/A (see WTK-CM-3-5, Sec. 12.7)		Reason for Transmittal (G) 1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist (Receipt Acknow. Required)			Disposition (H) & (I) 1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged						
17. SIGNATURE/DISTRIBUTION (See Approval Designer for required signatures)											
(G) Reason	(H) Disp	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp	(J) Name	(K) Signature	(L) Date	(M) MSIN
		Design Auth.				1	1	RR Bafus		5/25/00	R3-73
1	1	Design Agent MA Dippre	<i>MADippre</i>	6/12/00	R3-73	1	1	Design Agent		6/12/00	R2-12
1	1	Cog. Eng. CE Grenard	<i>CE Grenard</i>	5/25/00	R3-73	1	1	GC DeWeese		5/25/00	R3-73
1	1	Cog. Mgr. TJ Conrads	<i>TJ Conrads</i>	5/25/00	R3-73	1	1	HR Hopkins		5/25/00	R2-58
		QA				1		GB Leach		6/1/00	R1-44
		Safety				1	1	GW McLellan		6/1/00	R3-47
		Env.				1	2	RM Orme		5/11/00	R3-73
1	1	PJ Certa	<i>PJ Certa</i>	6/8/00	R3-73	1	1	SM O'Tool		5/25/00	R2-53
1	1	AF Choho	<i>AF Choho</i>	6/15/00	R3-73	1	1	RP Tucker		5/30/00	R3-72
18. MA Dippre <i>MADippre</i> 5-24-00 Signature of EDT Originator		19. TJ Conrads <i>TJ Conrads</i> 6/12/00 Authorized Representative for Receiving Organization		20. TJ Conrads <i>TJ Conrads</i> 6/12/00 Design Authority/ Cognizant Manager		21. DOE APPROVAL (if required) Ctrl. No. <u>N/A</u> ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments					

DISTRIBUTION SHEET

To:	From:	Page 1 of 12
Distribution	Retrieval Engineering	Date June 02, 2000
Project Title/Work Order: HNF-5145, <i>High Level Waste Feed Process Control Strategy</i> and HNF-5146, <i>Low Activity Waste Feed Process Control Strategy</i> .		EDT No. 625321
		ECN No. ---

Name	MSIN	Text With All Attach.	Text Only	Attach/ Appendix Only	EDT/ECN Only
R. R. Bafus	R3-73	X			
D. G. Baide	S5-05	X			
M. H. Brown	T4-07	X			
P. J. Certa	R3-73	X			
A. F. Choho	R3-73	X			
T. J. Conrads	R3-73	X			
C. Defigh-Price	R2-12	X			
G. C. DeWeese	R3-73	X			
G. P. Duncan	R3-72	X			
W. J. Eischens	R3-75	X			
J. G. Field	R2-12	X			
D. P. Fassett	R3-73	X			
T. G. Goetz	R1-49	X			
C. E. Graves	R3-73	X			
C. E. Grenard	R3-73	X			
K. M. Hodgson	R2-11	X			
H. R. Hopkins	R2-58	X			
J. W. Hunt	R2-12	X			
N. W. Kirch	R2-11	X			
C. E. Leach	R1-44	X			
M. W. Leonard	R2-36	X			
G. A. Leshikar	S0-08	X			
T. H. May	R2-11	X			
G. W. McLellan	R3-47	X			
R. S. Nicholson	S5-05	X			
R. M. Orme	R3-73	X			
T. O. Oten	R3-83	X			
S. M. O'Toole	R2-53	X			
J. H. Rasmussen	R2-12	X			
D. W. Reberger	S5-13	X			
D. A. Reynolds	R2-11	X			
C. A. Rieck	R3-47	X			
C. P. Shaw	R3-73	X			
D. F. Smith	R3-73	X			
T. W. Staehr	R3-74	X			
K. S. Tollefson	R1-51	X			
R. P. Tucker	R3-72	X			
J. E. Van Beek	R3-47	X			
T. P. Yeh	R2-89	X			

DISTRIBUTION 272

Onsite

1	<u>U.S. Department of Energy</u> <u>Richland Operations Office</u>	
	DOE Public Reading Room	H2-53
1	<u>Pacific Northwest National Laboratory</u>	
	Hanford Technical Library	P8-55
2	<u>Lockheed Martin Services, Inc.</u>	
	Central Files	B1-07
	Document Processing Center	A3-94

High-Level Waste Feed Process Control Strategy

Prepared for the U.S. Department of Energy
Assistant Secretary for Environmental Management

CH2MHILL

Hanford Group, Inc.

Richland, Washington

Contractor for the U.S. Department of Energy
Office of River Protection under Contract DE-AC06-99RL14047

Approved for Public Release; Further Dissemination Unlimited

High-Level Waste Feed Process Control Strategy

T. W. Staehr
M. A. Dippre

Date Published
May 2000

CH2MHILL
Hanford Group, Inc.

P. O. Box 1500
Richland, Washington

Contractor for the U.S. Department of Energy
Office of River Protection under Contract DE-AC06-99RL14047

Approved for Public Release; Further Dissemination Unlimited

LEGAL DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

This report has been reproduced from the best available copy.

Available in paper copy and microfiche.

Available electronically at

<http://www.doc.gov/bridge>. Available for a processing fee to the U.S. Department of Energy and its contractors, in paper, from:

U.S. Department of Energy

Office of Scientific and Technical Information

P.O. Box 62

Oak Ridge, TN 37831-0062

phone: 865-576-8401

fax: 865-576-5728

email: reports@adonis.osti.gov(423) 576-8401

Available for sale to the public, in paper, from:

U.S. Department of Commerce

National Technical Information Service

5285 Port Royal Road

Springfield, VA 22161

Phone: 800-553-6847

fax: 703-605-6900

email: orders@ntis.fedworld.gov

online ordering:

<http://www.ntis.gov/ordering.htm>

Printed in the United States of America

High-Level Waste Feed Process Control Strategy

T. W. Staehr
COGEMA Engineering
Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-99RL-14047

EDT/ECN: 625321 UC: 721
Org Code: 6N100 Charge Code: 110293
B&R Code: Total Pages: 102

Key Words: double-shell tank, high-level waste, process control strategy, waste feed delivery

Abstract:

The primary purpose of this document is to describe the overall process control strategy for monitoring and controlling the functions associated with the Phase 1B high-level waste feed delivery. This document provides the basis for process monitoring and control functions and requirements needed throughout the double-shell tank system during Phase 1 high-level waste feed delivery.

This document is intended to be used by (1) the developers of the future Process Control Plan and (2) the developers of the monitoring and control system.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

6/14/00
Release Approval Date

APPROVED FOR PUBLIC RELEASE

CONTENTS

1.0	INTRODUCTION	1-1
1.1	SCOPE	1-1
1.2	DOCUMENT ORGANIZATION	1-2
1.3	ASSUMPTIONS	1-3
2.0	PROCESS OVERVIEW	2-1
2.1	DOUBLE-SHELL TANK SYSTEM FUNCTIONS	2-1
2.2	PROCESS DESCRIPTION	2-4
2.2.1	Store Waste In East/West Area Double-Shell Tanks	2-5
2.2.2	Prepare Waste in East/West Area Double-Shell Tanks	2-5
2.2.3	Transfer Waste to High-Level Waste Staging Tanks	2-5
2.2.4	Transfer High-Level Waste Cross-Site	2-7
2.2.5	Prepare High-Level Waste Sludges in High-Level Waste Staging Tanks	2-8
2.2.6	Transfer High-Level Waste Sludge to Low-Activity Waste/High- Level Waste Plant	2-8
2.2.7	Changes in Process with New Baseline Case 3S6D	2-8
2.3	RETRIEVAL SYSTEM DESCRIPTION	2-9
2.3.1	AZ Tank Farm	2-9
2.3.2	AY Tank Farm	2-10
2.3.3	AW Tank Farm	2-11
2.3.4	SY Tank Farm	2-12
2.3.5	Cross-Site Transfer System	2-12
2.3.6	200 East Area Tank Farms Transfer System	2-13
2.3.7	Changes In Retrieval Systems with the New Baseline Case 3S6D	2-14
3.0	PROCESS CONTROL	3-1
3.1	DEVELOPMENT OF PROCESS CONTROL STRATEGY	3-1
3.1.1	General Process Control Strategy Requirements	3-1
3.1.2	Process Control Strategy Matrices	3-3
3.1.3	Process Control Strategy Logic Diagram	3-4
3.1.4	Task Team Decisions	3-5
3.2	PROCESS CONTROL STRATEGY	3-5
3.2.1	Receive Waste	3-5
3.2.2	Store Waste	3-6
3.2.3	Mobilize and Suspend Insoluble Waste	3-9
3.2.4	Add Diluent to Source Tank	3-12
3.2.5	Mix/Blend Waste	3-13
3.2.6	Sample Waste	3-14
3.2.7	Establish Transfer Route	3-16
3.2.8	Suspend Waste	3-17
3.2.9	Provide Diluent During Transfers	3-17
3.2.10	Convey Waste	3-20
3.2.11	Confine Waste Leakage Along Transfer Route	3-24

3.2.12	Flush Transfer System	3-26
3.2.13	Drain Transfer Piping	3-27
3.2.14	Perform Material Balance	3-27
3.2.15	Reconfigure Transfer Route.....	3-28
3.3	INSTRUMENT AND EQUIPMENT REQUIREMENTS	3-29
3.4	CHANGES IN PROCESS CONTROL STRATEGY FROM CASE 3 TO CASE 3S6D	3-29
4.0	REFERENCES	4-1

APPENDICES

A	PROCESS CONTROL STRATEGY MATRICES	A-i
B	PROCESS CONTROL STRATEGY LOGIC DIAGRAMS.....	B-i
C	HIGH-LEVEL WASTE PROCESS CONTROL STRATEGY TASK TEAM DECISIONS MEETINGS MINUTES.....	C-i
D	HIGH-LEVEL WASTE PROCESS CONTROL STRATEGY UNRESOLVED ISSUES	D-i

FIGURES

Figure 2-1.	Level 1 Functional Flow Diagram.	2-2
-------------	---------------------------------------	-----

ACRONYMS AND ABBREVIATIONS

ALC	air-lift circulator
CAM	continuous air monitor
CFR	Code of Federal Regulations
cm	centimeter
COB	clean-out boxes
DCRT	double-contained receiver tanks
DOE	U.S. Department of Energy
DST	double-shell tank
ECR	effective cleaning radius
ft	feet
gal	gallon
g	gram
HEPA	high-efficiency particulate air
HLW	high-level waste
hp	horsepower
in.	inch
kW	kilowatt
LAW	low-activity waste
LCO	limiting condition of operation
LFL	lower flammability limit
m	meter
PC	Privatization Contractor
SHMS	standard hydrogen monitoring system
SpG	specific gravity
SST	single-shell tank
VFD	variable-frequency drive
WCA	waste compatibility assessment
WFD	waste feed delivery
w.g.	water gauge

DEFINITIONS

Certified	The waste has been sampled and meets the criteria of BNFL-5193-ID-20, <i>Interface Control Document for High-Level Waste Feed</i> , for the given transfer.
Diluent	Raw water, or water with added caustic and/or nitrite compounds, which may be temperature-adjusted.
HLW	High-level waste as defined in <i>DOE Contract DE-AC06-96RL13308, Waste Treatment Plant, Specification 8, "High-Level Waste Envelopes Definition"</i> (BNFL 1996).

Homogenized	The waste has been sufficiently mixed to meet the requirements for qualification and certification.
Mix/blend	The process of combining waste material from more than one tank.
Mobilize	The process of resuspending settled sludge from the bottom of a tank.
Multimoded	A function performed concurrently with several other functions.
Qualified	The waste has been determined to be pumpable.
Suspend	The process of putting or keeping fluidized waste particles into a uniform suspension within the liquid phase of the waste.
Transfer	The process of moving waste from one tank to another or from one tank to the LAW/HLW Plant.
Waste feed	Waste slurry to be transferred to the LAW/HLW Plant; it contains a mixture of solids and liquids.
Waste envelope	Waste defined in <i>DOE Contract DE-AC06-96RL13308, Waste Treatment Plant</i> , Specification 8, "High-Level Waste Envelopes Definition" (BNFL 1996).

1.0 INTRODUCTION

High-level radioactive wastes currently stored in underground storage tanks at the U.S. Department of Energy (DOE) Hanford Site are scheduled to undergo a vitrification process before final disposal. The initial phase (Phase 1B) of the high-level waste (HLW) feed delivery process includes retrieval of wastes from Tanks 241-AZ-101 and -102, 241-AY-101 and -102, 241-AW-103, and 241-SY-102. The waste contained in the HLW source tanks is made up of a settled sludge layer covered by a layer of liquid supernatant. In general, the retrieval process includes mobilizing, mixing, and suspending the settled solids into a dilute slurry using mixer pumps and then transferring the slurry via underground piping systems to the low-activity waste (LAW)/HLW Plant that will be provided by a Privatization Contractor (PC). Tank 241-AZ-101 is to serve as the initial feed staging tank for delivering HLW feed to the LAW/HLW Plant.

1.1 SCOPE

The primary purpose of this document is to describe the overall process control strategy for monitoring and controlling the functions associated with the Phase 1B HLW feed delivery. This document provides the basis for process monitoring and control functions and requirements needed throughout the Double-Shell Tank (DST) System during Phase 1 HLW feed delivery.

This document is intended to be used by (1) the developers of the future Process Control Plan, and (2) the developers of the monitoring and control system.

This document is based on the Case 3, Project Planning, DST usage scenario, which was the applicable baseline when this document was first prepared. Notice that Case 3S6D, 2006 Hot Start, will be documented in Revision 2 of HNF-SD-WM-SP-012 and will serve as the baseline case for the Readiness to Proceed-2 River Protection Project milestone. Case 3S6D incorporates changes to Case 3 to resolve feed staging tank issues, reflect changes in the assumptions, and include additional programmatic constraints, as directed by DOE Office of River Protection. Preliminary quantitative and qualitative assessments were performed to determine the impacts of these changes to this document. Generally, the requirements developed in this document were determined to be insensitive to the aforementioned changes; that is, the fundamental system-level requirements remained constant between Cases 3 and 3S6D (e.g., Case 3 included retrieval of single-shell tank (SST) waste as a part of the extended order, and Case 3S6D includes retrieval of SST waste as a part of minimum order and extended order quantities). In instances where quantitative assessments were performed, the enveloping case was selected to develop the requirements.

Performance requirements for the DSTs, which include the available storage and staging capacities, waste sources and volumes, physical, chemical, and radiological waste properties for storage/preparation/transfer, utility requirements, and transfer rates, are given in HNF-2168, *Performance Requirements for the Double-Shell Tank System: Phase 1*.

Requirements for monitoring and control instrumentation, including performance requirements, physical characteristics, environmental conditions, reliability, maintainability, and transportability are given in HNF-4155, *Double-Shell Tank Monitor and Control Subsystem Specification*.

The DST System includes six tank farms containing a total of 28 DSTs. Five of the DST farms are located in the 200 East Area (241-AN, 241-AP, 241-AW, 241-AY, and 241-AZ), and one is located in the 200 West Area (241-SY). The four tanks in the 241-AY and 241-AZ Tank Farms are designed to store high heat or "aging" waste and have a design storage capacity of 3,800 m³ (1 Mgal) each. Each of the other DSTs has a design capacity of 4,390 m³ (1.16 Mgal) per tank. Tank 241-AN-107, with a capacity of 4,390 m³ (1.16 Mgal), could be used as an aging waste storage tank. The planned usage of the DSTs during Phase 1 Waste Feed Delivery is detailed in the *Tank Waste Remediation System Operation and Utilization Plan to Support Waste Feed Delivery*, HNF-SD-WM-SP-012.

1.2 DOCUMENT ORGANIZATION

This document is organized as follows:

- Section 1.0, "Introduction," includes a brief description of the scope of the process control strategy; the document organization; and the general assumptions used.
- Section 2.0, "Process Overview," breaks down the DST System functions according to the functional decomposition presented in HNF-5136, *Functional Analysis for Double-Shell Tank Subsystems*, and describes existing retrieval systems at the tank farms.
- Section 3.0, "Process Control," describes the general objectives of the process control strategy, with reference to the matrices in Appendix A and the logic diagram in Appendix B. The specific process control strategy requirements for each of the functional decompositions of Section 2.0 are discussed. The general requirements of the instruments and equipment are described.
- Section 4.0, "References," provides full reference citations for the references used in the document.
- Appendix A, "Process Control Strategy Matrices," contains the breakdown of storage, preparation, and transfer functions, with associated process concerns, potential control variables, choice of controlling variables (monitored or controlled), and the basis for control variable selection. Two sets of matrices are provided, "Existing Process Concerns," and "Control Variable Consideration for Future Development."
- Appendix B, "Process Control Strategy Logic Diagrams," contains the logic train associated with the requirements developed in Section 3.0 and Appendix A. The logic diagrams indicate the types of decisions required (administrative or control logic) to operate each function (storage, preparation, or transfer).

- Appendix C, "High-Level Waste Process Control Strategy Task Team Decisions Meetings Minutes," provides documentation of decisions produced regarding the HLW and LAW process control strategy. Some decisions are in force on an interim basis, pending formal resolution.
- Appendix D, "High-Level Waste Process Control Strategy Unresolved Issues," contains a list of the existing issues that need to be resolved to fully document the selection of the specific controlling variables, as selected in the matrices (Appendix A) and logic diagrams (Appendix B).

1.3 ASSUMPTIONS

The following assumptions were made in the preparation of this document.

- HLW feed staging, Case 3 (from HNF-SD-WM-SP-012), is used as the basis for this document.
- Mixer pumps will be able to mobilize the required quantity of waste feed in HLW source/staging DSTs. For Case 3S6D, other equipment or technologies, such as sluicing, will be used to retrieve SST wastes.
- Instrumentation to measure sludge mobilization, blending, and suspension parameters, including the suspended solids profiler, gamma profiler, and ultrasonic interface level detector, will be tested in conjunction with mixer pump testing (HNF-SD-WM-PTP-027, *Mixer Pump Test Plan for Double-Shell Tank 241-AZ-101*). Successful testing of these instruments may justify monitoring additional process control parameters.
- Only parameters that have been monitored or measured previously or that can be proven to be measurable will be used for monitoring and control of HLW feed delivery.
- Mixer pumps and transfer pumps will be able to be installed and operated in sludge depths.
- Transfer pumps have a fixed suction approximately 0.3 m (1 ft) off the bottom of the tank.
- Transfer pumps will be operable with mixer pumps operating at low speed.
- The waste retrieval and delivery process for Phase 1B HLW feed is as described in Section 2.2.

This page intentionally left blank.

2.0 PROCESS OVERVIEW

2.1 DOUBLE-SHELL TANK SYSTEM FUNCTIONS

The HLW feed process has been broken down into three separate system-level functions, as described in HNF-SD-WM-TRD-007, *System Specification for the Double-Shell Tank System*: Store Waste in DSTs, Prepare HLW Sludges, and Transfer HLW Sludge. Waste storage includes those functions required for monitoring and control of the stored waste in DSTs and for receiving wastes from other tanks. Waste preparation includes those functions required for mobilizing, blending, sampling, diluting, and suspending the waste for transfer. Waste transfer functions are those required for transferring the waste contained in source or staging tanks to other tanks and to the LAW/HLW Plant. Note that the waste storage function is multimoded, i.e., performed simultaneously with the waste preparation and waste transfer functions; therefore, waste storage monitor and control functions must account for differing performance levels, depending on the activity being performed in the tank.

The Level 1 functional flow diagram is shown in Figure 2-1. It provides the framework within which the process control strategy is performed and documented. The functions depicted in Figure 2-1 that pertain to the HLW process control strategy are as follows:

- Store Waste in East/West Area DSTs
- Prepare Waste in East/West Area DSTs
- Transfer Waste to HLW Staging Tanks
- Transfer HLW Cross-Site
- Prepare HLW Sludges in HLW Staging Tanks
- Transfer HLW Sludge to LAW/HLW Plant.

The majority of the HLW feed delivery activities will take place in the 200 East Area; however, the 200 West Area DST System activities are included, because 200 West Area Tank 241-SY-102 is a Phase 1B HLW source tank. Existing waste stored in staging tanks (e.g., Tank 241-AZ-101) is sent to the LAW/HLW Plant via the Prepare HLW Sludges in HLW Staging Tanks function and the Transfer HLW Sludge to LAW/HLW Plant function. Waste stored in other HLW source tanks reaches the LAW/HLW Plant via the function sequence, Prepare Waste in East Area DSTs, Transfer Waste to HLW Staging Tanks, Prepare HLW Sludges in HLW Staging Tanks, Transfer HLW Sludge to LAW/HLW Plant. Waste is transferred from the 200 West Area to the 200 East Area via the Transfer HLW Cross-Site function.

Figure 2-1. Level 1 Functional Flow Diagram. (Sheet 1 of 2)

Figure 2-1. Level 1 Functional Flow Diagram. (Sheet 2 of 2)

2.2 PROCESS DESCRIPTION

The overall Phase 1B HLW feed delivery process is described below. The process is described as a series of ten transfers – five from waste source tanks to intermediate or staging tanks and five from staging tanks to the LAW/HLW Plant. In general, the process for retrieving waste from a source tank or staging tank is the same. Mixer pumps will be used to mobilize the settled sludge, mix the sludge and supernatant into a slurry, and maintain solids in suspension while the slurry is transferred out of the tank. After completion of the transfer, the transfer lines will be flushed with chemically adjusted water and allowed to drain.

The initial HLW feed batch will be from the existing waste contained in Tank 241-AZ-101. The process flowsheet that describes the process for retrieval and delivery of the Tank 241-AZ-101 waste feed is given in HNF-1939, Vol. II, *Waste Feed Delivery Technical Basis*, Rev. 0a, “Waste Feed Delivery Flowsheet for Tank 241-AZ-101.” Flowsheets describing subsequent staging and transfer of additional HLW feeds from other source tanks are being drafted and are not yet available.

In general, the overall process for Phase 1B HLW feed delivery is as follows:

- Store Waste in East/West Area DSTs

Tank parameters are monitored and controlled to assure containment and safe storage during waste retrieval activities.

- Prepare Waste in East/West Area DSTs

HLW settled solids contained in DSTs are mobilized and combined with the supernatant to form a slurry for transfer to the staging tanks or directly to the LAW/HLW Plant. Single-shell source tanks are retrieved by sluicing.

- Transfer Waste to HLW Staging Tanks

The HLW slurry is pumped out of the DST source tanks and transferred to the staging tanks via underground pipelines. The HLW slurry is sluiced out of the single-shell source tanks to an intermediate storage tank or to a staging tank.

- Transfer HLW Cross-Site.

Waste is transferred from the 200 West Area tanks to the 200 East Area tanks.

- Prepare HLW Sludges in HLW Staging Tanks

The waste in the staging tanks is mixed and/or blended with other wastes to form the HLW feed. The waste feed is sampled and certified prior to being transferred to the LAW/HLW Plant.

- Transfer HLW Sludge to LAW/HLW Plant

The HLW feed is pumped out of the staging tanks and transferred to the LAW/HLW Plant in batches via underground pipelines.

The process description for each of the HLW feed delivery functions is described below.

2.2.1 Store Waste In East/West Area Double-Shell Tanks

The process activities included in the "Store Waste in East/West Area DSTs" functions are primarily monitoring and control of tank parameters to assure containment and safe storage of the waste during retrieval activities, such as waste transfers, waste preparation, and blending. Waste confinement is evaluated by monitoring for waste leakage in the tank annulus and monitoring for contamination in the ventilation exhaust stacks. Parameters monitored to assure safe storage include waste volume, waste temperature, tank structure temperature, dome vacuum, and vapor space hydrogen concentration.

2.2.2 Prepare Waste in East/West Area Double-Shell Tanks

A typical HLW source tank contains a settled solids sludge layer, covered by a liquid supernatant layer. Mixer pumps will be used to mobilize the settled solids by directing a concentrated jet at the sludge layer. Current designs for mixer pumps have the pump intake near the bottom of the tank, with two opposing jets discharging between 1 and 2 ft above the suction. The pumps can be operated in a fixed mode or may be oscillated back and forth through 180 degrees. Mobilization of the solids may involve operation of the mixer pumps in the fixed mode and/or in the oscillating mode. Once mobilized, the solids are mixed and suspended in the supernatant by additional operation of the mixer pumps.

The addition of dilution water is also included as part of the waste preparation function. Dilution water may be required to start the mixer or transfer pumps, to make the waste slurry more dilute for transfer, or to adjust the waste height particularly during the final batch transfers. Water additions will be added either directly into the tank, or at the transfer pump suction.

None of the HLW source tanks retain an appreciable amount of gas, therefore degassing will not be required. Administrative controls are also in place so that waste cannot be transferred into a tank and create a situation where gas would be retained.

2.2.3 Transfer Waste to High-Level Waste Staging Tanks

Before transferring any waste to tanks containing residual heels, consideration will be given to the effects of combining different types of waste envelopes.

Additionally, for retrieval operations involving transfers, CPS-T-149-00010, *Criticality Prevention Specification*, requires that a criticality safety evaluation be performed per WHC-SD-SQA-CSA-20368, CSER 94-004: *Criticality Safety of Double-Shell Waste Storage Tanks*.

2.2.3.1 Transfer Waste from Double-Shell Tanks to High-Level Waste Staging Tanks.

Prior to starting the waste transfer, the transfer plan is prepared and the transfer route is established. Existing transfer pumps, if functional, may be used to transfer waste. The transfer valve positioning is confirmed by independent verification and is monitored during waste transfers. In addition, the transfer line is heated to reduce the possibility of solids precipitating during transfer by transferring heated diluent. The diluent transfer is also used to verify the transfer line routing before tank waste is admitted to the line. A flush pump at the Diluent and Flush Subsystem is used to pump the diluent through the transfer line. Valving at the transfer pit jumper is configured to allow the diluent transfer to be routed such that it bypasses the transfer pump.

The waste transfer is initiated by transferring the waste through a recirculation loop in the transfer pit jumper. Instrumentation contained in the jumper is monitored to verify waste transfer parameters such as flow, pressure, and, tentatively, density. Once parameters have been verified, valves in the transfer pit jumper are realigned to allow the transfer to proceed to its destination.

In-line dilution may also be required during the transfer. In this case, diluent flow to the transfer pump suction is initiated before the pump is started, then reduced until it is equal to the planned transfer pump flow rate. When the diluent flow rate is equal to the planned transfer pump flow rate, the transfer pump is started at a relatively low rotational speed. With the pump on, the diluent is recirculated through the recirculation loop. Transfer pump parameters and instrumentation contained in the jumper are monitored as described above to assure proper operation and to alert operators to potential problems. To initiate the transfer, diluent flow is reduced in steps while the pump outlet flow is held constant. As diluent flow is reduced, waste is drawn into the pump suction to make up the difference. A minimum ratio of diluent to total pump flow will be determined to maintain the transfer stream solids content below the allowable limit and prevent transfer line plugging. Waste composition and solids content data collected during the tank characterization process is used to determine the minimum diluent to total pump flow rate ratio and this ratio is correlated to transfer stream density.

Transfer stream parameters are monitored to comply with pumpability requirements and maintain the solids content within allowable limits. If the transfer pump and transfer stream parameters are as expected, diluent flow rate reductions continue until the minimum ratio of total flow to diluent is reached. Minimal or intermittent operation of the mixer pumps during the transfer operation may be required to maintain the solids in suspension.

Primary control of the transfer process is at the source tank. The operator approves start of transfer and monitors in-tank and transfer stream conditions during the transfer. The transfer system is monitored for waste leakage and misrouting, and the operator may interrupt the transfer if needed. Material balance information is collected and periodic material balances are performed. The transfer is continued until the predetermined tank level is achieved.

When the transfer is complete, flush solution is delivered to the pump suction at a flow rate slightly more than the pumping rate to flush waste from the transfer pump and transfer line. When the transfer system is sufficiently flushed, the transfer pump is shut off and valves are reconfigured to allow diluent flow in the reverse direction to flush solids from the suction line and intake screen. The remaining flush solution in the transfer line partially drains to the staging tank and the remainder drains back to the source tank through the pump.

Upon completion of the transfer, the transfer route is reconfigured by returning the transfer valves, diluent and flush solution supply equipment, and pump and monitoring systems to their off-line positions and settings. A final material balance is then completed for the waste transfer. The many factors that must be considered in material balance are discussed in Section 3.2.14.

2.2.3.2 Transfer Waste from Single-Shell Tanks to High-Level Waste Staging Tanks.

Waste contained in SSTs in the 241-C Tank Farm will also serve as HLW feed. The waste will be retrieved using a modified past practice sluicing process to suspend the solids for subsequent transfer to an intermediate storage tank or waste staging tank. The Waste Retrieval Sluicing System will be similar to that provided by the W-320 Project for sluicing Tank 241-C-106. The major equipment that make up the Waste Retrieval Sluicing System include two similar pumping systems, (one for delivery of the sluice stream, and one for delivery of the slurry to the receiver tank); a sluicer system; a slurry distributor; and interfarm piping to complete a dedicated closed loop sluicing system.

Prior to starting the sluicing operation, the transfer routes for both the sluicing medium and the slurry are established. The transfer valve positioning is confirmed by a manual walkdown and will be monitored during waste transfers. The initial operation will be to pump the sluicing medium made up of supernatant from the receiver tank. The tank liquid level will be monitored to maintain the correct elevation of the variable pump suction, and for material balance during and after the sluicing operation. The sluicing pump operating parameters will be monitored along with waste flow. Details of the retrieval system for Tank 241-C-106 are provided in HNF-SD-WM-PCP-013, *Tank 241-C-106 Waste Retrieval Sluicing System Process Control Plan*.

2.2.4 Transfer High-Level Waste Cross-Site

The HLW contained in the West Area tanks will be transferred cross-site to East Area intermediate or staging tanks before being sent to the LAW/HLW Plant for immobilization. The transfers will originate from one of the 241-SY Tank Farm DSTs and will be sent to Tank 241-AN-104 in the East Area. A transfer pump will be used to retrieve the HLW from the SY tank and the HLW will then be pumped cross-site by a booster pump. A high point vent is located approximately half way between the 200 East and 200 West areas to facilitate filling and draining the pipeline.

Before each transfer, the valves are configured for the routing required by the transfer. Once the route is set, the valves will be interlocked to prevent a misrouting. The pipeline will then be filled with waste to minimize vapor entrapment and water hammer. Heated diluent may be used if required for preheating the pipeline.

The transfer is started when the correct transfer parameters are determined (i.e., flow rate, pressure, and fluid temperature). Parameters will be monitored during the transfer to ensure proper operation. Material balance information is collected and periodic material balances are performed. After the transfer is completed, the pipeline will be flushed and allowed to drain. Finally, the valves are reconfigured to a non-transfer condition until the next transfer is required.

2.2.5 Prepare High-Level Waste Sludges in High-Level Waste Staging Tanks

The overall waste feed delivery (WFD) plan assigns staging tanks that are used to prepare waste batches for transfer to the LAW/HLW Plant. The preparation of waste in HLW staging tanks is essentially the same as for HLW source tanks. Waste contained in a number of the source tanks will be transferred directly to the LAW/HLW Plant.

The sludge is again mobilized by operation of the mixer pumps; however, the sludge is expected to be less consolidated than in source tanks due to shorter solids settling periods. Thus it is also expected that the mixer pumps will not have to be operated as long to mobilize the source tank waste. The next step, where applicable, is to blend the waste received from other source tanks with the existing waste to form a uniform mixture. This is also performed by operation of the mixer pumps.

Once the waste has been sufficiently mixed and blended, the waste is sampled and analyzed to verify that it meets contract requirements and to reach agreement with the PC that the waste feed is acceptable. The inventory of waste contained in each staging tank is transferred in a series of smaller batches. Waste certification is only required to be performed once prior to the first batch transfer.

2.2.6 Transfer High-Level Waste Sludge to Low-Activity Waste/High-Level Waste Plant

The process for transferring HLW feed from the staging tanks to the LAW/HLW Plant is essentially the same as for the source tank to staging tank transfers. The major difference is that control of the transfers will need to be coordinated between the DOE and the PC. The specific procedure of verifying valve configuration between DOE and the LAW/HLW Plant will be elaborated upon in the future Process Control Plan. The waste transfer pipeline leak detection system is interlocked with the transfer pumps. Material balance information is collected and periodic material balances are performed. The many factors that must be considered in material balance are discussed in Section 3.2.14.

2.2.7 Changes in Process with New Baseline Case 3S6D

The process steps above apply to Case 3S6D DSTs. Specific process steps for sluicing have yet to be developed for SST retrieval.

2.3 RETRIEVAL SYSTEM DESCRIPTION

Existing systems and equipment at the HLW feed tanks are primarily for maintaining the waste in a safe storage condition. The overall HLW retrieval system is in various stages of planning, design, and construction and will be installed by various projects. The waste transfer system and other upgrades also will be installed by these projects. Both existing and planned equipment are discussed further below. A detailed description of the retrieval system is provided in HNF-1939, *Waste Feed Delivery System Description*, Vol. III, "Waste Feed Delivery System Description," which will be updated this fiscal year.

2.3.1 AZ Tank Farm

The 241-AZ Tank Farm is made up of two 3,800 m³- (1 Mgal-) capacity DSTs, Tank 241-AZ-101 and Tank 241-AZ-102. Wastes currently contained in both of the tanks will be delivered to the LAW/HLW Plant as HLW feed during Phase 1B privatization. In addition, Tank 241-AZ-101 also will serve as a staging tank for waste received from other source tanks. Tank 241-AZ-101 will provide the first waste feed batch to the LAW/HLW Plant.

Mixer Pumps. Tank 241-AZ-101 contains two 224 kW (300-hp) mixer pumps installed by a current project for mobilization, mixing, and suspension of the waste. The mixer pumps are operated through variable-frequency drive (VFD) units located in the AZ-156 control room outside of the tank farm. Similarly designed mixer pumps will be installed in Tank 241-AZ-102 by another project.

Transfer Pumps. Transfer pumps and jumpers will be installed in the central pump pit at both Tank 241-AZ-101 and Tank 241-AZ-102. The Tank 241-AZ-101 pump and the Tank 241-AZ-102 pump will be provided by current projects. The pumps will be controlled through VFD units. The pumps will have the capability to provide in-line dilution at the pump suction. Piping jumpers will transfer the waste from the pump discharge to the transfer lines and also will contain a recirculation line to return waste to the tank if required.

Diluent and Flush Subsystem. The 241-AN Tank Farm system will be used for dilution and flushing for both tanks in the 241-AZ Tank Farm. The system will consist of a storage/makeup tank, heaters, chemical metering pumps, and a piping system. The diluent added to the tanks is introduced either at the transfer pump intake or directly to the tank. The majority of Tank 241-AZ-101 and Tank 241-AZ-102 additions will consist of water flushes with dilute caustic and nitrite solutions for removal of residual wastes from the transfer lines.

Ventilation Subsystem. The primary tank ventilation system is common to the four aging waste tanks (241-AY-101, 241-AY-102, 241-AZ-101, 241-AZ-102). A recirculation ventilation cooling system is provided for each tank to help reduce emissions and remove heat generated in the tanks. The cooling equipment includes a condenser, moisture separator, and recirculation fan for each system. Each tank is manifolded into a common exhaust header. The combined exhaust stream from all four tanks flows through a condenser, a high-efficiency mist eliminator, a pre-filter, and high-efficiency particulate air (HEPA) and high-efficiency gas adsorber filters.

before being exhausted through the stack to the atmosphere. The exhaust stack is equipped with radiation monitors and alarms.

The annulus ventilation system consisting of one fan is used for ventilation of both the Tank 241-AZ-101 and Tank 241-AZ-102 annuli. Air is drawn in through intake stations at the tank, which contain HEPA filters. The air is then drawn from the annulus and conveyed to a heater and first and second stage HEPA filters before being discharged out the stack.

Instrumentation, Monitoring, and Control System. Instrumentation is currently in place to measure storage parameters including tank liquid level, tank waste temperature, tank structure temperature, tank headspace pressure, flammable gas concentration, primary tank and annulus leak detection. *If necessary, flammable gas concentration will be monitored by sampling.* Current projects plan to install instruments for monitoring mixer pump and transfer pump operation, as well as also flow, mass flow, and pump outlet pressure in pit piping jumpers.

2.3.2 AY Tank Farm

The 241-AY Tank Farm is similar to the 241-AZ Tank Farm in that it has two 3,800 m³- (1 Mgal-) capacity DSTs, Tanks 241-AY-101 and 241-AY-102. Wastes currently contained in both of the tanks will be delivered to the LAW/HLW Plant as HLW feed during Phase 1B privatization. Tank 241-AY-102 contains waste that recently has been transferred from Tank 241-C-106. The waste contained in Tank 241-AY-101 also will be combined with other waste before it is transferred to the LAW/HLW Plant.

Mixer Pumps. Four 112 kW (150-hp) mixer pumps are scheduled to be installed in Tank 241-AY-101 for mobilization, mixing, and suspension of the waste. A current project is also scheduled to install four 112 kW (150-hp) mixer pumps in Tank 241-AY-102.

Transfer Pumps. Transfer pumps and jumpers will be installed in the central pump pit at both Tank 241-AY-101 and Tank 241-AY-102. The Tank 241-AY-101 pump will be provided by a current project, and the Tank 241-AY-102 pump will be provided by another project. The pumps will be controlled through VFD units. The pumps will have the capability to provide in-line dilution at the pump suction. Piping jumpers will transfer the waste from the pump discharge to the transfer lines and also will contain a recirculation line to return waste to the tank if required.

Diluent and Flush Subsystem. The diluent and flush subsystem that serves the 241-AZ Tank Farm will also be used for the 241-AY Tank Farm tanks.

Ventilation Subsystem. The primary ventilation system described in Section 2.3.1 serves both tanks in the 241-AY Tank Farm. The annulus ventilation system for the AY tanks is similar to the one serving the AZ tanks.

Instrumentation, Monitoring and Control System. Instrumentation currently is in place to measure storage parameters including tank liquid level, tank waste temperature, tank structure temperature, tank headspace pressure, flammable gas concentration, and primary tank and annulus leak detection. Current projects plan to install instruments for monitoring mixer pump

and transfer pump operation as well as flow, mass flow, and pump outlet pressure in pit piping jumpers.

2.3.3 AW Tank Farm

The 241-AW Tank Farm is made up of six 4,390 m³ - (1.16 Mgal-) capacity DSTs (241-AW-101, -102, -103, -104, -105, -106, and -107). Tank 241-AW-103 contains approximately 1,900 m³ (500,000 gal) of waste that will be retrieved and delivered to the LAW/HLW Plant as HLW feed during Phase 1B privatization. Portions of the Tank 241-AW-103 waste will be mixed with wastes contained in Tanks 241-AY-102, 241-AY-101, and 241-SY-102 to form three separate batches.

Mixer Pumps. Two 224 kW (300-hp) mixer pumps will be required in Tank 241-AW-103 to mobilize and suspend the waste for retrieval. The mixer pumps will be provided as part of a current project.

Transfer Pumps. A transfer pump and jumper assembly will be required in the central pump pit to transfer the waste out of Tanks 241-AW-103 and 241-AW-104. A current project will provide equipment as required for transferring the waste to the appropriate staging tanks.

Diluent and Flush Subsystem. A new system will be provided by a current project and located in the 241-AW Tank Farm. The system will be used for dilution and flushing of transfers from Tank 241-AW-101. The system will be similar to that proposed by a current project for the 241-AZ Tank Farm.

Ventilation Subsystem. The primary ventilation system serves all six of the AW tanks. Air infiltration is provided through pit cover blocks and is conveyed through ductwork to an exhaust fan and is discharged out an exhaust stack. The exhaust train contains a de-entrainer, heater, prefilter, and a first and second stage HEPA filter. The exhaust stack is equipped with radiation monitors and alarms. The system design is such that one primary fan operates while another fan remains in standby as a backup.

The annulus exhaust system consists of two exhaust fans that each provide ventilation for three tanks. Outside air enters through intake stations at each tank, which contain a prefilter and HEPA filter. The air is drawn from the annulus and conveyed through a demister, heater, prefilter, and a first and second stage HEPA filters before being discharged out the exhaust stack. Should either exhaust fan assembly fail or require maintenance, partial air flow from all the tanks can be maintained by manually switching the valve arrangement to allow the operating fan to draw from all tanks.

Instrumentation, Monitoring, and Control System. Instrumentation is currently in place to measure storage parameters including tank liquid level, tank waste temperature, tank structure temperature, tank headspace pressure, flammable gas concentration, and primary tank and annulus leak detection. A current project will install instruments for monitoring mixer pump and transfer pump operation as well as flow, mass flow, and pump outlet pressure in pit piping jumpers.

2.3.4 SY Tank Farm

The 241-SY Tank Farm is made up of three 4,390 m³ (1.16 Mgal-) capacity DSTs (241-SY-101, -102, and -103). Tank 241-SY-102 contains approximately 2,800 m³ (730,000 gal) of waste that will be retrieved and delivered to the LAW/HLW Plant as HLW feed during Phase 1B privatization. The waste will be transferred to Tank 241-AZ-101 before it is sent to the LAW/HLW Plant.

Mixer Pumps. Two 224 kW (300-hp) mixer pumps will be required in Tank 241-SY-102 to mobilize and suspend the waste for retrieval. The mixer pumps will be provided as part of a current project.

Transfer Pumps. A transfer pump and jumper assembly will be required in the central pump pit to transfer the waste out of Tank 241-SY-102. A current project will design and install the retrieval equipment.

Diluent and Flush Subsystem. The existing system will be used for dilution and flushing of transfers from Tank 241-SY-102.

Ventilation Subsystem. The primary ventilation system serves all three 241-SY tanks. Air is directed through the tank and ductwork to a moisture separator, steam heater, and first and second stage HEPA filters before being exhausted out the stack. The exhaust stack is equipped with radiation monitors and alarms. System controls include pressure switches to control tank overpressurization or failure of the second HEPA filter. A trailer-mounted portable exhaustor is currently being used as a backup to the primary fan.

An exhaust fan provides annulus ventilation for the three tanks. Outside air is drawn into the annulus through HEPA-filtered intake stations at each tank. The exhaust is conveyed through ductwork to a moisture separator, steam heater, and first and second stage HEPA filters before being discharged out the exhaust stack. No back up system is available for the annulus exhaust system.

Instrumentation, Monitoring, and Control System. Instrumentation currently is in place to measure storage parameters including tank liquid level, tank waste temperature, tank structure temperature, tank headspace pressure, flammable gas concentration, and primary tank and annulus leak detection. A current project will install instruments for monitoring mixer pump and transfer pump operation, as well as flow, mass flow, and pump outlet pressure in pit piping jumpers.

2.3.5 Cross-Site Transfer System

The cross-site transfer system will be used to transfer wastes from the 241-SY Tank Farm in the 200 West Area to the 241-AN Tank Farm in the 200 East Area. The transfer system contains two separate double-encased transfer lines, one for transferring supernatant and the other for transferring slurry. Each line has a continuous leak detection cable located in the annulus space between the primary and secondary pipes. The HLW will be routed through the slurry line, which passes through one of two existing valve pits (241-SY-A and 241-SY-B), a diversion box,

and a vent station before arriving at the 241-AN Tank Farm. The diversion box contains two redundant booster pumps, which will only be used one at a time. The vent station contains a vent line that is supplied with a HEPA filter and two isolation valves.

Instrumentation is provided to monitor and control transfer system operation. Existing instrumentation includes pressure and temperature indication at the diversion box and vent station, continuous leak detection, booster pump VFDs and operating parameter indication, remote diversion box and vent system valve position indication, and vent line pressure indication.

2.3.6 200 East Area Tank Farms Transfer System

The existing 200 East Area Tank farms transfer system consists of a network of underground pipelines that are routed between various diversion boxes and pits and terminate at nozzles inside the pits. Routing jumpers can be attached to the nozzles to connect numerous transfer lines. The transfer lines are typically 5.1 or 7.6 cm- (2- or 3-in.-) diameter carbon or stainless steel and provided with a carbon steel or concrete encasement that is twice the diameter of the primary pipe. The pipe-in-pipe transfer lines are generally compliant except in some cases where the secondary containment does not extend through the pit walls. The concrete encased lines do not meet current secondary containment requirements. The transfer lines are sloped toward a pit on one end to allow waste left in the line to drain back and to allow waste leakage in the secondary containment to drain to the low point where a leak detection system is located. Leak detection consists of a conductivity probe located in the pit and/or a conductivity probe located in the transfer line secondary containment drain. The existing transfer lines need to be upgraded to meet waste feed delivery system requirements.

Valve pits provide a method to establish and change waste routings, through jumper changes, between the waste storage tanks and/or treatment facilities. Tank process pits (pump pits, drain pits, sluice pits, leak detection pits, annulus pump pits, etc.) provide tank access either to receive or remove waste. The existing valve and process pits need to be upgraded to minimize the number of components (e.g., valves, jumpers) to reduce the risk of transfer system upset.

In addition to the valve and process pits, the existing transfer system also contains certain ancillary components, including the following:

- Double-contained receiver tanks (DCRT), which provide small-capacity, short-term waste accumulation points
- Clean-out boxes (COB), which houses nozzles to clean out waste transfer lines in the event of line pluggage (The use of COBs has been discontinued.)
- Seal pots, which receive condensate drained from tank ventilation systems and return the condensate to the tanks via a dedicated drain line.

Current projects will replace the existing 200 East Area tank farm transfer system. Modification to the existing systems is required to

- Provide cross-site transfers directly from the 241-SY Tank Farm to the 241-AN Tank Farm
- Provide compliant transfer lines in the 200 East Area for waste feed delivery between the 241-AN, -AP, -AW, -AY, and -AZ Tank Farms and the LAW/HLW Plant interface point
- Provide instrumentation and controls for performing waste transfers including leak detection and valve indication
- Replace the existing Master Pump Shutdown System to provide transfer flexibility, increased reliability, and expandability to accommodate future system needs.

2.3.7 Changes In Retrieval Systems with the New Baseline Case 3S6D

The systems described above for DST farms are essentially unchanged from Case 3 to Case 3S6D. The SST farm involved in Case 3S6D (241-C Tank Farm) will be equipped with a different retrieval system. These systems (not yet defined) are to be installed by a current project and will undergo conceptual design in fiscal year 2001.

3.0 PROCESS CONTROL

3.1 DEVELOPMENT OF PROCESS CONTROL STRATEGY

The process control strategy was developed using the following tools:

- Existing references related to tank farm safety and operation
- A matrix indicating the selection of control variables related to each process concern
- A logic diagram detailing the logic sequence required to operate the system functions
- A task team that provided key decisions regarding process control logic.

The references are provided at the end of each text section following "*Basis:...*", in Section 4.0, and in Appendix A at the end of Tables A-1a, A-2a, and A-3a.

3.1.1 General Process Control Strategy Requirements

The general process control strategy requirements relating to safe storage, preparation, and transfer of waste were developed based on HNF-SD-WM-TSR-006, *Tank Waste Remediation System Technical Safety Requirements*; OSD-T-151-00007, *Operating Specifications for the 241-AN, AP, AW, AY, AZ, and SY Tank Farms*; OSD-T-151-00017, *Operating Specifications for Aging-Waste Operations in 241-AY and 241-AZ*; HNF-SD-WM-OCD-015, *Tank Farm Waste Transfer Compatibility Program*; and interface control documents, which require that certified waste be delivered to the LAW/HLW Plant. Listed under the appropriate functional decomposition in HNF-5136, these requirements are as follows:

Store Waste in East/West Area DSTs

- Receive waste
- Direct waste additions within DSTs
- Perform material balance
- Control DST hydrostatic loads
- Control DST primary confinement leaks
- Control DST tank and waste temperature
- Control DST chemical composition
- Control DST gaseous discharge

Prepare Waste in East/West Area DSTs

- Mobilize and suspend insoluble waste
- Monitor mixer pump operating parameters and control mixer pump operation
- Monitor in-tank components structural integrity
- Monitor tank and tank waste temperatures
- Control mixer pump operation to ensure maximum waste mobilization
- Add diluent to source tank

- Control in-tank additions
- Mix/blend waste
- Control mixer pump operation to ensure uniform waste blending
- Sample waste
- Perform waste compatibility assessment

Transfer Waste to HLW Staging Tanks

- Establish transfer route
- Verify transfer route
- Verify transfer component status
- Suspend waste
- Provide diluent during transfers
- Control in-line additions
- Convey waste
- Evaluate for line plugging
- Monitor transfer pump operation
- Monitor transfer jumper operation
- Confine waste leakage along transfer route
- Confine waste leakage within secondary confinement piping
- Confine waste leakage within transfer-associated structures
- Monitor for leaks in transfer-associated structures
- Transfer-associated structure leak detection
- Monitor for DST transfer pipe leakage
- Pipeline leak-detection monitoring
- Compare transfer structure leak detection data to process limit
- Compare transfer pipe leak detection data to process limit
- Shut down transfer pump through interface with Master Pump Shutdown System
- Perform material balance
- Flush transfer system
- Control transfer line flushes
- Deliver flush water to transfer-associated structures
- Monitor flush water supply to transfer structures
- Confine flush water within manifolds and jumpers
- Confine flush water within DST transfer piping
- Monitor transfer valve position
- Carry flush water to transfer pump suction
- Drain transfer piping
- Reconfigure transfer route
- Position valves for off-line service
- Monitor valve position

Transfer HLW Cross-Site

Same functions as "Transfer Waste to HLW Staging Tanks" except omit the following:

- Provide diluent during transfers
- Control in-line additions

Prepare HLW Sludges in HLW Staging Tanks

- Same functions as "Prepare Waste in East/West Area DSTs"

Transfer HLW Sludge to LAW/HLW Plant

- Same functions as "Transfer Waste to HLW Staging Tanks."

Because the "Prepare Waste in East/West Area DSTs" functions are the same as those in "Prepare HLW Sludges in HLW Staging Tanks," the functions are listed only once. Similarly, because the "Transfer Waste to HLW Staging Tanks" functions are the same as those in "Transfer HLW Sludge to LAW/HLW Plant," these functions are listed only once.

3.1.2 Process Control Strategy Matrices

The process control strategy matrices (Appendix A) were developed by observing the breakdown of storage, preparation, and transfer functions per HNF-5136, with associated process concerns, potential control variables, choice of controlling variables (monitored or controlled), and the basis for control-variable selection. The first set of matrices, "Existing Process Concerns" (Tables A1a, A2a, and A3a), defines existing process concerns and the basis for those concerns. The second set of matrices, "Control Variable Consideration for Future Development" (Tables A1b, A2b, and A3b), provide existing and potential future control variables. The matrices present a compact, quick reference for determining the basis for the selection of control variables, with traceability to the functional breakdown per HNF-5136.

The goal of the matrices is to develop the existing and future process control requirements. The matrices are set up as follows.

"Existing Process Concerns" (Tables A1a, A2a, and A3a):

- Column 1, "Flowsheet Process Step," is derived from the process flowsheets in the waste feed technical requirements, HNF-1939, Vol. II, Rev. 0a.
- Columns 2, 3, and 4, "DST 2nd Tier Function," "DST 3rd Tier Function," and "DST 4th Tier Function," are structured according to the HNF-5136.
- Column 5, "Associated Process Concerns," displays the process concerns that arise during operations indicated by the fourth-tier functions.
- Column 6, "Basis for Concerns," displays the basis for concerns. The bases for concerns include existing document requirements.

“Control Variable Consideration for Future Development” (Tables A1b, A2b, and A3b):

- Column 1, “Flowsheet Process Step,” is derived from the process flowsheets in the waste feed technical requirements, HNF-1939, Vol. II, Rev. 0a.
- Columns 2, 3, and 4, “DST 2nd Tier Function,” “DST 3rd Tier Function,” and “DST 4th Tier Function,” are structured according to the HNF-5136.
- Column 5, “Associated Process Concerns,” displays the process concerns that arise during operations indicated by the fourth-tier functions.
- Column 6, “Potential Control Variables,” displays examples of possible choices for control variables that meet the concerns indicated in Column 5.
- Column 7, “Choice Variables to be Controlled,” displays the selected control variables, based on historical usage, directness of measurement, and acceptable operability and maintainability.
- Column 8, “Monitor/Control,” displays the use of the variable, whether it is monitored and/or controlled.

3.1.3 Process Control Strategy Logic Diagram

The process control strategy logic diagram (Appendix B) contains the logic sequence associated with the requirements developed in the process control strategy matrices (Appendix A) and in Section 3.2. The logic diagram indicates the types of decisions required (administrative or control logic) to operate each type of function (storage, preparation, or transfer). Additionally, the logic diagrams show the dependence of operations on enabling functions. Thus, a satisfactory Store Waste enabling function must be maintained to prepare or transfer waste. Additionally, a satisfactory Prepare Waste enabling function must be maintained to transfer waste, and a satisfactory Transfer Waste enabling function must be maintained to continue waste transfer.

The process control strategy logic diagram contains symbols that indicate predefined functions (per HNF-5136), processes, manual operations, administrative decisions, control logic decisions, and enabling functions.

The process control strategy logic diagram also indicates which functions occur in parallel during system operation. Thus, Store Waste functions are occurring continuously while Prepare Waste and Transfer Waste functions are proceeding. Similarly, the Prepare Waste function occurs continuously while Transfer Waste functions are proceeding, and the Transfer Waste function occurs continuously while Store Waste functions are proceeding.

The decision blocks that have three lines indicate that the succeeding functions are continuously checked, while satisfactory conditions provide input to enabling functions and unsatisfactory conditions produce alarms to the operator. While inputs to an enabling function exist, the function is enabled.

3.1.4 Task Team Decisions

Several key decisions regarding the process control strategy logic were developed by a task team. These decisions are documented in Appendix C.

3.2 PROCESS CONTROL STRATEGY

The process control monitoring and control functions typically include the subfunctions of measuring parameters, comparing data measurements to operational limits, maintaining the parameters within limits, and responding to off-normal conditions. This document does not address the subfunction specifics of recovering from off-normal conditions. The specified operational limits are to be provided in the future process control plan. Prediction and mitigation of impending pipe plugging is included in the process control strategy.

3.2.1 Receive Waste

Staging of HLW for transfer to the LAW/HLW Plant will require the transfer of waste from source tanks to intermediate tanks, such as Tank 241-AN-104, and to staging tanks. This section discusses the process control strategy and requirements for receiving waste. This function is limited to those requirements that pertain only to the actual receipt of waste in the tank.

The process control strategy for receiving waste is to monitor the waste storage parameters specified in Section 3.2.2 and to monitor the parameters specific to waste receipt activities. Incremental transferring of the waste in batches will provide an additional measure of control. The process control strategy will ensure mass balance and control of temperatures, flammable gas, leak detection, and chemical composition.

For retrieval operations involving transfers, CPS-T-149-00010 requires that a criticality safety evaluation be performed per WHC-SD-SQA-CSA-20368.

3.2.1.1 Direct Waste Additions Within Double-Shell Tanks. Waste will be transferred into DSTs directly below the dome or through a drop leg or slurry distributor. The waste must be monitored to ensure that the transfer pump and mixer pumps will remain operable when the sludge depth exceeds the elevation of the pump intake. If the received or settled waste is expected to cover the pump suction, the mixer pumps may have to be operated either continuously or intermittently, to ensure that they will remain operational.

3.2.1.2 Perform Material Balance. A final material balance is required to be performed after transfers have been completed to verify that no leakage or misrouting has occurred. Verification of the volume of waste received will be determined by obtaining the waste level before and after the waste has been received, calculating the volume received, and comparing that value with the volume of waste transferred.

Basis: A material balance calculation is required during each waste transfer per HNF-SD-WM-TSR-006, Section 5.12.2.b.

3.2.2 Store Waste

Mixed wastes are stored in DSTs on an interim basis until they can be prepared and transferred to the LAW/HLW Plant for final treatment and disposal. The waste storage process control strategy pertains to the containment of waste stored in source or staging tanks during WFD operations. The process control strategy for monitoring and controlling waste storage, as described in this section, also applies during the waste preparation and waste transfer stages. Requirements to perform operations during waste storage and transfer are contained in HNF-SD-WM-TSR-006, OSD-T-151-00007, OSD-T-151-00017, and HNF-SD-WM-OCD-015. The basic process control strategy for containing waste in DSTs is to monitor and control the various parameters specific to tank integrity and waste containment.

The process requirements for monitoring these parameters are described in the following sections.

3.2.2.1 Control Double-Shell Tank Hydrostatic Loads. The hydrostatic head allowable on the primary tank wall is measured as the sum of the primary tank pressure and the tank liquid level, assuming a specific gravity (SpG) of 2.0. The maximum head is limited to meet seismic design criteria. In the event of an earthquake, a larger hydrostatic head could damage the tank because of hydrodynamic loading of the waste sloshing in the vessel. The minimum hydrostatic load is limited to prevent high stress to, and possible uplifting of, the tank bottom.

Minimum liquid levels are required (1) to allow the air-lift circulators (ALCs) in the aging waste tanks to be functional and (2) to block a pathway into the tank annulus. A minimum liquid waste height of 777 cm (306 in.) is required for operation of the seventeen 6.70 m (22-ft) long ALCs, and a minimum liquid waste height of 6.70 m (264 in.) is required for operation of the five 5.2 m (17-ft) long ALCs. The absolute minimum liquid-level limit with the annulus ventilation system operating is 160 cm (64 in.). This limit corresponds to the height that will cover the annulus pump pit and leak-detection pit drains, preventing a pathway for vapors to escape into the annulus. If the waste limit falls below the 160 cm (64-in.) limit, the annulus ventilation system must be shut off. When the annulus ventilation system is not operating, the minimum limit is that which will meet the allowable hydrostatic load.

Liquid-level measurements are currently taken with the ENRAF liquid-level monitoring instrument. As a backup to the ENRAF instrument, tank liquid level also can be measured with a manual tape instrument. If waste levels fall below the minimum limit, addition of dilution water or waste is required to bring the level back into compliance.

Basis: Requirements for control of DST hydrostatic loads are specified in OSD-T-151-00007, Sections 7.2.2 and 7.2.3, and OSD-T-151-00017, Section 17.2.1.1.

3.2.2.2 Control Double-Shell Tank Primary Confinement Leaks. Primary tank liner leak-detection instrumentation is required to be monitored throughout phases of the HLW feed delivery process to alert operators of the presence of a leak. Primary tank leak detection is performed by a continuous air monitor (CAM) in the annulus ventilation system, by conductivity probes mounted in the tank annulus, or by change in the tank annulus level as detected by ENRAF. The CAM is used to detect increases in radioactivity, indicating a potential leak into the annulus. An air sample is continuously extracted from the annulus exhaust flow upstream of

the HEPA filter and routed through the CAM, which monitors the sample flowstream for radionuclide particles. An increase in radioactive particle activity above the CAM setpoint will activate an alarm, signifying a potential leak. The conductivity probe has electrodes at different electrical potentials that are short-circuited by the conductivity of the waste leakage. The establishment of the short-circuit generates an alarm, signifying a leak. The State of Washington has approved the use of the ENRAF as a primary leak-detection method.

Waste leakage from the bottom of the aging waste tanks is collected in slots cut in the insulating concrete below the tank that have been designed to drain to a leak-detection pit. A leak from the primary tank will be contained in the annulus between the primary and secondary tanks. The annulus is designed to collect leaked waste at the annulus leak-detection pit in the annulus.

Basis: Requirements for control of DST primary confinement leaks are specified in WAC 173-303, "Dangerous Waste Regulations;" 40 CFR 264, "Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities;" DOE 5820.2A, Radioactive Waste Management; HNF-SD-WM-TSR-006, LCO 3.1.4; and OSD-T-151-00017, Section 17.2.1.2.A.

3.2.2.3 Control Double-Shell Tank and Waste Temperature. Tank waste temperatures will be monitored to ensure that temperatures necessary for potential tank bumps and for organic salt-nitrate reactions to occur are not exceeded. If either of these limits is exceeded, action shall be taken to mitigate the cause of the temperature increase and to restore waste temperatures to within allowable limits. Mitigation of high tank waste temperatures will be performed by (1) operation of the primary Ventilation Subsystem, (2) operation of the annulus ventilation system, and/or (3) shutdown of the mixer pumps.

The waste temperatures also are limited to prevent excessive stresses to the primary tank and structural degradation of the primary shell. High temperatures, rapid temperature cycling, and extreme temperature gradients can cause concrete temperature transients, which can cause concrete damage. Areas of high heat that have developed in the sludge may be mitigated by brief operation of the mixer pump.

Basis: Requirements for control of DST tank and waste temperatures are specified in HNF-SD-WM-TSR-006, SL 2.1, LCO 3.3.2; OSD-T-151-00007, Sections 7.2.6 and 7.2.7; and OSD-T-151-00007, Section 17.4.5.C.

3.2.2.4 Control Double-Shell Tank Chemical Composition. Stored waste composition will be monitored through periodic waste sampling and analysis. As applicable, the analysis may include measuring for chemical composition for control of tank bumps, temperature excursions, and tank corrosion.

Control of the waste chemical composition includes administratively controlling tank inputs, sampling waste periodically, comparing DST chemical composition to operational limits, and maintaining DST waste chemical composition.

Basis: OSD-T-151-00007, Section 7.2.1, "Basis for Limit" paragraph cites SD-WM-TI-150, Technical Basis for Waste Tank Corrosion Specifications, and TWRS-PP-94-025, Sludge Washing Materials Study: The Behavior of Carbon Steel in a Dilute Waste Environment, which

establish the technical basis for corrosion specifications to prevent corrosion/stress-corrosion cracking.

3.2.2.4.1 Control Tank Bumps and Temperature Excursions. Past operating experience in the aging waste farms led to adoption of the 5 molar sodium rule as a limiting operating specification. In the past, certain aging waste tanks containing excessive sodium salts were subject to bumping and to temperature excursions. The 5 molar sodium rule is intended to prevent bumping and temperature excursions by limiting the maximum sodium ion concentration in aging waste tanks to 5 molar.

3.2.2.4.2 Control Corrosion. Tank waste chemical composition (nitrite, nitrate, and hydroxide concentrations) is controlled to prevent tank bumping and temperature excursions caused by chemical reactions and to inhibit general corrosion, pitting corrosion, and stress-corrosion cracking. If these phenomena are not controlled, deterioration of the primary tank may occur at a faster rate.

A minimum concentration of waste hydroxide is required to keep aluminum dissolved in the aluminate form, inhibit the formation of gibbsite, inhibit general corrosion, inhibit pitting corrosion, and inhibit stress corrosion cracking.

Basis: Requirements for control of waste chemical composition are specified in OSD-T-151-00007, Section 7.2.1, and OSD-T-151-00017, Sections 17.4.1.1.2, 17.4.1.1.3, and 17.4.1.1.4.

3.2.2.5 Control Double-Shell Tank Gaseous Discharge. Operation of the primary tank Ventilation Subsystem is required to remove flammable gases from the tank vapor space and to control tank vapors and radionuclides exhausted from the tanks. The Ventilation Subsystem also will provide cooling of the waste. The primary process control strategy for verifying Ventilation Subsystem operation is to monitor tank vapor pressure to ensure that it is <0 kPa (0 in. water gauge [w.g.]). The requirement to maintain negative pressure in the primary tank ventilation system is given by HNF-SD-WM-TSR-006, Section 3.2.1, which indicates that the ventilation system must be operable and verified by primary tank vapor space being <0 in. w.g. Additionally, DOE Order 6430.1A, *General Design Criteria*, Section 1300, indicates that radiological enclosures maintain at least -0.3 in. w.g. Output from a tank vapor pressure transmitter can be continually monitored through a control room computer, recorded on a strip chart, or read from a local gauge. Ventilation Subsystem operation also can be verified by monitoring the airflow rate. Monitoring frequency shall be a minimum of once every 24 hours. This frequency was conservatively based upon the determination that the worst-case tank required 7 days to reach a lower flammability limit of 25 percent.

A CAM system is required on the primary and annulus Ventilation Subsystem exhaust stack to monitor and control the release of radionuclides in the tank exhaust. The exhaust stream will be monitored through isokinetic sampling. The CAM must measure the radiation level in the sampled flowstream and detect levels in excess of a preset level. The CAM shall activate an interlock to shut down the exhaust fan when preset radiation levels are exceeded. Upon CAM failure, the monitors must actuate an alarm and/or interlock to shut down the exhaust system.

If, after being mobilized and suspended, the waste is allowed to settle for a period of time such that gas is generated and accumulated within the waste, the gas could be released by operation of the mixer pumps.

Various instruments contained in the Ventilation Subsystem will be used to monitor increases in air emissions caused by mixer pump operation. Radiation readings also can be taken at these locations with hand-held instruments.

During the recent sluicing operation of Tank 241-C-106, the State of Washington approved the use of administrative controls if the ventilation system was inoperable. Thus, if the ventilation system was inoperable or tank vapor pressure was > 0 kPa (0 in. w.g.) at any time, personnel were evacuated. Personnel with respiratory personal protective equipment then would enter the area and reestablish the vacuum. Once vacuum was reestablished, the area would be monitored for the presence of organics and ammonia before personnel reentry. This administrative procedure may be applicable to future operations that involve the potential for gaseous discharges.

Basis: Requirements for gaseous discharge control are specified in WAC 173-400, "General Regulations for Air Pollution Sources;" WAC 173-460, "Controls for New Sources of Toxic Pollutants;" and 29 CFR 1910, Subpart Z, "Occupational Safety and Health Standards – Toxic and Hazardous Substances." Requirements for the CAM interlock that shuts down the Ventilation Subsystem when high radionuclide particulate activity is detected are specified in HNF-SD-WM-TSR-006, LCO 3.1.4, and WAC 246-247, "Radiation Protection – Air Emissions".

3.2.3 Mobilize and Suspend Insoluble Waste

Solids settled at the tank bottom may form a hard heel after extended settling times and must be mobilized before they can be suspended for retrieval and/or blended with other tank wastes. Wastes that have been initially mobilized, or wastes that are transferred into staging tanks from source tanks, may need to be remobilized if allowed to settle for long periods. The waste also may need to be kept in suspension if the settled waste depth would inhibit the operation of the mixer pumps or transfer pump. The waste retrieval system typically uses two 224 kW (300-hp) or four 112 kW (150-hp) variable-speed pumps. Each pump has two opposing submerged jets that discharge 180 degrees apart and approximately 46 cm (18 in.) above the tank bottom. The pumps also can be rotated at various speeds for 180 degrees in either direction about their vertical axis.

Both pumps are operated in the oscillating mode during waste mobilization. Scale-model mixer pump experiments at 1/12 scale (Fow 1987) have indicated that at least 90 percent of the waste can be mobilized using the two-mixer-pump system in Tank 241-AZ-101. It is expected that the mixer pumps will need to be operated longer and/or at a higher speed during initial mobilization of the waste than when the waste needs to be suspended for transfer. Operation of the pumps in both the fixed and oscillating modes may be required to mobilize the most waste. Operating parameters, including pump speed, pump oscillating speed, and duration of operation, will be better defined after a full-scale demonstration test in Tank 241-AZ-101 that is planned to be performed before retrieval operations begin.

For mixer pump operations in tanks where significant depths of solids will be added, the mixer pump specifications (HNF-4164, *Double-Shell Tank Mixer Pump Subsystem Specification*) includes a "Type 2" unit that utilizes mid-level suction and discharges near the bottom of the tank. Thus, the mixer pump can start with liquid at the suction and will discharge at an elevation where in-tank component deflection would be satisfactory. The discharge of the mixer pump jets must be at a location that is low enough to avoid structural damage to ALCs or other in-tank components.

Waste mobilization will be controlled to ensure safe operations, accomplish processing goals, and comply with technical operating requirements. The process control requirements during mobilization, the process control strategy, and the basis for those requirements are listed below.

Basis: Fow, et al., Development and Demonstration of Technology for Retrieving Waste from Double-Shell Tanks, 1987, DOE Contract DE-AC06-76RL01830. The mixer pump test is described in HNF-SD-WM-PTP-027.

3.2.3.1 Monitor Mixer Pump Operating Parameters and Control Mixer Pump Operation.

Mixer pump operation is monitored to ensure proper operation and mechanical integrity of the pump, to prevent premature pump failure, and to limit impingement on other in-tank equipment. Measured parameters will be used to detect mixer pump cavitation, plugged outlet nozzles, pump drive problems, and low-seal or bearing-water supply. Pump-specific parameters will be monitored as applicable per the Basis. General pump parameters, which will be monitored, include pump speed, motor current, and motor voltage.

Basis: WHC-SD-WM-DGS-006, Tank Farms Pump Critical Characteristics and Specification Guide, establishes the basis for controlling pump operation to maximize pump life and comply with safety requirements. WHC-SD-WM-DGS-006, Sections 4.2.2 and 4.6.5, establish the basis for monitoring motor power draw and rotational speed. The bases for monitoring bearing temperature, motor winding temperature, seal-water flow, and pump vibration are from HNF-4553, Operations and Maintenance Philosophy, and from vendor recommendations. The bases for monitoring position and rotation speed are WHC-SD-WM-DGS-006, Section 4.6.6, and WHC-SD-W151-ER-001, Stress Cycles and Forces on In-Tank Components Resulting from Mixer Pump Operation in DST 101-AZ (Design Input).

3.2.3.2 Monitor In-Tank Component Structural Integrity. The aging waste tanks contain several components that are supported from the tank dome and hang in the tank. These components include ALCs, dry wells, thermocouple assemblies, and a steam-coil assembly. Calculations and analyses have been performed to determine the loads imparted by the mixer pumps that these in-tank components could withstand. The calculations were performed based on an assumed sludge buildup on the components and corrosion factors. To mitigate the risk of a component failing and falling in the tank, it is required that the structural integrity of the in-tank components be monitored during mixer pump operations.

The process control strategy for ensuring the integrity of in-tank components during mixer pump operations will be to monitor component deflections using a closed-circuit television, and to compare the readings to calculated allowable values. If actual component deflections exceed allowable values, mixer pump operations may have to be altered. Options for mixer pump operation include running one pump instead of two, indexing the pump so that the jet does not

impinge directly on the component, running the pumps only in the fixed mode, or reducing the pump speed while passing the component.

A procedure has been developed for closed-circuit television use during the Tank 241-AZ-101 mixer pump test. Other aging waste tanks may require monitoring of component deflection. Monitoring requirements may be revised pending results of the test.

Basis: In-tank components in aging waste tanks may need to be monitored pending results of the Tank 241-AZ-101 mixer pump test. In-tank component loads were evaluated in HNF-SD-W151-DA-008, Evaluation of the Effect of Project W-151 Mixer Pump Jets on In-Tank Equipment Considering Potential Sludge Buildup on Equipment in Waste Tank 241-AZ-101, Hanford Site, Richland, Washington.

3.2.3.3 Monitor Tank and Tank Waste Temperatures. Thermal modeling of the current conditions in aging waste was performed to evaluate the tank temperature profile during mixer pump operation (Letter 8C453-97-KS-002, *Thermal Analysis in Support of Project W-151 Tank AZ-101 Mixer Pump Test*). Waste temperatures will increase because of the operation of the mixer pumps and/or the increased radiolytic heat load. The extended operation of the mixer pump during mobilization of the waste adds mechanical heat to the tank waste. Also, the mobilization of hot spot solids may increase certain readings. The waste temperature will continue to rise after the mixer pump has been turned off because of the increased “fluffed” sludge layer.

A temperature baseline will be established before any retrieval operations are performed. During retrieval operations, tank waste temperatures and insulating concrete temperatures will be monitored, and the observed temperatures will be correlated with heat balance data provided by the Ventilation Subsystem airflow rates. From these measurements, steady-state temperatures can be predicted and compared with the temperature limits and the expected thermal behavior as the retrieval progresses.

If tank temperatures approach or exceed allowable limits, mitigating actions will be performed. Temperature control may be accomplished by operating the primary and/or annulus ventilation systems, restarting the mixer pump to remix fluffed waste or mitigate hot spots, conducting the retrieval operation in increments, and/or operating the ALCs when the waste height will allow it.

Basis: Tank waste temperature requirements are specified in HNF-SD-WM-TSR-006, SL 2.1, LCO 3.3.2; OSD-T-151-00007, Sections 7.2.6 and 7.2.7; and OSD-T-151-00017, Section 17.4.5.C.

3.2.3.4 Control Mixer Pump Operation to Ensure Maximum Waste Mobilization. The effective cleaning radius (ECR) is defined as the extent that waste has been mobilized. This extent is determined by measuring the radial distance from the mixer pump centerline that the waste has been removed from the tank bottom. Measurement of the ECR is required to estimate the volume of sludge that can be successfully mobilized and retrieved so that planning for subsequent waste feed batches and volumes can be performed. This requirement will reduce the risk of not providing the minimum required feed volume to the LAW/HLW Plant.

The initial WFD operation will remove the settled sludge from the bottom of the tank and put the resulting waste particles into a fluid form. This waste mobilization activity is expected to require more extensive operation of the mixer pumps than when the waste solids are later suspended for transfer. The extent of mixer pump operation will be partially dependent on the waste-settling period before the waste is transferred.

Operation of the mixer pumps will mobilize the settled waste in a radial direction from the centerline of the mixer pump. The mixer pumps will be operated in an oscillating mode such that the two opposing discharge jets will rotate 180 degrees, thus covering the entire tank.

Instrumentation and methods to measure the ECR achieved by operation of the mixer pumps will be tested during the Tank 241-AZ-101 mixer pump test. The primary method to measure the ECR is to monitor the decrease in sludge thermocouple temperatures as the sludge is swept away from the thermocouple.

A correlation between mixer pump operating time and maximum sludge mobilization will be developed based on the results of Tank 241-AZ-101 mixer pump test.

Basis: HNF-SD-WM-PTP-027.

3.2.4 Add Diluent to Source Tank

The HLW may require in-tank treatment before it is transferred to the LAW/HLW Plant. Treatment may be in the form of diluent addition, caustic or other chemical addition, or a combination of both. In any case, the additions will originate from the same diluent/caustic supply system.

3.2.4.1 Control In-Tank Additions. Diluent may be added to the waste to adjust the waste composition determined by waste sample analysis or to meet tank control parameters. Additions may be required for chemical adjustment, to make the waste slurry more dilute for transfer, or for other reasons. Additions may be added either directly to the tank, as discussed in this section, or in-line as discussed in Section 3.2.9.

Dilution water is made up at the Diluent and Flush Subsystem. Caustic is delivered to the Diluent and Flush Subsystem by truck and pumped or unloaded into a blending tank. Raw water will be heated and also sent to the blending tank to be blended with the caustic. The blended solution will be pumped to the waste retrieval system as needed for in-tank dilution, pump intake dilution, line flushing, or transfer-line preheating. The Diluent and Flush Subsystem will supply hot water additions, chemical additions, or combinations of both.

The diluent/caustic solution will be supplied to the tank pump pit via a supply pipe. The supply pipe will connect to the piping jumper, which will allow the distribution of diluent directly into the tank through a diluent injection line that will transfer the diluent to the transfer pump inlet, or directly to the transfer line for preheating or flushing. In-tank dilution additions can be made either by routing the diluent directly into the tank or by routing it through the transfer pump and recirculating the discharge back into the tank.

Process control of the in-tank diluent additions will be provided by equipment and instrumentation at the Diluent and Flush Subsystem as well as at the pump pit. Diluent flow will be monitored and controlled as required, as well as diluent temperature and line pressure. The caustic addition supply line pressure will be monitored and compared to the pump discharge line to prevent any backflow through the supply line. Detection of high pressure in the supply line is required to actuate an alarm and/or provide an interlock to shut down the transfer pump.

Valve position indicators of the pit jumpers also will be monitored to verify the correct line configuration. The tank liquid level will be monitored during in-tank addition, per waste storage requirements (Section 3.2.2.1).

Basis: Requirements for control of in-tank additions are specified in OSD-T-151-00007, Sections 7.2.1, 7.2.2, and 7.2.3, and OSD-T-151-00017, Sections 17.2.1.1, 17.4.1.1.2, 17.4.1.1.3 and 17.4.1.1.4. Fill limits for diluent are specified in SD-RE-T1-008, 241-AW Tank Farm Process Specifications, Section 3.a.

3.2.5 Mix/Blend Waste

The HLW feed delivery strategy includes combining wastes from different source tanks into a single feed-staging tank. After the wastes are received, they will be blended together to make up a HLW feed. Mixing and/or blending of the waste will be performed by operation of mixer pumps.

Mixer pump operation for blending will be essentially the same as that for waste mobilization. Both pumps are planned to be operated concurrently in the oscillating mode to obtain the most uniform mixture, but it is expected that the pumps can be operated at a lower speed and/or for less time during blending than during waste mobilization, because the settled and compacted solids already have been mobilized.

Process control requirements for waste blending are essentially the same as for waste mobilization, because the operation is the same (see Section 3.2.3). The only difference is that mixer pump operation will be controlled for waste uniformity as described below.

3.2.5.1 Control Mixer Pump Operation to Ensure Uniform Waste Blending. Tank wastes must be certified before they are transferred to the LAW/HLW Plant for treatment. Samples typically will be taken at up to 20 separate elevations in the tank to ensure uniformity. Before being sampled, the wastes will be mixed or blended by operation of the mixer pumps to obtain a uniform consistency of the waste. Controls are required to determine the speed at which the mixer pumps need to be operated, how long the mixer pumps need to be run, and other modes of operation such as intermittent operation.

Waste uniformity during blending will be controlled by monitoring the waste profile during or immediately after mixer pump operation. Several methods can be used to perform this function, including measuring the suspended solids concentration, gamma activity above cesium, and slurry density, as a function of depth. In addition to slurry concentration profiles, slurry interface levels will provide additional information on waste uniformity.

Mixer pump operating parameters and operating time will be determined from models, experience of mobilizing other tanks, and from Tank 241-AZ-101 mixer pump tests.

Sampling of the waste will be required before transfer operations begin to verify that the waste slurry meets specification requirements per BNFL-5193-ID-20, *Interface Control Document for High-Level Waste Feed*.

As the waste is transferred out of the tank and the waste level is reduced, mixer pump operation may need to be altered to prevent unwanted conditions such as pump cavitation, the release of excessive aerosols into the tank head space, and excessive waste temperatures.

Basis: Waste will be blended by operation of the mixer pumps for a time period to be determined by HNF-SD-WM-PTP-027.

3.2.6 Sample Waste

Once the waste contained in staging tanks has been suspended, the pumps will be turned off and the tank waste will be sampled to verify that the waste concentrations are within the contractor specification limits and within site specifications for waste transfer. Sampling should be performed as soon as possible after the pumps have been turned off to provide a sample representative of a completely mixed tank without the effects of solids settling. When specification requirements are confirmed, waste transfer can begin. Waste samples provide data to perform the following:

- Determine the extent of waste blending uniformity
- Determine the waste solids concentration profile as a function of tank height
- Verify and calibrate operation of waste mobilization monitoring instruments
- Provide samples for the PC and archive.

Waste slurry grab samples will be taken, as a minimum, before each feed envelope is transferred to the LAW/HLW Plant for feed certification. For HLW, approximately equal volumes of grab samples will be taken from every 0.60 m (2 ft) of waste height below a single riser. The total sample volume will meet sample needs for analyses to support feed certification, a sample for the PC containing at least 200 g (0.44 lb) of solids, and an archive sample.

The interface control documents only require that waste be certified once. It is assumed that the waste characteristics will not change between sampling and transfer. Sampling is required only for staging tank certification.

Basis: Waste sampling requirements are specified in BNFL-5193-ID-20.

3.2.6.1 Waste Sampling Procedure. The HLW feed will be sampled and analyzed as follows.

1. Mobilize and suspend the waste using mixer pumps.
2. Immediately following the shutdown of the mixer pumps, obtain eight approximately equal volume grab samples of waste material, equally spaced over the height of the waste, from a single riser. Identify tank waste conditions, such as waste temperature and

tank volume, at the time of sampling. The bottom sample will be approximately 0.3 m (1 ft) above the bottom of the tank and the top sample will be approximately 0.3 m (1 ft) below the surface of the waste. As an alternative, core sampling may also be used, in which case the entire height of the tank waste will be obtained. The sample volume will meet the sample volume needs for analysis of the tank waste to support feed certification, a sample for the PC, and archive sample material. Tank archive sample material will be stored until the tank waste has been immobilized and accepted by the DOE.

3. Prepare a tank waste composite by combining equal quantities, by weight, of the grab samples for analysis and transfer to the PC and archive.
4. Use at least three subsamples of the composite sample for feed verification analysis. The arithmetic mean concentration for each analyte identified in the waste feed specification will be determined from the analysis of the three subsamples.
5. Certify the waste feed by combining information on the tank volume and tank waste composition. The mean composition of each of the analytes is determined by an analysis of the subsamples.
6. Determine the waste tank volume liquid level and calculate waste volume.
7. Measure and report the tank waste composition analytes to an accuracy identified in the contract documents.
8. Provide feed certification documentation to the PC that consists of a statement that the waste feed meets specification requirements, and provide the waste composition in the staging tank. The estimate of the composition of the HLW feed will account for the addition of dilution and flush water.

Basis: Waste sampling requirements are specified in BNFL-5193-ID-20, Section 3.2.6.1.

3.2.6.2 Waste Certification. The PC is responsible for notifying the Office of River Protection that they are ready to receive an HLW feed batch. Notification will confirm the following:

- The waste sample is within specification requirements
- The LAW/HLW Plant receiver tanks are empty and ready to receive waste
- The PC monitoring system, including connection to the Master Pump Shutdown System, is operational.

A number of steps is required (BNFL-5193-ID-20) to be performed before waste is transferred to the LAW/HLW Plant. At least 30 days before any transfers are performed, the DOE, Office of River Protection, is required to provide representative waste samples to the PC. Certification and documentation that the HLW feed batch meets contract requirements must accompany the samples. Just before initiating the transfer, the PC will provide verification that the PC systems for receipt of the waste, including receipt vessels, transfer lines, and monitoring instrumentation, are operational.

Basis: Waste certification requirements are specified in BNFL-5193-ID-20, Section 4.3.1.

3.2.6.3 Perform Waste Compatibility Assessment. Before any waste transfer in the DST System (i.e., transfers from waste feed source tanks to other tanks for staging), the proposed transfer will be evaluated to ensure continued safe storage and handling of these wastes during and after the transfer. Decision rules for assessing these parameters are included in HNF-SD-WM-OCD-015. The waste-compatibility assessment (WCA) will compare compositions of the waste source, waste receivers and transfer conditions as applied to safety, operational, regulatory and programmatic decision criteria. If the proposed transfer is determined to be acceptable, the decision is documented in the WCA with a recommendation for proceeding with the transfer. The documented WCA is signed by DST Farms Engineering, Process Engineering, and Environmental Permits/Policy before it is issued. Assessment documentation shall include, as a minimum, disposition of each applicable decision rule as listed in the HNF-SD-WM-OCD-015 Compatibility Compliance Table, the transfer requirements, and the WCA expiration date.

Basis: A waste compatibility assessment is required per HNF-IP-1266, Tanks Farms Operations Administrative Controls, Section 5.12, "Transfer Controls."

3.2.7 Establish Transfer Route

3.2.7.1 Verify Transfer Route. Transfer route verification reduces the risk of an accident caused by misroutings, equipment out of position, or equipment failure. The facility manager has the overall responsibility to ensure that pre-transfer requirements are met. The transfer route will be designated and maintained on an official routing board. Waste transfer system as-built drawings and jumper configurations are maintained as part of configuration management.

Independent verification will be performed to provide independent field verification. This will include verification that the transfer route is appropriate for the intended transfer, that piping and jumpers are in place per the configuration status controls, that correct and operable pumps are specified, and that valves are properly aligned. Inspections will be performed to ensure that open nozzles connected to jumpers in transfer routes will be sealed with caps, process blanks, or equivalent to prevent misroutings. The shift manager shall verify that the appropriate jumpers are indicated on the official routing board.

The specific procedure of verifying valve configuration between DOE and BNFL facilities will be elaborated upon in the future Process Control Plan. This could include agreement from both parties as signatories to the verification of valve configuration at separate facilities.

Basis: Waste transfer paths shall be isolated where valves exist, and an independent verification of the waste transfer route and valve status shall be performed before transfer, per HNF-SD-WM-TSR-006, Section 5.12.2.

3.2.7.2 Verify Transfer Component Status. The status of certain equipment and components related to the waste transfer is verified before the start of any waste transfers. Verification can be performed by data analysis or by confirmation of instrument readings or inspection records. The following conditions need to be verified:

- Newly installed jumpers have been leak tested before use
- Sufficient space is available in the receiver tank for the waste to be transferred
- Catch tanks that are physically connected to, but not in, the direct transfer route are less than 50 percent full before the waste transfer
- Primary Ventilation Subsystems of the affected receiving tanks are operable
- Preventive maintenance and surveillance or functional checks of instruments that are necessary for the waste transfer are current.

Basis: Transfer system components shall be checked for operability and calibration before a transfer per HNF-IP-1266. HNF-4553 establishes the need to ensure the flow is isolated during waste transfers. HNF-4533 is to be incorporated in the next revision of HNF-1939, Vol. IV, "Waste Feed Delivery Operations and Maintenance Concept."

3.2.8 Suspend Waste

Waste solids will be distributed throughout the supernatant to form a slurry that meets transfer requirements. It is important that the solids be mobilized as much as possible to minimize the amount of solids left for the final transfers. The objective is that the final batch transfers will require the addition of a minimum of dilution water to meet transfer requirements. The suction of the transfer pump will be near the bottom of the tank so that the maximum amount of the tank contents can be retrieved. The solids settling rate therefore also will be important in terms of the timing of the transfers and the need to operate the mixer pumps to maintain the uniform waste concentration.

Solids suspension will be performed by operation of mixer pumps. Mixer pump operation for solids suspension will be essentially the same as that for waste blending. Both mixer pumps are operated concurrently in the oscillating mode. Process control requirements for solids suspension will be the same as for waste blending (see Section 3.2.5). Controls are required to determine the speed at which the mixer pumps need to be operated, how long the mixer pumps need to be run, and other modes of operation such as intermittent operation.

The HLW in each staging tank will be transferred to the LAW/HLW Plant in a series of batch transfers. The time span between batch transfers could be over a year, allowing the waste solids to resettle at the bottom of the tank. In this case, the solids will have to be remobilized and/or resuspended prior to making the next transfer.

Basis: Waste solids are required to be suspended within the supernatant for transfer.

3.2.9 Provide Diluent During Transfers

HLW may require in-line diluent during transfer to the LAW/HLW Plant. Treatment may be in the form of water addition, caustic or other chemical addition, or a combination of both. In any case, the additions will originate from the same diluent/caustic supply system.

3.2.9.1 Control In-Line Additions. In-line dilution may be required for a variety of reasons, including heating of the transfer lines (not currently planned for HLW transfers), dilution of waste to meet transfer requirements, or flushing. Each application of caustic/diluent additions will require a different configuration; however, the control strategy is similar.

In-line dilution of the waste is not expected to be required for the initial feed transfers of waste currently stored in Tank 241-AZ-101; however, subsequent feeds from other source tanks likely will require in-line and/or in-tank dilution capabilities. In-line additions may be particularly useful when the staging tank is full or where there is an upset condition involving the transfer pump or the transfer line. Either process slurry or diluent introduced at the pump suction may be used for the initial startup of the pump. An advantage to using diluent is that it can be heated and used to preheat the transfer line before the process slurry is transferred. The transfer pump speed will be controlled during startup and operations through a VFD unit.

The diluent/caustic solution will be supplied to the pump pit via a supply pipe. The supply pipe will connect to a piping jumper located in the pump or valve pit, where different routing configurations can be set for different applications. To preheat or flush the transfer line, valves will be configured to introduce the diluent directly into the transfer line, bypassing the transfer pump. The line will be heated by filling the line with hot dilution and then closing the valves on either end to hold the solution in the line for a prescribed time. During filling of the line, flow will be controlled by a VFD on the Diluent and Flush Subsystem supply pump. Solution temperature, line pressure, and valve position also will be monitored.

In-line dilution will be accomplished by reconfiguring the valves so that diluent is introduced at the pump suction via a supply line originating in the pump pit. Various transfer parameters including pump amperage, flow, and in-line density will be monitored to determine the amount of dilution required. The transfer pump will be operated to pump the diluent to the pump discharge located in the pump pit, where it will be discharged into a transfer jumper for recirculation back into the tank or for transfer. After completion of the transfer, valves also may be configured to backflush through the pump.

Flushing of the transfer lines will be performed in the same manner as for preheating the transfer line. The only difference is that the flow will be open ended and will continue until the line has been flushed with a flush solution not to exceed twice the transfer-line capacity.

Process control of the in-line diluent additions will be provided by equipment and instrumentation at the Diluent and Flush Subsystem as well as at the pump pit. Diluent flow will be monitored and controlled as required, as will diluent temperature and line pressure. The caustic addition supply line pressure will be monitored and compared to the pump discharge line to prevent any backflow through the supply line. Detection of high pressure in the supply line actuates an alarm and/or provides an interlock to shut down the transfer pump. Valve position indication of the pit jumpers also will be monitored to verify the correct addition line configuration. The tank liquid level will be monitored during in-tank addition per waste storage requirements (Section 3.2.2.1).

Basis: In-line addition is required for transfer system flushing and may be required for in-line dilution of the waste stream.

3.2.9.2 Deliver Diluent to Transfer-Associated Structures. Diluent delivery to transfer-associated structures is controlled to prevent accidental overfilling of tanks, maintain the desired waste dilution ratio, and provide data for cross-checking other in-line instruments and completing material balances. If transfer lines are preheated, the control function also ensures adequate preheating of the transfer system. For diluent supply lines that are connected to the transfer system downstream of the transfer pump discharge, this function includes controls to prevent backflow of radioactive waste into diluent supply lines. Diluent delivery to transfer structures shall be controlled by monitoring diluent supply to transfer structures, comparing the system parameters to limiting control values, and maintaining diluent additions within limits.

3.2.9.3 Monitor Diluent Supply to Transfer Structures. Diluent supply is monitored to obtain data that are compared with predetermined or preset process limits or used to complete material balances. The system shall monitor the following parameters:

- Diluent flow rate
- Total diluent addition
- Diluent temperature.

The diluent chemistry is determined before addition and must meet compatibility requirements per HNF-SD-WM-TSR-006.

3.2.9.4 Provide Backflow-Detection Pressure Switches and Isolation Valves. Two isolation valves and two pressure switches per line shall be provided for diluent flush supply lines that connect to the transfer piping upstream of the transfer pump. The valves and pressure switches isolate the Diluent and Flush Subsystem from the transfer piping for backflow prevention.

Basis: HNF-SD-WM-SAR-067, Tank Waste Remediation System Final Safety Analysis Report, Section 4.3.6, establishes the basis for backflow prevention with pressure switches and isolation valves and extends the concept to raw water systems in general.

3.2.9.5 Compare Diluent Supply System Monitorings to Process Limits. The system compares data from the Monitor Diluent Supply to Transfer Structures function (Section 3.2.13.2) with process limits and initiates responses as follows.

- The Diluent and Flush Subsystem shall maintain the supply system temperature to be greater than or equal to the temperature of the waste to be transferred.
- The backflow-detection pressure switches shall provide an alarm signal to the Master Pump Shutdown Operator Station and actuate an interlock to shut down associated transfer pump operations.

Basis: HNF-SD-WM-SAR-067, Section 4.3.6.3, indicates that the pressure switch interlock system shall provide an alarm or actuate an interlock to prevent or stop operation of the associated pump when the pressure in the service water piping reaches a preset limit.

3.2.9.6 Confine Diluent within Valve Manifolds and Jumpers. Diluent is confined within valve manifolds and jumpers to provide primary confinement for diluent flow through diversion

boxes, valve pits, and pump pits. The diluent is confined along the supply route to ensure that the waste is sufficiently diluted for transfers.

Basis: DOE Order 6430.1A and the Standard Design Code requirements in ASME B31.3, Process Piping.

3.2.9.7 Confine Diluent Water Within Double-Shell Tank Transfer Piping. Diluent is confined within the double confinement system along the transfer route to prevent any leaks of radioactive diluent/waste that could increase the radiation dose to the operators and spread contamination.

Basis: WAC 173-303-640, "Tank Systems," DOE Order 6430.1A, Sections 1300-7.4 and 1323-5.2, and ASME B31.3.

3.2.9.8 Carry Diluent Water to Transfer Pump Suction. Diluent is supplied to the transfer pump suction to flush the transfer pump suction line before pump startup, desaturate salt solutions, dissolve incidental solids, and maintain the desired dilution ratio.

3.2.10 Convey Waste

Transfer system conditions and parameters will be monitored during the transfer to ensure that the HLW feed is delivered to the LAW/HLW Plant and to determine whether there are any upset conditions. The process control strategy will include monitoring for transfer-line leak detection, line pluggage, and other transfer parameters such as temperature, in-line density (tentative), and pressure. This section establishes how the transfer of wastes will be controlled to accomplish the processing goals and comply with technical operating requirements.

Communications are maintained between the tank farm operators and the PC during the waste transfer process. The PC facility manager will provide notification if a leak detector alarm is received at the LAW/HLW Plant that was initiated from the waste transfer pipeline or from within the HLW feed receipt process cell. Additionally, the LAW/HLW Plant manager will provide notification of monitoring instrumentation or Ventilation Subsystem malfunctions and will request that the transfer be halted should such malfunctions occur.

After receiving the HLW feed batch and transfer-pipeline flush, the LAW/HLW Plant manager will provide notification of the volume of waste received so that material balance calculations can be performed. Waste temperature changes and waste dissolution will be accounted for in material balance calculations.

The tank liquid level is measured during waste storage operations to establish a volume baseline before transfer operations begin. Mixer pumps will be shut down while liquid-level readings are taken.

The transfer pump suction will be located close to the tank floor, resulting in a waste heel of approximately 125 m³ (33,032 gal) remaining in the tank after the final batch has been transferred. The transfer line may need to be preheated to prevent the precipitation of gibbsite in the transfer lines. After each batch transfer, the transfer line will be flushed with a volume of

flush water, at a minimum of twice the transfer line capacity. After the flushing operation has been completed, the flush solution remaining in the line will be allowed to drain back to the source or staging tank and the receiver tank.

A waste transfer system will be used for transferring HLW feeds within the tank farms for staging and for transferring to the LAW/HLW Plant for processing. The transfer system is made up of an 80 mm (3-in.-) nominal diameter stainless steel and carbon steel primary pipe encased in a 150 mm (6-in.-) nominal diameter carbon steel pipe, which serves as secondary confinement along straight runs. At expansion loops, the encasement diameter increases to 12 in. Leakage from the primary transfer piping is detected and contained in the encasement piping. The pipeline is sloped downward toward the pump pit or valve pits, and a leak-detection element is located at the lower end of the secondary encasement pipe. The leak-detection elements in the pits will actuate an alarm and an annunciator light in the control room if a leak is detected, and the transfer will be terminated. Any leak in the transfer line will drain into the pump pit or valve pit, from which it subsequently will drain into the source tank, staging tank or LAW/HLW Plant tank.

3.2.10.1 Monitor Transfer Pump Operation. Transfer pumps will be a vertical turbine-type stick pump capable of transferring the waste at a minimum rate of 530 L/min (140 gal/min). The transfer pump suction will be located as near as possible to the tank floor to allow for maximum retrieval of the waste. The pump will be driven by an electric motor controlled by a VFD. The VFD controls pump-rotation speed and reports pump rotational speed and amperage to the control building. Pump speed and motor amperage will be used in conjunction with other data such as flow to verify that the pump is operating properly and to evaluate whether the transfer is proceeding satisfactorily.

Basis: WHC-SD-WM-DGS-006, Sections 4.2.2 and 4.6.5, establishes the bases for monitoring motor power draw and rotational speed. The basis for monitoring bearing and motor winding temperature is established in HNF-4553 and will be incorporated in the next revision of HNF-1939, Vol. IV.

3.2.10.2 Monitor Transfer Jumper Operation. A process transfer jumper will be installed in the pump pit for the purpose of directing the pump discharge flow to the transfer line or recirculating it back into the tank. The jumper will have a connection for receiving diluent from the caustic addition system for in-tank or in-line dilution and flushing. Switching between the various modes, such as between transfer and recirculation modes, is accomplished through three-way electric motor-operated valves. The following parameters are monitored to control the operation of the transfer jumper.

- A pressure relief system may be required to protect transfer system piping from overpressurization. The relief system will be located downstream of the pump outlet and will include a rupture disc, high-pressure switch with alarm, and pressure-relief valve. Fluid that passes through the rupture disc and pressure-relief valve is returned to the tank.
- The volumetric flow rate of waste discharged from the pump outlet is required as a basis for setting pump speed and the diluent flow setpoint. It also provides material-balance data and flow rate data to verify that the system is operating as expected and data for troubleshooting.

- Line pressure is monitored to detect pressure readings higher than expected for the measured flow rate, which may indicate that solids or other debris have accumulated in the line, that valves are not open all the way, that waste is more viscous than expected (for example transferring high solids content when not planned), or that there is an error in flow rate measurement. Pressure that is lower than expected may have one of several causes. If flow cannot be maintained at the rate indicated by the pump curve, this generally indicates pump cavitation if the pump power draw is low. Low outlet pressure also could indicate low pump suction pressure (high suction line pressure drop), restriction between pump and pressure tap, or other pump problems. Pressure measurement also may provide useful information during line flushing or attempts to remove solids accumulations or other line blockages.
- Discharge flow is required to compare pump operating parameters and pump curves. This parameter will be monitored in both the recirculation and the transfer modes.
- Volumetric flow rate and density is required to set transfer flow rate and provides the basis for establishing the diluent addition setpoint. Density measurement provides verification that the waste is being drawn in and that the diluent addition is reasonably close to what is expected. Higher than expected density indicates that solids are being drawn in or correct diluent flow is not entering the pump suction (for example, because of diluent misrouting, erroneous diluent flow rate measurement, or a diluent line broken or leaking at the pump). Lower than expected density indicates an excessive diluent-to-waste ratio (several possible causes) or liquid waste being drawn in when solids slurry is planned.
- Valve position indications are required to verify valve configuration.

Basis: Equipment and instrumentation contained in pump pits and valve pits shall be monitored for operability.

3.2.10.3 Monitor Process Parameters for Waste Transfer. Process parameters for waste transfer are monitored to prevent overpressurization of the lines, maintain the flow rate within specified limits, avoid solids buildup in the transfer lines, and ensure that sufficient diluent and/or flush water is supplied to maintain the rheological properties of the fluid within specified limits. Waste being delivered to the LAW/HLW Plant must also meet the contract specifications. Control of the process parameters for waste transfers includes measuring transfer stream parameters, comparing data with process limits, and maintaining transfer stream parameters within process limits.

Basis: WHC'-SD-WM-DGS-006, Table 4-1, establishes waste property limits after dilution at the pump suction. HNF-SD-WM-OCD-015 establishes waste compatibility and pumpability requirements.

3.2.10.4 Measure Transfer Stream Parameters. Transfer stream parameters are measured to detect impending transfer line plugging, a plugged pump inlet, higher-than-expected waste viscosity, or stream density that is outside of the acceptable range. The system shall monitor the following parameters:

- Transfer stream flow rate
- Transfer line pressure
- Transfer stream density (tentative)
- Transfer stream temperature (as part of densitometer functionality).

The tentative requirement to measure transfer steam density was determined during Task Team discussions.

Basis: HNF-SD-WM-OC'D-015 establishes waste compatibility and pumpability requirements. BNFL-5193-ID-20 establishes requirements for HLW transferred to the LAW/HLW Plant.

3.2.10.5 Compare Transfer Stream Data to Process Limits. The system compares data from the Measure Transfer Stream Parameters function (Section 3.2.12.7) to process limits and initiates the appropriate alarms. The responses shall include the appropriate alarms.

Basis: The basis for process limits and alarms will be developed from analysis of the requirements specified in WHC-SD-WM-DGS-006; HNF-SD-WM-OC'D-015; and HNF-SD-WM-SEL-040, Tank Waste Remediation System Facility Safety Equipment List. The analysis includes demonstrating the correlation between a requirement and the controlled parameter.

3.2.10.6 Evaluate for Line Plugging. Reasonable assurance must be obtained that transfer lines will not become plugged during waste transfers from source tanks to staging tanks, and from staging tanks to the LAW/HLW Plant. For waste streams where it is planned or suspected that solids will be entrained or formed during transfer, an analysis of the system flow conditions must be performed to assess the probability that line plugging can be avoided. For waste streams with < 5 percent solids by volume and a $SpG \leq 1.35$, no evaluation is required. The evaluation will be accomplished by obtaining and/or analyzing the following parameters:

- The carrier liquid density
- The particulate solids density
- The slurry density during transfer
- The system flow rate
- The particle-size volume distribution from which unhindered settling velocity can be determined
- The carrier liquid viscosity or some other analytical measure such as the maximum expected slurry temperature during transfer from which the carrier viscosity can be determined
- The volume percent solids.

The indicated parameters may not all be measurable and may be determined or obtained from past practice.

Basis: Evaluation for line plugging shall be performed per HNF-SD-WM-OC'D-015, Section 6.4, and per RPP-5346, Waste Feed Delivery Transfer System Analysis.

3.2.10.7 Confine Waste Along Transfer Route. The waste is confined in a double-confinement system along the transfer route to prevent any leaks of the radioactive waste that could increase the radiation dose to the operators and spread contamination and to ensure that adequate waste is transported to the LAW/HLW Plant to meet contractual quantities. Leakage from the primary piping drains to low points where leak detection is provided. Transfer-associated structures will have dedicated leak detectors. Confinement of waste includes monitoring for leakage, comparing the leak-detection data to the operational limit, initiating the appropriate alarm, and automatically shutting down transfer pump operation.

Basis: WAC 173-303-640; DOE Order 6430.1A, Sections 1300-7.4 and 1323-5.2; and ASME B31.3.

3.2.10.8 Confine Waste Within Valve Manifolds and Jumpers. Waste is confined in valve manifolds and jumpers to provide the primary containment for waste routed through diversion boxes, pump pits, and valve pits.

Basis: HNF-SD-WM-SAR-067 and ASME B31.3.

3.2.10.9 Confine Waste Within Double-Shell Tank Transfer Piping. Waste is confined in the double-containment DST transfer piping subsystem.

Basis: HNF-SD-WM-SAR-067; WAC 173-303; ASME B31.3; and DOE Order 6430.1A, Section 1323.

3.2.11 Confine Waste Leakage Along Transfer Route

Waste leakage from the primary transfer piping is confined in the secondary containment system along the transfer route. Transfer pipes and pits have leak-detection capability to determine a pipe or jumper leak. Leakage from the primary transfer piping (inner pipe) is contained in the secondary containment (outer pipe). The transfer lines are sloped so that any leakage will drain down to a low point, typically at the pump pit, which contains encasement leak-detection instrumentation. Pump pits also contain leak detectors with alarm functions in addition to a high capacity pit drain. The leak detector is designed to detect any leak in the pit from a variety of sources, including the transfer lines, new AZ transfer pit, transfer pump, and transfer pit jumper manifolds. If the leak detector alarms, the retrieval operation will enter a controlled shutdown. The new AZ valve pit will have its own leak-detection system. Transfer leak-detection systems are required to detect a 5.1-cm (2.0-in.) (maximum) accumulation of liquid waste in the bottom of the pit and shall provide an alarm when such an accumulation is detected.

Basis: Transfer system leak detection is required per HNF-SD-WM-TSR-006, Section 3.1.3; WAC 173-303; and DOE 6430.1A. The basis for the 2.0-in. detection limit is per HNF-SD-WM-SAR-067, Section 3.4.2.7.

3.2.11.1 Confine Waste Leakage Within Secondary Confinement Piping. Waste leakage from the primary piping primary containment is confined in the encasement piping, which directs the flow to a waste transfer-associated structure.

Basis: HNF-SD-WM-SAR-067, Section 4.3.5, and DOE 6430.1A, Section 1323-5.1

3.2.11.2 Confine Waste Leakage Within Transfer-Associated Structures. Waste leakage from valve manifolds and jumpers in transfer-associated structures is confined within the structure boundaries.

Basis: HNF-SD-WM-SAR-067 and WAC 173-303-640, (4).f.

3.2.11.3 Monitor for Leaks in Transfer-Associated Structures. The monitoring system shall detect leaks from the primary piping that flows into waste transfer-associated structures.

Basis: WAC 173-303-640, (4).f, and (4).b.i, and ii.

3.2.11.4 Transfer-Associated Structure Leak Detection. The transfer-associated leak detection system shall be capable of detecting a 5-cm (2-in.) maximum-deep accumulation at the bottom of the pit and shall provide an alarm when such accumulation is detected.

Basis: HNF-SD-WM-SEL-040, Section 6.8.1.4.

3.2.11.5 Monitor for Double-Shell Tank Transfer Pipe Leakage. The transfer piping is monitored for leakage from the primary confinement pipe into the secondary piping.

Basis: WAC 173-303-640, (4).b.ii.

3.2.11.6 Pipeline Leak-Detection Monitoring. The pipeline leak-detection system shall be capable of detecting a primary confinement boundary leak within 24 hours. Specific instrument requirements will be provided in the future process control plan.

Basis: WAC 173-303-640, (4).c.iii.

3.2.11.7 Compare Transfer Structure Leak-Detection Data to Process Limit. The system shall detect waste leaks in transfer-associated structures and either provide an alarm to alert operators to take mitigative actions or provide an interlock to shut down the transfer pump.

Basis: HNF-SD-WM-SAR-067, Section 4.3.17, establishes the basis for the alarm signal or transfer pump interlock to shut down pump operation on leak detection.

3.2.11.8 Compare Transfer Pipe Leak-Detection Data to Process Limit. The system shall compare the leak-detection data to the limit specified, initiate the appropriate alarm signal, and shut down the associated transfer pump operation by means of an automatic interlock.

Basis: WAC 173-303-640, (4).c.iii.

3.2.12 Flush Transfer System

When the transfer is complete, flush solution is supplied by the Diluent and Flush Subsystem to flush the transfer line. Flushing of the system will be required when the transfer has been interrupted because of an upset condition or when a transfer has been completed. Flush solution flow rate and total volume are monitored. When the desired quantity of flush solution has been transferred, the diluent pump is shut off. This function includes monitoring and delivering the flush solution to transfer-associated structures and confining the flush solution along the transfer route.

3.2.12.1 Control Transfer-Line Flushes. After each batch transfer, the transfer line will be flushed with a volume of flush water, at a minimum of twice the transfer line capacity. The flush will (1) prevent the potential buildup of unacceptable flammable gas concentrations in the transfer pipeline, (2) reduce personnel exposure during jumper changes, and (3) displace slurry from the transfer line.

Basis: Flushing of the transfer system is required after a transfer per HNF-1939, Vol. II, Rev. 0a, Section 3.1.3.

3.2.12.2 Deliver Flush Water to Transfer-Associated Structures. The routing of the flush water is controlled to ensure that the lines are adequately cleaned after waste transfer is complete, to minimize use of flush water to clean the lines, and to ensure that the pump receives flush water when the process is in the flush mode. Delivery of the flush water to transfer-associated structures includes monitoring flush water supply, comparing flush water data with process limits and initiating the appropriate action, and confining the flush solution along the transfer route. The total quantity of flush water added needs to be tracked for material balance calculations and to ensure that the waste meets the contractual specifications. Because flush water can be supplied to the transfer pump suction or downstream of the transfer pump discharge, this function includes controls to prevent backflow of radioactive waste into flush water supply lines.

Basis: HNF-1939, Vol. II, Rev. 0a, Section 3.1.3, establishes that the transfer lines are flushed before terminating the transfer. BNFL-5193-ID-20, Sections 4.1.3 and 4.2, require documentation of the flush solution volume and composition and limit the maximum flush volume to twice the transfer line capacity.

3.2.12.3 Monitor Flush Water Supply to Transfer Structures. Flush water supply is monitored to obtain data that are compared to predetermined or preset process limits or used to complete material balances.

Basis: BNFL-5193-ID-20, Sections 4.1.3 and 4.2, require documentation of the flush solution volume and composition and limit the maximum flush volume to twice the transfer line capacity. HNF-1939, Vol. II, Rev. 0a, Section 3.1.3, states that the flush solution is temperature-adjusted.

3.2.12.4 Confine Flush Water Within Valve Manifolds and Jumpers. Flush water is confined in valve manifolds and jumpers to provide the primary containment for flush water or waste routed through diversion boxes, pump pits, and valve pits. Section 3.2.11.4 contains the

flush water leak-detection requirements for leakage from valve manifolds and jumpers into transfer-associated structures.

Basis: HNF-SD-WM-SAR-067 and ASME B31.3.

3.2.12.5 Confine Flush Water within Double-Shell Tank Transfer Piping. Flush water is confined within the double-confinement piping system along the transfer route to prevent any leaks of radioactive flush water or waste that could increase the radiation dose to the operators and spread contamination. Section 3.2.15 contains the flush water leak-detection requirements for leakage from primary piping into secondary piping.

Basis: HNF-SD-WM-SAR-067; WAC 173-303-640; DOE Order 6430.1A, Sections 1300-7.4 and 1323-5.2; and ASME B31.3.

3.2.12.6 Position Valves for Flushing. The flushing route is established by positioning valves to ensure the transfer route is flushed and to prevent any misroutings. The required valves and positions will be identified and controlled through the applicable transfer procedure.

Basis: HNF-IP-1266, Chapter 5.12, "Transfer Controls," Section C.4.

3.2.12.7 Carry Flush Water to Transfer Pump Suction. Flush water is supplied to the transfer pump suction at a flow rate equal to the transfer pump flow rate, and the flush solution is pumped through the transfer piping.

Basis: HNF-1939, Vol. II, Rev. 0a, Section 3.1.3, establishes that the transfer lines are flushed before terminating the transfer.

3.2.13 Drain Transfer Piping

When the transfer line has been flushed sufficiently, the flush pump is shut off and the transfer lines are allowed to drain. A portion of the flush solution in the transfer line will drain to the staging tank, with the remainder draining to the LAW/HLW Plant receiver tank. This function is controlled by administrative procedures. No monitoring and control functions are associated with this function.

Basis: Flushwater will be allowed to drain back to the tank per HNF-1939, Vol. II, Rev. 0a, Section 3.1.3, "Process Description." WHC-SD-GN-DGS-30011, Radiological Design Guides, Section 3.4.2, establishes the basis for draining transfer lines.

3.2.14 Perform Material Balance

Material balance calculations are performed during transfer to provide early leak detection and avoid filling tanks above safe levels. The volume of waste transferred is monitored by comparing the waste volumes in the source tank and destination tank to the flow rate at the pump discharge. Waste volume measurements should account for any dilution addition before or during transfer and for any flushing performed after batch transfers.

Tank liquid levels are read and monitored before the transfer, at 30 minutes, 60 minutes, every 2 hours after starting the transfer pump, and after the transfer has been completed as required per HNF-IP-1266, Chapter 5.12. Flow readings are measured, recorded, and used to calculate materials balance. Waste transferred from the source tank will be estimated based on level drop, with adjustments for diluent addition at the pump suction, other water additions to the tank, trapped gas released during the transfer, and gas expansion as pressure on the retained gas is reduced. Waste temperature changes and waste dissolution can also have large impacts on material balance and must also be accounted for in calculations. A more complete material balance is calculated after each transfer. Final volume and sample analyses of waste in the destination tank are included to allow calculation of selected waste components delivered to the destination tank and the quantity remaining in the source or staging tank. The existing requirement for source or staging tank level agreement with destination tank level is likely to be inaccurate because of these factors. Consideration should be given to changing the requirement to transfer pump volumetric flowmeter/totalizer agreement with destination tank level changes, thus eliminating several uncertainties.

The requirement for liquid level measurements during mixer pump operation may not be met with current instrumentation. The 241-AZ-101 mixer pump test may determine whether this is possible. For material balance during mixer pump operation, it may be possible to use the transfer pump discharge volumetric flow rate (including the in-line dilution volumetric flow rate). This method has been accepted and was successful for recent transfers.

If periodic material balance calculations indicate a variance that exceeds the criteria, the transfer shall be stopped.

Analysis will be performed to model the temperature profile when source tank waste streams are added to staging tanks. Waste transfers will be controlled to ensure that waste temperatures remain below established temperature limits. Temperature control will be accomplished by operating the primary and annulus ventilation systems and by conducting retrieval in increments.

Tank waste temperatures and tank bottom temperatures are monitored, and the observed temperatures are correlated with heat-balance data provided by the Ventilation Subsystem airflow rates, temperatures, and humidities. From these measurements, steady-state temperatures can be predicted and compared with the temperature limits and the expected thermal behavior as the retrieval progresses. If, at any time during retrieval operations, the sludge temperature profile indicates a significant departure from the estimates, retrieval operations will be suspended to allow for further analysis of the tank conditions and to restore waste temperatures to allowable limits.

Basis: A material balance calculation is required during each waste transfer per HNF-SD-WM-TSR-006, Section 5.12.2.b.

3.2.15 Reconfigure Transfer Route

After completion of the transfer, line flush, and transfer line drain, the transfer route will be put in a configuration such that inadvertent operation of the transfer pump will not result in a transfer of waste to an unwanted location.

Basis: Transfer system configuration management requires that transfer paths be isolated from active waste transfer pumps per HNF-SD-WM-TSR-006, Section 5.12.2.

3.2.15.1 Position Valves for Off-line Service. The positions of transfer valves are controlled to ensure that they are in their predetermined off-line condition to prevent any misrouting of waste resulting from an inadvertent startup of the transfer pump. Control of the transfer valve positioning shall include maintaining an official routing board, independent field verification, and electronic monitoring of the transfer valve positioning.

3.2.15.2 Monitor Valve Position. The positions of transfer valves are monitored to ensure that they are in their predetermined off-line condition to prevent any misrouting of waste resulting from an inadvertent startup of the transfer pump.

3.3 INSTRUMENT AND EQUIPMENT REQUIREMENTS

Instrument and equipment will be required to ensure efficient and reliable WFD operations. Existing instrumentation can be utilized for monitoring and control of several of the WFD functions, particularly for Waste Storage functions. Additional instrumentation may be beneficial to monitor certain Prepare and Transfer Waste functions that are unique to WFD. For example, waste mixing and/or sludge mobilization efficiency will be measured by analyzing grab samples taken after the mixer pumps have been turned off. It would be more accurate if samples could be taken while the mixer pumps were still operating and before solids had begun to settle. Alternatively, it would certainly be less costly if the suspended solids concentration or waste density could be measured in situ without having to sample at all.

Currently, several prototype instruments are being developed, and commercially available instruments are being tested for use during WFD. Several of these instruments are being tested a part of the Tank 241-AZ-101 mixer pump test.

This process control strategy assumes that existing and proven instrumentation and equipment will be used for the monitoring and control of HLW feed delivery. If current instruments prove to be inadequate, the strategy will be revised as applicable to incorporate new instrumentation or equipment that has been developed and proven to be reliable.

3.4 CHANGES IN PROCESS CONTROL STRATEGY FROM CASE 3 TO CASE 3S6D

Section 3.0 is not tank-specific. Therefore, it applies equally to Case 3S6D DSTs, as it applies to Case 3 DSTs. For Case 3S6D SST retrieval, specific process controls will have to be developed.

This page intentionally left blank.

4.0 REFERENCES

- 29 CFR 1910, Subpart Z, "Occupational Safety and Health Standards – Toxic and Hazardous Substances," *Code of Federal Regulations*, as amended.
- 40 CFR 264, "Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities," *Code of Federal Regulations*, as amended.
- ASME B31.3, 1999, *Process Piping*, American Society of Mechanical Engineers, New York, New York.
- BNFL-5193-ID-20, 2000, *Interface Control Document For High-Level Waste Feed*, Rev. 4f, BNFL Inc., Richland, Washington.
- BNFL, 1996, *DOE Contract DE-AC06-96RL13308, Waste Treatment Plant*, as amended by Modification A012, Specification 8, "High-Level Waste Envelope Definition," January 2000, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- CPS-T-149-00010, 1998, *Criticality Prevention Specification*, Rev. 1-0, Lockheed Martin Hanford Corporation, Richland, Washington.
- DOE Order 5820.2A, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C.
- DOE Order 6430.1A, *General Design Criteria*, U.S. Department of Energy, Washington, D.C.
- Fow, C. L., P. A. Scott, G. A. Whyatt, and C. M. Ruecker, 1987, *Development and Demonstration of Technology for Retrieving Waste from Double-Shell Tanks*, Contract DE-AC06-76RL01830, U.S. Department of Energy, Richland, Washington.
- HNF-1939, Rev. 0a, 1999, *Waste Feed Delivery Technical Basis*, Vol. II, Addendum 1-1, "Waste Feed Delivery Flowsheet for Tank 241-AZ-101," Numatec Hanford Company for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-1939, 1999, *Waste Feed Delivery Technical Basis*, Vol. III, "Waste Feed Delivery System Description," Rev. 0, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-1939, 1999, *Waste Feed Delivery Technical Basis*, Vol. IV, "Waste Feed Delivery Operations and Maintenance Concept," Vol. III, Rev. 0, Lockheed Martin Hanford Corporation, Richland, Washington.
- HNF-2168, 2000, *Performance Requirements for the Double-Shell Tank System: Phase 1*, Rev. 1, CH2M HILL Hanford Group, Inc., Richland, Washington.

- HNF-2938, 1998, *Evaluation of 241-AN Tank Farm Supporting Phase 1 Waste Feed Delivery*, Rev. 0, Numatec Hanford Corporation and COGEMA Engineering Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-4155, 2000, *Double-Shell Tank Monitor and Control Subsystem Specification*, Rev. 0, CH2M HILL Hanford Group, Inc., Richland, Washington.
- HNF-4164, 2000, *Double-Shell Tank Mixer Pump Subsystem Specification*, Rev. 0, CH2M HILL Hanford Group, Inc., Richland, Washington.
- HNF-4553, 1999, *Operations and Maintenance Philosophy*, Rev. 0, Lockheed Martin Hanford Corporation, Richland, Washington.
- HNF-5136, 2000, *Functional Analysis for Double-Shell Tank Subsystems*, Rev. 0, CH2M HILL Hanford Group, Inc., Richland, Washington.
- HNF-IP-1266, 1999, *Tank Farms Operations Administrative Controls*, Rev. 2, DE&S Hanford, Inc., for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-SD-W151-DA-008, 1997, *Evaluation of the Effect of Project W-151 Mixer Pump Jets on In-Tank Equipment Considering Potential Sludge Buildup on Equipment in Waste Tank 241-AZ-101, Hanford Site, Richland, Washington*, Rev. 0, Fluor Daniel Northwest, Inc., for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-SD-WM-OCD-015, 1999, *Tank Farm Waste Transfer Compatibility Program*, Rev. 2, Lockheed Martin Hanford Corporation, Richland, Washington.
- HNF-SD-WM-PCP-013, 1998, *Tank 241-C-106 Waste Retrieval Sluicing System Process Control Plan*, Rev. 1, Lockheed Martin Hanford Corporation, Richland, Washington.
- HNF-SD-WM-PTP-027, 2000, *Mixer Pump Test Plan for Double-Shell Tank 241-AZ-101*, Rev. 4, COGEMA Engineering Corporation for CH2M HILL Hanford Group, Inc., Richland, Washington.
- HNF-SD-WM-SAR-067, 1999, *Tank Waste Remediation System Final Safety Analysis Report*, Rev. 1, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-SD-WM-SEL-040, 1998, *Tank Waste Remediation System Facility Safety Equipment List*, Rev. 1, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-SD-WM-SP-012, 1999, *Tank Waste Remediation System Operation and Utilization Plan to Support Waste Feed Delivery*, Rev. 1, Numatec Hanford Corporation, Lockheed Martin Hanford Corporation, and COGEMA Engineering Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

- HNF-SD-WM-TRD-007, 1998, *System Specification for the Double-Shell Tank System*, Rev. E, COGEMA Engineering Corporation/Numatec Hanford Corporation/TRW Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-SD-WM-TSR-006, 1999, *Tank Waste Remediation System Technical Safety Requirements*, Rev. 1, Fluor Daniel Hanford, Inc., Richland, Washington.
- Letter, 8C453-97-KS-002, 1997, *Thermal Analysis in Support of Project W-151 Tank AZ-101 Mixer Pump Test*, May 29, by K. Sathyanarayana, Numatec Hanford Corporation, Richland, Washington.
- OSD-T-151-00007, 1998, *Operating Specifications for the 241-AN, AP, AW, AY, AZ, and SY Tank Farms*, Rev. H-21, Lockheed Martin Hanford Corporation, Richland, Washington.
- OSD-T-151-00017, 1997, *Operating Specifications for Aging-Waste Operations in 241-AY and 241-AZ*, Rev. D-10, Lockheed Martin Hanford Corporation, Richland, Washington.
- OSD-T-151-00031, 1999, *Operation Specifications for Tank Leak Detection and Single-Shell Tank Intrusion Detection*, Rev. D-0, Lockheed Martin Hanford Corporation, Richland, Washington.
- RPP-5346, 2000, *Waste Feed Delivery Transfer System Analysis*, Rev. 0, L. J. Julyk and T. C. Oten, CH2M HILL Hanford Group, Inc., and W. L. Willis, Numatec Hanford Corporation, Richland, Washington.
- SD-RE-TI-008, 1980, 241-AW Tank Farm Process Specifications (Letter No. 65431-80-043 from F. R. Vollert to T. J. Ehli, April 4), Rockwell International, Richland, Washington.
- SD-WM-TI-150, 1984, *Technical Basis for Waste Tank Corrosion Specifications*, Rev. 0, Rockwell Hanford Operations, Richland, Washington.
- TWRS-PP-94-025, 1994, *Sludge Washing Materials Study: The Behavior of Carbon Steel in a Dilute Waste Environment*, Westinghouse Hanford Company, Richland, Washington.
- WAC 173-303, "Dangerous Waste Regulations," *Washington Administrative Code*, as amended.
- WAC 173-400, "General Regulations for Air Pollution Sources," *Washington Administrative Code*, as amended.
- WAC 173-460, "Controls for New Sources of Toxic Pollutants," *Washington Administrative Code*, as amended.
- WAC 246-247, 1999, "Radiation Protection—Air Emissions," *Washington Administrative Code*, as amended.
- WHC-SD-GN-DGS-30011, 1994, *Radiological Design Guides*, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

WHC-SD-SQA-CSA-20368, 1994, *C/SER 94-004: Criticality Safety of Double-Shell Waste Storage Tanks*, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

WHC-SD-W151-DA-008, 1997, *Evaluation of the Effect of Project W-151 Mixer Pump Jets on In-Tank Equipment Considering Potential Sludge Buildup on Equipment in Waste Tank 241-AZ-101, Hanford Site, Richland, Washington*, Rev. 0, Fluor Daniel Hanford, Inc., Richland, Washington.

WHC-SD-W151-ER-001, 1993, *Stress Cycles and Forces on In-Tank Components Resulting from Mixer Pump Operation in DST 101-AZ (Design Input)*, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

WHC-SD-WM-DGS-006, 1997, *Tank Farms Pump Critical Characteristic and Specification Guide*, Rev. 0, prepared by ARES Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

APPENDIX A

PROCESS CONTROL STRATEGY MATRICES

This page intentionally left blank.

Table A-1a. High-Level Waste Process Control Strategy Store Waste Function
Existing Process Concerns. (7 Sheets)

Process/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
Waste is initially stored in DSTs. Store supernate in staging tank Store sludge dissolute in staging tank	Store waste in East/West Area DSTs	Direct waste additions within DSTs		Material balance	<p>Ref. D, Section 7.2.2 minimum level for protection against tank bottom uplifting.</p> <p>Ref. A, for aging-waste tanks, Section 17.2.1.1 minimum level for ALC operation and minimum level for radioactivity containment</p> <p>Ref. E, Section to control waste accounting, leaks, hydrostatic load, and overflow of tank</p> <p>Ref. E, Verify waste receipt routing</p> <p>Ref. A, Section 17.2.3 for minimum and maximum hydrostatic load</p> <p>Ref. A, Section 17.2.3 Specific Gravity to be used with liquid level to determine tank hydrostatic load</p> <p>Ref. F</p> <p>Ref. H</p>
				Solids distribution	<p>Ref. E, Section to control waste accounting, leaks, hydrostatic load, and overflow of tank</p> <p>Ref. A, Section 17.2.3 for minimum and maximum hydrostatic load</p> <p>Ref. C, Sections 2.1.1 and 3.3.2 DST waste temperature</p> <p>Ref. D, Sections 7.2.6 waste temperature limits, rate of change, and gradients</p> <p>Ref. E, Section C.6 insoluble solids limit</p> <p>Ref. A, Section 7.2.7 structure damage</p> <p>Ref. E, Section C.6, Prevent waste pile up</p> <p>Ref. D, Sections 7.2.7.a and 7.2.7.b temperature limits and gradients applied to concrete to prevent structure degradation</p> <p>Ref. A, Sections 17.2.6.b dome concrete temperature limit and gradient prevent concrete degradation</p> <p>Ref. D, Sections 7.3.3 and 7.3.4 used to help control waste and structure temperatures</p> <p>Ref. A, Section 17.4.6</p>

Table A-1a. High-Level Waste Process Control Strategy Store Waste Function
Existing Process Concerns. (7 Sheets)

Flowsheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
				Compatibility	Ref. D, Section 7.2.1 nitrate, nitrite, and hydroxide concentrations, and Section 17.4.1.1.3 for 241-AZ tanks maximum hydroxide, and Section 17.4.1.1.4 for 241-AZ and AZ tanks maximum nitrite and nitrate, all for corrosion control Ref. G
				Tank thermal cycle	Ref. C, Sections 2.1.1 and 3.3.2 DST waste temperature. Ref. D, Sections 7.2.6 waste temperature limits, rate of change, and gradients Ref. D, Sections 7.2.7 a and 7.2.7 b temperature limits and gradients applied to concrete to prevent structure degradation Ref. A, Sections 17.2.6 b dome concrete temperature limit and gradient prevent concrete degradation Ref. D, Sections 7.3.3 and 7.3.4 used to help control waste and structure temperatures Ref. A, Section 17.4.6
				Tank ventilation overwhelmed	Ref. B, Section 4.3.2.1 to prevent the accumulation of flammable gases due to steady-state releases
				Criticality	Ref. O, Criticality evaluation required for waste transfer Ref. P
Store sludge decantate in staging tank		Control DST waste chemical composition	Monitor waste chemical composition Compare waste chemical composition to operating limits Maintain waste chemical composition	Tank corrosion	Ref. D, Section 7.2.1 nitrate, nitrite, and hydroxide concentrations Ref. A, Section 17.4.1.1.3 for 241-AZ tanks maximum hydroxide, and Section 17.4.1.1.4 for 241-AZ and AZ tanks maximum nitrite and nitrate, all for corrosion control

Table A-1a. High-Level Waste Process Control Strategy Store Waste Function
Existing Process Concerns. (7 Sheets)

Flowheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
				Flammable gas	Ref. E, Section C.6 insoluble solids limit Ref. A, Section 7.2.7 structure damage Ref. D, Section 7.2.1 nitrate, nitrite, and hydroxide concentrations, and Section 17.4.1.1.3 for 241-AY tanks maximum hydroxide, and Section 17.4.1.1.4 for 241-AY and AZ tanks maximum nitrite and nitrate, all for corrosion control Ref. C, Section 3.2.1 ventilation system operability to prevent accumulation of flammable gas in the tank headspace
				Temperature excursions	Ref. D, Section 7.2.1 nitrate, nitrite, and hydroxide concentrations, and Section 17.4.1.1.3 for 241-AY tanks maximum hydroxide, and Section 17.4.1.1.4 for 241-AY and AZ tanks maximum nitrite and nitrate, all for corrosion control Ref. C, Section 3.2.1 ventilation system operability to prevent accumulation of flammable gas in the tank headspace
				Vapor bubble	Ref. E, Section C.6 insoluble solids limit Ref. A, Section 7.2.7 structure damage Ref. C, Section 3.2.1 ventilation system operability to prevent accumulation of flammable gas in the tank headspace Ref. A, Section 17.2.3 for minimum and maximum hydrostatic load
				Structural damage of primary tank structure	Ref. C, Sections 2.1.1 and 3.3.2 DST waste temperature Ref. D, Sections 7.2.6 waste temperature limits, rate of change, and gradients Ref. D, Sections 7.3.3 and 7.3.4 used to help control waste and structure temperatures
		Control DST and waste temperature	Compare DST and waste temperature to operating limits Maintain DST and waste temperature		

Table A-1a. High-Level Waste Process Control Strategy Store Waste Function
Existing Process Concerns. (7 Sheets)

Flowheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
				Structural damage to concrete shell	Ref. D, Sections 7.2.7.a and 7.2.7.b temperature limits and gradients applied to concrete to prevent structure degradation Ref. A, Sections 17.2.6.b dome concrete temperature limit and gradient prevent concrete degradation Ref. B, Section 4.3.2.3 to prevent the accumulation of flammable gases due to steady-state releases
				Pressurization of tank	Ref. C, Sections 2.1.1 and 3.3.2 DST waste temperature Ref. D, Sections 7.2.6 waste temperature limits, rate of change, and gradients Ref. D, Section 7.2.1 nitrate, nitrite, and hydroxide concentrations, and Section 17.4.1.1.3 for 241-AY tanks maximum hydroxide, and Section 17.4.1.1.4 for 241-AY and AZ tanks maximum nitrite and nitrate, all for corrosion control
Waste is initially stored in DSTs Store supernate in staging tank Store sludge dissolve in staging tank	Store waste in East/West Area DSTs			Deflagration (org/nitrate)	Ref. A, Section 17.4.6 Ref. D, Section 7.2.1 nitrate, nitrite, and hydroxide concentrations, and Section 17.4.1.1.3 for 241-AY tanks maximum hydroxide, and Section 17.4.1.1.4 for 241-AY and AZ tanks maximum nitrite and nitrate, all for corrosion control Ref. E, Section 4.3 mixer pump used in staging tank to produce homogeneous mixture as feed
				Structural tank damage due to High waste level	Ref. D, Section 7.2.2 minimum level for protection against tank bottom uplifting Ref. A, for aging-waste tanks, Section 17.2.1.1 minimum level for ALC operation and minimum level for radioactivity containment Ref. A, Section 17.2.3 for minimum and maximum hydrostatic load Ref. A, Section 17.2.3 Specific Gravity to be used with liquid level to determine tank hydrostatic load
				Control DST hydrostatic loads	
				Monitor DST waste level Monitor DST vapor space pressure Monitor DST annulus pressure Compare DST hydrostatic loads to operating limits Maintain DST waste level	

Table A-1a. High-Level Waste Process Control Strategy Store Waste Function
Existing Process Concerns. (7 Sheets)

Flowheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
			Maintain DST vapor space pressure Maintain DST annulus pressure		<p>Rev. D, reduce tank liquid level below leak level</p> <p>Ref. E, Section C.6 insoluble solids limit</p> <p>Ref. A, Section 7.2.7 structure damage</p> <p>Ref. E, Section C.6, prevent waste pile up</p>
				Tank over/under pressurization	<p>Ref. C, Sections 2.1.1 and 3.3.2 DST waste temperature</p> <p>Ref. D, Sections 7.2.6 waste temperature limits, rate of change, and gradients</p> <p>Ref. B, Section 4.3.2.3 to maintain vapor space pressures of all tanks < 0 Kpa (< 0 in w.g.)</p>
				High/Low annulus pressure	<p>Ref. D, Sections 7.3.3 and 7.3.4 used to help control waste and structure temperatures</p> <p>Ref. A, Section 7.3.1 maximum pressure drop across system filters to protect filters and prevent release of radioactive species</p> <p>Ref. B, Maintain annulus pressure greater than or equal to primary tank pressure and less than or equal to atmospheric to prevent radioactivity release</p>
				Low liquid level (<10")	<p>Ref. A, Section 17.2.3 for minimum and maximum hydrostatic load</p> <p>Ref. D, Reduce tank liquid level below leak level</p> <p>Ref. D, Section 7.2.2 b. Detection of liquid level limits to prevent structure damage to primary and secondary tanks and to allow responsive monitoring of a radioactive material leak</p>

Table A-1a. High-Level Waste Process Control Strategy Store Waste Function
Existing Process Concerns. (7 Sheets)

Flowsheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basics for Concerns
Waste is initially stored in DST's. Store supernate in staging tank Store sludge dissolute in staging tank	Direct waste additions within DST's	Control DST primary confinement leaks	Monitor DST annulus for primary leaks Compare DST annulus leak detection data to operating limits	Undetected liquid leak from primary tank containment	Ref. B, Section 4.3.7.3 to detect primary tank leak Ref. B, Section 4.3.7.2 requires liquid level monitoring in annulus leak detection pit Ref. A, Section 17.2.3 for minimum and maximum hydrostatic load Ref. D, Reduce tank liquid level below leak level Ref. M Ref. H Ref. I
			Monitor DST vapor space pressure Monitor DST annulus pressure Compare DST vapor space pressure to operating limits Compare DST annulus pressure to operating limits Maintain DST vapor space pressure Maintain DST annulus pressure	Release to environment due to HEPA failure	Ref. C, Section 3.2.1 flammable gas level limits Ref. B, Section 4.3.19.1 CAM interlock system to shut down exhaust fan when high radionuclide activity is detected Ref. A, Section 17.4.7 Ref. D, Section 7.3.1 E design constraints limiting airborne emissions Ref. C, Section 3.2.1 Ref. D, Section 7.3.1 A gaseous discharge limits for primary and annulus Ref. J Ref. D, Section 7.3.1. A to prevent exhaust filter damage Ref. D, Section 7.3.1 B Air inlet air temperature limit to protect HEPA Ref. H

Table A-1a. High-Level Waste Process Control Strategy Store Waste Function
Existing Process Concerns. (7 Sheets)

FlowSheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
		Control DST gaseous discharge	Monitor DST gaseous discharge Monitor DST flammable gas concentration Compare DST gaseous discharge to operating limits Compare DST flammable gas concentration to operating limits Maintain DST gaseous discharge within limits	Gaseous release due to loss of vacuum	Ref. B, Section 4.3.2.3 to maintain vapor space pressures of all tanks < 0 Kpa (<0 in. w.g.) Ref. C, Section 3.2.1 flammable gas level limits Ref. L, Maintain < 0.3 in. w.g. Ref. A, Section 17.4.7 Ref. D, Section 7.3.1 E design constraints limiting airborne emissions Ref. H Ref. K Ref. C, Section 3.2.1 Ref. D, Section 7.3.1.A gaseous discharge limits for primary and annulus Ref. J Ref. D, Section 7.3.1 A to prevent exhaust filter damage

References:

- A. OSD-T-151-00017, 1997, *Operating Specifications for Aging Waste Operations in 241-A.Y and 241-AZ*, Rev. D-10, Lockheed Martin Hanford Corporation, Richland, Washington.
- B. HNF-SD-WM-SAR-067, 1999, *Tank Waste Remediation System Final Safety Analysis Report*, Rev. 1, Fluor Daniel Hanford, Inc., Richland, Washington.
- C. HNF-SD-WM-TSR-008, 1999, *Tank Waste Remediation System Technical Safety Requirements*, Rev. 1, Lockheed Martin Hanford Corporation, Richland, Washington.
- D. OSD-T-151-00007, 1998, *Unclassified Operating Specifications for the 241-AN, AP, AW, AY, AZ, & SY Tanks Farm*, Rev. H-21, Lockheed Martin Hanford Corporation, Richland, Washington.
- E. BNFL-5193-ID-20, 2000, *Interface Control Document for High-Level Waste Feed*, Rev. 4f, BNFL Inc., Richland, Washington.
- F. HNF-SD-WM-TRD-0071998, *System Specification of the Double-Shell Tank System*, Rev. 0-E, COGEM/Numatec/TRW Corporation, Richland, Washington.
- G. HNF-SD-WM-OC-D-015, 1999, *Tank Farm Waste Compatibility Program*, Rev. 2, Lockheed Martin Hanford Corporation, Richland, Washington.
- H. WAC-173-303, "Dangerous Waste Regulations," *Washington Administrative Code*, as amended, Olympia, Washington.
- I. 40 CFR 264, "Standard for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities," *Code of Federal Regulations*, as amended.
- J. WAC-173-400, 1997, "General Regulations for Air Pollutants Sources," *Washington Administrative Code*, as amended, Olympia, Washington.
- K. WHC-SD-WM-DGS-006, 1987, *Tank Farms Pump Characteristics and Specification Guide*, Rev. 0, ARES Corporation and Lockheed Martin Hanford Corporation, Richland, Washington.
- L. WAC-246-247, "Radiation Protection - Air Emissions," *Washington Administrative Code*, as amended, Olympia, Washington.
- M. DOE Order 5820.2A, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C.
- N. DOE Order 6430.1A, *General Design Criteria*, U.S. Department of Energy, Washington, D.C.
- O. CPS-T-149-00010, 1998, *Criticality Prevention Specification*, Rev. I-0, Lockheed Martin Hanford Corporation, Richland, Washington.
- P. WHC-SD-SQA-CSA-20368, 1994, CSER 94-004: *Criticality Safety of Double-Shell Waste Storage Tanks*, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Table A-2a. High-Level Waste Process Control Strategy Prepare Waste Function
Existing Process Concerns. (3 Sheets)

Process/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basic Tier Concerns
Mobilize waste for transfer	Prepare waste in West/East Area DSTs	Mobilize and suspend insoluble waste within West Area DSTs - Mobilize HLW	Mobilize HLW in source/staging tank	Mixer pump will fail	WHC-CM-WM-DGS-006
				Mixer pump is not operating efficiently	WHC-CM-WM-DGS-006
				Mixer pump is not oriented correctly	WHC-SD-W151-ER-001
				Mixer pump is not oscillating at the correct speed	WHC-SD-W151-ER-001
				Waste shear stress too high	HNF-1939
				UoD too low	HNF-1939
				In-tank components will fail structurally due to mixer pump forces	HNF-1939 HNF-SD-W151-DA-008
				Sludge cannot be mobilized for retrieval at "x" distances from mixer pump	HNF-1939 Fow et al.
				Sludge piles-up around the perimeter of the tank	HNF-1939 BNFL-5193-ID-20

Table A-2a. High-Level Waste Process Control Strategy Prepare Waste Function
Existing Process Concerns. (3 Sheets)

Flowsheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Beats for Concerns
		Mobilize and suspend insoluble waste within West Area DSTs - Diluent addition	Add Diluent to HLW source/staging tank	Diluent temperature is too low	
				Diluent supply pressure is low	
				Diluent addition causes tank to overflow	HNF-SD-RE-TI-006
				Diluent leak or misrouting due to valve position error	HNF-SD-WM-TSR-006
		Mobilize and suspend insoluble waste within West Area DSTs - Mix/blend HLW	Mix/blend HLW in source tank	Waste has not been blended to a uniform mixture	BNFL-5193-ID-20 HNF-SD-WM-OCD-015
				Waste at pump suction does not meet feed specification	BNFL-5193-ID-20 HNF-SD-WM-OCD-015
				Generation of off-gas LFL and organics	WAC 173-303 WAC 173-400
				Waste at pump suction does not meet transfer requirements	BNFL-5193-ID-20 HNF-SD-WM-OCD-015
		Mobilize and suspend insoluble waste within West Area DSTs - Sample HLW waste	Sample HLW source/staging tank	Waste is not sampled at a representative location	HNF-1939
				Assure waste is sampled while still uniformly blended	HNF-1939

Table A-2a. High-Level Waste Process Control Strategy Prepare Waste Function
Existing Process Concerns. (3 Sheets)

Flowheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
				Individual batches differ	BNFL-5193-ID-20 HNF-SD-WM-OCD-015
				Solids char. differ between sampling times and transfer time	BNFL-5193-ID-20 HNF-SD-WM-OCD-015
	Mobilize and suspend insoluble waste within West Area DSTs - Suspend solids	Suspend HLW in source/staging tank		The maximum amount of waste is not suspended	BNFL-5193-ID-20 HNF-SD-WM-OCD-015
				Assure mixer pumps are operated efficiently	WHC-SD-WM-DGS-006
	Mobilize and suspend insoluble waste within West Area DSTs - Mix/blend waste	Mix/blend HLW staging tank		Waste has not been blended to a uniform mixture	BNFL-5193-ID-20 HNF-SD-WM-OCD-015
				Waste at pump suction does not meet feed specification	BNFL-5193-ID-20

References:

- HNF-SD-WM-TSR-006, 1999, Tank Waste Remediation System Technical Safety Requirements, Rev 1, Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-1939, 1999, Waste Feed Delivery Technical Basis, Waste Feed Delivery Flowsheet for Tank AZ-101, Volume II, Rev. 0a, Numatec Hanford Corporation, Richland, Washington.
- BNFL-5193-ID-20, 2000, Interface Control Document for High-Level Waste Feed, Rev. 4f, BNFL Inc., Richland, Washington.
- HNF-SD-WM-OCD-015, 1999, Tank Farm Waste Transfer Compatibility Program, Rev. 2, Lockheed Martin Hanford Corporation, Richland, Washington.
- WHC-SD-W151-ER-001, 1993, Stress Cycles and Forces on In-Tank Components Resulting from Mixer Pump Operation in DST 101-AZ (Design Input), Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- HNF-SD-RE-TI-008, 1980, 241-AW Tank Farm Process Specifications, Vollett, F. R., Rockwell Hanford Operations, Richland, Washington.
- HNF-SD-W151-DA-008, 1997, Evaluation of the Effect of Project W-151 Mixer Pump Jets on In-Tank Equipment Considering Potential Sludge Buildup on Equipment in Waste Tank 241-AZ-101, Hanford Site, Richland, Washington, Fluor Daniel Northwest, Inc., for Fluor Daniel Hanford, Inc., Richland, Washington.
- Fow, C. L., P. A. Scott, G. A. Whyatt, and C. M. Ruecker, 1987, Development and Demonstration of Technology for Retrieving Waste from Double-Shell Tanks, U.S. Department of Energy Contract DE-AC06-76RL01830.
- WHC-SD-WM-DGS-006, 1997, Tank Farm Pump Characteristic and Specification Guide, Rev. 0, ARES and Lockheed Martin Hanford Corporation, Richland, Washington.

Table A-3a. High-Level Waste Process Control Strategy Transfer Waste Function
Existing Process Concerns. (3 sheets)

FlowSheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
Transfer waste	Transfer waste cross site/transfer waste to HLW staging tanks/ transfer HLW sludge to LAW/HLW plant	Establish transfer route for waste transfer	Position valves for transfer Monitor valve position	Assure valves are in the proper alignment for transfer	HNF-IP-1266 HNF-SD-WM-TSR-006
				Assure connecting piping is isolated by 2 closed valves	HNF-1939
				Assure valve position remains correct during transfer	HNF-IP-1266
	Confine waste along transfer route	Confine waste within DST transfer piping Confine waste within valve manifold and jumpers	Confine waste within DST transfer piping Confine waste within valve manifold and jumpers	Assure there are no leaks in the primary piping	HNF-IP-1266 HNF-SD-WM-TSR-006
				Assure there are no leaks in valve manifolds or jumpers	WAC-173-303-640 DOE Order 6430.1A ASME B 31.3
	Provide diluent during transfers		Deliver caustic of diluent to transfer associated structures Deliver caustic of diluent to transfer pump suction Confine caustic and diluent within valve manifolds and jumpers Confine diluent/flush waste within DST transfer piping	Assure that the correct amount of diluent is delivered	HNF-SD-WM-OCD-015
				Assure that the correct amount of diluent is delivered to the transfer pump suction	HNF-SD-WM-OCD-015
				Assure there are no leaks in valve manifolds or jumpers	HNF-IP-1266 HNF-SD-WM-TSR-006 DOE Order 6430.1A
				Assure there are no leaks in the primary piping	HNF-IP-1266 HNF-SD-WM-TSR-006 DOE Order 6430.1A

Table A-3a. High-Level Waste Process Control Strategy Transfer Waste Function
Existing Process Concerns. (3 sheets)

Flowsheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Basis for Concerns
Transfer waste	Transfer waste cross site/transfer waste to HLW staging tanks/ transfer HLW sludge to LAW/HLW plant	Convey waste	Pump waste Confine waste in transfer pump Monitor transfer pump operation Monitor process parameters for waste transfers	Assure waste concentration is within transfer and specification parameters	HNF-SD-WM-OCD-015 BNFL-5193-ID-20
				Avoid gelling, salt precipitation, and solids settling	HNF-1939
				Assure there are no leaks in transfer pump or jumpers	WAC 173-303
				Assure transfer pumps will operate during transfers	HNF-1939 WHC-SD-WM-DGS-006
				Assure transfer pump will not cavitate	HNF-1939
				Pump failure	HNF-1939 WHC-SD-WM-DGS-006
				Assure that transfer lines will not get plugged during transfer	HNF-SD-WM-OCD-015
				Assure no waste leaks from transfer pipe into the environment	HNF-IP-1266 DOE Order 6430.1A WAC 173-303
				Assure no waste leaks from transfer associated structures into the environment	WAC 173-303 DOE Order 6430.1A
		Confine waste leakage along transfer route	Confine waste leakage within secondary containment piping Monitor for DST transfer pipe leakage Confine waste leakage within transfer associated structures Monitor for leaks in transfer associated structures		

Table A-3a. High-Level Waste Process Control Strategy Transfer Waste Function
Existing Process Concerns. (3 sheets)

FlowSheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Beats for Concerns
Transfer waste	Transfer waste Cross Site/transfer waste to HLW staging tanks/ transfer HLW sludge to LAW/HLW plant	Flush transfer system	Deliver flush water to transfer associated structures	Leak of contaminated flush water	BNFL-5193-ID-20 DOE Order 6430 1A HNF-1939
			Confine flush water within valve manifolds and jumpers		
			Confine flush water within DST Transfer piping		
			Deliver flush water to transfer pump suction	Flush water misrouted	HNF-IP-1266
		Drain transfer piping			
				Misrouting of residual waste	HNF-1939
		Perform material balance for DST transfers		Material balance discrepancy	HNF-SD-WM-TSR-006
		Reconfigure transfer route	Position valve for offline service	Assure no accidental startup of the transfer pump will result in a waste misrouting	HNF-SD-WM-TSR-006
			Monitor valve position	Assure that all waste transferred has been received	HNF-SD-WM-TSR-006

References:

- HNF-IP-1266, *Tank Farms Operations Administrative Controls*, Rev. 1, DE&S Hanford, Incorporated, for Fluor Daniel Hanford, Inc., Richland, Washington.
- HNF-SD-WM-TSR-006, 1999, *Tank Waste Remediation System Technical Safety Requirements*, Rev. 1, Lockheed Martin Hanford Corporation, Richland, Washington.
- HNF-1939, 1999, *Waste Feed Delivery Technical Basis, Waste Feed Delivery Flowsheet for Tank AN-104*, Volume II, Rev. 0c, Numatec Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- WAC-173-303, "Dangerous Waste Regulations," Washington Administrative Code, Olympia, Washington.
- DOE Order 6430.1A, *General Design Criteria*, U.S. Department of Energy, Washington, D.C.
- ASME B31.3, 1999, *Process Piping*, American Society of Mechanical Engineers, New York, New York.
- BNFL-5193-ID-19, 2000, *Tank Waste Remediation System Privatization Project, Interface Control Document for Low Activity Waste Feed*, BNFL, Inc., Richland, Washington.
- WHC-SD-WM-DGS-006, 1997, *Tank Farms Pump Characteristic and Specification Guide*, Rev. 0, ARES Corporation and Lockheed Martin Hanford Corporation, Richland, Washington.
- HNF-SD-WM-OCD-015, 1999, *Tank Farm Waste Transfer Compatibility Program*, Rev. 2, Lockheed Martin Hanford Corporation, Richland, Washington.

Table A-1b. High-Level Waste Process Control Strategy Store Waste Function
Control Variable Consideration for Future Development. (6 Sheets)

Flowchart/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (assumed)	Choices of Variables to be Controlled	Monitor/Control
Waste is initially stored in DSTs. Store supernate in staging tank Store sludge dewater in staging tank	Store waste in East/West Area DSTs	Direct waste additions within DSTs		Material balance	Liquid/sludge level and specific gravity	Liquid/sludge level and specific gravity	M
					Leak detection	Leak detection	M, C
					Flowmeter totalizers	Flowmeter totalizers	M
					CCTV		
				Solids distribution	Waste temperature	Waste temperature	M
					Headspace temperature		
					Concrete temperature	Concrete temperature	M
					Annulus temperature		
					Slurry distributor nozzle location	Slurry distributor nozzle location	M, C
					Sampling/material balance of solids	Sampling/material balance of solids	M, C
				Compatibility	Solids content		
					ALCs		
					Samples for chemical composition prior to receipt		
					pH monitoring		
					Process knowledge	Process knowledge	M, C
					Electrochemical monitoring		
					Temperature of the waste	Temperature of the waste	M
					Temperature of the concrete	Temperature of the concrete	M
				Tank thermal cycle	Temperature of the headspace		
					Rate of waste addition		

Table A-1b. High-Level Waste Process Control Strategy Store Waste Function
Control Variable Consideration for Future Development. (6 Sheets)

Flowheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
					Temperature of the annulus		
					Waste analysis (BTU load)	Waste analysis (BTU load)	C
					HVAC flow rate	HVAC flow rate	M, C
					ALCs		
				Tank ventilation overwhelmed	Head space pressure	Head space pressure	M, C
					HVAC fan sizing	HVAC fan sizing	C
					Evacuation flow rate		
					HEPA, HEMA, HEGA differential pressure	HEPA, HEMA, HEGA differential pressure	M
Waste is initially stored in DSTs. Store supernate in staging tank	Store waste in East/West Area DSTs				CAM monitoring system	CAM monitoring system	M
					Moisture removal system	Moisture removal system	M
					Ventilation balance	Ventilation balance	C
					Waste flow rate		
					Volatile monitoring/control		
					Head space H2		
					Radiation monitoring		
Store sludge dissolve in staging tank				Tank corrosion	Off gas VOC by FID		
					Nitrate/nitrite concentrations	All monitored via chemical analysis/ process knowledge	M
					Hydroxide concentrations	NaOH additions	C
					Diluent addition	Water additions	C

Table A-1b. High-Level Waste Process Control Strategy Store Waste Function
Control Variable Consideration for Future Development. (6 Sheets)

FlowSheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
				Flammable gas	Organics	Nitrite additions	C
					Nitrate concentration	Waste transfer	C
					Ventilation balance	Ventilation balance	M
					Mixer pump operations	Mixer pump operations	M
					Radionuclides		
					Insoluble solids		
				Temperature excursions	Ammonia		
					Ventilation balance	Ventilation balance	M, C
					Mixer pump operations	Mixer pump operations	M
					Organics		
				Vapor bubble	Radionuclides		
					Organics		
					Ventilation balance	Ventilation balance	M, C
					Mixer pump operations	Mixer pump operations	M
					Radionuclides/fissile material		
					Insoluble solids		
					Sodium concentration		
	Control DST and waste temperature	Compare DST and waste temperature to operating limits Maintain DST and waste temperature	Structural damage of primary tank structure	Primary structure HVAC flow	Primary structure HVAC flow	Primary structure HVAC flow	M, C
				Annulus HVAC flow	Annulus HVAC flow	Annulus HVAC flow	M, C
				Waste temperature	Waste temperature	Waste temperature	M
				Waste transfer	Waste transfer	Waste transfer	C
	Structural damage to concrete shell			Concrete temperature	Concrete temperature	Concrete temperature	M
				Waste temp rate of rise	Waste temp rate of rise	Waste temp rate of rise	M
				Headspace temperature			

Table A-1b. High-Level Waste Process Control Strategy Store Waste Function
Control Variable Consideration for Future Development. (6 Sheets)

Flowsheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
				Pressurization of tank	Waste temperature Primary structure HVAC flow Chemical/radionuclide composition	Waste temperature Primary structure HVAC Chemical/radionuclide composition	M M, C C
Waste is initially stored in DSTs. Store supernate in staging tank Store sludge decantate in staging tank	Store waste in East/West Area DSTs			Deflagration (org/nitrate)	Sludge temperature Mixer pump ALCs Chemical/radionuclide composition	Sludge temperature Mixer pump Chemical/radionuclide composition	M C C
		Control DST hydrostatic loads	Monitor DST waste level Monitor DST vapor space pressure Monitor DST annulus pressure Compare DST hydrostatic loads to operating limits Maintain DST waste level	Structural tank damage due to: High waste level	Liquid level SpG Solids level Waste transfer	Liquid level SpG Solids level Waste transfer	M M M C
			Maintain DST vapor space pressure Maintain DST annulus pressure	Tank over/under pressurization	Head space pressure Primary HVAC rate	Head space pressure Primary HVAC rate	M M, C
				High/low annulus pressure	Annulus pressure Annulus HVAC rate	Annulus pressure Annulus HVAC rate	M M, C
				Low liquid level (<10")	Liquid level Waste transfer	Liquid level Waste transfer	M C

Table A-1b. High-Level Waste Process Control Strategy Store Waste Function
Control Variable Consideration for Future Development. (6 Sheets)

FlowSheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
Waste is initially stored in DSTs. Store supernate in staging tank Store sludge dissolute in staging tank	Direct waste additions within DSTs	Control DST primary confinement leaks	Monitor DST annulus for primary leaks Compare DST annulus leak detection data to operating limits	Undetected liquid leak from primary tank containment	Pit liquid level leak detection	Pit liquid level leak Detection	M, C
					Annulus exhaust CAM radiation detection	Annulus exhaust CAM radiation detection	M
					Tank liquid level	Tank liquid level	M
					Waste transfer	Waste transfer	C
					Other leak monitors		
			Monitor DST vapor space pressure Monitor DST annulus pressure Compare DST vapor space pressure to operating limits Compare DST annulus pressure to operating limits Maintain DST vapor space pressure Maintain DST annulus pressure	Release to environment due to HEPA failure	Primary ventilation stack monitoring	Primary ventilation stack monitoring	M
					Relative humidity of gaseous effluent stream	Relative humidity of gaseous effluent stream	M
					HEPA differential pressure	HEPA differential pressure	M
					Primary HVAC flow	Primary HVAC flow	M, C
					Toxic or radiological vapor concentrations	Toxic or radiological vapor concentrations	M
	Control DST gaseous discharge	Control DST gaseous discharge	Monitor DST gaseous discharge Monitor DST flammable gas concentration Compare DST gaseous discharge to operating limits Compare DST flammable gas concentration to operating limits Maintain DST gaseous discharge within limits	Gaseous release due to loss of vacuum or vapor bubble	Primary headsace pressure	Primary headsace pressure	M
					Primary HVAC flow rate	Primary HVAC flow rate	M, C
					HEPA differential pressure	HEPA differential pressure	M
					Mixer pump operation	Mixer pump operation	M, C
					Solids content	Solids content	C
					Flammable gas concentrations	Flammable gas concentrations	M

Table A-2b. High-Level Waste Process Control Strategy Prepare Waste Function Control Variable Consideration for Future Development. (4 Sheets)

FlowSheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (assumed)	Choice of Variable(s) to be Controlled	Monitor/Control
Mobilize waste for transfer	Prepare waste in West/East Area DSTs	Mobilize and suspend insoluble waste within West Area DSTs . Mobilize HLW	Mobilize HLW in source/staging tank	Mixer pump will fail	Pump flow rate	Pump flow rate	C
					Pump motor amperage	Pump motor amperage	M
					Pump rotational speed		
					Pump bearing temperature		
					Pump discharge pressure		
					Pump specific operating parameters	Pump specific operating parameters	M
				Mixer pump is not operating efficiently	Pump flow rate	Pump flow rate	C
					Pump motor amperage	Pump motor amperage	M
					Pump rotational speed		
					Pump bearing temperature		
					Pump discharge pressure		
					Pump specific operating parameters	Pump specific operating parameters	M
				Mixer pump is not oriented correctly			
					Nozzle orientation	Nozzle orientation	M
				Mixer pump is not oscillating at the correct speed	Oscillation speed	Oscillation speed	M, C
					Oscillation angles	Oscillation angles	M, C
				Waste shear stress too high	Discharge pressure	Discharge pressure	M
				UoD too low			

Table A-2b. High-Level Waste Process Control Strategy Prepare Waste Function
Control Variable Consideration for Future Development. (4 Sheets)

FlowSheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
				In-tank components will fail structurally due to mixer pump forces	Discharge pressure	Discharge pressure	M
					Component deflection		
					Component resonance frequency		
					Component strain		
					Nozzle orientation		
					Design strength	Design strength	C
				Sludge cannot be mobilized for retrieval at "x" distances from mixer pump	Effective cleaning radius		
					Pump speed		
					Pump discharge pressure	Pump discharge pressure	M, C
				Sludge piles-up around the perimeter of the tank	Pump orientation	Pump orientation	M, C
					Mixer pump discharge pressure	Mixer pump discharge pressure	M, C
					Mixer pump operation time	Mixer pump operation time	M, C
				Add diluent to HLW source/staging tank	Diluent temperature too low/high	Diluent supply temperature	M
					Diluent supply pressure too low/high	Diluent supply pressure	M
					Overfilling of DSTs with diluent	Tank liquid level	M
					Material balance	Material balance	M
					Diluent volume	Diluent volume	M, C
				Mobilize and suspend insoluble waste within West Area DSTs - Diluent addition	Leak detection		

Table A-2b. High-Level Waste Process Control Strategy Prepare Waste Function
Control Variable Consideration for Future Development. (4 Sheets)

Flowheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choses of Variables(s) to be Controlled	Monitor/Control
Mobilize waste for transfer	Prepare waste in West/East Area DST			Diluent leak or misrouting	Leak detection - line	Leak detection - line	M, C
					Leak detection - tank	Leak detection - tank	M, C
					Valve position	Valve position	M, C
					Tank liquid level	Tank liquid level	M
					Diluent flow rate		
	Mobilize and suspend insoluble waste within West Area DSTs - Mix/blend HLW		Mix/blend HLW in source tank	Waste has not been blended to a uniform mixture	Sampling	Sampling	M
					Mixing time	Mixing time	M, C
					Sampling	Sampling	M
					In-line instrumentation		
	Mobilize and suspend insoluble waste within West Area DSTs - Sample HLW waste			Waste at pump suction does not meet feed specification	SpG		
					pH		
					Pump discharge pressure	Pump discharge pressure	M, C
	Mobilize and suspend insoluble waste within West Area DSTs - Sample HLW waste			Generation of off-gas LFL and organics	Ventilation	Ventilation	M, C
					Sampling	Sampling	M
					In-line instrumentation		
	Mobilize and suspend insoluble waste within West Area DSTs - Sample HLW waste			Waste at pump suction does not meet transfer requirements			
	Mobilize and suspend insoluble waste within West Area DSTs - Sample HLW waste			Waste is not sampled at a representative location	Sample locations	Sample locations	M, C
					Lateral distribution of samples	Lateral distribution of samples	M, C
					Sampling	Sampling	M
					Mixing time	Mixing time	M, C
	Mobilize and suspend insoluble waste within West Area DSTs - Sample HLW waste			Assure waste is sampled while still uniformly blended	Waste characterization		

Table A-2b. High-Level Waste Process Control Strategy Prepare Waste Function
Control Variable Consideration for Future Development. (4 Sheets)

Process/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
				Individual batches differ	Mixing time	Mixing time	M, C
					Sampling	Sampling	M
				Solids char differ between sampling times and transfer time	Characterization of tank waste	Characterization of tank waste	M
					Lab turnaround time	Lab turnaround time	C
					Remixing	Remixing	C
				The maximum amount of waste is not suspended	Mixing time	Mixing time	M, C
					Mixer pump UoD	Mixer pump UoD	M, C
					Sampling	Sampling	M
				Assure mixer pumps are operated efficiently	Pump flow rate	Pump flow rate	M, C
					Pump motor amperage	Pump motor amperage	M
					Pump rotational speed		
					Pump bearing temperature		
					Pump discharge pressure		
					Sampling		
					Pump specific operating parameters	Pump specific operating parameters	M
	Mobilize and suspend insoluble waste within West Area DSTs - Mix/blend waste	Max/blend HLW staging tank		Waste has not been blended to a uniform mixture	Sampling	Sampling	M
					Mixing time	Mixing time	M, C
					Waste characterization		
				Waste at pump suction does not meet feed specification	Sampling	Sampling	M
					In-line instrumentation		

Table A-3b. High-Level Waste Process Control Strategy Transfer Waste Function
Control Variable Consideration for Future Development. (5 Sheets)

Flowheet/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
Transfer waste	Transfer waste cross Site/transfer waste to HLW staging tanks/transfer HLW sludge to LAW/HLW plant	Establish transfer route for waste transfer	Position valves for transfer Monitor valve position	Assure valves are in the proper alignment for transfer	Leak detection	Leak detection	M, C
					Valve positioning	Valve positioning	M, C
				Assure connecting piping is isolated by 2 closed valves	Valve positioning	Valve positioning	M, C
				Assure valve position remains correct during transfer	Leak detection	Leak detection	M, C
					Valve positioning	Valve positioning	M, C
					Tank liquid level	Tank liquid level	M
					Waste flow rate		
					Material balance		
					Line pressure		
				Assure there are no leaks in the primary piping	Leak detection	Leak detection	M, C
					Valve positioning		
					Tank liquid level	Tank liquid level	M
					Waste flow rate		
					Material balance	Material balance	M
					Line pressure	Line pressure	M
					Encasement leak detection	Encasement leak detection	M
				Assure there are no leaks in valve manifolds or jumpers	Leak detection	Leak detection	M, C
					Valve positioning		
					Tank liquid level	Tank liquid level	M
					Waste flow rate	Waste flow rate	M, C
					Material balance	Material balance	M

Table A-3b. High-Level Waste Process Control Strategy Transfer Waste Function Control Variable Consideration for Future Development. (5 Sheets)

Flowheet/Process Step	D&T 2nd Tier Function	D&T 3rd Tier Function	D&T 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control				
		Provide diluent during transfers	Deliver diluent to transfer associated structures	Assure that the correct amount of diluent is delivered	Metering pump flow rate	Metering pump flow rate	M, C				
			Deliver diluent/flush water to transfer pump suction		Diluent supply flow rate	Diluent supply flow rate	M, C				
			Confine diluent within valve manifolds and jumpers		Line pressure						
					Material balance	Material balance	M				
			Confine diluent/flush water within DST transfer piping	Waste flow rate							
			Assure that the correct amount of diluent is delivered to the transfer pump suction	Metering pump flow rate	Metering pump flow rate	M, C					
				Diluent supply flow rate	Diluent supply flow rate	M, C					
				Material balance	Material balance	M					
			Assure there are no leaks in valve manifolds or jumpers	Leak detection	Leak detection	M, C					
				Valve positioning	Valve positioning	M, C					
				Tank liquid level	Tank liquid level	M					
				Waste flow rate							
Assure there are no leaks in the primary piping	Material balance	Material balance	M								
				Assure waste concentration is within transfer and specification parameters	Leak detection	Leak detection	M, C				
					Valve positioning						
					Tank liquid level	Tank liquid level	M				
					Waste flow rate						
					Material balance	Material balance	M				
					Line Pressure						
					Convey waste	Pump waste			Sampling	Sampling	M

Table A-3b. High-Level Waste Process Control Strategy Transfer Waste Function
Control Variable Consideration for Future Development. (5 Sheets)

Flowheet/Process Step	D&T 2nd Tier Function	D&T 3rd Tier Function	D&T 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
Transfer waste	Transfer waste cross Site/transfer waste to HLW staging tanks/transfer HLW sludge to LAW/HLW plant		Confine waste in transfer pump Monitor transfer pump operation Monitor process parameters for waste transfers		Waste concentration profile		
					Sludge layer interface elevation		
					Solids settling rate		
				Transfer pump failure	Pump discharge pressure	Pump discharge pressure	M
					Pump suction location	Pump suction location	M, C
					Pump power	Pump power	M
					Pump rotational speed		
					Pump motor amperage	Pump motor amperage	M
					Pump bearing temperature		
					Seal water flow		
					Pump specific operating parameters	Pump specific operating parameters	M
					Waste properties		
				Avoid gelling, salt precipitation, and solids settling	Mixing time	Mixing time	M, C
					Waste characterization	Waste characterization	M
					Solids Settling time		
					Sampling		
				Assure there are no leaks in transfer pump or jumpers	Transfer pit leak detection	Transfer pit leak detection	M
					Material balance	Material balance	M

Table A-3b. High-Level Waste Process Control Strategy Transfer Waste Function
Control Variable Consideration for Future Development. (5 Sheets)

Process/Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (examples)	Choice of Variable(s) to be Controlled	Monitor/Control
				Assure transfer pump will not cavitate	Pump discharge pressure	Pump discharge pressure	M
					Pump suction location	Pump suction location	M, C
					Pump power	Pump power	M
					Pump rotational speed		
				Assure that transfer lines will not get plugged during transfer	Change in differential pressure in transfer lines	Change in differential pressure in transfer lines	M
					Pump discharge pressure	Pump discharge pressure	M
					Waste SpG		
					Flow rate	Flow rate	M, C
			Confine waste leakage along transfer route Confine waste leakage within secondary containment piping Monitor for DST transfer pipe leakage Confine waste leakage within transfer associated structures Monitor for leaks in transfer associated structures	Assure no waste leaks from transfer pipe into the environment	Line pressure		
					Waste flow rate	Waste flow rate	M
					Encasement leak detection	Encasement leak detection	M
					Waste transfer	Waste transfer	C
					Leak detection - line	Leak detection - line	M, C
					Material balance	Material balance	M
					Line pressure		
					Encasement leak pit liquid level	Encasement leak pit liquid level	M
					Waste transfer	Waste transfer	C
					Leak detection - line	Leak detection - line	M, C
					Material balance	Material balance	M

Table A-3b. High-Level Waste Process Control Strategy Transfer Waste Function
Control Variable Consideration for Future Development. (5 Sheets)

Flowchart/Process Step	DST 2nd Tier Function	DST 3rd Tier Function	DST 4th Tier Function	Associated Process Concerns	Potential Control Variables (assumed)	Choice of Variables to be Controlled	Monitor/Control
Transfer waste	Transfer waste cross Site/transfer waste to HLW staging tanks/transfer HLW sludge to LAW/HLW plant	Flush transfer system	Deliver flush water to transfer associated structures	Leak of contaminated flush water	Line pressure	Line pressure	M, C
			Confine flush water within valve manifolds and jumpers		Leak detection-line	Leak detection-line	M
			Confine flush water within DST transfer piping		Limit flush volume	Limit flush volume	C
			Deliver flush water to transfer pump suction				
	Drain transfer piping			Flush water misrouted via transfer pump, waste mixes with flush water	Valve position	Valve position	M, C
	Perform material balance for DST transfers			Misrouting of residual waste	Valve position	Valve position	M, C
	Reconfigure transfer route		Position valve for offline service	Material balance discrepancy	Tank liquid level	Tank liquid level	M
					Material balance calc	Material balance calc	M
				Assure no accidental startup of the transfer pump will result in a waste misrouting	Transfer pump lockout	Transfer pump lockout	C
			Monitor valve position	Assure that all waste transferred has been received	Material balance	Material balance	M

This page intentionally left blank.

APPENDIX B

PROCESS CONTROL STRATEGY LOGIC DIAGRAMS

This page intentionally left blank.

Off-Normal
Conditions

APPENDIX C

**HIGH-LEVEL WASTE PROCESS CONTROL STRATEGY TASK TEAM
DECISIONS MEETINGS MINUTES**

This page intentionally left blank.

FOSTER WHEELER ENVIRONMENTAL CORPORATION

April 16, 2000
FWRD-ADM-00-024

Tom Conrads,
CH2M Hill Hanford Group, Inc.
P.O. Box 1500
MS R3-73
Richland, WA 99352

**SUBJECT: LAW AND HLW PROCESS CONTROL STRATEGY TASK TEAM
DECISIONS MEETINGS MINUTES**

Dear Mr. Conrads:

Attached are the results of a series of meetings held on 2/10/00, 2/14/00, and 2/22/00 to resolve key issues which have arisen during the production of the LAW/HLW process control strategy logic drawings. The purpose of this letter is to document these decisions as a basis for formalizing parts of the Process Control Strategy (PCS). Attendees on 2/10/00 included C. Grenard, T. Staehr, P.E., R. Bafus, R. Orme, D. Tulberg, P.E., C. Weingardt and M. Dippre, P.E. Attendees on 2/14/00 included T. Staehr, R. Bafus, R. Orme, C. Weingardt, and M. Dippre. Attendees on 2/22/00 included C. Grenard, T. Staehr, R. Bafus, R. Orme, C. Weingardt, and M. Dippre. The resolved issues will be integrated into the PCS Logic drawings.

Please contact me at (425) 688-3749 or Connie Weingardt at (509) 373-0000 if you have any questions or concerns regarding these documents.

Sincerely,

D. Mark Gerboth, P.E.
Western Region Engineering Manager
Foster Wheeler Environmental Corporation

DMG/jbw

Attachment(s)

cc: Dean Tulberg
Marc Dippre
Connie Weingardt
Charles Grenard

The resolutions of issues from these meetings are grouped according to the Functional Analysis 2nd Tier breakdowns:

Store Waste (LAW / HLW):

1. The air lift circulators are not planned to be maintained operable for WFD. The reference to them as a method for controlling tank and waste temperature should be deleted.
2. References to the specific thermocouple locations for measuring tank or waste temperature should be avoided and will be part of the Process Control Plan (future).
3. A distinction should be made between supernate and sludge temperature, since they can be significantly different and are measured separately.
4. A basis for monitoring tank headspace temperature should be documented, if available. (Note: author cannot find a reference to support this measurement, therefore deleted).
5. The ventilation system parameters should be shown as a unit input to the store function. Hence, annulus temperature, radioactivity release, and LFL are now replaced with a "Ventilation System Operational" block input to the "Store Waste Function Enabled".
6. There is an administrative check on the dp between the annulus and tank headspace. This will be taken account by the "Tank Hydrostatic Pressure OK" decision, shown as an operator input/decision since it is a manual calculation.
7. The administrative decision for "waste temperature rate of rise" should be relocated to below the block for "tank concrete temperature".
8. The administrative decision block for "tank liquid level constant" should only be made when preparation or transfer functions are not occurring, as these operations would disturb the liquid levels significantly.
9. The decision block for "GRE bubble possible" should be changed to "Vapor bubble possible" for HLW, and changed to a manual decision, which requires an adjustment to ventilation if the possibility exists. The "GRE bubble possible" for LAW should remain unchanged.
10. In the PCS logic decision block for "Primary liquid leak detection", remove "Primary". Also, delete the decision block for "Leak tolerable".
11. Remove the decision block for "Offgas FID VOC >xppm", as there is currently no requirement for this control variable.
12. An administrative decision block for "Chemical composition OK" should be shown as an input to the "Store Waste Function Enabled". The unacceptable condition should indicate "Adjust chemical composition of tank".

Prepare Waste:

LAW / HLW:

1. Show an administrative decision block for "Adjust Primary Ventilation" before the "Ramp up mixer pump VFD", as the ventilation will possibly be adjusted before ramping up the mixer pump.

2. Remove mixer pump parameters which may be specific to only certain types of mixer pumps, including pump column water pressure, motor bearing temperature, pump shaft vibration, and pump column filter dp. Lump these variables as a manual decision for "Mixer pump specific operation parameters OK".
3. Remove the decision block for "In-tank component deflection OK per CCTV", and associated adjustments for mixer pump speed and jet angle.
4. In-tank dilution (if required) should be shown as an option, any time during the "Prepare" function, regardless of mixer pump operation.
5. Flushing of the mixer pump should not be shown, as the available volume of flush water would be insignificant in the current configuration.
6. The administrative decision for "Re-Perform mixing" should be changed to "Perform additional mixing" to imply that improved mobilization or homogenization could be expected by this repetition.
7. A manual operation for "Bump mixer pump periodically" should be shown during the "Settle solids in source tank" process.

HLW only:

1. For the manual decision block "ECR OK per thermocouples or strain gauges", delete the portion "per thermocouples or strain gauges". The Process Control Plan (future) will determine which instrumentation methodology will be used.

LAW only:

1. The decision block for "Storage time adequate" during "Store Diluted Supernate in Staging Tank" should be deleted.
2. An administrative decision block for "Settling Time Adequate" should be shown just before "Settle Solids in Source Tank".
3. An administrative decision block for "In-tank dilution" should be shown just before the process block for "Settle Solids in Source Tank". This would allow re-dilution of the solids in the source tank, if sampling indicates the necessity.

Transfer Waste:

LAW/HLW:

1. The operation of the mixer pump for suspension of the waste before transfer should show an option for turning the mixer pump off.
2. An in-line dilution option shown is for the purposes of transfer line preheating. This option should be available in parallel with the operation of the mixer pump.
3. An option for in-line dilution should be shown after "Start transfer pump".
4. A configuration check for bypassing the transfer pump during transfer line preheating should be shown.
5. An administrative decision block for recirculating the transfer pump discharge during initial in-line dilution should be shown. A PLC logic check for flow volume ratios and a manual check for densitometer readings should be shown as a permissive for opening the recirculation valve to the transfer line.
6. A configuration check during in-line dilution for preheating should include "preheat water arrives at PC within x minutes".

FOSTER WHEELER ENVIRONMENTAL CORPORATION

7. The operation "Drain transfer line" after shutdown of transfer pump should be shown.
8. The operation "Reconfigure transfer/dilution lines" should be shown after waste transfer is complete.
9. Flushing of the mixer pump should not be shown, as the available volume of flush water would be insignificant in the current configuration.
10. Shutdown of the transfer pump without line flushing should be shown for the condition of diluent line backflow.
11. The transfer pump operation should be shown as disabled when doing a direct diluent flush of the transfer line.
12. An administrative decision should be shown for transfer line preheating, with preheating defined as complete when a predetermined volume of preheat water is pumped.
13. The manual operation "Position Transfer Pump" should indicate "Position Transfer Pump Suction", and be located immediately before "Start Transfer Pump".
14. The check for "Transfer pump discharge pressure OK" should be changed to an administrative decision block indicating "Transfer pump discharge pressure rate of change OK".
15. The PLC logic decision block for determining when flushing of the transfer line begins should indicate "Flush volume remains", upon which the diluent pump ramps up.
16. A PLC logic permissive for transfer enable should be added for "minimum waste level in source tank exceeded". If the minimum tank level is exceeded, the system should immediately begin a normal shutdown with transfer line flushing.

LAW only:

1. After sludge dissolution in the source tanks, the waste is allowed to settle and decanted to the PC tank. There is no staging tank for dissolved sludge.
2. An option should be shown for operating the mixer pump during the process "Decant diluted supernate from Staging Tank to PC Tank".

The unresolved issues remain as follows. These issues are shown as dashed blocks on the logic diagrams:

1. The parameters, which define adequate mixing, remain undefined.
2. The time, which is allowable between waste sampling and transfer, remains undefined. If adequate mixing can be defined, then remixing would solve this question.
3. It is uncertain whether sampling of the tank waste will be implemented during mixer pump operation, as complex technology would have to be developed. Thus, the option of shutting down the mixer pump before sampling is shown as tentative.
4. Does the in-tank diluent water (if used) need to match the waste temperature to any extent? Since diluent water may be added for cooling purposes, the temperatures may be considerably different. The addition of relatively cold water may impact the concrete rate-of-rise criteria.
5. The check for material balance during waste transfer as an operator decision is tentative. The ICD requirements, which determine an agreeable material balance, are uncertain at this time.

FOSTER WHEELER ENVIRONMENTAL CORPORATION

APPENDIX D

**HIGH-LEVEL WASTE PROCESS CONTROL STRATEGY
UNRESOLVED ISSUES**

This page intentionally left blank.

High-Level Waste Process Control Strategy Unresolved Issues. (2 Sheets)

Issue No.	Functional Analysis Reference	Unresolved Issue
1	<ul style="list-style-type: none"> Prepare Waste/Transfer Waste 	A process flowsheet for HLW feed delivery has not been issued for any of the processes beyond the initial Tank 241-AZ-101 retrieval. Until these additional flowsheets are completed, it will not be known if there will be any additional requirements to accommodate waste receipt, blending, and pretreatment.
2	<ul style="list-style-type: none"> Transfer Waste 	Tank 241-AZ-101 mobilization efficiency is currently an undemonstrated projection based on small scale testing. If minimum quantities cannot be retrieved from Tank 241-AZ-101 to meet contract requirements, a revision to the current HLW feed delivery strategy will be required, with the possibility of adding more source tanks and controls.
3	<ul style="list-style-type: none"> Prepare Waste 	Instrumentation to monitor waste slurry uniformity and solids concentration has not been proven at the Hanford Site. Without these instruments, additional samples will have to be taken to determine mixer pump effectiveness. The mixer pump test in Tank 241-AZ-101 should be performed as soon as possible to mitigate this risk.
4	<ul style="list-style-type: none"> Prepare Waste Prepare Waste in West/East Area DSTs Mobilize and Suspend Insoluble Waste Within West Area DSTs Mix/Blend HLW in Source Tank 	The parameters that define adequate mixing remain undefined. It is uncertain that current instrumentation will be sufficient to measure these parameters.
5	<ul style="list-style-type: none"> Prepare Waste/Prepare Waste in West/East Area DSTs Mobilize and Suspend Insoluble Waste Within West Area DSTs Sample HLW Source/Staging Tank 	The time that is allowable between waste sampling and transfer remains undefined. If adequate mixing can be defined, then remixing may potentially solve this question.
6	<ul style="list-style-type: none"> Prepare Waste Prepare Waste in West/East Area DSTs Mobilize and Suspend Insoluble Waste Within West Area DSTs Add diluent to HLW Source/Staging Tank 	Does the in-tank diluent water (if used) need to match the waste temperature to any extent? Because diluent water may be added for cooling purposes, the temperatures may be considerably different. The addition of relatively cold water may impact the concrete rate-of-rise criteria.
7	<ul style="list-style-type: none"> Transfer Waste Transfer Waste Cross Site Transfer Waste to HLW Staging Tanks Transfer HLW Sludge to LAW/HLW Plant Monitor Process Parameters for Waste Transfers 	Will a densitometer be used as an administrative control variable to determine if transferred waste is within solids concentration specifications?

High-Level Waste Process Control Strategy Unresolved Issues. (2 Sheets)

Issue No.	Functional Analysis Reference	Unresolved Issue
8	<ul style="list-style-type: none"> Transfer Waste Transfer Waste Cross Site Transfer Waste to HLW Staging Tanks Transfer HLW Sludge to LAW/HLW Plant Monitor Process Parameters for Waste Transfers 	The method for indicating line pluggage has not been determined. For example, PNNL recommended observing variations in differential pressure in line sections during transfers.
9	<ul style="list-style-type: none"> Transfer Waste Transfer Waste Cross Site Transfer Waste to HLW Staging Tanks Transfer HLW Sludge to LAW/HLW Plant Perform Material Balance for DST Transfers 	The check for material balance during waste transfer as an operator decision is tentative. The ICD requirements that determine an agreeable material balance are uncertain at this time. The existing requirement for source tank level agreement is likely to be inaccurate because of gas release, mixer pump operation, and in-line dilution (if required). Consideration should be given to changing the requirement to transfer pump volumetric flow meter/totalizer agreement with destination tank level changes. This method would eliminate several uncertainties.
10	<ul style="list-style-type: none"> Transfer Waste Transfer Waste to Intermediate/LAW Staging Tanks and to LAW/HLW Plant Establish transfer route 	The procedure for verifying valve configuration between DOE and BNFL facilities needs to be discussed, agreed upon, and placed into the ICDs. This procedure may involve signatories from both parties verifying their respective facility valve configuration since each party will not have full access to the transfer route.
11	<ul style="list-style-type: none"> Transfer Waste 	What administrative controls exist to ensure that waste transfers will consider the impact of adding supernatant to tanks containing heels of different envelope types?
12	<ul style="list-style-type: none"> Transfer Waste 	For tanks containing significant depths of insoluble solids, there is no equipment and sequence of processes which can mix/transfer the entire tank contents. If a mid-level suction mixer pump is used, mixing will only be possible with liquid available down to mid-level. If a bottom suction mixer pump is used, it cannot start while the suction is in solids.

BNFL = BNFL Inc.
 DOE = U.S. Department of Energy.
 DST = double-shell tank.
 HLW = high-level waste.
 ICD = interface control document.
 LAW = low-activity waste.
 PNNL = Pacific Northwest National Laboratory.

DISTRIBUTION

Onsite

1	<u>U.S. Department of Energy</u> <u>Richland Operations Office</u>	
	DOE Public Reading Room	H2-53
1	<u>Pacific Northwest National Laboratory</u>	
	Hanford Technical Library	P8-55
2	<u>Lockheed Martin Services, Inc.</u>	
	Central Files	B1-07
	Document Processing Center	A3-94

This page intentionally left blank.