S

APR 11 2000

Sta 4 (S)

ENGINEERING DATA TRANSMITTAL

Page 1 of 1

1. EDT 627890

2. To: (Receiving Organization) LMHC Characterization Engineering		3. From: (Originating Organization) Characterization Engineering		4. Related EDT No.: N/A	
5. Proj./Prog./Dept./Div.: Characterization Project		6. Design Authority/Design Agent/Cog. Engr.: GP Janicek/BL Coverdell / RN Dale		7. Purchase Order No.: N/A	
8. Originator Remarks: Justification for addition of lead shielding to shielded receiver tube submitted for review and approval prior to release.				9. Equip./Component No.: N/A	
				10. System/Bldg./Facility: 200G	
11. Receiver Remarks: 11A. Design Baseline Document? ☐ Yes ☒ No				12. Major Assm. Dwg. No.: N/A	
				13. Permit/Permit Application No.: N/A	
				14. Required Response Date: ASAP	
15. DATA TRANSMITTED					
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Approval Designator
1	RPP-6018	N/A	0	JUSTIFICATION FOR SHIELDED RECEIVER TUBE ADDITIONAL LEAD SHIELDING	N/A
16. KEY					
Approval Designator (F)		Reason for Transmittal (G)		Disposition (H) & (I)	
E, S, Q, D or N/A (see WHC-CM-3-5, Sec. 12.7)		1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)		1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged	
17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)					
(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN
1	1	Design Authority	GP Janicek	3/29/00	S7-12
1	1	Design Agent	BL Coverdell	3/27/00	S7-12
1	1	Cog. Eng.	RN Dale	3/28/00	S7-12
1	1	Cog. Mgr.	JS Schofield	3/28/00	S7-12
		QA	N/A		
1	1	Safety	CD Jackson	3/28/00	S7-12
		Env.	N/A		
18.		19.		20.	
BL Coverdell Signature of EDT Originator		RM Boger Authorized Representative For Receiving Organization		JS Schofield Design Authority/Cognizant Manager	
3/27/00 Date		4/6/00 Date		3/28/00 Date	
21. DOE APPROVAL (if required) Ctrl No. ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments					

JUSTIFICATION FOR SHIELDED RECEIVER TUBE ADDITIONAL LEAD SHIELDING

R. M. Boger
Prepared by CH2M Hill Hanford Group, Inc.
2400 Stevens
Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-96RL13200

EDT/ECN: 627890
Org Code: 74900
B&R Code: EW3130000

UC: 2000
Charge Code: CACN: 102250 COA: EI00
Total Pages: 138 *100 4/1/00*

Key Words: Core Sampling, Shielded Receiver, Shielded Receiver Tube, Lead, Shielding

Abstract: In order to reduce high radiation dose rates encountered when core sampling some radioactive waste tanks the addition of 240 lbs. of lead shielding is being considered to the shielded receiver tube on core sample trucks #1, #3 and #4. The lead shielding is 4" diameter x 1/2" thick half rounds that have been installed around the SR tube over its full length. Using three unreleased but independently reviewed structural analyses HNF-6018 justifies the addition of the lead shielding.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop 116-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

[Signature] 4/7/00
Release Approval

Approved for Public Release

JUSTIFICATION FOR SHIELDED RECEIVER TUBE ADDITIONAL LEAD SHIELDING

Prepared for CH2M Hill Hanford Group, Inc.
Characterization Engineering Group

By
B. L. Coverdell
COGEMA Engineering Corporation

March, 2000

JUSTIFICATION FOR SHIELDED RECEIVER TUBE ADDITIONAL LEAD SHIELDING

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	IDENTIFICATION OF APPLICABLE ANALYSES.....	1
3.0	DISCUSSION OF ANALYSES	1
3.1	SHIELDED RECEIVER TUBE.....	1
3.2	CORE SAMPLE TRUCK #1	1
3.3	CORE SAMPLE TRUCK #3 AND #4	2
4.0	CONCLUSION.....	2
5.0	REFERENCES	3

APPENDICES

Appendix A:	Stress Analysis of Shielded Receiver Tube to Support An Additional 250 lbs.....	A-1
Appendix B:	Structural and Stress Analysis, Shielded Receiver Lifting Frame, Core Sample Truck #1	B-1
Appendix C:	Structural and Stress Analysis, Shielded Receiver Lifting Frame and Jack Assemblies, Core Sample Truck #3 and #4	C-1

JUSTIFICATION FOR SHIELDED RECEIVER TUBE ADDITIONAL LEAD SHIELDING

1.0 INTRODUCTION

High radiation doses have been encountered during recent core sampling of Hanford radioactive waste tanks. Temporary lead shielding has been identified for installation on the Shielded Receiver (SR) tube for Core Sample Trucks (CST) #1, #3 and #4. The half round lead shielding installed around the SR tube have a 4 1/2" inside diameter and 1/2" thick wall. The total weight of the lead shielding added is 240 lb. The purpose of this document is to verify that the Shielded Receiver Lifting Frames (SRLF) on CSTs #1, #3 and #4 are adequate to support the addition of 240 lbs of lead shielding.

2.0 IDENTIFICATION OF APPLICABLE ANALYSES

An engineering calculation was prepared that structurally analyzes the effect of adding 240 lb. of lead shielding to the identical SR tubes on CSTs #1, #3 and #4. The engineering calculation in Appendix A, *Stress Analysis of Shielded Receiver Tube*, is not released into the Hanford Document Control System but has been independently reviewed.

Two structural analyses have been completed analyzing the structural components that make up SRLF (Appendix B). The first analysis is *Structural and Stress Analysis, Shielded Receiver Lifting Frame, Core Sample Truck #1*. The second is *Structural and Stress Analysis, Shielded Receiver Lifting Frame and Jack Assemblies, Core Sample Truck #3 and #4* (Appendix C). Neither of these documents are released into the Hanford Document Control System, however, both documents have been independently Reviewed.

3.0 DISCUSSION OF ANALYSES

3.1 SHIELDED RECEIVER TUBE

Appendix A contains a short analysis used to determine if the SR tube, the SR tube welds and SR tube to SR Hoist base plate bolted connection on CST #1, #3 and #4 are adequate. The analysis determined that the SR tube and its' structural connections are more than adequate to support an additional 240 lbs of temporary lead shielding.

3.2 CORE SAMPLE TRUCK #1

The text excerpt from the SRLF structural analysis in Appendix B evaluates the structural adequacy of CST #1 SRLF to support the dead weight of the SR Hoist, SR tube, SRLF structure and associated transportation loads. Page B-11 identifies the maximum SRLF member stresses as being 21,300 psi. This stress occurs in the Tube Steel (TS) 2x2x1/4 structural tube members connecting the SR fixed frame to the truck frame.

The analysis conservatively assumes the allowable stress for this member to be based on that for ASTM A36 carbon steel. According to the American Institute of Steel Construction (AISC 1989) for the given section size and yield stress, the allowable stress was determined to be 23,760 psi. However, the SRLF 2x2x1/4 structural tube members are actually fabricated using ASTM A500 Grade B material. This material has yield stress of 46,000 psi as opposed to 36,000 psi for ASTM A36 material. Therefore, the allowable stress for the ASTM A500 Grade B material should actually be 30,360 psi. This is a 27.8% increase in the allowable stress for the TS 2x2x1/4.

The high stress members on CST #1, the TS 2x2x $\frac{1}{4}$ structural tube members, are actually TS 3x2x5/16 and TS 3x3x5/16 (see drawings H-2-91715, Sht. 1, Rev. 9, H-2-91716, Sht. 3, Rev. 0, Sht. 4, Rev. 0). Using the smaller sized structural tubing as a reference, the increased size in structural tubing provides a 287% increase in structural rigidity about the X-X axis, 94% about the Y-Y axis and 72% increase in cross-sectional area. In addition to using larger structural tube members, the SRLF has been significantly strengthened to accommodate the addition of hydraulic cylinders with a 1 $\frac{3}{4}$ " diameter rod in lieu of cylinders with 1" diameter rods (see ECN 626650).

3.3 CORE SAMPLE TRUCK #3 AND #4

The text excerpt of the CST #3 and #4 SRLF structural analysis in Appendix C evaluates the structural adequacy of the SRLF to support the dead weight of the SR Hoist, SR tube, SRLF structure and associated transportation loads. Page C-14 identifies the maximum SRLF member stresses as being 23,740 psi. This stress occurs in the TS 2x2x $\frac{1}{4}$ structural tube members connecting the SR fixed frame to the truck frame.

The analysis conservatively assumes the allowable stress for this member to be based on that for ASTM A36 carbon steel. According to AISC 1989 given the section size and yield stress, the allowable stress was determined to be 23,760 psi. However, the SRLF 2x2x $\frac{1}{4}$ structural tube members are actually fabricated using ASTM A500 Grade B material. This material has yield stress of 46,000 psi as opposed to 36,000 psi for ASTM A 36 material. Therefore, from AISC 1989 the allowable stress for the ASTM A500 Grade B material should actually be 30,360 psi. This is a 27.8% increase in the allowable stress for the TS 2x2x $\frac{1}{4}$.

On CSTs #3 and #4, the members determined to have the highest stresses (TS 2x2x $\frac{1}{4}$ connecting the SR fixed frame to the CST frame) were analyzed as simple shapes when, in fact, they are composite shapes. The TS 2x2x $\frac{1}{4}$ have $\frac{1}{4}$ " gusset plates welded between them and the CST frame (see H-2-690043, Rev. 2, zone F-4). The addition of the gusset plates significantly increases the structural capacity of the TS 2x2x $\frac{1}{4}$ connecting members. In addition, the SRLF has been significantly strengthened to accommodate the addition of hydraulic cylinders with a 1 $\frac{3}{4}$ " diameter rod in lieu of cylinders with 1" diameter rods (see drawings H-2-690043, Rev. 2 and H-2-690044, Sht. 1, Rev. 3 and Sht 2, Rev. 2).

4.0 CONCLUSION

Half round lead shielding weighing equal to or less than 240 lb may be added to the SR tube on CST #1, #3 and #4 based on the following facts:

- The structural analysis of the SR tube, the SR tube welds and SR tube to SR hoist base plate bolted connections determined that the structural integrity was more than adequate to support the additional load.
- Both analyses of the SRLFs (Appendices B & C) use a very conservative allowable stress for the evaluation of the SRLFs structural tubing.
- Structural modifications increasing the strength of the SRLFs were made subsequent to the performance of the analyses in appendices B and C. The modifications increased the strength of the high stress members of the SRLFs for all three CSTs.

Operational loading of SRLF was not considered by either of the structural analyses in the appendices B or C, however, after review of the analyses it was determined that transportation loads (longitudinal = -.43g, lateral = .37g and vertical = -.18g) bound all operational loads. Review of the structural analysis of the SR tube and SR tube connections in Appendix A determined that it is adequate to support operational loading.

5.0 REFERENCES

AISC, 1989, *Manual of Steel Construction - Allowable Stress Design*, American Institute of Steel Construction, Ninth Edition, Chicago, Illinois.

Appendix A: Stress Analysis of Shielded Receiver Tube.

TWRS ADMINISTRATION
TEMPORARY SHIELDING

Manual
Volume
Section
Page
Effective Date

HNF-IP-0842
VII, Radiological Control
3.2, REV 2
8 of 10
July 31, 1998

Figure 1. Temporary Shielding Authorization Form.

TEMPORARY SHIELDING AUTHORIZATION

ID Number: _____		TEMPORARY SHIELDING AUTHORIZATION		Shielding Location: <u>EMCST SHIELDED RECEIVER</u>	
A. RWP # _____ Work Package # _____	Pre-Job Survey Data: 30cm Contact	OW _____ CW _____	OW _____ CW _____		
<p>B. Shielding <u>Installation</u> Alteration or Removal: (Circle one) Instructions: (attach drawings if necessary) <u>INSTALL 1/2" THK LEAD PIPE SHIELDING</u> <u>OVER LENGTH OF EMCST SHIELDED RECEIVER, AS REQ'D.</u></p>					
<p>C. Approvals</p> <p>Facility Engineering <u>[Signature]</u> Date <u>8/4/99</u> Weight Limitations <u>250lb</u> (For Installation or Modification Only)</p> <p>Radiological Control _____ Date _____</p>					
<p>D. Comments:</p> <p><u>1/2" THK x 4" Ø PIPE SHIELDING MAY BE INSTALLED OVER</u> <u>LENGTH OF EMCST SHIELDED RECEIVER, AS REQ'D. SEE ATTACHED</u> <u>ANALYSIS.</u></p>					
E. Installation, Alteration, and Removal					
Final Configuration: _____ Shielding Removed _____ Shielding Modified/Installed (Attach drawings or photographs)					
Shielding In Place		Amount			
Final estimated weight of Shielding:					
Radiation Dose Rates:		Distance		Shielded	
		30 cm		OW _____ CW _____	
		Contact		OW _____ CW _____	
				Unshielded	
				OW _____ CW _____	
Completed By: (HPT) _____				Date _____	

DESIGN ANALYSIS

Calc. No. _____
 Revision 0
 Page No. _____

Client: Characterization Equipment
 Subject: Shielded Receiver Tube Analysis

WO/Job No. _____

Date: 8/04/99

Checked: 8/4/99

Revised: _____

By: B. L. Coverdell

By: [Signature]

By: _____

1.0 OBJECTIVE This set of calculations determines the adequacy the shielded receiver tube to carry an additional loading of 250 lb due to lead shielding.

2.0 DESIGN INPUTS

2.1 Drawing: H-2-690020 Rev. 3

3.0 ASSUMPTIONS

3.1 None

4.0 METHODS OF ANALYSIS (Hand calculations completed in Mathcad ver. 8.0)

5.0 REFERENCES

5.1 AISC, 1989, Manual of Steel Construction, 9th Edition, American Institute of Steel Construction, Chicago, Illinois.

5.2 Blodgett, O W, 1991, *Design of Welded Structures*, Fourteenth Printing, The James F. Lincoln Arc Welding Foundation, Cleveland, Ohio.

6.0 FINDINGS AND CONCLUSIONS The calculations below determine the shielded receiver tube is adequate to carry the expected 250 lbf additional loading with a large factor-of-safety.

7.0 CALCULATIONS

7.1 Determine the loads on the shielded receiver tube and include the addition of lead shield.

$$\text{Tube} := 250 \cdot \text{lbf}$$

Weight of added lead shield.

$$L := 77 \cdot \text{in} - 1.12 \cdot \text{in} - .75 \cdot \text{in}$$

$$L = 6.261 \text{ ft}$$

Length of shielded receiver tube.

$$\text{Tube}_4 := L \cdot 10.79 \frac{\text{lbf}}{\text{ft}}$$

$$\text{Tube}_4 = 67.554 \cdot \text{lbf}$$

Weight of 4" schedule 40 pipe.

$$\text{Tube}_2 := L \cdot 3.65 \frac{\text{lbf}}{\text{ft}}$$

$$\text{Tube}_2 = 22.852 \cdot \text{lbf}$$

Weight of 2" sch 40 pipe.

$$\text{Lead} := L \cdot \left[\frac{\pi}{4} \cdot \left[(10.02 \cdot \text{in})^2 - (2.375 \cdot \text{in})^2 \right] \right] \cdot 710 \frac{\text{lbf}}{\text{ft}^3}$$

$$\text{Lead} = 2297 \cdot \text{lbf}$$

Weight of lead.

$$\text{Flange} := \frac{\pi}{4} \cdot \left[(8.5 \cdot \text{in})^2 - (2.39 \cdot \text{in})^2 \right] \cdot .75 \cdot \text{in} \cdot 490 \frac{\text{lbf}}{\text{ft}^3}$$

$$\text{Flange} = 11.114 \cdot \text{lbf}$$

Weight of lower flange.

Weight of ball valve, view port and dust cap is estimated at 100 lb.

$$W_{\text{total}} := \text{Tube} + \text{Tube}_2 + \text{Tube}_4 + \text{Lead} + \text{Flange}$$

$$W_{\text{total}} = 2649 \cdot \text{lbf}$$

Misc weight.

7.2 Assuming the 4" sch 40 pipe carries the entire load, determine the maximum stress in pipe.

Completed By:
Checked By:

$$A_4 := 3.17 \cdot \text{in}^2$$

Cross sectional area of 4" sch 40 pipe.

$$\sigma_t := \frac{W_{\text{total}}}{A_4}$$

$$\sigma_t = 835.629 \cdot \text{psi}$$

OK

7.3 Determine the adequacy of the 1/4" weld attaching the 4" sch 40 pipe to the upper flange.

$$d := 4.5 \cdot \text{in}$$

Diameter of weld.

$$w_a := \frac{1}{4} \cdot \text{in}$$

Weld size.

$$\sigma_{\text{base}} := 36000 \cdot \text{psi}$$

Yield stress of the base metal.

$$\sigma_{\text{weld}} := 60000 \cdot \text{psi}$$

Yield stress of the weld metal.

Connection Loads:

$$F_x := 0 \cdot \text{lbf}$$

$$F_y := 0 \cdot \text{lbf}$$

$$F_z := W_{\text{total}}$$

$$M_x := 0 \cdot \text{in} \cdot \text{lbf}$$

$$M_y := 0 \cdot \text{in} \cdot \text{lbf}$$

$$M_z := 0 \cdot \text{in} \cdot \text{lbf}$$

Weld Properties per Blodgett 1991

$$C_x := \frac{d}{2}$$

$$C_x = 2.25 \cdot \text{in}$$

The distance to the outer fiber in the x-direction.

$$C_y := \frac{d}{2}$$

$$C_y = 2.25 \cdot \text{in}$$

The distance to the outer fiber in the y-direction.

$$A_w := \pi \cdot d$$

$$A_w = 14.137 \cdot \text{in}$$

The linear area of the weld.

$$S_{wx} := \frac{\pi \cdot d^2}{4}$$

$$S_{wx} = 15.904 \cdot \text{in}^2$$

The linear section modulus about the x-axis.

$$S_{wy} := \frac{\pi \cdot d^2}{4}$$

$$S_{wy} = 15.904 \cdot \text{in}^2$$

The linear section modulus about the y-axis.

$$J_w := \frac{\pi \cdot d^3}{4}$$

$$J_w = 71.569 \cdot \text{in}^3$$

The linear polar moment of inertia.

Linear Weld Stress:

$$f_w := \sqrt{\left(\frac{F_z}{A_w} + \frac{M_x}{S_{wx}} + \frac{M_y}{S_{wy}} \right)^2 + \left(\frac{F_x}{A_w} + \frac{M_z \cdot C_y}{J_w} \right)^2 + \left(\frac{F_y}{A_w} + \frac{M_z \cdot C_x}{J_w} \right)^2} \quad f_w = 187.375 \cdot \frac{\text{lbf}}{\text{in}}$$

Required Fillet Weld Size:

$$w_r := \text{if} \left[\frac{f_w}{0.707 \cdot (0.3) \cdot \sigma_{\text{weld}}} \leq \frac{f_w}{0.4 \cdot \sigma_{\text{base}}}, \frac{f_w}{0.4 \cdot \sigma_{\text{base}}}, \frac{f_w}{0.707 \cdot (0.3) \cdot \sigma_{\text{weld}}} \right] \quad w_r = 0.015 \cdot \text{in}$$

0.707 is for shear through throat of fillet weld, 0.3 is allowable stress reduction factor for shear through throat of fillet weld and 0.4 is for shear on base metal. See AISC 1989, Table J2.5, Page 5-70.

The Margin of Safety:

$$FS := \frac{w_a}{w_r}$$

$$FS = 16.979$$

OK

Completed By:
Checked By:

7.4 Check bolts attaching upper flange and shielded receiver tube to the hoist box.

$n := 8$ Number of 5/8" A193 bolts.

$\sigma_{t_allow} := 90000 \cdot \text{psi}$ Minimum yield stress for an A193 bolt (no class specified).

$W_{flange} := \frac{\pi}{4} \cdot [(13.5 \cdot \text{in})^2 - (2.39 \cdot \text{in})^2] \cdot 1.12 \cdot \text{in} \cdot 490 \cdot \frac{\text{lbf}}{\text{ft}^3}$ $W_{flange} = 44.035 \cdot \text{lbf}$ Weight of upper flange.

$W_{total} := W_{total} + W_{flange}$ Total weight of shielded receiver tube assembly.

$A_c := .202 \cdot \text{in}^2$ Cross sectional area of a 5/8" bolt.

$\sigma_t := \frac{W_{total}}{n \cdot A_c}$ $\sigma_t = 1666 \cdot \text{psi}$ Maximum stress in a 5/8" bolt.

$FS := \frac{\sigma_{t_allow}}{\sigma_t}$ $FS = 54.007$ OK

ADVANCED SHIELDING TECHNOLOGY, LLC
PRICING STRUCTURE
EFFECTIVE DATE: May 1, 1999 (rev.1)

I. Coated Pipe Shields, 0.50" thick lead, price per liner foot

PIPE DIAMETER	RadKlad 140		Metalized	
	Half Round	Full Round	Half Round	Full Round
4" or less	\$80	\$160	\$94	\$238
6"	\$105	\$210	\$119	\$300
8"	\$124	\$248	\$147	\$372
10" & 12"	\$140	\$280	\$166	\$420
14" & 16"	\$140	\$280	\$166	\$420
18" & 20"	\$150	\$300		

II. Coated Pipe Elbow Shields, 0.50" thick lead, price per elbow

PIPE DIAMETER	RadKlad 140		Metalized	
	Half Round	Full Round	Half Round	Full Round
4" or less	\$168	\$336	\$199	\$505
6"	\$248	\$496	\$294	\$742
8"	\$360	\$720	\$427	\$1,078
10"	\$518	\$1036	\$615	\$1,554
12"	\$835	\$1,670	\$993	\$2,505
14" - 20"	\$900	\$1800		

ADVANCED SHIELDING TECHNOLOGY, LLC**III. Coated Shield Panels, 0.25" thick lead**

SIZE	RadKlad 140		Metalized
1' x 3'	\$130		\$210
1' x 4'	\$160		\$245
2' x 4'	\$225		\$295

* includes 4 grommetted holes

IV. Coated Valve Shields, 0.75" thick lead

VALVE SIZE	RadKlad 140	RadKlad 340	Metalized
3/4" to 1"	\$470		\$705
2"	\$575		\$860
3/4" to 1" Karotest	\$575		\$860

V. Whole Body Monitor Shield Enclosure

Specifications (standard model):

- will accommodate most whole body monitors in use (IPM, PCM, etc.)
- modular dimensions
- single entry/exit
- seismic qualification available
- modular design allows for easy installation and removal of individual shield panels
- modular design allows for easy access to whole body monitor for maintenance
- safe and easy assembly/disassembly
- side shielding available up to 1.0" lead thickness in 1/4" increments
- roof shielding available up to 1/2" lead thickness in 1/4" increments
- stainless steel panel finish
- options available at Customer request
- Special Design Whole Body Monitor Shield Enclosures available

Prices (standard model):

- 1/4" thick lead shielding on sides and roof {call for estimate}
- 1/2" thick lead shielding on sides and roof "
- 3/4" thick lead shielding on sides, 1/2" thick on roof "
- 1.0" thick lead shielding on sides, 1/2" thick on roof "

ADVANCED SHIELDING TECHNOLOGY, LLC

Notes:

1. All prices are subject to change without notification.
 2. Prices are non-inclusive of handling and freight charges, installation materials (fasteners), or installation support services, if applicable.
 3. Products shown here are indicative of most commonly fabricated shield products. Please contact us for pricing on other shielding products.
 4. 10 working days are required to process requests for all special shield designs.
 5. Fabrication of special size valve shields requires a 4 to 6 week lead time.
-

WEIGHT INFORMATION**I. Pipe Shields (0.5" thick lead)**

Diameter	Weight per liner foot (half-round shield coverage)
1"	6.75 lbs
2"	11.5
3"	15.5
4"	19.75
5"	23.75
6"	28
8"	35.5
10"	45
12"	53.25

II. Valve Shields (0.75" thick lead)

Valve size	Weight
3/4"	15 lbs
1"	15
2"	80

III. Shield Panels (1/4" thick)

15 lbs per square foot

Appendix B: Structural and Stress Analysis, Shielded Receiver Lifting Frame, Core Sample Truck #1

ENGINEERING DATA TRANSMITTAL						Page 1 of <u>1</u>	
						1. EDT 508380	
2. To: (Receiving Organization) Characterization Equipment			3. From: (Originating Organization) Structural Integrity Assessment			4. Related EDT No.: N/A	
5. Proj./Prog./Dept./Div.: Tank Farms			6. Cog. Engr.: F. R. Vollert			7. Purchase Order No.: N/A	
8. Originator Remarks: For review and approval. <i>Appendices are not attached.</i>						9. Equip./Component No.: N/A	
11. Receiver Remarks:						10. System/Bldg./Facility: 200 Area Tank Farms	
						12. Major Assm. Dwg. No.: H-2-140300	
						13. Permit/Permit Application No.: N/A	
						14. Required Response Date: 03/03/95	
15. DATA TRANSMITTED							
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Impact Level	(G) Reason for Transmittal	(H) Originator Disposition
1	WHC-SD-WM-ER-412		0	STRUCTURAL AND STRESS ANALYSES, SHIELDED RECEIVER LIFTING FRAME, CORE SAMPLER TRUCK #1	Q	1	1
16. KEY							
Impact Level (F)		Reason for Transmittal (G)			Disposition (H) & (I)		
1, 2, 3, or 4 (see MRP 5.43)		1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)			1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged		
17. SIGNATURE/DISTRIBUTION (See Impact Level for required signatures)							
(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.
1		Cog. Eng. F. R. Vollert	<i>F.R. Vollert</i>	<i>2-21-95</i>	H5-52		
1		Cog. Mgr. K. V. Scott			H5-52		
1		QA J. J. Verderber			S1-57		
1		28 J. L. Smalley			R1-17		
1		R. J. Blanchard			R1-17		
1		T. S. Hundal			H5-52		
1		H. H. Ziada	<i>H. Ziada</i>	<i>2-21-95</i>	H5-52		
18. F. R. Vollert Signature of EDT Originator Date		19. R. J. Blanchard Authorized Representative Date for Receiving Organization		20. K. V. Scott Cognizant/Project Engineer's Manager Date		21. DOE APPROVAL (if required) Ltr. No. N/A ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments	

BD-7400-172-2 (07/91) GEF097

STRUCTURAL AND STRESS ANALYSES, SHIELDED RECEIVER LIFTING FRAME, CORE SAMPLER TRUCK #1

1.0 INTRODUCTION

Structural and stress analyses have been conducted for the shielded receiver lift frame (SRLF) mounted on core sampler truck number 1. Analyses cases were: the normal operational static vertical (deadweight) loads and the deadweight combined with additional static vertical and horizontal loads intended to account for the potential demands of transporting the SRLF on the truck.

The SRLF is a space frame structure with welded joints. It is fabricated from various size structural steel tubes, except the two main members for the fixed frame portion are 6 inch deep channels. The objectives of the structural analyses include determining and evaluating the stresses in the frame members and the weld joints. Three dimension static finite (beam) element analyses of the SRLF were conducted (Images 1993) with models to represent the SRLF in the raised and lowered position, and to envelope the restraint provided by the welded attachments to the truck. Fully fixed joints were used in the finite element models. The results were member (beam) stresses and joint forces. The joint forces were used to calculate the weld stresses for the joints with methods from Blodgett 1982. The member and weld stresses were evaluated and determined to be in conformance with AISC 1989 and AWS 1992. The analyses results do not predict the potential affects of residual stresses, cyclic stresses, stress concentrations, and potential defects. The welds, including the attachments to the truck, should frequently be thoroughly cleaned and visually inspected.

2.0 CONCLUSIONS AND RECOMMENDATIONS

The SRLF structural analyses results are the stresses and joint forces for the structural members. The joint forces were then used to calculate the welded joint stresses, including the stresses in the gusset plates that stiffen 4 joints. These calculated member and weld stresses all are within the allowable values. However, the SRLF structural member ends are simply and directly welded together at the joints or connections. Therefore, the analyses and the results do not predict or incorporate the potential affects of:

- residual stresses due to fabrication
- cyclic stress changes during operation and transportation (fatigue)
- stress concentrations, sharp corners, and potential defects in the welded joints.

The computed stresses in the members and welds would directly superimpose with residual stresses. This increases the potential for overstress under all load conditions, particularly for the welds. Cyclic stresses have the

potential to initiate and propagate fatigue cracks. Again the welds with the higher likelihood for stress concentrations and defects are the most vulnerable. Further more comprehensive analyses to account for these potential effects could be conducted. A number of enveloping assumptions would be necessary. It is believed that, after further analyses, too many uncertainties would remain to eliminate this concern.

It is recommended that the weld joints in the SRLF and the attachments to the truck be thoroughly cleaned and visually inspected frequently. For example, after each 30 days of operation, and after each relocation to another tank farm. The inspections would be for evidence of structural and joint distress including cracks. They should be frequent, because visual inspection may not be able to find cracks before they have advanced considerably.

In the event structural distress occurs where joint repair is necessary, evaluation should be made to determine if the design details can be readily improved.

3.0 MATERIALS AND ALLOWABLE STRESSES

Design drawing H-2-91716 (WHC 1994b) for the SRLF specifies either ASTM A36 or ASTM A500, Grade B steel for the structural tubes and channels. The steel plates and other components used are ASTM A36. The weld metal used has a specified minimum ultimate strength of 70,000 lbf/in².

3.1 STRUCTURAL STEEL STRENGTH AND ALLOWABLE STRESSES

The strength, allowable stresses, and other material properties used for all the structural steel members and components in the SRLF were established conservatively from ASTM A36 steel minimum specifications as follows:

Modulus of Elasticity, E	= 29,000,000 lbf/in ²
Shear Modulus, G	= 11,200,000 lbf/in ²
Poisons Ratio, μ	= 0.300
Ultimate Tensile Strength, F_u	= 58,000 lbf/in ²
Yield Strength, F_y	= 36,000 lbf/in ²
Allowable Axial Stress, F_t	= $0.60 \times F_y = 21,600$ lbf/in ²
Allowable Bending Stress, F_b	= $0.66 \times F_y = 23,760$ lbf/in ²
Allowable Shear Stress, F_v	= $0.40 \times F_y = 14,400$ lbf/in ²

3.2 WELD ALLOWABLE STRENGTH

The ultimate and allowable strength for the welds joining the SRLF structural members were established in accordance with the Structural Welding code (AWS 1992), and the Manual of Steel Construction (AISC 1989). These force per unit length values are determined based on the minimum ultimate strength (F_{uwm}) of the weld metal, and the thickness (t_w) of the weld as follows:

$$\text{Weld Metal Ultimate Strength, } F_{uwm} = 70,000 \text{ lbf/in}^2$$

$$\text{Fillet Weld Ultimate Strength, } F_{uw} = 0.707 \times t_w \times F_{uwm} \text{ lbf/in}$$

$$\text{Fillet Weld Allowable Strength}^1, F_w = 0.30 \times F_{uw} = 14,800 \times t_w \text{ lbf/in}$$

4.0 CONFIGURATION AND LOADS

The configuration of the SRLF structure for core sampler truck 1 obtained from the design drawing H-2-91716 (WHC 1994b) is shown in Figures 1, 2, and 3. It is a space frame structure with welded joints. It is fabricated from various size structural steel tubes, except the two main members for the fixed frame portion are 6 inch deep channels. The fixed frame and its two bracing members are welded to the truck. The moveable portion is raised and lowered during normal operation by the two vertical actuators. Figure 1 also shows the location of the normal operation vertical static (deadweight) loads on the moveable portion of the structure. These loads (maximum) are: the sampler hoist shielded receiver box and base plate (1,900 lbf), plus the shielded sampler tube (2,800 lbf).

The maximum allowable speed on paved roadways is 15 mi/h for the core sampler truck 1. This limit was established to prevent truck rollover from the results of a previous analysis for core sampler truck 2 (WHC 1994a). The potential demands of transporting the SRLF on the truck at the 15 mi/h maximum allowed speed, also estimated by the rollover analysis for truck 2 (WHC 1994a), are represented as additional static forces on the SRLF. These are: 0.18 g vertical, 0.43 g longitudinal, and 0.37 g lateral. The moveable portion of the SRLF is only in the lowered position during transport.

5.0 STRUCTURAL ANALYSES AND RESULTS

Three dimension finite element static analyses were conducted for the SRLF structure (Images 1993) for the normal operation deadweight loads, and for deadweight combined with the additional transportation loads. Finite beam element models with the SRLF in the raised and lowered position were developed and used. Also, the fixed frame was both: modeled to be fully restrained at all welds to the truck, and with only the two braces providing the overturning restraint. Fully fixed joints were used in the finite element models, because the SRLF structural member ends are simply and directly welded together at the

¹For fillet weld (t_w) = 3/16 in., (F_w) = 2775 lbf/in.

joints or connections. Four of the SRLF connections are stiffened with gusset plates.

Four deadweight loads analyses cases were run. This was necessary to obtain analyses results for the SRLF in both the raised and lowered position, and for the two restraint conditions assumed for the fixed frame. Four transportation loads analyses cases were run with the SRLF in the lowered position. This was necessary to obtain analyses results for both forward and aft direction longitudinal loads, and for the two restraint conditions assumed for the fixed frame. The finite (beam) element models are described in detail, and all the Images 1993 analyses results are provided in Appendix A.

The Images 1993 analyses results include the forces and moments in the members and joints, and the member stresses. The bending, axial, shear, and combined stresses are calculated for each beam element in the SRLF model. The maximum bending, shear, and combined stress values in the SRLF members for deadweight loads, and the transportation loads are listed and compared to the allowable in Table 1 and Table 2, respectively. All of the calculated potential stresses in SRLF structural members are within the allowable.

The stresses in the weld joints due to the member/joint forces and moments were calculated. Weld stress analysis methods from Blodgett 1982 were used. The weld joint stress calculations and evaluations are provided in Appendix B. Table 3 lists the maximum potential weld stresses for the normal deadweight loads, and transportation loads. For comparison, the allowable weld strengths for the welds are also listed in Table 3. All of the calculated potential weld stresses in the SRLF joints are within the allowable strengths. For the normal deadweight loads the calculated weld stresses, with few exceptions, are very low. For the additional transportation loads, most of the calculated weld stresses increase significantly. Two of the weld joint stresses essentially equal their allowable strength. Several others are within 20% of the allowable strength.

It was also necessary to use member/joint forces to calculate the bending stresses in the gusset plates that stiffen 4 joints in the SRLF. The maximum calculated bending stresses in the plates for the deadweight and transportation load cases are 10,318 lbf/in² and 14,085 lbf/in², respectively. These are within the 23,760 lbf/in² allowable bending stress.

6.0 REFERENCES

- AISC, 1989, *Manual of Steel Construction, Allowable Stress Design*, Ninth Edition, American Institute of Steel Construction, Chicago, Illinois.
- ASTM, 1989, *Annual Book of ASTM Standards*, American Society for Testing and Materials, Philadelphia, Pennsylvania.
- AWS, 1992, *Structural Welding Code-Steel*, ANSI/AWS D1.1-92, American Welding Society, Miami, Florida
- Blodgett, O. W., 1982, *Design of Welded structures*, James F. Lincoln Arc Welding Foundation, Cleveland, Ohio
- Images, 1993, *Interactive Microcomputer Analysis and Graphics of Engineering Systems, IMAGES-3D*, Version 3.0, RLCA/Celestial Software, Berkeley, California.
- WHC, 1994a, *Rollover Analysis of Rotary Mode Core Sampler Truck #2*, WHC-SD-WM-ER-391, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1994b, *Shielded Receiver Lifting Frame Assembly, Core Sample Truck*, Drawing Number H-2-91716, Sheets 1 to 4, Westinghouse Hanford Company, Richland, Washington.

FIGURE 3: SHIELDED RECEIVER FIXED SUPPORT FRAME ASSEMBLY

Table 1. Maximum Member Stresses Normal Deadweight Loads

Member*	Type of Stress	Maximum (lbf/in ²)	Allowable (lbf/in ²)
40	Axial	518	21600
41	Bending	7475	23760
107	Shear	8019	14400
39	Combined**	7970	23760

Table 2. Maximum Member Stresses Deadweight Plus Transportation Loads

Member*	Type of Stress	Maximum (lbf/in ²)	Allowable (lbf/in ²)
82	Axial	2364	21600
44	Bending	18180	23760
16	Shear	4708	14400
41	Combined**	21300	23760

*Beam number from Images-3D Model, see Appendix A.

**Mostly bending stress, use bending stress allowable.

Table 3. Calculated and Allowable Weld Stresses

Joining Members	Calculated Weld Stress (lbf/in)		Allowable Weld Stress** (lbf/in)
	Deadweight	Transportation	
11 to 9*	268	2091	2775
5 to 5 bracing	139	429	2775
5 to 6 bracing	635	1658	2775
5 to 6 upper bracing	406	861	2775
5 to 6 cross members	156	426	2775
32 to 11*	136	1445	2775
32 to 32*	81	1765	2775
32 to 34*	119	1640	2775
34 to rig*	118	2714	2775
5 to 7 upper bracing	247	327	2775
5 to 6 cross members	1202	2299	2775
6 to 6 main cross member	1976	2355	2775
6 to 7	1036	1900	2775
Gusset to 10	743	1363	2775
32 to 7 end weld	1273	2535	2775
6 to 7 gusset to 35	3222	4399	5550 ($t_w = 3/8$ in.)
6 to 7 weld on side of members	306	1635	2775
5 to 5 lower bracing	63	687	2775
5, 5 to 7 lower bracing to vertical tube	114 145	713 326	2775 2775
5 to 5 lower bracing	64	1425	2775
Actuator support (90° joint)	976	1133	3700 ($t_w = 1/4$ in.)
Actuator support to C 5x9	3/16" fillet equiv reqd	3/16" fillet equiv reqd	3/4" weld thickness available

*Fixed frame joint

**For fillet weld thickness (t_w) = 3/16 in. unless otherwise specified.

Appendix C: Structural and Stress Analysis, Shielded Receiver Lifting Frame and Jack Assemblies, Core
Sample Truck #3 and #4

TSH

ENGINEERING DATA TRANSMITTAL	Page 1 of <u>1</u> 1. EDT No 612145
-------------------------------------	---

2. To: (Receiving Organization) Characterization Equipment		3. From: (Originating Organization) Life Extension Engineering		4. Related EDT No.: N/A							
5. Proj./Prog./Dept./Div.: Tank Farms		6. Cog. Engr.: F. R. Vollert		7. Purchase Order No.: N/A							
8. Originator Remarks: For review and approval.				9. Equip./Component No.: N/A							
11. Receiver Remarks:				10. System/Bldg./Facility: N/A							
				12. Major Assm. Dwg. No.:							
				13. Permit/Permit Application No.: N/A							
				14. Required Response Date: 07/28/95							
15. DATA TRANSMITTED											
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Impact Level	(G) Reason for Transmittal	(H) Originator Disposition	(I) Receiver Disposition			
1	WHC-SD-WM-ER-469		0	STRUCTURAL AND STRESS ANALYSES, SHIELDED RECEIVER LIFTING FRAME AND JACK ASSEMBLIES, CORE SAMPLER TRUCKS #3 AND #4	Q	1	1				
16. KEY											
Impact Level (F)		Reason for Transmittal (G)			Disposition (H) & (I)						
1, 2, 3, or 4 (see MRP 5.43)		1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)			1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged						
(G)	(H)	17. SIGNATURE/DISTRIBUTION (See Impact Level for required signatures)						(G)	(H)		
Reason	Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	Reason	Disp.
1		Cog. Eng. F. R. Vollert	<i>F. R. Vollert</i>	<i>7/5/95</i>	H5-52						
1	1	Cog. Mgr. K. V. Scott	<i>K. V. Scott</i>	<i>7-14-95</i>	H5-52						
1		QA J. J. Verderber			S1-57						
1		J. L. Smalley			R1-17						
1		R. J. Blanchard			R1-17						
1		T. S. Hundal	<i>T. S. Hundal</i>	<i>7/5/95</i>	H5-52						
1		H. H. Ziada	<i>H. H. Ziada</i>	<i>7-7-95</i>	H5-52						
18. F. R. Vollert		19. R. J. Blanchard		20. K. V. Scott		21. DOE APPROVAL (if required) Ltr. No. N/A					
Signature of EDT Originator		Authorized Representative for Receiving Organization		Cognizant/Project Engineer's Manager		[] Approved [] Approved w/comments [] Disapproved w/comments					

80-7400-172-2 (07/91) GEF097

SUPPORTING DOCUMENT		1. Total Pages
2. Title	3. Number	4. Rev No.
STRUCTURAL AND STRESS ANALYSES, SHIELDED RECEIVER LIFTING FRAME AND JACK ASSEMBLIES, CORE SAMPLER TRUCKS #3 AND #4	WHC-SD-WM-ER-469	0
5. Key Words	6. Authors	
Core Sampler Trucks #3 and #4, Shielded Receiver Lifting Frame (SRLF), Finite Element Static Three Dimensional Structural Analyses, Deadweight (normal) and Transportation Loads, Member and Welded Joint Forces and Stresses, Three Jack Assemblies, Vertical and Horizontal Loads.	Name: F. R. Vollert/T. S. Hundal	
	<i>F.R. Vollert</i> 7/5/95 Signature	
	<i>T.S. Hundal</i> 7/5/95 Signature	
	Organization/Charge Code: 74410/N4XB1	
7. Abstract		
<p>Structural and stress analyses have been completed for the shielded receiver lifting frame (SRLF), and the jack assemblies mounted on core sampler trucks #3 and #4.</p> <p>The SRLF is a space frame structure fabricated from structural steel tubes and channels, with welded joints. Analyses cases were run for the deadweight loads and the deadweight combined with loads representing potential transportation demands. Three dimensional, static finite element analyses were conducted. The analyses results include: the structural member stresses, and the forces in the welded joints. The joint forces were used to calculate the weld stresses. The member and weld stresses were determined to be in conformance with AISC 1989 and AWS 1992. The analyses results, particularly for the welds, do <u>not</u> predict the potential affects of residual stresses, cyclic stress, stress concentrations, and potential defects. Therefore, it is recommended that the welded joints, including the attachments to the truck, be thoroughly cleaned and visually inspected frequently.</p> <p>The front, center and rear jack assemblies are beam structures connected to the trucks. Stress analyses were conducted for the vertical forces applied by the jacks. Also, horizontal jack forces were considered for the front and rear assemblies. For the vertical loads, the member, weld, and bolt stresses in the load paths to the truck were determined to be in conformance with AISC 1989 and AWS 1992. The assemblies have low capacity for horizontal jack loads. Finally, these assemblies are frequently used lifting fixtures for the trucks and core sampling equipment. They should have frequent, comprehensive preventive maintenance (PM) visual inspections for structural distress.</p>		
		8. RELEASE STAMP

CONTENTS

	<u>PAGE</u>
1.0 INTRODUCTION	1
2.0 CONCLUSIONS AND RECOMMENDATIONS	2
3.0 MATERIALS AND ALLOWABLE STRESSES	3
3.1 STRUCTURAL STEEL STRENGTH AND ALLOWABLE STRESSES	4
3.2 WELD ALLOWABLE STRENGTH	4
3.3 BOLT ALLOWABLE STRESSES	5
4.0 CONFIGURATION AND LOADS	5
4.1 SHIELDED RECEIVER LIFTING FRAMES	5
4.2 JACK ASSEMBLIES	5
5.0 STRUCTURAL ANALYSES AND RESULTS	9
5.1 SHIELDED RECEIVER LIFTING FRAME ANALYSES	9
5.2 JACK ASSEMBLY ANALYSES	12
5.2.1 Front Jack Assembly	12
5.2.2 Rear Jack Assembly	13
5.2.3 Center Jack Assembly	13
6.0 ROLLOVER STABILITY ANALYSES	14
7.0 REFERENCES	17
APPENDIX A - FINITE BEAM ELEMENT ANALYSES, SHIELDED RECEIVER LIFTING FRAME, CORE SAMPLER TRUCKS #3 AND #4	
APPENDIX B - STRESS ANALYSES, WELDED JOINTS, SHIELDED RECEIVER LIFTING FRAME, CORE SAMPLER TRUCKS #3 AND #4	
APPENDIX C - STRESS ANALYSES, JACK ASSEMBLIES, CORE SAMPLER TRUCKS #3 AND #4	

STRUCTURAL AND STRESS ANALYSES, SHIELDED RECEIVER LIFTING FRAME AND JACK ASSEMBLIES, CORE SAMPLER TRUCKS #3 AND #4

1.0 INTRODUCTION

Stress analyses and structural evaluations have been conducted for the shielded receiver lifting frames (SRLF) and the jack assemblies mounted on core sampler trucks number 3 and 4. The SRLF was analyzed for the normal operational static vertical (deadweight) loads. It was also analyzed to determine the effects of the deadweight loads combined with additional static vertical and horizontal loads intended to account for the potential demands of transporting the SRLF on the truck. The front, center, and rear jack assemblies including their connections or attachments to the trucks were analyzed for vertical forces applied when the jacks are deployed. These analyses also computed the maximum capacities for concurrent horizontal jack forces for the front and rear jack assemblies.

The SRLF is a space frame structure with welded joints (WHC 1995a). It is fabricated from various size structural steel tubes, except the two main members for the fixed frame portion are 6 inch deep channels. The objectives of the structural analyses include determining and evaluating the stresses in the frame members and the weld joints. Three dimensional static finite beam element analyses of the SRLF were conducted (Images 1993). The models used represent the SRLF in the raised and lowered position, and envelope the restraint provided by the welded attachments to the truck. Fully fixed joints were used in the finite element models. The results were member stresses and joint forces. The joint forces were used to calculate the weld stresses for the joints with methods from Blodgett 1982. The member and weld stresses were evaluated and determined to be in conformance with AISC 1989 and AWS 1992. However, AISC 1989 and AWS 1992 advise that successful welded connections require detailing considerations and precautions for residual welding stresses, load or stress distribution, cyclic stresses, and stress raisers or defects. The SRLF structural member ends are simply and directly welded together. Therefore, the analyses do not predict the potential effects of these factors. To compensate, the SRLF welds including the attachments to the truck should frequently be cleaned and visually inspected.

The front jack assembly is a simple beam (W 5x16) with a center mounted jack. The center jack assemblies (two per truck) act as cantilever beams (W 14x22) with concentrated end loads from the jacks. The rear jack assembly is a simple beam (W 14x22) supported or lifted by end mounted jacks, with concentrated loads at the two attachment points to the truck chassis (WHC 1995b). The objectives of the jack assembly analyses were to calculate the stresses for and evaluate all the structural members, joints (e.g., welds and bolts) and connections in the load path from the jacks and bolsters to the truck chassis. Standard design stress analysis methods for structural steel beam type members and their connections were used. The member, bolt, and weld stresses were determined to be in conformance with AISC 1989 and AWS 1992. The jack assemblies are lifting fixtures for the core sampler trucks, drilling platforms, and the SRLF (with receiver and sample tube). The assemblies will be in frequent use. The front and rear assemblies are potentially stressed near their design allowables in some locations. The assemblies including the

attachments to the trucks should, as preventative maintenance (PM), be thoroughly cleaned and visually inspected frequently.

In addition, a roll over evaluation was performed. The results were used to develop the recommended maximum acceptable speed for trucks 3 and 4.

2.0 CONCLUSIONS AND RECOMMENDATIONS

The SRLF structural analyses results are the stresses and joint forces for the structural members. The joint forces were then used to calculate the welded joint stresses, including the stresses in the gusset plates that stiffen four joints. These calculated member and weld stresses all are within the allowable values. The allowable fillet weld stress basis is the shear stress value at its throat. The AISC 1989 and AWS 1992 further advise that successful welded connections require detailing considerations and precautions for residual welding stresses, load or stress distribution, cyclic stresses, and stress raisers or defects. The SRLF structural member ends are simply and directly welded together. Connection hardware and detailing precautions, e.g., clip angles, which balance joint forces, avoid defects and stress raisers, and minimize residual and secondary stresses, were not used. Therefore, the analyses and the results do not predict or incorporate the potential affects of:

Residual stresses due to fabrication (welding)

Cyclic stress changes during operation and transportation (fatigue)

Stress concentrations, sharp corners, and potential defects in the welded joints

The computed stresses in the members and welds would directly superimpose with residual stresses. This increases the potential for over stresses under all load conditions, particularly for the welds. Cyclic stresses have the potential to initiate and propagate fatigue cracks. Again, the welds with the higher likelihood for stress concentrations and defects are the most vulnerable. Comprehensive analyses to account for these potential effects could be conducted. A number of enveloping assumptions would be necessary. It is believed that, after further analyses, too many uncertainties would remain to eliminate this concern.

It is recommended that the weld joints in the SRLF and the attachments to the truck be thoroughly cleaned and visually inspected frequently. For example, inspect after each 30 days of operation, and after each relocation to another tank farm. The inspections would be for evidence of structural and joint distress including cracks. They should be frequent, because visual inspection may not be able to find cracks before they have advanced considerably.

In the event SRLF structural distress occurs where joint repair is necessary, evaluation should be made to determine if the design details can be readily improved.

For all three jack assemblies subject to the given (WHC 1995c) maximum vertical jack loads only, the calculated member stresses, welds stresses, bolt forces, and bearing loads are within the allowable values and capacities. The jack assemblies are not designed to support horizontal jack loads. Therefore, one recommendation is to post signs on the trucks to warn against allowing side loads on the jacks. Another is that the operating procedures include precautions to prevent the application of any side loads on the jacks.

The front jack maximum vertical 11,100 lbf (WHC 1995c) load alone will develop about 82% of the allowable shear force capacity in the 5/8-in. SAE Grade 8 bolts in the connection to the truck chassis. Therefore, about a 450 lbf horizontal concurrent load on the front jack will over stress these bolts in shear.

The rear jack assembly vertical load capacity is governed by the stress in the 3/16-in. fillet welds to the truck chassis. The 10,000 lbf (WHC 1995c) maximum vertical rear jack loads develop 58% of the allowable stress capacity in these welds. The bolsters on the rear assembly highly limit the capacity for horizontal jack loads. A 500 lbf horizontal rear jack load in the forward or aft longitudinal direction will develop the allowable bending stress capacity in the 1/4-in. thick bolster end plates. A 1,250 lbf horizontal jack load in the left or right lateral direction will develop the allowable stress in the attachment welds for the jack mounting plates on the bolsters.

The center jack given vertical 10,000 lbf design load (WHC 1995c) would develop 55% of the allowable stress capacity in the 3/16-in. fillet welds attaching the end plate to the W 14x22 beam. An evaluation of the center jack assembly for horizontal jack loads was not required.

The jack assemblies are lifting fixtures for the core sampler trucks, drilling platforms, and the SRLF (with receiver and sample tube). The assemblies will be in frequent use. The front and rear assemblies, particularly if subjected to concurrent horizontal jack forces, are potentially stressed near their design allowables in some locations. The assemblies including the attachments to the trucks should, as preventative maintenance (PM), be thoroughly cleaned and visually inspected frequently. These should be comparable to the comprehensive inspections (third party) required for cranes and lifting fixtures with potential serious safety consequences due to failure, and conducted by qualified personnel. Major structural repair should be evaluated in advance by qualified engineering personnel. Damaged lifting fixtures will often be replaced, because the possible repairs could still leave uncertainties and safety concerns.

The recommended maximum acceptable speed for trucks 3 and 4 on Hanford site paved roads is 15 mi/h. This is the same as determined for truck 2 (WHC 1994a).

3.0 MATERIALS AND ALLOWABLE STRESSES

The design drawings (WHC 1995a), (WHC 1995b) for the SRLF and the jack assemblies specify either ASTM A36 or ASTM A500, Grade 8 steel for the structural tubes and channels. The steel plates and other components used are

ASTM A36. The weld metal used has a specified minimum ultimate strength of 70,000 lbf/in². Steel SAE Grade 8 bolts attach the front and center jack assemblies to the trucks. Finally, the truck chassis longitudinal steel members have a minimum ultimate tensile strength (F_u) of 103 Kips/in².

3.1 STRUCTURAL STEEL STRENGTH AND ALLOWABLE STRESSES

The strength, allowable stresses, and other material properties used for all the structural steel members and components in the SRLF and jack assemblies were established conservatively from ASTM A36 steel minimum specifications as follows:

Modulus of Elasticity, E	= 29,000,000 lbf/in ²
Shear Modulus, G	= 11,200,000 lbf/in ²
Poisons Ratio, μ	= 0.300
Ultimate Tensile Strength, F_u	= 58,000 lbf/in ²
Yield Strength, F_y	= 36,000 lbf/in ²
Allowable Tensile Stress, F_t	= $0.60 \times F_y = 21,600$ lbf/in ²
Allowable Bending Stress, F_b	= $0.66 \times F_y = 23,760$ lbf/in ²
Allowable Shear Stress, F_v	= $0.40 \times F_y = 14,400$ lbf/in ²

3.2 WELD ALLOWABLE STRENGTH

The ultimate and allowable strength for the welds joining the SRLF and jack assembly structural members were established in accordance with the Structural Welding Code (AWS 1992), and the Manual of Steel Construction (AISC 1989). These force per unit length values are determined based on the minimum ultimate strength (F_{uwm}) of the weld metal, and the thickness (t_w) of the weld as follows:

Weld Metal Ultimate Strength, F_{uwm}	= 70,000 lbf/in ²
<u>Fillet</u> Weld Ultimate Strength, F_{uw}	= $0.707 \times t_w \times F_{uwm}$ lbf/in
<u>Fillet</u> Weld Allowable Strength, F_w	= $0.30 \times F_{uw} = 14,800 \times t_w$ lbf/in

3.3 BOLT ALLOWABLE STRESSES

Steel structural bolts, SAE Grade 8 (equivalent to ASTM A490), are used to attach the front and center jack assemblies to the core sampler trucks 3 and 4. The front assembly bolted connections to the chassis are bearing (shear) type. The allowable shear stress in these bolts is 28,000 lbf/in². The fixed end supports for the center jack assemblies are provided by end plates bolted to the truck frames. The fixed end moments when the center jacks are deployed will put these bolts in tension. The allowable tension stress in these bolts is 54,000 lbf/in². The allowable bolt bearing stress in the truck chassis members (1/4-in. thickness) is $1.5 \times F_u$, or 1.5×103 Kips/in² = 154 Kips/in².

4.0 CONFIGURATION AND LOADS

4.1 SHIELDED RECEIVER LIFTING FRAMES

The configuration of the SRLF structure for core sampler trucks 3 and 4 obtained from the design drawings H-2-690043 and H-2-690044 (WHC 1995a) is shown in Figures 1, 2, and 3. It is a space frame structure with welded joints. It is fabricated from various size structural steel tubes, except the two main members for the fixed frame portion are 6 inch deep channels. The fixed frame and its two bracing members are welded to the truck. The moveable portion is raised and lowered during normal operation by the two vertical actuators. Figure 1 also shows the location of the normal operation vertical static (deadweight) loads on the moveable portion of the structure. These loads (maximum) are: the sampler hoist shielded receiver box and base plate (2,100 lbf), plus the sampler tube (900 lbf).

The maximum allowable speed on paved roadways is 15 mi/h for the core sampler trucks 3 and 4. This limit was established to prevent truck rollover from the results of a previous analysis for core sampler truck 2 (WHC 1994a). The potential demands of transporting the SRLF on the truck at the 15 mi/h maximum allowed speed, also estimated by the rollover analysis for truck 2 (WHC 1994a), are represented as additional static forces on the SRLF. These are: 0.18 g vertical, 0.43 g longitudinal, and 0.37 g lateral (see Section 6.0). The moveable portion of the SRLF is in the lowered position during transport.

4.2 JACK ASSEMBLIES

The configurations of the front, center, and rear jack assemblies and their connections to core sample trucks 3 and 4 are shown by the design drawings (WHC 1995b). Configuration sketches are also included with the stress analyses in Appendix C. The front and rear assemblies are simple beams with bolted and welded connections, respectively, to the truck chassis. The center assemblies are cantilever beams bolted to the truck frames. Vertical static loads are applied to the assemblies when the jacks are deployed to lift or support the core sample trucks during operation.

Figure 1. Shielded Receiver Lifting Frame Assembly.

Figure 2. Shielded Receiver Support Frame Assembly.

Figure 3. Shielded Receiver Fixed Support Frame Assembly.

The front assembly maximum vertical load on the single center mounted jack is 11,100 lbf. The rear assembly maximum vertical load on each end mounted jack is 10,000 lbf. The maximum capacities for concurrent horizontal jack forces for the front and rear jacks were calculated. The center assemblies were analyzed for a 10,000 lbf vertical (upward) jack or end design load only (WHC 1995c).

5.0 STRUCTURAL ANALYSES AND RESULTS

5.1 SHIELDED RECEIVER LIFTING FRAME ANALYSES

Three dimensional finite element static analyses were conducted for the SRLF structure (Images 1993) for the normal operation deadweight loads, and for deadweight combined with the additional transportation loads. Finite beam element models with the SRLF in the raised and lowered position were developed and used. Also, the fixed frame was modeled two ways: to be fully restrained at all welds to the truck, and with only the two braces providing the overturning restraint. Fully fixed joints were used in the finite element models, because the SRLF structural member ends are simply and directly welded together at the joints or connections. Four of the SRLF connections are stiffened with gusset plates.

Four deadweight loads analyses cases were run. This was necessary to obtain results for the SRLF in both the raised and lowered position, and for the two restraint conditions assumed for the fixed frame. Four transportation load cases were run with the SRLF in the lowered position. This was necessary to obtain results for both forward and aft direction longitudinal loads, and for the two restraint conditions assumed for the fixed frame. The finite beam element models are described in detail, and all the Images 1993 analyses results are provided in Appendix A.

The Images 1993 results include the forces and moments in the members and joints, and the member stresses. The bending, axial, shear, and combined stresses are calculated for each beam element in the SRLF model. The maximum bending, shear, and combined stress values in the SRLF members for deadweight loads, and the transportation loads are listed and compared to the allowables in Table 1 and Table 2, respectively. All of the calculated potential stresses in SRLF structural members are within the allowable.

The stresses in the weld joints due to the member/joint forces and moments were calculated. Weld stress analysis methods from Blodgett 1982 were used. The weld joint stress calculations and evaluations are provided in Appendix B. Table 3 lists the maximum potential weld stresses for the normal deadweight loads, and transportation loads. For comparison, the allowable weld strengths for the welds are also listed in Table 3. All of the calculated potential weld stresses in the SRLF joints are within the allowable strengths. For the normal deadweight loads the calculated weld stresses, with few exceptions, are very low. For the additional transportation loads, most of the calculated weld stresses increase significantly. Three of the weld joint stresses essentially equal their allowable strength. Several others are within 20% of the allowable strength.

Table 1. Maximum SRLF Member Stresses, Normal Deadweight Loads.

Type of Stress	Maximum (lbf/in ²)	Allowable (lbf/in ²)
Bending ⁽¹⁾	9,274	23,760
Shear ⁽²⁾	2,185	14,400
Combined ⁽¹⁾	9,618	23,760

(1) Maximum deadweight bending and combined stresses in the aft 2x2x1/4 tube cross member supporting the shielded receiver.

(2) Maximum deadweight shear stress in the 4x2x1/4 tube main cross member.

Table 2. Maximum SRLF Member Stresses, Deadweight Plus Transportation Loads.

Type of Stress	Maximum (lbf/in ²)	Allowable (lbf/in ²)
Bending	22,080	23,760
Shear	3,975	14,400
Combined	23,740	23,760

Note: All maximum transportation load stresses in the 2x2x1/4 tube members connecting the fixed frame to the truck frame.

Table 3. Calculated and Allowable SRLF Weld Stresses.

Joining Members	Calculated Weld Stress (lbf/in)		Allowable Weld Stress (lbf/in)
	Dead Weight	Transportation	
3 and 3 to 5 with gusset plates (3 joints)	1738 814 990	2387 2251 2525	2775 2775 2775
4 to 3 main cross member	744	969	2775
3 to 3 middle horizontal member	264	1978	2775
3 to 3 edge horizontal member	282	857	2546
3 to 5 top brace to vertical	295	447	2775
3 to 3 top brace to horizontal	280	413	2775
3 to 3 vertical to lower brace	100	236	2775
3 to 3 lower brace to horizontal	376	948	2775
3 to 3 bottom of vertical brace	66	531	2775
3 to 3 bottom of horizontal brace	103	1068	2775
3 and 3 to 5 (3 joints)	150 75 125	446 654 48	2775 2775 2775
6 to 9*	80	1584	2775
9 to 7*	199	4881	5550
7 to C 5x9* (on rig)	195	2589	2775
3 to 6* top of diagonal brace	173	2278	2775
3 to 3* bottom of diagonal brace	144	2336	2775
3 to rig* with gusset plates	237	2762	2775
Actuator support (90° joint)	647	1023	3700
Actuator support to C 5x9 (on rig)	3/16" fillet equivalent required	3/16" fillet equivalent required	1/2" weld thickness available

*Fixed Frame Joint

It was also necessary to use member/joint forces to calculate the bending stresses in the gusset plates that stiffen four joints in the SRLF. The maximum calculated bending stresses in the plates for the deadweight and transportation load cases are 6,992 lbf/in² and 10,413 lbf/in², respectively. These are within the 23,760 lbf/in² allowable bending stress.

5.2 JACK ASSEMBLY ANALYSES

The general scope of the jack assembly analyses was to calculate the stresses for the structural members and joints in the load path from the jack mounting plates and bolsters to the truck chassis. The front, center, and rear jack assemblies including their connections or attachments to the trucks were analyzed for vertical forces applied when the jacks are deployed. These analyses also presumed concurrent horizontal jack forces for the front and rear jack assemblies. The calculations for all three assemblies are provided in Appendix C.

5.2.1 Front Jack Assembly

The front jack assembly is a simple beam (W 5x16) with a single center mounted jack. On each end it is connected to the front ends of the truck chassis longitudinal members. These two connections (or pair) are 5-in. deep brackets fabricated from 3/4-in. plate. They are welded to the ends of the jack assembly, and attached to the chassis with 5/8-in. SAE Grade 8 bolts. The analyses were conducted for the maximum vertical front jack load, 11,100 lbf, and continued to estimate the capacity of the assembly for concurrent longitudinal and lateral jack loads.

For the 11,100 lbf vertical load only on the front jack, the analyses results are:

The maximum shear force in the 5/8-in. bolts is 7,088 lbf. This is about 82% of the allowable 8,600 lbf.

The bending stress in the main W 5x16 beam is 11,149 lbf/in² maximum, compared to 23,760 lbf/in² allowable.

The bending and shear stresses in the bracket connections to the truck chassis are 10,451 lbf/in² and 3,061 lbf/in², respectively. These values are within their allowables, 23,760 lbf/in² bending stress and 14,400 lbf/in² shear stress.

The stress in the 1/4-in. fillet welds attaching the brackets to the ends of the W 5x16 main beam is 336 lbf/in, well within the 3,700 lbf/in allowable.

The bearing stress from the bolts at the holes in the truck chassis members is 45.4 Kips/in². The allowable is 154 Kips/in².

The bearing load capacity for the 7-in. wide jack mounting plate, based on the W 14x22 web crippling potential, is 47.25 Kips. This is very sufficient for the 11.1 Kips maximum vertical jack load.

The shear forces in the 5/8-in. bolts attaching the front jack assembly to the chassis are at 82% allowable due to the 11,100 lbf maximum vertical jack load. Therefore, about a 450 lbf horizontal concurrent load on the jack over stresses these bolts.

5.2.2 Rear Jack Assembly

The rear jack assembly is a simple beam (W 14x22) supported (or lifted) by end mounted jacks, with concentrated loads at the two attachment points to the truck chassis. The attachments to the chassis are 1/4 in thick steel bracket plates welded to the flanges and web on the inside of the W 14x22 beam, and to one side of the chassis longitudinal members. The maximum vertical load on each rear jack is 10,000 lbf. It was also necessary to evaluate the horizontal jack load limits for this assembly.

For the 10,000 lbf maximum vertical rear jack load, the stress analyses results for this assembly are:

The maximum stress in the 3/16-in. fillet welds to the truck chassis is 1,610 lbf/in which is 58% of the allowable 2,775 lbf/in.

The maximum bending stress in the W 14x22 beam is 5,600 lbf/in², compared to 23,760 lbf/in² allowable.

The bearing load capacity, based on web crippling potential, for the bolsters supporting the jacks is 37 Kips. This is very sufficient for the 10 Kips maximum vertical jack load.

The bolsters on the rear jack assembly highly limit the capacity for horizontal jack loads. The design is very similar to the rear jack assembly for core sampler truck number 2. Therefore, the analyses and results for that assembly for horizontal loads apply (WHC 1994b). A 500 lbf horizontal jack load in the forward or aft longitudinal direction will develop the bending stress capacity in the 1/4-in. thick bolster end plates. A 1,250 lbf left or right lateral load will develop the stress capacity in the attachment welds for the jack mounting plates on the bolsters. The other components potentially over stressed by horizontal jack loads exceeding these values are: the main W 14x22 beam, both in bending and torsional shear, the mounting bolts for the jacks to the bolsters, and the attachment welds to the truck chassis.

5.2.3 Center Jack Assembly

The center jack assemblies (two per truck) act as cantilever beams (W 14x22) with concentrated end loads from the jacks. The fixed end supports are provided by the 3/4-in. thick end plates, welded to the end of the beam and bolted (1-in. and 3/4-in. SAE Grade 8 bolts) to the lower frames of the core sampler trucks. The assembly was analyzed for a 10,000 lbf vertical (upward) jack or end load. The analysis results are:

The bending stress in the W 14x22 beam is 10,600 lbf/in² maximum, the allowable is 23,760 lbf/in².

The maximum tension forces in the 1-in. and 3/4-in. bolts attaching the end plates to the truck are 9.3 Kips and 1.9 Kips, versus the 42.4 Kips and 23.9 Kips respective allowables.

The maximum stress in the cantilever beam end plate 3/16-in. fillet weld is 1,533 lbf/in which is 55% of the allowable 2,775 lbf/in.

The bearing load capacity, based on web crippling potential, for the bolster supporting the jack is 37 Kips. This is very sufficient for the 10 Kips maximum vertical jack load.

6.0 ROLLOVER STABILITY ANALYSES

The WHC 1994a rollover stability analysis for core sample truck number 2 which estimates the acceptable 15 mi/h limiting speed on Hanford site paved roads applies to trucks 3 and 4. The potential transportation acceleration loads at 15 mi/h will also be the same as for truck 2, 0.43g longitudinal, 0.37g lateral, and 0.18g vertical. Another analysis was required to estimate the minimum turning radii versus speed for differing roadway bank (super elevation) angles for trucks 3 and 4. Less restrictive turning radii are theoretically required for trucks 3 and 4.

The recommended 15 mi/h maximum speed for truck 2 (WHC 1994a) is governed by the center of gravity (cg) height for the truck with the drilling platform and its equipment. For truck 2 the cg height is 64.3 inches (WHC 1994a). For trucks 3 and 4 it is 60.0 inches, see Table 4, Weight Distributions for Core Sample Trucks 3 and 4 (WHC 1995c). To allow the speed limit for trucks 3 and 4 to increase by 1 mi/h to 16 mi/h, the cg height would have to be 57.0 inches or lower. This would increase the transportation loads by about 10%, which could affect the structural design for the SRLF. Therefore, the recommended maximum acceptable speed for trucks 3 and 4 on paved roads remains at 15 mi/h.

The WHC 1994a minimum turning radii analysis for truck 2 was repeated for trucks 3 and 4. Table 5 has the results, and the comparable results for truck 2 from WHC 1994a. Shorter turning radii are theoretically required for trucks 3 and 4 for given speeds and bank angles due to its lower cg. For both cases, about a 0.7 coefficient of friction is required to prevent skidding during minimum radii turns.

Table 4. Weight Distribution, Core Sample Trucks Number 3 & 4.

	Longitudinal, $x^{(1)}$ (in)	Lateral, $y^{(1)}$ (in)	Vertical, $z^{(2)}$
Truck Chasis	120	0	21
Total	49	0	60

(1) Distance from vertical centerline of rotating platform, +x towards cab, and +y towards driver side.

(2) Distance from ground level, +z up.

Table 5. Theoretical Minimum Turn Radii Core Sample Trucks.

Trucks 3 and 4 with $\beta = 10^\circ$ Body Roll				
Truck Speed (mi/h)	Bank Angle (deg)	Minimum Turn Radius ⁽¹⁾ (ft)	With 0.37 g Force Minimum Turn Radius ⁽¹⁾ (ft)	Coef Friction Req'd ⁽²⁾
15	-10	33	165	0.69
	-3	24	60	0.69
	0	22	46	0.69
12	-10	21	105	0.69
	-3	16	38	0.69
	0	14	30	0.69
9	-10	12	59	0.69
	-3	9	22	0.69
	0	8	17	0.69

Truck 2 with $\beta = 10^\circ$ Body Roll				
Truck Speed (mi/h)	Bank Angle (deg)	Minimum Turn Radius ⁽¹⁾ (ft)	With 0.37 g Force Minimum Turn Radius ⁽¹⁾ (ft)	Coef Friction Req'd ⁽²⁾
15	-10	35	242	0.66
	-3	26	70	0.66
	0	23	52	0.66
12	-10	22	155	0.66
	-3	16	45	0.66
	0	15	33	0.66
9	-10	13	87	0.66
	-3	9	25	0.66
	0	8	19	0.66

¹Minimum radius of turn without rollover.²Minimum required coefficient of static friction between tires and roadway for no skidding.

7.0 REFERENCES

- AISC, 1989, *Manual of Steel Construction, Allowable Stress Design*, Ninth Edition, American Institute of Steel Construction, Chicago, Illinois.
- ASTM, 1989, *Annual Book of ASTM Standards*, American Society for Testing and Materials, Philadelphia, Pennsylvania.
- AWS, 1992, *Structural Welding Code-Steel*, ANSI/AWS D1.1-92, American Welding Society, Miami, Florida
- Blodgett, O. W., 1982, *Design of Welded structures*, James F. Lincoln Arc Welding Foundation, Cleveland, Ohio
- Images, 1993, *Interactive Microcomputer Analysis and Graphics of Engineering Systems, IMAGES-3D*, Version 3.0, Celestial Software, Inc., Berkeley, California.
- WHC, 1994a, *Rollover Analysis of Rotary Mode Core Sampler Truck #2*, WHC-SD-WM-ER-391, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1994b, *Stress analysis of Jacks, Frame, and Bearing Connections and Drill Rod For Core Sampler Truck #2*, WHC-SD-WM-ER-392, Rev 0, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1995a, *Shielded Receiver Lifting Frame Assembly, Core Sample Truck*, Drawing Numbers H-2-690043 and H-2-690044, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1995b, *Rear, Center, and Front Jack Assemblies*, Drawing Numbers H-2-690010, H-2-690011, H-2-690017, and H-2-690106-1, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1995c, Internal Memo, J. L. Smalley to H. H. Ziada, *Estimates of Actual Loads For The Rotary Mode Core Sample Trucks #3 and #4*, Westinghouse Hanford Company, Richland, Washington.

APPENDIX A

FINITE BEAM ELEMENT ANALYSES
SHIELDED RECEIVER LIFTING FRAME
CORE SAMPLER TRUCKS # 3 & 4

A-1

INDEPENDENT REVIEW CHECKLIST

Document Reviewed Finite Element Analyses of Shielded Receiver Lifting Frame for Core Sampler Trucks No. 3 & 4

Author T. S. Hundal

Document No. WHC-SD-WM-ER-467 Rev. 0

Yes No N/A

- ☒ ☐ ☐ Problem completely defined.
- ☒ ☐ ☐ Necessary assumptions explicitly stated and supported.
- ☒ ☐ ☐ Computer codes and data files documented.
- ☒ ☐ ☐ Data used in calculations explicitly stated in document.
- ☒ ☐ ☐ Data checked for consistency with original source information as applicable.
- ☒ ☐ ☐ Mathematical derivations checked including dimensional consistency of results.
- ☒ ☐ ☐ Models appropriate and used within range of validity or use outside range of established validity justified.
- ☒ ☐ ☐ Hand calculations checked for errors.
- ☒ ☐ ☐ Code run streams correct and consistent with analysis documentation.
- ☒ ☐ ☐ Code output consistent with input and with results reported in analysis documentation.
- ☐ ☐ ☒ Acceptability limits on analytical results applicable and supported. Limits checked against sources.
- ☐ ☐ ☒ Safety margins consistent with good engineering practices.
- ☒ ☐ ☐ Conclusions consistent with analytical results and applicable limits.
- ☒ ☐ ☐ Results and conclusions address all points required in the problem statement.

MANDATORY

Software QA Log Number FRV-95-019

F.R. Vollett
Reviewer

6/28/95
Date

CONTENTS OF APPENDIX A

Section	Page
A1. FINITE-ELEMENT MODELS	A-4
A2. FINITE-ELEMENT ANALYSIS INPUTS AND OUTPUTS	A-31

A-3

A1. FINITE-ELEMENT MODELS

The Shielded Receiver Lifting Frame Assembly (SRLF) (Drawing H-2-690044, Sh. 1 & 2) is installed on the core sampler truck drill rig (Drawing H-2-690043) and supports the Shielded Receiver Assembly (Drawing H-2-90020). The Lifting Frame Assembly consists of two parts; the Moveable Frame Assembly shown on Drawing H-2-690044, Sh. 1 (Page A-6) to which the Receiver Assembly is attached, and the Stationary Fixed Support Frame Assembly as shown on Drawing H-2-690044, Sh. 2, (Page A-7) which provide alignment for the moveable frame. The moveable frame is raised and lowered by a pair of hydraulic cylinders. During transportation the moveable frame is in the down position and facing forward, while for operation it is in its full up position. Both frames are fabricated from standard structural steel shapes connected with welded joints.

The purpose of these analyses was to determine the forces in the welded joints and the stresses in the members of the SRLF. The analyses loads are: the receiver assembly deadweight, self weight of the frames, and potential transportation loads. To accomplish this, three dimensional finite-element models were generated for both frames utilizing the IMAGES-3D computer program. One model depicted the moveable frame located in the operating (up) position while the second located it in the transportation (down) position. Beam elements were used for all of the frame members and truss elements for the hydraulic cylinders. Lateral loading between the frames was accomplished with stiff linear springs located at the roller locations which were in contact. Pages A-8 through A-24 show various plots of the geometry models.

The Receiver Assembly deadweight was applied as uniform loads to the moveable frame's horizontal forward and aft members (P/N 3), at the attachment points. This is shown in on page A-25. In addition, the self weight of the frame was included by a 1G gravity load. The potential dynamic loads generated during transportation were applied in three orthogonal directions and were combined with the deadweight of frames and receiver in lower position and for two longitudinal load cases. One case being the aft load and the second as forward load condition. The aft ($f_x = +0.43G$), forward ($f_x = -0.43G$), side ($f_z = 0.37G$) and vertical ($f_y = -.18G$) loads applied to the frame assembly to simulate the effect of dynamic loading as reported in Rollover Analysis of Rotary Mode Core Sampler Truck #2 (WHC-SD-WM-ER-391, Rev.0). The boundary conditions imposed on the model included vertical restraint of the actuators and fixed joints between the drill rig and the Fixed Support Frame aft bracing horizontal members (P/N 3). The 6x4 tube steel bottom member (P/N 7) of the Fixed Support Frame was also restrained against translation and rotation about its torsional axis for one case and only against translation in the second case. These two boundary condition cases were analyzed to provide the worst case loads for these welded joints as well as other affected joints.

The input and output for each of the up/down deadweight and aft/forward transport finite-element models for each of the two boundary conditions is given in Section A2. The resulting weld joint forces, the maximum stresses in frame members and their evaluation are given in Appendix B.

DWG. H-2-690043

A-5

DWG. H-2-690044 SH.2

A-7

IMAGES-3D
Ver. 3.0
Geometry Plot

A-8

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/17/95
15:27: 9

IMAGES-3D
Ver. 3.0
Geometry Plot

A-9

CORE SAMPLER TRUCK NOS. 3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/17/95
15:31:41

IMAGES-3D
Ver. 3.0
Geometry Plot

A-II

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/17/95
15:18:49

IMAGES-3D
Ver. 3.0
Geometry Plot

A-12

C-33

CORE SAMPLER TRUCK NOS. 3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/17/95
15:39: 9

IMAGES-3D
Ver. 3.0
Geometry Plot

A-13

C-34

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME 3/16/95
Wireframe Plot 14:23:48

IMAGES-3D
Ver. 3.0
Geometry Plot

A-14

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/16/95
14:39:15

IMAGES-3D
Ver. 3.0
Geometry Plot

A-15

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/16/95
15:19:59

IMAGES-3D
Ver. 3.0
Geometry Plot

A-16

CORE SAMPLER TRUCK NOS. 3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/16/95
14:58:40

IMAGES-3D
Ver. 3.0
Geometry Plot

A-18

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME 3/16/95
Wireframe Plot 15: 4:38

IMAGES-3D
Ver. 3.0
Geometry Plot

A-20

CORE SAMPLER TRUCK NOS. 3 & 4 SHIELDED RECEIVER LIFTING FRAME 3/16/95
Wireframe Plot 14:54: 7

IMAGES-3D
Ver. 3.0
Geometry Plot

A-21

C-41

CORE SAMPLER TRUCK NOS. 3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/16/95
14:32:38

IMAGES-3D
Ver. 3.0
Geometry Plot

A-22

C-42

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot
3/16/95
14:35:58

IMAGES-3D
Ver. 3.0
Geometry Plot

A-23

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME
Wireframe Plot

IMAGES-3D
Ver. 3.0
Geometry Plot

A-24

CORE SAMPLER TRUCK NOS.3 & 4 SHIELDED RECEIVER LIFTING FRAME 3/16/95
Wireframe Plot 15:27:48

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 1 of 5
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject TRUCK #3 & 4 SELF ASSEMBLY
 (8) Originator P. Schneider Date 3-14-95
 (9) Checker F.R. Vongert Date 5/4/95

(10) APPLIED LOADS DEADWEIGHT LOADS: (-1G, Y AXIS)

$$\text{BEAMS } 37, 38 \text{ \& } 39 = (8.25 \times 900 + 25.25 \times 2100) / (26.5 \times 42) = 54.31 \text{ \# / in } \Rightarrow 76\%$$

$$\text{BEAMS } 41, 42 \text{ \& } 43 = (18.25 \times 900 + 1.25 \times 2100) / (26.5 \times 42) = 17.12 \text{ \# / in } \Rightarrow 24\%$$

A-25

9D-6400-060 I (12:87)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 2 of 5
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject TRUCK #3 & 4 SRLF ASSEMBLY
 (8) Originator [Signature] Date 3-14-95
 (9) Checker F.R. VOLLETT Date 5/4/95

(10) APPLIED LOADS (AFT) i.e. $F_x = 1G$ & $F_z = 1G$

A-26

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 3 of 5
 (4) Building _____ (5) Rev. _____ (6) Job No. _____
 (7) Subject TRUCKS NO. 3 & 4
 (8) Originator T. Staudal Date 3-14-95
 (9) Checker F.R. VOLBERT Date 5/4/95

(10)

LOADS: AFT (+F_x) & LEFT (+F_z)

TRANSPORTATION LOADS W/FRAME IN DOWN POSITION

DETERMINE LOADS ON OUTER BEAMS (37, 38 & 39, 41, 42 & 43):

DUE TO (+F_x) LOADS (TAKE MOMENTS @ PT. A, P. 2)

$$(900 \times 32.5 - 2100 \times 9.5) / 26.5 = 351 \#$$

$$\text{UPLIFT @ NODE 51 \& 52} = 351 / 2 = 176 \#$$

$$\text{DOWN LOAD ON BEAMS 41, 42 \& 43} = 351 / 42 = 8.36 \#/\text{in}$$

F_x LOAD @ FOUR ANCHOR POINTS (NODES 51, 52, 53 & 54)

ASSUME SAME PROPORTIONS AS FOR 1G DOWN LOADS

I.e. 76% @ NODES 51 & 52 & 24% @ NODES 53 & 54

$$\therefore F_x @ 51 \& 52 = 3000 \times 76 / 2 = 1140 \#$$

$$53 \& 54 = 3000 \times 24 / 2 = 360 \#$$

DUE TO (+F_z) LOADS

TAKE MOMENTS @ PT. B

$$(900 \times 32.5 - 2100 \times 9.5) / 18 = 517 \#$$

$$\text{UPLIFT @ 51} = 517 \times 76 = 393 \#$$

$$53 = 517 \times 24 = 124 \#$$

DOWN UDL ON BEAMS 38, 39 & 42, 43

BEAM	(NODE) TO	(NODE)	LOAD	LOAD
38	(51)	(52)	0	12 x 1.1 = 13.2 #/in
39	(52)	(45)	13.2 #/in	29.11 #/in
42	(53)	(54)	0	12 x 3.4 = 4.1 #/in
43	(54)	(45)	4.1 #/in	9.19 #/in

SHEAR LOADS @ 4 ANCHOR POINTS (F_z)

$$F_z @ \text{NODE 51, 52} = 1140 \# \quad \& \quad @ \text{53 \& 54} = 360 \#$$

A-27

$$124 = 27 \times b / 2$$

$$b = 9.19 \#/\text{in}$$

$$9.19 / 27 = .34 \#/\text{in/in}$$

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 4 of 5
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject TRUCK #3 & 4 SRLF ASSEMBLY
 (8) Originator [Signature] Date 3-14-95
 (9) Checker F.R. VOLLEKT Date 5/4/95

(10) APPLIED LOADS (FORWARD) i.e. $F_x = -1G$ & $F_z = 1G$

A-28

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 5 of 5
 (4) Building _____ (5) Rev. _____ (6) Job No. _____
 (7) Subject TRUCKS NO. 3 & 4
 (8) Originator T. Stundal Date 3-14-95
 (9) Checker F.R. VOLLERT Date 5/4/95

(10)

LOADS: FORWARD $(-F_x)$ & LEFT $(+F_z)$

TRANSPORTATION LOADS W/FRAME IN DOWN POSITION

DETERMINE LOADS ON OUTER BEAMS (37, 38, 39 & 41, 42, 43)

DUE TO $(-F_x)$ LOADS (SEE P. 3)SINCE F_x IS REVERSED

∴ UPLIFT @ NODE 53 & 54 = 176 #

DOWN UDL ON BEAMS 37, 38 & 39 = 8.36 #/lin

SHEAR (F_x) @ 4 ANCHOR POINTS (NODES 51, 52, 53 & 54) F_x @ 51, 52 = -1140 #

53, 54 = -360 #

DUE TO $(+F_x)$ LOADS

SAME LOADING AS FOR AFT & LEFT (SEE P. 3)

UPLIFT @ 51 = 393 #

53 = 124 #

DOWN UDL ON BEAMS 38, 39, 42 & 43

BEAM	(NODE) LOAD	TO	(NODE) LOAD
38	(51) 0		(52) 13.2 #/lin
39	(52) 13.2		(45) 29.11 #/lin
42	(53) 0		(54) 4.1 #/lin
43	(54) 4.1		(49) 9.19 #/lin

SHEAR LOADS @ 4 ANCHOR POINTS

 F_z @ 51, 52 = 1140 #

53, 54 = 360 #

A-29

APPENDIX B

STRESS ANALYSES, WELDED JOINTS, SHIELDED RECEIVER LIFTING FRAME,
CORE SAMPLER TRUCKS #3 AND #4

ANALYTICAL CALCULATIONS

Page 1 of 02Subject SRLF STRUCTURAL ANALYSES, TRUCKS 3-4Originator F.R. VOLBERT Date 5/3/95Checker HAROLD H. T. J. M. Date 6-30-95

COMPUTER RUN ID NUMBERS
IMAGES 3D, VERSION 3.0

DEADWEIGHT ANALYSES

LIFT FRAME POSITION	M _z FOR NODES 85, 86	RUN ID NUMBER
UP	RESTRAINED	CM83195
DOWN	RESTRAINED	KØ18365
UP	FREE	EU43418
DOWN	FREE	PY79828

TRANSPORTATION ANALYSES

LONGITUDINAL LOAD DIRECTION	M _z FOR NODES 85, 86	RUN ID NUMBER
FORWARD	RESTRAINED	IB 33923
AFT	RESTRAINED	YE 49602
FORWARD	FREE	GT 73150
AFT	FREE	HK 76347

THE MEMBER FORCES AND STRESSES, AND WELD JOINT FORCES FOR THE SRLF WERE COMPUTED BY THESE ANALYSES.

B-2

BD-6400-060.1 (07/93)

C-51

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 2 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. Vellert Date 1/5/95
 (9) Checker Hazen H. Zinke Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS (3) AND (3) TO (5)

Frame LIFTING

JOINT SKETCH:

B37, N50
 B39, N45
 B14, N38
 B32, N44

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B37, N50	0	1150	203	7065	223	1
	B39, N45	0	1150	203	7063	225	1
	B14, N38	211	1091	112	1688	146	5506
	B32, N44	211	1092	112	1688	146	5507
DOWN	B37, N50	0	1150	252	7136	146	1
	B39, N45	0	1150	252	7134	147	1
	B14, N38	19	1119	156	1597	525	5872
	B32, N44	18	1119	156	1597	524	5872

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B37, N50	0	1150	198	7055	232	1
	B39, N45	0	1150	198	7052	233	1
	B14, N38	212	1091	108	1703	110	5504
	B32, N44	217	1092	109	1703	110	5505
DOWN	B37, N50	0	1150	255	7141	142	1
	B39, N45	0	1150	255	7139	143	1
	B14, N38	19	1119	158	1590	343	5873
	B32, N44	19	1119	158	1589	342	5873

B-3

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. (3) Page 3 of 62
 (4) Building N/A (5) Rev. (6) Job No.
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F. R. Vossert Date 4/5/95
 (9) Checker Hansen H. Tuck Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (3) AND (3) TO (5)

JOINT SKETCH: GLOBAL COORDINATES

Frame LIFTING

B37, N50
 B39, N45
 B14, N38
 B32, N44

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B37, N50	485	1516	1728	12050	3950	223
	B39, N45	503	1350	878	5434	4329	223
	B14, N38	10	1556	590	115	4557	8027
	B32, N44	288	1109	783	2877	5318	6346
AFT	B37, N50	504	1443	491	12750	4334	183
	B39, N45	485	1121	360	3349	3937	183
	B14, N38	281	1562	466	957	3730	7567
	B32, N44	34	1021	284	2976	3005	5456

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B37, N50	489	1537	2057	12280	4062	249
	B39, N45	500	1330	1207	5305	4300	249
	B14, N38	31	1570	574	204	4361	8067
	B32, N44	308	1101	798	3336	5379	6367
AFT	B37, N50	502	1441	491	12710	4299	209
	B39, N45	486	1123	360	3395	3971	209
	B14, N38	289	1566	466	960	3740	7564
	B32, N44	40	1017	285	2979	3000	5461

B-4

ANALYTICAL CALCULATIONS

Page 4 of 62Subject SRL WELD JOINT STRESS ANALYSES, TRUCKS 3 + 4Originator F.R. VOLBERTDate 4/19/95Checker Harold H. ZintaDate 6-30-95MEMBERS (3) AND (3) TO (5)

JOINT SKETCH:

Frame LIFTINGB37, N50
B39, N45B14, N38
B32, N44 GUSSET PL RESISTS M_z IN B14/B32

$$S_z = \frac{4.5^2}{6} = 3.38 \text{ IN}^2 \quad (\text{WELD ONE SIDE ONLY})$$

(FOR DEADWEIGHT:) $(M_z)_{\text{MAX}} = 5873 \text{ IN LB}$

$$FW = \frac{5873}{3.38} = 1738 \text{ LB/IN} < 2775 \text{ ALLOWABLE}$$

(FOR TRANSPORTATION:) $(M_z)_{\text{MAX}} = 8067 \text{ IN LB}$

$$FW = \frac{8067}{3.38} = 2387 \text{ LB/IN} < 2775 \text{ ALLOWABLE}$$

B-5

BD-8400-060.1 (07/93)

ANALYTICAL CALCULATIONS

Page 5 of 62Subject SELF WELD JOINT STRESS ANALYSIS, TRUCKS 3+4Originator F.R. VOLBERT Date 4/19/95Checker Herman H. Zink Date 6-30-95

$$\bar{X} = 1.64", \bar{Y} = 0.57", S_x = 2.13 \text{ IN}^2, S_y = 7.85 \text{ IN}^2$$

WELD STRESS $F_w = \frac{M_x}{S_x} + \frac{M_y}{S_y}$
(FOR DEADWEIGHT,)

$$F_w = \frac{1703}{2.13} + \frac{110}{7.85} = 814 \text{ LB/IN} < 2775 \text{ LB/IN ALLOWED}$$

(FOR TRANSPORTATION:)

$$F_w = \frac{3336}{2.13} + \frac{5374}{7.85} = 2251 \text{ LB/IN} < 2775 \text{ LB/IN ALLOWED}$$

B37/B39 TO (5) WELDS

WELD TO GUSSET ϕ

LET $S_y = 5.33 \text{ IN}^2$ (NEGLECT GUSSET ϕ)

$$\bar{y} = \frac{8 \times 1 + 4.5 \times 3.25}{12.5} = 1.81 \text{ IN}$$

$$I_x = 5.33 + \frac{4.5^3}{12} + 4.5(1.44)^2 + 8 \times 0.81^2 = 27.50 \text{ IN}^3$$

$$S_x = 27.50 / 3.69 = 7.45$$

B-6

BD-6400-060.1 (07/93)

ANALYTICAL CALCULATIONS

Page 5A of 62Subject SELF WELD JOINT STRESS ANALYSIS, TRUCKS 3 AND 4Originator F.R. VOLBERTDate 6/30/95Checker HAROLD H. ZIEGLERDate 7-5-95SECTION PROPERTIES, WELD B14/B32 TO 5 (CHANNEL)

(REF SKETCH, PG 5)

$$\bar{X} = \frac{2 \times 3.5 + 3 \times 1.5 + 2 \times 0}{7} = 1.64 \text{ IN}$$

$$\bar{Y} = \frac{2 \times 2 \times 1 + 3 \times 0}{7} = 0.57 \text{ IN}$$

$$I_x = \frac{2 \times 2^3}{12} + 2 \times 2 \times 0.43^2 + 3 \times 0.57^2 = 3.05 \text{ IN}^3$$

$$S_x = \frac{I_x}{2 - 0.57} = \frac{3.05}{1.43} = 2.13 \text{ IN}^2$$

$$I_y = \frac{3^3}{12} + 3 \times 0.14^2 + 2 \times 1.64^2 + 2 \times 1.86^2 = 14.61 \text{ IN}^3$$

$$S_y = \frac{I_y}{1.86} = 7.85 \text{ IN}^2$$

B-7

BD-6400-060.1 (07/93)

ANALYTICAL CALCULATIONS

Page 6 of 62Subject SELF WELD JOINT STRESS ANALYSES, TRUCKS 3+4Originator F.R. VOLKERTDate 4/19/95Checker Herman H. ZanderDate 6-30-95B31/B39 TO (3) WELDS CONTINUED

(WELD STRESSES)

$$\therefore F_w = \frac{M_x}{S_x} + \frac{M_y}{S_y}$$

(FOR DEAD WEIGHT)

$$F_w = \frac{7065}{7.45} + \frac{223}{5.33} = 990 \text{ LB/IN} < 2775 \text{ LB/IN ALLOWABLE}$$

(FOR TRANSPORTATION)

$$F_w = \frac{12780}{7.45} + \frac{4334}{5.33} = 2525 \text{ LB/IN} < 2775 \text{ LB/IN ALLOWABLE}$$

GUSSET PLATE STRESSES1/4" PL SUPPORTING B14/B32

$$S_2 = \frac{4.5^2}{6} \times 0.25 = 0.84 \text{ IN}^3$$

$$\text{BENDING STRESS} = f_b = \frac{M_3}{S_3}$$

(DEADWEIGHT)

$$f_b = \frac{5873}{0.84} = 6992 \text{ PSI} \quad \text{OK}$$

(TRANSPORTATION)

$$f_b = \frac{8067}{0.84} = 9604 \text{ PSI} \quad \text{OK}$$

B-8

BD-6400-060.1 (07/93)

ANALYTICAL CALCULATIONS

Page 7 of 62

Subject SELF WELD JOINT STRESS ANALYSES TRUCKS 3 & 4Originator F.R. VOLBERT Date 5/1/95Checker Herman H. Zink Date 6-30-95③ AND ③ TO ⑤ CONTINUED

GUSSET PL STRESSES CONTINUED

 $\frac{1}{4}$ PL SUPPORTING B37/B39 WITH $2 \times 2 \times \frac{1}{4}$ TUBE
RESISTS M_x AND M_y FROM B39/B39

$$\bar{x} = \frac{1.59 \times 1}{1.59 + 0.25 \times 4.5} = 0.59 \text{ in}$$

$$I_x = 0.766 + 0.766 \times 0.93^2 + \frac{0.25 \times 4.5^3}{12} + 4.5 \times 0.25 \times 1.32^2$$

$$I_x = 5.28 \text{ in}^4$$

$$I_y = 7.66 + 1.59 \times 0.41^2 + 0.25 \times 4.5 \times 0.59^2 = 1.42 \text{ in}^4$$

FOR MAX GUSSET PL BENDING STRESS:

$$S_y = \frac{I_y}{0.59} = \frac{1.42}{0.59} = 2.41 \text{ in}^3$$

$$S_x = \frac{I_x}{3.57} = \frac{5.28}{3.57} = 1.48 \text{ in}^3$$

$$\text{BENDING STRESS } f_b = \frac{M_x}{S_x} + \frac{M_y}{S_y}$$

(DEADWEIGHT)

$$f_b = \frac{7065}{1.48} + \frac{223}{2.41} = 4866 \text{ PSI OK}$$

(TRANSPORTATION)

$$f_b = \frac{12750}{1.48} + \frac{4334}{2.41} = 10413 \text{ PSI OK}$$

$$F_b = 23760 \text{ PSI ALLOWABLE}$$

B-9

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 8 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F. R. V. LERT Date 4/3/95
 (9) Checker H. M. L. T. With Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS ④ ACTUATOR BM TO ③ Frame LIFTING

JOINT SKETCH:

B44, N40
B46, N47

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B44, N40	0	1653	631	5653	299	2
	B46, N47	0	1653	631	5653	299	2
DOWN	B44, N40	0	1653	646	5633	300	1
	B46, N47	0	1653	646	5633	301	1

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B44, N40	0	1653	629	5655	300	2
	B46, N47	0	1653	629	5655	300	2
DOWN	B44, N40	0	1653	647	5633	300	1
	B46, N47	0	1653	647	5633	300	1

B-10

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 9 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VALERT Date 4/6/95
 (9) Checker H. H. Z. H. Date 5-2-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS ④ ACTUATOR BM TO ③ Frame LIFTING

JOINT SKETCH: GLOBAL COORDINATES

B44, N40

B46, N47

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B44, N40	59	2319	682	5216	496	457
	B46, N47	77	1584	666	7538	2355	457
AFT	B44, N40	72	2445	1245	5267	1983	331
	B46, N47	54	1458	1229	7911	674	331

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B44, N40	62	2343	605	5534	499	493
	B46, N47	80	1560	589	7686	2485	493
AFT	B44, N40	72	2445	1245	5271	1981	388
	B46, N47	54	1459	1229	7908	671	388

B-11

ANALYTICAL CALCULATIONS

Page 10 of 62Subject SELF WELD JOINT STRESS ANALYSES, TRUCKS 3+4Originator F.R. VALERT Date 4/14/95Checker Hazan H. Zia Date 6-30-95MEMBERS ④ ACTUATOR BM TO ③ Frame LIFTING

JOINT SKETCH:

B44, N40

B46, N47

MAX WELD FORCES

DEADWEIGHT: $F_y = 1653 \text{ LB}$, $M_x = 5655 \text{ IN LB}$ TRANSPORTATION: $F_y = 1458 \text{ LB}$, $M_x = 7911 \text{ IN LB}$

WELD JOINT

$$I_x = \frac{2 \times 2^3}{12} + 2 \times 4 = 9.33 \text{ IN}^3, \quad S_x = 9.33 \text{ IN}^2$$

(WELD STRESSES)

DEADWEIGHT

$$F_w = \frac{F_y}{12} + \frac{M_x}{S_x} = \frac{1653}{12} + \frac{5655}{9.33} = 744 \text{ LB/IN}$$

 $F_w < 2700 \text{ LB/IN ALLOW ABCE}$

TRANSPORTATION:

$$F_w = \frac{F_y}{12} + \frac{M_x}{S_x} = \frac{1458}{12} + \frac{7911}{9.33} = 969 \text{ LB/IN OK}$$

 $F_w < 2775 \text{ LB/IN ALLOWABLE}$

B-12

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 11 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. YOLLERT Date 4/3/95
 (9) Checker Harlan H. Zink Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS ③ TO ③ MID HORIZ Frame LIFTING

JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B40, N41	0	9	761	205	49	1
	B40, N46	0	9	761	205	50	1
DOWN	B40, N41	0	9	834	215	49	0
	B40, N46	0	9	834	215	50	0

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B40, N41	0	9	756	204	49	1
	B40, N46	0	9	756	204	50	1
DOWN	B40, N41	0	9	837	215	49	0
	B40, N46	0	9	837	215	50	0

B-13

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 12 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLBERT Date 4/6/95
 (9) Checker Harold H. Zink Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (3) TO (3) MID HORIZ Frame LIFTING

JOINT SKETCH: GLOBAL COORDINATES

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B40, N41	1	69	1333	1514	59	155
	N46	9	47	1340	935	285	155
AFT	N41	10	90	938	1947	258	112
	N46	2	68	995	1379	5	112

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B40, N41	1	75	1244	1608	69	167
	N46	9	52	1251	1062	296	167
AFT	N41	9	90	937	1944	242	132
	N46	1	68	944	1377	12	132

B-14

ANALYTICAL CALCULATIONS

Page 13 of 62Subject SRLF WELD JOINT STRESS ANALYSES, TRUCKS 3 & 4Originator F.R. VOLLERTDate 4/19/95Checker H. ZandaDate 6-30-95MEMBERS (3) TO (3) MID HORT Frame LIFTING

JOINT SKETCH:

MAXIMUM WELD FORCES(DEADWEIGHT) $F_z = 837 \text{ LB}$, $M_x = 215 \text{ IN LB}$ (TRANSPORTATION) $F_z = 938 \text{ LB}$, $M_x = 1947 \text{ IN LB}$ WELD IS $\frac{1}{2}$ $L_w = 4"$, $s_x = 1.33$ WELD STRESSES

(DEADWEIGHT)

$$\text{BENDING } F_{w,B} = \frac{M_x}{s_x} = \frac{215}{1.33} = 162 \text{ LB/IN}$$

$$\text{SHEAR } F_{w,S} = \frac{F_z}{L_w} = \frac{837}{4} = 209 \text{ LB/IN}$$

$$\sqrt{F_{w,B}^2 + F_{w,S}^2} = \sqrt{162^2 + 209^2} = 264 \text{ LB/IN} < 2775 \text{ LB/IN}$$

ALLOWABLE

(TRANSPORTATION)

$$\text{BENDING } F_{w,B} = \frac{M_x}{s_x} = \frac{1947}{1.33} = 1464 \text{ LB/IN}$$

$$\text{SHEAR } F_{w,S} = \frac{F_z}{L_w} = \frac{938}{4} = 234$$

$$\sqrt{F_{w,B}^2 + F_{w,S}^2} = \sqrt{1464^2 + 234^2} = 1478 \text{ LB/IN} < 2775 \text{ LB/IN}$$

ALLOWABLE

B-15

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 14 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLLERT Date 4/4/95
 (9) Checker Hazen H. Tink Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS ③ TO ③ EDGE Horiz Frame LIFTING

JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B41, N42	0	369	49	1424	193	1
	B43, N49	0	369	49	1426	192	1
DOWN	B41, N42	0	369	60	1503	176	0
	B43, N49	0	369	60	1504	176	0

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B41, N42	0	369	51	1423	194	1
	B43, N49	0	369	51	1425	193	1
DOWN	B41, N42	0	369	59	1504	176	0
	B43, N49	0	369	59	1505	175	0

B-16

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 15 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F. R. YOUNG Date 4/7/95
 (9) Checker Hassan H. Zaidin Date 5-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (3) TO (3) EDGE HORIZONTAL Frame LIFTING

JOINT SKETCH: GLOBAL COORDINATES

With M_z Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	F_x lbs	F_y lbs	F_z lbs	M_x in-lbs	M_y in-lbs	M_z in-lbs
FORWARD	B41, N42	124	423	59	3022	368	99
	B43, N49	194	269	214	470	1823	99
AFT	B41, N42	194	589	277	4263	2450	32
	B43, N49	124	432	4	143	692	32

Without M_z Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	F_x lbs	F_y lbs	F_z lbs	M_x in-lbs	M_y in-lbs	M_z in-lbs
FORWARD	B41, N42	126	429	70	3067	388	107
	B43, N49	191	291	203	650	1753	107
AFT	B41, N42	193	591	277	4290	2141	51
	B43, N49	125	431	4	115	701	51

B-17

ANALYTICAL CALCULATIONS

Page 16 of 62Subject SALF WELD JOINT STRESS ANALYSES, TRUCKS 3 & 4Originator F.R. VOLBERTDate 4/19/85Checker Hanan H. ZaidDate 6-20-85MEMBERS (3) TO (3) EDGE HORIZ Frame LIFTING

JOINT SKETCH:

MAXIMUM WELD FORCES(DEADWEIGHT) $M_x = 1509 \text{ IN LB}$ (TRANSPORTATION) $M_x = 4290 \text{ IN LB}$, $M_y = 2141 \text{ IN LB}$

WELD IS $I_x = I_y = 5.33 \text{ IN}^3$
 $S_x = S_y = 5.33 \text{ IN}^2$
 $J_w = 10.66 \text{ IN}^3$, $r' = \sqrt{2} \text{ IN}$

WELD THICKNESS $AWE = (3 \times \frac{3}{16} + \frac{1}{8}) \times \frac{1}{4} = 0.172 \text{ IN}$ ALLOWABLE WELD STRESS $= 0.172 \times 14800 = 2546 \text{ LB/IN}$ WELD STRESSES(DEADWEIGHT) $F_{w,B} = \frac{M_x}{S_x} = \frac{1509}{5.33} = 282 \text{ LB/IN}$ OK

(TRANSPORTATION)

BENDING $F_{w,B} = \frac{M_x}{S_x} = \frac{4290}{5.33} = 809 \text{ LB/IN}$ SHEAR $F_{w,S} = \frac{M_y r'}{J_w} = \frac{2141 \times \sqrt{2}}{10.66} = 284 \text{ LB/IN}$ $\sqrt{F_{w,B}^2 + F_{w,S}^2} = \sqrt{809^2 + 284^2} = 857 \text{ LB/IN} < 2546 \text{ LB/IN}$

ALLOWABLE

B-18

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 17 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLVERT Date 4/4/95
 (9) Checker HARRIS H. ZIMMER Date 4-7-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS (3) TO TOP OF (5) Frame LIFTING

JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B 17, N 4	192	56	20	84	396	1175
	B 35, N 21	192	56	20	84	396	1175
DOWN	B 17, N 4	31	108	20	58	336	1098
	B 35, N 21	31	107	20	58	335	1099

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B 17, N 4	193	57	21	93	410	1173
	B 35, N 21	193	57	21	93	410	1173
DOWN	B 17, N 4	30	108	19	54	329	1099
	B 35, N 21	30	108	19	54	329	1100

B-19

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. (3) Page 18 of 62
 (4) Building N/A (5) Rev. (6) Job No.
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. Volcent Date 4/7/95
 (9) Checker Hassan H. Zaid Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (3) TO TOP OF (5)

Frame LIFTING

GLOBAL COORDINATES
 JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B17, N4	133	56	63	828	726	1640
	B35, N21	13	176	10	546	514	1915
AFT	B17, N4	108	77	8	298	522	1424
	B35, N21	42	181	77	744	1017	1038

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B17, N4	146	44	60	791	664	1650
	B35, N21	26	184	21	494	220	1354
AFT	B17, N4	117	68	9	297	521	1429
	B35, N21	50	188	78	746	1019	1033

B-20

ANALYTICAL CALCULATIONS

Page 19 of 62Subject SELF WELD JOINT STRESS ANALYSIS, TRUCKS 3-4Originator F.R. VOLBERTDate 9/20/95Checker Hassan H. ZakeDate 6-30-95MEMBERS (3) TO (5) TOPFrame LIFTING

JOINT SKETCH:

B 17, N 4

B 35, N 21

MAXIMUM WELD FORCES(DEADWEIGHT) $M_z = 1175 \text{ IN-LB}$, $M_y = 396 \text{ IN-LB}$ (TRANSPORTATION) $M_z = 1650 \text{ IN-LB}$, $M_y = 664 \text{ IN-LB}$, $M_x = 791 \text{ IN-LB}$

WELD $\approx$ $S_y = S_z = 5.33$, $J_w = 10.66 \text{ IN}^3$
 $r' = \sqrt{2}$

WELD STRESSES

(DEADWEIGHT) $F_w = \frac{M_z + M_y}{S_y} = \frac{1175 + 396}{5.33} = 295 \text{ LB/IN}$
 OK

(TRANSPORTATION) BENDING $F_{w,B} = \frac{M_z + M_y}{S_y} = \frac{1650 + 664}{5.33} = 434 \text{ LB/IN}$

SHEAR $F_{w,S} = \frac{M_x r'}{J_w} = \frac{791 \times \sqrt{2}}{10.66} = 105 \text{ LB/IN}$

$\sqrt{2} F_w = \sqrt{434^2 + 105^2} = 447 \text{ LB/IN} \leq 2775 \frac{\text{LB}}{\text{IN}}$
 ALLOWABLE

B-21

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 20 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLLEERT Date 4/2/95
 (9) Checker Hassan H. Zink Date 6-20-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS (3 TO 3) (UPPER BRACE) Frame LIFTING

JOINT SKETCH:

B17, N39

B35, N48

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B17, N39	192	44	20	350	19	1979
	B35, N48	192	44	20	350	19	1979
DOWN	B17, N39	31	120	20	376	79	1947
	B35, N48	31	120	20	376	79	1947

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B17, N39	193	45	21	364	27	1978
	B35, N48	193	45	21	364	27	1978
DOWN	B17, N39	30	120	19	369	75	1947
	B35, N48	30	120	19	369	75	1948

B-22

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 21 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F. R. Volpert Date 4/5/95
 (9) Checker Hassan H. Zaid Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS ③ TO ③ (UPPER BRACE) Frame LIFTING

JOINT SKETCH: GLOBAL COORDINATES

B17, N39
B35, N48

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B17, N39	128	70	68	611	698	2550
	B35, N48	18	190	6	366	342	2078
AFT	B17, N39	113	91	13	520	734	2745
	B35, N48	37	196	82	998	646	2021

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B17, N39	141	59	65	582	646	2580
	B35, N48	32	199	26	1007	710	2020
AFT	B17, N39	122	82	13	531	744	2749
	B35, N48	44	203	82	1008	655	2017

B-23

ANALYTICAL CALCULATIONS

Page 22 of 62Subject SRLF WELD JOINT STRESS ANALYSIS, TRUCKS 3 & 4Originator F. R. VOLLEERTDate 4/19/95Checker H. H. T. H. T. H.Date 6-30-95MEMBERS (3 TO 3) (UPPER BRACE) Frame LIFTING

JOINT SKETCH:

B17, N39

B35, N48

MAXIMUM WELD FORCES(DEADWEIGHT) $M_x = 364 \text{ IN LB}$, $M_z = 1978 \text{ IN LB}$ (TRANSPORTATION) $M_x = 531 \text{ IN LB}$, $M_y = 744 \text{ IN LB}$, $M_z = 2749 \text{ IN LB}$ WELD SKETCH

$$I_x = \frac{2 \times 2^3}{12} + 2 \times 2 \sqrt{2} (1)^2 = 7.0 \text{ IN}^3$$

$$S_x = 7.0 \text{ IN}^2$$

$$I_y = \frac{(2\sqrt{2})^3 (2)}{12} + 2 \times 2 (\sqrt{2})^2$$

$$I_y = 11.8 \text{ IN}^3$$

$$S_y = \frac{I_y}{H/\sqrt{2}} = 4.90 \text{ IN}^2$$

$$J_w = 18.8 \text{ IN}^3$$

$$r = \sqrt{1^2 + (1 + \sqrt{2})^2} = 2.61 \text{ IN}$$

WELD STRESSES

(DEADWEIGHT)

$$\text{BENDING, } F_{w,B} = \frac{M_x}{S_x} = \frac{364}{7} = 52 \text{ LB/IN}$$

$$\text{SHEAR, } F_{w,S} = \frac{M_z}{J_w} = \frac{1978 \times 2.61}{18.80} = 275 \text{ LB/IN}$$

$$\sqrt{\sum F_w^2} = \sqrt{52^2 + 275^2} = 280 \text{ LB/IN} < 2779 \text{ LB/IN}$$

ALLOWED

B-24

ANALYTICAL CALCULATIONS

Page 23 of 62Subject SRIE WELD JOINT STRESS ANALYSIS, TRUCKS 3 & 4Originator F.R. VOLLERT Date 4/19/95Checker H. H. Zierke Date 6-30-95③ TO ③ (UPPER), WELD STRESSES, CONTINUED

(TRANSPORTATION)

$$\text{BENDING } F_{w,B} = \frac{M_x}{S_x} + \frac{M_y}{S_y} = \frac{531}{7.0} + \frac{744}{4.9} = 228 \text{ LB/IN}$$

$$\text{SHEAR } F_{w,S} = \frac{M_{z'}'}{J_w} = \frac{2479 \times 2.61}{18.8} = 344 \text{ LB/IN}$$

$$\sqrt{F_{w,B}^2 + F_{w,S}^2} = \sqrt{228^2 + 344^2} = 413 \text{ LB/IN} < 2775 \text{ LB/IN ALLOWABLE}$$

B-25

BD-8400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 24 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F. R. VOLLEERT Date 7/3/95
 (9) Checker Hansen H. Tzida Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS ③ TO ③ VERT GRADE Frame LIFTING

JOINT SKETCH:

With M_z Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	F _x lbs	F _y lbs	F _z lbs	M _x in-lbs	M _y in-lbs	M _z in-lbs
UP	B66, N57	11	121	23	522	63	716
	B67, N58	11	120	23	523	64	115
DOWN	B66, N57	2	60	18	431	25	99
	B67, N58	2	60	18	431	26	99

Without M_z Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	F _x lbs	F _y lbs	F _z lbs	M _x in-lbs	M _y in-lbs	M _z in-lbs
UP	B66, N57	11	120	24	529	75	114
	B67, N58	11	120	24	530	76	113
DOWN	B66, N57	2	60	18	427	19	98
	B67, N58	2	60	18	428	20	97

B-26

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 25 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLBERT Date 4/5/95
 (9) Checker Hassan H. Zinda Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Shi. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS ③ TO ③ VERT BRACE Frame LIFTING

JOINT SKETCH: GLOBAL COORDINATES

With M_z Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	F_x lbs	F_y lbs	F_z lbs	M_x in-lbs	M_y in-lbs	M_z in-lbs
FORWARD	B66, N57	5	242	122	1241	52	123
	B67, N58	20	135	111	605	250	419
AFT	B66, N57	15	298	134	1082	47	188
	B67, N58	10	104	113	637	162	336

Without M_z Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	F_x lbs	F_y lbs	F_z lbs	M_x in-lbs	M_y in-lbs	M_z in-lbs
FORWARD	B66, N57	3	235	123	1260	36	96
	B67, N58	19	133	99	417	212	401
AFT	B66, N57	15	301	138	1094	63	190
	B67, N58	9	107	114	649	178	339

D-27

ANALYTICAL CALCULATIONS

Page 26 of 62

Subject SRL WELD JOINT STRESS ANALYSIS, TRUCKS 3 & 4Originator F. R. VOLERTDate 7/19/95Checker Hassan H. ZaidanDate 6-30-95MEMBERS ③ TO ③ VERT BASE Frame LIFTING

JOINT SKETCH:

B66 N 57

B67 N 58

MAXIMUM WELD FORCES(DEADWEIGHT) $M_x = 530 \text{ IN LB}$ (TRANSPORTATION) $M_x = 1260 \text{ IN LB}$ WELD IS CLOSELY A 2x2 (SLOPED EDGES LONGER)
Sx $\approx 5.33 \text{ IN}^2$ WELD STRESSES(DEADWEIGHT) $F_w = \frac{M_x}{S_x} = 100 \text{ LB/IN OK}$ (TRANSPORTATION) $F_w = \frac{M_x}{S_x} = 236 \text{ LB/IN OK}$

B-28

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 27 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLTERT Date 4/3/95
 (9) Checker Hasan H. Zinda Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS (3) TO (3) LOWER FRAME LIFTING

JOINT SKETCH:

B64, N6
B65, N23

With M_z Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B64, N6	19	215	12	789	715	1443
	B65, N23	19	214	12	790	716	1443
DOWN	B64, N6	49	24	8	657	67	1263
	B65, N23	49	24	8	658	67	1263

Without M_z Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B64, N6	20	216	12	798	731	1443
	B65, N23	19	216	13	799	732	1443
DOWN	B64, N6	49	23	7	653	59	1263
	B65, N23	49	23	8	654	59	1263

B-29

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 28 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLBERT Date 4/6/95
 (9) Checker Hassan H. Zick Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS ③ TO ③ LOWER BRACE Frame LIFTING

JOINT SKETCH: GLOBAL COORDINATES

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B64, N6	48	185	71	2194	511	1967
	B65, N23	15	21	104	1640	259	804
AFT	B64, N6	114	97	136	3095	886	2431
	B65, N23	70	138	82	1223	296	978

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B64, N6	42	196	74	2204	393	1984
	B65, N23	10	7	97	1365	315	739
AFT	B64, N6	114	100	137	3120	876	2442
	B65, N23	70	140	83	1247	286	966

B-30

ANALYTICAL CALCULATIONS

Page 29 of 62Subject SELF WELD JOINT STRESS ANALYSES, TRUCKS 3 & 4Originator F.R. VOLLERTDate 4/19/95Checker Hassan H. ZiedaDate 6-30-95

MEMBERS (3) TO (3) LOWER BRAKE Frame LIFTING

JOINT SKETCH:

MAXIMUM WELD FORCES(DEADWEIGHT) $M_x = 798 \text{ IN-LB}$, $M_z = 1443 \text{ IN-LB}$ (TRANSPORTATION) $M_y = 3120 \text{ IN-LB}$, $M_z = 876 \text{ IN-LB}$, $M_z = 2442 \text{ IN-LB}$

$$S = \frac{2}{\sin 64^\circ} = 2.22 \text{ IN}$$

$$I_z = 2 \times 2 \times (1.11)^2 + 2 \times 2.22^3 / 12 = 6.75 \text{ IN}^3, S_z = 6.08 \text{ IN}^2$$

$$I_x = \frac{2 \times 2^3}{12} + 2 \times 2.22^2 = 5.77 = S_x$$

NOTE: AVE WELD σ IS $\frac{0.25 + 0.1875}{2} = 0.22''$
 ALLOWABLE = 3150 LB/IN

$$J_w = 11.85 \text{ IN}^3, r' = \sqrt{1^2 + 1.11^2} = 1.49$$

WELD STRESSES

$$\text{(DEADWEIGHT)} F_w = \frac{M_x}{S_x} + \frac{M_z}{S_z} = \frac{798}{5.77} + \frac{1443}{6.08} = 376 \text{ LB/IN}$$

(TRANSPORTATION)

$$\text{BENDING } F_{w,z} = \frac{M_x}{S_x} + \frac{M_z}{S_z} = \frac{3120}{5.77} + \frac{2442}{6.08} = 942 \text{ LB/IN}$$

$$\text{SHEAR, } F_{w,s} = \frac{M_y r'}{J_w} = \frac{876 \times 1.49}{11.85} = 110 \text{ LB/IN}$$

$$\sqrt{F_w^2} = \sqrt{942^2 + 110^2} = 948 \text{ LB/IN} < 3150 \text{ LB/IN ALLOWED}$$

B-31

BD-8400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 30 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOZ-ERT Date 4/4/95
 (9) Checker Haas H. Zink Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS ③ TO 3 VERT BRACE BOTTOM Frame LIFTING

JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B66, N35	11	108	23	131	63	206
	B67, N36	11	108	23	132	64	205
DOWN	B66, N35	2	47	18	85	25	29
	B67, N36	2	47	18	86	26	29

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B66, N35	11	108	24	145	75	205
	B67, N36	11	107	24	146	76	204
DOWN	B66, N35	2	47	18	78	19	30
	B67, N36	2	48	18	79	20	30

B-32

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 31 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. Voulbert Date 4/7/05
 (9) Checker Hassan H. Zinde Date 6-20-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS ③ TO ③ VERT BRACE BOTTOM Frame LIFTING
 GLOBAL COORDINATES
 JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B66, N35	10	228	126	2237	52	89
	B67, N36	14	150	115	2563	250	60
AFT	B66, N35	10	283	141	2809	47	156
	B67, N36	15	119	118	2599	162	7

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B66, N35	9	220	128	2252	36	68
	B67, N36	13	148	104	2431	212	49
AFT	B66, N35	9	286	142	2832	63	151
	B67, N36	15	122	119	2621	178	2

B-33

ANALYTICAL CALCULATIONS

Page 32 of 62Subject SRL WELD JOINT STRESS ANALYSIS, TRUCKS 3 & 4Originator F.R. VOLLETTDate 4/19/95Checker Hason H. ZickDate 6-30-95MEMBERS (3) TO (3) VERT BRACE
Frame LIFTING

JOINT SKETCH:

MAXIMUM WELD FORCES(DEADWEIGHT) $M_X = 145 \text{ IN LB}$, $M_Z = 205 \text{ IN LB}$ (TRANSPORTATION) $M_X = 2832 \text{ IN LB}$

FOR END WELD, 2x2

$$S_X = S_Z = 5.33 \text{ IN}^2$$

WELD STRESSES

$$\text{(DEADWEIGHT)} \quad F_W = \frac{M_X + M_Z}{S} = \frac{145 + 205}{5.33} = 66 \frac{\text{LB}}{\text{IN}} \text{ OK}$$

$$\text{(TRANSPORTATION)} \quad F_W = \frac{M_X}{S} = \frac{2832}{5.33} = 531 \frac{\text{LB}}{\text{IN}} \text{ OK}$$

B-34

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. (3) Page 33 of 62
 (4) Building N/A (5) Rev. (6) Job No.
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.P. VOLVERT Date 4/4/95
 (9) Checker Hason H. Zinda Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES:

MEMBERS (3) TO (3) LOWER BRACE HORIZONTAL Frame LIFTING

JOINT SKETCH:

B48, N35 + N36

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B48, N35	0	9	47	311	196	1
	N36	0	9	47	312	192	1
DOWN	N35	0	9	14	283	66	0
	N36	0	9	14	283	64	0

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B48, N35	0	9	57	309	241	1
	N36	0	9	57	310	237	1
DOWN	N35	0	9	9	284	44	0
	N36	0	9	9	285	41	0

B-35

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 34 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLVERT Date 4/7/95
 (9) Checker Hasan H. Zia Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (3) TO (3) LOWER BRAKE HORIZONTAL Frame LIFTING

GLOBAL COORDINATES
JOINT SKETCH:

B48, N35 & N36

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B48, N35	55	174	93	3727	1858	71
	N36	64	152	86	3107	692	71
AFT	N35	67	186	122	3876	1738	53
	N36	59	163	114	3450	897	53

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B48, N35	58	166	40	3595	1674	108
	N36	66	144	33	2931	921	108
AFT	N35	70	186	121	3891	1800	75
	N36	62	164	114	3465	961	75

B-36

ANALYTICAL CALCULATIONS

Page 35 of 62

Subject SRL F WELD JOINT STRESS ANALYSES, TRUCKS 3+4Originator F. P. VOWARTDate 4/19/95Checker Hanan H. ZiadDate 6-30-95MEMBERS (3) TO (3) LOWER BRACE HORIZONTAL Frame LIFTING

JOINT SKETCH:

B48, N35 + N36

MAXIMUM WELD FORCES(DEADWEIGHT) $M_x = 309 \text{ IN LB}$, $M_y = 241 \text{ IN LB}$ (TRANSPORTATION) $M_x = 3891 \text{ IN LB}$, $M_y = 1800 \text{ IN LB}$

END WELD 2x2

$$S_x = S_y = 5.33 \text{ IN}^2$$

3 0 AX

WELD STRESSES

$$\text{(DEADWEIGHT)} \quad F_w = \frac{M_x + M_y}{S_x} = \frac{309 + 241}{5.33} = 103 \frac{\text{LB}}{\text{IN}} \quad \text{OK}$$

$$\text{(TRANSPORTATION)} \quad F_w = \frac{M_x + M_y}{S_x} = \frac{3891 + 1800}{5.33} = 1068 \frac{\text{LB}}{\text{IN}} \quad \text{OK}$$

B-37

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. (3) Page 36 of 62
 (4) Building N/A (5) Rev. (6) Job No.
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator E.R. VALERT Date 4/5/95
 (9) Checker Hagan H. Tilden Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS ③ AND ③ TO ⑤

Frame LIFTING

BOTTOM ENDS
 JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B47, N37	12	92	24	180	65	1101
	B49, N43	11	92	24	180	67	1099
	B18, N37	8	73	12	423	24	585
	B36, N43	7	72	12	422	24	584
DOWN	B47, N37	2	32	4	198	148	446
	B49, N43	3	32	4	198	147	447
	B18, N37	47	58	10	402	44	327
	B36, N43	47	58	10	401	44	327

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B47, N37	11	92	33	164	134	1096
	B49, N43	11	92	33	164	136	1094
	B18, N37	8	75	12	407	11	583
	B36, N43	8	74	12	406	11	582
DOWN	B47, N37	2	32	9	206	183	449
	B49, N43	2	32	9	206	182	449
	B18, N37	47	59	11	410	50	328
	B36, N43	47	59	11	410	50	328

B-38

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. (3) Page 37 of 62
 (4) Building N/A (5) Rev. (6) Job No.
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLLERT Date 4/5/95
 (9) Checker Hazen H. Zick Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS ③ AND ③ TO ⑤
 BOTTOM ENDS
 JOINT SKETCH: GLOBAL COORDINATES

Frame LIFTING

With M_z Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B47, N37	43	46	222	1490	1110	525
	B49, N43	52	6	32	544	24	101
	B18, N37	49	82	43	1151	555	225
	B36, N43	44	131	1	514	298	251
AFT	B47, N37	60	96	265	1067	1920	1076
	B49, N43	41	37	6	851	674	612
	B18, N37	138	226	7	160	128	595
	B36, N43	70	59	23	59	200	580

Without M_z Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B47, N37	47	47	170	1343	677	512
	B49, N43	55	11	73	500	273	60
	B18, N37	35	65	41	1019	466	220
	B36, N43	38	175	6	617	236	228
AFT	B47, N37	63	92	266	1060	1889	1086
	B49, N43	44	35	7	844	702	600
	B18, N37	138	226	7	171	134	594
	B36, N43	70	58	23	48	196	580

B-39

ANALYTICAL CALCULATIONS

Page 38 of 62Subject SRLF WELD JOINT STRESS ANALYSES, TRUCKS 2 & 4Originator F.R. VOLLERTDate 4/18/95Checker Hoon H. TahaDate 6-30-95MEMBERS (3) AND (3) TO (5)BOTTOM ENDS

JOINT SKETCH:

Frame LIFTING MAXIMUM FORCES(DEADWEIGHT)

$$B18/B36 - M_x = 423 \text{ ft-LB}, M_z = 585 \text{ ft-LB}$$

$$B47/B49 - M_x = 180 \text{ ft-LB}, M_z = 1101 \text{ ft-LB}$$

(TRANSPORTATION)

$$B18/B36 - M_x = 1151 \text{ ft-LB}, M_y = 555 \text{ ft-LB}, M_z = 225 \text{ ft-LB}$$

$$B47/B49 - M_x = 1490 \text{ ft-LB}, M_y = 1110 \text{ ft-LB}, M_z = 525 \text{ ft-LB}$$

WELD JOINTS(B47/B49)

$$L_w = 9.125$$

$$\bar{y} = \frac{2 \times 1 + 2.75 \times 2}{9.125} = 0.82 \text{ IN}$$

$$\bar{x} = \left(\frac{2.75^2}{2} + \frac{4.375^2}{2} \right) \times \frac{1}{9.125} = 1.46 \text{ IN}$$

$$I_x = \frac{2^3}{12} + 2 \times 0.18^2 + 4.375 \times 0.82^2 + 2.75 \times 1.18^2 = 7.50 \text{ IN}^3$$

$$I_y = \frac{2.75^3}{12} + \frac{4.375^3}{12} + 2 \times 1.46^2 + 4.375 \times 0.73^2 + 2.75 \times 0.085^2 = 15.32$$

$$J_w = 22.82 \text{ IN}^3, r' = \sqrt{0.82^2 + 2.92^2} = 3.03 \text{ IN}$$

B-40

BD-6400-060.1 (07/93)

ANALYTICAL CALCULATIONS

Page 39 of 62

Subject SRLF WELD JOINT STRESS ANALYSES, TRUCKS 3 & 4Originator F.D. VOLVERTDate 4/18/95Checker Hagan H. ZindaDate 6-30-95

③ AND ③ TO ⑤ CONTINUED
(WELDS CONTD)

B18 / B36

$$S = \frac{2}{\cos 64^\circ} = 4.56 \text{ IN}$$

$$h = S \sin 64^\circ = 4.10 \text{ IN}$$

$$\bar{y} = \frac{h}{2} = 2.05 \text{ IN}$$

$$\bar{x} = \frac{S \times 1}{S + h} = 0.53 \text{ IN}$$

$$I_x = \frac{2 \times 4.10^3}{12} = 11.49 \text{ IN}^3$$

$$I_y = \frac{2^3}{12} + h \times 0.53^2 = 1.82 \text{ IN}^3$$

(ALSO END WELDED ON 3 EDGES)

$$\bar{z} = \frac{4}{6} = 0.67 \text{ IN}$$

$$I_x = \frac{2 \times 2^3}{12} + 2 \times 0.67^2 + 2 \times 2 \times 0.33^2 = 2.67 \text{ IN}^3$$

$$I_z = \frac{2^3}{12} + 2 \times 2 \times 1 = 4.67 \text{ IN}^3$$

(IT IS SAFE TO PRESUME)

WELD RESISTS M_x AND M_y

AND

END WELD RESISTS M_z

B-41

BD-6400-060.1 (07/93)

ANALYTICAL CALCULATIONS

Page 40 of 62

Subject SPRUE WELD JOINT STRESS ANALYSIS, TRUCKS 3 & 4
 Originator F.R. VOLTERT Date 4/19/95
 Checker Herman H. Zinda Date 6-30-95

③ AND ③ TO ⑤ CONTINUED

WELD STRESSESB47/B99

(DEADWEIGHT)

$$\text{BENDING } F_{w,B} = \frac{M_1 \times 2.92}{I_y} = \frac{180 \times 2.92}{15.32} = 34 \text{ LB/IN}$$

$$\text{SHEAR } F_{w,S} = \frac{M_2}{J_w} r' = \frac{1101 \times 3.03}{22.82} = 146 \text{ LB/IN}$$

$$\sqrt{\Sigma F_w^2} = \sqrt{34^2 + 146^2} = 150 \text{ LB/IN OK}$$

(TRANSPORTATION)

$$\text{BENDING } F_{w,B} = \frac{M_1 \times 1.18}{I_x} + \frac{M_2 \times 2.92}{I_y} = \frac{1490 \times 1.18}{7.5} + \frac{1101 \times 2.92}{15.32}$$

$$F_{w,B} = 446 \text{ LB/IN}$$

SHEAR $F_{w,S}$ DUE TO M_3 BY PROPORTION

$$F_{w,S} = \frac{525}{1101} \times 146 = 6.9 \text{ LB/IN}$$

$$\sqrt{\Sigma F_w^2} = \sqrt{446^2 + 6.9^2} = 451 \text{ LB/IN} < 2775 \text{ LB/IN ALLOWABLE}$$

B18/B36

(DEADWEIGHT)

$$F_{w,1} = \frac{M_1 \times 2.05}{I_x} = \frac{423 \times 2.05}{11.49} = 7.5 \text{ LB/IN OK } \textcircled{\wedge}$$

$$\text{AND } F_{w,2} = \frac{M_2 \times 1}{I_3} = \frac{585}{4.67} = 125 \text{ LB/IN OK } \textcircled{\sqcup}$$

(TRANSPORTATION)

$$F_{w,1} = \frac{M_1 \times 2.05}{11.49} + \frac{M_2 \times 1.47}{I_2} = \frac{1151 \times 2.05}{11.49} + \frac{555 \times 1.47}{1.82} = 654 \text{ LB/IN OK } \textcircled{\wedge}$$

$$F_{w,2} = \frac{M_2 \times 1}{4.67} = \frac{225}{4.67} = 48 \text{ LB/IN OK } \textcircled{\sqcup}$$

B-4Z

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 41 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLBERT Date 4/4/95
 (9) Checker Hansen H. Zink Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS (6) TO (9) Frame FIXED

JOINT SKETCH:

B77, N64

B79, N70

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B77, N64	36	189	88	497	337	171
	B79, N70	35	188	88	497	337	169
DOWN	B77, N64	40	207	20	697	25	118
	B79, N70	40	206	20	696	24	117

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B77, N64	71	351	87	999	331	68
	B79, N70	70	350	87	999	331	67
DOWN	B77, N64	71	352	29	1135	54	31
	B79, N70	71	351	29	1135	54	30

B-43

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 42 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F. R. VULBERT Date 4/6/95
 (9) Checker Hassan H. Zinda Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS ⑥ TO ⑨ Frame FIXED

JOINT SKETCH: GLOBAL COORDS

B77, N64

B79, N70

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B77, N64	709	1438	515	12750	2660	932
	B79, N70	197	662	249	3725	2218	71
AFT	B77, N64	283	1327	582	970	1101	636
	B79, N70	268	1665	380	10680	703	172

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B77, N64	476	2663	812	17530	3859	1824
	B79, N70	502	2138	599	3279	3437	794
AFT	B77, N64	670	3116	681	6210	1927	3944
	B79, N70	628	3352	485	15940	1057	1254

B-44

ANALYTICAL CALCULATIONS

Page 43 of 62Subject SRL WELD JOINT STRESS ANALYSES, TRUCKS 3 & 4Originator F.R. Volz-Eng Date 4/18/95Checker Hansen H. Zinda Date 6-30-95MEMBERS ⑥ TO ⑨Frame FIXED

JOINT SKETCH:

B77, N69

B79, N70

MAXIMUM FORCES(DEADWEIGHT) $M_x = 1135 \text{ IN-LB}$ (TRANSPORTATION) $M_x = 17530 \text{ IN-LB}$, $M_y = 3859 \text{ IN-LB}$ $M_z = 1824 \text{ IN-LB}$, $F_y = 2663 \text{ LB}$ WELD JOINT

$$I_y = \frac{2 \times 2.5^3}{12} + 2 \times 3(1.25)^2 = 11.98 \text{ IN}^3$$

$$S_y = \frac{I_y}{1.25} = 9.58 \text{ IN}^2$$

$$I_z = \frac{2 \times 3^3}{12} + 2 \times 2.5(1.5)^2 = 15.75 \text{ IN}^3$$

$$S_z = \frac{I_z}{1.5} = 10.50 \text{ IN}^2$$

$$J_w = 27.73 \text{ IN}^3, r = \sqrt{1.25^2 + 1.5^2} = 1.95$$

WELD STRESSES(DEADWEIGHT) $F_w = \frac{M_x r}{J_w} = \frac{1135 \times 1.95}{27.73} = 80 \text{ LB/IN. OK}$

(TRANSPORTATION)

$$\text{SHEAR } F_{w,s} = \frac{F_y}{L_w} = \frac{2663}{11} = 242 \text{ LB/IN}$$

$$\text{TORSION SHEAR } F_{w,T} = \frac{M_x r}{J_w} = \frac{17530 \times 1.95}{27.73} = 1233 \text{ LB/IN}$$

$$F_{w,T} + F_{w,s} = 1475 \text{ LB/IN}$$

$$\text{BENDING } F_{w,B} = \frac{M_y}{S_y} + \frac{M_z}{S_z} = \frac{3859}{9.58} + \frac{1824}{10.50} = 577 \text{ LB/IN}$$

$$2F_w = \sqrt{1475^2 + 577^2} = 1584 \text{ LB/IN} < 2075 \text{ LB/IN ALLOWED}$$

B-45

BD-5400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. (3) Page 94 of 62
 (4) Building N/A (5) Rev. (6) Job No.
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.P. VAUGHN Date 4/3/95
 (9) Checker Hassan H. Traib Date 6-30-95

DEAD WEIGHT ANALYSIS GLOBAL COORDINATES

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES:

MEMBERS ⑨ TO ⑦ Frame FIXED

JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B68, N65	35	121	12	6	13	2346
	B88, N59	36	122	12	4	13	2353
DOWN	B68, N65	40	140	90	348	57	2100
	B88, N59	40	140	90	349	57	2104

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B68, N65	70	234	22	28	18	139
	B88, N59	71	235	22	30	19	143
DOWN	B68, N65	71	234	86	402	62	141
	B88, N59	71	235	86	403	62	143

B-46

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. (3) Page 45 of 62
 (4) Building N/A (5) Rev. (6) Job No.
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. JONES Date 4/5/95
 (9) Checker Hazen H. Zink Date 6-20-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (9) TO (7) Frame FIXED

JOINT SKETCH: GLOBAL COORDINATES

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B68, N65	729	741	291	9119	173	23520
	B88, N59	365	1516	783	10210	116	11700
AFT	B68, N65	304	1586	465	8192	94	18260
	B88, N59	642	1248	682	12510	44	28490

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B68, N65	424	2217	291	10610	151	3889
	B88, N59	96	2742	784	9803	106	4982
AFT	B68, N65	55	3274	509	7900	156	4158
	B88, N59	256	3038	583	13080	113	3702

B-47

ANALYTICAL CALCULATIONS

Page 46 of 62Subject SRIF WELD JOINT STRESS ANALYSES, TRUCKS 3 & 4Originator F.R. VOLLETTDate 4/14/95Checker Hann H. ZideDate 6-30-95MEMBERS (9) TO (7)Frame FIXED

JOINT SKETCH:

(MAXIMUM WELD FORCES)

DEADWEIGHT: $M_x = 349 \text{ IN LB}$, $M_z = 2104 \text{ IN LB}$ TRANSPORTATION: $M_x = 12510 \text{ IN LB}$, $M_z = 28490 \text{ IN LB}$

WITHOUT 4 1/2 x 4 1/2 x 1/4 GUSSET PLATE THIS JOINT IS 3/16" FILLET AROUND THE END OF THE MC 6x12

WELD STRESS, DEADWEIGHT:

$$F_w = \frac{M_x}{S_x} + \frac{M_z}{S_z} = \frac{349}{3.55} + \frac{2104}{21.0} = 199 \text{ LB/IN}$$

 $F_w < 2 \times 2700 \text{ LB/IN ALLOWABLE}$ WELD STRESS, TRANSPORTATION:

$$F_w = \frac{M_x}{S_x} + \frac{M_z}{S_z} = \frac{12510}{3.55} + \frac{28490}{21.0} = 4881 \text{ LB/IN}$$

 $F_w < 5550 \text{ LB/IN ALLOWABLE}$

B-48

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 48 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLBERT Date 4/7/95
 (9) Checker Harlan H. Zick Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (7) TO C5X9 ON RIG Frame FIXED

JOINT SKETCH: GLOBAL COORDINATES

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	J85	161	300	4136	0	0	12040
	J86	960	668	5233	0	0	25830
AFT	J85	857	37	5692	0	0	30200
	J86	116	2796	4582	0	0	18500

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	J85	87	4124	9340	0	0	0
	J86	634	910	10940	0	0	0
AFT	J85	456	1801	12600	0	0	0
	J86	228	4936	11480	0	0	0

B-50

ANALYTICAL CALCULATIONS

Page 49 of 62Subject SELF WELD JOINT STRESS ANALYSES, TRUCKS 3+4Originator F. R. Voller Date 4/18/95Checker H. T. H. T. H. Date 6-30-95MEMBERS ⑦ TO C5X9 ON RIG Frame FIXED

JOINT SKETCH:

MAXIMUM FORCES(DEADWEIGHT) $M_z = 2275 \text{ IN LB}$ (TRANSPORTATION) $M_z = 30200 \text{ IN LB}$ NOTE: THIS WELD PROVIDES LITTLE M_z RESISTANCE PRESUME CENTER OF M_z ROTATION AT ϕ ⑦

$$J_z = \frac{6^3}{12} + 6 \times 2^2 = 42 \text{ IN}^3, \quad r' = \sqrt{3^2 + 2^2} = 3.60 \text{ IN}$$

WELD STRESSES

$$\text{(DEADWEIGHT)} \quad F_w = \frac{M_z r'}{J_z} = \frac{2275 \times 3.60}{42} = 195 \frac{\text{LB}}{\text{IN}} \text{ OK}$$

(TRANSPORTATION)

$$F_w = \frac{M_z r'}{J_w} = \frac{30200 \times 3.60}{42} = 2589 \frac{\text{LB}}{\text{IN}}$$

$$F_w = 2589 \frac{\text{LB}}{\text{IN}} < 2975 \frac{\text{LB}}{\text{IN}} \text{ ALLOWABLE}$$

B-51

BD-5400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 50 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOIGT Date 4/4/95
 (9) Checker Hasan H. Zinda Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: GLOBAL COORDINATES

MEMBERS (3) TO (6) Frame FIXED

JOINT SKETCH:

B80, N77

B82, N80

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B80, N77	36	203	13	384	126	170
	B82, N80	35	202	13	383	126	170
DOWN	B80, N77	40	222	12	358	91	118
	B82, N80	40	221	12	357	90	118

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B80, N77	71	366	23	677	198	68
	B82, N80	70	364	23	676	197	67
DOWN	B80, N77	71	366	21	623	159	30
	B82, N80	71	365	21	622	158	30

B-52

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 51 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOUGENT Date 4/6/95
 (9) Checker Hagan H. Zula Date 6-30-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (3) TO (6) Frame FIXED

JOINT SKETCH: GLOBAL COORDINATES

B80, N77

B82, N80

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B80, N77	183	920	160	4364	399	384
	B82, N80	233	1146	66	1618	225	477
AFT	B80, N77	326	1739	24	473	372	190
	B82, N80	238	1287	189	5280	1012	275

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B80, N77	446	2150	225	6252	231	1208
	B82, N80	544	2618	1	271	213	1410
AFT	B80, N77	714	3550	85	2799	1257	919
	B82, N80	596	2953	292	8904	1768	729

B-53

ANALYTICAL CALCULATIONS

Page 52 of 62Subject SRL WELD JOINT STRESS ANALYSES, TRUCKS 364Originator F.R. VOLLETTDate 4/18/85Checker Hanson H. T. J.Date 6-30-85MEMBERS (3) TO (6)Frame FIXED

JOINT SKETCH:

MAXIMUM FORCES(DEADWEIGHT) $F_y = 366 \text{ LB}$, $M_x = 677 \text{ IN-LB}$ (TRANSPORTATION) $F_y = 2953$, $M_x = 8404$, $M_y = 1768$ (WELD JOINT) $\frac{3}{4}$ $L_w = 8 \text{ IN}$ WELD STRESSES(DEADWEIGHT) $F_w = \frac{F_y}{L_w} + \frac{M_x}{S_x} = \frac{366}{8} + \frac{677}{5.33} = 173 \text{ LB/IN OK}$

(TRANSPORTATION)

$$F_w = \frac{F_y}{L_w} + \frac{M_x}{S_x} + \frac{M_y}{S_y} = \frac{2953}{8} + \frac{8404}{5.33} + \frac{1768}{5.33} = 2278 \frac{\text{LB}}{\text{IN}}$$

$$< 2755 \text{ LB/IN}$$

B-54

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 53 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOLLEKT Date 4/9/95
 (9) Checker Harold H. Zick Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: LOCAL COORDINATES

MEMBERS ③ TO ③ BRACE LOWER END Frame FIXED

JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B80, N78	229	4	13	58	282	69
	B82, N81	228	4	13	58	281	69
DOWN	B80, N78	248	2	12	28	280	93
	B82, N81	248	2	12	27	280	93

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B80, N78	396	2	23	78	491	304
	B82, N81	394	2	23	78	490	304
DOWN	B80, N78	396	3	21	49	468	300
	B82, N81	395	3	21	49	467	300

B-55

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 54 of 62
 (4) Building NIA (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator E. R. VOLLEERT Date 4/6/95
 (9) Checker Hassan H. Taha Date 6-20-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS ③ TO ③ BRACE LOWER END Frame FIXED

JOINT SKETCH:

LOCAL COORDINATES

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B80, N78	912	37	169	358	4235	1146
	B82, N81	1143	47	74	56	2033	1616
AFT	B80, N78	1798	27	33	448	1074	1466
	B82, N81	1338	18	198	88	4735	1075

Without Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B80, N78	2169	84	234	356	5706	2824
	B82, N81	2647	100	8	163	478	3430
AFT	B80, N78	3649	97	74	756	1253	4033
	B82, N81	3040	83	301	295	6924	3503

B-56

ANALYTICAL CALCULATIONS

Page 55 of 62Subject SRLF WELD JOINT STRESS ANALYSES TRUCKS 3 & 4Originator F. R. VOLLERTDate 4/18/95Checker Hasan H. ZuhDate 6-30-95LOCAL COORDINATESMEMBERS (3) TO (3) BRACE LOWER END Frame FIXED

JOINT SKETCH:

MAXIMUM FORCES(DEADWEIGHT) $M_y = 468 \text{ IN-LB}$, $M_z = 300 \text{ IN-LB}$ (TRANSPORTATION) $F_x = 3090 \text{ LB}$, $M_y = 6924 \text{ IN-LB}$
 $M_z = 3503 \text{ IN-LB}$ FOR WELD AROUND END OF $2 \times 2 \times 1/4$ TUBE $S_y = S_z = 5.33 \text{ IN}^2$, $L_w = 4 \times 2 = 8 \text{ IN}$ WELD STRESSESFOR DEADWEIGHT: $F_w = \frac{M_y}{S_y} + \frac{M_z}{S_z} = \frac{468 + 300}{5.33} = 144 \frac{\text{LB}}{\text{IN}}$
OK

FOR TRANSPORTATION:

 $F_w = \frac{F_x}{L_w} + \frac{M_y}{S_y} + \frac{M_z}{S_z} = \frac{3090}{8} + \frac{6924 + 3503}{5.33} = 2336 \frac{\text{LB}}{\text{IN}}$ $F_w = 2336 \text{ LB/IN} < 2775 \text{ LB/IN ALLOWABLE}$

B-57

BD-6400-060.1 (07/93)

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 56 of 62
 (4) Building N/A (5) Rev. _____ (6) Job No. _____
 (7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
 (8) Originator F.R. VOUERT Date 4/6/95
 (9) Checker Hassan H. T. J. Date 6-30-95

DEAD WEIGHT ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: LOCAL COORDINATES

MEMBERS (3) WELDED TO C5x9 Frame FIXED

JOINT SKETCH:

C5x9

(3)

B81, N79

B83, N82

With Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B81, N79	13	232	4	69	38	871
	B83, N82	13	230	4	69	37	866
DOWN	B81, N79	12	251	3	93	14	967
	B83, N82	12	250	3	93	14	964

Without Mz Restrained at Nodes 85 and 86

Moveable Frame Position	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
UP	B81, N79	23	398	2	304	90	1493
	B83, N82	23	396	2	304	89	1489
DOWN	B81, N79	21	398	3	300	64	1518
	B83, N82	21	397	3	300	64	1514

B-58

DESIGN CALCULATION

(1) Drawing H-2-690044 (2) Doc. No. _____ (3) Page 57 of 62
(4) Building N/A (5) Rev. _____ (6) Job No. _____
(7) Subject Core Sampler Truck Nos. 3 & 4 Shielded Receiver Lifting Frame Assembly
(8) Originator F.R. Vincent Date 4/6/95
(9) Checker H. Aaron 14. Trish Date 6-22-95

TRANSPORT LOADS ANALYSIS

(Ref. Drawings H-2-690043 and 690044 Sh. 1 & 2)

WELD JOINT FORCES: (Moveable Frame in Down Position)

MEMBERS (3) WELDED TO C5X9 Frame FIXED

LOCAL COORDINATES (ON RIG)
JOINT SKETCH:

With Mz Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B81, N79	170	910	36	1146	171	321
	B83, N82	75	1141	49	1616	292	7744
AFT	B81, N79	33	1801	28	1466	584	10070
	B83, N82	199	1341	18	1075	179	1463

Without M_z Restrained at Nodes 85 and 86

Longitudinal Load Direction	Beam and Node Numbers	Fx lbs	Fy lbs	Fz lbs	Mx in-lbs	My in-lbs	Mz in-lbs
FORWARD	B81, N79	234	2167	86	2824	70	5133
	B83, N82	9	2644	101	3430	666	13710
AFT	B81, N79	76	3652	98	4033	1244	17000
	B83, N82	302	3043	84	3503	714	8284

B-59

ANALYTICAL CALCULATIONS

Page 58 of 62Subject SRLF WELD JOINT STRESS ANALYSIS, TRUCKS 344Originator F.R. VOULTDate 4/25/95Checker Hassan H. ZaidDate 6-20-95MEMBERS ③ WELDED TO C5x9 Frame FIXED

JOINT SKETCH:

B81, N79

B83, N82

LOCAL
COORDINATES MAXIMUM WELD FORCES(DEADWEIGHT:) $M_z = 1518 \text{ IN LB}$ (TRANSPORTATION) $F_y = 3652 \text{ LB}$, $M_x = 4033 \text{ IN LB}$,
 $M_y = 1244 \text{ IN LB}$, $M_z = 17000 \text{ IN LB}$ WELD TO TUBE AND GUSSETS:

$$\bar{y} = \frac{8 \times 1 + 2 \times 3 \times 2}{14} = 1.43 \text{ IN}$$

$$I_z = 5.33 + 8 \times 0.43^2 + \frac{2 \times 3^3}{12} + 6 \times 0.57^2$$

$$I_z = 13.26 \text{ IN}^3$$

$$S_z = \frac{13.26}{2.07} = 6.41$$

$$I_y = 5.33 + 2 \times 3 = 11.33$$

$$S_y = 11.33$$

$$J_w = 24.54 \text{ IN}^3$$

$$r' = \sqrt{12 + 2.07^2} = 2.30 \text{ IN}$$

WELD STRESSES

(DEADWEIGHT)

$$F_w = \frac{M_z}{S_z} = \frac{1518}{6.41} = 237 \text{ LB/IN OK}$$

B-60

BD-6400-060.1 (07/93)

ANALYTICAL CALCULATIONS

Page 59 of 62

Subject SELF WELD JOINT STRESS ANALYSES, TRUCKS 3-4
 Originator FR Vincent Date 4/26/95
 Checker Hossein H. Zaidi Date 6-30-95

③ WELDED TO C5X9 CONTINUED

WELD STRESSES, (TRANSPORTATION)

$$F_w = \frac{M_y}{S_y} + \frac{M_z}{S_z} = \frac{1244}{11.33} + \frac{17000}{6.41} = 2762 \text{ LB/IN}$$

$$F_w \approx 2775 \text{ LB/IN OK}$$

GUSSET PLATES

PLATES ACT WITH TUBES AS COMPOSITE SECTION.

$$\bar{y} = \frac{0.25 \times 3 \times 2 \times 2 + 1.59 \times 1}{1.59 + 6 \times 0.25}$$

$$\bar{y} = 1.49 \text{ IN}$$

$$I_z = 0.766 + 1.59 \times 0.49^2 + \frac{0.25 \times 3^3 \times 2}{12} + 6 \times 0.51^2$$

$$I_z = 3.83 \text{ IN}^4 \quad S_z = \frac{I_z}{2.01} = 1.91 \text{ IN}^3$$

$$I_y = 0.766 + 2 \times 3 \times 1 = 6.766 \text{ IN}^4$$

$$S_y = 6.766 \text{ IN}^3$$

(DEAD WEIGHT)

$$f = \frac{M_z}{S_z} = \frac{1518}{1.91} = 795 \text{ PSI OK}$$

(TRANSPORTATION)

$$f = \frac{M_y}{S_y} + \frac{M_z}{S_z} = \frac{1244}{6.766} + \frac{17000}{1.91} = 9084 \text{ PSI}$$

$$f < 23760 \text{ PSI ALLOWABLE OK}$$

B-61

ANALYTICAL CALCULATIONS

Page 60 of 62

Subject SALF WELD JOINT STRESS ANALYSIS, TRUCKS 3 & 4Originator F.R. VOLLEERTDate 3/31/95Checker HAROLD H. ZACHDate 6-30-95ACTUATOR SUPPORT

H-2-690043

WITH AND WITHOUT M_2 RESTRAINT AT NODES B5 & B6

FRAME POSITION	DEADWEIGHT (PA)	TRANSPORT (PA) FWD	TRANSPORT (PA) AFT
UP	1690	X	X
DOWN	1681	2531	2671

DEADWEIGHT ANALYSIS, WELD STRESSES

(90° WELD JOINT 7" LONG)

$$F_u = P_A = 1690 \text{ LB MAX}$$

$$M_z = 6 \times P_A = 6 \times 1690 = 10140 \text{ IN-LB}$$

$$\text{WELD SHEAR } F_{w,s} = \frac{3}{2} \times \frac{F_u}{7} = 362 \text{ LB/IN}$$

$$\text{BENDING STRESS } F_{w,b} = \frac{M_z}{S_x} = \frac{10140 \times 6}{72} = 1242 \text{ LB/IN}$$

$$\sqrt{\Sigma F_w^2} = \sqrt{362^2 + 1242^2} = 1294 \text{ LB/IN}$$

$$\text{OR } \frac{1294}{2} = 647 \text{ LB/IN ON EACH } \frac{1}{4} \text{ FILLET}$$

$$647 \text{ LB/IN} < 370.0 \text{ LB/IN ALLOWABLE}$$

B-62

BD-6400-060.1 (07/93)

ANALYTICAL CALCULATIONS

Page 6.1 of 62Subject SRL WELD JOINT STRESS ANALYSIS, TRACKS 3+4Originator F.R. VOLBERTDate 4/13/95Checker H. ZindDate 6-30-95ACTUATOR SUPPORT CONTINUED

(DEAD WEIGHT) WELD AT C 5+9

$$b = 1.885, d = 5.0, \bar{z} = 0.478$$

$$S_z = 13.6 \text{ in}^2, J_w = 37 \text{ in}^3, r' = 2.87$$

$$F_y = P_A = 1690 \text{ LB MAX}$$

$$M_z = F_y \times 6.75 = 11408 \text{ IN LB}$$

$$\text{(TORSION)} M_x = F_y \times (6.375 - \bar{z}) = 9966 \text{ IN LB}$$

WELD STRESSES

$$\text{(SHEAR)} F_{w,s} = \frac{F_y}{(2b+d)} = \frac{1690}{8.77} = 193 \text{ LB/IN}$$

$$\text{(TORSION SHEAR)} F_{w,T} = \frac{M_x r'}{J_w} = 773 \text{ LB/IN}$$

$$F_{w,s} + F_{w,T} = 966 \text{ LB/IN}$$

$$\text{(BENDING)} F_{w,B} = \frac{M_z}{S_z} = \frac{11408}{13.6} = 839 \text{ LB/IN}$$

$$\sqrt{2F_w^2} = \sqrt{966^2 + 839^2} = 1279 \text{ LB/IN}$$

$$1279 \text{ LB/IN} < 2755 \text{ LB/IN} \text{ ALLOWABLE FOR } 3/16 \text{ FILLET EQUIVALENT}$$

B-63

ANALYTICAL CALCULATIONS

Page 62 of 62Subject SRLF WELD JOINT STRESS ANALYSES, TRUCKS 3-4Originator F.R. VOLLEERTDate 4/19/95Checker HAROLD H. ZIMMDate 6-30-95ACTUATOR SUPPORT CONTINUEDTRANSPORTATION LOAD ANALYSIS, WELD STRESSES
(90° WELD JOINT)

$$F_y = 2671 \text{ LB (MAX)}$$

$$\text{BY PROPORTION: SHEAR } F_{w,s} = \frac{2671}{1690} \times 362 = 572 \text{ LB/IN}$$

$$\text{AND BENDING } F_{w,b} = \frac{2671}{1690} \times 1242 = 1963 \text{ LB/IN}$$

$$\sqrt{\Sigma F_w^2} = \sqrt{572^2 + 1963^2} = 2045 \text{ LB/IN OR:}$$

$$\frac{2045}{2} = 1023 \text{ LB/IN ON EACH } \frac{1}{4} \text{ " FILLET}$$

$$1023 \text{ LB/IN} \ll 3700 \text{ LB/IN ALLOWABLE}$$

(WELD AT C 5x9)

$$\text{(SHEAR)} F_{w,s} = \frac{2671}{1690} \times 193 = 305 \text{ LB/IN}$$

$$\text{(TORSION SHEAR)} F_{w,t} = \frac{2671}{1690} \times 773 = 1223 \text{ LB/IN}$$

$$F_{w,s} + F_{w,t} = 1528 \text{ LB/IN}$$

$$\text{(BENDING)} F_{w,b} = \frac{2671}{1690} \times 839 = 1326 \text{ LB/IN}$$

$$\sqrt{\Sigma F_w^2} = \sqrt{1528^2 + 1326^2} = 2023 \text{ LB/IN}$$

$\frac{3}{16}$ " FILLET EQUIV, ALLOWABLE = 2700 LB/IN
IS REQUIRED FOR TRANSPORTATION LOAD.

$\frac{1}{2}$ " EQUIV WELD THICKNESS EXISTS, OK

B-64

BD-6400-060.1 (07/93)