SEP 23 1999

ENGINEERING DATA TRANSMITTAL

Page 1 of 1

1. EDT 627137

2. To: (Receiving Organization) Process Development, NHC		3. From: (Originating Organization) Process Engineering, LMHC		4. Related EDT No.: NA	
5. Proj./Prog./Dept./Div.: RPP/Process Development		6. Design Authority/Design Agent/Cog. Engr.: Robert W. Harmsen, Cog. Engr.		7. Purchase Order No.: NA	
8. Originator Remarks: Complete document with reviewer comments incorporated for initial release.				9. Equip./Component No.: NA	
				10. System/Bldg./Facility: NA	
				12. Major Assm. Dwg. No.: NA	
				13. Permit/Permit Application No.: NA	
11. Receiver Remarks:				11A. Design Baseline Document? ☐ Yes ☒ No	
				14. Required Response Date: Sept 22, 1999	

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Approval Designator	Reason for Transmittal	Originator Disposition	Receiver Disposition
1	HNF-3719		0	HTWOS OWVP V&V PROCEDURE	NA	2	1	1

16. KEY		
Approval Designator (F)	Reason for Transmittal (G)	Disposition (H) & (I)
E, S, Q, D OR N/A (See WHC-CM-3-5, Sec. 12.7)	1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)											
(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN
		Design Authority				1	1	J.N. Strode	<i>J.N. Strode</i>	9/22/99	R2-11
		Design Agent				1	1	R.S. Wittman	<i>R.S. Wittman</i>	9/22/99	R3-75
1	1	Cog. Eng. R.W. Harmsen	<i>R.W. Harmsen</i>	9/22/99	R3-75						
1	1	Cog. Mgr. K.M. Harmsen	<i>K.M. Harmsen</i>	9/22/99	R2-11						
		QA									
		Safety									
		Env.									

18. Signature of EDT Originator <i>R.W. Harmsen</i> 9/22/99 Date	19. Authorized Representative for Receiving Organization <i>K.M. Harmsen</i> 9/23/99 Date	20. Design Authority Cognizant Manager <i>K.M. Harmsen</i> 9/22/99 Date	21. DOE APPROVAL (if required) Ctrl No. _____ ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments

Hanford Tank Waste Operation Simulator Operational Waste Volume Projection Verification And Validation Procedure

R. W. Harmsen, J. N. Strode, and R. S. Wittman

Fluor Daniel Hanford, Inc., Richland, WA 99352

U.S. Department of Energy Contract DE-AC06-96RL13200

EDT: 627137

UC: 721

Org Code: 82410

Charge Code: 106436

B&R Code: EW02J1190

Total Pages: ~~120~~ 118

of 4.2244

Key Words: Waste Volume Projection, Hanford Tank Waste Operation Simulator, Verification, Double-Shell Tank, Integrated Dynamic Simulation, Test Procedure, Operational Constraints, Assumption Matrix

Abstract: The Hanford Tank Waste Operation Simulator is tested to determine if it can replace the FORTRAN-based Operational Waste Volume Projection computer simulation that has traditionally served to project double-shell tank utilization. Three Test Cases are used to compare the results of the two simulators; one incorporates the cleanup schedule of the Tri Party Agreement.

* UNIX is a registered trademark of UNIX System Laboratories, Inc.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

9/23/99
Release Approval Date

Approved for Public Release

Hanford Tank Waste Operation Simulator Operational Waste Volume Projection Verification and Validation Procedure

R. W. Harmsen
J. N. Strode
Lockheed Martin Hanford Corporation

R. W. Wittman
Numatec Hanford Corporation

Date Published
September 1999

Prepared for the U.S. Department of Energy
Assistant Secretary for Environmental Management

FLUOR DANIEL HANFORD, INC.

P.O. Box 1000
Richland, Washington

Hanford Management and Integration Contractor for the
U.S. Department of Energy under Contract DE-AC06-96RL13200

This page intentionally left blank.

CONTENTS

1.0	INTRODUCTION	1-1
1.1	TRADITIONAL OPERATIONAL WASTE VOLUME PROJECTION PROCESS	1-1
1.2	DYNAMIC SIMULATION OPERATIONAL WASTE VOLUME PROJECTION APPROACH	1-2
1.3	CHANGES IN OPERATIONAL WASTE VOLUME PROJECTION IMPLEMENTATION	1-2
1.4	OPERATIONAL WASTE VOLUME PROJECTION VERIFICATION AND VALIDATION PHASES	1-2
2.0	SUMMARY OF RESULTS	2-1
2.1	REQUIREMENTS PHASE SUMMARY	2-1
2.2	TEST PHASE SUMMARY	2-1
3.0	REQUIREMENTS PHASE PROCEDURE	3-1
3.1	REQUIREMENTS TRACEABILITY TO OPERATIONAL WASTE VOLUME PROJECTION DOCUMENTATION	3-1
	3.1.1 Requirements for Generating Annual Report	3-1
	3.1.2 Requirements for Generating Reports in Response to Special Case Requests	3-4
3.2	REQUIREMENTS TRACEABILITY FOR REVISED CAPABILITIES	3-4
3.3	REQUIREMENTS INTERFACE ANALYSIS	3-5
	3.3.1 Requirements for Operational Waste Volume Projection Work Station	3-5
	3.3.2 Interface Specification for Postprocessing Software	3-5
	3.3.3 User Interface	3-5
4.0	REQUIREMENTS PHASE RESULTS	4-1
4.1	TRACEABILITY TO OPERATIONAL WASTE VOLUME PROJECTION DOCUMENTATION	4-1
	4.1.1 Traceability to Operational Waste Volume Projection Annual Report Requirements	4-1
	4.1.2 Traceability to Operational Waste Volume Projection Unscheduled Special Report Requirements	4-1
4.2	TRACEABILITY TO NEW OPERATIONAL WASTE VOLUME PROJECTION REQUIREMENTS	4-2
4.3	REQUIREMENTS INTERFACE ANALYSIS RESULTS	4-2
4.4	DIRECTIONS FOR TEST PROCEDURE PREPARATION	4-2
5.0	TEST PHASE PROCEDURE	5-1
5.1	PREPARATION OF THREE TEST CASES	5-1
	5.1.1 Test Case 1	5-1
	5.1.2 Test Case 2	5-2
	5.1.3 Test Case 3	5-2

5.2	ACCEPTANCE CRITERIA FOR EACH TEST CASE	5-2
5.3	TEST READINESS REVIEW	5-3
5.4	ACCEPTANCE TEST SEQUENCE.....	5-3
6.0	TEST PHASE RESULTS	6-1
6.1	OPERABILITY RESULTS	6-1
6.2	OPERATIONAL WASTE VOLUME PROJECTION REPORT GRAPHICS AND TABLES PRODUCTION RESULTS	6-1
6.3	OPERATIONAL WASTE VOLUME PROJECTION ACCURACY RESULTS	6-2
7.0	REFERENCES	7-1

APPENDIXES

A	- REQUIREMENTS PHASE SEQUENCE AND LOG	A-1
B	- REQUIREMENTS PHASE ANOMALY REPORT	B-1
C	- TEST PHASE SEQUENCE AND LOG.....	C-1
D	- TEST CASE 1 ASSUMPTIONS.....	D-1
E	- TEST CASE 2 ASSUMPTIONS	E-1
F	- TEST CASE 3 ASSUMPTIONS	F-1
G	- TEST CASE 1--PROJECTION ACCEPTANCE CRITERIA	G-1
H	- TEST CASE 2--PROJECTION ACCEPTANCE CRITERIA	H-1
I	- TEST CASE 3--PROJECTION ACCEPTANCE CRITERIA.....	I-1
J	- TEST PHASE ANOMALY REPORT.....	J-1

LIST OF FIGURES

6-1.	Waste Inventory Projection Comparison.....	6-3
6-2.	Double-Shell Tank Requirements Comparison.....	6-4

LIST OF TABLES

3-1.	General Requirements Verification Checklist.....	3-7
3-2.	Operational Waste Volume Projection Report Figure Verification Checklist	3-11
3-3.	Operational Waste Volume Projection Report Table Verification Checklist.....	3-14
3-4.	Operational Waste Volume Projection New Requirements Traceability Checklist.....	3-18
3-5.	Operational Waste Volume Projection User Interface Requirements Traceability Checklist.....	3-21

LIST OF TERMS

DST	Double-shell tank
FY	Fiscal year
HLAN	Hanford Local Area Network
HLW	High-level waste
HTWOS	Hanford Tank Waste Operation Simulator
LAW	Low-activity waste
LERF	Liquid Effluent Retention Facility
OWVP	Operational Waste Volume Projection
RPP	River Protection Project
SST	Single-shell tank
SWL	Salt Well Liquid
TAF	Tank Activity File
TCO	Terminal Cleanout
Tri-Party Agreement	<i>Hanford Federal Facility Agreement and Consent Order</i>
V&V	Verification and validation
WVR	Waste Volume Reduction

This page intentionally left blank.

HANFORD TANK WASTE OPERATION SIMULATOR OPERATIONAL WASTE VOLUME PROJECTION VERIFICATION AND VALIDATION PROCEDURE

1.0 INTRODUCTION

This document presents the test procedures used to verify and validate the Operational Waste Volume Projection (OWVP) capability of the Hanford Tank Waste Operation Simulator (HTWOS). The document also presents the detailed results of the test sequences including recommendations for operability enhancements.

The OWVP presents a defensible basis for evaluating double-shell tank (DST) space over the next 18 years. Each year in August, a report is issued with projections based on three sets of assumptions or cases. These unique projection cases are defined at least two months prior to report issuance and are designed to span the probable range of tank needs. The report contains projection results, full documentation of case assumptions, and annual DST content by waste type to substantiate projection results. The report results are used to support recommendations regarding site activities, waste management activities, and facility requirements including need for additional DSTs.

The OWVP FORTRAN software that has been successfully used for many years is now being replaced with the same "object-oriented" modeling tool used in the Waste Feed Delivery Program. The HTWOS is an integrated, dynamic simulation of every tank farm transfer, processing step, and disposal action with a mass balance of chemicals and radionuclides for the life of the program. HTWOS imports data from the Best Basis Inventory as a starting point and serves to electronically link several programs (Characterization, Operations, Waste Feed Delivery, and Process Engineering) with a comprehensive flowsheet model of an integrated planning case.

1.1 TRADITIONAL OPERATIONAL WASTE VOLUME PROJECTION PROCESS

The traditional OWVP process combines manual and computer-automated processes. The principal manual operation is creation of the Tank Activity File (TAF). The user must implement the defined case by defining tank transactions and evaporator campaigns. The user must also manually implement the operational constraints including waste segregation/mixing rules and present/scheduled outages. Trial TAF runs or iterations are made with a FORTRAN code running on an IBM^{TM1}-compatible personal computer until non-overflow conditions are satisfied. Conservation of volume is the underlying principle governing the code; the principle is accepted as providing sufficient accuracy for the level of analysis being performed. The process is repeated for the remaining two cases. Finally, output files representing the three cases are combined in postprocessing software to generate the various graphs and tables found in the

---

¹ IBM is a trademark of International Business Machines Corporation, Armonk, New York.

annual report. The results of this process are accepted as the valid or reference OWVP and are used to define acceptance criteria for the HTWOS OWVP capability.

1.2 DYNAMIC SIMULATION OPERATIONAL WASTE VOLUME PROJECTION APPROACH

HTWOS is a computer simulation that models the dynamic operation of the Hanford tank farm systems through disposal of all retrieved tank waste. HTWOS is programmed in G2², an object-oriented, artificial-intelligence, commercial software package that operates in a UNIX environment. Multiple users may access the simulation (host processor) over the Hanford Local Area Network (HLAN) through IBM^{TM} compatible PCs using terminal emulation software (Telewindows³). By modeling the tank farm systems, low-level waste feed staging activities, high-level waste feed staging activities, and Phase 1 /2 single-shell tank (SST) retrieval activities, the HTWOS is able to determine the demand imposed on the DST resource thereby providing an OWVP capability.

This OWVP capability includes G2^{TM} application software features, postprocessing software for OVWP specific graphs and tables, and a Users' Guide with instructions for executing projections and generating reports.

1.3 CHANGES IN OPERATIONAL WASTE VOLUME PROJECTION IMPLEMENTATION

Besides major differences in hardware, software, and user interface between the two models, underlying implementation approaches differ. HTWOS has a broader scope; initial feed delivery (to disposal privatization contractor) and SST retrieval details are modeled. Unlike the traditional OWVP process, volume is not conserved in HTWOS. For example, when solids (primarily NaNO₃) are dissolved in a DST, a slight volume increase occurs as a result of specific gravity changes. Also, HTWOS requires less manual control in modeling the tank farm system processes than with traditional OWVP. Normally, HTWOS schedules tank-to-tank transfers, receipts of new waste from generators, and evaporator campaigns with little or no user intervention.

1.4 OPERATIONAL WASTE VOLUME PROJECTION VERIFICATION AND VALIDATION PHASES

Because of the many differences between the two models, the volume projections will not be identical. Acceptance criteria are based primarily on traditional OWVP results for three cases but take into account expected differences in the models. The more highly automated process is

---

²G2 is a trademark of Gensym Corporation, Cambridge, Massachusetts.

³Telewindows is a trademark of Gensym Corporation, Cambridge, Massachusetts.

expected to provide projections that demonstrate somewhat improved utilization of the DST resource. The requirements are addressed in this verification and validation (V&V) procedure.

The V&V of HTWOS OWVP follows the guidelines of the Project Hanford procedures including a Requirements Phase and a Test Phase as defined in HNF-PRO-2778, *IRM Application Software System Life Cycle Standard* (PHMC 1999). The Requirements Phase provides V&V of the actual requirements, including traceability and interface analysis, imposed on the HWTOS. The Test Phase establishes the ability of HWTOS to satisfy these requirements. This V&V procedure does not replicate the previous tests of underlying model calculations (Wittman 1997). The test reports are defined in PHMC 1999.

This page intentionally left blank.

2.0 SUMMARY OF RESULTS

The Requirements Phase Summary (Section 2.1) summarizes the results of the Requirements Phase V&V and is prepared before performing the Test Phase procedure. The Test Phase Summary (Section 2.2) defines the overall ability of HTWOS to meet the requirements of OWVP.

2.1 REQUIREMENTS PHASE SUMMARY

Although HTWOS requirements were designed to capture the River Protection Project flowsheet, certain requirements relating to current operating details and initial conditions in the field were overlooked initially. The tanks assigned as cross-site transfer receivers differed from actual practice; evaporator logic ignored campaigns; tank constraints were missing allowing invalid transfers; two salt well liquid receivers were interchanged; and the initial volume inventory was not synchronized to measured tank volumes. All these requirements were addressed during the Requirements Phase; and all requirements anomalies were later cleared.

A pervasive requirements issue during the Requirements Phase was the responsibility for setup of operational constraints. The simulation developers made provisions for accepting these constraints (e.g., tank lockouts resulting from equipment outages or project schedule interference) but left the user (or test performer) to load the actual constraints. The actual near-term operational constraints (which help define the initial state of the system) were not stated explicitly in the simulation specification.

Resolution of initial volume inventory synchronization was deferred to the Test Phase. A set of tank transactions or transfers was used to update the Best Basis Inventory values to actual measured volumes on October 1, 1998. The actual simulation began on that date. The requirements and process for establishing initial volume inventory were verified, but the actual transactions to update inventories to October 1, 1998, were not verified in the Requirements Phase.

2.2 TEST PHASE SUMMARY

Three test cases were completed successfully using established simulation scenarios. The test cases were (1) Project Planning with Tri-Party Agreement- (TPA-) (Ecology et al. 1996) Compliant SST Retrieval, (2) Project Planning, and (3) Tank Usage Optimization. Each case included operational constraints identified during the Requirements Phase representing actual field conditions and operations practices. The HTWOS results compared very favorably to the OWVP results presented in the annual report (Strode and Boyles 1999).

Test Case 2, Project Planning, was performed first. Comparisons included average difference, root-mean-square (RMS) difference, and peak DST Requirement. The average difference is used to reveal a bias or offset between the models. The RMS difference is used to reveal randomness primarily due to timing offsets. The peak DST Requirement is the maximum number of simultaneous DSTs that must be available during any segment of the simulation interval. For the

interval 1998 through 2018, the average inventory difference was 0.1 Mgal and the RMS inventory difference was 1.1 Mgal. The average DST Requirement difference was half a tank (1.8 %), and the RMS DST Requirement difference was 2.3 tanks (8.2%). The peak DST Requirement predicted by both models is 29. These results are well within the acceptance criteria.

Test Case 1, Project Planning with TPA-Compliant SST Retrieval, was performed second. DST storage capacity is added as needed to accommodate SST retrieval completion by 2018. The capacity is used for feed staging to vitrification plants that are unable keep pace with this accelerated SST retrieval rate. The HTWOS DST storage capacity was set to increase beginning in 2013. The OWVP DST capacity was set to increase starting in 2007 with the surge in capacity occurring after 2011. The late start in HTWOS was used to avoid conflicts with the Phase 1 logic that automates retrieval and feed staging. Although the accelerated SST retrieval intervals differ, the end result is expected to be the same as long as the vitrification plants are never deprived of feed. By 2018, both models had completed SST retrieval, and total DST inventories were approximately 112 Mgal (agreement within 3.5%). Both simulations predicted a DST Requirement of 105 to 106 (standard size tanks). Again, this showed excellent agreement, well within the 5% acceptance criteria.

Test Case 3, Tank Usage Optimization, was the final test case. The user started with the Project Planning model from Test Case 2 and manually updated the low-activity waste (LAW) and high-level waste (HLW) vitrification plant ramp-up parameters, as well as the HLW staging sequence and dates, to the Tank Usage Optimization definition. The HTWOS was set to operate within the existing 28 DST constraint. After 2010 OWVP retrieves SSTs at the same predefined target rate but begins adding DST capacity in 2013 because of capacity limitations of the HLW vitrification plant. The two simulations were operated differently during Phase 2; therefore, the comparison is made through 2012. The average inventory difference was 0.3 Mgal, the RMS difference was 1.2 Mgal, the average DST Requirement difference was 0.9 tanks (3.2%), and the RMS DST Difference was 2.3 tanks (8.2%). These results are well within the acceptance criteria.

The capability to perform OWVP using HTWOS was verified. Several corrective actions were identified. Most were completed during this test activity. Outstanding corrective actions and enhancements are identified under Disposition in the anomaly reports with "shall be updated" or "will be corrected." A reduced scope test activity should be executed when the remaining corrective actions are completed. These activities should be complete before using HTWOS to generate the fiscal year (FY) 2000 OWVP annual report.

3.0 REQUIREMENTS PHASE PROCEDURE

The user shall follow and complete the Requirements Phase Procedure before proceeding to the Test Phase Procedure. The Requirements Phase Procedure verifies HTWOS requirements traceability to historical OVWP requirements and to requirements for revised capabilities. The analysis includes evaluation of HTWOS OVWP requirements specifications against hardware, user, and system interface requirements. Included is an evaluation of user system interface requirements satisfied by the HTWOS Users' Guide.

An indicator, **RECORD>**, is used in this procedure to direct the user to enter the results (for section, item, or step) into the test log. The test log consists of a set of tables provided in appendices (Appendix A for Requirements Phase and Appendix C for Test Phase). The user shall prepare an anomaly report where a clear deviation from criteria occurs. The anomaly report forms are contained in Appendix B (Requirements Phase) and Appendix J (Test Phase). Anomaly reports shall indicate anomaly disposition and shall be attached as appendices to this document.

3.1 REQUIREMENTS TRACEABILITY TO OPERATIONAL WASTE VOLUME PROJECTION DOCUMENTATION

The primary OVWP product is the annual report HNF-SD-WM-ER-029, *Operational Waste Volume Projection* (Strode and Boyles 1998). Requirements for generating projections and presentation materials for this report are discussed in Section 3.1.1. Special requirements for unscheduled reports are discussed in Section 3.1.2. Finally, the user interface requirements are described in Section 3.3.3.

3.1.1 Requirements for Generating Annual Report

The requirements for generating the annual OVWP report were derived from previous annual reports (Strode and Boyles 1997, 1998) and are divided into three categories: (1) General, (2) Graphics, and (3) Tables.

3.1.1.1 Annual Report General Requirements. Projections shall use a configuration-controlled model (HTWOS) of the planned Hanford tank farm system that is complete with operating documentation. Sixteen years of historical DST utilization data shall be retained for comparison purposes. Facilities shall be provided for the user to define, create, execute, and store three distinct projection cases: Case 1, Case 2, and Case 3. Operating assumptions, including the following, are defined and stored for each case:

1. Waste-generation streams, types, schedules, and sources
2. Waste retrieval and treatment/disposal schedules
3. Schedule dependencies among tanks and facilities
4. System configuration changes that further constrain DST utilization

5. System configuration changes providing up to four additional DSTs
6. Operational constraints with project (construction) interference and evaporator timing parameters for an initial operations interval.

An enhanced user interface shall be provided to efficiently enter, edit, view, and print operating assumptions and to view and save projection results. A means shall be provided to select the graphs and tables used for report generation. Specific requirements for graphs and tables are presented in the next sections.

The tank farm historical database shall be incorporated in the model. The records are from a defined date, typically 16 years, before the projection interval. For tank farm historical database maintenance, a user interface similar to that used for loading operating assumptions and for viewing and saving projection results will be included.

Table 3-1 (located at the end of this section) shall be used as a verification checklist.

RECORD> Complete Section 3.1.1.1 of Requirements Log Book in Appendix A.

3.1.1.2 Annual Report Graphics Requirements. The graphs available to the user are as follows:

1. Historical waste generation for all facilities
2. Evaporator status and contingency space for restart
3. Short and long range tank space summaries
4. DST requirements versus a waste volume projection
5. Comparison of tank requirements for two waste volume projections
6. Summary of combined tank space
7. Dilute receiver tanks and evaporator operations
8. West area waste generation and SY tank levels
9. Terminal Cleanout waste generation
10. Aging waste tank usage
11. DST requirements for special case
12. DST requirements (usage) by waste type for control case
13. DST requirements for control case
14. Comparison of DST requirements for present and previous FY

15. Comparison of DST requirements for the three cases
16. Inflow, outflow, and accumulative volumes for the control case
17. Evaporator operations for the control case
18. Aging tank usage of the control case
19. Volume uncertainty associated with the control case.

This graphic capability is presented as 22 figures from the most current annual reports (Strode and Boyles 1997, 1998). These figures are considered the report figure requirement templates. Verify traceability of report figure generation requirements to these templates. Table 3-2 (located at the end of this section) shall be used as a verification checklist.

RECORD> Complete Section 3.1.1.2 of Requirements Log Book in Appendix A

3.1.1.3 Annual Report Table Requirements. The tables available to the user shall include the following:

1. DST inventory at the end of previous FY
2. DST inventory volumes for the control case
3. Dilute waste generation volumes for the trended case
4. Waste types and waste volume reduction factors for present FY
5. Yearly generation of salt well liquid
6. Waste generation rate of S Plant waste
7. DST waste projected for 5 years in the future
8. Total DST space available 5 years in the future
9. DST waste type and space allocation 5 years in the future
10. Tank waste origin information.

This table-generation capability is presented as twelve tables from the most current annual reports (Strode and Boyles 1997, 1998). These tables are considered the report tabular requirement templates. The user should verify traceability of report table generation requirements to these templates. Table 3-3 (located at the end of this section) shall be used as a verification checklist.

RECORD> Complete Section 3.1.1.3 of Requirements Log Book in Appendix A.

3.1.2 Requirements for Generating Reports in Response to Special Case Requests

A reduced scope report feature shall be provided that allows the user to select the limited features needed for a special assumption case. Those graphs and tables that provide comparison to the control case shall be available.

RECORD> Complete Section 3.1.2 of Requirements Log Book in Appendix A.

3.2 REQUIREMENTS TRACEABILITY FOR REVISED CAPABILITIES

HTWOS has implemented new OVWP requirements, many of which relate to a broader mission assigned to the model. The sources of these requirements are WHC-EP-016, *Tank Waste Technical Options Report* (Boomer et al. 1993), and HNF-SD-WM-WP-012, *Tank Waste Remediation System Operation and Utilization Plan* (Kirkbride et al. 1999), which includes the process flowsheet. New capabilities include the following:

1. Initial feed delivery (to disposal privatization contractor)
2. SST retrieval details
3. Dissolution volume effects added. Volume is not conserved when solids (primarily NaNO_3) are dissolved in a DST. A slight volume increase occurs as a result of changes in specific gravity
4. Automatic scheduling of salt well liquid receipts and tank-to-tank transfers. Simulator logic replaces the manually generated TAF
5. Automatic scheduling (favorable to tank farm operations) of receipts of new waste from generators
6. Automatic scheduling of evaporator campaigns with little or no user intervention
7. Automatic calculation of evaporator water removal based on operational characteristics and waste constituents rather than assigned waste volume reduction factor
8. Waste type volume logic. Volumes of each waste type are accounted for and waste types with small volumes (heels) are not renamed to match new waste type additions
9. Finer time resolution provided
10. Available time for feed sampling and characterization is calculated based on the staging process rather than an input parameter that controls staging process delays.

The user should verify traceability of new OWVP capability source requirements to implementation documents, model modules, model procedures, and G2™ description documents. Table 3-4 (located at the end of this section) shall be used as a verification checklist.

RECORD> Complete Section 3.2 of Requirements Log Book in Appendix A.

3.3 REQUIREMENTS INTERFACE ANALYSIS

The user should evaluate HTWOS system requirements specifications against hardware, OWVP user, and system interface requirements. This evaluation includes the data interface for those tables and figures required for OWVP but not created by HTWOS directly (internally). The interface for any historical (existing) or new external software that is used to provide OWVP capability is included. Also, the evaluation includes interface requirements for user work stations and user interface requirements for performing OWVP.

3.3.1 Requirements for Operational Waste Volume Projection Work Station

The OWVP work station shall consist of an IBM-compatible personal computer with the following minimum requirements: 233 megahertz clock, 64 megabytes random access memory, one gigabyte available hard drive space, and connection to, the HLAN. Using Telewindows™ software, the work station shall emulate a UNIX terminal. Using a personal computer with the stated minimum requirements, the user should determine that successful connection is made to the HTWOS model when Telewindows™ is selected. The HTWOS administrator must provide a "TW.EXE" file and the appropriate privileges to enable this connection.

RECORD> Complete Section 3.3.1 of Requirements Log Book in Appendix A.

3.3.2 Interface Specification for Postprocessing Software

The postprocessing software has three input file format categories called Short Range, Long Range and Detailed. The four Short Range data files have month end or monthly total values projected 3 years. The seven Long Range data files have FY end values or yearly totals to 2043. The four Detailed data files have month end volumes to September 2015. The user should determine that the HTWOS implementation has addressed the requirements for these interface file formats.

RECORD> Complete Section 3.3.2 of Requirements Log Book in Appendix A.

3.3.3 User Interface

The user interface shall allow the user to efficiently select and execute the functions necessary to prepare, execute, and verify projections and to generate OWVP reports. A menu system shall be provided that is easily operated by an individual with rudimentary training on HTWOS and G2™. The Users' Guide shall provide overview information regarding the menu system and case setup, execution, presentation, and retention. The Users' Guide shall adequately explain the

operation of postprocessing software for report generation. Table 3-5 (located at the end of this section) shall be used as a verification checklist.

RECORD> Complete Section 3.3.3 of Requirements Log Book in Appendix A.

Table 3-1. General Requirements Verification Checklist. (4 Sheets)

Requirement ID Number	Requirement Description	Source Requirement: A= Kirkbride et al. 1999 B= Strode & Boyles 1998 C= <i>Boomer et al. 1993</i> D= PHMC 1999	Traceable to HTWOS	Requirement Traceability Issue	General Requirements V&V (Date Complete)
1	HTWOS model is under configuration management and complete with operating documentation.	A. Sect 5.8, para 2 and 3, D. Sect 8.0 and 5.2.f	Master version of HTWOS software is maintained on UNIX server and can be updated only by the software custodian. All remote users access the master version.		7/7/99
2	HTWOS model reflects the RPP flowsheet for Privatization Phase 1 and Phase 2 disposal processes.	A. Sect 3.4 and 4.4.	Logic diagrams for LAW and HLW feed delivery, OWVP, and Phase 2 provide visual evidence that the flowsheet is modeled.		7/7/99
3	Facilities are provided for defining and storing three projection cases.	B. Sect 1.	Save/Delete Case, Save/Delete Results, and Save/Restore Case as well as provisions for unique file names and case descriptive texts provide for storage and retrieval of projection cases and results.	Procedures will be developed to guide the user to enter the necessary and sufficient textual description for each projection case.	6/15/99
4	Facilities are provided for loading, maintaining and presenting 16 years of historical DST utilization data.	B. Table 4, Fig 1, 3, 5 to 7, 9 to 19, and 21 C. Sect 6.1.1, 7.3.1 and 7.4.1.	Show Assumptions; WVP Assumptions; Scheduled historical transfer operations; Show/Change	As an alternative, the 16 years of historical data are separately maintained with the OWVP postprocessing software.	6/15/99
5	Operating assumptions for waste-generation streams (including SWL pumping), types, schedules, and sources are user-definable and storable in HTWOS.	B. Tables 1, 11 and 14	Run WVP Calculations; Scheduled salt well pumping operations and Options; Calculate waste types; OWVP Logic; West Waste Receipts and East Waste Receipts Modules		6/16/99

Table 3-1. General Requirements Verification Checklist. (4 Sheets)

Requirement ID Number	Requirement Description	Source Requirement: A= Kirkbride et al. 1999 B= Strode & Boyles 1998 C= Boomer et al. 1993 D= PHMC 1999	Traceable to HTWOS	Requirement Traceability Issue	General Requirements V&V (Date Complete)
6	Operating assumptions defining waste retrieval and treatment/disposal schedules are user definable and storable in HTWOS.	B. Tables 4, 6, 7, 8, 12, and 13	Run Phase 1 Assumptions; Show/Edit Assumptions; Scheduled LLW and HLW feed staging operations and Phase 2 Logic; LAW and HLW Vitrification Plant; Show/Edit ramp processing rate		6/16/99
7	Operating assumptions defining schedule dependencies among tanks and facilities are user definable and storable in HTWOS.	B. Table 9	Phase 1 LAW Logic; LAW; Show tank lockouts, Phase 2 Logic; Staging; Show Phase 2 locked tanks, Run OWVP Logic; Evaporator; Show evaporator lockouts	Tanks are assigned to functions in logic diagrams to implement waste type compatibility. The lockouts (predefined outages) must be installed with care to sufficiently define the other "dependencies among tanks and facilities."	6/16/99
8	Operating assumptions defining system configuration changes that further constrain DST utilization are user definable and storable in HTWOS.	B. Sect 3.22 and Tables 5, 9, 17, and 19	Phase 1 LAW Staging Logic; LAW (Show tanks of...), HLW Staging Logic, Phase 2 Logic; Select function(block); Highlight item to edit or insert tank for function; Assumptions; route/transfer	On logic diagrams, tanks are assigned to functions. Most assignment changes occur with the start of Phase 2. Three tank route/transfer assumptions are available, and transfer route setup time is user assigned.	6/16/99
9	Operating assumptions defining system configuration changes to provide up to four additional DSTs are user definable and storable in HTWOS.	B. Fig 1, Cases 1 and 3	Show East Area; Red Tanks; Select Spare-101 to Spare-104	To be useful, the tanks must be connected at the process pinch points, usually HLW solids staging.	6/16/99

Table 3-1. General Requirements Verification Checklist. (4 Sheets)

Requirement ID Number	Requirement Description	Source Requirement: A= Kirkbride et al. 1999 B= Strode & Boyles 1998 C= <i>Boomer et al. 1993</i> D= PHMC 1999	Traceable to HTWOS	Requirement Traceability Issue	General Requirements V&V (Date Complete)
10	Operational constraints with project (construction) interference, facility outages and evaporator timing parameters for an initial 3-year operations interval are identified, entered, and reflected in the assumptions output file.	B. Sect 2.2 and Tables 17 and 19	Phase 1 LA W Logic; LA W; Show tank lockouts, Phase 2 Logic; Staging; Show Phase 2 locked tanks, Run OWVP Logic; Evaporator; Show evaporator lockouts and Evaporator Definition; Minimum Days Between Campaigns, Maximum Campaign Days	The evaporator operates by rules and lockouts rather than a pre-assigned 3-year schedule. The maximum campaign duration and minimum time between campaigns are user assigned to reasonably approximate the traditional 3-year schedule.	6/7/99
11	A means is provided for the user to efficiently view and save the projection results including special files for OWVP. Case definition including descriptive test, assumptions, and constraints, schedules, and sequences shall be provided in output files.	B. Sect 5 and C.	See Item 1 of Table 3-5 OWVP User Interface Requirements Traceability Checklist		6/16/99

Table 3-1. General Requirements Verification Checklist. (4 Sheets)

Requirement ID Number	Requirement Description	Source Requirement: A= Kirkbride et al. 1999 B= Strobe & Boyles 1998 C= Boomer et al. 1993 D= PHMC 1999	Traceable to HTWOS	Requirement Traceability Issue	General Requirements V&V (Date Complete)

DST = Double-shell tank
 HLW = High-level waste
 HTWOS = Hanford Tank Waste Operations Simulator
 LAW = Low-activity waste
 LLW = low-level waste
 OWVP = Operational Waste Volume Projection
 RPP = River Protection Project
 SWL = Salt well liquids
 V&V = Verification and validation
 WVP = Waste volume production

Boomer, K. D., S. K. Baker, A. L. Boldt, J. D. Galbraith, J. S. Garfield, C. E. Golberg, B. A. Higley, L. J. Johnson, M. J. Kupfer, R. M. Marusich, R. J. Parazin, A. N. Praga, G. W. Reddick, J. A. Reddick, E. J. Slaathaug, L. M. Swanson, T. L. Waldo, and C. E. Worcester, 1993, Tank Waste Technical Options Report, WHC-EP-0616, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Kirkbride, R. A., G. A. Allen, R. M. Orme, and R. S. Wittman, (Numatec Hanford Corporation); J. H. Baldwin, T. W. Crawford, and J. Jo (Lockheed Martin Hanford Corporation); L. J. Fergestrom, T. M. Hohl, and D. L. Penwell (COGEMA), 1999, *Tank Waste Remediation System Operation and Utilization Plan*, HNF-SD-WM-SP-012, Rev. 1, Numatec Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

PHMC, 1999, *IRM Application Software System Life Cycle Standard*, HNF-PRO-2778, Fluor Daniel Hanford, Inc., Richland, Washington [RLR8].

Strobe, J. N., and V. C. Boyles, 1998, Operational Waste Volume Projection, HNF-SD-WM-ER-029, Rev. 24, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

Table 3-2. Operational Waste Volume Projection Report Figure Verification Checklist. (3 sheets)

Figure No. in OWVP Report (Rev. 23 & 24) (Strode and Boyles 1997, 1998)	Graphics Requirement: Stability: Difference Between Rev. 23 & 24 of OWVP Report (Strode and Boyles 1997, 1998)	Generated by Model or from Model Output File?	Figure Special Features	Additional Output Files and/or Software Needed for Graphics Generation (HTWOS or External)	Figure Generation Capability (Date Complete)
1	SAME—Three Case Comparison	YES ^a	Annotation of plants and assumptions of graph		7/16/99
2	SAME—Methodology	NO			NA
3	Rev. 23, Tri-Party Agreement; Rev. 24, Case 1	YES ^a	Annotation of plants and assumptions of graph		7/16/99
4	Rev. 23, Tri-Party Agreement; Rev. 24, Case 1	YES	Complex stacked bar graph with vertically stacked legend at far right		7/16/99
5	SAME—Facility Waste Generation Short (PUREX)	YES ^a	Annotation of lines and areas on graphs	Request East waste-generation history files	7/16/99
6	SAME—Tank Fill (TCO)	YES ^a	Annotation of lines and areas on graphs		7/16/99
7	SAME—Tank Level Short	YES ^a	Multiple graphs with annotation of lines and areas		7/16/99
8	SAME—Schematic	NO			NA
9	SAME—Receiver and Evaporator Operations Short	YES ^a	Multiple graphs with annotation of lines and areas		7/16/99
10	SAME—Waste Generation and Levels Short	YES ^a	Multiple graphs with annotation of lines and areas	Request East waste-generation history files	7/16/99
11	SAME—West Area Waste Generator Short	YES ^a	Multiple graphs with annotation of lines and areas	Request West waste-generation history files	7/16/99
12	SAME—Hanford Facility Waste Short	YES ^a	Multiple graphs with annotation of lines and areas	Request East waste-generation history files	7/16/99
13	SAME—AP Tank Farm Levels Short	YES ^a	Multiple graphs with annotation of lines and areas		7/16/99

Table 3-2. Operational Waste Volume Projection Report Figure Verification Checklist. (3 sheets)

Figure No. in OWVP Report (Rev. 23 & 24) (Strode and Boyles 1997, 1998)	Graphics Requirement Stability: Difference Between Rev. 23 & 24 of OWVP Report (Strode and Boyles 1997, 1998)	Generated by Model or from Model Output File?	Figure Special Features	Additional Output Files and/or Software Needed for Graphics Generation (HTWOS or External)	Figure Generation Capability (Date Complete)
14	SAME—AN Tank Farm Levels Short	YES ^a	Multiple graphs with annotation of lines and areas		7/16/99
15	SAME—Aging Tank Requirements	YES ^a	Annotation of lines and areas on graphs		7/16/99
16	SAME—Aging Waste Tank Usage	YES ^a	Multiple stacked graphs with annotation of transitions and areas		7/16/99
17	Rev. 23, Disposal Planning Case; Rev. 24, Case 2	YES ^a	Annotation of plants and assumptions of graph		7/16/99
18	Rev. 23, Tri-Party Agreement; Rev. 24, Cases 2 & 3	YES ^a	Annotation of plants and assumptions of graphs		7/16/99
19	SAME—Generators versus Target	YES ^a	Combination stacked area graph (annotated) and table	Uses waste-generation history files.	7/16/99
20	SAME—Monthly Generators versus Targets	YES ^a	Vertical bar graph (annotated) with target rate line	Uses waste-generation history files.	7/16/99
21	SAME—Salt Well Liquid Pumping	YES ^a	Combination stacked area graph (annotated) and table	Request East and West receiver tank history files. Target file is generated externally.	7/16/99
22	SAME—Contribution from TCO	YES ^a	Vertical 3D bar graph (annotated) with total allocated line	Request East waste-generation history files.	7/16/99

Table 3-2. Operational Waste Volume Projection Report Figure Verification Checklist. (3 sheets)

Figure No. in OWVP Report (Rev. 23 & 24) (Strode and Boyles 1997, 1998)	Graphics Requirement Stability: Difference Between Rev. 23 & 24 of OWVP Report (Strode and Boyles 1997, 1998)	Generated by Model or from Model Output File?	Figure Special Features	Additional Output Files and/or Software Needed for Graphics Generation (HTWOS or External)	Figure Generation Capability (Date Complete)

HTWOS = Hanford Tank Waste Operations Simulator

NA = Not applicable

OWVP = Operational Waste Volume Projection

PUREX = Plutonium-Uranium Extraction (Facility)

Short = Three-year projection by month

TCO = Terminal Cleanup

SAME = Same graphic in both revisions; requirement for graphic is stable.

^aAnnotation is added to figures in postprocessing, not automatically added by simulator.

Ecology, EPA, and DOE-RL, 1996, *Hanford Federal Facility Agreement and Consent Order*, (commonly called the Tri-Party Agreement), Washington State Department of Ecology, U.S. Environmental Protection Agency, U.S. Department of Energy, Richland Operations Office, Olympia, Washington, amended periodically.

Strode, J. N. and V. C. Boyles, 1997, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 23, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

Strode, J. N., and V. C. Boyles, 1998, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 24, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

Table 3-3. Operational Waste Volume Projection Report Table Verification Checklist. (4 Sheets)

Table Number in OWVP Report (Rev. 24) (Strode and Boyles 1998)	Table Requirement Stability- Difference Between OWVP Report, Rev. 23 and 24 (Strode and Boyles 1997, 1998)	Table Generated from Model Output File?	Table Special Features	Additional Software Needed for Table Generation (HTWOS or External)	Table Generation Requirements (Date Complete)
1	SAME—Assumptions Summary 3 Cases Compared	NO			NA
2	SAME—Risk	NO			NA
3	SAME—Historical Evaporator Campaigns and WVR	NO	These historical data could be made part of HTWOS database.		NA
4	SAME—Salt Well Pumping	YES ^a		Run WVP Calculations –Scheduled salt well pumping operations provides total volume per SWL tank, pumping duration, start date, and waste type. External software is needed to convert to the format in Table 4.	6/16/99
5	SAME—Current Tank Usage	YES ^a	Tables showing the tanks assigned to functions are output to files at user request for Phase 1 and 2.	The table is generated by hand and can be automated with the appropriate software that concatenates the function files.	6/16/99
6	SAME—In-Tank Washing	YES ^a	Phase 2 Logic has WRF4, Staging, and Init DSTs feeding the Sludge Wash function block. The tanks of WRF4 are 241-AW-101 and 241-AY-101. Staging tanks are AN, AP, and AW (-102 to -106) farms. The tanks of Init DSTs are the 4 spare DSTs.	The table is generated by hand and can be automated with the appropriate software, which strips the sludge wash activities from the TAF output file.	6/16/99
7	SAME—Quantity Processed	YES ^a	The first two columns of the table are contract specifications and not model generated.	Software is needed to sum the processing of each envelope and format results in the form of Table 7.	6/16/99

Table 3-3. Operational Waste Volume Projection Report Table Verification Checklist. (4 Sheets)

Table Number in OWVP Report (Rev. 24) (Strode and Boyles 1998)	Table Requirement Stability: Difference Between OWVP Report, Rev. 23 and 24 (Strode and Boyles 1997, 1998)	Table Generated from Model Output File?	Table Special Features	Additional Software Needed for Table Generation (HTWOS or External)	Table Generation Requirements (Date Complete)
8	SAME—Phase 1B Schedule	YES ^a	The processing schedule for Case 1.	The table is generated by hand and can be automated with the appropriate software, which strips the appropriate records from the TAF output file and formats the results.	6/16/99
9	SAME—Compatibility Matrix	NO	Compatibility rules are implemented HTWOS by DST assignment to function.		NA
10	SAME—DST Solids Levels	YES	Solids inventory data.	This table is generated by hand and can be automated by striping solids from the starting inventory and formatting the results.	6/16/99
11	SAME—Assumption Matrix	YES ^a	If automated, this table provides an excellent check on simulation setup.	Table was generated by hand for three test cases and is reflected in Appendices F, G, and H. Software for automatic generation of Assumption Matrix requires further development.	6/1/99
12	Rev. 23, SST Solids Retrieval; Rev. 24, Process Schedule	YES, Process Schedule	This is the same as Table 8, except for Case 2 rather than Case 1.	Same software as used for Table 8.	6/16/99
13	REV. 24 only SWL Pumping Schedule for Case 2	YES	This is the same as Table 4, except for Case 2 rather than Case 1.	Same software as used for Table 4.	6/16/99
14	SAME—Additions and Reductions, Case 1	YES		This table is generated manually and can be automated by concatenating many output files and formatting the results.	6/16/99

Table 3-3. Operational Waste Volume Projection Report Table Verification Checklist. (4 Sheets)

Table Number in OWVP Report (Rev. 24) (Strode and Boyles 1998)	Table Requirement Stability: Difference Between OWVP Report, Rev. 23 and 24 (Strode and Boyles 1997, 1998)	Table Generated from Model Output File?	Table Special Features	Additional Software Needed for Table Generation (HTWOS or External)	Table Generation Requirements (Date Complete)
15	SAME—Projected Tank Usage for Case 1	YES	Comment field requires user annotation.	This table is generated manually and can be partially automated by concatenating 28 output files and formatting the results	6/16/99
16	SAME—Evaporator WVR and LERF Adds, Case 1	YES			6/16/99
17	SAME—Evaporator Schedule, Case 1	YES ^a			6/16/99
18	Rev. 24, only Evaporator WVR and LERF Adds 2	YES			6/16/99
19	Rev. 24, only Evaporator Schedule, Case 2	YES ^a			6/16/99
20	SAME—Monthly Generation Rates 3 Periods	YES ^a	Model must provide the values for at least the previous fiscal year.	Monthly Average Waste Generation Rates are not provided in HTWOS output files. Format conversion software is used to combine (waste) Source Monthly History files to build Table 20. Requirements traceability is provided.	6/16/99

Table 3-3. Operational Waste Volume Projection Report Table Verification Checklist. (4 Sheets)

Table Number in OWVP Report (Rev. 24) (Strode and Boyles 1998)	Table Requirement Stability: Difference Between OWVP Report, Rev. 23 and 24 (Strode and Boyles 1997, 1998)	Table Generated from Model Output File?	Table Special Features	Additional Software Needed for Table Generation (HTWOS or External)	Table Generation Requirements (Date Complete)

DST = double-shell tank
 HTWOS = Hanford Tank Waste Operations Simulator
 LERF = Liquid Effluent Retention Facility
 NA = not applicable
 SST = single-shell tank
 SWL = salt well liquid
 TAF = Tank Activity File
 TCO = Terminal Cleanout
 WRF4 = Waste Retrieval Facility
 WVR = Waste Volume Reduction
 *Desirable enhancement for HTWOS OWVP.

Strode, J. N. and V. C. Boyles, 1997, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 23, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

Strode, J. N., and V. C. Boyles, 1998, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 24, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

Table 3-4. Operational Waste Volume Projection New Requirements Traceability Checklist. (3 Sheets)

Requirement Id Number	Requirement Description	Source requirement A= Kirkbride et al. 1999 B= Boomer et al. 1993 C= Fowler 1995	Traceable to HTWOS	Expected Impacts on OWVP Results	New OWVP Requirements V&V (Date Complete)
1	Automated initial feed delivery to disposal privatization contractor.	A. Sect 3.1, 3.2, 5.3, and 5.4 and Fig 3.1-1, 3.1-2, and 3.2-2	Phase 1 LAW Feed Staging Logic-LAW Module (Show Tanks of...)	More rapid simulation changes to explore impacts of alternate feed sequences. Care must be taken that appropriate tank lockouts are in place.	6/15/99
2	SST retrieval details implementation including sluicing process.	A. Sect 3.3, 4.3, 5.5, and 5.6 and Fig 1.0-1 and 4.4-1	Phase 2 Calculations Retrieval Assumptions Module	More accurate simulation during the Phase 2 to SST waste retrieval and treatment completion.	6/15/99
3	Dissolution volume effects added. Volume is not conserved when solids (primarily NaNO_3) are dissolved in a DST. A slight volume increase occurs because of changes in specific gravity.	A. Sect 5.0, para 5	Calculating Tank Properties Module	When 1000 kg of NaNO_3 is dissolved, the original liquid plus solid volume (tank waste plus dissolution liquid) is increased by about 18 gal. Expected to have negligible effect on comparison with traditional OWVP.	6/15/99
4	Automatic scheduling of salt well liquid receipts and tank-to-tank transfers. Simulator logic replaces the manually generated TAF.	A. Sect 5.4	Waste Volume Projection Assumptions-Schedule d Salt Well Pumping Operations; Phase 1 LAW Staging and Phase 2 Logic-tank Lockouts	Certain operational constraints captured in the TAF are not captured in the HTWOS logic. The full logic used to build these files was not converted to specifications for HTWOS. This results in predicting near-term transfers that actual operational constraints prohibit. These constraints must be added by the user through the use of facility and tank lockouts.	6/15/99
5	Annual waste from generators defined by input file; automatic receipt scheduling (favorable to tank farm operations) during each year.	A. Sect 5.2, first and last para	OWVP Logic; West Waste Receipts and East Waste Receipts Modules	Improved waste generator receipt schedulings during the year may reduce predicted DST requirement by one tank for brief periods each year that generated waste is received.	6/15/99

Table 3-4. Operational Waste Volume Projection New Requirements Traceability Checklist. (3 Sheets)

Requirement Id Number	Requirement Description	Source requirement A= Kirkbride et al. 1999 B= Boomer et al. 1993 C=Fowler 1995	Traceable to HTWOS	Expected Impacts on OWVP Results	New OWVP Requirements V&V (Date Complete)
6	Automatic scheduling of evaporator campaigns with little or no user intervention.	A. Sect 5.9, OWVP Input	OWVP Logic; Evaporator Definition; Minimum Days Between Campaigns; Maximum Campaign Days; and Lockouts	Evaporator runs and recycles automatically based on tanks ready for evaporation (below set specific gravity) and set target concentration. The user must set outages (lockouts), campaign duration (for one or two tanks), and time between campaigns based on maintenance and operational cost constraints. Provided target specific gravity and WVRF are close to equivalent, the automatic HTWOS evaporator operation should closely represent actual operations and the traditional OWVP results.	6/15/99
7	Automatic calculation of evaporator water removal based on operational characteristics and waste constituents rather than assigned waste volume reduction factor.	A. Sect 5.2, 1 st para and 5.9, OWVP Input (soft-coded evaporator operation)	OWVP Logic; Evaporator-target specific gravity, recycle maximum boil-off gal/min	Because WVRF is calculated based on waste constituents, computing water removal in evaporator code based on waste constituents should give same result. Minimal volume impact.	6/15/99
8	Waste-type volume logic. Volumes of each waste type are accounted for, and waste types with small volumes (heels) are not renamed to match new waste-type additions.	A. Sect 5.0, para 3, C. Sect 3.1 and 3.2	Options; Calculate Waste Types; Show East Area and Show West Area (each DST has waste type table for liquids and solids)	Little impact on DST requirement after the first few years of projection. OWVP Report (Strode and Boyles 1998), Figure 4 waste-type distribution will change moderately for first few years of projection.	6/15/99
9	Two-hour time resolution is provided by HTWOS, while traditional OWVP resolution is one month.	A representative tank farm simulation was rerun using increasingly large time steps. The largest step with accurate volume profile was chosen (2 hr).	Developer Mode; not assessable by normal user.	Main impact is when model comparisons are made at beginning or end of a month (or beginning or end of a year). Care must be taken to "synchronize" results from the two models. Finer time resolution is expected to improve accuracy and reduce volume peaks.	6/15/99

Table 3-4. Operational Waste Volume Projection New Requirements Traceability Checklist. (3 Sheets)

Requirement Id Number	Requirement Description	Source requirement A= Kirkbride et al. 1999 B= Boomer et al. 1993 C=Fowler 1995	Traceable to HTWOS	Expected Impacts on OWVP Results	New OWVP Requirements V&V (Date Complete)
10	HTWOS stages feed to vitrification facilities early and computes the amount of time available for feed sampling and characterization. Traditional OWVP stages feed based on a fixed sampling and characterization interval, typically 270 days before predicted completion of the previous tank's waste treatment.	A. Sect 5.3	Phase 1 LAW Feed Staging Logic; LAW block (Show tanks of...); Phase 2 Tank Farm Logic and Run Phase 2 Calculations; Show/Edit Assumptions; Phase 2 Retrieval Assumptions; Current SST retrieval order operations	Well-defined rules have not been established defining feed staging lead time. Different implementations could give a one- or two-tank variation in DST Requirements.	6/15/99

DST = double-shell tank
 HTWOS = Hanford Tank Waste Operations Simulator
 LAW = low-activity waste
 OWVP = Operational Waste Volume Projection
 SST = single-shell tank
 TAF = Tank Activity File

V&V = verification and validation
 WVRF = Waste Volume Retrieval Facility

Boomer, K. D., S. K. Baker, A. L. Boldt, J. D. Galbraith, J. S. Garfield, C. E. Golberg, B. A. Higley, L. J. Johnson, M. J. Kupfer, R. M. Marusich, R. J. Parazin, A. N. Praga, G. W. Reddick, J. A. Reddick, E. J. Slaathaug, L. M. Swanson, T. L. Waldo, and C. E. Worcester, 1993, *Tank Waste Technical Options Report*, WHC-EP-0616, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
 Fowler, K. D., 1995, *Tank Farm Waste Transfer Compatibility Program*, WHC-SD-WM-OCDD-015, Rev. 1, Westinghouse Hanford Company, Richland, Washington.
 Kirkbride, R. A., G. A. Allen, R. M. Orme, and R. S. Wittman, (Numatec Hanford Corporation); J. H. Baldwin, T. W. Crawford, and J. Jo (Lockheed Martin Hanford Corporation); L. J. Fergestrom, T. M. Hohl, and D. L. Penwell (COGEMA), 1999, *Tank Waste Remediation System Operation and Utilization Plan*, HNF-SD-WM-SP-012, Rev. 1, Numatec Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
 Strode, J. N., and V. C. Boyles, 1998, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 24, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

Table 3-5. Operational Waste Volume Projection User Interface Requirements Traceability Checklist. (3 Sheets)

Requirement Id Number	Requirement Description	Source requirement: A – Kirkbride et al 1999 B – Srode and Boyles 1998 C – Fowler 1995	Traceable to HTWOS User Menu	Comments from User Prospective	OWVP User Interface (Date Complete)
1	The user interface shall allow the user to efficiently select and execute the functions necessary to prepare, run, and verify projections. Preparation includes user entry of (1) scenario or case name, number, and text description; (2) operational constraints, schedules, and sequences including vitrification plant capacity ramp-ups, initial feed delivery tanks and SST retrieval; and (3) selection of special calculations and output files for OWVP; (4) running the simulation includes having access to the output files needed for generating the OWVP report; (5) verification includes access to case definition parameters echoed in simulation output files (waste generators, salt well pumping targets, constraints, schedules, and sequences).	A. Sect 5.2, 5.3, 5.4, 5.5, 5.6, 5.7, and 5.9; OWVP Input (soft-coded evaporator operation)	Menu System Show Assumptions: (1) Show/Edit Current Case Description; (2) Run Phase 1 Assumptions-Show/Edit Assumptions-Scheduled LLW and HLW feed staging operations and Phase 2 Logic-LAW and HLW Vitrification Plant-Show/Edit ramp processing rate and Run Phase 2 Calculations-Show/Change Current SST retrieval order operations, Phase 2 Logic-Staging-Show Phase 2 locked tanks, Run OWVP Logic-Evaporator-Show evaporator lockouts; (3-5) Run WVP Calculations – Scheduled salt well pumping operations and Options-Calculate waste types, Run WVP Calculations –Input tank solid retrieval fractions	(1) The user is not limited in the amount of text he may enter to describe a case. A protocol will be needed to identify the information that should be recorded to adequately define a case and to verify that the constraint, schedule, and retrieval sequence files reflect the case definition. (2) Many facility lockout (outage) and tank lockout constraints must be entered by the user to define current operational conditions, project interference, etc. These are entered manually for each facility or tank. The user must request an output file for each facility and tank to obtain an electronic verification that the constraints are correct. (3) Selection of OWVP features is from a clearly defined menu structure. (4) Files for generated waste and SWL Pumping are not automatically placed in output files. Table entries must be highlighted by the user who then requests output to a file and provides a file name. (5) Verification requires the user to access the case definition parameters from several locations in the simulation's menu system and multiple requests for parameter definition files if an electronic record is desired. As an alternative, the user may save the case. The saved model becomes the documentation (of configuration) for the case.	6/15/99

Table 3-5. Operational Waste Volume Projection User Interface Requirements Traceability Checklist. (3 Sheets)

Requirement Id Number	Requirement Description	Source requirement. A = Kirkbride et al. 1999 B = Strode and Boyles 1998 C = Fowler 1995	Traceable to HTWOS User Menu	Comments from User Prospective	OWVP User Interface (Date Complete)
2	A menu system shall be provided that is easily operated by an individual with rudimentary training on HTWOS and G2™.	A. Sect 5.0, para 2	A one-sheet menu navigation guide would be useful as a memory aid to those who do not use HTWOS on a daily basis.	A transition in thinking is required for regular Windows 95 or 98™ users when in the HTWOS environment. The underlying operating system is UNIX, and the window, pane, and file structures are different.	6/15/99
3	A menu system shall be provided allowing the user to edit the historical tank inventory data file.	B. Sect 1.0, Fig 1; Sect 5.1, Fig 3, 5, 6, 7, and 9-16; Sect 5.2, Fig 17; Sect 5.3, Fig 18; Sect 5.4, Fig 19 and 21	Menu System Show Assumptions: WVP Assumptions-Scheduled historical transfer operations-Show/Change	Starts at 10/1/1996 and ends at 9/15/1998. Does not contain the 16 years of historical data used in some of the OWVP Report graphics. Editing of this two year file is straight forward, and the file is easily saved (highlight, select disc button, and provide file name).	6/14/99
4	The Users' Guide shall provide overview information regarding the menu system and case setup, execution, presentation, and retention. The Users' Guide shall adequately explain the operation of postprocessing software for report generation.	Source requirement is inferred based on nature and use of HTWOS.	On-line HELP menus are used as the Users' Guide. Access is through internet connection to (GANDALF) UNIX file server providing the Users' Guide library.	Contents: Chapter 1 SHOW Menu Description with no other chapters. Index: 30 entries are provided, 2 are specific to Waste Volume Projection. Individual entries have graphics and tables from model with little or no textual description.	6/15/99

Table 3-5. Operational Waste Volume Projection User Interface Requirements Traceability Checklist. (3 Sheets)

Requirement Id Number	Requirement Description	Source requirement: A = Kirkbride et al. 1999 B = Strode and Boyles 1998 C = Fowler 1995	Traceable to HTWOS User Menu	Comments from User Prospective	OWVP User Interface (Date Complete)

DST = double-shell tank
 G2 = a trademark of Gensym Corporation, Cambridge, Massachusetts
 HLW = high-level waste
 HTWOS = Hanford Tank Waste Operations Simulator
 LAW = low-activity waste
 LLW = low-level waste
 OWVP = Operational Waste Volume Projection
 SST = single-shell tank
 SWL = salt well liquid
 V&V = verification and validation
 WVP = Waste Volume Projection

Fowler, K. D., 1995, *Tank Farm Waste Transfer Compatibility Program*, WHC-SD-WM-OCDD-015, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

Kirkbride, R. A., G. A. Allen, R. M. Orme, and R. S. Wittman, (Numatec Hanford Corporation); J. H. Baldwin, T. W. Crawford, and J. Jo (Lockheed Martin Hanford Corporation); L. J. Fergestrom, T. M. Hohl, and D. L. Penwell (COGEMA), 1999, *Tank Waste Remediation System Operation and Utilization Plan*, HNF-SD-WM-SP-012, Rev. 1, Numatec Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

Strode, J. N., and V. C. Boyles, 1998, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 24, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

This page intentionally left blank.

4.0 REQUIREMENTS PHASE RESULTS

The results from Section 3.0, "Requirements Phase Procedure," are summarized in this section. Results of traceability to OWVP documentation are discussed in Section 4.1. Traceability to new requirements is discussed in Section 4.2, followed by a Discussion of Interface Requirements in Section 4.3. These results are used to further define the directions for Test Phase preparation (Section 4.4).

4.1 TRACEABILITY TO OPERATIONAL WASTE VOLUME PROJECTION DOCUMENTATION

Traceability results for requirements for generating projections and presentation materials for the OWVP annual report are discussed in Section 4.1.1. Traceability results for requirements for unscheduled reports are discussed in Section 4.1.2.

4.1.1 Traceability to Operational Waste Volume Projection Annual Report Requirements

Simulation requirements take many forms, and the HTWOS was clearly coded to the general requirements applied to OWVP. A significant requirement traceability problem developed when the HTWOS design team decided to discontinue use of the input TAF. The transfers contained in the TAF capture the near-term operational constraint logic. Without this file, the HTWOS user must manually enter the constraints by reassigning tank functions, assigning tank and facility lockouts, and setting evaporator scheduling parameters. These constraints are not compiled formally and provided as part of the simulator documentation. The Requirements Phase testing determined that provisions were made in the HTWOS logic for the types of constraints previously captured in the TAF.

The generation and storage of volume data meet the minimum requirements for OWVP. The requirement for 16 years of historical data of graphs and tables in the annual report must presently be met by a database external to HTWOS. The user must request several specific monthly graphs and HTWOS output files to gather all the information necessary for generating the OWVP graphics and tables. The user then must process these files through file format conversion software before postprocessing for generation of OWVP graphics and tables.

4.1.2 Traceability to Operational Waste Volume Projection Unscheduled Special Report Requirements

The requirements for unscheduled reports are a subset of those for the annual report. The user, however, executes fewer functions. Again the minimum requirements for OWVP are implemented, but the same burdens discussed in Section 4.1.1 are placed on the user.

4.2 TRACEABILITY TO NEW OPERATIONAL WASTE VOLUME PROJECTION REQUIREMENTS

The traceability results for new OVWP requirements were discussed. These are the requirements for additional capabilities not available in the traditional OWVP. Many of these additional requirements relate to the broader mission assigned to the HTWOS model. The requirement traceability verifications were completed successfully although three requirement anomalies were logged and later closed out. The HTWOS requirements had to be expanded as a result of Requirements Phase testing anomalies to ensure proper operation of OWVP. First, the evaporator requirements were updated to include maximum campaign days (duration) and minimum days between campaigns. Next, automatic scheduling of salt well liquid pumping required update to the January 1999 model, and dilution factors are assigned on a per tank basis rather than per farm. Finally, near-term operational constraints (previously captured in the TAF input) are now contained in HTWOS logical elements.

4.3 REQUIREMENTS INTERFACE ANALYSIS RESULTS

The requirements interface analysis was completed successfully. The HTWOS system requirements specifications were evaluated against hardware, OWVP user, and system interface requirements. The evaluation included the HTWOS output data format conversion definition to support report graphics postprocessing capability. The user developed the software necessary to convert HTWOS output files into the format needed by the postprocessing software. Two interface requirements anomalies were logged and later closed out: (1) the 16 years of historical tank information used in OWVP graphics and tables must now be maintained in a database external to HTWOS, and (2) the HTWOS Users' Guide (online HELP menu) does not cover many of the newest HTWOS features. The Users' Guide also does not discuss the use of postprocessing software. These anomalies were closed because traceability to the underlying requirements was satisfied. Adequacy of the actual implementation is addressed in the Test Phase.

4.4 DIRECTIONS FOR TEST PROCEDURE PREPARATION

The V&V test procedure shall be prepared for an integrated OWVP capability. This capability includes the setup of test cases (assumptions) and generation of the annual OWVP report. Generation of an unscheduled OWVP special report is optional in that it contains a subset of the annual report contents and is assembled using the same process as the annual report. The integrated OWVP capability to be verified incorporates the historical OVWP requirements; new requirements (primarily related to the broader HTWOS mission); and requirements for hardware, user and system interfaces. The procedure shall define the three test cases and provide general test steps for test execution. The procedure shall refer to the HTWOS Users' Guide for user interactions with HTWOS and with postprocessing software.

5.0 TEST PHASE PROCEDURE

The user shall follow the instructions of this V&V procedure for test sequence while following the Users' Guide for details of running the OWVP and of generating reports. A goal of this procedure is to verify the adequacy of the Users' Guide.

The user shall complete the Test Phase Sequence and Log found in Appendix C during execution of this procedure. An indicator, **RECORD>**, directs the user to enter the results (for section, item, or step) into the test log. The user shall prepare an anomaly report where a clear deviation from criteria occurs. The anomaly report forms are contained in Appendix J. Anomaly reports shall indicate anomaly disposition and shall be attached as appendices to this document.

5.1 PREPARATION OF THREE TEST CASES

The test cases shall be taken from Kirkbride et al. (1999), which uses updated schedules and assumptions regarding the waste treatment privatization contractor. The first test case shall be the TPA planning case (Case 3S3 Modified, Project Planning). The case is modified with expanded DST storage for retrieved SST solids. The case uses additional DST storage capacity to support the SST retrieval rates necessary to achieve TPA compliance (i.e., complete SST retrieval by 2018). Test Case 2 shall be Case 3S3, Project Planning, the RPP planning baseline. Test Case 3 shall be Case 6b, Tank Usage Optimization. Test Case 3 investigates the benefits of higher Phase 2 vitrification plant capacities and of temporarily retaining pretreated LAW (Envelope B) and certain entrained solids in storage tanks provided with the vitrification plants.

Because of limited Phase 2 LAW and HLW vitrification plant capacities, Test Case 1 will require expanded DST capacity. That is, significantly more than 28 DSTs are needed to complete the retrieval and disposal mission. At least 4 additional (SPARE designation) DSTs shall be activated in HTWOS for this case. The adjusted Phase 2 processing schedules and assumptions shall be agreed on by the representatives of Process Engineering and Disposal Engineering. Test Cases 2 and 3 are expected to be completed without expanded DST capacity.

The test cases shall be defined using the Assumption Matrix format found in the annual OWVP report (Strode 1998), Table 11 and by near-term operational constraints.

5.1.1 Test Case 1

Test Case 1 is Case 3S3 Modified, Project Planning with TPA-Compliant SST Solids Retrieval. The Phase 2 vitrification plant capacities shall be the same as for Test Case 2 (unmodified Case 3S3). The case is defined by the Assumption Matrix in Appendix D.

RECORD> Complete Section 5.1.1. of Test Phase Sequence and Log in Appendix C, Table C-1.

5.1.2 Test Case 2

Test Case 2 is the Project Planning case; the case provides information used to schedule projects that support the tank waste cleanup mission. The case is defined by the Assumption Matrix in Appendix E.

RECORD> Complete Section 5.1.2 of Test Phase Sequence and Log in Appendix C, Table C-1.

5.1.3 Test Case 3

Test Case 3 is the Tank Usage Optimization case. The case is defined by the Assumption Matrix in Appendix F.

RECORD> Complete Section 5.1.3. of Test Phase Sequence and Log in Appendix C, Table C-1.

5.2 ACCEPTANCE CRITERIA FOR EACH TEST CASE

The acceptance criteria for each test case must be developed based on predictions from the traditional OWVP model and adjustments resulting from the new requirements for revised capabilities.

Step 1. Obtain results for Test Case 1 using traditional OWVP.

Step 2. Use the "Expected Impacts on OWVP Results" data from Table 3-4 to estimate adjustments to DST waste volume and DST requirements (utilization) projections.

Step 3. Combine the results from Steps 1 and 2 to obtain acceptance criteria for the HTWOS projections of DST waste volume and DST requirements (utilization).

Step 4. Place the acceptance criteria from Step 3 for Test Case 1 in Appendix G for later use in Section 5.4.

RECORD> Complete Section 5.2, Step 4, of Test Phase Sequence and Log in Appendix C, Table C-1.

Step 5. Repeat Steps 1 through 3 for Test Case 2 placing acceptance criteria in Appendix H.

RECORD> Complete Section 5.2, Step 5, of Test Phase Sequence and Log in Appendix C, Table C-1.

Step 6. Repeat Steps 1 through 3 for Test Case 3 placing acceptance criteria in Appendix I.

RECORD> Complete Section 5.2, Step 6, of Test Phase Sequence and Log in Appendix C, Table C-1.

5.3 TEST READINESS REVIEW

The Acceptance Test Sequence (Section 5.4) may be performed for each test case independently. Before proceeding to the first test case, a readiness review including Items 1 through 5 below shall be completed. Also, the appropriate acceptance criteria (Item 6, 7, or 8) shall be completed for the test case undergoing the Acceptance Test Sequence.

- Item 1. HTWOS is under configuration management; software change control is in place.
- Item 2. Traceability for the HTWOS OWVP General Requirements (Table 3-1) is verified.
- Item 3. Requirements for HTWOS OWVP Figure Generation (Table 3-2) are verified.
- Item 4. Requirements for HTWOS OWVP Table Generation (Table 3-3) are verified.
- Item 5. Traceability for new OWVP requirements is verified (Table 3-4).
- Item 6. Traceability for OWVP User Interface is verified (Table 3-5)
- Item 7. Test Case 1 is defined and acceptance criteria are established.
- Item 8. Test Case 2 is defined and acceptance criteria are established.
- Item 9. Test Case 3 is defined and acceptance criteria are established.

RECORD> Complete Section 5.3, Items 1 through 9, of Test Phase Sequence and Log in Appendix C, Table C-2.

5.4 ACCEPTANCE TEST SEQUENCE

The sequence below shall be repeated for each of three test cases. After each step, the user shall log the result in Test Phase Sequence and Log for Section 5.4 in Appendix C. If a test anomaly is encountered, the user shall prepare a Test Phase Anomaly Report using the form provided in Appendix J. The report shall be attached to Appendix J as part of the test results.

- Step 1. Establish Telewindows™ workstation connection with HTWOS model.
- Step 2. Load the appropriate history file for this case into HTWOS.
- Step 3. Using the assumption matrix for this case, load the assumptions into HTWOS.
- Step 4. Load the near-term operational constraints for this case into HTWOS.
- Step 5. Run projection (with OVWP calculations and output files) through year 2043.

- Step 6. Observe the Message Board during the projection. Warnings may indicate improper setup of assumptions. Print warnings and attach printout to Anomaly Report. Evaluate and restart at Step 3 if necessary.
- Step 7. Activate total DST utilization graph and request printout. Compare projection results with acceptance criteria for this test case. Large deviations may indicate improper setup of assumptions. Evaluate assumption setup and restart at Step 3 (and attach printout to Anomaly Report) if necessary.
- Step 8. Request that OWVP files be saved with test case number identified.
- Step 9. Transfer the OWVP files for this test case to the report graphics post-processing computer.
- Step 10. Request processing of the OWVP files to create and print the annual report graphics for this test case.
- Step 11. Request processing of the OWVP files to create and print the annual report tables for this test case.
- Step 12. Compare the results with the acceptance criteria for this test case. See Appendixes G, H, and I for Test Cases 1, 2, and 3, respectively.

RECORD> Complete Section 5.4 of Test Phase Sequence and Log in Appendix C, Table C-3 for Test Case 1, Table C-4 for Test Case 2, and Table C-5 for Test Case 3.

6.0 TEST PHASE RESULTS

6.1 OPERABILITY RESULTS

The user interface allowed the user to select and execute the functions necessary to prepare, execute, and verify projections. The user interface is not yet in place to automate the functions necessary to generate OWVP reports. These functions can be executed manually, but the process is not fully documented. The HTWOS menu system is easily operated by an individual with rudimentary training on HTWOS and G2™. An online Users' Guide was operational but not complete. Overview information was provided regarding the menu system and case setup, execution, presentation, and retention; many details must be added for completeness. The Users' Guide does not address the operation of postprocessing software for report generation. Since most of this information pertains to functions external to HTWOS, an external addendum to the Users' Guide that fully addresses postprocessing functions should be prepared.

Each test case exercised specific aspects of the user interface. Test Case 2 exercised the functions needed to load a test scenario (Case 3S3 Project Planning), enter case descriptive information, select special calculations and output files for OWVP, and enter an extensive set of operational constraints. The constraints included tank assignments to functions, tank lockouts, tank cascade operations supporting salt well liquid pumping, and evaporator campaign operations. Test Case 1 exercised the spare DST capability of HTWOS and effectively demonstrated tank requirements for the TPA case (SST retrieval complete by 2018). Test Case 3 exercised the functions needed to adjust HLW and LAW vitrification plant capacity rampup and feed staging schedules.

Additionally, each case demonstrated the functions to save and recall HTWOS results and models (cases) and to verify proper case setup. For example, the Source Monthly History files were used to verify that all generated waste was entering the system on the correct schedules. Similarly, the salt well pumping schedule may be output to a file for user verification. The cases demonstrated the edit features for the 2-year historical tank inventory data file; the 16-year historical tank inventory used in the OWVP report requires maintenance of a history file external to HTWOS.

6.2 OPERATIONAL WASTE VOLUME PROJECTION REPORT GRAPHICS AND TABLES PRODUCTION RESULTS

HTWOS generates specific output files for creation of the OWVP report graphics and tables. These files include DST availability, waste source (generator), monthly history (10 files), DST monthly waste type history (28 files), and evaporator 242A throughput history. These files are converted to the format used by OWVP postprocessing graphics software and processed to generate the figures used in the OWVP reports. Although each test case generates a portion of report graphics, the Test Case 2 results were used to generate the vast majority of the graphics. Full graphics capability was demonstrated with the exception of Contributions from Salt Well Liquid Pumping (Strode and Boyles 1999), Figure 20, which requires several tank volume history files to be combined into a Salt Well Liquid material balance file.

The OWVP report tables may be generated through an application of HTWOS output files, manual queries, file format conversion, data averaging, and table generation postprocessing software. The process is not automated. Likewise, the traditional OWVP process for table generation was not automated. Future refinements to HTWOS output file structure and postprocessing software will significantly ease the production of the OWVP report tables.

6.3 OPERATIONAL WASTE VOLUME PROJECTION ACCURACY RESULTS

For Test Case 2, HTWOS and OWVP were run with the same parameters over the entire simulation interval and exhibited very similar predictions over the entire interval. Figure 6-1 shows the waste inventory projection comparison for this "Project Planning" case. The excess initial inventory in HTWOS is worked off by the end of FY 2000 using the evaporator. The average inventory difference was 0.1 Mgal, and the RMS inventory difference was 1.1 Mgal. The accuracy demonstrated by the other two cases was similar and within the acceptance criteria for the OWVP capability.

Figure 6-2 shows the DST Requirement comparison for Test Case 2. This corrected comparison was generated after the Phase 1 Allocation logic was corrected. The average DST Requirement difference was 0.5 tank, and the RMS DST Requirement difference was 2.3 tanks. The accuracy demonstrated by the other two cases was similar with the average difference in DST Requirements within the acceptance criteria for the OWVP capability. The rather high RMS DST Requirement difference is due primary to different time steps used in the two models, different DST Requirement accounting, and different feed staging lead times. This difference can be reduced by modifying the HTWOS DST Requirement code to more closely compare to that used in OWVP and by carefully defining the feed staging lead time logic.

Figure 6-1. Waste Inventory Projection Comparison.

Figure 6-2. Double-Shell Tank Requirements Comparison.

7.0 REFERENCES

- Boomer, K. D., S. K. Baker, A. L. Boldt, J. D. Galbraith, J. S. Garfield, C. E. Golberg, B. A. Higley, L. J. Johnson, M. J. Kupfer, R. M. Marusich, R. J. Parazin, A. N. Praga, G. W. Reddick, J. A. Reddick, E. J. Slaathaug, L. M. Swanson, T. L. Waldo, and C. E. Worcester, 1993, *Tank Waste Technical Options Report*, WHC-EP-0616, Rev. 0, Westinghouse Hanford Company, Richland, Washington.
- Ecology, EPA, and DOE-RL, 1996, *Hanford Federal Facility Agreement and Consent Order*, (commonly called the Tri-Party Agreement), Washington State Department of Ecology, U.S. Environmental Protection Agency, U.S. Department of Energy, Richland Operations Office, Olympia, Washington, amended periodically.
- Fowler, K. D., 1995, *Tank Farm Waste Transfer Compatibility Program*, WHC-SD-WM-OCD-O15, Rev. 1, Westinghouse Hanford Company, Richland, Washington.
- Kirkbride, R. A., G. A. Allen, R. M. Orme, and R. S. Wittman, (Numatec Hanford Corporation); J. H. Baldwin, T. W. Crawford, and J. Jo (Lockheed Martin Hanford Corporation); L. J. Fergstrom, T. M. Hohl, and D. L. Penwell (COGEMA), 1999, *Tank Waste Remediation System Operation and Utilization Plan*, HNF-SD-WM-SP-012, Rev. 1, Numatec Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- PHMC, 1999, IRM Application Software System Life Cycle Standard, HNF-PRO-2778, Fluor Daniel Hanford, Inc., Richland, Washington[RLR9].
- Strode, J. N. and V. C. Boyles, 1997, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 23, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- Strode, J. N., and V. C. Boyles, 1998, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 24, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- Strode, J. N., and Boyles, V. C., 1999, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 25, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.
- Wittman, R. S., 1997, *Verification and Validation of the Tank Waste Remediation System Hanford Tank Waste Operations Simulator*, HNF-SD-TWR-RPT-006, Rev. 0, Numatec Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

This page intentionally left blank.

APPENDIX A

REQUIREMENTS PHASE SEQUENCE AND LOG

This page intentionally left blank.

Table A-1. Requirements Phase Sequence and Log. (2 Sheets)

Section	Requirement Description	Observation or Reference to Requirements Anomaly Report Item	Date Accepted
3.1.1.1	Traceability Annual Report General	The verifications listed in Table 3-1 were completed. 19 anomalies were logged. All were closed out on or before 6/30/99.	6/30/99
3.1.1.2	Traceability Annual Report Graphics	The verifications listed in Table 3-2 were completed. The determination was made to use the same graphics postprocessing software used by the traditional OWVP. File format conversion software was developed to convert the HTWOS output files to the format required by postprocessing software. Three anomalies were logged through 6/21/99; and all were cleared by 6/30/99. Traceability requirements are met. Actual graphics generation will be provided in the Test Phase.	7/7/99
3.1.1.3	Traceability Annual Report Tables	The verifications listed in Table 3-3 were completed. Two anomalies were logged on 6/9/99, and cleared on 6/21/99.	6/21/99
3.1.2	Traceability Special Report	Cases are set up in the same manner as for the annual report. The same HTWOS output files are requested. A subset of the graphs and tables are generated using the same postprocessing software as used for the annual report. Requirements traceability for the special report is satisfied.	6/30/99
3.2	Traceability Revised Capabilities	The verifications listed in Table 3-4 were completed. Three requirement anomalies were logged and closed out by 6/30/99.	6/30/99
3.3.1	OWVP Work Station Interface	The user interface on the personal computer over the HLAN appears identical to the interface on the UNIX terminal connected directly to the UNIX server (master processor).	6/7/99

Table A-1. Requirements Phase Sequence and Log. (2 Sheets)

Section	Requirement Description	Observation or Reference to Requirements Anomaly Report Item	Date Accepted
3.3.2	Postprocessing Software Interface	The files generated by HTWOS require conversion prior to use in the postprocessing software. The conversion software for monthly and yearly file formats and waste type volumes was completed on 6/24/99.	6/24/99
3.3.3	User Interface	The verifications listed in Table 3-5 were completed. Two anomalies were logged on 6/16/99; and both were closed by 6/7/99.	7/7/99

HLAN = Hanford local area network
 HTWOS = Hanford Tank Waste Operations Simulator
 OWVP = Operational Waste Volume Projection

APPENDIX B

REQUIREMENTS PHASE ANOMALY REPORT

This page intentionally left blank.

Table B-1. Requirements Phase Anomaly Report. (6 Sheets)

Requirement Phase Anomaly Number	Requirement Phase Procedure Section	Source Requirement or Special Feature	Anomaly Description	Date found	Disposition	Close-out Date
1	3.1.1.1, Table 3-1, ID 4	Kirkbride et al. 1999, App. A, 8.0, "Inventory"	Initial inventory records have volume discrepancies. April 1999 Hanlon transferable liquid inventory for 101-AY is 27 Kgal. The generated TAF for Case 3S3 shows a 232 Kgal transfer out on June 1, 1999. Similar discrepancy for 241-AN-106 on 8/20/99.	5/25/99	Enter corrected starting inventories for both tanks. Complete verification of the 28 initial inventories is to occur in the Test Phase.	6/17/99
2	3.1.1.1, Table 3-1, ID 4	Kirkbride et al. 1999, - SPApp A, 11.0, "Architecture"	The first cross-site transfer was to 241-AP-107, not 241-AW-103 (6/17/99). Operational constraints and plans call for using 241-AP-107 and 241-AP-104 alternatively to allow cross-site, staging, characterization, and evaporation.	5/25/99	Change the tanks in the cross-site transfer logic block to reflect alternating between 241-AP-107 and 241-AP-104 or cross site transfers.	6/17/99
3	3.1.1.1, Table 3-1, ID 10	Kirkbride et al. 1999, - SPApp A, 6.0, "Operations"	The evaporator model allowed 241-AW-103 to be evaporated (1/19/99) two days after cross-site transfer. Constraints cause a minimum 120 day between 241-AP-107 fill and evaporator start.	5/25/99	On evaporator logic, set batch sample days of the feed tanks to 120 days.	6/17/99
4	3.1.1.1, Table 3-1, ID 8	Kirkbride et al. 1999, - SPApp A, 6.0, "Operations"	A broken pump in 241-AW-104 will prevent evaporation (TAF 7/8/99) until June 2001 or later.	5/25/99	Set the tank lockouts date to 6/1/2001 for 104-AW in the Dilute DST 2 Tanks block.	6/17/99
5	3.1.1.1, Table 3-1, ID 8	Kirkbride et al. 1999, - SPApp. A, 11.0, "Architecture"	Due to Project 314 interference, SWL may be pumped within AN but not to other farms until 8/2002. The transfer from 101-AN to 102-AW can not occur on 8/2/99. Plans call for transfer to 106-AN.	5/25/99	Set the tank lockouts date to 8/2/99 for 102-AW. On OWVP Logic, set 106-AN as Dilute Receiver receiving transfers from A-AX Receiver.	6/17/99

Table B-1. Requirements Phase Anomaly Report. (6 Sheets)

Requirement Phase Anomaly Number	Requirement Phase Procedure Section	Source Requirement or Special Feature	Anomaly Description	Date found	Disposition	Close-out Date
6	3.1.1.1, Table 3-1, ID 8	Kirkbride et al. 1999, - SPApp. A, 11.0, "Architecture"	The transfer of dilute phosphate from 101-AP can not occur on 9/15/99. Transfer from 101-AP is constrained to occur October 2002 or later.	5/25/99	Place tank lockouts date on 101-AP to 10/1/2002.	6/17/99
7	3.1.1.1, Table 3-1, ID 8	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	The transfer from A-101 to 108-AP can not occur on 5/13/2000. New operational constraints will send SWL from A-101 and AX-101 to 101-AN. 101-AN is cascaded to 106-AN.	5/25/99	Remove 108-AP from A-AP Receiver block of OWVP Logic. Also, see actions for Item 5.	6/17/99
8	3.1.1.1, Table 3-1, ID 4	Kirkbride et al. 1999, - SPApp. A, 8.0, "Inventory"	The C-106 inventory was not transferred in July 1998. Rather the transfers are occurring over several months in 1999.	5/25/99	Edit C-106 start in Phase 1 Retrieval Assumptions-Scheduled HLW feed staging operations.	6/17/99
9	3.1.1.1, Table 3-1, ID 10 and 3.2 Table 3-4 ID 6	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	An evaporator operational constraint imposed by cost placed 4 months between the start of (one or two tank) campaigns. The goal is to achieve 8 months between campaigns. The nearly continuous evaporator operation in June, July, and August 1999 does not reflect the constraint.	5/25/99	Evaporator logic (OWVP Logic window) was changed to accept Maximum Campaign Days and Minimum Days Between Campaigns parameters. This logic can be used to correctly space campaigns as long as the properly calculated campaign time (including recycle time) is provided.	6/7/99
10	3.1.1.1, Table 3-1, ID 8	Kirkbride et al. 1999, - SPApp. A, 3.0, "DST System"	For 102-SY, special maximum and minimum levels are applied. The fill limit is 1082 Kgal, and minimum draw-down is 358 Kgal to avoid disturbing the solids. The rule reverts once the solids are transferred out. This constraint was missed.	5/25/99	Model will not allow solids pumping until solids are mixed. Draw-down is automatically calculated to avoid disturbing solids.	6/17/99

Table B-1. Requirements Phase Anomaly Report. (6 Sheets)

Requirement Phase Anomaly Number	Requirement Phase Procedure Section	Source Requirement or Special Feature	Anomaly Description	Date found	Disposition	Close-out Date
11	3.1.1.1, Table 3-1, ID 6	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	The transfer file shows no flushes for SWL pumping. Historically, 26% flush has been used.	5/25/99	An inline dilution factor (0.1-0.5) is assigned to each farm (edit on Farm Graphic) being salt well pumped. A feature is available that optionally places these additions in the output TAF.	6/21/99
12	3.1.1.1	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	None of the facility generations or terminal cleanout volumes are included in transfers beyond FY 1998.	5/25/99	Logic corrected except for Phase 2 West Area on 6/7/99. Logic correction for West (102-SY) complete on 6/17/99.	6/17/99
13	3.1.1.1	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	Waste generators table uses label "flush %" but presents values as flush fraction.	5/26/99	Heading corrected to "fraction flush."	6/17/99
14	3.1.1.1, Table 3-1, ID 8 and 10	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	Tank Farm (TAF) file is no longer read as input resulting in the loss of certain operational constraints for the first 5 years of simulation.	5/24/99	Tank lockout intervals are manually entered in the tank logic definition to capture known early year operational constraints. The user must identify all constraints and convert to appropriate lockout values.	6/21/99
15	3.1.1.1, Table 3-1, ID 7	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	Early evaporations are modeled contrary to operations schedules and planning. 101-AP, 105-AP, and 104-AW will not be evaporated in 1999 as indicated in HTWOS. Schedule dependencies are missing.	5/24/99	Resolution of Item 14 should clear this item. Tank lockout entries are required for 101-AP, 105-AP, and 104-AW to mid FY 2000.	6/21/99

Table B-1. Requirements Phase Anomaly Report. (6 Sheets)

Requirement Phase Anomaly Number	Requirement Phase Procedure Section	Source Requirement or Special Feature	Anomaly Description	Date found	Disposition	Close-out Date
16	3.1.1.1, Table 3-1, ID 5	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	Waste Generator discrepancies were found for PFP, PUREX TCO, 100K TCO, 100N TCO, and 300 Area. Also, HTWOS does not indicate maximum monthly generations as needed in OWVP Report. See details in Table D-1.	6/2/99	The generation event file definition is editable. The "Show monthly output history" shows graph of declining source volume. Maximum total generation must be computed externally from saved monthly history files.	6/21/99
17	3.1.1.1, Table 3-1, ID 11	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	Waste Generator data are not reflected in output (echo) files but are needed for setup verification. Likewise, SWL pumping targets and achieved results are not reflected in output files.	6/9/99	Use the "Show monthly output history" of the waste generator to display a bar graph of the monthly output. This output is saved with the OWVP results. Also see No. 16 disposition.	6/21/99
18	3.1.1.2, Table 3-2, Fig. 5, 10, 11, 19, 20, and 22	Strode and Boyles 1998, - ERgraphics	Waste-generation graphics lack required input files.	6/9/99	Resolution of Item 17 should clear this item. Monthly history files can be saved for each generator and converted externally to the format used for OWVP report graphics.	6/21/99
19	3.1.1.2, Table 3-2, Fig. 21	Strode and Boyles 1998, - ERgraphics	SWP graphics lack required input files.	6/9/99	Resolution of Item 17 should clear this item. A feature is available that optionally places SWL dilution additions in the output TAF. Monthly history files for dilute receivers 108-AP, 106-AN, and 102-SY may be analyzed in postprocessing to generate SWL pumping files.	6/21/99
20	3.1.1.3, Table 3-3, Tab 4 and 14	Strode and Boyles 1998, - ERTables	SWP tables lack required input files.	6/9/99	Resolution of Item 17 should clear this item. Also see No. 19 disposition.	6/21/99

Table B-1. Requirements Phase Anomaly Report. (6 Sheets)

Requirement Phase Anomaly Number	Requirement Phase Procedure Section	Source Requirement or Special Feature	Anomaly Description	Date found	Disposition	Close-out Date
21	3.1.1.3, Table 3-3, Tab 15 and 20	Strode and Boyles 1998, - ERtables	New Waste Additions data are not provided in HTWOS output (echo) files.	6/9/99	Resolution of Item 17 should clear this item. Also see No. 18 disposition.	6/21/99
22	3.2, Table 3-4, Requirement. ID 4	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	The full logic used to build TAF files was not converted to specifications for HTWOS. This results in predicting near-term transfers that neglected constraints prohibit.	6/9/99	Resolution of Item 14 should clear this item. See No. 14 disposition.	6/21/99
23	3.1.1.1, Table 3-1 Requirement. ID 4 and 3.3.3, Table 3-5 Requirement. ID 3	Kirkbride et al. 1999, - SPApp. A, 8.0 "Tank Waste Inventories and Composition"	Traditional OWVP shows up to 16 years of historical tank information on report graphics. HTWOS provides a 2 year (editable) table for historical data.	6/15/99	Initially, a separately maintained history file (from Traditional OWVP) will be used to construct the graphics.	6/30/99
24	3.3.3, Table 3-5, Requirement. ID 4	HNF-PRO-2778, Section 5.2.f	A HELP menu system is provided as the HTWOS Users' Guide but is not up to date and has very little textual information explaining procedures, tables, and logic graphics for the user.	6/15/99	During the Test Phase, the user shall log specific areas where the User's Guide is deficient. A Test Phase anomaly shall be prepared to track User's Guide update commitments.	7/7/99
25	3.1.1.1, Table 3-1, ID 5 and 3.2 Table 3-4, Requirement. ID 4	Kirkbride et al. 1999, - SPApp. A, 6.0, "Operations"	HTWOS needs to be updated to the 1/13/99 SWL Pumping Duration Model values. Three tanks have revised pumping volumes. SX Farm has three different dilution factors; S Farm has two.	6/21/99	104-SX has 68,489 gal, 106-SX has 118,205 gal, 104-T has 26,309 gal and 110-T has 36,589 gal. 102-S has 0.5 dilution, 104-SX has 1.0 dilution, and 106-SX has 0.33 dilution.	6/30/99
26	3.1.1.2, Table 3-2, Fig. No. 4	Strode and Boyles 1998, - ERgraphics	Two current OWVP waste-type designations are not implemented in HTWOS, "SS" SST (retrieved) Solids and "SC" SST (retrieved) Saltcake.	6/21/99	Rename "BT" (which is obsolete solid) to "SS" and rename "BA" (which is an obsolete liquid due to privatization) to "SC".	6/30/99

Table B-1. Requirements Phase Anomaly Report. (6 Sheets)

Requirement Phase Anomaly Number	Requirement Phase Procedure Section	Source Requirement or Special Feature	Anomaly Description	Date found	Disposition	Close- out Date

FY = Fiscal year
 HTWOS = Hanford Tank Waste Operations Simulator
 OWVP = Operational Waste Volume Projection
 PFP = Plutonium Finishing Plant
 PUREX = Plutonium-Uranium Extraction (facility)
 SWL = Salt well liquid
 TAF = Tank Activity File
 TCO = Terminal cleanout

Kirkbride, R. A., G. A. Allen, R. M. Orme, and R. S. Wittman, (Numatec Hanford Corporation); J. H. Baldwin, T. W. Crawford, and J. Jo (Lockheed Martin Hanford Corporation); L. J. Fergstrom, T. M. Hohl, and D. L. Penwell (COGEMA), 1999, *Tank Waste Remediation System Operation and Utilization Plan*, HNF-SD-WM-SP-012, Rev. 1, Numatec Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

PHMC, 1999, *IRM Application Software System Life Cycle Standard*, HNF-PRO-2778, Fluor Daniel Hanford, Inc., Richland, Washington.

Strode, J. N., and V. C. Boyles, 1998, *Operational Waste Volume Projection*, HNF-SD-WM-ER-029, Rev. 24, Lockheed Martin Hanford Corporation for Fluor Daniel Hanford, Inc., Richland, Washington.

APPENDIX C

TEST PHASE SEQUENCE AND LOG

This page intentionally left blank.

Table C-1. Test Phase Sequence and Log—Test Cases and Acceptance Criteria.

Section	Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.1.1	Test Case 1 Defined	This is the Tri-Party Agreement Compliant case. The two models will behave differently after 32 (28 + 4) DSTs are full. Revision: Both models are operated to complete SST retrieval by 2018 by using a "final DST" with at least 100 Mgal.	7/16/99 Revision 8/16/99
5.1.2	Test Case 2 Defined	This is the Project Planning case and uses maximum rates and HLW waste oxide loading. The case is used to establish various operational need dates.	7/16/99
5.1.3	Test Case 3 Defined	This case explores the benefits of using alternate HLW tanks to optimize DST use. The privatization contractor provides a LAW feed tank for recycle from HLW processing.	7/16/99
5.2 Step 4	Case 1 Acceptance Criteria Defined	The criteria take into account the different behavior of the two models after 32 DSTs are full. HTWOS throttles SST retrieval while historical OWVP keeps adding DST capacity to meet the 2018 SST retrieval completion date (Tri-Party Agreement). Revision: All SSTs shall be retrieved by 2018, and the DST waste inventories and DST Requirements shall agree within 5% for the two models at the end of 2018.	7/16/99 Revision 8/16/99
5.2, Step 5	Case 2 Acceptance Criteria Defined	The criteria take into account the improved time resolution of HTWOS and the improved scheduling of generated waste receipts.	7/16/99
5.2, Step 6	Case 3 Acceptance Criteria Defined	The criteria take into account the improved time resolution of HTWOS and the improved scheduling of generated waste receipts.	7/16/99

DST = Double-shell tank
 HLW = High-level waste
 HTWOS = Hanford Tank Waste Operations Simulator
 LAW = Low-activity waste

Ecology, EPA, and DOE-RL, 1996, *Hanford Federal Facility Agreement and Consent Order*, (commonly called the Tri-Party Agreement), Washington State Department of Ecology, U.S. Environmental Protection Agency, U.S. Department of Energy, Richland Operations Office, Olympia, Washington, amended periodically.

Table C-2. Test Phase Sequence and Log—Test Readiness Review.

Section	Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.3, Item 1	HTWOS is under configuration management		7/7/99
5.3, Item 2	General Requirements traceability is verified		7/7/99
5.3, Item 3	Figure generation requirements are verified.		7/16/99
5.3, Item 4	Table generation requirements are verified.		6/19/99
5.3, Item 5	Traceability for new OWVP requirements is verified.		6/30/99
5.3, Item 6	Traceability for OWVP User Interface verified.	Two anomalies were logged on June 16, 1999, and both were closed by July 7, 1999.	7/7/99
5.3, Item 7	Test Case 1 Acceptance Criteria established		7/16/99
5.3, Item 8	Test Case 2 Acceptance Criteria established		7/16/99
5.3, Item 9	Test Case 3 Acceptance Criteria established		7/16/99

HTWOS = Hanford Tank Waste Operations Simulator
OWVP = Operational Waste Volume Projection

Table C-3. Test Phase Sequence and Log—Test Case 1 Acceptance Test Sequence. (2 sheets)

Section	Test Case 1 Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.4, Step 1	Establish HTWOS connection.	Began using Telewindows™ on personal computer as workstation for the Tri-Party Agreement Compliant case on 8/4/99. On 8/9/99, switched to UNIX terminal as personal computer interface failed; two test anomalies were written. This is the second case in the testing sequence but called Test Case 1, Project Planning with Accelerated SST Retrieval (Scenarios Case 3S3 with Operational Constraints and Provision for Retrieved SST Solids).	8/9/99
5.4, Step 2	Load history file.	The baseline history file is used.	N/A
5.4, Step 3	Load test case assumptions.	Most test case assumptions are the same as loaded for Test Case 2 with the exception of added retrieval machines, added DST capacity (for Solids staging) and SST retrieval free from category constraints. Multiple iterations were needed to tune the aggregate SST retrieval rate.	8/12/99
5.4, Step 4	Load near-term operational constraints.	Near-term operational constraints are the same as loaded for Test Case 2.	8/9/99
5.4, Step 5	Run projection with required options.	Saved DST utilization and availability data and standard "Results" files. Directory is case3S3-tpa__8-13-99.	8/13/99
5.4, Step 6	Log anomalies and restart at Step 3 if necessary.	A total of eight test anomalies were logged for this test case. Three were cleared by 8/12/99. The remainder applies to overall simulator operations and was cleared by 8/17/99. The Phase 1 Allocations accounting anomaly logged during the previous test was cleared on 8/12/99. This should significantly improve the comparison with OWVP.	8/13/99 (Overall simulator operations anomalies 8/17/99)
5.4, Step 7	Compare results to criteria during run restart at Step 3 if necessary.	The final SPARE DST was set to 100 Mgal capacity allowing SST retrieval to complete by 2018.	8/16/99

Table C-3. Test Phase Sequence and Log—Test Case 1 Acceptance Test Sequence. (2 sheets)

Section	Test Case 1 Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.4, Step 8	Save OWVP file with Test Case identification.	Results saved to f:\gandalf\results\case3S3-tpa_8-13-1999 directory. The Test Case identification is within the saved HTWOS model.	8/13/99
5.4, Step 9	Transfer OWVP file for postprocessing.	Processed on spreadsheet for comparison with traditional OWVP results.	8/16/99
5.4, Step 10	Process files and print report graphics.	Figure 3 DST Requirements for Case 1—TPA Compliant was generated. Generation of the remaining graphs was demonstrated in Test Case 2.	8/16/99
5.4, Step 11	Process files and print report tables.	The End of Year Inventories of Table 11 were compared for Case 1 (HTWOS and OWVP). Generation of the remaining tables was demonstrated in Test Case 2.	8/16/99
5.4, Step 12	Compare results with acceptance criteria for test case.	The HTWOS DST capacity was set to increase beginning in 2013. The OWVP DST capacity was set to increase starting in 2007 with the surge in capacity occurring after 2011. By 2018, both models had completed SST retrieval and total DST inventories were approximately 112 Mgal (agreement within 3.5%). Both predicted a DST Requirement of 105 to 106 (standard size tanks). Both predicted inventory and DST Requirements satisfied the acceptance criteria (5% maximum difference).	8/16/99

DST = Double-shell tank
 HTWOS = Hanford Tank Waste Operations Simulator
 OWVP = Occupational Waste Volume Projection
 SST = Single-shell tank

Ecology, EPA, and DOE-RL, 1996, *Hanford Federal Facility Agreement and Consent Order*, (commonly called the Tri-Party Agreement), Washington State Department of Ecology, U.S. Environmental Protection Agency, U.S. Department of Energy, Richland Operations Office, Olympia, Washington, amended periodically.

Table C-4. Test Phase Sequence and Log—Test Case 2 Acceptance Test Sequence. (3 sheets)

Section	Test Case 2 Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.4, Step 1	Establish HTWOS connection.	Using Telewindows™ on personal computer as workstation. Starting with Test Case 2 which is Project Planning (Scenarios Case 3S3 with Operational Constraints).	7/29/99
5.4, Step 2	Load history file.	The baseline history file is used.	N/A
5.4, Step 3	Load test case assumptions.	Load assumptions from original Case 3S3 into updated HTWOS (updated due to Requirements Phase findings and other refinements).	7/29/99
5.4, Step 4	Load near-term operational constraints.	Started on 7/29/99. Nine procedure changes/additions were required to accommodate the operational constraint anomalies identified in the Requirements Phase. The changes included the addition of a DST cascade feature to handle salt well pumping with project interference.	7/30/99
5.4, Step 5	Run projection with required options.	Saved TAF, volume histories for 241-AN-101, 241-AP-106, 241-AN-106, 241-AP-108, 241-SY-101, 241-SY-102, 241-SY-103, West DST, East DST, all generator monthly outputs. These are used for verification of items related to Requirements Phase anomalies. Requested monthly wasted type history files for all DSTs. Requested save all results and verified that Waste Volume Projection, Phase 1 and Phase 2 were sent to different directories.	8/3/99
5.4, Step 6	Log anomalies and restart at Step 3 if necessary.	Eight anomalies were logged for this case. Six anomalies were cleared by 8/3/99. The remaining two anomalies are accounting problems associated with initial volume inventory and tanks allocated to Phase 1 operations. The Phase 1 Allocation accounting is to be corrected before completion on the next Test Case.	8/4/99

Table C-4. Test Phase Sequence and Log—Test Case 2 Acceptance Test Sequence. (3 sheets)

Section	Test Case 2 Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.4, Step 7	Compare results to criteria during run restart at Step 3 if necessary.	The mean difference in inventory projections was 0.10 Mgal between 1998 and 2018 while the RMS of the difference was 1.07 Mgal. The peak difference was 2.29 Mgal. The mean difference in DST requirement was 0.6 tanks between 2010 and 2018, while the RMS difference was 1.61 tanks. The HTWOS Phase 1 Allocation accounting overestimates DST requirements (Anomaly 7) at least through 2009; thus DST Requirements for the early years are overstated and excluded from the comparison.	8/3/99
5.4, Step 8	Save OWVP file with Test Case identification.	Saved DST Available Volumes to directory Case3S3_8_3_99. The TAF is available on \\gandalf\HTWOS-TW.	8/3/99
5.4, Step 9	Transfer OWVP file for post-processing.	File dst-available-volumes.xls was saved in "Case 3S3 with constraints" directory. The 28 DST monthly volume by waste type files are stored in the "DST Waste Type Volume Files" subdirectory.	8/17/99
5.4, Step 10	Process files and print report graphics.	Figure 15DST Requirements for Case 2 was generated. Graphs of waste generation from all facilities were generated (Figures 4, 5, and 9). Figure 8 242-A Evaporator Operations was generated. General DST level graphics generation was demonstrated (Figures 6 and 8-12). Files for generation of Figure 20, Contributions from Salt Well Liquid Pumping, were not requested. Aging Tank Requirements graphs were generated (Figures 13 and 14). Graphs of DST volume inventories by wasted type were demonstrated for individual DSTs; combined these graphs form Figure 16.	8/18/99

Table C-4. Test Phase Sequence and Log—Test Case 2 Acceptance Test Sequence. (3 sheets)

Section	Test Case 2 Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.4, Step 11	Process files and print report tables.	The Salt Well Pumping output file (DST, start date, and end date) does not fully support generation of Tables 4 and 13; remaining data are extracted manually. Tables 5, 6, 8, 10, 12, 15, 17, and 19 must be generated manually by querying model. Table 11, Assumption Matrix, was generated manually from HTWOS queries and is shown in Appendices D, E, and F for the three cases. To generate Table 14, Waste Additions and Reductions for Case 2, many output files must be combined. The End of Year Inventories of Table 14 were compared for Case 2 (HTWOS and OWVP). Table 16 and 18 are generated directly from the 242-a-throughput.his files. Table 20 requires many output files to be combined and requires external monthly average calculations.	8/18/99
5.4, Step 12	Compare results with acceptance criteria for test case.	The Phase 1 Allocation accounting (Anomaly 7) was corrected on 8/12/99 for Test Case 1, and the DST Requirements through 2009 were then applied to Test Case 2. For the interval from 1998 through 2018, the average inventory difference was 0.1 Mgal and the RMS inventory difference was 1.1 Mgal. The average DST Requirement difference was half a tank, and the RMS DST Requirement difference was 2.3 tanks. These results satisfy the Test Case 2 acceptance criteria.	8/18/99

DST = Double-shell tank
 HTWOS = Hanford Tank Waste Operations Simulator
 OWVP = Occupational Waste Volume Projection
 RMS = Root-mean-square
 TAF = Tank activity file

Table C-5. Test Phase Sequence and Log—Test Case 3 Acceptance Test Sequence. (2 sheets)

Section	Test Case 3 Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.4, Step 1	Establish HTWOS connection.		8/19/99
5.4, Step 2	Load history file.	The baseline history file is used.	N/A
5.4, Step 3	Load test case assumptions.	Operational constraints are the same as loaded for Test Case 2; therefore, that case was used as the starting point. LAW and HLW vitrification plant ramp-up rates were manually reset to Case 6b values (Phase 2 capacities double that of other test cases). Slight adjustments were made to the staging sequences.	8/23/99
5.4, Step 4	Load near-term operational constraints.	See Step 3.	8/23/99
5.4, Step 5	Run projection with required options.		8/23/99
5.4, Step 6	Log anomalies and restart at Step 3 if necessary.	Five Test Anomalies were logged and cleared. These all dealt with complexities in setting HLW feed staging parameters and HLW vitrification plant ramp-up rates.	8/24/99
5.4, Step 7	Compare results to criteria during run restart at Step 3 if necessary.	Two repeats were necessary; the initial set of HLW staging parameters caused a bottleneck that inhibited SST retrieval and extended retrieval beyond 2050.	8/24/99
5.4, Step 8	Save OWVP file with Test Case identification.	Saved to \\results\case6b8_24_99 directory.	8/24/99
5.4, Step 9	Transfer OWVP file for postprocessing.	Saved as AvailableDSTs6b.xls in Case 6b (Test Case 3) directory of "HTWOS Eval"	8/24/99
5.4, Step 10	Process files and print report graphics.	Figure 17, DST Requirements for Test Case 3, was generated. Generation of the remaining graphs was demonstrated in Test Case 2.	8/25/99
5.4, Step 11	Process files and print report tables.	The End of Year Inventories of Table 14 were compared for Case 3 (HTWOS and OWVP) Generation of the remaining tables was demonstrated in Test Case 2.	8/25/99

Table C-5. Test Phase Sequence and Log—Test Case 3 Acceptance Test Sequence. (2 sheets)

Section	Test Case 3 Sequence Description	Observation or Reference to Test Phase Anomaly Report Item	Date Accepted
5.4, Step 12	Compare results with acceptance criteria for test case.	Through 2010, the average inventory difference was 0.6 Mgal and the RMS difference was 1.0 Mgal. The average DST Requirement difference was 0.7 tanks, and the RMS difference was 2.3 tanks. Much of the RMS DST Requirement difference is related to Test Phase Anomaly 15 (DST Requirements calculation). These results satisfy the Test Case 3 acceptance criteria.	8/25/99

DST = Double-shell tank
 HLW = High-level waste
 HTWOS = Hanford Tank Waste Operations Simulator
 LAW = Low-activity waste
 OWVP = Occupational Waste Volume Projection
 RMS = Root-mean-square
 SST = Single-shell tank
 TAF = Tank activity file

This page intentionally left blank.

APPENDIX D

TEST CASE 1 ASSUMPTIONS

This page intentionally left blank.

Table D-1. Assumption Matrix for Test Case 1--Modified Project Planning with Tri-Party Agreement-Compliance Retrieval. (5 sheets)

Assumption Category	Assumptions
<u>Meets Tri-Party Agreement Milestones</u>	Yes
<u>Facility Generations</u>	
Total Limit, Kgal/mo	~25
<u>PUREX</u>	
Yearly Rate, Kgal/yr	5
TCO Scheduled	Completed
TCO Volume, Kgal	0
Flush for TCO	---
WVRF for TCO (to DSSF)	99
<u>B Plant</u>	
TCO Scheduled	Completed
TCO Volume, Kgal	0
Flush for TCO	---
WVRF for TCO (to DSSF)	99
<u>Waste Encapsulation Safety Facility</u>	
Monthly Rate, Kgal/mo	5 Kgal/yr (0.5 per month OWVP 1998)
Flush for Miscellaneous Waste	0%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>S Plant</u>	
Monthly Rate, Kgal/mo	2.1
Flush for Miscellaneous Waste	22%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>T Plant</u>	
Monthly Rate, Kgal/mo	1.4 to 2.7
Flush for Miscellaneous Waste	22%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>300 Area</u>	
Monthly Rate, Kgal/mo	4.2
Flush for Miscellaneous Waste	44%
WVRF, Miscellaneous Waste (to DSSF)	94
<u>400 Area</u>	
Rate, Kgal-every 3 rd yr	7 (1999)
Flush for Miscellaneous Waste	44%
WVRF, Miscellaneous Waste (to DSSF)	94
<u>WCSF</u>	
Monthly Rate, Kgal/mo	0.0
<u>Tank Farms</u>	
Monthly Rate, Kgal/mo	10
WVRF, Flushes (to DSSF)	99
<u>IMUST Wastes</u>	
Total Volume, Kgal (2011-2015)	500

Table D-1. Assumption Matrix for Test Case 1--Modified Project Planning with Tri-Party Agreement-Compliance Retrieval. (5 sheets)

Assumption Category	Assumptions
<u>100 Area</u>	
100-N	
TCO Scheduled	Completed

100-K Basin Cleanout	
TCO Scheduled	2004-2005
TCO Volume, Kgal	430
Volume of Solids Included	98

105-F and 105-H Basins	
TCO Waste in 2001, Kgal	40
TCO Waste in 2008, Kgal	200

Flush, ALL 100 Area Waste	44%
WVRF, ALL TCO Waste (to DSSF)	Not used in HTWOS (99 in OWVP 1998)
<u>Tank 107-AN Caustic Addition</u>	
Addition in FY 2000, Kgal	0 (66 in OWVP 1998)
<u>SWL Pumping</u>	
Volume Remaining, Mgal	5
Volume to be Pumped in 1999, Mgal	1
West Area Receiver	Tank 241-SY-102
Start Complexed SWL in 200 West Area	2000 (241-U-103) (2002 in OWVP 1998)
Pumping Completion, FY	8/2003 Early Finish (2004 in OWVP 1998)
Dilute Complexed SWL, Mgal	~1 (1.64 in OWVP 1998)
Porosity Saltcake/Sludge	Not used in HTWOS (50%/21% in OWVP 1998)
Flush for SWL Pumping	0% (28% in OWVP 1998)
WVRF, Noncomplexed (to DSSF)	Not used in HTWOS (47 in OWVP 1998)
WVRF, Complexed (to DSSF)	Not used in HTWOS (10 in OWVP 1998)
<u>SST Solids</u>	
Tank 106-C Retrieval	In Progress
Tank 104-C Retrieval	1/2007 (3/2005 in OWVP 1998)
Number of Tanks to Store 106-C Solids	1
Start Remaining SST Retrieval	7/2008 (241-C-107)
Tank Farm Closure Start	8/2017 (AX)
Approximate Dilution Ratio	(3:1 in OWVP 1998)
Meets Tri-Party Agreement Milestones	Yes
Number of SSTs Retrieved by 2018	149
Sludge Retrieved, Mgal	12.2
Saltcake Retrieved, Mgal	23.4
<u>Plutonium Finishing Plant Stabilization</u>	
Dates	1999-2012
Volume, Kgal	33 (27 in OWVP 1998)
Flush	22%
WVRF	81

Table D-1. Assumption Matrix for Test Case 1--Modified Project Planning with Tri-Party Agreement-Compliance Retrieval. (5 sheets)

Assumption Category	Assumptions
<u>Evaporator</u>	
242A Shutdown	2011
New Evaporator (Privatize)	2011
Next Outage Date	2004 (1 year)
Training Volume, Kgal (bi-yearly)	50
Average Evaporation Rate, Kgal/mo	500
Maximum Boil-off Rate, gal/min	50
Evaporation Product	dilute DSSF
Evaporation Limit (g/mL)	1.41
Liquid Effluent Retention Facility Capacity, Mgal	13
Gallons Condensate/Gallon WVR	1.20
Yearly Evaporation of DN (except for scheduled outage)	Yes
<u>Effluent Treatment Facility</u>	
Rate, Mgal/yr	50
<u>Watch List/Safety</u>	
101-SY Dilution, 650 Kgal	10/1999 – 3/2000
103-SY Processing Dilution	7/2010 (4/2010 in OWVP 1998)
<u>Spare/Contingency Space</u>	
Spare Space, Mgal	2.28
Use 0.72 Mgal of Operational Space in 106-AW as part of Spare Space from 2000 on	Yes
Contingency Space, Mgal	None
<u>Waste Segregation/DST Solids</u>	
Total DST Solids, Mgal	5
Store DSSF on NCRW Solids	Yes
Store DSSF on NCAW Solids	Yes
Segregate Complexed Wastes	If Possible
<u>Loss of DST Space</u>	
Number of Tanks Removed from Service	None
<u>New DST Construction</u>	
Number of Tanks Constructed	As needed for SST retrieval 4 (allowed to float in OWVP)
Date Constructed	Phased 2010-2017
<u>New Cross-Site Transfer Line</u>	
New Line Operational	Yes
Old Line Operational	Yes
<u>DST Retrieval</u>	
102-SY Solids Retrieved to 200 East Area Consolidation of NCRW Solids in 103-AW and 105-AW	8/2008 (1/2008 in OWVP 1998)
	No

Table D-1. Assumption Matrix for Test Case 1--Modified Project Planning with Tri-Party Agreement-Compliance Retrieval. (5 sheets)

Assumption Category	Assumptions
<u>Waste Processing</u>	
HLW Processing Start	10/2004
HLW Vitrification Start	4/2006
LAW Processing Start	10/2005
LAW Vitrification Start	3/2007
Phase Treatment Ends	12/2023 (extended)
Phase 1 Extension	Overlap Phase 2 to 12/2023
ILAW Product Rate, ILAW units per year	800 yr 1-3, 1100 yr 4-11, 2200 thereafter
IHLW Rate, canisters per year	100 yr 1-2, 120 yr 3-12, 480 thereafter
Total Processed Quantities:	
Envelope A, MT Na	~7900
Envelope B, MT Na	~615
Envelope C, MT Na	~3800
Staging/Characterization	
Time per Tank, days	<u>270</u>
Approximate Concentration of Retrieved DSSF, CC	<u>7 molar Na</u>
<u>LAW Retrieval Schedule—</u>	
Dates to Stage First Five Batches:	
Batch 1	241-AN-107 (5/2005)
Batch 2	241-AN-104 (10/2006)
Batch 3	241-AN-102 (8/2007)
Batch 4	241-AN-105 (10/2008)
Batch 5	241-SY-101 (3/2010)
Number of Intermediate Feed Staging Tanks	2
Number of LAW Contractors	1
Number of Vendor Feed Tanks	1
Pretreated NCAW Receipt Tank	0
Entrained Solid Receipt Tanks	1
<u>Phase 2 Privatization Processing</u>	
Contract Award	2005
LAW Operations (latest completion by agreement)	2011–2028+
HLW Operations (latest completion by agreement)	2011–2028+
Number of HLW Return Tanks	3
Includes New Evaporator	Yes
Processing Rates @ 60% Total Operating Efficiency	
ILAW (units per year)	2200 (~60 MT ILAW/day)
IHLW (canisters per year)	480 (~6 MT IHLW/day)

Table D-1. Assumption Matrix for Test Case 1--Modified Project Planning with Tri-Party Agreement-Compliance Retrieval. (5 sheets)

Assumption Category		Assumptions	
<u>In-Tank Washing</u>			
In-tank Washing of NCAW		No	
Consolidation of NCAW Solids		No	
DSSF	= Double-shell slurry feed	LAW	= Low-activity waste
DST	= Double-shell tank	NCAW	= Neutralized current acid waste
FY	= Fiscal year	NCRW	= Neutralized cladding removal waste
HLW	= High-level waste	OWVP	= Operational Waste Volume Projection
HTWOS	= Hanford Tank Waste Operation Simulator	SWL	= Salt well liquid
IHLW	= Immobilized high-level waste	SST	= Single-shell tank
ILAW	= Immobilized low-activity waste	TCO	= Terminal cleanout
IMUST	= Inactive miscellaneous underground storage tank	WVRF	= Waste Volume Reduction Facility

Ecology, EPA, and DOE-RL, 1996, *Hanford Federal Facility Agreement and Consent Order*, (commonly called the Tri-Party Agreement), Washington State Department of Ecology, U.S. Environmental Protection Agency, U.S. Department of Energy, Richland Operations Office, Olympia, Washington, amended periodically.

This page intentionally left blank.

APPENDIX E

TEST CASE 2 ASSUMPTIONS

This page intentionally left blank.

Table E-1. Assumption Matrix for Test Case 2--Project Planning. (5 sheets)

Assumption Category	Assumptions
<u>Meets Tri-Party Agreement Milestones</u>	No
<u>Facility Generations</u>	
Total Limit, Kgal/mo	~25
<u>PUREX</u>	
Yearly Rate, Kgal/yr	5
TCO Scheduled	Completed
TCO Volume, Kgal	0
Flush for TCO	---
WVRF for TCO (to DSSF)	99
<u>B Plant</u>	
TCO Scheduled	Completed
TCO Volume, Kgal	0
Flush for TCO	---
WVRF for TCO (to DSSF)	99
<u>Waste Encapsulation And Storage Facility</u>	
Monthly Rate, Kgal/mo	5 Kgal/yr (0.5 per month OWVP 1998)
Flush for Miscellaneous Waste	0%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>S Plant</u>	
Monthly Rate, Kgal/mo	2.1
Flush for Miscellaneous Waste	22%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>T Plant</u>	
Monthly Rate, Kgal/mo	1.4 to 2.7
Flush for Miscellaneous Waste	22%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>300 Area</u>	
Monthly Rate, Kgal/mo	4.2
Flush for Miscellaneous Waste	44%
WVRF, Miscellaneous Waste (to DSSF)	94
<u>400 Area</u>	
Rate, Kgal-every 3 rd yr	7 (1999)
Flush for Miscellaneous Waste	44%
WVRF, Miscellaneous Waste (to DSSF)	94
<u>WCSF</u>	
Monthly Rate, Kgal/mo	0.0
<u>Tank Farms</u>	
Monthly Rate, Kgal/mo	10
WVRF, Flushes (to DSSF)	99
<u>IMUST Wastes</u>	
Total Volume, Kgal (2011-2015)	500

Table E-1. Assumption Matrix for Test Case 2--Project Planning. (5 sheets)

Assumption Category	Assumptions
<u>100 Area</u>	
100-N	
TCO Scheduled	1999

100-K Basin Cleanout	
TCO Scheduled	2004-2005
TCO Volume, Kgal	430
Volume of Solids Included	98

105-F and 105-H Basins	
TCO Waste in 2001, Kgal	40
TCO Waste in 2008, Kgal	200

Flush, ALL 100 Area Waste	44%
WVRF, ALL TCO Waste (to DSSF)	Not used in HTWOS (99 in OWVP 1998)
<u>Tank 107-AN Caustic Addition</u>	
Addition in FY 2000, Kgal	0 (66 in OWVP 1998)
<u>SWL Pumping</u>	
Volume Remaining, Mgal	5
Volume to be Pumped in 1999, Mgal	1
West Area Receiver	Tank 241-SY-102
Start Complexed SWL in 200 West Area	2000 (241-U-103) (2002 in OWVP 1998)
Pumping Completion, FY	8/2003 Early Finish (2004 in OWVP 1998)
Dilute Complexed SWL, Mgal	~ 1 (1.64 in OWVP 1998)
Porosity Saltcake/Sludge	Not used in HTWOS (50%/21% in OWVP 1998)
Flush for SWL Pumping	0% (28% in OWVP 1998)
WVRF, Noncomplexed (to DSSF)	Not used in HTWOS (47 in OWVP 1998)
WVRF, Complexed (to DSSF)	Not used in HTWOS (10 in OWVP 1998)
<u>SST Solids</u>	
Tank 241-C-106 Retrieval	In Progress
Tank 241-C-104 Retrieval	1/2007 (3/2005 in OWVP 1998)
Number of Tanks to Store 241-C-106 Solids	1
Start Remaining SST Retrieval	7/2008 (241-C-107)
Tank Farm Closure Start	8/2017 (AX)
Approximate Dilution Ratio	(3:1 in OWVP 1998)
Meets TPA Milestones	No
Number of SSTs Retrieved	149 by 2033
Sludge Retrieved, Mgal	12.2
Saltcake Retrieved, Mgal	23.4
<u>Plutonium Finishing Plant Stabilization</u>	
Dates	1999-2012
Volume, Kgal	33 (27 in OWVP 1998)
Flush	22%
WVRF	81

Table E-1. Assumption Matrix for Test Case 2--Project Planning. (5 sheets)

Assumption Category	Assumptions
<u>Evaporator</u>	
242A Shutdown	2011
New Evaporator (Privatize)	2011
Next Outage Date	2004 (1 year)
Training Volume, Kgal (bi-yearly)	50
Average Evaporation Rate, Kgal/mo	500
Maximum Boil-off Rate, gal/min	50
Evaporation Product	dilute DSSF
Evaporation Limit, g/mL	1.41
Liquid Effluent Retention Facility Capacity, Mgal	13
Gallons Condensate/Gallon WVR	1.20
Yearly Evaporation of DN (except for scheduled outage)	Yes
<u>Effluent Treatment Facility</u>	
Rate, Mgal/yr	50
<u>Watch List/Safety</u>	
101-SY Dilution, 650 Kgal	10/1999 – 3.2999
103-SY Processing Dilution	7/2010 (4/2010 in OWVP 1998)
<u>Spare/Contingency Space</u>	
Spare Space, Mgal	2.28
Use 0.72 Mgal of Operational Space in 106-AW as Part of Spare Space from 2000 on	Yes
Contingency Space, Mgal	None
<u>Waste Segregation/DST Solids</u>	
Total DST Solids, Mgal	5
Store DSSF on NCRW Solids	Yes
Store DSSF on NCAW Solids	Yes
Segregate Complexed Wastes	If Possible
<u>Loss of DST Space</u>	
Number of Tanks Removed from Service	None
<u>New DST Construction</u>	None
Date Constructed	N/A
<u>New Cross-Site Transfer Line</u>	
New Line Operational	Yes
Old Line Operational	Yes
<u>DST Retrieval</u>	
102-SY Solids Retrieved to 200 East Area Consolidation of NCRW Solids in 103-AW and 105-AW	8/2008 (1/2008 in OWVP 1998) No

Table E-1. Assumption Matrix for Test Case 2--Project Planning. (5 sheets)

Assumption Category	Assumptions
<u>Waste Processing</u>	
HLW Processing Start	10/2004
HLW Vitrification Start	4/2006
LAW Processing Start	10/2005
LAW Vitrification Start	3/2007
Phase 1 Treatment Ends	12/2023 (extended)
Phase 1 Extension	Overlap Phase 2 to 12/2023
ILAW Product Rate, ILAW units per year	800 yr 1-3, 1100 yr 4-11, 2200 thereafter
IHLW Rate, canisters per year	100 yr 1-2, 120 yr 3-12, 480 thereafter
Total Processed Quantities:	
Envelope A, MT Na	~7900
Envelope B, MT Na	~615
Envelope C, MT Na	~3800
Staging/Characterization	
Time per Tank (days)	<u>270</u>
Approximate Concentration of Retrieved DSSF, CC	<u>7 molar Na</u>
<u>LAW Retrieval Schedule—</u>	
Dates to Stage First Five Batches:	241-AN-107 (5/2005)
Batch 1	241-AN-104 (10/2006)
Batch 2	241-AN-102 (8/2007)
Batch 3	241-AN-105 (10/2008)
Batch 4	241-SY-101 (3/2010)
Batch 5	2
Number of Intermediate Feed Staging Tanks	1
Number of LAW Contractors	1
Number of Vendor Feed Tanks	0
Pretreated NCAW Receipt Tank	1
Entrained Solid Receipt Tanks	
<u>Phase 2 Privatization Processing</u>	
Contract Award	2005
LAW Operations (latest completion by agreement)	2011 –2028+
HLW Operations (latest completion by agreement)	2011-2028+
Number of HLW Return Tanks	3
Includes New Evaporator	Yes
Processing Rates @ 60% Total Operating Efficiency	
ILAW (units per year)	2200 (~60 MT ILAW/day)
IHLW (canisters per year)	480 (~6 MT IHLW/day)

Table E-1. Assumption Matrix for Test Case 2--Project Planning. (5 sheets)

Assumption Category		Assumptions	
<u>In-Tank Washing</u>			
In-tank Washing of NCAW		No	
Consolidation of NCAW Solids		No	
DSSF	= Double-shell slurry feed	LAW	= Low-activity waste
DST	= Double-shell tank	NCAW	= Neutralized current acid waste
FY	= Fiscal year	NCRW	= Neutralized cladding removal waste
HLW	= High-level waste	OWVP	= Operational Waste Volume Projection
HTWOS	= Hanford Tank Waste Operation Simulator	SWL	= Salt well liquid
IHLW	= Immobilized high-level waste	SST	= Single-shell tank
ILAW	= Immobilized low-activity waste	TCO	= Terminal cleanout
IMUST	= Inactive miscellaneous underground storage tank	WVRF	= Waste Volume Reduction Facility

Ecology, EPA, and DOE-RL, 1996, *Hanford Federal Facility Agreement and Consent Order*, (commonly called the Tri-Party Agreement), Washington State Department of Ecology, U.S. Environmental Protection Agency, U.S. Department of Energy, Richland Operations Office, Olympia, Washington, amended periodically.

This page intentionally left blank.

APPENDIX F

TEST CASE 3 ASSUMPTIONS

This page intentionally left blank.

Table F-1. Assumption Matrix for Test Case 3--Tank Usage Optimization. (5 sheets)

Assumption Category	Assumptions
<u>Meets TPA Milestones</u>	No
<u>Facility Generations</u>	
Total Limit, Kgal/mo	~25
<u>PUREX</u>	
Yearly Rate, Kgal/yr	5
TCO Scheduled	Completed
TCO Volume, Kgal	0
Flush for TCO	---
WVRF for TCO (to DSSF)	99
<u>B Plant</u>	
TCO Scheduled	Completed
TCO Volume, Kgal	0
Flush for TCO	---
WVRF for TCO (to DSSF)	99
<u>Waste Encapsulation And Storage Facility</u>	
Monthly Rate, Kgal/mo	5 Kgal/yr (0.5 per month OWVP 1998)
Flush for Miscellaneous Waste	0%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>S Plant</u>	
Monthly Rate, Kgal/mo	2.1
Flush for Miscellaneous Waste	22%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>T Plant</u>	
Monthly Rate, Kgal/mo	1.4 to 2.7
Flush for Miscellaneous Waste	22%
WVRF, Miscellaneous Waste (to DSSF)	99
<u>300 Area</u>	
Monthly Rate, Kgal/mo	4.2
Flush for Miscellaneous Waste	44%
WVRF, Miscellaneous Waste (to DSSF)	94
<u>400 Area</u>	
Rate, Kgal-every 3 rd yr	7 (1999)
Flush for Miscellaneous Waste	44%
WVRF, Miscellaneous Waste (to DSSF)	94
<u>WCSF</u>	
Monthly Rate, Kgal/mo	0.0
<u>Tank Farms</u>	
Monthly Rate, Kgal/mo	10
WVRF, Flushes (to DSSF)	99
<u>IMUST Wastes</u>	
Total Volume, Kgal (2011-2015)	500

Table F-1. Assumption Matrix for Test Case 3--Tank Usage Optimization. (5 sheets)

Assumption Category	Assumptions
<u>100 Area</u>	
100-N	
TCO Scheduled	Completed

100-K Basin Cleanout	
TCO Scheduled	2004-2005
TCO Volume, Kgal	430
Volume of Solids Included	98

105-F and 105-H Basins	
TCO Waste in 2000, Kgal	40
TCO Waste in 2005, Kgal	200

Flush, ALL 100 Area Waste	44%
WVRF, ALL TCO Waste (to DSSF)	Not used in HTWOS (99 in OWVP 1998)
<u>Tank 107-AN Caustic Addition</u>	
Addition in FY 2000, Kgal	0 (66 in OWVP 1998)
<u>SWL Pumping</u>	
Volume Remaining, Mgal	5
Volume to be Pumped in 1999	1
West Area Receiver	Tank 241-SY-102
Start Complexed SWL in 200 West Area	2000 (241-U-103) (2002 in OWVP 1998)
Pumping Completion, FY	8/2003 Early Finish (2004 in OWVP 1998)
Dilute Complexed SWL, Mgal	~1 (1.64 in OWVP 1998)
Porosity Saltcake/Sludge	Not used in HTWOS (50%/21% in OWVP 1998)
Flush for SWL Pumping	0% (28% in OWVP 1998)
WVRF, Noncomplexed (to DSSF)	Not used in HTWOS (47 in OWVP 1998)
WVRF, Complexed (to DSSF)	Not used in HTWOS (10 in OWVP 1998)
<u>SST Solids</u>	
Tank 106-C Retrieval	In Progress
Tank 104-C Retrieval	9/2009 (3/2005 in OWVP 1998)
Number of Tanks to Store 106-C Solids	1
Start Remaining SST Retrieval	7/2008 (241-C-107)
Tank Farm Closure Start	8/2017 (AX)
Approximate Dilution Ratio	(3:1 in OWVP 1998)
Meets Tri-Party Agreement Milestones	No
Number of SSTs Retrieved	149 by 2026
Sludge Retrieved, Mgal	12.2
Saltcake Retrieved, Mgal	23.4
<u>Plutonium Finishing Plant Stabilization</u>	
Dates	1999-2012
Volume, Kgal	33 (27 in OWVP 1998)
Flush	22%
WVRF	81

Table F-1. Assumption Matrix for Test Case 3--Tank Usage Optimization. (5 sheets)

Assumption Category	Assumptions
<u>Evaporator</u>	
242A Shutdown	2011
New Evaporator (Privatize)	2011
Next Outage Date	2004 (1 year)
Training Volume, Kgal (bi-yearly)	50
Average Evaporation Rate, Kgal/mo	500
Maximum Boil-off Rate, gal/min	50
Evaporation Product	dilute DSSF
Evaporation Limit, g/mL	1.41
Liquid Effluent Retention Facility Capacity, (Mgal)	13
Gallons Condensate/Gallon WVR	1.20
Yearly Evaporation of DN (except for scheduled outage)	Yes
<u>Effluent Treatment Facility</u>	
Rate, Mgal/yr	50
<u>Watch List/Safety</u>	
241-SY-101 Dilution, 650 Kgal	10/1999 – 3/2000
241-SY-103 Processing Dilution	7/2010 (4/2010 in OWVP '98)
<u>Spare/Contingency Space</u>	
Spare Space, Mgal	2.28
Use 0.72 Mgal of Operational Space in 241-AW-106 As Part of Spare Space from 2000 on	Yes
Contingency Space, Mgal	None
<u>Waste Segregation/DST Solids</u>	
Total DST Solids, Mgal	5
Store DSSF on NCRW Solids	Yes
Store DSSF on NCAW Solids	Yes
Segregate Complexed Wastes	If Possible
<u>Loss of DST Space</u>	
Number of Tanks Removed from Service	None
<u>New DST Construction</u>	
Date Constructed	N/A
<u>New Cross-Site Transfer Line</u>	
New Line Operational	Yes
Old Line Operational	Yes
<u>DST Retrieval</u>	
102-SY Solids Retrieved to 200 East Area Consolidation of NCRW Solids in 103-AW And 105-AW	8/2008 (1/2008 in OWVP '98)
	No

Table F-1. Assumption Matrix for Test Case 3--Tank Usage Optimization. (5 sheets)

Assumption Category	Assumptions
<u>Phase 1B Privatization Processing</u>	
HLW Processing Start	10/2004
HLW Vitrification Start	4/2006
LAW Processing Start (Feed to 106-AP)	10/2005
LAW Vitrification Start	3/2007
Phase 1 Treatment Ends	8/2015 (extended)
Phase 1 Extension	Yes-through FY 2015
ILAW Product Rate, MT ILAW/day @ 60% TOE	3.6, 10.8 and 18, one-year steps, then 36 at 5 th year and 72 from 6 th year on
IHLW Rate, MT NVOL/day @ 60 % TOE ..with 32% Average Waste Oxide Loading	0.06, 0.17, and 0.288, one-year steps, then 1.15 at 6 th year and 2.3 from 7 th year on
Total Processed Quantities:	
Envelope A, MT Na	~7900
Envelope B, MT Na	~615
Envelope C, MT Na	~3800
Staging/Characterization	
Time per Tank, days	270
Approximate Concentration of Retrieved DSSF, CC	7 molar Na
LAW Retrieval Schedule—	
Dates to Stage First Five Batches:	
Batch 0	Pretreated LAW (Vendor Tank)
Batch 1	241-AN-107 (4/2005)
Batch 2	241-AN-104 (8/2007)
Batch 3	241-AN-102 (10/2009)
Batch 4	241-AN-105 (4/2010)
Batch 5	241-SY-101 (6/2011)
Number of Intermediate Feed Staging Tanks	2
Number of LAW Contractors	1
Number of Vendor Feed Tanks	1
Pretreated NCAW Receipt Tank	0
Entrained. Solid Receipt Tanks	1
<u>Phase 2 Privatization Processing</u>	
Contract Award	2005
LAW Operations (processing extends past 2028)	2011-2028+
HLW Operations (processing extends past 2028)	2011-2028+
Number of HLW Return Tanks	3
Includes New Evaporator	Yes
Processing Rates @ 60 % TOE	
LAW, MT Na/day @ 20 % Avg. NaO ₂ Loading	6.02
HLW, MT IHLW/day @ 32 % Waste Oxide Loading	7.2

Table F-1. Assumption Matrix for Test Case 3--Tank Usage Optimization. (5 sheets)

Assumption Category		Assumptions	
<u>In-Tank Washing</u>			
In-tank Washing of NCAW		No	
Consolidation of NCAW Solids		No	
DSSF	= Double-shell slurry feed	LAW	= Low-activity waste
DST	= Double-shell tank	NCAW	= Neutralized current acid waste
FY	= Fiscal year	NCRW	= Neutralized cladding removal waste
HLW	= High-level waste	OWVP	= Operational Waste Volume Projection
HTWOS	= Hanford Tank Waste Operation Simulator	SWL	= Salt well liquid
IHLW	= Immobilized high-level waste	SST	= Single-shell tank
ILAW	= Immobilized low-activity waste	TCO	= Terminal cleanout
IMUST	= Inactive miscellaneous underground storage tank	TOE	= Total Operating Efficiency
		WVRF	= Waste Volume Reduction Facility

Ecology, EPA, and DOE-RL, 1996, *Hanford Federal Facility Agreement and Consent Order*, (commonly called the Tri-Party Agreement), Washington State Department of Ecology, U.S. Environmental Protection Agency, U.S. Department of Energy, Richland Operations Office, Olympia, Washington, amended periodically.

This page intentionally left blank.

APPENDIX G

TEST CASE 1--PROJECTION ACCEPTANCE CRITERIA

This page intentionally left blank.

ACCEPTANCE CRITERIA ISSUES

This is known as the Tri-Party Agreement- (TPA-) compliant case. The primary purpose of this Test Case is to assess the closeness of the Hanford Tank Waste Operation Simulator (HTWOS) and Operational Waste Volume Projection (OWVP) models' double-shell tank (DST) Requirements predictions at the end of fiscal year (FY) 2018 when all single-shell tanks (SSTs) are retrieved. At this point, the demand on DST storage reaches its peak. Because the high-level waste and low-activity waste vitrification plant capacities are not sufficient to keep pace with the required SST retrieval rate, the retrieved SST solids are stored in expanded DST storage capacity.

The predicted differences between HTWOS and historical OWVP are most pronounced for this Test Case that assumes expanded DST storage can be made available as needed for retrieval of entrained SST solids. To avoid conflicts with Phase 1 logic, HTWOS will not make the spare DSTs available for solids storage until 2013. Also HTWOS will limit the maximum number of retrieval machines to 16 and will not necessarily distribute them optimally to the various farms. Also, the category logic that normally constrains the SST retrieval sequence will be disabled to allow the accelerated rates needed for retrieval completion by 2018. These actions are expected to provide SST retrieval completion in 2017 or 2018. The process will not be fine-tuned any further.

Since OWVP uses a relatively manual approach to calculating SST solids retrieval based on aggregates, the retrieval rates are better matched to actual completion at the end of FY 2018. Also, OWVP begins expanded DST storage for SST retrieval in 2007, with a surge in storage expansion rate in 2011.

ACCEPTANCE CRITERIA

Nonetheless, there should be good general agreement between the volume projections (with HTWOS possibly completing early). Comparing the HTWOS results with those of the OWVP model, the peak DST Requirements shall agree within 10% (even 5% may be a reasonable expectation). Likewise, the peak DST waste inventories shall agree within 5%.

This page intentionally left blank.

APPENDIX H

TEST CASE 2--PROJECTION ACCEPTANCE CRITERIA

This page intentionally left blank.

ACCEPTANCE CRITERIA ISSUES

The predicted agreement between Hanford Tank Waste Operation Simulator (HTWOS) and historical Operational Waste Volume Projection (OWVP) for Test Case 2 (Project Planning) is within a double-shell tank (DST) particularly at critical or limiting time windows. HTWOS is expected to predict a slightly lower DST capacity requirement than the OWVP model because of better scheduling of generated waste receipts and better time resolution. Peak tank demands should occur no more than six months apart. The divergence is expected to increase slowly after about 2012 because of the more crude modeling of vitrification plant operation used in the historical OWVP.

ACCEPTANCE CRITERIA

The difference between HTWOS and historical OWVP for Test Case 2 (Project Planning) shall be within one DST on the average. Peak DST Requirements shall agree within one DST. Peak DST Requirements shall occur no more than a year apart. The root mean square difference in DST Requirement over the entire interval will not exceed three tanks. The average inventory difference shall not exceed one million gallons.

This page intentionally left blank.

APPENDIX I

TEST CASE 3--PROJECTION ACCEPTANCE CRITERIA

This page intentionally left blank.

ACCEPTANCE CRITERIA ISSUES

The predicted agreement between Hanford Tank Waste Operation Simulator (HTWOS) and historical Operational Waste Volume Projection (OWVP) for Test Case 3 (Tank Usage Optimization) is within a double-shell tank (DST) particularly at critical or limiting time windows. Peak tank demands should occur no more than six months apart. A shortened interval of comparison is used for Test Case 3 (Tank Usage Optimization) because the OWVP model retrieves single-shell tanks at a higher rate after 2010 and adds DST storage capacity. HTWOS is operated within the 28 DST limit. During this interval, HTWOS is expected to predict a slightly lower DST capacity requirement because of better scheduling of generated waste receipts and better time resolution. The divergence is expected to increase slowly after about 2012 because of the more crude modeling of vitrification plant operation used in the historical OWVP.

ACCEPTANCE CRITERIA

For the interval from fiscal years 1998 through 2010, the difference between HTWOS and historical OWVP for Test Case 3 (Alternative HLW Tanks) shall be within one DST on the average. Peak DST Requirements shall agree within one DST. Peak DST Requirements shall occur no more than a year apart. The root mean square difference in DST Requirement over the entire interval will not exceed three tanks. The average inventory difference shall not exceed one million gallons.

This page intentionally left blank.

APPENDIX J

TEST PHASE ANOMALY REPORT

This page intentionally left blank.

Table J-1 Test Phase Anomaly Report. (5 sheets)

Rqmt. Phase Anomaly Number	Test. Phase Procedure Section And Step Or Item	Anomaly Description	Date Found	Disposition	Closeout Date
1	5.4, Step 5 (Test Case 2)	Simulation would not complete the required waste work off sequences with the operational constraints active.	7/26/99	Operational constraints were added individually and consequences assessed. Additional tank reassignments were made as needed. Nine additional procedures were defined or modified to accommodate the operational constraints defined during Requirements Phase testing.	7/30/99
2	5.4, Step 5 (Test Case 2)	DSTs will not resume their assigned functions after an operational constraint (lockout) has expired.	6/26/99	Underlying logic for locks must be corrected. Programming initiated on 7/27/99. Logic for resumed operation after lockout was corrected.	7/28/99
3	5.4, Step 5 (Test Case 2)	Grid lock occurred because AN-101 became full and salt well liquid pumping could not continue per schedule.	7/29/99	Operations has planned a cascade from 101-AN to 106-AN to deal with project imposed lockout on 101-AN transfers to 102-AW. Procedure as added to implement this cascade operation in HTWOS. A special lockout was created that allows a tank to receive waste but not transfer out until the lockout is expired.	7/29/99
4	5.4, Step 5 (Test Case 2)	Sequencing problems occurred with corrected start of 106-C retrieval.	7/29/99	Adjust sluice material (102-AY) timing to 15 days before 106-C start (as before).	7/29/99

Table J-1 Test Phase Anomaly Report. (5 sheets)

Rqmt. Phase Anomaly Number	Test. Phase Procedure Section And Step Or Item	Anomaly Description	Date Found	Disposition	Closeout Date
5	5.4, Step 5 (Test Case 2)	Experienced three anomalous shutdowns of Telewindows™ during Test Case 2 Run. Restarted Telewindows™ and determined that underlying model was still running on UNIX server and Telewindows™ resumed its proper function.	7/30/99	Run Telewindows™ with all other tasks off. Restart Telewindows™ as necessary during a run. Investigate ways to make operation more stable.	8/3/99
6	5.4, Step 5 (Test Case 2)	Graphs of evaporator operations by month show the 3-mo (minimum) down time between campaigns as level sections on ramping volumes. Feed can accumulate to more than 5 Mgal. Condensate can accumulate to nearly 2 Mgal. The graphs are difficult to interpret.	8/2/99	HTWOS programming staff indicated that evaporator plots represent one year accumulations specified by HTWOS requirements.	8/3/99
7	5.4, Step 7 (Test Case 2)	The Phase 1 allocated tanks take all available DST space (less total waste and flammable gas allocated) from October 1998 to October 2007. The 2.3 Mgal reserve is violated.	8/3/99	HTWOS programming staff indicated that the Available DST Space plotting procedure was unchanged and functioning properly. An outdated accounting procedure was discovered and replaced with the newer, corrected procedure.	8/12/99
8	5.4, Step 7 (Test Case 2)	HTWOS initial volume inventory (10/1/1998) is 1.1 Mgal high. AN-106 and AP-107 are 0.4 Mgal. high; AW-102 and SY-102 are 0.5 Mgal. Low; AW-106 is 0.25 Mgal. low; and AY-101 is 0.75 Mgal. high.	8/4/99	Near-term transfers and evaporations which adjust the Best Basis Inventory to the HTWOS start date (10/1/1998) shall be updated to correct the HTWOS initial volume inventory.	9/7/99

Table J-1 Test Phase Anomaly Report. (5 sheets)

Rqmt. Phase Anomaly Number	Test Phase Procedure Section And Step Or Item	Anomaly Description	Date Found	Disposition	Closeout Date
9	5.4, Step 5 (Test Case 1)	Telewindows™ would not connect to HTWOS for set up of next Test Case. Support staff on hand could not reestablish connection as master workstation will not accept passwords of other UNIX network users.	8/9/99	Telewindows™ was made operational by lead member of HTWOS support staff who returned from week's vacation. Verbal instructions were given regarding use of TW directory for restarting Telewindows™ applications.	8/17/99
10	5.4, Step 5 (Test Case 1)	No menu item is provided to view or save SPARE DST volume history. Spare Utilization (annual tank depth graphic) provides minimum functionality.	8/10/99	In Administrator Mode, SPARE Utilization may be selected. This provides the annual volume on a tank graphic for each SPARE. The values from the graphic may be printed to file.	8/12/99
11	5.4, Step 5 (Test Case 1)	No procedure is in place that allows HTWOS server operability to be reestablished in the absence of the HTWOS administrator. This resulted in one week outage.	8/11/99	Related to item 9. The user requested that the administrator have a notebook defining procedures for restarting Telewindows™ applications and for remounting disks (in the UNIX network) to allow logging in at alternate workstations.	8/17/99
12	5.4, Step 3 (Test Case 1)	The case definition states that four additional (spare) DSTs are used for SST retrieval staging. The first two spares were found to be used for Phase 1 LAW processing facility operations.	8/10/99	SPARE-103 and SPARE-104 were available for Test Case 1 SST retrieval staging. SPARE-104 was assigned a 10 Mgal capacity to approximate the behavior of multiple tanks.	8/10/99
13	5.4, Step 5 (Test Case 1)	The process for making use of SPARE DST for SST retrieval staging is complex because of interference with Phase 1 operations and no procedure is provided for using these SPARE DSTs.	8/11/99	SPARE DSTs will be setup for SST retrieval staging and normally be locked out. The lockouts are cleared for cases exploring use of additional DSTs.	8/17/99

Table J-1 Test Phase Anomaly Report. (5 sheets)

Rqmt. Phase Anomaly Number	Test. Phase Procedure Section And Step Or Item	Anomaly Description	Date Found	Disposition	Closeout Date
14	5.4, Step 5 (Test Case 1)	Tank lockouts do not function on Phase 2 Logic diagram. SPARE-103 and SPARE-104 were set for lockout to 2012 but were previously filled.	8/11/99	A manually entered procedure is used to control the behavior of the SPARE DSTs.	8/11/99
15	5.4, Step 7 (Test Case 1)	HTWOS has no procedure to compute "DST Requirements" as defined for OWVP. A DST is required during a given fiscal year if its contents exceed 50 Kgal.	8/16/99	In comparisons of DST Requirements, the Waste Inventory portion will use a 95% storage efficiency. Also, a procedure will be added to HTWOS to implement the DST Requirement definition.	8/17/99
16	5.4, Step 9 (Test Case 1)	SWL entering a DST is not credited as DN or DC in the waste type inventories. AN-101 is an example where neither entering DN nor DC SWL is credited to the waste type inventories. However, the total liquid volume is properly credited.	8/17/99	The 241-AN-101 SWL waste type will be corrected to DN. The DST waste type calculation will be corrected to account for the incoming (source) wastes by waste type.	8/17/99
17	5.4, Step 5 (Test Case 3)	No Phase 1 "Show/edit ramp process rate" is provided for HLW.	8/19/99	Use Administrator Mode and edit HLW Vitrification Plant code of LAW Logic diagram. The "Show/edit" logic for HLW is to be added in September 1999.	8/19/99

Table J-1 Test Phase Anomaly Report. (5 sheets)

Rqmt. Phase Anomaly Number	Test Phase Procedure Section And Step Or Item	Anomaly Description	Date Found	Disposition	Closeout Date
18	5.4, Step 5 (Test Case 3)	No explanatory comments are provided in HLW ramp-up code; can not print or save edits to code from Telewindows™.	8/19/99	Editing code is a temporary user activity; the show/edit procedure is to replace user interaction with underlying code. Plans call for providing print capability from Telewindows™ by September 1999.	8/23/99

DST = Double-shell tank
 HLW = High-level waste
 HTWOS = Hanford Tank Waste Operation Simulator
 LAW = Low-activity waste
 OWVP = Operational Waste Volume Projection
 SWL = Salt well liquid
 SST = Single-shell tank

This page intentionally left blank.

DISTRIBUTION SHEET

To	From	Page 1 of 1
Distribution	R. W. Harmsen	Date 09/22/99
Project Title/Work Order		EDT No. 627137
Hanford Tank Waste Operation Simulator OWVP V&V Procedure, HNF-3719, Revision 0		ECN No. N/A

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
LMHC Correspondence Control	H7-09	X			
DOE Reading Room	H2-53	X			
G. K. Allen	R3-73	X			
H. L. Boston	H6-64	X			
V. C. Boyles	R2-11	X			
P. J. Certa	R3-73	X			
A. F. Choho	R3-73	X			
J. S. Garfield	R3-73	X			
C. E. Grenard	R3-74	X			
R. W. Harmsen (10)	R3-75	X			
K. M. Hodgson	R2-11	X			
T. M. Hoh1	R3-73	X			
J. Jo	R2-12	X			
R. A. Kirkbride (5)	R3-73	X			
G. M. Koreski	R2-11	X			
D. L. Penwell	R3-73	X			
C. DeFigh-Price	R2-12	X			
J. N. Strode (3)	R2-11	X			
D. J. Washenfelder	G1-27	X			
R. S. Wittman	R3-73	X			