RECORD OF TECHNICAL CHANGE

Technical Change No. CADD-1

Page 1 of 1

Project/Job No. DP04-010

Date 07/28/2005

Project/Job Name Corrective Action Decision Document for CAU 322: Areas 1 and 3 Release Sites and Injection Wells, Nevada Test Site, Nevada

The following technical changes (including justification) are requested by:

Robert Boehlecke
(Name)

Industrial Sites Program Manager
(Title)

Description of Change:

1. **Executive Summary.** On page ES-2, replace the 3rd bullet item under "Closure in Place with Administrative Controls" with the following:
 - "CAS 03-20-05, TPH-DRO, metals and radiological contamination are present in the injection well casing soils. Recommend corrective action includes solidification of the liquid in the injection well sump (approximately 3 feet [ft] of liquid at 60 ft below ground surface), grouting the sump, removing the upper two ft of soil within the injection well casing, and backfilling the area within the injection well casing to ground level."
2. **Section 3.3.3.3 CAS 03-20-05, Injection Wells.** Beginning with the 5th sentence in item f, replace the remainder of the paragraph with the following:
 - "Removal of at least the upper two feet of contaminated soil followed by backfilling the excavated area to surface grade will eliminate the need to provide an impervious cap to the immediate area. Removal of the radiological and metals contaminated soils from the injection well casing to a depth of two feet requires the removal of approximately 4 yd³ of soil."

Modify the first bullet with the following:

 - "Removal and disposal of approximately 4 yd³ of soil contaminated with metals, PCBs, radionuclides, and TPH-DRO, from the injection well vault and backfill to grade."
3. **Section 4.0 Recommended Alternatives.** Replace the 1st bullet in the "CAS 03-20-05, Injection Wells" section with the following:
 - "Removal of the higher toxicity soil associated with the lead, TCLP cadmium, Aroclor-1254, Am-241, Pu-239, and Cs-137, and higher levels of TPH-DRO contamination within the injection well vault (represented by sample locations C06 and C07) to a depth of at least 2 ft, followed by backfilling the void created from the removed soil"

Modify the bullet stating "Grout the injection well sump" to read the following:

 - "Solidify the liquid (approximately 3 ft in depth located approximately 60 ft bgs) in the injection well and grout the injection well sump"
4. **Section E.1.2.** Replace the 4th paragraph with the following:
 - "At CAS 03-20-05 the TPH contamination above PALs that will remain in place will be at depths greater than 2 ft bgs. The soils above this depth will be removed and will result in the removal of the high concentrations of lead, PCBs, and radiological contamination as well as that for TPH-DRO. The remaining contamination is not considered a potential impact to groundwater because of the limited precipitation and large evapotranspiration associated with the desert climates. In addition to the removal of the surface contamination and the initiation of the use of a use restriction at this CAS, the well will be grouted and sealed which will further limit the exposure routes for the residual contamination."

Justification:

The depth of the soil contamination in the injection well casing to be managed using Best Management Practices resides in the upper two feet of the soil. Removal of this upper two feet of soil satisfies the intent of the Best Management Practices. Removal of additional soil is impractical considering the physical dimensions of the injection well casing and the potential hazards associated with attempting removal of deeper material.

Because the liquid located at the bottom of the injection well sump contains no COCs, solidification of the liquid prior to grouting the sump is a better management practice than removing the liquid before grouting the sump.

The project time will be unchanged.

Applicable Project-Specific Document(s): Corrective Action Decision Document for CAU 322: Areas 1 and 3 Release Sites and Injection Wells, Nevada Test Site, Nevada Nevada Test Site, Nevada Rev. 0, December 2004

Approved By:

Lebini Curtis
NNSA/NSO Project Manager

Date 6/7/05

Janet Spiegler-Wj
NNSA/NSO Environmental Restoration Division Director

Date 6/7/05

Don Cole
NDEP

Date 6/13/05

Nevada
Environmental
Restoration
Project

DOE/NV-1023

Corrective Action Decision Document for Corrective Action Unit 322: Areas 1 and 3 Release Sites and Injection Wells Nevada Test Site, Nevada

Controlled Copy No.: ____

Revision No.: 0

December 2004

Approved for public release; further dissemination unlimited.

Environmental Restoration
Division

U.S. Department of Energy
National Nuclear Security Administration
Nevada Site Office

Uncontrolled When Printed

Available for public sale, in paper, from:

U.S. Department of Commerce
National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161
Phone: 800.553.6847
Fax: 703.605.6900
Email: orders@ntis.gov
Online ordering: <http://www.ntis.gov/ordering.htm>

Available electronically at <http://www.osti.gov/bridge>

Available for a processing fee to U.S. Department of Energy and its contractors,
in paper, from:

U.S. Department of Energy
Office of Scientific and Technical Information
P.O. Box 62
Oak Ridge, TN 37831-0062
Phone: 865.576.8401
Fax: 865.576.5728
Email: reports@adonis.osti.gov

Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

**CORRECTIVE ACTION DECISION DOCUMENT
FOR CORRECTIVE ACTION UNIT 322: AREAS 1 AND 3
RELEASE SITES AND INJECTION WELLS
NEVADA TEST SITE, NEVADA**

U.S. Department of Energy
National Nuclear Security Administration
Nevada Site Office
Las Vegas, Nevada

Controlled Copy No.: ____

Revision No.: 0

December 2004

Approved for public release; further dissemination unlimited.

Uncontrolled When Printed

**CORRECTIVE ACTION DECISION DOCUMENT
FOR CORRECTIVE ACTION UNIT 322: AREAS 1 AND 3
RELEASE SITES AND INJECTION WELLS
NEVADA TEST SITE, NEVADA**

Approved by: Signature Approved Date: 11/29/04
Janet Appenzeller-Wing, Project Manager
Industrial Sites Project

Approved by: Signature Approved Date: 11/29/04
Robert M. Bangerter, Acting Division Director
Environmental Restoration Division

Table of Contents

List of Figures	vii
List of Tables	viii
List of Acronyms and Abbreviations	xi
Executive Summary	ES-1
1.0 Introduction	1
1.1 Purpose	1
1.2 Scope	5
1.3 Corrective Action Decision Document Contents	5
2.0 Corrective Action Investigation Summary	8
2.1 Investigation Activities	8
2.1.1 CAS 01-25-01, AST Release	10
2.1.2 CAS 03-25-03, Mud Plant and AST Diesel Release	11
2.1.2.1 CAS 03-25-03, Area A, AST Release	11
2.1.2.2 CAS 03-25-03, Area B, Mud Plant	11
2.1.3 CAS 03-20-05, Injection Wells	11
2.2 Results	12
2.2.1 Summary of Characterization Data	12
2.2.1.1 CAS 01-25-01, AST Release	13
2.2.1.2 CAS 03-25-03, Mud Plant and AST Diesel Release	14
2.2.1.2.1 Area A	14
2.2.1.2.2 Area B	15
2.2.1.3 CAS 03-20-05, Injection Wells	15
2.2.2 Data Assessment Summary	18
2.3 Need for Corrective Action	19
2.3.1 CAS 01-25-01, AST Release	20
2.3.2 CAS 03-25-03, Mud Plant and AST Diesel Release	20
2.3.2.1 CAS 03-25-03, Area A, AST Release	20
2.3.2.2 CAS 03-25-03, Area B, Mud Plant	20
2.3.3 CAS 03-20-05, Injection Wells	21
3.0 Evaluation of Alternatives	22
3.1 Corrective Action Objectives	22
3.2 Screening Criteria	23
3.2.1 Corrective Action Standards	23
3.2.2 Remedy Selection Decision Factors	24
3.3 Development of Corrective Action Alternatives	26
3.3.1 Alternative 1 - No Further Action	27
3.3.2 Alternative 2 - Clean Closure	27
3.3.2.1 CAS 01-25-01 AST Release	28

Table of Contents (Continued)

3.3.2.2	CAS 03-25-03 Area B, Mud Plant	28
3.3.2.3	CAS 03-20-05 Injection Wells	28
3.3.3	Alternative 3 - Close in Place with Administrative Controls	29
3.3.3.1	CAS 01-25-01, AST Release	29
3.3.3.2	CAS 03-25-03 Area B, Mud Plant	30
3.3.3.3	CAS 03-20-05, Injection Wells	32
3.4	Evaluation and Comparison of Alternatives.....	34
4.0	Recommended Alternatives	39
5.0	References.....	41

Appendix A - Corrective Action Investigation Results for CAU 322

A.1.0	Introduction.....	A-1
A.1.1	Project Objectives.....	A-2
A.1.2	Content	A-2
A.2.0	Investigation Overview	A-3
A.2.1	Preliminary Conceptual Models	A-4
A.2.2	Sample Locations	A-4
A.2.2.1	Housekeeping Removal of Debris.....	A-5
A.2.3	Investigation Activities.....	A-5
A.2.3.1	Surface Radiological Surveys	A-5
A.2.3.2	Site Walk-Over.....	A-6
A.2.3.3	Field Screening	A-6
A.2.3.4	Surface and Subsurface Sampling	A-6
A.2.3.4.1	Surface Radiological Surveys and Swiping	A-7
A.2.3.4.2	Waste Characterization and Sampling	A-7
A.2.3.4.3	Sample Location Documentation	A-8
A.2.4	Laboratory Analytical Information.....	A-8
A.2.5	Comparison to Action Levels.....	A-10
A.2.6	Geology.....	A-10
A.2.7	Hydrology.....	A-10
A.3.0	CAS 01-25-01, AST Release.....	A-12
A.3.1	Corrective Action Investigation	A-12
A.3.1.1	Deviations	A-12
A.3.2	Investigation Results.....	A-15
A.3.2.1	Radiological Survey Results	A-15
A.3.2.2	Sampling	A-15

Table of Contents (Continued)

A.3.2.3	Field Screening	A-17
A.3.2.4	Sample Analysis	A-17
A.3.2.5	Analytes Detected Above Minimum Reporting Limits	A-17
A.3.2.5.1	Total VOCs	A-18
A.3.2.5.2	Total SVOCs	A-18
A.3.2.5.3	Total RCRA Metals and Beryllium	A-18
A.3.2.5.4	PCBs	A-18
A.3.2.5.5	TPH-GRO and TPH-DRO	A-19
A.3.2.5.6	Gamma-Emitting Radionuclides	A-19
A.3.2.6	Contaminants of Concern	A-20
A.3.3	Nature and Extent of Contamination	A-20
A.3.4	Revised Conceptual Site Model	A-22
A.4.0	CAS 03-25-03, AST Release and Mud Plant	A-25
A.4.1	Corrective Action Investigation	A-25
A.4.1.1	Deviations	A-26
A.4.2	Investigation Results	A-26
A.4.2.1	Radiological Survey Results	A-26
A.4.2.2	Inspection and Sampling	A-30
A.4.2.3	Field-Screening Results	A-35
A.4.2.4	Sample Analysis	A-35
A.4.2.5	Analytes Detected Above Minimum Reporting Limits	A-35
A.4.2.5.1	Total VOCs	A-36
A.4.2.5.2	Total SVOCs	A-36
A.4.2.5.3	PCBs	A-37
A.4.2.5.4	Total RCRA Metals and Beryllium	A-37
A.4.2.5.5	TPH (DRO/GRO)	A-37
A.4.2.5.6	Gamma-Emitting Isotopes	A-44
A.4.2.5.7	Strontium-90	A-46
A.4.2.5.8	Plutonium	A-46
A.4.2.5.9	Uranium	A-46
A.4.2.6	Contaminants of Concern	A-52
A.4.3	Nature and Extent of Contamination	A-52
A.4.4	Revised Conceptual Site Model	A-53
A.5.0	CAS 03-20-05, Injection Well	A-54
A.5.1	Corrective Action Investigation	A-54
A.5.1.1	Deviations	A-54
A.5.2	Investigation Results	A-54
A.5.2.1	Radiological Survey Results	A-59
A.5.2.2	Inspection and Sampling	A-63

Table of Contents *(Continued)*

A.5.2.3	Field-Screening Results	A-64
A.5.2.4	Sample Analysis	A-64
A.5.2.5	Analytes Detected Above Minimum Reporting Limits	A-64
A.5.2.5.1	Total VOCs	A-65
A.5.2.5.2	Total SVOCs	A-65
A.5.2.5.3	Total RCRA Metals and Beryllium	A-65
A.5.2.5.4	PCBs	A-66
A.5.2.5.5	TPH	A-66
A.5.2.5.6	Gamma-Emitting Radionuclides	A-74
A.5.2.5.7	Plutonium	A-81
A.5.2.5.8	Strontium-90	A-82
A.5.2.5.9	Uranium	A-82
A.5.2.6	Contaminants of Concern	A-82
A.5.3	Nature and Extent of Contamination	A-90
A.5.4	Revised Conceptual Site Model	A-91
A.6.0	Waste Management.	A-92
A.6.1	Characterization	A-93
A.6.2	Waste Streams.	A-93
A.6.3	Investigation-derived Waste Generated	A-93
A.6.4	Waste Characterization Samples	A-94
A.6.5	Additional Analytical Results Collected For Remediation	
	Waste Characterization.	A-94
A.6.5.1	Results for Liquid and Oil Samples.	A-94
A.6.5.2	TCLP Metals	A-97
A.7.0	Quality Assurance.	A-99
A.7.1	Data Validation	A-99
A.7.1.1	Tier I Evaluation	A-99
A.7.1.2	Tier II Evaluation.	A-100
A.7.1.3	Tier III	A-101
A.7.2	Field Quality Control Samples	A-102
A.7.2.1	Field Quality Control Samples	A-102
A.7.2.2	Laboratory Quality Control Samples.	A-103
A.7.3	Field Nonconformances	A-103
A.7.4	Laboratory Nonconformances	A-103
A.8.0	Summary.	A-104
A.9.0	References.	A-106

Table of Contents (Continued)

Appendix B - Data Assessment

B.1.0	Data Assessment	B-1
B.1.1	Precision	B-1
B.1.1.1	Precision for Chemical Analysis	B-2
B.1.1.2	Precision for Radiochemical Analysis	B-3
B.1.1.3	Precision Summary	B-8
B.1.2	Accuracy	B-8
B.1.2.1	Accuracy for Chemical Analysis	B-8
B.1.2.2	Accuracy for Radiochemical Analysis	B-11
B.1.2.3	Accuracy Summary	B-14
B.1.3	Completeness	B-14
B.1.3.1	Completeness Summary	B-16
B.1.4	Rejected Data	B-16
B.1.5	Representativeness	B-30
B.1.6	Comparability	B-30
B.1.7	Reconciliation of Conceptual Site Models to the Data.	B-30
B.1.7.1	Conceptual Site Models	B-30
B.1.7.1.1	Leakage or Spilling from ASTs and Associated Processes Conceptual Site Model	B-31
B.1.7.1.2	Injection Wells and Associated Soils Conceptual Site Model	B-31
B.1.7.2	Contaminant Nature and Extent.	B-32
B.1.8	Conclusions	B-32
B.2.0	References	B-33

Appendix C - Cost Estimates for CAU 322

Appendix D - Sample Location Coordinates for CAU 322: Release Sites and Injection Wells Nevada Test Site, Nevada

D.1.0	Sample Location Coordinates	D-1
D.1.1	CAS 01-25-01, AST	D-1
D.1.2	CAS 03-20-03, AST and Mud Plant	D-1
D.1.3	CAS 03-20-05, Injection Wells	D-1

Appendix E - Evaluation of Risk

E.1.0	Evaluation of Risk	E-1
-------	--------------------------	-----

Table of Contents (Continued)

E.1.1	Human Health Screening	E-1
E.1.2	Risk Evaluation.....	E-2
E.1.3	Uncertainty Analysis.....	E-4
E.1.4	Interpretation.....	E-5
E.2.0	References.....	E-6

Appendix F - Project Organization for CAU 322

F.1.0	Project Organization.....	F-1
-------	---------------------------	-----

Appendix G - Nevada Division of Environmental Protection Comments

List of Figures

<i>Number</i>	<i>Title</i>	<i>Page</i>
1-1	Nevada Test Site Location Map	2
1-2	CAU 322 CAS Location Map	3
A.3-1	Sample Location Map, CAS 01-25-01, AST Berm	A-14
A.3-2	Radiological Survey Map for CAS 01-25-01, AST Berm	A-16
A.3-3	Vertical Profile of TPH-DRO Concentrations for CAS 01-25-01, AST Berm	A-21
A.3-4	TPH-DRO Data Regression Plot for CAS 01-25-01, AST Berm	A-23
A.4-1	Sample Location Map for CAS 03-25-03, AST Release Area A, AST Berm	A-31
A.4-2	Sample Location Map for CAS 03-25-03, AST Release Area B, Mud Plant	A-32
A.4-3	Radiological Survey Map for CAS 03-25-03, AST Release	A-34
A.4-4	Plan View Plot of TPH-DRO Hits above PALs at CAS 03-25-03, AST Release, Site B (East Side of Mud Plant).	A-47
A.4-5	Vertical Cross Section of TPH-DRO Concentrations at CAS 03-25-03, AST Release, Site B (East Side of Mud Plant).	A-48
A.5-1	Soil Sample Location Map for CAS 03-20-05, Injection Wells	A-60
A.5-2	Sample Locations for Tanks and Sumps at CAS 03-20-05, Injection Wells	A-61
A.5-3	Radiological Survey Map for CAS 03-20-05, Injection Wells	A-62
A.5-4	Profile of Injection Well Sump and Vault with Analytical Results	A-75

List of Tables

<i>Number</i>	<i>Title</i>	<i>Page</i>
1-1	Corrective Action Unit 322 Corrective Action Sites	1
3-1	Corrective Action Alternatives Evaluated for CAU 322	27
3-2	Detailed Evaluation of Alternatives for Corrective Action Unit 322.	35
3-3	Comparative Evaluation of Alternatives for Corrective Action Unit 322	38
A.2-1	Corrective Action Investigation Activities Conducted at Each Corrective Action Site to Meet Corrective Action Investigation Plan Requirements	A-3
A.2-2	Laboratory Analytical Parameters and Methods, CAU 322 Investigation Samples	A-9
A.3-1	Samples Collected at CAS 01-25-01, AST	A-13
A.3-2	Soil Sample Results for Total VOCs Detected Above Minimum Reporting Limits at CAS 01-25-01, AST	A-18
A.3-3	Soil Sample Results for Metals Detected Above Minimum Reporting Limits at CAS 01-25-01, AST.	A-19
A.3-4	Soil Sample Results for TPH (DRO and GRO) Detected Above Minimum Reporting Limits at CAS 01-25-01, AST.	A-20
A.3-5	Soil Sample Results for Gamma-Emitting Radionuclides Detected Above Minimum Detectable Concentrations at CAS 01-25-01, AST.	A-22
A.4-1	Samples Collected at CAS 03-25-03, AST and Mud Plant	A-27
A.4-2	Samples Collected During the CAU 34 CAI at CAS 03-25-03, Area B (East of Mud Plant)	A-33
A.4-3	Soil Sample Results for Total VOCs Detected Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release	A-36

List of Tables (Continued)

Number	Title	Page
A.4-4	Soil Sample Result for Total SVOCs Detected Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release	A-36
A.4-5	Soil Sample Results for PCBs Detected Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release	A-37
A.4-6	Soil Sample Results for Metals Detected Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release	A-38
A.4-7	Soil Sample Results for TPH (DRO and GRO) Detected Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release	A-43
A.4-8	Vertical Bounding of TPH-DRO at Area B	A-45
A.4-9	Soil Sample Results for Gamma-Emitting Radionuclides Detected Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release	A-49
A.4-10	Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release	A-51
A.5-1	Samples Collected at CAS 03-20-05, Injection Well.	A-55
A.5-2	Soil Sample Results for Total VOCs Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well	A-65
A.5-3	Soil Sample Results for Total SVOCs Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well	A-66
A.5-4	Soil Sample Results for Metals Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well	A-67
A.5-5	Soil Sample Results for PCBs Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well	A-72
A.5-6	Soil Sample Results for TPH-DRO Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well	A-73

List of Tables (Continued)

Number	Title	Page
A.5-7	Soil Sample Results for Gamma-Emitting Radionuclides Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well	A-76
A.5-8	Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well	A-83
A.6-1	Liquid and Oil Samples Collected at CAS 03-20-05, Injection Well	A-94
A.6-2	Soil Samples for TCLP Metals Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well	A-98
B.1-1	Chemical Precision Measurements for CAU 322	B-4
B.1-2	Radiological Precision Measurements for CAU 322	B-6
B.1-3	Chemical Accuracy Measurements for CAU 322	B-9
B.1-4	Radiological Accuracy Measurements for CAU 322	B-12
B.1-5	Chemical Completeness Measurements for CAU 322	B-14
B.1-6	Radiological Completeness Measurements for CAU 322	B-15
B.1-7	CAU 322 Rejected Data at CAS 01-25-01, AST	B-17
B.1-8	CAU 322 Rejected Data at CAS 03-25-03, Mud Plant AST Diesel Release. . .	B-18
B.1-9	CAU 322 Rejected Data at CAS 03-20-05, Injection Well	B-21
D.1-1	Sample Location GPS Coordinates for CAS 01-25-01	D-1
D.1-2	Sample Location GPS Coordinates for CAS 03-25-03	D-2
D.1-3	Sample Location GPS Coordinates for CAS 03-20-05	D-3

List of Acronyms and Abbreviations

AL	Action level
Am	Americium
AR/COC	Analysis requests/chain-of-custody
AST	Aboveground storage tank
bgs	Below ground surface
BOP	Blowout Preventer
CADD	Corrective Action Decision Document
CAI	Corrective Action Investigation
CAIP	Corrective Action Investigation Plan
CAS	Corrective Action Site
CAU	Corrective Action Unit
CFR	<i>Code of Federal Regulations</i>
CLP	Contract Laboratory Program
COC	Contaminants of concern
COPC	Contaminants of potential concern
Cs	Cesium
CSM	Conceptual site models
DOE	U.S. Department of Energy
DQI	Data quality indicators
DQO	Data quality objectives
DRO	Diesel-range organics
EPA	U.S. Environmental Protection Agency
FADL	Field activity daily log
FAL	Final action level
FID	Flame ionization detector
FFACO	<i>Federal Facility Agreement and Consent Order</i>

List of Acronyms and Abbreviations (Continued)

FSL	Field-screening levels
FSR	Field-screening results
ft	Foot (feet)
ft ²	Square feet
ft ³	Cubic feet
GPS	Global positioning system
GRO	Gasoline-range organics
HWAA	Hazardous Waste Accumulation Area
IDW	Investigation-derived waste
ID	Identification number
in.	Inch
LCS	Laboratory control samples
LCSD	Laboratory control sample duplicates
LD	Laboratory duplicate
LLNL	Lawrence Livermore National Laboratory
LLW	Low-level radioactive waste
MADEP	Massachusetts Department of Environmental Protection
MDC	Minimum detectable concentration
mg/kg	Milligrams per kilogram
mg/L	Milligrams per liter
mi	Mile
MRL	Minimum reporting limit
mrem/yr	Millirem per year
MS	Matrix spike
MSD	Matrix spike duplicate
NAC	<i>Nevada Administrative Code</i>
NCRP	National Council on Radiation Protection and Measurement

List of Acronyms and Abbreviations (Continued)

ND	Normalized difference
NDEP	Nevada Division of Environmental Protection
NIST	National Institute for Standards and Technology
NNSA/NSO	U.S. Department of Energy, National Nuclear Security Administration Nevada Site Office
NTS	Nevada Test Site
NTSWAC	Nevada Test Site Waste Acceptance Criteria
PAL	Preliminary action level
PB	Preparation blanks
PCB	Polychlorinated biphenyls
POC	Performance objective criteria
PPE	Personal protective equipment
ppm	Parts per million
PRG	Preliminary Remediation Goal
Pu	Plutonium
QA	Quality assurance
QAPP	Quality Assurance Project Plan
QC	Quality control
RAGS	Risk Assessment Guidance
RCRA	<i>Resource Conservation and Recovery Act</i>
ROTC	Record of Technical Change
RPD	Relative percent difference
RWMS	Radioactive Waste Management Site
SCL	Sample collection log
SDG	Sample delivery group
SVOC	Semivolatile organic compounds
TCLP	Toxicity characteristic leaching procedure

List of Acronyms and Abbreviations (Continued)

TPH	Total petroleum hydrocarbons
VOC	Volatile organic compounds
VSP	Visual Sample Plan
yd ³	Cubic yards
µg	Microgram
%R	Percent recovery

Executive Summary

This Corrective Action Decision Document has been prepared for Corrective Action Unit (CAU) 322, Areas 1 and 3 Release Sites and Injection Wells, Nevada Test Site, Nevada, in accordance with the *Federal Facility Agreement and Consent Order* (1996). Corrective Action Unit 322 is comprised of the following corrective action sites (CASs):

- 01-25-01 - AST Release Site
- 03-25-03 - Mud Plant and AST Diesel Release*
- 03-20-05 - Injection Wells and BOP Shop

*Note: CAS 03-25-03 is presented as Areas A and B based on technical evaluations.

The purpose of this Corrective Action Decision Document is to identify and provide the rationale for the recommendation of a corrective action alternative for each CAS within CAU 322. Corrective action investigation activities were performed from April 2004 through September 2004, as set forth in the Corrective Action Investigation Plan. The purposes of the activities as defined during the data quality objectives process were:

- Determine if contaminants of concern (COCs) are present
- If COCs are present, determine their nature and extent
- Provide sufficient information and data to recommend appropriate corrective actions for the CASs.

Analytes detected during the corrective action investigation were evaluated against appropriate preliminary action levels to identify contaminants of concern for each corrective action site.

Radiological field measurements were compared to unrestricted release criteria. Assessment of the data generated from investigation activities revealed the following:

- CAS 01-25-01 contains an AST berm contaminated with total petroleum hydrocarbons (TPH) diesel-range organics (DRO).
- CAS 03-25-03 includes two distinct areas: Area A where no contamination remains from a potential spill associated with an AST, and Area B where TPH-DRO contamination associated with various activities at the mud plant was identified. The Area B contamination was found at various locations and depths.

- CAS 03-25-03 Area B contains TPH-DRO contamination at various locations and depths in the area associated with the Mud Plant.
- CAS 03-20-05 contains TPH-DRO, metals, and radiological contamination within the injection well casing soil and TPH-DRO contamination at the depth coincidental with the bottom of the injection well sump.

Based on the evaluation of analytical data from the corrective action investigation, review of future and current operations in Areas 1 and 3 of the Nevada Test Site, and the detailed and comparative analysis of the potential corrective action alternatives, the following corrective actions are recommended for the Corrective Action Unit 322 CASs.

Closure in Place with Administrative Controls is the preferred corrective action for the following CASs:

- CAS 01-25-01, removal of TPH-DRO contamination would pose a significant safety hazard due to the site location.
- CAS 03-25-03 No contamination remains at Area A (AST Berm); and thus, no further action is the preferred alternative at this part of the CAS. However at Area B, TPH-DRO contamination is varied in concentration and location and the footprint of the CAS is large, removal of contaminated “pockets” would be laborious and cost prohibitive.

The plutonium-239 surface contamination identified at CAS 03-25-03 Area B has been removed and drummed as a best management practice.

- CAS 03-20-05, TPH-DRO, metals, and radiological contamination are present in the injection well casing soils. Recommend corrective action includes removal of the liquid in the injection well sump (approximately 3 feet (ft) of liquid at 60 ft below ground surface), grouting the sump, and the area within the injection well casing.

The plutonium-239 surface contamination identified at CAS 03-20-05 has been removed and drummed as a best management practice and will be disposed of as low-level radioactive waste. It is recommended that the liquids be removed from the holding tank wells and the sumps of the two outer holding tanks within the BOP Shop, and the sumps be grouted, and the holding tanks filled in to the BOP Shop floor surface.

The preferred corrective action alternatives were evaluated on technical merit focusing on performance, reliability, feasibility, and safety. The alternatives were judged to meet all requirements

for the technical components evaluated. The alternatives meet all applicable state and federal regulations for closure of the site and will reduce potential future exposure pathways to the contaminated media at Corrective Action Unit 322.

1.0 Introduction

This Corrective Action Decision Document (CADD) has been prepared for Corrective Action Unit (CAU) 322: Areas 1 and 3 Release Sites and Injection Wells, Nevada Test Site (NTS), Nevada, in accordance with the *Federal Facility Agreement and Consent Order* (FFACO) that was agreed to by the State of Nevada, U.S. Department of Energy (DOE), and the U.S. Department of Defense (FFACO, 1996).

This CADD provides or references the specific information necessary to recommend corrective actions for the three CAU 322 corrective action sites (CASs) indicated in Table 1-1

Table 1-1
Corrective Action Unit 322 Corrective Action Sites

Nevada Test Site Area	Corrective Action Site	CAS Description ^a	Facility, Program, or Location Association ^b
Area 1	01-25-01	AST Release	Area 1 Batch Plant
Area 3	03-25-03	Mud Plant AST Diesel Release	Former Area 3 Mud Plant
	03-20-05	Injection Wells	Blowout Preventer Shop and Injection Wells

^aCAS description from the FFACO (1996)

^bGeneral location from the FFACO (1996)

The NTS is located approximately 65 miles (mi) northwest of Las Vegas in Nye County, Nevada (Figure 1-1). The CASs within CAU 322 are located in Areas 1 and 3 of the NTS, as shown on Figure 1-2.

1.1 Purpose

This CADD develops and evaluates potential corrective action alternatives for each CAS within CAU 322 and provides a rationale for the selection of a recommended corrective action alternative for each CAS. The need for evaluation of corrective action alternatives is based on process knowledge and the results of investigative activities conducted in accordance with the CAU 322 Corrective Action Investigation Plan (CAIP) (NNSA/NSO, 2003).

Figure 1-1
Nevada Test Site Location Map

Figure 1-2
CAU 322 CAS Location Map

This CAU was investigated due to the existing process knowledge which indicated that the CASs within this CAU may have been used to store or dispose of material considered to be hazardous or radioactive waste by current standards. All CASs within CAU 322 were found to be as described in the CAIP and are discussed below:

Corrective Action Site 01-25-01 is located in the northern portion of the Shaker Plant facility in Area 1 of the NTS. The CAS consists of a potential release from a 10,000 gallon diesel fuel tank housed in an earthen and gravel berm that was once used to fuel the batch plant operation.

Corrective Action Site 03-25-03 is located at the Mud Plant in Area 3 of the NTS, in an area referred to as the Area 3 Man Camp. The CAS consists of two distinct areas (Area A and Area B). Area A, on the western end of the CAS, consists of a potential release from a diesel fuel tank once housed in a J-shaped berm. Area B is located on the eastern end of the CAS and on the east side of the Mud Plant. Area B was theorized to consist of multiple potential discrete fuel releases or was contaminated by subsurface migration of contaminants from Area A.

Corrective Action Site 03-20-05 is located in Area 3 of the NTS at the Blowout Preventer (BOP) Shop in an area referred to as the Area 3 Man Camp. This CAS consists of several potential releases, including contaminants from one or more of the three in-ground holding tanks and sumps (in the two outermost tanks only) within the BOP Shop, overflow of one or more of the holding tanks onto the floor of the BOP Shop, leakage from the underground transfer line from the holding tanks to the injection well, dispersion from the injection well sump into the surrounding soils, and percolation from the injection well casing soils into underlying soils. The injection well is located approximately 65 feet (ft) to the east of the southern end of the BOP Shop. The well is fed by an underground pipe from the BOP Shop, and is approximately 65 ft in depth. The sump in the injection well is approximately 10 inches (in.) in diameter and slotted beginning at approximately 28 ft below ground surface (bgs). Approximately 2 to 3 ft of liquid is currently at the bottom of the sump.

Additional information regarding the history of each site, planning, and the scope of the investigation is presented in the CAU 322 CAIP (NNSA/NSO, 2003).

1.2 Scope

The scope of the activities used to identify, evaluate, and recommend corrective action alternatives for each CAS within CAU 322 included the following:

- Evaluation of current site conditions, including the concentration and extent of contaminants of concern (COCs)
- Development of corrective action objectives commensurate with the complexity of each CAS
- Identification of corrective action alternative screening criteria
- Performance of detailed and comparative evaluations of corrective action alternatives in relation to corrective action objectives and screening criteria

1.3 Corrective Action Decision Document Contents

This CADD is divided into the following sections and appendices:

Section 1.0 - Introduction: Summarizes the purpose, scope, and contents of this CADD.

Section 2.0 - Corrective Action Investigation Summary: Summarizes the investigation field activities, the results of the investigation, and the need for corrective action at this CAU.

Section 3.0 - Evaluation of Alternatives: Describes, identifies, and evaluates the steps taken to determine a preferred corrective action alternative for each CAS.

Section 4.0 - Recommended Alternatives: Presents the preferred corrective action alternative for each CAS and the rationale for selecting that alternative based on the corrective action objectives and screening criteria.

Section 5.0 - References: Provides a list of all referenced documents used in the preparation of this CADD.

Appendix A: Corrective Action Investigation Results for CAU 322: Provides a description of the project objectives, field investigation and sampling activities, investigation results, waste management, and quality assurance practices. Section A.3.0 through Section A.5.0 provide

CAS-specific information regarding field activities, sampling methods, and laboratory analytical results from the investigation sampling.

Appendix B: Data Assessment of Sample Results for CAU 322: Provides an assessment of data obtained during the CAU 322 investigation. The appendix also summarizes and compares the investigation results to the requirements set forth during the data quality objective (DQO) process.

Appendix C: Cost Estimates for CAU 322: Presents cost estimates for the construction, operation, and maintenance of each corrective action alternative evaluated for each CAS.

Appendix D: Sample Location Coordinates for CAU 322: Provides the global positioning system (GPS) coordinates for investigation sample locations and points of interest at each CAS.

Appendix E: Risk Evaluation for CAU 322: Provides a discussion of the risks associated with leaving contamination above action levels (ALs) in place.

Appendix F: Project Organization: Identifies the Project Manager and other appropriate personnel involved with the CAU 322 characterization and closure activities.

Appendix G: Response to Nevada Division of Environmental Protection comments.

To ensure all project objectives, health and safety requirements, and quality control procedures were adhered to, all investigation activities were performed in accordance with the following documents:

- *Corrective Action Investigation Plan for CAU 322: Area 1 and 3 Release Sites and Injection Wells* (NNSA/NSO, 2003).
- Record of Technical Change (ROTC) No. 1 to the CAIP (NNSA/NSO, 2003), was prepared in April 2004 and has been approved by the Nevada Division of Environmental Protection (NDEP). This ROTC documents changes to the radiological PALs and adds appropriate references. The ROTC also changes a requirement for laboratory analysis of all samples obtained at the Mud Plant aboveground storage tank (AST) release site to indicate that all samples collected will be field screened for total petroleum hydrocarbon (TPH) diesel-range organics (DRO), and appropriate samples will be forwarded for laboratory analysis. Finally, references to quick turn-around analyses for samples taken at the Mud Plant AST release site were removed.
- *Industrial Sites Quality Assurance Project Plan* (QAPP) (NNSA/NV, 2002)

- *Federal Facility Agreement and Consent Order* (1996)
- *Project Management Plan* (DOE/NV, 1994)

2.0 Corrective Action Investigation Summary

The following sections summarize the CAU 322 investigation activities, investigation results, and identify the need for corrective action at each CAS. Detailed investigation activities and results for CAU 322 are presented in Appendix A.

2.1 Investigation Activities

Corrective action investigation activities were performed from April 12 through September 12, 2004, as set forth in the CAU 322 CAIP (NNSA/NSO, 2003). Investigation activities were conducted to:

- Determine if contaminants of potential concern (COPCs) are present within environmental media at the CAS
- Determine whether the COPCs, if present, exceed ALs, thereby becoming COCs
- Determine the lateral and vertical extent of identified COCs
- Collect sufficient data to address the decision statements as outlined in the CAIP
- Ensure adequate data have been collected to evaluate and recommend a corrective action alternative
- Collect sufficient data to make waste disposal decisions

Sufficient information was obtained to define the nature and extent of contamination associated with each CAS, and develop and evaluate corrective action alternatives for each CAS located within CAU 322.

General investigation activities included:

- Collecting environmental soil samples for laboratory analyses to determine the nature of COCs.
- Identifying COCs at CASs and collected additional environmental samples for laboratory analyses to define the vertical and lateral extent of contamination.
- Collecting GPS coordinates at sample locations.

- Collecting and analyzing samples to support waste characterization.
- Field-screening soil samples at each CAS for alpha and beta/gamma radiation, volatile organic compounds (VOCs), and TPH at all CASs.
- Collecting quality control (QC) samples for laboratory analyses to ensure that the data generated from the analysis of investigation samples meet the requirements of the data quality indicators (DQIs).

A judgemental (nonprobabilistic) sampling scheme was implemented to select sample locations and evaluate analytical results. Judgemental sampling allows the methodological selection of sample locations that target the populations of interest (defined in the DQOs) rather than the non-selective random locations. Random sample locations are used to generate average contaminant concentrations that estimate the true average (characteristic) contaminant concentration of the site to some specified degree of confidence.

Since individual sample results, rather than an average concentration, will be used to compare to action levels, statistical methods used to generate site characteristics (averages) will not be necessary. Section 0.4.4 of the U.S. Environmental Protection Agency (EPA) Data Quality Objectives for Hazardous Waste Site Investigations (EPA, 2000) guidance states that the use of statistical methods may not be warranted by program guidelines of site-specific sampling objectives. The need for statistical methods is dependent upon the decisions being made. Section 7.1 of the EPA QA/G-4HW guidance states that a nonprobabilistic (judgemental) sampling design is developed when there is sufficient information on the contamination sources and history to develop a valid conceptual site model and to select specific sampling locations. This design was used to confirm the existence of contamination at specific locations and provide information (such as extent of contamination) about specific areas of the site.

Confidence in judgemental sampling results will be established qualitatively through the validation of the conceptual site model (CSM) developed and concurred to by stakeholder participants (U.S. Department of Energy, National Nuclear Security Administration Nevada Site Office [NNSA/NSO] and NDEP) during the DQO process based on investigation results and by evaluating the quality of the data based on DQI parameters.

Two CSMs were developed for CAU 322 to represent the release mechanisms and potential migration pathways for each CAS. These are provided in Appendix A of the CAU 322 CAIP. The system configurations, migration pathways, and release mechanisms identified during the field investigation were consistent with the CSMs provided in the CAIP except where otherwise specified in this CADD. The CSMs included soil potentially impacted by surface and/or subsurface disposal and or release of contaminants. The release mechanisms include intentional and accidental releases. The models assumed that any contamination would be concentrated in the soil immediately beneath and adjacent to the location of the release. The extent of underlying soil impacted was expected to be variable and dependent upon the volume of material released, physical and chemical properties of the surrounding media, geological conditions, and physical and chemical properties of the impacted media as well as the COPCs.

The following sections summarize the specific investigation activities at each CAS and discusses the validity of the CSMs.

2.1.1 CAS 01-25-01, AST Release

Investigation activities conducted at CAS 01-25-01 included walk-over radiological survey, biased surface and shallow subsurface soil sampling, field screening for TPH-DRO and VOCs, and collection and analysis of material suspected of containing TPH-DRO.

Investigation results indicate TPH-DRO contamination was more extensive than indicated in the Preliminary Assessments investigation; however, it was not necessary to modify the CSM for this CAS. The entire soil surface of the berm floor contained TPH-DRO at concentrations exceeding the preliminary action level (PAL). Additional samples were obtained outside the berm to determine lateral extent of contamination and a backhoe was used to obtain samples to demonstrate vertical depth within the berm.

Samples were shipped to an off-site laboratory for the analyses listed in Table A.3-1. Investigation activities associated with CAS 01-25-01 are further detailed in Section A.3.0.

2.1.2 CAS 03-25-03, Mud Plant and AST Diesel Release

Investigation activities at CAS 03-25-03 involved characterization sampling of the CAS components including soils at the site of a J-shaped berm that once contained a diesel fuel AST (Area A).

Additional activities include the sampling of soils along the east side of the Mud Plant (Area B) for TPH-DRO contamination based on sample results obtained from CAU 34.

2.1.2.1 CAS 03-25-03, Area A, AST Release

Activities at this area of interest included a radiological walk-over survey, surface and shallow subsurface soil sampling using hand augurs and a backhoe, drilling with a roto sonic drill rig, and field screening for TPH-DRO and VOCs.

Samples were shipped to an off-site laboratory for the analyses listed in Table A.4-1. Investigation activities associated with CAS 03-25-03 are further detailed in Section A.4.0.

2.1.2.2 CAS 03-25-03, Area B, Mud Plant

Activities at this area of interest included a radiological walk-over survey, surface and shallow subsurface soil sampling using hand augurs and a backhoe, drilling with a roto sonic drill rig, and field screening for TPH-DRO and VOCs. Samples were shipped to an off-site laboratory for the analyses outlined in Table A.4-1. Investigation activities associated with CAS 03-25-03 are further detailed in Section A.4.0.

2.1.3 CAS 03-20-05, Injection Wells

Investigation activities at CAS 03-20-05 were comprised of a radiological walk-over survey, characterization sampling of three in-ground holding tanks and their sumps (present in only two of the tanks) within the BOP Shop, sampling of soils adjacent to the holding tanks outside the BOP Shop, sampling of surface and shallow subsurface soils outside the BOP Shop, sampling of soils adjacent to the injection well, and soil sampling along the underground piping leading from the BOP Shop holding tanks to the injection well. Liquid samples were collected from the sump of the injection well (at a depth of approximately 62 ft bgs), as well as soil samples from within the injection well vault surrounding the injection well sump. Radiation surveys were also conducted of the BOP

Shop floor, the lids covering the in-ground holding tanks, the inner walls of the in-ground holding tanks, the lid covering the injection well, the inner walls of the casing surrounding the injection well, and the injection well sump to its depth of approximately 62 ft bgs.

Samples were shipped to an off-site laboratory for the analyses listed in Table A.5-1. Investigation activities associated with CAS 03-20-05 are further detailed in Section A.5.0.

For each CAS, the conceptual site model is considered valid based upon the analytical results provided by the laboratory.

2.2 Results

A summary of characterization data from the CAU 322 CAI is provided in Section 2.2.1. This information illustrates the degree of characterization accomplished through the field effort and identifies those COPCs that exceed PALs and were subsequently classified as COCs. Section 2.2.2 summarizes the assessment made in Appendix B which demonstrates the correlation between the investigation results and the DQOs.

2.2.1 Summary of Characterization Data

Chemical and radiological results for investigation samples collected at each of the CASs are summarized in Section 2.2.1.1 through Section 2.2.1.3. The PALs for the CAU 322 investigation were determined during the DQO process and are discussed in Section 3.3 of the CAIP (NNSA/NSO, 2003). Record of Technical Change No. 1 to the CAS was completed to document subsequent agreements between NDEP and NNSA/NSO regarding the reference source and values for dose-based radiological PALs and the application of those PALs to the findings of the CAU 322 CAI.

Details about the methods used during this investigation and a comparison of environmental sample results to the ALs defined in Section 3.1 are presented in Appendix A. Sample locations that support the presence and/or extent of contamination at each CAS are shown in the Appendix A figures. Based on the results presented in Appendix A, the nature and extent of COCs at CAU 322 have been adequately identified to develop and evaluate corrective action alternatives.

The following sections summarize CAI analytical results on a CAS-specific basis.

2.2.1.1 CAS 01-25-01, AST Release

The TPH-DRO was identified as a COC based on analytical results of soil samples collected within the AST berm. Additional sampling was performed both within and outside the bermed area to delineate the lateral and vertical extent of the TPH-DRO contamination. Results of the analyses provide the following information for CAS 01-25-01.

Samples collected at locations A01 and A02 confirm the presence of TPH-DRO above the PAL at all depths. Samples 322A004 and 322A009 through 322A011 at sample location A02 show a decrease in TPH-DRO concentration with depth and distance from the source, as theorized in the CSM.

Samples collected at location A02 were unable to define the vertical depth to TPH-DRO concentrations below the PAL due to safety considerations. The deepest sample (collected at 10 ft beneath the berm floor in the native soil at sample site A02) indicated the concentration of TPH-DRO was 140 parts per million (ppm). Contamination associated with the AST berm was laterally bounded by samples 322A008 and 322A012 through 322A015 at sample location A04, and samples 322A016 through 322A020 at sample location A05.

Because of site-specific conditions, the sampling at this CAS was limited. The steep slope on the north side of the berm restricted sampling to the north and west, and the presence of a power substation and an aboveground diesel fuel line from the current AST to the Shaker Plant prevented additional sampling to the east of the berm. No discoloration was identified in the soil within the sheer wall north of the berm. The wall is approximately 3 ft north of the berm perimeter, and drops approximately 50 to 60 ft at a nearly vertical slope.

Based on these results, the nature and extent of TPH-DRO contamination at CAS 01-25-01 has been defined as being restricted to within the physical boundaries of the berm laterally, but not completely defined vertically within the berm. Additional depth sampling using such equipment as a sonic drill rig is not advisable from a safety viewpoint owing to the close proximity and steepness of the land immediately to the north of the berm. An estimate was developed and applied to the existing concentrations and depth to identify a depth at which TPH-DRO is expected to decrease to a level of one-half the PAL. This theoretical depth is 12 ft bgs (see Appendix A for further explanation of the

estimation method used to determine this depth). Details of analytical results associated with this CAS are located in Section A.3.0.

2.2.1.2 CAS 03-25-03, Mud Plant and AST Diesel Release

This CAS is divided into Area A (the J-shaped AST berm located at the west end) and Area B (the Mud Plant located at the east end).

2.2.1.2.1 Area A

TPH-DRO was identified above the PAL at two locations in Area A. The first was a surface sample collected at sample location B04. The concentration of TPH-DRO was 370 milligrams per kilogram (mg/kg) at this location. TPH-DRO was not identified at other depths at this location or adjacent sample locations; therefore, the contamination is considered bounded. The soil at sample location B04 was removed to a depth of 1 ft bgs and drummed for management as hydrocarbon waste. A confirmation sample was collected at the bottom of the excavation and determined to be free of TPH-DRO.

A second sample location with TPH-DRO contamination (140 mg/kg) was identified at 2 to 3 ft bgs at sample location B01. No other TPH-DRO contamination was identified above the PAL vertically or laterally from this location and depth. The 2 to 3 ft bgs interval was removed and drummed for management as hydrocarbon waste. Confirmation samples were collected from the bottom of the excavation, as well as the northwest and southeast walls of the excavation (the excavation itself ran northeast to southwest). These results were nondetect for TPH-DRO.

Historical documentation indicated the potential presence of significant TPH-DRO contamination in addition to that described above. This contamination was not encountered despite the biasing of sample locations to areas identified during previous field activities.

No contamination remains at this location.

2.2.1.2.2 Area B

At area B, TPH-DRO was identified above the PAL at several locations and at varying depths. The two sample locations with the highest TPH-DRO contamination are located off the southeast corner of the Mud Plant facility and to the east-northeast along a compacted gravel roadway running between the Mud Pit Disposal Crater and the Mud Plant Pond (both described in the CADD for CAU 34). Identification of a TPH-DRO plume from any single potential source was not possible. The TPH-DRO contamination appeared highly variable in both concentration and location, both vertically and laterally. These areas of contamination have been delineated both vertically and horizontally through step-out sampling efforts within the physical constraints associated with the Mud Pit Disposal Crater located to the north and the Mud Plant Pond located to the southeast of the site. The analytical results did not suggest the presence of a TPH-DRO plume from a single source but suggested that multiple small releases and anomalies resulting from equipment fueling activities, dust suppression applications, and soil excavation/placement were the source of the contamination. Partial excavation of contaminated locations is another possible explanation for TPH-DRO presence at depth, while samples collected above these areas show no contamination. Analytical results indicate that the TPH-DRO contamination in Area B is not, as hypothesized in the CAIP, the result of TPH-DRO migration from Area A of this CAS.

Plutonium contamination was identified at one surface sample location in Area B (sample location B12). The plutonium contaminated soil was removed and drummed for waste disposal. Step-out samples collected to confirm the removal of plutonium contamination indicated no contamination above the PAL.

Based on these results, the nature and extent of COCs at CAS 03-20-05 has been defined and in accordance with the CSM. No contamination other than TPH-DRO remains in Area B. Details of analytical results associated with this CAS are located in Section A.5.0.

2.2.1.3 CAS 03-20-05, Injection Wells

No contamination was identified in association with the liquid contents of the holding tanks within the BOP Shop. However, samples collected from the central sumps in the two outer holding tanks contained two discreet layers. For analytical purposes, these were designated as an oil layer and a

water layer by the analytical laboratory. The water layer samples collected from both sumps contains no COPCs above their respective PALs. The oil layers were essentially pure TPH. The sample from the sump in holding tank #1 (HT-1) contains TPH-DRO at a concentration of 990,000 milligrams per liter (mg/L), and that from the sump of holding tank #3, (HT-3) is 880,000 mg/L. In addition to TPH-DRO, the samples from the two holding tank sumps also contained bis(2-ethylhexyl) phthalate at concentrations of 210,000 and 300,000 mg/L for HT-1 and HT-3, respectively. No other COPCs are identified above their respective PALs from these holding tank sumps. Based on radiological surveys, no contamination was associated with the floor of the BOP Shop, the interior of the holding tanks or their covers, or the interior of the injection well vault and its cover. No contamination was identified in association with the underground rinsate transfer line running from the BOP Shop to the injection well.

Aroclor-1254 was identified at the surface of sample location C08 at a concentration of 1.1 mg/kg, and was bounded laterally and vertically.

Total petroleum hydrocarbon-DRO was identified at levels above the PAL in surface soil samples adjacent to the injection well, and the extent of contamination was bounded vertically. These surface samples contained small pieces of asphalt, and it was believed this provided the TPH-DRO results above the PAL.

Total petroleum hydrocarbon-DRO contamination was identified above the PAL at sample locations C08 and C19 at a depth of 60 ft bgs. The TPH-DRO contamination at these locations (730 mg/kg at C08 and 1,800 mg/kg at C19) coincides with the approximate depth of the injection well sump. The physical configuration of the injection well was designed for the siphoning off of the lighter TPH-DRO components from liquids injected into the well casing. No other deep subsurface TPH-DRO concentration above the PAL was identified in any other of the samples taken from sample location C08 to a depth of 120 ft bgs or C19 to a depth of 70 ft bgs. No other TPH-DRO contamination was identified at any depth to 120 ft bgs in samples collected from deep-subsurface borings surrounding the identified contamination and the injection well (sample locations C11 and C12). It is believed that this contamination is a component of a lens-shaped plume of contamination that extends in all directions from the bottom of the injection well sump.

The soil within the injection well casing was sampled at two locations to a depth of 6 ft bgs. Additional sampling below this depth using a drill rig was not possible owing to site physical constraints as well as the structure of the drill rig itself. The soil within the injection well casing received the liquids from the holding tanks within the BOP Shop, and resided there until the level of liquid reached the top of the sump, where the lighter components of the liquid drained down the sump, or leached through the soils within the vault surrounding the sump. The semiporous material making up the soil surrounding the injection well sump to the depth investigated appeared to have allowed a significant amount of COPCs to accumulate. The soil was clearly hydrocarbon stained and emitted a musty hydrocarbon odor. Concentrations of TPH-DRO decreased with depth, ranging from 45,000 mg/kg (surface) to 6,600 mg/kg (3 to 4 ft bgs) to 6,400 mg/kg (6 to 7 ft bgs) at location C06, and from 35,000 mg/kg (surface) to 5,900 mg/kg (3 to 4 ft bgs) to 3,300 mg/kg (5 to 6 ft bgs) at location C07. Sample location C06 was from the soil beneath the underground pipe that fed liquids from the holding tanks into the injection well casing. TPH-DRO contamination was not completely bounded vertically within this boring. Because of this lack of vertical bounding, it is conservatively estimated that the TPH-DRO contamination extends in a cylindrical geometry to the depth of the injection well sump bottom (approximately 62 ft bgs), where it becomes part of the lens-shaped plume emanating from base of the sump.

Aroclor-1254 concentrations are above the PAL in the same two surface soil samples at locations C06 and C07. The Aroclor-1254 concentration at sample location C06 is 3.3 mg/kg, and 2.4 mg/kg at sample location C07. The concentrations of Aroclor-1254 decrease to below the PALs in the two samples collected beneath each surface sample location, a depth of 4 to 5 ft bgs.

Lead is also identified above the PAL in the surface soil samples at both locations within the injection well casing. The sample location C06 showed a lead concentration of 2,500 mg/kg, and 1,500 mg/kg at sample location C07. The lead concentrations decrease to below the PALs in the two samples collected beneath each surface sample location, a depth of 4 to 5 ft bgs.

Toxicity characteristic leaching procedure (TCLP) cadmium was identified at a concentration of 2.9 mg/L, which was above the *Resource Conservation and Recovery Act* (RCRA) regulatory limit for toxicity of 1 mg/L at location C06 (2 to 3 ft bgs) and 1.9 mg/L at sample location C07 (2 to 3 ft bgs). TCLP results for samples collected below these depth intervals indicate that the TCLP

regulatory limit is not exceeded vertically. Lateral contamination for TCLP metals was not found above the RCRA regulatory limit in any samples collected.

Plutonium (Pu)-239 was identified above the PAL in the surface sample collected at sample location C09. The Pu-239 contamination is bounded both vertically and laterally. Pu-239 is also identified above the PAL in the surface sample taken at sample location C08. The Pu-239 contamination is bounded vertically, but additional Pu-239 surface contamination was identified southeast of sample location C08 at sample location C18 and to the southwest at sample location C14. The surface soils at these locations were removed and drummed, and the material beneath the removed soils was sampled and analyzed. The drummed soil will be disposed of as low-level radioactive waste. The results for these analyses indicate the contamination was removed. There was no modification to the CSM as this surface contamination is the result of deposition from aboveground testing; therefore, not a COPC for this CAS.

Sample locations C06 and C07 also showed contamination above the PALs for Pu-239 (15 pCi/g at 2 to 3 ft bgs and 29.1 pCi/g at 5 to 6 ft bgs), americium (Am)-241 (19.7 pCi/g at 2 to 3 ft bgs and 11.9 pCi/g at 5 to 6 ft bgs), and cesium (Cs)-137 (10.1 pCi/g at 5 to 6 ft bgs). Because the vertical extent of these contaminants was not bounded, additional sampling was required. The additional samples collected to a depth of 25 ft bgs showed contaminant levels for these parameters decreased below their respective PALs at a depth of 14 ft bgs, and remained below their respective PALs in samples collected at 19 to 20 and 24 to 25 ft bgs, vertically bounding these radiological contaminants.

Samples were collected from the liquid contained in the sump of the injection well. No COPCs are identified above their respective PALs. It is believed that the liquid is predominantly rainwater.

Based on these results, the nature and extent of COCs at CAS 03-20-05 has been defined. Details of analytical results associated with this CAS are located in Section A.5.0.

2.2.2 Data Assessment Summary

An assessment of CAU 322 investigation results determined that the data collected met the DQOs and support their intended use in the decision-making process. The assessment, provided in Appendix B, includes an evaluation of the DQIs to determine the degree of acceptability and usability of the

reported data in the decision-making process. Additionally, a reconciliation of the data with the CSMs established for this project was conducted. Conclusions were based on results of the quality control measurements and are discussed in Appendix A and Appendix B.

The overall results of the assessment indicate that the DQI goals for precision, accuracy, completeness, representativeness, and comparability have been achieved. Precision and accuracy of the datasets were demonstrated to be within acceptable limits for a high percentage of the data. It should be noted that the percentage of acceptable laboratory control spikes was greater than 98 percent for all analyses, indicating that the low recoveries were not an analytical or laboratory problem, but may be due to matrix interference. Therefore, accuracy results for CAU 322 are considered acceptable.

Completeness objectives for this CAU have been achieved. Completeness for chemical analyses were 97 percent or better. Completeness for radiochemical analyses was 100 percent. Rejected data were thoroughly reviewed and questions concerning these data have been addressed in Appendix B. The rejected data are not considered to have adversely impacted the decision-making process.

Representativeness of site characteristics was demonstrated with the CAU 322 data. An evaluation of comparability provides high confidence that the datasets for this project are comparable to other NTS projects and other data generated by accepted industry standards. The evaluation also ensures that project data are comparable to PALs and regulatory disposal limits. Data were analyzed per SW-846 protocols, meeting specifications identified in the CAU 322 CAIP (NNSA/NSO, 2003). Achieving all of the DQI goals supports acceptance of the CAU 322 datasets; thereby, meeting the DQOs established for this project and the subsequent use of these data in the decision-making process.

2.3 *Need for Corrective Action*

Analytes detected during the corrective action investigation were evaluated against ALs to determine COCs for each CAS in CAU 322. The identification of COCs above ALs in surface and subsurface soil requires that corrective action alternatives be considered and evaluated. The impacted volume/characteristics and site-specific constraints are provided in each CAS-specific section.

2.3.1 CAS 01-25-01, AST Release

One COC, TPH-DRO, was identified at CAS 01-25-01. Approximately 267 cubic yards (yd³) of soil within the berm's confines and extending to a depth of approximately 12 ft bgs is contaminated with TPH-DRO at concentrations above the PAL (100 mg/kg) and up to 7,000 mg/kg. The source of the TPH-DRO is associated with AST filling operations, in which overfilling of the AST occurred regularly. If excavated, the contaminated soil would not be considered a RCRA-listed hazardous waste.

2.3.2 CAS 03-25-03, Mud Plant and AST Diesel Release

The need for corrective action at this CAS is addressed separately for the two areas, Area A (the AST Release) and Area B (the Mud Plant), and are presented individually in the following sections.

2.3.2.1 CAS 03-25-03, Area A, AST Release

Total petroleum hydrocarbon-DRO is the only COC identified at this CAS. TPH-DRO was identified at two locations in Area A. The contaminated soil was removed for disposal and confirmation samples collected. All confirmation samples were clean. The Area A portion of this CAS is considered clean, and no further action is required.

2.3.2.2 CAS 03-25-03, Area B, Mud Plant

Total petroleum hydrocarbon-DRO was identified at several locations at concentrations above the PAL at various depths within the Area B portion of the CAS. The random appearance of TPH-DRO contamination suggests several isolated sources. Removal of the identified TPH-DRO contamination would require the removal of large volumes of clean material in order to access the contaminated soils because the depths and locations of the contamination are widely scattered across the footprint of the area of interest.

The Pu-239 surface contamination identified during sampling was removed and drummed. Confirmation samples indicated no additional Pu-239 contamination.

2.3.3 CAS 03-20-05, Injection Wells

Analytical results from samples collected from the soil around the BOP Shop indicated some surface TPH-DRO contamination likely due to the presence of asphalt in certain sample locations. Although bounded both vertically and laterally, TPH-DRO arising from asphalt is not a COC associated with this CAS. Some surface sample locations indicated the presence of Pu-239, which was delineated both vertically and laterally. Although not a COC associated with this CAS, the Pu-239 contamination was removed and drummed as a Best Management Practice to mitigate potential personnel exposures.

Aroclor-1254 contamination was identified above its PAL at sample location C08. Samples collected below and surrounding this sample location bound this contamination both laterally and vertically. No other contaminants were identified in the samples collected around the BOP Shop and injection well.

Soils within the injection well vault are contaminated with TPH-DRO above its PAL. These soils are also contaminated with metals, polychlorinated biphenyls (PCBs), and radionuclides above their respective PALs to a depth of 14 ft bgs. These contaminants are bounded below this depth. The samples collected at sample locations C06 and C07 are also contaminated with TCLP cadmium at a depth of 2 to 3 ft bgs). Samples collected below this interval are clean for this parameter.

The soils collected at a depth of 60 ft bgs at locations C08 and C19 are contaminated with TPH-DRO above the PAL. Samples collected both above and below this sample depth are clean. It is assumed that the TPH-DRO contamination from the injection well vault soils is connected to this contamination as a cylindrically-shaped plume, as no interception of a laterally-extending plume of contamination was identified in any of the soil borings.

It is recommended that the liquids from the holding tanks and sumps within the BOP Shop and the liquids from the injection well sump be removed as a Best Management Practice.

3.0 Evaluation of Alternatives

The purpose of this section is to present the corrective action objectives for CAU 214, describe the general standards and decision factors used to screen the various corrective action alternatives, and develop and evaluate a set of corrective action alternatives that will meet the corrective action objectives.

3.1 Corrective Action Objectives

The corrective action objectives ensure that each release site will not pose an unacceptable risk to human health and the environment and that conditions at each site are in compliance with all applicable laws and regulations. To ensure that these objectives are met, DQOs identified the information necessary to evaluate the available data against the investigation objectives. This process ensured sufficient data was collected to support the DQO decisions for each CAS. This process involved the comparison of CAI analytical data to risk-based cleanup goals defined herein as final action levels (FALs). The FALs for all the constituents detected at CAU 322 CASs are the PALs determined during the DQO process. For chemical COPCs, PALs are based on EPA Region 9 Industrial Preliminary Remediation Goals (PRGs) (EPA, 2002) and 100 milligrams per kilogram (mg/kg) for hydrocarbon-impacted soil (NAC, 2002a).

The background concentration for arsenic at NTS was used for the arsenic PAL instead of its PRG because natural concentrations at NTS exceed the Region 9 PRG. The background concentration for arsenic is considered to be the mean plus two times the standard deviation for sediment samples collected by the Nevada Bureau of Mines and Geology throughout the Nevada Test and Training Range (formerly the Nellis Air Force Range) (NBMG, 1998; Moore, 1999).

The radiological PALs are as presented in ROTC No. 1 to the CAIP (NNSA/NSO, 2003). The PALs for radiological contaminants are based on the National Council on Radiation Protection and Measurement (NCRP) Report No. 129 recommended screening limits for construction, commercial, and industrial land use scenario (NCRP, 1999) scaled from 25 to 15 millirem (mrem) per year dose and the generic guidelines for residual concentrations of radionuclides in DOE Order No. 5400.5 (DOE, 1993).

3.2 Screening Criteria

The screening criteria used to evaluate and select the preferred corrective action alternatives are identified in the EPA *Guidance on RCRA Corrective Action Decision Documents* (EPA, 1991) and the *Final RCRA Corrective Action Plan* (EPA, 1994).

Corrective action alternatives are evaluated based on four general corrective action standards and five remedy selection decision factors. All corrective action alternatives must meet the general standards to be selected for evaluation using the remedy selection decision factors.

The general corrective action standards are as follows:

- Protection of human health and the environment
- Compliance with media cleanup standards
- Control the source(s) of the release
- Comply with applicable federal, state, and local standards for waste management

The remedy selection decision factors are as follows:

- Short-term reliability and effectiveness
- Reduction of toxicity, mobility, and/or volume
- Long-term reliability and effectiveness
- Feasibility
- Cost

3.2.1 Corrective Action Standards

The following text describes the corrective action standards used to evaluate the corrective action alternatives.

Protection of Human Health and the Environment

Protection of human health and the environment is a general mandate of the RCRA statute (EPA, 1994). This mandate requires that the corrective action include any necessary protective measures. These measures may or may not be directly related to media cleanup, source control, or management of wastes. The corrective action alternatives are evaluated for the ability to meet corrective action objectives as defined in Section 3.1.

Compliance With Media Cleanup Standards

Each corrective action alternative must meet the proposed media cleanup standards as set forth in applicable state and federal regulations, and as specified in the CAU 322 CAIP (NNSA/NSO, 2003). For this CAU, the media cleanup standards are the FALs defined in Section 3.1.

Control the Source(s) of the Release

An objective of a corrective action remedy is to stop further environmental degradation by controlling or eliminating additional releases that may pose a threat to human health and the environment. Unless source control measures are taken, efforts to clean up releases may be ineffective or, at best, will essentially involve a perpetual cleanup. Therefore, each corrective action alternative must use an effective source control program to ensure the long-term effectiveness and protectiveness of the corrective action.

Comply with Applicable Federal, State, and Local Standards for Waste Management

During implementation of any corrective action alternative, all waste management activities must be conducted in accordance with applicable state and federal regulations (e.g., *Nevada Revised Statutes* [NRS] 459.400-459.600, “Disposal of Hazardous Waste” [NRS, 1998]; Title 40 *Code of Federal Regulations* (CFR) Parts 260-282, “Hazardous Waste Management” [CFR, 2002]; and NAC 459.9974, “Disposal and Evaluation of Contaminated Soil” [NAC, 2002b]).

The requirements for management of the waste, if any, derived from the corrective action will be determined based on applicable state and federal regulations, field observations, process knowledge, characterization data, and data collected and analyzed during corrective action implementation. Administrative controls (e.g., decontamination procedures and corrective action strategies) will minimize waste generated during site corrective action activities. Decontamination activities will be performed in accordance with approved procedures and will be designated according to the COCs present at the site.

3.2.2 Remedy Selection Decision Factors

The following text describes the remedy selection decision factors used to evaluate the corrective action alternatives.

Short-Term Reliability and Effectiveness

Each corrective action alternative must be evaluated with respect to its effects on human health and the environment during implementation of the corrective action. The following factors will be addressed for each alternative:

- Protection of the community from potential risks associated with implementation, such as fugitive dusts, transportation of hazardous materials, and explosion
- Protection of workers during implementation
- Environmental impacts that may result from implementation
- The amount of time until the corrective action objectives are achieved

Reduction of Toxicity, Mobility, and/or Volume

Each corrective action alternative must be evaluated for its ability to reduce the toxicity, mobility, and/or volume of the contaminated media. Reduction in toxicity, mobility, and/or volume refers to changes in one or more characteristics of the contaminated media by the use of corrective measures that decrease the inherent threats associated with that media.

Long-Term Reliability and Effectiveness

Each corrective action alternative must be evaluated in terms of risk remaining at the CAU after the corrective action alternative has been implemented. The primary focus of this evaluation is on the extent and effectiveness of the control that may be required to manage the risk posed by treatment residuals and/or untreated wastes.

Feasibility

The feasibility criterion addresses the technical and administrative feasibility of implementing a corrective action alternative and the availability of services and materials needed during implementation. Each corrective action alternative must be evaluated for the following criteria:

- Construction and Operation: Refers to the feasibility of implementing a corrective action alternative given the existing set of waste and site-specific conditions.

- **Administrative Feasibility:** Refers to the administrative activities needed to implement the corrective action alternative (e.g., permits, public acceptance, rights of way, off-site approval).
- **Availability of Services and Materials:** Refers to the availability of adequate off-site and on-site treatment, storage capacity, disposal services, necessary technical services and materials, and prospective technologies for each corrective action alternative.

Cost

Costs for each alternative are estimated for comparison purposes only. The cost estimate for each corrective action alternative includes both capital and operation and maintenance costs, as applicable. The following is a brief description of each component:

- **Capital Costs:** These costs include both direct and indirect costs. Direct costs may consist of materials, labor, mobilization, demobilization, site preparation, construction materials, equipment purchase and rental, sampling and analysis, waste disposal, and health and safety measures. Indirect costs include such items as engineering design, permits and/or fees, start-up costs, and any contingency allowances.
- **Operation and Maintenance:** These costs include labor, training, sampling and analysis, maintenance materials, utilities, and health and safety measures.

Cost estimates for the corrective action alternatives are provided in Appendix C.

3.3 Development of Corrective Action Alternatives

This section identifies and briefly describes the viable corrective action technologies and the corrective action alternatives considered for the affected media at the various CASs within CAU 322. Based on the review of existing data, future use, and current operations at the NTS, the following alternatives have been developed for consideration at CAU 322:

- Alternative 1 - No Further Action
- Alternative 2 - Clean Closure
- Alternative 3 - Closure in Place with Administrative Controls

Other technologies, such as bioremediation, were considered; however, it would not be effective because of the limited volume and concentrations of contaminated material. These alternatives will not receive further consideration in this CADD. Table 3-1 summarizes the corrective action alternatives evaluated for each CAS within CAU 322.

Table 3-1
Corrective Action Alternatives Evaluated for CAU 322

Corrective Action Site	Alternative 1	Alternative 2	Alternative 3
CAS 01-25-01	X	X	X
CAS 03-25-03 Area A	X		
CAS 03-25-03 Area B	X	X	X
CAS 03-20-05	X	X	X

3.3.1 Alternative 1 - No Further Action

Under the No Further Action Alternative, no corrective action activities will be implemented. This alternative is a baseline case, considered for all CASs, with which to compare and assess the other corrective action alternatives and their ability to meet the corrective action standards.

This alternative meets the corrective action objectives for CASs 03-25-03 Area A, where there are no COCs remaining in the soil.

3.3.2 Alternative 2 - Clean Closure

For contaminated surface and subsurface soil, Alternative 2 includes excavating and disposing of soil and debris containing COCs. Impacted soil will be removed. Contaminated media with activity exceeding the unrestricted release criteria will be excavated and properly disposed. A visual inspection will be conducted to ensure that debris and visible contamination have been removed. Verification soil samples will also be collected and analyzed for the presence of COCs. This will verify that the removal of COCs is complete.

Any contaminated material that is removed will be disposed of at an appropriate disposal facility. All excavated areas will be returned to surface conditions compatible with the intended future use of the site. Clean fill will be used to backfill excavations after removal of the contaminated soil. As feasible, clean borrow soil will be removed from a nearby location for placement in voids.

The following subsections provide appropriate CAS-specific information regarding Alternative 2, Clean Closure.

3.3.2.1 CAS 01-25-01 AST Release

Alternative 2 includes removal and proper disposal of the TPH-DRO contaminated soil. Verification samples would be collected from the excavation floor and sidewalls and analyzed for site-specific COCs to ensure adequate removal of the contaminated soil. As necessary, the excavated area will be backfilled with clean soil and/or graded to satisfaction. The AST berm is located on an elevated ledge on the south side of the Shaker Plant. The northern border of the berm drops off approximately 50 to 60 ft at a steep slope (angle of approximately 80 degrees from the edge of the berm). This severe physical feature makes removal of the contaminated soil at this location highly problematic. Removal of the contaminated soil from this location would compromise the integrity of the northern wall of the remaining berm, and the presence of any heavy equipment compressing and vibrating the soil around and within the northern wall of the berm would enhance its instability. Therefore, soil removal is not a viable option.

3.3.2.2 CAS 03-25-03 Area B, Mud Plant

Alternative 2 includes removal and proper disposal of the TPH-DRO contaminated soil. Verification samples would be collected from the excavation floor and sidewalls and analyzed for site-specific COCs to ensure adequate removal of the contaminated soil. As necessary, the excavated area will be backfilled with clean soil and/or graded. This alternative is not considered viable because of the large amount of soil that would require removal to achieve clean closure, and the added complications associated with the extensive amount of underground utilities located at this site. Additionally, two craters adjacent to Area B are closed in place with administrative controls for TPH-DRO as a result of CAU 34 investigations. Removing TPH-DRO contamination from Area B does not necessarily mean the area will be clean.

This CAS would be closed in accordance with the administrative requirements identified in NAC 445A (NAC, 2002a), as described in this section.

3.3.2.3 CAS 03-20-05 Injection Wells

Alternative 2 includes removal and proper disposal of soils contaminated with TPH-DRO and other contaminants within the injection well vault. Although feasible for the shallow subsurface

contamination, it is not feasible to remove the TPH-DRO contamination at the 60 ft bgs level. Therefore, Alternative 2 is not a viable option for this CAS.

3.3.3 Alternative 3 - Close in Place with Administrative Controls

Alternative 3 will use administrative controls to prevent inadvertent contact with chemical COCs and contaminated media with radiological activity exceeding the unrestricted release criteria. These controls would consist of use restrictions to minimize access and prevent unauthorized intrusive activities (e.g., fencing and signage). The future use of the CAS would be restricted from any activity that would alter or modify the containment control unless appropriate concurrence was obtained from NDEP. The combination of these measures will effectively prevent inadvertent intrusive activities by humans and native wildlife and the potential subsequent mobilization of COCs.

The following subsections provide appropriate CAS-specific information regarding Alternative 3, Closure in Place with Administrative Controls.

3.3.3.1 CAS 01-25-01, AST Release

Alternative 3 includes administrative activities and costs associated with the use restriction for the AST Release site. Additionally, appropriate signage around the AST berm is recommended for this alternative. This site is located within the Shaker Plant facility of the NTS Area 1.

The following evaluation of NAC 445A.227 (2) (a-k) (NAC, 2002) supports the protection of groundwater from COCs at this CAS:

- a. Depth to groundwater at the nearest water supply well, UE-16d, located approximately 7,875 ft west of the site (situated upon the western edge of Yucca Flat on Syncline Ridge), is approximately 755 ft bgs (USGS, 2002). Groundwater flow in this region generally is from the northeast to the southwest, eventually discharging at Ash Meadows (USGS, 1996).
- b. The distance to the nearest active water-supply well, UE-16d, is approximately 1.5 miles west of the site (USGS, 2002). This well is primarily used to provide drinking water for this area. Groundwater flow is generally to the southwest (DOE/NV, 1996)
- c. Soil type at this CAS is typical desert alluvium composed of mostly fine soil and rock particles and includes loose rocks measuring up to 3 in. in diameter.

- d. Average annual precipitation in the vicinity of the Shaker Plant is approximately 5.51 to 6.61 in. annually (NOAA, 2002). Annual evaporation is roughly 5 to 25 times the annual precipitation. The high potential evaporation and low precipitation rates create a negative water balance for the area; therefore, no driving force associated with precipitation is available to mobilize COCs vertically.
- e. TPH-DRO is present above PALs in the soil directly beneath the berm floor and is believed to have occurred as a result of years of AST overfilling.
- f. TPH-DRO contamination existed to a depth of approximately 12 ft bgs and is confined to the vertical volume beneath the berm floor.
- g. Presently, CAS 01-25-01 is located on a government-controlled facility. The NTS is a restricted area that is guarded on a 24-hour, 365 day-per-year basis; unauthorized personnel are not admitted to this facility. The site is currently inactive, and no known future use of the site is identified.
- h. Preferred routes of vertical and lateral migration are seepage into the native soil beneath the contaminated area. The source of the contamination has been removed, so no additional TPH-DRO is being released.
- i. See Section 2.3.1 of this CADD for site-specific considerations.
- j. The potential for hazard related to fire, vapor, or explosion is nonexistent for the COCs at this site.
- k. No other site-specific factors are known at this site.

Based on this evaluation, impacts to groundwater are not expected from this site. Therefore, groundwater monitoring is not proposed for this site and is not considered an element of the alternatives.

3.3.3.2 CAS 03-25-03 Area B, Mud Plant

Alternative 3 includes administrative activities and costs associated with use restrictions for the storage yards. Additionally, appropriate signage around the east side of the Mud Plant is recommended for this alternative.

The following evaluation of NAC 445A.227 (2) (a-k) (NAC, 2002a) supports the protection of groundwater from COCs at this CAS:

- a. Depth to groundwater at the nearest well (USGS Water Well A, located approximately 4,515 ft southwest of the CAS) is approximately 1,610 ft bgs (Winograd and Thordarson 1975). Movement of groundwater within the Ash Meadows subbasin is to the south-southwest, towards Death Valley and Ash Meadows.
- b. The distance to the nearest active water-supply well (USGS Water Well A) is approximately 4,515 ft southwest of this CAS (USGS, 2002). This well was primarily used to provide potable water for Area 3 until 1991. Groundwater flow is generally to the south-southwest (DOE/NV, 1996).
- c. Soil type at this CAS is generally compacted silty sands with gravel, typical of the desert in this area.
- d. Average annual precipitation for valleys in the South-Central Great Basin ranges from 3 to 6 in. (Winograd and Thordarson, 1975). Annual evaporation is roughly 5 to 25 times the annual precipitation. The high potential evaporation and low precipitation rates create a negative water balance for the area; therefore, no driving force associated with precipitation is available to mobilize COCs vertically.
- e. TPH-DRO contamination was identified above the PAL.
- f. Contaminant concentrations in sampling horizons below the widespread TPH-DRO-stained soil were below PALs, demonstrating minimal vertical migration. The vertical extent of the widespread TPH-DRO contamination is varied in both concentration and location. The lateral and vertical extent of the TPH-DRO contamination is isolated such that no contaminant plume originating from an identifiable source can be ascertained. Removal of all isolated locations of TPH-DRO contamination at this CAS amounts to the removal of approximately 1,500 yd³ of soil.
- g. Presently, CAS 03-25-03 Area B is located on a government-controlled facility. The NTS is a restricted area that is guarded on a 24-hour, 365 day-per-year basis; unauthorized personnel are not admitted to this facility. The site is currently inactive and no known future use of the site is identified.
- h. Preferred routes of vertical and lateral migration are seepage into the native soil beneath the contaminated locations. No additional source of TPH-DRO is identified at this location.
- i. See Section 4.0 of this CADD for site-specific considerations.

- j. The potential for hazard related to fire, vapor, or explosion is nonexistent for the COCs at this site.
- k. No other site-specific factors are known at this site.

Based on this evaluation, impacts to groundwater are not expected from this site. Therefore, groundwater monitoring is not proposed for this site and is not considered an element of the alternatives.

3.3.3.3 CAS 03-20-05, Injection Wells

Alternative 3 includes administrative activities and costs associated with use restrictions for the injection well. Additionally, appropriate signage around the injection well is recommended for this alternative.

The following evaluation of NAC 445A.227 (2) (a-k) (NAC, 2002) supports the protection of groundwater from COCs at this CAS:

- a. Depth to groundwater at the nearest well (USGS Water Well A, located approximately 392 ft northeast of the CAS) is approximately 1,610 ft bgs (Price and Thordarson 1961; Wuellner 1994). Movement of groundwater within the Ash Meadows subbasin is to the south-southwest, towards Death Valley and Ash Meadows.
- b. The distance to the nearest active water-supply well (USGS Water Well A) is approximately 392 ft northeast of this CAS (USGS, 2002). This well was primarily used to provide potable water for Area 3 until 1991 (Wuellner, 1994). Groundwater flow is generally to the south-southwest.
- c. Soil type at this CAS is generally fill material composed of silty sands with gravel.
- d. Average annual precipitation for valleys in the South-Central Great Basin ranges from 3 to 6 in. (Winograd and Thordarson, 1975). Annual evaporation is roughly 5 to 25 times the annual precipitation. The high potential evaporation and low precipitation rates create a negative water balance for the area; therefore, no driving force associated with precipitation is available to mobilize COCs vertically.
- e. TPH-DRO, lead, Aroclor-1254, americium-221, cesium-137, and plutonium-239 were identified above their respective PALs at this CAS.
- f. The nature and extent of contaminants in soil within the injection well casing have been delineated. The activities at the BOP Shop that led to the contamination no longer exist,

precluding the addition of more contaminants. The injection well is covered, reducing the likelihood of additional contaminant migration through percolation from rainwater intrusion. The lateral extent of the contamination is isolated to the confines of the injection well casing. Removal of the contaminated soils from the injection well casing would eliminate the need to provide an impervious cap to the immediate area. It is infeasible to remove the TPH-DRO contamination at 60 ft bgs. Removal of the radiological and metals contaminated soils from the injection well casing amounts to a depth of 14 ft bgs and requires the removal of approximately 30 yd³ of soil. However, TPH-DRO contamination will remain below 14 ft bgs.

- g. Presently, CASs 03-20-05 is located on a government-controlled facility. The NTS is a restricted area that is guarded on a 24-hour, 365 day-per-year basis; unauthorized personnel are not admitted to this facility. The site is currently inactive and no known future use of the site is identified.
- h. Preferred routes of vertical and lateral migration are seepage into the native soil beneath the contaminated locations, and no additional source of contaminants has been identified at this location.
- i. See Section 4.0 of this CADD for site-specific considerations.
- j. The potential for hazard related to fire, vapor, or explosion is nonexistent for the COCs at this site.
- k. No other site-specific factors are known at this site.

Based on this evaluation, impacts to groundwater are not expected from this site. Therefore, groundwater monitoring is not proposed for this site and is not considered an element of the alternatives.

In addition to the actions described above, Best Management Practices are also recommended for CAS 03-20-05 to eliminate the potential for environmental contamination in the future and to remove the areas of highest contamination to limit the potential for human exposure. These include:

- Removal and disposal of approximately 52 cubic yards of soil contaminated with metals, PCBs, radionuclides, and TPH-DRO, from the injection well vault and backfill to grade
- Removal and disposal of approximately 2 to 5 cubic ft of PCB-contaminated soil at location C08
- Removal and disposal of liquids from the holding tanks and the holding tank sumps

- Grouting of the holding tanks and holding tank sumps
- Grouting of the injection well

3.4 *Evaluation and Comparison of Alternatives*

The general corrective action standards and remedy selection decision factors described in Section 3.2 were used to conduct detailed and comparative analyses of each corrective action alternative presented in Section 3.3. The advantages and disadvantages of each alternative were assessed to select preferred alternatives for CAU 322. Table 3-2 and Table 3-3 present the detailed comparative evaluation of closure alternatives for each CAS requiring corrective action. The cost estimates listed in Table 3-2 and Table 3-3 are detailed in Appendix C.

Table 3-2
Detailed Evaluation of Alternatives for Corrective Action Unit 322
(Page 1 of 3)

Evaluation Criteria	Alternative 1 No Further Action	Alternative 2 Clean Closure	Alternative 3 Closure in Place with Administrative Controls
Closure Standards			
Protection of Human Health and the Environment	<ul style="list-style-type: none"> Does not meet corrective action objective of preventing or mitigating exposure to surface and subsurface soil containing COCs or media exceeding unrestricted release criteria. Does not meet corrective action objective of preventing or mitigating exposure to contamination with concentrations exceeding unrestricted release criteria. Does not prevent potential spread of COCs. NAC 445.227 (2) (a-k) analysis shows the contaminants are not expected to impact groundwater. No worker exposure associated with implementation. 	<ul style="list-style-type: none"> Meets corrective action objectives. Low to moderate risk to workers associated with heavy equipment and potential contact with impacted media during excavation, transportation, and closure activities. Low risk to public due to remote location and controlled access to NTS. Low to moderate risk to public during transportation off NTS. NAC 445.227 (2) (a-k) analysis shows the contaminants are not expected to impact groundwater. Moving contaminated media to an appropriate disposal facility mitigates exposure to impacted media after closure. 	<ul style="list-style-type: none"> Meets corrective action objectives. Prevents inadvertent intrusion into the contaminated media. Low risk to workers associated with heavy equipment and potential contact with impacted media during closure activities. Low risk to public because of remote location and controlled access to the NTS. NAC 445.227 (2) (a-k) analysis shows the contaminants are not expected to impact groundwater. Proposed alternative would eliminate the potential exposure pathway.
Compliance with Media Cleanup Standards	<ul style="list-style-type: none"> Does not comply with media cleanup standards because COCs exceeding unrestricted release criteria remain. NAC 445.227 (2) (a-k) analysis shows the contaminants are not expected to impact groundwater. 	<ul style="list-style-type: none"> Complies with media cleanup standards because media containing COCs will be excavated and disposed of at an appropriate facility. Removal of COCs will be verified with confirmation sampling. NAC 445.227 (2) (a-k) analysis shows the contaminants are not expected to impact groundwater. 	<ul style="list-style-type: none"> Complies with media cleanup standards by controlling exposure pathways. NAC 445.227 (2) (a-k) analysis shows the contaminants are not expected to impact groundwater.

Table 3-2
Detailed Evaluation of Alternatives for Corrective Action Unit 322
(Page 2 of 3)

Evaluation Criteria	Alternative 1 No Further Action	Alternative 2 Clean Closure	Alternative 3 Closure in Place with Administrative Controls
Control the Source(s) of Release	<ul style="list-style-type: none"> The sources of each Corrective Action Site (CAS) have been discontinued. 	<ul style="list-style-type: none"> The sources of each CAS have been discontinued. 	<ul style="list-style-type: none"> The sources of each CAS have been discontinued.
Comply with Applicable Federal, State, and Local Standards for Waste Management	<ul style="list-style-type: none"> No waste generated 	<ul style="list-style-type: none"> All waste (primarily contaminated soil, CAS components, and disposable personal protective equipment) will be handled and disposed of in accordance with applicable standards. 	<ul style="list-style-type: none"> All waste (primarily disposable PPE, system components) will be handled and disposed of in accordance with applicable standards.
Remedy Selection Decision Factors			
Short-Term Reliability and Effectiveness	Not evaluated	<ul style="list-style-type: none"> Low risk to workers associated with heavy equipment and potential contact with impacted media during excavation, transportation, and closure activities. Public protected during removal by remote location and NTS site access controls. Low to moderate risk to public during transportation off NTS. Environmental impacts are not anticipated due to implementation. Appropriate measures will be taken at the site to protect desert tortoises. Implementation should not require an extended period of time. 	<ul style="list-style-type: none"> Low risk to workers associated with heavy equipment and potential contact with impacted media during closure activities. Public protected by remote location and NTS site access controls. Environmental impacts are not anticipated due to implementation. Appropriate measures will be taken at the site to protect desert tortoises. Implementation should not require an extended period of time.

Table 3-2
Detailed Evaluation of Alternatives for Corrective Action Unit 322
(Page 3 of 3)

Evaluation Criteria	Alternative 1 No Further Action	Alternative 2 Clean Closure	Alternative 3 Closure in Place with Administrative Controls
Reduction of Toxicity, Mobility, and/or Volume	Not evaluated	<ul style="list-style-type: none"> • Clean closure would effectively eliminate associated toxicity, mobility, and volume of wastes at each CAS. • Proper disposal of the waste will result in an ultimate reduction of mobility. 	<ul style="list-style-type: none"> • The mobility of the remaining soil contamination is significantly reduced by administrative controls, solidification of any free liquid, and lack of viable driving forces. • Toxicity and volume of the soil contamination are effectively unchanged. • The mobility of the remaining subsurface soil contamination is significantly reduced by administrative controls and lack of viable driving forces.
Long-Term Reliability and Effectiveness	Not evaluated	<ul style="list-style-type: none"> • All risk will be eliminated on site upon completion. • No maintenance required. • Moving contaminated media to an appropriate disposal media facility addresses the persistent adsorption of contaminants. 	<ul style="list-style-type: none"> • Controls inadvertent intrusion to remaining contaminated media. • Administrative controls must be maintained.
Feasibility	Not evaluated	<ul style="list-style-type: none"> • Removal of contaminated media requires controls to protect workers. • Options for disposal of contaminated media is limited and require coordination with multiple entities. 	<ul style="list-style-type: none"> • Easily implemented • Coordination of all entities is necessary to ensure compliance with administrative controls to prevent intrusion into contaminated zones.
Cost	CAS 01-25-01: \$0 CAS 03-25-03 Areas A and B: \$0 CAS 03-20-05: \$0	CAS 03-25-03 Area B: \$262,078	CAS 01-25-01: \$22,151 CAS 03-25-03 Area B: \$22,420 CAS 03-20-05: \$156,591

NA = Not applicable

**Table 3-3
 Comparative Evaluation of Alternatives for Corrective Action Unit 322**

Evaluation Criteria		Comparative Evaluation	
Closure Standards			
Protection of Human Health and the Environment	Alternatives 2 and 3 meet corrective action objectives; Alternative 1 does not. No worker exposures to risks are associated with Alternative 1. Low risks are associated with Alternative 3 and slightly higher risks with Alternative 2. <i>Nevada Administrative Code 445A.227 (2) (a-k)</i> analysis shows the contaminants are not threatening groundwater.		
Compliance with Media Cleanup Standards	Alternative 1 does not comply with media cleanup standards. Alternative 2 meets media cleanup standards by removing contaminated soil and CAS components exceeding unrestricted release criteria and eliminating exposure pathways at the site. Alternative 3 controls access to contaminants, effectively eliminating exposure pathways.		
Control the Source(s) of Release	The sources at each Corrective Action Site (CAS) have been discontinued.		
Comply with Applicable Federal, State, and Local Standards for Waste Management	Alternative 1 does not generate waste. Alternatives 2 and 3 will generate waste that will be handled in accordance with applicable standards.		
Remedy Selection Decision Factors			
Short-Term Reliability and Effectiveness	Low risks are associated with Alternative 3 and slightly higher risks with Alternative 2.		
Reduction of Toxicity, Mobility, and/or Volume	Alternative 2 results in an immediate reduction of all three characteristics at each CAS. Alternative 3 results in a reduction of mobility, but does not reduce toxicity or volume. Worker exposure to risks associated with Alternative 2.		
Long-Term Reliability and Effectiveness	Residual risk at each CAS is low for Alternative 3 and nonexistent for Alternative 2. Alternative 3 requires administrative measures to control intrusive activities.		
Feasibility	Alternatives 2 and 3 are feasible; however, Alternative 2 will be more resource intensive, and beyond the capability of current technology to remove deep (60 ft bgs) contamination efficiently and cost effectively.		
Cost	CAS 01-25-01: \$0 CAS 03-25-03, Area A: \$0 CAS 03-25-03, Area B: \$0 CAS 03-20-05: \$0	CAS 03-25-03, Area B: \$262,078	CAS 01-25-01: \$22,151 CAS 03-25-03, Area B: \$22,420 CAS 03-20-05: \$156,591

NA = Not applicable

4.0 Recommended Alternatives

The preferred corrective action alternatives were evaluated on their technical merit with focus on performance, reliability, feasibility, and safety. The selected alternatives were judged to meet all requirements for the technical components evaluated. The selected alternatives meet all applicable state and federal regulations for closure of the sites and will minimize potential future exposure pathways to the contaminated media at CAU 322. Cost estimates, and in one case safety and site stability considerations, were used to support the selection of preferred corrective action alternatives.

Alternative 1, No Further Action, is the preferred corrective action for the following CAS:

- None

Alternative 2, Clean Closure, is the preferred corrective action for the following CAS:

- None

Alternative 3, Closure in Place with Administrative Controls, is the preferred corrective action for the following CASs:

- CAS 01-25-01, AST Berm - Because of safety and site stability concerns, this corrective action was selected. Owing to its isolated location, access to the CAS is easily limited by administrative controls. Because there is no current source of additional contamination, natural bioattenuation is expected to be a factor in reducing contamination over time. Administrative controls will be implemented for the remaining TPH-DRO contamination.
- CAS 03-25-03, Area B - Even though CAS 03-25-03 Area A, AST Berm does not contain contamination, the presence of contamination at Area B, the Mud Plant, and the requirement that the corrective action alternative applies to the entire CAS, a corrective action is required at this CAS. This corrective action was selected because of the nature of occurrence of TPH-DRO contamination at this CAS, in addition to the large footprint of the area of interest and the extensive network of underground utilities. As there is no identifiable isolated source of TPH-DRO contamination and no identifiable continued source of TPH-DRO contamination, natural bioattenuation is expected to be a significant factor in reducing contamination over time. In addition, TPH-DRO contamination will remain in the surrounding craters identified as contaminated in CAU 34. Administrative controls will be implemented for the remaining TPH-DRO contamination.

- CAS 03-20-05, Injection Wells - Because of the depth of the TPH-DRO contamination associated with the injection well, Alternatives 1 and 2 are necessarily excluded. It is unreasonable to remove the TPH-DRO contamination from this depth. As a Best Management Practice the following actions will be taken to reduce the potential for further contamination and to reduce the risk to human health and the environment to acceptable levels:
 - Removal of the higher toxicity soil associated with the lead, TCLP cadmium, Aroclor-1254, Am-241, Pu-239, and Cs-137, and higher levels of TPH-DRO contamination in the soils within and directly below the injection well vault (represented by sample locations C06 and C07) to a depth of at least 10 ft bgs, followed by backfilling the void created from the removed soil
 - Removal of a 2 by 2ft area approximately 1 ft deep to ensure complete removal of Aroclor-1254 at sample location C08 (the borehole at C08 is grouted to a depth of 120 ft bgs; some of the surface grouting will require removal as well)
 - Grout the injection well sump
 - Grout the holding tank sumps and the holding tanks themselves

Implementation of corrective actions at any of these CASs may potentially present risks to site workers and equipment.

5.0 References

CFR, see *Code of Federal Regulations*.

Code of Federal Regulations. 2002. Title 40 CFR Parts 260 - 282, "Hazardous Waste Regulations." Washington, DC: U.S. Government Printing Office.

DOE, see U.S. Department of Energy.

DOE/NV, see U.S. Department of Energy, Nevada Operations Office.

EPA, see U.S. Environmental Protection Agency.

FFACO, see *Federal Facility Agreement and Consent Order*.

Federal Facility Agreement and Consent Order. 1996 (as amended). Agreed to by the State of Nevada, the U.S. Department of Energy, and the U.S. Department of Defense.

Moore, J., Science Applications International Corporation. Las Vegas. 1999. Memo to M. Todd (ITLV) entitled, "Background Concentrations for NTS and TTR Soil Samples," 3 February. Las Vegas, NV.

NAC, see *Nevada Administrative Code*.

NCRP, see National Council on Radiation Protection and Measurements.

NMBG, see Nevada Bureau of Mines and Geology.

NNSA/NSO, see U.S. Department of Energy, National Nuclear Security Administration Nevada Site Office.

NOAA, see National Oceanic and Atmospheric Administration.

NRS, see *Nevada Revised Statutes*.

National Council on Radiation Protection and Measurements. 1999. *Recommended Screening Limits for Contaminated Surface Soil and Review of Factors Relevant to Site-Specific Studies*, Report No. 129. Bethesda, MD.

National Oceanic and Atmospheric Administration. 2002. "Precipitation Summary." As accessed at http://www.sord.nv.doe.gov/home_climate.htm on 13 November.

Nevada Administrative Code. 2002a. NAC 445A, "Water Controls." Carson City, NV.

Nevada Administrative Code. 2002b. NAC 459, "Hazardous Materials." Carson City, NV.

Nevada Bureau of Mines and Geology. 1998. *Mineral and Energy Resource Assessment of the Nellis Air Force Range*, Open-File Report 98-1. Reno, NV.

Nevada Revised Statutes. 1998. NRS 459.400-459.600, "Disposal of Hazardous Waste." Carson City, NV.

USGS, see U.S. Geological Survey.

U.S. Department of Energy. 1993. DOE Order 5400.5 Change 2, "Radiation Protection of the Public and the Environment." Washington, D.C.

U.S. Department of Energy, National Nuclear Security Administration Nevada Operations Office. 2002. *Industrial Sites Quality Assurance Project Plan, Nevada Test Site, Nevada*, Rev. 3, DOE/NV-372. Las Vegas, NV.

U.S. Department of Energy, National Nuclear Security Administration Nevada Site Office. 2003. *Corrective Action Investigation Plan for Corrective Action Unit 322: Areas 1 and 3 Release Sites and Injection Wells, Nevada Test Site, Nevada*, Rev. 0, DOE/NV--901. Las Vegas, NV.

U.S. Department of Energy, Nevada Operations Office. 1994. *Project Management Plan*, Rev. 0. Las Vegas, NV.

U.S. Department of Energy, Nevada Operations Office. 1996. *Final Environmental Impact Statement for the Nevada Test Site and Off-Site Locations in the State of Nevada*, DOE/EIS-0243. Las Vegas, NV.

U.S. Environmental Protection Agency. 1991. *Guidance on RCRA Corrective Action Decision Documents*, EPA/540/G-91/011. Washington, DC: Office of Research and Development.

U.S. Environmental Protection Agency. 1994. *Final RCRA Corrective Action Plan*, EPA/520-R-94-004. Washington, DC: Office of Solid Waste and Emergency Response.

U.S. Environmental Protection Agency. 2000. *Data Quality Objectives Process for Hazardous Waste Site Investigations*, EPA/600/R-00/007. Washington, DC: Office of Environmental Information.

U.S. Environmental Protection Agency. 2002. *Region IX Preliminary Remediation Goals (PRGs)*. As accessed at www.epa.gov/region09/waste/sfund/prg/index.htm on 8 January. Prepared by S.J. Smucker. San Francisco, CA.

U.S. Geological Survey. 2002. "USGS/DOE Nevada Water Use Wells," as accessed at http://nevada.ugsgs.gov/doe_nv/wateruse/ on 19 June.

Winograd, I.J., and W. Thordarson. 1975. *Hydrologic and Hydrochemical Framework South-Central Great Basin, Nevada-California, with Special Reference to the Nevada Test Site*, USGS Professional Paper 712C. Washington, DC: U.S. Government Printing Office.

Appendix A

Corrective Action Investigation Results for CAU 322

A.1.0 Introduction

This appendix details corrective action investigation activities and analytical results for CAU 322. Corrective Action Unit 322 is located in Areas 1 and 3 of the NTS (Figure 1-1 of the main document), and is comprised of the three CASs listed below:

- 01-25-01, AST
- 03-25-03, AST and Mud Plant
- 03-20-05, Injection Well

Corrective Action Site 01-25-01 is located in Area 1 of the NTS and consists of a release from an AST that once contained diesel fuel.

Corrective Action Site 03-25-03 is located in Area 3 of the NTS, in an area referred to as the Mud Plant and AST Diesel Release, and consists of two distinct release sites: Area A which consists of a release from an AST and fueling station west of the Mud Plant and Area B which consists of multiple potential releases in the area immediately to the east of the Mud Plant where diesel-fueled equipment and heavy vehicular traffic once resided.

Corrective Action Site 03-20-05 is located in Area 3 and consists of potential releases from the operations at the Lawrence Livermore National Laboratory (LLNL) BOP Shop including three in-ground cleaning/holding tanks and an injection well located approximately 65 ft from the southeast corner of the BOP Shop. Two of the three cleaning/holding tanks and the injection well are posted as containing "Underground Radiation".

This CAU was investigated because process knowledge indicated the associated CASs were the site of fuel spillage and/or radiation contamination at levels that may be considered to be hazardous or radioactive waste by current standards. The CAI was conducted in accordance with the CAU 322 CAIP as developed under the FFACO (1996).

Additional information regarding the history of each site, planning, and the scope of the investigation is presented in the CAU 322 CAIP (NNSA/NSO, 2003a).

A.1.1 Project Objectives

The primary objective of the investigation was to provide sufficient information and data to develop appropriate corrective action alternatives for each CAS in CAU 322. This objective was achieved by identifying the absence or presence of COPCs, the nature of the COCs (i.e., COPCs at concentrations above PALs), and the vertical and lateral extent of the COCs.

The selection of soil and/or waste characterization sample locations was based on site conditions, and the strategy developed during the DQO process as outlined in the CAU 322 CAIP. The sampling strategy primarily involved bias sample locations.

A.1.2 Content

This appendix contains information and data in sufficient detail to support the selection of a preferred corrective action alternative in the CADD. The contents of this appendix are as follows:

- Section A.1.0 describes the investigation background, objectives, and content
- Section A.2.0 provides an investigation overview
- Section A.3.0 through Section A.5.0 provides CAS-specific information regarding the field activities, sampling methods, and laboratory analytical results from investigation sampling
- Section A.6.0 summarizes waste management activities
- Section A.7.0 discusses the quality assurance (QA) and QC procedures followed and results of the QA/QC activities
- Section A.8.0 is a summary of the investigation results
- Section A.9.0 lists the cited references

The complete field documentation and laboratory data, including field activity daily logs (FADLs), sample collection logs (SCLs), analysis request/chain-of-custody forms (AR/COCs), soil sample descriptions, laboratory certificates of analyses, analytical results, and surveillance results are retained in project files as hard copy files or electronic media.

A.2.0 Investigation Overview

Field investigation and sampling activities for the CAU 322 CAI were conducted from April 12 through September 16, 2004. Table A.2-1 lists the CAI activities conducted at each of the CASs.

Table A.2-1
Corrective Action Investigation Activities Conducted at Each Corrective Action Site to Meet Corrective Action Investigation Plan Requirements

Corrective Action Investigation Activities	Corrective Action Site		
	01-25-01	03-25-03	03-20-05
Inspected CAS system components	X	X	X
Conducted surface land area radiological surveys	X	X	X
Collected biased soil samples	X	X	X
Field screened samples for alpha and beta/gamma radiation	X	X	X
Field screened soil samples for volatile organic compounds (Decision I sampling only)	X		
Field screened soil samples for total petroleum hydrocarbons via on-site gas chromatograph	X	X	X
Submitted select samples for off-site laboratory analysis	X	X	X
Removed minor surface and near surface contamination and collected confirmation samples		X	X
Conducted waste characterization sampling			X
Performed swipe sampling for removable radioactivity and/or metals		X	X

The investigation and sampling program was managed in accordance with the requirements set forth in the CAU 322 CAIP (NNSA/NSO, 2003a). Field activities were performed in accordance with the approved CAU 322 site-specific health and safety plan (SNJV, 2003) which is consistent with the DOE Integrated Safety Management System. Samples were collected and documented following approved protocols and procedures indicated in the CAU 322 CAIP (NNSA/NSO, 2003a). Quality control samples (e.g., field blanks, equipment rinsate blanks, trip blanks, and duplicate samples) were collected as required by the *Industrial Sites Quality Assurance Project Plan* (QAPP) (NNSA/NV, 2002) and approved procedures. During field activities, waste minimization practices were followed according to approved procedures, including segregation of waste by waste stream.

Weather conditions at the site varied to include sun (moderate to high temperatures), rain, intermittent cloudiness, and light to strong winds. Winds and storms (accompanied by lightening) occasionally delayed site operations.

The CASs were investigated by various combinations of sampling potential contaminant sources, radiological surface screening and surveys, and surface and subsurface soil sampling. Surface soil samples were collected by hand. Subsurface soil samples were collected using hand augering and drilling operations. Investigation intervals and soil samples were field screened for VOCs, alpha and beta/gamma radiation, and TPH at specific locations. The results were compared against screening levels to guide in the CAS-specific investigations. Samples were shipped to off-site laboratories to be analyzed for appropriate chemical and radiological parameters.

Except as noted in the following CAS-specific sections, CAU 322 sampling locations were accessible and sampling activities at planned locations were not restricted by buildings, storage areas, active operations, or aboveground/underground utilities. Required sampling step-out locations were accessible and remained within anticipated spatial boundaries except where otherwise noted.

Section A.2.1 through Section A.2.7 provide the investigation methodology, site geology and hydrology, and laboratory analytical information. Additional activity-specific details for the individual CASs are presented in Section A.3.0 through Section A.5.0.

A.2.1 Preliminary Conceptual Models

The revised conceptual site models for CAU 322 are generally consistent with the preliminary conceptual site models provided in the CAU 322 CAIP. Variations to the CSMs are discussed in detail in the CAS-specific sections.

A.2.2 Sample Locations

Investigation locations selected for sampling were based on interpretation of existing engineering drawings, aerial and land photographs, interviews with former and current site employees, information obtained during site visits, and site conditions as provided in the CAU 322 CAIP. Sampling points for each site were selected based on the approach provided in the CAIP. The planned biased sample locations are discussed in text and shown on figures in the CAIP. All actual

sample locations are depicted on the figures included in Section A.3.0 through Section A.5.0. Some locations were modified slightly from planned positions due to field conditions and observations. In some cases, field-screening results (FSR) and/or laboratory analytical results determined the need for step-out sampling locations. Sample locations were staked, labeled appropriately, and surveyed with a GPS instrument. The actual locations have been plotted based on the coordinates collected by the GPS instrument. In addition to the sampling locations, the figures in Appendix D of this document show points of interest with their associated GPS coordinates.

A.2.2.1 Housekeeping Removal of Debris

Before the CAU 322 CAI, removal and/or disposition of housekeeping items were performed at CAS 03-20-05. Animal waste was removed from the interior of the LLNL BOP Shop, and vegetation surrounding the injection well and adjacent to the east side of the BOP Shop building was removed.

A.2.3 Investigation Activities

The investigation activities performed at CAU 322 were based on general field investigation activities discussed in the CAU 322 CAIP (NNSA/NSO, 2003a). The technical approach consisted of the activities listed in Section A.2-1. The investigation strategy allowed the nature and extent of contamination associated with each CAS to be established. The following sections describe the specific investigation activities that took place at CAU 322.

A.2.3.1 Surface Radiological Surveys

Surface radiological land surveys were performed on all three CASs within CAU 322 during the CAI. The surveys were performed to identify the presence and extent of surficial beta/gamma-emitting radiological contaminants at activities statistically greater than background. This was done using a TSA Model PRM-470B scintillation detector in conjunction with a Trimble Pathfinder Pro XRS™ Global Positioning Receiver with TSCI™ Datalogger. The CASs surveyed were:

- CAS 01-25-01
- CAS 03-25-03
- CAS 03-20-05

The radiological land area survey for these CASs generally did not indicate the presence of radiological contamination above background levels.

A.2.3.2 Site Walk-Overs

Site walkovers were performed on the CASs within CAU 322. Observations were made to identify biased sampling locations (e.g., stained soil, unidentified or out-of-place objects).

A.2.3.3 Field Screening

Field-screening activities for VOCs, TPH, and alpha and beta/gamma radiation were performed as specified in the CAU 322 CAIP. The field-screening level (FSL) for VOC headspace was established at 20 ppm or 2.5 times background, whichever was greater. The TPH FSL was established at 75 ppm. Site-specific FSLs for alpha and beta/gamma radiation were defined as the mean background activity level plus two times the standard deviation of readings from 10 background locations selected near each CAS. The radiation FSLs are instrument-specific and were established for each instrument and CAS prior to use.

All field screening for VOCs was conducted using a flame ionization detector (FID) during Decision I activities at all CASs. Alpha and beta/gamma radiation screening was performed at each CAS using a handheld alpha and beta/gamma survey instrument. Field screening for TPH was conducted using a SRI Gas Chromatograph.

The CAS-specific sections of this document identify the CASs where field screening was conducted and how the FSLs were used to aid in the selection of sample locations. Field-screening results are recorded on sample collection logs that are retained in project files.

A.2.3.4 Surface and Subsurface Sampling

Intrusive investigation activities (i.e., surface and subsurface soil sampling), were conducted at all CASs within CAU 322 to support Decision I and Decision II investigation activities. Soil samples were collected using “scoop and trowel” (surface hand-grab sampling), hand auger, backhoe, and roto sonic drilling. Field screening for alpha and beta/gamma radiation was conducted during sample collection to both guide the investigation and serve as a health and safety control to protect the

sampling team. Labeled sample containers were filled according to the following sequence: total VOCs and TPH-gasoline-range organics (GRO) sample containers were filled with soil directly from the surface location, backhoe bucket, or core bag, followed by the collection of soil for VOC field screening using headspace analysis as appropriate. Additional soil was transferred into an aluminum pan, homogenized, and field screened for alpha and beta/gamma radiation. All remaining sample containers were then filled. Excess soil was returned to its original location.

Surface soil samples were collected from 0.0 to 0.5 ft bgs at biased locations focusing on stained soil, potential effluent locations, or areas with elevated radiological measurements. Subsurface soil samples were collected as a continuation at a surface soil sample location where staining was noted and/or analytical results indicated contamination.

A.2.3.4.1 *Surface Radiological Surveys and Swiping*

To support unrestricted release determinations per the *NV/YMP Radiological Control Manual* (DOE/NV, 2000), radiological surveys were performed at all CASs using a NE Technology Electra with dual-alpha and beta/gamma radiation scintillation probe. Swipe samples were also collected for determination of removable activity at the injection well, holding tanks, BOP Shop floor, and all lids covering the tanks and well at CAS 03-20-05. Both the surveys and swipe samples indicated all surfaces met unrestricted release criteria (Alderson, 2004). A datalogger was used to measure radiation levels at 10-ft intervals within the injection well sump, to the liquid level depth of 62 ft bgs. The interior walls of the holding tanks within the BOP Shop, and the interior walls of the casing surrounding the injection well were also screened using swipe samples. The analytical results of the swipe samples are presented in Section A.4.0.

A.2.3.4.2 *Waste Characterization and Sampling*

Characterization of CAS-specific soils and liquids was performed to support disposal of these items during anticipated closure activities. The information collected at CAS 03-20-05 was used to determine if the holding tank/sump and injection well sump liquids in question could be acting as a source of potential soil contamination. Investigation methods included visual inspection, radiological surveys, swipe sample collection, and direct sampling of feature contents. Waste characterization

activities were intended to gather adequate information and data about the CAS to support decisions regarding the disposal of materials located within the CAS.

Samples were analyzed in accordance with the procedures specified in the CAU 322 CAIP. The specific analyses for CAS 03-20-05 are listed and the analytical results are compared to the Federal limits for hazardous waste (40 CFR 261 [CFR, 2002]), NDEP hydrocarbon action limit, landfill acceptance criteria, and the limits in the NTS performance objective criteria (POC) (BN, 1995). The POC limits have been established for NTS hazardous waste generators to ensure that all hazardous waste being shipped off-site contains no “added radioactivity.”

Specific waste characterization sampling and analysis were conducted on the following potential waste streams at CAS 03-20-05:

- Liquid contents of the holding tanks within the BOP Shop
- Liquid contents of the holding tank sumps within the BOP Shop
- Liquid within the injection well sump

A.2.3.4.3 Sample Location Documentation

A GPS instrument was used for determining the sample location coordinates as well as CAS points of interest. Appendix D presents this data in both tabular and graphic forms.

A.2.4 Laboratory Analytical Information

Chemical and radiological analyses were performed by Paragon Analytics, Inc., Fort Collins, Colorado. The analytical parameters and laboratory analytical methods used to analyze investigation samples are listed in Table A.2-2. Organic and inorganic analytical results are reported in this appendix if they were detected at or above the minimum reporting levels (MRLs) established in Table 3-3 of the CAU 322 CAIP (NNSA/NSO, 2003a). Radionuclide analytical results are reported in this appendix if they are detected at or above minimum detectable concentrations (MDCs).

Validated analytical data for CAU 322 investigation samples have been compiled and evaluated to confirm the presence of contamination and define the extent of contamination, if present. The analytical results for each CAS are presented in Section A.3.0 through Section A.5.0. The analytical results have been compared to MRLs or MDCs as appropriate, and only those above MRLs or MDCs

Table A.2-2
Laboratory Analytical Parameters and Methods,
CAU 322 Investigation Samples

Analytical Parameter	Analytical Method
Total volatile organic compounds	SW-846 8260B ^a
Total semivolatile organic compounds	SW-846 8270C ^a
Total petroleum hydrocarbons - gasoline-range organics	SW-846 8015B (modified) ^a
Total petroleum hydrocarbons - diesel-range organics	
Polychlorinated biphenyls	SW-846 8082 ^a
Total <i>Resource Conservation and Recovery Act</i> (RCRA) metals ^b	Water - SW-846 6010B/7470A ^a Soil - SW-846 6010B/7471A ^a
Total Beryllium	
Toxicity characteristic leaching procedure (TCLP) volatile organic compounds	SW-846 1311/8260B ^a
TCLP semivolatile organic compounds	SW-846 1311/8270C ^a
TCLP RCRA metals ^b	SW-846 1311/6010B/7470A ^a
Tritium	Paragon Method 754/704
Gamma-Emitting Radionuclides	Water - EPA 901.1 Soil - HASL-300
Isotopic Uranium	Water - ASTM D3972-02 Soil - ASTM C1000-00
Isotopic Plutonium	Water - ASTM D3865-02 Soil - ASTM C1001-90
Strontium-90	Water - ASTM D5811-00 Soil - HASL-300

^aU.S. Environmental Protection Agency (EPA), *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods*, 3rd Edition, Parts 1-4, SW-846 CD ROM. Washington, DC. (EPA, 1996)

^bArsenic, barium, cadmium, chromium, lead, mercury, selenium, and silver

are included in CAS-specific tables. The complete laboratory data packages are available in the project files.

The analytical parameters are CAS-specific and were selected through the application of site process knowledge according to the EPA's *Guidance for the Data Quality Objectives Process* (EPA, 1994b). Samples collected during step-out sampling were only analyzed for the COPCs that exceeded PALs in the original samples. Bioassessment samples were not collected because FSRs and observations did not indicate the need.

A.2.5 Comparison to Action Levels

Chemicals and radionuclides detected in samples at concentrations greater than ALs are identified as COCs. If COCs are present, corrective action must be considered for the CAS. The PALs for the CAU 322 investigation were identified and agreed to during the DQO process. The FALs are defined in Section 3.1 of this CADD.

Sample data that exceed MRLs are tabulated in the CAS-specific sections that follow. Results that are greater than FALs (a subset of those that exceed MRLs) are identified by bold text in the corresponding tables and discussed in Section A.3.0 through Section A.5.0.

Nondetected results and results below MRLs have been excluded to minimize the size of this document. However, the unedited dataset for CAU 322 is retained in an electronic format in the project files.

A.2.6 Geology

Regional native surface soil consists of poorly graded, moderately consolidated, alluvial silty sands with gravel, and some cobble-sized volcanic and sedimentary detritus. Subsurface soil ranged from gravelly sands with fines to well-graded sands. The percentage of organic matter in the soil is low and decreases with depth beyond the native soil interface.

Auger refusal (buried railroad tie) was encountered during hand-auger sampling at CAS 01-25-01 at locations A01 and A02 at a depth of 30 in. bgs at each location. However, a backhoe was able to unearth the railroad tie and soil samples were collected at deeper intervals.

A general field description for each sample was recorded on SCLs. A more detailed description of the regional geology for the NTS is provided in the CAU 322 CAIP (NNSA/NSO, 2003a).

A.2.7 Hydrology

Dry washes provide channels that concentrate surface runoff; however, there is no perennial stream flow in the region. Surface topography at the CAU 322 CASs range from generally flat at CASs 03-25-03 and 03-20-05 to steeply sloping outside the AST berm at CAS 01-25-01.

Due to the depth to groundwater and climatic conditions, groundwater at the NTS in Areas 1 and 3 is not expected to have been impacted by COPCs. In Area 1, the depth to groundwater is estimated to be 750 ft bgs based on depth to water found at the UE-16d Eleana Water Well located some 3,000 ft from the CAS. In Area 3, the closest well is designated as USGS Water Well A, and the depth to water here is approximately 1,610 ft bgs. (Winograd and Thordarson, 1975).

No saturated zones (e.g., perched water, contaminant saturation) were found anywhere in the subsurface adjacent to or below the CASs, nor were saturated intervals identified during sampling activities.

Potential evapotranspiration at the NTS is significantly greater than precipitation, thus limiting vertical migration of contaminants. The annual average precipitation for the area associated with all CASs within CAU 322 is approximately 5.5 to 6.6 in. per year (DRI, 1985). The potential annual evaporation is the dominant factor influencing the movement of water in the upper saturated zone. Therefore, recharge to groundwater from precipitation is not significant at the NTS and does not provide a significant mechanism for migration of contaminants to groundwater.

A.3.0 CAS 01-25-01, AST Release

The location of the former AST is located in Area 1 of the NTS, within the boundaries of the Shaker Plant, and is located in the northern portion of the plant grounds. The berm in which the AST was located is constructed of earth and gravel, and the berm floor contains several pieces of large wooden plywood for tank support. Additional pieces of heavy railroad ties were discovered under the berm floor surface while conducting backhoe excavation. The berm once contained a 10,000 gallon diesel fuel AST, which has been relocated to a concrete berm approximately 40 ft to the southeast of the CAS. The AST once provided fuel to the Shaker Plant for its operation. The terrain surrounding the AST drops off steeply to the entire north side of the berm. Drop-offs of a less severe sloping also occur to the west and southwest of the AST. The pipeline running from the current AST location to the Shaker Plant and an electrical substation bound the CAS immediately to the east. Additional detail is provided in the CAIP (NNSA/NSO, 2003a).

A.3.1 Corrective Action Investigation

A total of 20 soil samples (including 2 field duplicates) were collected during investigation activities at CAS 01-25-01. The sample identification numbers (IDs), locations, types and analyses are listed in Table A.3-1. The sample locations are shown on Figure A.3-1. The specific CAI activities conducted to satisfy the CAIP requirements at this CAS are described in the following sections.

A.3.1.1 Deviations

There were no significant deviations to the CAIP requirements at this CAS. However, the visual assessment of the site during sampling activities and field screening analyses indicated the presence of TPH-DRO contamination within the floor of the berm. The sampling strategy was altered to account for this evidence. All samples submitted to the laboratory from this CAS were requested to be analyzed for TPH-DRO analysis.

Table A.3-1
Samples Collected at CAS 01-25-01, AST

Sample Location	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
A01	322A001	0 - 0.5	Soil	SC	Set 1, Set 2
	322A002	2 - 3	Soil	SC	Set 1, Set 2
A02	322A003	0 - 0.5	Soil	SC, MS/MSD	Set 1, Set 2
	322A004	2 - 3	Soil	SC	Set 2, Set 3
	322A005	2 - 3	Soil	Field Duplicate of 322A004	Set 2, Set 3
	322A009	4 - 5	Soil	SC	TPH-DRO
	322A010	6 - 7	Soil	SC	TPH-DRO
	322A011	9 - 10	Soil	SC	TPH-DRO
A04	322A008	0 - 0.5	Soil	SC, MS/MSD	TPH-DRO
	322A012	2 - 3	Soil	SC	TPH-DRO
	322A013	4 - 5	Soil	SC	TPH-DRO
	322A014	7 - 8	Soil	SC	TPH-DRO
	322A015	9 - 10	Soil	SC	TPH-DRO
A05	322A016	0 - 0.5	Soil	SC	TPH-DRO
	322A017	2 - 3	Soil	SC	TPH-DRO
	322A018	4 - 5	Soil	SC	TPH-DRO
	322A019	7 - 8	Soil	SC	TPH-DRO
	322A020	9 - 10	Soil	SC	TPH-DRO
NA	322A301	NA	Water	Trip Blank	Total VOCs
	322A302	NA	Water	Field Blank	Set 1, Set 2
	322A303	NA	Water	Equipment Rinsate Blank	TPH-DRO
	322A304	NA	Water	Field Blank	TPH-DRO

No samples were collected from sample location designation A03.

Set 1 = Total VOCs, Total SVOCs, Total RCRA Metals, Total Beryllium, PCBs, Gamma Spectroscopy

Set 2 = TPH-GRO, TPH-DRO

Set 3 = Total VOCs, Total SVOCs, Total RCRA Metals, Total Beryllium, PCBs

ft bgs = feet below ground surface

SC = Site characterization

MS/MSD = Matrix spike/matrix spike duplicate

NA = Not applicable

Figure A.3-1
Sample Location Map, CAS 01-25-01, AST Berm

A.3.2 Investigation Results

The following sections provide descriptions of the CAS-specific activities conducted to complete investigation activities as outlined in the CAIP. Investigation activities included, visual inspection of the CAS, field screening, and soil and liquid sampling and analysis.

A.3.2.1 Radiological Survey Results

A radiological walk-over survey was performed at CAS 01-25-01 in April 2004. The survey was performed to determine if radiological contamination is present in surficial soil at CAS 01-25-01 at concentrations statistically greater than surface soil from undisturbed background locations. The results were plotted on a color-coded contour map (Figure A.3-2).

Measurements of the gamma radiation emission rate for surface soil were taken with a TSA Systems Model PRM-470B handheld plastic scintillator over an area of approximately 1,386 square feet (ft²). A total of 370 data points were recorded at this site with a mean gamma radiation emission rate of 138 counts per second versus the mean undisturbed background radiation emission rate of 154 counts per second. The maximum gamma radiation emission rate was 175 counts per second. This rate is approximately 1.1 times the mean undisturbed background gamma emission rate (Alderson, 2004).

A.3.2.2 Sampling

No obvious release of contaminants was observed during the visual inspection of the site surface.

Decision I sampling activities included the collection of two surface and shallow subsurface soil samples from western and eastern ends of the berm where the fuel input and output locations were believed to have been located. Visual examination of the extracted samples indicated the presence of petroleum hydrocarbons adhering to the subsurface material. Laboratory analyses indicated the presence of high level of TPH-DRO (i.e., above the PAL) at both sample locations at both depths collected. Additional soil sampling at increased depths was attempted by hand collection; however, refusal was met at approximately 3 ft bgs, and a backhoe was brought in to collect samples. No other COPCs were identified.

Figure A.3-2
Radiological Survey Map for CAS 01-25-01, AST Berm

Decision II sampling activities included the collection of additional subsurface samples at the location within the berm with the highest levels of TPH-DRO contamination (i.e., location A02). This coincides with the end of the AST where fuel was added, (i.e., the west end of the berm). This location was excavated to the depth determined to be practical based on the berm's physical location and for safety considerations (approximately 10 ft bgs).

Samples were collected as outlined in the CAU 322 CAIP (NNSA/NSO, 2003) and submitted for laboratory analysis.

A.3.2.3 Field Screening

Soil samples were field screened for VOCs, TPH, and alpha and beta/gamma radiation. The FSRs were compared to FSLs to guide subsequent sampling decisions, with the exception of the samples collected from within the berm, where practical and safety constraints limited the depth of sample collection. The VOC headspace and alpha and beta/gamma radiation FSLs were not exceeded during sampling activities. The TPH FSRs indicated that the deepest sample collected from location A02 within the berm was still above the FSL for TPH-DRO.

A.3.2.4 Sample Analysis

Investigation samples were analyzed for the CAIP-specified COPCs which included total VOCs, total SVOCs, TPH (DRO/GRO), total RCRA metals and beryllium, and PCBs. The analytical parameters and laboratory methods used to analyze the investigation samples are listed in Table A.2-2. Table A.3-1 lists the sample-specific analytical suite for CAS 01-25-01.

A.3.2.5 Analytes Detected Above Minimum Reporting Limits

Analytical results from the soil samples with concentrations exceeding MRLs or MDCs are summarized in the following sections. These results are compared to PALs and are a subset of the results that exceed MRLs or MDCs. Results greater than PALs are identified by bold text in the analytical tables. A portion of the analytical results for this CAS were rejected during validation; however, these rejected data did not adversely impact closure decisions as discussed in Appendix B, Section B.1.4.

A.3.2.5.1 Total VOCs

Total VOC analytical results for soil samples collected at CAS 01-25-01, which were detected above MRLs, are presented in Table A.3-2. No VOCs were detected in soil samples above PALs.

**Table A.3-2
Soil Sample Results for Total VOCs
Detected Above Minimum Reporting Limits at CAS 01-25-01, AST**

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (µg/kg)			
			1,3,5-Trimethylbenzene	Acetone	P-Isopropyltoluene	Tetrachloroethene
Preliminary Action Levels ^a			70,000	6,000,000	NI	3,400
A02	322A004	2 - 3	11	210	5.9	8.7
	322A005	2 - 3	6.7	120	--	--

^aBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002)

ft bgs = Feet below ground surface

µg/kg = Micrograms per kilogram

A.3.2.5.2 Total SVOCs

Total SVOC analytical results for soil samples collected at CAS 01-25-01 were not detected above the MRLs or the PALs.

A.3.2.5.3 Total RCRA Metals and Beryllium

Total RCRA metals and beryllium analytical results for soil samples collected at CAS 01-25-01, which were detected above MRLs, are presented in Table A.3-3. No metals were detected in soil samples above PALs.

A.3.2.5.4 PCBs

Analytical results for PCBs in soil samples collected at CAS 01-25-01 did not exceed the MRLs or PALs.

**Table A.3-3
Soil Sample Results for Metals Detected
Above Minimum Reporting Limits at CAS 01-25-01, AST**

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)					
			Arsenic ^a	Barium ^b	Beryllium ^b	Chromium ^b	Lead ^b	Selenium ^b
Preliminary Action Levels			23	67,000	1,900	450	750	5,100
A01	322A001	0 - 0.5	6.1	230 (J)	0.93 (J)	24	13 (J)	0.98
	322A002	2 - 3	6.6	250 (J)	1.1 (J)	13	12 (J)	0.98 (J)
A02	322A003	0 - 0.5	4.9	180 (J)	--	9.4	9.6 (J)	--
	322A004	2 - 3	11	320 (J)	0.74 (J)	10	9 (J)	--
	322A005	2 - 3	11	260 (J)	0.77 (J)	11	8.7 (J)	1.1 (J)

^aBased on the background concentrations for metals. Background is considered the mean plus two times the standard deviation for sediment samples collected by the Nevada Bureau of Mines and Geology throughout the Nevada Test and Training Range (NBMG, 1998; Moore, 1999).

^bBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002).

ft bgs = Feet below ground surface

mg/kg = Milligrams per kilogram

J = Estimated value

-- = Not detected above minimum reporting limits

A.3.2.5.5 TPH-GRO and TPH-DRO

Analytical results for TPH-GRO and TPH-DRO in soil samples collected at CAS 01-25-01 that exceeded the MRLs are presented in Table A.3-4. Samples collected at both Decision I locations indicated TPH-DRO concentrations above the PALs. Location A02 was chosen for further sampling to define the depth of contamination. Samples collected from location A02 up to 10 ft bgs all contained TPH-DRO above the PAL (highest concentration is 7,000 mg/kg). The concentrations of TPH-DRO decreased with increasing depth (see Figure A.3-3). Sampling was halted at approximately 10 ft bgs due to both physical and safety considerations.

A.3.2.5.6 Gamma-Emitting Radionuclides

Analytical results for gamma-emitting radionuclides in soil samples collected at CAS 01-25-01, that exceeded MDCs are presented in Table A.3-5. No gamma-emitting radionuclides were detected above PALs.

**Table A.3-4
Soil Sample Results for TPH (DRO and GRO) Detected
Above Minimum Reporting Limits at CAS 01-25-01, AST**

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)	
			Gasoline Range Organics	Diesel Range Organics
Preliminary Action Levels ^a			100	100
A01	322A001	0 - 0.5	--	2,900 (J)
	322A002	2 - 3	--	480 (D)
A02	322A003	0 - 0.5	--	5,900 (J)
	322A004	2 - 3	10 (H)	7,000 (J)
	322A005	2 - 3	15 (H)	6,900 (D)
	322A009	4 - 5	--	6,700 (D)
	322A010	6 - 7	--	1,100 (D)
	322A011	9 - 10	--	140 (D)

^aBased on *Nevada Administrative Code*; Contamination of soil: Establishment of action levels (NAC, 2002)

ft bgs = Feet below ground surface

mg/kg = Milligrams per kilogram

D = A pattern resembling diesel was detected in the samples

H = The fuel pattern was in the heavier end of the retention time window for the analyte of interest

J = Estimated value; qualifier added to laboratory data, record accepted; surrogates diluted out

A.3.2.6 Contaminants of Concern

Based on the analytical results, the only COC identified was TPH-DRO within the AST berm.

A.3.3 Nature and Extent of Contamination

Analytical results from within the berm indicate TPH-DRO is present at concentrations above the PAL. Because sampling had to be halted at approximately 10 ft bgs due to safety considerations, a “clean” vertical sample was not obtained. The TPH-DRO concentrations for the five samples collected at location A01 were applied to a model in order to estimate the depth beneath the berm at which the TPH-DRO concentration fell below the PAL. Analytical results suggested that the adsorption of TPH-DRO with depth in the soil column is not a linear phenomenon. Application of a logarithmic adsorption model versus soil depth for the laboratory analytical results provides a linear correlation (correlation coefficient of -0.966 [Figure A.3-4]). Applying a conservative value of 50 ppm TPH-DRO (the PAL is 100 ppm) to the model resulted in a corresponding depth of 11.7 ft bgs (rounded off to 12 ft bgs, again as a conservative measure).

Figure A.3-3
Vertical Profile of TPH-DRO Concentrations for CAS 01-25-01, AST Berm

**Table A.3-5
Soil Sample Results for Gamma-Emitting Radionuclides
Detected Above Minimum Detectable Concentrations at CAS 01-25-01, AST**

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)			
			Actinium-228	Bismuth-214	Lead-212	Lead-214
Preliminary Action Levels ^a			5	5	5	5
Depth bgs (cm)			<15	<15	<15	<15
A01	322A001	0 - 0.5	1.93 (G)	0.85 (G)	1.66 (J)	1.04 (J)
A02	322A003	0 - 0.5	2.14 (G)	1.19 (G)	1.32 (J)	1.03 (J)

^aBased on the generic guidelines for residual concentrations of radium-226, radium-228, thorium-230, and thorium-232 as found in Chapter IV of DOE order 5400.5 Change 2 Radiation Protection of the Public and Environment. The PAL for these isotopes is specified as 5 picocuries per gram (pCi/g) averaged over the first 15 centimeters of soil and 15 pCi/g for deeper soils. For purposes of this document, 15 centimeters is assumed to be equivalent to 0.5 ft (6 inches) (DOE, 1993).

ft bgs = Feet below ground surface

cm = Centimeter

pCi/g = Picocuries per gram

< = Less than

G = Sample density differs by more than 15 percent of laboratory control sample density.

J = Estimated value. Qualifier added to laboratory data; record accepted. Sample does not meet counting geometry requirements.

Step-out samples located outside the berm at sample locations A04 and A05 indicated no TPH-DRO presence. Due to the physical constraints of the site, step-out samples were collected at only two locations. The TPH-DRO contamination was determined to be within the confines of the berm.

There is an estimated 267 yd³ of soil contaminated with TPH-DRO above the PAL at this CAS.

A.3.4 Revised Conceptual Site Model

While the CSM is satisfied for this CAS, the magnitude of the TPH-DRO contamination is significantly greater than originally thought. It was originally believed that no TPH-DRO contamination existed at this site. However, once the gravel covering of the berm floor was moved aside (a gravel thickness of 2 to 3 in.) and the first penetration into the underlying soil was made, it was clear TPH-DRO contamination existed. During the Decision I sampling, refusal was encountered at the 2 to 3 ft bgs depth at both sampling locations, requiring the use of a backhoe and the planning for Decision II sampling. The CSM indicated the contamination that might arise from TPH-DRO spillage/overfilling at this CAS would migrate both laterally and vertically. The Decision

A TPH-DRO concentration of 50 mg/kg was used as a conservative estimate of "depth to clean"
The "depth to clean" was determined to be 11.7 ft bgs (rounded off to 12 ft bgs)

Log (conc)	Depth
3.85	3
3.82	5
3.04	7
2.15	10
Corr coeff =	-0.966
r squared =	0.9320

Figure A.3-4
TPH-DRO Data Regression Plot for CAS 01-25-01, AST Berm

II sampling demonstrates vertical movement of TPH-DRO, and the step-out samples indicate that any lateral movement does not extend beyond the bounds of the berm.

A.4.0 CAS 03-25-03, AST Release and Mud Plant

Corrective Action Site 03-25-03 is located in Area 3 of the NTS. The CAS is divided into two “Areas” (A and B). Area A is in the western portion of the CAS and consists of a J-shaped berm which once housed a diesel fuel AST. The Area B portion of the CAS is located along the eastern side of the Area 3 Mud Plant, and is bounded to the west by the Mud Plant footprint, to the north by the Mud Disposal Crater (CAU 34) and to the east by the Mud Plant Pond (CAU 34).

Investigation activities at CAS 03-25-03 Area A included characterization sampling of selected locations to identify the presence and concentrations of COPCs, especially TPH-DRO which was historically documented to have spilled onto the surface at the AST and filling pump, and leaked from the piping from the AST. Based on information available at the time the CAIP was written, much of the spilled fuel was remediated, but it was reported that some remained at depth between 10 to 15 ft bgs.

Investigation activities at Area B include collection of data to complement the data obtained from CAU 34 conducted two years earlier. In the course of investigation activities for CAU 34, several locations and various depth were found to be contaminated with TPH-DRO. However, none of the TPH-DRO contamination was removed and the CAU 322 CAI was to augment the information from CAU 34 to identify any potential sources and the extent of the contamination.

The CSM for CAS 03-25-03 included potential soil contamination originating from COPCs associated with a leaking AST (Area A) and from potential unknown point sources and/or general activity associated with Mud Plant operations (Area B). Radioactive contamination resulting from safety experiments and atmospheric nuclear testing is not considered part of the CAS.

A.4.1 Corrective Action Investigation

A visual assessment of both areas (A and B) was made to identify any biasing factors such as staining and/or sheens that might indicate contamination to the soil. No biasing factors were noted at the site surface.

A total of 75 soil samples and 1 swipe sample were collected at CAS 03-25-03. The swipe sample was collected in Area B when a concrete pad was discovered under approximately 2 in. of soil that was removed because analytical results indicated the location was over the PAL for plutonium-239. The concrete pad was swipe sampled, and three step-out soil samples were collected around the hot spot. Thirty-six samples were collected from Area A of CAS 03-25-03 and thirty-nine samples were collected from Area B. These samples were analyzed for the parameters listed in Table A.4-1. Sample locations for Area A are shown on Figure A.4-1 and sample locations for Area B are shown in Figure A.4-2.

The CAI for CAS 03-25-03 Area B also used sample analytical results for TPH-DRO generated during the CAI for CAU 34. Table A.4-2 includes the samples collected during the CAI for CAU 34 that provided information used for the CAS 03-25-03 Area B investigation. These locations are also included on Figure A.4-2.

A.4.1.1 Deviations

There were no deviations to the CAIP requirements at this CAS. The investigation and sampling at CAS 03-25-03 is considered sufficient to meet the DQOs.

A.4.2 Investigation Results

The following sections provide descriptions of the CAS-specific activities conducted to complete investigation activities as outlined in the CAIP. Investigation activities included visual inspection of the CAS, collection of soil samples, collection of a swipe sample from the location of a localized area of elevated radiological activity, and sample analysis.

A.4.2.1 Radiological Survey Results

A radiological walk-over survey was performed at CAS 03-25-03 in April 2004. The survey was performed to determine if radiological contamination is present in surficial soil at CAS 03-25-03 at concentrations statistically greater than surficial soil from undisturbed background locations. The results were plotted on a color-coded contour map (Figure A.4-3).

Table A.4-1
Samples Collected at CAS 03-25-03, AST and Mud Plant
(Page 1 of 4)

Sample Location	Area	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
B01	A	322B007	0 - 0.5	Soil	SC	Sets 1, 2, 3, and 4
		322B038	2 - 3	Soil	SC	Sets 1 and 3
		322B069A	4.5 - 5.5	Soil	Confirmation	TPH-DRO
		322B070A	4.5 - 5.5	Soil	Confirmation	TPH-DRO
		322B071	4.5 - 5.5	Soil	Confirmation	TPH-DRO
		322B039	19 - 20	Soil	SC	Sets 1 and 3
B02	A	322B008	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B036	2 - 3	Soil	SC	Sets 1 and 3
		322B037	19 - 20	Soil	SC	Sets 1 and 2
B03	A	322B009	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B033	2 - 3	Soil	SC	Sets 1 and 3
		322B034	2 - 3	Soil	Field Duplicate of 322B033	Sets 1 and 3
		322B035	19 - 20	Soil	SC	Sets 1 and 3
B04	A	322B010	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B028	2 - 3	Soil	SC	Sets 1 and 3
		322B032	19 - 20	Soil	SC, MS/MSD	Sets 1 and 3
		322B068A	0 - 0.5	Soil	Confirmation	TPH-DRO
B05	A	322B011	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B023	3 - 4	Soil	SC	Sets 1 and 3
		322B024	7 - 8	Soil	SC	Sets 1 and 3
		322B025	11 - 12	Soil	SC	Sets 1 and 3
		322B026	15 - 16	Soil	SC	Sets 1 and 3
		322B027	19 - 20	Soil	SC	Sets 1 and 3
B06	A	322B001	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B003	2 - 3	Soil	SC	Sets 1, 4, and TPH-GRO
		322B004	6 - 7	Soil	SC	Sets 1, 4, and TPH-GRO
		322B021	15 - 16	Soil	SC	Sets 1 and 3

Table A.4-1
Samples Collected at CAS 03-25-03, AST and Mud Plant
(Page 2 of 4)

Sample Location	Area	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
B07	A	322B002	0 - 0.5	Soil	SC	Sets 1, 3 and 4
		322B005	2 - 3	Soil	SC	Sets 1, 3 and 4
		322B006	5 - 6	Soil	SC	Sets 1, 3 and 4
		322B022	15 - 16	Soil	SC	Sets 1 and 3
B08	B	322B012	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B053	2 - 3	Soil	SC	Sets 1 and 3
		322B054	14 - 15	Soil	SC	Sets 1 and 3
		322B055	14 - 15	Soil	Field Duplicate of 322B054	Sets 1 and 3
		322B072	4 - 5	Soil	SC	TPH-DRO
		322B073	4 - 5	Soil	Field Duplicate of 322B072	TPH-DRO
B09	B	322B013	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B051	2 - 3	Soil	SC	Sets 1 and 3
		322B052	14 - 15	Soil	SC, MS/MSD	Sets 1 and 3
B10	B	322B014	0 - 0.5	Soil	SC, MS/MSD	Sets 1, 2, 3 and 4
B11	B	322B015	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B047	2 - 3	Soil	SC	Sets 1 and 3
		322B048	14 - 15	Soil	SC	Sets 1 and 3
B12	B	322B016	0 - 0.5	Soil	SC	Sets 1, 2, 3, and 4
		322B017	0 - 0.5	Soil	Field Duplicate of 322B016	Sets 1, 2, 3 and 4
		322B049	2 - 3	Soil	SC	Sets 1 and 3
		322B050	14 - 15	Soil	SC	Sets 1 and 3
B13	B	322B018	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B040	2 - 3	Soil	SC	Sets 1 and 3
		322B041	14 - 15	Soil	SC	Sets 1 and 3
B14	B	322B019	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B042	2 - 3	Soil	SC	Sets 1 and 3
		322B043	14 - 15	Soil	SC	Sets 1 and 3

Table A.4-1
Samples Collected at CAS 03-25-03, AST and Mud Plant
(Page 3 of 4)

Sample Location	Area	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
B15	B	322B020	0 - 0.5	Soil	SC	Sets 1, 2, 3 and 4
		322B044	2 - 3	Soil	SC	Sets 1 and 3
		322B045	10 - 11	Soil	SC	Sets 1 and 3
		322B046	14 - 15	Soil	SC	Sets 1 and 3
B16	B	322B059	1 - 2	Soil	SC	Sets 1 and 3
		322B060	15 - 16	Soil	SC	Sets 1 and 3
		322B061	20 - 21	Soil	SC	Sets 1 and 3
B17	B	322B062	2 - 3	Soil	SC	Sets 1 and 3
		322B063	7 - 8	Soil	SC	Sets 1 and 3
B18	B	322B056	15 - 16	Soil	SC	Sets 1 and 3
		322B057	20 - 21	Soil	SC	Sets 1 and 3
		322B058	25 - 26	Soil	SC	Sets 1 and 3
B19	A	322B064	0 - 1	Soil	SC, MS/MSD	Sets 1, 2, 3 and 4
		322B065	15 - 16	Soil	SC	Sets 1 and 3
		322B066	19 - 20	Soil	SC	Sets 1 and 3
		322B067	19 - 20	Soil	Field Duplicate of 322B066	Sets 1 and 3
B20	B	322B068	2 - 3	Soil	SC	Sets 1 and 3
		322B069	6 - 7	Soil	SC	Sets 1 and 3
		322B070	9 - 10	Soil	SC	Sets 1 and 3
B21	B	322B074	4 - 5	Soil	SC, MS/MSD	TPH-DRO
B22	B	322B075	4 - 5	Soil	SC	TPH-DRO
B23	B	322B076	0 - 0.5	Soil	SC	Iso-Pu
B24	B	322B077	0 - 0.5	Soil	SC	Iso-Pu
B25	B	322B078	0 - 0.5	Soil	SC	Iso-Pu

Table A.4-1
Samples Collected at CAS 03-25-03, AST and Mud Plant
(Page 4 of 4)

Sample Location	Area	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
NA	NA	322B301	NA	Water	Trip Blank	Total VOCs
		322B302	NA	Water	Trip Blank	Total VOCs
		322B303	NA	Water	Trip Blank	Total VOCs
		322B304	NA	Water	Trip Blank	Total VOCs
		322B305	NA	Water	Trip Blank	Total VOCs
		322B306	NA	Water	Field Blank	Sets 1, 2, and 3
		322B307	NA	Water	Trip Blank	Total VOCs
		322B308	NA	Water	Trip Blank	Total VOCs
		322B309	NA	Water	Trip Blank	Total VOCs
		322B310	NA	Water	Field Blank	Sets 1, 2, and 3
		322B311	NA	Water	Field Blank	TPH-DRO

Set 1 = Total VOCs, Total SVOCs, Total RCRA Metals, PCBs, Total Beryllium
Set 2 = Gamma Spectroscopy
Set 3 = TPH-GRO, TPH-DRO
Set 4 = Isotopic Uranium, Isotopic Plutonium, Strontium-90

ft bgs = Feet below ground surface
NA = Not applicable
SC = Site characterization
MS/MSD = Matrix spike/matrix spike duplicate

Measurements of the gamma radiation emission rate for surficial soil were taken with a TSA Systems Model PRM-470B handheld plastic scintillator over an area of approximately 68,512 ft². A total of 5,724 data points were recorded at this site with a mean gamma radiation emission rate of 1,770 counts per second versus the mean undisturbed background radiation emission rate of 1,805 counts per second. The maximum gamma radiation emission rate was 2,241 counts per second. This rate is approximately 1.2 times the mean undisturbed background gamma emission rate (Alderson, 2004).

A.4.2.2 Inspection and Sampling

No obvious release of contaminants or biasing factors were observed at the surface of either Area A; or Area B during the visual inspection. Decision I sampling included collection of soil samples from

Figure A.4-1
Sample Location Map for CAS 03-25-03, AST Release
Area A, AST Berm

Figure A.4-2
Sample Location Map for CAS 03-25-03, AST Release
Area B, Mud Plant

Table A.4-2
Samples Collected During the CAU 34 CAI at CAS 03-25-03,
Area B (East of Mud Plant)

Sample Location	Sample Number	Depth (ft bgs)	Sample Matrix	Analyses
CS-01	CS0100	0 - 0.5	soil	TPH
	CS0101	0.5 - 1.5	soil	TPH
	CS0102	1.5 - 2.5	soil	TPH
CS-02	CS0200	0 - 0.5	soil	TPH
	CS0201	0.5 - 1.5	soil	TPH
	CS0202	1.5 - 2.5	soil	TPH
CS-03	CS0300	0 - 0.5	soil	TPH
	CS0301	0.5 - 1.5	soil	TPH
	CS0302	1.5 - 2.5	soil	TPH
	CS0306	6 - 7	soil	TPH
CS-04	CS0400	0 - 0.5	soil	TPH
	CS0401	1 - 2	soil	TPH
	CS0402	2 - 3	soil	TPH
CS-06	CS0601	1.5 - 2.5	soil	TPH
	CS0699	1.5 - 2.5	soil	TPH
	CS0610	10 - 12	soil	TPH
CS-07	CS0710	10 - 12	soil	TPH
CS-08	CS0806	6 - 7	soil	TPH
	CS0810	10 - 12	soil	TPH
CS-09	CS0902	2.5 - 3.5	soil	TPH
CS-10	CS1002	2.5 - 3.5	soil	TPH
	CS1006	6 - 7	soil	TPH

ft bgs = Feet below ground surface

Figure A.4-3
Radiological Survey Map for CAS 03-25-03, AST Release

predesignated locations throughout the CAS. Decision II soil sampling was necessary to define the extent of contamination at Area B. In addition a swipe sample was collected from a concrete pad located beneath a shallow soil layer where a elevated area of radiological activity was identified at Area B.

Confirmation soil samples were collected after the removal of a small amount of TPH-DRO contaminated soil at Area A.

A.4.2.3 Field-Screening Results

Field-screening results for VOCs using a FID provided no readings above the FSL of 20 mg/kg. Field-screening results obtained using a thermal desorption gas chromatograph with FID detector indicated the presence of TPH-DRO above the PAL at various locations and was used to guide additional sampling. Field-screening results for radiological contamination provided no results above background.

A.4.2.4 Sample Analysis

Investigation samples were analyzed for the CAIP-specified COPCs which included total RCRA metals and total beryllium, total VOCs, total SVOCs, PCBs, TPH (DRO/GRO), gamma-emitting radionuclides, isotopic uranium, isotopic plutonium, and strontium-90. The analytical parameters and laboratory methods used to analyze the investigation samples are listed in Table A.2-2. Table A.4-1 lists the sample-specific analytical suite for CAS 03-25-03.

A.4.2.5 Analytes Detected Above Minimum Reporting Limits

Analytical results from the soil samples with concentrations exceeding MRLs or MDCs are summarized in the following sections. These results are compared to PALs and are a subset of the results that exceed MRLs or MDCs. Results greater than PALs are identified by bold text in the analytical tables. A portion of the analytical results for this CAS were rejected during validation; however, these rejected data did not adversely impact closure decisions as discussed in Appendix B, Section B.1.4.

A.4.2.5.1 Total VOCs

Total VOC analytical results for soil samples collected at CAS 03-25-03, which were detected above MRLs, are presented in Table A.4-3. No VOCs were detected in soil samples above PALs.

Table A.4-3
Soil Sample Results for Total VOCs Detected Above
Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (µg/kg)
			Acetone
Preliminary Action Levels ^a			6,000,000
B08	322B053	2 - 3	23
B18	322B056	15 - 16	33
	322B057	20 - 21	36

^aBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002)

ft bgs = Feet below ground surface
µg/kg = Micrograms per kilogram

A.4.2.5.2 Total SVOCs

Total SVOC analytical results for soil samples collected at CAS 03-25-03, which were detected above MRLs, are presented in Table A.4-4. No SVOCs were detected in soil samples above PALs.

Table A.4-4
Soil Sample Result for Total SVOCs Detected Above Minimum
Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (µg/kg)
			Di-N-Butyl Phthalate
Preliminary Action Levels ^a			62,000,000
B07	322B002	0 - 0.5	370

^aBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002)

ft bgs = Feet below ground surface
µg/kg = Micrograms per kilogram

A.4.2.5.3 PCBs

Polychlorinated biphenyl analytical results for soil samples collected at CAS 03-25-03, which were detected above MRLs, are presented in Table A.4-5. No PCBs were detected in soil samples above PALs.

Table A.4-5
Soil Sample Results for PCBs Detected Above Minimum
Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (µg/kg)	
			Aroclor 1016	Aroclor 1254
Preliminary Action Levels			21,000	740
B08	322B012	0 - 0.5	--	94 (J)
B15	322B020	0 - 0.5	41	--

^aBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals (PRGs)* (EPA, 2002)

ft bgs = Feet below ground surface

µg/kg = Micrograms per kilogram

-- = Not detected above minimum reporting limits

J = Estimated value; qualifier added to laboratory data, record accepted; percent difference between columns >25.

A.4.2.5.4 Total RCRA Metals and Beryllium

Total RCRA metals and beryllium analytical results for soil samples collected at CAS 03-25-03, which were detected above MRLs, are presented in Table A.4-6. No metals were detected in soil samples above PALs.

A.4.2.5.5 TPH (DRO/GRO)

Total petroleum hydrocarbons analytical results for soil samples collected at CAS 03-25-03, which were detected above MRLs, are presented in Table A.4-7. Table A.4-7 also identifies the portion of CAS 03-25-03 from which each sample was collected (i.e., Area A or B). The results for each of these areas are discussed in following subsections.

Table A.4-6
Soil Sample Results for Metals Detected Above Minimum
Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release
(Page 1 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic ^a	Barium ^b	Beryllium ^b	Cadmium ^b	Chromium ^b	Lead ^b	Mercury ^b	Selenium ^b	Silver ^b
Preliminary Action Levels			23	67,000	1,900	450	450	750	310	5,100	5,100
B01	322B007	0 - 0.5	4.3	140	0.86	--	6.5	10	--	0.58 (J) ^c	--
	322B038	2 - 3	4.4	140	0.79	--	6	16	--	--	--
	322B039	19 -20	4.1	120	0.6	--	5.5	8	--	--	--
B02	322B008	0 - 0.5	4.6	200	0.83	--	6.3	13	--	0.81 (J) ^c	--
	322B036	2 - 3	5	140	0.87	--	6.7	11	--	--	--
	322B037	19 - 20	3.5	170	0.64	--	4.9	7.3	--	--	--
B03	322B009	0 - 0.5	4.3	130	0.81	--	6	11	--	--	--
	322B033	2 - 3	4.6	140	0.79	--	5.8	9.2	--	--	--
	322B034	2 - 3	4.2	150	0.78	--	5.7	10	--	0.63	--
	322B035	19 - 20	4	130	0.61	--	4.7	8.3	--	--	--
B04	322B010	0 - 0.5	4.6	250	0.75	--	6.4	27	--	--	--
	322B028	2 - 3	3	140	0.61	--	4.1	7.5	--	--	--
	322B032	19 - 20	5	150	0.68	--	7.6	11	--	--	--
B05	322B011	0 - 0.5	4	160	0.83	--	5.3	10	--	--	--
	322B023	3 - 4	4	160	0.64	--	4.3	9.5	--	--	--
	322B024	7 - 8	3.7	100	0.75	--	5.3	8.9	--	--	--
	322B025	11 - 12	3.9	82	0.79	--	5.2	9.6	--	--	--
	322B026	15 - 16	4.6	170	0.71	--	8.2	9.4	--	--	--
	322B027	19 - 20	4.5	120	0.62	--	6.3	7.4	--	--	--

Table A.4-6
Soil Sample Results for Metals Detected Above Minimum
Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release
(Page 2 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic ^a	Barium ^b	Beryllium ^b	Cadmium ^b	Chromium ^b	Lead ^b	Mercury ^b	Selenium ^b	Silver ^b
Preliminary Action Levels			23	67,000	1,900	450	450	750	310	5,100	5,100
B06	322B001	0 - 0.5	4.5	260	0.63	--	6.5	9.5	--	1 (J) ^c	--
	322B003	2 - 3	4.6	140	0.89	--	6.6	11	--	0.75 (J) ^c	--
	322B004	6 - 7	4.2	120	--	--	4	8.7	--	--	--
	322B021	15 - 16	3.7	160	0.86	--	4.8	9.8	--	--	--
B07	322B002	0 - 0.5	5.2	210	0.73	--	7.2	9.4	--	0.66 (J) ^c	--
	322B005	2 - 3	6	140	0.97	--	7.2	11	--	0.71 (J) ^c	--
	322B006	5 - 6	8	120	0.97	--	7.9	11	--	0.64 (J) ^c	--
	322B022	15 - 16	4.9	180	0.7	--	7.9	10	--	--	--
B08	322B012	0 - 0.5	5.6	770	0.7	--	17	15	--	0.65 (J) ^c	--
	322B053	2 - 3	4.2	580	0.62	--	14	12	--	--	--
	322B054	14 - 15	3.9	120	0.54	--	8	6.6	--	--	--
	322B055	14 - 15	4.6	150	0.64	--	6.9	9.4	--	--	--
B09	322B013	0 - 0.5	6.3	820	0.69	--	15	11	--	0.77 (J) ^c	--
	322B051	2 - 3	4.1	140	0.73	--	6.1	9.8	--	--	--
	322B052	14 - 15	3	130	--	--	8.1	6.1	--	--	--
B10	322B014	0 - 0.5	5.6	1,300	0.74	1.6 (J-) ^d	16	20	0.11	0.73 (J) ^c	--

Table A.4-6
Soil Sample Results for Metals Detected Above Minimum
Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release
(Page 3 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic ^a	Barium ^b	Beryllium ^b	Cadmium ^b	Chromium ^b	Lead ^b	Mercury ^b	Selenium ^b	Silver ^b
Preliminary Action Levels			23	67,000	1,900	450	450	750	310	5,100	5,100
B11	322B015	0 - 0.5	5.1	580	0.73	--	14	12	--	0.83 (J) ^c	--
	322B047	2 - 3	3.9	120	0.68	--	5.9	9.3	--	--	--
	322B048	14 - 15	3.3	91	--	--	4.3	6.8	--	--	--
B12	322B016	0 - 0.5	3.6	180	0.72	--	7	9.1	--	--	--
	322B017	0 - 0.5	4	200	0.72	--	6.2	12	--	0.52 (J) ^c	--
	322B049	2 - 3	3.5	140	0.6	--	5.5	7.9	--	--	--
	322B050	14 - 15	4.4	100	--	--	7.2	7	--	--	--
B13	322B018	0 - 0.5	5.6	680	0.74	--	15	11	--	--	--
	322B040	2 - 3	3.9	130	--	--	5.2	8.3	--	--	--
	322B041	14 - 15	3.9	110	0.84	--	6.9	11	--	0.56 (B)	--
B14	322B019	0 - 0.5	5.7	370	0.7	--	10	12	--	0.67 (J) ^c	--
	322B042	2 - 3	3.1	120	--	--	5.3	7.4	--	--	--
	322B043	14 - 15	4.3	88	0.56	--	8.3	7.9	--	0.55	--
B15	322B020	0 - 0.5	4.5	1,400	0.67	--	18	16	--	0.52 (J) ^c	--
	322B044	2 - 3	3.7	190	0.77	--	6	11	--	--	--
	322B045	10 - 11	3	210	--	--	3.2	13	--	--	--
	322B046	14 - 15	5.3	98	0.6	--	10	8	--	0.86	--

Table A.4-6
Soil Sample Results for Metals Detected Above Minimum
Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release
(Page 4 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic ^a	Barium ^b	Beryllium ^b	Cadmium ^b	Chromium ^b	Lead ^b	Mercury ^b	Selenium ^b	Silver ^b
Preliminary Action Levels			23	67,000	1,900	450	450	750	310	5,100	5,100
B16	322B059	1 - 2	4.9	360 (J) ^e	0.69 (J) ^f	--	8.8	11 (J) ^e	--	--	--
	322B060	15 - 16	5.3	120 (J) ^e	0.7 (J) ^f	--	7.7	12 (J) ^e	--	--	--
	322B061	20 - 21	5.7	140 (J) ^e	1.1 (J) ^f	--	8.1	11 (J) ^e	--	--	--
B17	322B062	2 - 3	5	140 (J) ^e	0.72 (J) ^f	--	6.3	12 (J) ^e	--	--	--
	322B063	7 - 8	2.7	98 (J) ^e	--	--	3.7	7.6 (J) ^e	--	--	--
B18	322B056	15 - 16	4.9	110 (J) ^e	--	--	12	8.6 (J) ^e	--	--	--
	322B057	20 - 21	5.6	210 (J) ^e	0.71 (J) ^f	--	11	9.3 (J) ^e	--	--	--
	322B058	25 - 26	4.4	150 (J) ^e	0.87 (J) ^f	--	5.5	9.3 (J) ^e	--	--	--
B19	322B064	0 - 1	4.5	130 (J) ^e	0.71 (J) ^f	--	6	11 (J) ^e	--	0.63	--
	322B065	15 -16	4.8	140 (J) ^e	0.81 (J) ^f	--	7.3	11 (J) ^e	--	0.73	--
	322B066	19 - 20	4.6	180 (J) ^e	0.71 (J) ^f	--	5.5	8 (J) ^e	--	--	--
	322B067	19 - 20	4.1	160 (J) ^e	0.73 (J) ^f	--	6.5	9.9 (J) ^e	--	--	--

Table A.4-6
Soil Sample Results for Metals Detected Above Minimum
Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release
(Page 5 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic ^a	Barium ^b	Beryllium ^b	Cadmium ^b	Chromium ^b	Lead ^b	Mercury ^b	Selenium ^b	Silver ^b
Preliminary Action Levels			23	67,000	1,900	450	450	750	310	5,100	5,100
B20	322B068	2 - 3	4.6	130	0.71	--	8.7	8.8	--	--	3.2
	322B069	6 - 7	5.5	210	0.69	--	13	16	--	--	--
	322B070	19 -20	4.6	110	0.86	--	6.5	9.9	--	0.77 (J-) ^g	--

^aBased on the background concentrations for metals. Background is considered the mean plus two times the standard deviation for sediment samples collected by the Nevada Bureau of Mines and Geology throughout the Nevada Test and Training Range (NBMG, 1998; Moore, 1999).

^bBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002)

^cQualifier added to laboratory data; record accepted. Value less than 5 times contamination in continuing calibration/method blank.

^dMatrix spike recovery outside control limits. Duplicate precision analysis (relative percent difference) outside control limits.

^eQualifier added to laboratory data; record accepted. Matrix spike recovery outside control limits.

^fQualifier added to laboratory data; record accepted. Serial dilution %D outside control limits. Matrix effects may exist.

^gNegative bias found in continuing calibration/method blank.

ft bgs = Feet below ground surface

mg/kg = Milligrams per kilogram

B = Analyte found in both sample and associated blank.

J = Estimated value.

J- = The result is an estimated quantity, but the result may be biased low.

-- = Not detected above minimum reporting limits

Table A.4-7
Soil Sample Results for TPH (DRO and GRO) Detected Above
Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release

Sample Location	Area	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)	
				Diesel Range Organics	Gasoline Range Organics
Preliminary Action Levels ^a				100	100
B01	A	322B038	2 - 3	140 (D, H, M)	--
B04		322B010	0 - 0.5	370 (H, M)	--
B08	B	322B012	0 - 0.5	72 (H, M)	--
		322B053	2 - 3	170 (H, M)	--
B09		322B051	2 - 3	74 (H, M)	--
B10		322B014	0 - 0.5	76 (H, M)	--
B11		322B015	0 - 0.5	86 (H, M)	--
B14		322B043	14 - 15	300 (H, Y)	--
B15		322B020	0 - 0.5	150 (H, M)	--
		322B044	2 - 3	4,000 (Y)	5.3 (H)
B17		322B062	2 - 3	1,500 (H, M)	--

^aBased on *Nevada Administrative Code*; Contamination of soil: Establishment of action levels (NAC, 2002)

ft bgs = Feet below ground surface

mg/kg = Milligrams per kilogram

D = A pattern resembling diesel was detected in the sample.

H = The fuel pattern was in the heavier end of the retention time window for the analyte of interest

M = A pattern resembling motor oil was detected

Y = Multippeak chromatogram does not match target analyte

-- = Not detected above minimum reporting limits

Total petroleum hydrocarbon-DRO was identified at two locations in Area A. One location (B04) contained TPH-DRO above the PAL. Based on visual observation of the sample location it is possible the positive TPH-DRO results may be due to the presence of paint chips (from oil based paint) which appear to have flaked off of an old wooden road barricade that was found lying directly on top of the sample location. Approximately 2 cubic feet (ft³) of soil was removed and drummed, and the underlying soil sampled. The analytical results of this verification sample indicate the contamination above PALs was removed.

The second location (B01) contained TPH-DRO contamination above the PAL at the 2 to 3 ft bgs interval. The overlying soil was removed and the 2 to 3 ft bgs interval (approximately 4 ft³) was collected and drummed. Confirmation samples were collected from the excavation floor and from the

sides of the excavation at the 2 to 3 ft bgs interval. Analytical results indicated that the TPH-DRO contamination was removed. No TPH-DRO contamination remained at Area A.

Sampling at sites B06 and B07 were intended to determine if TPH-DRO contamination had migrated along a buried utility corridor and showed up as TPH-DRO contamination at Area B. This was determined not to be the case, and Areas A and B were isolated as discreet areas of interest within this CAS.

At Area B, TPH-DRO was identified at several locations and various depths. Each of the TPH-DRO detections above the PAL and all other samples collected from the same borehole are presented in Table A.4-8. The identification of TPH-DRO contaminated locations in Area B do not appear to be associated with specific identifiable point sources of contamination. There is no anticipated gradient of contamination, as expected when a point source (e.g., fuel overfilling, leaking piping, tank rupture) is identifiable. The highest concentrations of TPH-DRO are not associated with surface samples, but instead with deeper subsurface samples at noncontiguous locations. The TPH-DRO contamination is defined laterally where physical barriers do not interfere with step-out locations (Figure A.4-4). The vertical extent of contamination is defined at each location where TPH was detected above PALs as shown in Table A.4-8 except where otherwise noted. Figure A.4-5 provides a cross section view of the TPH-DRO contamination along one transect. Specific vertical boundary samples were not obtained at three locations. At each of these locations (CS01, CS02, and CS04), TPH-DRO was detected above the PAL to a depth of approximately 3 ft bgs. These specific locations were not further evaluated during the CAU 322 CAI. However, vertical boundary was demonstrated at other nearby locations (Table A.4-8 and Figure A.4-4).

A.4.2.5.6 *Gamma-Emitting Isotopes*

Analytical results for gamma-emitting radionuclides in soil samples collected at CAS 03-25-03 that exceeded MDCs are presented in Table A.4-9. No gamma-emitting radionuclides were detected above PALs.

Table A.4-8
Vertical Bounding of TPH-DRO at Area B
(Page 1 of 2)

Borehole	Sample Number	Depth (ft bgs)	TPH-DRO (mg/kg)	Comments
B08	322B012	0 - 0.5	72 (H, M)	Vertical bounding sample obtained
	322B053	2 - 3	170 (H, M)	
	322B072	4 - 5	ND	
	322B073 (Duplicate of 322B072)	4 - 5	ND	
	322B054	14 - 15	ND	
	322B055 (Duplicate of 322B054)	14 - 15	ND	
B14 & B18	322B019	0 - 0.5	ND	Vertical bounding sample obtained Borehole B14 was completed at 15 ft bgs. When sample results were returned and indicated contamination above the PAL at 15 ft bgs, borehole B18 was drilled alongside B14 (approximately 6 ft away) as a continuation of sampling at this location.
	322B042	2 - 3	ND	
	322B043	14 - 15	300 (H, Y)	
	322B056	15 - 16	ND	
	322B057	20 - 21	ND	
	322B058	25 - 26	ND	
B15 & CS06	322B020	0 - 0.5	150 (H, M)	Vertical bounding sample obtained Borehole CS06 and Borehole B15 were drilled within approximately 10 ft of each other.
	CS0601	1.5 - 2.5	3,800 (J)	
	CS0699	1.5 - 2.5	10,000 (J)	
	322B044	2 - 3	4,000 (Y)	
	322B045	10 - 11	ND	
	322B046	14 - 15	ND	
B17	322B062	2 - 3	1,500 (H, M)	Vertical bounding sample obtained
	322B063	7 - 8	ND	
CS01	CS0100	0 - 0.5	100	Samples were collected at this location during investigation of CAU 34. No specific vertical bounding samples were collected for this borehole. However, all locations sampled during the 322 CAI were bounded.
	CS0101	0.5 - 1.5	540	
	CS0102	1.5 - 2.5	510	
CS02	CS0200	0 - 0.5	91	Samples were collected at this location during investigation of CAU 34. No specific vertical bounding samples were collected for this borehole. However, all locations sampled during the 322 CAI were bounded.
	CS0202	1.5 - 2.5	160	
CS03 & B12	CS0300	0 - 0.5	100	Vertical bounding sample obtained Boreholes CS03 and B12 were drilled within approximately 10 ft of each other.
	322B016	0 - 0.5	ND	
	322B017	0 - 0.5	ND	
	CS0301	0.5 - 1.5	93	
	CS0302	1.5 - 2.5	11,000 (J)	
	322B049	2 - 3	ND	
	CS0306	6 - 7	23,000 (J)	
	322B050	14 - 15	ND	

Table A.4-8
Vertical Bounding of TPH-DRO at Area B
(Page 2 of 2)

Borehole	Sample Number	Depth (ft bgs)	TPH-DRO (mg/kg)	Comments
CS04	CS0401	1 - 2	60	Samples were collected at this location during investigation of CAU 34. No specific vertical bounding samples were collected for this borehole. However, all locations sampled during the 322 CAI were bounded.
	CS0402	2 - 3	260	

ND = Not detected above MRLs

J = Estimated value; qualifier added to laboratory data, record accepted; surrogates diluted out

H = The fuel pattern was in the heavier end of the retention time window for the analyte of interest

M = A pattern resembling motor oil was detected

Y = Multippeak chromatogram does not match target analyte

A.4.2.5.7 Strontium-90

Analytical results for strontium (Sr)-90 in soil samples collected at CAS 03-25-03 did not exceed the MDCs or PALs.

A.4.2.5.8 Plutonium

Analytical results for plutonium in soil samples collected at CAS 03-25-03, that exceeded MDCs are presented in Table A.4-10. Plutonium was detected above the PAL in soil sample 322B017 collected at the surface at location B12 at Site B on the east side of the mud plant. The plutonium was likely present at this location due to fallout from atmospheric testing at the NTS; therefore, it is not a COC for this CAS. However, as a best management practice to mitigate potential personnel exposures the impacted soil (less than 1 ft³) was removed and placed in a drum for disposal. A concrete pad was found immediately under the location where the soil was removed. A swipe sample was collected and analyzed in the field from the pad. Results of this sample indicated that the concrete was below the unrestricted release criteria. Three step out samples around sample location B12 (sample locations B23, B24, and B25) also confirm that the contamination had been removed.

A.4.2.5.9 Uranium

Analytical results for uranium in soil samples collected at CAS 03-25-03 that exceeded MDCs are presented in Table A.4-10. Uranium was not detected above the PALs.

Figure A.4-4
Plan View Plot of TPH-DRO Hits above PALs at
CAS 03-25-03, AST Release, Site B (East Side of Mud Plant)

Figure A.4-5
Vertical Cross Section of TPH-DRO Concentrations at
CAS 03-25-03, AST Release, Site B (East Side of Mud Plant)

Table A.4-9
Soil Sample Results for Gamma-Emitting Radionuclides Detected
Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release
(Page 1 of 2)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)											
			Actinium-228 ^a		Americium-241 ^b	Bismuth-214 ^a		Cesium-137 ^b	Lead-212 ^a		Lead-214 ^a		Thallium-208 ^a	
			5	15	7.62	5	15	7.3	5	15	5	15	5	15
Depth bgs (cm)		<15	>15	<15		>15	<15		>15	<15	>15	<15	>15	
B01	322B007	0 - 0.5	1.98 (G)	NA	--	1.04 (G)	NA	--	2.05 (J)	NA	1.25 (J)	NA	0.61 (G)	NA
B02	322B008	0 - 0.5	1.72 (G)	NA	--	0.76 (G)	NA	--	2.08 (J)	NA	1.06 (J)	NA	0.65 (G)	NA
B03	322B009	0 - 0.5	1.89 (G)	NA	--	1.22 (G)	NA	--	2.04 (J)	NA	1.17 (J)	NA	0.65 (G)	NA
B04	322B010	0 - 0.5	1.52 (G)	NA	--	1.06 (G)	NA	--	2.08 (J)	NA	1.15 (J)	NA	0.56 (G)	NA
B05	322B011	0 - 0.5	2.03 (G)	NA	--	0.77 (G)	NA	--	2.22 (J)	NA	1.17 (J)	NA	0.56 (G)	NA
B06	322B001	0 - 0.5	1.4 (G)	NA	--	0.89 (G)	NA	--	1.56 (J)	NA	1 (J)	NA	0.48 (G)	NA
B08	322B012	0 - 0.5	1.59 (G)	NA	--	1.01 (G)	NA	--	1.69 (J)	NA	1.23 (J)	NA	0.56 (G)	NA
B09	322B013	0 - 0.5	1.33 (G)	NA	--	1.13 (G)	NA	--	1.57 (J)	NA	1.19 (J)	NA	0.58 (G)	NA
B10	322B014	0 - 0.5	1.46 (G)	NA	0.78 (J)	1.14 (G)	NA	--	1.86 (J)	NA	1.33 (J)	NA	0.55 (G)	NA
B11	322B015	0 - 0.5	1.64 (G)	NA	--	1.12 (G)	NA	--	1.83 (J)	NA	1.2 (J)	NA	0.56 (G)	NA
B12	322B016	0 - 0.5	1.69 (G)	NA	--	0.9 (G)	NA	0.3 (G, LT)	2.1 (J)	NA	0.97 (J)	NA	0.6 (G)	NA
	322B017	0 - 0.5	1.71 (G)	NA	--	1.07 (G)	NA	--	2.09 (J)	NA	1.03 (J)	NA	0.74 (G)	NA
B13	322B018	0 - 0.5	1.47 (G)	NA	--	0.93 (G)	NA	--	1.82 (J)	NA	1.15 (J)	NA	0.53 (G)	NA
B14	322B019	0 - 0.5	1.37 (G)	NA	--	0.94 (G)	NA	--	1.91 (J)	NA	1.27 (J)	NA	0.5 (G)	NA

Table A.4-9
Soil Sample Results for Gamma-Emitting Radionuclides Detected
Above Minimum Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release
(Page 2 of 2)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)											
			Actinium-228 ^a		Americium-241 ^b	Bismuth-214 ^a		Cesium-137 ^b	Lead-212 ^a		Lead-214 ^a		Thallium-208 ^a	
Preliminary Action Levels			5	15	7.62	5	15	7.3	5	15	5	15	5	15
Depth bgs (cm)			<15	>15		<15	>15		<15	>15	<15	>15	<15	>15
B15	322B020	0 - 0.5	1.82 (G)	NA	0.48 (J)	1.23 (G)	NA	--	2.08 (J)	NA	1.05 (J)	NA	0.69 (G)	NA
B19	322B064	0 - 1	NA	1.31	--	NA	0.86	0.98	NA	1.92 (J)	NA	0.77 (J)	NA	0.39

^aTaken from the generic guidelines for residual concentrations of actinium-228, bismuth-214, lead 212, thallium-208, and thorium-232, as found in Chapter IV of DOE Order 5400.5, Change 2, "Radiation Protection of the Public and Environment." (DOE, 1993). The PALs for these isotopes is specified as 5 picocuries per gram (pCi/g) averaged over the first 15 centimeters (cm) of soil and 15 pCi/g for deeper soils (DOE, 1993). For purposes of this document, 15 cm is assumed to be equivalent to 0.5 ft (6 inches); therefore, 5 pCi/g represents the PALs for these radionuclides in the surface soil (0 to 0.5 ft depth).

^bTaken from the construction, commercial, industrial land use scenario in Table 2.1 of the NCRP Report No. 129, *Recommended Screening Limits for Contaminated Surface Soil and Review Factors Relevant to Site-Specific Studies* (NCRP, 1999). The values provided in this source document were scaled to a 15-mrem/yr. dose.

ft bgs = Feet below ground surface

cm = Centimeter

pCi/g = Picocuries per gram

-- = Not detected above minimum reporting limits

> = Greater than

< = Less than

G = Sample density differs by more than 15 percent of laboratory control sample density.

J = Estimated value. Qualifier added to laboratory data; record accepted. Sample does not meet counting geometry requirements.

LT = Result is less than the requested minimum detectable concentration, greater than the sample-specific minimum detectable concentration.

NA = Not applicable

Table A.4-10
Soil Sample Results for Isotopes Detected Above Minimum
Reporting Limits at CAS 03-25-03, Mud Plant AST Diesel Release

Sample Location	Area	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)				
				Plutonium-238	Plutonium-239	Uranium-234	Uranium-235	Uranium-238
Preliminary Action Levels ^a				7.78	7.62	85.9	10.5	63.2
B01	A	322B007	0 - 0.5	--	1.22	1.13	0.088	1.12
B02		322B008	0 - 0.5	--	1.06	0.97	--	0.94
B03		322B009	0 - 0.5	--	0.045 (LT)	1.13	0.057	1.12
B04		322B010	0 - 0.5	--	2.79	1.03	0.062	0.93
B05		322B011	0 - 0.5	--	0.178	0.99	--	1.02
B06		322B001	0 - 0.5	0.105	7.4	0.97	0.056	0.93
		322B003	2 - 3	--	--	1.05	0.071	1.01
		322B004	6 - 7	--	--	1.11	--	1.03
B07		322B002	0 - 0.5	--	0.215	1.16	--	1.17
		322B005	2 - 3	--	0.057	1.03	0.078	1.1
		322B006	5 - 6	--	--	1.79	0.14	1.57
B08	B	322B012	0 - 0.5	--	0.61	0.98	--	1.03
B09		322B013	0 - 0.5	--	0.55	1.06	0.062	1.06
B10		322B014	0 - 0.5	--	1.72	1.31	0.063	1.12
B11		322B015	0 - 0.5	--	0.59	1.42	0.072	1.27
B12		322B016	0 - 0.5	0.042 (LT)	0.37	1.23	--	1.07
		322B017	0 - 0.5	1.21	25.9	1.14	--	0.98
B13		322B018	0 - 0.5	--	0.086	1.01	0.085	1.1
B14		322B019	0 - 0.5	--	0.155	1.21	0.067	1.08
B15		322B020	0 - 0.5	0.029 (LT)	1.51	0.98	0.061	1
B23		322B076	0 - 0.5	0.06	0.58	--	--	--
B24		322B077	0 - 0.5	0.63	1.97	--	--	--
B25		322B078	0 - 0.5	--	0.354	--	--	--

^aTaken from the construction, commercial, industrial land use scenario in Table 2.1 of the NCRP Report No. 129 *Recommended Screening Limits for Contaminated Surface Soil and Review Factors Relevant to Site-Specific Studies* (NCRP, 1999). The values provided in this source document were scaled to a 15-mrem/yr dose.

ft bgs = Feet below ground surface

pCi/g = Picocuries per gram

LT = Result is less than the requested minimum detectable concentration, greater than the sample-specific minimum detectable concentration.

-- = Not detected above minimum reporting limits

A.4.2.6 Contaminants of Concern

In Area A, the only COC identified was TPH-DRO; however, all soil contaminated with TPH-DRO at Area A was removed and containerized for waste disposal. Verification samples indicated no additional contamination remained. Therefore, there are no COCs remaining a Area A.

In Area B, Pu-239 was identified above PALs. Data obtained from sample 322B017 collected in Area B of this CAS indicated Pu-239 above the PAL. Although the Pu-239 is not believed to be present due to activities associated with CAS 03-25-03 the contaminated soil was removed and drummed for disposal as a best management practice to mitigate potential personnel exposures.

Also in Area B TPH-DRO was identified above the PAL in several locations and is considered a COC.

A.4.3 Nature and Extent of Contamination

In Area A, no contamination above PALs remains.

In Area B, TPH-DRO contamination was identified at several locations and at varying depths. There was no identifiable pattern or plume to the presence of TPH-DRO contamination that would lend itself to identify a point source for the contamination observed. The TPH-DRO contamination pattern (or lack thereof) supports the CSM which identifies the possibility that TPH-DRO contamination is the result of random spills, leaks, and overflows associated with mobile equipment (e.g., generators), mobile vehicles (e.g., trucks, front-end loaders), or fixed equipment (e.g., pumps) that required diesel fuel for power generation. The lateral extent of contamination was identified by step-out sampling at locations B16 and B20 to the northwest, B13 to the northeast, B21 to the southwest, and B22 to the southeast. The contaminated area is also bordered by CAU 34, CAS 03-09-06, Mud Disposal Crater to the north; the Mud Plant structure to the west; and CAU 34, CAS 03-47-02, Mud Plant Pond to the east. Corrective actions sites 03-09-06 and 03-47-02 were closed in place with use restrictions due to TPH contamination. The contaminated area encompasses approximately 7,600 ft². The vertical extent of contamination was variable (Table A.4-8); however, the deepest contamination identified was confined to 10 ft bgs.

A.4.4 Revised Conceptual Site Model

No variations in the CSM were identified; however, some additional clarification is provided.

At Area A there was no indication of TPH-DRO contamination of the type described in the historical documents referenced in the CAIP. These documents indicated TPH-DRO contamination remained after the 1992 remediation activities. Investigation activities were designed to identify the presence and location of the residual contamination. None was found, with the exception of one surface soil sample (location B04) and one 2 to 3 ft bgs interval (location B01). The surface soil sample TPH-DRO contamination at location B04 may be due to the presence of oil-based paint chips observed at the sample location. Sampling beneath the surface soil revealed no TPH-DRO contamination, and a confirmation sample taken beneath the removed and containerized soil was nondetect for TPH-DRO. The TPH-DRO contamination at the 2 to 3 ft bgs interval at location B01 was removed and confirmation samples indicate no TPH-DRO contamination remained.

The CSM developed in the CAIP for Area B offered several potential sources of TPH-DRO contamination including contaminant transport along a preferred pathway such as utility lines from Area A. However, investigation results indicate the TPH-DRO contamination is more likely the result of random spills, leaks, and overflows associated with mobile equipment (e.g., generators), mobile vehicles (e.g., trucks, front-end loaders), or fixed equipment (e.g., pumps) that required diesel fuel for power generation. The appearance of TPH-DRO at different locations and depths may have been enhanced by grading, removal of soil, and/or placement of fill during operations at the mud plant and the use of diesel and/or oil for dust suppression.

A.5.0 CAS 03-20-05, Injection Well

Corrective Action Site 03-20-05, Injection Well, is located in Area 3 and is associated with the LLNL BOP Shop.

The CSM for CAS 03-20-05 included potential soil contamination originating from the holding/cleaning tanks, the injection well, the line running from the BOP Shop to the injection well, and runoff from the BOP Shop floor resulting from possible overfills of the holding/cleaning tanks. The CAIP called for the collection of soil samples commensurate with the depths of possible sources of contamination. Because the assumed depth of the holding/cleaning tanks within the BOP Shop was 30 to 50 ft bgs, samples collected around the holding/cleaning tanks were taken to 100 ft bgs. Because the depth of the injection well sump was estimated to be between 60 and 100 ft bgs, the soil samples taken around the injection well were taken to approximately 120 ft bgs. The soil samples collected just off the BOP Shop floor were taken to a depth of approximately 6 ft bgs.

A.5.1 Corrective Action Investigation

A total of 106 samples were collected at CAS 03-20-05. Eleven of the samples collected were liquids from the holding/cleaning tanks and associated sumps and the injection well sump. Two of the liquid samples were classified by the laboratory as oil samples. Soil samples were collected at locations identified in the CAU 322 CAIP. The liquid and soil samples were analyzed for the parameters listed in Table A.5-1. The soil sample locations are shown in Figure A.5-1 and the sample locations from tanks and sumps are shown in Figure A.5-2. The specific CAI activities conducted to satisfy the CAIP requirements at CAS 03-20-05 are described in the following sections.

A.5.1.1 Deviations

There were no deviations to the CAIP requirements at this CAS.

A.5.2 Investigation Results

The following sections provide descriptions of the CAS-specific activities conducted to complete investigation activities as outlined in the CAIP. Investigation activities included the visual inspection of the CAS, sampling of the liquid contents of the holding/cleaning tanks and associated sumps, the

Table A.5-1
Samples Collected at CAS 03-20-05, Injection Well
(Page 1 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
C01	322C001	0 - 0.5	Soil	SC	Sets 1, 2, 3, and 6
	322C002	2 - 3	Soil	SC	Sets 1, 2, 3, and 6
	322C003	4 - 5	Soil	SC	Sets 1, 2, 3, and 6
C02	322C004	0 - 0.5	Soil	SC	Sets 1, 2, 3, and 6
	322C005	2 - 3	Soil	SC	Sets 1, 2, 3, and 6
	322C006	5 - 6	Soil	SC	Sets 1, 2, 3, and 6
C03	322C007	0 - 0.5	Soil	SC	Sets 1, 2, 3, and 6
	322C008	2 - 3	Soil	SC	Sets 1, 2, 3, and 6
	322C009	5 - 6	Soil	SC	Sets 1, 2, 3, and 6
C04	322C010	0 - 0.5	Soil	SC	Sets 1, 2, 3, and 6
	322C011	4 - 5	Soil	SC, MS/MSD	Sets 1, 2, 3, and 6
	322C012	7 - 8	Soil	SC	Sets 1, 2, 3, and 6
	322C013	7 - 8	Soil	Field Duplicate of 322C012	Sets 1, 2, 3, and 6
C05	322C013A	0 - 0.5	Soil	SC	Sets 1, 2, 3, and 6
	322C014	2 - 3	Soil	SC	Sets 1, 2, 3, and 6
	322C015	5 - 6	Soil	SC	Sets 1, 2, 3, and 6
C06	322C016	0 - 1	Soil	SC	Sets 1 through 7
	322C017	3 - 4	Soil	SC	Sets 1 through 7
	322C018	5 - 6	Soil	SC	Sets 1 through 7
C07	322C019	0 - 2	Soil	SC	Sets 1 through 7
	322C020	3 - 4	Soil	SC	Sets 1 through 7
	322C021	5 - 6	Soil	SC	Sets 1 through 7
	322C091	14 - 15	Soil	SC	Set 8, SVOCs
	322C092	19 - 20	Soil	SC	Set 8, SVOCs
	322C093	24 - 25	Soil	Sc	Set 8, SVOCs
HT-1	322C023	NA	Liquid	WC	TPH-DRO, PCBs, Tritium, Total SVOCs
	322C023A	NA	Liquid	WC	Sets 2, 3, 4, Total VOCs, TPH-GRO, RCRA Metals, Be
HT-2	322C039	NA	Liquid	WC	Sets 1, 2, 3, 4 and 6 ^a
	322C039A	NA	Liquid	WC	Tritium
	322C040	NA	Liquid	Field Duplicate of 322C039	Sets 1 through 6
HT-3	322C022	NA	Liquid	WC	TPH-DRO, PCBs, Tritium, Total SVOCs
	322C022A	NA	Liquid	WC	Sets 2, 3, 4, Total VOCs, TPH-GRO, RCRA Metals, Be

Table A.5-1
Samples Collected at CAS 03-20-05, Injection Well
(Page 2 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
C08	322C024	0 - 2	Soil	SC	Sets 1 through 6
	322C025	9 - 10	Soil	SC	Sets 1 through 6
	322C026	20 - 21	Soil	SC, MS/MSD	Sets 1 through 6
	322C027	30 - 31	Soil	SC	Sets 1 through 6
	322C028	40 - 41	Soil	SC	Sets 1 through 6
	322C029	50 - 51	Soil	SC	Sets 1 through 6
	322C030	60 - 61	Soil	SC	Sets 1 through 6
	322C031	70 - 71	Soil	SC	Sets 1 through 6
	322C032	80 - 81	Soil	SC	Sets 1 through 6
	322C033	91 - 92	Soil	SC	Sets 1 through 6
	322C034	100 - 101	Soil	SC	Sets 1 through 6
	322C035	111 - 112	Soil	SC	Sets 1 through 6
	322C036	122 - 123	Soil	SC	Sets 1 through 6
	322C105	0.5 - 1.5	Soil	SC	Iso-Pu
C09	322C037	0 - 0.5	Soil	SC	Sets 1 through 6
	322C038	0 - 0.5	Soil	Field Duplicate of 322C037	Sets 1 through 6
	322C042	10 - 11	Soil	SC	Sets 1 through 6
	322C043	20 - 21	Soil	SC	Sets 1 through 6
	322C044	30 - 31	Soil	SC	Sets 1 through 6
	322C045	40 - 41	Soil	SC	Sets 1 through 6
	322C046	51 - 52	Soil	SC	Sets 1 through 6
	322C047	60 - 61	Soil	SC, MS/MSD	Sets 1 through 6
	322C048	70 - 71	Soil	SC	Sets 1 through 6
	322C049	81 - 82	Soil	SC	Sets 1 through 6
	322C050	92 - 93	Soil	SC	Sets 1 through 6
	322C051	101 - 102	Soil	SC	Sets 1 through 6
	322C052	111 - 112	Soil	SC	Sets 1 through 6
	322C053	121 - 122	Soil	SC	Sets 1 through 6
	322C089	1 - 2	Soil	SC	Iso-Pu
	322C103	0.5 - 1.5	Soil	SC	Iso-Pu
HT-1 sump	322C055O	NA	Oil	WC	Sets 1 through 6
	322C055L	NA	Liquid	WC	Sets 1 through 6
HT-3 sump	322C054O	NA	Oil	WC	Sets 1 through 6
	322C054L	NA	Liquid	WC	Sets 1 through 6

Table A.5-1
Samples Collected at CAS 03-20-05, Injection Well
(Page 3 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
C10	322C056	1 - 2	Soil	SC	Sets 1 through 6
	322C057	10 - 11	Soil	SC	Sets 1 through 6
	322C058	21 - 22	Soil	SC	Sets 1 through 6
	322C059	30 - 31	Soil	SC	Sets 1 through 6
	322C060	41 - 42	Soil	SC	Sets 1 through 6
	322C061	51 - 52	Soil	SC	Sets 1 through 6
	322C062	60 - 61	Soil	SC	Sets 1 through 6
	322C063	71 - 72	Soil	SC, MS/MSD	Sets 1 through 6
	322C064	81 - 82	Soil	SC	Sets 1 through 6
	322C065	81 - 82	Soil	Field Duplicate of 322C064	Sets 1 through 6
	322C066	91 - 92	Soil	SC	Sets 1 through 6
	322C067	101 - 102	Soil	SC	Sets 1 through 6
C11	322C068	0 - 1	Soil	SC	Sets 1, 2, 3, 4 and 6
	322C069	49 - 50	Soil	SC	Sets 1, 2, 3, 4 and 6
	322C070	59 - 60	Soil	SC	Sets 1, 2, 3, 4 and 6
	322C071	69 - 70	Soil	SC	Sets 1, 2, 3, 4 and 6
C12	322C072	0 - 1	Soil	SC	Sets 1, 2, 3, 4 and 6
	322C073	49 - 50	Soil	SC	Sets 1, 2, 3, 4 and 6
	322C074	59 - 60	Soil	SC	Sets 1, 2, 3, 4 and 6
	322C075	69 - 70	Soil	SC	Sets 1, 2, 3, 4 and 6
C13	322C076	0 - 0.5	Soil	SC	Iso-Pu
	322C077	0 - 0.5	Soil	Field Duplicate of 322C076	Iso-Pu
	322C078	1 - 2	Soil	SC	Iso-Pu
C14	322C079	0 - 0.5	Soil	SC	Iso-Pu
	322C080	1 - 2	Soil	SC	Iso-Pu
	322C104	0.5 - 1.5	Soil	SC	Iso-Pu
C15	322C081	0.5 - 1	Soil	SC	Iso-Pu
	322C082	1 - 2	Soil	SC	Iso-Pu
C16	322C083	0.5 - 1	Soil	SC	Iso-Pu
	322C084	1 - 2	Soil	SC	Iso-Pu
C17	322C085	0.5 - 1	Soil	SC	Iso-Pu
	322C086	1 - 2	Soil	SC	Iso-Pu
C18	322C087	0.5 - 1	Soil	SC	Iso-Pu
	322C088	1 - 2	Soil	SC	Iso-Pu
	322C106	0.5 - 1.5	Soil	SC	Iso-Pu

Table A.5-1
Samples Collected at CAS 03-20-05, Injection Well
(Page 4 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
C19	322C095	9 - 10	Soil	SC	Set 8, SVOCs
	322C100	49 - 50	Soil	SC	Set 8, SVOCs
	322C101	59 - 60	Soil	SC	Set 8, SVOCs
	322C102	69 - 70	Soil	SC	Set 8, SVOCs
IJ-1 sump	322C041	60 - 61	Liquid	SC	Sets 1, 4, and TPH-DRO, Iso-U
NA	322C301	NA	Water	Trip Blank	Total VOCs
NA	322C302	NA	Water	Trip Blank	Total VOCs
NA	322C303	NA	Water	Trip Blank	Total VOCs
NA	322C304	NA	Water	Equipment Rinsate Blank	Sets 1, 2, 3, 5, and 6
NA	322C305	NA	Water	Source Blank	Sets 1, 2, 3, 5, and 6
NA	322C306	NA	Water	Trip Blank	Total VOCs
NA	322C307	NA	Water	Trip Blank	Total VOCs
NA	322C308	NA	Water	Equipment Rinsate Blank	Sets 1, 2, 3, 5, and 6
NA	322C309	NA	Water	Field Blank	Sets 1, 2, 3, 5, and 6
NA	322C310	NA	Water	Source Blank	Sets 1, 2, 3, 5, and 6
NA	322C311	NA	Water	Trip Blank	Total VOCs
NA	322C312	NA	Water	Trip Blank	Total VOCs
NA	322C313	NA	Water	Trip Blank	Total VOCs
NA	322C314	NA	Water	Trip Blank	Total VOCs
NA	322C315	NA	Water	Trip Blank	Total VOCs
NA	322C318	NA	Water	Trip Blank	Total VOCs
NA	322C319	NA	Water	Trip Blank	Total VOCs
NA	322C320	NA	Water	Trip Blank	Total VOCs
NA	322C321	NA	Water	Equipment Rinsate Blank	Sets 1 through 6
NA	322C322	NA	Water	Equipment Rinsate Blank	Sets 1 through 6
NA	322C323	NA	Water	Trip Blank	Total VOCs
NA	322C324	NA	Water	Trip Blank	Total VOCs
NA	322C325	NA	Water	Trip Blank	Total VOCs
NA	322C326	NA	Water	Source Blank	Sets 1 through 6 ^b
NA	322C327	NA	Water	Trip Blank	Total VOCs
NA	322C328	NA	Water	Trip Blank	Total VOCs
NA	322C329	NA	Water	Equipment Rinsate Blank	Sets 1 through 6
NA	322C330	NA	Water	Trip Blank	Total VOCs

Table A.5-1
Samples Collected at CAS 03-20-05, Injection Well
(Page 5 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Sample Matrix	Purpose	Analyses
NA	322C331	NA	Water	Trip Blank	Total VOCs
NA	322C332	NA	Water	Trip Blank	Total VOCs
NA	322C333	NA	Water	Trip Blank	Total VOCs
NA	322C334	NA	Water	Field Blank	Sets 1 through 6
NA	322C335	NA	Water	Field Blank	Iso-U
NA	322C336	NA	Water	Field Blank	Set 8
NA	322C337	NA	Water	Field Blank	SVOCs

^aTritium sample broken prior to shipment to lab

^bPCB not analyzed

Set 1 = Total VOCs, Total SVOCs, Total RCRA Metals, Total Beryllium, PCBs

Set 2 = Gamma Spectroscopy

Set 3 = Isotopic Uranium, Isotopic Plutonium, Strontium-90

Set 4 = Gross Alpha, Gross Beta

Set 5 = Tritium

Set 6 = TPH-GRO, TPH-DRO

Set 7 = TCLP VOCs, TCLP SVOCs, TCLP RCRA Metals

Set 8 = Total RCRA Metals, PCBs, Gamma Spectroscopy, Iso-uranium,
Iso-plutonium, strontium-90

ft bgs = Feet below ground surface

NA = Not applicable

SC = Site characterization

WC = Waste characterization

HT = Holding tank

IJ = Injection well

injection well sumps, soils, and sample analysis. Also, a full, gridded, rad survey was conducted of the BOP Shop floor, holding/cleaning tank interiors and lids, and injection well casing interior and cover. One additional sample location was identified upon discovery of a sink within the BOP Shop with a flexible tube drain that ran through the shop wall and onto the ground just outside.

A.5.2.1 Radiological Survey Results

A radiological walk-over survey was performed at CAS 03-20-05 in April 2004. The survey was performed to determine if radiological contamination is present in surficial soil at CAS 03-20-05 at concentrations statistically greater than surficial soil from undisturbed background locations. The results were plotted on a color-coded contour map (Figure A.5-3).

Measurements of the gamma radiation emission rate for surface soils was performed with a TSA Systems Model PRM-470B handheld plastic scintillator over an area of approximately 8,837 ft². A total of 4,605 data points were recorded at this site with a mean gamma radiation emission rate of 166 counts per second versus the mean undisturbed background radiation emission rate of 176 counts

Figure A.5-1
Soil Sample Location Map for CAS 03-20-05, Injection Wells

Figure A.5-2
Sample Locations for Tanks and Sumps at
CAS 03-20-05, Injection Wells

per second. The maximum gamma radiation emission rate was 234 counts per second. This rate is approximately 1.3 times the mean undisturbed background gamma emission rate (Alderson, 2004).

A gridded survey was performed over the floor of the BOP Shop. The entire floor was divided into 2 by 2 ft square grids, and a swipe sample was taken within each grid. Analysis of the swipe samples indicated that there were no measurements above the unrestricted release criteria.

A radiological survey was conducted on the tank interior walls and lids of the three holding tanks within the BOP Shop. Random swipe samples were collected at various locations on the inside walls of the holding tanks and on the bottom of the tank lids (the tops of the lids were sampled in the gridded survey of the BOP Shop floor). Analysis of the swipe samples indicated that no radiation existed above the unrestricted release criteria.

Swipe samples were collected from the interior walls of the injection well casing and from the top and bottom of the injection well cover. Analysis of these samples indicated that no radiological contamination existed above the unrestricted release criteria.

A datalogger radiological probe was lowered into the injection well sump and readings were collected at 10-ft intervals from the top of the sump to the level of its liquid contents, beginning approximately 60 ft bgs. The readings were all below background levels established prior to the injection well sump measurements.

A.5.2.2 Inspection and Sampling

The holding/cleaning tanks within the BOP Shop and line running from the BOP Shop to the injection well were inspected for integrity and leakage. The injection well casing was inspected for standing liquids; none were present. The injection well sump depth was determined to be approximately 62 ft bgs with liquid beginning at 60 ft bgs. A video mole was run the length of the 10 in. diameter injection well sump and it was determined that there was a pipe joint at 25 ft bgs and that the pipe was slotted beginning at 28 ft bgs. The slotting of the lower pipe became more crusted as the depth increased, and by approximately 50 ft bgs, the slotting became difficult to visualize. It was unidentifiable due to crusting over the entire inner pipe surface at a depth of approximately 55 ft bgs. Samples of all liquids in the holding/cleaning tanks and associated sumps and liquids contained

within the injection well sump were collected. Soil samples were collected from specified locations selected to provide information regarding environmental contamination arising from leakage associated with the holding/cleaning tanks, drain line, and injection well and associated sump.

Swipe samples for radiation contamination were obtained from the locations identified in Section A.5.2 and the CAU 322 CAIP.

A.5.2.3 Field-Screening Results

Field screening of samples for VOCs using a FID detector identified no contamination above the PAL of 20 ppm. Field screening samples for TPH-DRO identified levels of the contaminant above the PAL of 75 ppm at several locations, predominantly within the soils in the injection well vault.

Radiological field screening of all samples was performed, and none of the results indicated readings above that of background.

A.5.2.4 Sample Analysis

Investigation samples were analyzed for the CAIP-specified COPCs which included total VOCs, total SVOCs, total and TCLP (where applicable) RCRA metals, total beryllium, TPH (DRO and GRO), PCBs, gamma-emitting radionuclides, isotopic uranium, isotopic plutonium, strontium-90, tritium, and alpha/beta emitting radionuclides. The analytical parameters and laboratory methods used to analyze the investigation samples are listed in Table A.2-2. Table A.5-1 lists the sample-specific analytical suite for CAS 03-20-05.

A.5.2.5 Analytes Detected Above Minimum Reporting Limits

Analytical results from samples with concentrations exceeding MRLs or MDCs are summarized in the following sections. Although the liquid and oil samples obtained from the holding/cleaning tanks and associated sumps will be used primarily for waste characterization purposes, the sample results are presented in this section for completeness. Analytical results from the soil, liquid, and oil samples with concentrations exceeding MRLs or MDCs are summarized in the following sections. These results are compared to PALs and are a subset of the results that exceed MRLs or MDCs. A portion

of the analytical results for this CAS were rejected during validation; however, these rejected data did not adversely impact closure decisions as discussed in Appendix B, Section B.1.4.

A.5.2.5.1 Total VOCs

Total VOC analytical results for soil samples collected at CAS 03-20-05, which were detected above MRLs, are presented in Table A.5-2. No VOCs were detected in soil samples above PALs.

**Table A.5-2
Soil Sample Results for Total VOCs Detected
Above Minimum Reporting Limits at CAS 03-20-05, Injection Well**

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (µg/kg)			
			2-Butanone	2-Hexanone	4-Methyl-2-Pentanone	Acetone
Preliminary Action Levels ^a			27,000	NI	2,800	6,000,000
C07	322C019	0 - 2	97 (J)	87 (J)	74 (J)	350 (J)
	322C021	5 - 6	--	--	--	25
C08	322C030	60 - 61	--	--	--	24

^aBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002)

ft bgs = Feet below ground surface

µg/kg = Micrograms per kilogram

J = Estimated value. Qualifier added to laboratory data; record accepted. Surrogate recovery exceeded the upper limits.

-- = Not detected above minimum reporting limits.

A.5.2.5.2 Total SVOCs

Total SVOC analytical results for soil samples collected at CAS 03-20-05, which were detected above MRLs, are presented in Table A.5-3. No SVOCs were detected in soil samples above PALs.

A.5.2.5.3 Total RCRA Metals and Beryllium

Analytical results for total RCRA metals and beryllium for soil samples collected at CAS 03-20-05, which were detected above MRLs, are presented in Table A.5-4. Samples collected from the soil within the injection well exhibited results above the PAL for lead. Samples 322C016 and 322C019 collected at locations C06 (0 to 0.5 ft bgs interval) and C07 (0 to 2 ft bgs interval) provided results for lead of 2,500 and 1,500 mg/kg respectively. Samples collected below these intervals were below the PAL for lead.

Table A.5-3
Soil Sample Results for Total SVOCs Detected
Above Minimum Reporting Limits at CAS 03-20-05, Injection Well

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (µg/kg)
			Bis(2-Ethylhexyl)Phthalate
Preliminary Action Levels ^a			120,000
C06	322C016	0 - 1	8,900 (J)
C07	322C019	0 - 2	6,800 (J)

^aBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002)

ft bgs = Feet below ground surface

µg/kg = Micrograms per kilogram

J = Estimated value. Qualifier added to laboratory data; record accepted. Matrix effects may exist. Internal area response show extremely low count.

A.5.2.5.4 PCBs

Analytical results for PCBs in samples collected at CAS 03-20-05, which were detected above MRLs, are presented in Table A.5-5. Sample 322C024 collected at sample location C08 indicated Aroclor-1254 at a concentration of 1.1 mg/kg at a depth of 0 to 2 ft bgs. Samples collected around and below this location and interval were below the PAL. Samples 322C016 and 322C019 collected from the injection well soil at locations C06 and C07 at depths of 0 to 1 and 0 to 2 ft bgs, respectively, indicated Aroclor-1254 results of 3.3 and 2.4 mg/kg. Samples collected below these intervals were below the PAL for Aroclor-1254.

A.5.2.5.5 TPH

Total TPH-DRO analytical results for soil samples collected at CAS 03-20-05, which were detected above MRLs, are presented in Table A.5-6. Total petroleum hydrocarbons analytical results for samples collected at CAS 03-20-05 indicated the presence of TPH-DRO above PALs at several locations.

At sample location C18, TPH-DRO was detected at a concentration of 150 mg/kg. This detection is presumably due to the presence of asphalt at the site surface. Analytical results for surface samples collected at several other locations (i.e., C02, C04, C05, C08, C09, and C11) indicated TPH-DRO at concentrations over the MRL but less than the PAL. Samples collected below each of these locations

Table A.5-4
Soil Sample Results for Metals Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 1 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic	Barium	Beryllium	Cadmium	Chromium	Lead	Mercury	Selenium	Silver
Preliminary Action Levels			23 ^a	67,000 ^b	1,900 ^b	450 ^b	450 ^b	750 ^b	310 ^b	5,100 ^b	5,100 ^b
C01	322C001	0 - 0.5	6.4	300	0.66	--	6.4	12	--	0.61 (J-)	--
	322C002	2 - 3	4.3	150	0.79	--	5.9	9.6	--	--	--
	322C003	4 - 5	4	140	0.57	--	4.3	12	--	--	--
C02	322C004	0 - 0.5	4.8	170	0.76	0.89	8.8	41	--	--	--
	322C005	2 - 3	4.3	130	0.85	--	6.5	9.9	--	--	--
	322C006	5 - 6	5.4	120	0.97	--	7	12	--	--	--
C03	322C007	0 - 0.5	4.6	140	0.79	--	6.1	15	--	--	--
	322C008	2 - 3	4.9	150	0.96	--	6.9	12	--	--	--
	322C009	5 - 6	3.1	100	--	--	4.2	8.2	--	--	--
C04	322C010	0 - 0.5	6.2	190	0.67	--	7.6	21	--	--	--
	322C011	4 - 5	7.1	140	1.2	--	8.3	13	--	--	--
	322C012	7 - 8	5.1	120	0.76	--	5.5	12	--	--	--
	322C013	7 - 8	5.3	120	0.78	--	5.9	10	--	--	--
C05	322C013A	0 - 0.5	3.7	130	0.57	7.4	7.7	42	--	--	--
	322C014	2 - 3	4.7	160	0.87	0.6	7.5	15	--	--	--
	322C015	5 - 6	6.2	170	1	--	7.7	16	--	--	--
C06	322C016	0 - 1	8.3	460	--	320	170	2,500	1.4	--	1.4
	322C017	3 - 4	5.1	190	0.7	22	13	170	0.52	0.74	--
	322C018	5 - 6	9	240	0.74	45	22	420	0.77	0.94	--

Table A.5-4
Soil Sample Results for Metals Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 2 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic	Barium	Beryllium	Cadmium	Chromium	Lead	Mercury	Selenium	Silver
Preliminary Action Levels			23 ^a	67,000 ^b	1,900 ^b	450 ^b	450 ^b	750 ^b	310 ^b	5,100 ^b	5,100 ^b
C07	322C019	0 - 2	10	320	--	130	96	1,500	0.97	0.79	2
	322C020	3 - 4	6.2	170	0.74	13	14	110	0.17	--	--
	322C021	5 - 6	5.5	210	0.68	17	15	150	0.2	--	--
	322C091	14 - 15	4.1	230	--	--	4.7	13	--	--	--
	322C092	19 - 20	6.6	260	--	--	7.6	10	--	--	--
	322C093	24 - 25	3.7	120	--	--	6.7	8.5	--	--	--
C08	322C024	0 - 2	4.6	220	0.69	--	10	38	--	--	--
	322C025	9 - 10	4	110	0.65	--	5.2	8.4	--	--	--
	322C026	20 - 21	6.3	260	0.92	--	7.4	12	--	--	--
	322C027	30 - 31	5.6	130	0.93	--	6.5	11	--	--	1.6
	322C028	40 - 41	4.6	140	0.89	--	6.1	9.8	--	--	1.5
	322C029	50 - 51	4.1	150	0.71	--	8.9	16	--	--	--
	322C030	60 - 61	4.8	160	0.99	--	6.5	12	--	--	--
	322C031	70 - 71	3.6	110	0.73	--	5.2	8.7	--	--	--
	322C032	80 - 81	2.8	110	0.69	--	2.9	7.3	--	--	--
	322C033	91 - 92	5.7	130	1	--	6.6	11	--	--	--
	322C034	100 - 101	3.5	110	0.8	--	4.4	11	--	--	--
	322C035	111 - 112	4.1	140	0.93	--	15	8.4	--	--	--
	322C036	122 - 123	5.3	130	0.84	--	7.6	10	--	--	1.1 (B)

Table A.5-4
Soil Sample Results for Metals Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 3 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic	Barium	Beryllium	Cadmium	Chromium	Lead	Mercury	Selenium	Silver
Preliminary Action Levels			23 ^a	67,000 ^b	1,900 ^b	450 ^b	450 ^b	750 ^b	310 ^b	5,100 ^b	5,100 ^b
C09	322C037	0 - 0.5	5.3	140	0.71	--	6.2 (J+)	14	--	--	--
	322C038	0 - 0.5	4.3	140	0.75	--	6.7 (J+)	27	--	0.79 (J-)	--
	322C042	10 - 11	4.5	160	0.92	--	5.6 (J+)	12	--	--	1.4
	322C043	20 - 21	4.3	140	0.78	--	6.6 (J+)	8.4	--	--	--
	322C044	30 - 31	3.9	130	0.7	--	5 (J+)	7.6	--	--	--
	322C045	40 - 41	4.3	140	0.81	--	5.8 (J+)	9.3	--	--	--
	322C046	51 - 52	4.6	180	0.76	--	11	8.5	--	--	1.1
	322C047	60 - 61	3.3	150	0.66	--	4.8 (J+)	8.5	--	0.67	--
	322C048	70 - 71	4.5	120	0.78	--	42	9.7	--	0.56	--
	322C049	81 - 82	3.2	150	0.9	--	4.5 (J+)	22	--	--	--
	322C050	92 - 93	5.1	120	0.81	--	5.6	9	--	--	--
	322C051	101 - 102	3.9	110	0.9	--	5.5	8.2	--	--	--
	322C052	111 - 112	5	150	1.1	--	5.7	10	--	--	--
	322C053	121 - 122	4.4	120	0.73	--	5.3	8.9	--	--	--

Table A.5-4
Soil Sample Results for Metals Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 4 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic	Barium	Beryllium	Cadmium	Chromium	Lead	Mercury	Selenium	Silver
Preliminary Action Levels			23 ^a	67,000 ^b	1,900 ^b	450 ^b	450 ^b	750 ^b	310 ^b	5,100 ^b	5,100 ^b
C10	322C056	1 - 2	3.3	130	0.69	--	5	7.8	--	--	--
	322C057	10 - 11	2.7	100	--	--	4.5	6.2	--	--	--
	322C058	21 - 22	4.4	130	0.61	--	7.8	9.2	--	--	--
	322C059	30 - 31	4.2	150	0.75	--	5	8.2	--	--	--
	322C060	41 - 42	4.9	140	0.96	--	6.1	9.6	--	--	--
	322C061	51 - 52	6	160	0.92	--	8	11	--	0.91	--
	322C062	60 - 61	4.3	140	0.78	--	5.6	9.2	--	--	--
	322C063	71 - 72	3.1	98	0.55	--	3.8	7.4	--	--	--
	322C064	81 - 82	3.4	110	0.75	--	3.6	12	--	--	--
	322C065	81 - 82	2.7	99	0.68	--	3.2	7.3	--	--	--
	322C066	91 - 92	3	120	0.62	--	3.4	9.2	--	--	--
	322C067	101 - 102	3.3	100	0.91	--	5.1	8.6	--	--	--
C11	322C068	0 - 1	4.4	140	0.82	--	6.3	13	0.57	--	--
	322C069	49 - 50	4.3	250	0.65	--	4.2	8.6	--	--	--
	322C070	59 - 60	3.3	200	0.73	--	3.1	6.2	--	--	--
	322C071	69 - 70	4	110	0.73	--	4.6	8.4	--	--	--

Table A.5-4
Soil Sample Results for Metals Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 5 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)								
			Arsenic	Barium	Beryllium	Cadmium	Chromium	Lead	Mercury	Selenium	Silver
Preliminary Action Levels			23 ^a	67,000 ^b	1,900 ^b	450 ^b	450 ^b	750 ^b	310 ^b	5,100 ^b	5,100 ^b
C12	322C072	0 - 1	4.4	150	0.76	--	5.8	10	--	--	--
	322C073	49 - 50	4.1	180	0.89	--	5.9	10	--	--	--
	322C074	59 - 60	4	180	0.78	--	4.9	11	--	--	--
	322C075	69 - 70	5	110	0.94	--	5.6	9.9	--	0.69	--
C19	322C095	9 - 10	4.4	130	--	--	5.5	9.9	--	--	--
	322C100	49 - 50	6.2	180	--	--	8.3	10	--	--	--
	322C101	59 - 60	4.2	150	--	--	9.1	11	--	--	--
	322C102	69 - 70	3.3	130	--	--	6.7	7.7	--	--	--

^aBased on the background concentrations for metals. Background is considered the mean plus two times the standard deviation for sediment samples collected by the Nevada Bureau of Mines and Geology throughout the Nevada Test and Training Range (NBMG, 1998; Moore, 1999).

^bBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002)

ft bgs = Feet below ground surface

mg/kg = Milligrams per kilogram

B = Analyte found in both sample and associated blank.

J+ = This result is an estimated quantity, but the result may be biased high. Field Blank or Equipment Rinsate Blank or Source Blank contamination.

J- = The result is an estimated quantity, but the result may be biased low. Negative bias found in continuing calibration/method blank.

-- = Not detected above minimum reporting limits

**Table A.5-5
Soil Sample Results for PCBs Detected Above
Minimum Reporting Limits at CAS 03-20-05, Injection Well**

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (µg/kg)	
			Aroclor 1254	Aroclor 1260
Preliminary Action Levels ^a			740	740
C01	322C001	0 - 0.5	45 (J) ^b	--
C02	322C004	0 - 0.5	71 (J) ^b	89
C03	322C007	0 - 0.5	130 (J) ^b	--
C05	322C013A	0 - 0.5	110 (J) ^b	--
C06	322C016	0 - 1	3,300 (J) ^c	--
	322C017	3 - 4	280 (J) ^d	--
	322C018	5 - 6	580 (J) ^d	--
C07	322C019	0 - 2	2,400 (J) ^c	--
	322C020	3 - 4	250 (J) ^d	--
	322C021	5 - 6	180 (J) ^d	--
	322C091	14 - 15	--	69
	322C092	19 - 20	110	160
	322C093	24 - 25	130 (J) ^e	140 (J) ^e
C08	322C024	0 - 2	1,100 (J) ^c	--
C09	322C037	0 - 0.5	43 (J) ^b	--
	322C038	0 - 0.5	37 (J) ^b	--
C19	322C101	59 - 60	--	46

^aBased on U.S. Environmental Protection Agency, *Region 9 Preliminary Remediation Goals* (PRGs) (EPA, 2002)

^bQualifier added to laboratory data; record accepted. %D between columns > 25.

^cQualifier added to laboratory data; record accepted. %D between columns > 25. Surrogates diluted out.

^dQualifier added to laboratory data; record accepted. %D between columns > 25. Surrogate recovery exceeded the lower limits.

^eQualifier added to laboratory data; record accepted. Surrogate recovery exceeded the lower limits.

ft bgs = Feet below ground surface

µg/kg = Micrograms per kilogram

J = Estimated value.

-- = Not detected above minimum reporting limits.

and location C18 did not indicate TPH-DRO above the PAL. Asphalt is not considered an environmental contaminant when applied for its intended purpose; therefore, the detection of TPH-DRO above the PAL at location C18 is not considered a COC.

Higher levels of TPH contamination were identified in conjunction with the injection well including sample locations C06 and C07 inside the well vault and C08 and C19 outside the well vault. Concentrations of TPH-DRO at locations C06 and C07 were relatively high (maximum of 45,000 mg/kg) and generally decreased with depth. At the maximum depth of location C06,

Table A.5-6
Soil Sample Results for TPH-DRO Detected Above
Minimum Reporting Limits at CAS 03-20-05, Injection Well

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (mg/kg)
			Diesel Range Organics
Preliminary Action Levels ^a			100
C02	322C004	0 - 0.5	26 (H, M)
C04	322C010	0 - 0.5	77 (H, M)
C05	322C013A	0 - 0.5	40 (H, M)
C06	322C016	0 - 1	45,000 (J)
	322C017	3 - 4	6,600 (J)
	322C018	5 - 6	6,400 (J)
C07	322C019	0 - 2	35,000 (J)
	322C020	3 - 4	5,900 (J)
	322C021	5 - 6	3,300 (J)
	322C091	14 - 15	2,000 (H, M)
	322C092	19 - 20	1,100 (H, M)
	322C093	24 - 25	1,000 (H, M)
C08	322C024	0 - 2	91 (H, M)
	322C029	50 - 51	57 (H, M)
	322C030	60 - 61	730 (H, M)
C09	322C037	0 - 0.5	47 (H, M)
	322C038	0 - 0.5	55 (H, M)
C11	322C068	0 - 1	45 (H, M)
C18	322C087	0.5 - 1	150 (D, M)
C19	322C095	9 - 10	33 (M)
	322C101	59 - 60	1,800 (H, M)
	322C102	69 - 70	32 (H)

^aBased on *Nevada Administrative Code*; Contamination of soil: Establishment of action levels (NAC, 2002)

ft bgs = Feet below ground surface

mg/kg = Milligrams per kilogram

D = A pattern resembling diesel was detected in the sample.

H = The fuel pattern was in the heavier end of the retention time window for the Analyte of interest

M = A pattern resembling motor oil was detected.

J = Estimate value. Qualifier added to laboratory data; record accepted. Surrogates diluted out.

5 to 6 ft bgs, the concentration of TPH-DRO was 6,400 mg/kg. At the maximum depth of location C07, 25 to 25 ft bgs, the concentration of TPH-DRO was 1,000 mg/kg (Figure A.5-4).

At locations C08 and C19 located approximately 16 ft and 6 ft from the injection well sump, respectively, TPH-DRO contamination was identified above the PAL only in samples collected at the 60 to 61 ft bgs interval. Samples above and below this interval indicated no TPH-DRO contamination above PALs. The 60 to 61 ft bgs interval approximately coincides with the observed depth of the injection well sump, approximately 62 ft bgs.

The lateral extent of TPH-DRO contamination associated with the Injection Well was established by field screening and sample results at locations C11 to the north and C12 to the south. Contamination associated with the shallow subsurface around the vault does not appear to extend beyond the vault casing as demonstrated by the TPH-DRO results in C04 and C19. Contamination associated with the bottom of the injection well does not extend beyond approximately 20 ft laterally from the injection well sump, as demonstrated by the fact that TPH-DRO was not detected above MRLs in samples collected at location C12. It is unclear if the contamination in the two zones are connected; however, for purposes of recommending a closure alternative it will be assumed the contamination extends the entire length of the injection well sump from the surface of the soils within the injection well vault to a depth of 62 ft bgs (Figure A.5-4).

A.5.2.5.6 *Gamma-Emitting Radionuclides*

Analytical results for gamma-emitting radionuclides in soil samples collected at CAS 03-20-05, that exceeded MDCs are presented in Table A.5-7. Samples 322C020 and 322C021 at sample location C07 indicated americium-141 results of 19.7 pCi/g and 11.9 pCi/g at depths of 3 to 4 ft bgs and 5 to 6 ft bgs, respectively. Sample 322C021 at sample location C07 indicated a result for cesium-137 of 10.1 pCi/g at a depth of 5 to 6 ft bgs. Additional samples were collected to determine the vertical extent of these contaminants. Samples collected below the original samples indicate the radiological contamination ends prior to 14 ft bgs (a clean sample was obtained at 14 to 15 ft bgs and the last dirty sample was obtained at 5 to 6 ft bgs; no samples were collected in between). Sample analytical results for the 14 to 15 ft bgs interval and those below this depth indicate a deficiency of the radiological contaminants relative to background levels. Lateral extent of contamination is believed

Figure A.5-4
Profile of Injection Well Sump and Vault with Analytical Results

Table A.5-7
Soil Sample Results for Gamma-Emitting Radionuclides
Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 1 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)															
			Actinium-228 ^a		Americium-241 ^b	Bismuth-212 ^a		Bismuth-214 ^a		Cesium-137 ^b	Europium-152 ^b	Lead-212 ^a		Lead-214 ^a		Thallium-208 ^a		Thorium-234 ^b
			5	15	7.62	5	15	5	15	7.3	3.4	5	15	5	15	5	15	63.2
Depth bgs (cm)		<15	>15	<15		>15	<15	>15	<15			>15	<15	>15				
C01	322C001	0 - 0.5	1.72 (G)	NA	—	—	NA	1.13 (G)	NA	—	—	1.63 (J)	NA	1.27 (J)	NA	0.51 (G)	NA	3.2 (J)
	322C002	2 - 3	NA	2.08 (G)	—	NA	—	NA	0.82 (G)	—	—	NA	1.86 (J)	NA	1.18 (J)	NA	0.54 (G)	—
	322C003	4 - 5	NA	1.68 (G)	—	NA	—	NA	0.97 (G)	—	—	NA	1.91 (J)	NA	1.13 (J)	NA	0.47 (G)	—
C02	322C004	0 - 0.5	1.65 (G)	NA	0.76 (J)	—	NA	1 (G)	NA	1.05 (G)	—	2.12 (J)	NA	1.12 (J)	NA	0.63 (G)	NA	—
	322C005	2 - 3	NA	1.72 (G)	—	NA	—	NA	1.32 (G)	—	—	NA	2.17 (J)	NA	1.37 (J)	NA	0.76 (G)	—
	322C006	5 - 6	NA	1.96 (G)	—	NA	—	NA	1.55 (G)	—	—	NA	2.35 (J)	NA	1.34 (J)	NA	0.72 (G)	—
C03	322C007	0 - 0.5	1.93 (G)	NA	—	—	NA	0.86 (G)	NA	—	—	2.17 (J)	NA	1.24 (J)	NA	0.59 (G)	NA	—
	322C008	2 - 3	NA	1.79 (G)	—	NA	—	NA	1.18 (G)	—	1.03 (G)	NA	2.17 (J)	NA	1.4 (J)	NA	0.63 (G)	—
	322C009	5 - 6	NA	1.3 (G)	—	NA	—	NA	0.87 (G)	—	—	NA	1.78 (J)	NA	0.91 (J)	NA	0.58 (G)	—
C04	322C010	0 - 0.5	1.78 (G)	NA	—	—	NA	1.14 (G)	NA	—	—	1.84 (J)	NA	0.95 (J)	NA	0.48 (G)	NA	—
	322C011	4 - 5	NA	2.04 (G)	—	NA	—	NA	1.35 (G)	—	—	NA	2.52 (J)	NA	1.35 (J)	NA	0.76 (G)	—
	322C012	7 - 8	NA	1.59 (G)	—	NA	—	NA	1.29 (G)	—	—	NA	2.2 (J)	NA	0.98 (J)	NA	0.72 (G)	—
	322C013	7 - 8	NA	1.86 (G)	—	NA	3.3 (G)	NA	1.23 (G)	—	—	NA	2.2 (J)	NA	1.49 (J)	NA	0.6 (G)	—
C05	322C013A	0 - 0.5	1.66 (G)	NA	4.64 (J)	—	NA	1.25 (G)	NA	0.39 (G, LT)	—	2.39 (J)	NA	1.22 (J)	NA	0.61 (G)	NA	—
	322C014	2 - 3	NA	1.9 (G)	1.66 (J)	NA	—	NA	0.84 (G)	2.86 (G)	0.76 (G)	NA	2.1 (J)	NA	1.35 (J)	NA	0.59 (G)	—
	322C015	5 - 6	NA	2.67 (G)	—	NA	—	NA	1.4 (G)	—	—	NA	2.4 (J)	NA	1.51 (J)	NA	0.63 (G)	—
C06	322C016	0 - 1	NA	—	2.51 (J)	NA	—	NA	—	3.03 (G)	—	NA	1.07 (J)	NA	—	NA	0.48 (G)	—
	322C017	3 - 4	NA	—	3.91 (J)	NA	—	NA	—	0.84 (G)	—	NA	1.11 (J)	NA	0.97 (J)	NA	0.52 (G)	—
	322C018	5 - 6	NA	—	2.06 (J)	NA	—	NA	0.92 (G)	2.97 (G)	—	NA	1.44 (J)	NA	1.04 (J)	NA	0.57 (G)	—

Table A.5-7
Soil Sample Results for Gamma-Emitting Radionuclides
Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 2 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)															
			Actinium-228 ^a		Americium-241 ^b	Bismuth-212 ^a		Bismuth-214 ^a		Cesium-137 ^b	Europium-152 ^b	Lead-212 ^a		Lead-214 ^a		Thallium-208 ^a		Thorium-234 ^b
			5	15	7.62	5	15	5	15	7.3	3.4	5	15	5	15	5	15	63.2
Depth bgs (cm)		<15	>15	<15		>15	<15	>15	<15			>15	<15	>15	<15	>15		
C07	322C019	0 - 2	NA	—	—	NA	—	NA	—	2 (G)	—	NA	1.01 (J)	NA	—	NA	—	—
	322C020	3 - 4	NA	—	19.7 (J)	NA	—	NA	—	4.23 (G)	—	NA	1.5 (J)	NA	—	NA	—	—
	322C021	5 - 6	NA	—	11.9 (J)	NA	—	NA	—	10.1 (G)	—	NA	1.34 (J)	NA	0.98 (J)	NA	—	—
	322C091	14 - 15	NA	1.69 (G)	—	NA	—	NA	0.83 (G,J)	—	—	NA	1.83 (J)	NA	1.02 (G,J)	NA	0.56 (G)	—
	322C092	19 - 20	NA	1.74 (G)	—	NA	2.9 (G)	NA	1.07 (G,J)	—	—	NA	2.11 (J)	NA	1.4 (G,J)	NA	0.73 (G)	—
	322C093	24 - 25	NA	1.5 (G)	—	NA	—	NA	1.14 (G,J)	—	—	NA	2.18 (J)	NA	1.42 (G,J)	NA	0.59 (G)	4.8 (J)
C08	322C024	0 - 2	NA	—	—	NA	—	NA	—	2.19 (G)	1.31 (G, TI)	NA	1.39 (J)	NA	0.95 (J)	NA	0.58 (G)	—
	322C025	9 - 10	NA	—	—	NA	—	NA	1.15	—	—	NA	1.44	NA	0.93	NA	0.6	—
	322C026	20 - 21	NA	—	—	NA	—	NA	—	—	—	NA	1.68 (J)	NA	0.95 (J)	NA	—	—
	322C027	30 - 31	NA	1.5 (G)	—	NA	—	NA	0.9 (G)	—	—	NA	1.88 (J)	NA	0.98 (J)	NA	—	—
	322C028	40 - 41	NA	1.71 (G)	—	NA	—	NA	—	—	—	NA	1.87 (J)	NA	0.86 (J)	NA	0.46 (G)	—
	322C029	50 - 51	NA	—	—	NA	—	NA	—	—	—	NA	1.66	NA	0.81	NA	—	—
	322C030	60 - 61	NA	—	—	NA	—	NA	—	—	—	NA	1.43 (J)	NA	0.79 (J)	NA	0.49 (G)	—
	322C031	70 - 71	NA	1.91 (G)	—	NA	—	NA	—	—	—	NA	1.4 (J)	NA	1.18 (J)	NA	0.5 (G)	—
	322C032	80 - 81	NA	1.67 (G)	—	NA	—	NA	—	—	—	NA	1.89 (J)	NA	0.88 (J)	NA	0.47 (G)	—
	322C033	91 - 92	NA	—	—	NA	—	NA	—	—	—	NA	1.68 (J)	NA	1.02 (J)	NA	0.73 (G)	—
	322C034	100 - 101	NA	2.02 (G)	—	NA	—	NA	—	—	—	NA	1.65 (J)	NA	1.21 (J)	NA	0.81 (G)	—
	322C035	111 - 112	NA	—	—	NA	—	NA	1.47 (G)	—	—	NA	1.71 (J)	NA	1.05 (J)	NA	0.61 (G)	—
	322C036	122 - 123	NA	2.23 (G, TI)	—	NA	—	NA	1.22 (G)	—	—	NA	1.72 (J)	NA	1.06 (J)	NA	0.64 (G)	—

Table A.5-7
Soil Sample Results for Gamma-Emitting Radionuclides
Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 3 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)															
			Actinium-228 ^a		Americium-241 ^b	Bismuth-212 ^a		Bismuth-214 ^a		Cesium-137 ^b	Europium-152 ^b	Lead-212 ^a		Lead-214 ^a		Thallium-208 ^a		Thorium-234 ^b
			5	15		5	15	5	15			5	15	5	15	5	15	
Preliminary Action Levels			5	15	7.62	5	15	5	15	7.3	3.4	5	15	5	15	5	15	63.2
Depth bgs (cm)			<15	>15		<15	>15	<15	>15			<15	>15	<15	>15	<15	>15	
C09	322C037	0 - 0.5	1.68 (G)	NA	—	—	NA	1.2 (G)	NA	0.6 (G)	—	1.78 (J)	NA	1.2 (J)	NA	0.59 (G)	NA	—
	322C038	0 - 0.5	1.62 (G)	NA	—	—	NA	1.29 (G)	NA	0.71 (G)	—	1.79 (J)	NA	1.17 (J)	NA	0.49 (G)	NA	—
	322C042	10 - 11	NA	1.95 (G)	—	NA	—	NA	1.18 (G)	—	—	NA	2.17 (J)	NA	1.06 (J)	NA	0.75 (G)	—
	322C043	20 - 21	NA	1.57 (G)	—	NA	—	NA	0.88 (G)	—	—	NA	2.02 (J)	NA	1.17 (J)	NA	0.67 (G)	—
	322C044	30 - 31	NA	1.79 (G)	—	NA	—	NA	1.12 (G)	—	—	NA	1.94 (J)	NA	1.11 (J)	NA	0.42 (G)	—
	322C045	40 - 41	NA	1.7 (G)	—	NA	—	NA	1.27 (G)	—	—	NA	2.11 (J)	NA	1.17 (J)	NA	0.7 (G)	—
	322C046	51 - 52	NA	1.75 (G)	—	NA	—	NA	1.2 (G)	—	—	NA	1.99 (J)	NA	1.31 (J)	NA	0.63 (G)	—
	322C047	60 - 61	NA	1.32 (G)	—	NA	—	NA	0.86 (G)	—	—	NA	1.48 (J)	NA	0.7 (J)	NA	0.55 (G)	—
	322C048	70 - 71	NA	1.75 (G)	—	NA	—	NA	1.02 (G)	—	—	NA	2.19 (J)	NA	1.23 (J)	NA	0.56 (G)	—
	322C049	81 - 82	NA	1.64 (G)	—	NA	—	NA	1.52 (G)	—	—	NA	2.23 (J)	NA	1.5 (J)	NA	0.67 (G)	—
	322C050	92 - 93	NA	—	—	NA	—	NA	1.58 (G)	—	—	NA	2.05 (J)	NA	1.31 (J)	NA	0.48 (G)	—
	322C051	101 - 102	NA	—	—	NA	—	NA	1.27 (G)	—	—	NA	1.53 (J)	NA	1.25 (J)	NA	0.58 (G)	—
	322C052	111 - 112	NA	—	—	NA	—	NA	—	—	—	NA	1.57 (J)	NA	1.03 (J)	NA	0.55 (G)	—
	322C053	121 - 122	NA	—	—	NA	—	NA	1.16 (G)	—	—	NA	1.5 (J)	NA	0.91 (J)	NA	0.55 (G)	—

Table A.5-7
Soil Sample Results for Gamma-Emitting Radionuclides
Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 4 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)															
			Actinium-228 ^a		Americium-241 ^b	Bismuth-212 ^a		Bismuth-214 ^a		Cesium-137 ^b	Europium-152 ^b	Lead-212 ^a		Lead-214 ^a		Thallium-208 ^a		Thorium-234 ^b
Preliminary Action Levels			5	15	7.62	5	15	5	15	7.3	3.4	5	15	5	15	5	15	63.2
Depth bgs (cm)			<15	>15		<15	>15	<15	>15			<15	>15	<15	>15	<15	>15	
C10	322C056	1 - 2	NA	—	—	NA	—	NA	—	—	—	NA	1.47 (J)	NA	0.84 (J)	NA	0.41 (G)	—
	322C057	10 - 11	NA	1.34	—	NA	—	NA	0.92	—	—	NA	1.66	NA	0.91	NA	0.41	—
	322C058	21 - 22	NA	1.66	—	NA	—	NA	0.9	—	—	NA	1.62	NA	0.98	NA	0.57	—
	322C059	30 - 31	NA	1.41 (G)	—	NA	—	NA	—	—	—	NA	1.41 (J)	NA	0.78 (J)	NA	0.37 (G)	—
	322C060	41 - 42	NA	—	—	NA	—	NA	1.09 (G)	—	—	NA	1.65 (J)	NA	1.29 (J)	NA	0.52 (G)	—
	322C061	51 - 52	NA	—	—	NA	—	NA	—	—	—	NA	1.38 (J)	NA	0.92 (J)	NA	0.51 (G)	—
	322C062	60 - 61	NA	—	—	NA	—	NA	0.95	—	—	NA	1.32	NA	0.9	NA	0.54	—
	322C063	71 - 72	NA	1.42 (Ti)	—	NA	—	NA	—	—	—	NA	1.38	NA	0.94	NA	—	—
	322C064	81 - 82	NA	1.48 (G)	—	NA	—	NA	—	—	—	NA	1.92 (J)	NA	0.96 (J)	NA	0.54 (G)	—
	322C065	81 - 82	NA	1.49 (G)	—	NA	—	NA	—	—	—	NA	2.06 (J)	NA	0.92 (J)	NA	0.39 (G)	—
	322C066	91 - 92	NA	1.71	—	NA	—	NA	0.84	—	—	NA	1.44	NA	0.86	NA	0.4	—
	322C067	101 - 102	NA	1.92 (G)	—	NA	—	NA	1.18 (G)	—	—	NA	1.8 (J)	NA	1.25 (J)	NA	0.61 (G)	—
C11	322C068	0 - 1	NA	1.95 (G)	2.17 (J)	NA	—	NA	1.35 (G)	1.04 (G)	1.3 (G)	NA	2.14 (J)	NA	1.43 (J)	NA	0.74 (G)	—
	322C069	49 - 50	NA	1.5 (G)	—	NA	—	NA	1.02 (G)	—	—	NA	1.84 (J)	NA	1.23 (J)	NA	0.66 (G)	—
	322C070	59 - 60	NA	1.68 (G)	—	NA	—	NA	0.95 (G)	—	—	NA	1.87 (J)	NA	0.97 (J)	NA	0.51 (G)	—
	322C071	69 - 70	NA	1.92 (G)	—	NA	—	NA	1.14 (G)	—	—	NA	2.14 (J)	NA	1.2 (J)	NA	0.63 (G)	—

Table A.5-7
Soil Sample Results for Gamma-Emitting Radionuclides
Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 5 of 5)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)															
			Actinium-228 ^a		Americium-241 ^b	Bismuth-212 ^a		Bismuth-214 ^a		Cesium-137 ^b	Europium-152 ^b	Lead-212 ^a		Lead-214 ^a		Thallium-208 ^a		Thorium-234 ^b
			5	15	7.62	5	15	5	15	7.3	3.4	5	15	5	15	5	15	63.2
Depth bgs (cm)		<15	>15	<15		>15	<15	>15	<15			>15	<15	>15				
C12	322C072	0 - 1	NA	1.84 (G)	7.28 (J)	NA	--	NA	1.16 (G)	5.45 (G)	0.91 (G, TI)	NA	1.88 (J)	NA	1.23 (J)	NA	0.56 (G)	--
	322C073	49 - 50	NA	2.04 (G)	--	NA	--	NA	0.97 (G)	--	--	NA	2.1 (J)	NA	1.21 (J)	NA	0.68 (G)	--
	322C074	59 - 60	NA	1.93 (G)	--	NA	--	NA	0.87 (G)	--	--	NA	1.95 (J)	NA	1.14 (J)	NA	0.54 (G)	--
	322C075	69 - 70	NA	2.05 (G)	--	NA	--	NA	1.11 (G)	--	--	NA	2.25 (J)	NA	1.45 (J)	NA	0.71 (G)	--
C19	322C095	9 - 10	NA	1.88 (G)	--	NA	--	NA	1.08 (G,J)	--	--	NA	1.92 (J)	NA	1.04 (G,J)	NA	0.49 (G)	--
	322C100	49 - 50	NA	1.73 (G)	--	NA	--	NA	1.26 (G,J)	--	--	NA	1.84 (J)	NA	1.18 (G,J)	NA	0.61 (G)	--
	322C101	59 - 60	NA	1.64 (G)	--	NA	--	NA	1.09 (G,J)	--	--	NA	1.97 (J)	NA	1.1 (G,J)	NA	0.65 (G)	--
	322C102	69 - 70	NA	1.74 (G)	--	NA	1.45 (G)	NA	1.05 (G,J)	--	--	NA	2.00 (J)	NA	1.02 (G,J)	NA	0.52 (G)	2.3 (J)

^aTaken from the generic guidelines for residual concentrations of actinium-228, bismuth-214, lead 212, thallium-208, and thorium-232, as found in Chapter IV of DOE Order 5400.5, Change 2, "Radiation Protection of the Public and Environment" (DOE, 1993). The PALs for these isotopes is specified as 5 picocuries per gram (pCi/g) averaged over the first 15 centimeters (cm) of soil and 15 pCi/g for deeper soils (DOE, 1993). For purposes of this document, 15 cm is assumed to be equivalent to 0.5 ft (6 inches); therefore, 5 pCi/g represents the PALs for these radionuclides in the surface soil (0 to 0.5 ft depth).

^bTaken from the construction, commercial, industrial land use scenario in Table 2.1 of the NCRP Report No. 129, *Recommended Screening Limits for Contaminated Surface Soil and Review Factors Relevant to Site-Specific Studies* (NCRP, 1999). The values provided in this source document were scaled to a 15-mrem/yr dose.

ft bgs = Feet below ground surface

cm = Centimeter

pCi/g = Picocuries per gram

-- = Not detected above minimum reporting limits

> = Greater than

< = Less than

G = Sample density differs by more than 15 percent of laboratory control sample density.

TI = Tentatively identified

J = Estimated value. Qualifier added to laboratory data; record accepted. Sample does not meet counting geometry requirements.

LT = Result is less than the requested minimum detectable concentration, greater than the specific minimum detectable concentration.

NA = Not applicable

to be confined to within the injection well casing. This is established by sample results for samples collected at locations C04, C08, C12, and C19 (Figure A.5-4).

A.5.2.5.7 Plutonium

Analytical results for plutonium in soil samples collected at CAS 03-20-05, that exceeded MDCs are presented in Table A.5-8. Plutonium contamination above PALs was found in two patterns at this site (i.e., surface contamination and contamination within the injection well vault).

Surface plutonium contamination was identified at four sample locations at concentrations above the PAL. Sample 322C038 at sample location C09 indicated a plutonium-239 result of 37.8 pCi/g at a depth of 0 to 1 ft bgs. Samples collected around and beneath this location were below the PAL. Sample 322C079 at sample location C14 indicated a plutonium-239 result of 44.2 pCi/g at a depth of 0 to 0.5 pCi/g ft bgs. Samples collected around and beneath this location were below the PAL. Sample 322C024 at sample location C08 indicated a plutonium-239 result of 40.4 pCi/g at a depth of 0 to 2 ft bgs. Samples collected below this location were below the PAL; however, sample 322C078 at the adjacent sample location (C18) indicated a plutonium-239 result of 8.3 pCi/g at a depth of 0 to 0.5 ft bgs. All of these were surface samples collected outside the injection well casing and are believed to be the result of deposition from atmospheric testing; therefore, the plutonium is not considered to be a COC detection at these locations. However, as a best management practice approximately 1 ft³ of soil was removed from each of these locations and drummed for management as waste to mitigate potential personnel exposures. Verification samples were collected; however, these sample results are still pending and will be reported in the Final CADD.

Samples 322C020 and 322C021 at sample location C07 (inside the injection well vault) indicated plutonium-239 results of 15 and 29.1 pCi/g at depths of 3 to 4 ft bgs and 5 to 6 ft bgs, respectively. These detections are bounded laterally by uncontaminated sample results at locations C04, C08, C12, and C19 (Figure A.5-4). Additional samples were collected to determine the vertical extent of contamination. Samples collected below the original samples indicate the radiological contamination ends prior to 14 ft bgs. Readings at this depth and those below this depth indicate a deficiency of the radiological contaminants relative to background levels.

A.5.2.5.8 *Strontium-90*

Analytical results for Strontium-90 in soil samples collected at CAS 03-20-05, that exceeded MDCs are presented in Table A.5-8. Strontium-90 was not detected above the PAL.

A.5.2.5.9 *Uranium*

Analytical results for gamma-emitting radionuclides in soil samples collected at CAS 03-20-05, that exceeded MDCs are presented in Table A.5-8. Uranium was not detected above the PAL.

A.5.2.6 *Contaminants of Concern*

The COCs lead, Aroclor-1254, TPH-DRO, cesium-137, americium-141, and plutonium-239 were identified in samples taken from the injection well. In addition, Aroclor-1254 and TPH-DRO was identified at several surface locations at CAS 03-20-05. Lead and cadmium were identified above the FAL for samples within the injection well soils (cadmium was above the RCRA TCLP minimum for the characteristic of toxicity in the surface samples of soils within the injection well). Samples collected around the outside of the injection well and from deeper locations within the injection well provide results below the FALs and RCRA TCLP maximums for these metals.

Aroclor-1254 was identified above the FAL at three locations, two within the injection well vault and one at a surface location outside the vault. The surface location was excavated to remove colocated Pu-239 contamination.

Total petroleum hydrocarbon-DRO contamination was identified within the injection well vault soils, within soils collected at the depth of the bottom of the injection well sump, and at various surface locations outside the injection well at concentrations above the PAL.

The radionuclides cesium-137, americium-141, and plutonium-239 are contaminants of concern only as their release can be associated with operations that occurred at the BOP Shop. This association requires that their presence be associated with samples collected from the injection well soils as a result of direct deposition from the activities within the BOP Shop via underground piping. Surface deposition of plutonium-239 outside the injection well from atmospheric testing is not considered to be a COC for this CAS, as its origin is not associated with processes occurring at the BOP Shop.

Table A.5-8
Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 1 of 7)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)					
			Plutonium-238	Plutonium-239	Strontium-90	Uranium-234	Uranium-235	Uranium-238
Preliminary Action Levels ^a			7.78	7.62	503	85.9	10.5	63.2
C01	322C001	0 - 0.5	0.142	0.45	--	1.02	--	1.04
	322C002	2 - 3	--	--	--	0.98	--	0.89
	322C003	4 - 5	--	--	--	1.12	--	0.94
C02	322C004	0 - 0.5	0.348	2.82	--	1.11	0.073	0.97
	322C005	2 - 3	--	--	--	0.96	--	0.97
	322C006	5 - 6	--	--	--	0.94	--	1.07
C03	322C007	0 - 0.5	0.73	2.59	--	0.91	--	1.06
	322C008	2 - 3	0.36	2.64	--	0.95	0.054	1.14
	322C009	5 - 6	--	--	--	0.89	--	0.8
C04	322C010	0 - 0.5	0.154	0.82	--	0.92	--	1.05
	322C011	4 - 5	--	--	--	1.13	0.054	1.11
	322C012	7 - 8	--	--	--	1.18	--	0.98
	322C013	7 - 8	--	--	--	0.96	--	1.11

Table A.5-8
Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 2 of 7)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)					
			Plutonium-238	Plutonium-239	Strontium-90	Uranium-234	Uranium-235	Uranium-238
Preliminary Action Levels ^a			7.78	7.62	503	85.9	10.5	63.2
C05	322C013A	0 - 0.5	0.052	0.97	--	0.94	--	0.8
	322C014	2 - 3	0.47	2.77	--	0.76	--	0.87
	322C015	5 - 6	--	0.143	--	1.08	0.088	1.24
C06	322C016	0 - 1	0.143	2.29	--	1.99	0.074	0.97
	322C017	3 - 4	0.274	2.29	--	1.24	--	0.96
	322C018	5 - 6	0.76	5.56	0.51 (J) ^b	1.78	--	1.18
C07	322C019	0 - 2	0.266	2.54	--	1.63	--	0.86
	322C020	3 - 4	1.27	15 (J) ^c	--	1.71	0.081	1.02
	322C021	5 - 6	0.95	29.1	--	1.47	--	0.94
	322C091	14 - 15	--	--	--	0.94	--	0.86
	322C092	19 - 20	--	0.044 (LT)	--	1.29	0.075	1.22
	322C093	24 - 25	--	--	--	1.27	0.081	1.11

Table A.5-8
Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 3 of 7)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)					
			Plutonium-238	Plutonium-239	Strontium-90	Uranium-234	Uranium-235	Uranium-238
Preliminary Action Levels ^a			7.78	7.62	503	85.9	10.5	63.2
C08	322C024	0 - 2	2.29	40.4	--	0.98	--	0.93
	322C025	9 - 10	--	--	--	1.32	--	1.16
	322C026	20 - 21	--	--	--	1.22	0.083	1.12
	322C027	30 - 31	--	--	--	1.06	0.06	1.05
	322C028	40 - 41	--	--	--	1.03	0.056	1.01
	322C029	50 - 51	--	--	--	1	--	0.96
	322C030	60 - 61	--	--	--	0.89	--	1
	322C031	70 - 71	--	--	--	1.07	0.075	1.05
	322C032	80 - 81	--	--	--	1.09	--	1.07
	322C033	91 - 92	--	--	--	1.36	--	1.46
	322C034	100 - 101	--	--	--	1.35	0.082	1.24
	322C035	111 - 112	--	--	--	1.19	0.09	1.27
	322C036	122 - 123	--	--	--	1.11	--	1.16
	322C105	0.5 - 1.5	0.283	4.29	--	--	--	--

Table A.5-8
Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 4 of 7)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)					
			Plutonium-238	Plutonium-239	Strontium-90	Uranium-234	Uranium-235	Uranium-238
Preliminary Action Levels ^a			7.78	7.62	503	85.9	10.5	63.2
C09	322C037	0 - 0.5	0.078	0.74	--	0.84	--	0.88
	322C038	0 - 0.5	0.55	37.8	--	1.01	0.071	1.08
	322C042	10 - 11	--	--	--	1.18	--	1.04
	322C043	20 - 21	--	--	--	0.94	0.068	0.94
	322C044	30 - 31	--	--	--	0.99	0.076	1.08
	322C045	40 - 41	--	--	--	1.16	0.069	1.04
	322C046	51 - 52	--	0.046 (LT)	--	1.1	0.089	1.12
	322C047	60 - 61	--	--	--	0.82	--	0.72
	322C048	70 - 71	--	--	--	1	--	0.98
	322C049	81 - 82	--	--	--	1.05	--	1.21
	322C050	92 - 93	--	--	--	1.53	0.094	1.61
	322C051	101 - 102	--	--	--	1.64	0.085	1.58
	322C052	111 - 112	--	--	--	1.26	0.056	1.32
	322C053	121 - 122	--	--	--	1.02	--	1.07
	322C089	1 - 2	1.4	4.69	--	--	--	--
322C103	0.5 - 1.5	--	0.24	--	--	--	--	

Table A.5-8
Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 5 of 7)

Sample Location		Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)				
				Plutonium-238	Plutonium-239	Strontium-90	Uranium-234	Uranium-235
Preliminary Action Levels ^a			7.78	7.62	503	85.9	10.5	63.2
C10	322C056	1 - 2	0.191	0.88	--	0.93	--	0.9
	322C057	10 - 11	--	--	--	0.94	--	1
	322C058	21 - 22	--	--	--	0.82	0.075	0.72
	322C059	30 - 31	--	--	--	1.03	--	0.98
	322C060	41 - 42	--	--	--	1.09	0.059	1.19
	322C061	51 - 52	--	--	--	0.92	0.058	1
	322C062	60 - 61	--	--	--	0.99	--	1.04
	322C063	71 - 72	--	--	--	0.95	--	0.9
	322C064	81 - 82	--	--	--	0.99	--	1
	322C065	81 - 82	--	--	--	0.97	--	1.09
	322C066	91 - 92	--	--	--	0.89	--	1.02
	322C067	101 - 102	--	--	--	1.32	--	1.39
C11	322C068	0 - 1	--	2.46	--	1	--	0.94
	322C069	49 - 50	--	--	--	1.05	0.033 (LT)	1.16
	322C070	59 - 60	--	--	--	1.04	0.037 (LT)	1.08
	322C071	69 - 70	--	--	--	1.13	0.073	1.09

Table A.5-8
Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 6 of 7)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)					
			Plutonium-238	Plutonium-239	Strontium-90	Uranium-234	Uranium-235	Uranium-238
Preliminary Action Levels ^a			7.78	7.62	503	85.9	10.5	63.2
C12	322C072	0 - 1	0.199 (J) ^c	0.97	--	0.92	--	0.97
	322C073	49 - 50	--	--	--	0.99	0.057	0.98
	322C074	59 - 60	--	--	--	0.97	--	0.99
	322C075	69 - 70	--	--	--	1.21	0.062	1.09
C13	322C076	0 - 0.5	0.042 (LT)	0.47	--	--	--	--
	322C077	0 - 0.5	0.032 (LT)	0.46	--	--	--	--
	322C078	1 - 2	0.105	1.21	--	--	--	--
C14	322C079	0 - 0.5	1.42	44.2	--	--	--	--
	322C080	1 - 2	0.103	0.46	--	--	--	--
	322C104	0.5 - 1.5	--	0.297	--	--	--	--
C15	322C081	0.5 - 1	0.074	0.45	--	--	--	--
	322C082	1 - 2	0.055	0.6	--	--	--	--
C16	322C083	0.5 - 1	--	0.303	--	--	--	--
	322C084	1 - 2	--	0.57	--	--	--	--
C17	322C085	0.5 - 1	--	0.248	--	--	--	--
	322C086	1 - 2	1.05	5.82	--	--	--	--

Table A.5-8
Soil Sample Results for Isotopes Detected Above Minimum Reporting Limits at CAS 03-20-05, Injection Well
(Page 7 of 7)

Sample Location	Sample Number	Depth (ft bgs)	Contaminants of Potential Concern (pCi/g)					
			Plutonium-238	Plutonium-239	Strontium-90	Uranium-234	Uranium-235	Uranium-238
Preliminary Action Levels ^a			7.78	7.62	503	85.9	10.5	63.2
C18	322C087	0.5 - 1	0.131	8.3	--	--	--	--
	322C088	1 - 2	0.73	2.97	--	--	--	--
	322C106	0.5 - 1.5	--	0.7	--	--	--	--
C19	322C095	9 - 10	--	--	--	1.1	--	1.09
	322C100	49 - 50	--	--	--	1.09	0.051	1.18
	322C101	59 - 60	--	--	--	0.97	--	0.87
	322C102	69 - 70	--	--	--	1.08	0.082	0.097

^aTaken from the construction, commercial, industrial land use scenario in Table 2.1 of the NCRP Report No. 129 *Recommended Screening Limits for Contaminated Surface Soil and Review Factors Relevant to Site-Specific Studies* (NCRP, 1999). The values provided in this source document were scaled to a 15-mrem/yr dose.

^bQualifier added to laboratory data; record accepted. Laboratory control sample and/or laboratory control sample duplicate recovery outside control limits.

^cQualifier added to laboratory data; record accepted. Duplicate precision analysis (relative percent difference) outside control limits.

ft bgs = Feet below ground surface

pCi/g = Picocuries per gram

LT = Result is less than the requested minimum detectable concentration, greater than the specific minimum detectable concentration.

-- = Not detected above minimum reporting limits

J = Estimated value.

No other COCs were identified at this site.

A.5.3 Nature and Extent of Contamination

Contamination found within the injection well casing is believed to be the result of processes that occurred within the BOP Shop, as the waste from the Shop was routed to the injection well via underground piping. Additional contamination may have resulted from direct dumping of waste into the injection well casing, as reported by interviewees.

Lead and cadmium contamination was restricted to the injection well vault soils and is bounded vertically by samples collected outside the injection well casing and by samples collected at sampling intervals beneath the contamination.

Aroclor-1254 contamination was limited to the surface soil samples collected within the injection well, and to one location outside the injection well. The contamination outside the injection well was excavated to remove colocated Pu-239 contamination. Vertical extent of Aroclor-1254 contamination was defined by samples collected beneath the surface contamination.

Total petroleum hydrocarbon-DRO was found to be present at levels above the PAL in the soil within the injection well casing. Additional sampling to a depth of 25 ft bgs indicated that TPH-DRO contamination continues to exist above the PAL, and is assumed to be connected to the TPH-DRO contamination associated with samples collected at 60 ft bgs, the depth of the injection well sump.

Total petroleum hydrocarbon-DRO was also identified at a depth of 60 to 61 ft bgs at drilling locations immediately adjacent to the injection well. Sample 322C030 at sample location C08 indicated a TPH-DRO result of 730 ppm. Samples collected above and below this location were below the PAL for TPH-DRO. The source of the TPH-DRO contamination is believed to be the injection well sump, which was determined to end 62 ft bgs. Additional sampling was performed to determine that the TPH-DRO contamination at this depth was not the result of a plume of contamination from the soils within the injection well vault. An additional sample location (C19) was chosen that was closer to the injection well than sample location C08. Location C19 would intercept the plume of contamination (if it existed as an inverted cone) from the injection well soils before the 60 to 61 ft bgs interval was reached. The analytical results indicated that no contamination was

encountered until the 60 to 61 ft bgs interval was reached. At the 60 to 61 ft interval the TPH-DRO concentration was determined to be 1,800 mg/kg. It is assumed that the surface soil contamination is connected as a cylindrical plume until the bottom of the injection well sump is reached.

Also found above their respective PALs was cesium-137, americium-241, and plutonium-239. Subsequent sampling and analysis indicated that the concentrations of these radiological contaminants dropped to below their respective PALs prior to 14 ft bgs.

A.5.4 Revised Conceptual Site Model

No variations in the conceptual site model were identified. However, a more conclusive statement can be made regarding the conceptual site model for the injection well itself. Contamination identified at the 60 to 61 ft bgs interval originates from the bottom of the injection well sump, not from the soils within the injection well vault. The process that placed contaminants within the injection well vault allowed for the percolation of the heavier components (e.g., metals, radionuclides) within the soil surrounding the sump, while the lighter components of the BOP Shop effluent (e.g., petroleum hydrocarbons) were directed down the sump. The location of contaminants identified in the injection well are consistent with its intended design. This conception was realized, as only TPH-DRO was identified at the depth of the injection well sump, and metals and radionuclides were identified within the soils of the injection well vault.

A.6.0 Waste Management

Investigation-derived waste (IDW) was generated during the field investigation activities of CAU 322. The waste streams generated include disposable personal protective equipment (PPE), plastic, disposable sampling equipment, soil and debris, and miscellaneous waste removed as best management practice during the investigation activities. Investigation-derived waste was segregated to the greatest extent possible and waste minimization techniques were integrated into the field activities to reduce the amount of waste generated. Controls were in place to minimize the use of hazardous materials and the unnecessary generation of hazardous and/or mixed waste.

Decontamination activities were planned and executed to minimize the volume of rinsate generated.

The amount, type, and source of waste placed into each drum was recorded in waste management logbooks. Potentially hazardous or potentially radioactive wastes generated during the investigation were placed in containers and labeled as “Hazardous Waste - Pending Analysis, or “Radioactive Waste Pending Analysis.” Three Hazardous Waste Accumulation Areas (HWAAs) were established to manage hazardous and potentially hazardous waste generated during the CAI.

No drums of waste were generated during the investigation of CAS 01-25-01.

Four drums of waste were generated at CAS 03-25-03. One drum contains soil with plutonium-239 contamination and was labeled as “Radioactive Waste - Pending Analysis.” One drum contains soil contaminated with TPH-DRO and was labeled as “Hydrocarbon Waste”, and one drum contains hydrocarbon contaminated plastic liners. The remaining drum contains plastic sample sleeves, and has been deemed to be sanitary waste.

Nine drums of waste were generated at CAS 03-20-05. Three drums are sanitary, and contain plastic core liners from samples obtained during drilling activities and/or plastic sampling equipment and sample containers. One drum contains hydrocarbon-contaminated plastic sheeting that was placed underneath equipment used on site. Four drums contain sanitary soils removed from drilling activities. One drum contains soils removed from surface locations where plutonium-239 was identified, and they are both labeled “Radioactive Waste - Pending Analysis.”

A.6.1 Characterization

Analytical results for each drum of waste or associated samples were reviewed to ensure compliance with federal regulations, state regulations, DOE directives/policies, guidance, and waste disposal criteria. Analytical data was reviewed through Tier I, Tier II, and Tier III validation methods.

A.6.2 Waste Streams

Investigation-derived waste generated during the investigation was segregated into the following waste streams:

- PPE and disposable sampling equipment
- Plastic sheeting and plastic sample sleeves
- Debris including, but not limited to: glass/plastic sample jars, sampling scoops, aluminum foil, and bowls
- Soil and associated debris

A.6.3 Investigation-derived Waste Generated

A total of thirteen (13) drums of IDW have been generated during the investigation:

- Eight (8) drums were characterized as sanitary waste and recommended for disposal at the NTS-permitted sanitary facilities. These drums were generated at CASs 03-25-03 and 03-20-05.
- Three (3) drums of IDW were characterized as hydrocarbon waste exceeding the regulatory threshold established by State of Nevada regulations (NDEP, 1997a and b). The recommended disposal of these drums is at the permitted NTS Hydrocarbon Landfill. The hydrocarbon waste was generated at CASs 03-25-03 and 03-20-05.
- Two (2) drums of soil were characterized as low-level radioactive waste (LLW) and recommended for disposal at the NTS in accordance with the requirements contained in the NTS Waste Acceptance Criteria (NTSWAC) (NNSA/NSO, 2003b). One drum, 322B03 (generated at CAS 03-25-03), is recommended for disposal at the LLW Landfill. Two drums of waste, 322C01 and 322C09 (generated at CAS 03-20-05), are recommended for shipment to the Area 5 Radioactive Waste Management Site (RWMS).

Office waste was disposed of throughout the project at the NTS sanitary landfill. Sanitary industrial waste was inspected and disposed of in the NTS industrial waste landfill. Additional waste (e.g., decontamination pad liners) may be generated during completion of waste management activities and closure of HWAAs.

A.6.4 Waste Characterization Samples

Waste characterization samples were collected from the holding tanks and sumps within the CAS 03-20-05 BOP Shop to facilitate full characterization of the liquids for disposal. A summary of the results of these waste characterization samples is presented in Section A.5.0. Complete results for all samples are maintained in project files. The following sections describe the waste characterization samples collected during the investigation of CAU 322.

A.6.5 Additional Analytical Results Collected For Remediation Waste Characterization

Several additional samples were collected and/or specific analyses added to samples for the purposes of providing information that can be used to characterize wastes removed from this CAS during potential closure activities. The results from these analyses are compared to disposal criteria and not to PALs.

A.6.5.1 Results for Liquid and Oil Samples

Liquid and oil samples were collected from the holding tanks, the tank sumps, and the injection well sump so that these materials could be characterized for disposal. Sample results are presented in Table A.6-1.

Table A.6-1
Liquid and Oil Samples Collected at CAS 03-20-05, Injection Well
(Page 1 of 4)

Sample Number	Sample Matrix	Parameter	Result	Units
322C054L	Liquid	H-3	6,500	pCi/L
322C055L	Liquid	H-3	10,000	pCi/L
322C022A	Liquid	Uranium-238	0.53	pCi/L
322C022A	Liquid	Uranium-234	1.03 (M3)	pCi/L

Table A.6-1
Liquid and Oil Samples Collected at CAS 03-20-05, Injection Well
(Page 2 of 4)

Sample Number	Sample Matrix	Parameter	Result	Units
322C023A	Liquid	Uranium-238	0.44	pCi/L
322C023A	Liquid	Uranium-234	0.63	pCi/L
322C039	Liquid	Uranium-235	0.41 (M3)	pCi/L
322C039	Liquid	Uranium-238	5 (M3)	pCi/L
322C039	Liquid	Uranium-234	17.8 (M3)	pCi/L
322C040	Liquid	Uranium-238	5.11 (M3)	pCi/L
322C040	Liquid	Uranium-234	15.9 (M3)	pCi/L
322C041	Liquid	Uranium-234	0.41	pCi/L
322C022A	Liquid	Gross Beta	143 (M3)	pCi/L
322C023A	Liquid	Gross Beta	191 (M3)	pCi/L
322C039	Liquid	Gross Beta	54 (M3)	pCi/L
322C040	Liquid	Gross Beta	53 (M3)	pCi/L
322C041	Liquid	Gross Alpha	5	pCi/L
322C041	Liquid	Gross Beta	18.5	pCi/L
322C054L	Liquid	Strontium-90	1.19	pCi/L
322C054L	Liquid	Gross Beta	46	pCi/L
322C055L	Liquid	Gross Beta	28.7	pCi/L
322C022A	Liquid	Selenium	0.054 (J-)	mg/L
322C022A	Liquid	Chromium	0.34	mg/L
322C022A	Liquid	Lead	0.39	mg/L
322C022A	Liquid	Cadmium	1.8	mg/L
322C023A	Liquid	Lead	0.33	mg/L
322C023A	Liquid	Cadmium	0.87	mg/L
322C039	Liquid	Lead	0.037 (J-)	mg/L
322C041	Liquid	Lead	0.3	mg/L
322C022A	Liquid	Mercury	0.0074	mg/L
322C023A	Liquid	Mercury	0.0045	mg/L
322C039	Liquid	Diesel Range Organics	37 (D, H, M)	mg/L
322C040	Liquid	Diesel Range Organics	31 (D, H, M)	mg/L
322C054L	Liquid	Diesel Range Organics	26 (H, M, Z)	mg/L
322C055L	Liquid	Diesel Range Organics	29 (H, M, Z)	mg/L

Table A.6-1
Liquid and Oil Samples Collected at CAS 03-20-05, Injection Well
(Page 3 of 4)

Sample Number	Sample Matrix	Parameter	Result	Units
322C023	Liquid	Aroclor 1254	1 (J) ^a	µg/L
322C039	Liquid	Aroclor 1254	0.98 (J) ^b	µg/L
322C022A	Liquid	2-Butanone	20	µg/L
322C022A	Liquid	Acetone	61	µg/L
322C023A	Liquid	Acetone	26	µg/L
322C041	Liquid	Acetone	23	µg/L
322C054LRR1	Liquid	Acetone	1,100	µg/L
322C054LRR2	Liquid	4-Methyl-2-Pentanone	32 (J) ^c	µg/L
322C054LRR2	Liquid	2-Butanone	130 (J) ^c	µg/L
322C055L	Liquid	4-Methyl-2-Pentanone	55	µg/L
322C055LRR1	Liquid	Methylene Chloride	61 (J) ^c	µg/L
322C055LRR1	Liquid	2-Butanone	85 (J) ^c	µg/L
322C055LRR1	Liquid	Acetone	540 (J) ^c	µg/L
322C022	Liquid	Phenol	59	µg/L
322C022	Liquid	4-Methylphenol	66	µg/L
322C022	Liquid	Bis(2-Ethylhexyl)Phthalate	160 (J) ^d	µg/L
322C039	Liquid	Bis(2-Ethylhexyl)Phthalate	25 (J) ^d	µg/L
322C040	Liquid	Bis(2-Ethylhexyl)Phthalate	41 (J) ^d	µg/L
322C054LRR1	Liquid	Phenol	4,200 (J) ^e	µg/L
322C054LRR1	Liquid	4-Methylphenol	11,000 (J) ^f	µg/L
322C055L	Liquid	4-Methylphenol	1,300 (J) ^f	µg/L
322C055LRR1	Liquid	Phenol	1,500 (J) ^e	µg/L
322C054O	Oil	Chromium	9	mg/kg
322C054O	Oil	Lead	15	mg/kg
322C054O	Oil	Cadmium	17 (J) ^g	mg/kg
322C055O	Oil	Lead	16	mg/kg
322C055O	Oil	Cadmium	16 (J) ^g	mg/kg
322C054O	Oil	Diesel Range Organics	880,000 (J) ^f	mg/kg
322C055O	Oil	Diesel Range Organics	990,000 (J) ^f	mg/kg
322C054O	Oil	Methylene Chloride	340	µg/kg

Table A.6-1
Liquid and Oil Samples Collected at CAS 03-20-05, Injection Well
(Page 4 of 4)

Sample Number	Sample Matrix	Parameter	Result	Units
322C054O	Oil	Acetone	350 (J)	µg/kg
322C054O	Oil	Bis(2-Ethylhexyl)Phthalate	300,000 (J) ^b	µg/kg
322C055O	Oil	Bis(2-Ethylhexyl)Phthalate	210,000 (J) ^b	µg/kg

^aQualifier added to laboratory data; record accepted. %D between columns >25.

^bQualifier added to laboratory data; record accepted. %D between columns >25. Surrogate recovery <10 percent.

^cQualifier added to laboratory data; record accepted. Exceeded holding time.

^dQualifier added to laboratory data; record accepted. Matrix effects may exist. Internal area response show extremely low count.

^eQualifier added to laboratory data; record accepted. Calibration verification did not meet criteria or was not performed. Surrogates diluted out.

^fQualifier added to laboratory data; record accepted. Surrogates diluted out.

^gQualifier added to laboratory data; record accepted. Matrix spike recovery outside control limits.

^hQualifier added to laboratory data; record accepted. Matrix effects may exist. Internal standard area count outside control limits

pCi/L = Picocuries per liter

mg/L = Milligrams per liter

µg/L = Micrograms per liter

µg/kg = Micrograms per kilogram

mg/kg = Milligrams per kilogram

D = A pattern resembling diesel was detected in the sample.

H = The fuel pattern was in the heavier end of the retention time window for the analyte of interest

M = A pattern resembling motor oil was detected.

Z = The reported result did not resemble the patterns of the following petroleum hydrocarbon products: gasoline, JP-4, JP-8, diesel, mineral spirits, motor oil, Stoddard solvent and bunker C.

M3 = The requested minimum detectable concentration was not met, but the reported activity is greater than the reported minimum detectable concentration.

J = Estimated value

J- = The result is an estimated quantity, but the result may be biased low. Negative bias found in continuing calibration/method blank.

A.6.5.2 TCLP Metals

Analytical results for TCLP metals for soil samples collected at CAS 03-20-05 are presented in Table A.6-2. High concentrations of total metals were detected in soils from within the injection well vault and removal of this soil was considered as a potential corrective action. Therefore, in order to provide sufficient data for the characterization of soil within the vault as a waste stream, samples from this location were analyzed for TCLP metals.

Cadmium was the only TCLP metal detected at a concentration above the RCRA toxicity characteristic level (CFR, 2002). Cadmium was detected in the uppermost layer of soil on either side of the well sump. Samples collected at the next lower interval were below the RCRA limit. If soil is

removed from inside the well vault the first two feet of soil may need to be managed as hazardous waste.

Table A.6-2
Soil Samples for TCLP Metals Detected Above Minimum
Reporting Limits at CAS 03-20-05, Injection Well

Borehole	Sample Number	Parameter	Result	RCRA Limit ^a	Units
C06	322C016	Lead	1.3	5	mg/L
		Cadmium	2.9	1	mg/L
	322C017	Lead	0.086	5	mg/L
		Cadmium	0.41	1	mg/L
	322C018	Lead	0.13	5	mg/L
		Cadmium	0.6	1	mg/L
C07	322C019	Lead	0.66	5	mg/L
		Cadmium	1.9	1	mg/L
	322C020	Lead	0.033	5	mg/L
		Cadmium	0.24	1	mg/L
	322C021	Lead	ND	5	mg/L
		Cadmium	0.16	1	mg/L

^a40 CFR 261 "Identification and Listing of Hazardous Waste," (CFR, 2002)

mg/L = Milligrams per liter

A.7.0 Quality Assurance

This section contains a summary of QA/QC measures implemented during the sampling and analysis activities conducted in support of the CAU 322 corrective action investigation. The following sections discuss the data validation process, QC samples, and nonconformances. A detailed evaluation of the DQIs is presented in Appendix B.

Laboratory analyses were conducted for samples used in the decision-making process to provide a quantitative measurement of any COPCs present. Rigorous QA/QC was implemented for all laboratory samples including documentation, verification and validation of analytical results, and affirmation of DQI requirements related to laboratory analysis. Detailed information regarding the QA program is contained in the Industrial Sites QAPP (NNSA/NV, 2002).

A.7.1 Data Validation

Data validation was performed in accordance with the Industrial Sites QAPP (NNSA/NV, 2002) and approved protocols and procedures. All laboratory data from samples collected and analyzed for CAU 322 were evaluated for data quality according to the EPA Functional Guidelines (EPA, 1994a and 1999). These guidelines are implemented in a tiered process and are presented in Section A.7.1.1, Section A.7.1.2, and Section A.7.1.3. Data were reviewed to ensure that samples were appropriately processed and analyzed, and the results were evaluated using validation criteria. Documentation of the data qualifications resulting from these reviews is retained in project files as a hard copy and electronic media.

One hundred percent of the data analyzed as part of this investigation were subjected to Tier I and Tier II evaluations. A Tier III evaluation was performed on approximately five percent of the data analyzed.

A.7.1.1 Tier I Evaluation

Tier I evaluation for chemical and radiochemical analysis examines, but is not limited to:

- Sample count/type consistent with chain of custody
- Analysis count/type consistent with chain of custody

- Correct sample matrix
- Significant problems stated in cover letter or case narrative
- Completeness of certificates of analysis
- Completeness of Contract Laboratory Program (CLP) or CLP-like packages
- Completeness of signatures, dates, and times on chain of custody
- Condition-upon-receipt variance form included
- Requested analyses performed on all samples
- Date received/analyzed given for each sample
- Correct concentration units indicated
- Electronic data transfer supplied
- Results reported for field and laboratory QC samples
- Whether or not the deliverable met the overall objectives of the project

A.7.1.2 Tier II Evaluation

Tier II evaluation for chemical and radiochemical analysis examines, but is not limited to:

Chemical:

- Correct detection limits achieved
- Sample date, preparation date, and analysis date for each sample
- Holding time criteria met
- Quality control batch association for each sample
- Cooler temperature upon receipt
- Sample pH for aqueous samples, as required
- Detection limits properly adjusted for dilution, as required
- Blank contamination evaluated and applied to sample results/qualifiers
- Matrix spike (MS)/matrix spike duplicate (MSD) percent recoveries (%R) and relative percent differences (RPDs) evaluated and qualifiers applied to laboratory results, as necessary
- Field duplicate RPDs evaluated using professional judgment and qualifiers applied to laboratory results, as necessary
- Laboratory duplicate RPDs evaluated and qualifiers applied to laboratory results, as necessary
- Surrogate %R evaluated and qualifiers applied to laboratory results, as necessary
- Laboratory control sample %R evaluated and qualifiers applied to laboratory results, as necessary
- Initial and continuing calibration evaluated and qualifiers applied to laboratory results, as necessary
- Internal standard evaluation

- Mass spectrometer tuning criteria
- Organic compound quantitation
- Inductively coupled plasma interference check sample evaluation
- Graphite furnace atomic absorption quality control
- Inductively coupled plasma serial dilution effects
- Recalculation of 10 percent of laboratory results from raw data

Radioanalytical:

- Correct detection limits achieved
- Blank contamination evaluated and, if significant, qualifiers are applied to sample results
- Certificate of Analysis consistent with data package documentation
- Quality control sample results (duplicates, laboratory control samples, laboratory blanks) evaluated and used to determine laboratory result qualifiers
- Sample results, uncertainty, and minimum detectable concentration evaluated
- Detector system calibrated with National Institute for Standards and Technology (NIST)-traceable sources
- Calibration sources preparation was documented, demonstrating proper preparation and appropriateness for sample matrix, emission energies, and concentrations
- Detector system response to daily or weekly background and calibration checks for peak energy, peak centroid, peak full-width half-maximum, and peak efficiency, depending on the detection system
- Tracers NIST-traceable, appropriate for the analysis performed, and recoveries that met QC requirements
- Documentation of all QC sample preparation complete and properly performed
- Spectra lines, photon emissions, particle energies, peak areas, and background peak areas support the identified radionuclide and its concentration

A.7.1.3 Tier III

The Tier III review is an independent examination of the Tier II evaluation. The Tier III review duplicates the Tier II review for a limited number of samples (typically 5 percent) by an independent agency and includes the following additional evaluations:

Chemical:

- Recalculation of all laboratory results from raw data

Radioanalytical:

- QC sample results (e.g., calibration source concentration, %R, and RPD) verified
- Radionuclides and their concentration validated as appropriate considering their decay schemes, half-lives, and process knowledge and history of the facility and site
- Each identified line in spectra verified against emission libraries and calibration results
- Independent identification of spectra lines, area under the peaks, and quantification of radionuclide concentration in a random number of sample results

A Tier III review of at least five percent of the sample analytical data was performed by TechLaw, Inc., of Lakewood, Colorado. Tier II and Tier III results were compared and where differences were noted, data were reviewed and changes made accordingly.

A.7.2 Field Quality Control Samples

There were 31 trip blanks, 6 equipment rinsate blanks, 10 field blanks, 3 source blanks, 11 MS/MSDs, and 12 field duplicates collected and submitted for analysis by laboratory analytical methods as specified in the CAIP. The quality control samples were assigned individual sample numbers and sent to the laboratory “blind.” Additional samples were selected by the laboratory to be analyzed as laboratory duplicates.

A.7.2.1 Field Quality Control Samples

Review of the field blank analytical data for soil sampling indicates that there was no cross-contamination due to transportation practices or the ambient conditions, and that equipment decontamination was adequate. Field, equipment rinsate, and source blanks were analyzed for the applicable parameters listed in Table A.2-2 and trip blanks were analyzed for VOCs only.

During the sampling events, 12 field duplicates were sent as blind samples to the laboratory to be analyzed for the investigation parameters listed in the CAIP. For these samples, the duplicate results precision (i.e., RPDs between the environmental sample results and their corresponding field duplicate sample results) were evaluated to the guidance set forth in the EPA Functional Guidelines (EPA, 1994a).

A.7.2.2 Laboratory Quality Control Samples

Analysis of method QC blanks were performed on each sample delivery group (SDG) for inorganics. Analysis for surrogate spikes and preparation blanks (PBs) were performed on each SDG for organics only. Initial and continuing calibration and laboratory control samples (LCSs) were performed for each SDG by Paragon Analytical, Inc. The results of these analyses were used to qualify associated environmental sample results according to the EPA Functional Guidelines (EPA, 1994a and 1999). Documentation of data qualifications resulting from the application of these guidelines is retained in project files as both hard copy and electronic media.

The laboratory included a PB, LCS, and a laboratory duplicate sample with each batch of field samples analyzed for radionuclides.

A.7.3 Field Nonconformances

There were no field nonconformances identified for the corrective action investigation.

A.7.4 Laboratory Nonconformances

Laboratory nonconformances are generally due to inconsistencies in the analytical instrumentation operation, sample preparations, extractions, missed holding times, and fluctuations in internal standard and calibration results. Fourteen nonconformances were issued by the laboratory that resulted in qualifying data and have been accounted for during the data qualification process.

A.8.0 Summary

Analytes detected in soil samples during the CAI were evaluated against FALs to determine the nature and extent of COCs for CAU 322. Assessment of the data generated from investigation activities indicates the FALs were exceeded in soil samples at all CAU 322 CASs. The following summarizes the results for each CAS.

CAS 01-25-01, AST Berm. Analytical results from all locations within the AST berm indicate that TPH-DRO is present at concentrations above the FAL. The vertical extent of contamination is limited to approximately 12 ft bgs. The lateral extent of contamination was limited to the confines of the berm, as demonstrated by step-out samples.

CAS 03-25-03, AST Berm, Area A. Based on observations made and analytical results of samples collected at CAS 03-25-03 Area A, two locations identified TPH-DRO concentrations above the PALs. The positive result at one of these locations may be due to the presence of oil based paint chips observed on the surface. The source of the paint chips, the paint chips, and the surface soil from this location were removed. Confirmation sampling indicated the contamination was removed. The second location contained TPH-DRO contamination at the 2 to 3 ft bgs interval. Sample collected above and below this interval indicated no contamination. Removal of the upper two feet of the soil, followed by drumming of the 2 to 3 ft interval and confirmation sampling indicated the contamination had been removed. No contamination remains at this site.

CAS 03-25-03 Area B, Mud Plant. Based on observations made and analytical results of samples collected at CAS 03-25-03 Area B, TPH-DRO contamination was identified at various locations and at varying depth throughout the area of interest. However, there was no contiguous TPH-DRO contamination that would allow for the identification of a contaminant plume from any specific source at the site. One sampling location contained plutonium-239 at the surface. The Pu-239 contaminated soil was removed and drummed, and confirmation samples were collected. The confirmation samples indicated that the contamination was removed. It is believed that the surface plutonium-239 contamination arose from surface deposition resulting from atmospheric testing, a common phenomenon in this area of the NTS.

CAS 03-20-05, Injection Wells. Analytical results indicated several COPCs including TPH, PCBs, lead, and radiological constituents are present at the site above the PAL.

Total petroleum hydrocarbon-DRO contamination was identified at several surface locations on the grounds around the injection well. However, these are bounded laterally by step-out samples and vertically by clean samples beneath the identified contamination, and are believed to be the result of asphalt associated with these sample locations. Soils within the injection well casing showed radiological, metals, and TPH-DRO contamination. The contamination is bounded laterally by samples collected just outside the casing and the metal casing comprising the injection well vault. Vertical extent of contamination was identified by additional samples taken with a drill rig modified to gain access to specific sampling locations.

Plutonium-239 surface contamination was identified at several locations at this CAS, and is believed to be the result of aerial deposition from atmospheric testing. The locations were not contiguous, and not believed to be associated with activities ascribed to the historical use of the site. Removal of these areas of elevated radiological activity was performed as a best management practice to mitigate potential personnel exposure.

A.9.0 References

Alderson, S.L., Stoller-Navarro Joint Venture. 2004. Memorandum to R. Boehlecke (Stoller-Navarro Joint Venture), "CAU 322 Radiological Land Area Surveys," 4 May. Las Vegas, NV.

BN, see Bechtel Nevada.

Bechtel Nevada. 1995. *Nevada Test Site Performance Objective for Certification of Nonradioactive Hazardous Waste*, Rev. 0, G-E11/96.01. Las Vegas, NV.

CFR, see *Code of Federal Regulations*.

Code of Federal Regulations. 2002. Title 40 CFR, "Protection of Environment," Parts 260-282, "Hazardous Waste Management." Washington, DC: U.S. Government Printing Office.

DOE, see U.S. Department of Energy.

DOE/NV, see U.S. Department of Energy, Nevada Operations Office.

DRI, see Desert Research Institute.

Desert Research Institute. 1985. *Additional Intensity Duration Analyses and Design Hyetograph Parameters for Various Parameters for Various Precipitation Stations of the Nevada Test Site, Nevada*, August. Prepared by R.H. French. Las Vegas, NV: Water Resources Center.

Desert Research Institute and Carey & Co., Inc. 1996. *Nevada Test Site Historic Building Survey*, November. Las Vegas, NV.

EPA, see U.S. Environmental Protection Agency.

FFACO, see *Federal Facility Agreement and Consent Order*.

Federal Facility Agreement and Consent Order. 1996 (as amended). Agreed to by the State of Nevada, the U.S. Department of Energy, and the U.S. Department of Defense.

Moore, J., Science Applications International Corporation. 1999. Memorandum to M. Todd (SAIC), "Background Concentrations for NTS and TTR Soil Samples," 3 February. Las Vegas, NV.

NAC, see *Nevada Administrative Code*.

NBMG, see Nevada Bureau of Mines and Geology.

NCRP, see National Council on Radiation Protection and Measurements.

NDEP, see Nevada Division of Environmental Protection.

NNSA/NV, see U.S. Department of Energy, National Nuclear Security Administration Nevada Operations Office.

NNSA/NSO, see U.S. Department of Energy, National Nuclear Security Administration Nevada Site Office.

National Council on Radiation Protection and Measurements. 1999. *Recommended Screening Limits for Contaminated Surface Soil and Review of Factors Relevant to Site-Specific Studies*, Report No. 129. Bethesda, MD.

Nevada Administrative Code. 2002. NAC 445A.2272, "Contamination of Soil: Establishment of Action Levels." Carson City, NV.

Nevada Bureau of Mines and Geology. 1998. *Mineral and Energy Resource Assessment of the Nellis Air Force Range*, Open-File Report 98-1. Reno, NV.

Nevada Division of Environmental Protection. 1997a (as amended). *Class III Solid Waste Disposal Site for Hydrocarbon Burdened Soils, Area 6 of the NTS*, Permit SW 13 097 02. Reno, NV.

Nevada Division of Environmental Protection. 1997b (as amended). *Class III Solid Waste Disposal Site; U10C, Area 9 of the NTS*, Permit SW 1309703. Carson City, NV.

Stoller-Navarro Joint Venture. 2003. *Site-Specific Health and Safety Plan for CAU 322, Areas 1 and 3, Release Sites and Injection Wells, Nevada Test Site, Nevada*. Las Vegas, NV.

U.S. Department of Energy. 1993. DOE Order 5400.5 Change 2, "Radiation Protection of the Public and the Environment." Washington, DC.

U.S. Department of Energy, Nevada Operations Office. 2000. *NV/YMP Radiological Control Manual*, Rev. 4, DOE/NV/11718-079. Prepared by A.L. Gile of Bechtel Nevada. Las Vegas, NV.

U.S. Department of Energy, National Nuclear Security Administration Nevada Operations Office. 2002. *Industrial Sites Quality Assurance Project Plan, Nevada Test Site, Nevada*, Rev. 3, DOE/NV--372. Las Vegas, NV.

U.S. Department of Energy, National Nuclear Security Administration Nevada Site Office. 2003a. *Corrective Action Investigation Plan for Corrective Action Unit 322: Areas 1 and 3, Release Sites and Injection Wells, Nevada Test Site, Nevada*, DOE/NV--893, Rev. 0. Las Vegas, NV.

U.S. Department of Energy, National Nuclear Security Administration Nevada Site Office. 2003b. *Nevada Waste Acceptance Criteria*, Rev. 5, DOE/NV--325. Las Vegas, NV.

- U.S. Environmental Protection Agency. 1994a. *Contract Laboratory Program National Functional Guidelines for Inorganic Data Review*, EPA/540/R-94/013. Washington, DC.
- U.S. Environmental Protection Agency. 1994b. *Guidance for the Data Quality Objectives Process*, EPA QA/G-4. Washington, DC.
- U.S. Environmental Protection Agency. 1996. *Test Methods for Evaluating Solid Waste, Physical/Chemical Methods*, SW-846, 3rd Edition, CD-ROM PB97-501928GEI. Washington, DC.
- U.S. Environmental Protection Agency. 1999. *Contract Laboratory Program National Functional Guidelines for Organic Data Review*, EPA 540/R-99/008. Washington, DC.
- U.S. Environmental Protection Agency. 2002. *Region IX Preliminary Remediation Goals (PRGs)*. Available at www.epa.gov/region09/waste/sfund/prg. San Francisco, CA.

Appendix B

Data Assessment

B.1.0 Data Assessment

This appendix provides an assessment of the CAU 322 investigation results to determine whether the data collected met the DQOs and can support their intended use in the decision-making process. This assessment includes a reconciliation of the data with the general CSMs established for this project.

The following sections provide an evaluation of the DQIs in determining the degree of acceptability or usability of the reported data for the decision-making process.

B.1.1 Precision

Precision is a measure of agreement among a replicate set of measurements of the same property under similar conditions. This agreement is expressed as the RPD between duplicate measurements (EPA, 1996).

For the purpose of determining data precision of sample analyses, all water and soil samples, including field QC samples (e.g., trip blanks, equipment rinsate samples, field blanks) were evaluated and incorporated into the precision calculation.

The RPD is determined by dividing the difference between the replicate measurement values by the average measurement value and multiplying the result by 100, or:

$$RPD = |100 \times [(a_1 - a_2)/(a_1 + a_2)/2]|$$

Where:

a_1 = The sample value

a_2 = The duplicate sample value

Determinations of precision can be made for field samples, laboratory duplicates (LD), or both. For field samples, duplicates are collected simultaneously with a sample from the same source under similar conditions in separate containers. The duplicate sample is treated independently of the original sample in order to assess field impacts and laboratory performance on precision through a comparison of results. Laboratory precision is evaluated as part of the required QC program to assess performance of analytical procedures. The laboratory sample duplicates are an aliquot or subset of a

field sample generated in the laboratory. They are not a separate sample but portions of an existing sample. Typically, other laboratory duplicate QC samples include MSD and laboratory control sample duplicate (LCSD).

The variability in the results from the analysis of field duplicates is generally greater than the variability in the results of laboratory duplicates. This higher variability for field duplicates results from the increased potential to introduce factors influencing the analytical results during sampling, sample preparation, containerization, handling, packaging, preservation, and environmental conditions before the samples reach the laboratory. Laboratory QC samples only assess the variability of results introduced by sample handling and preparation in the laboratory and by the analytical procedure, which also impacts field duplicates. In addition, the variability in duplicate results is expected to be greater for soil samples than water samples, primarily due to the inherent heterogeneous nature of soil samples, despite sample preparation methods that include mixing to improve sample homogeneity.

B.1.1.1 Precision for Chemical Analysis

The RPD criteria used for assessment of laboratory sample duplicate precision for analytical results of samples collected at CAU 322 were established as follows:

- Inorganic analysis RPD criteria is obtained from the EPA's *Contract Laboratory Functional Guidelines for Inorganic Data Review* (EPA, 1994).
- Organic analysis RPD criteria is established by the laboratory to evaluate precision for MSD and LCSD analyses.

The control limits are evaluated at the laboratory on a quarterly basis by monitoring the historical data and performance for each method. No review criteria for organic field duplicate RPD comparability have been established by EPA; therefore, the laboratory MS/MSD RPD criteria is applied for precision evaluation of field duplicates.

Precision values for organic and inorganic analysis that are within the established control criteria indicate that analytical results for associated samples are valid. Laboratory duplicate RPD values that are outside the criteria for organic analysis do not necessarily result in the qualification of analytical data. It is only one factor in making an overall judgment about the quality of the reported analytical

results. Inorganic laboratory duplicate RPD values outside the established control criteria do result in the qualification of associated analytical results as estimated. Field duplicate RPD values that are outside the criteria for organic and inorganic analyses do not result in the qualification of analytical data. Out of control RPD values do not necessarily indicate that the data is not useful for the purpose intended; however, it is an indication data precision should be considered for the overall assessment of the data quality and potential impact on data application in meeting project site characterization objectives. Method-specific precision as RPD is determined by taking the number of measurements within criteria, dividing that by the number of measurements analyzed, and multiplying by 100.

For the purpose of determining data precision of sample analyses for CAU 322, all soil and water samples, including field QC samples (e.g., trip blanks, equipment rinsate samples, field blanks) were evaluated and incorporated into the precision calculation.

Precision for the measurement of target compounds or analytes collected at CAU 322 was determined for total RCRA metals plus beryllium, SVOCs, VOCs, PCBs, TPH-DRO, and TPH-GRO.

Table B.1-1 provides the chemical precision analysis results.

Inorganic laboratory duplicate RPD values outside the established control criteria result in estimation for that measurement of all associated samples in the SDG. For example, if a laboratory duplicate had a RPD value for lead outside the established control criteria, lead results for all of the samples in that SDG would be qualified as estimated.

Out of control RPD values do not necessarily indicate that the data is not useful for the purpose intended. It does indicate that precision should be considered in the overall assessment of the data quality and impact to the application of associated data to meeting the project's objectives.

B.1.1.2 Precision for Radiochemical Analysis

The precision of radiochemical measurements is evaluated by measuring two aliquots of a sample and comparing the results. A laboratory duplicate is measured with every batch of samples analyzed by the laboratory. Field duplicate data is available when two aliquots of a sample are submitted to the laboratory for analysis. Matrix spike duplicates, also used to evaluate precision, are performed by the laboratory upon request.

Table B.1-1
Chemical Precision Measurements for CAU 322

	ORGANICS					INORGANICS	
	VOCs	SVOCs	TPH-DRO	TPH-GRO	PCBs	Metals*	Mercury
Matrix Spike Duplicate (MSD) Precision							
Total Number of MSD Measurements	85	176	16	15	30	103	13
Total Number of RPDs Within Criteria	85	175	16	15	30	102	13
MSD Percent Precision	100	99.4	100	100	100	99	100
Laboratory Control Sample Duplicate (LCSD) Precision							
Total Number of LCSD Measurements	100	253	23	20	46	173	17
Total Number of RPDs Within Criteria	100	253	23	20	46	173	17
LCSD Percent Precision	100	100	100	100	100	100	100
Field Sample Duplicate (FD) Precision							
Total Number of FD Measurements	621	639	9	9	63	72	9
Total Number of RPDs Within Criteria	614	638	8	8	62	67	8
FD Percent Precision	98.9	99.8	88.9	88.9	98.4	93.1	88.9
Laboratory Sample Duplicate (Lab-Dup) Precision							
Total Number of Lab-Dup Measurements	NA	NA	NA	NA	NA	103	13
Total Number of RPDs Within Criteria	NA	NA	NA	NA	NA	103	13
Lab-Dup Percent Precision	NA	NA	NA	NA	NA	100	100

*Measurements include arsenic, barium, beryllium, cadmium, chromium, lead, selenium, silver

NA = Not applicable