OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT ANALYSIS/MODEL COVER SHEET

1. QA: L

Page: 1 of: 9

Complete Only Applicable Items

2. ☒ Analysis ☒ Engineering ☐ Performance Assessment ☐ Scientific
3. ☐ Model ☐ Conceptual Model Documentation ☐ Model Documentation ☐ Model Validation Documentation

4. Title:

Classification of the MGR Performance Confirmation Emplacement Drift Monitoring System

5. Document Identifier (including Rev. No. and Change No., if applicable):

ANL-PCM-SE-000001 REV 00

6. Total Attachments:

Three (3)

7. Attachment Numbers - No. of Pages in Each:

I-1, II-4, III-6

	Printed Name	Signature	Date
8. Originator	Robert Garrett		8/21/99
9. Checker	Kelvin J. Montague		8/31/99
10. Lead/Supervisor	Thomas D. Dunn		8/31/99
11. Responsible Manager	Dealis W. Gwyn		8/31/99

12. Remarks:

This analysis contains no To Be Verified (TBV) design input.

The Document Identifier for this document previously was BCA000000-01717-0200-00035 REV 00.

This analysis bases the classification of Monitored Geologic Repository structures, systems and components on the criteria of proposed rule 10 CFR 63 (64 FR 8640). A review has determined that the changes made to proposed rule 10 CFR 63 by *Interim Guidance Pending Issuance of New U. S. Nuclear Regulatory Commission (NRC) Regulations for Yucca Mountain, Nevada* (Dyer 1999) do not impact the classifications made in this analysis.

**OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT
ANALYSIS/MODEL REVISION RECORD**

1. Page: 2 of: 9

Complete Only Applicable Items

2. Analysis or Model Title:

Classification of the MGR Performance Confirmation Emplacement Drift Monitoring System

3. Document Identifier (including Rev. No. and Change No., if applicable):

ANL-PCM-SE-000001 REV 00

4. Revision/Change No.

5. Description of Revision/Change

00

Initial issue. This system-specific analysis was performed to supercede the applicable portion of B00000000-01717-0200-00134 REV 01 (CRWMS M&O 1998d).

CONTENTS

	Page
1. PURPOSE	4
2. QUALITY ASSURANCE	4
3. COMPUTER SOFTWARE AND MODEL USAGE	4
4. INPUTS	4
4.1 PARAMETERS	4
4.2 CRITERIA	5
4.3 CODES AND STANDARDS	5
5. ASSUMPTIONS	5
6. ANALYSIS	5
6.1 METHOD	5
6.2 MGR DESIGN CONFIGURATION AND ARCHITECTURE	6
6.3 DESIGN BASIS EVENT ANALYSIS	7
6.4 QUALITY ASSURANCE CLASSIFICATION OF MGR STRUCTURES, SYSTEMS, AND COMPONENTS	7
7. CONCLUSIONS	7
8. REFERENCES	8
8.1 DOCUMENTS CITED	8
8.2 CODES, STANDARDS, AND REGULATIONS	8
8.3 PROCEDURES	9
9. ATTACHMENTS	9

Tables

Table 1. Performance Confirmation Emplacement Drift Monitoring System QA Classification	7
--	---

1. PURPOSE

The purpose of this analysis is to document the Quality Assurance (QA) classification of the Monitored Geologic Repository (MGR) performance confirmation emplacement drift monitoring structures, systems and components (SSCs) performed by the MGR Safety Assurance Department. This analysis also provides the basis for revision of YMP/90-55Q, *Q-List* (YMP 1998). The Q-List identifies those MGR SSCs subject to the requirements of DOE/RW-0333P, *Quality Assurance Requirements and Description* (QARD) (DOE 1998).

This QA classification incorporates the current MGR design and the results of the *Preliminary Preclosure Design Basis Event Calculations for the Monitored Geologic Repository* (CRWMS M&O 1998a).

2. QUALITY ASSURANCE

This analysis is subject to the requirements of the QARD (DOE 1998) as determined by procedures QAP-2-0, *Conduct of Activities*, and NLP-3-18, *Documentation of QA Controls on Drawings, Specifications, Design Analyses, and Technical Documents. Design Basis Event Definition & Analysis/QA Classification Analysis (1.2.1.11) Activity Evaluation* (CRWMS M&O 1999a) presents the QAP-2-0 activity evaluation addressing the QA classification of MGR SSCs. This analysis is performed in accordance with procedures QAP-2-3, *Classification of Permanent Items*, and AP-3.10Q, *Analyses and Models*, and provides input to the design of SSCs included on the Q-List (YMP 1998). Unverified design inputs are identified and tracked in accordance with NLP-3-15, *To Be Verified (TBV) and To Be Determined (TBD) Monitoring System*.

3. COMPUTER SOFTWARE AND MODEL USAGE

This analysis uses no software which is required to be controlled in accordance with procedure AP-SI.1Q, *Software Management*.

4. INPUTS

4.1 PARAMETERS

The offsite radiological consequences of MGR Category 1 and 2 design basis events (DBEs), as calculated in *Preliminary Preclosure Design Basis Event Calculations for the Monitored Geologic Repository* (CRWMS M&O 1998a), are utilized in the QA classification of MGR SSCs. These results represent a conservative evaluation of MGR DBEs and the best information available. As discussed in Section 6.1 of this analysis, NUREG-1318, *Technical Position on Items and Activities in the High-Level Waste Geologic Repository Program Subject to Quality Assurance Requirements*

(NRC 1998, Section 4.2(a)) allows the use of engineering judgement and conservative bounding assumptions in the QA classification of facility SSCs when data sources are limited. Also, procedure YAP-2.7Q, *Item Classification and Maintenance of the Q-List* (Attachment 3, Section a), directs the use of the highest level of detail available to support the conclusion of the QA classification analysis. Currently, no DBEs associated with this system are identified by the preliminary DBE calculations (CRWMS M&O 1998a).

4.2 CRITERIA

The criteria used in the QA classification of MGR SSCs are provided in procedure QAP-2-3 as discussed in Section 6.1. These criteria satisfy the requirement of Section 2.2.2, *Classifying Items*, of DOE/RW-0333P (DOE 1998).

4.3 CODES AND STANDARDS

10 CFR 20. Energy: Standards for Protection Against Radiation. January 1, 1999.

64 FR 8640. Disposal of High-Level Radioactive Wastes in a Proposed Geologic Repository at Yucca Mountain, Nevada. Proposed rule 10 CFR 63. February 22, 1999.

5. ASSUMPTIONS

The following assumptions were made in the performance of this analysis.

- 5.1 This analysis assumes that system design and SSC functions are established in the text of the *Performance Confirmation Emplacement Drift Monitoring System Description Document* (CRWMS 1998c). This assumption is based on the fact that this type of information is found in this System Description Document (SDD). This analysis also assumes that the MGR architecture is established by *Monitored Geologic Repository Architecture* (CRWMS M&O 1999b) and that MGR operations are described by *Monitored Geologic Repository Concept of Operations* (CRWMS M&O 1998b). This assumption is utilized in Section 6.2 to define the system design configuration and system functions.

6. ANALYSIS

6.1 METHOD

The basic process for classifying MGR permanent SSCs is provided by procedure QAP-2-3. Guidance provided by procedure YAP-2.7Q is also used in this analysis. The process consists of establishing the configuration and function of MGR SSCs and the effect of the SSC on MGR radiological safety. This information is then evaluated against criteria provided in QAP-2-3 to

determine the QA classification of the particular item. The classification criteria are provided in the form of checklists in procedure QAP-2-3. A copy of these criteria checklists is provided in Attachment II. The following classification categories are specified by QAP-2-3 to meet the requirements of Section 2 of the QARD (DOE 1998).

Quality Level 1 (QL-1) Those SSCs whose failure could *directly* result in a condition adversely affecting public safety. These items have a high safety or waste isolation significance.

Quality Level 2 (QL-2) Those SSCs whose failure or malfunction could *indirectly* result in a condition adversely affecting public safety, or whose *direct* failure would result in consequences in excess of normal operational limits. These items have a low safety or waste isolation significance.

Quality Level 3 (QL-3) Those SSCs whose failure or malfunction would not significantly impact public or worker safety, including those defense-in-depth design features intended to keep doses ALARA (As Low As Reasonably Achievable). These items have a minor impact on public and worker safety and waste isolation.

Conventional Quality (CQ) Those SSCs not meeting any of the criteria for Quality Levels 1, 2, or 3. Conventional quality items are not subject to the requirements of QARD.

This analysis method is based on an iterative design-classification process where each analysis iteration is considered a final product for that phase of design. In this case, the system design and the DBE analysis are evaluated to determine which of the system's SSCs require design control under the QA program. The analysis presented in this document, therefore, will be reevaluated as necessary using a methodology appropriate to the level of DBE analysis and system design detail. This approach is consistent with NUREG-1318, *Technical Position on Items and Activities in the High-Level Waste Geologic Repository Program Subject to Quality Assurance Requirements* (NRC 1998, Section 4.2(a)), which allows engineering judgement and conservative bounding assumptions to be used in cases where data are limited.

6.2 MGR DESIGN CONFIGURATION AND ARCHITECTURE

Prior to the QA classification of MGR SSCs, the system design configuration as well as the function of the system's SSCs are established. This classification analysis is based upon the system design and functions as established by the *Performance Confirmation Emplacement Drift Monitoring System Description Document* (SDD) (CRWMS M&O 1998c) and the *MGR Concept of Operations* (CRWMS M&O 1998b). In the process of QA classification, if two or more subsystems perform similar functions or are similarly classified, these subsystems are classified as a group under the higher level system and not listed individually.

6.3 DESIGN BASIS EVENT ANALYSIS

A preliminary analysis of MGR DBEs (CRWMS M&O 1998a) has been performed to determine the effects of internal and external events on facility radiological safety and is utilized by this analysis in the classification of MGR SSCs. The DBE analysis addresses both the DBE frequencies and dose consequences at the site boundary. This analysis utilizes the results of the DBE analysis to evaluate MGR SSCs against the classification criteria of procedure QAP-2-3.

6.4 QUALITY ASSURANCE CLASSIFICATION OF MGR STRUCTURES, SYSTEMS AND COMPONENTS

The MGR SSCs are evaluated against the criteria of QAP-2-3 to determine the item QA classification level. The results of the MGR preliminary DBE calculations (CRWMS M&O 1998a) are utilized in this evaluation.

7. CONCLUSIONS

The results of this QA classification analysis are provided in Table 1. This analysis is based on current MGR system design and the preliminary MGR DBE analysis (CRWMS M&O 1998a). As the design of the MGR proceeds and further analyses of MGR hazards are performed, this classification analysis will be reviewed for impact and revised as necessary. The MGR classification checklists included in procedure QAP-2-3 are reproduced in Attachment II. The basis for the classification evaluation is provided in Attachment III.

Table 1. Performance Confirmation Emplacement Drift Monitoring System QA Classification

Performance Confirmation Emplacement Drift Monitoring System (PCM)	QL-1	QL-2	QL-3	CQ	TBV
Emplacement Drift Monitoring System			X		N/A
Inspection Gantry			X		N/A
Waste Package Monitoring System			X		N/A

8. REFERENCES

8.1 DOCUMENTS CITED

CRWMS M&O (Civilian Radioactive Waste Management System Management and Operating Contractor) 1998a. *Preliminary Preclosure Design Basis Event Calculations for the Monitored Geologic Repository*. BC00000000-01717-0210-00001 REV 00. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19981002.0001.

CRWMS M&O 1998b. *Monitored Geologic Repository Concept of Operations*. B000000000-01717-4200-00004 REV 02. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19980810.0283.

CRWMS M&O 1998c. *Performance Confirmation Emplacement Drift Monitoring System Description Document*. BCA0000000-01717-1705-00020. Rev 00. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19981117.0426.

CRWMS M&O 1998d. *Classification of the Preliminary MGDS Repository Design*. B000000000-01717-0200-00134 REV 01. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19981103.0546.

CRWMS M&O 1999a. *Design Basis Event Definition & Analysis/QA Classification Analysis (1.2.1.11) Activity Evaluation*. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19990325.0008.

CRWMS M&O 1999b. *Monitored Geologic Repository Architecture*. B000000000-01717-5700-00011 REV 02 ICN 01. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19990713.0203.

DOE (U.S. Department of Energy) 1998. *Quality Assurance Requirements and Description*. DOE/RW-0333P, Rev. 8. Washington D.C.: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: MOL.19980601.0022.

Dyer, J.R. 1999. *Interim Guidance Pending Issuance of New U. S. Nuclear Regulatory Commission (NRC) Regulations for Yucca Mountain, Nevada*. Letter from J. Russell Dyer (DOE) to D. R. Wilkins (YMP), June 18, 1999. OL&RC:AVG:1435. ACC: MOL.19990623.0026 and MOL.19990623.0027.

YMP (Yucca Mountain Site Characterization Project) 1998. *Q-List*. YMP/90-55Q, Rev. 5. Las Vegas, Nevada: Yucca Mountain Site Characterization Office. ACC: MOL.19980513.0132.

8.2 CODES, STANDARDS, AND REGULATIONS

10 CFR (Code of Federal Regulations) 20. Energy: Standards for Protection Against Radiation. January 1, 1999.

64 FR (Federal Register) 8640. Disposal of High-Level Radioactive Wastes in a Proposed Geologic Repository at Yucca Mountain, Nevada. Proposed rule: 10 CFR 63. February 22, 1999.

NRC (Nuclear Regulatory Commission) 1998. *Technical Position on Items and Activities in the High-Level Waste Geologic Repository Program Subject to Quality Assurance Requirements*. NUREG-1318. Washington, D.C.: U.S. Nuclear Regulatory Commission.

8.3 PROCEDURES

AP-3.10Q, Rev. 0, ICN 0. *Analyses and Models*. ACC: MOL.19990225.0335.

AP-SI.1Q, Rev. 1, ICN 0. *Software Management*. ACC: MOL.19990520.0164.

NLP-3-15, Rev. 5. *To Be Verified (TBV) and To Be Determined (TBD) Monitoring System*. ACC: MOL.19981117.0148.

NLP-3-18, Rev. 04. *Documentation of QA Controls on Drawings, Specifications, Design Analyses, and Technical Document*. ACC: MOL.19960611.0170.

QAP-2-0, Rev. 5. *Conduct of Activities*. ACC: MOL.19980826.0209.

QAP-2-3, Rev. 10. *Classification of Permanent Items*. ACC: MOL.19990316.0006.

YAP-2.7Q, Rev. 1, ICN 1. *Item Classification and Maintenance of the Q-List*. ACC: MOL.19990115.0065.

9. ATTACHMENTS

Attachment I	Acronyms
Attachment II	MGR Classification Checklists
Attachment III	MGR QA Classification

Attachment I Acronyms

ALARA	As Low As Reasonably Achievable
CFR	Code of Federal Regulations
CQ	Conventional Quality
CRWMS	Civilian Radioactive Waste Management System
DBE	Design Basis Event
DOE	U. S. Department of Energy
FR	Federal Register
M&O	Management and Operating Contractor
MGR	Monitored Geologic Repository
NLP	Nevada Line Procedure
NRC	U. S. Nuclear Regulatory Commission
QA	Quality Assurance
QAP	Quality Administrative Procedure
QARD	Quality Assurance Requirements and Description
QL	Quality Level
SDD	System Description Document
SSCs	Structures, Systems, and Components
TBD	To Be Determined
TBV	To Be Verified
TEDE	Total Effective Dose Equivalent
YAP	YMP Administrative Procedure
YMP	Yucca Mountain Site Characterization Project

Page: 1 Of: 4

Attachment II MGR Classification Checklists

CRWMS/M&O

Importance to Safety or Waste Isolation Evaluation
for MGR

Complete only applicable items.

QA: L

Page: 2 Of: 4

MGR Quality Level 2 Checklist

Yes	No	
		<p>8. Preclosure Phase:</p> <p>2.1. Does the item function to provide control and management (i.e., collection and/or confinement) of site-generated liquid, gaseous, or solid low-level or mixed radioactive waste?</p> <p>NOTE: Systems with trace concentration of radionuclides, the failure of which could result in offsite doses less than 0.25 mrem per year, are not considered to perform radioactive waste management or control functions for the purpose of this quality level determination.</p>
		2.2. Does the item provide fire detection, fire suppression, or otherwise protect the important-to-radiological safety or waste isolation functions of Quality Level 1 SSCs from the hazards of a fire?
		2.3. As a result of a DBE, could consequential failure of the item, which is not intended to perform a Quality Level 1 radiological safety function, prevent Quality Level 1 SSCs from performing their intended radiological safety function?
		2.4. Is the item required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 25 mrem TEDE, per event, to any member of the public located on or beyond the site boundary (10 CFR 63.111(a) and 10 CFR 20.1301(a)(1))? Category 1 DBE "per event" limits are interpreted as the sum of the normal operating dose and anticipated operational occurrences plus the consequences from any single additional low frequency Category 1 DBE. This sum is stated on an annual basis and consistent with 10 CFR 63.111(a) or 10 CFR 20.
		2.5. Is the item, in conjunction with an additional item or administrative control (i.e., indirect impact), required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 100 mrem TEDE, per event, to any member of the public located on or beyond the site boundary? Category 1 DBE "per event" limits are interpreted as the sum of the normal operating dose and anticipated operational occurrences plus the consequences from any single additional low frequency Category 1 DBE. This sum is stated on an annual basis and consistent with 10 CFR 63.111(a) or 10 CFR 20.
		2.6. Is the item, in conjunction with an additional item or administrative control (i.e., indirect impact), required to prevent or mitigate a Category 2 DBE that could result in offsite doses greater than or equal to 5 rem TEDE, 50 rem combined deep dose equivalent and committed dose equivalent to any individual organ or tissue (other than the lens of the eye), 15 rem dose equivalent to the lens of the eye, or 50 rem shallow dose equivalent to the skin, per event, to any individual located on or beyond any point on the boundary of the site?
		<p>9. Postclosure Phase:</p> <p>2.7. As a result of a DBE, could consequential failure of the item, which is not intended to perform a Quality Level 1 waste isolation function, result in:</p> <p>a. the inability of Quality Level 1 engineered barriers to perform their intended long-term waste isolation function in the postclosure phase?</p>
		b. long-term changes to the hydrological characteristics of natural barriers by creating significant ponding or the possibility of drainage into the postclosure underground?
		c. the introduction of fluids or other materials that could adversely affect the long-term geo-mechanical characteristics of natural barriers in the postclosure phase?
		d. compromising the ability of the natural barriers to isolate waste in the postclosure phase?
		10. Do the answers to Blocks 8 and 9 qualify the item as a Quality Level 2 item?

PCM

Performance Confirmation

Emplacement Drift Monitoring System

SSC: Emplacement Drift Monitoring System

Level 3: N/A

Level 4: N/A

PCM

QL1 ☐

PS1 ☐ QL2 ☐

PS2 ☒ QL3 ☒

PS CQ ☐ CQ ☐

Q-List Rationale

SDD / SSC Reference: CRWMS M&O 1998c

TBVs Applicable to this Item: N/A

Pre-Screen - Importance to Safety or Waste Isolation Evaluation

	Yes	No	Rationale:
PS1	☐	☒	a. This item is not directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled at the MGR: confinement or containment, criticality control, shielding, heat transfer, structural integrity, or operations support necessary for waste handling safety.
	☐	☒	b.
	☐	☒	c.
	☐	☒	d.
	☐	☒	e.
	☐	☒	f.
PS2	☒	☐	This item is indirectly relied upon to provide an Important to Waste Isolation function.

Note: A Yes answer has been selected for either PS1 or PS2, therefore, the item is subject to QARD requirements. An Importance to Safety or Waste Isolation evaluation is required. Please continue with the evaluation checklists below.

QL1 - Quality Level 1: High Safety or Waste Isolation Significance

	Yes	No	Rationale:
1.1	☐	☒	Failure of the Emplacement Drift Monitoring System will not directly result in loss of waste package containment or criticality control.
1.2	☐	☒	The Performance Confirmation Emplacement Drift Monitoring System acquires pertinent data associated with verifying the performance of the waste isolation system. The drift monitoring system does not prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 100 mrem total effective dose equivalent (TEDE).
1.3	☐	☒	The Performance Confirmation Emplacement Drift Monitoring System is not required to function to prevent or mitigate a Category 2 DBE that would otherwise result in a radioactive release consequence above 10 CFR 63.111(b)(2) limits.
1.4	☐	☒	a. The Emplacement Drift Monitoring System is not part of the natural or engineered barriers that perform a waste isolation function.
	☐	☒	b.

QL2 - Quality Level 2: Low Safety or Waste Isolation Significance

	Yes	No	Rationale:
2.1	☐	☒	The Emplacement Drift Monitoring System is not designed for the collection, containment, and/or monitoring of site-generated radioactive waste.
2.2	☐	☒	The Emplacement Drift Monitoring System does not perform a fire protection function.
2.3	☐	☒	Failure of the Performance Confirmation Emplacement Drift Monitoring System as a result of a DBE does not impair the capability of QL1 High Safety Significant to perform their intended radiological safety function.

PCM

Performance Confirmation
Emplacement Drift Monitoring System

SSC: Emplacement Drift Monitoring System

Level 3: N/A

Level 4: N/A

PCM

QL1 ☐

PS1 ☐ QL2 ☐

PS2 ☒ QL3 ☒

PS CQ ☐ CQ ☐

Q-List Rationale

- 2.4 ☐ ☒ This item is not required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 25 mrem TEDE, per event, to any member of the public located on or beyond the site boundary [10 CFR 63.111(a) and 10 CFR 20.1301 (a)(1)].
- 2.5 ☐ ☒ This item, in conjunction with an additional item or administrative control (i.e., indirect impact), is not required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 100 mrem TEDE, per event, to any member of the public located on or beyond the site boundary.
- 2.6 ☐ ☒ This item, in conjunction with an additional item or administrative control (i.e., indirect impact), is not required to prevent or mitigate a Category 2 DBE that could result in offsite doses greater than or equal to the more limiting of 10 CFR 63.111(b)(2) doses to any individual located on, or beyond, any point on the site boundary.
- 2.7 ☐ ☒ a. Failure of the Emplacement Drift Monitoring System would not result in the inability of QL-1 engineered barriers to perform long-term waste isolation functions in the postclosure phase, would not create ponding in the postclosure underground, introduce fluids, or compromise the ability of natural barriers to isolate waste.
- ☐ ☒ b.
- ☐ ☒ c.
- ☐ ☒ d.

QL3 - Quality Level 3: Minor Safety Significance or Occupational Exposure Significance

	Yes	No	Rationale:
3.1	☐	☒	This item does not function to provide an alarm to warn of significant increases in radiation levels or concentrations of radioactive materials.
3.2	☒	☐	The system emplaces and recovers coupons to and from the emplacement drifts. The system also provides information for analysis and information to conduct field and laboratory experiments. The system may also be used to assess off normal events that occur within the emplacement drift. Therefore, this item functions to monitor variables to verify that operating conditions are within technical specifications.
3.3	☒	☐	This system is not used in MGR emergency response to provide prompt evacuation of personnel. However, this system is to be available to help determine the cause or consequences of DBEs during post-accident investigations. This system is to be available to assess off-normal conditions.
3.4	☒	☐	This item collects radiological, thermal, and other data while in the emplacement drift. Therefore, this system functions as part of the radiological monitoring system required to assess radionuclide dispersion following a DBE.
3.5	☐	☒	This item is not part of the design or design objectives for keeping levels of radioactive material in effluent to unrestricted areas as low as practicable during normal operations.
3.6	☐	☒	This item is not required to limit onsite worker doses from normal operations and during Category 1 DBEs, including planned recovery operations, to less than 10 CFR 63.111(a)(1) [10 CFR 20.1201] requirements.

PCM

Performance Confirmation
Emplacement Drift Monitoring System

SSC: Inspection Gantry

Level 3: N/A

Level 4: N/A

PCM

QL1 ☐

PS1 ☐ QL2 ☐

PS2 ☒ QL3 ☒

PS CQ ☐ CQ ☐

Q-List Rationale

SDD / SSC Reference: CRWMS M&O 1998c

TBVs Applicable to this Item: N/A

Pre-Screen - Importance to Safety or Waste Isolation Evaluation

	Yes	No	Rationale:
PS1	☐	☒	a. This item is not directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled at the MGR: confinement or containment, criticality control, shielding, heat transfer, structural integrity, or operations support necessary for waste handling safety.
	☐	☒	b.
	☐	☒	c.
	☐	☒	d.
	☐	☒	e.
	☐	☒	f.
PS2	☒	☐	This item is indirectly relied upon to provide an Important to Waste Isolation function.

Note: A Yes answer has been selected for either PS1 or PS2, therefore, the item is subject to QARD requirements. An Importance to Safety or Waste Isolation evaluation is required. Please continue with the evaluation checklists below.

QL1 - Quality Level 1: High Safety or Waste Isolation Significance

	Yes	No	Rationale:
1.1	☐	☒	Failure of the inspection gantry will not directly result in loss of waste package containment or criticality control.
1.2	☐	☒	The inspection gantry is used to position performance confirmation monitoring equipment within the emplacement drift. The gantry is not required to provide reasonable assurance that high-level waste can be received, handled, packaged, stored, emplaced, and retrieved without exceeding the requirements of 10 CFR 63.111(b)(1) and 10 CFR 20.1301(a)(1) for Category 1 DBEs.
1.3	☐	☒	The gantry is not required to function to prevent or mitigate a Category 2 DBE that would otherwise result in a radioactive release consequence above 10 CFR 63.111(b)(2) limits.
1.4	☐	☒	a. The inspection gantry does not perform a waste isolation function.
	☐	☒	b.

QL2 - Quality Level 2: Low Safety or Waste Isolation Significance

	Yes	No	Rationale:
2.1	☐	☒	The inspection gantry is not designed for the collection, containment, and/or monitoring of site-generated radioactive waste.
2.2	☐	☒	The inspection gantry does not perform a fire protection function.
2.3	☐	☒	Failure of the inspection gantry as a result of a DBE would not impair the capability of QL-1 SSCs to perform their intended radiological safety functions.

PCM

Performance Confirmation
Emplacement Drift Monitoring System

SSC: Inspection Gantry

Level 3: N/A

Level 4: N/A

PCM

QL1 ☐

PS1 ☐ QL2 ☐

PS2 ☒ QL3 ☒

PS CQ ☐ CQ ☐

Q-List Rationale

- 2.4 ☐ ☒ This item is not required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 25 mrem TEDE, per event, to any member of the public located on or beyond the site boundary [10 CFR 63.111(a) and 10 CFR 20.1301 (a)(1)].
- 2.5 ☐ ☒ This item, in conjunction with an additional item or administrative control (i.e., indirect impact), is not required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 100 mrem TEDE, per event, to any member of the public located on or beyond the site boundary.
- 2.6 ☐ ☒ This item, in conjunction with an additional item or administrative control (i.e., indirect impact), is not required to prevent or mitigate a Category 2 DBE that could result in offsite doses greater than or equal to the more limiting of 10 CFR 63.111(b)(2) doses to any individual located on, or beyond, any point on the site boundary.
- 2.7 ☐ ☒ a. Failure of the inspection gantry as a result of a DBE would not impair the capability of QL-1 SSCs to perform their intended waste isolation functions.
☐ ☒ b.
☐ ☒ c.
☐ ☒ d.

QL3 - Quality Level 3: Minor Safety Significance or Occupational Exposure Significance

	Yes	No	Rationale:
3.1	☐	☒	This item does not function to provide an alarm to warn of significant increases in radiation levels or concentrations of radioactive materials.
3.2	☒	☐	This item functions to assist in the monitoring of variables to verify that operating conditions are within technical specifications.
3.3	☒	☐	The inspection gantry is not used in MGR emergency response to provide for prompt evacuation of personnel. However, this item is available to assist in the determination of the cause and/or consequences of DBEs during pre-closure accident/off-normal event investigations.
3.4	☐	☒	This item does not function as part of the radiological, meteorological, or environmental monitoring systems required to assess radionuclide release or dispersion following a DBE.
3.5	☐	☒	This item is not part of the design or design objectives for keeping levels of radioactive material in effluent to unrestricted areas as low as practicable during normal operations.
3.6	☐	☒	This item is not required to limit onsite worker doses from normal operations and during Category 1 DBEs, including planned recovery operations, to less than 10 CFR 63.111(a)(1) [10 CFR 20.1201] requirements.

PCM

Performance Confirmation
Emplacement Drift Monitoring System

SSC: Waste Package Monitoring System

Level 3: N/A

Level 4: N/A

PCM

QL1 ☐

PS1 ☐ QL2 ☐

PS2 ☒ QL3 ☒

PS CQ ☐ CQ ☐

Q-List Rationale

SDD / SSC Reference: CRWMS M&O 1998c

TBVs Applicable to this Item: N/A

Pre-Screen - Importance to Safety or Waste Isolation Evaluation

	Yes	No	Rationale:
PS1	☐	☒	a. This item is not directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled at the MGR: confinement or containment, criticality control, shielding, heat transfer, structural integrity, or operations support necessary for waste handling safety.
	☐	☒	b.
	☐	☒	c.
	☐	☒	d.
	☐	☒	e.
	☐	☒	f.
PS2	☒	☐	This item is indirectly relied upon to provide an Important to Waste Isolation function.

Note: A Yes answer has been selected for either PS1 or PS2, therefore, the item is subject to QARD requirements. An Importance to Safety or Waste Isolation evaluation is required. Please continue with the evaluation checklists below.

QL1 - Quality Level 1: High Safety or Waste Isolation Significance

	Yes	No	Rationale:
1.1	☐	☒	Failure of the Waste Package Monitoring System would not directly result in loss of waste package containment or criticality control.
1.2	☐	☒	The Waste Package Monitoring System acquires pertinent data associated with verifying the performance of the waste package. The system is not required to provide reasonable assurance that high-level waste can be received, handled, packaged, stored, emplaced, and retrieved without exceeding the requirements of 10 CFR 63.111(b)(1) and 10 CFR 20.1301(a)(1) for Category 1 DBEs.
1.3	☐	☒	The system is not required to function to prevent or mitigate a Category 2 DBE that would otherwise result in a radioactive release consequence above 10 CFR 63.111(b)(2) limits.
1.4	☐	☒	a. The Waste Package Monitoring System is not part of the natural or engineered barriers that perform a waste isolation function.
	☐	☒	b.

QL2 - Quality Level 2: Low Safety or Waste Isolation Significance

	Yes	No	Rationale:
2.1	☐	☒	The Waste Package Monitoring System is not designed for the collection, containment, and/or monitoring of site-generated radioactive waste.
2.2	☐	☒	The Waste Package Monitoring System does not perform a fire protection function.
2.3	☐	☒	Failure of the Waste Package Monitoring System as a result of a DBE does not impair the capability of QL-1 SSCs to perform their intended radiological safety function.

PCM

Performance Confirmation
Emplacement Drift Monitoring System

SSC: Waste Package Monitoring System

Level 3: N/A

Level 4: N/A

PCM

QL1 ☐

PS1 ☐ QL2 ☐

PS2 ☒ QL3 ☒

PS CQ ☐ CQ ☐

Q-List Rationale

- 2.4 ☐ ☒ This item is not required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 25 mrem TEDE, per event, to any member of the public located on or beyond the site boundary [10 CFR 63.111(a) and 10 CFR 20.1301 (a)(1)].
- 2.5 ☐ ☒ This item, in conjunction with an additional item or administrative control (i.e., indirect impact), is not required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 100 mrem TEDE, per event, to any member of the public located on or beyond the site boundary.
- 2.6 ☐ ☒ This item, in conjunction with an additional item or administrative control (i.e., indirect impact), is not required to prevent or mitigate a Category 2 DBE that could result in offsite doses greater than or equal to the more limiting of 10 CFR 63.111(b)(2) doses to any individual located on, or beyond, any point on the site boundary.
- 2.7 ☐ ☒ a. Failure of the Waste Package Monitoring System would not result in the inability of QL-1 engineered barriers to perform long-term waste isolation functions in the postclosure phase, would not create ponding in the postclosure underground, introduce fluids, or compromise the ability of natural barriers to isolate waste.
- ☐ ☒ b.
- ☐ ☒ c.
- ☐ ☒ d.

QL3 - Quality Level 3: Minor Safety Significance or Occupational Exposure Significance

	Yes	No	Rationale:
3.1	☐	☒	This item does not function to provide an alarm to warn of significant increases in radiation levels or concentrations of radioactive materials.
3.2	☒	☐	This item functions to monitor variables to verify that operating conditions are within technical specifications. The system obtains and transfers waste package visual, thermal, and radiological monitoring data.
3.3	☐	☒	This item is not used in MGR emergency response to provide prompt evacuation of personnel, or to monitor variables used in helping to determine the cause or consequences of DBEs (during post accident investigations).
3.4	☒	☐	The data collected by the performance confirmation emplacement drift monitoring system (and the waste package monitoring system) can be used to assess off-normal conditions. Therefore, this system does function as part of the monitoring systems required to assess radionuclide release or dispersion following a DBE.
3.5	☐	☒	This item is not part of the design or design objectives for keeping levels of radioactive material in effluent to unrestricted areas as low as practicable during normal operations.
3.6	☐	☒	This item is not required to limit onsite worker doses from normal operations and during Category 1 DBEs, including planned recovery operations, to less than 10 CFR 63.111(a)(1) [10 CFR 20.1201] requirements.