OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT
SPECIAL INSTRUCTION SHEET

1. QA: N/A

Page: 1 of: 1

Complete Only Applicable Items

This is a placeholder page for records that cannot be scanned or microfilmed

2. Record Date
12/18/2000

3. Accession Number

MOL. 20001218.0004

4. Author Name(s)
JERALD W. KEIFER

5. Author Organization
N/A

6. Title
BUSTED BUTTE PHASE II EXCAVATION ANALYSIS

7. Document Number(s)
BABEE0000-01717-0200-00025

8. Version
REV. 00

9. Document Type
REPORT * 121801
DESIGN DOCUMENT

10. Medium
OPTIC/PAPER

11. Access Control Code
PUB

12. Traceability Designator
DC #26850

13. Comments
THIS IS A ONE OF A KIND DOCUMENT DUE TO THE COLORED GRAPHS ENCLOSED AND CAN BE LOCATED THROUGH THE RPC

OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT ANALYSIS/MODEL COVER SHEET

1. QA: N/A

Page: 1 of: 18

Complete Only Applicable Items

2. ☒ Analysis Check all that apply

Type of Analysis
☒ Engineering
☐ Performance Assessment
☐ Scientific

Intended Use of Analysis
☐ Input to Calculation
☐ Input to another Analysis or Model
☐ Input to Technical Document
☒ Input to other Technical Products

Describe use:
See Remarks (Block 12)

3. ☐ Model Check all that apply

Type of Model
☐ Conceptual Model ☐ Abstraction Model
☐ Mathematical Model ☐ System Model
☐ Process Model

Intended Use of Model
☐ Input to Calculation
☐ Input to another Model or Analysis
☐ Input to Technical Document
☐ Input to other Technical Products

Describe use:

4. Title:
Busted Butte Phase II Excavation Analysis

5. Document Identifier (including Rev. No. and Change No., if applicable):
BABEE0000-01717-0200-00025 REV 00

6. Total Attachments:
None

7. Attachment Numbers - No. of Pages in Each:
N/A

	Printed Name	Signature	Date
8. Originator	Jerald W. Keifer		11/29/00
9. Checker	Stephen Goodin		11/29/00
10. Lead/Supervisor	Jerald W. Keifer		11/29/00
11. Responsible	Lawrence R. Morrison		11/29/00

12. Remarks:
Block 2- Describe use: (continued)

This analysis provides excavation layout, ground support and pillar design input to the *Busted Butte Phase II Excavation Layout and Ground Support Plan and Sections Drawing*.

**OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT
ANALYSIS/MODEL REVISION RECORD**

1. Page: 2 of: 18

Complete Only Applicable Items

2. Analysis or Model Title:
Busted Butte Phase II Excavation Analysis

3. Document Identifier (including Rev. No. and Change No., if applicable):

BABEE0000-01717-0200-00025 REV 00

4. Revision/Change No.	5. Description of Revision/Change
00	Initial Issue

1. PURPOSE

The purpose of this analysis is to provide an engineering excavation and ground support design for the Busted Butte phase II mine back. The analysis will apply engineering practices and previous proven design methods for pillar design and ground support in accordance with applicable Integrated Safety Management principles and functions. The scope of this analysis is limited to the Busted Butte Test Facility. The intended use of this analysis is to provide testing excavation boundaries, ground support and pillar design input to drawing(s) to support test operations implementation. This design activity has been prepared under *Technical Work Plan For Test Facilities Design FY01 Work Activities* (TWP) (CRWMS M&O 2000b). No deviations from the TWP have been necessary for this analysis.

2. QUALITY ASSURANCE

2.1 APPLICABILITY OF THE QARD

Results of the Activity Evaluation (for Busted Butte mine back design task) in the TWP (CRWMS M&O 2000b, Attachment A, Page A-6, Block 15a) have determined that the preparation of this engineering analysis is not subject to the requirements of the *Quality Assurance Requirements and Description* (QARD) (DOE 2000b).

Special QA controls applicable to this analysis are identified by Determination of Importance Evaluations (DIEs), Classification Analysis and Design Analysis (CRWMS M&O 2000b, Section 18). The items addressed in this technical analysis are outside of the potential repository block and are not classified in accordance with QAP-2-3, *Classification of Permanent Items*. The *Determination of Importance Evaluation for Exploratory Studies Facility (ESF) Subsurface Testing Activities* (CRWMS M&O 2000c) is the only DIE which is applicable to activities at Busted Butte. There are no QA requirements from the DIE that apply to this engineering design analysis and thus no QA controls resulting from design analyses. Therefore, there is no special QA control that makes this analysis subject to the requirements of the QARD (DOE 2000b).

2.2 APPLICABILITY OF ISMQAP

No special controls have been identified for the *Integrated Safety Management Quality Assurance Program* Addendum 1 of the QARD (DOE 2000a) in the TWP (CRWMS M&O 2000b, Section 19). However, the requirements of the Addendum 1 are satisfied by preparation of this analysis in accordance with the Quality Affecting Design Control Procedure (AP-3.13Q) as required by the TWP (CRWMS M&O 2000b, Section 6).

2.3 MANAGEMENT OF ELECTRONIC DATA

No controls are specified through the TWP (CRWMS M&O 2000b, Section 10) for the management of electronic data.

3. COMPUTER SOFTWARE AND MODEL USAGE

This analysis was prepared using Microsoft Word, office automation system that is maintained by the information technology organization. In accordance with AP-SI.1Q Section 2.1, Microsoft Word is exempt from qualification and documentation under that procedure. No quality affecting software has been identified as being applicable to this work (CRWMS M&O 2000b, Section 13).

4. INPUTS

4.1 DATA AND PARAMETERS

4.1.1 Compressive strengths of core samples

See Table 1 for tabulated compressive strengths. (Used in Section 6.3.1 & 6.3.2)

4.1.2 Main Drift Survey Data

See Table 2 for the Main Drift, also known as the Running Drift (RD), survey profile data for pillar height and opening width adjacent to pillar location. (Used in Section 6.2.2 & 6.4)

4.1.3 Test Alcove Survey Data

See Table 3 for Test Alcove (TA) Survey Profile Data For Pillar Height And Opening Width Adjacent To Pillar Location. (Used in Section 6.2.2 & 6.4)

4.1.4 Saturated Bulk Density Of Overburden.

Topopah Spring (Welded Devitrified) Saturated Bulk density $147.8 \pm 1.4 \text{ lb/ft}^3$ (Maximum 149.2 lb/ft^3) Topopah Springs (Vitrophyre) Saturated Bulk density $144.5 \pm 1.1 \text{ lb/ft}^3$ (Nimick, 1987) (Used in Assumption 5.2)

4.1.5 Highest Surface Point

Highest surface elevation contour above the mine back pillar is $3620 \text{ ft} \pm 5 \text{ ft}$. (Sub Terra 1998, Section 2.1 Drawing 1) (Used in Section 6.2.2)

4.1.6 Pillar Geology

The Calico Hills formation (Tac) is located from the invert to about 2 m above the invert in the ribs of the pillar area along both the cross drift and running drift. The Topopah Springs tuffs (Ttpv1 & Ttpv2) overlie the Calico Hills, with the Ttpv2 forming the back and top 1 m of the pillar. (DTN: GS990708314224.008, Drawing OA-46-349) (Used in Section 6.3.1)

Topopah Spring Welded Unconfined Compressive Strength of 2.54 mm ϕ cores in MPa (Nimick 1987)	Calico Hills Unconfined Compressive Strength of 2.54 mm ϕ cores in MPa (Price 1982)	Topopah Spring Nonwelded Unconfined Compressive Strength of 2.54 mm ϕ cores in MPa (Nimick 1987)
22.1	21.7	22
22.0	22	29
22.7	27.4	28
23.6	22.9	23
33.9	18.9	27
18.8	20.7	35
31.8	35.9	28
20.5	30.5	
35.9	14.2	
35.5	15.3	
	26.5	
	19.4	
	26.2	
	34.1	
	41	
	32.7	
	24.7	
	23.4	
	25.4	
	15.7	
	16.7	
	21.5	
	19.9	
	20.1	
	27.4	
	39.1	
	42	
	15.4	
	14.8	

Table 1. Compressive Strengths

Description / RD Centerline Sta. (m)	Invert Elevation	Back Elevation	Offset – Right Rib.	Offset – Left Rib.
Pillar Corner 0+60.30	1069.02	1075.33	3.78	2.56
Pillar Side 0+60.87	1068.99	1074.81	2.94	2.55
Pillar Side 0+61.84	1068.95	1074.08	2.48	2.66
Pillar Side 0+66.13	1068.75	1075.60	2.65	2.87
End of Pillar 0+69.89	1068.70	1075.12	2.87	2.90

Table 2. Main Drift Survey Data (DTN: MO0003GSC00115.000)

Description / TA Centerline Sta. (m)	Invert Elevation	Back Elevation	Offset – Right Rib.	Offset – Left Rib.
Pillar Corner 0+02.80	1069.17	1074.87	3.04	2.98
Pillar Side 0+05.58	1069.19	1075.03	2.78	2.50
Pillar Side 0+09.92	1069.18	1074.9	3.18	2.99
Pillar Side 0+11.04	1069.19	1075.02	3.25	3.40
End of Pillar 0+12.08	1069.19	1075.56	3.09	2.92

Table 3. Test Alcove Survey Data (DTN: MO0003GSC00115.000)

4.2 Criteria

4.2.1 Test Integration Criteria Letter

- 4.2.1.1 Collection face mine back is located past the test alcove in the main drift on the right side. The excavation dimensions are 4 to 5 meters high, 4 to 5 meters wide and 4 to 9 meters long and provide a pillar between the test alcove of 3 to 5 meters thick. The minimum pillar width will be defined by the A/E design analysis. (CRWMS M&O 2000a, Page 2 Para. 3&4) (Used in Section 6.1)
- 4.2.1.2 Injection face mine back is located on the left rib of the Test Alcove. The excavation size of 4 to 5 meters high, 4 to 5 meters wide and 4 to 9 meters long and leaving a pillar between the test alcove of 3 to 5 meters thick. The minimum pillar width will be defined by the A/E design analysis. (CRWMS M&O 2000a, Page 2 Para. 3&4) (Used in Section 6.1)
- 4.2.1.3 The actual final breakout location for the minebacks will be determined in the field by the Principal Investigator (PI), Site Facilities Office, Title III Design, and Test Integration Department (TCO) and within the bounds of the design analysis. (CRWMS M&O 2000a, Page 3 Para. 8) (Used in Section 6.6.1)
- 4.2.1.4 Flexibility is allowed to modify transmitted criteria. Criteria modifications must be documented in formal comments at design review by TCO. (CRWMS-M&O 2000, Page 5 Para. 6) (Used in Section 6.1 & 6.6.1)

4.2.2. Design Requirement Documents.

There are no design requirement documents for the Busted Butte Test Facility.

4.3 Codes and Standards

4.3.1 29 CFR 1926.800 Underground construction

4.3.1.1 1926.800(b)(1)

"The employer shall provide and maintain safe means of access and egress to all work stations." (Used in Section 6.7)

4.3.1.2 1926.800(o)(3)(i)(A)

"A competent person shall inspect the roof, face, and walls of the work area at the start of each shift and as often as necessary to determine ground stability." (Used in Section 6.7)

5. Assumptions

- 5.1 The pillar design and scaling formulas used for coal pillars are assumed applicable for the bedded tuffs in the Busted Butte Test Facility. This assumption is based upon the applicability of the pillar design formula to coal seams regardless of the rock quality index of the coal seam. In contrast the bedded tuffs are homogenous and the geotechnical mapping (DTN: GS990708314224.008) indicates a good rock quality index at the intersection of the drifts. Therefore, the design parameters used for coal pillar design are considered more conservative than those necessary for tuff pillar design. (Used in Section 6.3.2)
- 5.2 Topopah Spring – Welded Devitrified Saturated Bulk density of 149.2 lbs/ ft³ (Input 4.1.4) can be used to represent the bulk density for the entire overlying units. This assumption is necessary since the relative thickness of the units overlying the pillar is unknown. This assumption does not need to be verified since the assumption is conservative by using the heaviest of the measured densities. (Used in Section 6.2.2)
- 5.3 The minimum excavated width of an opening by methods described in the criteria letter (CRWMS-M&O 2000a) is 2 m. (Used in Section 6.6.1)

Figure 1. Simplified Layout of Busted Butte Mineback

Block designator	Block Shape	Shape coefficient	Width (m)	Length (m)	Area (m ²)	Sum
a	Rectangle	1	1.00	2.00	2.00	
b	Rectangle	1	9.00	3.90	35.10	
c	Rectangle	1	5.00	5.10	25.50	
Pillar Area						62.60
d	Triangle	0.5	2.00	2.00	2.00	
e	Rectangle	1	3.00	2.00	6.00	
f	Rectangle	1	2.00	3.10	6.20	
g	Rectangle	1	2.00	1.50	3.00	
h	Rectangle	1	5.00	1.50	7.50	
i	Rectangle	1	3.01	1.50	4.52	
j	Rectangle	1	3.01	9.00	27.09	
k	Rectangle	1	3.01	2.81	8.46	
l	Rectangle	1	9.00	2.81	25.29	
					tributary fringe (pillar + fringe)	90.05
Tributary Area						152.65

Table 4. Pillar Area Calculation.

6. ANALYSIS/MODEL

6.1 MODIFIED DESIGN CRITERIA.

The original design criteria provided by Test Integration Department -Test Coordination Office Team (TCO) through the criteria letter (CRWMS M&O 2000a) was evaluated. In that evaluation a 5 meter by 5 meter pillar, the maximum pillar recommendation, and the minimum width of 4 meter excavation opening were used in the pillar design formulas described in section 6.2 through 6.5 (Criteria 4.2.1.1 and 4.2.1.2). The results of the calculation produced an unacceptable Safety Factor to proceed with the design under those criteria.

Based upon discussion with the TCO, pillar widths (for a free standing pillar) that produced a satisfactory design safety factor were unacceptable. That is, the excavation would fail to explore the target areas where the Principal Investigator (PI) required the information. Therefore, a solution that would meet the needs of the PI and provide a viable engineering design was required.

The problem with the pillar design was that the amount of tributary loading had to be minimized. The tributary loading is expressed as the ratio of tributary area to pillar area. The ratio had to be lowered to achieve a safety factor between 1.8 and 2.2. (Section 6.5). The ratio benefits from increasing the pillar area and minimizing the amount of the excavation around the pillar to the extent possible. The general arrangement as shown in Figure 1, achieves the desired ratio and allows excavation of the area where the injection hole intersects the collection holes.

Because the criteria from the letter are subject to modification during design review by the TCO (Criteria 4.2.1.4), the design process was continued. The pillar general arrangement as shown in Figure 1 is considered the accepted layout criteria.

6.2 PILLAR STRESS CALCULATIONS

6.2.1 Load Stress In The Pillar

The saturated bulk density and height of the overlying rock column is used to calculate the tributary load that a pillar is assigned to carry. The actual calculated density of the overlying rock will be used since the bulk density significantly varies from the assumed value of 1.1 psi per foot of depth commonly used in pillar loading formulas (Hartman 1992, Section 10.5.6.2). The rectangular pillar formulas are not applicable to the site-specific conditions because the pillar is irregular in shape and the saturated bulk density of tuff is lighter than the typical geologic formation. Therefore, the stress in the pillar (S_p) will be determined by multiplying the saturated bulk density by the overburden height times the ratio of the Tributary Area ($Area_T$) over the Pillar Area ($Area_p$) (Hartman 1992, Section 10.5.6.2). The Tributary Area is the total area assigned to be carried by the pillar,

which is the rock load directly above the pillar and the load half way to the center of the surrounding openings. Expressing the above as a formula form results in:

$$S_p = (Density)(Height) \frac{Area_T}{Area_P}$$

6.2.2 Pillar Stress Inputs

The back elevation of the drifts, adjacent to the pillar (see Figure 1), is the top of the pillar and forms the lower boundary for the overburden calculation. The mean of the back elevations (Input 4.1.2 & 4.1.3) is 1075.0 m. 1075.0 m is converted to feet by dividing by 0.3048 m/ft, which gives 3527 ft.

The highest elevation contour for the area directly about the pillar is 3620 ft $\pm$ 5 ft (Input 4.1.5). Therefore, 3625 ft will be used as the top boundary elevation for the overburden.

A bulk density of 149.2 lbs/ft³ (Assumption 5.2) will be used for the overburden.

The tributary loading area is the pillar area plus the area half way across the opening space. See Figure 1 for general arrangement of the pillar. The widths across the test alcove (a.k.a. Cross Drift) and the Running Drift (a.k.a. Main Drift) are irregular. The drift width used in the calculation will be the mean of the surveyed widths for each drift. The mean width of the Running Drift and Test Alcove is 5.62 m and 6.02 m, respectively. (Inputs 4.1.2 & 4.1.3)

Table 4 is the tabulated area calculations using the blocks and dimensions identified in Figure 1, and the mean widths of the Running Drift and the Test Alcove.

Therefore, Area_P is 62.6 m² and Area_T is 152.65 m² (Table 4). Because the tributary area to pillar area is a ratio and the dimensional units cancel, conversion to English units is not performed.

6.2.3 Pillar Stress Calculation

Substituting the inputs into the formula in Section 6.2.1 and rounding to three significant figures:

$$S_p = (149.2 \text{ lbs} / \text{ft}^3)((3625 \text{ ft} - 3527 \text{ ft})) \frac{152.65 \text{ m}^2}{62.60 \text{ m}^2} = 35700 \text{ psf} = 248 \text{ psi}$$

6.3 ROCK MASS STRENGTH CALCULATION.

6.3.1 Pillar Geology

Based upon the full-periphery geologic maps of the Busted Butte Test Facility, the pillar is comprised of Calico Hills (Tac), Topopah Springs (Ttpv1) and Topopah Springs (Ttpv2) (Input 4.1.6). The weakest member of the three units is the Calico Hills, based upon the mean compressive strength (Input 4.1.1). The pillar design will use the Calico Hills compressive strength in the design to represent the strength of the entire pillar.

6.3.2 Rock Strength

The mean strength of the Calico Hills core samples is 24.7 MPa or 3580 psi (Input 4.1.1). However, these strengths are from 25.4 mm core diameters (1 in) (Input 4.1.1), which must be scaled to represent the strength of the rock mass. For the specific design the scaling formula for coal pillar will be used (Assumption 5.1). The scaling formula is a two-part formula. The first formula takes various size diameter test results and prorates them into equivalent 1 inch results.

$$k = \sigma_c \sqrt{D} = 3580 \text{ psi} \sqrt{1} = 3580 \text{ psi}$$

(Hartman 1992, formula 10.5.20)

Where:

k is the equivalent average compressive strength
 σ_c is the average compressive strength of 3580 psi
D is the diameter of the core in inches (Input 4.1.1).

The second formula uses the equivalent 1 inch strength and scales into a rock mass strength for a large-sized pillar.

$$\sigma_L = \left(\frac{k}{\sqrt{36}} \right) = \left(\frac{3580 \text{ psi}}{\sqrt{36}} \right) = 597 \text{ psi}$$

(Hartman 1992, formula 10.5.18)

Where:

σ_L is the allowable stress for large-sized pillars
k is the calculated equivalent inch compressive strength.

6.4 PILLAR STRENGTH (ALLOWABLE STRESS)

The final pillar design formula is the "Holland formula" which takes the pillar dimensions of width and height into the design. Using the mean difference of the back to invert elevations for both drifts adjacent to the pillar (Inputs 4.1.2 & 4.1.3), the average height of the pillar is 6.0 m. For the width of these irregular pillars, the smallest

dimensional width along the pillar is used as the worst case. The segment width across block b in figure 1 is the smallest width at 3.9m.

$$\sigma_P = \sigma_L \sqrt{\frac{w}{h}} = 597 \text{ psi} \sqrt{\frac{3.9\text{m}}{6.0\text{m}}} = 481 \text{ psi}$$

(Hartman 1992, formula 10.5.23)

Where:

σ_P is the allowable stress for the pillar

w is the width of pillar

h is the height of the pillar

6.5 SAFETY FACTOR

The safety factor (SF) of the design is then calculated by dividing the allowable stress for the pillar (σ_P) by the stress in the pillar (S_P).

$$SF = \frac{\sigma_P}{S_P} = \frac{481 \text{ psi}}{248 \text{ psi}} = 1.94$$

Holland specified a safety factor from 1.8 to 2.2 for the design of coal pillars (Hartman 1992, Section 10.5.6.1).

6.6 BOUNDS OF THE PILLAR DESIGN

6.6.1 Flexibility

The design (Criteria 4.2.1.3 & 4.2.1.4) requires that maximum flexibility be provided to make adjustments due to the unexpected geological conditions and the needs of the PI. Therefore, the general layout in Figure 1 uses conservative and worst case configurations to provide flexibility in the design.

The square sides of the pillar that are shown in Figure 1, that are adjacent to the Test Alcove and the Main Drift should be located within the boundaries of the as-constructed rib profile, so that the layout pillar will have a slightly greater area than the area shown.

The excavation area shown as block "e" in Figure 1 is configured as the worst case. This excavation is calculated as a 3 meter width but will be specified as 2.5 meter in width to compensate for overbreak that will likely form around the corners. This excavation may be located anywhere along the 4 meter working face, since the location in Figure 1 is worst case and bounds all locations along the face.

The width of the access drift that is driven off the Test Alcove is analyzed as a 3 meter wide opening. This will be the maximum width. The minimum width is 2 meters (Assumption 5.3).

The pillar width and length dimensions along the Test Alcove and Main Drift are minimum dimensions. Increasing the width or length or both width and length increases the safety factor of the pillar by favorably affecting the tributary area to pillar area ratio. These dimensions may be increased as needed. (Criteria 4.2.1.3)

The average pillar height used in the calculations is 6.0 m. Therefore, the phase II mineback excavation average height should not exceed the 6.0m height without further evaluation. The 6.0m average height is the upper bounds for this analysis with no minimum height identified.

6.6.2 Constraints

The minimum width of the pillar at any location is 3.9 m, which is the minimum analyzed width (Section 6.4). Therefore, it is prudent to set the maximum excavation tolerance to leave a 4.0 meter thickness at the minimum point. However, since this minimum thickness is not free standing, i.e., the thin area is confined by larger rockmass areas (See Figure 1), the 3.9 m thickness does not need to be considered as a single location minimum but may be considered as an average thickness when evaluating post construction overbreak.

Overbreak, chamfering corners and intentional miscellaneous excavations are within the bounds of this analysis provided that the pillar bearing area of 57.3 m² or greater is maintained. This pillar area is the threshold for meeting the minimum acceptable safety factor when substituted for the design area of 62.6 m² in calculations of Sections 6.2 through 6.6. As-constructed surveys should be made as required during construction as a means of monitoring encroachment of the minimum pillar area.

6.7 SUPPORT OF OPENINGS.

Ground support design, both the pillar design and back and rib reinforcement are necessary to provide stability to the opening, and to provide protection for personnel and equipment against potential falls of loose rock for the back and rib of the excavation. (Criteria 4.3.1.1)

Both the original Busted Butte design (Sub Terra 1998, Section 4.2) and the design confirmation analysis (CRWMS M&O 1998, Section 7.4) identify a bolting pattern of 1500 mm X 1500 mm with 2 m rockbolts. Therefore, the 1500 mm X 1500 mm pattern are an analyzed quantity and the pattern should be considered the maximum spacing for rockbolting the excavations. A nominal space of 1300 mm should be specified with the 1500 mm maximum to ensure compliance to the maximum spacing.

Welded Wire Fabric should be used for personnel safety and should be in accordance with Exploratory Studies Facility (ESF) specifications. The type of rockbolts used were Swellex and Split Set rockbolts. Shotcrete, 50 to 75 mm thickness, was specified at the intersections by Sub Terra (Sub Terra, Inc. 1998, Section 4.2) based upon empirical

design. However, the FLAC analysis in the confirmation analysis (CRWMS-M&O 1998, Section 7.4) determined that the shotcrete was unnecessary. Mandatory installation of shotcrete should not be specified; but the use of shotcrete should be allowed by the direction of the A/E or Constructor with TCO concurrence based upon site specific conditions. The empirical design thickness of 50 to 75 mm should be adequate.

The Busted Butte Test Facility should be monitored on a daily basis when the facility is occupied (Criteria 4.3.1.2). Convergence monitoring should be part of the monitoring program to provide warning should unexplainable acceleration in convergence occur.

6.8 QA CONTROLS ON ACTIVITIES.

The TWP (CRWMS M&O 2000b, Section 18) identifies the DIEs as a source for Special QA Controls applicable to the scope of work. However, the *Determination of Importance Evaluation for Exploratory Studies Facility (ESF) Subsurface Testing Activities* (CRWMS M&O 2000c), which is applicable for the activities at Busted Butte Test Facility, applies only to the test organization. The general practice is to write a construction DIE for the construction of a test facility. The facility is turned over to the testers after the construction has been completed. The testing DIE subsequently provides QA controls on the test activities. However, for the Phase II Mine Back the excavation is an integral part of the test, i.e., the excavation is to examine the tracer plumes in the rock. Therefore, the scope of work is a testing activity.

The testing DIE (CRWMS M&O 2000c) evaluated the construction and operations associated with the activities at Busted Butte. The QA Controls generated in the testing DIE (CRWMS M&O 2000c) are normally implemented by the testing organization through the Field Work Package (FWP). Therefore, the QA Controls from the DIE (CRWMS M&O 2000c) should flow down through the Field Work Package (FWP) to the constructor. The TCO is responsible to ensure that the applicable QA controls are contained in the work instructions. Title III A/E should review the work instructions to ensure the QA Controls are adequately covered by the work instruction.

7. CONCLUSIONS

- 7.1 The dimensions of Figure 1 should be used for the general arrangement drawing except as provided in Section 7.4. This pillar provides a safety factor of 1.94, which is satisfactory. (Section 6.5)
- 7.2 The as-constructed dimensions of the Busted Butte Test Facility should be used for the drawing. The square pillar perimeter of Figure 1 should be laid out within the boundaries of the as-constructed ribs of the test alcove and main drift. (Section 6.6.1)
- 7.3 The width and length of the pillar are minimum dimensions, and may be extended due to the unexpected geological conditions. (Section 6.6.1)

- 7.4 The excavation area (shown as block "e" in Figure 1) shall have a maximum width of 2.5 m. The maximum depth of the mine back shall not violate a 3.9 m minimum average thickness of the pillar between the excavation and the main drift and the drawing layout thickness shall not be less than 4.0 m. The location of the 2.5 m excavation may be adjusted along the 4 m working face. The specific location of the 2.5 m excavation shall be determined by the PI prior to excavation. (Section 6.6.2)
- 7.5 The entry drift from the Test Alcove shall be a minimum width of 2 m and a maximum width of 3 m. (Section 6.6.1)
- 7.6 Over-break, chamfering corners and intentional miscellaneous excavations are allowed provided that the final pillar bearing area of 57.3 m² or greater is maintained. As-constructed survey shall be made to assess encroachment on the minimum pillar area, as required. (Section 6.6.2)
- 7.7 Swellex, Superswellex or Split Set Rockbolts of 2 m minimum length shall be used to reinforce the back. The rockbolts shall be installed on a nominal 1300 mm square pattern with a maximum of 1500 mm between rockbolts. Welded Wire Fabric shall be used in conformance with A/E Specifications. (Section 6.7)
- 7.8 Shotcrete shall be installed, as directed by the A/E or as required by the Constructor, for personnel safety with TCO concurrence. The shotcrete shall be in accordance with A/E specifications and shall be installed a nominal 75 mm (minimum of 50 mm) thickness. (Section 6.7)
- 7.9 Convergence monitoring by the construction personnel is required in the Busted Butte Test Facility. This measurement shall be on a daily basis during excavation of the mine back area as a means to assess stability of the excavation. Monitoring is only necessary when the facility is occupied. (Section 6.6.2)
- 7.10 QA Controls on excavation activities are the responsibility of the TCO will be in the FWP. The TCO is responsible for ensuring QA controls are contained in the work instructions. Title III A/E to ensure QA controls are adequately documented in work instructions. (Section 6.8)
- 7.11 The maximum average height of the phase II excavations shall not exceed 6.0 m with out further evaluation. There is no minimum height limitations. (Section 6.6.1)

8. INPUTS AND REFERENCES

8.1 DOCUMENTS CITED

CRWMS M&O 1998. *Busted Butte Test Facility Ground Support Confirmation Analysis*. BABEE0000-01717-0200-00020 REV 00. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19980818.0227.

CRWMS M&O 2000a. *Design and Test-related Information for Design and Construction of the Busted Butte Phase II Mineback*. Input Transmittal 00340.T. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20000929.0217.

CRWMS M&O 2000b. *Technical Work Plan For Test Facilities Design FY01 Work Activities*. TWP-MGR-MD-000012, REV 00, 11/01/00. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20001108.0004.

CRWMS M&O 2000c. *Determination of Importance Evaluation for Exploratory Studies Facility (ESF) Subsurface Testing Activities*. BAB000000-01717-2200-00011 REV 02 ICN 05. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20001107.0377.

DOE (U.S. Department of Energy) 2000a. *Integrated Safety Management Quality Assurance Program*. Addendum 1, DOE/RW-0333P, Rev. 0. [Washington, D.C.]: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: MOL.20000419.0915.

DOE (U.S. Department of Energy) 2000b. *Quality Assurance Requirements and Description*. DOE/RW-0333P, Rev. 10. Washington, D.C.: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: MOL.20000427.0422.

GS990708314224.008. Full-Periphery Geologic Maps for Station 0+00.00 to 0+55.00 for Busted Butte: Cross Drift and Access Drift. Submittal date: 12/08/1999.

Hartman, H.L., ed. 1992. *SME Mining Engineering Handbook*. 2nd Edition. Volume 1. Littleton, Colorado: Society for Mining, Metallurgy and Exploration. TIC: 206894.

MO0003GSC00115.000. Busted Butte Test Facility Profile Alignment. Submittal date: 03/16/2000.

Nimick, F.B.; Van Buskirk, R.G.; and McFarland, A.F. 1987. Uniaxial and Triaxial Compression Test Series on the Topopah Spring Member from USW G-2, Yucca Mountain, Nevada. SAND85-0703. Albuquerque, New Mexico: Sandia National Laboratories. ACC: NNA.19891019.0289.

Price, R.H. and Jones, A.K. 1982. *Uniaxial and Triaxial Compression Tests Series on Calico Hills Tuff*. SAND82-1314. Albuquerque, New Mexico: Sandia National Laboratories. ACC: NNA.19900810.0480.

SubTerra 1998. *Final Report, TRW Environmental Safety Systems, Inc., Busted Butte Test Facility*. Project: 97-35. Kirkland, Washington: SubTerra, Inc. TIC: 247628.

8.2 REGULATIONS, STANDARDS, AND DIRECTIVES CITED

29 CFR 1926. Labor: *Safety and Health Regulations for Construction*. Readily Available.

8.3 PROCEDURES CITED

AP-3.13Q, Rev. 1, ICN 0. *Design Control*. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20000131.0432.

AP-SI.1Q, Rev. 2, ICN 4, ECN 1. *Software Management*. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20001019.0023.

QAP-2-3, Rev. 10. *Classification of Permanent Items*. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19990316.0006.

9. ATTACHMENTS

Not Used.