**OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT
ANALYSIS/MODEL COVER SHEET**

1. QA: L

Page: 1 of: 11

Complete Only Applicable Items

2. ☒ Analysis ☒ Engineering ☐ Performance Assessment ☐ Scientific	3. ☐ Model ☐ Conceptual Model Documentation ☐ Model Documentation ☐ Model Validation Documentation
---	--

4. Title:
Classification of the MGR Carrier Preparation Building System

5. Document Identifier (including Rev. No. and Change No., if applicable):
ANL-CBS-SE-000001 REV 00

6. Total Attachments:
Three (3)

7. Attachment Numbers - No. of Pages in Each:
I-1, II-4, III-10

	Printed Name	Signature	Date
8. Originator	Scott E. Salzman		8/30/99
9. Checker	James A. Kappes		8/30/99
10. Lead/Supervisor	Thomas D. Dunn		8/30/99
11. Responsible Manager	Dealis W. Gwyn		8/31/99

12. Remarks:
This analysis contains To Be Verified (TBV) design input as follows: TBV-457, TBV-459, & TBV-460.

The document number for this analysis was previously BCB000000-01717-0200-00012 REV00.

This analysis bases the classification of Monitored Geologic Repository structures, systems and components on the criteria of proposed rule 10 CFR 63 (64 FR 8640). A review has determined that the changes made to proposed rule 10 CFR 63 by Interim Guidance Pending Issuance of New U. S. Nuclear Regulatory Commission (NRC) Regulations for Yucca Mountain, Nevada (Dyer 1999) do not impact the classifications made in this analysis.

**OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT
ANALYSIS/MODEL REVISION RECORD**

1. Page: 2 of: 11

Complete Only Applicable Items

2. Analysis or Model Title:
Classification of MGR Carrier Preparation Building System

3. Document Identifier (including Rev. No. and Change No., if applicable):

ANL-CBS-SE-000001 REV 00

4. Revision/Change No.	5. Description of Revision/Change
00	Initial issue. This system specific analysis was performed to supersede the applicable portion of B000000000-01717-0200-00134 Rev 01 (CRWMS M&O 1998d).

CONTENTS

	Page
1. PURPOSE.....	4
2. QUALITY ASSURANCE.....	4
3. COMPUTER SOFTWARE AND MODEL USAGE.....	4
4. INPUTS.....	4
4.1 PARAMETERS.....	4
4.2 CRITERIA.....	5
4.3 CODES, STANDARDS, AND REGULATIONS.....	5
5. ASSUMPTIONS.....	5
6. ANALYSIS.....	6
6.1 METHOD.....	6
6.2 MGR DESIGN CONFIGURATION AND ARCHITECTURE.....	7
6.3 MGR SAFETY STRATEGY.....	7
6.4 DESIGN BASIS EVENT ANALYSIS.....	8
6.5 QUALITY ASSURANCE CLASSIFICATION OF MGR STRUCTURES, SYSTEMS, AND COMPONENTS.....	8
7. CONCLUSIONS.....	8
7.1 MGR QA CLASSIFICATION.....	8
7.2 IMPACT OF UNVERIFIED DATA.....	9
8. REFERENCES.....	10
8.1 DOCUMENTS CITED.....	10
8.2 CODES, STANDARDS, AND REGULATIONS.....	11
8.3 PROCEDURES.....	11
9. ATTACHMENTS.....	11

Tables

1. CARRIER PREPARATION BUILDING SYSTEM QA CLASSIFICATION.....	9
---	---

1. PURPOSE

The purpose of this analysis is to document the Quality Assurance (QA) classification of the Monitored Geologic Repository (MGR) carrier preparation building system structures, systems and components (SSCs) performed by the MGR Safety Assurance Department. This analysis also provides the basis for revision of YMP/90-55Q, *Q-List* (YMP 1998). The Q-List identifies those MGR SSCs subject to the requirements of DOE/RW-0333P, *Quality Assurance Requirements and Description* (QARD) (DOE 1998).

This QA classification incorporates the current MGR design and the results of the *Preliminary Preclosure Design Basis Event Calculations for the Monitored Geologic Repository* (CRWMS M&O 1998a).

2. QUALITY ASSURANCE

This analysis is subject to the requirements of the QARD (DOE 1998) as determined by procedures QAP-2-0, *Conduct of Activities*, and NLP-3-18, *Documentation of QA Controls on Drawings, Specifications, Design Analyses, and Technical Documents. Design Basis Event Definition & Analysis/QA Classification Analysis (1.2.1.11) Activity Evaluation* (CRWMS M&O 1999a) presents the QAP-2-0 activity evaluation addressing the QA classification of MGR SSCs. This analysis is performed in accordance with procedures QAP-2-3, *Classification of Permanent Items*, and AP-3.10Q, *Analyses and Models*, and provides input to the design of SSCs included on the Q-List (YMP 1998). Unverified design inputs are identified and tracked in accordance with NLP-3-15, *To Be Verified (TBV) and To Be Determined (TBD) Monitoring System*.

3. COMPUTER SOFTWARE AND MODEL USAGE

This analysis uses no software which is required to be controlled in accordance with procedure AP-SI.1Q, *Software Management*.

4. INPUTS

4.1 PARAMETERS

The offsite radiological consequences of MGR Category 1 and 2 design basis events (DBEs), as calculated in *Preliminary Preclosure Design Basis Event Calculations for the Monitored Geologic Repository* (CRWMS M&O 1998a), are utilized in the QA classification of MGR SSCs. These results represent a conservative evaluation of MGR DBEs and the best information available. As discussed in Section 6.1 of this analysis, NUREG-1318, *Technical Position on Items and Activities in the High-Level Waste Geologic Repository Program Subject to Quality Assurance Requirements* (NRC 1998, Section 4.2(a)) allows the use of engineering judgement and conservative bounding assumptions in the QA classification of facility SSCs when data sources are limited. Also, procedure YAP-2.7Q, *Item Classification and Maintenance of the Q-List* (Attachment 3, Section a), directs the

use of the highest level of detail available to support the conclusion of the QA classification analysis.

Although MGR DBE calculations (CRWMS M&O 1998a) postulate a release of radioactive material for the carrier preparation building system and performs subsequent consequence analysis, the incorporation of the MGR preclosure safety strategy prevents the breach of transportation casks and the release of radioactive material within the building. The MGR preclosure safety strategy is discussed in Sections 5.2 and 6.3.

4.2 CRITERIA

The criteria used in the QA classification of MGR SSCs are provided in procedure QAP-2-3 as discussed in Section 6.1. These criteria satisfy the requirement of Section 2.2.2, *Classifying Items*, of DOE/RW-0333P (DOE 1998).

4.3 CODES, STANDARDS, AND REGULATIONS

10 CFR (Code of Federal Regulations) 20. Energy: Standards for Protection Against Radiation. January 1, 1999.

10 CFR 71. Energy: Packaging and Transportation of Radioactive Material. January 1, 1999.

64 FR (Federal Register) 8640. Disposal of High-Level Radioactive Wastes in a Proposed Geologic Repository at Yucca Mountain, Nevada. Proposed rule 10 CFR 63.

NRC (Nuclear Regulatory Commission) 1998. *Technical Position on Items and Activities in the High-Level Waste Geologic Repository Program Subject to Quality Assurance Requirements*. NUREG-1318. April 1988. Washington, D.C.: U.S. Nuclear Regulatory Commission.

5. ASSUMPTIONS

The following assumptions are made in the performance of this analysis.

- 5.1 This analysis assumes that system design, architecture and functions are established by the *Carrier Preparation Building System Description Document* (CRWMS M&O 1998c). This analysis also assumes that the MGR architecture is established by *Monitored Geologic Repository Architecture* (CRWMS M&O 1999b) and that MGR operations and architecture are described by *Monitored Geologic Repository Concept of Operations* (CRWMS M&O 1998b). These documents represent the best available MGR design information. This assumption is utilized in Section 6.2 to define the carrier preparation building system design configuration and SSC functions.
- 5.2 This analysis assumes the implementation of guidance provided by the "Strategy to Mitigate Preclosure Offsite Exposure" (Hastings 1998, Attachment 3 [all]), hereafter referred to as the

"safety strategy." The safety strategy proposes general guidance focused on reducing the risks associated with the handling of spent nuclear fuel, high-level waste and the associated casks, canisters, and containers. This assumption is utilized in Section 6.5 for the classification of the carrier preparation building system. In the case of the carrier preparation building system, the safety strategy assumes that a design basis impact will be determined for a transportation cask with impact limiters removed and that cask handling operations will be performed such that the design impact is not exceeded. As a result of this assumption, no event resulting in breach of a transportation cask is expected as part of carrier preparation building operations and the cask is assumed to maintain confinement of radioactive material. (TBV-460).

- 5.3 The 10 CFR Part 63 definition of *Important to Safety* invokes the 10 CFR Part 20 radiation exposure limits for Category 1 DBEs. However, the analysis of occupational exposures as a result of Category 1 DBEs has not been performed to date. This analysis assumes that the radiation doses to facility workers as the result of Category 1 DBEs associated with the carrier preparation building system, do not exceed the occupational dose limits of 10 CFR Part 20, Subpart C. This assumption is based on the waste form remaining within the shielded transportation cask during operations (CRWMS M&O 1998b) and Assumption 5.2 that assumes system design prevents DBEs that result in a breach of the transportation cask. This assumption is utilized in Section 6.5 for the classification of system SSCs. (TBV-459)
- 5.4 This analysis assumes that system fire protection systems are not required to prevent exceeding 10 CFR Part 63 dose limits for Category 1 and 2 DBEs. This assumption is based on engineering judgement and analyses performed for the Centralized Interim Storage Facility (DOE 1997). This assumption is utilized in Section 6.5 for the classification of system fire protection systems. (TBV-457)

6. ANALYSIS

6.1 METHOD

The basic process for classifying permanent MGR SSCs is provided by procedure QAP-2-3. Guidance provided by procedure YAP-2.7Q is also used in this analysis. The process consists of establishing the configuration and function of MGR SSCs and the effect of the SSC on MGR radiological safety. This information is then evaluated against criteria provided in QAP-2-3 to determine the QA classification of the particular item. The classification criteria are provided in the form of checklists in procedure QAP-2-3. A copy of these criteria checklists is provided in Attachment II. The following classification categories are specified by QAP-2-3 to meet the requirements of Section 2 of the QARD (DOE 1998).

Quality Level 1 (QL-1) Those SSCs whose failure could *directly* result in a condition adversely affecting public safety. These items have a high safety or waste isolation significance.

Quality Level 2 (QL-2) Those SSCs whose failure or malfunction could *indirectly* result in a condition adversely affecting public safety, or whose *direct* failure would result in consequences in excess of normal operational limits. These items have a low safety or waste isolation significance.

Quality Level 3 (QL-3) Those SSCs whose failure or malfunction would not significantly impact public or worker safety, including those defense-in-depth design features intended to keep doses ALARA (As Low As Reasonably Achievable). These items have a minor impact on public and worker safety and waste isolation.

Conventional Quality (CQ) Those SSCs not meeting any of the criteria for Quality Levels 1, 2, or 3. Conventional quality items are not subject to the requirements of QARD.

This analysis method is based on an iterative design-classification process where each analysis iteration is considered a final product for that phase of design. In this case, the system design and the DBE analysis (CRWMS M&O 1998a) are evaluated to determine which of the system's SSCs require design control under the QA program. The analysis presented in this document, therefore, will be reevaluated as necessary using a methodology appropriate to the level of DBE analysis and system design detail. This approach is consistent with NUREG-1318, *Technical Position on Items and Activities in the High-Level Waste Geologic Repository Program Subject to Quality Assurance Requirements* (NRC 1998, Section 4.2(a)), which allows engineering judgement and conservative bounding assumptions to be used in cases where data are limited.

6.2 MGR DESIGN CONFIGURATION AND ARCHITECTURE

Prior to the QA classification of MGR SSCs, the system design configuration as well as the function of system's SSCs are established. This classification analysis is based upon the system design and functions as established by the System Description Document (SDD) (CRWMS M&O 1998c) and the MGR Concept of Operations (CRWMS M&O 1998b). In the process of QA classification, if two or more subsystems perform similar functions or are similarly classified, these subsystems are classified as a group under the higher level system and not listed individually.

6.3 MGR SAFETY STRATEGY

The MGR safety strategy provides general guidance that limits or reduces the risks associated with the receipt, handling, packaging and emplacing of spent nuclear fuel and other high level wastes in the planned repository. The strategy is described in "Strategy to Mitigate Preclosure Offsite Exposure" (Hastings 1998 [all]) which suggests a combination of containment and event prevention concepts for the following functional areas of the MGR: (1) receipt of waste, (2) transfer of waste to WP, (3) packaging/sealing waste in WP, (4) transfer of the WP to the emplacement drift, and (5) emplacement of the WP.

Implementation of the safety strategy is assumed in this analysis to determine SSC QA

classifications. If the proposed safety strategy is not or cannot be implemented, the QA classification of the affected SSCs will be reviewed and the SSCs reclassified appropriately.

Operations in the carrier preparation building involve radiation and contamination surveys of the carrier/cask and removal of personnel barriers and impact limiters from the transportation cask. The removal of the impact limiters changes the cask design basis drop height from 9 meters to some unknown value as the analysis of cask drops without impact limiters is not required by 10 CFR 71 and has not been performed. The preclosure safety strategy assumes that a design basis impact will be determined for a transportation cask with impact limiters removed and that lifts or transports that exceed this design impact will not be performed. As a result of this assumption, no event resulting in a breach of the transportation cask is expected as part of carrier preparation building operations and the cask is assumed to maintain confinement of radioactive material. Consequently, no confinement function is required by the carrier preparation building and no requirement exists for a carrier preparation building confinement ventilation system.

6.4 DESIGN BASIS EVENT ANALYSIS

A preliminary analysis of MGR DBEs (CRWMS M&O 1998a) has been performed to determine the effects of internal and external events on facility radiological safety and is utilized by this analysis in the classification of MGR SSCs. The DBE analysis addresses both the DBE frequencies and dose consequences at the site boundary. In addition to internal events associated with the above systems, selected seismic, loss of offsite power, and criticality events were also addressed.

As discussed in Section 6.3, the MGR preclosure safety strategy assumes that no release of radioactive material occurs in the carrier preparation building system.

6.5 QUALITY ASSURANCE CLASSIFICATION OF MGR SSCS

The MGR SSCs are evaluated against the criteria of QAP-2-3 to determine the item QA classification level. The results of the MGR preliminary DBE calculations (CRWMS M&O 1998a) are utilized in this evaluation.

7. CONCLUSIONS

7.1 MGR QA CLASSIFICATION

The results of this QA classification analysis are provided in Table 1. As the design of the MGR proceeds and further DBE analyses of MGR hazards are performed, this classification analysis will be reviewed for impact and revised as necessary. The MGR classification checklists included in procedure QAP-2-3 are reproduced in Attachment II. The basis for the classification evaluation is provided in Attachment III.

Table 1 Carrier Preparation Building System QA Classification

Carrier Preparation Building System (CBS)	QL-1	QL-2	QL-3	CQ	TBV
Carrier Preparation Building				X	459, 460
Electrical Systems				X	459, 460
Fire Protection System				X	457
Non-Nuclear HVAC System				X	459, 460
Piped Utility Systems				X	459

7.2 IMPACT OF UNVERIFIED DATA

7.2.1 TBV-457

This analysis assumes that carrier preparation building fire protection systems are not required to prevent exceeding the dose limits of 10 CFR 63.111(a) and (b) (64 FR 8640) and as a result are classified CQ. This assumption is utilized in Section 6.5 for the classification of system SSCs. Inability to verify this assumption could result in the reclassification of carrier preparation building fire protection systems from CQ to QL-1 or QL-2.

7.2.2 TBV-459

This analysis assumes that the radiation doses to facility workers as the result of Category 1 DBEs associated with the carrier preparation building system do not exceed the occupational dose limits of 10 CFR Part 20, Subpart C.

The basis of this assumption is provided in Section 5.3. TBV-459 requires that future DBE analysis verify this assumption. If the assumptions addressed by TBV-459 cannot be verified by MGR DBE analysis, system SSCs may be reclassified from CQ to QL-3.

7.2.3 TBV-460

The safety strategy assumes that a design basis impact for a transportation cask with impact limiters removed is determined and that impacts exceeding the design value are prevented (occurrence frequency less than 1×10^{-6} /year). The impact of not achieving the strategy objective may include:

- No transfers of transportation casks outside of confined, HEPA (High Efficiency Particulate Air)-filtered areas after removal of impact limiters. This may require carrier preparation in the waste handling building carrier bay and provision of the carrier bay with a HEPA-filtered exhaust system and required airlocks.
- Reclassification of the carrier preparation building system SSCs from CQ to QL-1 or QL-2.

8. REFERENCES

8.1 DOCUMENTS CITED

CRWMS M&O (Civilian Radioactive Waste Management System Management and Operating Contractor) 1998a. *Preliminary Preclosure Design Basis Event Calculations for the Monitored Geologic Repository*. BC00000000-01717-0210-00001 REV 00. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19981002.0001.

CRWMS M&O 1998b. *Monitored Geologic Repository Concept of Operations*. B000000000-01717-4200-00004 REV 02. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19980810.0283.

CRWMS M&O 1998c. *Carrier Preparation Building System Description Document*. BCB0000000-01717-1705-00002, REV 00. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19981111.0032.

CRWMS M&O 1998d. *Classification of the Preliminary MGDS Repository Design*. B000000000-01717-0200-00134 REV 01. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19981103.0546.

CRWMS M&O 1999a. *Design Basis Event Definition & Analysis/QA Classification Analysis (1.2.1.11) Activity Evaluation*. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19990325.0008.

CRWMS M&O 1999b. *Monitored Geologic Repository Architecture*. B000000000-01717-5700-00011 REV 02 ICN 01. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19990713.0203.

DOE (U.S. Department of Energy) 1997. *Centralized Interim Storage Facility Topical Safety Analysis Report*. Docket No. 72-21. Washington, D.C.: U. S. Department of Energy. ACC: MOV.19970523.0004.

DOE 1998. *Quality Assurance Requirements and Description*. DOE/RW-0333P, Rev. 8. Washington D.C.: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: MOL.19980601.0022.

Dyer, J.R. 1999. *Interim Guidance Pending Issuance of New U. S. Nuclear Regulatory Commission (NRC) Regulations for Yucca Mountain, Nevada*. Letter from J. Russell Dyer (DOE) to D. R. Wilkins (YMP), June 18, 1999. OL&RC:AVG:1435. ACC: MOL.19990623.0026 and MOL.19990623.0027.

Hastings, C. R. 1998. "Strategy to Mitigate Preclosure Offsite Exposure." Hastings (CRWMS M&O) Interoffice Correspondence to Distribution (CRWMS M&O). LV.SEI.CRH.7/98-024. July 21, 1998. ACC: MOL.19980916.0357, MOL.19980916.0358, MOL.19980916.0359, and MOL.19980916.0360.

YMP (Yucca Mountain Site Characterization Project) 1998. *Q-List*. YMP/90-55Q, Rev. 5. Las Vegas, Nevada: Yucca Mountain Site Characterization Office. ACC: MOL.19980513.0132.

8.2 CODES, STANDARDS, AND REGULATIONS

10 CFR (Code of Federal Regulations) 20. Energy: Standards for Protection Against Radiation. January 1, 1999.

10 CFR 71. Energy: Packaging and Transportation of Radioactive Material. January 1, 1999.

64 FR (Federal Register) 8640. Disposal of High-Level Radioactive Wastes in a Proposed Geologic Repository at Yucca Mountain, Nevada. Proposed rule 10 CFR 63.

NRC (Nuclear Regulatory Commission) 1998. *Technical Position on Items and Activities in the High-Level Waste Geologic Repository Program Subject to Quality Assurance Requirements*. NUREG-1318. April 1988. Washington, D.C.: U.S. Nuclear Regulatory Commission.

8.3 PROCEDURES

AP-3.10Q, Rev. 0, ICN 0. *Analyses and Models*. ACC: MOL.19990225.0335.

AP-SI.1Q, Rev. 1, ICN 0. *Software Management*. ACC: MOL.19990520.0164.

NLP-3-15, Rev. 5. *To Be Verified (TBV) and To Be Determined (TBD) Monitoring System*. ACC: MOL.19981117.0148.

NLP-3-18, Rev. 04. *Documentation of QA Controls on Drawings, Specifications, Design Analyses, and Technical Document*. ACC: MOL.19960611.0170.

QAP-2-0, Rev. 5. *Conduct of Activities*. ACC: MOL.19980826.0209.

QAP-2-3, Rev. 10. *Classification of Permanent Items*. ACC: MOL.19990316.0006.

YAP-2.7Q, Rev. 1, ICN 1. *Item Classification and Maintenance of the Q-List*. ACC: MOL.19990115.0065.

9. ATTACHMENTS

Attachment I	Acronyms
Attachment II	MGR Classification Checklists
Attachment III	MGR QA Classification

Attachment I

Acronyms

ALARA	As Low As Reasonably Achievable
CFR	Code of Federal Regulations
CQ	Conventional Quality
CRWMS	Civilian Radioactive Waste Management System
DBE	Design Basis Event
DOE	U. S. Department of Energy
FR	Federal Register
HEPA	High Efficiency Particulate Air
HVAC	Heating, Ventilation and Air Conditioning
M&O	Management and Operating Contractor
MGR	Monitored Geologic Repository
NLP	Nevada Line Procedure
NRC	U. S. Nuclear Regulatory Commission
QA	Quality Assurance
QAP	Quality Administrative Procedure
QARD	Quality Assurance Requirements and Description
QL	Quality Level
SDD	System Description Document
SSCs	Structures, Systems, and Components
TBD	To Be Determined
TBV	To Be Verified
TEDE	Total Effective Dose Equivalent
WP	Waste Package
YAP	YMP Administrative Procedure
YMP	Yucca Mountain Site Characterization Project

CRWMS/M&O	Importance to Safety or Waste Isolation Evaluation Pre-Screening Checklist
-----------	---

Page: 1 Of: 1

1. Classification Analysis I.D.:	2. SDD/SSC Evaluated:
3. Description of SDD/SSC (or reference):	

4.		PS1. Is the item directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled?
		a. Confinement or containment
		b. Criticality control
		c. Shielding
		d. Heat transfer
		e. Structural integrity
		f. Operations support necessary for waste handling safety (refer to Quality Level 3 checklists in Attachments II, III, or IV for guidance)
5.		PS2. Is the item directly or indirectly relied upon to provide an Important to Waste Isolation function?
6.		Do the answers to Blocks 4 and 5 indicate the need for an Importance to Safety evaluation?

This image shows a single sheet of white paper with horizontal blue or grey ruling lines. The lines are evenly spaced and run across the width of the page. There is no handwriting or other markings on the paper.

Attachment II MGR Classification Checklists

CRWMS/M&O

Importance to Safety or Waste Isolation Evaluation for MGR

QA: L

Page: 1 Of: 4

Complete only applicable items.

1. Classification Analysis I.D.:	2. SDD/SSC Evaluated:
3. Description of SDD/SSC (or reference):	

MGR Quality Level 1 Checklist

Yes No

	Preclosure Phase:	
4.		1.1. Can failure of the item directly result in loss of waste package containment or criticality control for the spent nuclear fuel, high-level wastes, or other radioactive materials received for emplacement at the MGR?
		1.2. Is the item required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 100 mrem Total Effective Dose Equivalent (TEDE), per event, to any member of the public located on or beyond the site boundary [10 CFR 63.111(b)(1) and 20.1301(a)(1)]? Category 1 DBE "per event" limits are interpreted as the sum of the normal operating dose and anticipated operational occurrences plus the consequences from any single additional low frequency Category 1 DBE. This sum is stated on an annual basis and consistent with 10 CFR 63.111(a) or 10 CFR 20.
		1.3. Is the item required to prevent or mitigate a Category 2 DBE that could result in offsite doses greater than or equal to 5 rem TEDE, 50 rem combined deep dose equivalent and committed dose equivalent to any individual organ or tissue (other than the lens of the eye), 15 rem dose equivalent to the lens of the eye, or 50 rem shallow dose equivalent to the skin, per event [10 CFR 63.111(b)(2)] to any individual located on or beyond any point on the boundary of the site?
5.		Postclosure Phase: 1.4. Does the item perform a waste isolation function that is required to meet the performance objectives in 10 CFR 63.113(b) by: a. forming part of the natural barriers or an engineered barrier system required by 10 CFR 63.113(a)? b. being directly credited in the performance assessments required by 10 CFR 63.113(c) and 10 CFR 63.113(d) to demonstrate the ability of the geologic repository to limit expected annual dose to the average member of the critical group to less than 25 mrem TEDE at any time during the first 10,000 years after permanent closure?
6.		Do the answers to Blocks 4 and 5 qualify the item as a Quality Level 1 item?
7. Comments/Justification: 		

Attachment II MGR Classification Checklists

CRWMS/M&O

Importance to Safety or Waste Isolation Evaluation
for MGR

Complete only applicable items.

QA: L

Page: 2 Of: 4

MGR Quality Level 2 Checklist

Yes	No	
8.		<p>Preclosure Phase:</p> <p>2.1. Does the item function to provide control and management (i.e., collection and/or confinement) of site-generated liquid, gaseous, or solid low-level or mixed radioactive waste?</p> <p>NOTE: Systems with trace concentration of radionuclides, the failure of which could result in offsite doses less than 0.25 mrem per year, are not considered to perform radioactive waste management or control functions for the purpose of this quality level determination.</p>
		2.2. Does the item provide fire detection, fire suppression, or otherwise protect the important-to-radiological safety or waste isolation functions of Quality Level 1 SSCs from the hazards of a fire?
		2.3. As a result of a DBE, could consequential failure of the item, which is not intended to perform a Quality Level 1 radiological safety function, prevent Quality Level 1 SSCs from performing their intended radiological safety function?
		2.4. Is the item required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 25 mrem TEDE, per event, to any member of the public located on or beyond the site boundary [10 CFR 63.111(a) and 10 CFR 20.1301(a)(1)]? Category 1 DBE "per event" limits are interpreted as the sum of the normal operating dose and anticipated operational occurrences plus the consequences from any single additional low frequency Category 1 DBE. This sum is stated on an annual basis and consistent with 10 CFR 63.111(a) or 10 CFR 20.
		2.5. Is the item, in conjunction with an additional item or administrative control (i.e., indirect impact), required to prevent or mitigate a Category 1 DBE that could result in offsite doses greater than or equal to 100 mrem TEDE, per event, to any member of the public located on or beyond the site boundary? Category 1 DBE "per event" limits are interpreted as the sum of the normal operating dose and anticipated operational occurrences plus the consequences from any single additional low frequency Category 1 DBE. This sum is stated on an annual basis and consistent with 10 CFR 63.111(a) or 10 CFR 20.
		2.6. Is the item, in conjunction with an additional item or administrative control (i.e., indirect impact), required to prevent or mitigate a Category 2 DBE that could result in offsite doses greater than or equal to 5 rem TEDE, 50 rem combined deep dose equivalent and committed dose equivalent to any individual organ or tissue (other than the lens of the eye), 15 rem dose equivalent to the lens of the eye, or 50 rem shallow dose equivalent to the skin, per event, to any individual located on or beyond any point on the boundary of the site?
9.		<p>Postclosure Phase:</p> <p>2.7. As a result of a DBE, could consequential failure of the item, which is not intended to perform a Quality Level 1 waste isolation function, result in:</p> <p>a. the inability of Quality Level 1 engineered barriers to perform their intended long-term waste isolation function in the postclosure phase?</p>
		b. long-term changes to the hydrological characteristics of natural barriers by creating significant ponding or the possibility of drainage into the postclosure underground?
		c. the introduction of fluids or other materials that could adversely affect the long-term geo-mechanical characteristics of natural barriers in the postclosure phase?
		d. compromising the ability of the natural barriers to isolate waste in the postclosure phase?
10.		Do the answers to Blocks 8 and 9 qualify the item as a Quality Level 2 item?

Attachment II MGR Classification Checklists

CRWMS/M&O

Importance to Safety or Waste Isolation Evaluation for MGR

Complete only applicable items.

QA: L

Page: 4 Of: 4

MGR Quality Level 3 Checklist

Yes No

[illegible]

Q-List Rationale

SDD / SSC Reference: CRWMS M&O 1998c

TBVs Applicable to this Item: 459, 460

Pre-Screen - Importance to Safety or Waste Isolation Evaluation

	Yes	No	Rationale:
PS1	☐	☒	a. This item is not directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled at the MGR: confinement or containment, criticality control, shielding, heat transfer, structural integrity, or operations support necessary for waste handling safety.
	☐	☒	b.
	☐	☒	c.
	☐	☒	d.
	☐	☒	e.
	☐	☒	f.
PS2	☐	☒	This item is not directly or indirectly relied upon to provide an Important to Waste Isolation function.

Note: If only No answers are given, the item is not subject to QARD requirements. The item is classified as Conventional Quality and an Importance to Safety or Waste Isolation evaluation is not required. Stop Here.

QL1 - Quality Level 1: High Safety or Waste Isolation Significance

	Yes	No	Rationale:
1.1	☐	☐	N/A
1.2	☐	☐	N/A
1.3	☐	☐	N/A
1.4	☐	☐	a. N/A
	☐	☐	b.

QL2 - Quality Level 2: Low Safety or Waste Isolation Significance

	Yes	No	Rationale:
2.1	☐	☐	N/A
2.2	☐	☐	N/A
2.3	☐	☐	N/A

Q-List Rationale

2.4	☐	☐	N/A
2.5	☐	☐	N/A
2.6	☒	☐	N/A
2.7	☒	☒	N/A
	☒	☐	a.
	☐	☐	b.
	☐	☐	c.
	☐	☐	d.

QL3 - Quality Level 3: Minor Safety Significance or Occupational Exposure Significance

	Yes	No	Rationale:
3.1	☐	☐	N/A
3.2	☒	☒	N/A
3.3	☐	☐	N/A
3.4	☐	☐	N/A
3.5	☐	☐	N/A
3.6	☐	☐	N/A

Q-List Rationale

SDD / SSC Reference: CRWMS M&O 1998c

TBVs Applicable to this Item: 459, 460

Pre-Screen - Importance to Safety or Waste Isolation Evaluation

	Yes	No	Rationale:
PS1	☐	☒	This item is not directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled at the MGR: confinement or containment, criticality control, shielding, heat transfer, structural integrity, or operations support necessary for waste handling safety.
	☐	☒	
	☐	☒	
	☐	☒	
	☐	☒	
	☐	☒	
PS2	☐	☒	This item is not directly or indirectly relied upon to provide an Important to Waste Isolation function.

Note: If only No answers are given, the item is not subject to QARD requirements. The item is classified as Conventional Quality and an Importance to Safety or Waste Isolation evaluation is not required. Stop Here.

QL1 - Quality Level 1: High Safety or Waste Isolation Significance

	Yes	No	Rationale:
1.1	☐	☐	N/A
1.2	☐	☐	N/A
1.3	☐	☐	N/A
1.4	☐	☐	N/A
	☐	☐	

QL2 - Quality Level 2: Low Safety or Waste Isolation Significance

	Yes	No	Rationale:
2.1	☐	☐	N/A
2.2	☐	☐	N/A
2.3	☐	☐	N/A

Q-List Rationale

2.4	☐	☐	N/A
2.5	☐	☐	N/A
2.6	☐	☐	N/A
2.7	☐	☐	a. N/A
	☐	☐	b.
	☐	☐	c.
	☐	☐	d.

QL3 - Quality Level 3: Minor Safety Significance or Occupational Exposure Significance

	Yes	No	Rationale:
3.1	☐	☐	N/A
3.2	☐	☐	N/A
3.3	☐	☐	N/A
3.4	☒	☐	N/A
3.5	☐	☐	N/A
3.6	☐	☐	N/A

Q-List Rationale

SDD / SSC Reference: **CRWMS M&O 1998c**

TBVs Applicable to this Item: **457**

Pre-Screen - Importance to Safety or Waste Isolation Evaluation

	Yes	No	Rationale:
PS1	☐	☒	a. This item is not directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled at the MGR: confinement or containment, criticality control, shielding, heat transfer, structural integrity, or operations support necessary for waste handling safety.
	☐	☒	b.
	☐	☒	c.
	☐	☒	d.
	☐	☒	e.
	☐	☒	f.
PS2	☐	☒	This item is not directly or indirectly relied upon to provide an Important to Waste Isolation function.

Note: If only No answers are given, the item is not subject to QARD requirements. The item is classified as Conventional Quality and an Importance to Safety or Waste Isolation evaluation is not required. Stop Here.

QL1 - Quality Level 1: High Safety or Waste Isolation Significance

	Yes	No	Rationale:
1.1	☐	☐	N/A
1.2	☐	☐	N/A
1.3	☐	☐	N/A
1.4	☐	☒	a. N/A
	☐	☐	b.

QL2 - Quality Level 2: Low Safety or Waste Isolation Significance

	Yes	No	Rationale:
2.1	☐	☐	N/A
2.2	☐	☐	N/A
2.3	☐	☐	N/A

Q-List Rationale

2.4	☐	☐	N/A
2.5	☐	☐	N/A
2.6	☒	☐	N/A
2.7	☐	☐	a. N/A
	☐	☐	b.
	☐	☐	c.
	☐	☐	d.

QL3 - Quality Level 3: Minor Safety Significance or Occupational Exposure Significance

	Yes	No	Rationale:
3.1	☐	☐	N/A
3.2	☐	☐	N/A
3.3	☐	☐	N/A
3.4	☐	☐	N/A
3.5	☐	☐	N/A
3.6	☐	☐	N/A

Q-List Rationale

SDD / SSC Reference: **CRWMS M&O 1998c**

TBVs Applicable to this Item: **459, 460**

Pre-Screen - Importance to Safety or Waste Isolation Evaluation

	Yes	No	Rationale:
PS1	☐	☒	a. This item is not directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled at the MGR: confinement or containment, criticality control, shielding, heat transfer, structural integrity, or operations support necessary for waste handling safety.
	☐	☒	b.
	☐	☒	c.
	☐	☒	d.
	☐	☒	e.
	☐	☒	f.
PS2	☐	☒	This item is not directly or indirectly relied upon to provide an Important to Waste Isolation function.

Note: If only No answers are given, the item is not subject to QARD requirements. The item is classified as Conventional Quality and an Importance to Safety or Waste Isolation evaluation is not required. Stop Here.

QL1 - Quality Level 1: High Safety or Waste Isolation Significance

	Yes	No	Rationale:
1.1	☐	☐	N/A
1.2	☐	☐	N/A
1.3	☐	☐	N/A
1.4	☐	☐	a. N/A
	☐	☐	b.

QL2 - Quality Level 2: Low Safety or Waste Isolation Significance

	Yes	No	Rationale:
2.1	☐	☐	N/A
2.2	☐	☐	N/A
2.3	☐	☐	N/A

Q-List Rationale

2.4	☐	☐	N/A
2.5	☒	☐	N/A
2.6	☐	☐	N/A
2.7	☐	☐	a. N/A
	☐	☐	b. N/A
	☐	☐	c. N/A
	☐	☐	d. N/A

QL3 - Quality Level 3: Minor Safety Significance or Occupational Exposure Significance

	Yes	No	Rationale:
3.1	☐	☐	N/A
3.2	☐	☐	N/A
3.3	☐	☐	N/A
3.4	☐	☐	N/A
3.5	☐	☐	N/A
3.6	☐	☐	N/A

Q-List Rationale

SDD / SSC Reference: CRWMS M&O 1998c

TBVs Applicable to this Item: 459

Pre-Screen - Importance to Safety or Waste Isolation Evaluation

	Yes	No	Rationale:
PS1	☐	☒	a. This item is not directly or indirectly relied upon to provide one of the following Important to Safety functions for radioactive wastes received or handled at the MGR: confinement or containment, criticality control, shielding, heat transfer, structural integrity, or operations support necessary for waste handling safety.
	☐	☒	b.
	☐	☒	c.
	☐	☒	d.
	☐	☒	e.
	☐	☒	f.
PS2	☐	☒	This item is not directly or indirectly relied upon to provide an Important to Waste Isolation function.

Note: If only No answers are given, the item is not subject to QARD requirements. The item is classified as Conventional Quality and an Importance to Safety or Waste Isolation evaluation is not required. Stop Here.

QL1 - Quality Level 1: High Safety or Waste Isolation Significance

	Yes	No	Rationale:
1.1	☐	☐	N/A
1.2	☐	☐	N/A
1.3	☐	☐	N/A
1.4	☐	☐	a. N/A
	☐	☐	b.

QL2 - Quality Level 2: Low Safety or Waste Isolation Significance

	Yes	No	Rationale:
2.1	☐	☐	N/A
2.2	☐	☐	N/A
2.3	☐	☐	N/A

Q-List Rationale

2.4	☐	☐	N/A
2.5	☐	☐	N/A
2.6	☐	☐	N/A
2.7	☐	☐	a. N/A
	☐	☐	b.
	☐	☐	c.
	☐	☐	d.

QL3 - Quality Level 3: Minor Safety Significance or Occupational Exposure Significance

	Yes	No	Rationale:
3.1	☒	☐	N/A
3.2	☐	☐	N/A
3.3	☐	☐	N/A
3.4	☐	☐	N/A
3.5	☐	☐	N/A
3.6	☐	☐	N/A