CRWMS/M&O

Non-Q Design Analysis Cover Sheet

Complete only applicable items.

①

QA: N/A

Page: 1 Of: 25

2. DESIGN ANALYSIS TITLE			
WATER SUPPLY ANALYSIS			
3. DOCUMENT IDENTIFIER (Including Rev. No.)		4. REV. NO.	5. TOTAL PAGES
B00000000-01717-0200-00074 REV 01		01	25
6. TOTAL ATTACHMENTS	7. ATTACHMENT NUMBERS - NO. OF PAGES IN EACH		8. SYSTEM ELEMENT
4	I-4, II-3, III-3, IV-7		MGDS
	Print Name	Signature	Date
9. Originator	<i>for</i> Roy D. Clark	<i>[Signature]</i>	02/06/96
10. Checker	H. Andrew Asgarian	<i>[Signature]</i>	02-06-96
11. Lead Design Engineer	Hector R. Montalvo	<i>[Signature]</i>	02/06/96
12. Department Manager	Gene H. Kimura	<i>[Signature]</i>	2-6-96
13. Remarks			

Design Analysis Revision Record

Complete only applicable items.

①

Page: 2

Of: 24

2. DESIGN ANALYSIS TITLE	
WATER SUPPLY ANALYSIS	
3. DOCUMENT IDENTIFIER (Including Rev. No.)	
B00000000-01717-0200-00074 REV 01	
4. Revision No.	5. Description of Revision
01	The layout of the pad was changed through drawing revisions which required this analysis be changed. The type of material was also changed. This is a major analysis revision with changes throughout. The format of the analysis was changed to conform to QAP-3-9, Rev. 05. Issued for discipline check.

1. PURPOSE

This analysis defines and evaluates the surface water supply system from the existing J-13 well to the North Portal. This system includes the pipe running from J-13 to a proposed Booster Pump Station at the intersection of H Road and the North Portal access road. Contained herein is an analysis of the proposed Booster Pump Station with a brief description of the system that could be installed to the South Portal and the optional shaft. The tanks that supply the water to the North Portal are sized, and the supply system to the North Portal facilities and up to Topopah Spring North Ramp is defined.

2. QUALITY ASSURANCE

The products covered with this analysis are not permanent and there are no quality assurance (QA) controls applicable to this design analysis, as the analysis does not discuss either items classified in accordance with QAP-2-3 or items or activities subject to QA control requirements per Determination of Importance Evaluations (DIEs) BABC00000-01717-2200-00001 or BABBDA000-01717-2200-00001. There are no impacts from the DIEs on this analysis.

3. METHOD

The method used to analyze the system will be to evaluate the existing system of pumps at J-13 and determine whether they are adequate for the needs of the North Portal. Pipe sizes and location shall be based on anticipated system demands for the North Portal pad. The South Portal and the optional shaft will not be analyzed due to the lack of information at this time.

4. DESIGN INPUTS

4.1 DESIGN PARAMETERS

- 4.1.1 Potable water distribution system mains shall be sized based on the greatest demand to be satisfied. Water velocity shall be minimized to prevent water hammer. Potable water distribution systems shall be designed to deliver the peak domestic flow of 2.50 times the average daily demand, plus any special demands, at a minimum residual pressure of 30 pounds per square inch (psi) at ground elevation (or higher if special conditions require). (Exploratory Studies Facility [ESF] Basis for Design [BFD] BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.1)
- 4.1.2 Water mains shall be designed to have a minimum pressure rating of 150 psi. Water distribution systems shall be designed to maintain a normal operating pressure range of 40 psi to 100 psi (at ground level) in distribution mains and building service lines. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.2)

- 4.1.3 Each fire hydrant within the distribution system shall be designed to deliver 1,000 gallons per minute (gpm) at a residual pressure of not less than 10 psi. Fire hydrant branches (from main to hydrant) shall be not less than 6 inches in diameter and no longer than 300 feet. A gate valve shall be installed within each fire hydrant branch to facilitate maintenance. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.3)
- 4.1.4 Fire hydrants shall be installed at a maximum spacing of 400 feet. Fire hydrants shall be located no more than 300 feet from the buildings to be protected. Each building shall be protected by a minimum of two fire hydrants. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.6)
- 4.1.5 The potable water system for the ESF North Portal shall be designed for a maximum daily occupancy of 400 people with a consumption rate of 50 gallons per capita per day. A chlorination system shall be provided to treat potable water as necessary to meet safe drinking water standards. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.10)
- 4.1.6 Design Analysis ST-ME-001 Underground Water Distribution System; 700 gpm was the estimated underground fire flow; 80 psi static pressure was required at the North Portal.
- 4.1.7 The elevation of the Booster Pump Station is 3,712 feet above mean sea level (MSL), based on Package 1A drawing [Yucca Mountain Site Characterization Project] YMP-025-1-CIVL-GP103.
- 4.1.8 The elevation of the North Portal water storage tank pad is 3,864 feet above MSL, based on Package 1A drawing YMP-025-1-CIVL-PR126.
- 4.1.9 The elevation of the North Portal is 3,682 feet above MSL, based on Package 1A drawing YMP-025-1-CIVL-GP101.
- 4.1.10 The length of pipe from J-13 to the Booster Pump Station is 20,068 feet, based on Package 1A drawings YMP-025-1-CIVL-PR117 through PR124.
- 4.1.11 The length of pipe from the Booster Pump Station to the North Portal tank site is 2,568 feet, based on Package 1A drawings YMP-025-1-CIVL-PR124, PR125, and PR126.
- 4.1.12 The length of pipe from the North Portal tank site to the North Portal is 1,405 feet, based on Package 1A drawing YMP-025-1-CIVL-PL140.
- 4.1.13 Sprinkler demand at the Electrical Switchgear Building is 1,206 gpm, based on the Raytheon Services Nevada sprinkler design calculation of Mechanical Analysis ST-ME-205.

4.2 CRITERIA

- 4.2.1 Use of pressure relief and surge relief valves shall be considered as necessary to preclude system damage from water hammer. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.4)
- 4.2.2 Gate valves shall be installed at maximum intervals of 5,000 feet on long supply lines and at maximum intervals of 1,200 feet on main distribution loops, feeders, and all primary branches connected to these lines. Gate valves shall also be installed at selected points throughout the distribution system to provide system control over each service area. At intersections of distribution mains, one less gate valve than the total number of intersecting mains shall be provided. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.5)
- 4.2.3 Air release and vacuum valves shall be installed at high points within the distribution system and in long supply lines. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.7)
- 4.2.4 Distribution system mains shall be installed at a minimum depth of cover of 2.5 feet. Additional cover shall be provided to prevent freezing in cold climates, at roadway crossings in high-traffic areas, and at railroad crossings. The system shall be looped on the pad to provide redundant and backup water source to each building. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.8)
- 4.2.5 Building service lines shall be a minimum of 1 inch in diameter. Service lines less than 2 inches in diameter shall be connected to the distribution main by a corporation stop and a copper gooseneck, with a service stop below frostline. Service lines larger than 2 inches in diameter shall be connected to the distribution main by a rigid connection and a gate valve located below the frostline. The point of interface with each building will be 5 feet from the exterior wall of the building. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.9)
- 4.2.6 Pipe sizing of the water systems shall be based on Hazen-Williams flow formula, equation 39, American Water Works Association (AWWA) Manual M23. The pipe shall be sized to maintain velocities that will reduce water hammer. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.11)
- 4.2.7 Two independent water systems shall be provided in the North Portal Pad (i.e., one system for the potable water and a separate system for the non-potable water). Each system shall be labeled independently. A different type or color of material for each system shall be used in the design. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.12)
- 4.2.8 The route of the water line shall be adequately marked with plastic warning tape buried above the pipe to minimize the possibility of damage from future

construction activities. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.16)

4.2.9 The fire protection and construction water system shall be sized to meet the greatest demand to be specified. Water velocity shall be minimized to prevent water hammer. This system shall also supply construction water to the underground for construction operation and testing. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.19)

4.2.10 Valves shall be provided at the portal entrance to prevent excessive water flow into the ESF in the event of a pipe break. (ESF BFD BAB000000-01717-6300-00002 Section 7.2.4.2, IV.A.21)

4.3 ASSUMPTIONS

4.3.1 The design information contained on the Holmes & Narver, Inc. "Exploratory Shaft" drawing JS-025-055-C44 (check dated September 23, 1986) is correct; the elevation of J-13 is 3,316 feet MSL. This assumption requires confirmation and is used in Section 7.1.1 and 7.2.2.

4.3.2 The total dynamic head (static head and friction loss) from the Booster Pump Station to the optional shaft is not more than 600 feet. This assumption requires confirmation and is used in Section 7.2.1, and is based on, assumed locations, pipe material, pipe size and length of pipe.

4.3.3 The equivalent pipe length shall be increased by 5 percent to account for all appurtenances (valves, fittings, meters, etc.) on the line. This assumption is based on engineering and construction practices, and on the fact that there are no other requirements for establishing the equivalent pipe length. This assumption is used in Section 7 of this analysis.

4.3.4 The horizontal length from the Booster Pump Station to the South Portal is 8,700 feet (based on an assumed location), and the horizontal length from the Booster Pump Station to the optional shaft is 9,000 feet (based on an assumed location). This assumption requires confirmation and is used in Section 7.2.3.

4.3.5 Elevation of the South Portal pad is 3,930 feet (based on an assumed location), with a 24-foot tall tank (based on average height of water tanks and 8' tank steel sections). This assumption requires confirmation and is used in Section 7.2.3.

4.3.6 Fires on the surface or underground will cause construction to stop, and no construction water will be used. There will not be a surface and an underground fire at the same time. There will be only one fire on the surface at one time. These assumptions are used throughout Section 7 of this analysis. This is based on normal fire protection engineering practice, and on the fact that there are no requirements to protect against two simultaneous fires.

- 4.3.7** The surface fire protection system is considered "stand-alone"; that is, there are no external pumps or trucks attached to the system to help in the event of a fire. This assumption is used throughout Section 7 of this analysis. This is based on normal fire protection engineering practice, and on the fact that fire protection system design is based on gravity flow.
- 4.3.8** A maximum of 400 people will use the North Portal daily (based on project population). This number shall be used to size the domestic water supply system. This assumption is used in Section 7.4.3 (see Reference 5.8).
- 4.3.9** The Main Warehouse has the ability to store Class III storage with the possibility of stacking the stored material 16 feet high, with 8-foot aisles and double row racks, and uses 286-degree sprinkler heads producing a density of 0.21 gpm/square foot over a 3,000-square-foot area. This assumption is used in Section 7.4.1, and is based on the criteria of NFPA 231C and the anticipated use of the warehouse.
- 4.3.10** Storage of 2.5 days is required for domestic service (based on an engineering assumption, and on the fact that there are no other storage requirements). This assumption is used in Subsection 7.4.3.
- 4.3.11** The water temperature shall remain below 73.4 degrees F (based on an engineering assumption, and on the fact that there are no other water temperature requirements). This assumption is used throughout Section 7 of this analysis.
- 4.3.12** Minimum fire flow into buildings shall be 1,000 gpm unless otherwise noted (based on an engineering assumption for requirements of sprinkler system). This assumption is used in subsection 7.5.3.4.
- 4.3.13** For building calculation purposes, it is assumed that the firewater line is out of service as described within this analysis, based on the fact that there are no other requirements.

4.4 CODES AND STANDARDS

4.4.1 U.S. Department of Energy (DOE)

DOE Order 6430.1A
April 6, 1989

General Design Criteria

4.4.2 National Fire Protection Association (NFPA)

NFPA 231C, 1995 Edition

Standard for Rack Storage of Materials

NFPA 22, 1993 Edition

Standard for Water Tanks for Private Fire Protection

NFPA 24, 1992 Edition

Standard for the Installation of Private Fire
Service Mains and Their Appurtenances**4.4.3 Code of Federal Regulations (CFR)**

10 CFR 60

Part 60, Disposal of High-Level Radioactive
Wastes in Geologic Repositories**5. REFERENCE**

- 5.1 Pump Data - "Exploratory Shaft" as-built drawing No. JS-025-055-C44, (check dated September 26, 1983).
- 5.2 Polyvinyl Chloride (PVC) Pipe Design and Installation; American Water Works Association (AWWA) Manual M23, 1980.
- 5.3 Sandia National Laboratories letter from Laurence S. Costin, to J. Russell Dyer of the Department of Energy, dated July 24, 1992.
- 5.4 Exploratory Studies Facility Design Requirements (ESFDR), Document No. YMP/CM-0019: Appendix I, Performance Assessment Analyses, Rev.1/ICN-3.
- 5.5 DIE ESF Water Supply System, BABC00000-01717-2200-00001, Rev 00.
- 5.6 DIE ESF Water Distribution System, BABBDA000-01717-2200-00001, Rev 00.
- 5.7 Raytheon Services Nevada Design Analysis Number ST-ME-205: Building 7007 Electrical Switchgear Room Fire Protection System Calculation.
- 5.8 Raytheon Services Nevada Review Comment Number PO-MR3-ESFN-1A-97, Document Title ESF Package 1A Number ST-CI-20 Item Number 97 from James Gardiner and signed by Bruce T. Stanley, which establishes the number of people to use the site.
- 5.9 ESF Package 1A Booster Pump Station Grading Plan, YMP-025-1-CIVL-GP103, Rev 3.
- 5.10 ESF Package 1A Raw Water Supply Line Plan and Profile, YMP-025-1-CIVL-PR117, Rev 1.
- 5.11 ESF Package 1A Raw Water Supply Line Plan and Profile, YMP-025-1-CIVL-PR118, Rev 1.
- 5.12 ESF Package 1A Raw Water Supply Line Plan and Profile, YMP-025-1-CIVL-PR119, Rev 1.
- 5.13 ESF Package 1A Raw Water Supply Line Plan and Profile, YMP-025-1-CIVL-PR120, Rev 1.
- 5.14 ESF Package 1A Raw Water Supply Line Plan and Profile, YMP-025-1-CIVL-PR121, Rev 1.

- 5.15 ESF Package 1A Raw Water Supply Line Plan and Profile, YMP-025-1-CIVL-PR122, Rev 1.
- 5.16 ESF Package 1A Raw Water Supply Line Plan and Profile, YMP-025-1-CIVL-PR123, Rev 1.
- 5.17 ESF Package 1A Raw Water Supply Line Plan and Profile, YMP-025-1-CIVL-PR124, Rev 2.
- 5.18 ESF Package 1A Water Storage Tank Access Road Waterline, Plan and Profile, YMP-025-1-CIVL-PR125, Rev 2.
- 5.19 ESF Package 1A Water Storage Tank Access Road Waterline, Plan and Profile, YMP-025-1-CIVL-PR126, Rev 2.
- 5.20 ESF Package 1A Water Supply Plan YMP-025-1-CIVL-PL140, Rev 00.
- 5.21 ESF BFD BAB000000-01717-6300-000002 REV 05.
- 5.22 Raytheon Services Nevada Design Analysis Number ST-ME-001, Rev 0: Underground Water Distribution System.
- 5.23 ESF Package 1A Sheet 1 Grading Plan, YMP-025-1-CIVL-GP101, Rev 4.
- 5.24 Steel Pipe - A Guide for Design and Installation, AWWA Manual M11, Third Edition.
- 5.25 Yucca Mountain Site Characterization Project; Tracers, Fluids, and Materials (TFM) Management Plan, YMP/91-23, Rev 2.

6. USE OF COMPUTER SOFTWARE

Not used.

7. DESIGN ANALYSIS

7.1 J-13 PUMP TO BOOSTER PUMP STATION

7.1.1 General Description

The pump at J-13 has the ability to deliver 150 gpm against 545 feet of head (Reference 5.1).

Distance from J-13 to the intersection of H Road with the proposed North Portal access road (the location of the proposed Booster Pump Station) is 20,068 feet.

Equivalent length

--> $20,068 \times 1.05$ (additional 5 percent for fittings) = 21,071 feet

Elevation Differential

J-13 well site elevation: 3,316 feet MSL
 Booster pump elevation: 3,712 feet MSL
 Difference in elevation: 396 feet

Tank height = 18 feet

--> total vertical elevation difference = 414 feet

Pipe sizing is based on Hazen-Williams flow formula, which is equation 39 in AWWA Manual M23. The coefficients of friction are described in M23. Loss of head and pressure drop can be calculated from the Hazen-Williams theory. AWWA M23 contains charts showing head loss for various types and classes of pipe. These charts are included in Attachment I.

Input data

--> 150 gpm with a total pipe length of 21,071 feet which will have to be pumped against. Start with PVC C900, Diameter Ratio (DR) 14, Class 200 PVC

with 6-inch pipe loss of head = 0.194 feet per 100 feet

--> $210.7 \times 0.194 = 40.9$ feet,

velocity = 1.7 feet per second (fps)

with 8-inch pipe loss of head = 0.052 feet per 100 feet

--> $210.7 \times 0.052 = 11.0$ feet,

velocity = 1.0 feet per second (fps)

Use an 8-inch line, as a 6-inch would produce excessive head loss.

Total dynamic head

Static Head:	414 feet
Friction head loss:	11 feet
Total =	425 feet

Pump at J-13 has the ability to pump against 545 feet, $545 - 425 = 120$ feet of pressure available.

Pressure rating and wall thickness of the pipe are based on the hydrostatic internal pressure and surge pressure that shall act on the pipe. The design stress as defined by equation 1 in AWWA Manual M23 is as follows:

Design Stress = hydrostatic design basis $\div$ factor of safety

Hydrostatic pressure = $425 \text{ feet} \times 62.4 \text{ pounds/cubic feet} \times 1 \text{ square foot}/144 \text{ square inch} \Rightarrow 185 \text{ psi}$

Using Table 8 of M23, DR 14, which has a pressure class of 200 psi, is required for this working pressure. There is 40 psi additional surge allowance figured into the pipe as long as the velocity is below 2 fps.

7.1.2 Emergency Pumping Criteria

In the event of a fire that depletes the fire-fighting water from the tank, NFPA 22 Section 11-4.2, requires the tank to be refilled within eight hours. The refilling would be accomplished by using both pumps at J-13 to pump together for eight hours. The head loss in this 8-inch line should also be addressed to ensure that losses are not excessive.

Pumping of 300 gpm is required through an 8-inch PVC line for 21,071 feet. Table 17 of AWWA M23 8-inch DR 14 Class 200 Loss of Head-->0.187 feet/100 feet, which gives 39.4 feet of loss. With static head of 414 feet and friction head of 39 feet, the total head is 453 feet which is within the capacity of the existing pumps and proposed 8-inch PVC waterline. The pressure remains below critical as the velocity is below 2 fps.

453 feet of head = 196 psi; this is within the working pressure of this type of pipe.

7.2 PUMP STATION

7.2.1 General Description

The Booster Pump Station will be designed for the North Portal and the future development of the South Portal and an optional shaft. It is uncertain where or how "high up" the hill this optional shaft will be located. It is therefore assumed that the total dynamic head (static head + friction head loss) between the Booster Pump Station and the optional shaft or the Booster Pump Station and an additional booster pump shall not exceed 600 feet. These assumptions are made at this time to size the auxiliary pump at the Booster Pump Station. An auxiliary system is needed in the event the main pump goes out of service. Only one auxiliary pump shall be used for the three main pumps. The pump to the North Portal shall be sized to meet the needs outlined below. Pump curves are provided in Attachment II for two pumps that could meet the needs of this site.

Horizontal distance to storage tanks from the Booster Pump Station to the North Portal tank site is 2,568 feet.

Equivalent length = $2,568 \times 1.05$ (5 percent) = 2,696 feet

Tank pad elevation:	3,864 feet MSL
Booster station elevation:	3,712 feet MSL
Difference in elevation:	152 feet

Tank height: 24 feet
Total difference in elevation: 176 feet

7.2.2 Fire Protection

NFPA 22 Section 11-4.2 requires the fire protection tank to be filled in eight hours. The filling can be accomplished using the two proposed pumps at J-13 pumping at 100 percent capacity. This activity would also require the two pumps at J-13 (of comparable capacity) to be running simultaneously.

Total fire demand

--> 144,000 gallons, see Section 7.4.1

2 pumps pumping at 150 gpm

--> 300 gpm

time to fill

--> $144,000 \div 300 = 480$ minutes = 8 hours

Pump rate of 150 gpm with total length of 2,696 feet using a 6-inch pipe, head loss 0.701 feet/100 feet

--> 18.9 feet

use 6-inch line minimum for supply purposes.

To account for undefined future development that may require water from this line, an 8-inch line will be installed. The cost difference between the 6-inch and 8-inch PVC waterline is minimal; therefore, an 8-inch line will be specified. The lines that will be installed in the Booster Pump Station for future sites will also be sized based upon potential future development.

Total dynamic head

Static head: 176 feet

Friction head loss (feet): 19 feet

Total = 195 feet

Use a 1,750 revolution per minute (rpm) 2TU12 Peerless pump (as an example of a pump that may be used, pump curves are found in Attachment II) with a 15-horsepower motor and an 11-inch impeller at 61 percent efficiency.

7.2.3 Emergency Condition

Tank water replacement demand

--> 300 gpm

Length of pipe

--> 2,696 feet

Head loss in 8-inch PVC pipe

--> 0.187 feet/100 feet of pipe

--> 5.0 feet of loss

It is assumed that pump 2 in the Booster Pump Station will require a total dynamic head of 600 feet and a flow of 150 gpm. Therefore, a Peerless 2TU10 3,500 rpm pump (for example) with a 50-horsepower motor as a backup pump for all three main pumps (1 present construction, 2 future) will be used.

Pipe sizing to the South Portal and shaft. Distance from the Booster Pump Station to the South Portal is 8,700 feet. Elevation of high water level in tank:

Elevation of pad:	3,930 feet MSL (assumed)
Tank height:	+ 24 feet
Water height:	3,954 feet MSL

Static head:	Elevation of tank:	3,954 feet MSL (assumed)
Elevation of Booster Pump Station:	3,712 feet MSL	
Difference:	242 feet	

Friction Head loss:
 8-inch pipe
 --> 0.052 feet/100 feet
 Pipe length 8,700 + 5 percent
 ---> 9,140 feet
 Friction loss
 --> 4.8 feet

Total dynamic head: 242 feet + 5 feet = 247 feet

This is not unreasonable with a similar pump as used on the North Portal; therefore, use an 8-inch PVC line to the South Portal, based on the same criteria established for the North Portal waterline.

Distance from Booster Pump Station to shaft: 9,000 feet + 5 percent
 --> 9,450 feet

Total dynamic head available with auxiliary booster pump is 600 feet.

Total head loss for the 9,450 feet of pipe: 8-inch pipe
 --> 0.46 feet/1,000 feet
 Head loss = 4.3 feet

For the reasons given earlier, an 8-inch line will be used for the future waterlines.

7.3 WATERLINE FROM BOOSTER PUMP STATION TO NORTH PORTAL STORAGE TANKS

The demand requirement is for 150 gpm to fill storage tanks, plus 300 gpm for emergency filling requirements. See Subsection 7.2.2 for sizing of the 8-inch line.

7.4 NORTH PORTAL WATER STORAGE TANKS

Water tanks are required to store water at the North Portal. The tanks will be sufficiently sized to store both fire protection and potable water. A packaged chlorination system shall be installed to provide disinfection for the potable water. No chlorine shall be permitted in the fire protection water as it may interfere with the tracers and testing for which the construction water will be used.

7.4.1 Fire Protection Tank

The size of the fire protection tank shall be based on the need to extinguish an assumed fire for the maximum demand on the pad. The Main Warehouse has been identified as the probable maximum demand and has the ability to store Class III storage with the possibility of stacking the stored items 16 feet high, with 8-foot aisles and double row racks. Using 286-degree sprinkler heads with a density of 0.21 gpm/square foot @ 3,000 square foot area (based on NFPA 231C, Figure 6-11.1(c) curve E, see assumption 4.3.9) is required. Water supply duration of 120 minutes is required (based on NFPA 231C paragraph 5-10). DOE Order 6430.1A, Section 1530-3.3.2, requires a minimum hose stream volume of 500 gpm.

3,000 square feet x 0.21 gpm/square feet = 630 gpm

10 percent hydraulic increase factor = 63 gpm

Hose stream allowance = 500 gpm

Maximum demand = 1,193 gpm: Use

--> 1,200 gpm

NFPA 231C requires 120 minutes for Types I, II, and III commodities

1,200 gpm x 120 minutes = 144,000 gallons

7.4.2 Construction Water

Title I construction water estimates indicate 35 gpm demand for construction water for a 24-hour period.

35 gpm for 24 hours

--> 50,400 gallons

Total Demand

--> 144,000 gallons + 50,400 gallons = 194,400 gallons

Use 200,000-gallon tank

7.4.3 Domestic Water Storage Tank

A separate tank is required for this system to provide contact time for chlorination. The design assumption is that 400 people per day (24-hour day) will use the surface facility (Reference Assumption 4.3.8).

Individual usage

Lavatories:	15.0 gallons
Shower:	25.0 gallons
Sink:	6.0 gallons
Drinking water:	2.5 gallons
Total	48.5 gallons; therefore, use >50 gallons

Total usage requires 2.5 days of storage (reference Assumption 4.3.10):
 $50 \text{ gallons} \times 400 \text{ people/day} \times 2.5 \text{ days} = 50,000 \text{ gallons}$

7.4.4 Type and Location of Water Tanks

To achieve the pressure required to fight fires, tanks must be located above areas they are designed to protect. This placement can be done in one of two ways: elevate the tank and locate it near the pad; or locate it on high ground. The major difference between these two concepts is construction cost. The following options describe various types of tanks and presents a budgeted cost estimate for each (reference Attachment IV).

Option 1: Ground-mounted tanks (one 200,000- and one 50,000-gallon) based on Seismic Zone 4 and 100 mile/hour winds exclusive of the foundation.
 --->\$80,000 and \$50,000

Option 2: Portal elevated tanks (one 200,000- and one 50,000-gallon) based on the above criteria on the portal. -->\$555,800 and \$319,200

Option 3: A single elevated 250,000-gallon tank constructed on the portal with the bottom of the water at least 187 feet above the portal elevation. The design would be based on the same criteria as that shown in Option 1.
 -->\$1,100,000

Option 4: A single tank for both potable and fire water located on the portal built as a single unit without legs known as a "standpipe" 150 feet high and 43 feet in diameter. This would be designed to the same criteria as above with water from the bottom of the tank to the top. The head would be developed using the height of the standpipe.
 -->\$425,000

Option 5: A single tank similar to Option 4, except this could be located halfway up the hill. This tank would be 100 feet high and 45 feet in diameter.
-->\$350,000

Based on cost, two ground-mounted tanks will be used. These tanks should be located on the south end of Exile Hill. This location will provide the head necessary to meet the pressure requirements and will protect the portal, in that if either of the tanks were to develop a leak, water would not enter the portal.

7.5 FIRE MAIN SIZING FOR THE PAD

7.5.1 Design Criteria

The design of the water distribution piping complies with the requirements of NFPA 24. All material used in the installation of the water distribution system shall be Underwriters Laboratory, Inc. (UL) listed or Factory Mutual (FM) approved.

PVC shall be used for water distribution lines on the pad. This material is used throughout the building industry for its ease of use and handling. To meet the ESFDR requirement of identifying potable and firewater lines so that there is no cross connection, two different pipe colors shall be specified. Pipe color is a function of the manufacturer.

Tank bottom elevation

--> 3,864 feet

Average portal elevation

--> 3,682 feet

Difference in elevation

-->182 feet

Fire protection requirements on the portal are assumed to be greatest at the proposed Main Warehouse:

500 gpm hose stream from the fire hydrants

630 gpm for the Main Warehouse sprinklers

63 gpm for 10 percent hydraulic increase factor

1,200 gpm total with 40 psi residual pressure

DOE Order 6430.1A Section 0266-4 requires each hydrant to be capable of delivering a flow of 1,000 gpm with a residual pressure of not less than 10 psi. This requirement can be met if a pumper truck is attached to the hydrant and 1,000 gpm is withdrawn from the large or pumper nozzle. However, it is assumed that the system will be "stand alone" and no pumping equipment will be used in conjunction with the system. Hydrant demand of 500 gpm and a residual pressure of 40 psi are based on the requirements of DOE Order 6430.1A Section 1530-3.3.2, and 6430.1A Section 0266-4 statement of minimum pressure.

7.5.2 Size Based on Surface Requirements

Start with a 12-inch PVC pipe from the tank to the portal

1,200 gpm with 12-inch pipe

--> head loss = 0.168 feet/100 feet

length of pipe from the tank to the pad is 1,405 feet + 5 percent = 1,475 feet

182 feet of static head less the velocity head loss ($14.75 \times 0.168 = 2.5$)

available pressure at the pad is $182 - 2.5 = 179.5$ feet = 77.8 psi

7.5.3 Fire Protection Layout

System layout is as shown on Sketch 1 of Attachment III. Four conditions shall be analyzed to determine the size and adequacy of the system. The four systems are described in the following sections.

7.5.3.1 Electrical Switchgear Building Fire

The first scenario is if there is a fire at the Electrical Switchgear Building and the main were out of service between Tee#1 and the tee to FH#2. The fire would be fought using FH#1, the building sprinklers, and FH#2. The routing of the water to FH#2 would be the long route around the site.

The length of 10-inch PVC pipe to this point is (in feet):

$12 + 21 + 80 + 96 + 31 + 56 + 80 + 267 + 370 + 10 + 205 + 51 + 20 + 327 + 100 + 170 = 1,896$

5 percent increase for fittings = $1,896 \text{ feet} \times 1.05 = 1,991 \text{ feet}$

The length of 6-inch PVC pipe to FH#2 = 185 feet plus 5 percent = 194 feet

The demand at the Switchgear Building is 746 gpm.

The building must be protected by two hydrants with a hose stream of at least 250 gpm from each hydrant.

Total demand for the building is 1,206 gpm.

Demand at the tee to FH#2 is 1,206 gpm through 1,896 feet of 10-inch PVC pipe (1,991 feet of equivalent length).

Head loss is 0.904 feet/100 feet for 10-inch (using 1,200 gpm from Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at this tee is:
 $179.5 - (19.91 \times 0.904) = 161.5 \text{ feet} \Rightarrow 70 \text{ psi}$

Demand at FH#2 is 250 gpm through 185 feet of 6-inch PVC (194 feet of equivalent length).

Head loss is 0.500 feet/100 feet for 6-inch (Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at this hydrant is:
 $161.5 - (1.94 \times 0.500) = 160.5 \Rightarrow 70 \text{ psi}$ **Okay**

Because the line to FH#1 and the lateral to the building occurs "upstream" of Tee#1, the entire system would have to be out of service. This occurrence is within normal bounds of logic for service interruptions.

7.5.3.2 Warehouse Fire

The second area of concern is if there were a fire in the warehouse and the main were out of service between the tee to FH#3 and Tee#1. The fire would be fought with FH#3, the warehouse sprinklers, and FH#4. The routing of the water to FH#3 would be the long route around the site.

The length of 10-inch PVC pipe TEE#2 is (in feet):

$$12 + 21 + 80 + 96 + 31 + 56 + 80 + 267 + 370 + 10 + 205 = 1,228$$

$$5 \text{ percent increase for fittings} = 1,228 \times 1.05 = 1,289 \text{ feet}$$

Demand at this point is the full 1,700 gpm (1,200 gpm for the building and 500 gpm hydrant demand).

Head loss is 1.737 feet/100 feet for 10-inch (approximated from Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at this tee is:
 $179.5 - (12.28 \times 1.737) = 158.2 \text{ feet}$

There is 20 feet (equivalent is 21 feet) of 10-inch plus 215 feet (equivalent is 226 feet) of 6-inch with 250 gpm flow.

Head loss is 0.049 feet/100 feet for 10-inch (Table 17 in M23 DR 14 pipe) class 200 pipe.

Head loss is 0.500 feet/100 feet for 6-inch (Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at FH#4 is:

$$158.2 - (.21 \times 0.049 + 2.26 \times 0.500) = 157.0 \text{ feet} \Rightarrow 68 \text{ psi } \textbf{Okay}$$

Demand at the tee that supplies water to the warehouse is 1,450 gpm (1,200 gpm building plus 250 gpm hydrant).

Head at TEE#2 is 149.9 feet with 51 feet (equivalent is 54 feet) of 10-inch PVC pipe to the tee that feeds the building with 1,450 gpm flow.

Head loss is 1.287 feet/100 feet for 10-inch (approximated from Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at the tee to the warehouse is:

$$158.2 - (0.54 \times 1.287) = 157.5 \text{ feet}$$

Demand to the warehouse is 1,200 gpm through 57 feet (equivalent 60 feet) of 8-inch PVC pipe is:

Head loss is 2.020 feet/100 feet for 10-inch (using 1,200 gpm from Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at the warehouse is:

$$158.2 - (0.60 \times 2.020) = 157.0 \text{ feet} \Rightarrow 68 \text{ psi } \textbf{Okay}$$

7.5.3.3 Civilian Radioactive Waste Management System Management and Operating (CRWMS M&O) Contractor Trailer Fire

The third scenario addresses the demand at the CRWMS M&O trailer. The longest length of 10-inch PVC pipe supplying water to the trailer is (in feet):

$$12 + 21 + 80 + 96 + 31 + 56 + 80 + 267 + 370 + 10 + 205 + 20 + 205 + 25 + 52 = 1,530$$

$$5 \text{ percent increase for fittings } 1,530 \times 1.05 = 1,607 \text{ feet}$$

Assumed demand at office trailer is 1,500 gpm (1,000 gpm to the trailer and 250 gpm each to two different hydrants).

Head loss is 1.3715 feet/100 feet for 10-inch (using 1,500 gpm from Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at the CRWMS M&O office trailer is

$$179.5 \text{ feet} - (16.07 \times 1.3715) = 157.5 \text{ feet} \Rightarrow 69 \text{ psi } \textbf{Okay}$$

7.5.3.4 Available Pressure at the Change House

The fourth scenario address the available flow into the Change House. The demand for this building is unknown from a building fire protection standpoint; therefore, an assumed value of 1,000 gpm at the building is used for this analysis. The hydrants will not be evaluated separately as they were addressed previously in this analysis. The worst case for this building is if the line were out of service between TEE#3 and TEE#1. The routing of the water for the building would be the long route. Fire will be fought with the closest hydrants.

The length of 10-inch PVC pipe to this point is (in feet):

$$12 + 21 + 80 + 96 + 31 + 56 + 80 + 267 + 370 + 10 + 205 + 51 + 20 + 327 + 100 + 170 + 12 = 1,908$$

$$5 \text{ percent increase for fittings} = 1,908 \times 1.05 = 2,003 \text{ feet}$$

Demand at the TEE#3 is 1,000 gpm through 1,908 feet (2,003 feet of equivalent length) of 10-inch PVC pipe with 1,000 gpm.

Head loss is 0.645 feet/100 feet for 10-inch (Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at TEE#3 is:

$$179.5 - (20.03 \times 0.645) = 166.6 \text{ feet}$$

The length of 6-inch to the Change House is: 58 feet + 70 feet = 128 feet

$$5 \text{ percent increase for fittings} = 128 \text{ feet} \times 1.05 \text{ feet} = 134 \text{ feet}$$

Demand at the building is 1,200 gpm through 128 feet (134 feet of equivalent length) of 6-inch PVC pipe with 1,200 gpm.

Head loss is 6.519 feet/100 feet for 6-inch (Table 17 in M23 DR 14 pipe) class 200 pipe.

Total head at the building is:

$$166.6 - (1.34 \times 6.519) = 157.8 \text{ feet} \Rightarrow 69 \text{ psi } \textbf{Okay}$$

7.5.4 Size Based On Subsurface Requirement

As stated in Design Input 4.1.6, 700 gpm is required at the portal for fire protection underground. This demand does not govern.

7.6 POTABLE WATERLINE SIZE REQUIREMENT

Based on 20,000 gallons per day use, and estimating that half that water could be used in a one-hour period, demand is approximately 150 gpm.

Worst case is if that demand occurred in the Change House and the eastern half of the line were out of service at the same time.

Length of pipe from tank to North Portal edge is 1,405 feet
Elevation difference is 182 feet

Head loss from tank to pad 1,405 feet + 5 percent = 1,475 feet

Head loss through an 8-inch PVC pipe at 150 gpm = 0.058 feet/100 feet of pipe

8-inch PVC pipe

--> $12.29 \times 0.058 = 0.7$ feet of loss

Total head at portal

--> $182 - 0.7 = 181.3$ feet

Length of pipe from 8-inch tee to Change House

8-inch PVC pipe

--> $355 \text{ feet} + 5 \text{ percent} \Rightarrow 373$ feet

Demand at Change House is 150 gpm

Head loss through 8-inch pipe

--> $0.052 \text{ feet}/100 \text{ feet} \Rightarrow 0.3$ feet

Total head $181.3 - 0.3 = 181$ feet

--> 78 psi

Pressure reducing stations required for each building.

7.7 WATER HAMMER

AWWA M11 equation 5-1 states that a "...pressure rise for instantaneous closure is directly proportional to the fluid velocity at cutoff and to the magnitude of the surge wave velocity and it is independent of the length of the conduit." Since this system is buried underground and the tank is open to the atmosphere, this excess pressure can be transmitted into the ground and into the water storage tank. M11 states that if diameter ratio is less than 90 and the system is not complex, studies are not needed.

7.8 ALLOWABLE LEAKAGE

7.8.1 AWWA Manual M23 defines leakage as the quantity of water added to a newly laid pipe to maintain pressure within 5 psi of the specified test pressure. The minimum acceptable leakage rate is defined by the following equation:

$$L = N \times D \times \text{square root of } P \text{ divided by } 7,400$$

L = allowable leakage in gallons per hour
 N = number of joints in the length of pipeline tested
 D = nominal diameter of the pipe in inches
 P = average test pressure during the leakage test in psig

There is 4,965 feet of firewater line: 12-inch, 10-inch, and 8-inch in diameter. For calculation purposes, 10-inch will be used as the nominal pipe size. There are 494 joints from the fittings.

$L = 494 \times 10 \times \text{square root } (200) / 7,400$
 $L = 9.4$ gallons per hour

- 7.8.2** NFPA 24 defines leakage no more than 2 quarts per hour per 100 joints regardless of the pipe size.

leakage = $494 / 100 = 4.94$ use 5
 therefore the allowable leakage is 2.5 gallons per hour of test.

7.9 PERFORMANCE CRITERIA

Based on an analysis done by Sandia National Laboratories dated July 24, 1992, "Infiltration from a potential rupture of the . . . water tanks and from the emergency overflows . . ." will not interfere with the tests on the North Portal or ramp. The report goes on to state leak ". . . detection is a must for identifying the potential for test interference." A meter will be provided at the edge of the pad and at J-13 to monitor leakage.

This issue is also addressed in the ESFDR Appendix I, Analysis 3, wherein it was concluded ". . . that water leakage from . . . the sewage ponds have no effect on the saturation at the repository horizon and will not interfere with experiments conducted in the ESF." Appendix I indicates that waste water ponds should be located at least 700 feet from site characterization activities. At this time, no specific tests have been identified within 700 feet of the waterline routes.

7.10 DIE CRITERIA

- 7.10.1** The DIEs as referenced in Sections 5.7 and 5.8 were not complete at the time Revision 00 of this analysis was complete. These documents are now complete. The following is a combined list of controls (Requirements) found in the DIE.

Requirement 1: The following limits apply to the total use of water for construction, dust control, compaction of engineered fill and structure, facility and improvement operations within the Conceptual Controlled Area Boundary as indicated in the Yucca Mountain Site Characterization Atlas and in accordance with 10 CFR 60.15 (c)(1)

- (1a) Minimize to the extent practical water utilization (including equipment leakage) while maintaining standard construction and engineering practices for surface construction activities at the ESF. Application of such water shall not exceed 2 gal/yd²/day averages over a six-month period (excluding water used to mix concrete or shotcrete).
- (1b) All water utilized for construction, dust control, and other operations on the ESF shall be measured.
- (1c) Weekly records shall be made and provided in accordance with the TFM Management Plan for ESF surface construction and operational water use by specific activity (dust suppression, compaction of engineered fill, form watering, building operations, etc.) for specific structures, facilities or other site improvements to be built and operated in the Conceptual Controlled Area Boundary.
- (1d) Tracers will not be added to construction water for surface use without additional evaluation and with Architect/Engineer (A/E) concurrence.
- (1e) Chlorinated water shall not be used for construction purposes.

Requirement 2: A record shall be made and provided in accordance with the TFM Management Plan of all tracers, fluids, and materials consumed during construction and operation for the ESF North Portal Water Supply System.

Requirement 3: The amount of hydrocarbons (i.e., hydraulic fluid, fuels, oils, etc.) spilled and lost in the construction and operation of the surface ESF shall be minimized in accordance with 10 CFR 60.15(c)(1). Any unrecovered spill material shall be recorded and reported in accordance with the TFM Management Plan.

Requirement 4: The following controls apply to minimize chronic water losses and subsurface infiltration which could potentially occur in the North Portal Water Supply Distribution Systems in accordance with 10 CFR 60.15(c)(1):

- (4a) Water Supply/Distribution System leakage shall be minimized. Combined Water Supply/Distribution System leakage in excess of 2,000 gallons in a one

week period will be identified, recorded, and reported in accordance with TFM management plan.

- (4b) Monthly visual inspection or test shall be conducted to determine water leakage.
- (4c) If combined Water Supply/Distribution System leakage in excess of 2,000 gallons in a one week period occurs then the system shall be taken out of service until such time as the leaks are found and repaired.

Requirement 5: The following controls apply to minimize potential test interference on carbon based testing required for site characterization at the ESF in accordance with 10 CFR 60.140(b):

- (5a) Hydrocarbon material infiltration into the soils or rock at the ESF shall be minimized to the extent practical when using oil-soaked sand beneath water tanks or other similar storage vessels. Design features to implement this requirement may include, for example, the use of impermeable liners, etc.
- (5b) Record and report hydrocarbon quantities applied, the locations used and mitigation measures applied to limit their potential penetration into soils and rock at the ESF in accordance with TFM Management Plan.

Requirement 6: Annual monitoring of the J-13 well water for C1-36 and reporting in accordance with the TFM Management Plan shall be required.

Requirement 7: An Important To Waste Isolation (ITWI) requirement is indicated to minimize the control material releases from the water supply disinfection equipment into the surrounding soil in order to prevent potential impacts on chlorine testing as part of site characterization activities.

7.10.2 Requirements 1, 2, 3, and 5 are germane to all DIES and provide no specific controls to this analysis.

7.10.3 Requirement 4 addresses minimizing chronic water loss that could occur within the site. The method used to meet this requirement will be provided by water meters at various locations within the site to balance the flow in to and out of the system. These meters will be read and compared against the balance to determine whether there are any leaks within the system. The meters show up on the plans and will be

detailed in the specification. The process of reading the meter will also be contained in the analysis.

- 7.10.4** Requirements 6 and 7 provide no specific design requirements to this analysis. This criteria, however, is contained within this analysis.

8. CONCLUSIONS

The pumps, pipes, tanks, and appurtenances will provide sufficient water at an acceptable pressure to supply the construction, fire fighting, and potable water demands.

9. ATTACHMENTS

ATTACHMENT	TITLE
I	Pipe Head Loss and Discharge
II	Typical Pump Curves
III	Water System Layout Sketches
IV	Water Storage Tank Price Quotations

PIPE HEAD LOSS AND DISCHARGE

AWWA M23 80 ■ 2595512 0062657 1 ■

HYDRAULICS

57

Table 17 (Continued)

12" CI (AWWA C900) DR 25				12" CI (AWWA C900) DR 18			
Actual O.D. 13.200 In., Press. Class 100				Actual O.D. 13.200 In., Press. Class 150			
Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft	Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft
300	0.840	0.021	0.009	300	0.904	0.023	0.011
350	0.980	0.027	0.012	350	1.054	0.033	0.014
400	1.120	0.033	0.013	400	1.205	0.042	0.018
450	1.260	0.044	0.019	450	1.355	0.052	0.023
500	1.400	0.053	0.023	500	1.506	0.064	0.028
600	1.679	0.073	0.032	600	1.807	0.089	0.039
700	1.959	0.099	0.043	700	2.108	0.119	0.051
800	2.239	0.127	0.055	800	2.410	0.152	0.066
1000	2.799	0.192	0.083	1000	3.012	0.230	0.099
1200	3.359	0.269	0.117	1200	3.614	0.322	0.139
1400	3.919	0.358	0.155	1400	4.217	0.428	0.185
1600	4.479	0.459	0.199	1600	4.819	0.548	0.237
2000	5.598	0.654	0.300	2000	6.024	0.829	0.339
2500	6.998	1.049	0.454	2500	7.530	1.253	0.543
3000	8.397	1.470	0.636	3000	9.036	1.737	0.761
3500	9.797	1.935	0.846	3500	10.542	2.337	1.012
4000	11.196	2.504	1.084	4000	12.048	2.993	1.296
4500	12.596	3.114	1.348	4500	13.554	3.722	1.611

12" CI (AWWA C900) DR 14			
Actual O.D. 13.200 In., Press. Class 200			
Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft
300	0.977	0.030	0.013
350	1.140	0.040	0.017
400	1.302	0.051	0.022
450	1.465	0.063	0.027
500	1.628	0.077	0.033
600	1.954	0.108	0.047
700	2.279	0.143	0.062
800	2.605	0.184	0.079
1000	3.256	0.278	0.120
1200	3.907	0.389	0.168
1400	4.559	0.518	0.224
1600	5.210	0.663	0.287
2000	6.512	1.002	0.434
2500	8.140	1.515	0.656
3000	9.768	2.123	0.919
3500	11.397	2.825	1.223
4000	13.025	3.618	1.566
4500	14.653	4.499	1.948

From the American Waterworks Association, "PVC Pipe-Design and Installation" manual M23; copyright 1980.

AWWA M23 80 ■ 2595512 0062656 T ■

58

PVC PIPE — DESIGN AND INSTALLATION

Table 17 (Continued)

8" CI (AWWA C900) DR 14
Actual O.D. 9.050 In., Press. Class 100

Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft
100	0.692	0.024	0.011
125	0.866	0.037	0.016
150	1.039	0.052	0.022
175	1.212	0.069	0.030
200	1.385	0.088	0.038
250	1.731	0.134	0.058
300	2.077	0.187	0.081
350	2.424	0.249	0.108
400	2.770	0.319	0.138
450	3.116	0.397	0.172
500	3.462	0.482	0.209
600	4.135	0.676	0.292
700	4.847	0.899	0.389
800	5.540	1.151	0.498
1000	6.924	1.740	0.733
1200	8.309	2.439	1.056
1400	9.694	3.245	1.405
1600	11.079	4.155	1.799
2000	13.849	6.282	2.719

10" CI (AWWA C900) DR 25
Actual O.D. 11.100 In., Press. Class 100

Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft
175	0.693	0.018	0.008
200	0.792	0.023	0.010
250	0.990	0.034	0.015
300	1.188	0.048	0.021
350	1.385	0.064	0.028
400	1.583	0.082	0.035
450	1.781	0.102	0.044
500	1.979	0.124	0.054
600	2.375	0.173	0.075
700	2.771	0.231	0.100
800	3.167	0.295	0.128
1000	3.958	0.446	0.193
1200	4.750	0.626	0.271
1400	5.542	0.832	0.360
1600	6.333	1.066	0.461
2000	7.917	1.612	0.698
2500	9.896	2.436	1.055
3000	11.875	3.415	1.478

10" CI (AWWA C900) DR 18
Actual O.D. 11.100 In., Press. Class 150

Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft
175	0.746	0.021	0.009
200	0.852	0.027	0.012
250	1.063	0.041	0.018
300	1.278	0.057	0.025
350	1.491	0.076	0.033
400	1.704	0.098	0.042
450	1.917	0.122	0.053
500	2.130	0.148	0.064
600	2.556	0.207	0.090
700	2.982	0.276	0.119
800	3.409	0.353	0.153
1000	4.261	0.534	0.231
1200	5.113	0.748	0.324
1400	5.965	0.996	0.431
1600	6.817	1.275	0.552
2000	8.521	1.927	0.834
2500	10.552	2.914	1.261
3000	12.782	4.084	1.768

10" CI (AWWA C900) DR 14
Actual O.D. 11.100 In., Press. Class 200

Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft
175	0.806	0.026	0.011
200	0.921	0.033	0.014
250	1.151	0.049	0.021
300	1.381	0.069	0.030
350	1.612	0.092	0.040
400	1.842	0.118	0.051
450	2.072	0.147	0.064
500	2.302	0.179	0.077
600	2.763	0.250	0.108
700	3.223	0.333	0.144
800	3.684	0.427	0.185
1000	4.605	0.645	0.279
1200	5.526	0.904	0.391
1400	6.447	1.203	0.521
1600	7.368	1.540	0.667
2000	9.210	2.328	1.008
2500	11.512	3.520	1.524
3000	13.814	4.934	2.136

1400 - 1.203
1600 - 1.540

$\Delta = 0.337$

1450 - 1.287

1600 - 1.54
2000 - 2.328

$\Delta = 0.788$

$\Delta/4 = 0.197$

1700 $\rightarrow$ 1.737

From the American Waterworks Association, "PVC Pipe-Design and Installation" manual M23; copyright 1980.

AWWA M23 80 2595512 0062657 1

HYDRAULICS

57

Table 17 (Continued)

12" CI (AWWA C900) DR 25				12" CI (AWWA C900) DR 18			
Actual O.D. 13.200 In., Press. Class 100				Actual O.D. 13.200 In., Press. Class 150			
Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft	Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft
300	0.840	0.021	0.009	300	0.904	0.025	0.011
350	0.980	0.027	0.012	350	1.054	0.033	0.014
400	1.120	0.035	0.015	400	1.205	0.042	0.018
450	1.260	0.044	0.019	450	1.355	0.052	0.023
500	1.400	0.053	0.023	500	1.506	0.064	0.028
600	1.679	0.075	0.032	600	1.807	0.089	0.039
700	1.959	0.099	0.043	700	2.108	0.119	0.051
800	2.239	0.127	0.055	800	2.410	0.152	0.066
1000	2.799	0.192	0.083	1000	3.012	0.230	0.099
1200	3.359	0.269	0.117	1200	3.614	0.322	0.139
1400	3.919	0.358	0.155	1400	4.217	0.428	0.185
1600	4.479	0.459	0.199	1600	4.819	0.548	0.237
2000	5.598	0.694	0.300	2000	6.024	0.829	0.359
2500	6.998	1.049	0.454	2500	7.530	1.253	0.543
3000	8.397	1.470	0.636	3000	9.036	1.757	0.761
3500	9.797	1.955	0.846	3500	10.542	2.337	1.012
4000	11.196	2.504	1.084	4000	12.048	2.993	1.296
4500	12.596	3.114	1.348	4500	13.554	3.722	1.611

12" CI (AWWA C900) DR 14

Actual O.D. 13.200 In., Press. Class 200			
Flow gpm	Velocity fps	Loss of Head ft/100 ft	Pressure Drop psi/100 ft
300	0.977	0.030	0.013
350	1.140	0.040	0.017
400	1.302	0.051	0.022
450	1.465	0.063	0.027
500	1.628	0.077	0.033
600	1.954	0.108	0.047
700	2.279	0.143	0.062
800	2.605	0.184	0.079
1000	3.256	0.278	0.120
1200	3.907	0.389	0.168
1400	4.559	0.518	0.224
1600	5.210	0.663	0.287
2000	6.512	1.002	0.434
2500	8.140	1.515	0.636
3000	9.768	2.123	0.919
3500	11.397	2.825	1.223
4000	13.025	3.618	1.566
4500	14.653	4.499	1.948

From the American Waterworks Association, "PVC Pipe-Design and Installation" manual M23; copyright 1980.

TYPICAL PUMP CURVES

Title: Water Supply Analysis

Title: Water Supply Analysis

VELOCITY HEAD INCLUDED
TOTAL EYE AREA 8.95 IN²
SPHERE SIZE 1/4"

2TU10

Curve No. 2868655

Impeller No.

2677916/17
2657688/89

1750 RPM

1750 RPM

2TU12

Curve No. 2880457

Impeller No.

2677918/19
2662877/78

1750 RPM

2TU10

Curve No. 2861697

Impeller No.

2677914/15

36-2TU10 - 1/2

3500 RPM

2TU10

Curve No. 2868666

Impeller No.

2677916/17

2657688/89

3500 RPM

WATER SYSTEM LAYOUT SKETCHES

POTABLE WATER layout

WATER STORAGE TANK PRICE QUOTATIONS

Title: Water Supply Analysis

TELEPHONE QUOTATION

SUPPLIER: Brown Steel Tank PROJECT: YHP

ADDRESS: Phacis, Jr. I.O. NO.: _____

PHONE NO.: 9-602-243-3053 DATE: 1/31/92

PERSON QUOTING: Wally Brown RECEIVED BY: GERRY D. WINDA

DELIVERED: YES ☒ NO ☐ PRICE GOOD UNTIL: _____ AFTER ESCALATE: _____

INSTALLED/ERECTED: YES ☒ NO ☐ F.O.B.: _____ SHIPPING WEIGHT: _____

TAX INCLUDED: YES ☐ NO ☒ DELIVERY TIME AFTER ORDER: _____

WRITTEN QUOTE TO FOLLOW: YES ☐ NO ☒ INSTALLATION/ERECTION TIME: _____

EXCLUSIONS OR ALTERNATES: NONE ☐ SEE BELOW ☐

DISCOUNT: _____

NO.	ITEM SPECIFICATION SECTION; DESCRIPTION, REMARKS, ETC.	QTY.	UNIT QUOTE	TOTAL QUOTE
	GROUND LEVEL WATER TANK - 200,000 GALLON	1	80,000	
	GROUND LEVEL WATER TANK - 50,000 GALLON	1	40,000	
ENTER ALTERNATE QUOTE BELOW:				

Title: Water Supply Analysis

as Office 2600 E. Nutwood Avenue Suite 750 Fullerton, CA 92631 714/871-1811

July 2, 1991

RAYTHEON
101 Convention Center Drive
Suite P 250
Las Vegas, NV 89109

Attention: Mr. Roy Clark

Subject: YUCCA MOUNTAIN PROJECT
Budget Estimates for
(2) 50,000 Gallon Elevated Water Towers
(2) 200,000 Gallon Elevated Water Towers

Gentlemen:

We are pleased to furnish budget estimates for four elevated water towers. The following data was used for estimating purposes: Zone 4 earthquake, 200 feet of head, and the towers will be purchased fourth quarter 1991.

50,000 Gallon	Double Cone	\$ 319,200 each	Diameter 29'8"
200,000 Gallon	Torospherical	\$ 555,800 each	Diameter 40'8"

Pricing includes all engineering, materials, fabrication, delivery, erection on foundations by others, and painting. PDM is the primary erector of elevated water towers for almost 100 years. We would be pleased to help you in your endeavors of this project. Enclosed are some brochures of the elevated water tanks and PDM. If you have any questions or comments, please do not hesitate to contact me at (714) 871-1811.

Yours very truly,

PITT-DES MOINES, INC.

Angela L. Gribble, P.E.
Contracting Engineer

ALG:cg

Attachment

Title: Water Supply Analysis

Page: IV-4 of 7

TELEPHONE QUOTATION

SUPPLIER: Chicago Bridge & Iron (CBI) PROJECT: YMC
 ADDRESS: 1751 I.D. NO.: _____
 PHONE NO.: 8.314-986-2550 DATE: 3/31/92
 PERSON QUOTING: Tim Ford RECEIVED BY: Geary DiWoodard
 DELIVERED: YES ☒ NO ☐ PRICE GOOD UNTIL: _____ AFTER ESCALATE: _____
 INSTALLED/ERECTED: YES ☒ NO ☐ F.O.B.: _____ SHIPPING WEIGHT: _____
 TAX INCLUDED: YES ☐ NO ☒ DELIVERY TIME AFTER ORDER: _____
 WRITTEN QUOTE TO FOLLOW: YES ☐ NO ☒ INSTALLATION/ERECTION TIME: _____
 EXCLUSIONS OR ALTERNATES: NONE ☐ SEE BELOW ☐
 DISCOUNT: _____

NO.	ITEM SPECIFICATION SECTION; DESCRIPTION, REMARKS, ETC.	QTY.	UNIT QUOTE	TOTAL QUO
	150' HIGH 43' Ø ZONE IV SEISMIC ELEVATED WATER TANK - 250,000 GALLON. QUOTES ARE BUDGETARY, NOT FIRM PRICE.	1	\$25,000	
ENTER ALTERNATE QUOTE BELOW:				

Title: Water Supply Analysis

Page: IV-5 of 7

TELEPHONE QUOTATION

SUPPLIER: Chicago Bridge & Iron Inc. PROJECT: UMP

ADDRESS: CLC I.O. NO.: _____

PHONE NO.: 8-714-986-2550 DATE: 3/30/92

PERSON QUOTING: Tim Ford RECEIVED BY: GERRY D. Woodward

DELIVERED: YES ☒ NO ☐ PRICE GOOD UNTIL: _____ AFTER ESCALATE: _____

INSTALLED/ERECTED: YES ☒ NO ☐ F.O.B.: _____ SHIPPING WEIGHT: _____

TAX INCLUDED: YES ☐ NO ☒ DELIVERY TIME AFTER ORDER: _____

WRITTEN QUOTE TO FOLLOW: YES ☐ NO ☒ INSTALLATION/ERECTION TIME: _____

EXCLUSIONS OR ALTERNATES: NONE ☐ SEE BELOW ☐

DISCOUNT: _____

NO.	ITEM SPECIFICATION SECTION; DESCRIPTION, REMARKS, ETC.	QTY.	UNIT QUOTE	TOTAL QUO
	100' HIGH 43' Ø ZONE III SEISMIC Elevated WATER TANK - 250,000 GALLON. Quotes Are Budgetary, NOT FIRM PRICE.	1	320,000	
ENTER ALTERNATE QUOTE BELOW:				

Title: Water Supply Analysis

TELEPHONE QUOTATION

SUPPLIER: PDM Inc. PROJECT: YMP

ADDRESS: Fremont CA I.O. NO.: _____

PHONE NO.: 714 871 1811 DATE: 6-9-92

PERSON QUOTING: Bob Aendt RECEIVED BY: Ray Clark

DELIVERED: YES ☒ NO ☐ PRICE GOOD UNTIL: _____ AFTER ESCALATE: _____

INSTALLED/ERECTED: YES ☒ NO ☐ F.O.B.: _____ SHIPPING WEIGHT: _____

TAX INCLUDED: YES ☐ NO ☒ DELIVERY TIME AFTER ORDER: _____

WRITTEN QUOTE TO FOLLOW: YES ☐ NO ☒ INSTALLATION/ERECTION TIME: _____

EXCLUSIONS OR ALTERNATES: NONE ☐ SEE BELOW ☐ DISCOUNT: _____

NO.	ITEM SPECIFICATION SECTION; DESCRIPTION, REMARKS, ETC.	QTY.	UNIT QUOTE	TOTAL QUO
	100' x 45' ϕ STEEL WATER STORAGE TANK INC. PAINT & ERECTION IN ZONE 4	1		\$350,000
	<p>This quote was given to by R. Clark stating that Another company has given a quote of \$425,000 in zone 4 and how much did he think the price would increase over the \$300,000 given to Gamover. He said he thought that the price by PDM could be the difference, so he stated \$350,000. I have little confidence in this quote.</p> <p>ENTER ALTERNATE QUOTE BELOW:</p>			

Title: Water Supply AnalysisPage: IV-7 of 7

CBI Services, Inc.

41777 Boyce Road, P.O. Box 5005
Fremont, California 94527-5005

VIA FACSIMILE (702) 794-7081

510 657 1600
FAX: 510 657 1606

April 10, 1992

Mr. Roy Clark
Raytheon Services
101 Convention Center
Las Vegas, NV 89109Subject: 250,000 Elevated Tank
Nevada Test Site
CBI Reference B-096

Dear Mr. Clark:

Enclosed are preliminary foundation sketches for the 250,000 gallon elevated steel storage tank with 187 feet to the bottom capacity line.

We have discussed the possibility of providing a standpipe for this service. We have concluded that the non-usable volume of water (below 187 feet) would cause a standpipe to be prohibitively expensive compared with the post supported Ellipsoidal elevated tank.

Our budget price for the 250,000 gallon Ellipsoidal elevated tank is \$1,100,000. This price includes the design of the tank and foundation and the construction of the tank on a foundation provided by others. Our budget price includes for painting the tank.

We trust that this information meets your needs. Let us know if you have any questions.

Very truly yours,

A handwritten signature in dark ink, appearing to read "R. C. Maier".
Richard C. Maier
Contract Engineering

RCM/dd

Enclosure