INQUIRY #: 3161481.1

YEAR: 1994

| = 604'

INQUIRY #: 3161481.1

YEAR: 2006

| = 604'

INQUIRY #: 3161481.1

YEAR: 2008

| = 604'

Jacquie Payette

Ms. Payette has more than fifteen years of experience in cultural resources management. Ms. Payette has worked as a consultant for private industry, academic institutions, and federal agencies, including the US Army Corps of Engineers (USACE). This range of experience has given Ms. Payette a broad view of federal and state compliance regulations from different angles.

Ms. Payette deals directly with State Historic Preservation Offices and federally recognized tribes throughout the United States on behalf of clients in compliance with the National Historic Preservation Act and the National Environmental Policy Act. Ms. Payette also works directly with several federal agencies, both on behalf of Applicants in compliance efforts, and as a third-party contractor directly assisting agencies. Ms. Payette's experience includes thousands of cultural resource projects from archaeological surveys through full excavations, analysis of archaeological assemblages, contributions to cultural resource reports, Environmental Assessments (EA), Environmental Impact Statements (EIS), and teaching at the university level.

Fields of Competence

- Section 106 Consultation
- NEPA Compliance, including EA and EIS
- NAGPRA Compliance
- Development of Memoranda of Agreement
- Development of Historic Property Management Plans and Preservation Covenants
- Sensitivity modeling for likelihood of archaeological sites in specific locations
- National Register of Historic Places eligibility evaluations
- Phase I Archaeological Survey

- Tribal Consultation, with well established relationships with tribes throughout the continental US
- Phase II Evaluative Archaeological Testing for historic and prehistoric archaeological sites
- Phase III Mitigation for impacts to historic and prehistoric archaeological sites
- Analysis of human and faunal osteological remains from historic and prehistoric archaeological sites
- Analysis of bone tools and implements from archaeological assemblages
- Historic documentary research
- Historic structure architectural survey
- Development of research and fieldwork designs for cultural resources compliance projects
- Sensitivity modeling for likelihood of archaeological sites in specific locations
- National Register of Historic Places eligibility evaluations
- Consultation with members of the public and local government agencies
- Communication skills for both mid level and senior management audiences

Education

- M.A., Anthropology, focusing on Archaeology and Physical Anthropology, University of Pittsburgh, 1996
- M.A., English, Kent State University, 1987
- B.A., English, Kent State University, 1985
- Wetland Delineation and Management Training, Richard Chinn Environmental Training, 2001
- Hazardous Waste Operations and Emergency Response 40-hour Training, North Central Environmental and Industrial Safety Training Center, 2001

Professional Affiliations

- Register of Professional Archaeologists
- Ohio Archaeological Council

Selected Cultural Resource Documents and Papers

- Payette, Jacquie, and Leslie Kirchler. *Cultural Resources Concerns in Windfarm Siting*. Presented at EUEC Conference, Phoenix AZ, February 2, 2010.
- *Complete Preliminary Draft Environmental Impact Statement-- first sulfide mining EIS in state of Minnesota*. For MN DNR. Author of Cultural Resources Chapter (2009).
- Hendrix, Patrick, and Jacqueline M. Payette. *A Cultural Resources Survey of the Fowler II Proposed Wind Farm, Benton County, Indiana*. Prepared for BP Alternative Energy, 2009.
- Payette, Jacqueline M. *Alternatives Analysis: OH Pleasant Hill Lake 2*. Submitted to FCC and consulting parties on behalf of Alltel Corporation, April 2008.
- Payette, Jacqueline M., Lynelle Peterson, and Edwin Hajic, "Investigations at the Vestal Site (24FR760): An Avonlea Bison Processing Site", *Archaeology in Montana*, Vol. 47, No. 1, 2006.
- Numerous authors, various chapters. *Environmental Evaluation Report: Thoney Parcel, Menominee County, Michigan*. Submitted to Minerals Processing Corp. Author of Cultural and Historic Sites Chapter (2003).
- Payette Jacqueline M., various co-authors, for 1000+ reports on Phase I archaeological surveys for FCC undertakings, nationwide, 1998-present.
- Payette, Jacqueline M., *Estimation of Sex for Humans Based on the First Metacarpal and First Metatarsal*, presented at Society for American Archaeology meetings, Philadelphia, PA, April 8, 2000.
- Payette, Jacqueline M., *Report on White Fort (33Ln2) Faunal Assemblage*, Cleveland Museum of Natural History Archaeology Research Report #138:1-85, Cleveland Museum of Natural History Archaeology Department, 1999.

- Payette, Jacqueline M., *Effect Determination Documentation for the Johnstown Local Flood Protection Project Rehabilitation, Cambria County, Pennsylvania*, for USACE, Pittsburgh District, 1996.
- Payette, Jacqueline M., *Lower Monongahela River Navigation System Improvements Public Facility Relocations: National Register of Historic Places Eligibility Evaluation*, for the USACE, Pittsburgh District, 1996
- Kollecker, Mark A., and Jacqueline M. Payette, *Phase I and II Investigations of the Proposed WAY-30-11.86 Project Area, Wayne County, Ohio*, 1996.

Key Projects

Cultural Resources Consultant to USACE for one year. Awarded the Achievement Medal for Civilian Service in recognition of outstanding performance, specifically for bringing Pittsburgh District into compliance with the Native American Graves Protection and Repatriation Act.

For clients in telecommunications industry, Ms. Payette leads a team who have performed all aspects of cultural resources compliance for thousands of proposed telecommunications towers locations over the last ten years. Specific challenges have included adverse effects, both direct and indirect. In cases where negotiation and project revisions could not avoid the adverse effect, Memoranda of Agreement were developed and executed. Another challenge was coordinating government-to-government consultation between FCC and Plains Tribes to successfully negotiate placement of towers in culturally sensitive areas.

In the mining sector, Ms. Payette has authored the cultural resources chapter of a Complete Preliminary Draft Environmental Impact Statement released in 2009. The DEIS pertains to mining permit application for a large sulfide mine in Minnesota.

For clients in the energy industry, Ms. Payette has led surveys of large footprint projects, including pipeline corridors, LNG facility siting, and windfarms. In addition, Ms. Payette has supported relicensing for energy facilities, contributing to EISs for these efforts.

Danna Gosney Allen

Ms. Danna Allen has over six years of experience in cultural resource management and the field of historic preservation. Ms. Allen meets the Federal qualifications [36 CFR61] for Architectural Historian. Ms. Allen's experience includes a wide range of historic preservation and cultural resource projects for public and private sector clients. These projects have included Section 106 Review Studies, preservation plans, design reviews, existing conditions surveys, historic site surveys, National Register nominations, HABS documentation, historic structure reports and historic resource impact studies. In addition, Ms. Allen has conducted historic research employing primary and secondary sources such as deeds, wills, tax records, atlases and maps, newspapers, and published histories to produce technical reports. Ms. Allen has written cultural resource reports according to local, state and federal guidelines.

Since coming to ERM in the fall of 2006, Ms. Allen has worked as the Architectural Historian for a nation-wide NEPA Compliance Program for Telecommunications clients. Performed cultural resource investigations for more than 400 cell tower sites in over 35 states including South Carolina, North Carolina, Virginia, Georgia, Florida, Tennessee, Mississippi, Arkansas, Ohio, West Virginia, Michigan, Iowa, Nebraska, Kansas, Missouri, Minnesota, Wyoming, Montana, Colorado, Texas, and New Mexico.

Ms. Allen is also responsible for performing research at a variety of state and local offices. Additional responsibilities include assisting with preparation of compliance submittals to state reviewing agencies and other consulting entities. Ms. Allen also performs fieldwork contributing to Phase I Environmental Site Assessments.

Fields of Competence

- Architectural surveys & evaluations
- Historic documentary research
- Development of research and fieldwork designs for cultural resource and historic preservation compliance projects
- Historic Resource Impact Studies
- Section 106 Review Studies
- Compliance with local, state, and federal cultural resource regulations, including the National Historic Preservation Act and the National Environmental Policy Act
- National Register of Historic Places eligibility evaluation for historic resources
- Development of Memoranda of Agreements
- Environmental Assessments in compliance with the National Environmental Protection Act
- Cultural resources portions of Environmental Impact Statements
- ASTM Phase I Environmental Site Assessments

Education

- M.F.A., Historic Preservation, Savannah College of Art & Design
- B.A., Historic Preservation, Goucher College
- 2007 Eastern New Mexico University and BLM Carlsbad Field Office Archaeology Field School (Black River Project)

Key Projects

With ERM

Telecommunications Client - Nation-wide

Architectural Historian for a nation-wide NEPA Compliance Program for this Telecommunications

company. Performed cultural resource investigations for more than 400 cell tower sites in over 35 states including, South Carolina, North Carolina, Virginia, Georgia, Florida, Tennessee, Kentucky, Mississippi, Arkansas, Ohio, West Virginia, Michigan, Iowa, Nebraska, Kansas, Missouri, Minnesota, Wyoming, Montana, Colorado, Texas, and New Mexico. Findings contributed to NEPA Phase I Assessments and Reports.

U.S. Department of Commerce, National Telecommunications Information Administration (NTIA) - Broadband Technology Opportunities Program (BTOP)

Served as lead Architectural Historian for a NEPA Environmental Assessment for confidential clients to satisfy Special Award Conditions (SAC) for grant funding provided by the NTIA through the BTOP. Tasks included researching SHPO files and databases, Phase I cultural resources surveys, and consultation with the SHPO, the USFS, and NPS in accordance with the National Historic Preservation Act and NEPA.

National Park Service, Southeast Region-Ft. Sumter and Battery Huger, Charleston, South Carolina

ERM Project Manager/ Architectural Historian for a Historic Structures Report for Ft. Sumter and Battery Huger in Charleston, South Carolina. ERM is part of a team recently awarded an IDIQ contract for Architecture and Engineering with the National Park Service Southeast Region.

Wind Resource Site Studies, Nation-wide

Served as Cultural Resources lead/ Architectural Historian for over thirty Site Characterization Studies conducted for proposed wind farms throughout the U.S. The purpose of the Cultural Resources section of the study was to identify permitting related to cultural resources, identify known cultural resources within the vicinity of each site as well as the projects potential to impact those cultural resources.

BP Wind Energy-Wind Energy Project, Ford County, Illinois.

Assisted in the preparation of reports regarding the architectural survey component for the proposed development.

White Pines Wind Power Project- Manistee National Forest, Michigan.

Assisted in the preparation of the cultural resources reporting regarding architectural resources identified during the field survey.

Confidential Client, Northeast U.S.

Served as Cultural Resources lead/ Architectural Historian for over ten Site Characterization Studies conducted for proposed new transmission lines and improvements to existing transmission lines. The purpose of the Cultural Resources section of the study was to identify permitting related to cultural resources, identify known cultural resources within the vicinity of each site as well as the projects potential to impact those cultural resources.

Telecommunications/Wireless Client-NEPA Compliance Program, Greater Boston Area, Massachusetts

Project Manager and Architectural Historian for a NEPA Compliance Program for a telecommunications/wireless company. Performed cultural resource investigations for more than 70 wireless telecommunications sites in the greater Boston Area. Findings contributed to NEPA Assessments and Reports.

Confidential Client, New Jersey

Served as Cultural Resources lead/ Architectural Historian for a Phase IA Cultural Resources Survey was completed as part of the client's application under N.J.A.C 7:7A Freshwater Wetlands Protection Act. This project included research of NJSHPO and NJSM files for previously identified historic and archaeological sites as well as previous surveys and projects, an intensive level architectural survey with the completion of NJSHPO survey forms, pedestrian archaeological survey, and the completion of a Phase IA Cultural Resources Report.

Historic Sites Survey, Georgia

Project Manager/ Architectural Historian for historic sites survey of approximately 50 square miles in the vicinity of Madray Springs, Wayne County, Georgia; which required completion of online historic resources survey forms and a written report.

City of Elba, Alabama Historic District National Register of Historic Places Nomination, Coffee County, Alabama

Project Manager/ Architectural Historian for a National Register of Historic Places Nomination for the City of Elba Historic District as a mitigation measure for a proposed telecommunications project.

With Others

BPG Development, Ellis Preserve, Newtown Township, Delaware County, Pennsylvania

Conducted a Phase II Historic Sites Evaluation for campus of former girls' school, eligible for listing on the National Register of Historic Places, in compliance with the PA History Code. Conducted feasibility study for potential donation of façade easements and possible pursuit of Federal Rehabilitation Tax Credits.

Chester City, Delaware County, Pennsylvania

Conducted a Phase I Historic Sites Survey of the Central Business District in the City of Chester, Delaware County, Pennsylvania. The survey included over 200 historic resources; the top 125 of which required the completion of the Pennsylvania Historic Resource Survey form as well as a written report.

Erickson Retirement Communities, Charlestown, Baltimore County, Maryland

Conducted a Phase II Historic Sites Evaluation for two buildings associated with a former Catholic Seminary, listed on the National Register of Historic Places, in compliance with Baltimore County Landmarks Commission guidelines.

Erickson Retirement Communities, Maris Grove, Concord Township, Delaware County, Pennsylvania

Conducted a Phase I Historic Site Study for a former A.M.E. Church, the ruins of a school house, and the ruins of a farmstead, in compliance with the Concord Township.

Commerce Bank, Edison, New Jersey

Assisted in the completion of mitigation tasks including the design and production of an exhibit panel per the MOA between the consulting parties.

Matzel Development, Pocono Manor, Pocono Township, Mount Pocono Borough, and Tobyhanna Townships, Monroe County, Pennsylvania

Assisted in a Phase I Historic Sites Study for this 3,000 acre mountain resort, listed on the National Register of Historic Places, in compliance with the PA History Code.

Conectiv Power Delivery, Atlantic, Burlington, and Ocean Counties New Jersey

Conducted Phase 1 historic sites survey preliminary to Section 106 review along a 46-mile corridor.

Select Publications

Hendrix, Patrick and Danna Gosney. "The Development and Construction of Fort Sumter." Carologue. Vol. 26, No. 3, Winter 2010: 10-21.

Phase 1 Preliminary Assessment
Environmental Justice
Seneca Compressed Air Energy Storage Project
New York State Electric and Gas

Town of Reading
Schuyler County, New York

Environmental Resources Management
399 Boylston Street
Boston, MA 02116

1.0	INTRODUCTION	1
2.0	METHODOLOGY	1
3.0	PROJECT DESCRIPTION AND LOCATION	2
4.0	POTENTIAL ENVIRONMENTAL JUSTICE AREAS MAPPING	4
5.0	ANALYSIS	6
6.0	CONCLUSIONS	8
6.1	Minority populations	8
6.2	Low income populations	8
7.0	DEFINITIONS	8
8.0	REFERENCES CITED	11

1.0

INTRODUCTION

This report provides a review and an analysis of potential environmental justice areas that could be affected by the New York State Electric & Gas (NYSEG) compressed air energy storage (CAES) project and identifies existing environmental burden conditions on the area and evaluates additional burden of any significant adverse environmental impact. The review assesses the socioeconomic and demographic conditions of the area surrounding the proposed CAES facility in Schuyler County, New York. Schuyler County is one of 62 counties in New York. Schuyler County's 2010 population of 18,343 makes it one of the least populated counties in the State (U.S. Census Bureau, 2010). This report was prepared for WorleyParsons by ERM and describes the study area investigated, methods and criteria used to evaluate this area, and the findings and conclusions from the evaluation.

The history of environmental justice (EJ) in the United States is frequently traced to the early 1980s. The EJ movement gained strength and greater prominence in 1994 when President Clinton issued Executive Order 12898, "Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations" (EO 12898). The Executive Order was designed to focus the attention of federal agencies on human health and environmental conditions in minority communities and low-income communities. This Executive Order was issued to ensure that disproportionately high and adverse human health or environmental effects on minority and low-income populations do not occur. A disproportionate environmental impact occurs when the risk or rate for a minority population or low income population from exposure to an environmental hazard significantly exceeds the risk or rate to the general population and, where available, to another appropriate comparison group.

2.0

METHODOLOGY

In 2002 the State of New York Department of Environmental Conservation (DEC) adopted Commissioner Policy 29 (CP-29), Environmental Justice and Permitting, that provides guidance for incorporating environmental justice concerns into the New York State DEC environmental permit review process, including application of the State Environmental Quality Review Act. It is the general policy of the DEC to promote environmental justice and incorporate measures for achieving environmental justice into its programs, policies, regulations, legislative proposals and activities. CP-

29 is specifically intended to ensure that DEC's environmental permit process promotes environmental justice.

ERM followed the guidance of both DEC and Executive Order (EO) 12898 to evaluate EJ concerns. Both policies require a preliminary screen to identify whether the proposed action is in or near potential environmental justice populations and determine whether potential adverse environmental impacts related to the project are likely to affect any potential environmental justice populations. To make this determination, ERM mapped the proposed site and established an analysis area for the CAES project containing the Census Tract in which the site is located. ERM reviewed census data for the analysis area using two groups of metrics for minority populations and low income populations and concluded that the project site does not fall in a potential environmental justice area.

3.0 PROJECT DESCRIPTION AND LOCATION

The proposed CAES Project is a 130 to 180 MW compressed air energy storage plant that consists of an electrically driven compression cycle and a turbine expansion cycle that will produce electricity. The CAES plant is intended to provide sufficient storage to allow full operation during peak demand time periods in support of transmission system and market needs (approximately 10 hours per day). The CAES Project will be located off State Route 14A, in Reading, Schuyler County, New York. The facility is located west of Seneca Lake in northern Schuyler County (Figure 1).

Figure 1: Project Facility Location

POTENTIAL ENVIRONMENTAL JUSTICE AREAS MAPPING

As established in DEC CP-29 on Environmental Justice and Permitting, potential EJ areas are 2000 U.S. Census block groups of 250 to 500 households each that, in the 2000 Census, had populations that met or exceeded at least one of the following statistical thresholds:

- At least 51.1% of the population in an urban area reported themselves to be members of minority groups; or
- At least 33.8% of the population in a rural area reported themselves to be members of minority groups; or
- At least 23.59% of the population in an urban or rural area had household incomes below the federal poverty level.
- Urban and rural designations for census block groups were established by the U.S. Census Bureau. See CP-29 for more information.

ERM downloaded the GIS data layer of Potential Environmental Justice Areas (PEJAs) from DEC's Google Maps and Earth page in KMZ format to map the area using Google Earth. Figure 2 presents the PEJAs (as purple shaded polygons) in the Schulyer County region of New York. The PEJA areas identified by DEC are located in Ithaca and Elmira, approximately 22 miles east and south of the CAES project site, respectively.

Figure 2: Potential EJ Areas

According to DEC guidance, the census block groups meeting the GIS application thresholds for a potential environmental justice area should fall substantially within the affected area. If no census block group(s) meeting the GIS application thresholds for a potential environmental justice area is identified, the proposed action is not likely to affect a potential environmental justice area and the permit review process may continue independent of the elements of this policy. Because the CAES project site does not fall into one of the defined PEJAs, ERM elected to look at the entire census tract in which the CAES project is located rather than the individual block group in order to provide a more comprehensive analysis.

The CAES project site is located in Schuyler County, New York. Table 1 presents the demographic composition of the census tract in which the project site lies (950200), Schuyler County, and the State of New York for comparison. Table 2 presents a breakdown of ethnicity data into percent and compares Census Tract 950200 (see Figure 1) to Schuyler County and New York State. The analysis area had a minority share significantly lower than 33.8% threshold for rural areas at the time of the 2010 Census. Census Tract 950200 had a 3.5% minority population, or 59 persons out of a total population of 1,707. Comparatively, Schuyler County had a minority population of 2.9% and the State of New York had a minority population of 34.3%. While the census tract had a slightly higher minority population than Schuyler County, it was significantly lower than New York's minority population share.

Based on the data presented in Tables 1 and 2, the CAES project site does not have the potential for Environmental Justice concerns with regard to minority populations. While Census Tract 950200 has a slightly larger percentage of minority population share when compared to Schuyler County, it is still significantly lower than the 33.8% minority share that would raise concern based on DEC guidance.

Table 1 Schuyler County Demographic Composition (Source: US Census Bureau, 2010 Census)

Demographic	New York	Schuyler County	Census Tract 950200
Total population	19,378,102	18,343	1,707
Male	9,377,147	9,122	833
Female	10,000,955	9,221	874
Median Age (years)	38.0	44.2	46.0
Under 5 years	1,155,822	881	79
18 years and over	15,053,173	14,453	1,339
65 years and over	2,617,943	3,116	338
One Race	18,792,253	18,103	1,694
White	12,740,974	17,803	1,648
Black or African American	3,073,800	159	26
American Indian and Alaska Native	106,906	47	7
Asian	1,420,244	53	5
Native Hawaiian and Other Pacific Islander	8,766	4	0
Other	1,441,563	37	8
Two or More Races	585,849	240	13
Hispanic or Latino	3,416,922	234	30

Table 2 Schuyler County Ethnicity Composition (Source: US Census Bureau, 2010 Census)

Area	Pop Total	Non-Hispanic or Latino							Hispanic or Latino
		Population of one Race							
		White	Black	American Indian	Asian	Pacific Islander	Other Race		
Census Tract 950200	1,707	96.5%	1.5%	0.4%	0.3%	0.0%	0.5%	1.8%	
Schuyler County	18,343	97.1%	0.9%	0.3%	0.3%	0.0%	0.2%	1.3%	
New York	19,378,102	65.7%	15.9%	0.6%	7.3%	0.0%	7.4%	17.6%	

The Bureau of the Census measures poverty based on 48 thresholds that vary by age and number of family members. These thresholds do not vary by geographic location; however they are annually adjusted for inflation. Poverty level for Census Tract 950200, Schuyler County, and New York State are presented in Table 3. Based on the metrics identified by the Bureau of the Census, 7.7% of the population in the project area was below the poverty level at the time of the 2000 Census. In comparison, the poverty rate for Schuyler County was slightly higher (11.8%) while New York State had a rate nearly double that of Census Tract 950200 (14.6%). The poverty rate for the project area is lower than that of Schuyler County and the State of New York, leading to the conclusion that there are no Environmental Justice concerns for the CAES project with respect to low-income populations.

Table 3 Poverty Levels in Schuyler County (Source: US Census Bureau, Census 2000)

Area	Total Households	Median Household Income²	Persons Below Poverty Level²
Census Tract 950200	701	\$38,618	7.7%
Schuyler County	7,375	\$36,010	11.8%
New York	7,060,595	\$43,393	14.6%

Based on our review of the socioeconomic and demographic data, development of the CAES project would not result in disproportionately high or adverse impacts to low income populations, or to minority or other identifiable groups. No impacts to environmental justice populations as defined by the applicable policies and regulations are anticipated by the CAES project.

6.0 *CONCLUSIONS*

The proposed CAES project in Schuyler County, NY does not have the potential for EJ concerns.

6.1 *Minority populations*

The potentially affected area surrounding the proposed CAES project does not exceed the 33.8 percent minority threshold established by DEC for this analysis, and the analysis area's minority population share does not meaningfully exceed the minority population shares of Schuyler County or the State of New York.

6.2 *Low income populations*

There are no environmental justice concerns regarding low income populations in the project area. The analysis reveals that the project area has a poverty rate lower than Schuyler County and significantly lower than New York State and well below the threshold level of 23.59% for populations in urban or rural areas having household incomes below the federal poverty level.

7.0 *DEFINITIONS*

The following definitions are from the U.S. Bureau of the Census and DEC.

Block group. A block group is a cluster of census blocks having the same first digit of their four-digit identifying numbers within a census tract. For example, block group 3 (BG 3) within a census tract includes all blocks numbered from 3000 to 3999. BGs generally contain between 600 and 3,000 people, with an optimum size of 1,500 people.

Census block. Census blocks are areas bounded on all sides by visible features, such as streets, roads, streams, and railroad tracks, and by invisible boundaries, such as city, town, township, and county limits, property lines, and short, imaginary extensions of streets and roads. Generally, census blocks are small in area; for example, a block bounded by city streets. However, census blocks in sparsely settled areas may contain many square miles of territory. Census block groups generally contain between 250 and 500 housing units.

Census tract. Census tracts are small, relatively permanent statistical subdivisions of a county. Census tracts generally have between 1,500 and 8,000 people, with an optimum size of 4,000 people. When first delineated, census tracts are designed to be relatively homogeneous with respect to population characteristics, economic status, and living conditions. The spatial size of census tracts varies widely depending on the density of settlement. Census tract boundaries are delineated with the intention of being maintained over many decades so that statistical comparisons can be made from census to census. Census tracts are identified by a four-digit basic number and may have a two-digit numeric suffix; for example, 6059.02.

Environmental justice. The fair treatment and meaningful involvement of all people regardless of race, color, or income with respect to the development, implementation, and enforcement of environmental laws, regulations, and policies. Fair treatment means that no group of people, including a racial, ethnic, or socioeconomic group, should bear a disproportionate share of the negative environmental consequences resulting from industrial, municipal, and commercial operations or the execution of federal, state, local, and tribal programs and policies.

Family household (Family). A family includes a householder and one or more people living in the same household who are related to the householder by birth, marriage, or adoption. All people in a household who are related to the householder are regarded as members of his or her family. A family household may contain people not related to the householder, but those people are not included as part of the householder's family in census tabulations.

Household. A household includes all the people who occupy a housing unit as their usual place of residence.

Low-income community. A census block group or contiguous area with multiple census block groups, having a low-income population equal to or greater than 23.59% of the total population.

Low-income population. A population having an annual income that is less than the poverty threshold. For purposes of this policy, poverty thresholds are established by the U.S. Census Bureau.

Major project. Any action requiring a permit identified in section 621.2 of title 6 of the Official Compilation of Codes, Rules and Regulations of the State of New York (6 NYCRR Part 621.2), which is not specifically defined as minor.

Minority community. A census block group, or contiguous area with multiple census block groups, having a minority population equal to or greater than 51.1%* in an urban area and 33.8%* in a rural area of the total population.

Minority population. A population that is identified or recognized by the U.S. Census Bureau as Hispanic, African-American or Black, Asian and Pacific Islander or American Indian.

Potential environmental justice area. A minority or low-income community that may bear a disproportionate share of the negative environmental consequences resulting from industrial, municipal, and commercial operations or the execution of federal, state, local, and tribal programs and policies.

Poverty. Following the Office of Management and Budget's (OMB's) Directive 14, the Census Bureau uses a set of money income thresholds that vary by family size and composition to detect who is poor. If the total income for a family or unrelated individual falls below the relevant poverty threshold, then the family or unrelated individual is classified as being "below the poverty level."

Rural. Territory, population, and housing units that are not classified as an urban area. See definition for 'urban area' below. For purposes of this policy, rural classifications are established by the U.S. Census Bureau.

Urban area. All territory, population, and housing units located in urbanized areas and in places of 2,500 or more inhabitants outside of an urbanized area. An urbanized area is a continuously built-up area with a

population of 50,000 or more. For purposes of this policy, urban classifications are established by the U.S. Census Bureau.

8.0 *REFERENCES CITED*

Environmental Protection Agency (EPA). 1998. Final Guidance for Incorporating Environmental Justice Concerns in EPA's NEPA Compliance Analyses. April 1998.

New York State Department of Environmental Conservation. 2003. Commissioner Policy 29, Environmental Justice and Permitting. DEC Policy. <http://www.dec.ny.gov/regulations/36951.html>.

U.S. Bureau of the Census. 2010. U.S. Census of Population and Housing Summary File 1 (SF 1).

U.S. Bureau of the Census. 2000. Profile of Selected Economic Characteristics Summary File 3 (SF 3).

Executive Order No. 12898, Citation 59 Federal Register 7629 (Feb. 16, 1994). President Clinton.

Phase 1 Preliminary Assessment

Land Use

Seneca Compressed Air Energy Storage Project

New York State Electric and Gas

**Town of Reading
Schuyler County, New York**

**Environmental Resources Management
399 Boylston Street
Boston, MA 02116**

TABLE OF CONTENTS

1.0	LAND USE	1
1.1	EXISTING CONDITIONS.....	1
1.2	TOWN SERVICES.....	3
1.3	SPECIAL LAND USE DESIGNATIONS	3
2.0	POTENTIAL FUTURE LAND USE	5
3.0	ZONING AND LAND USE REGULATIONS.....	6
4.0	LAND USE COMPATIBILITY AND POTENTIAL IMPACTS	8
5.0	REFERENCES	10

FIGURES

ATTACHMENT 1 *Land Use Law for the Town of Reading, NY*

ATTACHMENT 2 *Comprehensive Plan for the Town of Reading*

1.0 LAND USE

The purpose of this report is to identify existing land uses at and in proximity to the proposed Seneca Compressed Air Energy Storage (CAES) Project (Project) and to provide a preliminary assessment of the compatibility of such development at the proposed location. The Project is proposed within a primarily rural area in the Town of Reading in Schuyler County, New York. The project components include the CAES plant site (Facility); underground water supply, wastewater discharge and natural gas pipelines; water supply pump house at the western shore of Seneca Lake; and aboveground power lines and substation, which results in a combined Project site that extends over one mile in length from east to west. A Land Cover map containing data from the U.S. Department of Agriculture - National Agricultural Statistics Service is provided as Figure 1 and depicts land cover and the approximate Project location (USDA, 2010).

1.1 EXISTING CONDITIONS

The dominant land cover in Schuyler County is forest, which covers approximately 142,000 acres, while agriculture, open water, and development cover approximately 64,000 acres, 8,800 acres, and 3,000 acres, respectively (Schuyler County Planning Commission, 2004). Within the 1-mile radius and 2-mile radius of the Project location, the land cover datalayer was reduced to obtain approximate area and type of land usage within these two buffer zones. The summarized information is provided below in Table 1 using broad categories to define the land uses.

Table 1. Land Use Estimates Based on Land Cover Types

Land Cover / Use	1 mile radius (acres)	% of 1 mile radius	2 mile radius (acres)	% of 2 mile radius
Developed/High Intensity	2.7	0.1%	2.7	0.0%
Developed/Medium Intensity	9.5	0.2%	16.2	0.1%
Developed/Low Intensity	43.5	1.0%	104.5	0.8%
Developed/Open Space	200.3	4.6%	644.6	5.1%
Open Water	1,022.8	23.5%	2,800.7	22.3%
Agriculture	1,065.9	24.5%	3,267.0	26.1%
Forest	2,012.4	46.2%	5,696.2	45.5%
TOTAL	4,356.9	100.0%	12,531.9	100.0%

As Table 1 conveys, the land use/cover in these two close-in areas is similar to the land use/cover for Schuyler County as a whole and is primarily rural with forest, agriculture, and open water combining to cover approximately 94 percent of both the one- and two-mile radii around the Project. Within the two-mile radius, the developed/open space land cover category appears to include primarily roadways, a golf course, and a few other small and discrete areas that intersect with agricultural fields and even one small residential neighborhood to total approximately 4.6 percent of the area, while developed areas total approximately just over one percent of the land area. It should be noted that this land cover data are designed to be used for planning-level purposes only.

Seneca Lake is within the one- and two-mile radii of the Project. Primary land use in and around the lake is a combination of residential and recreational uses, with additional commercial operations related to the presence of the Lake. Also within the one-mile radius is at least one cemetery, the Town of Reading Town Hall, and low-density residential areas. Industrial land uses in the Town of Reading include natural gas storage and transmission, a salt mining and evaporation plant, and a metal fabrication/machining company (Town of Reading, 2008).

The Project boundary crosses primarily areas of open former agricultural land and forest, with smaller areas of transportation land uses, including public roadways and an active railroad right-of-way. Proximate to the proposed Facility, the land uses include:

- *To the North:* a truck repair center, a solid waste transfer station, State Route 14A, agricultural crop fields (vineyard), and wooded vacant lands.
- *To the South:* wooded land, with a cemetery approximately 0.7 miles to the southeast.
- *To the East:* wooded land, State Route 14, and further to the east are salt mining facilities and Seneca Lake.
- *To the West:* Open agricultural land, an active railroad corridor, wooded lands, and further to the west residential property, County Route 28, and an active electric utility right-of-way.

In the vicinity of the overhead power line route west of the Facility, a series of marked trails were noted by ERM during a preliminary site reconnaissance within the wooded area between the railroad corridor and

County Route 28. No local, state, or federal public recreational trails are known to exist in this area; therefore, it is expected that the trails are for private use on privately owned land.

1.2 TOWN SERVICES

According to the Superintendent of Utilities at the Department of Public Works (DPW) in Watkins Glen, New York, all water and sewer for the Town of Reading is managed by Watkins Glen (ERM, 2011a). However, this water and sewer coverage serves only a very small portion of the southernmost area of Reading that abuts the northern border of Watkins Glen on the western side of Seneca Lake. Specifically, Watkins Glen manages municipal water and sewer up to the point that Reading Road meets State Route 14. Additional sewerage is provided north of this boundary only to the U.S. Salt Company facilities, which are on the western shore of Seneca Lake at approximately the same latitude as Lovers Lane (Figure 2). Therefore, there is no water or sewer service available at the Project site. Properties in the Town of Reading operate on septic systems and well water.

There are two fire departments in the vicinity of the Project: 1) the Dundee Fire Department, and 2) the Watkins Glen Fire Department (ERM, 2011b). The Project site is within the service area of the Watkins Glen Fire Department given that this department covers properties north of the Village of Watkins Glen along State Route 14 northward up to Chase Road; the Dundee Fire Department covers properties north of Chase Road.

According to the National Center for Education Statistics, which maintains a database of school district demographics, the Project site is located within the boundaries of the Watkins Glen Central School District (U.S. Schools, 2011). This school district encompasses the Town of Reading, and includes three schools (elementary, middle, and high school).

1.3 SPECIAL LAND USE DESIGNATIONS

The Federal Emergency Management Agency (FEMA) Community Status Book for New York indicates that there are no special flood hazard areas in the Town of Reading (FEMA, 2010). The entire community is Zone C,

which means there are no 100-year floodplain boundaries mapped for this community. Despite this documentation, a Flood Mitigation Action Plan developed for Schuyler County identifies specific areas of flooding and bank erosion along Seneca Lake (Figure 3) in the area of the proposed intake structure (Schuyler County, 1999).

According to the New York Department of Environmental Conservation (NYSDEC), no geographic areas have been designated as Critical Environmental Areas (CEAs) within Schuyler County (NYSDEC, 2011). Seneca Lake is designated as a municipal potable water supply source for the Town of Hector and the Village of Watkins Glen.

Portions of the Town of Reading, including areas within the Project boundaries are located in Agricultural District #2. The 2008 Schuyler County Agriculture Development and Farmland Protection Plan acknowledges that agricultural land has increased within the county from 1997 to 2007. However, development pressure is acknowledged in “selected areas near Seneca Lake” where land is prime for vineyards and recreation (Schuyler County, 2008). The “selected areas” were not identified by Town or the location on Seneca Lake. The development pressure, however, is noted as a result of second-home construction and the concern is the loss of prime agricultural land, particularly that which is suited for vineyards.

2.0

POTENTIAL FUTURE LAND USE

Immediately adjacent to the proposed CAES Project, to the northwest, is the proposed Finger Lakes Liquid Petroleum Gas (LPG) Storage Project, for which a Draft Supplemental Environmental Impact Statement (SDEIS) has been submitted to NYSDEC for review. The LPG Storage Project includes the construction of a rail siding and truck loading area, underground storage caverns that will store LPG, and a brine storage pond, as well as an office building and underground pipelines to support the facility. If the Finger Lakes LPG Storage Project is approved and constructed, it will represent a new industrial land use immediately adjacent to the proposed CAES Project site. The scoping session for the SDEIS prepared for the LPG Storage Project did not identify this shift in land use as a substantial environmental concern; therefore, land use was not one of the factors evaluated in the SDEIS (Finger Lakes LPG, 2011). This conversion to industrial land use immediately adjacent to the CAES Project is not anticipated to adversely impact the CAES Project development and potentially implies that a similar conversion to industrial land use for the CAES Project will not be identified as a significant adverse impact.

3.0

ZONING AND LAND USE REGULATIONS

The Town of Reading does not have any zoning districts, nor does it implement conventional zoning laws. Instead, proposed land uses are reviewed and permitted on a case-by-case basis governed by criteria established by the Town Planning Board in the Land Use Law for the Town of Reading, NY (Attachment 1). This law was established to ensure that community goals set forth in the Comprehensive Plan for the Town of Reading (Attachment 2) were protected, pursued, and met.

Based on the footprint of the Project to include greater than 15,000 square feet of area, and the proposed Project elements near Seneca Lake, the Land Use Law for the Town of Reading, NY, Chapter 2, Part 3, indicates the issuance of a "Special Permit" would be required from the Planning Board. To obtain the required "Special Permit", the following documents must be submitted to the Town of Reading Planning Board along with an established fee for permit review and processing:

- A Special Permit application form;
- A Special Permit Site Plan, as described in Appendix I of the Land Use Law;
- A narrative report describing how the proposed land use will satisfy the criteria set forth by the Town Planning Board, as well as any other applicable requirements relating to the specific land use proposed; and
- A long-form Environmental Assessment Form or Draft Environmental Impact Statement.

The development of a land parcel in the Town of Reading is not permitted to result in excessive noise, dust, odors, solid waste, or glare, or create any other nuisances. Several other restrictions apply, including the prevention of emissions into the air, protection of public health and safety, and protection of the surface and ground water. A portion of the Project boundary is located within the Seneca Lake Protection Area defined in Chapter 4, Part 10 of the Land Use Law. This area is protected based on its value to the community as a recreational and economic resource. The Seneca Lake Protection Area includes all land lying east of Route 14 as well as within 50 feet of all first order streams that drain into Seneca Lake. The documenting the presence of first order streams within the proposed CAES Project boundary will be required during Phase 2 of the Project.

It should be noted that several land uses and activities are prohibited within the Seneca Lake Protection Area. However, most of the prohibited uses are not relevant to the CAES Project. One of the prohibited activities identified, "Storage of hazardous materials, except in sealed or unopened containers for resale or as needed for ordinary household use", may need to be addressed, depending on the final design requirements of the CAES Project pump house and associated facilities adjacent to Seneca Lake.

In addition to the prohibited uses, the following limitations (Section 4 Part 10-3 of the Land Use Law) are defined for activities within the Seneca Lake Protection Area:

- No structure shall be built [or] expanded within 25 feet of Seneca Lake (measured horizontally from the mean high water line) or within the 100-year flood plain as shown on the Flood Insurance Rate Maps (FIRM) of the Federal Emergency Management Agency, except docks, boat houses, and storage buildings not exceeding 300 square feet.
- No excavation or fill shall be permitted within 25 feet of Seneca Lake excepting shore wells (also know[n] as beach wells), seawalls, and permitted docks.
- Residential density shall not under any circumstances exceed one dwelling unit per two acres.
- All uses which would otherwise require Site Plan Only Approval shall instead be subject to Special Permit review.
- Maximum lot coverage by roofed structures or other impervious surfaces shall be 20%.
- Within 200 feet of Seneca Lake minimum lot width shall be 100 feet for dwellings which use the lake, or a municipal or off-site system for water supply and 150 feet for dwellings which use a private well and septic system both located on the lot.

Chapter 4 of the Land Use Law identifies supplementary provisions that are to be complied with for all land uses. Applicable provisions include parts identifying General Land Use Performance Standards (4.1), Steep Slope Regulations (4.4), Resource Extraction Conditions (4.6), Rural Siting Principals (4.8), and Storm Water and Erosion Control Guidelines (4.9).

In addition to the Land Use Law requirements, the Schuyler County Flood Mitigation Action Plan states a goal of no new buildings within flood-prone areas (including areas outside of the 100-year floodplain).

4.0

LAND USE COMPATIBILITY AND POTENTIAL IMPACTS

Development of the Project will directly affect current land uses within the Project boundary and may indirectly affect land uses of adjacent and proximate properties. As noted on Figure 1, the two-mile radius of the Project boundaries is confined to the Town of Reading to the north, west, and south of the Project, and crosses over Seneca Lake and into the Town of Hector to the east.

The recreational and commercial land uses associated with Seneca Lake may be impacted if an adverse visual impact from Seneca Lake or any other sensitive receptors were to result from the Project. This visual impact assessment is discussed in a separate section of this Phase 1 preliminary impact assessment.

In general, the local and regional land use laws and plans share a similar goal of protecting viable farmland as a cornerstone of the local economy and to maintain the rural character of the region. The Project would be compatible within the Town of Reading if all provisions established in the Land Use Law are met. The Project's proximity to a proposed industrial land use (Finger Lake LPG storage), an existing industrial land use (salt mining), and a commercial land use (truck repair facility) would likely be considered more compatible than locating the Project in a more residential or strictly agricultural area within the Town of Reading. The project will result in the conversion of small areas of former agricultural fields and forest to industrial land uses for the 1) CAES facility, 2) aboveground power lines extending west from the facility, and 3) a portion of the underground pipeline route extending southeast from the facility. Given the fact that land use conversion for the LPG Storage Project was not identified by NYSDEC as an impact warranting evaluation in their SDEIS may be interpreted that it was not considered a significant adverse environmental impact. Thus with the similarities of the two projects, i.e., the LPG storage facility and the CAES Project in terms of size and location, it is possible that a similar "no impact to land use" determination would be made for the CAES Project.

The portion of the Project within the Seneca Lake Protection Area includes the pump house and associated overhead power lines, the CAES plant water supply intake structure, and underground pipelines extending west from Seneca Lake. To be compatible (as defined by the Town of Reading Land Use Law) within this area, no hazardous materials are permitted to

be stored and no structures are permitted within 25 feet of the mean high water line; therefore, design, construction, and operation of the pump house would be required to comply with these conditions.

Construction of the water supply intake structure and discharge pipe within Seneca Lake conflicts with a strict interpretation of Section 4 Part 10-3 of the Land Use Law given the proposed structure's location within 25 feet of the mean high water line. There is a potential that this prohibition could be limited to aboveground structures and would not apply to underground pipelines used for the intake of water from and discharge of wastewater to Seneca Lake. As noted above, this provision would apply to the proposed pump house along the shore. Additional information on the final infrastructure design will be needed prior to initiating a discussion with the Town of Reading. If underground pipelines are considered 'structures' and are subject to this prohibition, additional investigation regarding the potential for a variance from this requirement is required. If the intake structure and associated intake and discharge pipelines were installed as part of or in conjunction with Inergy/US Salt's planned new cavern solution mining infrastructure, potential allowable "grandfather" rules may apply due to the existing water intake infrastructure on Seneca Lake. This matter will need to be researched further during Phase 2 once more design information is available.

5.0

REFERENCES

Environmental Resources Management, 2011a. Personal communication with Mark Specchio, Superintendent of Utilities at the DPW for Watkins Glen. Subject: water and sewer services in the Town of Reading, NY. September 26.

Environmental Resources Management, 2011b. Personal communication with Joy Fuller, Dundee Fire Department and Bill Kennedy, Watkins Glen County Coordinator's Office. Subject: fire services in the Town of Reading, NY. September 26.

Federal Emergency Management Agency, 2010. Community Status Book Report, New York. Communities Participating in the National Flood Program. Accessed online 23 September 2011:
<http://www.fema.gov/cis/NY.pdf>.

Finger Lakes LPG Storage, LLC, 2011. Draft Supplemental Environmental Impact Statement. LPG Storage Facility. Date accepted for public review: August 2011.

New York Department of Environmental Conservation (NYSDEC), 2011. Environmental Impact Assessment in New York State, Critical Environmental Areas. Accessed online 22 September 2011:
<http://www.dec.ny.gov/permits/6184.html>.

Schuyler County, 1999. Flood Mitigation Action Plan, Schuyler County, New York. October. Southern Tier Central Regional Planning and Development Board, 145 Village Square, Painted Post, NY 14870.

Schuyler County, 2004. Schuyler County Comprehensive Plan. Comprehensive Plan Subcommittee. Schuyler County Planning Commission.

Schuyler County, 1999. Schuyler County Agricultural Development and Farmland Protection Plan. Schuyler County Agricultural and Farmland Protection Board. Shepstone Management Company and Cornell Cooperative Extension of Schuyler County.

Schuyler County, 2008. Schuyler County Agricultural Development and Farmland Protection Plan 2008 Supplemental Revision. Schuyler County Agricultural and Farmland Protection Board. Shepstone Management Company and Cornell Cooperative Extension of Schuyler County.

Town of Reading, Undated. Comprehensive Plan of the Town of Reading New York. Prepared by Joel S. Russell, Woodlea Associates, Salt Point, New York. Access online 22 September 2011:

https://2995944274571788296-a-schuylerplans-org-sites.googlegroups.com/a/schuylerplans.org/schuyler-county/town-of-reading/compplanread.pdf?attachauth=ANoY7cpb8mBbC-6EP6YInCfzSGdfIDKn9QufpgidrKyRcNpBEr4lfp2w2ot1fOZDUgJJAdKElCfvDxvRJYQL-wjX5a8qAJoru0bazC3E7Yr-A2Z4IL8x3dVpn-oLQ0PzjVUNONJuxkxYmg2OGMZgVPZLJR9D7dJLdYZ5YFZBQH1Bwv74yrtHfra6yWg0VZKt1t27TJPJEwDn-BgZh-XGfDxKRcoSlgkLFmL_j1BNjZYPLxDKSbyMAnk%3D&attredirects=1

Town of Reading, 1995. Local Law No. 1 for the year 1995. Local Land Use Law for the Town of Reading New York.

Town of Reading, 2008. Town of Reading home page, last updated 2008. Accessed online 23 September 2011:

<http://home.htva.net/~townofreading/index.htm>

United States Department of Agriculture (USDA), 2010. National Agricultural Statistics Service - 2010 New York Cropland Data Layer.

United States Schools, 2011. American Communities Project. Brown University. Accessed online 26 September 2011:

<http://www.s4.brown.edu/usschools/query.htm> and http://nces.ed.gov/ccd/schoolsearch/school_list.asp?Search=1&DistrictID=3630240.

Legend

- Approximate Site Location
- 1 Mile Buffer of Project Area
- 2 Mile Buffer of Project Area
- Municipal Boundaries
- 2010 TIGER / Line - Roads

USDA 2010 Cropland Data Layer

Cultivated Crops (various)	Developed/Medium Intensity	Open Water
Barren	Developed/Open Space	Other Hay
Deciduous Forest	Evergreen Forest	Pasture/Grass
Developed/High Intensity	Fallow/Idle Cropland	Shrubland
Developed/Low Intensity	Herbaceous Wetlands	Woody Wetlands
	Mixed Forest

SOURCE: United States Department of Agriculture (USDA)
National Agricultural Statistics Service - 2010 New York Cropland Data Layer
Roads - 2010 Census TIGER Line

Figure 1: Land Cover
NYSEG
Seneca Compressed Air Energy
Storage Project (CAES)
Town of Reading
Schuyler County, NY

Figure 3

Town of Reading Flood Hazards and Problems

Attachment 1
Land Use Law for the Town of Reading, NY

(Use this form to file a local law with the Secretary of State.)

Town of Reading

Local Law No. 1 of the year 1995

A local law establishing and regulating Land Uses in the Town of Reading, Schuyler County, NY.

Be it enacted by the Town Board of the

Town of Reading as follows:

LAND USE LAW FOR THE TOWN OF READING, NEW YORK

TABLE OF CONTENTS

Chapter 1. INTRODUCTION AND PURPOSE.....	3
Chapter 2. APPLICABILITY	6
2.1 Uses Allowed by Right	6
2.2 Uses Allowed by "Site Plan Only" Approval	7
2.3 Special Permit Uses	7
2.4 Subdivisions	8
Chapter 3: DIMENSIONAL STANDARDS	9
3.1 By-right Dimensional Standards	9
3.2 Modification of Dimensional Standards	9
Chapter 4: SUPPLEMENTARY PROVISIONS	10
4.1 General Land Use Performance Standard	10
4.2 Minimum Lot Sizes and Buildable Land Area on a Lot	10
4.3 Junkyards and Outdoor Storage	10
4.4 Steep Slope Regulations	11
4.5 Protection of Agriculture from Potentially Incompatible Uses	12
4.6 Resource Extraction	13
4.7 Signs	13
4.8 Rural Siting Principles	14
4.9 Storm Water and Erosion Control	15
4.10 Seneca Lake Protection Area	15
Chapter 5: "SITE PLAN ONLY" REVIEW	17
5.1 Contents of a "Site Plan Only" Application	17
5.2 Procedure	17
5.3 Findings Required	21
Chapter 6: SPECIAL PERMITS	23
6.1 Required Plans	23
6.2 Procedure	23

6.3	Findings Required	23
Chapter 7:	NON-CONFORMING USES, STRUCTURES, AND LOTS	25
7.1	Continuation of Non-conforming Uses and Structures	25
7.2	Discontinuance	25
7.3	Special Permit and Site Plan Only Uses	25
7.4	Expansion, Alteration, and Restoration	25
7.5	Construction Started Prior To This Land Use Law	25
7.6	Existing Non-conforming Lots	26
Chapter 8:	ADMINISTRATION AND ENFORCEMENT	27
8.1	Requirement of Building Permit, Land Use Permit, and Certificate of Occupancy	27
8.2	Violations	28
8.3	Appeal of Action By Land Use Officer	29
Chapter 9:	MISCELLANEOUS PROVISIONS	29
9.1	Interpretation as Minimum Requirements	29
9.2	Severability	29
9.3	Conflict with Other Laws	29
9.4	Appeal of Planning Board Action	29
9.5	Effective Date	29
Chapter 10:	DEFINITIONS	30
APPENDIX I		34
REVIEW OF SPECIAL PERMIT SITE PLANS		34

LAND USE LAW
FOR THE TOWN OF READING, NEW YORK

Chapter 1. INTRODUCTION AND PURPOSE

- 1.1 The Town of Reading, through a series of public surveys and meetings, culminating in an intensive public planning “charrette” held June 4 through 6, 1993, has determined that it is necessary to regulate certain aspects of land use in order to manage future development. The Town, respectful of the individual rights of its citizens, seeks to minimize any burden such regulations might impose.
- 1.2 The purpose of these regulations is to maintain not only the rural appearance and physical character of the Town, but also its rural way of life and social environment. This rural tradition is one in which landowners are free to use their property in any manner that does not harm their neighbors or the Town or region as a whole. The people of Reading desire to allow their town to evolve organically, based upon the changing needs and circumstances they face, rather than upon a predetermined plan of development.
- 1.3 The people of Reading recognize that almost any “use” of land can be made compatible with any other use and can be integrated into its surroundings if the size, scale, design, siting, and operation of the use are appropriate. The Town wishes to encourage the growth of small-scale businesses that provide employment without adversely impacting environmental and community resources. The Town is concerned more with integrating development into the landscape than with comprehensively designating specific future uses of land.
- 1.4 In the charrette and at subsequent meetings, Town residents have expressed the following as goals for the future of the Town:
 - 1.4-1 Strengthen the sense of community and improve communication within the Town.
 - 1.4-2 Where possible, keep agriculture economically healthy.
 - 1.4-3 Preserve open space.
 - 1.4-4 Allow flexibility of uses without harming neighbors.
 - 1.4-5 Encourage non-polluting small business and industry growth that provides year-round employment.
 - 1.4-6 Maintain an economically diverse community with affordable housing
 - 1.4-7 Revitalize selected old buildings and hamlets with businesses and housing.
 - 1.4-8 Discourage large-scale development that changes the Town’s character.

- 1.4-9 Protect Seneca Lake water quality and other important environmental resources.
- 1.4-10 Balance the property rights of individuals with community interests, maintaining rural traditions of freedom of land use.
- 1.4-11 Increase citizen involvement in local government.
- 1.4-12 Keep the Town rural, with moderate growth.
- 1.4-13 Establish a flexible system to regulate development.
- 1.4-14 Provide better public access to Seneca Lake.
- 1.4-15 Improve the appearance of the Town.
- 1.5 The goals in Section 1.4 are intended to guide the application of the specific regulations contained in this document in a flexible manner.
- 1.6 The Town has considered and rejected the idea of adopting a conventional zoning law to implement a physical plan of development. The Town finds that a zoning law based on use districts creates expectations of development and a static vision of the future that are not appropriate for a rural community. Zoning arbitrarily limits flexibility of land use without protecting a town's most important resources and character. The citizens of Reading see their community as dynamic, and they desire to create a system that effectively manages changes as it occurs.
- 1.7 The purpose of this land use law is to provide a flexible framework for decision making that enables different land uses to coexist productively within the community. Unlike zoning, which seeks uniformity and separation of land use by districts, this land use law fosters and embraces integration and diversity. The economic and soil vitality that results from the harmonious mixing of different activities and uses is as the core of the quality of life the Town seeks to preserve.
- 1.8 This land use law therefore establishes a case-by-case site plan and special permit decisions process to regulate land use changes. This decisions process is governed by criteria applied by the Planning Board to specific applications for any construction or land uses regulated by this land use law, enabling an applicant, surrounding landowner, and other interested citizens to work together cooperatively to resolve potential conflicts. The Planning Board's function is to oversee this cooperative process, resolve conflicts when parties are unable to do so, and assure that the criteria established in this land use law are satisfied.
- 1.9 This land use local law is enacted under the powers granted to towns under Article 2 of the Municipal Home Rule Law (MHRL). This land law is not intended to be a zoning law as provided for in Sections 261 through 269 of the Town Law of New York State, although some of its provisions may govern matters similar to those covered by zoning. To the extent that any provisions in this land use law may be inconsistent with Sections 261 through 269

of the Town Law, it is the intent of the Town to supersede such provisions of the Town Law under the supersession provisions of Article 2 of the MHRL.

- 1.10 Because this land use is not a zoning ordinance, has built-in flexibility, and does not restrict land use in a manner likely to cause unnecessary hardship or practical difficulties, it contains no provision for a separate Board of Appeals. Under the standards and purposes of this land use law, the Planning Board is empowered and shall be required to grant relief wherever necessary to avoid any unconstitutional intrusion upon the property rights of landowners. (See Section 8.3 for appeal procedure.)

Chapter 2. APPLICABILITY

This land use law is not intended to affect most single-family or small-scale business uses (as defined below). Rather, it requires Planning Board review of those uses, activities and construction listed in Section 2.2 and 2.3, which could have harmful impacts on neighbors or the Town. In addition to the requirements of this land use law, all requirements of the Schuyler County Watershed Department, New York State Department of Environmental Conservation, the New York State Uniform Fire Prevention and Building Code as administered through the Town's Building Inspector, and other Town, County, State and Federal laws and regulations must also be satisfied.

2.1 Uses Allowed By Right

Because these uses are adequately regulated by existing laws and regulations, their establishment does not require Site Plan review or a Special Permit under this land use law. Land Use Permits are required only for those uses that are not required to obtain Building Permits because they do not involve building. Such uses require only a Building Permit or "Land Use Permit" (unless otherwise noted) from the Building Inspector. Such a permit must be issued if the proposed use or structure is in compliance with applicable federal, state, county and local laws (see Section 8.1).

2.1-1 One-family and two-family dwellings at a density no greater than one dwelling unit per two acres of land without municipal water and sewer services, or two dwelling units per acre with municipal water and sewer services. **However, dwellings may still be built on existing lots that do not satisfy these requirements with approval of the Schuyler County Watershed Department.**

2.1-2 Agriculture and forestry (no Land Use Permit required).

2.1-3 Business or institutional uses (as defined in Chapter 10) occupying less than 2,000 square feet of enclosed floor space in a structure and occupying or using less than 5,000 square feet of land area (except as provided in Subsection 2.3-1 below).

2.1-4 Multi-family dwelling units in buildings that were in existence on the effective date of this law.

2.1-5 Single mobile homes meeting current state and federal standard for mobile home construction, when placed on individual lots meeting the same lot size requirements as conventional single family residences (Para 2.1-1).

2.1-6 Activities that are duly licensed under the Town of Reading's "Ordinance Licensing and Regulating Dealers in Second Hand Junk and Auto Parts Activities and Businesses" (no Land Use Permit required).

2.2 Uses Allowed BY "Site Plan Only" Approval

The following activities and construction, when conducted outside the Seneca Lake Protection Area described in Section 4.10 are permitted by right, subject to review of a

Site Plan to assure that they are appropriately planned. (See Chapter 5 for Site Plan Only review requirements and procedures.)

- 2.2-1 Construction or enlargement of any structure for business or institutional purposes, containing 2,000 to 6,000 square feet of enclosed floor space. This shall include enlargement of an existing structure so that it exceeds the 2,000 square foot threshold. Any business or institutional use that handles refuse or hazardous substances is subject to Special Permit requirements (see Section 2.3 below).
- 2.2-2 The use or occupancy of 5,000 to 15,000 square feet of land, whether or not within structures, for any business or institutional use. For purposes of this Chapter 2, "occupancy of land" shall refer to land that is being actively used or is being cleared, graded, or otherwise altered for site preparation, operations, parking, or other business or institutional purposes, and shall not refer to portions of a parcel left in a natural or undeveloped condition.
- 2.2-3 Multi-family dwelling in new buildings, up to a total of 5 dwelling units per project, at an overall density no greater than one unit per acre.
- 2.2-4 Mobile home parks with no more than 5 units, or older individual mobile homes that do not meet current state or federal standards, at an overall density no greater than one unit per acre.
- 2.2-5 The subdivision of land into lots that do not comply with Section 2.1-1 above, unless the Town adopts subdivision regulations, in which case this provisions shall not apply.

2.3 Special Permit Uses

The following uses and activities, because of their potential for disruption to neighbors, the environment, or others in the community and region are permitted only upon the granting of a Special Permit. Any use or combination of uses covered by both Sections 2.2 and 2.3 shall require a Special Permit. (See Chapter 6 for Special Permit requirements and Procedures.)

- 2.3-1 Solid Waste Management Facilities, as defined in NYCRR Part 360, Subparts 360-2 through 360-14, shall require a Land Use Permit. They shall be reviewed under 6 NYCRR Part 617 (State Environmental Quality Review) and shall be screened with opaque fences, mature evergreen buffers, earthen berms, or other barriers or enclosures which will render the material and activities in the facilities invisible from public roads and adjacent properties. All Solid Waste manage Facilities require a special permit, which permit shall stipulate that the facilities shall be open for inspection at any time by the person or person designated by the Town to monitor the facilities.
- 2.3-2 Construction or enlargement of any structure for business or institutional purposes containing over 6,000 square feet of enclosed floor space. This shall include enlargement of an existing structure so that it exceeds the 6,000 square foot threshold.

- 2.3-3 The use or occupancy of more than 15,000 square feet of land, whether or not within structures, for any business or institutional use.
- 2.3-4 Construction of more than 5 units of multi-family housing, or less than 10 units at a density greater than one unit per acre.
- 2.3-5 Mobile home parks with more than 5 units, or mobile home park with less than 5 units at a density greater than one dwelling unit per acre.
- 2.3-6 Any construction or activity listed in Section 2.2 that occurs within the Seneca Lake Protection Area (see Section 4.10).

2.4 Subdivisions

All subdivisions of land shall be governed by the Town of Reading Land Subdivision Regulations, if and when they are adopted.

Chapter 3: DIMENSIONAL STANDARDS

3.1 By-right Dimensional Standards

(Note: These standards may all be varied by the Planning Board pursuant to Section 3.2.)
The Town wishes to provide for separation between adjoining buildings and uses to avoid disturbance and encroachment, and to protect public health and safety. In seeking to balance individual property rights with the need for individual privacy, it has established the following flexible dimensional standards. For protection from road noise, fumes, and dust, there shall be a minimum setback of 20 feet from the right-of-way of the road. For privacy, the minimum width of the lot at the front side lot lines shall be 15 feet, and from rear lot lines, 25 feet. The minimum width of the lot at the front of the principal building shall be 80 feet. To assure road access, the minimum road frontage shall be 20 feet. In order to protect groundwater in the surrounding area, the minimum lot size with on-site well and septic systems shall be 2 acres. ***(Note: Schuyler County has regulations that cover minimum lot size, but they are designed primarily to assure that septic systems will work on each lot; they do not protect against the cumulative impact on groundwater and surface water of building many units in the same area.)***

3.2 Modification of Dimensional Standards

- 3.2-1 Any applicant for a Site Plan Only approval, Special Permit, or Subdivision approval may request a modification of the Section 3.1 dimensional standards. Such a modification shall be approved if it satisfies applicable review criteria in Chapters 5 or 6 of this land use law or the Land Subdivision Regulations, as appropriate.
- 3.2-2 Any application for a Building Permit or Land Use Permit for a use that is allowed by right may file a Site Plan Only review application requesting a modification of the Section 3.1 dimensional standards. Such a modification shall be approved if it satisfies applicable review criteria in Chapter 5.
- 3.2-3 The entire Town of Reading outside the limits of the incorporated Village of Watkins Glen is hereby declared to be an "open development area" pursuant to Section 280-a(4) of the Town Law of New York State. **Lots may therefore be created which do not have road frontage**, providing that they are served by common driveways or private roads that satisfy the requirements of this land use law and the Subdivision Regulations, and that legally sufficient right-of-way and maintenance agreements are recorded.

Chapter 4: SUPPLEMENTARY PROVISIONS

4.1 General Land Use Performance Standards

The following performance standards shall apply to all land uses **other than the customary practice of agriculture**:

- 4.1-1 No nuisances such as vibration, glare, or odor shall be noticeable at or beyond the property line.

- 4.1-2 No activity shall create a safety or health hazard, by reason of fire, explosion, radiation, or similar causes, to persons or property.
- 4.1-3 There shall be no discharge of liquid or solid waste, or of any other materials, in a manner that may contaminate surface water or ground water.
- 4.1-4 There shall be no storage of any materials either indoors or outdoors that may endanger public health and safety or the natural environment.
- 4.1-5 There shall be no emissions into the ambient air such as smoke, dust, gases, or other material in a manner that may damage the health of persons, animals, or plants, or that damages property.
- 4.1-6 No permanent structure containing toilet facilities, including but not limited to a dwelling, mobile home, travel trailer, boat, business or institutional use, or agricultural structure, shall be occupied unless it is connected to an approved sanitary waste system. This shall not apply to structures with self-contained chemical or composting toilet facilities.

4.2 Minimum Lot Sizes and Buildable Land Area on a Lot

Notwithstanding any other provisions of this land use law, any lot on which a habitable building is constructed must contain a minimum area of buildable land. Such buildable land must be contiguous, with a minimum dimension of 50 feet on all sides, and must be accessible by emergency vehicles from a public or private road. The minimum buildable area for lots containing on-site septic disposal systems or wells shall be 15,00 square feet; for lots connected to off-site septic or sewage disposal and water systems, the minimum shall be 2,500 square feet. Areas covered by the setbacks specified in Chapter 3 may be included in the buildable area of a lot.

4.3 Junkyards and Outdoor Storage

- 4.3-1 Junkyards shall comply with and be subject to applicable licensing requirements of the Town of Reading's "Ordinance Licensing and Regulating Dealers in Second Hand Junk and Auto Parts Activities and Businesses.
- 4.3-2 Junk and junk cars shall be set back at least fifty feet from the right-of-way of a public road and shall be screened from view from the road and adjoining property. The junkyard shall have a roofed work area on a impervious pad with a collection system for automotive fluids and other hazardous substances. Junk cars stored for more than one week shall have all fluids drained and batteries removed. No portion of the junkyard shall be closer than 100 feet to a first order stream or lake.
- 4.3-3 Where practical, trees and shrubs shall be planted, or natural woodlands shall be encouraged to grow, in order to screen the following from view from public roads: junkyards, outdoor storage areas for construction or other heavy equipment or vehicles, and the storage or collection of junk or junk cars.

4.4 Steep Slope Regulations

The Town finds that the alteration of steep slope areas poses potential risks of erosion, sedimentation, landslides, and the degradation of scenic views. Accordingly, the following requirements are hereby imposed in areas with slopes exceeding fifteen percent (15%).

- 4.4-1 No approval of a Subdivision, Site Plan, or Special Permit that involved the disturbance of slopes greater than fifteen percent (15%) shall be granted unless conditions are attached to ensure that:
- a. Adequate erosion control and drainage measures will be in place so that erosion and sedimentation does not occur during or after construction (see Section 4.9).
 - b. Cutting of trees, shrubs, and other vegetation will be minimized except in conjunction with logging operations performed pursuant to applicable guidelines of the New York State Department of Environmental Conservation.
 - c. Safety hazards will not be created due to excessive road or driveway grades or due to potential subsidence, road washouts, landslides, flooding, or avalanches.
 - d. Proper engineering review of plans and construction activities will be conducted by the Town, at the applicant's expense, to ensure compliance with this Section.
 - e. No Certificate of Occupancy will be granted until all erosion control and drainage measures required pursuant to this Section have been satisfactorily completed.
- 4.4-2 No disturbance, including cutting of vegetation or construction of driveways, shall be permitted on any slope of thirty percent (30%) or greater, except as may be needed for foot trails and utility lines, and except in conjunction with logging operations performed pursuant to applicable guidelines of the New York State Department of Environmental Conservation.
- 4.4-3 Slope determinations shall be made based upon the topographic information required for a particular approval, along with such other topographic information as the Planning Board shall reasonably require or the applicant shall offer. In cases of uncertainty or dispute, an engineer retained by the Town, at the applicant's expense, shall determine the location of regulated slopes. For purposes of establishing steep slope area, only contiguous sloped areas owned by the applicant containing at least 5,000 square feet of slopes over 15% or 30% shall be considered.

4.5 Protection of Agriculture from Potentially Incompatible Uses

- 4.5-1 Required Disclosure
- In the case of any proposed residential development that abuts agricultural uses, the Planning Board shall require the applicant to issue a disclosure to potential purchasers of lots or dwelling units as follows: "This property adjoins land used for agricultural purposes. Farmers have the right to apply approved chemical and organic fertilizers, pesticides, and herbicides, and to engage in farm practices which may generate dust, odor, smoke, noise and vibration." This disclosure shall be required as a note on a Subdivision Plat or Site Plan, and may also be required to be made through other means reasonably calculated to inform a prospective purchaser, such as by posting or letter of notification. This Subsection 4.5-3 may also be applied to any business or institutional development within the jurisdiction of the Planning Board which abuts agricultural land, at the discretion of the Planning Board.

4.5-2 Agricultural Buffers

Wherever agricultural uses and other new uses unrelated to the agricultural operations abut, buffers, if desired shall be provided by the proponent of the non-agricultural use to reduce the exposure of the non-agricultural uses to odors, noise, and other potential nuisances related to the agricultural operation. Provision and maintenance of buffers shall be the responsibility of the proponent of the non-agricultural use, unless such use predates the agricultural use. Such buffers may consist of vegetative screening, woodlands, vegetated berms, or natural topographic features.

4.5-3 Agricultural Data Statement

[Note: This section will only apply if Reading adopts county agricultural districts as recommended in the Comprehensive Plan.] Any application for a Special Permit, Site Plan approval, or Subdivision approval for a project that would occur on property within an agricultural district containing a farm operation, or on property with boundaries within five hundred feet of a farm operation located in an agricultural district, shall include an agricultural data statement as defined in Chapter 10. The Planning Board shall evaluate and consider the agricultural data statement in its review of the possible impacts of the proposed project upon the functioning of farm operations within the agricultural district.

4.6 Resource Extraction

4.6-1 An applicant for a Special Permit for resource extraction shall submit to the Planning Board copies of all applications and other materials submitted to the New York State Department of Environmental Conservation (DEC) in connection with its resource extraction application.

4.6-2 In considering whether to grant or deny a resource extraction Special Permit, the Planning Board shall consider all relevant criteria contained in Section 5.2.

4.6-3 In issuing a Special Permit for resource extraction, the Planning Board shall impose conditions designed to protect the public health, safety, and welfare. Such conditions shall be limited to the following, unless the laws of New York State allow the imposition of additional conditions.

- a. Ingress from egress to public thoroughfares controlled by the Town;
- b. Routing of mineral transport vehicles on roads controlled by the Town;
- c. Requirements and conditions specified in the permit issues by the DEC concerning setback from property boundaries and public thoroughfare rights-of-way, natural or man-made barriers to restrict access, dust control, and hours of operation.
- d. Enforcement of reclamation requirements contained in any DEC permit.

4.6-4 In issuing a Special Permit for resource extraction uses not subject to regulation by DEC, the Planning Board may require additional conditions as it deems necessary.

4.7 Signs

Installation of signs shall require a Land Use Permit from the Building Inspector unless exempted by Section 4.7-1 or 4.7-4. Where a sign is erected in conjunction with a project that is subject to Site Plan or Special Permit review, the proposed sign shall be reviewed by the Planning Board as part of the approval process, and shall not require a separate Land Use Permit.

- 4.7-1 Non-illuminated signs less than 16 square feet per side shall not require a Land Use Permit. However, no more than two such signs per building shall be permitted without a Land Use Permit.
- 4.7-2 Commercial signs 16 square feet per side or larger shall require a Land Use Permit in accordance with the following standards.
 - a. Attached signs shall not project more than three (3) feet from the main wall of a building or into a public way.
 - b. Free-standing signs shall not interfere with visibility of pedestrians or vehicles and shall be compatible in design with the business and area.
 - c. No Sign may be larger than one hundred (100) square feet per side.
 - d. Signs shall not interfere with street and traffic lighting nor cause off-premises glare.
 - e. Permanent banners, streamers, flashing lights, and similar devices shall not be permitted on commercial signs.
 - f. No sign shall extend above the height of the associated business establishment or twenty-four (24) feet, whichever is less.
- 4.7-3 Community directory signs larger than twenty-four (24) square feet may be allowed by Site Plan Approval.
- 4.7-4 Non-commercial signs shall be permitted in any locations without a Land use Permit, subject to the restrictions in Section 4.7-2.

4.8 Rural Siting Principles

The following guidelines shall apply to the siting of residences in new subdivisions and to business and institutional uses that are subject to Site Plan or Special Permit approval. **They do not apply to the siting of individual residences on existing lots.** The Planning Board may adopt an illustrated siting guide or refer applicants to a published design manual to provide further guidance on complying with these principles.

- 4.8-1 Wherever feasible, retain and reuse existing old farm roads and country lanes rather than constructing new roads or driveways. This minimizes clearing and disruption of the landscape and takes advantage of the attractive way that old lanes are often lined with trees and stone walls. (This is not appropriate where reuse of a road would require widening in a manner that destroys trees or stone walls.)
- 4.8-2 Preserve stone walls and hedgerows. These traditional landscape features define outdoor areas in a natural way and create corridors useful for wildlife. Using these features as property lines is often appropriate, as long as

setback requirements do not result in constructing buildings in the middle of fields.

- 4.8-3 Avoid placing buildings in the middle of open fields. Place them either at the edges of fields or in wooded areas. Septic systems and leach fields may be located in fields, however
- 4.8-4 Unless buildings are designed traditionally and located close to the road in the manner historically found in the Town, use existing vegetation and topography to buffer and screen them if possible. Group buildings in clusters rather than spreading them out across the landscape in a “sprawl” pattern.
- 4.8-5 Minimize clearing of vegetation at the edge of the road, clearing only as much as is necessary to create a driveway entrance with adequate sight distance. Use curves in the driveway to increase the screening of buildings.
- 4.8-6 Site buildings so that they do not protrude above treetops and crestlines of hills as seen from public places and roads. Use vegetation as a backdrop to reduce the prominence of the structure. Wherever possible, open up views by selective cutting of small trees and pruning lower branches of large trees, rather than by clearing large areas or removing mature trees.
- 4.8-7 Minimize crossing of steep slopes with roads and driveways. When building on slopes, take advantage of the topography by building multi-level structures with entrances on more than one level (e.g. walk-out basements, garages under buildings), rather than grading the entire site flat. Use the flattest portions of the site for subsurface sewage disposal systems and parking area.

4.9 Storm Water and Erosion Control

The Stormwater and Erosion Control Guidelines of the New York State Department of Environmental Conservation shall apply to the following activities:

- 4.9-1 Excavation within 50 feet of a first order stream.
- 4.9-2 Excavation, grading, or construction on slopes over 8% or in any area in excess of 20,000 square feet.
- 4.9-3 Any project subject to Site Plan Only, Subdivision, or Special Permit approval.
- 4.9-4 Agriculture, unless conducted pursuant to an approved current US Department of Agriculture Natural Resources Conservation Service Conservation Plan.

4.10 Seneca Lake Protection Area

The Town of Reading finds that Seneca Lake is a recreational and economic resource of great value to the community and desires special protection of this valuable asset.

4.10-1 Applicability

This Section 4.10 shall apply to all land lying east of New York State Route 14 as well as within 50 feet of the banks of first order streams that drain into Seneca Lake:

4.10-2 Prohibited Uses

The following uses, when conducted at a scale larger than that of an ordinary household, shall be prohibited in the Seneca Lake Protection Area. Existing activities that engage in these activities may continue and expand, provided that they comply with all applicable federal, state, and county laws and regulations and do not increase their non-compliance with this section. Existing activities that are in full compliance with a valid State Pollution Discharge Elimination System (SPDES) Permit shall be exempt from Section 4.10.

- a. Disposal of hazardous materials or solid waste including operation of a landfill.
- b. Treatment of hazardous materials, except rehabilitation programs authorized by a government agency for treating hazardous materials that existed on the site prior to the adoption of this land use law.
- c. Storage of hazardous materials, except in sealed or unopened containers for resale or as needed for ordinary household use.
- d. Production of hazardous materials.
- e. Dry-cleaning and dyeing establishments and laundries that use cleaning solvents.
- f. Printing and photo processing establishments.
- g. Furniture and finish stripping establishments.
- h. Disposal of septic sludge.
- i. Uses which discharge hazardous materials into groundwater or surface water.
- j. Automotive service stations.
- k. Junkyards.

4.10-3 Regulations

- a. No structure shall be built on expanded within 25 feet of Seneca Lake (measured horizontally from the mean high water line) or within the 100-year flood plain as shown on Flood Insurance Rate Maps (FIRM) of the Federal Emergency Management Agency, except docks, boat houses, and storage buildings not exceeding 300 square feet.
- b. No boat house or storage building shall be used for residential purposes.
- c. No excavation or fill shall be permitted within 25 feet of Seneca Lake excepting shore wells (also known as beach wells), seawalls and permitted docks.
- d. Residential density shall not under any circumstances exceed one dwelling unit per two acres.
- e. All uses which would otherwise require Site Plan Only approval shall instead be subject to Special Permit review.
- f. Maximum lot coverage by roofed structures or other impervious surfaces shall be 20%.
- g. Within 200 feet of Seneca Lake minimum lot width shall be 100 feet for dwellings which use the lake, or a municipal or off-site system for water supply and 150 feet for dwellings which use a private well and septic system both located on the lot.

Chapter 5: “SITE PLAN ONLY” REVIEW

The Town has established in Chapter 2 a three-tiered system of reviewing land use and development. Most small-scale uses require only a Land Use Permit or Building Permit, issued by the Building Inspector. Larger-scale projects outside of the Seneca Lake Protection Area (listed in Section 2.2) require Planning Board review of a site plan only, to assure that such projects will be compatible with their surroundings. Very large projects and those located in the Seneca Lake Protection Area must follow the Special Permit requirements in Chapter 6.

5.1 Contents of a “Site Plan Only” Application

An applicant for a Site Plan Only approval shall submit:

- 5.1-1 A Site Plan Only application form.
- 5.1-2 A site plan drawn to scale with accurate dimensions providing information sufficient to enable the Planning Board to make an informed decisions; an agricultural data statement as defined in Chapter 10, if required by Section 4.5-3; and a vicinity map of appropriate scale showing adjacent lots and annotated with the names of adjacent lot owners. The Planning Board may require the submission of some of the information listed in Appendix I, Section I.1, as appropriate to the specific application.
- 5.1-3 A brief narrative describing the proposed use.
- 5.1-4 A short-form Environmental Assessment Form (EAF) (unless the Planning Board determines that the proposed Site Plan approval is a Type I action under the State Environmental Quality Review Act (SEQRA), in which case a long-form EAF shall be required).
- 5.1-5 The Site Plan only application fee as established by the Town Board, and an escrow deposit if required to cover reasonable professional review costs.

5.2 Procedure

5.2-1 Application

- a. Application for a Site Plan Only approval shall be made to the Planning Board, on forms prescribed by the Planning Board.
- b. If an application is for a parcel or parcels on which more than one use requiring Site Plan Only approval is proposed, the applicant may submit a single application for all such uses. The Planning Board may grant the application with respect to some proposed uses and not others. For purposes of determining whether the application require Site Plan Only or Special Permit approval (and for SEQRA compliance), all proposed uses on a single parcel or related uses on nearby or contiguous parcels shall be considered together.

5.2-2 Informal Meeting

Before filing an application, an informal meeting with the Planning Board is recommended to discuss the nature of the proposed use and to determine the information that will need to be submitted.

5.2-3 Mediation

At any point in a project review process the Planning Board may, if it deems appropriate and the applicant consents, appoint a mediator to work informally with the applicant, neighboring property owners, and other interested parties to address concerns raised about the proposed use. Any party may request mediation. Such mediation may be conducted by a member of another municipal board, by the Planning Board's consultant, or any other qualified and impartial person acceptable to the parties and the Planning Board. The mediator shall have no power to impose a settlement or bind the parties or the Planning Board, and any settlement reached shall require Planning Board approval to assure compliance with all provisions of this land use law. The cost of such mediation will be charged to the applicant as part of the cost of project review. Such cost may also be shared by other interested parties with their written consent.

5.2-4 SEQRA Compliance

Upon receipt of application materials it deems complete, the Planning Board shall initiate the New York State Environmental Quality Review process by either circulating the application and Environmental Assessment Form to all involved agencies (if coordinated review is undertaken) or by issuing its determination of significance within twenty (20) days. Where the proposed action may have a significant effect on the environment, the Planning Board shall issue a positive declaration and require the submission of a Draft Environmental Impact Statement (DEIS). No time periods for decision making in this land use law shall begin to run until either acceptance of a DEIS as satisfactory pursuant to NYCRR Section 617.8(b)(1) or the issuance of a negative declaration. The Planning Board may prepare the DEIS at the applicant's expense, with the applicant's consent.

5.2-5 Referral to County Planning Commission

- a. Upon receipt of application materials it deems to be complete, the Planning Board shall refer to the Schuylar County Planning Commission any application for Site Plan approval affecting real property within five hundred (500) feet of the boundary of the Town of Reading, the boundary of any existing or proposed County or State park or other recreational area, the boundary of any existing or proposed County or State roadway; the boundary of any existing or proposed right-of-way for a stream or drainage channel owned by the County for which the County has established channel lines, the boundary of any existing or proposed County or State-owned land on which a public building or Institution is situated, or the boundary of a farm operation within an agricultural district as defined in Article 25AA of the Agriculture and Markets Law, pursuant to General Municipal Law, Article 12-B, Sections 239-I and 239-m, as amended.
- b. No action shall be taken on applications referred to the County Planning Commission until its recommendation has been received, or thirty (30) days have elapsed after its receipt of the complete application, unless the County and Town agree to an extension beyond the thirty (30)-day requirement for the County Planning Commission's review.

- c. County Disapproval. A majority plus one (1) vote of the Planning Board shall be required to grant any Site Plan approval which receives a recommendation of disapproval from the County Planning Commission because of the referral process specified about, along with a resolution setting forth the reasons for such contrary action.

5.2-6 Notice and Hearing

- a. The Planning Board shall hold a public hearing on a complete Site Plan Only application within 62 days not counting Saturdays, Sundays and Holidays. At least seven (7) calendar days prior to the date thereof, the applicant shall notify all of the following of the hearing by registered mail, return receipt requested and shall give public notice of such hearing by causing publication of a notice of such hearing in the official newspaper.
 - 1. Owners of all real property as shown on the current tax map, located within 200 feet in all directions of the property, which is the subject of the hearing.
 - 2. The clerks of all adjoining municipalities whose boundaries are located within 200 feet of the property, which is the subject of the hearing.
 - 3. The County planning board where the hearing concerns property adjacent to an existing county road or proposed road shown on the official county map, adjoining other county land or situated within 500 feet of a municipal boundary.
 - 4. The State Commissions of Transportation where the hearing concerns an application for development of property adjacent to a state highway.
- b. The cost of mailing the notices shall be borne by the applicant.

5.2-7 Action

- a. The Planning Board by a majority vote of the full Board, shall grant, deny, or grant subject to conditions the application for a Site Plan Only approval within sixty-two (62) days after the hearing. Any decisions shall contain written findings explaining the rationale for the decision in light of the standards contained in this land use law.
- b. A copy of the decision shall be immediately filed in the Town Clerk's office and mailed to the applicant. A resolution of either approval with modifications shall include authorization to the Planning Board Chairman to stamp and sign the site plan upon the applicant's compliance with applicable conditions and the submission requirements stated herein.
- c. If the Planning Board's resolution includes a requirement that modifications be incorporated in the Site Plan, conformance with these modifications shall be considered a condition of approval. If the Site Plan is disapproved, the Planning Board may recommend further study of the Site Plan and resubmission to the Planning Board after it has been revised or redesigned.
- d. Within six (6) months after receiving Site Plan approval, with or without modifications, the applicant shall submit four (4) copies of the Site Plan to the Planning Board for stamping and signing. The Site Plan submitted for stamping shall conform strictly to the Site Plan approved by the Planning Board, except that it shall further incorporate any required revisions or other modifications and shall be accompanied by the following additional information:
 - 1. Record of application for and approval status of all necessary permits from Federal, State, and County officials.
 - 2. Detailed sizing and final material specification of all required improvements.

3. An estimated project construction schedule. If a performance guaranty pursuant to Subsection 5.2-8 is to be provided by the applicant for all or some portion of the work, a detailed site improvements cost estimate shall be included.
4. Proof of payment of the Planning Board's reasonable review costs.
- e. Upon stamping and signing the Site Plan, the Planning Board shall forward a copy of the approved Site Plan to the Building Inspector and the applicant. The Building Inspector may then issue a Building Permit or Certificate of Occupancy if the project conforms to all other applicable requirements.

5.2-8 Performance guaranty

No Certificate of Occupancy shall be issued until all improvements shown on the Site Plan are installed, or a sufficient performance guaranty has been posted for improvements not yet completed. Such performance guaranty shall be posted in accordance with the procedures specified in Section 277 of the Town Law relating to subdivisions. The amount and sufficiency of such performance guaranty shall be determined by the Planning Board after consultation with the Town Attorney, the Building Inspector, other local officials, or its designated consultants.

5.2-9 Inspection of Improvements

The Building Inspector shall be responsible for the inspection of site improvements, including coordination with the Town's consultants and other local officials and agencies, as may be appropriate.

5.2-10 Expiration, Change of Use, Revocation, and Enforcement

- a. A Site Plan approval shall expire if the approved use or uses cease for more than twenty-four (24) consecutive months for any reason, if the applicant fails to obtain the necessary Building Permit or Land Use Permit or fails to comply with the conditions of the Site Plan approval within eighteen (18) months of its issuance, or if its time limit expires without renewal.
- b. A Site Plan approval shall apply to the use for which it has been granted, as well as to any subsequent use of the property which complies with all terms and conditions of the Site Plan approval (as determined by the Building Inspector in issuing a Building or Land Use Permit) and which does not involve any new construction, enlargement, exterior alteration of existing structures, or changed use of outdoor areas. Any other change to a use allowed by Site Plan approval shall require the granting of a new Site Plan approval or a Site Plan amendment.
- c. A Site Plan approval may be revoked by the Planning Board if the permittee violates the conditions of the Site Plan approval or engages in any construction or alteration not authorized by the Site Plan approval.
- d. Any violation of the conditions of a Site Plan approval shall be deemed a violation of this land use law, and shall be subject to enforcement action as provided herein.

5.2-11 Amendments

The terms and conditions of any Site Plan Only approval may be amended in the same manner as required for the issuance of a Site Plan Only approval, following the criteria and procedures in this Chapter. Any enlargement, alteration, or

construction of accessory structures not previously approved shall require a Site Plan amendment.

5.2-12 Reservation of Parkland

For any Site Plan containing residential units, the Planning Board may require the reservation of parkland pursuant to Town Law, Section 274-a(6).

5.3 Findings Required

In order to grant a Site Plan Only approval, the Planning Board must find that the proposal:

- 5.3-1 Will not cause undue traffic congestion, unduly impair pedestrian or vehicular safety, or overload existing roads, considering their current width, surfacing, and condition, and will have appropriate parking and be accessible to fire, police, and other emergency vehicles. Road access points will have sufficient sight distances to assure visibility of vehicles.
- 5.3-2 Will not overload any public water, drainage, or sewer system, or any other municipal facility, or degrade any natural resource or ecosystem, including Seneca Lake or its tributaries.
- 5.3-3 Will be suitable for the property on which it is proposed, considering the property's size, location, topography, vegetation, soils, natural habitat, and hydrology, and if appropriate, its ability to be buffered or screened from neighboring properties and public roads.
- 5.3-4 Will not result in excessive noise, dust, odors, liquid or solid waste, or glare, or create any other nuisances, and will satisfy the General Land Use Performance Standards in Section 4.1.
- 5.3-5 Will comply with the Rural Siting Guidelines in Section 4.8, if applicable.

Chapter 6: SPECIAL PERMITS

In recognition that large-scale uses and certain other uses located within the Seneca Lake Protection Area tend to have the greatest impacts on the Town and its environment, such uses shall be allowed only upon the granting of a Special Permit as described below.

6.1 Required Plans

An applicant for a Special Permit shall submit:

- 6.1-1 A special Permit application form.
- 6.1-2 A Special Permit Site Plan, as described in Appendix I, Review of Special Permit Site Plans, and an agricultural data statement as defined in Chapter 10, if required by Section 4.5-2 of this land use law.
- 6.1-3 A narrative report describing how the proposed use will satisfy the criteria set forth in the findings requirements of Section 6.3, as well as any other applicable requirements relating to the specific use proposed.
- 6.1-4 A long-form Environmental Assessment Form or Draft Environmental Impact Statement.
- 6.1-5 The Special Permit application fee, as established by the Town Board, and any required escrow deposit for review costs, as required by the Planning Board.

6.2 Procedure

The procedures contained in Section 5.2 for Site Plan Only approval shall be followed for Special Permit applications.

6.3 Findings Required

In granting or denying Special Permits, the Planning Board shall take into consideration the scale of the proposed project, the possible impact of the proposed project on the functioning of nearby farm operations, the constitutional rights of the applicant to an economically viable use of property, and the rural tradition of freedom of land use where such use does not harm others. The Planning Board shall also take into account any proposed conservation easements, architectural restrictions, or other measures that would tend to mitigate potential adverse impacts and preserve or enhance the scenic and historic character of the Town. Before granting a Special Permit, the Planning Board shall make specific written findings that the proposed use:

- 6.3-1 Will comply with all provisions and requirements of this and other local laws and regulations, and will fulfill the purposes of this land use law as stated in Chapter 1.
- 6.3-2 Will not result in excessive noise, dust, odors, solid waste, or glare, or create any other nuisances, and will satisfy the General Land Use Performance Standards in Section 4.1.
- 6.3-3 Will be suitable for the property on which it is proposed, considering the property's size, location, topography, vegetation, soils, natural habitat, and hydrology, and, if

appropriate, its ability to be buffered or screened from neighboring properties and public roads.

- 6.3-4 Will not cause undue traffic congestions, unduly impair pedestrian or vehicular safety, or overload existing roads, considering their current width, surfacing, and condition, and will have appropriate parking and be accessible to fire, police, and other emergency vehicles. Road access points will have sufficient sight distances to assure visibility of vehicles.
- 6.3-5 Will not overland any public water, drainage, or sewer system, or any other municipal facility, or degrade any natural resource or ecosystem, including Seneca Lake or its tributaries.
- 6.3-6 Will be subject to such conditions on design and layout of structures, provision of buffer areas, and operation of the use as may be necessary to ensure compatibility with surrounding uses and to protect the natural, historic, and scenic resources of the Town. Where water and sewer services are available, the Planning Board may require development to be clustered in the pattern of a traditional village or hamlet with visually or environmentally important open space preserved by a deed restriction or conservation easement. Where water and sewer utilities are not available, the Planning Board shall encourage such a pattern to the extent feasible.
- 6.3-7 Will be consistent with the goals of concentrating retail uses in hamlets, and incorporated villages, avoiding strip commercial development and residential sprawl development, and locating non-residential uses, that are incompatible with residential use in well-buffered rural locations.
- 6.3-8 Will comply with the Rural Siting Guidelines in Section 4.8, if applicable, and with the Site Plan criteria in Appendix I, Section I.3

Chapter 7: NON_CONFIRMING USES, STRUCTURES, AND LOTS

7.1 Continuation of Non-conforming uses and Structures

Any lawful structure of use existing at the time of enactment or amendment of this land use law (pre-existing use or structure) which becomes non-conforming as a result of such enactment or amendment may be continued.

7.2 Discontinuance

A non-conforming use of land or structures which is discontinued for a period of twenty-four (24) consecutive months shall not be re-established without compliance with applicable provisions of this land use law, and any subsequent use of the same property shall conform to the requirements of this land use law.

7.3 Special Permit and Site Plan Only Uses

7.3-1 Any pre-existing use or structure which can be allowed by Special Permit under this land use law, but which has not been issued a Special Permit, shall be permitted to continue as a non-conforming use until such time as it is granted a Special Permit. Upon the granting of such a Special Permit, the use shall become conforming and shall be governed by the conditions attached to the Special Permit. If such a Special Permit is denied, the use may continue as a non-conforming use, subject to the requirements of this Chapter 7.

7.3-2 Any pre-existing use or structure which requires a "Site Plan Only" approval under this land use law shall be deemed a conforming use, and may be expanded by a total cumulative amount of 25% of the enclosed floor space and/or occupied outdoor area, without requiring Site Plan Only approval.

7.4 Expansions, Alteration, and Restoration

7.4-1 A non-conforming use or structure may be expanded or enlarged by a maximum of 25% of its floor area or occupied outdoor area. The extensions of a lawful use to any portion of a non-conforming structure shall not be deemed the extensions of a non-conforming structure or use.

7.4-2 A non-conforming structure or use may be rebuilt by right in the event of total or partial destruction thereof, to occupy no more space than permitted in Subsection 7.4-1.

7.4-3 A non-conforming use or structure may be repaired or restored as necessary to a safe condition.

7.5 Construction Started Prior To This Land Use Law

Any non-conforming structure for which construction was begun prior to the effective date of this land use law, or of any amendment thereto, may be completed and used in accordance with the approved plans and specifications for such structure. Any non-conforming structure for which construction has not begun, pursuant to approved plans shall be subject to the provisions of this land use law and any amendments thereto, even if all approvals previously required have been granted.

7.6 Existing Non-conforming Lots

- 7.6-1 Any lot of record created prior to the enactment of this law which does not comply with the area, density, or dimensional requirements of this land use law shall be deemed to comply with such requirements, provided that:
- a. The lot contains at least 5,000 square feet.
 - b. There is no contiguous lot in the same ownership to which the non-conforming lot may be joined.
 - c. The dimensional requirements in Section 3.1 are satisfied.
 - d. Any residential use of a non-conforming lot shall be limited to one single-family dwelling.

7.6-2 A non-conforming lot may be subdivided only if every portion of such lot will be transferred to owners of adjoining properties to increase the size of such owner's properties, thereby eliminating the non-conforming lot.

Chapter 8: ADMINISTRATION AND ENFORCEMENT

8.1 Requirement of Building Permit, Land Use Permit, and Certificate of Occupancy

In order to assure compliance with this land use law, it is necessary for the Town to be aware of proposed development activities. Most such activities already require a Building

Permit under the New York State Uniform Fire Prevent and Building Code ("Building Code"), administered by the Building Inspector.

8.1-1 This Law shall be enforced by the Land Use Officer (LUO) who shall be appointed by the Town Board. No Building Permit or Certificate of Occupancy shall be issued by the LUO unless all provisions of this law have been complied with. The LUO shall also serve as the Town Building Inspector. References to the "Building Inspector" in this local law shall be deemed to refer to the "Land Use Officer" as well.

8.1-2 Building Permit Types

Under the terms of this law the following classes of Building Permits may be issued by the LUO:

- a. Permitted Use. A building permit for a "by right" use as defined in section 2.1 may be issued by the LUO of his own authority.
- b. Site Plan Only. A Building and Land Use Permit for a Site Plan Only laude use may be issued by the LUO after review and approval by the Planning Board following procedures defined in Chapter 5 of this law.
- c. Special Permit. A Building and/or Land Use Permit for projects requiring Special Permits may be issued by the LUO after review and approval by the Planning Board following procedures defined in Chapter 6 of this law.
- d. Permits After Appeal. Building and/or Land Use Permits may be issued by the LUO upon the order of the Board of Appeals and after a public hearing held by the Board of Appeals for the purpose of deciding up the Appeal.

8.1-3 Except as provided in Subsection 8.1-5, no buildings or structures, including accessory buildings and signs, shall be erected, moved, enlarged, or extended, nor shall any new commercial use of land be initiated or excavation of land be begun unless and until a Building Permit or Land Use Permit has been issued by the Building Inspector.

8.1-4 Commercial activities that are not covered by the Building Code require a town "Land Use Permit," which shall be granted if the proposed use complies with this land use law. Land Use Permits shall be required only in situations where a Building Permit is not required or has not yet been issued, including erection of free-standing signs, land disturbance (including excavation, grading and site clearing) of more than 2,000 square feet of land, or business or institutional uses not involving buildings.

8.1-5 No Land use Permit shall be required for agriculture or forestry activities, or for activities duly licensed under the Town of Reading's "Ordinance Licensing and Regulating Dealers in Second Hand Junk and Auto Parts Activities and Businesses"

8.1-6 No structure or expansion of an existing structure shall be occupied or used until the Building Inspector issues a Certificate of Occupancy certifying compliance of such structure with the terms of its Building Permit, this land use law, and with all other applicable laws and regulations.

8.2 Violations

8.2-1 Penalties

A violation of this land use law is an offense punishable by a fine not to exceed three hundred-fifty dollars (\$350.00), or imprisonment for a period not to exceed six (6) months, or both for conviction of a first offense. Conviction of a second offense, committed with five (5) years of the first offense, is punishable by a fine not less than three hundred-fifty dollars (\$350.00) nor more than seven hundred dollars

(\$700.00) or imprisonment for a period not to exceed six (6) months, or both. Conviction of a third or subsequent offense committed within a period of five (5) years is punishable by a fine of not less than seven hundred dollars (\$700.00) nor more than one thousand dollars (\$1,000.00), or imprisonment for a period not to exceed six (6) months, or both. Each week's continued violation shall constitute a separate violation.

8.2-2 Complaints of Violations

Whenever a suspected violation of this land use law occurs, any person may file a signed written complaint reporting such violation to the Land Use Officer. All such complaints must be in writing (unless the suspected violation threatens life, health, or safety, in which case the Land Use Officer is authorized to act on an oral complaint) and shall be submitted to the Land Use Officer, who shall properly record such complaint and immediately investigate and report thereon to the Town Board.

8.2-3 Abatement of Violations

Whenever a suspected violation of this land use law occurs, the Town Board or, with its approval, the Land Use Officer, may institute an appropriate legal action or proceeding to prevent, restrain, correct, or abate such violation, to prevent the occupancy of the premises, or to prevent any illegal act, conduct, business, or use in or about the premises. The Land Use Officer shall also be empowered to issue a "stop work order" upon determining that a violation of this local law has occurred or is in progress.

8.2-4 Taxpayer Action

Upon the failure or refusal of the Land Use Officer or Town Board to institute an appropriate legal action or proceeding for a period of ten (10) days after written request by a resident taxpayer of the Town to do so, any three (3) taxpayers of the Town residing in the district in which such violation exists, who are jointly or severally aggrieved by such violation, may institute such appropriate action or proceeding in the same manner as the Land Use Officer or Town Board.

8.2-5 Accountability

For every violation of the provisions of this land use law, the owner, agent, contractor, lessee, ground lessee, tenant, licensee, or any other person who commits, takes part, or assists in such violation or who maintains any structures or premises in which any such violation exists, shall be punishable according to the provisions of this land use law.

8.3 Appeal of Action By Land Use Officer

Any person aggrieved by an order, determination, interpretation, or other action taken by the Land Use Officer may appeal such action to the Planning Board following the procedural steps contained in Section 5.2. In hearing such appeal, the Planning Board shall have the powers of a board of appeals as provided in Section 267-b of the Town Law of New York State.

Chapter 9: MISCELLANEOUS PROVISIONS

9.1 Interpretation as Minimum Requirements

In their interpretation and application, the provisions of this land use law shall be deemed minimum requirements, adopted for the promotion of the public health, morals, safety, or the general welfare. Whenever the requirements of this land use law differ from the

requirements of any other lawfully adopted laws, regulations, or ordinances, the most restrictive, or that imposing the higher standard, shall govern.

9.2 Severability

If any provision of this land use law or the application thereof to any person, property, or circumstances is held to be invalid, the remainder of this land use law and the application of each provision to other persons, property, or circumstances shall not be affected thereby.

9.3 Conflict with Other Laws

This land use law shall not repeal, abrogate, annul, or in any way impair or interfere with any provisions of law or rules of regulations previously adopted or issued and still in effect relating to the use of structures or premises, provided that where this land use law imposes a greater restriction upon the use of structures or premises or requires larger lots or yards that are imposed or required by such existing laws, rules, or regulations, the provisions of this land use law shall control.

9.4 Appeal of Planning Board Action

Any person aggrieved by a decision of the Planning Board may apply to the Supreme Court for review by a proceeding under Article 78 of the Civil Practice Law and Rules.

9.5 Effective Date

This land use law shall take effect upon filing in the office of the Secretary of State.

Chapter 10: DEFINITIONS

Except where specifically defined herein, all words used in this ordinance shall carry their customary meaning as defined in generally accepted dictionaries. Words used in the present

tense include the future and the plural includes the singular: the word “structure” includes the word “building”, the word “shall” is intended to be mandatory: “occupied” or “used” shall be considered as though followed by the words “or intended, arranged or designed to be used or occupied.”

Accessory Use and Structure. A use of or structure on a lot or portion of a lot customarily incidental and subordinate to the lot or structure and not changing the character of the principal use of the structure or lot.

Agricultural Data Statement. An identification of farm operations within an agricultural district located within five hundred feet of the boundary of property upon which a Subdivision is proposed, as provided in Section 305-a of the Agriculture and Markets Law. An agricultural data statement shall include the following information: the name and address of the applicant; a description of the proposed Subdivision and its location; the name and address of any owner of land within the agricultural district, which land contains farm operations and is located within five hundred feet of the boundary of the property upon which the Subdivision is proposed’ and a tax map or other map showing the site of the proposed Subdivision relative to the location of farm operations identified in the agricultural data statement.

Agriculture. The management of land for agriculture and crops; raising of cows, horses, pigs, poultry, and other livestock, and horticulture of orchards; including the construction, alteration, or maintenance of fences, agricultural roads, agricultural drainage systems and farm ponds, barn, stable, shed, soil, garage, fruit and vegetable stand, or other building or structure directly and customarily associated with agricultural use and production.

Buildable Land. That portion of a lot which is suitable for building structures and locating septic disposal facilities, excluding wetlands and watercourses, slopes exceeding fifteen percent (15%), and flood hazard areas as mapped on the Federal Emergency Management Agency’s Flood Insurance Rate Map.

Business or Institutional Use. A non-agricultural involving the sale or rental of goods, services, or commodities, either on a retail or whole basis, or the provision of services or entertainment, whether or not for profit, including without limitation stores, campgrounds, tourist attractions, motels, clinics, offices, restaurants, resorts, service and gas stations, and industry. As defined in this land use law, business or institutional use shall generally refer to any non-residential, non-agricultural use of land for commercial, educational, charitable, religious, or scientific purposes.

Distances. Distances shall mean the shortest horizontal linear distance from the nearest point of a regulated activity to the mean high watermark of the nearest watercourse or the edge, margin or top of a precipitous bank adjoining forming the mean high water mark of a watercourse. Additionally distances shall mean the shortest footage between two or more objects.

Dwelling Unit. One or more rooms constituting a separate independent housekeeping unit establishment with cooking, living, sanitary, and sleeping facilities for the use of no more than one family.

Farm Operation. Land used in agricultural production, farm buildings, equipment, and farm residential buildings.

First Order Stream. A first order stream is a stream which is mapped as a continuous blue line on the US Geological Survey Reading Center Quadrangle Map, 1950 edition revised 1978, 1:24,000 scale.

Flood Plain shall mean those areas designated by either the New York State Department of Environmental Conservation or the United States Federal Emergency Management Agency as likely to flood within one hundred years.

Forestry. The management, including logging, of a forest, woodland, or plantation, and related research and educational activities, including construction, alteration, or maintenance of woodroads, skidways, landings, fences, forest drainage systems, barn, shed, garage, temporary sawmill sites, research, and educational or administrative building or cabin directly and customarily associated with forestry use.

Industry. The manufacture and production or assembly of goods or materials.

Institutional Use. See Business or Institutional Use.

Junk. Any worn-out, cast-off, discarded, or neglected article or material which is ready for destruction or has been collected or store for salvage or conversion to another use.

Junkyard. The use of two hundred (200) square feet or more of area on any lot outside a structure for the storage or collection of junk or junk cars.

Lot or Parcel. An area or plot of land with definite boundaries, all parts of which are owned by the same person(s) or entities, the boundaries of which were established either by the filing of a Subdivisions Plat or by the recording of a deed.

Marina. Any facility for the docking or stage of boats which contains more than three docks, slips, or lifts.

Mobile Home. A self-contained dwelling unit that is designed to be transported in one or more sections on its own wheels or those of another vehicle, that may contain the same water supply, sewage disposal, and electrical system as immobile housing, and that is used for either permanent or seasonal occupancy. A dwelling unit that is constructed in sections and transported and assembled on the side with a solid foundation is not considered a Mobile Home.

Mobile Home Park. Parcel of land under single ownership which is designed and improved for the placement of two or more Mobile Homes upon units thereof.

Multi-Family Dwelling. A residential building containing three (3) or more dwelling units.

Non-conforming Lot. A lot of record which does not comply with the dimensional requirements of this land use law (see Chapter 7).

Non-conforming Structure. A structure which contains a permitted use, but which does not meet the dimensional requirements of this land use law, and which was lawful when constructed (see Chapter 7).

Non-conforming Use. Any use lawfully existing prior to and at the time of the adoption of amendment of this land use law or any preceding local law or ordinance, which is not permitted by right or does not conform with the provisions of this land use law. A pre-existing lawful use which is allowed only by Special Permit under this land use law shall be considered a non-conforming use until such time as a Special Permit is granted for it (See Chapter 7.)

Occupied Outdoor Area. That portion of a lot used for driveways, parking lots and outdoor storage.

Resource Extraction. Use of more than 15,000 square feet of land for the purpose of quarrying, extracting, and selling stone, minerals, oil, gas, sand, and/or gravel, not including the process of preparing land for construction of a structure for which a Building Permit has been issued.

Setback. The distance in feet from a property line or a street centerline to a structure on a lot.

Sign. Any billboard, signboard, inscription, pennant, insignia, or other structure or device composed of lettered or pictorial material that is placed for outdoor display (including inside a window), used as advertisement, announcement, or direction.

Sign, Commercial. A sign advertising a product, use, service, or activity sold or conducted for private financial gain.

Single-Family Dwelling. A detached building containing one dwelling unit, not including a Mobile Home.

Solid Waste Management Facilities. Solid Waste Management Facilities are all those uses specified in 6 NYCRR 360, Subparts 360-2 through 360-14.

Subdivisions. Any division of land into two or more lots, parcels, or sites, whether adjoining or not, for the purpose of sale, lease, license, or any form of separate ownership or occupancy.

Subdivisions Regulations. The Town of Reading Land Subdivisions Regulations.

Town Law. The Town Law of the State of New York.

Wetland. Any land which is subject to periodic or continual inundation by water or which contains hydric soils as defined by the Natural Resources Conservation Service of the U.S. Department of Agriculture.

APPENDIX I

REVIEW OF SPECIAL PERMIT SITE PLANS

The Planning Board shall review Site Plans for all Special Permit applications in order to determine the probable impact of the proposed use on the surrounding area and to impose appropriate conditions on the siting, location, and design of the proposed use. The submission requirements for Special Permit Site Plans are more elaborate than those for Site Plan Only review because of the greater potential impact of Special Permit uses. Some of the information listed below may also be required by the Planning Board for Site Plan Only review where such information is necessary to conduct an informed review.

I.1 Required Information

A Special Permit Site Plan shall include plans and descriptive information sufficient to clearly portray the intentions of the applicant. Site Plans shall be prepared by a registered professional engineer, architect, or landscape architect, and shall include the following:

- a. Name of the project, boundaries, date, north arrow, and scale of the Site Plan.
- b. Name and address of the owner of record, developer, and seal of the engineer, architect, or landscape architect.
- c. A vicinity map drawn at the scale of two thousand (2,000) feet to the inch or larger that shows the relationship of the proposal to existing community facilities which affect or serve it, such as roads, shopping areas, schools, etc. The map shall also show all properties, subdivisions, streets, and easements within five hundred (500) feet of the property. Such a sketch may be superimposed on a United States Geological Survey map of the area.
- d. A Site Plan drawn at a scale of forty feet to the inch (1" = 40') or such other scale as the Planning Board may deem appropriate, on standard 24" x 36" sheets, with continuation on 8 1/2" x 11" sheets as necessary for written information.
- e. The location and use of all existing and proposed structures within the property, including all dimensions of height and floor area, all exterior entrances, and all anticipated future additions and alterations.
- f. The location of all present and proposed public and private ways, off-street parking areas, driveways, outdoor storage areas, sidewalks, ramps, curbs, paths, landscaping, walls, and fences. Location, type, and screening details for all waste disposal containers shall also be shown.
- g. The location, height, intensity, and bulb type (sodium, incandescent, etc.) of all external lighting fixtures. The direction of illumination and methods to eliminate glare onto adjoining properties must also be shown.
- h. The location, heights, size, materials, and design of all proposed signs.
- i. The location of all present and proposed utility systems including:
 1. Sewage or septic system;
 2. Water supply system;
 3. Telephone, cable, and electrical systems; and
 4. Storm drainage system including existing and proposed drain lines, culverts, catch basins, headwalls, endwalls, hydrants, manholes, and drainage swales.

- j. Plans to prevent the pollution of surface or groundwater, erosion of soil both during and after construction, excessive runoff, excessive raising or lowering of the water table, and flooding of other properties, as applicable.
- k. Existing and proposed topography at two (2) foot contour intervals, or such other contour interval as the Planning Board shall specify. All elevations shall refer to the nearest United States Costal and Geodetic Bench Mark. If any portion of the parcel is within the 100-year floodplain, the area will be shown, and base flood elevations given. Areas shall be indicated within the proposed site and within fifty (50) feet of the proposed site where soil removal or filling is required, showing the approximate volume in cubic yards.
- l. A landscape plan showing all existing natural land features that may influence the design of the proposed use such as rock outcrops, single trees eight (8) or more inches in diameter four feet above the ground, forest cover, and water resources, and all proposed changes to these features including sizes and types of plants. Water resources include ponds, lakes, wetlands and watercourses, aquifers, floodplains, and stormwater retention areas.
- m. Traffic flow patterns within the site, entrances and exits, and loading and unloading areas, as well as curb cuts on the site and within one hundred (100) feet of the site. The Planning Board may, at its discretion, require a detailed traffic study for large developments or for those in heavy traffic areas, which shall include:
 - 1. The projected number of motor vehicle trips to enter or leave the site, estimated for daily and peak hour traffic levels;
 - 2. The projected traffic flow pattern including vehicular movements at all major intersections likely to be affected by the proposed use of the site;
 - 3. The impact of this traffic upon existing abutting public and private ways in relation to existing road capacities. Existing and proposed daily and peak hour traffic levels and road capacity levels shall also be given.
- n. For new construction or alterations to any structure, a table containing the following information shall be included:
 - 1. Estimated area of structure to be used for particular uses such as retail operation, office, storage, etc;
 - 2. Estimated maximum number of employees;
 - 3. Maximum seating capacity, where applicable; and
 - 4. Number of parking spaces existing and required for the intended use.
- o. Elevations at a scale of one-square inch equals one foot ($\frac{1}{4}'' = 1'$) for all exterior facades of the proposed structure(s) and/or alterations to or expansions of existing facades, showing design features and indicating the type and color or materials to be used.
- p. For large or environmentally intrusive developments, the Planning Board may require soil logs, test well and percolation test results, and storm runoff calculations.
- q. Plans for disposal of construction and demolition waste, either on-site or at an approved disposal facility.

1.2 Waivers

In the case of Special Permit uses that are likely to have a minimal impact on the surrounding area, the Planning Board may waive information requirements in Section I.1 above, as it deems appropriate.

1.3 Criteria

The Planning Board, in reviewing Special Permit Site Plans, shall consider the criteria set forth below. The Planning Board may adopt or recommend illustrated design guidelines to assist applicants in complying with this Section I.3.

a. Layout and Design

1. All structures in the plan shall be integrated with each other and with adjacent structures, and shall have convenient pedestrian and vehicular access to and from adjacent properties.
2. Individual structures shall be compatible with each other and with traditional structures in the surrounding area in architecture, design, massing, materials, and placement, and shall harmonize with traditional elements in the architectural fabric of the area.
3. Where appropriate, setbacks shall maintain and continue the existing setback pattern of surrounding properties.
4. The Planning Board shall encourage the creation of landscaped parks or plazas easily accessible by pedestrians.

b. Landscaping

1. Landscaping shall be an integral part of the entire project area, and shall buffer the site from and/or integrate the site with the surround areas, as appropriate.
2. Primary landscape treatment shall consist of native plant communities, including shrubs, ground cover, and shade trees, and shall combine with appropriate walks and street surfaces to provide an attractive development pattern.
3. Where appropriate, existing trees and other vegetation shall be conserved and integrated into the landscape design plan.
4. If deemed appropriate for the site by the Planning Board, shade trees at least six (6) feet shall be planted and maintained at twenty (20) to forty (40) foot intervals along roads, at a setback distance acceptable to the Highway Superintendent.

c. Parking, Circulation, and Loading

1. Roads, driveways, sidewalks, off-street parking, and loading space shall be safe, and shall encourage pedestrian movement.
2. Vehicular and pedestrian connections between adjacent sites shall be provided to encourage pedestrian use and to minimize traffic entering existing roads. The construction of service roads and new public street to connect adjoining properties shall be required by the Planning Board, where appropriate.
3. Off-street parking and loading requirements of this land use law shall be fulfilled.
4. Access from and egress to public highways shall be approved by the appropriate Highway Department, including Town, County, State, and Federal, to the extent that said Highway Department or Departments have jurisdiction over such access.
5. All buildings shall be accessible by emergency vehicles.

d. Miscellaneous Standards

1. Materials and design of paving, light fixtures, retaining walls, fences, curbs, benches, etc., shall be attractive and easily maintained.
2. The light level at the lot line shall not exceed two-tenths (0.2) footcandle, measure at ground level. To achieve this, luminaries shall be shielded to prevent light from shining beyond the lot lines onto neighboring properties or public ways. Where residential uses adjoin business or institutional uses, light standards shall be restricted to a maximum of twenty (20) feet in height.
3. Drainage of this site shall recharge ground water to the extent practical, and surface water flowing off-site shall not adversely affect drainage on adjacent properties or public roads.
4. Additional Site Plan requirements and standards for review set forth in other Sections of this land use law shall be fulfilled.
5. Requirements for proper disposal of construction and demolition waste shall be fulfilled, and any necessary permits or agreements for off-site disposal shall be provided to the Planning Board.

Attachment 2
Comprehensive Plan for the Town of Reading

COMPREHENSIVE PLAN OF THE

TOWN OF READING, NEW YORK

prepared by:
JOEL S. RUSSELL
WOODLEA ASSOCIATES
SALT POINT, NEW YORK
(914) 266-3150

TOWN OF READING COMPREHENSIVE PLAN

INTRODUCTION

This plan is based on the results of a mail survey of registered voters in the town, conducted in 1991, a 3 day public workshop (Charrette) held in June 1993, and a number of public meetings held from time to time over the past several years. All of these activities were conducted by the town to attract maximum public participation from all segments of the community. This comprehensive plan summarizes the goals agreed upon by most Reading residents and outlines preliminary community plans.

INTRODUCTORY OBSERVATIONS

The Town of Reading is a diverse community which includes a wide range of different land uses. Most of its population lies within the eastern and southeastern parts of the town, near Seneca Lake and the Village of Watkins Glen. The portion of the Town which is inside the Village of Watkins Glen is not being actively considered in this planning process, since it is within the planning and zoning jurisdiction of the Village.

Reading's development has been and will continue to be shaped by its infrastructure. Two state highways (14 and 14A) and two active freight railroad lines are located in the eastern portion of the Town. The Watkins Glen water and sewage systems extend a short distance beyond the Village limits into the Town. With excess capacity in the systems, these water and sewer lines represent an important resource for attracting and concentrating new development.

The Village of Watkins Glen is limited by topography and wetlands from expanding in any direction except to the northwest, into Reading. This has and will continue to place development pressure on the southeastern corner of the Town. Reading therefore needs to develop a strategy for incremental extension of water and sewer lines to serve high intensity land uses, while protecting the lakeshore and the rural open space further away.

Reading may also need water and sewer infrastructure in the hamlets of Reading Center and Irelandville, but this will be more difficult to provide because of their distance from Watkins Glen. Reading Center, which needs infrastructure more, is also much further away. This makes it unlikely that an extension of water and sewer services to Reading Center will be economically feasible.

Reading has a well-balanced tax base because of such non-residential properties as the Nobel-Akzo salt plant, the Texas Eastern gas pipeline facilities, the two railroad lines, and several tourist businesses. In addition, Reading has considerable woodland and some farmland, although it appears that much farmland has been growing back to woods.

Geographically, Reading functions in many ways as an extension of Watkins Glen, with many residents served by the Watkins Glen Post Office, and most served by the Watkins Glen school system and fire company. The character of the western part of Reading is more rural and sparsely populated than the eastern half. However, Reading's people expressed a strong desire to become a more cohesive community with a stronger identity.

Southeastern Reading is suitable for large-scale development that could change its character because of the availability of infrastructure and easy access to Watkins Glen. Without any planning regulations, Reading is therefore vulnerable to the impacts of such development. Recognizing this, many residents feel a sense of urgency about planning in order to make development fit into Reading's existing character.

COMMUNITY GOALS

Residents of the Town of Reading expressed the following as community goals:

1. Strengthen the sense of community and improve communication within the Town.
2. Where possible, keep agriculture economically healthy.
3. Preserve open space.
4. Allow flexibility of uses without harming neighbors.
5. Encourage non-polluting small business and industry growth that provides year-round employment.
6. Maintain an economically diverse community with affordable housing.
7. Revitalize old buildings and hamlets with businesses and housing.
8. Discourage large-scale development that changes the Town's character.
9. Protect Seneca Lake water quality and other important environmental resources.
10. Balance the property rights of individuals with community interests, maintaining rural traditions of freedom of land use.
11. Increase citizen involvement in local government.
12. Keep the Town rural, with moderate growth.
13. Establish a flexible system to regulate development.
14. Provide better access to the lake.
15. Improve the appearance of the Town.

COMMUNITY PLAN

The challenge of implementing a community plan is to reconcile development and conservation objectives in a way that respects rural traditions. A plan does not need to spell out specific land uses for each portion of a town. Rather, it can establish an appropriate framework for making decisions on land use and development, striking a balance between landowners' property rights and community goals.

The most important elements of a plan for Reading are flexibility and responsiveness to individual and community needs and desires. Based upon the goals and priorities expressed by residents of Reading at the charrette, Reading appears to be ready to begin drafting a set of development regulations tailored to its needs. This report outlines the major points that such a plan and regulations would cover. The Town could choose some combination of these elements, modify them, and/or invent new ones.

1. Allow one-family, two-family, agricultural, and most small-scale business uses "by right" throughout the town. Small-scale businesses can be defined by square footage (for example, under 2,000 square feet of floor space and 5,000 square feet of total coverage of land in active use). Businesses that manufacture, store, use, or dispose of hazardous materials, tires, junk, etc., would not be allowed by right, regardless of their size.
2. Allow new medium-scale businesses (up to three times the size of the small-scale ones mentioned above) by right, subject only to site plan review by the Planning Board. Site plan review would cover issues such as road access, traffic impact, parking, building layout, appropriateness of design, drainage, waste disposal, environmental impact, provision of buffers, minimum distance from nearby residences, and protection of neighbors from harmful effects of the use. Existing medium-scale businesses would be "grandfathered," but their expansion by more than 25% would require site plan approval.
3. Allow new large-scale business uses, as well as those that manufacture, store, use or dispose of hazardous materials, tires, junk, solid waste, etc. only by special permit, which would include site plan review. In determining whether to grant a special permit, the planning board would follow specific criteria relating to the suitability of the use to its proposed location, its impact on the surrounding area, the availability of rail, highway, water, and sewer infrastructure, its proximity to existing industrial uses, its compatibility with the town goals listed above, its impact on town infrastructure and fiscal capacity, and its environmental and social impact. Existing large-scale businesses would be "grandfathered," but expanding them by more than 25% would require a special permit. If legally possible, out-of-town waste would be precluded from being dumped at a facility in the Town of Reading. Conditions necessary to assure fulfillment of developers' infrastructure construction responsibilities would be imposed.
4. Allow multi-family use of existing buildings by right. New buildings for multi-family use (3 or more units) would be allowed with site plan review for up to 5 units. For more than 5 units, a special permit would be required.
5. Allow individual mobile homes meeting state and federal standards for new mobile home construction by right. All others (including two or more homes on a lot or in a subdivision) would require site plan review. Mobile home parks with more than 10 units would require special permits.

6. Establish density guidelines (not minimum lot sizes) limiting the number of residential units allowed by right within a given tract of land to, say, one unit per two acres in areas that lack water and sewer service. This could be varied by special permit, provided that all applicable impact criteria are satisfied. Areas with water and sewer could have considerably higher density, provided that they satisfy special permit performance standards.
7. Establish minimum setbacks from lot lines for by-right uses. These could be varied according to the circumstances in the course of site plan and special permit review.
8. Pass subdivision regulations to allow the planning board to review land subdivisions. Review of subdivisions of less than 5 lots would be expedited as "minor subdivisions." Subdivision regulations would enable the planning board to ensure that subdivided land was suitable for development, that proper roads are constructed, and that such roads are either properly constructed or bonded prior to final approval. Narrow, unpaved country roads would be allowed with a suitable base and drainage, provided that the developer committed to permanent low density. Clustering would be encouraged but not required unless water and sewer service is available.
9. Offer the option of resolving all site plan, special permit, and subdivision controversies through a mediation process involving the applicant and neighbors. The agreed settlement would be submitted to the planning board for approval.
10. Create a lake area "overlay" with more stringent criteria for land lying within 1/2 mile of Seneca Lake or within 100 feet of designated major streams flowing into the lake (see SLPWA recommendations).
11. Adopt storm water and erosion control guidelines for site plan and special permit uses (see SLPWA recommendations).
12. Establish a volunteer community organization to do some or all of the following:
 - ▶ Publish a community newsletter and directory of businesses.
 - ▶ Seek funds for housing and building improvements.
 - ▶ Seek funds for the construction or extension of water and sewer infrastructure.
 - ▶ Investigate possible sites and funding for a lakefront town park.
 - ▶ Plan for tree planting and other civic improvements.
 - ▶ Sponsor a community day social event and organized flea market.
 - ▶ Develop a voluntary community consultation process (or design guidelines) so that new development is consistent with the special character of the Town.
 - ▶ Investigate possibilities for hamlet revitalization, business retention and expansion, and attraction of new businesses.
13. Improve administration of the Uniform Fire Prevention and Building Code (possibly sharing staff with another town) and use the same personnel to administer a land use law. Interpret the Code in a flexible manner to encourage reuse of old buildings.
14. Work with the Farm Bureau and Cornell Cooperative Extension to establish an agricultural district to provide tax relief and right-to-farm protection for farmers.

Phase 1 Preliminary Assessment

Vegetation and Wildlife

Seneca Compressed Air Energy Storage Project

New York State Electric and Gas

**Town of Reading
Schuyler County, New York**

**Environmental Resources Management
399 Boylston Street
Boston, MA 02116**

TABLE OF CONTENTS

1.0	VEGETATION AND WILDLIFE BACKGROUND	1
1.1	VEGETATION COMMUNITIES	1
1.1.1	Threatened and Endangered Species	3
1.2	WILDLIFE AND WILDLIFE HABITAT	4
1.2.1	Threatened and Endangered Species	7
2.0	POTENTIAL IMPACTS	8
2.1	VEGETATION	8
2.2	WILDLIFE AND HABITATS	9
2.2	MITIGATION MEASURES	11
3.0	REFERENCES	13

FIGURES

FIGURE 1 TERRESTRIAL ECOLOGICAL ZONES

ATTACHMENT 1

PHOTO DOCUMENTATION

ATTACHMENT 2

AGENCY CORRESPONDENCE

1.0

VEGETATION AND WILDLIFE BACKGROUND

This report presents a preliminary assessment of the terrestrial natural resources within the vicinity of the Seneca compressed air energy storage (CAES) Project and identifies potential impacts from the construction and operation of the Project on these resources. The proposed CAES Project will be a 130 to 180 MW compressed air energy storage plant that consists of an electrically driven compression cycle and a turbine expansion cycle that will produce electricity. The CAES plant is intended to provide sufficient storage to allow full operation during peak demand time periods in support of transmission system and market needs (approximately 10 hours per day). The CAES Project will be located west of Seneca Lake in Reading, Schuyler County, New York.

Terrestrial ecological resources are defined as native or naturalized plants and animals and the habitats in which they exist. The terrestrial ecological resources within the Project area have been preliminarily identified through a desktop review and an initial site walkover by an ERM scientist. The types of vegetation, wildlife, wildlife habitat, and wildlife travel corridors observed are discussed herein. Additionally, information available from the New York State Department of Environmental Conservation (NYSDEC) and the United States Fish and Wildlife Service (USFWS) has been reviewed for the presence of endangered or threatened species in the vicinity of the CAES Project area.

1.1

VEGETATION COMMUNITIES

The CAES Project lies within the Zone A Appalachian Plateau A04 Finger Lake Highlands Ecological Zone in West-Central New York (NYSGIS, 1990; Figure 1). The dominant vegetation type historically was northern hardwood forest. However, agricultural clearing has left the region approximately 15 percent forested (USDA, 2010). The area can be characterized primarily as agricultural croplands interspersed with parcels of mixed deciduous and coniferous forest; emergent, forested, and scrub-shrub wetlands; hedgerows; and abandoned cropland. Photographs of the natural setting surrounding the proposed CAES Plant Facility Site, underground pipeline corridor to Seneca Lake and the overhead power line route to the substation off County Route 28 were taken during preliminary field reconnaissance on September 2, 2011 and are provided in Attachment 1, Photodocumentation.

CAES Plant Site

The vegetation community on the proposed CAES plant site includes early successional species on a former agricultural field with one hedgerow. The field appears to no longer be actively managed for agriculture, based on the presence of small shrubs and the dominant herbaceous vegetation, including goldenrod (*Solidago* spp.), Queen Anne's lace (*Daucus carota*), and a variety of grasses. At least two emergent wetlands and a small pond are located within this area, as described in the separate Wetlands section of this Phase 1 project. Wetland species observed on the CAES plant site include rice cutgrass (*Leersia orzoides*), green bulrush (*Scirpus atrovirens*), soft rush (*Juncus effusus*), purple loosestrife (*Lythrum salicaria*), lurid sedge (*Carex lurida*), and water plantain (*Alisma* sp.). Hedgerow tree species typically include sugar maple (*Acer saccharum*), red maple (*Acer rubrum*), white ash (*Fraxinus americana*), shagbark hickory (*Carya ovata*), basswood (*Tilia americana*), boxelder (*Acer negundo*), black locust (*Robinia pseudoacacia*), and oak species (*Quercus* spp.).

Both herbaceous and shrub invasive species, including purple loosestrife, reed canarygrass (*Phalaris arundinacea*), honeysuckle shrubs (*Lonicera* sp.), and multiflora rose (*Rosa multiflora*) were noted in this field environment and are listed on the New York Interim Invasive Species Plant List. The abandoned field is bordered to the south and east by forested areas, as described in the following section and an operating vineyard occurs to the north (across State Route 14A). To the west, the field is separated from a nearby forested habitat by an active railroad corridor.

Proposed Underground Pipeline Route (and Pump House)

The mixed deciduous and coniferous forest located to the south and southeast of the proposed CAES plant site extends along the proposed underground pipeline route. These forests are generally dominated by northern hardwood species, the historic dominant forest type in the region (USDA, 1993). Oaks (*Quercus* spp.), maples (*Acer* spp.), white ash, and eastern hemlock (*Tsuga canadensis*) are typical species in these forests. Successional growth species are interspersed throughout the wooded areas. There are occurrences of plantation species in the region including scotch pine (*Pinus sylvestris*) and red pine (*Pinus resinosa*), mixed with native species including trembling aspen (*Populus tremuloides*), grey birch (*Betula populifolia*), shagbark hickory, basswood, boxelder, black locust, and white pine (*Pinus strobus*).

The forest extends from the proposed CAES plant site east to Route 14, and also continues east from Route 14 to Seneca Lake. East of Route 14, the vegetation communities vary with a patchwork of open field and forested areas along the relatively steep slope that extends to Seneca Lake. Several intermittent and perennial streams cross through these forested and open field habitats, including a New York State Department of Conservation (NYSDEC) Class C stream that approximately parallels the proposed underground pipeline route between Route 14 and the proposed pump house location on Seneca Lake. Small pockets of pooled water and hydrophytic species such as cattail (*Typha* spp.) are scattered where the streams intersect existing unpaved access roads throughout a salt mining road network located between State Route 14 and Seneca Lake. Along the shore of Seneca Lake at the approximate location of the proposed underground water intake and discharge pipelines and the pump house, the vegetation community shifts from a narrow fringe of woody vines, small shrubs, and herbaceous plants to a maintained grass area that surrounds existing US Salt infrastructure. An assessment of the presence of submerged aquatic vegetation has not yet been conducted, but is recommended in the area where the water intake and wastewater discharge structures and associated pipelines are proposed within Seneca Lake.

Proposed Overhead Power Line Route and Substation

Similar to the proposed underground pipeline routes, the overhead power line route crosses through mixed deciduous and coniferous forest, which is bisected by an active railroad corridor west of the proposed CAES plant site. One small emergent wetland, dominated by sensitive fern (*Onoclea sensibilis*), is located along the aboveground power line route in the south, southwestern corner of the field containing the proposed CAES plant site. Vegetation in the forested area is similar to typical species composition for the region as described above. The proposed substation location consists of a thin band of maintained grasses along County Route 28 with a shrub and vine community extending west to the existing electric utility right-of-way.

1.1.1 *Threatened and Endangered Species*

The NYSDEC Environmental Resource Mapper (Mapper) was used to determine if the CAES Project boundary intersected with any known locations of threatened and endangered (T&E) plant species. The results of this desktop review indicate no known occurrences of T&E plant species in the immediate vicinity of the Project's footprint. Thus, it is

unlikely that such species would occur in the vicinity of the project area. A letter requesting confirmation of this information was submitted to the New York State Natural Heritage Program and a written response was received (Attachment 2, Agency Correspondence). The New York State Natural Heritage Program response indicates that no rare or state-listed animals and plants, significant natural communities, or other significant habitats occur on or in the vicinity of the CAES Project. The only noted finding was one winter waterfowl concentration area, which is discussed below.

A review of the USFWS website identified Leedy's roseroot (*Rhodiola integrifolia* ssp. *leedyi*) as a threatened species in Schuyler County (USFWS, 2011). Two known occurrences of Leedy's Roseroot have been identified in New York State and they are both in Schuyler County. These locations are: 1) the Glenora Cliffs along the west shore of Seneca Lake and 2) a single plant located in Watkins Glen State Park.

Approximate locations of the Hamlet of Glenora and Watkins Glen State Park are depicted in the inset on Figure 1. The exact location of the Glenora Cliffs location was not identified in publicly available materials; however, the Hamlet of Glenora is located approximately 5 miles north of the proposed CAES plant site. Watkins Glen State Park is located approximately three miles south of the project footprint. Therefore, these two known populations do not intersect the Project footprint. These assumptions are supported by the letter from New York State Natural Heritage Program which identifies no plant species of concern in the vicinity of the CAES project.

1.2 WILDLIFE AND WILDLIFE HABITAT

A preliminary field reconnaissance was conducted on September 2, 2011 to view the general wildlife habitats present within the CAES Project footprint.

CAES Plant Site

The wildlife habitats on and surrounding the CAES plant site can be described as open field bordered by forested habitat. Wildlife species that thrive in edge habitat are likely to be present at the CAES plant site. These species include white-tailed deer (*Odocoileus virginianus*), eastern cottontail (*Sylvilagus floridanus*), woodchuck (*Marmota monax*), raccoon (*Procyon lotor*), eastern wild turkey (*Meleagris gallopavo silvestris*), red fox (*Vulpes vulpes*), eastern chipmunk (*Tamias striatus*), grey squirrel (*Sciurus carolinensis*), red squirrel (*Tamiasciurus hudsonicus*), and numerous species of bats, moles, mice, rats, and shrews. Additionally, species of birds, insects, amphibians, and reptiles most likely utilize the project area for habitat periodically throughout the year.

Wildlife species known to occur in emergent wetlands and ponds include amphibians, including frogs and salamanders, as well as snakes, turtles, and a variety of invertebrates.

Proposed Underground Pipeline Route (and Pump House)

Forest habitat extends from the proposed CAES plant site east to Route 14, and also continues east from Route 14 to Seneca Lake. East of Route 14, the environment consists of a patchwork of open field and forested areas along the relatively steep slope down to Seneca Lake. Several intermittent and perennial streams cross through these forested and open field habitats, including a mapped NYSDEC stream with a combination of bedrock and unconsolidated bed and banks that approximately parallel the proposed underground pipeline routes between Route 14 and the proposed pump house location on Seneca Lake. Forested areas provide valuable habitat to many animals commonly found in agricultural areas. Many wildlife species are dependent on forest communities for food and shelter, and streams are an important water source for wildlife. Annual mast crops such as acorns and beech nuts often supply wildlife with essential nutrients to survive the winter. The forest also provides a refuge for wildlife as protection from predation. The forest and open fields between Route 14 and Seneca Lake contain evidence of industrial uses, including overhead power lines, and abandoned aboveground pipelines that once supported the salt mining industry in this location. At the proposed pump house location, the habitat shifts to the shore of Seneca Lake, including the unconsolidated material along the lake bank.

Streams are also an integral part of the ecosystem in this region. Several tributaries to Seneca Lake are located in close proximity to the CAES Project site and the proposed linear corridors cross these streams in

multiple locations. Streams are addressed in more detail in the Water Quality report of this Phase 1 project.

The shore of Seneca Lake in the vicinity of the proposed pump house shows evidence of prior disturbance, with the existence of several structures located on the immediate shore of the lake. The shore of the lake provides habitat for waterfowl. The proposed water intake and wastewater discharge structures will be located in the lake bed of Seneca Lake that is a lacustrine habitat known to contain a variety of aquatic species, which are described in the separate Water Resources report of the Phase 1 project.

Overhead Power Line Route and Substation

The forested area along the overhead power line route is bisected by an active railroad corridor that runs approximately parallel to County Route 28. Further west, the habitat is similar to the forested habitat description and wildlife usage discussed above for the underground pipeline route. The proposed substation is located in an area of shrub land. Shrub lands in this region are generally comprised of former agricultural fields where crops are no longer planted. These areas commonly provide the densest vegetation growth and cover due to the lack of shade from a canopy. This provides habitat required by many species of ground- or low-bush nesting birds. Additionally, many of the common vegetative shrub species produce fruit, providing foraging opportunities for many wildlife species. This habitat is typical within electric utility right-of-way corridors, one of which is located to the west immediately adjacent to the substation location.

Wildlife Corridors

Hedgerows in agricultural areas provide habitat for many wildlife species, as well as creating a connective corridor between wooded lots. They provide important pathways for the movement of wildlife species, allowing them to reach isolated forest patches across a matrix of open agricultural fields. Streams with undeveloped riparian buffers also act as corridors for the movement of wildlife. Narrow forested areas linking larger forested areas also function as wildlife corridors. The CAES Project footprint intersects very few hedgerows, but does cross larger parcels of forested area and several streams with vegetated riparian areas. The species anticipated to utilize these areas are common wildlife species typical in the region. Larger expanses of forested and riparian areas are prevalent throughout the general vicinity of the CAES Project.

1.2.1

Threatened and Endangered Species

The NYSDEC Mapper was utilized to identify state-listed threatened or endangered (T&E) animal species that have potential to occur near the CAES Project site. The Mapper tool identified no T&E animal species within the Project's vicinity. A separate listing of the Endangered, Threatened and Special Concern Fish and Wildlife Species of New York State and their habitat ranges, identifies Schuyler County within the range of the following four avian and bat species:

- short-eared owl (*Asio flammeus*)
- Henslow's sparrow (*Ammodramus henslowii*)
- northern harrier (*Circus cyaneus*)
- Indiana bat (*Myotis sodalis*)

Based on the correspondence received from the New York State Natural Heritage Program, a Seneca Lake waterfowl winter concentration area is the only rare or state-listed animals, significant natural communities, or other significant habitats that occurs on or in the vicinity of the CAES Project (Attachment 2). This area has a New York State ranking of S3S4, Vulnerable. These rankings are defined as follows:

- S3 Ranking = Typically 21 to 100 occurrences, limited acreage, or miles of stream in New York State.
- S4 Ranking = Apparently secure in New York State.

Based on the information provided by the Natural Heritage Program, the four protected species listed above with habitat ranges in Schuyler County are not anticipated to be within the vicinity of the CAES Project.

A review of the USFWS database of federally listed endangered and threatened species and candidate species revealed no federally protected animal species known to occur within Schuyler County (Attachment 2).

2.0

POTENTIAL IMPACTS

Impacts to vegetation and wildlife from construction and operation of the CAES Project will vary across the Project area, depending on the vegetation and wildlife communities present combined with the type of duration of activity proposed. A preliminary assessment of anticipated impacts to vegetation and wildlife is presented below.

2.1

VEGETATION

CAES Plant Site

The open-field habitat on the parcel where the CAES plant will be located will be impacted by the clearing of vegetation and replacement with the industrial facility and resultant impervious surfaces. In addition to the open field habitat, a small wetland and pond area will also be converted to a developed industrial environment, resulting in the loss of those vegetation communities. Given the relatively small footprint (~20 acres) of the CAES plant as compared to the surrounding natural environments within the Finger Lakes Highland Ecological Zone, these impacts to open field and wetland vegetation are anticipated to be minor.

Underground Pipeline Route, Overhead Power Line and Pump House

The linear corridors where underground pipelines and overhead power lines will be installed will result in clearing vegetation in areas of mixed deciduous and coniferous forest, open fields, and riparian areas. Most of the linear corridor is forested areas; therefore, construction will result in the removal of the tree canopy and successional replacement with shrub and herbaceous habitats. Removal of the overstory will create new space and light conditions that will foster growth of different types of vegetation than existing conditions. Existing seed banks in the soil are likely to provide a source of vegetation following construction. However, additional efforts may be required to revegetate disturbed areas following construction (see Mitigation section below).

One of the key concerns when disturbing areas of land and allowing portions to re-grow is the introduction or increased occurrence of invasive species. These species tend to favor recently disturbed soil and could thrive along the linear corridors where vegetation is restored following construction. As noted above, invasive plant species were observed in the open field area. The presence of invasive species should be documented

prior to construction and, if found to be prevalent, an invasive species management plan may be required to accompany permit applications to state and federal agencies.

To comply with Section 7 of the federal Endangered Species Act, field reconnaissance by an experienced biologist is required in Phase 2 of the CAES Project to determine if the area to be disturbed along the western shore of Seneca Lake for the installation of underground pipelines, overhead power lines, and the pump house is suitable habitat for the threatened Leedy's roseroot. If no habitat is found within the footprint of the area to be disturbed, then no impacts to this protected species are anticipated to result from the Project.

As described in the Air Quality report of this Phase 1 project, the CAES Project is located in an area that is attaining US Environmental Protection Agency's primary and secondary National Ambient Air Quality Standards (NAAQS) for all the standards with the exception of ozone. The State of New York is in the ozone transport region (OTR) and is classified as a moderate nonattainment area for ozone. The "primary" standard has been established to protect the public, including children, people with asthma, and the elderly from health risk. The "secondary" standard was established to prevent unacceptable effects on public welfare, e.g., unacceptable damage to crops and vegetation, buildings and property, and ecosystems. The construction phase of this Project is anticipated to result in short-term impacts to local air quality due to construction vehicle and equipment fuel combustion emissions as well as the generation of dust from earth moving and vehicle activities. These impacts are anticipated to be minor and will cease upon completion of the construction phase with no long-term effects. During the operation and maintenance phase of the CAES Project, air emissions are not anticipated to cause a local or regional exceedance of the applicable primary and secondary NAAQS and also not contribute to further degradation of the moderate nonattainment status for ozone for the area. Therefore, no adverse impacts to vegetation are anticipated to result from Project-related air emissions at or in close proximity to the Project site.

2.2 *WILDLIFE AND HABITATS*

Wildlife may be subject to some disturbance and displacement during the construction phase of the CAES Project. Temporary impacts that would result from the construction of the CAES Project include:

- elevated noise levels in the vicinity of construction activities;
- temporary disturbance of natural habitats;
- wildlife mortality due to interactions between animals and machinery during construction; and
- temporary displacement of wildlife from habitats within and adjacent to the work zones.

These impacts are anticipated to be minor and will cease upon completion of the project. Due to the lack of unique habitat or protected species over the majority of the CAES Project area, with the exception of Seneca Lake, the common wildlife that currently uses the site is anticipated to be adaptable and utilize existing adjacent habitats. An estimate of the area of impact within Seneca Lake and its shores has not yet been prepared and will be based on the final design of the intake and discharge pipes and the intake structure itself. However, given the scale of the Project and the likely area to be impacted during the construction phase of the Project, the area is anticipated to be extremely small compared to the overall surface area (67.7 square miles) of Seneca Lake and is not expected to result in a significant adverse environmental impact to the waterfowl concentration area. The operation of the underwater structures will require specific design features to avoid impacts to waterfowl and their prey during the water withdrawal and wastewater discharge. Similarly, the wastewater discharged from the Facility will be required to comply with the NYS surface water quality standards to avoid adverse impacts to Seneca Lake water quality, which is directly related to the aquatic and terrestrial wildlife usage of the Lake. By instituting good engineering design practices, the long-term operation and maintenance of the underwater structures are not anticipated to adversely impact winter waterfowl usage of Seneca Lake.

Removal of the tree canopy within existing forested areas will result in a loss of habitat for species that utilize tall trees as foraging, perching, or nesting habitat. The new shrub and herbaceous habitat that will be created in these new open areas will provide new habitat for species that require and utilize non-forested habitat. Given the abundance and broad range of forested and open field habitats that exist nearby the CAES Project site that will not be disturbed, impacts to wildlife and wildlife corridors are anticipated to be minor.

Based on the response from the Natural Heritage Program, no detailed assessment of the four protected wildlife species with ranges that extend into Schuyler County appears to be required, because none of these species is known to occur in the vicinity of the CAES Project area.

As described in the Air Quality report of this Phase 1 project, the CAES Project is located in an area that is attaining US Environmental Protection Agency's primary and secondary National Ambient Air Quality Standards (NAAQS) for all the standards with the exception of ozone. As noted above, the "secondary" NAAQS were established to prevent unacceptable effects on public welfare, e.g., unacceptable damage to crops and vegetation, buildings and property, and ecosystems. The construction phase of this Project is anticipated to result in short-term impacts to local air quality due to construction vehicle and equipment fuel combustion emissions as well as the generation of dust from earth moving and vehicle activities. These impacts are anticipated to be minor and will cease upon completion of the construction phase with no long-term effects. During the operation and maintenance phase of the CAES Project, air emissions are not anticipated to cause a local or regional exceedance of the applicable primary and secondary NAAQS and also not contribute to further degradation of the moderate nonattainment status for ozone for the area. Therefore, no adverse impacts to wildlife are anticipated to result from Project-related air emissions at or in close proximity to the Project site.

2.2 *MITIGATION MEASURES*

Mitigation measures are anticipated to be required during both the construction phase and the post-construction phase of the Project to prevent significant impacts to vegetation and wildlife.

During the construction phase, mitigation is anticipated to include the following actions:

- implementation of standard best management practices during construction;
- minimization of construction clearances and work zones to the maximum extent practicable;
- erosion prevention and sediment control in areas of disturbed soils to prevent migration of sediments to protected resource areas (streams, wetlands, Seneca Lake);
- water management during all stream crossings and work in Seneca Lake;
- revegetation of all disturbed areas;
- dust control;
- prevention of the spread of invasive species with machinery by inspecting and cleaning as needed before moving from an area with a known invasive species population

During the post-construction phase, mitigation will likely include the following actions:

- invasive species inspection and control;
- slope stabilization inspections to prevent erosion and migration of sediments to protected resource areas
- operation of submerged water intake and wastewater discharge structures will need to avoid impacts to waterfowl and their prey.

This list of mitigation measures is not exhaustive, but is representative of what would be expected for a project of this scale. Permitting agencies will need to be consulted and may require additional mitigation measures.

New York State Geographic Information Systems (NYSGIS), 1990. GIS Data set: Boundaries of the Ecological Regions of New York State, taken from Will et. al. (1982) and Dickinson (1983).

<http://www.nysgis.state.ny.us/gisdata/inventories/details.cfm?DSID=1131>

U.S. Department of Agriculture (USDA), 2010. National Agricultural Statistics Service - 2010 New York Cropland Data Layer.

USDA, 1993. *American Forests, A History of Resiliency and Recovery*. Forest Service, FS-540. Douglas W. MacCleery. In cooperation with Forest History Society, Durham, North Carolina.

U.S. Fish & Wildlife Service (USFWS), 2011. Federally Listed Endangered and Threatened Species and Candidate Species in New York (By County). Revised June 1.

Figures

Attachment 1
Photo Documentation

PHOTODOCUMENTATION - September 02, 2011
Compressed Air Energy Storage (CAES) Project - Reading, NY
Page 1 of 3

Facing South (from Route 14A) across the open-field environment along the eastern side of the proposed CAES Plant Site.

Facing Southeast in the mixed forest along the proposed underground pipeline route between the proposed CAES plant facility and State Route 14.

PHOTODOCUMENTATION - September 02, 2011
Compressed Air Energy Storage (CAES) Project - Reading, NY
Page 2 of 3

Facing East across the mixed forest along the underground pipeline route between State Route 14 and Seneca Lake.

Facing Northwest across the Seneca Lake unconsolidated shore habitat with a fringe of woody vines and shrubs where the underground intake and discharge pipeline route are proposed.

PHOTODOCUMENTATION - September 02, 2011
Compressed Air Energy Storage (CAES) Project
Reading, NY
Page 3 of 3

Facing East through the deciduous forest toward the proposed overhead power line route between the railroad corridor and County Route 28.

Facing Southwest across the maintained grasses to the shrub area where the substation is proposed, with existing electric right-of-way in the distance.

Attachment 2
Agency Correspondence

ERM
5788 Widewaters Parkway
DeWitt, New York 13214
(315) 445-2554
(315) 445-2543 Fax
www.erm.com

23 September 2011

New York Department of Environmental Conservation
New York Natural Heritage Program Information Services
625 Broadway
Albany, NY 12233

RE: Protected Species Screening

Dear Sir or Madam:

Environmental Resources Management (ERM) is gathering data related to three locations off State Route 14A and State Route 28 in the Town of Reading, Schuyler County, New York (see enclosed map). As shown on the attached figure, the site is located west of Seneca Lake and to the north of Watkins Glen.

The purpose of this letter is to solicit information from the New York Natural Heritage Program concerning the occurrence of plants and wildlife and any endangered, threatened, proposed, or candidate species or their critical habitats on or in the vicinity of the site. If there are any occurrences, ERM requests a list of federal, state and regional protected species, or proposed species, or critical habitats and wildlife areas known or suspected to be on or in the vicinity of the project area.

Please send all correspondences concerning this matter to:

Jarrold Hughes
Environmental Resources Management
5788 Widewaters Parkway
DeWitt, New York 13214

If you have any question regarding this matter, please contact me at 315-461-7397.

Sincerely,

Jarrold Hughes
Project Scientist

enclosure: Site Location Map

DRAFT

APPROXIMATE SITE AREA

0.1 0 0.1 0.2 0.3 0.4 0.5
Miles

1:24,000

Figure 1 - Site Locus Map

SOURCE

USGS scanned topographic quad maps provided
by National Geographic Society (© 2011).

Town of Reading
Schuyl County, NY

NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION

Division of Fish, Wildlife & Marine Resources

625 Broadway, 5th Floor, Albany, New York 12233-4757

Phone: (518) 402-8935 • **Fax:** (518) 402-8925

Website: www.dec.ny.gov

Joe Martens
Commissioner

October 5, 2011

Jarrold Hughes
ERM
5788 Widewaters Pkwy
De Witt, NY 13214

Dear Mr. Hughes:

In response to your recent request, we have reviewed the New York Natural Heritage Program database with respect to an Environmental Assessment for the proposed Energy Facility Utilizing Compressed Air, site as indicated on the map you provided, located in the Town of Reading, Schuyler County.

Enclosed is a report of rare or state-listed animals and plants, significant natural communities, and other significant habitats, which our databases indicate occur, or may occur, on your site or in the immediate vicinity of your site. For most sites, comprehensive field surveys have not been conducted; the enclosed report only includes records from our databases. We cannot provide a definitive statement as to the presence or absence of all rare or state-listed species or significant natural communities. This information should not be substituted for on-site surveys that may be required for environmental impact assessment.

The enclosed report may be included in documents that will be available to the public. However, any enclosed maps displaying locations of rare species are considered sensitive information, and are intended only for the internal use of the recipient; they should not be included in any document that will be made available to the public, without permission from the New York Natural Heritage Program.

The presence of the plants and animals identified in the enclosed report may result in this project requiring additional review or permit conditions. For further guidance, and for information regarding other permits that may be required under state law for regulated areas or activities (e.g., regulated wetlands), please contact the appropriate NYS DEC Regional Office, Division of Environmental Permits, as listed at www.dec.ny.gov/about/39381.htm.

Our databases are continually growing as records are added and updated. If this proposed project is still under development one year from now, we recommend that you contact us again so that we may update this response with the most current information.

Sincerely,

Jean Pietrusiak, Information Services
NYS Department Environmental Conservation

Enc.
cc: Region 8

982

Natural Heritage Report on Rare Species and Ecological Communities

NY Natural Heritage Program, NYS DEC, 625 Broadway, 5th Floor,
Albany, NY 12233-4757
(518) 402-8935

~The information in this report includes only records entered into the NY Natural Heritage databases as of the date of the report. This report is not a definitive statement on the presence or absence of all rare species or significant natural communities at or in the vicinity of this site.

~Refer to the User's Guide for explanations of codes, ranks and fields.

~Location maps for certain species and communities may not be provided 1) if the species is vulnerable to disturbance, 2) if the location and/or extent is not precisely known, 3) if the location and/or extent is too large to display, and/or 4) if the animal is listed as Endangered or Threatened by New York State.

Natural Heritage Report on Rare Species and Ecological Communities

OTHER

Waterfowl Winter Concentration Area

NY Legal Status: Unlisted

NYS Rank: S3S4 - Vulnerable

Office Use
5657

Federal Listing:

Global Rank: GNR - Not ranked

Last Report: 1994-01-21

EO Rank: Excellent

County: Ontario, Schuyler, Seneca, Yates

Town: Benton, Dix, Fayette, Geneva - City, Geneva - Town, Hector, Lodi, Milo, Ovid, Reading, Romulus, St

Location: Seneca Lake

General Quality and Habitat: A long and narrow inland lake of glacial origin, with a mean depth of 291 ft.

1 Records Processed

More detailed information about many of the rare and listed animals and plants in New York, including biology, identification, habitat, conservation, and management, are available online in Natural Heritage's Conservation Guides at www.acris.nynhp.org, from NatureServe Explorer at <http://www.natureserve.org/explorer>, from NYSDEC at <http://www.dec.ny.gov/animals/7494.html> (for animals), and from USDA's Plants Database at <http://plants.usda.gov/index.html> (for plants).

More detailed information about many of the natural community types in New York, including identification, dominant and characteristic vegetation, distribution, conservation, and management, is available online in Natural Heritage's Conservation Guides at www.acris.nynhp.org. For descriptions of all community types, go to <http://www.dec.ny.gov/animals/29384.html> and click on Draft Ecological Communities of New York State.

Schuyler County**Federally Listed Endangered and Threatened Species and Candidate Species**

This list represents the best available information regarding known or likely County occurrences of Federally-listed and candidate species and is subject to change as new information becomes available.

<u>Common Name</u>	<u>Scientific Name</u>	<u>Status</u>
Leedy's roseroot	<i>Rhodiola integrifolia</i> ssp. <i>leedyi</i> (= <i>Sedum integrifolium</i> ssp. <i>l.</i>)	T

Status Codes: E=Endangered, T=Threatened, P=Proposed, C=Candidate, D=Delisted.

Information current as of: 10/15/2011

Phase 1 Preliminary Assessment

Visual Resources

Seneca Compressed Air Energy Storage Project

New York State Electric and Gas

**Town of Reading
Schuyler County, New York**

**Environmental Resources Management
399 Boylston Street
Boston, MA 02116**

TABLE OF CONTENTS

1	PHASE 1 PRELIMINARY ASSESSMENT VISUAL RESOURCES	1
1.1	EXISTING ENVIRONMENT	1
1.1.1	<i>Project Description and Location</i>	1
1.1.2	<i>Visual Appearance of the Project Area</i>	2
1.2	VISUAL RESOURCES ASSESSMENT APPROACH	3
1.2.1	<i>Overview</i>	3
1.2.2	<i>Viewshed Analysis</i>	4
1.3	POTENTIAL VISUAL RESOURCES IMPACTS	20
1.3.1	<i>Overview of Potential Visibility</i>	20
1.3.2	<i>Views from Key Vantage Points</i>	22
1.3.3	<i>Inventory of Aesthetic Resources</i>	37
1.4	PRELIMINARY FINDINGS	43

ATTACHMENT 1

NYSEG CAES GEP Stack Height Estimation

1 PHASE 1 PRELIMINARY ASSESSMENT VISUAL RESOURCES

1.1 EXISTING ENVIRONMENT

1.1.1 Project Description and Location

The proposed Seneca compressed air energy storage (CAES) Project will be a 130 to 180 MW plant that consists of an electrically driven compression cycle and a turbine expansion cycle that will produce electricity. The CAES plant is intended to provide sufficient storage to allow full operation during peak demand time periods in support of market needs (approximately 10 hours per day). The proposed CAES plant will be located off State Route 14A, in Reading, Schuyler County, New York. The facility is located west of Seneca Lake in northern Schuyler County (*Figure 1.1*).

More specifically, the site is located within the municipal boundary of Reading in Schuyler County, NY approximately one mile southeast of Reading Center (population 1,786 – 2000 Census) and approximately one mile west of Seneca Lake. The site is situated on a gradual incline which rises from the lake shoreline at 450 feet above sea level to approximately 1000 feet at the main plant site.

The CAES plant will be located on an undeveloped field consisting of low shrubs and small wetland areas, bordered by mixed and deciduous forest to the south and east. The site will be accessed from State Route 14A to the north and adjacent to existing light commercial buildings to the north, northwest. On the western edge of the site an active railroad right-of-way extends north-south with additional mixed forest and fields farther west.

Figure 1.1 *Existing Setting of Proposed Project Site*

1.1.2 *Visual Appearance of the Project Area*

With respect to the broader context, the area surrounding the CAES Project primarily consists of agricultural land, mixed and deciduous forest, small towns and other scattered residences. There are isolated industrial facilities in the area, e.g., U.S. Salt operations on the western shore of Seneca Lake, approximately 1.5 miles to the southeast of the proposed project facility, but otherwise the project area is rural. There are very few existing large vertical man-made structures in the Project Area that would have a similar visual impact to the proposed facility other than occasional radio masts and transmission towers and lines.

Watkins Glen (population 2,149 - 2000 Census), 3.5 miles to the southeast, is the largest settlement in the area and has a commercial center focused on recreational tourism at Seneca Lake. Small neighborhoods and water front houses occur along the entire lake shore.

Seneca Lake is oriented north-south and is approximately one mile east of the proposed project area. On either side of the lake, the ground rises rapidly on to ridges running parallel to the lake, up to 2,100 feet on the western side and 1,800 feet to the east.

The broader area surrounding the Project location contains many aesthetic resources, mostly to the south and east of the proposed project site. To the east, between Seneca and Cayuga lakes, is the Finger Lakes National Forest. The North Country Scenic Trail extends through the southern part of this National Forest to Seneca Lake, and then extends south through Watkins Glen. There is also a State Park and additional state-owned lands to the south of the site in Watkins Glen. Scattered to the north and south of the Project site are several locations of potential scenic interest that are on the list of National Registry of Historic Places, such as churches, historic villages and homes. All of these sites of interest are described in more detail in *Section 1.3.3*.

1.2 VISUAL RESOURCES ASSESSMENT APPROACH

1.2.1 Overview

This preliminary assessment reviews potential visibility impacts associated with proposed structures on the CAES plant site and is based on the surrounding ground surface elevation and potential screening forest cover. Consistent with New York Department of Environmental Conservation (NYSDEC) Program Policy DEP-00-2, *Assessing and Mitigating Visual Impacts* guidelines, ERM has applied a spatial modeling technique called Viewshed Analysis to define areas of potential visibility of the following structures:

- CAES stack: 213 feet (maximum estimated good engineering practice (GEP) height);
- CAES Cycle 2 stack: 190 feet (best current height estimate). Tall blue stack in *Figure 1.2*;
- Turbine Building Cycle 2: 76 feet. Rectangular orange buildings in *Figure 1.2*; and
- The CAES power line connecting to the Transmission Line to the west: Various heights for individual poles ranging from 56.5 to 74.5 feet.

Information about building and stack dimensions and calculated GEP for both CAES cycles was provided by WorleyParsons (Attachment 1).

Figure 1.2 *Proposed Site Layout (Cycle 2) Looking Southeast*

1.2.2 *Viewshed Analysis*

1.2.2.1 *Bare Earth Model*

ERM acquired digital elevation data from the United States Geological Survey (USGS) National Elevation Dataset (NED) that provides ground elevations on an approximate 3-meter grid. The NED is a bare earth model (i.e., provides elevation of the actual ground surface) and therefore removes any screening effects potentially provided by trees or buildings. This bare earth model can therefore be considered a worst-case scenario for potential visibility of a site. In conformance with NYSDEC Policy DEP-00-2, this bare-earth analysis enables the identification of all locations and visual resources from which the proposed project facility may be visible.

The Viewshed is calculated by placing an observer (assumed viewer height of 6 feet or 1.8 meters) on every grid point (3-meter spacing) in the elevation model and evaluating whether a mapped structure (e.g. top of emissions stack) can be seen from that location or whether intervening topography (hills, ridges, etc.) blocks the view. The output of this analysis is a grid of the entire study area showing locations where the mapped structure is potentially visible.

The standard Viewshed output simply shows whether a structure is visible or not from a given location and does not consider how much of the structure can be seen. The visual impact of seeing only the uppermost

part of a structure, e.g., top 10 feet of a stack) is very different from seeing the entire structure, e.g., full 213 feet of CAES GEP stack.

ERM has therefore developed an enhancement to the standard Viewshed analysis required by the NYSDEC Policy that takes into account how much of an individual structure is potentially visible. For each structure being assessed the total structure height was divided into four equal sections as shown schematically in *Figure 1.3* for the 213 foot CAES GEP stack. By running the Viewshed analysis iteratively for these four separate structure heights and combining the results it is possible to differentiate the area of potential visibility into categories based on the approximate percentage of the structure that is visible, rather than simply visible or not visible.

Figure 1.3 Schematic of Stack Visibility Percentage Estimates for Different Observers

For example, as shown in *Figure 1.3*, Observer A is able to see the top of the stack (213 feet) but is unable to see top of the next modeled section (160 feet) because of the intervening terrain. Therefore Observer A is able to see less than 25% of the stack or alternatively they can see a maximum of the upper 53 feet of the stack. Similarly, Observer B has a less obstructed view but is still unable to see the top of the lowest modeled section (53 feet). Observer B is able to see between 50 and 75% of the stack or alternatively they can see up to a maximum of the upper 160 feet of the stack.

This principle is illustrated further in *Table 1.1* overleaf for the CAES GEP Stack. Observer A would fall into the category $\leq 25\%$ Visible (shown in green) while Observer B would fall into the category 50-75% Visible (shown in orange). This color scheme, used in both *Figure 1.3* and *Table 1.1*, is carried through on all of the following map figures presenting the Viewshed analysis results.

Table 1.1 *Percentage Visibility of CAES GEP stack (213 feet)*

Visibility Map Category	Modeled Stack Height for Viewshed			
	213 ft	160 ft	107 ft	53 ft
≤ 25% Visible (≤ top 53 feet Visible)	Visible	Not Visible	Not Visible	Not Visible
25-50% Visible (≤ top 53-106 feet Visible)	Visible	Visible	Not Visible	Not Visible
50-75% Visible (≤ top 106-160 feet Visible)	Visible	Visible	Visible	Not Visible
75-100% Visible (≥ top 160 feet Visible)	Visible	Visible	Visible	Visible

Further differentiation of the outputs into narrower percentage ranges is possible. However, for the scope of this preliminary assessment 25% increments represent a good compromise between modeling time and visibility assessment detail. At this initial stage the primary purpose of applying this categorization is to identify areas where potential visual impacts will be highest and determine the best viewpoints from which to take photographs to capture viewshed lines of sight (see section below).

For this assessment, ERM has calculated separate Viewsheds from the bare earth data for a stack at an estimated GEP height of 213 feet (*Figure 1.4*), a stack at 190 feet (Cycle 2) (*Figure 1.5*) and the proposed Turbine Building at 76 feet (Cycle 2) (*Figure 1.6*). The results of this analysis are discussed in *Section 1.3.1*.

Legend

- Seneca Lake Shoreline
- Municipal Boundaries
- Proposed Site Boundary
- 1 & 5 Mile Buffers of Site Boundary
- Potential Visibility of Turbine Building**
 - Not Visible
 - < 25% of Structure Visible
 - 25 - 50% of Structure Visible
 - 50 - 75% of Structure Visible
 - 75 - 100% of Structure Visible

NOTES:
This figure depicts the potential visibility of a 76 foot Turbine Building using a bare earth elevation model of the ground surface from the National Elevation Dataset (NED). Refer to the accompanying report for a full description of the analysis methodology.

Figure 1.6: Potential Visibility of 76 foot Turbine Building
Bare Earth Elevation Model
NYSEG
Compressed Air Energy Storage (CAES) Project
Town of Reading
Schuyler County, NY

SOURCE: Aerial Imagery - ESRI World Imagery
Reproduced under license with ArcGIS 10

1.2.2.2 Vegetation Screening Model

As described in the previous section, a bare earth model excludes the potential screening effects of vegetation and buildings. As the surrounding area, particularly immediately adjacent to the site, is largely forested (>50% forest cover within 5 miles of the site) then these screening effects are potentially significant and need to be considered in any assessment of potential visibility. *Figure 1.7* presents a schematic representation of vegetation screening, showing how this can significantly reduce the potential visibility of a development. It is expected that existing forest cover will provide considerable screening of the proposed project site, either screening structures completely or reducing the portion of the structure that is visible.

Figure 1.7 *Schematic of Reduction in Visibility from Vegetation Screening*

For this assessment, ERM extracted areas of forest cover from the United States Department of Agriculture (USDA) 2010 Cropland Data Layer (CDL), which provides crop-specific land cover information, including forest cover, at a ground resolution of 30 meters. Based on field observations, ERM assumed a conservative estimate for tree heights of 30 feet across the surrounding forested areas. These were added to the existing NED elevation model to create screens across the entire Project Area. It should be noted that this approach creates a complete barrier to view as if the trees were a continuous wall. Depending on the time of year the screening effects will vary (e.g., in winter with no leaves the screening effect will be reduced). As described in *Section 1.4* further detailed assessment (under Phase 2) will need to incorporate these seasonal effects in judging visibility.

The Viewshed was then re-calculated using this vegetation corrected elevation model for the same structures as the bare earth model. In addition to the screens from vegetation it was assumed that no structures would be visible from within the forested areas. The results of this analysis are presented in the following figures: stack at a GEP height of 213 feet (*Figure 1.8*), a stack at 190 feet (Cycle 2) (*Figure 1.9*) and the Turbine Building (Cycle 2) at 76 feet (*Figure 1.10*). To facilitate comparison to the bare-earth model *Figure 1.11* provides a side-by-side comparison of the two model types for the 213 foot stack. The results of this analysis are discussed in *Section 1.3.1*.

Legend

- Seneca Lake Shoreline
- Municipal Boundaries
- Proposed Site Boundary
- 1 & 5 Mile Buffers of Site Boundary

Potential Visibility of Emissions Stack

- Not Visible
- < 25% of Structure Visible
- 25 - 50% of Structure Visible
- 50 - 75% of Structure Visible
- 75 - 100% of Structure Visible

NOTES:
This figures depicts the potential visibility of a 213 foot high Emissions Stack using a vegetation corrected elevation model of the ground surface from the National Elevation Dataset (NED). The effect of screening from existing interpretation has been included in this analysis using information on forest cover extents from the USDA 2010 Cropland Data Layer. Refer to the accompanying report for a full description of the analysis methodology.

Figure 1.8: Potential Visibility of 213 foot Emissions Stack
Vegetation Corrected Elevation Model
NYSEG
Compressed Air Energy Storage (CAES) Project
Town of Reading
Schuyler County, NY

Legend

- Seneca Lake Shoreline
- Municipal Boundaries
- Proposed Site Boundary
- 1 & 5 Mile Buffers of Site Boundary

Potential Visibility of Emissions Stack

- Not Visible
- < 25% of Structure Visible
- 25 - 50% of Structure Visible
- 50 - 75% of Structure Visible
- 75 - 100% of Structure Visible

NOTES:

This figure compares the potential visibility of a 213 foot Emissions Stack using a bare earth elevation model of the ground surface and a vegetation corrected elevation model from the National Elevation Dataset (NED). Refer to the accompanying report for a full description of the analysis methodology.

Figure 1.11: Potential Visibility of 213 foot Emissions Stack
Bare Earth and Vegetation Corrected Elevation Model

NYSEG
Compressed Air Energy Storage (CAES) Project
Town of Reading
Schuyler County, NY

1.2.2.4 Transmission Line Assessment

ERM also applied a Viewshed analysis to the proposed overhead transmission line running west from the CAES plant site. As shown in *Figure 1.12* the proposed route of the transmission line from the plant to connect with the substation passes primarily through existing forest. Due to variations in topography and the need to have specific clearance over barrier features (e.g., a railway) the individual transmission poles vary in height from 56.5 to 74.5 feet as shown in *Figure 1.12*.

Figure 1.12 *Proposed Transmission Line Route with Pole Heights (feet)*

For the transmission line Viewshed, both a bare-earth and vegetation-corrected model were calculated using the same method as described for the main plant structures with two key differences. For the vegetation-corrected model, the forest cover was removed along the proposed route providing 50 feet of clearance on either side of the power line to create the effect of a right-of-way along the transmission line.

The other key difference is that rather than look at the percentage of each pole that is visible, the total number of poles visible from any location was assessed. The Viewshed output therefore consists of a grid covering the entire Project Area with numeric values from 0 (no poles visible) up to 10

(10 poles visible). This cumulative Viewshed analysis gives a better indication of the variation in visual impacts when there are multiple structures and is commonly used in both wind turbine and transmission line visual assessments.

The results of this analysis are presented in the following figures: proposed transmission line, bare earth model (*Figure 1.13*), and proposed transmission line, vegetation corrected model (*Figure 1.14*). The results of this analysis are discussed in *Section 1.3.1*.

1.3 *POTENTIAL VISUAL RESOURCES IMPACTS*

1.3.1 *Overview of Potential Visibility*

The preceding figures show the potential visibility of both structures on the main plant site and the transmission line as described in the previous section. For the purposes of describing the results of the assessment all stated percentages of structure visibility (see *Section 1.2.2*) and general descriptions **are based on the potential visibility of the 213 foot GEP stack from the vegetation-corrected model unless otherwise stated in the text.**

1.3.1.1 *Main Plant Site*

As depicted in the preceding figures, the area with the highest potential visibility of structures on the main plant site is the eastern side of Seneca Lake. The eastern shoreline of the lake, directly due east of the CAES project site, has a high predicted visibility (75-100%), due to the lower elevation and direct line of site created by the open water. The forest cover on the eastern side of the lake, however, extends to the shoreline and so when vegetation screening is taken into account, the potential visibility decreases dramatically (*Figure 1.8*) away from the shoreline. There are, however, remaining pockets of high visibility from some of the larger agricultural areas where vegetation screening does not occur and isolated cases where there are breaks in the tree canopy. As noted in *Section 1.2.2.2* the screening effect of tree cover will be seasonal to some extent due to the presence of deciduous trees and further evaluation of leaf-off conditions is recommended.

Further east, the potential visibility of the site decreases due to elevation changes, with the ridge dropping away to the east. North, south, and west of the site generally have lower predicted visibility because of topographic variations and existing forest cover screening the site from view.

To the southeast, the village of Watkins Glen (largest settlement in the area) has moderate (50-75%) to high (75-100%) potential visibility of the project site. In particular, areas along the waterfront on the south-eastern corner of Seneca Lake have the highest potential visibility. Waterfront areas on the southwestern corner of Seneca Lake have a lower predicted visibility due to a reduced line of site created by the intervening topography. Although the downtown area has a predicted unrestricted visibility of the project site, the buildings can also be expected to screen many views of the proposed stack.

As discussed above and evident from the Viewshed maps, the screening effect of vegetation can be expected to substantially reduce potential visibility between the bare-earth model and the vegetation-corrected model. *Table 1.2* quantifies the potential visibility for the two models and the different project structures within a 5-mile radius of the main facility boundary. Comparing the two models shows that based on the current modeling assumptions, a significant reduction in visibility can be expected from existing vegetation screening. The next phase of assessment should include refining the estimate of tree canopy height and density, and assessing the variation in screening at different time of year. Buildings should also be integrate into the assessment.

Table 1.2 ***Viewshed Analysis Results - 5-mile radius of Project Site***

	Bare Earth Model		Vegetation Corrected Model	
	Area (sq. miles)	% of Total Area	Area (sq. miles)	% of Total Area
213 ft. Emissions Stack Visibility				
Not visible	445.27	78.9%	523.66	92.8%
<25%	8.23	1.5%	3.44	0.6%
25-50%	9.11	1.6%	4.12	0.7%
50-75%	10.10	1.8%	5.43	0.9%
75-100%	91.70	16.2%	27.62	4.9%
190 ft. Emissions Stack Visibility				
Not visible	449.02	79.6%	525.12	93.1%
<25%	7.29	1.3%	3.27	0.6%
25-50%	8.38	1.5%	3.82	0.7%
50-75%	9.33	1.7%	5.58	1.0%
75-100%	90.39	16.0%	26.48	4.7%
76 ft. Turbine Buildings Visibility				
Not visible	466.26	82.6%	532.86	94.4%
<25%	3.76	0.7%	2.15	0.4%
25-50%	4.27	0.8%	4.35	0.8%
50-75%	5.87	1.0%	7.96	1.4%
75-100%	84.23	15.0%	16.95	3.0%

1.3.1.2 *Proposed Transmission Line*

As for structures on the main plant site, the bare earth Viewshed model (Figure 1.13) shows extensive potential visibility of the transmission line poles, particularly from the eastern side of Seneca Lake, both on the water and along the shoreline. Incorporating the screening effect of forest cover, however, substantially reduces the potential visibility (Figure 1.14) such that only a limited number of locations will potentially be able to see the transmission line. If the current estimate of tree height is too conservative, then this will be reduced even further. In addition, the potentially slender profile of the transmission poles will reduce the distance from which they can effectively be seen.

Further assessments should specifically evaluate the tree cover height and density along the proposed power line route and assess the visibility of existing transmission lines in the area (some are visible in the following viewpoint examples).

1.3.2 *Views from Key Vantage Points*

Using the results of the Viewshed Analysis, ERM selected a series of viewpoints for preliminary field evaluation. These were selected to ensure coverage from all directions at varying distances from the proposed site. Only locations that were identified as being visible (with a high percentage visibility) from the Viewshed Analysis were selected. Wherever possible, locations that coincided with both visibility and the presence of existing aesthetic resources were selected. Figure 1.154 shows the location of the viewpoints described in the following sections.

For each viewpoint a brief description of the setting and potential visibility is provided with a field photo indicating the approximate position of the proposed project site. During the more detailed Phase 2 stage of the project, after the project has been officially announced to the public and full access to the plant property can be obtained, a visible balloon will be stationed at the Project Site and photographic documentation from the field points will be made.

Viewpoint 1: State Route 414 - Inland: 5.8 miles NE of Site

Depending upon forest cover and elevation, the project will be visible from various locations in this general area on the eastern side of Seneca Lake. At this specific location, which is 150 feet lower than the project site and within a large field, 75-100% of the 213 foot proposed stack (height $\geq$ 53 feet of the 213 foot stack) is predicted to be visible. The only significant

visual resource near Viewpoint 1 is the First Presbyterian Church of Hector (1.25 miles in the opposite direction from the site) and at 5.8 miles from the Project Site the stack and buildings should have limited impacts on the view. The site is obscured from view in the field photo by a large tree in the foreground but would be visible from other nearby areas where vegetation screening does not occur. The single row of trees in this photo provides a good example of where a reduction in screening effects may occur under leaf-off conditions.

Photo 1.1 Viewpoint 1: Facing southwest across Seneca Lake

Viewpoints 2-4: Northeastern and eastern Waterfront: 2-5.5 miles E and NE of Site

The Project Site is predicted to be visible from the entire eastern shoreline of Seneca Lake from 3.5 miles to the southeast to 12 miles to the northeast of the Site. The lakeshore is approximately 560 feet below the project site, but despite this height differential the 213 foot stack will primarily be visible, although against a background of trees rather the sky due to the presence of the ridge rising behind the site to the west.

Significant tree cover along most of the shoreline will likely screen the visibility of the Project Site further inland to the east. However, the lakeshore and lake itself has a high recreational value with many waterfront residents along the shoreline. Few public access points exist along the shoreline except for Warren Clute Public Park and the North Country Scenic Trail, both to the southeast in Watkins Glen. Photographs were taken along the eastern coast at 5.5 miles NE (Viewpoint 2), 3.5 miles NE (Viewpoint 3) and 2 miles E (Viewpoint 4). Photos were taken from a boat on the lake and the exact position of the Project Site cannot be pinpointed in the photographs.

Photo 1.2 *Viewpoint 2: Facing south across Seneca Lake from the lakeshore*

Photo 1.3 *Viewpoint 3: Facing southwest across Seneca Lake from the lakeshore*

Photo 1.4 Viewpoint 4: Facing west across Seneca Lake from the lakeshore

Viewpoint 5: Country Road 9 - Inland: 3 miles ESE of Site

Viewpoint 5 lies within a large agricultural area with extensive fields on top of the ridge on the eastern side of the lake. This elevation, combined with an increasing density in forest cover, shields the inland areas east of Seneca Lake to the view of the Project Site. However, areas with expansive agricultural fields have a predicted visibility of the Site. The only documented aesthetic resource in the area of Viewpoint 5 is the North Country Scenic Trail (0.5 miles west of Viewpoint 5). Because of the higher elevation of the project site and extensive agricultural fields in the vicinity of the Viewpoint, approximately 75-100% of the 213 foot proposed emissions stack is predicted to be visible from this viewpoint.

Photo1.5 Viewpoint 5: Facing northwest from the ridge on the eastern side of Seneca Lake

Viewpoint 6: Watkins Glen Lakeside Park - Waterfront: 3.5 miles SE of Site

This viewpoint is low-lying, not much higher than the lake surface itself approximately 540 feet lower than the Project Site, primarily consisting of high-density development, mixed and deciduous forest and wetland. Due to the lower elevation and Seneca Lake, approximately 75-100% of the 213 foot proposed stack is predicted to be visible from this viewpoint, which is situated in front of the Lakeside Park. This view already includes the US Salt Works on the lakeshore, which is visible in the same line of sight.

In general, the southern end of Seneca Lake, including a large portion of Watkins Glen (~3 miles away), has a high predicted visibility (>50% of proposed 213 foot stack). The southeastern corner of the lake has the highest probability of visibility (75-100% of proposed 213 foot stack). Further inland to the east the predicted visibility drops as forest cover increases and shields the project site (4 miles SE). However, inland areas to the east with high agricultural use still have high predicted visibility due to open, expansive fields. Most of the downtown area and the entire waterfront along the southern edge of Seneca Lake have some level of predicted visibility of the proposed 213 foot stack. The southwestern corner of the lake has the lowest potential visibility along the shoreline (25-50%), versus the southeastern corner of the lake which has a higher predicted visibility (75-100%).

Approximately 50-75% of the 213 foot stack is predicted to be visible from the downtown Watkins Glen area. However, within these developed areas of Watkins Glen existing buildings should provide additional screening of the Project Site depending on building height (accounting for building screening has not been included in this Phase 1 analysis). Various aesthetic resources can be found in this area (see *Section 1.3.3*), although in several cases these aesthetic resources exist in areas of intense development, where as noted above the buildings may screen the view of the Project Site.

Photo 1.6 Viewpoint 6: Facing northwest from Warren Clute Park

Viewpoint 7: Highway 409: 3.5 miles S of Site

Viewpoint 7 is taken from Highway 409, which is part of the historic route of the Watkins Glen Grand Prix Course, to the south of the Project Site at approximately the same elevation. There is extensive agricultural activity in this area with visibility likely from within the fields to the north of the viewpoint. However, the majority of the CAES plant structures will be screened by tree cover. The 213 foot stack is an exception to this and would be visible rising above the treeline against the sky (75-100% of the stack). For reference, according to the Federal Communications Commission (FCC) website the radio tower visible in the center of *Photo 1.7* (2.6 miles from viewpoint) has a reported elevation of 96 feet.

The viewpoint is taken from a Nationally Registered Site – the Watkins Glen Grand Prix Course, 1948-1952, and is also on the northern boundary of Watkins Glen State Park which partially overlaps the Grand Prix route. However, due to forest cover, there is no predicted visibility within the State Park although this may be subject to seasonal variation and should be re-evaluated during Phase 2. Sugar Hill State Forest, 3.5 miles to the west, also has zero predicted visibility due to intervening topography.

Photo 1.7 *Viewpoint 7: Facing north from Highway 409*

Viewpoint 8: Irelandville: 1 mile S of Site

This viewpoint is situated to the south of the Project Site at approximately the same elevation. Tree cover will likely screen most of the site structures. However, 50-75% of the 213 foot stack will be visible above the trees against the sky.

Photo 1.8 *Viewpoint 8: Facing north towards the Project Site*

Viewpoint 9: Gabriel's Junction – Route 14: 0.5 miles SE of Site

Viewpoint 9 is on highway 14A to the southeast of the site where there is a small cemetery adjacent to the road. Although this does not classify as a specific aesthetic resource under NYSDEC guidelines, the site will have cultural value to users from the local community. The adjacent forest and elevation below the site will obscure most of the Project Site structures. However 25-50% of the 213-foot stack (top 107 feet) is predicted to be visible above the trees from this viewpoint.

Due to its close proximity to the site, seasonal changes in tree cover may drastically reduce screening of the site and this viewpoint will require re-evaluation under leaf-off conditions.

Photo 1.9 **Viewpoint 9**

Viewpoint 10: Route 14 A: 0.2 miles NW of Site

This Viewpoint is taken from Route 14A, approximately 0.2 miles NW of the proposed CAES Project site. Areas directly north of the site have a high predicted visibility (75-100% of 213-foot stack) depending upon forest cover and agricultural fields. This viewpoint is taken from the same approximate elevation and no aesthetic resources exist in the area. Due to proximity this viewpoint has a high predicted visibility (75-100%) of the 213 foot stack above the visible tree cover. Existing commercial/industrial buildings can be seen in the foreground of the view and it would be expected that new CAES structures and buildings on the proposed site will benefit from similar partial screening by the surrounding vegetation.

Photo 10 *Viewpoint 10: Facing southeast towards the site from Route 14A*

Viewpoint 11: Jennings Road: 1.3 miles W of Site

Areas directly west of the site have a high predicted visibility due to the lack of forest cover and abundance of agricultural fields. This viewpoint is taken along Jennings road that extends directly west and provides a direct line of sight to the proposed site. This viewpoint is situated approximately 400 feet above the Project Site. To the west of this viewpoint, elevation increases and then flattens, screening most areas further to the west. From this location 75-100% of the proposed stack is predicted to be visible against the backdrop of fields and forest on the eastern side of Seneca Lake. In addition, this viewpoint includes the area along the transmission line right-of-way which will reduce screening of the site.

Photo 11 Viewpoint 11: Facing east downhill towards the Project site

Viewpoint 12: Chase Road: 2.4 miles N of Site

Areas north of the CAES Project site have a low predicted visibility due to elevation and forest cover. This viewpoint is situated at approximately the same elevation as the Project site and approximately 25-50% of the proposed stack is predicted to be visible above the tree cover that forms the skyline.

Photo 12 *Viewpoint 12: Facing south across agricultural fields*

Viewpoint 13: Route 44: 5.5 mile N of Site

Viewpoint 13 has a high predicted visibility (75-100% of proposed stack), although from this distance the effect the proposed stack would have on the surrounding landscape will be appreciably reduced. This viewpoint is situated at approximately the same elevation as the Project site; therefore the stack will be visible above the trees on the skyline. For reference, the existing transmission towers visible on the left hand side of the photo are approximately 0.7 miles away.

Photo 13 **Viewpoint 13**

1.3.3 *Inventory of Aesthetic Resources*

In accordance with the NYSDEC Program Policy (DEP-00-2) titled, “Assessing and Mitigating Visual Impacts” (7/31/2000), important aesthetic resources, as defined by the state, were inventoried and analyzed to determine if the proposed CAES Project site may adversely affect these sensitive visual resources. *Figure 1.14* shows the location of all qualifying aesthetic resources (i.e., must be evaluated by a visual assessment) as defined by the NYSDEC regulations within a 10-mile radius of the Project Site. These aesthetic resources are described in the following sections with their location relative to the Project Site, and the predicted visibility based on the Viewshed analysis. Note, all estimates of visibility cited are based on the vegetation corrected model for the 213-foot stack.

1.3.3.1 *National or State Register of Historic Places*

There are 24 properties in the National Register of Historic Places within a 10-mile radius of the site (*Table 1.3*)

Table 1.3 *Predicted Visibility of Project Stack from sites on National or State Register of Historic Places*

Map ID	Site Description	Distance from Site	Predicted Visibility
1	Watkins Glen Grand Prix Course	2.7 miles south	Zero from majority of site. <75% from visible sections
2	Chapman, A.F., House	3.2 miles south	0%
3	First Baptist Church of Watkins Glen	3.4 miles south	50-75%
4	US Post Office - Watkins Glen	3.4 miles south	50-75%
5	Schuyler County Courthouse Complex	3.5 miles south	50-75%
6	First Presbyterian Church of Hector	5.5 miles northeast	75-100%
7	Brick Tavern Stand	5.9 miles southeast	75-100%
8	Montour Falls Historic District	5.9 miles southeast	<25%
9	Logan Methodist Church	6.0 miles southeast	0%
10	Noyes, John, House	6.8 miles north	Zero from majority of site. 75-100% from visible sections

Map ID	Site Description	Distance from Site	Predicted Visibility
11	Lee School	7.2 miles southeast	0%
12	McCloud, J.M., House	7.5 miles north	0%
13	Dundee Village Historic District	7.5 miles north	<25%
14	First Presbyterian Church	7.6 miles north	0%
15	Dundee Methodist Church	7.7 miles north	0%
16	Starkey Corners Methodist Church	7.9 miles north	0%
17	Hair, Uriah, House	8.1 miles north	0%
18	Weston Schoolhouse	8.4 miles west	0%
19	Curtis, Thomas Bennet, House	8.5 miles north	0%
20	Spicer-Millard House	8.6 miles northwest	0%
21	Queen's Castle	8.9 miles north-northeast	75-100%
22	Swortz, William, House	9.2 miles north	75-100%
23	Spence, Dr. Henry, Cobblestone Farmhouse and Barn Complex	9.3 miles north	0%
24	Supplee, Daniel, Cobblestone Farmhouse	9.4 miles north	50-75%

1.3.3.2 *State Parks*

Watkins Glen State Park is approximately 3.2 miles south of the Project Site. Apart from a small section of open land on the western edge of the park, the proposed stack has no predicted visibility due to the extensive forest cover.

1.3.3.3 *Urban Cultural Parks*

There are no Urban Cultural Parks within a 10-mile radius of the Project Site

1.3.3.4 *State Forest Preserve*

The site is not located near the Adirondack or Catskill Parks which are defined as The State Forest Preserve by the NYS Constitution Article XIV. However, Sugarhill State Forest is approximately 3 miles southwest of the Project site, extending to 10 miles southwest. Due to the raised elevation between the state owned forest and the Project site, there is no predicted

visibility of the proposed 213-foot stack from any part of this property. Similarly, Texas Hollow State Forest (6 miles southeast) is also blocked from view by the intervening ridge.

1.3.3.5 *National Wildlife Refuges, State Game Refuges and State Wildlife Management Areas*

There are no National Wildlife Refuges in a 10-mile radius of the Proposed site. However, there is a state-owned Wildlife Management area located approximately 4 miles southeast of the proposed site, extending to 6 miles southeast called the Catharine Creek Wildlife Management Area (WMA). This WMA is low-lying and primarily consists of herbaceous wetlands. The majority of the WMA has a predicted visibility of 75-100% of the proposed 213-foot stack.

1.3.3.6 *National Natural Landmarks*

There are no National Natural Landmarks within a 10-mile radius of the Proposed site

1.3.3.7 *The National Park System, Recreation Areas, Seashores, Forests*

The Green Mountain and Finger Lakes National Forest is located approximately 3 miles east of the Project site and extends until roughly 14 miles northeast of the site. The vast majority of this National Forest has no predicted visibility of the proposed 213-foot stack as the forest will screen potential views. However, some areas where there are breaks in tree cover are predicted to have high visibility of the stack.

1.3.3.8 *Rivers designated as National or State Wild, Scenic or Recreational*

There are no rivers designated as National, or State Wild, Scenic or Recreational within a 10-mile radius of the Proposed site.

1.3.3.9 *A site, area, lake, reservoir or highway designated or eligible for designation as scenic*

There is a proposed scenic byway that will cross south of Seneca Lake through Watkins Glen, Hector, and Lodiⁱ. At this time, ERM was unable

ⁱ Source: <https://www.nysdot.gov/display/programs/scenic-byways/seneca-lake-hector-lodi>

to obtain the exact route of this proposed Scenic Byway and therefore could not perform a determination of visibility impact for this resource.

1.3.3.10 Scenic Areas of Statewide Significance

There are no Scenic Areas of Statewide Significance within a 10-mile radius of the Proposed site.

1.3.3.11 A State or federally designated trail, or one proposed for designation

The North Country National Scenic Trail spans seven states and once completed, it will be the longest contiguous hiking trail in the United States (<http://northcountrytrail.org/>). Once constructed, the trail will pass through the southern edge of the Finger Lakes National Forest, extend west to the eastern edge of Seneca Lake, turn south and pass through Watkins Glen and then head West towards Sugarhill State Forest. The majority of the trail that passes within 10 miles of the Project Site does not have a predicted visibility of the proposed 213-foot stack. However, some sections near Seneca Lake, 3-5 miles southeast of the Proposed site, would have some visibility impacts. The southeastern section of the trail that passes through Watkins Glen along Seneca Lake (4.6 miles SE of proposed site) has the highest predicted visibility (large areas of 75-100% predicted visibility of proposed 213 foot stack).

1.3.3.12 Adirondack Park Scenic Vistas

The Proposed Site is not located near Adirondack Park.

1.3.3.13 State Nature and Historic Preserve Areas

There are no State Nature or Historic Preserve areas located within a 10-mile radius of the Proposed Site.

1.3.3.14 Palisades Park

The Proposed site is not located near Palisades Park.

1.3.3.15 *Bond Act Properties purchased under Exceptional Scenic Beauty or Open Space category*

Research has not identified any Bond Act Properties purchased under Exceptional Scenic Beauty or Open Space category near the Proposed site. Prior visual resource studies in the area have also not identified any Bond Act Properties.

SOURCE: Aerial Imagery - ESRI World Imagery
Reproduced under license with ArcGIS 10

This Phase 1 Visual Resources assessment provides a preliminary overview of potential visibility impacts of the proposed CAES Project site. This preliminary review reveals that while Project structures will be visible from many locations, areas of forest cover surrounding the Project site and more generally throughout the Project area will in many instances limit visibility of the 213 foot stack, the tallest project structure. Other structures, such as the turbine building, will be more effectively screened by nearby tree stands, limiting the visibility of the CAES plant. Assumptions made, e.g., height of tree cover, for Phase 1 have been conservative, to ensure that visibility is overestimated rather than underestimated.

At this preliminary stage based on both the Viewshed Analysis and the subsequent field survey the primary areas of concern for potential visual impacts are:

- **Watkins Glen:** From within the town and along the waterfront at the southern end of the Seneca Lake the proposed project is predicted to be visible when looking out across the lake. This view already contains the US Salt Works on the lake shore (*Viewpoint 6*)
- **Eastern Shore of Seneca Lake:** Lake shore residents on this side of the lake and recreational users will have direct views of some of the project structures (*Viewpoints 2, 3 & 4*).
- **Project Site Vicinity:** In the immediate vicinity of the site (< 1 mile) views are likely to be impacted not only by the stack but also by other project structures such as the turbine building, and transmission line. Of the four viewpoints recorded within this radius (*8, 9, 10 & 11*), *Viewpoint 9* poses the greatest potential for concern because of the impact on the cemetery at this location.

This Phase 1 preliminary assessment provides an initial review of anticipated visual resource impacts associated with building the CAES Project. However, there are limitations with the current approach that will need to be addressed during Phase 2 of the Project. Key points to be addressed during Phase 2 include:

- **Accurate Screening Heights:** More accurate estimates of tree cover heights are available by using existing Light Detection and Ranging (LiDAR) elevation data for the CAES study area coupled with field verification. LiDAR is an airborne sensor to capture high resolution elevations of the ground surface and includes data on treetop heights

and any other screening features (e.g., buildings) and is already available in the vicinity of the site from a commercial data provider. Any change in tree cover height, particularly in the immediate vicinity of the Project Site may substantially alter the areas of potential visibility. Building heights and their screening effects in Watkins Glen should also be further evaluated.

- **Seasonal Field Surveys:** The majority of forest cover in the Project Area is mixed deciduous and coniferous. Consequently, some variation in screening can be expected at different times of year corresponding to leaf-on and leaf-off conditions. ERM recommended viewpoints should be visited again in winter conditions to assess these variations. If possible, additional field surveys should make use of an observable balloon tethered over the site to aid viewing of the proposed stack location during surveys. Typically this procedure uses a brightly colored (e.g., yellow, orange) 10-15 foot high balloon that would be clearly visible against the expected background (i.e., trees, sky). Note placement of the balloon would need to occur after the CAES Project has been officially communicated to the public so as not draw undue attention to the project.
- **Cultural Resources:** In addition to the aesthetic resources defined by NYSDEC, there are additional cultural resources in the area that have been identified during the cultural resource assessment. It will be necessary to include an evaluation of potential visibility for all of these sites during Phase 2.
- **Cooling Tower Plume Assessment:** While the CAES stack will be the most permanent prominent visual structure for the project, the associated plume from the cooling tower could potentially be more extensively visible under certain atmospheric conditions. ERM recommends that for Phase 2, once the final engineering design has been completed, that a comprehensive cooling tower plume visibility assessment be undertaken using the CALPUFF air quality dispersion model to understand the potential temporal and spatial visibility of the plume.
- **Mitigation Strategies:** In general, the stack will most commonly be visible against the skyline, although from some locations the background will be forest and field cover. Phase 2 will need to consider mitigation options for building materials and surface finishes for all CAES project structures, taking into account the visible background. Following the seasonal vegetation screening assessment, it is also recommended that options be considered for new plantings to provide additional screening either at the site itself or potentially at key resource locations on other landowners property.

Assessing and Mitigating Visual Impacts, (7/31/2000). *New York State Department of Environmental Conservation (NYSDEC DEP-00-2.*

National Elevation Dataset, (1999). *U.S. Geological Survey (USGS), EROS Data Center.*

USDA, National Agricultural Statistics Service, 2010 New York Cropland Data Layer, (1/10/2011). *United States Department of Agriculture (USDA), National Agricultural Statistics Service (NASS), Research and Development Division (RDD), Geospatial Information Branch (GIB), Spatial Analysis Research Section (SARS).*

Using Viewshed and Observer Points for visibility analysis, (6/29/2011). *Environmental Systems Research Institute (ESRI).*
(<http://help.arcgis.com/en/arcgisdesktop/10.0/help/index.html#/009z000000v8000000.htm>),

Attachment 1 - NYSEG CAES GEP Stack Height Estimation

NYSEG CAES GEP Stack Height Estimation

(Revision 1, 26-Sept-2011)

The following is a preliminary estimation of the stack heights associated with Cycles 1 and 2 for the NYSEG CAES Project based on updated building dimensions. From the regulations pertaining to the prevention of significant deterioration of air quality (PSD), 40 CFR 52.21(h) Stack heights - The degree of emission limitation required for control of any air pollutant under this section shall not be affected in any manner by -- (i) So much of the stack height of any source as exceeds good engineering practice (GEP), or (ii) Any other dispersion technique. So the height of the new stack was estimated based on not exceeding GEP stack height.

The EPA has promulgated regulations which establish the practice of using a formula for determining the GEP stack height needed to avoid excessive concentrations of air pollutants in the immediate vicinity of the source as a result of atmospheric downwash, wakes or eddies which may be caused by the source itself, nearby structures or nearby terrain features (40 CFR 51.100(ii)). According to this regulation, "Good engineering practice" (GEP) stack height means the greater of:

1. 65 meters (213 feet), measured from the ground-level elevation at the base of the stack, or
2. $H_g = H + 1.5L$,

Where:

H_g = GEP stack height, measured from the ground-level elevation at the base of the stack

H = Height of nearby structure(s) measured from the ground-level elevation at the base of the stack

L = Lesser dimension, height or projected width, of nearby structure(s)

The following table presents a preliminary GEP stack height determination/calculation based on an interpretation of the regulations and guidelines, and the predominant structures "nearby" the new stack, which is the Turbine/Compressor Building for both Cycles. There are no nearby elevated terrain features nor prominent off-site structures to affect this determination.

<u>STRUCTURE</u>	<u>- ESTIMATED DIMENSION -</u>				<u>ESTIMATED GEP STACK HEIGHT, Hg</u>
	<u>HEIGHT (1)</u>	<u>WIDTH</u>	<u>LENGTH</u>	<u>PROJECTED WIDTH (2)</u>	
Cycle 1-Turbine/Compressor Building	57'-6" (L)	75'-8"	394'-4"	NA	143'-9"
Cooling Tower	72'-4" (L)	66'-0"	240'-0"	NA	180'-10" (G)
Cycle 2-Turbine/Compressor Building	76'-0" (L)	109'-8"	447'-11"	NA	190 ft (G)
Cooling Tower	72'-4" (L)	66'-0"	240'-0"	NA	180'-10"

L = Lesser dimension of height or projected width. (Ground level elevation at stack foundations assumed to be the same as throughout the site.)

G = Per regulation GEP stack height is 213 feet.

- Note: (1) Heights are based on a ground level elevation of the stack. The height of the mechanical draft cooling tower includes the five, 34'-4" diameter, 13'-9" high exhausts.
- (2) The new stacks are being located west of the cooling tower in both cycles, and south of the Turbine/Compressor Building in Cycle 1 and north of the Turbine/Compressor Building in Cycle 2. Because the Cooling Tower for Cycle 1 and the Turbine/Compressor Building for Cycle 2 are the highest structure in the vicinity of the stacks and are wider than they are tall, the projected widths were not estimated in order to simplify the determination.

Based on the above estimation of the stack height, a stack height of 180'-10" was determined to be GEP for Cycle 1 and 190 feet for Cycle 2. Per the regulation, a stack up to 65 meters (213 feet) can be installed and not exceed GEP. So a stack height of **213 feet** is the **maximum** height that can be used in the PSD air quality modeling. A stack taller than 213 feet can be installed, but credit can only be taken for that portion that does not exceed GEP. Likewise a stack shorter than 180'-10" for Cycle 1 and 190 feet for Cycle 2 can be installed as long as the emissions from the source do not cause a violation of ambient air quality standards, do not exceed PSD ambient air increments, do not cause impairment to visibility, and do not cause a violation of any applicable safety and building codes.

The reviewing agency may require the use of a field study or fluid model to verify GEP stack height for the source.

There is a computer program (Building Profile Input Program [BPIP]) that calculates Building Heights and Projected Building Widths "values for every quarter of a degree for a full 360 degrees" of wind direction. The information presented in this document is not nearly as detailed as can be performed by this program. The BPIP probably should be utilized to confirm the GEP calculation presented here.

Reference:

Drawing Number: CAES-1-DW-111-002-101, Revision C, General Arrangement Cycle 1, Site Plan

Drawing Number: CAES-1-DW-111-002-102, Revision A, General Arrangement Cycle 1, Elevations and Sections

Drawing Number: CAES-1-DW-111-002-201, Revision D, General Arrangement Cycle 2, Site Plan

Drawing Number: CAES-1-DW-111-002-202, Revision A, General Arrangement Cycle 2, Elevations and Sections (In Preparation)

“Guideline for Determination of Good Engineering Practice Stack Height”, (Technical Support Document for the Stack Height Regulations), EPA, EPA-450/4-80-023R, June 1985.

Phase 1 Preliminary Assessment

Water Resources

Seneca Compressed Air Energy Storage Project

New York State Electric and Gas

**Town of Reading
Schuyler County, New York**

**Environmental Resources Management
399 Boylston Street
Boston, MA 02116**

TABLE OF CONTENTS

1.0	WATER RESOURCES.....	1
1.1	EXISTING CONDITIONS.....	1
1.1.1	Overview	1
1.1.2	Hydrology	3
1.1.3	Watershed	3
1.1.4	Water Quality	7
1.1.5	Sediment Characterization	12
1.1.6	Water Use	14
1.1.7	Aquatic Resources.....	15
1.2	PRELIMINARY ASSESSMENT OF POTENTIAL IMPACTS.....	15
1.2.1	Proposed Action and Potential Impacts	15
2.0	REFERENCES.....	28

1.0 WATER RESOURCES

This report presents a preliminary assessment of the water resources within the vicinity of the Seneca Compressed Air Energy Storage (CAES) Project and identifies potential impacts from the construction and operation of the Project on these resources. The proposed CAES Project will be a 130 to 180 MW compressed air energy storage plant that consists of an electrically driven compression cycle and a turbine expansion cycle that will produce electricity. The CAES plant is intended to provide sufficient storage to allow full operation during peak demand time periods in support of transmission system and market needs (approximately 10 hours per day). The CAES Project will be located west of Seneca Lake in Reading, Schuyler County, New York off State Route 14A (see Figure 1). The CAES property will occupy approximately 18 acres, of which, approximately 13 acres of the property will be developed with CAES process equipment, support buildings, storm water retention pond, and parking areas.

1.1 EXISTING CONDITIONS

1.1.1 Overview

The overall CAES Project footprint will include the generating plant, underground water and natural gas pipelines, and overhead power lines. The underground water pipelines (one for water withdrawal and the other for wastewater discharge) will extend into Seneca Lake and cross two tributaries mapped by New York State Department of Environmental Conservation (NYSDEC) on the western shore of Seneca Lake. Seneca Lake, which is one of the eleven Finger Lakes in upstate New York, spans Seneca, Schuyler, and Yates Counties, and its watershed includes Chemung and Ontario Counties (see Figure 2). Net water flow in Seneca Lake is from south to north toward the Seneca River. The Seneca River travels north and then turns east toward the confluence with the Oneida River where it becomes the Oswego River, which flows into Lake Ontario.

1.1.2 *Hydrology*

1.1.2.1 *Surface Water*

With approximately 42,646 acres (172.6 million square meters) of surface area, Seneca Lake has the greatest surface area of all the Finger Lakes. With an average depth of 290 feet (88 meters) and maximum depth of 651 feet (198 meters), Seneca Lake is also the deepest Finger Lake. Seneca Lake and the other Finger Lakes were formed by glacial activity that began approximately 2 million years ago and ended 10,000 years ago as continental glaciers moved southward from the Hudson Bay area, accentuating existing river valleys to form the present-day Finger Lakes. Table 1 provides a summary of the geometric characteristics of Seneca Lake.

Table 1: Geometric characteristics of Seneca Lake (NYSDEC, 2001).

Mean Depth (ft) (m)	Max Depth (ft) (m)	Length (mi) (km)	Volume (10 ⁶ gal) (10 ⁶ m ³)	Surface Area (mi ²) (km ²)	Watershed Area (mi ²) (km ²)	Elevation above MSL (ft) (m)
291 (88.6)	651 (198.4)	35.1 (56.6)	4,105,000 (15,539)	67.7 (175.4)	455.8 (1180.6)	444.9 (135.6)

With a volume of approximately 4.1 trillion gallons (15.5 billion cubic meters), Seneca Lake represents almost 50% of the combined volume of all eleven Finger Lakes. According to the 2001 NYSDEC report, its shoreline is approximately 75 miles (121 kilometers) and its hydraulic residence time is approximately 18.1 years.

1.1.2.2 *Groundwater*

According to the United States Geological Survey (USGS) (2005), groundwater withdrawal from the counties surrounding Seneca Lake ranges from 1.0 to 9.9 million gallons per day (mgd). At the location of the CAES Project, the USGS does not define any unconsolidated aquifers; however, south of the project site in the area of Watkins Glen, the USGS defines both unconfined and confined aquifers (USGS, 1987). The nearest primary-supply aquifer to the CAES Project is located east of Ithaca, NY. The vast majority of drinking water for the towns surrounding Seneca Lake is derived from surface water sources including Seneca Lake (NYSDEC, 2005).

1.1.3 *Watershed*

The United States Geological Survey (USGS) assigns an 8-digit Hydrologic Unit Code (HUC) to all watersheds across the United States as identification and tracking system. The HUC for Seneca Lake is 04140201

(EPA, 2011). As presented in Table 1, the watershed draining into Seneca Lake is approximately 456 square miles (1181 square kilometers), including the catchment area of Keuka Lake, which flows into Seneca Lake at its northwestern bank. Seneca Lake is part of the larger Oswego River/Finger Lakes Watershed, as presented in Figure 2.

The Seneca Lake sub-watershed consists of 29 sub-watersheds covering 32 local municipalities, totaling 40 communities (see Figure 3). The water level of Seneca Lake is controlled by hydroelectric plant operations and facilities at Waterloo Falls and Seneca Falls (G/FLRPC, 1999). During winter, Seneca Lake is drawn down to approximately 445 feet above mean sea level (msl) to minimize ice and wind damage to shoreline structures and properties and to provide storage for the spring runoff and ice melt. In summer, the elevation of Seneca Lake is maintained at approximately 446 feet above msl to support recreational activities (G/FLRPC, 1999).

Figure 3. Seneca Lake sub-watershed map (G/FLRPC, 1999).

1.1.3.1 Land Use

Land use in the Seneca Lake Watershed consists of agriculture (39.1%), undeveloped forest (41.3%), idle/undeveloped land (11.3%), and developed land (commercial, industrial, and residential) (8.3%) (G/FLRPC, 1999). From the 1970s to 1997, the land use distribution in the watershed area experienced a decrease in agricultural practices and an expansion and maturation of forests. According to the 2008 Schuyler County Agriculture Development and Farmland Protection Plan, between 1997 and 2007, Schuyler County experienced an increase in agricultural land. Of the land use categories, residential development has changed the most since the 1970s as lot sizes and house footprints in the county have

been steadily increasing. See the Phase 1 Land Use Report for additional discussion of land use in the CAES Project area.

1.1.3.2 *Climate*

The Finger Lakes region is characterized by cold winters and humid summers. According to the National Oceanic and Atmospheric Administration (NOAA) Climate Visualization System (CLIMVIS), average precipitation for the region is 34 inches per year with the average driest months between 1951 and 2011 being January and February (see Figure 4). The region is one of the driest in New York, but supports agriculture and horticulture practices in the area. Snowmelt occurs in spring (late-March through April) and the wettest months are June through September. Figure 5 summarizes the average temperature data between 1951 and 2011 for the Central Lakes Region of New York (CLIMVIS, 2011). On average, July is the hottest month and January the coldest. The average maximum temperature is 69 degrees Fahrenheit (F) and the average minimum temperature is 24 degrees F.

Figure 4. Average monthly precipitation in the Central Lakes Region (CLIMVIS, 2011).

Figure 5. Average monthly temperature for the Central Lakes Division of New York (CLIMVIS, 2011).

1.1.4 Water Quality

1.1.4.1 NYSDEC Classification

NYSDEC regulations assign classification, use and quality standards to surface waters throughout New York. According to NYSDEC classifications for 2010, Seneca Lake is indexed into four sections under the index designation Ont. 66-12-P 369:

1. The portion of Seneca Lake from the northernmost point southward 2.4 miles to an imaginary east-west line across the lake passing through Pastime Park;
2. The portion of Seneca Lake within a 1-mile radius of the mouth of Keuka Lake Outlet coming into Seneca Lake;
3. The portion of Seneca Lake beginning at an imaginary east-west line across the lake passing through Pastime Park extending southerly approximately 32 miles, excluding any area within section 2; and
4. The portion of Seneca Lake southerly of an imaginary line across the lake passing through Quarter Mile Creek.

Sections 1, 2, and 4 of Seneca Lake are classified as Class B, Standards B(T)¹. Section 3 of Seneca Lake, where the intake and discharges of the proposed project would occur, is classified as Class AA, Standards AA(T).

¹ The standard designation of (T) indicates that, according to NYSDEC, "the classified waters...are trout waters. Any water quality standard, guidance value, or thermal criterion that specifically refers to trout or trout waters, applies."

The two tributaries feeding into Seneca Lake that will be crossed by linear corridors of the Project are classified as Class C waters.

NYSDEC Chapter X, Division of Water, Part 701: Classifications-Surface Waters and Groundwaters describes the Class AA ranking as:

“The best usages of Class AA waters are: a source of water supply for drinking, culinary or food processing purposes; primary and secondary contact recreation; and fishing. The waters shall be suitable for fish, shellfish, and wildlife propagation and survival. This classification may be given to those waters that, if subjected to approved disinfection treatment, with additional treatment if necessary to remove naturally present impurities, meet or will meet New York State Department of Health drinking water standards and are or will be considered safe and satisfactory for drinking water purposes.”

NYSDEC describes the Class B ranking as:

“The best usages of Class B waters are primary and secondary contact recreation and fishing. These waters shall be suitable for fish, shellfish, and wildlife propagation and survival.”

NYSDEC describes the Class C ranking as:

“The best usage of Class C waters is fishing. These waters shall be suitable for fish, shellfish, and wildlife propagation and survival. The water quality shall be suitable for primary and secondary contact recreation, although other factors may limit the use for these purposes.”

In addition to the NYSDEC 303(d) List of Impaired/TMDL Waters and the Part 701 classifications, NYSDEC publishes a list of “Priority Water Bodies” in its “Waterbody Inventory/Priority Waterbodies List.” This list is a statewide inventory of water bodies in New York that characterizes water quality, supported water uses, progress toward identifying water quality problems and sources, and activities to restore and protect each water body. According to this list, which was most recently updated in June 2010, Section 2 of Seneca Lake (as described above) has the use impairment of “Water Supply POSSIBLY THREATENED.”

Seneca Lake is not listed on the 303(d) List of Impaired/TMDL Waters or list of “Other Impaired Water Body Segments Not Listed” for 2010 (NYSDEC, 2010). As such, Seneca Lake does not require development of a Total Maximum Daily Load (TMDL) or other strategy to reduce the input of pollutants that restrict water body uses to restore and protect those uses.

Various entities conduct water quality monitoring at Seneca Lake, including the Finger Lakes Institute (founded by Hobart and William Smith Colleges in Geneva, New York), Seneca Lakes Pure Waters Association, and NYSDEC via its Citizens Statewide Lake Assessment Program (CSLAP). Each entity monitors different parameters, however the most comprehensive data include water temperature, specific conductance, chlorophyll, and turbidity. As mentioned in section 1.1.1 Overview, NYSDEC and the G/FLRPC have published reports assessing the water quality of Seneca Lake. Data used to develop these reports were gathered mostly between 1996 and 1999.

The trophic status of a lake is determined by examining water quality parameters including dissolved oxygen (DO), nutrients, chlorophyll, and turbidity. Trophic status describes the biological productivity of a water body and ranges from low/oligotrophic, to high/eutrophic. According to NYSDEC and G/FLRPC, the current trophic state of Seneca Lake is borderline oligotrophic-mesotrophic. This indicates that Seneca Lake has low biological activity, is nutrient poor, and has very clear waters.

Water temperature in Seneca Lake varies seasonally and experiences thermal stratification during summer. The onset of thermal stratification usually occurs between mid-June and early-July (G/FLRPC, 1999). Seneca Lake remains stratified until mid-October to early-November when changes in temperature and wind force the lake to turn-over and de-stratify. Water temperature affects oxygen solubility with colder water permitting higher DO concentrations. In Seneca Lake, dissolved oxygen concentrations are near saturation throughout the water column during the entire year, showing relative insensitivity to temperature. This is consistent with the oligotrophic status, since low biological productivity does not affect the oxygen demand. Furthermore, this makes any potentially adverse effects of stratification on dissolved oxygen virtually non-existent. Figure 6 provides a graph of dissolved oxygen concentrations and water temperatures in Seneca Lake when not stratified (June) and when stratified (August).

Figure 6. Temperature and dissolved oxygen profiles for Seneca Lake (NYSDEC, 2001).

Nitrate concentrations in Seneca Lake show range from 100 to 600 ug/L (much greater than the 10 ug/L NYSDEC standard; see Table 2) and phosphate concentrations range from 0.1 to 10 ug/L. Chlorophyll-a in Seneca Lake ranges from below detection limits to 10 ug/L (G/FLRPC, 1999); average chlorophyll-a concentrations, as reported by NYSDEC, are approximately 2.4 ug/L. As expected, concentrations of chlorophyll-a decrease as depth below the lake surface increases.

Owing to the relatively low biological productivity of Seneca Lake, water transparency can be quite high. Secchi disk (a circular disk used to measure water transparency in lakes) depths are shallower during summer when productivity is highest and deeper during fall and spring when productivity is lowest. The G/FLRPC reports a range of Secchi depths from a minimum of 1 meter to a maximum of 11 meters, with NYSDEC reporting an average Secchi disk depth of 6 meters.

Outside of these water quality parameters, other constituent concentrations are important to the health of a water body and its flora and fauna. Both NYSDEC and G/FLRPC report a variety of water quality constituents for Seneca Lake. Table 2 provides a summary of concentrations of constituents detected in Seneca Lake and shows the corresponding NYSDEC Class AA water quality standards.

Table 2: Seneca Lake water quality.

		NYSDEC ¹	USGS ²	GFLRPC ³			NYSDEC ⁴
Constituent	Units	Avg	Max	Min	Avg	Max	Standard
Total Phosphorous	ug/L	9.8	--	--	--	--	--
Chlorophyll a	ug/L	2.4	--	1.0	--	5.0	--
Secchi Disk Depth	m	6	--	1	--	11	--
Total Cations	mEq	6.13	--	--	--	--	--
Total Anions	mEq	6.3	--	--	--	--	--
pH	--	--	--	8	--	9	>6.5 and <8.5
Calcium	mg/L	~41	--	--	--	--	--
Magnesium	mg/L	~10	--	--	--	--	35
Potassium	mg/L	~2.55	--	--	--	--	--
Sodium	mg/L	~75	--	--	--	--	20
Chloride	mg/L	~130	--	--	150	--	250
Sulfate	mg/L	~37	--	--	--	--	250
Alkalinity	mg/L	~98	--	--	--	--	--
Atrazine	ug/L	--	0.143	0.05	0.13	0.23	7.5
Metachlor	ug/L	--	0.017	--	--	--	--
Calcium Carbonate (CaCO3)	mg/L	--	--	140	--	150	--
Deep Water Temperature	°C	--	--	--	4	--	--
Surface Water Temperature	°C	--	--	0	--	20	--
Nitrate	ug/L	--	--	100	--	600	10
Phosphate	ug/L	--	--	0.1	--	10	--
Dissolved Silica	ug/L	--	--	50	--	4000	--

Notes

1. Constituent concentrations as reported by the New York State Department of Environmental Conservation (NYSDEC) are for the average of measurements taken between 1996 and 1999, excluding 1998.
2. The United States Geological Survey (USGS) conducted sampling for current-use pesticides in the Finger Lakes in the late 1990s.
3. In 1999, the Genesee Finger Lakes Regional Planning Council (GFLRPC) reported water quality data for Seneca Lake. Data presented were collected and analyzed weekly at four offshore stations in the northern portion of Seneca Lake. Five additional sites in the southern portion of Seneca Lake were sampled in 1998.
4. Standards taken from NYSDEC Part 703: Surface Water and Groundwater Quality Standards and Groundwater Effluent Limitations.

1.1.4.3 Outlet

Seneca Lake is fed by groundwater inflow and tributaries, with the largest inflows from Catherine Creek and Keuka Lake. Most outflow from Seneca Lake is to the Cayuga-Seneca Canal, otherwise known as the Seneca River. Portions of the Seneca River are on the NYSDEC 2010 303(d) List of Impaired/TMDL Waters. However, those portions are far downstream of the Seneca Lake outlet.

The USGS monitors the Seneca River at the city of Seneca Falls that is approximately 8 miles downstream from the outlet of Seneca Lake. At this gauging location (Station No. 07051057, Seneca River in Seneca Falls), the USGS collected water quality data between May and November 2007. Water quality measured at this location is assumed to be representative of water quality leaving the outlet of Seneca Lake – only two small tributaries contribute to Seneca River after it outlets from Seneca Lake before this gauging station. Table 3 provides a summary of these data.

Table 3: Seneca River water quality.

Constituent	Units	USGS ¹			NYSDEC ²
		Min	Avg	Max	Standard
Alkalinity, Carbonate as CaCO ₃	mg/L	86.3	94.7	105	--
Aluminum	ug/L	ND ³	96.7	175.0	--
Ammonia as NH ₃	mg/L	0.03	0.05	0.10	--
Cadmium	ug/L	ND	0.125	0.212	--
Calcium	mg/L	33.6	40.5	46.5	--
Total Organic Carbon (TOC)	mg/L	2.44	2.86	3.34	--
Chloride	mg/L	122	137	153	250
Copper	ug/L	1.9	2.8	3.5	--
Dissolved Oxygen	mg/L	5.7	8.3	12.4	> 6.0
Fecal Coliform	#/100mL	12	66.7	180	--
Lead	ug/L	ND	0.26	0.61	--
Nickel	ug/L	1.1	1.7	2.4	--
pH	--	7.2	8.3	9.3	>6.5 and <8.5
Potassium	mg/L	2.37	2.70	3.03	--
Sodium	mg/L	86.9	111.7	157	20
Total Suspended Solids (TSS)	mg/L	ND	3.1	10.1	--
Specific Conductance	uS/cm	753	871	1169	--
Temperature	°C	5.6	17.6	24.5	--
Turbidity	NTU	0.88	3.05	10.2	< 5

Notes

1. The United States Geological Survey (USGS) monitored water quality parameters at the Seneca River at Seneca Falls between May and November 2007.
2. Standards taken from NYSDEC Part 703: Surface Water and Groundwater Quality Standards and Groundwater Effluent Limitations.
3. "ND" denotes "non detect" which indicates that the constituent was below the detection limit of the sampling instrumentation.

1.1.5 Sediment Characterization

In addition to water quality monitoring, NYSDEC completed a sediment core investigation of Seneca Lake between 1997 and 1998. Cooperating with Hobart and William Smith Colleges, one sediment core was collected from Seneca Lake at a depth of 130 meters. This location is at approximately the same latitude as Sampson State Park on the eastern shore of Seneca Lake (see Figure 7).

Figure 7. Location of sediment core (arrow) and Sampson State Park (point A) (Google, 2011).

Sediments are a combination of organic and inorganic material deposited by erosion, aerial deposition, biological growth and decay, and transport from other water bodies. Findings from the NYSDEC sediment investigation indicate a sediment accumulation rate of 0.23 centimeters per year in Seneca Lake. Due to a sampling oversight, total organic carbon (TOC) was not measured. However, organic and inorganic chemical data were collected. The only organics detected in Seneca Lake sediment were dichloro-diphenyl-trichloroethane (DDT) and its metabolites, and polychlorinated biphenols (PCB) congeners. The DDT concentration exceeded its threshold-effect level (TEL) but did not reach the probable-effect level (PEL)²; conversely PCB congener concentrations exceeded its PEL. Inorganic chemical findings for Seneca Lake sediment include measurements for arsenic, cadmium, calcium, chromium, copper, lead, mercury, nickel, and zinc. Table 4 presents the existing concentrations of

² The TEL represents the chemical concentration below which adverse effects are expected to occur infrequently. The PEL represents a second threshold value, above which adverse effects are expected to be frequently observed.

each constituent as measured in the Seneca Lake sediment core. Note further evaluation of potential impacts to aquatic life due to the disturbance of lake bed sediments during construction will be performed under Phase 2 of the Project after the design of the underwater infrastructure has been finalized.

Table 4: Constituent concentrations in Seneca Lake sediment core.

Measurement	Units	NYSDEC ¹
		Avg
¹³⁷ Cs marker depth (peak)	cm	7
¹³⁷ Cs marker depth (horizon)	cm	15
Sediment Accumulation rate (peak) ²	cm/yr	0.23
Sediment Accumulation rate (horizon) ⁴	cm/yr	0.33
Sediment Accumulation rate ³	cm/yr	0.32
Peak Sum of DDT (8-10cm depth)	ppb	153
Surface Sum of DDT	ppb	40
Sum of PCB Cogeners	ppb	466
Adjusted Sum of PCB Cogeners ⁴	ppb	408
Dieldren	ppb	ND
Arsenic (peak [occurred at surface])	ppm	19
Arsenic (surface)	ppm	19
Cadmium (peak [at 6-8cm, ~1970])	ppm	2.2
Calcium (peak [at 4-6cm, ~1978])	ppm	37200
Chromium (peak [at 6-8cm, ~1970])	ppm	30.1
Copper (peak [6-8cm, ~1970])	ppm	61.8
Lead (peak [6-8cm, ~1963])	ppm	84.6
Manganese (peak [0-2cm, 1994])	ppm	2450
Nickel (peak [6-8cm, ~1970])	ppm	46.1
Zinc (peak [6-8cm, 1970])	mg/kg	176

Notes

1. Constituent concentrations as reported by the New York State Department of Environmental Conservation (NYSDEC) are for the average of measurements taken between 1996 and 1997
2. Sediment accumulation rate based on ¹³⁷Cs.
3. Sediment accumulation rate based on ²¹⁰Pb
4. Total sum of cogeners minus IUPAC-85 and DDE.

1.1.6 Water Use

Forty communities have at least some portions of their jurisdictions in the Seneca Lake Watershed. Currently, Seneca Lake serves as a source of public water supply for the surrounding communities of Geneva, Ovid, Waterloo, and Watkins Glen and is the drinking water source for over 70,000 people in the Finger Lakes region (NYSDEC, 2001). In 2001, there were four permitted withdrawals with a total permitted withdrawal of approximately 9 million gallons per day (mgd) (NYSDEC, 2001) with the estimated actual surface water withdrawal of 7.9 mgd (USGS, 2010). Potable water from the lake to residents meets all drinking water standards published by the United States Environmental Protection

Agency (EPA) under the Safe Drinking Water Act (SDWA). Before it is distributed, drinking water from Seneca Lake is tested for heavy metals, volatile organics, organics, microbes, pesticides, and herbicides (G/FLRPC, 1999).

1.1.7 *Aquatic Resources*

1.1.7.1 *Aquatic Life*

Seneca Lake supports fisheries with lake trout (*Salvelinus namaycush*), smallmouth bass (*Micropterus dolomieu*), and yellow perch (*Perca flavescens*) serving as the mainstay of the lake since the first survey of Seneca Lake in 1927. Other species in the lake include rainbow trout (*Oncorhynchus mykiss*), brown trout (*Salmo trutta* sp.), land-locked Atlantic salmon (*Salmo salar*), northern pike (*Esox lucius*), large mouth bass (*Micropterus salmoides*), alewives (*Alosa pseudoharengus*), and rainbow smelt (*Osmerus mordax*). According to the 1999 G/FLRPC report, Seneca Lake is stocked annually with 60,000 lake trout, 65,000 brown trout, and 24,000 Atlantic salmon. Rainbow trout are sustained entirely by natural reproduction in Seneca Lake tributaries. Much of the perimeter of the lake supports a band of rooted aquatic vegetation consisting of Eurasian milfoil (*Myriophyllum spicatum*) primarily, and pondweeds (*Potamogeton* sp.), waterweeds (*Elodea* sp.), water plantain (*Alisma* sp.), stoneworts (*Chara connivens*), and muskgrass (*Chara* sp.), as well.

Both NYSDEC and G/FLRPC report that Seneca Lake is impacted by Zebra mussels and possibly Quagga mussels. Introduced to the United States in the late 1980s, Zebra mussels are an exotic species that can substantially alter aquatic ecosystems and impact human-made structures within a lake (e.g., clogging water intake pipes). About the size of a fingernail, Zebra mussels filter-feed on plankton. In its 1999 report, the G/FLRPC notes that phytoplankton populations in Seneca Lake decreased between 1992 and 1998, hypothetically corresponding with the timeframe in which Zebra mussels had established in the lake. It bears mention that calcium is often the limiting nutrient to Zebra mussel productivity and growth; therefore, increases in calcium concentrations within Seneca Lake could lead to exacerbated Zebra mussel populations.

1.2 *PRELIMINARY ASSESSMENT OF POTENTIAL IMPACTS*

1.2.1 *Proposed Action and Potential Impacts*

The CAES plant site is approximately 2000 feet (609.6 meters) west of Seneca Lake, immediately west of the intersection of State Route 14 and

Route 14A. Construction of the CAES plant is scheduled to begin in December 2013 with a target in-service date of late 2014. The CAES Project will use and impact water in various ways via its cooling water, make-up water, wastewater management, and stormwater management systems. Construction of the plant, the underground water and natural gas pipelines, and the aboveground power lines may also temporarily impact Seneca Lake and two tributaries during the construction phase of the Project.

1.2.1.1 *Water Demand*

For the CAES Project, two expansion cycle process alternatives are currently being evaluated. The first expansion cycle (Cycle 1) will employ expansion turbine generators with a natural gas combustor (i.e., process heater) to heat the stored air prior to entering the expansion turbine generators. The second expansion cycle (Cycle 2) will consist of a natural gas-fired combustion turbine with a heat exchanger downstream of the combustion turbine exhaust that will be used to heat the air prior to entering the expansion turbine generators.

Cycle 1 and Cycle 2 have different water budgets due to varying thermodynamic conditions between the two cycles. The driving variable affecting the water budget is ambient weather conditions, with ambient temperature being the most important. Figure 8 shows the average-demand water budget for Cycle 1 and Figure 9 shows the average-demand water budget for Cycle 2. Both cycles will withdraw water from Seneca Lake for use as:

1. Nitrogen oxide (NO_x) emissions control for the process heater (Cycle 1 only),
2. Combustion turbine water wash tank (Cycle 2 only),
3. Cooling tower make up,
4. Evaporative cooler (Cycle 2 only),
5. Service water, and
6. Potable water.

Figure 8. Cycle 1 average usage (WorleyParsons, 2011).

Figure 9. Cycle 2 average usage (WorleyParsons, 2011).

As presented in Figures 8 and 9, Cycle 1 and Cycle 2 will use water withdrawn from Seneca Lake and delivered to the facility via an underground pipeline. Approximately 12% of the water withdrawn from Seneca Lake will be returned to the lake (via an underground pipe) as wastewater produced from Cooling Tower blowdown. The balance of the water consumed by the CAES plant is evaporated from the Cooling Tower, water used for NO_x control for the Cycle 1 process heaters, combustion turbine water wash that will be hauled off-site (Cycle 2 only), or water disposed of via the on-site sanitary (septic) system.

For average ambient climatic conditions, it is expected that the CAES facility will withdrawal approximately 0.45 to 0.47 million gallons per day (mgd) from Seneca Lake, depending on Cycle design. In addition to water withdrawn from Seneca Lake, the CAES plant will use approximately 2,880 gallons per day supplied from the storm water retention pond to meet the make-up water demand of the cooling tower and lessen the amount of water needed to be withdrawn from Seneca Lake. According to the 2001 NYSDEC report, the average inflow to Seneca Lake is approximately 172,000 million gallons per year (approximately 470 mgd). As such, the average ambient climatic conditions CAES water intake rate of 0.46 mgd represents approximately 0.1 percent of the average inflow to Seneca Lake from tributaries and groundwater inflow. Through corresponding evaporation, blowdown, NO_x control, the combustion turbine water wash tank, and the on-site septic system, CAES Cycles 1 and 2 will consume between 395,000 and 415,000 gallons per day, respectively, which represents 0.08 percent and 0.09 percent, respectively of the average inflow to Seneca Lake.

1.2.1.2 *Water Storage*

A 700,000 gallon service/fire water storage tank will be placed in service at the CAES facility to moderate water balance flows during operational periods.

The CAES plant will employ stormwater management at the site. The stormwater management system will collect runoff within the property boundaries and store the runoff in an on-site retention pond. As much as practicable, this water will be used to supplement the cooling tower make up water demand and thus help minimize the amount of water withdrawn from Seneca Lake, as described above.

1.2.1.3 *Water Discharge*

The Cooling Tower blowdown, which will be discharged into Seneca Lake, will be the principal wastewater discharge from the facility.

Preliminary design information provided for the CAES plant includes an analysis of the “raw water” that the facility will receive from Seneca Lake and the cooling tower blowdown. Table 5 identifies key water quality parameters and associated concentrations for the cooling tower blowdown and raw intake water.

Table 5. Constituent concentrations in CAES intake and blowdown (WorleyParsons, 2011).

Constituent ¹	Units	Blowdown	Intake Water	Difference	% Difference	Standard ²
Calcium (as CaCO ₃)	mg/L	336.0	42.0	+294	700%	--
Magnesium (as CaCO ₃)	mg/L	88.0	11.0	+77	700%	35
Sodium (as Na)	mg/L	1072	134.0	+938	700%	20
Potassium (as K)	mg/L	21.6	2.7	+18.9	700%	--
Total Hardness	mg/L	424	--	N/A	N/A	--
Chloride (as Cl)	mg/L	1112	139.0	+973	700%	250
Sulfate (as SO ₄)	mg/L	1052	38.0	+1014	2668%	250
Silica (as SiO ₂)	mg/L	14.4	1.8	+12.6	700%	--
Phosphate (as PO ₄)	mg/L	85.6	10.7	+74.9	700%	--
Nitrate	mg/L	4.0	0.5	+3.5	700%	10
Total Alkalinity	mg/L	46	106	-60	-57%	--
pH	--	7.0	--	N/A	N/A	>6.5 and <8.5
Max Temperature	°F	80	60	+20	33%	--
Suspended Solids	mg/L	12	1.5	+10.5	700%	--

Notes

1. Data based on preliminary calculations conducted by the designer of the CAES plant in 2011.
2. Standards taken from NYSDEC Part 703: Surface Water and Groundwater Quality Standards and Groundwater Effluent Limitations.

As Table 5 reveals, each constituent, with the exception of total alkalinity, increases during water use at the CAES facility, which is not unexpected given the concentrating effect inherent in cooling tower blowdown. For the most part, the concentration of almost all of the parameters increases by a considerable amount.

The CAES plant will employ a packaged sanitary system to manage its domestic wastewater. The plant will generate domestic wastewater from its potable water uses such as on-site restrooms; no industrial wastewater enters the septic system. The packaged sanitary system will be equipped with a standard below-ground leach field. Approximately 14,400 gallons per day will flow through this system. Based on the modern design of the sanitary system no impacts to groundwater are anticipated.

1.2.1.4 Water Availability

As discussed in section 1.2.1.1 Water Demand, on average the CAES facility will withdraw approximately 0.46 mgd, which is approximately 0.1 percent of the average inflow to Seneca Lake from tributaries and groundwater inflow. It is anticipated that the facility will return approximately 55,000 gallons per day (gpd) or 12 percent of the withdrawal volume to Seneca Lake, with the balance of approximately 405,000 gpd associated with consumptive use.

As discussed in section 1.1.4.4 NYSDEC Classification, in the vicinity of the proposed CAES water intake and discharge structures, Seneca Lake is classified as Class AA. As promulgated by NYSDEC in Chapter X Division of Water Part 703: Surface Water and Groundwater Quality Standards and Groundwater Effluent Limitations, Class AA water quality limitations apply to various water quality constituents (as shown in Table 2, Table 3, and Table 4). During the operational phase of the Project, water discharged from the CAES plant would be diluted and mixed with water in Seneca Lake.³ For purposes of this preliminary assessment and to present one scenario, it is assumed that a mixing zone exists in the vicinity of the CAES wastewater discharge outfall in Seneca Lake. It is important to recognize, however, that the evaluation of the impacts of discharging cooling tower blowdown into Seneca Lake will require consultation with NYSDEC to determine acceptable analysis methodologies. These discussions would occur during Phase 2 of the Project.

That being said, performing a hydrodynamic simulation of the mixing zone would be one of the best methods to evaluate the horizontal and vertical extent of the mixing zone. Such a simulation would be performed under Phase 2 of the Project. However, as a first cut assessment, a simplistic approach is to conduct a dilution analysis to approximate the dilution that would be required to reduce effluent constituent concentrations to Class AA standards.

Data for the CAES facility indicate that the concentration of salt (sodium) in the cooling tower blowdown is on the order of 1000 mg/L. As presented in Table 5, the concentration of sodium in the CAES blowdown is seven times greater than the ambient sodium concentration in Seneca Lake. NYSDEC Class AA standards limit sodium concentration to 20 mg/L. However, as discussed above, discharge from the CAES facility will be diluted and mixed with water in Seneca Lake. With a discharge of 55,000 gallons per day to Seneca Lake, a simple dilution analysis yields a mixing volume of approximately 50 times the daily discharge volume (i.e., 2,750,000 gallons) to dilute the blowdown to 20 mg/L (as presented in Table 6).

³ Note: At this point in time, it is assumed that the cooling tower blowdown will be discharged through an underground pipeline into Seneca Lake and not discharged into the nearby tributary or treated on-site prior to discharge to a receiving water body.

Similar dilution calculations were performed for the concentration of magnesium, chloride, and sulfate projected for the cooling tower blowdown. Table 6 presents the results of this dilution analysis.

Table 6. Dilution requirements to reduce blowdown concentrations to Class AA standards.

Constituent	Cooling¹ Tower Blowdown (mg/L)	NYSDEC Class AA Standard² (mg/L)	Volume Required to Dilute Blowdown to Class AA Standard³ (gal)
Magnesium (as CaCO ₃)	88.0	35	138,286
Sodium (as Na)	1072	20	2,948,000
Chloride (as Cl)	1112	250	244,640
Sulfate (as SO ₄)	1052	250	231,440
Nitrate	4.0	10	--

Notes

1. Data based on preliminary calculations conducted by the designer of the CAES plant in 2011.
2. Standards are Class AA standards from NYSDEC Part 703: Surface Water and Groundwater Quality Standards and Groundwater Effluent Limitations.
3. Discharge from the CAES facility is approximately 55,000 gallons per day.

As presented above, a mixing volume of approximately 2.5 times the daily discharge volume (i.e., 140,000 gallons) is required to dilute the concentration of magnesium in the CAES blowdown (88.0 mg/L) to the Class AA standard (35 mg/L). Similarly, a mixing volume of approximately 4.5 times the daily discharge volume (i.e., 250,000 gallons) is required to dilute the concentration of chloride in the CAES blowdown (1,112 mg/L) to the Class AA standard (250 mg/L); and a mixing volume of approximately 4.2 times the daily discharge volume (i.e., 230,000 gallons) is required to dilute the concentration of sulfate in the CAES blowdown (1,052 mg/L) to the Class AA standard (250 mg/L). As presented in Table 6, the concentration of nitrate in the CAES blowdown is below the Class AA standard. Similarly, as shown in Table 5, the pH of the CAES blowdown is within the Class AA standard, as well.

Again, at this preliminary assessment phase of the CAES Project and as mentioned above, it is not known if the use of a mixing zone would be accepted by NYSDEC to meet water quality standards. Discussions with NYSDEC should be initiated as soon as possible during Phase 2 of the Project. If the use of a mixing zone is not allowed, achieving the water quality standards or prescribed NYSDEC state pollutant discharge elimination system (SPDES) permit limits would be required to be met at the discharge outfall in Seneca Lake.

Furthermore, with respect to reducing impacts on surface water quality, implementation of proper erosion and sedimentation controls, such as perimeter controls, silt curtains, and sediment basins during the

construction phase of the CAES Project will minimize adverse impacts to Seneca Lake and the two small Class C tributaries to Seneca Lake across which the underground pipelines and overhead power lines are proposed.

In the event that an alternate scenario is selected for the discharge of wastewater from the CAES plant to one of the nearby tributaries to Seneca Lake, as opposed to discharging into Seneca Lake, additional analyses would be required relative to potential impacts to water quality.

1.2.1.6 *Aquatic Resource and User Impacts*

As discussed in section 1.1.7.1 Aquatic Life, calcium is often the limiting nutrient to Zebra mussel productivity and growth. According to the 2001 NYSDEC report, the calcium threshold for Zebra mussel development ranges between 25 to 30 milligrams per liter, where calcium concentrations below this level do not appear to support the establishment of Zebra mussels. As such, increases in calcium concentrations within Seneca Lake could lead to exacerbated Zebra mussel populations. As shown in Table 5, the predicted calcium concentration in the cooling tower blowdown is considerably greater than that reported occurring in Seneca Lake. Any additional calcium delivered to the ecosystem has the potential to foster Zebra mussel growth especially immediately within the area surrounding the outfall of the cooling tower blowdown discharge. It is important to note that the current reported calcium concentration in Seneca Lake already exceeds the threshold for Zebra mussel development.

According to the 2001 NYSDEC report, Zebra mussel infestations can result in significant economic impacts by clogging of water supply intake pipes and other man-made structures. There is the potential for Zebra mussels to impact the function of the CAES plant intake and outfall structures, so both preventative and routine maintenance measures will need to be taken to ensure that Zebra mussel populations do not interfere with the functioning of these structures. Options for controlling Zebra mussels include in-line filter pumps to protect interior plumbing and ceramic filters. Many companies install equipment to pre-oxidize water at the point of intake to inhibit Zebra mussel populations. Similarly, physical barriers and chemical coatings can prevent Zebra mussels from attaching to structures. Removal of Zebra mussels can be accomplished with mechanical scrapers.

Additionally, given the classification of AA(T) in the section of Seneca Lake where the water intake and discharge pipes are proposed, a more detailed evaluation of potential impacts to the trout population and other fisheries will need to be performed under Phase 2 of the project after the

specific locations of the water intake and discharge pipes have been identified and in conjunction with assessing potential water quality impacts. Also, a thorough assessment of the applicability of §316(b) of the Clean Water Act (or comparable NYSDEC regulation or interpretative policy/guidance) that requires that the location, design, construction and capacity of cooling water intake structures apply best technology available for minimizing adverse environmental impact will need to be completed. Note that while the CAES project water withdrawal volumes may be below §316(b) applicability thresholds, NYSDEC state-specific regulations, New York State Public Service Commission's Article X provisions, or the New York State Environmental Quality Review Act SEQR process may require impingement and entrainment analyses and intake structure design considerations to be performed as part of the environmental approval process.

Furthermore, under Phase 2 of the project, after the locations of the water intake and discharge pipes have been identified, a survey of aquatic vegetation is recommended within Seneca Lake along the proposed alignment and intake/discharge points. Identification of the plant species present, if any, will allow a final assessment of the potential impacts to this resource.

1.2.17 *Potential Regulatory Permitting Considerations*

Using the results of this Phase 1 Preliminary Assessment coupled with the findings of WorleyParsons' Phase 1 engineering report, a comprehensive list of federal, state and local environmental permitting requirements will be developed prior to commencing Phase 2 of the CAES Project. This list will identify all applicable regulatory agency pre-construction permitting and approval obligations. As noted in this Phase 1 report, as the CAES Project design progresses, more in-depth analyses will be required regarding potential impacts to sensitive water quality concerns and aquatic resources associated with Seneca Lake. Addressing these concerns, in particular the following two key issues, will be critical to successfully positioning the CAES Project to meet the various federal, state, and local permitting and agency approval requirements relating to water resources:

- The potential exists that no mixing zone would be recognized by the regulatory agencies to allow dilution of the cooling tower blowdown wastewater discharged into Seneca Lake (a Classified AA(T) water resource. The result would be a requirement to meet the surface water quality standards or other restrictive limits at the outlet of the discharge pipe in Seneca Lake.
- Presently the §316(b) implementing regulations are under revision. A draft of the new regulations is anticipated to be issued in early

2012. These new regulations may have implications on the CAES Project in terms of the water withdrawal volume applicability threshold and requirements regarding impingement and entrainment at the water intake structure. Regardless of the changes to the regulations, impingement and entrainment impacts and design considerations are anticipated to be required by the permitting authorities and likely to be raised by interested stakeholder groups.

Table 7 provides a preliminary listing of the water resources-related permits, reviews, and approvals that may be required for the CAES Project. A final determination of which of these requirements will be applicable will depend on the CAES design and project configuration ultimately selected.

Table 7. Listing of Potential Required Environmental Approvals.

U.S. Army Corps of Engineers (USACE)	River & Harbor Act Section 10 - Navigable Waterways	Required when doing any work in, over, or under navigable waters of the United States. It is a detailed process that requires environmental surveys and may require mitigation.
	Clean Water Act – Section 404 – Discharge of Dredge or Fill Materials	Required when dredging or filling wetlands and crossing navigable waters. It is a detailed process that requires environmental surveys and may require mitigation.
U.S. Environmental Protection Agency	Clean Water Act NPDES Permits	Regulates discharges of pollutants into the waters of the United States
	Title 40 Code of Federal Regulations (CFR) Parts 110 and 112 - Spill Prevention Control and Countermeasure	An SPCC Plan will be required for the project. The plan identifies spill prevention measures, spill response actions and procedures for timely notifications.
	Clean Water Act Section 316(a) and 316(b)	Evaluation and design of cooling water discharge and intake facilities to manage, minimize and avoid adverse thermal impacts from cooling water discharges and fish impingement or entrainment from cooling water intakes

New York State Department of Environmental Conservation (NYSDEC)	Protection of Waters - Section 401 Water Quality Certification/ Stream Protection Permits	Discharge of Dredged or Fill Materials; Modification or disturbance of stream beds. Applicants for a Federal license or permit for activities (including but not limited to the construction or operation of facilities that may result in any discharge into waters of the United States) are required to apply for and obtain a Water Quality Certification from NYSDEC indicating that the proposed activity will not violate water quality standards.
	Environmental Impact Assessment in New York State via NYS Environmental Quality Review Act (SEQR). [Statutory authority: Environmental Conservation Law Sections 3-0301(1)(b), 3-0301(2)(m) and 8-0113] (Note for the CAES Project this requirement may be replaced by decision to file under New York State Public Service Commission Article X)	Most projects or activities proposed by a state agency or unit of local government, and all discretionary approvals (permits) from a NYS agency or unit of local government, require an environmental impact assessment. This process must be complete and the project deemed approvable through an Issuance of Findings Statement before State and Local permits can be issued. In general, any land use proposal requiring a permit from a local or state government, and requiring discretion on the part of the permitting agency, is subject to SEQR.
	Environmental Conservation Law (ECL) Article 15 - Freshwater Wetland Permit	Almost any activity that may adversely impact the natural values of the wetlands or their adjacent areas (within 100 feet of the wetland boundary as designated on the official NYSDEC freshwater wetlands map or as determined through site inspection) is regulated. Typically the wetland must be 12.4 acres or greater to be regulated under this program. Smaller wetlands can be

		regulated if certain criteria are met.
	Environmental Conservation Law (ECL) Article 15 - Protection of Waters Permit - Excavation or Placement of Fill in Navigable Waters and their Adjacent and Contiguous Wetlands	A Protection of Waters Permit is required for excavating or placing fill in navigable waters of the state, below the mean high water level, including adjacent and contiguous marshes and wetlands
	Environmental Conservation Law (ECL) Article 15 - Protection of Waters Permit - Major Construction, Reconstruction or Expansion of Docking and Mooring Facilities.	A Protection Of Waters Permit is required for constructing, reconstructing, or repairing docks or platforms and installing moorings on, in or above navigable waters to create docking facilities, mooring areas or to facilitate other activities.
	Environmental Conservation Law (ECL) Article 15 - Stream Bed or Bank Disturbance Permit	Required in any stream with a class C(T) or higher water quality classification and up for any activity that will affect drainage swales or water quality by disturbance of stream bed or bank. This permit would be required if utility lines will disturb stream beds or banks of qualifying streams.
	Environmental Conservation Law (ECL) Article 11 - Endangered Species	Provide review and evaluation of these potential impacts and make recommendations to the lead agency regarding suitability of the project.
NYSDEC	EPA's Phase II Stormwater Rules; NYSDEC GP-02-01 requires Spill Prevention, Control and Countermeasure Plan (SPCC), State Pollutant Discharge Elimination System (SPDES) Permit including a Stormwater Pollution Prevention Plan (SWPPP)	Required for construction or use of an outlet or discharge pipe (point sources) of wastewater discharging into the surface waters) or ground water of the State.
Local	Flood Hazard Area Permit	Required for the construction of any structure within areas classified by the Federal Emergency Management Agency as being in a flood hazard area (within the 100 -year flood plain).

	Site Plan Review	Site plan reviews are required to review the layout and design of a development site. It is completed to insure that the development is in harmony with the character of the area in which it is located and that important resources will be protected and to ensure compliance with local zoning and subdivision ordinances.
--	------------------	--

2.0 REFERENCES

- Genesee/Finger Lakes Regional Planning Council (G/FLRPC), 1999. Seneca Lake Watershed Management Plan. Accessed online 26 September 2011:
<http://www.gflrpc.org/Publications/SenecaLakeWMP.htm>.
- New York State Department of Environmental Conservation (NYSDEC) Division of Water, July 2001. Water Quality Study of the Finger Lakes. Accessed online 26 September 2011:
<http://www.dec.ny.gov/lands/25576.html>.
- NYSDEC, 2005. Water Use in New York in 2005. Accessed online 28 October 2011: <http://www.dec.ny.gov/lands/67073.html>
- United States Geological Survey (USGS), 1987. Water Resources Investigation Report 87-4122. Unconsolidated Aquifers in Upstate New York – Finger Lakes Sheet. Prepared by Todd S. Miller.
- USGS, 2000. New York Water-Use Program and Data. Accessed online 28 October 2011 :
<http://ny.water.usgs.gov/pubs/of/of051352/of2005-1352.pdf>
- USGS, 2010. Illinois Water Science Center. Estimated Withdrawals and Other Elements of Water Use in the Great Lakes Basin of the United States in 2005, Scientific Investigations Report 2010-5031. Accessed online 26 September 2011:
<http://pubs.usgs.gov/sir/2010/5031/pdf/sir2010-5031.pdf>.
- WorleyParsons, 2011. Preliminary Water Balances for Cycle 1 and Cycle 2, NYSEG Seneca Compressed Air Energy (CAES) Project, 2011.

**SENECA
LAKE**

Legend

- Approximate Site Location
 - 2 Mile Buffer of Project Area
 - NYS DEC - Stream**
 - Classification - C
 - 2010 TIGER / Line**
 - Roads
- NOTE: Site Location is approximate

Figure 1: General Site Area
NYSEG
Seneca Compressed Air Energy
Storage (CAES) Project
Town of Reading
Schuyler County, NY

SOURCE:
Streams - New York State Department of Environmental Conservation (DEC)
Aerial Imagery - ESRI World Imagery - Reproduced under License with ArcGIS 10

G:\Graphics\Clients_V_Z\WorleyParsons\Watkins Glen, NY\MXD\Working\Figures\Figure1_GeneralSiteAreaRev1.mxd

Wetlands Assessment

Seneca Compressed Air Energy Storage Project

New York State Electric and Gas

Town of Reading
Schuyler County, New York

Environmental Resources Management
399 Boylston Street
Boston, MA 02116

TABLE OF CONTENTS

1.0 INTRODUCTION AND BACKGROUND 1

2.0 EXISTING CONDITIONS 2

2.1 DESKTOP WETLAND INVESTIGATION AND FIELD
RECONNAISSANCE 2

2.2 DESKTOP REVIEW RESULTS..... 3

2.3 FIELD RECONNAISSANCE WETLAND OBSERVATIONS..... 3

3.0 DETERMINING JURISDICTION 5

4.0 IMPACTS AND MITIGATION REQUIREMENTS 6

5.0 REFERENCES CITED 8

FIGURES

ATTACHMENT 1 Wetlands Photo Log

In 1975, the New York State Legislature passed The Freshwater Wetlands Act with the intent to “preserve, protect, and conserve freshwater wetlands.” Pursuant to this act, the New York State Department of Environmental Conservation (NYSDEC) maps all wetlands regulated by the Act that includes: 1) wetlands greater than 12.4 acres in size, and 2) wetlands “of unusual local importance.” The NYSDEC mapped regulated wetlands in the greater vicinity of the New York State Electric and Gas (NYSEG) Seneca Compressed Air Energy Storage (CAES) project are presented in the inset of Figure 1. (Note that no NYSDEC mapped wetlands are within a two mile radius of the CAES project site.)

The United States Army Corps of Engineers (USACE) regulates most wetlands in New York State under the federal Clean Water Act. Wetlands are defined as those areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions (Environmental Laboratory, 1987). Identifying a federal wetland employs a three-parameter approach, including a dominance of wetland vegetation, hydrology, and hydric soils.

This wetlands assessment was performed under Phase 1 of the CAES project. Once unbridled access to the land parcels to be impacted is secured, formal wetland delineations will be conducted. These activities will be undertaken under Phase 2 of the project.

2.0 EXISTING CONDITIONS

2.1 DESKTOP WETLAND INVESTIGATION AND FIELD RECONNAISSANCE

An ERM scientist conducted both a desktop review and a field reconnaissance of the areas proposed to be disturbed as part of the construction and operation of the CAES facility. The project boundary comprising the CAES plant site and linear utility lines was discussed with NYSEG staff prior to performing the desktop wetland investigation and field reconnaissance, the latter performed with a NYSEG staff member.

Wetlands in the Project area were first investigated with a desktop review using two sources: the National Wetlands Inventory (NWI) and the NYSDEC freshwater wetland maps. The NWI is an online geographic database maintained by the U.S. Fish & Wildlife Service (USFWS) that identifies national wetlands and deepwater habitats (Cowardin, 1979). State-regulated wetlands are provided in an electronic database maintained by the NYSDEC and are identified using a combination of aerial photography, soil surveys, previous wetland inventories, and field verification. The NYSDEC categorizes regulated wetlands according to cover type, ecological association, special features, hydrological and pollution control features, and distribution and location. In addition to review of the NYS Geographic Information Systems (GIS) datalayers, the NYDEC Environmental Resource Mapper was employed to determine if the project boundary intersected with any mapped freshwater wetlands.

Potential wetland areas not identified in the federal and state databases were identified through desktop surveys of local topography using United States Geological Survey (USGS) topographic maps and color infrared aerial photography.

Following initial review of existing data sources for wetlands in the region, an ERM scientist conducted a preliminary field reconnaissance visit. The purpose of the field effort was to confirm the presence of wetlands depicted on publicly-available data sources and identify the potential for additional wetlands to be present that are not identified on existing state or federal wetland maps.

2.2

DESKTOP REVIEW RESULTS

The outcome of the resources evaluated resulted in the identification of one small open-water feature at the CAES plant site and three potential wetland areas (non-NYSDEC designated) at the CAES plant site. A small drainage channel was also identified at the intersection of Jennings Road and County Route 28 near the substation location. The multiple tributaries (or streams) to Seneca Lake, and Seneca Lake itself are identified in the Surface Water section and have potential to be jurisdictional under section 404 of the Clean Water Act (CWA) as Waters of the US.

The CAES Project is located approximately one mile west of Seneca Lake within the Seneca Lake sub-watershed (HUC code 04140201), which is located in the larger Oswego River/Finger Lakes Watershed. The NYSDEC Environmental Resource Mapper identifies no State-regulated freshwater wetlands or classified ponds in the vicinity of the CAES project site. The nearest State wetland mapped by NYSDEC is located greater than two miles to the southeast of the Project boundary (see inset of Figure 1). Three classified streams are within, or in the vicinity of, the project boundaries (see Figure 1). These are Class C streams in the vicinity of the CAES site, and as they enter Seneca Lake, the classification shifts to Class AA(T), which denotes that these streams are known to support a trout population. The first stream is located just south of the proposed CAES plant site and the second stream is located north of the proposed Facility. Both streams flow in an easterly direction, ultimately discharging into Seneca Lake.

2.3

FIELD RECONNAISSANCE WETLAND OBSERVATIONS

The field reconnaissance confirmed that areas identified in the desktop assessment are potential jurisdictional wetlands, based on observations of wetland vegetation, hydric soil characteristics, and hydrology. In addition, the field reconnaissance identified wetlands that are not depicted on the NWI or NYSDEC maps, which is not unexpected because these maps are used for planning level purposes only.

Within the proposed CAES plant site footprint, three areas of potential wetlands were noted (see Figure 2). Wetland 1 is proximate to a freshwater pond identified by the NWI database. Wetland 2 appears to be associated with a drainage channel that flows in an easterly direction across the proposed Project site, ultimately discharging to a stream located to the north of the Project site. Approximate to the proposed overhead power line route from the CAES site, one area of potential wetland,

Wetland 3, was noted to the west-southwest of the Project site. In addition to these three wetlands, a roadside drainage swale was noted along Jennings Road and State Route 28 near the proposed substation location. Based on this preliminary field reconnaissance, no wetlands were observed along the proposed underground pipeline route corridor leading approximately south and east of the project site. Photographs of Wetlands 1, 2, and 3 are provided in Attachment 1.

A list of wetland plant species observed in Wetlands 1, 2, and 3 is presented in Table 1. This list is not exhaustive, but represents those predominant species that were observed and noted during the preliminary site walkover. Soils observed in Wetlands 1 and 3 contained hydric features including a gleyed matrix and redoximorphic features, and evidence of hydrology at the three wetlands included aerial photo identification of standing water, saturation to the surface, inundation, and/or a dominance of wetland vegetation, as noted during field observations.

Table 1. List of Plant Species Observed in Potential Wetland Areas

Wetland Identifier	Approximate Size of Wetland (acres)	Observed plant species¹	Wetland Indicator Status
1	0.6	Rice cutgrass (<i>Leersia orzoides</i>) Green bulrush (<i>Scirpus atrovirens</i>) Soft rush (<i>Juncus effusus</i>) Purple loosestrife (<i>Lythrum salicaria</i>) ² Lurid sedge (<i>Carex lurida</i>) Water plantain (<i>Alisma</i> sp.)	OBL OBL FACW FACW OBL OBL ³
2	0.5	Purple loosestrife (<i>Lythrum salicaria</i>) ² Soft rush (<i>Juncus effusus</i>)	FACW FACW
3	0.2	Sensitive fern (<i>Onoclea sensibilis</i>)	FACW

OBL = Obligate; FACW = Facultative Wetland

¹ None of the listed plant species are identified as sensitive, threatened, endangered, or of special concern as listed by NYSDEC or USFWS.

²Listed on NYSDEC Interim Invasive Species Plant List

(<http://www.dec.ny.gov/animals/65408.html>)

³Water plantain not identified to species, but most *Alisma* species are OBL.

Based on the results of the field reconnaissance, formal wetland delineations will be required under Phase 2 of the project leading to licensing and permitting. The potential wetlands identified at the Project site are not mapped by NYSDEC as freshwater wetlands and none of them is large enough (each was determined to be less than 12.4 acres in size) or contain unusual local importance to trigger jurisdiction by NYSDEC.

Wetland 2 appears to have a potential connection to the NYSDEC Class C stream located north of the proposed CAES site. Therefore, this wetland is anticipated to be under federal jurisdiction as Waters of the US. Based on the field reconnaissance, the small open water area and Wetland 1 within the CAES plant footprint, as well as Wetland 3 nearby the overhead power line route, may be isolated and may not have a connection to any other wetland or water body. However, this will need to be confirmed during a formal wetlands delineation. It is important to note that it is often difficult to establish small pond and/or wetland areas as 'isolated' and not subject to jurisdiction under the federal Clean Water Act. A connection to navigable waters would indicate likely jurisdiction under section 404 of the CWA. Both the USACE and the US Environmental Protection Agency must approve any such determination of isolation.

Based on the results of this preliminary analysis, all three of the wetlands identified should be considered jurisdictional as Waters of the United States under Sections 401 and 404 of the federal Clean Water Act due to their potential connectivity to the tributaries to Seneca Lake. ERM recommends that following formal delineation of the wetland areas under Phase 2 of the project, a jurisdictional determination request be submitted to the USACE Buffalo Division.

All three potential wetlands identified in the vicinity of CAES project site are considered jurisdictional for the purposes of this preliminary analysis. The CAES plant footprint is anticipated to impact at least two of potentially jurisdictional federal wetland areas, Wetlands 1 and 2. Section 404 mitigation requirements include both avoidance and minimization of impacts to jurisdictional wetland areas. In those situations where impacts to wetlands cannot be avoided, compensatory mitigation options have been identified by USACE and in the US Environmental Protection Agency's (USEPA) Wetlands Compensatory Mitigation Rule (2008 Final Rule) and are ranked in a hierarchal fashion in order of preference. For the CAES Project, the following options identified in USEPA's Final Rule were reviewed in order:

1. Mitigation Banks;
2. In-Lieu Fee Program Credits;
3. Permittee-responsible mitigation under a watershed approach;
4. Permittee-responsible mitigation through on-site and in-kind mitigation; and
5. Permittee-responsible mitigation through off-site and/or out-of-kind mitigation.

Currently, there are no known approved wetland mitigation banks available to compensate for wetland impacts in Schuyler County. Similarly, no in-lieu fee programs have been established for use in this region of the State. Therefore, a permittee-responsible mitigation package is the primary option available for the CAES Project. The primary focus of the mitigation requirements is to restore the wetland functions and services lost from a project. A typical mitigation strategy is to re-establish a wetland in a suitable location to restore the functions and services within the Oswego River/Finger Lakes Watershed, or ideally in the Seneca Lake sub-watershed (HUC code 04140201). Site selection for a wetland mitigation project that includes the creation of a new wetland should consider the following factors:

- the hydrological conditions, soil characteristics, and other physical and chemical characteristics;
- watershed-scale features, such as habitat diversity and habitat connectivity;
- size and location of the site relative to the hydrologic sources;
- compatibility with adjacent land uses and watershed management plans; and

- potential for long-term protection.

Wetland creation as a compensatory mitigation tool typically requires the creation of an area at least as large as the area to be disturbed, and regulatory agencies may require that the created area be larger than the area disturbed.

Mitigation also can be in the form of restoration of wetland habitat. If this option were selected as a mitigation strategy, opportunities within the watershed would be explored to identify potential locations where wetland habitat has been degraded over time and could be restored to provide the functions and services it once provided. Restoration as compensatory mitigation typically requires the restoration of a larger area of restored wetland as compared to the area of wetland lost.

Areas created or restored for the purposes of compensatory mitigation would require long-term monitoring (typically five years) and documented long-term protection. Monitoring would be required to document the functions and services provided by the created/restored area, including the presence of wetland vegetation, the initial development of hydric soil characteristics, and evidence of hydrology. Conservation easements or another legal tenant of protection from future development or degradation would be a key component of a wetland mitigation plan.

Cowardin, L. M., V. Carter, F. C. Golet, and E. T. LaRoe. 1979. *Classification of Wetlands and Deepwater Habitats of the United States*. FWS/OBS-79-31. USDI Fish and Wildlife Service, Washington, DC. 103 pp.

Environmental Laboratory, 1987. Corps of Engineers Wetlands Delineation manual, Technical Report Y-87-1, U.S. Army Engineer Waterways Experiment Station, Vicksburg, MS.

- Legend**
- Approximate Site Location
 - 100-year Floodplain for Schuyler County
 - Wetlands (NWI)**
 - Freshwater Emergent Wetland
 - Freshwater Pond
 - Lake
 - Schuyler County Wetlands**
 - DEC Wetlands
 - Approximate Digitized Wetlands**
 - Potential Wetlands Observed During Field Reconnaissance
 - NYS DEC - Stream**
 - Classification - C
 - 2010 TIGER / Line**
 - Roads
 - 2 Mile Buffer of Project Area

NOTE: THE WETLANDS NOTED ON THIS FIGURE ARE A PRELIMINARY ANALYSIS FOR PLANNING PURPOSES ONLY. NO FORMAL WETLAND DELINEARTION HAS BEEN CONDUCTED

Figure 1: Preliminary Assessment of Wetland and Surface Water Features
NYSEG
Seneca Compressed Air Energy Storage (CAES) Project
Town of Reading
Schuyler County, NY

SOURCE: U.S. Fish & Wildlife Service National Wetland Inventory (NWI)
New York State Department of Environmental Conservation (DEC)
Aerial Imagery - ESRI World Imagery, Reproduced under License with ArcGIS 10
Southern Tier Central Regional Planning and Development
approx. 100-year flood plain

- Legend**
- Proposed CAES Facility Features
 - 2 Mile Buffer of Project Area
 - 100-year Floodplain for Schuyler County
 - Wetlands (NWI)**
 - Freshwater Emergent Wetland
 - Freshwater Pond
 - Lake
 - Schuyler County Wetlands**
 - DEC Wetlands
 - Approximate Digitized Wetlands**
 - Potential Wetlands Observed During Field Reconnaissance
 - NYS DEC - Stream**
 - Classification - C
 - 2010 TIGER / Line**
 - Roads

NOTE: THE WETLANDS NOTED ON THIS FIGURE ARE A PRELIMINARY ANALYSIS FOR PLANNING PURPOSES ONLY. NO FORMAL WETLAND DELINEARTION HAS BEEN CONDUCTED

0 100 200 400 600 Feet
1 in = 300 ft

Figure 2: Potential Wetland Areas on Proposed CAES Facility Site
NYSEG
Seneca Compressed Air Energy Storage (CAES) Project
Town of Reading
Schuyler County, NY

SOURCE: U.S. Fish & Wildlife Service National Wetland Inventory (NWI)
New York State Department of Environmental Conservation (DEC)
Aerial Imagery - ESRI World Imagery - Reproduced under License with ArcGIS 10
Southern Tier Central Regional Planning and Development
approx. 100-year floodplain

Attachment 1
Wetlands Photo Log

PHOTODOCUMENTATION - September 02, 2011
Compressed Air Energy Storage (CAES) Project
Reading, NY
Page 1 of 2

Facing East across the Pond associated with Wetland 1.

Facing South towards Wetland 2 (the wetland is within the concentration of purple loosestrife in the background).

PHOTODOCUMENTATION - September 02, 2011
Compressed Air Energy Storage (CAES) Project
Reading, NY
Page 2 of 2

Facing West across Wetland 3

**COMPRESSED AIR ENERGY STORAGE
NYSEG SENECA LAKE PROJECT
FINAL REPORT**

Prepared for

NYSEG

Binghamton, New York

Prepared by

PB ENERGY STORAGE SERVICES, INC.

Houston, TX

Project No. 50756B

December 2011

TABLE OF CONTENTS

SECTION	PAGE
1.0 INTRODUCTION.....	1
2.0 GEOLOGY^{A-D}	2
3.0 CAVERN CONCEPTUAL DESIGN^{E,F}	4
4.0 CAVERN THERMODYNAMIC MODELING^G	7
5.0 THERMAL AND THERMOMECHANICAL MODELING^H	8
5.1 Heat Transfer Finite Element Model	9
5.2 Thermomechanical modeling.....	10
6.0 DRILLING AND COMPLETION^{I-V}	11
6.1 Casing and Tubular Specifications	11
6.2 Wellhead Specifications.....	12
6.3 Drilling Program	12
7.0 DEWATERING^W	12
8.0 MECHANICAL INTEGRITY TESTING^X	13
9.0 CAVERN CONSTRUCTION EXECUTION^{Y-AA}	13
10.0 CAVERN CONSTRUCTION COST^{BB}	13
11.0 SUBMITTALS	14

NYSEG SENECA LAKE CAES PROJECT WATKINS GLEN CAES FACILITY

1.0 INTRODUCTION

NYSEG proposes to develop a compressed air energy storage (CAES) project near Watkins Glen, NY which has a rated generating capacity of 135 - 210 MW. The proposed site is located in the town of Reading, NY near the intersection of State Route 14 and State Route 14A (Figure 1).

Figure 1 – NYSEG CAES Site Location

CAES facilities use electricity from the electric grid, at times of low electricity demand, to compress air and store the compressed air in storage chambers for later use. During periods of high electricity demand air is withdrawn from the CAES reservoir, heated, and expanded through a turbine to drive an electric generator. The CAES plant electricity generation cycle uses about 1/3 the amount of fuel that is required to generate the electricity using conventional combined cycle gas turbines.

NYSEG plans to store the compressed air in underground caverns solution mined from the bedded salt deposits of the Syracuse Formation, located approximately 2,400 feet below the NYSEG Site. Water for the solution mining will be provided by the U.S. Salt and the brine

resulting from the salt dissolution will be processed in the U.S. Salt evaporation plant. Salt has been actively mined using solution mining techniques at the Watkins Glen Field since the 1890's.

This report is a synopsis of the individual contract submittals prepared by PB Energy Storage Services in its role as the Cavern Development Consultant. Each subject heading is followed by superscripts that reference contract submittals. The submittals are identified in Section 11.0 of this report.

2.0 GEOLOGY^{A-D}

Western New York lies in the north end of the Appalachian Synclinorium. The geologic setting consists of a series of gently dipping sedimentary formations overlying the basement complex. The sedimentary-rock surface is mantled by glacial deposits which resulted from glaciation of stream valleys. A generalized geologic column for Western New York is given in Figure 2.

Structural deformation of the Watkins Glen area salt deposits and overlying formations probably occurred during the Appalachian Orogeny, a major period having several cycles of major tectonic activity which took place between late Devonian and the end of Permian time. Compressive forces acting in a nearly north-south direction caused a series of parallel folds oriented approximately N 80° E., thrust faults striking in a similar direction, and high angle north-south strike-slip faults in Silurian and Devonian rocks in the area.

The salt beds underlying the NYSEG site are part of the Salina Group, deposited in the late Silurian time. Overlying the Salina Group is the Akron Dolomite and below the Salina is the Bertie Limestone. The Salina Group is made up of four formations (Figure 3), which are in ascending order:

- Vernon Formation
- Syracuse Formation
- Camillus Formation
- Bertie Formation

**Figure 2 - Generalized Geologic Column for Western New York
(From Van Tyne et al - 1983)**

The Syracuse Formation consists of layers of salt separated by layers of insoluble rock. The major non-salt beds are generally continuous across the field, although the thickness and composition of the beds change. Many of the thinner units cannot be traced between adjacent wells. Geologic interpretation of available well log data near the proposed NYSEG Site implies that the top of the F salt unit is at approximately 2,352 feet below ground level and it will be 475 to 480 feet thick.

3.0 CAVERN CONCEPTUAL DESIGN^{E,F}

Preliminary cavern design was based upon the anticipated geology at the NYSEG Site, the average brine flow rate that can be accommodated by U.S. Salt (350 gpm), the time allocated for solution mining by NYSEG (730 days), the need to maintain a salt roof for the cavern, and the desire to minimize the maximum cavern diameter.

The cavern will be mined in the F unit of the Salina formation. Figure 4 is a conceptual diagram of the F unit at the proposed location. The F unit extends from about 2,352 feet to about 2,827 feet below ground level and is about 475 feet thick at the NYSEG Site. Of the 475 foot F Unit thickness, about 334 feet is salt. For the conceptual design, 50 feet of salt will be left to form the roof of the cavern.

Cavern solution mining simulation modeling was performed to determine the maximum cavern volume that could be developed. All solution mining modeling was performed using SANSMIC. SANSMIC is a cavern simulation model designed to project the development of caverns from a single well. SANSMIC, a widely used cavern modeling program, was developed by Sandia National Laboratories. The model is a two-dimensional numerical simulation code, which approximates the dissolution of salt by water.

Table 1 shows the results of the SANSMIC modeling of caverns developed in three different intervals within the Syracuse Formation. As can be seen in the table, higher vertical percentages of salt in the cavern interval result in larger open cavern volumes. The difference in volume between the last two intervals in the table is very small; however, the increase in cavern diameter from the second to the third interval is significant. Based upon these modeling results a cavern interval from 2,402 feet to 2,632 feet was selected for cavern development.

Figure 3 - Generalized Section of the Salina Group in South Central NY (From Johnson)

Figure 4 - Cavern Location in Expected Stratigraphy of F Salt at CAES Site

SANSMIC modeling for the interval between 2,402 feet and 2,632 feet indicates that a cavern with an open volume of 970,000 barrels can be solution mined in 710 days. The solution mining will require an intermediate workover after the completion of the first reverse leaching stage to re-position leaching strings. Results from the leaching simulation runs are provided in Table 2 and the predicted final cavern shape, and position within the Salina Salt is shown in Figure 4.

Table 1 Comparison of Caverns Developed at Three Depth Ranges

Modeled Depth Range	Open Volume	Floor Depth	Maximum Diameter	Vertical Thickness of Salt
Feet	Barrels	Feet	Feet	Percent
2,402 – 2,832	933,000	2,567	258	66
2,402 – 2,632	970,000	2,527	266	71
2,402 – 2,532	974,000	2,508	284	79

Table 2 – Results of Final Leaching Simulation Model Runs

Mining Step	Step Time at 350 gpm Days	Total Mining Time Days	Open Mined Volume Barrels	Gross Cavern Volume Barrels	Brine Saturation Percent
Sump/Chimney	130	130	67,000	105,000	52.1
Reverse	150	280	272,000	324,000	84.8
Reverse	150	430	506,000	575,000	88.6
Reverse	150	580	752,000	840,000	90.8
Reverse	130	710	970,000	1,073,000	90.8

4.0 CAVERN THERMODYNAMIC MODELING^G

Site specific geology, preliminary CAES duty cycle, and cavern conceptual design data were used to perform thermodynamic modeling of cavern operations. Modeling was performed by RESPEC Inc. using the Salt Cavern Thermal Simulator (SCTS).¹ The SCTS Model was developed by PB Energy Storage Services and RESPEC Inc. to simulate the thermodynamic performance and heat transfer resulting from storage operations of a natural gas storage cavern developed in salt. The version of SCTS used by RESPEC Inc. was modified from the original to include the thermodynamic properties of hydrogen and air.

Thermodynamic modeling of a storage cavern with an open volume of 970,000 bbl, using the NYSEG duty cycle and operating at pressures between 800 psi and 1500 psi, indicated that large swings in temperature could occur. Temperature swings during cavern operation of more than 85°F were predicted by SCTS.² When air is withdrawn from a cavern the air will decompress, causing a decrease in the air temperature that results in the development of thermal stresses in the salt. If the pressure drop is too great, the resultant pressure drop creates a stress state in the salt surrounding the cavern that eventually becomes tensile and the salt fails in tension.

Preliminary geomechanical analyses were performed to assess the impact of the temperature swings on cavern stability. These analyses indicated that tensile stress would develop in the cavern wall due to thermodynamically induced stress when wellhead pressures fall below 1,150

¹ Nieland, J. D. . *Salt Cavern Thermal Simulator Version 2.0 User's Manual*. RSI-1760. RESPEC, Inc. 2004

² Ratigan, Joe L. Presentation to NYSEG. *Cavern Volume Review – Seneca Lake CAES Project*. August 3, 2011.

psi. Since salt has a very low tensile strength, caverns are designed to avoid tensile stress development. The preliminary modeling results indicated that three 970,000 bbl caverns, operated at pressures between 1,150 psi and 1,500 psi, would be required to eliminate the development of tensile stresses during CAES operations.

Based upon these modeling results, the cavern design basis was revised. The revised cavern preliminary design requirements are three storage caverns, each with an open volume of 970,000 barrels, operating between 1,150 psi and 1,500 psi.

Thermodynamic modeling of the revised cavern design was performed by RESPEC, using SCTS, to estimate the temperature boundary condition for the heat transfer numerical modeling and to establish the required diameters for the casing liners. The results of the thermodynamic modeling indicated that:

- The first cavern would require a 20 inch diameter casing liner to compress air at the design rate of 639 lbs per second and withdraw air at 617 lbs per second for 2.3 hours of electrical power generation.
- The second and third caverns require a 16 inch diameter casing to flow air at a combined rate of 639 lbs per second and to withdraw air at 617 lbs per second for 4.9 hours of electrical power generation.
- All three caverns combined are required to generate electricity in accordance with the preliminary NYSEG duty cycle.
- The wellhead temperature will vary from 71° F to 101° F during CAES operations.
- The Salt temperature will cycle between 85° F and 126° F during CAES operations.
- Wellhead Pressures will cycle between 1,150 psi and 1,500 psi at the wellhead during CAES operations.

5.0 THERMAL AND THERMOMECHANICAL MODELING^H

Numerical modeling of a single 970,000 barrel CAES cavern, operating at pressures between 1,150 psi and 1,500 psi, was performed by RESPEC. The modeling was performed to evaluate cavern stability, determine cavern closure due to creep, and to estimate well casing strains during CAES operation. The modeling was composed of two separate models; the heat transfer finite element model and the thermomechanical model.

Cavern stability is a function of the stress state in the salt surrounding the opening, which in turn is a function of the cavern shape, the air pressure inside the cavern, the insitu stress, cavern creep and the thermally induced stresses in the salt. The thermally induced stresses, due to

pressure cycling of the cavern during operation, have a significant impact on the stress state in the salt surrounding the cavern.

5.1 HEAT TRANSFER FINITE ELEMENT MODEL

SPECTROM-41³ was used to simulate the heat transfer between the cavern wall and the surrounding salt. SPECTROM-41 is a finite element heat transfer program developed by RESPEC, Inc. to model heat transfer in geologic formations.

Heat transfer modeling was performed to simulate a thirty year time period, during which the cavern was cycled between minimum and maximum operating pressure in accordance with the preliminary NYSEG CAES duty cycle. Temperature fluctuations in the salt surrounding the cavern, due to cavern operations, ranged from 25°F at the cavern wall to 0° F five feet beyond the wall of the cavern. Predicted temperatures at the salt walls of the cavern are shown in Figure 5.

Figure 5 – Salt Wall Predicted Temperatures After 5 Years of Operation

³ Svalstad, D. K. *Documentation of SPECTROM-41: A Finite Element Heat Transfer Analysis Program*. RE/SPEC Inc. 1989.

The preliminary geomechanical modeling results, discussed in Section 4.0, implied that tensile stress would not develop in the cavern walls for the temperature swing of 25°F. The results from the heat transfer modeling were used in the thermomechanical modeling to assess cavern stability.

5.2 THERMOMECHANICAL MODELING

Cavern salt temperature modeling results, predicted cavern pressures during operations, insitu stress, rock material properties, and rock thermal properties were used to model the thermomechanical behavior of the cavern over a 30 year operating period. The numerical modeling code SPECTROM-32⁴ was used for the thermomechanical modeling. SPECTROM 32 was developed by RESPEC for simulation of underground openings in both brittle rock and in rock which behaves viscoplastically like salt.

Thermomechanical modeling for a period of 5 years of cavern operations was performed to evaluate the potential for salt dilation and hydraulic fracture. A 30 year thermomechanical model, at minimum cavern pressure, was used to estimate cavern creep closure, shear failure of non-salt geologic units, and strain in the well casing.

Modeling results from the cavern operation model were evaluated by calculating factors of safety in the salt and non salt units relative to dilation (for salt) and shear failure in nonsalt units. Modeling results indicate that minimal salt dilation is predicted to occur in the upper corner of the cavern and the floor of the cavern during the first two weeks of operation. While the dilation may result in sloughing of the salt it is not expected to affect cavern stability. No shear failure of the nonsalt units above the cavern was predicted during cavern operations. Fracturing of thin nonsalt units intersecting the cavern are not expected to result in instability or loss of cavern integrity. Stresses surrounding the cavern remained compressive for the five year cavern operation modeling period, implying that no thermally induced fractures are predicted perpendicular to the cavern walls.

Cavern closure and strain in the cemented casing were evaluated during a simulated 30 year period of operation at minimum cavern pressure (1,150 psi). A creep closure of 0.48% was predicted over the 30 year simulation period. This magnitude of creep closure is very small relative to other salt storage caverns. This closure rate will result in strain rates in the cemented

⁴ Callahan, G. D., A. F. Fossum, and D. K. Svalstad. *Documentation of SPECTROM-32: A Finite Element Thermomechanical Stress Analysis Program*, RE/SPEC Inc., 1989.

casing of less than 7 microstrain and is not expected to result in casing failure during the life of the cavern.

6.0 DRILLING AND COMPLETION^{I-V}

The drilling and completion programs for the proposed NYSEG CAES wells are premised on the NYSEG requirements that:

- All three caverns must flow in parallel at the design rate for the NYSEG specified duty cycle.
- The first cavern must flow at the design flow rate.
- Any two caverns must flow in parallel at the design flow rate

6.1 CASING AND TUBULAR SPECIFICATIONS

Based upon these requirements the well casing, casing liner, and tubulars for solution mining and dewatering were selected. All casing performance was assessed in accordance with American Petroleum Institute (API 5C3).

Casing for the first well will be a 42" surface conductor casing set and cemented to approximately 175 feet below ground surface, a 30" diameter surface casing set and cemented to a depth of approximately 850 feet below ground surface, a 24" final cemented casing set and cemented to a depth of approximately 2,360 feet below ground surface, and a 20" suspended stainless steel production liner set at a depth of 2,407 feet below ground surface.

Casing for Wells 2 & 3 will be a 42" surface conductor casing set and cemented to approximately 175 feet below ground surface, a 26" diameter surface casing set and cemented to a depth of approximately 850 feet below ground surface, a 20" final cemented casing set and cemented to a depth of approximately 2,360 feet below ground surface, and a 16" suspended stainless steel production liner set at a depth of 2,407 feet below ground surface.

Leaching tubulars are sized for a brine flow rate of 350 gpm, subject to the requirement to be able to pass a 4" conventional sonar survey tool. The casing depths are specified in the leaching plan. Setting depths, at the start of solution mining, are 2,530 feet below ground level for the outer 8-5/8" casing and 2,630 feet below ground level for the inner 5-1/2" tubing.

6.2 WELLHEAD SPECIFICATIONS

Wellheads were specified in accordance with API 6A. The leaching wellhead was selected to suspend tubulars for solution mining. Upon completion of solution mining, the leaching wellhead sections above the bradenhead flange will be replaced with corrosion resistant wellhead sections. Following dewatering, the dewatering string will be snubbed out of the cavern, the master valve shut, and corrosion resistant wellhead components installed to prepare the cavern for CAES operations.

6.3 DRILLING PROGRAM

Final drilling procedures will be developed after selecting a drilling contractor and final casing setting depths will be established after wellbore logging. The drilling program developed for NYSEG consists of:

- Drilling, running, and cementing the conductor pipe.
- Mobilizing drilling rig to the wellpad.
- Drilling the surface hole, running the surface casing, and cementing it in place.
- Drilling the production hole, running the production casing, and cementing it in place.
- Drilling the hole through the cavern interval to the total depth. Coring will be performed during the drilling of Well No. 2 only.
- Running the leaching strings and installing the surface wellhead.
- Demobilizing drilling rig from wellpad.

7.0 DEWATERING^W

Upon completion of solution mining the cavern will undergo preliminary mechanical integrity testing, followed by a conversion workover to ready the cavern for dewatering. The workover consists of removing the leaching tubulars and leaching wellhead components, running and welding the stainless steel cemented casing liner, installing the dewatering sections of the wellhead, and running a dewatering string to a depth near the floor of the cavern.

Due to the low rate of brine acceptance by U.S. Salt it will be necessary to dewater the cavern using temporary compressors. Injection of air will take place down both the annulus between the dewatering string and the liner and between the liner and the final cemented casing to prevent casing collapse. The dewatering will take approximately 78 days. After the air / brine interface reaches the roof of the cavern the wellhead pressures will not increase significantly during

dewatering. A maximum air pressure of 1,300 psi and a maximum flow rate of 3,750 scfm are anticipated during dewatering.

8.0 MECHANICAL INTEGRITY TESTING^X

Each NYSEG cavern will undergo preliminary mechanical integrity testing prior to the start of the conversion workover. This test will assess the integrity of the cavern prior to running and welding the stainless steel liner. The nitrogen interface will be set between the casing shoe and the cavern roof by removing a portion of the nitrogen which makes up the roof blanket. Once the nitrogen interface is set, the wellbore integrity will be evaluated using nitrogen mechanical integrity testing techniques.

The final MIT for the NYSEG caverns will take place after running the stainless steel liner, and installing the dewatering casing and wellheads. This test is designed to test the cavern wellbore, dewatering wellhead components, and dewatering string for gross leakage prior to the start of dewatering.

9.0 CAVERN CONSTRUCTION EXECUTION^{Y-AA}

Cavern construction execution is composed of the overall project schedule, combined, with a proposed methodology of contracting wellpad construction, drilling, solution mining, workovers, and final conversion. A cavern development construction manager who is thoroughly familiar with drilling large diameter cavern storage wells, cavern well workover, and the management of solution mining of storage caverns is critical to the success of the project.

The responsibilities of the cavern development construction manager include specification development, specialized procurement, management and contracting of drilling and workover operations required, management of solution mining operations, and engineering support required to successfully develop storage caverns.

10.0 CAVERN CONSTRUCTION COST^{BB}

A final revised cavern construction cost estimate of \$36.6 million (2011 dollars) was developed by PB ESS based upon actual historical costs experienced along the Gulf Coast and in New York. This cost does not include land acquisition cost, access road cost, or costs associated with the permitting of a CAES facility in New York.

11.0 SUBMITTALS

- A. Eyermann, Thomas. *Overview of Geology of the Area Around the US Salt Watkins Glen Refinery*. PB Energy Storage Services Inc. September 2011.
- B. PB ESS Inc. Letter Report: *Location of TEPPCO Watkins Glen Propane Storage Facility*. October 20, 2011.
- C. PB ESS Inc. Letter Report: *Constituents and Quality of Formation's Salts*. October 24, 2011.
- D. PB ESS Inc. Letter Report: *Update of Earthquake Data 1998 – 2011*. November 30, 2011.
- E. Eyermann, Thomas. *Initial Cavern Design Watkins Glen CAES*. PB Energy Storage Services Inc. October 2011.
- F. PB ESS Inc. Drawing: *Storage Well Site Plan*. November 2011.
- G. Nieland, Joel. Letter Report. Nieland to McHenry. Subject: *Thermodynamic Evaluation of Proposed New York State Electric & Gas Corporation Compressed Air Energy Storage Cavern Design*. RESPEC Inc. October 4, 2011.
- H. RESPEC Inc. *Geomechanical Evaluation of the New York State Electric & Gas Corporation Compressed Air Energy Storage Cavern Design*. Topical Report RSI – 2240. November 2011.
- I. PB ESS Inc. *Well Casing and Tubulars – Watkins Glen CAES*. November 2011.
- J. PB ESS Inc. *NYSEG Seneca Lake CAES Proposed New Leaching Wellhead – Cavern No. 1*. November 2011.
- K. PB ESS Inc. *NYSEG Seneca Lake CAES Proposed New Leaching Wellhead – Cavern No. 2 & 3*. November 2011.
- L. PB ESS Inc. *NYSEG Seneca Lake CAES Proposed New Dewatering Wellhead – Cavern No. 1*. October 2011.
- M. PB ESS Inc. *NYSEG Seneca Lake CAES Proposed New Dewatering Wellhead – Cavern No. 2 & 3*. October 2011.
- N. PB ESS Inc. *NYSEG Seneca Lake CAES Proposed New Production Wellhead – Cavern No. 1*. October 2011.
- O. PB ESS Inc. *NYSEG Seneca Lake CAES Proposed New Production Wellhead – Cavern No. 2 & 3*. October 2011.
- P. PB ESS Inc. *NYSEG Watkins Glen Proposed CAES Well No. 1 – Drilling Program*. September 2011.
- Q. PB ESS Inc. *NYSEG Watkins Glen Proposed CAES Well No. 2 – Drilling Program*. November 2011.

- R. PB ESS Inc. *NYSEG Watkins Glen Proposed CAES Well No. 3 – Drilling Program*. November 2011.
- S. PB ESS Inc. *Intermediate Workover Program – Well No. 1, 2, & 3*. November 17, 2011.
- T. PB ESS Inc. *Conversion Workover Program – Well No. 1, 2, & 3*. November 17, 2011.
- U. PB ESS Inc. *Snubbing Program – Well No. 1, 2, & 3*. November 17, 2011.
- V. PB ESS Inc. *NYSEG Watkins Glen Open Hole Logging Plan*. November 2011.
- W. PB ESS Inc. Letter Report: *Dewatering Program for NYSEG CAES Caverns*. McHenry to Rettberg. December 13, 2011.
- X. PB ESS Inc. *Cavern Testing Program – CAES Storage Cavern*. November 2011.
- Y. PB ESS Inc. *Construction Execution Plan – CAES Storage Cavern*. November 2011.
- Z. PB ESS Inc. Drawing: *NYSEG Seneca Lake Wellpad Sections and Details*. November 2011.
- AA. PB ESS Inc. *NYSEG CAES Project Schedule*. Delivered in Microsoft Project 2007 Format. October 2011.
- BB. PB ESS Inc. *Individual Cost Estimates*.
 - a. Cavern Construction Cost Estimate. October 31, 2011.
 - b. Wellpad Cost Estimate. December 7, 2011.
 - c. MIT Cost Estimate – Cavern No. 1. October 2, 2011.
 - d. MIT Cost Estimate – Cavern No. 2 & 3. October 2, 2011.
 - e. Drilling Cost Estimate Well No. 1. October 2011.
 - f. Drilling Cost Estimate Well No. 2. October 2011.
 - g. Drilling Cost Estimate Well No. 3. October 2011.
 - h. Intermediate Workover Cost Estimate. October 31, 2011.
 - i. Conversion Workover Cost Estimate Well No. 1. October 15, 2011.
 - j. Conversion Workover Cost Estimate Well No. 2 & 3. October 15, 2011.
 - k. Final Wellhead Installation Cost Estimate Well No. 1. October 31, 2011.
 - l. Final Wellhead Installation Cost Estimate Well No. 2 & 3. October 10, 2011.
 - m. Set Nitrogen Blanket Cost Estimate Well No. 1. October 2, 2011.
 - n. Set Nitrogen Blanket Cost Estimate Well No. 2 & 3. October 2, 2011.
 - o. Snubbing Cost Estimate. October 31, 2011.
 - p. Sonar Survey Cost Estimate. October 11, 2011.
 - q. Wellpad Piping Cost Estimate. October 10, 2011.
- CC. PB ESS Inc. Letter Report: Preliminary Cavern Criteria. August 11, 2011.

DD. PB ESS Inc. Letter Report: Environmental Report Questionnaire Input. December 15, 2011.

OVERVIEW OF GEOLOGY OF THE AREA AROUND THE US SALT WATKINS GLEN REFINERY

Watkins Glen, New York

Prepared for

NYSEG

Binghamton, NY

Prepared by

Thomas Eyermann

PB ENERGY STORAGE SERVICES, INC.

Houston, TX

**Project No. 50756B
September 2011**

TABLE OF CONTENTS

SECTION	PAGE
1 SITE DESCRIPTION	3
2 GEOLOGICAL FRAMEWORK	3
2.1 Regional Geology:	3
2.1.1 Stratigraphy and Lithology	3
2.1.2 Structure	6
2.2 Site Geology	6
2.3 Faulting:	14
3 REFERENCES	16

LIST OF FIGURES

SECTION	PAGE
Figure 1 - Generalized Geologic Column for Western New York	5
Figure 2 - Generalized Section of the Salina Group in South Central NY	9
Figure 3 - Cavern Location in Expected Stratigraphy of F Salt at CAES Site	11
Figure 4 – Structural Contour Map of Syracuse Salt Near Seneca Lake NY	12
Figure 5 – Generalized Salt Isopachs Near Seneca Lake NY	13
Figure 6 - Geophysical Log of Well 58 Showing F Salts	15

LIST OF TABLES

<u>TABLE</u>	<u>PAGE</u>
Table 1 Expected Geologic Formations and Depths at the CAES Site	7
Table 2 Anticipated Lithology of F Unit at the CAES Site	8

1 SITE DESCRIPTION

Inergy's U S Salt facility is located on the west shore of Seneca Lake in Schuyler County, approximately 2 miles north of Watkins Glen, New York. New York State Route 14 highway passes from north to south across the property.

The terrain rises steeply from the lake toward the west at a rate of about 300 feet in one-half mile. Once above the lake, the ground continues to rise at a rate of about 400 feet per mile. The proposed CAES facility is at an elevation of about 1,000 feet. The site is covered with native vegetation. The site is cut by a number of west to east streams, most of which are seasonal.

The brinefield and proposed CAES facility are north of the town of Watkins Glen, at the southern end of Seneca Lake. It is part of the Finger Lakes district of the Allegheny Plateau physiographic province. The rocks that crop out in the Finger Lakes area are Devonian Age sedimentary formations that regionally dip gently to the southwest. Major surface features of the area result primarily from glaciation of stream valleys.

2 GEOLOGICAL FRAMEWORK

2.1 REGIONAL GEOLOGY:

Western New York lies in the north end of the Appalachian Synclinorium. The geologic setting consists of a series of gently dipping sedimentary formations overlying the basement complex. The sedimentary-rock surface is mantled by glacial deposits.

2.1.1 Stratigraphy and Lithology

A sequence of primarily Paleozoic sedimentary rocks overlies the crystalline Precambrian rocks. A generalized geologic column for western and central New York is shown in Figure 1. The lowermost sedimentary rocks are part of the Cambrian System. The Potsdam Sandstone is composed of fine to medium quartzitic and dolomitic sand. The Potsdam lies unconformably on the Precambrian and grades upward into the Theresa Formation of interbedded dolomite and sandstone. Overlying the Theresa in the southern half of the region is the Little Falls Dolomite. The relatively dense Little Falls contains significant quantities of quartz sand.

Ordovician rocks overlie the Cambrian System. With the exception of the lowermost unit-Beekmantown Group-the Ordovician strata lie above an erosional surface called the Knox unconformity. From the lowermost units, they are the Beekmantown Group (largely shales), Black River Group and Trenton Group (both carbonates), Lorraine Shale, Oswego Sandstone,

and the Queenstown Shale. The Knox unconformity is a significant horizon that controls oil and gas accumulation.

The Silurian System overlies the Ordovician and consists, from oldest to youngest, of the following: Medina Group, Clinton Group, Lockport Group, Salina Group, and Bertie Limestone (often included in Salina Group). The units consist of sandstone, carbonates, and shales. The salt beds of New York are part of the Salina Group, deposited during Late Silurian time in the northern part of the Appalachian Basin. The Salina group consists of four formations. These are in ascending order: Vernon, Syracuse, Camillus, and Bertie. Overlying the Salina Group is the Akron dolomite. A further subdivision (Figure 2) of the Salina Group (Landes, 1945) subdivides it into several units from A at the base to H at the top of the Group.

The Vernon formation (Salina units A, B and C) consists primarily of red shale but contains locally beds of green shale, dolomite, sandstone or gypsum. Salt beds are present near the middle of the Vernon in the B unit in western New York, but appear to be absent in the Watkins Glen area. These salt beds are mined at several locations in western New York.

Overlying the Vernon is the Syracuse Formation (Salina units D, E, and F) which consists of a series of interbedded salt, dolomite and dolomitic shale units. Salt beds are present in each of these subsurface units. The salt is interbedded with dolomite, argillaceous dolomite, and anhydrite. US Salt's newer wells are developed in the "F" unit. The older wells were initially developed in the "D" unit and mined up to the top of the formation.

The Camillus formation (unit G) conformably overlies the Syracuse. At Watkins Glen gray shales predominate with some quartzose sandstones and dolomites present. In some of the wells drilled (such as Wells 17 and 57) in the northern section of the US Salt brinefield, "black water" was encountered near the base of the Camillus. The Bertie formation (unit H) rests above the Camillus. The Bertie consists of dolomites interbedded with shale and gypsum.

Devonian rocks make up the surficial bedrock in the area of this study. The system largely consists of major groups of carbonates and shales near the bottom and then a succession of numerous shale, sand, and limestone units.

Glacial drift mantles most of the area in varying thickness. In most areas the drift is less than 25 ft thick, but in bedrock valleys and under the lakes it may be several hundred feet. In general, the drift is composed of fine-grained lacustrine sediments in the northern third of the area, with till capping most of the highlands, and sand and gravel outwash in the valley floors. Modern streams have reworked the drift and deposited alluvium adjacent to the streams.

**Figure 1 - Generalized Geologic Column for Western New York
(From Van Tyne et al - 1983)**

2.1.2 Structure

The sedimentary rocks above the Knox unconformity dip gently to the southwest at about 40 feet per mile. Most of the units thicken to the south. The sedimentary sequence has a gentle undulating structure. The Clarendon-Linden fault system occurs to the west as high-angle thrust faults associated with a north-trending anticline. Large anticlines are common near the surface in the area but apparently do not extend into the deeper formations below the Salina Group.

2.2 SITE GEOLOGY

Historically, solution mining operations at the Watkins Glen Refinery brine field have been ongoing since 1893. Detailed sample examinations, core descriptions and geophysical well logs run in wells drilled after 1955 provide detailed information on the geology underlying the site. From the data, a general description of the expected lithology at the proposed CAES site is given in Table 1. The anticipated lithology of the F unit at the proposed location is given in Table 2 and Figure 3.

The surface outcrop at the brinefield is a member of the upper Devonian West Falls Formation. Conformably, this overlies the remainder of Middle and Lower Devonian strata which consist of Genesee Formation, Tully limestone, Hamilton Group including the Moscow, Ludlowville, Skaneateles and Marcellus shales, Onondaga Limestone, Oriskany Sandstone and Helderberg Group with Manlius and Rondout Limestones. The Akron (Cobleskill) dolomite is the base of the Devonian strata.

The top of Silurian Period is the Salina Group with the Bertie (Bass Island) formation of limestone and shale beds underlain by the Camillus. The Camillus is predominantly shale at the brinefield. The salt beds at Watkins Glen are members of the Syracuse formation underlying the Camillus. The Syracuse lies above the Vernon which is shale immediately under the Syracuse.

Jacoby (1963) divided the Syracuse at the brinefield into general six distinct salt beds which are in turn separated by alternating layers of insoluble rock. In descending order from the top of the first halite, there is the No. 1 Salt, No. 1 Rock, No. 2 Salt and so forth through the base of the No. 6 Salt. Underlying the No. 6 salt is the Vernon shale which has been explored by one well at the brinefield. The well did not penetrate any salt in the Vernon.

Table 1 Expected Geologic Formations and Depths at the CAES Site

Geologic Unit	Approximate Thickness Feet	Approximate Elevation Top of Unit Feet
Genesee	830 (partial)	1000 (Ground Elevation)
Tully	17	170
Hamilton	921	153
Marcellus	98	-768
Onondaga	45	-866
Tristates Group	37	-911
Oriskany	8	-948
Helderberg Group	150	-956
Cobleskill/Akron	60	-1106
Bertie	90	-1166
Camillus	97	-1256
Syracuse	850	-1353

Table 2 Anticipated Lithology of F Unit at the CAES Site

Rock Type	Mean Sea Level ElevationTop	Base	Measured Depth Top	Base	Lithology Thickness	Insoluble Percentage
Salt	-1352	-1361	2352	2361	9	1
Shale	-1361	-1363	2361	2363	2	95
Salt	-1363	-1415	2363	2415	52	5
Shale	-1415	-1418	2415	2418	3	80
Salt	-1418	-1433	2418	2433	15	3
Shale	-1433	-1441	2433	2441	8	90
Salt	-1441	-1454	2441	2454	13	10
Shale	-1454	-1462	2454	2462	8	90
Salt	-1462	-1466	2462	2466	4	10
Dolomite	-1466	-1469	2466	2469	3	90
Salt	-1469	-1477	2469	2477	8	10
Shale	-1477	-1482	2477	2482	5	90
Salt	-1482	-1534	2482	2534	52	5
Dolomite/Shale	-1534	-1563	2534	2563	29	95
Salt	-1563	-1564	2563	2564	1	10
Shale	-1564	-1567	2564	2567	3	90
Salt	-1567	-1618	2567	2618	51	10
Shale/Dolomite	-1618	-1651	2618	2651	33	95
Salt	-1651	-1675	2651	2675	24	3
Shale	-1675	-1708	2675	2708	33	95
Salt	-1708	-1743	2708	2743	35	3
Shale	-1743	-1750	2743	2750	7	90
Salt	-1750	-1795	2750	2795	45	3
Shale	-1795	-1802	2795	2802	7	85
Salt	-1802	-1827	2802	2827	25	3

Figure 2 - Generalized Section of the Salina Group in South Central NY

Jacoby's divisions roughly relate to the Landes' Salina classification in that the No. 1 through 4 salt units correspond to F4 through F1 salt units although there is some overlap between units, The No. 5 salt and No. 6 salt are equivalent to the D Salt. The No. 3 rock of Jacoby is equivalent to the E unit.

Figure 4 shows the top of salt in the brinefield and CAES site area. Control on the salt is excellent to the east of the CAES site due to the presences of a large number of wells in the brinefield. Control to the north is fair with four wells within one and one half miles of the proposed site. However there is no nearby control to the west or south. The Corbett Point syncline is a major structural feature that is mapable from Ithaca to the east and westward to the Pennsylvania border. It appears that the CAES well will be located very near the axis of the syncline. This may result in some thickening of the Syracuse formation in general and particularly some of the individual salt beds within it.

The F salts at the US Salt facility vary in thickness from about 410 feet to 543 feet, generally thickening to the southwest. A generalized isopach map of the F unit (including salt and non-salt beds) is shown in Figure 5. Due to faulting in the area, the isopachs become difficult to define. There is a trend towards thickening of the salt along the Corbett Point Syncline. The isopach map indicates that the F Unit sequence will be about 475 to 480 feet thick at the CAES unit.

The Syracuse salt, as with most bedded salt deposits, is not only halite. The formation contains major and minor beds of dolomite, dolomitic shale, anhydrite and shale. Figure 6 shows an F Unit from Well 58, highlighting the sections that are primarily salt. In Figure 6, the white intrusions into the colored background are non-salt beds. In Well 58 the F Unit is about 475 feet thick, from about 2158 feet depth to 2633 feet. Within that interval, there are about 327 feet of halite, about 69% of the interval, and 148 feet of non-salt rocks. This ratio of halite to non-halite beds in the F Unit is typical at the US Salt facility and is expected to continue at the CAES facility with about 334 feet of halite beds and 141 feet of non-halite beds.

The major non-salt beds are generally continuous across the field, although the thickness and composition of the beds change. Many of the thinner units cannot be traced between adjacent wells.

Figure 3 - Cavern Location in Expected Stratigraphy of F Salt at CAES Site

Generalized F Salt Isopachs Seneca Lake, Schuyler County, New York

0 1000 2000 3000 Feet

JOB No.

DESIGN:

TE

DRAWN:

HH

CHECKED:

JM

DATE:

08/11

SCALE:

DRAWING No.

FIGURE 5

2.3 FAULTING

Structural deformation of the Watkins Glen area salt deposits and overlying formations probably occurred during the Appalachian Orogeny, a major period having several cycles of major tectonic activity which took place between late Devonian and the end of Permian time.

Compressive forces acting in a nearly north-south direction caused a series of parallel folds oriented approximately N 80° E., thrust faults striking in a similar direction, and high angle north-south strike-slip faults in Silurian and Devonian rocks in the area.

Faulting has complicated both conventional underground mining and solution mining of salt in the vicinity of Seneca Lake in Schuyler, Yates and Tompkins Counties. Within the US Salt brine field area, Jacoby and Dellwig (1973) report a major, near vertical, north-south strike-slip fault located east of Wells 41, 37 and 29. Jacoby and Dellwig also describe a low angle "bedding " thrust fault which passes through the sequence of salt and shale beds which has been developed by solution mining. The thrust fault strikes east-northeast and dips southerly. In the southern part of the US Salt study area, Jacoby and Dellwig (1973) report a single fault which then divides into several faults proceeding northward.

A considerable amount of hydrofracturing was done in the brine field to attempt to connect adjacent wells for solution mining purposes. Hydrofracturing, when successful, was conducted at the bottom of the Syracuse, generally in the D salt immediately above the Vernon. Hydrofracturing connected wells in the southern portion of the brinefield generally in an east-west alignment. In the northern portion of the field, wells were generally connected along a roughly north-south orientation.

Because of the fault-disrupted beds in the brine field frac-connecting of wells was often difficult or unsuccessful. Hydrofractures in some cases intersected faults in the brine field so leakage of fluids from the galleries could occur along natural or manmade breaks. Jacoby and Dellwig (1973) report that a hydrofracturing attempt In Well 29 resulted in a flow of brine to surface one-half mile to the north. They assumed the fluid traveled along the major north-south strike-slip fault.

Figure 6 - Geophysical Log of Well 58 Showing F Salts

3 REFERENCES

Jacoby, Charles H., 1963. *International Brine Field at Watkins Glen, New York, First Symposium on Salt*, Northern Ohio Geological Society. Cleveland, Ohio

Jacoby, Charles H. and L. F. Dellwig, 1973. *Appalachian Foreland Thrusting in Salina Salt*, Watkins Glen, New York, Fourth International Symposium on Salt, Northern Ohio Geological Society. Cleveland, Ohio

Johnson, Kenneth S and Serge Gonzales, 1978. *Salt Deposits in the United States and Regional Geologic Characteristics Important to the Storage of Radioactive Waste*.

Landes, K. K., 1945. *The Salina and Bass Islands Rocks in the Michigan Basin*, U. S. Geol. Survey, Prelim. Map No. 40, Oil and Gas Inv. Ser., Washington, DC

Ryder, Robert T., et al; 2007. *In search of a Silurian Total Petroleum System in the Appalachian basin of New York, Ohio, Pennsylvania and West Virginia*. U. S. Geological Survey Open File Report 2007-1003, Washington, DC

16285 Park Ten Place, Suite 400
Houston, Texas 77084

(281) 496-5590
Fax (281) 496-5865
www.pbenergy.com

October 20, 2011

James W. Rettberg, PE
Project Manager
NYSEG

Dear Mr. Rettberg;

Re: Location of TEPPCO Watkins Glen Propane Storage Facility

Introduction

Task 4.2.2.7 of the Technical Specification for the Cavern Development Consultant is to prepare a Letter Report addressing the proximity of the TEPPCO Propane Storage Cavern to the proposed NYSEG CAES cavern and evaluate any proposed risks associated with the location.

TEPPCO Cavern Description

The TEPPCO (owned by EPCO, Inc) propane storage cavern at Watkins Glen, NY was designed and constructed by Fenix and Scisson (now owned by PB ESS) and began operation during 1984¹. The facility is located on State Route 14 in Watkins Glen, a rural town with a population of approximately 2,150. The facility risk management plan² describes the Watkins Glen propane storage facility as a propane storage and loading facility. The propane is received by pipeline and stored in a shallow conventionally mined underground storage cavern.

The cavern was mined in the shales and siltstones at near Watkins Glen, NY between 535 ft MSL and 569 ft MSL. The cavern was mined in a room and pillar pattern within a competent siltstone. The completed cavern volume was approximately 1.3 MMB³. Conventionally mined LPG caverns are typically operated at pressures below the hydrostatic gradient.

Location Relative to Proposed NYSEG CAES Cavern

Figure 1 is an aerial photograph of the proposed location of the NYSEG CAES Cavern with the outline of the Watkins Glen Propane Storage Underground Facility superimposed. The outline of the Watkins Glen Facility was obtained from the files of Fenix & Scisson.

The proposed NYSEG CAES Cavern will be located nominally 1,900 ft deeper and approximately ½ mile north of the existing TEPPCO Watkins Glen Underground Storage Chamber.

Impact Evaluation

PB ESS does not believe that the location of the TEPPCO Watkins Glen Propane Storage Cavern relative to the proposed location of the NYSEG CAES Cavern presents any significant risks to either operation.

References

1. Fenix & Scisson. Brochure. *Mined Storage Caverns*. Undated.
2. Energy Storage Services Inc. Web site: www.pbenergy.com
3. U.S. Environmental Protection Agency. Risk Management Plan – Enterprise Watkins Glen Terminal. www.rtknet.org

Please do not hesitate to call or email if you have questions or suggestions.

Regards,

James M McHenry

16285 Park Ten Place, Suite 400
Houston, TX 77084

(281) 496-5590
Fax (281) 496-5865
www.pbenergy.com

October 24, 2011

James Rettberg, P.E.
Project Manager
NYSEG
18 Link Drive, Box 5224
Binghamton, NY 13902-5224

Dear Mr. Rettberg;

Re: Submittal 4.2.2.6 Constituents and Quality of Formation's Salts

Technical Specification Deliverable 4.2.2.6 is a letter report detailing the constituents and quality of the formation salt. This submittal discusses impurities and contaminants which have been identified in the brine produced at Watkins Glen.

Background

The brine produced from the proposed NYSEG cavern will be used as feedstock to the US Salt plant at Watkins Glen, NY. In order to be useful to the plant, the brine needs to be saturated and relatively free of impurities.

The brine produced from creation of the CAES caverns will not be saturated in sodium chloride. The brine from the wells will need to be cascaded through an existing large cavern to become fully saturated and suitable for plant use.

Impurities in the Salina Salt formation of New York State include shale, anhydrite, gypsum, dolomite, and pyrite. These rocks and minerals can break down to produce clay, sand, calcite, iron, magnesium, carbonate and sulfate. The impurities will occur as admixes to the brine. Typical analyses of brine produced from the Salina salt are listed in Table 1 (from Kaufmann, 1960.)

Table 1 Typical Compositions of Salina Brines

Chemical	Well A – Weight Percent	Well B – Weight Percent
Sodium Chloride	25.42	25.48
Calcium Chloride	0.09	0.58
Magnesium Chloride	0.04	0.14
Calcium Sulfate	0.45	0.25

The impurities that occur within the Salina formation have not caused difficulties in processing brine produced from the salt. However, some treatment is required to remove sulfates to produce a purified salt suitable for some purposes.

Solid particles such as clay are generally not in the brine due to the low velocity of the brine in the large diameter strings used for mining. Any particulate matter that may be carried with the brine will have opportunities to settle out when the brine is cascaded through another cavity to become saturated.

In some past in the US Salt Brinefield, there have been instances of hydrogen sulfide contaminating the brine. Historical cases have been traced to mining the salt to the overlying Camillus with subsequent collapse of roof. This allowed “black water” to flow into the cavity. This black water in the Camillus does not appear to be present everywhere in the field, but has been seen in the northern sections (Wells 17, 18 and 57) and possibly in the old wells along the lake shore. Another source of past contamination of the brine has been the overlying Oriskany/Marcellus section of the geology. Hydrogen sulfide bearing black water from this section has corroded through casing (particularly in old wells that were not cemented to surface), allowing the black water to mix with the cavern brine.

Issues related to hydrogen sulfide contamination can be prevented by leaving a salt roof above the cavity and by properly cementing the casing through the black water bearing zones.

Summary

The brine that will be produced from the proposed NYSEG CAES caverns will be of a quality, other than sodium chloride saturation, that can be processed in the US Salt plant without causing any upsets.

The major possible source of chemical impurities is black water in the overlying formations. This can be prevented from becoming an issue by leaving a thick salt roof as proposed and properly cementing the casings.

As discussed above, the produced brine from the CAES caverns will not be saturated. The brine will need to be cascaded through existing US Salt wells to become saturated before being sent to the refinery.

References

Kaufmann, Dale W., 1960. Sodium Chloride. American Chemical Society, Washington, D.C.

Sincerely,

Tom Eyermann
Solution Mining Engineer

cc: James McHenry, Joe Ratigan, Joel Nieland, John Osnes

16285 Park Ten Place
4th Floor
Houston, Texas 77084

(281) 496-5590
Fax (281) 589-5865

November 30, 2011

James W. Rettberg, PE
Project Manager
NYSEG

Dear Mr. Rettberg;

Re: Letter Report Update of Earthquake Data (1998 – 2011)

The NYSEG Cavern Development Consultant Technical Specification deliverable 4.2.2.8 directs PB ESS to prepare a letter report updating the seismic study dated 1998 with all seismic data generated to the current date. To support this effort NYSEG transmitted a report titled Earthquake Data Base Search Update¹ to PB ESS. This letter report documents the update of earthquake data performed for the time period 1998 to 2011.

Introduction

In June 1994 Fenix & Session, owned by PBESS, prepared a geological report² describing an investigation to assess possible geological impacts related to the pressure integrity of Gallery No. 1 at the Akzo Salt Brinefield near Watkins Glen, NY. The report was prepared in support of NYSEG's permit application for conversion of AKZO Gallery No. 1 to Natural Gas Storage. Included in the report was a brief discussion of historical earthquakes in the area surrounding Gallery No. 1.

The historical data presented in the F&S report was acquired from the National Geophysical Data Center of the National Oceanic and Atmospheric Administration. Earthquake data was acquired for a 150 kilometer radius circle centered at latitude 42.417°N, longitude 76.892°W (Akzo Gallery No. 1). The report concluded that “The Watkins Glen area, including the AKZO brinefield, is in a very quiet seismic area in which no appreciable seismic events have occurred during recorded history.” The four closest earthquake centers were approximately of 35 to 36 kilometers from Gallery No. 1.

In 2001 PB-KBB (now PBESS) updated the data in the 1994 earthquake database in support of a permit application by Seneca Lake Storage to convert AKZO Gallery No. 2¹ to natural gas storage. PB-KBB concluded in the report that “New earthquake data obtained for the period of

January 1, 1991 to the present indicate that the area containing Galleries Nos. 1 and 2 continues to be an area of very low seismicity.”

The historical data presented in the PB-KBB report were acquired from the USGS National Earthquake Information Center (NEIC). PB-KBB reported that the original data source for the 1994 report was no longer available from the National Geophysical Data Center; the service being transferred to the USGS. Three earthquakes with magnitudes 2.7 to 3.6 were reported in 1994, 1999, and 2001.

Earthquake Data 1998 to 2011

NYSEG has directed PB ESS to update the earthquake database for the period 1998 to present. The earthquake data for this update was obtained from the USGS website³. The database search revealed 7 earthquakes within the 150 kilometer radius of AKZO Gallery No. 2 between 1998 and 2011. The output from the NEIC search is provided below in Table 1 and the data is plotted on a Google Earth Image⁴ in Figure 1. All of the earthquakes were magnitude 3.2 and lower; the closest located approximately 25 miles from the NYSEG Site.

Earthquake Probabilities

The probability of an earthquake with a magnitude of greater than 5.0 near the NYSEG CAES Site was estimated using software developed by the USGS. The software was based upon the 2008 USGS National Seismic Hazard Mapping Project Update⁵, which was designed to predict the probability of the occurrence of an earthquake of magnitude 5.0 or greater within a specified distance from a location. PB ESS ran the USGS earthquake model for a 150 kilometer radius of Latitude 42.417°N / Longitude 76.892°W.

The annual probability of an earthquake occurrence and the cumulative probability of an earthquake occurrence, centered within a 150 kilometer radius of the NYSEG CAES Site, is given in Table 2. Figure 2 shows the probability of an earthquake of magnitude 5.0 or greater with an epicenter within 50 kilometers for locations within South Central New York and Pennsylvania.

The USGS earthquake probability prediction model implies that the probability of occurrence of an earthquake, with a magnitude greater than 5.0, within 150 kilometers of the NYSEG CAES Site is approximately 0.04 within a 30 year period.

Conclusion

In the 1994 report¹, PB-KBB states that “The entire Salina basin that covers parts of New York, Pennsylvania, Ohio, Michigan and West Virginia is characterized by a general lack of any significant seismic activity”. The USGS earthquake data collected for the time period 1998 to 2011 is consistent with this statement. PB ESS considers earthquake risk at the NYSEG Watkins Glen CAES site to be low.

References:

1. PB-KBB Inc. *Earthquake Data Base Search Update*. Prepared for Seneca Lake Storage, Inc. Undated.
2. Fenix & Scisson Inc. *Geological Report AKZO Cavern Gallery No 1, Schuyler County, New York*. Prepared for New York State Electric and Gas, Binghamton, NY 1994.
3. United States Geological Survey. National Earthquake Information Center.
http://earthquake.usgs.gov/earthquakes/eqarchives/epic/epic_circ.php
4. United States Geological Survey. Circular Search 150 km Radius from N42.491° - W 76.892°. Google Earth. November 8, 2011.
5. Petersen, Mark D. et al. *Documentation for the 2008 Update of the United States National Seismic Hazard Maps*. United States Geological Survey. Open File Report 2008-1128. May 2008.

Please do not hesitate to call or email if you have questions or suggestions.

Regards,

James M McHenry

Table 1 - USGS Earthquake Search Results 1998-2011

NEIC: Earthquake Search Results

UNITED STATES GEOLOGICAL SURVEY EARTHQUAKE DATA BASE

FILE CREATED: Tue Nov 8 15:19:56 2011
 Circle Search Earthquakes= 7
 Circle Center Point Latitude: 42.417N Longitude: 76.892W
 Radius: 150.000 km
 Catalog Used: PDE
 Date Range: 1998/01/01 to 2011/11/08
 Data Selection: Historical & Preliminary Data

CATALOG	D A T E	ORIGIN	***COORDINATES***	DEPTH STD	*****M A G N I T U D E S*****	F-E STA	***INFORMATION***	RADIAL
SOURCE	YEAR MO DA	TIME	LAT LONG	km DEV	Ofc mb Ms CONTRIBUTED VALUES	REG	IEMMDIP PHENOMENA NFAOEDF DTSVNWG TFP PED	DIST km
PDE	1999 01 25	201230	L 42.730 -77.850	3	2.7 2.7LgOTT 2.5MDPAL	472 009	.F...3P	85
PDE	2001 02 03	201515	L 42.345 -77.394	0G	3.2 3.2LgPAL 3.2LgOTT	472 011	.F...3P	42
PDE	2005 10 31	235929.95L	43.281 -77.316	2	2.6 2.7LgOTT 2.6MLPAL	472 031	3F...4P	102
PDE	2007 04 11	023217.48L	43.325 -76.966	7	2.6 2.6MLPAL	472 010	.F...3P	101
PDE	2007 12 13	032924	L 42.787 -78.205	7	2.6 2.6MDPAL	472 030	3P	115
PDE	2009 06 05	150752	L 42.828 -78.248	5G	2.9 2.9MDPAL	472 020	4F...3P	120
PDE	2009 09 23	034559.90L	42.825 -78.239	5G	2.4 2.4MDPAL	472 020	.F...3P	119

Table 2 – Earthquake Probabilities - NYSEG CAES Site

Earthquake Magnitude	Cumulative Rate of Annual Occurrence	Cumulative Probability of Occurrence within 30 Years
7.65	0.000001	0.000017
7.55	0.000001	0.000028
7.45	0.000004	0.000123
7.35	0.000010	0.000297
7.25	0.000013	0.000390
7.15	0.000019	0.000572
7.05	0.000031	0.000941
6.95	0.000037	0.001113
6.85	0.000048	0.001432
6.75	0.000069	0.002054
6.65	0.000077	0.002314
6.55	0.000094	0.002805
6.45	0.000124	0.003720
6.35	0.000137	0.004104
6.25	0.000178	0.005320
6.15	0.000208	0.006227
6.05	0.000266	0.007938
5.95	0.000289	0.008624
5.85	0.000362	0.010794
5.75	0.000417	0.012433
5.65	0.000521	0.015522
5.55	0.000566	0.016833
5.45	0.000707	0.020978
5.35	0.000882	0.026112
5.25	0.001100	0.032464
5.15	0.001100	0.032464
5.05	0.001372	0.040311

Figure 2 – Probability of Earthquake Within 30 Years - Centered Within 50 KM

INITIAL CAVERN DESIGN WATKINS GLEN CAES

Revision 2

Watkins Glen, New York

Prepared for

NYSEG

Binghamton, NY

Prepared by

Thomas Eyermann

PB ENERGY STORAGE SERVICES, INC.

Houston, TX

**Project No. 50756B
October 2011**

TABLE OF CONTENTS

SECTION	PAGE
1 BACKGROUND	2
2 TECHNICAL APPROACH	3
3 CAVERN DESIGN	5
4 DISCUSSION.....	7

LIST OF FIGURES

FIGURE	PAGE
Figure 1 Conceptual Stratigraphy of the F Unit at the CAES Facility	5
Figure 2 Cavern Shape at Each Solution Mining Stage	8
Figure 3 SANSMIC Simulated Shape of a CAES Single Well Cavern at Watkins Glen	9

LIST OF TABLES

TABLE	PAGE
Table 1 Comparison of Caverns Developed at Three Depth Ranges	2
Table 2 Setting Depths for Development of CAES Cavern	6
Table 3 Duration and Volumes for Development of CAES Cavern	6

1 BACKGROUND

The NYSEG Compressed Air Energy Storage (CAES) cavern at Watkins Glen will be developed on property in Inergy's US Salt brinefield. Brine from development will be disposed by sending it to the US Salt facility for use in the salt refinery. This will restrict solution mining rates to an average rate of about 350 gpm.

The schedule in the Technical Specification allows about 730 days for mining. This includes all downtime associated with mining such as interface logs, sonar surveys and workovers, as well as any outside-induced events such as power outages. This conceptual report limits cavern development to 730 days and *does not include* any allowance for downtimes or contingency.

The cavern will be mined in the F unit of the Salina formation. Figure 1 is a conceptual diagram of the F unit at the proposed location. The F unit extends from about 2,352 feet to about 2,827 feet in depth, about 475 feet thick of which about 334 feet is salt. For the conceptual design 50 feet of salt will be left to form the roof of the cavern.

Initial design of the cavern was done looking at three depths ranges:

- 2,402 feet to 2,827 feet
- 2,402 feet to 2,632 feet
- 2,402 feet to 2,532 feet

A cavern developed in each of the three depth ranges ends up being roughly similar in shape to the other depth ranges. However, the open space that is developed from each of the plans is different and the maximum diameter is significantly different. Key items of the three depth ranges are listed in Table 1.

Table 1 Comparison of Caverns Developed at Three Depth Ranges

Modeled Depth Range	Open Volume	Floor Depth	Maximum Diameter	Vertical Thickness of Salt
Feet	Barrels	Feet	Feet	Percent
2,402 – 2,832 (tall)	933,000	2,567	258	66
2,402 – 2,632 (medium)	970,000	2,527	266	71
2,402 – 2,532 (short)	974,000	2,508	284	79

The open cavern volume changes between the plans (depth intervals) are due to the increasing thickness of exposed non-salt beds relative to the thickness of salt mined in each plan. As the non-salt units are exposed, they fall to the bottom of the cavern and bulk up (increase in volume due to void (brine) space between the slabs and particles in the floor), thus filling up more of the cavern interval than the non-salt material originally occupied. Although the tall cavern plan mines 286 feet of salt compared to only 103 feet of salt in the short plan, the tall plan has 144 feet of non-salt beds included in the mining interval compared to only 27 feet in the short plan and 63 feet in the medium plan

Based on the almost equal open cavern volume between the medium and short interval and the large reduction in diameter (266 feet versus 284 feet), the medium depth range of 2,402 feet to 2,632 feet was chosen for development of a conceptual cavern design. The conceptual design is described in this report.

2 TECHNICAL APPROACH

The study used the SANSMIC cavern simulation model to project the development of caverns from a single well. SANSMIC, a widely used cavern modeling program developed by Sandia National Laboratories, is a two-dimensional numerical simulation code, which approximates the dissolution of salt by water.

The basic input for the model consists of average radii of the well, the depth of the water injection and brine production strings, the depth of the product level, water injection rates, and duration of mining. If a cavern exhibits a region of abnormal or nonsymmetric growth, SANSMIC cannot fully evaluate continued growth in such a region. However, the simulated growth can be interpreted to closely approximate future growth in regions of concern.

As with all numerical models, SANSMIC does not fully represent the actual salt caverns. This is due to (1) the axisymmetric assumption in the model (that the cavern will develop evenly about the central wellbore) and (2) limitations in the equations for flow within the cavern. In addition, SANSMIC was developed primarily for modeling in domal salts, where the salt is relatively clean without significant nonsalt interbeds.

The axisymmetric assumption is not necessarily a significant limitation to modeling the development of salt caverns in the Syracuse salt. The caverns developed in this salt tend to be reasonably uniform in horizontal cross sections when developed by means of a single well. The

limitations in the hydraulic equations result in overestimation of development near the bottom of the injection tubing in both reverse and direct mining and a corresponding underestimation of mining in the upper portions of the cavern.

The major difficulty in applying SANSMIC to bedded salt lies in its inability to comprehensively model the layers that are either nonsalt or have a low percentage of salt. SANSMIC has no ability to model the collapse of the nonsalt beds or to predict the behavior of units that are mostly nonsalt material. These limitations can be partially compensated for by altering the insoluble content and the dissolution factors of the various beds.

For the purposes of the simulation, the section between the depths of 2,352 feet to 2,632 feet was divided into fifteen 20-foot intervals. The percentage of salt within each interval was estimated from the Well 58 gamma log with the assumption that “clean” salt contains 5% nonsalt material and dirtier salts (higher gamma counts) contain up to 20% non-salt material. The non-salt units were estimated to have varying amounts of salt from 5% to 20% depending upon the gamma counts in the Well 58 log.

Salt was given a dissolution factor of “1”. To approximate conditions that will be experienced during mining of the insoluble beds, the dissolution factor of the various nonsalt intervals was also set at “1.” These values allow the nonsalt rocks to fall to the bottom of the cavern as mining progresses, which approximates the conditions seen in the Watkins Glen caverns where there are few or no overhanging ledges seen in the sonar surveys. The main consequence of the dissolution factor of the nonsalt units is in determining the amount of cavern space that will be filled by the fallen insoluble material. The non-salt material was given a bulking factor of 1.4, that is, the non-salt material on the floor of the cavity occupies 140% of the space it occupied in the undisturbed sequence.

Mining was simulated at a brine production rate of 350 gallons per minute. The tubing strings used for mining were 8-5/8 inches inside 13-3/8 inches. The actual tubing sizes are not material to the mining except in the very early days of mining.

The top of the cavern was placed at about 2,402 feet, about fifty feet below the top of salt estimated to be at a depth of 2,352 feet. The well was assumed to be drilled to 2,632 feet. Mining was simulated for 710 days, allowing 20 days of downtime for a workover and other events.

Figure 1 Conceptual Stratigraphy of the F Unit at the CAES Facility

3 CAVERN DESIGN

In the selected depth range, cavern design for a single well cavern was developed. To meet the air storage capacity desired by the CAES project, three caverns will be required, but all three caverns will be developed from the same basic plan. Detailed design of the mining program for each cavern may vary slightly depending upon the specific geology intersected by each well when drilled.

The well design requires one planned workover to reposition the string depths after development of an initial sump at the bottom of the selected interval. This initial step will be mined in direct mode – water injected in the inner deeper string and brine produced from the shallower outer string. Mining should be conducted at as high a rate as is feasible in order to mine the lower salt before it is covered with non-salt material from the overlying dolomitic shale.

For this initial sump stage, the blanket should be set low in order to mine the lowermost salt. Blanket refers to an insoluble liquid or gas which is used to stop upward solution mining and

help control cavern shape. The blanket and tubing depths are shown in Table 2. The cavern volume and salinity of the produced brine at the end of each step are shown in Table 3.

Table 2 Setting Depths for Development of CAES Cavern

Mining Step	Blanket Setting Depth Feet	Production Setting Depth Feet	Injection Setting Depth Feet	Insoluble Depth Feet
Sump/Chimney	2,520	2,530	2,630	2,538
Reverse	2,420	2,530	2,472	2,535
Reverse	2,410	2,515	2,472	2,531
Reverse	2,402	2,515	2,472	2,528
Reverse	2,402	2,515	2,472	2,527

Table 3 Duration and Volumes for Development of CAES Cavern

Mining Step	Step Time at 350 gpm Days	Total Mining Time Days	Open Mined Volume Barrels	Gross Cavern Volume Barrels	Brine Saturation Percent
Sump/Chimney	130	130	67,000	105,000	52.1
Reverse	150	280	272,000	324,000	84.8
Reverse	150	430	506,000	575,000	88.6
Reverse	150	580	752,000	840,000	90.8
Reverse	130	710	970,000	1,073,000	90.8

At the end of the sump/chimney stage, a workover is required to raise both strings for continued mining. After the workover, mining should be changed to reverse – water injected in the outer, shallower string and brine produced from the inner, deeper string. This reverse mining continues until completion of the cavern. During reverse mining the blanket depth will need to be reset at shallower depths twice as shown in Table 2.

The depth of the insolubles on the floor of the cavern will need to be monitored during reverse mining to ensure that the inner string remains above them. If the inner string becomes buried in insolubles, it will likely plug and require a workover to clean out.

The cavern volume that can be developed in the allotted time of 730 days (including 20 days an intermediate workover) is about 970,000 barrels. This will allow dewatering of about 940,000 barrels of space for air storage operations.

The simulated cavern shape at completion at each of the solution mining stages is shown in Figure 2 and the shape at completion of mining is shown in Figure 3.

4 DISCUSSION

The conceptual plan is not optimized. Further effort in optimization at this time may result in minor changes to the single well cavern volume and dimensions, but is probably best deferred until the well has been drilled. *Detailed design for the cavern(s) will need to be developed once the well(s) has been drilled and completed.* The actual geology (salt thickness particularly) may then result in significant changes to the cavern design including the cavern volume. The roof development plan particularly will need to be refined in order to shape the roof.

The mined volumes shown in this conceptual report do not include provision for any downtime in mining, except for a 20 day period for the workover at the end of the sump/chimney stage. **There is no allowance for other interruptions (electrical outages, pump failures, plant outages, etc.) that are likely to occur.**

Due to the relatively large volume of non-salt material in the Syracuse Salt, a plan that does not require a workover to reposition the strings is not feasible. The plan discussed above creates a sump for accumulation of insolubles that will be liberated in the reverse stages of mining when the main cavern is developed for compressed air storage. Without this initial sump stage, the cavern floor is shallower and the open cavern volume is about 15% lower.

Cost issues and well sizes are not considered in the cavern solution mining conceptual plan. Further treatment of the brine to bring it to saturation for use in the US Salt plant is likewise not considered.

Figure 2 Cavern Shape at Each Solution Mining Stage

Figure 3 SANSMIC Simulated Shape of a CAES Single Well Cavern at Watkins Glen

External Memorandum

To: Mr. Jim M. McHenry
Project Manager
PB Energy Storage Services, Inc.
16285 Park Ten Place, Suite 400
Houston, TX 77084

cc: Dr. Joe L. Ratigan, PB Energy Storage Services, Inc.
Dr. John D. Osnes, RESPEC
Project Central File 2040 — Category A

From: Mr. Joel D. Nieland
Staff Consultant
RESPEC
P.O. Box 725
Rapid City, SD 57709

Date: October 4, 2011

Subject: Thermodynamic Evaluation of Proposed New York State Electric & Gas Corporation
Compressed Air Energy Storage Cavern Design

The purpose of this memorandum is to present the results of a study to investigate the thermodynamic performance of the proposed cavern design for the compressed air energy storage (CAES) facility that New York State Electric & Gas Corporation (NYSEG) is planning to develop about 4 miles north of Watkins Glen, New York. The air storage caverns will be developed in the bedded salt deposits of the Syracuse Formation at a depth of about 2,400 feet below the ground surface. The performance issues examined here include: (1) cavern air storage capacity, (2) surface and underground pressures and temperatures, and (3) casing string (liner) sizes for the anticipated operations.

1.0 BACKGROUND

The proposed NYSEG CAES facility has a rated capacity between approximately 135 and 210 MW and will provide energy during peak periods in support of market needs. WorleyParsons Group, Inc. [2011] provided a typical daily air flow cycle that meets the power generation needs of the facility. The hourly flow rates for the typical cycle are listed in Table 1 and are shown graphically in Figure 1. The cycle has air injected into the cavern during off-peak hours and air is withdrawn from the cavern to generate power during peak periods. An air injection temperature at the wellhead of 95°F is specified. The daily cycle requires a total working gas of 17.7 million pounds of air. It was assumed in this analyses that there will not be any flow during weekend hours.

Table 1. Flow Rates for Typical Daily Cycle

Time of Day	Hours of Operation	Flow Rate ^(a) (lb/s) ^(b)
12 am – 5 am	5	639
5 am – 6 am	1	441
6 am – 8 am	2	–351
8 am – 9 am	1	0
9 am – 1 pm	4	–617
1 pm – 2 pm	1	0
2 pm – 4 pm	2	–617
4 pm – 5 pm	1	–510
5 pm – 10 pm	5	0
10 pm – 12 am	2	639

(a) Positive values indicate injection into cavern and negative values indicate withdrawal for power generation.

(b) lb/s = pounds per second.

RSI-2040-11-001

Figure 1. Typical Daily Air Flow Cycle.

Preliminary geomechanical analyses determined that an operating wellhead pressure range of 1,150 psi to 1,500 psi (about 1,260 psi to 1,630 psi within the cavern) will result in a structurally stable cavern. Based on preliminary thermodynamic analyses, a cavern volume of roughly 3 million barrels (MMbbls) is required to provide the required working gas for this pressure range. The rate of cavern volume development is governed by a brine disposal rate of about 350 gallons per minute (gpm) and it is estimated that approximately 6 years will be required to develop a cavern volume of 3 MMbbls. Because of solution-mining limitations and also to provide partial interim operation, three caverns each having a volume of approximately 1 MMbbls will be developed.

2.0 TECHNICAL APPROACH

The investigative analyses presented here were conducted with the Salt Cavern Thermal Simulator (SCTS) [Nieland, 2004], a program developed by PB Energy Storage Services, Inc. and RESPEC for simulating the thermodynamics and heat transfer related to the storage of natural gas in underground salt caverns. It accounts for the thermal effects associated with gas compression and expansion; the mass transfer during injection and withdrawal; and the heat transfer between the gas and its surroundings, both in the wellbore and in the cavern. Because the release version of SCTS only simulates natural gas storage, a modified version which allows the simulation of compressed air and hydrogen storage was used for this study.

The proposed cavern design analyzed in this study [Eyermann, 2011a] is based on solution-mining calculations performed following the preliminary analyses described above. The radius of the cavern design as a function of depth is shown in Figure 2. This cavern design has a mined volume of about 970,000 barrels (bbls) of which about 940,000 bbls can be dewatered and used for air storage. The roof of the cavern is at a depth of 2,402 feet (50 feet below the top of salt) and has a dewatered depth of about 2,525 feet. The casing seat is assumed to be at a depth of 2,360 feet, about 8 feet below the top of the salt¹.

In SCTS, the heat transfer between the air in the cavern and the surrounding rock is estimated using a one-dimensional spherical heat transfer model containing a single material (salt properties were used in this case). SCTS uses a parameter (the volume-to-area ratio) to modify the spherical model to approximate the actual shape of the cavern. The ratio of the volume to surface area of the proposed cavern design is 30.0 ft³/ft². The heat transfer between the air in the wellbore and surrounding rock is estimated using a stacked series of one-dimensional radial heat transfer models with properties assigned based on the surrounding rock. The stratigraphy used in the simulations of the wellbore heat transfer is based on local geology described by Eyermann [2011b]. Densities for the rock units are based on a density log conducted in Well No. 59 [Osnes and Eyermann, 1996]. Typical thermal properties [Croff et al., 1985; Callahan, 1981] for shale, sandstone, carbonates (limestone and dolomite), and salt were assigned to the units. The stratigraphic units and the properties assumed for them are listed in Table 2. The undisturbed in situ temperature profile assumed in this study is based on temperature logs conducted in Well No. 59 and is described in Table 3.

¹ This selection for the casing seat depth is based on the following: (1) the casing seat needs to be set in the salt, (2) placing the casing seat too close to the cavern roof will make mechanical integrity testing difficult or impossible, and (3) increasing the distance between the cavern roof and casing seat results in a lower amount of casing strain.

RSI-2040-11-002

Figure 2. Simulated Shape of the Proposed Compressed Air Energy Storage Cavern Design [Eyermann, 2011a].

Table 2. Thermal Properties and Rock Densities

Unit – Lithology	Depth Range (ft)	Density (lb/ft ³)	Thermal Conductivity (Btu/hr-ft-°F)	Specific Heat (Btu/lb-°F)
Genesee – Shale	0–830	164	0.804	0.190
Tully – Limestone	830–847	167	1.775	0.123
Hamilton – Shale	847–1,768	165	0.804	0.190
Marcellus – Shale	1,768–1,866	165	0.804	0.190
Onondaga – Limestone	1,866–1,911	164	1.775	0.123
Tristates Group – Sandstone	1,911–1,948	167	1.966	0.170
Oriskany – Sandstone	1,948–1,956	167	1.966	0.170
Helderberg Group – Limestone	1,956–2,106	168	1.775	0.123
Cobleskill/Akron – Dolostone	2,106–2,166	169	1.775	0.123
Bertie – Dolostone	2,166–2,255	175	1.775	0.123
Camillus – Shale	2,255–2,352	170	0.804	0.190
Syracuse – Salt	2,352–2,360	130	3.000	0.200

Table 3. In Situ Temperature Profile

Surface Temperature = 45.6°F	
Depth Range (ft)	Temperature Gradient (°F/ft)
0 – 1,110	0.0085
1,110 – 1,866	0.0225
Below 1,866	0.0088

In the thermodynamic simulations, properties of the brine and air are calculated in SCTS based on the fluid composition (or salinity) and are functions of the temperature and pressure. These properties include density, compressibility, thermal conductivity, specific heat, and viscosity. The assumed air composition is shown in Table 4.

Table 4. Air Composition

Component	Mole Percent
Nitrogen	78.0
Oxygen	21.0
Argon	1.0

The air storage simulations were preceded by leaching and dewatering of the cavern. The leaching was simulated over 730 days with a flow rate of 350 gpm. A freshwater injection temperature of 52°F at the wellhead was assumed during leaching. After leaching the cavern, the cavern was dewatered and filled with air at a wellhead pressure of 1,350 psi. The cavern was then depressurized to about 1,160 psi at the wellhead, which is representative of the wellhead pressure at the end of a weekend in the simulations. The conditions at this point were used as the starting point for all of the following compressed air storage simulations.

3.0 RESULTS

The results of the analyses are given in terms of well casing liner size selection and cavern performance, including storage capacity and estimated surface and down-hole pressures and temperatures.

3.1 Casing Liner Size Selection

The wellbores of the CAES caverns will be completed with stainless-steel liners to help prevent corrosion. Liner sizes were determined to ensure the operational air velocities will not result in excessive erosion of the liner surface and also to keep pressure losses in the wellbore to a reasonable level. Air velocities will depend on the air flow rate, the air density, and the cross-sectional area of the wellbore. Pressure losses in the wellbore will depend on the air flow rate,

the cross-sectional area of the wellbore, and the smoothness of the wellbore. New stainless-steel casing has an absolute roughness of about 0.0018 inch and this value was used in all of the calculations.

After all three caverns are developed and are operating in parallel, the maximum flow rate for each of the caverns will be one-third of the maximum total flow rate. However, after the first cavern is developed, it is desired to begin CAES operations while the other caverns are being developed, and likewise, to use the second cavern as the third cavern is being developed. Also, after all three caverns are developed, it is desirable to be able to operate with any two of the caverns so that a cavern may be taken off-line for any required maintenance. It is anticipated that while operating with less than all three caverns, that operations will be conducted at full power (i.e., at the flow rates specified in Table 1); albeit, for shorter periods than specified by the full operational cycle. Maximum flow rates under this assumption for the various cavern configurations are listed in Table 5.

Table 5. Maximum Cavern Air Flow Rates

Operating Configuration	Maximum Cavern Injection Flow Rate (lb/s)	Maximum Cavern Withdrawal Flow Rate (lb/s)
One Cavern	639	617
Two Caverns	319.5	308.5
Three Caverns	213	205.7

To evaluate casing size, the maximum injection flow rate for each of the operating configurations was evaluated for liners with outer diameters (OD) ranging from 6.625 inches to 24 inches. A wall thickness of ¼ inch was assumed for all liners. The liners were evaluated at the minimum wellhead pressure of 1,150 psi when the air density is at its lowest value and thus velocities are at their highest.

The maximum allowable air velocities to prevent casing erosion were calculated using the following equation provided by the American Petroleum Institute (API) [1991]:

$$V_e = \frac{C}{\sqrt{\rho}} \quad (3-1)$$

where:

V_e = velocity above which erosion may occur (ft/s)

C = empirical constant

ρ = density of the fluid (lb/ft³).

For continuous service flow with solids-free fluids where a corrosion-resistant alloy is used (in this case, stainless steel) the API recommends *C* values in the range of 150 to 200. As a conservative measure, the lower-end value of 150 was used in this study.

The velocities were evaluated at the casing seat (2,360-foot depth) and at the wellhead, as shown in Figures 3 and 4, respectively. The air velocities at the wellhead are slightly higher because the air is at a lower density. The maximum allowable velocities that mitigate erosion are about 57 to 60 feet per second (ft/s). Thus to prevent erosion, the recommended liner sizes are a 20-inch OD liner for a flow rate of 639 lb/s, a 14-inch OD liner for a flow rate of 320 lb/s, and a 10³/₄-inch OD liner for flows of 213 lb/s.

The pressure losses in the wellbore liner are a result of the friction between the flowing air and the wellbore liner surface. Friction losses will result in increased power consumption while air is injected into the cavern and a decrease in power recovery as the air is withdrawn from the cavern. Figure 5 shows the estimated wellbore liner pressure losses for the same flow rates as a function of liner diameter. The results indicate that the pressure losses for the maximum flow rate of 639 lb/s will increase significantly for wellbore liner diameters of less than about 20 inches. Thus the 20-inch liner is recommended for the first cavern developed and is expected to have a pressure loss of about 35 psi at the maximum flow rate of 639 lb/s. The pressure loss in the 20-inch liner will decrease to about 15 psi when two caverns are operating and to about 10 psi when all three caverns are operating.

To have comparable pressure losses in the case when any two caverns are being operated (a maximum flow rate of 320 lb/s), it is recommended to install 16-inch liners in the second and third caverns developed. The caverns with the 16-inch liners are expected to have pressure losses of about 30 psi when two caverns are operating and about 17 psi when all three caverns are operating.

3.2 Cavern Performance

The air storage capacity of a solution-mined cavern is governed by the gas equation-of-state, which, for a real gas, is defined as:

$$m = \frac{VPM}{zRT} \quad (3-2)$$

where:

m = mass of stored gas

V = cavern volume

P = absolute gas pressure in the cavern

M = molecular weight of the gas

z = compressibility factor of the gas

R = universal gas constant

T = absolute temperature of gas.

RSI-2040-11-003

Figure 3. Air Velocities and Maximum Allowable Velocities at the Casing Seat.

RSI-2040-11-004

Figure 4. Air Velocities and Maximum Allowable Velocities at the Wellhead.

RSI-2040-11-005

Figure 5. Calculated Wellbore Liner Pressure Losses for Various Air Flow Rates.

The storage pressure range is usually governed by cavern stability, regulation, or compressor capacity. In the case of the planned NYSEG CAES caverns, the maximum wellhead pressure of 1,500 psi is governed by the compressor capacity. The minimum pressure of 1,150 psi at the wellhead is based on preliminary cavern stability studies. The usable cavern volume of the solution-mining design is 940,000 bbls (5.3 million ft³). Assuming the air composition will be relatively constant, the main variable that will affect air storage capacity is air temperature in the cavern, which will be a function of the air injection temperature (95°F), the in situ rock temperature (estimated to be about 77°F), and the storage pressure cycle.

3.2.1 Typical Storage Cycle

To determine the storage capacity of the cavern design, a 5-year simulation was conducted in a single cavern (assuming three caverns are operating in parallel) where the flows of the typical daily cycle (Figure 1) were scaled to maintain the wellhead pressure between 1,150 psi and 1,500 psi. Because the salt around the cavern is cooled during leaching, the cavern gas temperature gradually warms with time during the 5-year simulation, as shown in Figure 6. Because of this gradual warming of the cavern, the amount of air that the cavern can hold gradually decreases with time, as shown in Figure 7. The scale factor of the flow rates of the typical daily cycle decreased from about 0.38 immediately after dewatering to 0.34 at the end of 5 years but is not expected to decrease significantly after that because thermal equilibrium is nearly reached. Thus developing three caverns similar to the cavern design should provide full capacity to operate with the typical daily cycle.

RSI-2040-11-006

Figure 6. Cavern Air Temperature During 5-Year Simulation of Scaled Typical Daily Cycle in a Single Cavern (Assuming Three Caverns Operating in Parallel).

RSI-2040-11-007

Figure 7. Cavern Air Inventory During 5-Year Simulation of Scaled Typical Daily Cycle in a Single Cavern (Assuming Three Caverns Operating in Parallel).

Figure 8 shows the wellhead and cavern pressures during a 1-week period at the end of the 5-year simulation. As shown in the figure, the cavern pressure is about 120 psi higher than the wellhead pressure. Figure 9 shows the estimated average cavern air temperature and the cavern wall temperature during this 1-week period. The average cavern air temperature is expected to vary between a minimum of 85°F and a maximum of about 126°F. Because the cavern temperature gradually warms over the weekend when there is no air flow, the highest temperature is expected after the first fill of the week. The cavern wall temperature is expected to range from about 91°F to 119°F. Figure 10 shows the estimated wellhead temperature. The wellhead temperature (shown in Figure 10) is expected to range from about 71°F at the end of the weekend to a maximum of about 101°F at the start of daily withdrawals.

Figure 11 shows the air flow rate and cavern air inventory during a 1-week period at the end of the 5-year simulation. The injection air flow rate at the beginning of the week required to pressurize to a wellhead pressure of 1,500 psi (about 211 lb/s) is slightly less than that during the rest of the week (about 217 lb/s) because of the gradual pressurization that occurs over the weekend. The withdrawal flow rates required to depressurize the wellhead pressure to 1,150 psi (about 207 lb/s) is nearly constant during the week and is about one-third of the total required withdrawal rate.

3.2.2 Operation With Partial Storage Capacity

To evaluate operations at partial storage capacity (i.e., when two caverns are in operation or when just a single cavern is in operation), the daily cycle was simplified to a single daily injection at the maximum injection rate of 639 lb/s and a single daily withdrawal at the maximum withdrawal rate of 617 lb/s. When operating with two caverns, half of these maximum flow rates were applied to each of the two caverns, and when operating with a single cavern, the full flow rates were applied to the single cavern. The durations of the flow periods were adjusted to keep the wellhead pressures below the maximum specified 1,500 psi and the cavern pressure above the minimum cavern pressure² of 1,260 psi predicted for the full power case.

The two-cavern operation simulation was conducted using a 16-inch OD liner. Figure 12 shows the air flow rate and cavern inventory for each cavern during a 1-week period of two-cavern operation. Air was injected into each cavern at a rate of 317.5 lb/s for about 4.78 hours to fill the caverns and was withdrawn at a rate of 308.5 lb/s for about 4.92 hours to bring the caverns down to minimum pressure. This results in a daily withdrawal of about 5.45 million pounds from each cavern or a total of 10.9 million pounds of air from both caverns—about 62 percent of full capacity. The pressure and temperature swings in the cavern, as shown in Figures 13 and 14, are comparable to those for the three-cavern operation. With the higher flow rates as compared to the three-cavern operation, the pressure losses in the wellbore are greater (note the peaks on the wellhead pressures in Figure 13 at the beginning and end of flow periods)

² Minimum cavern pressure is used here because it will dictate cavern stability. The higher flow rates required per cavern for the partial storage capacity cases will result in higher pressure losses in the wellbore (i.e., larger pressure differentials between the wellhead and the cavern). The maximum pressure is still limited at the wellhead as dictated by the compressor.

and filling of the cavern must be stopped prematurely to avoid exceeding 1,500 psi at the wellhead. By reducing the injection rate from 639 lb/s to 213 lb/s (while still withdrawing at RSI-2040-11-008

Figure 8. Wellhead and Cavern Pressure During a 1-Week Period After 5 Years of Operation of Scaled Typical Daily Cycle in a Single Cavern (Assuming Three Caverns Operating in Parallel).

RSI-2040-11-009

Figure 9. Average Cavern Air Temperature and Cavern Wall Temperature During 1-Week Period After 5 Years of Operations of Scaled Typical Daily Cycle in a Single Cavern (Assuming Three Caverns Operating in Parallel).

RSI-2040-11-010

Figure 10. Air Temperature at the Wellhead During a 1-Week Period After 5 Years of Operations of Scaled Typical Daily Cycle in a Single Cavern (Assuming Three Caverns Operating in Parallel).

RSI-2040-11-011

Figure 11. Air Flow Rate and Cavern Inventory of a Single Cavern (Assuming Three Caverns Operating in Parallel) During a 1-Week Period After 5 Years of Operations of Scaled Typical Daily Cycle.

RSI-2040-11-012

Figure 12. Air Flow Rate and Cavern Inventory for a Single Cavern During a 1-Week Period Assuming Two Caverns Operating in Parallel.

RSI-2040-11-013

Figure 13. Wellhead and Cavern Pressure for a Single Cavern During a 1-Week Period Assuming Two Caverns Operating in Parallel.

617 lb/s), the pressure losses in the wellbore are reduced during filling; consequently, more air can be injected into the cavern before reaching the maximum wellhead pressure of 1,500 psi and the two-cavern capacity can be increased by about 5 percent.

RSI-2040-11-014

Figure 14. Average Cavern Air Temperature and Cavern Wall Temperature During a 1-Week Period Assuming Two Caverns Operating in Parallel.

The single-cavern operation simulation was conducted using a 20-inch liner. Figure 15 shows the air flow rate and cavern inventory in the single cavern during a 1-week period of single-cavern operation. Air was injected into the cavern at a rate of 639 lb/s for about 2.26 hours to fill the cavern and was withdrawn at a rate of 617 lb/s for about 2.33 hours to bring the cavern down to minimum pressure. This results in a daily withdrawal of about 5.2 million pounds of air—about 29 percent of full capacity. The pressure and temperature swings in the cavern, as shown in Figures 16 and 17, are comparable to those for the three-cavern operation. If single-cavern operation were performed with a 16-inch liner, the additional wellbore pressure losses would result in a decrease in air capacity of about 17 percent. For the 20-inch liner, the air storage capacity can be increased by about 10 percent by filling the cavern at a rate of 213 lb/s rather than 639 lb/s.

4.0 SUMMARY AND CONCLUSIONS

A study was conducted to evaluate the thermodynamic performance of the NYSEG CAES cavern design and to determine the appropriate liner sizes for the caverns. The main findings of the study include:

- Based on estimated wellbore pressure losses, it is recommended that a 20-inch liner be installed in the first cavern developed and that 16-inch liners be installed in the second and third caverns developed. This will allow interim operation (at reduced power generation) with the first and second caverns developed and allow for taking any one of the caverns off-line for maintenance after all three caverns are developed.
- The minimum wellbore liner sizes required to prevent erosion of the liner walls were less than or equal to those required to keep pressure losses at acceptable levels. Thus, the liner sizes were selected based on pressure losses, and the maximum air velocities expected (about 50 ft/s) are not expected to result in erosion of wellbore liners.
- The proposed cavern design will provide about 34 percent of the total storage capacity required for the anticipated power generation with a single cavern. Thus three caverns of this design will need to be developed to operate the typical daily cycle.
- Two-cavern operation will provide about 62 percent of full-power generation when operating at the maximum injection and withdrawal rates. This capacity can be increased by about 5 percent by reducing the injection rate from 639 lb/s to 213 lb/s.
- Single-cavern operation will provide about 29 percent of full-power generation when operating at the maximum injection and withdrawal rates. This capacity can be increased by about 10 percent by reducing the injection rate from 639 lb/s to 213 lb/s.
- The predicted conditions at minimum and maximum pressures for the three-cavern operation after 5 years are listed in Table 6.

RSI-2040-11-015

— REVISION 1 —

Figure 15. Air Flow Rate and Cavern Inventory During a 1-Week Period of Single-Cavern Operation.

RSI-2040-11-016

Figure 16. Wellhead and Cavern Pressure During a 1-Week Period of Single-Cavern Operation.

RSI-2040-11-017

Figure 17. Average Cavern Air Temperature and Cavern Wall Temperature During a 1-Week Period of Single-Cavern Operation.

Table 6. Properties at Minimum and Maximum Pressure Conditions

Property	At Minimum Pressure	At Maximum Pressure
Wellhead Pressure	1,150 psi	1,500 psi
Cavern Pressure	1,267 psi	1,621 psi
Wellhead Temperature	71°F	101°F
Cavern Temperature	85°F	126°F
Cavern Wall Temperature	91°F	119°F

5.0 REFERENCES

American Petroleum Institute, 1991. *Recommended Practice for Design and Installation of offshore Production Platform Piping Systems*, API Recommended Practice 14E (RP 14E) Fifth Ed., American Petroleum Institute, Washington, DC, October.

Callahan, G. D., 1981. *Inelastic Thermomechanical Analysis of a Generic Bedded Salt Repository*, ONWI-125, prepared by RE/SPEC Inc., Rapid City, SD, for the Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, OH.

Croff, A. G., T. F. Lomenick, R. S. Lowrie, and S. H. Stow, 1985. *Evaluation of Five Sedimentary Rocks Other Than Salt for High-Level Waste Repository Siting Purposes*, prepared for Oak Ridge National Laboratory, Oak Ridge, TN.

Eyermann T. J., 2011a. *Conceptual Cavern for NYSEG Compressed Air Energy Storage at Watkins Glen, NY*, prepared by PB Energy Storage Services, Inc., Houston, TX (draft).

Eyermann T. J. 2011b. *Overview of Geology of the Area Around the US Salt Watkins Glen Refinery*, prepared for NYSEG, Binghamton, NY, by PB Energy Storage Services, Inc., Houston, TX.

Nieland, J. D., 2004. *Salt Cavern Thermal Simulator Version 2.0 User's Manual*, RSI-1760, prepared by RESPEC, Rapid City, SD, for Gas Technology Institute, Chicago, IL.

Osnes, J. D. and T. J. Eyermann, 1996. *Geomechanical Analyses of Compressed Natural Gas Storage in Gallery No. 1, Watkins Glen, New York*, RSI-0670, prepared by RE/SPEC Inc., Rapid City, SD, for PB-KBB Inc., Houston, TX.

WorleyParsons Group, Inc., 2011. Electronic communication between M. C. Holdridge, WorleyParsons Group, Inc., Reading, PA, and J. L. Ratigan, PB Energy Storage Services, Inc., Houston, TX, August 11.

JDN:kr1

**GEOMECHANICAL EVALUATION OF THE
NEW YORK STATE ELECTRIC & GAS CORPORATION
COMPRESSED AIR ENERGY STORAGE CAVERN DESIGN**

Topical Report RSI-2240

prepared for

PB Energy Storage Services, Inc.
16285 Park Ten Place, Suite 400
Houston, Texas 77084

November 2011

**GEOMECHANICAL EVALUATION OF THE
NEW YORK STATE ELECTRIC & GAS CORPORATION
COMPRESSED AIR ENERGY STORAGE CAVERN DESIGN**

Topical Report RSI-2240

by

Joel D. Nieland

RESPEC

P.O. Box 725

Rapid City, South Dakota 57709

prepared for

PB Energy Storage Services, Inc.

16285 Park Ten Place, Suite 400

Houston, Texas 77084

November 2011

FOREWORD

This report addresses a proposed new cavern for Compressed Air Energy Storage (CAES) developed in the bedded salt formation at Seneca Lake, New York. The size (roof span and volume) of a solution-mined storage cavern in this geologic setting depends on the intended function of the cavern and the associated impact of the cavern pressures on the stability of the cavern. Solution-mined galleries have been developed for brine production with roof spans (along the “short” axis of the cavern) of approaching 400 feet. A natural gas storage cavern developed in the bedded salts at Seneca Lake has a maximum roof span of approximately 300 feet. The volume of these caverns depends to a large degree on the vertical extent of the solution-mining. Natural gas storage caverns necessarily require that a salt roof (that can be demonstrated to be stable) must remain in place; whereas, a solution-mined cavern for brine production need not necessarily require an intact salt roof to meet its function.

The internal cavern pressures in a brine production cavern and a natural gas storage cavern are typically significantly different—resulting in different allowable maximum cavern roof spans. The internal pressure in a brine production cavern is generally very close to about 0.52 psi/foot of depth to the cavern; whereas, the internal pressure in a natural gas storage cavern can be as little as half of that and as high as about 0.85 psi/foot of depth to the cavern.

The maximum diameter and volume of the CAES cavern and the associated minimum and maximum operating pressures evaluated in this report are not necessarily the “optimum,” as variations in cavern diameter and solution-mined (vertical) interval were not addressed in detail. Nonetheless, based on experience with other caverns at Seneca Lake operating over a range of internal cavern pressures, it is expected that an “optimum” cavern geometry is not dramatically different than the cavern geometry evaluated in this report.

Final design of the CAES caverns at Seneca Lake will depend on the in situ stress and temperature conditions and the thermomechanical properties of the salt and nonsalt rocks surrounding the proposed cavern. The in situ conditions will be best determined by open-hole logs and testing, and the salt and nonsalt rock properties will be best determined with the open-hole logging and a comprehensive laboratory testing program (see for example, Appendix B).

TABLE OF CONTENTS

1.0 INTRODUCTION	1
1.1 BACKGROUND	1
1.2 SCOPE AND OBJECTIVES	1
1.3 REPORT ORGANIZATION	1
2.0 PROPOSED COMPRESSED AIR ENERGY STORAGE FACILITY	2
3.0 TECHNICAL APPROACH	6
3.1 NUMERICAL MODELING	6
3.1.1 Cavern Thermodynamics Program	6
3.1.2 Heat Transfer Finite Element Program	6
3.1.3 Thermomechanical Finite Element Program	7
3.1.4 Constitutive Model for Salt	7
3.2 STRATIGRAPHY	9
3.3 MATERIAL PROPERTIES	10
3.3.1 Elastic and Thermal Properties	11
3.3.2 Creep Properties	14
3.3.3 Air Characteristics	15
3.3.4 Brine Characteristics	17
3.4 IN SITU CONDITIONS	17
3.4.1 Temperature Profile	17
3.4.2 In Situ Stress	19
3.5 FINITE ELEMENT MODEL	20
3.6 CRITERIA FOR EVALUATING STRUCTURAL STABILITY	23
3.6.1 Tensile Zones	23
3.6.2 Salt Dilation	23
3.6.3 Shear Failure Criterion for Nonsalt Strata	24
4.0 MODELING RESULTS	26
4.1 THERMAL MODELING	27
4.2 CAVERN STABILITY	31
4.3 POTENTIAL FOR HYDRAULIC FRACTURE DEVELOPMENT	37
4.4 CAVERN CLOSURE AND CASING STRAIN	42
5.0 SUMMARY AND CONCLUSIONS	45
6.0 REFERENCES	47
APPENDIX A. THERMODYNAMICS MEMORANDUM	A-1

TABLE OF CONTENTS

(Continued)

APPENDIX B. MECHANICAL ROCK PROPERTIES TESTS	B-1
B.1 QUASI-STATIC COMPRESSION TEST.....	B-2
B.2 CONSTANT MEAN STRESS TEST	B-2
B.3 BRAZILIAN INDIRECT TENSION TEST.....	B-5
B.4 CONFINED CREEP TEST	B-5

LIST OF TABLES

TABLE		PAGE
2-1	Flow Rates for Typical Daily Cycle.....	2
3-1	Stratigraphy Modeled in the NYSEG Compressed Air Energy Storage Simulations.....	10
3-2	Stratigraphy Within the Syracuse Formation	11
3-3	Elastic and Thermal Properties.....	13
3-4	Munson-Dawson Creep Parameters Used to Model Syracuse Formation Salt	15
3-5	Assumed Air Composition.....	17
3-6	Assumed In Situ Temperature Profile.....	19

LIST OF FIGURES

FIGURE	PAGE
2-1 Typical Daily Air Flow Cycle for the Compressed Air Energy Storage Facility	3
2-2 Weekly Wellhead Pressure for Typical Air Flow Cycle	3
2-3 Simulated Shape of Proposed Compressed Air Energy Storage Cavern Design	5
3-1 Measured and Predicted Axial Creep Strains for Creep Tests Performed on Salt From Well No. 58	16
3-2 Measured and Predicted Axial Creep Strains for Creep Tests Performed on Salt From Well No. 59	17
3-3 Measured and Fitted Temperatures in Well No. 59	19
3-4 Axisymmetric Finite Element Model of the NYSEG Compressed Air Energy Storage Cavern Design	22
3-5 Mohr-Coulomb Envelope for Triaxial Compression Tests on Camillus Formation Core From Well No. 59.....	25
4-1 Average Cavern Air Temperature and Cavern Wall Temperature During 30 Years of Compressed Air Energy Storage Operations	28
4-2 Temperature Contours at Various Times From Immediately Following Dewatering Through 30 Years of Compressed Air Energy Storage Operations	29
4-3 Salt Temperature as a Function of Distance From the Cavern Wall Before and After Air Withdrawal During the First Compressed Air Energy Storage Cycle and During a Cycle After 5 Years of Compressed Air Energy Storage Operations at a Depth of 2,448 Feet	30
4-4 Dilation Factor-of-Safety Contours in the Salt During the First Day of Compressed Air Energy Storage Operations	32
4-5 Dilation Factor-of-Safety Contours in the Salt During the Fourteenth Day of Compressed Air Energy Storage Operations	33
4-6 Dilation Factor-of-Safety Contours in the Salt After 5 Years of Compressed Air Energy Storage Operations.....	34
4-7 Shear Failure Factor-of-Safety Contours in the Nonsalt Units at Various Times From Immediately Following Dewatering Through 30 Years at a Wellhead Pressure of 1,150 psi (In-Plane Horizontal In Situ Stress Equals 0.95 Times the Vertical Stress, Out-of-Plane Horizontal In Situ Stress Equals 1.9 Times the Vertical Stress)	35
4-8 Shear Failure Factor-of-Safety Contours in the Nonsalt Units at Various Times From Immediately Following Dewatering Through 30 Years at a Wellhead Pressure of 1,150 psi (In-Plane Horizontal In Situ Stress Equals 1.9 Times the Vertical Stress, Out-of-Plane Horizontal In Situ Stress Equals 0.95 Times the Vertical Stress)	36

LIST OF FIGURES (Continued)

FIGURE	PAGE
4-9 Stresses and Temperature at the Center of the Cavern Roof During the First Week of Compressed Air Energy Storage Operations	38
4-10 Stresses and Temperature at the Center of the Cavern Roof After 5 Years of Compressed Air Energy Storage Operations	39
4-11 Maximum Principal Stress Contours (Compression Negative) Before and After First Withdrawal After Dewatering (In-Plane Horizontal In Situ Stress Equals 0.95 Times the Vertical Stress, Out-of-Plane Horizontal In Situ Stress Equals 1.9 Times the Vertical Stress)	40
4-12 Maximum Principal Stress Contours (Compression Negative) Before and After Withdrawal After 5 Years of Compressed Air Energy Storage Operations (In-Plane Horizontal In Situ Stress Equals 0.95 Times the Vertical Stress, Out-of-Plane Horizontal In Situ Stress Equals 1.9 Times the Vertical Stress)	41
4-13 Predicted Cavern Closure Versus Time During 30 Years at a Wellhead Pressure of 1,150 psi	42
4-14 Predicted Vertical Casing Strain During 30 Years at a Wellhead Pressure of 1,150 psi	45
B-1 Schematic Illustration of (a) Confined Quasi-Static Compression Test and (b) Constant Mean Stress Test	B-3
B-2 Schematic Illustration of (a) Brazilian Indirect Tension Test and (b) Creep Test	B-4

1.0 INTRODUCTION

1.1 BACKGROUND

New York State Electric & Gas Corporation (NYSEG) is planning to develop a Compressed Air Energy Storage (CAES) plant at their facility at the southern end of Seneca Lake about 4 miles north of Watkins Glen, New York. Their plan is to develop air storage caverns in the bedded salt deposits of the Syracuse Formation at a depth of about 2,400 feet below the ground surface. RESPEC was engaged by PB Energy Storage Services, Inc. (PB ESS) to perform thermodynamic and geomechanics studies to evaluate the proposed CAES storage cavern. The results of the thermodynamic study were previously reported [Nieland, 2011] and are included in Appendix A of this report. This report presents the results of the geomechanics study that was conducted to ensure that the proposed operating conditions will not jeopardize the structural integrity of the proposed caverns.

During CAES operations, energy will be stored by compressing air into the cavern during off-peak periods when low-cost electricity is available. The compressed air will then be produced from the cavern to generate electricity during periods of peak demand. This mode of operation will likely require 250 or more injection/withdrawal cycles per year.

1.2 SCOPE AND OBJECTIVES

The scope of this study was to evaluate the proposed cavern design over the proposed storage pressure range using a typical storage cycle. The objective of this study was to perform thermo-mechanical calculations to evaluate the structural integrity of the proposed cavern design under the anticipated CAES operating conditions.

This objective was addressed in this study by numerical simulations of the proposed cavern design using software developed by RESPEC specifically for modeling excavations in salt. The assumptions associated with in situ conditions, geometric approximations, and material properties used in the models are described throughout the report.

1.3 REPORT ORGANIZATION

A description of the proposed NYSEG CAES facility is given in Chapter 2.0. Chapter 3.0 gives the technical approach used in this study, and Chapter 4.0 presents the numerical modeling results. Chapter 5.0 gives a summary of the modeling results and the study conclusions. Cited references are provided in Chapter 6.0. Appendix A contains a memorandum describing the thermodynamic analyses performed for the proposed cavern design. Appendix B contains a description of typical laboratory tests that can be conducted to determine the mechanical properties of salt and nonsalt rocks.

2.0 PROPOSED COMPRESSED AIR ENERGY STORAGE FACILITY

The proposed NYSEG CAES facility has a rated capacity between approximately 135 and 210 MW and will provide energy during peak periods in support of market needs. WorleyParsons Group, Inc. [2011] provided a typical daily air flow cycle that meets the power generation needs of the facility. The hourly flow rates for the typical cycle are listed in Table 2-1 and are shown graphically in Figure 2-1. Three caverns operating in parallel are planned for the facility. The flow rates for a single cavern are also shown in Table 2-1 and were used in this analyses to evaluate the cavern design. The cycle has air injected into the cavern during off-peak hours and air is withdrawn from the cavern to generate power during peak periods. An air injection temperature at the wellhead of 95°F is specified. The daily cycle requires a total working gas of 17.7 million pounds of air. It was assumed in this analyses that there will not be any flow during weekend hours. Figure 2-2 shows the weekly wellhead pressure for this cycle.

Table 2-1. Flow Rates for Typical Daily Cycle

Time of Day	Hours of Operation	Facility Flow Rate^(a) (lb/s)	Single Cavern Flow Rate (lb/s)
12 a.m.–5 a.m.	5	639	217
5 a.m.–6 a.m.	1	441	150
6 a.m.–8 a.m.	2	–351	–119
8 a.m.–9 a.m.	1	0	0
9 a.m.–1 p.m.	4	–617	–210
1 p.m.–2 p.m.	1	0	0
2 p.m.–4 p.m.	2	–617	–210
4 p.m.–5 p.m.	1	–510	–173
5 p.m.–10 p.m.	5	0	0
10 p.m.–12 a.m.	2	639	217

(a) Positive values indicate injection into storage and negative values indicate withdrawal for power generation.

Preliminary geomechanical analyses determined that an operating wellhead pressure range of 1,150 psi to 1,500 psi (about 1,260 psi to 1,630 psi within the cavern) will result in a structurally stable cavern. Based on preliminary thermodynamic analyses, a cavern volume of roughly 3 million barrels (MMbbls) is required to provide the required working gas for this pressure range. The rate of cavern volume development is governed by a brine disposal rate of

Figure 2-1. Typical Daily Air Flow Cycle for the Compressed Air Energy Storage Facility.

Figure 2-2. Weekly Wellhead Pressure for Typical Air Flow Cycle.

about 350 gallons per minute (gpm) and it is estimated that approximately 6 years will be required to develop a cavern volume of 3 MMbbls. Because of solution-mining limitations and also to provide partial interim operation, three caverns each having a volume of approximately 1 MMbbl will be developed.

The proposed cavern design analyzed in this study [Eyermann, 2011a] is based on solution-mining calculations performed following the preliminary analyses described above. The radius of the cavern design as a function of depth is shown in Figure 2-3. This cavern design has a mined volume of about 970,000 barrels (bbls) of which about 940,000 bbls can be dewatered and used for air storage. The roof of the cavern is at a depth of 2,402 feet (50 feet below the top of salt) and has a dewatered depth of about 2,525 feet. The casing seat is assumed to be at a depth of 2,360 feet, about 8 feet below the top of the salt¹.

¹ This selection for the casing seat depth is based on the following: (1) the casing seat needs to be set in the salt, (2) placing the casing seat too close to the cavern roof will make mechanical integrity testing difficult or impossible, and (3) increasing the distance between the cavern roof and casing seat results in a lower amount of casing strain.

Figure 2-3. Simulated Shape of Proposed Compressed Air Energy Storage Cavern Design [Eyermann, 2011a].

3.0 TECHNICAL APPROACH

The geomechanics study was performed using numerical modeling. Thermomechanical finite element simulations of the NYSEG CAES cavern design were performed to evaluate stability of the rock surrounding and overlying the cavern and to estimate cavern closure and associated casing strain during CAES operations. The following sections describe the numerical modeling software, material properties, in situ conditions, and the finite element model used in this evaluation.

3.1 NUMERICAL MODELING

Numerical modeling software was used to model the thermodynamics and heat transfer in the cavern, the heat transfer in the salt surrounding the cavern, and the mechanical behavior of the salt surrounding the cavern. These specialized computer programs and the constitutive model used to define the viscoplastic deformation of the salt are described in the following subsections.

3.1.1 Cavern Thermodynamics Program

The Salt Cavern Thermal Simulator (SCTS) [Nieland, 2004] is a program developed by PB ESS and RESPEC for simulating the thermodynamics and heat transfer related to the storage of natural gas in underground salt caverns. It accounts for the thermal effects associated with gas compression and expansion; the mass transfer during injection and withdrawal; and the heat transfer between the gas and its surroundings, both in the wellbore and in the cavern. A modified version of SCTS that allows the simulation of air storage was used in this study.

SCTS was used to estimate the cavern temperatures during cavern development, dewatering, and throughout the simulated air storage operations. SCTS calculates a single bulk cavern temperature and a cavern wall temperature. The cavern wall temperatures as a function of time, determined from SCTS, were applied as a boundary condition to the thermal finite element model to estimate the temperature of the salt surrounding the cavern as a function of time.

3.1.2 Heat Transfer Finite Element Program

SPECTROM-41 [Svalstad, 1989] is a finite element heat transfer analysis program that was developed by RESPEC to analyze thermal problems in geologic formations. The primary transport process modeled by SPECTROM-41 is conductive heat transfer. SPECTROM-41 has the capability to model complex material properties (including temperature-dependent thermal conductivity) and boundary conditions. SPECTROM-41 was used in this study to simulate the heat transfer between the cavern and the surrounding salt. The results of these calculations were

then integrated into the thermomechanical analyses to account for the thermal stresses and strains that are a result of the temperature changes in the salt surrounding the cavern.

3.1.3 Thermomechanical Finite Element Program

SPECTROM-32 [Callahan et al., 1989] is a thermomechanical, finite element program that was developed by RESPEC for the solution of rock mechanics problems. It was designed specifically for the simulation of underground openings and structures. SPECTROM-32 not only has the capability to model the elastic-plastic response that is commonly associated with brittle rock types, but it also has the capability to simulate the viscoplastic behavior that is observed in rock salt. The features and capabilities of SPECTROM-32 that were required specifically for this investigation include:

- Option for axisymmetric geometries.
- Kinematic and traction boundary conditions.
- Munson-Dawson multimechanism constitutive model for viscoplastic behavior of salt.
- Capability to represent arbitrary in situ stress and temperature fields.
- Capability to simulate excavation operations.

3.1.4 Constitutive Model for Salt

The deformation rate of salt can be decomposed into thermal expansion, elastic deformation, and inelastic deformation. The inelastic deformation is stress-, temperature-, and rate-dependent. It is comprised of both viscoplastic (creep) and brittle components, with the viscoplastic component usually dominating in the range of stress and temperature expected in the salt surrounding the storage caverns.

Considerable research has been performed to determine a satisfactory constitutive law that characterizes the viscoplastic behavior of rock salt. The Munson-Dawson multimechanism constitutive model (M-D model) has been found to perform reasonably well in fitting data from laboratory constant-stress tests and in predicting the response of laboratory, field, and bench-scale tests performed on Avery Island salt [DeVries, 1988].

Two differential rate equations comprise the M-D model: (1) the strain-rate equations which give the viscoplastic strain rates (Equation 3-1) and (2) the evolutionary equation which gives the rate of change of an internal variable (Equation 3-2). The three-dimensional form of the M-D model is given below:

$$\dot{\epsilon}_{ij}^{vp} = \frac{\partial \sigma_e}{\partial \sigma_{ij}} F \dot{\epsilon}_s \quad (3-1)$$

$$\dot{\varsigma} = (F - 1)\dot{\varepsilon}_s \quad (3-2)$$

where:

$$\dot{\varepsilon}_s = \sum_{i=1}^3 \dot{\varepsilon}_{s_i} \quad (3-3)$$

$$\dot{\varepsilon}_{s_i} = \text{steady-state strain rate for mechanism } i \quad (3-4)$$

$$\dot{\varepsilon}_{s_1} = A_1 \exp(-Q_1/RT) (\sigma_e/\mu)^{n_1} \quad (3-5)$$

$$\dot{\varepsilon}_{s_2} = A_2 \exp(-Q_2/RT) (\sigma_e/\mu)^{n_2} \quad (3-6)$$

$$\dot{\varepsilon}_{s_3} = [B_1 \exp(-Q_1/RT) + B_2 \exp(-Q_2/RT)] \cdot \sinh[q(\sigma_e - \sigma_o)/\mu] H(\sigma_e - \sigma_o) \quad (3-7)$$

$$F = \begin{cases} \exp\left[\Delta\left(1 - \frac{\varsigma}{\varepsilon_t^*}\right)^2\right] & \text{for } \varsigma < \varepsilon_t^* \\ 1 & \text{for } \varsigma = \varepsilon_t^* \\ \exp\left[-\delta\left(1 - \frac{\varsigma}{\varepsilon_t^*}\right)^2\right] & \text{for } \varsigma > \varepsilon_t^* \end{cases} \quad (3-8)$$

$$\varepsilon_t^* = K_o \exp(cT) (\sigma_e/\mu)^m \quad (3-9)$$

$$\Delta = \alpha + \beta \log(\sigma_e/\mu) \quad (3-10)$$

and

$$\dot{\varepsilon}_{ij}^{vp} = \text{viscoplastic strain-rate tensor}$$

$$\sigma_e = \sqrt{3J_2} \text{ (effective stress)}$$

$$J_2 = \frac{1}{2} s_{ij} s_{ji}$$

$$s_{ij} = \sigma_{ij} - \delta_{ij} \sigma_m \text{ (deviatoric stress tensor)}$$

$$\sigma_m = \frac{1}{3} \sigma_{kk} \text{ (mean stress)}$$

$$\sigma_{ij} = \text{stress tensor}$$

$$\delta_{ij} = \text{Kronecker delta}$$

$$\varsigma = \text{internal variable}$$

T = absolute temperature

$H(x)$ = Heaviside function

μ = $1.7985(10^6)$ a normalizing constant

$A_1, A_2, B_1, B_2, Q_1/R,$

$Q_2/R, n_1, n_2, q, \sigma_o,$

$\delta, K_o, c, m, \alpha, \beta$ = experimentally determined parameters.

As indicated by Equation 3-3, the steady-state creep rate ($\dot{\epsilon}_s$) based on the M-D model is composed of three terms. Each term is associated with a different creep mechanism. The first and third mechanisms ($\dot{\epsilon}_{s_1}$ and $\dot{\epsilon}_{s_3}$) are dislocation climb and dislocation glide, respectively, and the second mechanism ($\dot{\epsilon}_{s_2}$) is referred to as the undefined mechanism. The undefined mechanism is well characterized but is not defined in a sense of classical dislocation motion. The relative contribution of each mechanism to the steady-state creep rate strongly depends on the effective stress and temperature.

When pressure conditions in a cavern are changed, the transient nature of the M-D model can be an important factor in the response of the cavern. According to Equation 3-1, the steady-state creep rate is multiplied by a transient factor (F) to obtain the viscoplastic strain rate. The value of the transient factor depends on whether the internal variable (ς) is less than, equal to, or greater than the transient strain limit (ϵ_t^*), which is a function of the effective stress and temperature. When $\varsigma < \epsilon_t^*$, the viscoplastic strain rate is greater than the steady-state creep rate ($F > 1$). This is the work-hardening branch of the M-D model. The work-hardening branch is commonly associated with an increase in loading, such as when a cavern is excavated or when the cavern pressure is decreased. When $\varsigma > \epsilon_t^*$, the viscoplastic strain rate is less than the steady-state creep rate ($F < 1$). This is the recovery branch of the M-D model. This branch is commonly associated with a decrease in loading, such as when the cavern pressure is increased. Through the evolutionary equation, the value of the internal variable is always approaching the transient strain limit. In turn, the viscoplastic strain rate is always approaching the steady-state creep rate (i.e., F approaches unity as ς approaches ϵ_t^*).

The Munson-Dawson model has 16 parameters that must be determined experimentally or estimated empirically. The parameter values used to represent the salt surrounding the NYSEG CAES caverns are presented in Section 3.3.2.

3.2 STRATIGRAPHY

The stratigraphy modeled in the NYSEG CAES simulations is based on the local stratigraphy described by Eyermann [2011b]. Eyermann estimates the thickness of the entire Syracuse Formation to be 850 feet and calls out the salt and nonsalt units in the F Unit (the upper 450 feet in the Syracuse Formation). The lower portion of the Syracuse Formation was modeled as salt, and the units below the Syracuse Formation were simply defined as

“Underlying Groups” and modeled as shale. Because these lower units are so distant from the region of interest around the cavern, their individual thicknesses and properties should not have a significant effect in the simulation results. The densities for each of the units are based on a density log conducted in Well No. 59 [Osnes and Eyermann, 1996]. The complete stratigraphic column modeled is listed in Table 3-1, and the salt and nonsalt layers modeled within the Syracuse Formation are listed in Table 3-2.

Table 3-1. Stratigraphy Modeled in the NYSEG Compressed Air Energy Storage Simulations

Unit–Lithology	Top Depth (ft)	Bottom Depth (ft)	Thickness (ft)
Genesee–Shale	0	830	830
Tully–Limestone	830	847	17
Hamilton–Shale	847	1,768	921
Marcellus–Shale	1,768	1,866	98
Onondaga–Limestone	1,866	1,911	45
Tristates Group–Sandstone	1,911	1,948	37
Oriskany–Sandstone	1,948	1,956	8
Helderberg Group–Limestone	1,956	2,106	150
Cobleskill/Akron–Dolostone	2,106	2,166	60
Bertie–Dolostone	2,166	2,255	89
Camillus–Shale	2,255	2,352	97
Syracuse–Salt/Nonsalt	2,352	3,202	850
Underlying Groups	3,202	—	—

3.3 MATERIAL PROPERTIES

Of the geologic units listed in Table 3-1, only the Syracuse Formation contains significant thicknesses of salt. The nonsalt units are assumed to deform elastically and are further assumed not to yield or fail in shear in response to the CAES operations. This assumption is subsequently checked in the geomechanical analyses by calculating factors of safety against shear failure. The material properties used in the simulations are described in the following sections.

Table 3-2. Stratigraphy Within the Syracuse Formation

Lithology	Top Depth (ft)	Bottom Depth (ft)	Thickness (ft)
Salt	2,352	2,361	9
Shale	2,361	2,363	2
Salt	2,363	2,415	52
Shale	2,415	2,418	3
Salt	2,418	2,433	15
Shale	2,433	2,441	8
Salt	2,441	2,454	13
Shale	2,454	2,462	8
Salt	2,462	2,466	4
Dolomite	2,466	2,469	3
Salt	2,469	2,477	8
Shale	2,477	2,482	5
Salt	2,482	2,534	52
Dolomite/Shale	2,534	2,567	33
Salt	2,567	2,618	51
Shale/Dolomite	2,618	2,651	33
Salt	2,651	2,675	24
Shale	2,675	2,708	33
Salt	2,708	2,743	35
Shale	2,743	2,750	7
Salt	2,750	2,795	45
Shale	2,795	2,802	7
Salt	2,802	3,202	400

3.3.1 Elastic and Thermal Properties

Table 3-3 lists the elastic and thermal properties used to represent the rock in the numerical models. Densities for the rock units are based on a density log conducted in Well No. 59 [Osnes

and Eyermann, 1996]. The elastic properties of the Camillus Formation and the salt from the

Table 3-3. Elastic and Thermal Properties

Unit–Lithology	Young's Modulus (psi)	Poisson's Ratio	Density (lb/ft³)	Coefficient of Thermal Expansion (°F⁻¹)	Thermal Conductivity (Btu/(hr-ft-°F))	Specific Heat (Btu/lb-°F)
Genesee–Shale	2.93×10^6	0.242	164	4.39×10^{-6}	0.804	0.190
Tully–Limestone	6.30×10^6	0.242	167	11.1×10^{-6}	1.775	0.123
Hamilton–Shale	3.11×10^6	0.242	165	4.39×10^{-6}	0.804	0.190
Marcellus–Shale	3.11×10^6	0.242	165	4.39×10^{-6}	0.804	0.190
Onondaga–Limestone	5.22×10^6	0.242	164	11.1×10^{-6}	1.775	0.123
Tristates Group–Sandstone	4.75×10^6	0.242	167	5.56×10^{-6}	1.966	0.170
Oriskany–Sandstone	4.75×10^6	0.242	167	5.56×10^{-6}	1.966	0.170
Helderberg Group–Limestone	7.47×10^6	0.242	168	11.1×10^{-6}	1.775	0.123
Cobleskill/Akron–Dolostone	7.20×10^6	0.242	169	11.1×10^{-6}	1.775	0.123
Bertie–Dolostone	7.03×10^6	0.242	175	11.1×10^{-6}	1.775	0.123
Camillus–Shale	5.02×10^6	0.242	170	4.39×10^{-6}	0.804	0.190
Syracuse–Salt	3.61×10^6	0.242	130	21.6×10^{-6}	3.000	0.200
Syracuse–Nonsalt	5.02×10^6	0.242	170	4.39×10^{-6}	0.804	0.190
Underlying Groups	5.02×10^6	0.242	170	4.39×10^{-6}	0.804	0.190

Syracuse Formation are based on laboratory testing of core recovered from Well No. 58 (salt only) and Well No. 59 [Pfeifle, 1996]. The elastic properties of the units above the Camillus Formation are based on sonic velocity logs of Well No. 59 [Osnes and Eyermann, 1996]. The elastic properties of the nonsalt units within the Syracuse Formation and underlying units were assumed to be the same as those for the Camillus Formation. Published values of the elastic properties of rock in and below the Vernon Formation [Carmichael, 1982] indicate these are reasonable assumptions. Because no testing has been conducted to determine thermal properties of the rock units, typical thermal and thermoelastic properties [Croff et al., 1985; Callahan, 1981; Senseny et al., 1992] for shale, sandstone, carbonates (limestone and dolomite), and salt were assigned to the units.

3.3.2 Creep Properties

The Munson-Dawson constitutive model parameters that were used to model the viscoplastic (creep) behavior of the Syracuse salt in this study were determined by fitting the model to creep tests conducted on salt from the Syracuse Formation in the Watkins Glen cavern field [Pfeifle, 1996]. Three tests were conducted on salt core obtained from Well No. 58 and three on salt core from Well No. 59. All of the creep tests were performed at a temperature of 86°F. The three tests from each well were run at stress differences (the axial stress minus confining pressure) of 1,000 psi, 2,000 psi, and 3,000 psi.

Although a set of parameters for the Munson-Dawson constitutive model was previously determined using these creep tests [Osnes and Eyermann, 1996], our increased experience in both parameter fitting and use of the Munson-Dawson model warranted refitting the data. Because of the limited number of creep tests, not all of the Munson-Dawson model parameters could be uniquely determined. Several Munson-Dawson model parameter values were assumed to be the same as those determined from an extensive study of eight Gulf Coast domal salts [Munson, 1998]. Munson classified the creep of domal salt as forming two distinct groups, either soft or hard, where the difference is roughly a factor of seven in the leading coefficients for each of the three deformation mechanisms (and thus the steady-state creep rate) between the two groups. The ratio of the leading coefficients to those of the soft salt provided by Munson were determined for Syracuse salt. Additionally, the transient parameters K_0 , m , α , and β were determined. The parameters were estimated through the use of a nonlinear least-squares fitting procedure.

The resulting Munson-Dawson parameter values used for Syracuse salt are shown in Table 3-4. The creep test data for Well No. 58 and Well No. 59 and the fits predicted using these estimated Munson-Dawson parameter values are shown in Figures 3-1 and 3-2, respectively. These figures indicate that the Munson-Dawson model with the fitted parameters adequately characterizes the creep behavior of the Syracuse salt.

Table 3-4. Munson-Dawson Creep Parameters Used to Model Syracuse Formation Salt

Parameters	Units	Value	Basis for Value
A_1	day ⁻¹	7.69(10 ²⁷)	Syracuse Salt
A_2	day ⁻¹	8.87(10 ¹⁷)	Syracuse Salt
B_1	day ⁻¹	5.58(10 ¹¹)	Syracuse Salt
B_2	day ⁻¹	2,780	Syracuse Salt
Q_1/R	R	22,700	Munson [1998]
Q_2/R	R	9,060	Munson [1998]
n_1	—	5.5	Munson [1998]
n_2	—	5.0	Munson [1998]
q	—	5,340	Munson [1998]
σ_o	psi	2,980	Munson [1998]
K_o	—	8,090	Syracuse Salt
m	—	2.43	Syracuse Salt
c	—	0.00511	Munson [1998]
α	—	-14.6	Syracuse Salt
β	—	-8.82	Syracuse Salt
δ	—	0.580	Munson [1998]

3.3.3 Air Characteristics

Air is modeled in SCTS as a real gas using the American Gas Association's Detail Characterization Method as described by Starling and Savidge [1994]. The air composition used in the SCTS simulations is listed in Table 3-5.

In addition to the constituents listed above, the air in the cavern will likely contain a small amount of water vapor. However, the effects of the water vapor are expected to be extremely small and were not included in this study. Cavern air pressure was applied in the finite element model with tractions (applied pressure boundary conditions) on the cavern surface. A linear pressure gradient was assumed for the air in the cavern and is based on the casing seat pressures and cavern air densities estimated by SCTS.

RSI-2040-11-021

Figure 3-1. Measured and Predicted Axial Creep Strains for Creep Tests Performed on Salt From Well No. 58.

RSI-2040-11-022

Figure 3-2. Measured and Predicted Axial Creep Strains for Creep Tests Performed on Salt From Well No. 59.

Table 3-5. Assumed Air Composition

Gas Component	Mole Percent
Nitrogen	78.0
Oxygen	21.0
Argon	1.0

3.3.4 Brine Characteristics

Brine pressure was applied in the finite element model with tractions on the cavern surface. Because of the very small compressibility of brine (approximately $1.9 \times 10^{-6}/\text{psi}$), the increase in brine density associated with the hydrostatic pressure increase over the height of a cavern is negligible (about 0.1 percent change per 1,000 feet). Consequently, the brine density was assumed to remain a constant 75 pcf, resulting in a vertical pressure gradient of 0.52 psi/foot.

In the simulations performed here, the cavern was dewatered to a depth of 2,525 feet. The thermal properties of the brine and insolubles modeled in the bottom portion of the cavern were assigned typical values for brine (specific heat = 0.76 BTU/lb_m-°F, thermal conductivity = 0.35 BTU/hr-ft-°F).

3.4 IN SITU CONDITIONS

Since the creep rate of salt is dependent on temperature and stress, it is important to model temperatures and stresses which are representative of those in the vicinity of the CAES storage cavern. The following two subsections describe the in situ temperature and stress distributions assumed in this analysis.

3.4.1 Temperature Profile

The initial in situ temperature assumed in this study is based on temperature logs conducted during mechanical integrity testing of Well No. 59 in May 1996. Figure 3-3 shows the measurements from the three temperature logs conducted and the fitted temperature profile. Because of the elevation difference between Well No. 59 (about 540 feet above mean sea level (amsl)) and the proposed CAES site location (about 1,000 feet amsl), the temperature gradient in the upper portion of Well No. 59 was projected upward an additional 460 feet to obtain the estimated surface temperature of 45.6°F at the CAES location. The entire temperature profile assumed for the CAES site is defined in Table 3-6. Based on this profile, the estimated in situ temperature of the rock at the midheight of the cavern is about 77°F.

Figure 3-3. Measured and Fitted Temperatures in Well No. 59.
Table 3-6. Assumed In Situ Temperature Profile

Surface Temperature = 45.6°F		
CAES Site Depth Range (ft)	Elevation Range (ft amsl)	Temperature Gradient (°F/ft)
0 to 1,110	1,000 to -110	0.0085
1,110 to 1,866	-110 to -866	0.0225
Below 1,866	Below -866	0.0088

3.4.2 In Situ Stress

Principal in situ stresses are generally assumed to be aligned with an axis system that is vertical and horizontal. The magnitude of the vertical principal stress is typically assumed to be equal to the weight of the overburden. This assumption was made in the geomechanical analysis of the NYSEG CAES cavern design using the thicknesses (Tables 3-1 and 3-2) and densities (Table 3-3) of the geologic units in the stratigraphic model. In salt deposits, it is generally accepted that the horizontal components of in situ stress are nominally equal to the vertical component (i.e., the stress state is isotropic) because any differences between the horizontal and vertical components introduce shear stress components that are relieved by creep over geologic time frames. Consequently, it is reasonable to assume that the horizontal components of in situ stress in the Syracuse salt units are equal to the vertical stress determined by the weight of the overlying units.

In nonsalt rock that does not creep appreciably even over geologic time frames, differences between the two principal components of horizontal stress and the vertical stress can be sustained, and the in situ stress state is not necessarily isotropic. The inequality of the principal stresses in most regions is reflected in the regional faulting. The faulting in western New York State suggests that the in situ stresses are not equal in magnitude in the nonsalt strata. A literature review performed in the 1996 study of Gallery No. 1 revealed that the in situ stress state in western New York State is one in which the principal stress components are not equal [Osnes and Eyermann, 1996]. The two principal horizontal stresses are different from the vertical stress and are also different from each other. Based on regional stress measurements, it appears likely that the minimum horizontal stress at the Watkins Glen site is slightly lower than the vertical stress, with a ratio of about 0.95. Based on the same regional measurements, the maximum horizontal stress would be about 1.9 times the vertical stress.

The in situ stress state used in the 1996 modeling of Gallery No. 1 was adopted for this study. Because an axisymmetric model was used in this analysis, it was necessary to conduct each of the simulations twice to evaluate the anisotropic stress state. First, the simulations

were with the in-plane horizontal stresses in the nonsalt units at 1.9 times the vertical stress and the tangential or out-of-plane horizontal stresses in the nonsalt units at 0.95 times the vertical stress. The simulations were then repeated with the in-plane horizontal stresses in the nonsalt units at 0.95 times the vertical stress and the out-of-plane horizontal stresses in the nonsalt units at 1.9 times the vertical. The horizontal stresses in the salt units were assumed to be equal to the vertical stress in all simulations.

3.5 FINITE ELEMENT MODEL

Figure 3-4 shows the axisymmetric finite element model of the cavern used in the NYSEG CAES simulations. The modeled cavern radii as a function of depth were estimated by placing a smoothed curve through the estimated solution-mining geometry provided by Eyermann [2011a]. The small sump below a depth of 2,572 feet will have no impact on cavern stability and was not included in the model. The region immediately outside the walls of the cavern is very finely subdivided. This extremely fine subdivision was used to accurately represent the high stress and temperature gradients that were anticipated near the cavern periphery. The extents of the model were selected to isolate the response of the cavern from the influences of the radial and bottom boundaries which are artificial truncations of the actual horizontal and vertical extents of the stratigraphy.

In simulating CAES operations, the cavern was dewatered to a depth of 2,525 feet. The elements below this level (dark blue elements in Figure 3-4) represent the brine and insolubles left in the cavern after dewatering and were represented as brine in the simulations.

During heat transfer simulations, the outer boundaries of the model are insulated, and thus, no heat is transferred across these boundaries. The cavern wall temperature histories from the SCTS simulations were applied to the cavern boundary in the finite element model to calculate temperatures in the salt surrounding the cavern for each of the simulations in SPECTROM-41. These temporal temperature distributions were subsequently used in the thermomechanical simulations to account for thermal stresses.

During thermomechanical simulations, the kinematic boundary conditions specified along the sides of the axisymmetric model were:

- No radial displacement along the centerline.
- No radial displacement along the outer radius.
- No vertical displacement along the bottom surface.

The upper surface of the model is free to move in the vertical direction.

In the thermomechanical simulations, after excavation of the salt, normal tractions are specified along the surfaces of the cavern to simulate the fluid and air pressure inside the

cavern. The magnitudes of these tractions are equal to the hydrostatic pressure based on the

Figure 3-4. Axisymmetric Finite Element Model of the NYSEG Compressed Air Energy Storage Cavern Design.

density of brine during the solution-mining portion of the simulation and based on the respective casing seat pressure and the average air density during the CAES portion of the simulations.

3.6 CRITERIA FOR EVALUATING STRUCTURAL STABILITY

Cavern stability was evaluated by examining the stress states in the salt surrounding the cavern. Stress states that result in extensive salt dilation in the upper portion of the cavern can lead to spalling of the roof and/or walls of the cavern and subsequent damage to the casing seat or well. Tensile stresses around the cavern periphery that may result from temperature fluctuations in the cavern can also result in spalling of the salt. Thus the anticipated CAES operating cycles were evaluated and a minimum pressure was determined to ensure that no tensile zones or extensive regions of salt dilation occur.

3.6.1 Tensile Zones

Geologic materials are much stronger in compression than in tension. The unconfined compressive strength of most rocks is generally about ten times greater than the tensile strength. Therefore, tensile stresses in rocks surrounding storage caverns are to be avoided whenever possible through appropriate design of the cavern or through specification of operating pressures.

Laboratory testing of salt core from Wells No. 58 and No. 59 indicates the tensile strength of the bedded salts in the region is as high or higher than many other bedded salts. The average tensile strength of the salt is 205 psi and 328 psi for the core from wells No. 58 and No. 59, respectively [Pfeifle, 1996]. Laboratory testing of Camillus Formation core from Well No. 59 indicates that the tensile strength of this geologic unit, which overlies the roof of the proposed CAES cavern, is variable with an average value of 1,149 psi [Pfeifle, 1996] and ranges from 729 psi to 1,530 psi. The material models used in this analysis do not provide for tensile failure. Postprocessing of the modeling results was used to determine whether or not tensile stresses and fracturing have occurred.

3.6.2 Salt Dilation

The viscoplastic deformation of salt is isovolumetric, which means that the volume of the salt remains constant during creep deformation. An increase in salt volume, a phenomenon referred to as dilation, indicates the formation of microfractures within the salt. A criterion used to determine whether or not a stress state is one that results in salt dilation has been previously developed based on laboratory testing of Avery Island domal salt and Waste Isolation Pilot Plant (WIPP) bedded salt [Van Sambeek et al., 1993]. Two stress measures are used in defining the dilation criterion: the first invariant of the stress tensor (I_1) and the second invariant of the deviatoric stress tensor (J_2). These two stress measures are defined as follows:

$$I_1 = \sigma_1 + \sigma_2 + \sigma_3 \quad (3-11)$$

$$J_2 = \frac{1}{6} \left[(\sigma_1 - \sigma_2)^2 + (\sigma_2 - \sigma_3)^2 + (\sigma_3 - \sigma_1)^2 \right] \quad (3-12)$$

where:

$\sigma_1, \sigma_2, \sigma_3$ = principal stress components.

Van Sambeek et al. [1993] concluded that stress states satisfying the following inequality generally did not result in dilation of salt test specimens:

$$\sqrt{J_2} \leq 0.27 I_1 \quad (3-13)$$

The testing to determine the dilation properties of Syracuse salt included six multistage creep tests and five constant mean stress tests (eleven individual specimens) on salt core from Well No. 58 and Well No. 59 [Pfeifle, 1996]. Osnes and Eyermann [1996] concluded that based on these tests, Syracuse salt exhibits a dilation limit similar to that described by Equation 3-13.

The above criterion is based on triaxial compression testing of salt. Like all other rocks, salt is known to be weaker in triaxial extension than in triaxial compression. The stress state in the salt surrounding a cavern varies between triaxial compression and triaxial extension. As the cavern pressure is lowered, the stresses move closer to triaxial extension. To account for extensile stress states, the dilation limit described above was reduced conservatively to:

$$\sqrt{J_2} \leq 0.18 I_1 \quad (3-14)$$

Factors of safety were used to quantify the potential for dilation in the salt around the proposed CAES cavern design. The factor of safety (at constant I_1) is defined as:

$$\text{Factor of Safety} = \frac{0.18 I_1}{\sqrt{J_2}} \quad (3-15)$$

3.6.3 Shear Failure Criterion for Nonsalt Strata

The criterion used to determine whether or not a stress state is one that results in shear failure of the nonsalt strata is based on laboratory testing of Camillus Formation core from Well No. 59 [Pfeifle, 1996]. Six constant strain rate tests, each on an individual specimen, were performed. In these tests, the confining pressure is held constant at nominally 0, 500, or 1,000 psi while an axial strain rate of 10^{-4} s^{-1} is imposed until the specimen fails.

The Mohr-Coulomb failure criterion has been shown to adequately predict shear failure in brittle (nonsalt) rock types. The Mohr-Coulomb failure envelope is represented in shear (τ)

versus normal (σ_n) stress space by Equation 3-16 and is described by two parameters, the cohesion (S_0) and friction angle (ϕ). The Mohr-Coulomb failure criterion simply states that if the shear stress along any plane in the rock exceeds the shear strength along that same plane, failure will occur. The Mohr-Coulomb failure envelope is defined as:

$$\tau = S_0 + \sigma_n \tan \phi \quad (3-16)$$

Plotted in Figure 3-5 are the Mohr's circles for each of the tests at their failure point along with the fitted Mohr-Coulomb failure envelope. The resulting parameters for the failure envelope are a cohesion (S_0) of 735 psi and a friction angle (ϕ) of 59.0 degrees. Factors of safety were then used to quantify the potential for shear failure in the nonsalt strata, which is defined as the ratio between the shear strength, τ , as defined by Equation 3-16 above, divided by the actual shear stress. Failure is expected to occur when the factor of safety is less than 1.

RSI-2040-11-025

Figure 3-5. Mohr-Coulomb Envelope for Triaxial Compression Tests on Camillus Formation Core From Well No. 59.

4.0 MODELING RESULTS

Thermal and thermomechanical finite element simulations were conducted to evaluate the cavern design during CAES operations. Long-term simulations of a single cavern were conducted using the typical weekly CAES pressure cycle shown in Figure 2-2 with an air injection temperature of 95°F. The cavern wall temperature versus time obtained from the thermodynamic simulations (see Appendix A) was used as a boundary condition in the thermal finite element simulations to estimate the temperature distribution around the cavern as a function of time. These temporal temperature distributions were then used in the thermomechanical finite element simulations along with the daily pressure cycle to evaluate cavern stability and estimate cavern closure during CAES operations.

The stability of a solution-mined cavern is dependent upon the state of stress in the salt surrounding the cavern. The stress state around a cavern is used to determine the structural stability of the cavern roof and walls. The stress state in the salt around the cavern is dependent on (1) the original in situ state of stress, (2) the fluid pressure in the cavern, (3) cavern geometry, (4) salt creep, and (5) temperature changes in the salt. Because salt has a relatively high coefficient of thermal expansion, temperature changes in the salt can have a significant effect on stresses surrounding the cavern during air injection and withdrawal.

In all of the thermomechanical finite element simulations of the CAES cavern design, the cavern was instantaneously excavated and allowed to creep for 2 years under a brine pressure gradient (0.52 psi/foot) with a wellhead pressure of 30 psi. This pressure condition is representative of the pressure the cavern will experience during its development. After 2 years at brine pressure conditions, dewatering of the cavern with air was simulated. The stress and temperature conditions at the end of dewatering are the starting conditions for the simulations used in evaluating cavern stability. The simulations performed to evaluate cavern stability include:

- A single 30-year thermal simulation to estimate the thermal response of the rock surrounding the cavern. To make this simulation, SCTS was used to estimate the cavern wall temperature as a function of time while repeating the typical CAES cycle for 30 years. The cavern wall temperature as a function of time was used as a boundary condition on the cavern surface in the thermal model. The thermal response of this simulation was used in all of the thermomechanical simulations.
- A 5-year thermomechanical simulation of the typical CAES cycle. This model was used to evaluate the potential for salt dilation and to evaluate the potential for hydraulic fracture development.
- A 30-year thermomechanical simulation with the cavern at the minimum wellhead pressure of 1,150 psi. Maintaining the pressure at the minimum pressure provides a

conservative estimate of the creep closure that the cavern will experience. In turn, it also provides conservative estimates of all factors affected by creep closure, including shear failure of the nonsalt units and of casing strain.

As discussed in Section 3.4.2, all of the thermomechanical simulations were conducted with two scenarios for the in situ stress in the nonsalt units. The following sections presents the results of the models.

4.1 THERMAL MODELING

Figure 4-1 shows the average cavern air temperature and cavern wall temperature as a function of time during 30 years of cycling predicted with SCTS. As seen in the figure, the cavern temperatures increase significantly during the first couple of years, then only very gradually increases throughout the 30-year simulation. The predicted cavern wall temperature as a function of time was used as a boundary condition on the cavern surface in the thermal finite element simulation to predict temperatures in the rock surrounding the cavern as a function of time.

The rock surrounding the CAES cavern is expected to experience both short-term and long-term temperature changes. Figure 4-1 shows the long-term thermal changes expected in the rock around the cavern. During cavern development, a large volume of rock around the cavern will gradually cool because the assumed freshwater injection temperature of 52°F is cooler than the in situ rock temperature at the cavern elevation (77°F) and because the dissolution of salt is an endothermic process. The contours at a time of 0 years in Figure 4-2 show the temperatures expected at the end of dewatering. During CAES operations, air is injected at the wellhead at a temperature of 95°F and enters the cavern at around 105°F because of compression and friction in the wellbore. Continuous cycling with this injection temperature will gradually warm the rock around the cavern to temperatures well above the in situ rock temperature.

The daily injection and withdrawal of air from the cavern will also result in short-term temperature changes in the rock very near the cavern surface. Figure 4-3 shows the salt temperature as a function of radial distance from the cavern wall at a depth of 2,448 feet at minimum and maximum pressure for the first cycle after dewatering and for a cycle after 5 years of cycling. Note that although the magnitudes of the temperature profiles are higher after 5 years of cycling, the temperature changes that occur between minimum and maximum pressure are nearly the same. The temperature difference between minimum and maximum pressure is about 25°F at the cavern wall. The temperature changes between about 0.75 foot and 5 feet from the wall are less than 5°F over a single daily cycle. Temperature fluctuations related to the daily cycle are nearly nonexistent beyond a distance of 5 feet from the cavern wall.

Figure 4-1. Average Cavern Air Temperature and Cavern Wall Temperature During 30 Years of Compressed Air Energy Storage Operations.

Figure 4-2. Temperature Contours at Various Times From Immediately Following Dewatering Through 30 Years of Compressed Air Energy Storage Operations.

Figure 4-3. Salt Temperature as a Function of Distance From the Cavern Wall Before and After Air Withdrawal During the First Compressed Air Energy Storage Cycle and During a Cycle After 5 Years of Compressed Air Energy Storage Operations at a Depth of 2,448 Feet.

4.2 CAVERN STABILITY

Cavern stability was evaluated by examining the factors of safety with respect to dilation in the salt surrounding the cavern and with respect to shear failure in the nonsalt units intersecting and overlying the cavern. The effects of creep closure on the stability of the salt around a cavern are generally opposite to its effects on the stability of the nonsalt rocks. Because salt has the ability to redistribute the stresses to a more stable condition as it creeps, the stability of the salt around a cavern generally increases with time. However, the nonsalt units are not able to redistribute the stresses that develop because of creep closure and shear stresses tend to increase until brittle failure eventually occurs.

Figure 4-4 shows dilation factor-of-safety contours in the salt just before and just after the withdrawal from maximum pressure (1,500 psi at the wellhead) down to minimum pressure (1,150 psi at the wellhead) on the first day of CAES operations. At maximum pressure, dilation is predicted (factor-of-safety values less than 1) in the upper corner of the cavern and also in the floor of the cavern, and a large portion of the roof is predicted to have factor-of-safety values between 1 and 1.5. At minimum pressure, only a small amount of dilation is predicted below the upper nonsalt bed that intersects the cavern. These generally low factors of safety, especially those at higher pressure, are related to the cooling of the salt around the cavern during cavern development. After 2 weeks of operations (Figure 4-5), some warming of the salt has occurred and no dilation is predicted at maximum pressure, and the factor-of-safety values in the roof have increased significantly. At minimum pressure, there is a thin skin of dilating salt on the lower lobe of salt between the bottom two nonsalt beds. Although there may be some sloughing of salt in the area, it is in the lower portion of the cavern and is not expected to affect stability. After 5 years (Figure 4-6) of CAES operations, most of the dilation factor-of-safety values are greater than 3 when the cavern is at maximum pressure and greater than 2 at minimum pressure. The thin skin of dilating salt in the lower portion of the cavern is still predicted at minimum pressure after 5 years of operations. Based on these results, salt dilation is not expected to affect cavern stability for the pressure range evaluated.

Figures 4-7 and 4-8 show shear failure factor-of-safety contours in the nonsalt units assuming in situ horizontal stresses in the plane of the model of 0.95 and 1.9 times the vertical stress, respectively. In the thin overlying nonsalt unit within the Syracuse Formation, the factors of safety are greater than 1. In the Camillus Formation and other overlying formations, the factors of safety are greater than 1.5 and do not change significantly with time because the creep closure of the cavern is relatively low. The thin nonsalt units that intersect the cavern do have regions with factor-of-safety values less than 1 and the extent of the regions increases with time. These regions of failure are the result of tensile stresses that develop because these units will be continually pulled on by the salt as it creeps toward the cavern. As such, the failures are expected to result in vertical tensile fractures parallel to the cavern wall and are not expected to result in cavern instability or provide a pathway for leakage.

Figure 4-4. Dilation Factor-of-Safety Contours in the Salt During the First Day of Compressed Air Energy Storage Operations.

Figure 4-5. Dilation Factor-of-Safety Contours in the Salt During the Fourteenth Day of Compressed Air Energy Storage Operations.

Figure 4-6. Dilation Factor-of-Safety Contours in the Salt After 5 Years of Compressed Air Energy Storage Operations.

Figure 4-7. Shear Failure Factor-of-Safety Contours in the Nonsalt Units at Various Times From Immediately Following Dewatering Through 30 Years at a Wellhead Pressure of 1,150 psi (In-Plane Horizontal In Situ Stress Equals 0.95 Times the Vertical Stress, Out-of-Plane Horizontal In Situ Stress Equals 1.9 Times the Vertical Stress).

Figure 4-8. Shear Failure Factor-of-Safety Contours in the Nonsalt Units at Various Times From Immediately Following Dewatering Through 30 Years at a Wellhead Pressure of 1,150 psi (In-Plane Horizontal In Situ Stress Equals 1.9 Times the Vertical Stress, Out-of-Plane Horizontal In Situ Stress Equals 0.95 Times the Vertical Stress).

4.3 POTENTIAL FOR HYDRAULIC FRACTURE DEVELOPMENT

One of the main concerns with high-frequency pressure cycling in a CAES storage cavern is that the temperature fluctuations caused by the compression and decompression of the air will result in thermally induced tensile fractures perpendicular to the cavern surface. Such fractures in the roof or walls of a CAES cavern could result in instability of the cavern roof or walls or in the loss of air containment.

Figures 4-9 and 4-10 show the effect of pressure cycling on the stresses in the center of the roof during the first week after dewatering the cavern and after 5 years of CAES operations, respectively. With the sign convention of compressive stresses being negative, the normal stress is the negative of the internal cavern pressure and is perpendicular to the cavern surface. The tangential stress is horizontal (i.e., parallel to the cavern surface). As the cavern pressure increases, the temperature increases and both the normal and tangential stresses become more compressive. When the cavern pressure decreases, the opposite is true. This is contrary to the isothermal pressurization or depressurization where the changes in tangential stress are generally in the opposite direction of the normal stress. During the first week of CAES operations, the maximum tangential stress is expected to remain compressive by more than 500 psi. After 5 years, when the temperature fluctuations in the cavern have essentially attained a steady-state value, the tangential stress is expected to remain compressive by about 200 psi.

Figures 4-11 and 4-12 show the maximum principal stress² (the least-compressive or most-tensile stress) contours around the cavern at minimum and maximum pressure for the first cycle after dewatering and after 5 years of CAES operations for the case where the nonsalt units have an in situ stress of 0.95 times the vertical stress. The stresses in the nonsalt units are slightly more compressive for the case where the horizontal stresses in the plane of the model are 1.9 times the vertical stress. After withdrawal to minimum pressure during the first CAES cycle, the stresses in the salt around the cavern are all more than 500 psi in compression. As discussed in the previous section, some of the stresses in the nonsalt units intersecting the cavern are in tension because salt creep drags the nonsalt units toward the cavern. After 5 years of cycling, all of the stresses in the salt remain in compression and, as expected, the regions of tensile stress in the intersecting nonsalt units have increased. It should be noted that the elastic material model used for the nonsalt units does not fail the material in the simulations. In reality, these units will fail when the tensile stresses are larger than the tensile strength. The orientation of these fractures will be vertical and parallel to the cavern surface and thus are not expected to jeopardize cavern stability or air containment. Because all other stresses remain compressive, no development of tensile fractures perpendicular to the cavern surface is expected.

² Compressive stresses are negative.

Figure 4-9. Stresses and Temperature at the Center of the Cavern Roof During the First Week of Compressed Air Energy Storage Operations.

Figure 4-10. Stresses and Temperature at the Center of the Cavern Roof After 5 Years of Compressed Air Energy Storage Operations.

Figure 4-11. Maximum Principal Stress Contours (Compression Negative) Before and After First Withdrawal After Dewatering (In-Plane Horizontal In Situ Stress Equals 0.95 Times the Vertical Stress, Out-of-Plane Horizontal In Situ Stress Equals 1.9 Times the Vertical Stress).

Figure 4-12. Maximum Principal Stress Contours (Compression Negative) Before and After Withdrawal After 5 Years of Compressed Air Energy Storage Operations (In-Plane Horizontal In Situ Stress Equals 0.95 Times the Vertical Stress, Out-of-Plane Horizontal In Situ Stress Equals 1.9 Times the Vertical Stress).

4.4 CAVERN CLOSURE AND CASING STRAIN

Cavern closure occurs because the internal cavern pressure is lower than the stress in the salt surrounding the cavern. This stress difference results in continuous creep movement of the salt toward and into the cavern. The creep closure rate of the cavern during CAES operations will depend mostly on the internal air pressure and the temperature of the surrounding salt. However, because of the transient effects of pressure changes on work hardening and recovery, they will also depend on the pressurization and depressurization rates of the cavern.

Cavern closure was estimated during the 30-year simulation with the wellhead pressure at the minimum value of 1,150 psi. Figure 4-13 shows the estimated closure as a function of time for this simulation. The in situ stress assumption in the nonsalt units has no effect on the predicted cavern closure. Even at the minimum wellhead pressure of 1,150 psi, the predicted cavern closure is small. A total cavern closure of 0.48 percent was predicted after 30 years. The annual closure rate at the end of the 30 years is about 0.004 percent per year. This closure rate is considered quite small for a storage cavern.

RSI-2040-11-038

Figure 4-13. Predicted Cavern Closure Versus Time During 30 Years at a Wellhead Pressure of 1,150 psi.

As a cavern experiences creep closure, the salt flowing into the cavern can drag the casing string toward the cavern, resulting in casing string strain. This stretching of the casing results in axial tensions. Assuming that the salt/cement and cement/casing interfaces remain perfectly

bonded, elongation of the casing will continue until the tensile limit of the casing and/or connection is exceeded, compromising the integrity of the casing.

The steel casing strings were not modeled in this study. However, the predicted strains along the axis of symmetry above the cavern provide a conservative estimate for casing string strains because the salt at this location is free to move vertically in the model in response to cavern closure caused by salt creep. Figure 4-14 shows the predicted vertical strain near the bottom of the casing string. Assuming typical values for the Young's modulus (30×10^6 psi), yield strength (55×10^6 psi), and ultimate strength of steel³ (95×10^6 psi), the casing will begin to yield at a strain of 0.0018 with ultimate failure occurring at 0.0032 strain. As shown in the figure, it is predicted that the casing will begin to yield in about 15 years. However, because the strain rate is so low (about 7 microstrain per year), ultimate failure is not predicted for about 200 years. Based on these estimates, casing strain because of creep closure will not be a problem for the life of the cavern.

³ The yield and ultimate tensile strengths for K-55 grade casing are 55,000 and 95,000 psi, respectively [American Petroleum Institute, 1987].

Figure 4-14. Predicted Vertical Casing Strain During 30 Years at a Wellhead Pressure of 1,150 psi.

5.0 SUMMARY AND CONCLUSIONS

A study was completed to assess the performance of the proposed NYSEG CAES cavern design. The objective of this study was to perform a geomechanical analysis to evaluate cavern stability, cavern closure, and casing strain under the proposed CAES operations. This was achieved through the use of thermomechanical finite element simulations.

Because temperature and salt creep are history dependent, the entire history of the cavern was modeled. The history includes 2 years of cavern development; dewatering of the cavern; and finally, CAES operation using a typical pressure cycle. The typical CAES cycle used in the simulations includes daily injections and withdrawals and operates between wellhead pressures of 1,150 and 1,500 psi. The daily cycle was repeated for 5 years to allow the cavern to nearly reach a steady-state thermal condition. To provide conservative results for creep closure and creep-related factors, including stability of the nonsalts units and casing strain, a 30-year simulation was conducted at the minimum wellhead pressure of 1,150 psi.

Cavern stability was evaluated by examining the stress states in the salt and nonsalt units surrounding the cavern. Stress states that result in extensive salt dilation in the upper portion of the cavern or in shear failure of the nonsalt units overlying the cavern can lead to roof falls, resulting in loss of containment and/or damage to the casing seat or well.

During the first 2 weeks of CAES operations, some salt dilation is predicted in the upper corner of the cavern and also in the floor of the cavern. This is related to the cooling of the salt around the cavern during cavern development, and the dilating stresses dissipate within a couple of weeks as the salt warms up. Throughout the simulation, a small amount of dilation is predicted in the lower portion of the cavern. Although there may be some sloughing of salt in this area, it is not expected to affect stability. Based on these results, salt dilation is not expected to affect cavern stability for the typical CAES cycle that was evaluated.

No shear failure is predicted in the nonsalt units overlying the cavern. In the Camillus Formation and other overlying formations, the factors of safety are greater than 1.5 and do not change significantly with time because the creep closure rate of the cavern is relatively low. Factors of safety in the overlying nonsalt units do not vary significantly with respect to the in situ stress orientation. The thin nonsalt units that intersect the cavern do have regions with factor-of-safety values less than 1 and the extent of the regions increases with time. These regions of failure are the result of tensile stresses that develop because these units will be continually pulled on by the salt as it creeps toward the cavern. As such, the failures are expected to result in vertical tensile fractures parallel to the cavern wall and are not expected to result in cavern instability or provide a pathway for leakage.

One of the main concerns with high-frequency pressure cycling in a CAES storage cavern is that the temperature fluctuations caused by the compression and decompression of the air will result in thermally induced tensile fractures perpendicular to the cavern surface. Such fractures in the roof or walls of a CAES cavern could result in instability of the cavern roof or walls or in the loss of air containment. The stresses in the salt surrounding the cavern remained compressive throughout the 5-year simulation of CAES operations. Thus no thermally induced fractures perpendicular to the cavern surface are expected to develop during CAES operations. As mentioned above, some tensile fracturing of thinner nonsalt units intersecting the cavern is expected but is not expected to result in cavern instability or loss of containment. The extent of these tensile fractures is expected to be larger in the direction of the minimum horizontal in situ stress.

Cavern closure and the associated casing strain were estimated during the 30-year simulation at the minimum wellhead pressure of 1,150 psi. A total cavern closure of about 0.48 percent was predicted over the 30-year simulation. The annual cavern closure rate at the end of the 30-year simulation is about 0.004 percent per year. These closure rates are considered to be quite small for a salt storage cavern. In conjunction with the small closure rates predicted, the predicted casing strain rates are also quite small (about 7 microstrain per year) and are not expected to be a problem for the life of the cavern.

6.0 REFERENCES

American Petroleum Institute, 1987. *API Specifications for Casing, Tubing and Drill Pipe*, API Specification 5A, Thirty-Ninth Edition, American Petroleum Institute, Washington, DC, May 31.

Callahan, G. D., 1981. *Inelastic Thermomechanical Analysis of a Generic Bedded Salt Repository*, ONWI-125, prepared by RE/SPEC Inc., Rapid City, SD, for the Office of Nuclear Waste Isolation, Battelle Memorial Institute, Columbus, OH.

Callahan, G. D., A. F. Fossum, and D. K. Svalstad, 1989. *Documentation of SPECTROM-32: A Finite Element Thermomechanical Stress Analysis Program*, DOE/CH/10378-2, prepared by RE/SPEC Inc., Rapid City, SD, for the U. S. Department of Energy, Chicago Operations Office, Argonne, IL, Vols. I and II.

Carmichael, R. S. (ed.), 1982. *Handbook of Physical Properties of Rocks, Volume II*, CRC Press, Inc., Boca Raton, FL.

Croff, A. G., T. F. Lomenick, R. S. Lowrie, and S. H. Stow, 1985. *Evaluation of Five Sedimentary Rocks Other Than Salt for High-Level Waste Repository Siting Purposes*, prepared for Oak Ridge National Laboratory, Oak Ridge, TN.

DeVries, K. L., 1988. *Viscoplastic Laws for Avery Island Salt*, RSI-0333, prepared by RE/SPEC Inc., Rapid City, SD, for Stone & Webster Engineering Corporation, Boston, MA.

Eyermann T. J., 2011a. *Conceptual Cavern for NYSEG Compressed Air Energy Storage at Watkins Glen, NY*, prepared by PB Energy Storage Services, Inc., Houston, TX (draft).

Eyermann T. J. 2011b. *Overview of Geology of the Area Around the US Salt Watkins Glen Refinery*, prepared for NYSEG, Binghamton, NY, by PB Energy Storage Services, Inc., Houston, TX.

Munson, 1998. *Analysis of Multistage and Other Creep Data for Domal Salts*, SAND98-2276, Sandia National Laboratories, Albuquerque, NM.

Nieland, J. D., 2004. *Salt Cavern Thermal Simulator Version 2.0 User's Manual*, RSI-1760, prepared by RESPEC, Rapid City, SD, for Gas Technology Institute, Chicago, IL.

Nieland, J. D., 2011. *Thermodynamic Evaluation of Proposed New York State Electric & Gas Corporation Compressed Air Energy Storage Cavern Design*, Memorandum RSI(RCO)-2040/9-11/9, prepared by RESPEC, Rapid City, SD, for J. M. McHenry, PB Energy Storage Services, Inc., Houston, TX, September 22.

Osnes, J. D. and T. J. Eyermann, 1996. *Geomechanical Analyses of Compressed Natural Gas Storage in Gallery No. 1, Watkins Glen, New York*, RSI-0670, prepared by RE/SPEC Inc., Rapid City, SD, for PB-KBB Inc., Houston, TX.

Pfeifle, T. W., 1996. *Mechanical Properties of Salt and Dolostone From Akzo Nobel Salt Inc. Well No. 58 and NYSEG Well No. 59, Seneca Lake Storage Project, Watkins Glen, New York*, RSI-0668, prepared by RE/SPEC Inc., Rapid City, SD, for PB-KBB, Houston, TX.

Senseny, P. E., F. D. Hansen, J. E. Russell, N. L. Carter, and J. W. Handin, 1992. “Mechanical Behaviour of Rock Salt: Phenomenology and Micromechanisms,” *International Journal of Rock Mechanics and Mining Sciences & Geomechanics Abstracts*, Vol. 29, No. 4, pp. 363–378.

Starling, K. E. and J. L. Savidge, 1994. *Compressibility of Natural Gas and Other Related Hydrocarbon Gases*, Report No. 8, 2nd Edition, Catalog No. XQ9212, prepared for American Gas Association.

Svalstad, D. K., 1989. *Documentation of SPECTROM-41: A Finite Element Heat Transfer Analysis Program*, DOE/CH/10378-1, prepared by RE/SPEC Inc., Rapid City, SD, for the U.S. Department of Energy, Chicago Operations Office, Argonne, IL.

WorleyParsons Group, Inc., 2011. Electronic communication between M. C. Holdridge, WorleyParsons Group, Inc., Reading, PA, and J. L. Ratigan, PB Energy Storage Services, Inc., Houston, TX, August 11.

Van Sambeek, L. L., J. L. Ratigan, and F. D. Hansen, 1993. “Dilatancy of Rock Salt in Laboratory Tests,” *Proceedings, 34th U.S. Symposium on Rock Mechanics*, University of Wisconsin–Madison, Madison, WI, June 27–30, B. C. Haimson (ed.), *International Journal of Rock Mechanics and Mining Sciences & Geomechanics Abstracts*, Pergamon Press, Vol. 30, No. 7, pp. 735–738.

APPENDIX A

THERMODYNAMICS MEMORANDUM

APPENDIX B

MECHANICAL ROCK PROPERTIES TESTS

APPENDIX B

MECHANICAL ROCK PROPERTIES TESTS

There are four types of mechanical properties tests generally used for characterization of the strength and deformational behavior of salt and nonsalt rocks. These tests are schematically illustrated in Figures B-1 and B-2. The four test types are the (1) quasi-static compression test, (2) constant mean stress test, (3) Brazilian indirect tension test, and (4) confined creep test. Each of these tests is performed in our laboratory to standards that meet or exceed all applicable American Society for Testing and Materials (ASTM) or International Society of Rock Mechanics (ISRM) specifications. Because of the relatively large grain size of most salts, the cylindrical test specimens need to have a minimum diameter of 4 inches. Nonsalt rocks generally have a smaller grain size and smaller test specimens can be used. The quasi-static compression test, constant mean stress test, and confined creep test are performed on specimens that have a length-to-diameter ratio (L:D) of at least 2, while the L:D of the indirect tension specimens is 0.5. Each of the four test types is briefly described below.

B.1 QUASI-STATIC COMPRESSION TEST

The quasi-static compression test is shown in Figure B-1(a). The test is used to determine (1) the compressive strength; (2) Young's modulus, E ; and (3) Poisson's ratio, ν . For nonsalt rocks, the strength data from these tests are used to determine a Mohr-Coulomb strength model (cohesion and friction angle), which is then used in modeling to determine factors of safety with respect to shear strength. A variation of the quasi-static compression test in which the confining pressure is zero is typically known as the unconfined compression test. The unconfined strength is used as an index property for comparisons between rock types and for examining variations in the same rock type recovered from different locations. The deformation properties (Young's modulus and Poisson's ratio) are used directly in modeling and design of underground structures.

B.2 CONSTANT MEAN STRESS TEST

The constant mean stress (CMS) test (Figure B-1(b)) is also a variation of the confined quasi-static compression test and is used to characterize the dilational behavior of the salt. In this test, a hydrostatic stress or uniform pressure is applied to all surfaces of the specimen. Then, the axial stress (σ_a) is increased/decreased and the confining pressure (σ_c) is simultaneously decreased/increased in a manner that maintains the mean stress ($\sigma_m - (\sigma_a + 2\sigma_c)/3$) constant. The volumetric strain is monitored during the test and is used to determine the stress state that induces salt dilation (volume expansion caused by microfracturing). Not shown in Figure B-1(b) is the small stress difference applied at the initial hydrostatic confining pressure to obtain data

(a) QUASI-STATIC COMPRESSION

(b) CONSTANT MEAN STRESS COMPRESSION

Figure B-1. Schematic Illustration of (a) Confined Quasi-Static Compression Test and (b) Constant Mean Stress Test.

(a) BRAZILIAN INDIRECT TENSION

(b) CREEP

Figure B-2. Schematic Illustration of (a) Brazilian Indirect Tension Test and (b) Creep Test.

for estimating elastic constants (E and ν) under confined conditions. This is an inexpensive approach to obtaining elastic constants from nearly every specimen that gets tested.

RESPEC has developed and used two different load paths to complete CMS tests. The stress state in the conventional CMS test is generally termed triaxial compression (CMC), and the test is performed by simultaneously increasing the axial stress and decreasing the confining pressure. An alternative load path imposes a state of stress termed triaxial extension (CMX), and the test is performed by simultaneously decreasing the axial stress and increasing the confining pressure. Both the CMC and CMX tests impose the same difference between the maximum and minimum compressive principal stresses, but the intermediate principal stress is different between the two tests. In the CMC test, the intermediate principal stress equals the minimum compressive principal stress, while in the CMX test, the intermediate principal stress equals the maximum compressive principal stress. Dilational strength observed in CMX tests can be significantly lower than the dilation strength observed in CMC tests.

The dilational characteristics of the salt are used directly in the design of caverns in salt. Because the intermediate principal stresses around a cavern can range from a state of triaxial compression to a state of triaxial extension, both CMC and CMX constant mean stress tests are useful for establishing dilation criteria that are used for determining the minimum pressure in the cavern.

B.3 BRAZILIAN INDIRECT TENSION TEST

The Brazilian indirect tension test (Figure B-2(a)) is used to determine the apparent tensile strength of rocks. While the tensile strength is not generally used directly in any analysis (other than when damage accumulation or fracture is of concern), it is a useful measure for comparisons between rock types and for comparing variations in rock strength from one location to another. If tensile stresses are generated in an underground structural model, the apparent tensile strength can be used to estimate the propensity for rock tensile failure. The apparent tensile strength can also be used to estimate the intercept (dilation limit at zero mean stress) for the salt dilation criterion.

B.4 CONFINED CREEP TEST

The creep test (Figure B-2(b)) is used to determine the deformation of salt that occurs through time when a constant stress difference (axial stress minus confining pressure) is applied to the specimen. Although the test may be performed confined or unconfined, it is usually performed with confining pressure. Creep is the principal deformation mechanism in salt surrounding a storage cavern and leads to the closure or volume reduction of the cavern with time. Brittle (cracking) deformation mechanisms are suppressed when the test is “confined;” that is, when a pressure is applied to the external surface of the salt core being

tested. This test is useful for comparing different salts, for comparing variations in salt response from one location to another, and for numerical modeling of salt excavations. Salt creep is very dependent on the stress difference applied to the core specimen and the applied temperature. Typically, tests with at least three different stress differences are necessary to characterize the creep response of a particular salt.

WELL CASING AND TUBULARS WATKINS GLEN CAES

Revision 1

Watkins Glen, New York

Prepared for

NYSEG

Binghamton, NY

Prepared by

James McHenry

PB ENERGY STORAGE SERVICES, INC.

Houston, TX

**Project No. 50756B
November 2011**

TABLE OF CONTENTS

SECTION	PAGE
1 INTRODUCTION	4
2 CASING SELECTION RATIONALE	4
2.1 Brine String Selection	4
2.1.1 Brine String Hydraulic Calculations	4
2.2 Production Liner Selection	6
2.2.1 Production Liner Hydraulics	7
2.3 Cemented Casing Selection	8
3 CASING PERFORMANCE	8
4 REFERENCES	9

LIST OF FIGURES

SECTION	PAGE
Figure 1 - Water Injection Pressure Direct Circulation	5
Figure 2 - Raw Water Pressure - Reverse Circulation	6
Figure 3 - Casing Program Cavern No. 1 - Leaching Configuration	11
Figure 4 - Casing Program Cavern No. 2 / 3 - Leaching Configuration	12
Figure 5 – Casing Program Cavern 1 - Storage Configuration	14
Figure 6 - Casing Program Caverns 2 & 3 - Storage Configuration	15
Figure 7 - Conductor Pipe Calculations Cavern No. 1	16
Figure 8 - Surface Casing Calculations Cavern No. 1	17
Figure 9 - Production Casing Calculations Cavern No. 1	18

Figure 10 - Outer Leach String Calculations Cavern No. 1	19
Figure 11 - Inner Leach String Calculations Cavern No. 1.....	20
Figure 12 - Stainless Steel Production Liner Calculations Cavern No. 1	21
Figure 13 - Conductor Pipe Calculations Caverns No. 2 & 3.....	22
Figure 14 - Surface Casing Calculations Caverns No. 2 & 3.....	23
Figure 15 - Production Casing Calculations Caverns No. 2 & 3	24
Figure 16 - Outer Leach String Calculations Caverns No. 2 & 3	25
Figure 17 - Inner Leach String Calculations Caverns No. 2 & 3.....	26
Figure 18 - Stainless Steel Production Liner Calculations Caverns No. 2 & 3	27

LIST OF TABLES

TABLE	PAGE
Table 1 - Calculation Input Assumptions.....	5
Table 2 - Calculated Pressures (Direct and Reverse Circulation).....	6
Table 3 - Slip Crushing Calculation Well No. 1	28
Table 4 - Slip Crushing Calculation Well Nos. 2 & 3	29

1 INTRODUCTION

NYSEG has proposed to build a 170 MW CAES peak shaving facility on property owned by Inergy near Watkins Glen, NY. The maximum design air flow rate required is approximately 639 lb/sec during compression. Inergy will develop the required cavern space, provide water, and dispose of brine to the Watkins Glen brinefield. Inergy will provide water at a rate of 350 gpm for development of the cavern.

To meet the anticipated electrical duty cycle approximately 3 MMB (million barrels) of dewatered cavern volume will be required.¹ Based upon a review of local geology² a preliminary cavern development program³ was developed which indicated that three nominal 1 MMB caverns would be required. NYSEG directed PB ESS to develop casing specifications which will allow an air flow rate of 639 lb/sec for the first cavern and 320 lb/s for Caverns 2 and 3.

2 CASING SELECTION RATIONALE

2.1 BRINE STRING SELECTION

The inner leach string for NYSEG was sized to accommodate a modern sonar surveying tool. Modern sonar tools require a tubular with a minimum inside diameter of 4 inches. The minimum acceptable size for the inner solution mining string is 5.5 inch OD. A 5.5 inch diameter, 15.5 lb/ft, API J-55 tubular was selected for the inner string. Coupling diameters for the inner string require that the outside solution mining string no smaller than 7 inches. PB ESS selected an API 8-5/8 inch, 32 lb/ft, J-55 well casing for the outer solution mining casing to equalize velocities in both the inner string and the annulus.

2.1.1 Brine String Hydraulic Calculations

Hydraulic calculations across the wellbore were performed using a workbook specifically designed by PB ESS for solution mining calculations. Friction loss estimates are performed using the Darcy method, using the Colebrook Transition formula. Input parameters for calculations are given in Table 1.

Figure 1 (direct circulation) and Figure 2 (reverse circulation) show the wellhead water pressure for friction factor ratios ranging from 1 to 10 times the calculated friction factor. Typical wellbore performance is consistent with a friction factor ratio of about 4. Calculated pressures for a friction factor ratio of 4, and flow rates ranging from 100 gpm to 900 gpm are given in Table 2. As can be seen, the wellhead water pressure expected is 421 psi (assuming that the outlet pressure from the well is 50 psi) and the blanket pressure at the start of solution mining is 1,307 psi while circulating in direct mode. The calculated water pressure in reverse mode is 420 psi and the blanket pressure is 1,289 psi.

Table 1 - Calculation Input Assumptions

1.0 INPUT	Raw water roughness - 1 x brine roughness		10/24/11
PROJECT:	NYSEG - Seneca Lake CAES Cavern 1		9:19:19
	0		
Qmin	100 gpm	minimum flow rate	
dQ	50 gpm	delta flow rate	
pprod	50 psi	brine production pressure	Assumes saturation by injection into second cavern.
di	4.825 in	inner diameter (inner pipe)	5.5" 15.5#/ft J-55 Collapse = 4040 psi & Yield = 4810 psi
do	5.500 in	outer diameter (inner pipe)	
dco	6.050 in	inner pipe coupling outer diameter	
cl	0.667 ft	inner pipe coupling length	
jl	40.000 ft	inner pipe joint length	
li	2.630 ft	length of inner pipe	
nj	64 -	number of couplings	
Di	7.921 in	inner diameter (outer pipe)	8.625" 32#/ft J-55 Collapse = 2530 psi & Burst = 3930 psi
lo	2.530 ft	length of outer pipe	
lcs	2.360 ft	length of final cemented casing	
lpad	2.520 ft	depth of pad	
epsbr	0.018 in	roughness of pipe (brine side)	
epsrw	0.018 in	roughness of pipe (raw water side)	
peff	0.75 -	pump & motor efficiency	
temp	51 F	average raw water / brine temperature	
gravrw	1.000 -	specific gravity (raw water)	
	0.000 %	salinity (raw water)	
etarw	1.130 cP	dynamic viscosity (raw water)	
gravbr	1.198 -	specific gravity (brine)	
	97.242 %	salinity (brine)	
etabr	1.600 cP	dynamic viscosity (brine)	
gravpad	-	specific gravity (pad) or Gas Constant if Nitrogen	Nitrogen R=55.16 ft lb/lbm/R
grad	0.700 psi/ft	permissible pressure gradient at casing shoe	
equiv. dia.	1	$0 = (Di-do)/CF$ and $1 = (Di-do)$	

RAW WATER INJECTION PRESSURE - DIRECT LEACHING
Raw Water Roughness from 1x to 10x Brine Roughness

Figure 1 - Water Injection Pressure Direct Circulation

Figure 2 - Raw Water Pressure - Reverse Circulation

Table 2 - Calculated Pressures (Direct and Reverse Circulation)

Raw Water		Brine		Direct Leaching				Reverse Leaching				p cs max (psi)	pprod (psi)
Q rw (gpm)	Q rw (bpd)	Q br (gpm)	Q br (bpd)	p rw (psi)	p pad (psi)	p cs (psi)	Pump (bhp)	p rw (psi)	p pad (psi)	p cs (psi)	Pump (bhp)		
100	3,429	96	3,304	288	1,246	1,355	22	280	1,245	1,354	22	1,652	50
150	5,143	145	4,956	303	1,253	1,363	35	295	1,250	1,359	34	1,652	50
200	6,857	193	6,607	324	1,263	1,373	50	317	1,257	1,367	49	1,652	50
250	8,571	241	8,259	350	1,275	1,386	68	345	1,266	1,376	67	1,652	50
300	10,286	289	9,911	383	1,290	1,402	89	380	1,276	1,388	89	1,652	50
350	12,000	337	11,563	421	1,307	1,421	115	420	1,289	1,402	114	1,652	50
400	13,714	385	13,215	465	1,327	1,443	145	467	1,304	1,418	145	1,652	50
450	15,429	434	14,867	515	1,350	1,468	180	519	1,320	1,435	182	1,652	50
500	17,143	482	16,518	571	1,375	1,495	222	578	1,339	1,455	225	1,652	50
550	18,857	530	18,170	632	1,403	1,525	271	643	1,359	1,477	275	1,652	50
600	20,571	578	19,822	700	1,433	1,558	327	714	1,381	1,502	333	1,652	50
650	22,286	626	21,474	773	1,466	1,594	391	792	1,405	1,528	400	1,652	50
700	24,000	675	23,126	852	1,502	1,633	464	875	1,431	1,556	477	1,652	50
750	25,714	723	24,778	936	1,540	1,675	546	965	1,459	1,587	563	1,652	50
800	27,429	771	26,429	1,027	1,581	1,719	639	1,061	1,489	1,619	660	1,652	50
850	29,143	819	28,081	1,123	1,625	1,767	743	1,163	1,521	1,654	769	1,652	50
900	30,857	867	29,733	1,225	1,671	1,817	858	1,271	1,555	1,690	890	1,652	50

2.2 PRODUCTION LINER SELECTION

Carbon steel undergoes rapid corrosion in the presence of air and water. Huntorf, the site of the first commercial CAES facility in Germany, was initially built with carbon steel, however, severe corrosion took place within the first few months of operation⁴ and a fiberglass liner was installed to protect the carbon steel cemented casing string. Crotofino⁴ reported that the fiberglass casing liner used at Huntorf began exhibiting failure after approximately 20 years of operation. McIntosh, the site of the only commercial CAES facility in the US, was originally

designed to use fiberglass casing liners. The cavern was ultimately built using a 316L stainless steel casing liner suspended from the surface. Due to the high corrosion potential for this project PB ESS recommends the use of a corrosion resistant alloy or a fiberglass casing liner for the NYSEG CAES cavern.

The liner is designed to be suspended from a wellhead casing hanger to a depth approximately 5 feet below the cavern roof. A continuous flow of dry air or nitrogen will be injected down the annulus between the liner and the production casing to limit corrosion of the cemented casing. The liner is not equipped with a downhole packer to isolate the interval between the liner and the cemented casing. Due to the low collapse resistance of the liner and the pressure changes in the well during operation a packed off liner interval would be subject to collapse.

Fiberglass well casing with an outside diameter of 20" (largest diameter located)⁵ has a coupling diameter of 30" and an axial tension rating of 245,000 lb, or 136,000 lb using the design factors given in API-6A. The pipe weight suspended from the hanger liner would be 178,000 lb, which exceeds the recommended axial tension rating of the pipe. Further, the coupling diameter would require increasing the hole size to a minimum of 36", with consequent increases in drilling and casing costs. The 36" cemented casing would require wall thickness of greater than 1.5" in the salt section of the hole to prevent collapse, which in our experience is not possible to weld on the rig floor.

Stainless steel was used for a production liner in CAES service at both Huntorf and McIntosh. No definitive information on the corrosion levels of the stainless steel tubulars in CAES service has been located during our review of appropriate materials. The most commonly available stainless steel exhibiting corrosion resistance to salt water and marine environments is Type 316 stainless steel.⁶ Type 316L stainless steel is an extra low carbon version of Type 316 which was developed for improved weldability.⁷

PB ESS recommends that stainless steel be used for the production liner since erosion velocities in CAES service are high and the potential for severe corrosion exists. Due to its corrosion resistant properties, high erosion resistance⁸, use at McIntosh and Huntorf, high strength, and weldability PB ESS recommends that a suspended liner fabricated from 316L stainless steel be used by NYSEG at Watkins Glen.

2.2.1 Production Liner Hydraulics

The Salt Cavern Thermal Simulator (SCTS)⁹ was used to determine the size of the air production liner. The analyses performed are thoroughly described in the Thermodynamic Evaluation Report.¹ Casing diameter was modeled to determine the air velocity, relative to erosion velocity limits recommended in API-14E¹⁰. The results of this assessment were that air erosion velocity is not the limiting factor in selecting the liner diameter for this application.

Friction loss due to airflow was simulated for casing diameters between 6.6 in. and 24 in. Friction loss in the liner affects the working gas volume of a storage cavern. The higher the friction loss, the lower the working gas volume of the cavern is, and the larger the amount of gas that must be left in the cavern once the minimum operating pressure is reached. The SCTS

analyses indicated that a liner diameter of 20” would be required for 639 lb/s flow rate and 16” liner diameter would be required for a flow rate of 320 lb/s.

2.3 CEMENTED CASING SELECTION

Generally, cemented casing for bedded salt caverns includes conductor pipe, surface casing, and the final cemented casing. This philosophy is used for the NYSEG casing program.

The outermost well casing is the conductor casing. Conductor casing is a short string of pipe (175’ in this case) that provides a channel for the flow of drilling fluids, provides a secure attachment point for blowout prevention equipment during drilling of the surface hole, and prevents washout from occurring under the base of the drilling rig. For all wells a 42” steel conductor pipe was selected.

Inside the conductor casing is the surface casing. The surface casing protects the upper formations from possible contamination by salt saturated drilling and completion fluids. At Watkins Glen there are no significant fresh water aquifers¹¹, with bedrock encountered no deeper than 157 feet below ground surface. A significant review of groundwater resources was done during 1995 as a part of permitting the Akzo Gallery No. 1 for natural gas storage. Consequently, protection of groundwater can be accomplished by isolating the surface sediments and the Genesee formation. Based upon the anticipated geology of the cavern location a depth of approximately 850 ft is suggested. To provide adequate surface for cementing a 24” OD steel production casing inside a 30” OD steel casing was selected for the surface pipe for Cavern No. 1 and 26” OD steel casing for the surface pipe for caverns 2 & 3.

Inside the surface casing is the production casing. The purpose of the production casing is to provide a positive seal, anchored in relatively impermeable salt, for air storage. In bedded salt it is commonly not possible, or necessary, to place two final casing strings into salt. The final cemented casing depth was selected based upon site geology and the nominal depth for the 24” production casing is 2,360 ft below ground level. Since the cavern roof is planned for 2,402 ft and the top of salt is projected to be at 2,352 ft the shoe was placed just into the Syracuse Salt to allow development of the cavern to the largest reasonable volume.

Figure 3 shows the proposed casing program for Cavern No. 1, while the program for Caverns 2 & 3 is provided in Figure 4. These figures show the well in leaching configuration. Figures 5 and 6 show the casings in storage configuration (with the stainless steel liner in place).

3 CASING PERFORMANCE

PB ESS evaluates casing performance in accordance with API 5C3¹⁰ to determine the appropriate wall thickness. All casing strings were evaluated for collapse, pipe body yield, joint strength (where applicable) and internal pressure resistance. All cemented casings are cemented to the surface. Casing grades and thicknesses were selected to obtain an economic casing program. Usually, a lower grade or thin walled casing costs less than a higher grade or thick

walled casing. Consequently, the most economic program is achieved by selecting lower grade, thinner walled casing, and taking into account relative availability.

Figures 7- 12 provide basic casing program calculations for the casing proposed for Well No. 1 while Figures 13-19 provide program calculations for Wells No. 2 & 3, respectively.

Selection of the Stainless Steel Liners required an additional consideration. When installing casing, slips are commonly used to hold the casing while another section is being welded in place. On thin tubulars and on very deep completions the slips can crush the tubing. PB ESS used a method used for deep water landing design¹² to determine minimum thickness for the stainless steel hanging strings. Calculations based on this technique are provided in Table 3 and 4, respectively for Wells 1 and 2 & 3.

4 REFERENCES

1. Nieland, Joel, External Memorandum, *Thermodynamic Evaluation of Proposed New York State Electric & Gas Corporation Compressed Air Energy Storage Cavern Design*, RESPEC Inc, September 14, 2011.
2. Eyermann, Thomas, *Overview of Geology of the Area Around the US Salt Watkins Glen Refinery*, PB ESS, 2011.
3. Eyermann, Thomas, *Conceptual Cavern For NYSEG Compressed Storage at Watkins Glen*, NY, PB ESS 2011.
4. Crotogino, Fritz, *Huntorf CAES: More Than 20 Years of Successful Operation*, KBB Inc, Solution Mining Research Institute April 2001.
5. Future Pipe Industries. *High Pressure Epoxy Pipe Systems*. 2007.
6. American Society for Metals. *ASM Metals Reference Book*. 1983.
7. AK Steel. *Product Data Bulletin 316/316L Stainless Steel*. 2007.
8. Salama and Ventatesh. *Evaluation of API RP 14E Erosion Velocity Limitations for Offshore Gas Wells*. OTC 4485. Offshore Technology Conference. 1983.
9. Nieland, J. D., 2002, *Salt Cavern Thermal Simulator Version 1.5 User's Manual*, Revision 1, RSI-1650, prepared by RESPEC, Rapid City, SD, for Gas Technology Institute, Chicago, IL.
10. American Petroleum Institute, API Recommended Practice 14E, *Recommended Practice for Design and Installation of Offshore Production Platform Piping Systems*, March 2007.
11. Russell, Bruce, *Ground Water Review – Akzo Cavern Gallery No. 1*, Fenix and Scisson, July 1995.
12. American Petroleum Institute, *Bulletin on Formulas and Calculations for Casing, Tubing, Drill Pipe, and Line Pipe*, 1994.

13. Adams, Richard J., *Deepwater Landing String Design*, American Association of Drilling Engineers, AADE 01-NC-HO-05, 2001.

Figure 3 - Casing Program Cavern No. 1 - Leaching Configuration

Figure 4 - Casing Program Cavern No. 2 / 3 - Leaching Configuration

Figure 5 – Casing Program Cavern 1 - Storage Configuration

Figure 6 - Casing Program Caverns 2 & 3 - Storage Configuration

Figure 7 - Conductor Pipe Calculations Cavern No. 1

Figure 8 - Surface Casing Calculations Cavern No. 1

Figure 9 - Production Casing Calculations Cavern No. 1

Figure 10 - Outer Leach String Calculations Cavern No. 1

Figure 11 - Inner Leach String Calculations Cavern No. 1

Figure 12 - Stainless Steel Production Liner Calculations Cavern No. 1

Figure 13 - Conductor Pipe Calculations Caverns No. 2 & 3

Figure 14 - Surface Casing Calculations Caverns No. 2 & 3

Figure 15 - Production Casing Calculations Caverns No. 2 & 3

Figure 16 - Outer Leach String Calculations Caverns No. 2 & 3

Figure 17 - Inner Leach String Calculations Caverns No. 2 & 3

Figure 18 - Stainless Steel Production Liner Calculations Caverns No. 2 & 3

Table 3 - Slip Crushing Calculation Well No. 1

Outer Diameter (in)	20
String Length	2402
Inside Diameter (in)	19.25
Minimum Yield Strength (psi)	42000
Length of Slips (in)	16
Taper of Slips (degrees)	9.4625
Coefficient of Friction (slips to bowl)	0.08
API Tensile Design Factor	1.25
Cross Sectional Area (in ²)	23.12
Tensile Capacity (lb)	776,837
Tan ⁻¹ (m)	4.5739
Transverse Load Factor	4.00
Hoop Stress to Tensile Ratio	3.12
Maximum Allowable Tensile Load	248,790
String Weight	186,596
Available For Dynamic Loading	<u>62,193</u>

Table 4 - Slip Crushing Calculation Well Nos. 2 & 3

Outer Diameter (in)	16
String Length	2402
Inside Diameter (in)	15.25
Minimum Yield Strength (psi)	42000
Length of Slips (in)	16
Taper of Slips (degrees)	9.4625
Coefficient of Friction (slips to bowl)	0.08
API Tensile Design Factor	1.25
Cross Sectional Area (in ²)	18.41
Tensile Capacity (lb)	618,501
Tan ⁻¹ (m)	4.5739
Transverse Load Factor	4.00
Hoop Stress to Tensile Ratio	2.65
Maximum Allowable Tensile Load	233,774
String Weight	148,564
Available For Dynamic Loading	<u>85,210</u>

**NYSEG
SENECA LAKE CAES
PROPOSED NEW LEACHING WELLHEAD
CAVERN No.1**

Number

Date 11/11

Page 1 of 3

Section A

1. Casing Head – 30” API 2M x 30” SOW with bowl prep for slips (24”). Complete with (2) 2” LP Taps below Seal location. API 6A - Class CC, Temp U, PSL - 1, PR - 1
2. Slip & Seal assembly for 24” casing.
3. Bull Plug – 2-1/16” 2M LP w/1/2” NPT Tap.
4. Bull Plug – 2-1/16” 2M LP, Solid.

Section B

1. Double Studded Adapter – 30” API 2M x 20-3/4” API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class DD, Temp U, PSL - 1, PR - 1
2. Casing Spool – 20-3/4”, API 3M Bottom Flange (w/Double “P”-Seal for 24” casing) x 20-3/4” API 3M Top, w/ (2) 4”, API 3M, Extended Flanged Side Outlets. Top complete with Bowl for Mandrel to hang 8-5/8” OD Brine Casing, Lockscrews and Stuffing Boxes. API 6A – Class DD, Temp U, PSL – 1, PR – 1.
3. Mandrel Hanger w/ Extended Neck: 8-5/8” LT&C Threads (Top and Bottom). API 6A - Class DD, Temp U, PSL - 1, PR - 1.
4. Blind Flange. (1) API 3M, 4-1/16” w/1/2” NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
5. Ball Valve - (2) 4” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

Section C

1. Casing Spool – 20-3/4” API 3M Bottom Flange x 13-5/8” API 3M Top, w/(2) 4”, API 3M, Extended Flanged Side Outlets. Top complete with Bowl for Mandrel to hang 5 1/2” OD Brine Casing, Lockscrews and Stuffing Boxes. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
2. Mandrel Hanger w/ Extended Neck: 5-1/2”, LT&C Threads (Top and Bottom). API 6A – Class DD, Temp U, PSL - 1, PR - 1.
3. Ball Valve – (2) 4” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

PREPARED BY JMc	DATE 11/11/11	CHECKED BY MM	DATE 11/11/11	APPROVED BY JMc	DATE 11/11/11	REVISION 0	DATE
--------------------	------------------	------------------	------------------	--------------------	------------------	---------------	------

NYSEG
SENECA LAKE CAES
PROPOSED NEW LEACHING WELLHEAD
CAVERN No.1

Number

Date 11/11

Page 2 of 3

Section D

1. Casing Spool - 13-5/8", API 3M x 7-1/16" API 3M w/ (2) 4" API 3M Extended Flanged Side Outlets. API 6A – Class DD, Temp U, PSL - 1, PR - 1.(Bottom Flange w/Double "P"-Seal Sized for 5 1/2" Extended Neck Mandrel Hanger, Pos. B-2)
2. Ball Valve – (2) 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

Section E

1. Crown Valve – 6" ANSI 900 Flanged, Full Opening, Manual Operated. Ball Valve for Fresh Water, Brine, and Nitrogen Service.
2. Double Studded Adapter – 7-1/16" API 3M x 4-1/16" API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. API 6A – Class AA, Temp U, PSL - 1, PR - 1
3. Ball Valve – 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.
4. Blind Flange. API 3M, 4-1/16" w/1/2" NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.

Accessories

1. All required studs, nuts, ring gaskets and flange protectors for connecting the spools and valves to the spools.
 - ASTM A193 Grade B7 bolts, ASTM A194 2H nuts, Teflon coated.
 - All ring gaskets stainless steel.

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
JMc	11/11/11	MM	11/11/11	JMc	11/11/11	0

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

NYSEG
SENECA LAKE CAES
PROPOSED NEW LEACHING WELLHEAD
CAVERN No.1

Number

Date 11/11

Page 3 of 3

PREPARED BY
JMc

DATE
11/11/11

CHECKED BY
MM

DATE
11/11/11

APPROVED BY
JMc

DATE
11/11/11

REVISION
0

DATE

NYSEG
SENECA LAKE CAES
PROPOSED NEW LEACHING WELLHEAD
CAVERN No. 2 & 3

Number

Date 11/11

Page 1 of 3

Section A

1. Casing Head – 26-3/4” API 2M x 26” SOW with bowl prep for slips (20”). Complete with (2) 2” LP Taps below Seal location. API 6A - Class CC, Temp U, PSL - 1, PR - 1
2. Slip & Seal assembly for 20” casing.
3. 8 ft. section of 20”, 0.75 WT, API 5LX-56 pipe welded and tested to casing head.
4. Bull Plug – 2-1/16” 2M LP w/1/2” NPT Tap.
5. Bull Plug – 2-1/16” 2M LP, Solid.

Section B

1. Double Studded Adapter – 26-3/4” API 2M x 20-3/4” API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class CC, Temp U, PSL - 1, PR - 1
2. Casing Spool – 20-3/4”, API 3M Bottom Flange (w/Double “P”-Seal for 20” casing) x 16-3/4” API 3M Top, w/ (2) 4”, API 3M, Extended Flanged Side Outlets. Top complete with Bowl for Mandrel to hang 8-5/8” OD Brine Casing, Lockscrews and Stuffing Boxes. API 6A – Class DD, Temp U, PSL – 1, PR – 1.
3. Mandrel Hanger w/ Extended Neck: 8-5/8” LT&C Threads (Top and Bottom). API 6A - Class DD, Temp U, PSL - 1, PR - 1.
4. Blind Flange. (1) API 3M, 4-1/16” w/1/2” NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
5. Ball Valve - (2) 4” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

Section C

1. Casing Spool – 16-3/4” API 3M Bottom Flange x 13-5/8” API 3M Top, w/(2) 4”, API 3M, Extended Flanged Side Outlets. Top complete with Bowl for Mandrel to hang 5 1/2” OD Brine Casing, Lockscrews and Stuffing Boxes. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
2. Mandrel Hanger w/ Extended Neck: 5-1/2”, LT&C Threads (Top and Bottom). API 6A – Class DD, Temp U, PSL - 1, PR - 1.
3. Ball Valve – (2) 4” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

PREPARED BY
JMc

DATE
11/11/11

CHECKED BY
MM

DATE
11/11/11

APPROVED BY
JMc

DATE
11/11/11

REVISION
0

DATE

NYSEG
SENECA LAKE CAES
PROPOSED NEW LEACHING WELLHEAD
CAVERN No. 2 & 3

Number

Date 11/11

Page 2 of 3

Section D

1. Casing Spool - 13-5/8", API 3M x 7-1/16" API 3M w/ (2) 4" API 3M Extended Flanged Side Outlets. API 6A – Class DD, Temp U, PSL - 1, PR - 1.(Bottom Flange w/Double "P"-Seal Sized for 5 1/2" Extended Neck Mandrel Hanger, Pos. B-2)
2. Ball Valve – (2) 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

Section E

1. Crown Valve – 6" ANSI 900 Flanged, Full Opening, Manual Operated. Ball Valve for Fresh Water, Brine, and Nitrogen Service.
2. Double Studded Adapter – 7-1/16" API 3M x 4-1/16" API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class DD, Temp U, PSL - 1, PR - 1
3. Ball Valve – 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.
4. Blind Flange. API 3M, 7-1/16" w/1/2" NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.

Accessories

1. All required studs, nuts, ring gaskets and flange protectors for connecting the spools and valves to the spools.
 - ASTM A193 Grade B7 bolts, ASTM A194 2H nuts, Teflon coated.
 - All ring gaskets stainless steel.

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
JMc	11/11/11	MM	11/11/11	JMc	11/11/11	0

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

NYSEG
SENECA LAKE CAES
PROPOSED NEW LEACHING WELLHEAD
CAVERN No. 2 & 3

Number

Date 11/11

Page 3 of 3

PREPARED BY
JMc

DATE
11/11/11

CHECKED BY
MM

DATE
11/11/11

APPROVED BY
JMc

DATE
11/11/11

REVISION
0

DATE

**NYSEG
SENECA LAKE CAES
PROPOSED NEW DEWATERING WELLHEAD
CAVERN No. 1**

Number 50756B

Date 10/11

Page 1 of 3

Section A

Existing

Section B

1. Double Studded Adapter – 30” API 2M x 20-3/4” API 3M (w/Double “P”-Seal for 24” casing), Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class CC, Temp U, PSL - 1, PR - 1.
2. Casing Spool – 20-3/4”, API 3M Bottom Flange x 20-3/4” API 3M Top, w/ (2) 4”, API 3M, Extended Flanged Side Outlets. Top complete with Bowl for Mandrel to hang 20” OD Stainless Steel Casing, Lockscrews and Stuffing Boxes. API 6A – Class CC, Temp U, PSL - 1, PR - 1.
3. Mandrel Hanger w/ Extended Neck: 5’ Section 20” 316L 3/8” WT Welded to bottom and 20” LT&C Threads (Top). API 6A - Class DD, Temp U, PSL - 1, PR - 1.
4. Blind Flange. API 3M, 4-1/16” w/1/2” NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
5. Ball Valve (2) - 4” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

Section C

1. Master Ball Valve – 20”, ANSI 900 RTJ Flange, Seats and Ball 316 SST or CF8M SST, Full Internal 316 SST body overlay.

Section D

1. Casing Spool – 20-3/4” API 3M Bottom Flange x 13-5/8” API 3M Top, w / (2) 4”, API 3M, Extended Flanged Side Outlets. Top complete with Bowl for Mandrel to hang 5 1/2” OD Brine Casing, Lockscrews and Stuffing Boxes. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
2. Mandrel Hanger w/ Extended Neck: 5-1/2”, LT&C Threads (Top and Bottom). API 6A – Class DD, Temp U, PSL - 1, PR - 1.
3. Blind Flange. API 3M, 4-1/16” w/1/2” NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
4. Ball Valve (2) - 4” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

PREPARED BY JMc	DATE 11/11/11	CHECKED BY MM	DATE 11/11/11	APPROVED BY JMc	DATE 11/11/11	REVISION 0	DATE
--------------------	------------------	------------------	------------------	--------------------	------------------	---------------	------

**NYSEG
SENECA LAKE CAES
PROPOSED NEW DEWATERING WELLHEAD
CAVERN No. 1**

Number	50756B
Date	10/11
Page	2 of 3

Section E

1. Casing Spool - 13-5/8", API 3M x 7-1/16" API 3M w/ (2) 4" API 3M Extended Flanged Side Outlets. API 6A – Class DD, Temp U, PSL - 1, PR - 1. (Bottom Flange w/Double "P"-Seal Sized for 5 1/2" Extended Neck Mandrel Hanger, Pos. B-2)
2. Blind Flange. ANSI 900, 4-1/16" w/1/2" NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
3. Ball Valve (2) - 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

Section F

4. Crown Valve – 6" ANSI 900 Flanged, Full Opening, Manual Operated. Ball Valve for Fresh Water, Brine, and Nitrogen Service.
5. Double Studded Adapter – 7-1/16" API 3M x 4-1/16" API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class DD, Temp U, PSL - 1, PR - 1
6. Ball Valve – 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.
7. Blind Flange. ANSI 900, 4-1/16" w/1/2" NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.

Accessories

1. All required studs, nuts, ring gaskets and flange protectors for connecting the spools and valves to the spools.
 - ASTM A193 Grade B7 bolts, ASTM A194 2H nuts, Teflon coated.
 - All ring gaskets stainless steel.

PREPARED BY JMc	DATE 11/11/11	CHECKED BY MM	DATE 11/11/11	APPROVED BY JMc	DATE 11/11/11	REVISION 0	DATE
--------------------	------------------	------------------	------------------	--------------------	------------------	---------------	------

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

NYSEG
SENECA LAKE CAES
PROPOSED NEW DEWATERING WELLHEAD
CAVERN No. 1

Number 50756B

Date 10/11

Page 3 of 3

Brine to
Inergy

Air from
Compressors

PREPARED BY
JMc

DATE
11/11/11

CHECKED BY
MM

DATE
11/11/11

APPROVED BY
JMc

DATE
11/11/11

REVISION
0

DATE

Number 50756B

NYSEG
SENECA LAKE CAES
PROPOSED NEW DEWATERING WELLHEAD
CAVERN No. 2 & 3

Date 10/11

Page 1 of 3

Section A

Existing

Section B

1. Double Studded Adapter – 20 - 1/4" API 2M x 16-3/4" API 3M (w/Double "P"-Seal for 20" casing), Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class AA, Temp U, PSL - 1, PR – 1 (410 SST Body).
2. Casing Spool – 16-3/4", API 3M Bottom Flange x 16-3/4" API 3M Top, w/ (2) 4", API 3M, Extended Flanged Side Outlets. Top complete with Bowl for Mandrel to hang 20" OD Stainless Steel Casing, Lockscrews and Stuffing Boxes. API 6A – Class DD, Temp U, PSL – 1, PR – 1.
3. Mandrel Hanger w/ Extended Neck: 5' Section 20" 316L 3/8" WT Welded to bottom and 20" LT&C Threads (Top). API 6A - Class DD, Temp T, PSL - 1, PR – 2, 410 SST Body.
4. Blind Flange. ANSI 900, 4-1/16" w/1/2" NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
5. Ball Valve (2) - 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

Section C

1. Master Ball Valve – 16", ANSI 900 RTJ Flange, Seats and Ball 316 SST or CF8M SST, Full Internal 316 SST body overlay.

Section D

1. Casing Spool – 16-3/4" API 3M Bottom Flange x 13-5/8" API 3M Top, w / (2) 4", API 3M, Extended Flanged Side Outlets. Top complete with Bowl for Mandrel to hang 5 1/2" OD Brine Casing, Lockscrews and Stuffing Boxes. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
2. Mandrel Hanger w/ Extended Neck: 5-1/2", LT&C Threads (Top and Bottom). API 6A – Class DD, Temp U, PSL - 1, PR - 1.
3. Blind Flange. ANSI 900, 4-1/16" w/1/2" NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
4. Ball Valve (2) - 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
						0

**NYSEG
SENECA LAKE CAES
PROPOSED NEW DEWATERING WELLHEAD
CAVERN No. 2 & 3**

Number	50756B
Date	10/11
Page	2 of 3

Section E

1. Casing Spool - 13-5/8", API 3M x 7-1/16" API 3M w/ (2) 4" API 3M Extended Flanged Side Outlets. API 6A – Class DD, Temp U, PSL - 1, PR - 1. (Bottom Flange w/Double "P"-Seal Sized for 5 1/2" Extended Neck Mandrel Hanger, Pos. B-2)
2. Blind Flange. ANSI 900, 4-1/16" w/1/2" NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
3. Ball Valve (2) - 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.

Section F

4. Crown Valve – 6" ANSI 900 Flanged, Full Opening, Manual Operated. Ball Valve for Fresh Water, Brine, and Nitrogen Service.
5. Double Studded Adapter – 7-1/16" API 3M x 4-1/16" API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class AA, Temp U, PSL - 1, PR - 1
6. Ball Valve – 4" ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.
7. Blind Flange. ANSI 900, 4-1/16" w/1/2" NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.

Accessories

1. All required studs, nuts, ring gaskets and flange protectors for connecting the spools and valves to the spools.
 - ASTM A193 Grade B7 bolts, ASTM A194 2H nuts, Teflon coated.
 - All ring gaskets stainless steel.

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
						0

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

NYSEG
SENECA LAKE CAES
PROPOSED NEW DEWATERING WELLHEAD
CAVERN No. 2 & 3

Number 50756B

Date 10/11

Page 3 of 3

Brine to
Inergy

Air from
Compressors

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION 0	DATE
-------------	------	------------	------	-------------	------	---------------	------

**NYSEG
SENECA LAKE CAES
PROPOSED NEW PRODUCTION WELLHEAD
WELL No. 1**

Number 50756B

Date 10/11

Page 1 of 2

Section A

Existing

Section B

Existing

Section C

Existing

Section D

1. Casing Spool – 20-3/4” API 3M Bottom Flange x 13-5/8” API 3M Top, w/(2) 16-3/4”, API 3M, Extended Flanged Side Outlets. API 6A - Class CC, Temp U, PSL - 1, PR - 1.
2. Ball Valve (2) - 16” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service. Seats and Ball 316 SST or CF8M SST, Full Internal 316 SST body overlay.
3. Ball Valve (2) – 16” ANSI 900 Flanged Full Opening (Actuated). For Fresh Water, Brine, and Nitrogen Service. Seats and Ball 316 SST or CF8M SST, Full Internal 316 SST body overlay.

Section E

4. Double Studded Adapter – 16-3/4” API 3M x 7-1/16” API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class CC, Temp U, PSL - 1, PR - 1.
5. Ball Valve 6” ANSI 900 Flanged Full Opening (Actuated). For Fresh Water, Brine, and Nitrogen Service. Seats and Ball 316 SST or CF8M SST, Full Internal 316 SST body overlay.
6. Double Studded Adapter – 7-1/16” API 3M x 4-1/16” API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class CC, Temp U, PSL - 1, PR - 1
7. Ball Valve – 4” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.
8. Blind Flange. ANSI 900, 4” w/1/2” NPT Tap. API 6A - Class CC, Temp U, PSL - 1, PR - 1.

Accessories

1. All required studs, nuts, ring gaskets and flange protectors for connecting the spools and valves to the spools.
 - ASTM A193 Grade B7 bolts, ASTM A194 2H nuts, Teflon coated.
 - All ring gaskets stainless steel.

PREPARED BY JMc	DATE 11/11/11	CHECKED BY MM	DATE 11/11/11	APPROVED BY JMc	DATE 11/11/11	REVISION 0	DATE
--------------------	------------------	------------------	------------------	--------------------	------------------	---------------	------

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

NYSEG
SENECA LAKE CAES
PROPOSED NEW PRODUCTION WELLHEAD
WELL No. 1

Number 50756B

Date 10/11

Page 2 of 2

PREPARED BY
JMc

DATE
11/11/11

CHECKED BY
MM

DATE
11/11/11

APPROVED BY
JMc

DATE
11/11/11

REVISION
0

DATE

Number 50756B

NYSEG
SENECA LAKE CAES
PROPOSED NEW PRODUCTION WELLHEAD
WELL No. 2 & 3

Date 10/11

Page 1 of 2

Section A

Existing

Section B

Existing

Section C

Existing

Section D

1. Casing Spool – 16-3/4” API 3M Bottom Flange x 13-5/8” API 3M Top, w / (2) 16-3/4”, API 3M, Extended Flanged Side Outlets. API 6A - Class DD, Temp U, PSL - 1, PR - 1.
2. Ball Valve (2) - 16” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service. Seats and Ball 316 SST or CF8M SST, Full Internal 316 SST body overlay.
3. Ball Valve (2) – 12” ANSI 900 Flanged Full Opening (Actuated). For Fresh Water, Brine, and Nitrogen Service. Seats and Ball 316 SST or CF8M SST, Full Internal 316 SST body overlay.

Section E

4. Double Studded Adapter – 13-5/8” API 3M x 7-1/16” 3M API, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class AA, Temp U, PSL - 1, PR - 1 (410 SST Body).
5. Ball Valve (2) – 6” ANSI 900 Flanged Full Opening (Actuated). For Fresh Water, Brine, and Nitrogen Service. Seats and Ball 316 SST or CF8M SST, Full Internal 316 SST body overlay.
6. Double Studded Adapter – 7-1/16” API 3M x 4-1/16” API 3M, Including ASTM A-193 GR B7 Studs and ASTM GR 2H Nuts. PI 6A – Class AA, Temp U, PSL - 1, PR - 1
7. Ball Valve – 4” ANSI 900 Flanged, Full Opening, Manual Operated. For Fresh Water, Brine, and Nitrogen Service.
8. Blind Flange. ANSI 900, 4-1/16” w/1/2” NPT Tap. API 6A - Class DD, Temp U, PSL - 1, PR - 1.

Accessories

1. All required studs, nuts, ring gaskets and flange protectors for connecting the spools and valves to the spools.
 - ASTM A193 Grade B7 bolts, ASTM A194 2H nuts, Teflon coated.
 - All ring gaskets stainless steel.

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
						0

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

NYSEG
SENECA LAKE CAES
PROPOSED NEW PRODUCTION WELLHEAD
WELL No. 2 & 3

Number 50756B

Date 10/11

Page 2 of 2

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
						0

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 1 DRILLING PROGRAM		Date 09/11				
			Page 1 of 7				
<p>Well: CAES Well No. 1</p> <p>Operator: NYSEG Permit No. NA</p> <p>Field: Reading</p> <p>County: Schuyler</p> <p>Lease: NA Survey: NA</p> <p>Regulatory Information –</p> <p>Proposed wellbore configuration: Also see attached wellbore schematic</p> <p>42" Conductor: 0 - Approx. 175 ft.</p> <p>30" Surface Casing: 0 - Approx. 850 ft. (36" Hole)</p> <p>24" Final Casing: 0 – Approx. 2,360 ft. (30" Hole)</p> <p>8-5/8" Outer Leaching Casing: 0 – Approx. 2,530 ft.</p> <p>5-1/2" Inner Leaching Casing: 0 ft. – 2,630 ft.</p> <p>Total Depth: 2632 ft.</p> <p>Bottom of USDW –</p> <p>Top of Caprock – NA</p> <p>Top of F Salt – Approx. 2,352 ft.</p> <p>Note: All depths from Ground Level (GL)</p> <ol style="list-style-type: none"> 1. Move in the "Rat Hole" drilling rig and drill 48" conductor hole to approximately 175 ft. 2. Run and cement approximately 175 ft of 42" conductor pipe. 3. Drill rat hole and mouse hole according to drilling rig contractor's specifications. 4. Move in drilling rig with 27-1/2' rotary and set up over the 42" conductor pipe. 5. After 24 hours WOC, pressure test the 42" casing. Hold the test for 30 minutes, record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure. 6. Cut the 42" and nipple up flow line. 7. Pick up and run in a 39-1/2" center-punch assembly and run in hole to TD. 8. Circulate and condition the hole. 9. Drill out the cement and 10 - 15 feet of new formation. 							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 1 DRILLING PROGRAM		Date 09/11				
			Page 2 of 7				
<div>10. Circulate hole clean and treat mud for cement contamination.</div> <div>11. Pull the center-punch assembly out of the hole and lay down.</div> <div>12. Make a rough cut on the 42" casing. Pull the 42" casing out of the floor and lay it down.</div> <div>13. Install 42" x 20" swage w/ 21 1/4" 2M temporary flange.</div> <div>14. Nipple up the 20" well control equipment including drilling nipple and flow line.</div> <div>15. Function test the annular preventer.</div> <div>16. Pick up and run in a 17 1/2" rock bit to TD. Drill a 17 1/2" pilot hole to +/- 850 ft. GL, running a deviation survey (TOTCO) every 90 ft. (every 30 ft. if deviation is a problem). There shall be no more than 1 - 2 degree per 100 ft.</div> <div>17. Circulate and condition the hole for running logs.</div> <div>18. Rig up a wireline service company. Run the appropriate logs. Rig down and move out the wireline company.</div> <div>19. Pick up and run in a 27-1/2" hole-opener with a 17 1/2" rock bit strapped to the bottom.</div> <div>20. Open the 17-1/2" pilot hole to 27-1/2" to +/- 850 ft. GL.</div> <div>21. Circulate and condition the hole.</div> <div>22. POOH with the 27-1/2" hole opening assembly.</div> <div>23. Pick up and run in a 36" hole-opener with a 26" rock bit strapped to the bottom.</div> <div>24. Open the 27-1/2" hole to 36" from the end of the 42" to +/- 850 ft. GL.</div> <div>25. Circulate and condition the hole.</div> <div>26. Pick up and run in a 39.5" hole-opener with a pilot guide strapped to the bottom.</div> <div>27. Open 36" hole to 39.5" to +/- 850 ft. GL.</div> <div>28. Circulate and condition the hole.</div> <div>29. POOH with the 39.5" hole opening assembly.</div> <div>30. Rig up a wireline service company and run a 60" 4-arm XY Caliper log from TD to conductor pipe.</div> <div>31. Weld float shoe and float collar (stinger type) to the first double joint of surface casing.</div>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

APPROVED BY
JMc

DATE
11/11

REVISION
0

DATE

PB Energy Storage Services, Inc. <small>ENGINEERING · CONSTRUCTION · OPERATIONS · MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 1 DRILLING PROGRAM		Date 09/11				
			Page 3 of 7				
<p>32. Rig up a casing crew service and welders and run approx. 4 double joints of 30", .875" WT, and 6 double joints of 0.75 WT, PE casing to +/- 850 ft. GL. (install centralizers in the middle of the first two joints then one on every other joint to surface).</p> <p>33. Pick up and run in a cementing string of 5" drill pipe with a stinger sub on bottom and a bow centralizer in the middle of the first joint, to the top of the float collar (do not sting in).</p> <p>34. Strip a 30" by 7 5/8" 8rd cementing head over the string. Weld the 30" connection.</p> <p>35. Strip a 7 5/8" 8rd by 5" pack-off assembly over the string. Make it up onto the cementing head.</p> <p>36. Sting into the float collar then pack off the drill pipe (fill the 30" by 5" annulus before packing off).</p> <p>37. Circulate the well with the rig pumps until the cement pumping units are rigged up.</p> <p>38. Rig up a cementing company. Cement the 30" casing to surface. Top off if necessary.</p> <p>39. Pull the 5" cementing string out of the stab-in float collar. Test float equipment. Circulate the well "indirect" to check that the 5" cementing string is clear.</p> <p>40. Cut/split the 42" casing and flow line, and lay down.</p> <p>41. After 24 hours WOC, pressure test the 30" casing. Hold the test for 30 minutes; record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure.</p> <p>42. Unpack the 5" drill pipe. Loosen the 7 5/8" pack off assembly on top of the cementing head. Cut the 30" weld on the casing. Strip the 30" by 7 5/8" 8rd cementing head over the cementing string.</p> <p>43. Pull the 5" cementing string out of the hole.</p> <p>44. Cut the 30" casing and nipple up a flow line.</p> <p>45. Pick up and run in a 27-1/2" center-punch assembly to the top of the float collar.</p> <p>46. Circulate and condition the hole.</p> <p>47. Drill out the float collar, cement, float shoe, cement, and 10 - 15 feet of new formation.</p> <p>48. Circulate hole clean and treat mud for cement contamination.</p> <p>49. Pull the center-punch assembly out of the hole and lay down.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 1 DRILLING PROGRAM		Date 09/11				
			Page 4 of 7				
<p>50. Make a rough cut on the 30" casing. Pull the 30" casing out of the floor and lay it down. Install 30" x 20" swage w/21 1/4" 2M temporary flange.</p> <p>51. Nipple up the 20" well control equipment including drilling nipple and flow line. Function test the annular preventer.</p> <p>52. Pick up and run in a 17 1/2" rock bit to approx. 850 GL.</p> <p>53. Drill a 17 1/2" pilot hole to +/- 2300 ft. GL (Top of salt expected at approx. 2352 GL), running a deviation survey (TOTCO) every 90 ft. (every 30 ft. if deviation is a problem). There shall be no more than 1 - 2 degree per 100 ft.</p> <p>54. Clean out mud tanks and haul off fresh water mud for disposal. Fill tanks with salt saturated drilling mud.</p> <p>55. Displace the fresh water mud with salt-water gel.</p> <p>56. Drill 17 1/2" pilot hole to +/-2632'.</p> <p>57. Pull out of hole with 17 1/2" bit.</p> <p>58. Circulate and condition the hole for running logs.</p> <p>59. Rig up a wireline logging service company. Run the appropriate logs. Rig down and move out the wireline service company.</p> <p>60. Nipple down the well control equipment.</p> <p>61. Cut off the 30" by 20" swage and 21 1/4" 2M flange.</p> <p>62. Pick up the 42" drilling nipple and weld it back to the 42" conductor pipe. Nipple up fill-up line and flow-line.</p> <p>63. Pick up and run in a 27-1/2" hole-opener with a 17 1/2" rock bit strapped to the bottom.</p> <p>64. Open the 17-1/2" pilot hole to 27-1/2" to +/- 2360 ft. GL.</p> <p>65. Circulate and condition the hole.</p> <p>66. Pull out of the hole with the 27-1/2" hole opening assembly.</p> <p>67. Pick up and run in a 30" under reamer.</p> <p>68. Open 27-1/2" hole to 30" to +/- 2360 ft. GL.</p> <p>69. Circulate and condition the hole.</p> <p>70. Pull out of the hole with the under reamer assembly.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 1 DRILLING PROGRAM		Date 09/11				
			Page 5 of 7				
<p>71. Circulate and condition the hole.</p> <p>72. Run in the hole to +/- 2450 ft. GL with blank 5" DP. Pump a 50 ft cement plug through the 5" DP and spot in the 17-1/2" bore hole. Pull out of the hole with the 5" DP. Wait on cement approx. 24 hrs.</p> <p>73. Rig up a casing crew service and welders and run approx. 5 double joints of 24", 1.25"WT, 12 double joints of 24" & 1.0" WT and 12 double joints of 24" 0.75" WT, X-52, PE casing to +/- 2360 ft. GL. Float shoe and float collar (stinger type) will be welded to the first double joint, install centralizers in the middle of the first two joints then one on every other joint to surface.</p> <p>74. Pick up and run in a cementing string of 5" drill pipe with a stinger sub on bottom and a bow centralizer in the middle of the first joint, to the top of the float collar (do not sting in).</p> <p>75. Strip a 24" by 7-5/8" 8rd cementing head over the string.</p> <p>76. Weld the 24" connection. Strip a 7 5/8" 8rd by 5" pack-off assembly over the string. Make it up onto the cementing head.</p> <p>77. Sting into the float collar then pack off the drill pipe (fill the 24" by 5" annulus before packing off). Circulate the well with the rig pumps until the cement pumping units are rigged up.</p> <p>78. Rig up a cementing company. Cement the 24" casing to surface. Top off if necessary. Pull the 5" cementing string out of the stab-in float collar. Test float equipment. Circulate the well "indirect" to check that the 5" cementing string is clear.</p> <p>79. Cut/split the 42" casing and flow line, and lay down.</p> <p>80. After 72 hours WOC, pressure test the 24" casing. Hold the test for 30 minutes, record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure and open the annular preventer.</p> <p>81. Unpack the 5" drill pipe. Loosen the 7 5/8" pack off assembly on top of the cementing head. Cut the 24" weld on the casing. Strip the 24" by 7 5/8" 8rd cementing head over the cementing string. Pull the 5" cementing string out of the hole.</p> <p>82. Cut the 24" casing and nipple up a flow line.</p> <p>83. Pick up and run in a 21-1/2" center-punch assembly to the top of the float collar.</p> <p>84. Circulate and condition the hole.</p> <p>85. Drill out the float collar, cement; float shoe, cement, and 10 - 15 feet of new formation.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 1 DRILLING PROGRAM		Date 09/11				
			Page 6 of 7				
<p>86. Circulate hole clean and treat mud for cement contamination.</p> <p>87. Pull the center-punch assembly out of the hole and lay down.</p> <p>88. Make a rough cut on the 24" casing. Pull the 24" casing out of the floor and lay it down. Install 24" x 20" swage w/21 1/4" 2M temporary flange and 20" well control equipment.</p> <p>89. Pick up and run in hole with 17 ½" rock bit to approx. 2360' GL.</p> <p>90. Drill a 17 1/2" pilot hole to +/- 2632 ft. GL.</p> <p>91. Circulate and condition the hole for cement contamination and running logs.</p> <p>92. Rig up a wireline logging service company. Run the appropriate logs. Rig down and move out the wireline service company.</p> <p>93. Pick up 24" under reamer and open 17-1/2" hole to 2632' GL.</p> <p>94. Nipple down the well control equipment. Cut off the 24" by 20" swage and 21 1/4" 2M flange.</p> <p>95. Circulate the hole clean.</p> <p>96. Remove salt saturated drilling mud from the rig tanks and haul it off to a disposal site. Fill the tanks with clean 10 lb/gal brine water.</p> <p>97. Pick up and run in a 24" under reamer to TD.</p> <p>98. Rig up directional survey service company and run a multi-shot gyroscopic survey (measure wellbore deviation). Rig down and move out wireline truck.</p> <p>99. Pull out of the hole laying down the drilling assembly.</p> <p>100. Install the 24" 2M double studded adapter. Energize the 'P' seals then test the 24" casing section to the appropriate test pressure for 15 minutes.</p> <p>101. Install the leaching wellhead B spool.</p> <p>102. Rig up to run +/-2530 ft. of 8-5/8", J-55 casing with a modified BT&C thread. Run 8-5/8" casing, externally testing to 80% of collapse on each connection under tension for 60 to 90 seconds each.</p> <p>103. Install the leaching wellhead C (5-1/2") casing spool. Energize the 'P' seals then test the 8 5/8" hanger section to the appropriate test pressure for 15 minutes.</p> <p>104. Rig up to run +/-2630 ft. of 5-1/2", J-55 casing having a BT&C connection.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING · CONSTRUCTION · OPERATIONS · MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B	
	NYSEG WATKINS GLEN PROPOSED CAES WELL 1 DRILLING PROGRAM		Date 09/11	
			Page 7 of 7	
<p>105. Install the leaching wellhead D casing spool. Energize the 'P' seals then test the 5 1/2" hanger section to the appropriate test pressure for 15 minutes.</p> <p>106. Install the crown valve, DSA, logging valve, and blind flange. Install valves and flanges as needed to secure the well.</p> <p>107. Rig down and move out the drilling rig.</p>				
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc
				DATE 11/11
				REVISION 0
				DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 2 DRILLING PROGRAM		Date 11/11				
			Page 1 of 7				
<p>Well: CAES Well No. 2</p> <p>Operator: NYSEG Permit No. NA</p> <p>Field: Reading</p> <p>County: Schuyler</p> <p>Lease: NA Survey: NA</p> <p>Regulatory Information –</p> <p>Proposed wellbore configuration: Also see attached wellbore schematic</p> <p>42" Conductor: 0 - Approx. 175 ft.</p> <p>26" Surface Casing: 0 - Approx. 850 ft.</p> <p>20" Final Casing: 0 – Approx. 2,360 ft.</p> <p>8-5/8" Outer Leaching Casing: 0 – Approx. 2,530 ft.</p> <p>5-1/2" Inner Leaching Casing: 0 ft. – 2,630 ft.</p> <p>Total Depth: 2,632 ft.</p> <p>Bottom of USDW –</p> <p>Top of Caprock – NA</p> <p>Top of F Salt – Approx. 2,352 ft.</p> <p>Note: All depths from Ground Level (GL)</p> <ol style="list-style-type: none"> 1. Move in the "Rat Hole" drilling rig and drill 48" conductor hole to approximately 175 ft. 2. Run and cement approximately 175 ft of 42" conductor pipe. 3. Drill rat hole and mouse hole according to drilling rig contractor's specifications. 4. Move in drilling rig with 27-1/2' rotary and set up over the 42" conductor pipe. 5. After 24 hours WOC, pressure test the 42" casing. Hold the test for 30 minutes, record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure. 6. Cut the 42" casing and nipple up a flow line. 7. Pick up and run in a 39-1/2" center-punch assembly to the top of the float collar. 8. Circulate and condition the hole. 9. Drill out the cement and 10 - 15 feet of new formation. 							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 2 DRILLING PROGRAM		Date 11/11				
			Page 2 of 7				
<div>10. Circulate hole clean and treat mud for cement contamination.</div> <div>11. Pull the center-punch assembly out of the hole and lay down.</div> <div>12. Make a rough cut on the 42" casing. Pull the 42" casing out of the floor and lay it down. Install 42" x 20" swage w/ 21 1/4" 2M temporary flange. Nipple up the 20" well control equipment including drilling nipple and flow line. Function test the annular preventer.</div> <div>13. Pick up and run in a 17 1/2" rock bit to TD. Drill a 17 1/2" pilot hole to +/- 850 ft. GL, running a deviation survey (TOTCO) every 90 ft. (every 30 ft. if deviation is a problem). There shall be no more than 1 - 2 degree per 100 ft.</div> <div>14. Circulate and condition the hole for running logs.</div> <div>15. Rig up a wireline service company. Run the appropriate logs. Rig down and move out the wireline company.</div> <div>16. Nipple down 20" well control equipment and lay down.</div> <div>17. Pick up and run in a 27-1/2" hole-opener with a 17 1/2" rock bit strapped to the bottom.</div> <div>18. Open the 17-1/2" pilot hole to 27-1/2" to +/- 850 ft. GL.</div> <div>19. Circulate and condition the hole.</div> <div>20. POOH with the 27-1/2" hole opening assembly.</div> <div>21. Pick up and run in a 34-1/2" hole-opener with a 26" rock bit strapped to the bottom. Open the 27-1/2" hole to 36" from the end of the 34-1/2" to +/- 850 ft. GL.</div> <div>22. Circulate and condition the hole.</div> <div>23. POOH with the 34-1/2" hole opening assembly.</div> <div>24. Rig up a wireline service company and run a 60" 4-arm XY Caliper log from TD to conductor pipe.</div> <div>25. Rig up a casing crew service and welders and run approx. 5 double joints of 26", .625" WT, and approx. 6 double joints of 0.75"WT, X-56, PE casing to +/- 850 ft. GL. Float shoe and float collar (stinger type) will be welded to the first double joint, install centralizers in the middle of the first two joints then one on every other joint to surface.</div> <div>26. Pick up and run in a cementing string of 5" drill pipe with a stinger sub on bottom and a bow centralizer in the middle of the first joint, to the top of the float collar (do not sting in). Strip a 26" by 7 5/8" 8rd cementing head over the string. Weld the 26" connection. Strip a 7 5/8" 8rd by 5" pack-off assembly over the string. Make it up onto the cementing head. Sting</div>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 2 DRILLING PROGRAM		Date 11/11				
			Page 3 of 7				
<p>into the float collar then pack off the drill pipe (fill the 26" by 5" annulus before packing off). Circulate the well with the rig pumps until the cement pumping units are rigged up.</p> <p>27. Rig up a cementing company. Cement the 26" casing to surface. Top off if necessary. Pull the 5" cementing string out of the stab-in float collar. Test float equipment. Circulate the well "indirect" to check that the 5" cementing string is clear. Cut/split the 42" casing and flow line, and lay down.</p> <p>28. After 24 hours WOC, pressure test the 26" casing. Hold the test for 30 minutes; record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure.</p> <p>29. Unpack the 5" drill pipe. Loosen the 7 5/8" pack off assembly on top of the cementing head. Cut the 26" weld on the casing. Strip the 26" by 7 5/8" 8rd cementing head over the cementing string. Pull the 5" cementing string out of the hole.</p> <p>30. Cut the 26" casing and nipple up a flow line.</p> <p>31. Pick up and run in a 24" center-punch assembly to the top of the float collar.</p> <p>32. Circulate and condition the hole.</p> <p>33. Drill out the float collar, cement, float shoe, cement, and 10 - 15 feet of new formation.</p> <p>34. Circulate hole clean and treat mud for cement contamination.</p> <p>35. Pull the center-punch assembly out of the hole and lay down.</p> <p>36. Make a rough cut on the 26" casing. Pull the 26" casing out of the floor and lay it down. Install 26" x 20" swage w/21 1/4" 2M temporary flange.</p> <p>37. Nipple up the 20" well control equipment including drilling nipple and flow line.</p> <p>38. Function test the annular preventer.</p> <p>39. Pick up and run in a 17 1/2" rock bit to approx. 850 GL.</p> <p>40. Drill a 17 1/2" pilot hole to +/- 2290 ft. GL (Top of salt expected at approx. 2352 GL), running a deviation survey (TOTCO) every 90 ft. (every 30 ft. if deviation is a problem). There shall be no more than 1 - 2 degree per 100 ft.</p> <p>41. Clean out mud tanks and haul off fresh water mud for disposal. Fill tanks with salt saturated drilling mud.</p> <p>42. Displace the fresh water mud with salt-water gel.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 2 DRILLING PROGRAM		Date 11/11				
			Page 4 of 7				
<p>43. Pull out of hole with 17 ½” bit.</p> <p>44. Pick up and run in 8 1/2” core bit and 60 ft. of 4” (inner) x 6” (outer) core barrel to +/- 2290 ft. GL.</p> <p>45. Cut a 4” core from +/- 2290 ft. to 2350 ft. GL. Pull out of hole and lay out the core. Lay down coring assembly.</p> <p>46. Pick up and run in 8 1/2” core bit and 60 ft. of 4” (inner) x 6” (outer) core barrel to +/- 2350 ft. GL.</p> <p>47. Cut a 4” core from +/- 2350 ft. to 2410 ft. GL. Pull out of hole and lay out the core. Lay down coring assembly.</p> <p>48. Pick up and run in a 12-1/4” rock bit to +/- 2290 ft. GL.</p> <p>49. Open the 8 1/2” core hole to 12-1/4”. Drill a 12-1/4” pilot hole from to +/- 2475 ft. GL, running a deviation survey every 90 ft. (every 30 ft. if deviation is a problem). There shall be no more than 1 - 2 degree per 100 ft.</p> <p>50. Circulate and condition the hole for coring.</p> <p>51. Pull out of hole.</p> <p>52. Pick up and run in 8 1/2” core bit and 40 ft. of 4” (inner) x 6” (outer) core barrel to +/- 2475 ft. GL.</p> <p>53. Cut a 4” core from +/- 2475 ft. to 2515 ft. GL. Pull out of hole and lay out the core. Lay down coring assembly.</p> <p>54. Pick up and run in a 12-1/4” rock bit to +/- 2475 ft. GL.</p> <p>55. Open the 8 1/2” core hole to 12-1/4”.</p> <p>56. Drill a 12-1/4” pilot hole to +/- 2632 ft. GL, running a deviation survey every 90 ft. (every 30 ft. if deviation is a problem). There shall be no more than 1 - 2 degree per 100 ft.</p> <p>57. Nipple down the well control equipment. Cut off the 26” by 20” swage and 21 1/4” 2M flange. Pick up the 26” drilling nipple and weld it back to the 26” pipe. Nipple up fill-up line and flow-line.</p> <p>58. Pick up 17-1/2 inch hole opener with 12-1/4” rock bit strapped to bottom and open the 12-1/4” hole to 17-1/2” to +/- 2632 ft. GL.</p> <p>59. Pull out of hole</p> <p>60. Circulate and condition the hole for running logs.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 2 DRILLING PROGRAM		Date 11/11				
			Page 5 of 7				
<p>61. Rig up a wireline logging service company. Run the appropriate logs. Rig down and move out the wireline service company.</p> <p>62. Pick up and run in hole with a 26" under reamer. Open the 17-1/2" pilot hole to 26" to +/- 2360 ft. GL.</p> <p>63. Circulate and condition the hole.</p> <p>64. Pull out of the hole with the 26" under reamer assembly.</p> <p>65. Run in the hole to +/- 2450 ft. GL with blank 5" DP. Pump a 50 ft cement plug through the 5" DP and spot in the 17-1/2" bore hole. Pull out of the hole with the 5" DP. Wait on cement approx. 24 hrs.</p> <p>66. Rig up a casing crew service and welders and run approx. 11 double joints of 20", .906"WT, 12 double joints of 20" & .75" WT and 6 double joints of 20" 0.5" WT, X-56, PE casing to +/- 2360 ft. GL. Float shoe and float collar (stinger type) will be welded to the first double joint, install centralizers in the middle of the first two joints then one on every other joint to surface.</p> <p>67. Pick up and run in a cementing string of 5" drill pipe with a stinger sub on bottom and a bow centralizer in the middle of the first joint, to the top of the float collar (do not sting in).</p> <p>68. Strip a 20" by 7-5/8" 8rd cementing head over the string. Weld the 20" connection. Strip a 7 5/8" 8rd by 5" pack-off assembly over the string. Make it up onto the cementing head.</p> <p>69. Sting into the float collar then pack off the drill pipe (fill the 20" by 5" annulus before packing off).</p> <p>70. Circulate the well with the rig pumps until the cement pumping units are rigged up.</p> <p>71. Rig up a cementing company. Cement the 20" casing to surface. Top off if necessary.</p> <p>72. Pull the 5" cementing string out of the stab-in float collar. Test float equipment. Circulate the well "indirect" to check that the 5" cementing string is clear.</p> <p>73. Cut/split the 26" casing and flow line, and lay down.</p> <p>74. After 72 hours WOC, pressure test the 20" casing. Hold the test for 30 minutes, record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure and open the annular preventer.</p> <p>75. Unpack the 5" drill pipe. Loosen the 7 5/8" pack off assembly on top of the cementing head. Cut the 20" weld on the casing. Strip the 20" by 7 5/8" 8rd cementing head over the cementing string. Pull the 5" cementing string out of the hole.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 2 DRILLING PROGRAM		Date 11/11				
			Page 6 of 7				
<p>76. Cut the 20" casing and nipple up a flow line.</p> <p>77. Pick up and run in a 17-1/2" center-punch assembly to the top of the float collar.</p> <p>78. Circulate and condition the hole.</p> <p>79. Drill out the float collar, cement; float shoe, cement, and 10 - 15 feet of new formation.</p> <p>80. Circulate hole clean and treat mud for cement contamination.</p> <p>81. Pull the 17-1/2" center-punch assembly out of the hole and lay down.</p> <p>82. Make a rough cut on the 20" casing. Pull the 20" casing out of the floor and lay it down. Install 21 1/4" 2M temporary flange and 20" well control equipment.</p> <p>83. Pick up and run in hole with 17 ½" rock bit to approx. 2360' GL.</p> <p>84. Open hole to 17 1/2" to+/- 2632 ft. GL.</p> <p>85. Nipple down the well control equipment. Cut off the 21 1/4" 2M flange.</p> <p>86. Circulate the hole clean.</p> <p>87. Remove salt saturated drilling mud from the rig tanks and haul it off to a disposal site. Fill the tanks with clean 10 lb/gal brine water.</p> <p>88. Pick up and run in a 17 1/2" rock bit to TD.</p> <p>89. Rig up directional survey service company and run a multi-shot gyroscopic survey (measure wellbore deviation). Rig down and move out wireline truck.</p> <p>90. Pull out of the hole laying down the drilling assembly.</p> <p>91. Install the 20" 2M double studded adapter. Energize the 'P' seals then test the 20" casing section to the appropriate test pressure for 15 minutes.</p> <p>92. Install the leaching wellhead B spool.</p> <p>93. Rig up to run +/-2530 ft. of 8-5/8", J-55 casing with a modified BT&C thread. Run 8-5/8" casing, externally testing to 80% of collapse on each connection under tension for 60 to 90 seconds each.</p> <p>94. Install the leaching wellhead C (5-1/2") casing spool. Energize the 'P' seals then test the 8 5/8" hanger section to the appropriate test pressure for 15 minutes.</p> <p>95. Rig up to run +/-2630 ft. of 5-1/2", J-55 casing having a BT&C connection.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING · CONSTRUCTION · OPERATIONS · MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 2 DRILLING PROGRAM		Date 11/11				
			Page 7 of 7				
<p>96. Install the leaching wellhead D casing spool. Energize the 'P' seals then test the 5 1/2" hanger section to the appropriate test pressure for 15 minutes.</p> <p>97. Install the crown valve, DSA, logging valve, and blind flange. Install valves and flanges as needed to secure the well.</p> <p>98. Rig down and move out the drilling rig.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING · CONSTRUCTION · OPERATIONS · MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 3 DRILLING PROGRAM		Date 11/11				
			Page 1 of 6				
<p>Well: CAES Well No. 2</p> <p>Operator: NYSEG Permit No. NA</p> <p>Field: Reading</p> <p>County: Schuyler</p> <p>Lease: NA Survey: NA</p> <p>Regulatory Information –</p> <p>Proposed wellbore configuration: Also see attached wellbore schematic</p> <p>42" Conductor: 0 - Approx. 175 ft.</p> <p>26" Surface Casing: 0 - Approx. 850 ft.</p> <p>20" Final Casing: 0 – Approx. 2,360 ft.</p> <p>8-5/8" Outer Leaching Casing: 0 – Approx. 2,530 ft.</p> <p>5-1/2" Inner Leaching Casing: 0 ft. – 2,630 ft.</p> <p>Total Depth: 2,638 ft.</p> <p>Bottom of USDW –</p> <p>Top of Caprock – NA</p> <p>Top of F Salt – Approx. 2,352 ft.</p> <p>Note: All depths from Ground Level (GL)</p> <ol style="list-style-type: none"> 1. Move in the "Rat Hole" drilling rig and drill 48" conductor hole to approximately 175 ft. 2. Run and cement approximately 175 ft of 42" conductor pipe. 3. Drill rat hole and mouse hole according to drilling rig contractor's specifications. 4. Move in drilling rig with 27-1/2' rotary and set up over the 42" conductor pipe. 5. After 24 hours WOC, pressure test the 42" casing. Hold the test for 30 minutes, record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure. 6. Cut the 42" casing and nipple up a flow line. 7. Pick up and run in a 39-1/2" center-punch assembly to the top of the float collar. 8. Circulate and condition the hole. 9. Drill out the cement and 10 - 15 feet of new formation. 							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 3 DRILLING PROGRAM		Date 11/11				
			Page 2 of 6				
<div>10. Circulate hole clean and treat mud for cement contamination.</div> <div>11. Pull the center-punch assembly out of the hole and lay down.</div> <div>12. Make a rough cut on the 42" casing. Pull the 42" casing out of the floor and lay it down. Install 42" x 20" swage w/ 21 1/4" 2M temporary flange. Nipple up the 20" well control equipment including drilling nipple and flow line. Function test the annular preventer.</div> <div>13. Pick up and run in a 17 1/2" rock bit to TD. Drill a 17 1/2" pilot hole to +/- 850 ft. RKB, running a deviation survey (TOTCO) every 90 ft. (every 30 ft. if deviation is a problem). There shall be no more than 1 - 2 degree per 100 ft.</div> <div>14. Circulate and condition the hole for running logs.</div> <div>15. Rig up a wireline service company. Run the appropriate logs. Rig down and move out the wireline company.</div> <div>16. Pick up and run in a 27-1/2" hole-opener with a 17 1/2" rock bit strapped to the bottom. Open the 17-1/2" pilot hole to 27-1/2" to +/- 850 ft. RKB.</div> <div>17. Circulate and condition the hole.</div> <div>18. POOH with the 27-1/2" hole opening assembly.</div> <div>19. Pick up and run in a 34-1/2" hole-opener with a 26" rock bit strapped to the bottom. Open the 27-1/2" hole to 34-1/2" from the end of the 42" to +/- 850 ft. RKB.</div> <div>20. Circulate and condition the hole.</div> <div>21. POOH with the 34-1/2" hole opening assembly.</div> <div>22. Rig up a wireline service company and run a 60" 4-arm XY Caliper log from TD to conductor pipe.</div> <div>23. Rig up a casing crew service and welders and run approx. 5 double joints of 26", .625" WT, and approx. 6 double joints of 0.75"WT, X-56, PE casing to +/- 850 ft. RKB. Float shoe and float collar (stinger type) will be welded to the first double joint, install centralizers in the middle of the first two joints then one on every other joint to surface.</div> <div>24. Pick up and run in a cementing string of 5" drill pipe with a stinger sub on bottom and a bow centralizer in the middle of the first joint, to the top of the float collar (do not sting in). Strip a 26" by 7 5/8" 8rd cementing head over the string. Weld the 26" connection. Strip a 7 5/8" 8rd by 5" pack-off assembly over the string. Make it up onto the cementing head. Sting into the float collar then pack off the drill pipe (fill the 26" by 5" annulus before packing off). Circulate the well with the rig pumps until the cement pumping units are rigged up.</div>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 3 DRILLING PROGRAM		Date 11/11				
			Page 3 of 6				
<p>25. Rig up a cementing company. Cement the 26" casing to surface. Top off if necessary. Pull the 5" cementing string out of the stab-in float collar. Test float equipment. Circulate the well "indirect" to check that the 5" cementing string is clear. Cut/split the 42" casing and flow line, and lay down.</p> <p>26. After 24 hours WOC, pressure test the 26" casing. Hold the test for 30 minutes; record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure.</p> <p>27. Unpack the 5" drill pipe. Loosen the 7 5/8" pack off assembly on top of the cementing head. Cut the 26" weld on the casing. Strip the 26" by 7 5/8" 8rd cementing head over the cementing string. Pull the 5" cementing string out of the hole.</p> <p>28. Cut the 26" casing and nipple up a flow line.</p> <p>29. Pick up and run in a 24-1/2" center-punch assembly to the top of the float collar.</p> <p>30. Circulate and condition the hole.</p> <p>31. Drill out the float collar, cement, float shoe, cement, and 10 - 15 feet of new formation.</p> <p>32. Circulate hole clean and treat mud for cement contamination.</p> <p>33. Pull the center-punch assembly out of the hole and lay down.</p> <p>34. Make a rough cut on the 26" casing. Pull the 26" casing out of the floor and lay it down. Install 26" x 20" swage w/21 1/4" 2M temporary flange. Nipple up the 20" well control equipment including drilling nipple and flow line. Function test the annular preventer.</p> <p>35. Pick up and run in a 17 1/2" rock bit to approx. 850 RKB.</p> <p>36. Drill a 17 1/2" pilot hole to +/- 2300 ft. RKB (Top of salt expected at approx. 2352 GL), running a deviation survey (TOTCO) every 90 ft. (every 30 ft. if deviation is a problem). There shall be no more than 1 - 2 degree per 100 ft.</p> <p>37. Clean out mud tanks and haul off fresh water mud for disposal. Fill tanks with salt saturated drilling mud.</p> <p>38. Displace the fresh water mud with salt-water gel.</p> <p>39. Drill 17 1/2" pilot hole to +/-2632'.</p> <p>40. Pull out of hole with 17 1/2" bit.</p> <p>41. Circulate and condition the hole for running logs.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 3 DRILLING PROGRAM		Date 11/11				
			Page 4 of 6				
<p>42. Rig up a wireline logging service company. Run the appropriate logs. Rig down and move out the wireline service company.</p> <p>43. Nipple down the well control equipment. Cut off the 26" by 20" swage and 21 1/4" 2M flange. Pick up the 26" drilling nipple and weld it back to the 26" pipe. Nipple up fill-up line and flow-line.</p> <p>44. Pick up and run in a 24" hole-opener with a 17 1/2" rock bit strapped to the bottom. Open the 17-1/2" pilot hole to 24" to +/- 2360 ft. RKB.</p> <p>45. Circulate and condition the hole.</p> <p>46. Pull out of the hole with the 24" hole opening assembly.</p> <p>47. Pick up and run in a 26" under reamer. Open 24" hole to 26" to +/- 2360 ft. RKB.</p> <p>48. Circulate and condition the hole.</p> <p>49. Pull out of the hole with the under reamer assembly</p> <p>50. Run in the hole to +/- 2450 ft. GL with blank 5" DP. Pump a 50 ft cement plug through the 5" DP and spot in the 17-1/2" bore hole. Pull out of the hole with the 5" DP. Wait on cement approx. 24 hrs.</p> <p>51. Rig up a casing crew service and welders and run approx. 11 double joints of 20", .906"WT, 12 double joints of 20" & .75" WT and 6 double joints of 20" 0.5" WT, X-56, PE casing to +/- 2360 ft. RKB. Float shoe and float collar (stinger type) will be welded to the first double joint, install centralizers in the middle of the first two joints then one on every other joint to surface.</p> <p>52. Pick up and run in a cementing string of 5" drill pipe with a stinger sub on bottom and a bow centralizer in the middle of the first joint, to the top of the float collar (do not sting in). Strip a 20" by 7-5/8" 8rd cementing head over the string.</p> <p>53. Weld the 20" connection.</p> <p>54. Strip a 7 5/8" 8rd by 5" pack-off assembly over the string. Make it up onto the cementing head. Sting into the float collar then pack off the drill pipe (fill the 20" by 5" annulus before packing off).</p> <p>55. Circulate the well with the rig pumps until the cement pumping units are rigged up.</p> <p>56. Rig up a cementing company. Cement the 20" casing to surface. Top off if necessary. Pull the 5" cementing string out of the stab-in float collar. Test float equipment. Circulate the well "indirect" to check that the 5" cementing string is clear. Cut/split the 26" casing and flow line, and lay down.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 3 DRILLING PROGRAM		Date 11/11				
			Page 5 of 6				
<p>57. After 72 hours WOC, pressure test the 20" casing. Hold the test for 30 minutes, record it on a pressure test recorder. Use a chart recorder to record this test. There shall not be more than a 10% drop in pressure. If so, then the test must be repeated. Bleed off the pressure and open the annular preventer.</p> <p>58. Unpack the 5" drill pipe. Loosen the 7 5/8" pack off assembly on top of the cementing head. Cut the 20" weld on the casing. Strip the 20" by 7 5/8" 8rd cementing head over the cementing string. Pull the 5" cementing string out of the hole.</p> <p>59. Cut the 20" casing and nipple up a flow line.</p> <p>60. Pick up and run in a 17-1/2" center-punch assembly to the top of the float collar.</p> <p>61. Circulate and condition the hole.</p> <p>62. Drill out the float collar, cement; float shoe, cement, and 10 - 15 feet of new formation.</p> <p>63. Circulate hole clean and treat mud for cement contamination.</p> <p>64. Pull the 17-1/2" center-punch assembly out of the hole and lay down.</p> <p>65. Make a rough cut on the 20" casing. Pull the 20" casing out of the floor and lay it down. Install 21 1/4" 2M temporary flange and 20" well control equipment.</p> <p>66. Pick up and run in hole with 17 1/2" rock bit to approx. 2360' RKB.</p> <p>67. Open 17 1/2" pilot hole to +/- 2632 ft. RKB.</p> <p>68. Circulate and condition the hole for cement contamination.</p> <p>69. Nipple down the well control equipment. Cut off the 21 1/4" 2M flange.</p> <p>70. Circulate the hole clean.</p> <p>71. Remove salt saturated drilling mud from the rig tanks and haul it off to a disposal site. Fill the tanks with clean 10 lb/gal brine water.</p> <p>72. Pick up and run in a 17 1/2" rock bit to TD.</p> <p>73. Rig up directional survey service company and run a multi-shot gyroscopic survey (measure wellbore deviation). Rig down and move out wireline truck.</p> <p>74. Pull out of the hole laying down the drilling assembly.</p> <p>75. Install the 20" 2M double studded adapter. Energize the 'P' seals then test the 20" casing section to the appropriate test pressure for 15 minutes.</p> <p>76. Install the leaching wellhead B spool.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	SPECIFICATION		Number 50756B				
	NYSEG WATKINS GLEN PROPOSED CAES WELL 3 DRILLING PROGRAM		Date 11/11				
			Page 6 of 6				
<p>77. Rig up to run +/-2530 ft. of 8-5/8", J-55 casing with a modified BT&C thread. Run 8-5/8" casing, externally testing to 80% of collapse on each connection under tension for 60 to 90 seconds each.</p> <p>78. Install the leaching wellhead C (5-1/2") casing spool. Energize the 'P' seals then test the 8 5/8" hanger section to the appropriate test pressure for 15 minutes.</p> <p>79. Rig up to run +/-2630 ft. of 5-1/2", J-55 casing having a BT&C connection.</p> <p>80. Install the leaching wellhead D casing spool. Energize the 'P' seals then test the 5 1/2" hanger section to the appropriate test pressure for 15 minutes.</p> <p>81. Install the crown valve, DSA, logging valve, and blind flange. Install valves and flanges as needed to secure the well.</p> <p>82. Rig down and move out the drilling rig.</p>							
PREPARED BY J Mc	DATE 11/11	CHECKED BY MM	DATE 11/11	APPROVED BY JMc	DATE 11/11	REVISION 0	DATE

WORKOVER PROGRAM

Number 50756B

NYSEG WATKINS GLEN CAES CAVERNS 1,2, & 3 INTERMEDIATE WORKOVER AND SONAR

Date 11/17/2011

Page 1 of 7

INTRODUCTION

The NYSEG cavern has just finished first the stage of direct leaching. A workover is scheduled to bleed off the nitrogen blanket, remove and inspect the 5-1/2" casing, conduct a through pipe sonar survey, re-set the blanket protection string back into well to a new depth, re-run the 5-1/2" casing back into well to a new setting depth, and re-inject the nitrogen blanket.

WELL WORKOVER PLAN

1. Depressure the nitrogen to atmosphere through the 1/2 inch needle valve on the wellhead nitrogen injection manifold. Approximately 450,000 – 650,000 scf of nitrogen is in the well. Depressurization rate should not exceed 2.5 psi/minute (approximately 9 hrs). This activity will be performed prior to mobilization of the workover rig.
2. Depressure the freshwater (pressure in 5-1/2" tubing) from the well.
3. Remove the wellhead piping.
4. Install rig anchors per the workover rig requirements.
5. Rig up workover rig. The 5-1/2" casing weight is approximately 46,000 pounds in air (2,630 ft of 5-1/2", 17.5 lb/ft casing. The bottom of the 5-1/2" may be locked in insoluble on the bottom of the cavern.
6. Remove the upper section of the leaching wellhead along with the leaching wellhead D section. Nipple up the 13-5/8" annular preventer.
7. Back out lock down screws located in the top flange of the leaching wellhead C section.
8. Pick up a spear dressed for 5-1/2", 17.5 lb/ft casing and run in the hole. Set the spear. Pull 5 1/2" hanger/joint (approx. 46,000 lbs in air and set in slips on the annular preventer. Lay down spear and grapple.
9. Rig up the casing crew and tools to pull the 5-1/2" hanging casing.
10. Remove approx. 2,630 feet (estimate 65 joints + hanger joint) of 5-1/2", 17.5 lb/ft, J-55, LT&C casing. Place casing on location for on-site cleaning, inspection, and re-doping threaded connections. Transport the rejected 5-1/2" casing off-site for repairs
11. Nipple down the 13 5/8" well control equipment. Remove the leaching wellhead C section. Nipple up the 13-5/8" 2M annular preventer and 20-3/4" x 13-5/8" DSA.
12. Back out lock down screws located in the top flange of the leaching wellhead B section.
13. Pick up a spear dressed for 8-5/8", 32 lb/ft LT&C casing and run in the hole. Set the spear. Pull 8-5/8" hanger/joint (approx. 80,000 lbs in air) and set in slips in the annular preventer. Lay down spear and grapple.

PREPARED BY
JMc

DATE

CHECKED BY

DATE

APPROVED BY

DATE

REVISION

DATE

PB Energy Storage Services, Inc. <small>ENGINEERING - CONSTRUCTION - OPERATIONS - MAINTENANCE</small> <small>A Parsons Brinckerhoff Company</small>	WORKOVER PROGRAM		Number 50756B				
	NYSEG WATKINS GLEN CAES CAVERNS 1,2, & 3 INTERMEDIATE WORKOVER AND SONAR		Date 11/17/2011				
			Page 2 of 7				
<p>14. Rig up the casing crew and tools to pull the 8-5/8" hanging casing.</p> <p>15. Remove approx. 80 ft (estimate 2 joints + hanger joint) of 8-5/8", 32 lb/ft, J-55, LT&C casing. Place casing on location for on-site cleaning, inspection, and re-doping threaded connections. Hang 8-5/8", 32#, J-55, LT&C casing in slips set in annular preventer.</p> <p>16. Rig up wireline unit and run a sonar survey. Rig down wireline unit. Note: Have sonar company zero at bradenhead flange (BHF). Tie in the sonar tool with the cemented casing shoe and CCL (2,360 ft WLM). Take sonar survey at 5 ft stations</p> <p>17. Rig down wireline unit.</p> <p>18. Run in approx. 14 ft (estimate 1 pup joint) of 8-5/8", 32 lb/ft, J-55, LT&C casing plus hanger (setting depth of approx. 2,472 ft.). The J-55 casing connections will be made up to the optimum torque. Externally pressure test (the 32 lb/ft, J-55) to 1,600-psi and hold for 90 seconds as they are run in.</p> <p>19. Note: A digital recorder WILL be run in conjunction with the external tester.</p> <p>20. Land casing using a casing spear dressed for 8-5/8", 32.0 lb/ft casing. Screw in lock down screws located in the top flange of the leaching wellhead B section.</p> <p>21. Nipple down the 13-5/8" well control equipment and install the leaching wellhead C section. Activate and test P-seals (1,600 psi for 15 minutes).</p> <p>22. Nipple up 13-5/8" well control equipment.</p> <p>23. Pick up and run 2,530 ft (estimate 63 joints) of 5-1/2", 17.5 lb/ft, J-55, LT&C casing including hanger. The casing connections will be made up to the torque required to make the triangle on the pin end reach the end of the coupling.</p> <p>24. Land casing using a casing spear dressed for 5-1/2", 17.5 lb/ft casing. Screw in lock down screws located in the top flange of the leaching wellhead C section.</p> <p>25. Nipple down 13-5/8" well control equipment and install leaching wellhead D section. Activate and test P-seals. (1,600 psi for 15 minutes).</p> <p>26. Install the upper portion of the wellhead.</p> <p>27. Re-connect surface piping.</p> <p>28. Rig down and move out the workover rig.</p> <p>29. Close wellhead blanket valve and open nitrogen injection manifold valve. Remove blind from 4" nitrogen injection manifold and connect and test nitrogen injection hoses.</p> <p>30. Cool down nitrogen pumper.</p>							
PREPARED BY JMc	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE

WORKOVER PROGRAM		Number 50756B				
	NYSEG WATKINS GLEN CAES CAVERNS 1,2, & 3 INTERMEDIATE WORKOVER AND SONAR		Date 11/17/2011				
			Page 3 of 7				
<p>31. Inject nitrogen through blanket valve into annulus between 8-5/8" and last cemented casing at temperature of approximately 50° F.</p> <p>32. Contact Inergy Operations to set up cavern for reverse circulation.</p> <p>33. Contact Inergy control room and begin reverse circulation. Increase flow rate to 350 gpm water.</p> <p>34. Rig up wireline contractor to run pulsed neutron interface. Identify nitrogen interface and add or remove nitrogen to achieve interface of 2,420 feet.</p> <p>35. Rig down wireline contractor and nitrogen contractor.</p> <p>36. Close wellhead nitrogen blanket valve, nitrogen injection manifold valves, crown valve, and logging valve.</p> <p>37. Contact Inergy control room when operations are concluded.</p>							
PREPARED BY JMc	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

WORKOVER PROGRAM

Number 50756B

NYSEG WATKINS GLEN CAES CAVERNS 1,2, & 3 INTERMEDIATE WORKOVER AND SONAR

Date 11/17/2011

Page 4 of 7

Attachment 1 Casing Schematics

PREPARED BY JMc	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
--------------------	------	------------	------	-------------	------	----------	------

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

WORKOVER PROGRAM

Number 50756B

NYSEG WATKINS GLEN CAES CAVERNS 1,2, & 3 INTERMEDIATE WORKOVER AND SONAR

Date 11/17/2011

Page 5 of 7

PB - ENERGY STORAGE SERVICES, INC.

NYSEG

CAES Cavern No. 1 - Watkins Glen

DRAWN: JMc

CHECKED:

DATE: 09/19/11

SCALE: NONE

JOB NO. 50756B

PREPARED BY
JMc

DATE

CHECKED BY

DATE

APPROVED BY

DATE

REVISION

DATE

WORKOVER PROGRAM

Number 50756B

NYSEG WATKINS GLEN CAES CAVERNS 1,2, & 3 INTERMEDIATE WORKOVER AND SONAR

Date 11/17/2011

Page 6 of 7

Leaching Wellhead – Cavern No. 1

PREPARED BY
JMc

DATE

CHECKED BY

DATE

APPROVED BY

DATE

REVISION

DATE

**PB Energy
Storage
Services, Inc.**
ENGINEERING • CONSTRUCTION • OPERATIONS • MAINTENANCE
A Parsons Brinckerhoff Company

WORKOVER PROGRAM

Number 50756B

NYSEG WATKINS GLEN CAES CAVERNS 1,2, & 3 INTERMEDIATE WORKOVER AND SONAR

Date 11/17/2011

Page 7 of 7

Attachment 2 - Wellheads Caverns 1, 2, and 3

PREPARED BY
JMc

DATE

CHECKED BY

DATE

APPROVED BY

DATE

REVISION

DATE

NYSEG CAES CAVERNS **CONVERSION WORKOVER PROGRAM**

Number 50756B

Date 11/17/11

Page 1 of 3

A workover is necessary to convert the NYSEG CAES wells from brine production to compressed air energy storage. The steps to complete the conversion basically are: perform preliminary MIT, remove the nitrogen blanket, remove the 5-1/2" and 8-5/8" hanging casings, conduct baseline cased-hole logs, perform an open hole sonar survey, run in an 5-1/2" dewatering casing and install a gas wellhead.

1. Rig up wireline unit and run a density survey with CCL from the casing shoe to approx. 500 ft inside the casing. Zero wireline measurements at bradenhead flange.
2. Open nitrogen valve on leaching wellhead B section and track nitrogen / brine interface. Bleed nitrogen to a depth of approximately 2,380 ft and perform mechanical integrity test.
3. Depressure the nitrogen blanket into the frac atmosphere. Depressurization rate should not exceed 2.5 psi/minute. The operation will take approximately 9 hours.
4. Depressure the freshwater (pressure in 5-1/2" x 8-5/4" annulus) from the well.
5. Remove the wellhead piping. Install 1 (2 total) 4" ANSI 900 flange with 2" threaded connection on both the brine and fresh water side of the wellhead. Install 1 (2 total) 4" ANSI 900 blind flange on the opposite side of each.
6. Install rig anchors per the workover rig requirements.
7. Rig up workover rig. The 5-1/2" casing weight is approximately 46,000 pounds in air (2,630 ft of 5-1/2", 17.5 lb/ft casing. Rig up rig pump and tank.
8. Remove the upper section of the wellhead along with the wellhead brine B section. Nipple up the 13-5/8" well control equipment.
9. Back out lock down screws located in the top flange of the wellhead C section.
10. Pick up a spear dressed for 5-1/2", 15.5 lb/ft casing and run in the hole. Set the spear. Pull 5-1/2" hanger/joint (approx. 46,000 lbs in air. Lay down spear and grapple.
11. Rig up the casing crew and tools to pull the 5-1/2" hanging casing.
12. Remove approx. 2,300 feet of 5-1/2", 17.5 lb/ft, J-55, BT&C casing. Place casing on location for on-site cleaning, inspection, and re-doping threaded connections. Transport the rejected 5-1/2" casing off-site for repairs. Transport remainder of 5-1/2" casing to designated lay down area for future use.
13. Nipple down the 13-5/8" well control equipment. Remove the wellhead C section. Nipple up the well control equipment (annular preventer).
14. Back out lock down screws located in the top flange of the wellhead B section..
15. Pick up a spear dressed for 8-5/8", 32.0 lb/ft casing and run in the hole. Set the spear. Pull casing hanger joint (approx. 80,000 lbs in air) and set in slips in the annular preventor. Lay down spear and grapple.
16. Rig up the casing crew and tools to pull the 8-5/8" hanging casing.

PREPARED BY JMc	DATE 11/17/11	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
--------------------	------------------	------------	------	-------------	------	----------	------

NYSEG CAES CAVERNS **CONVERSION WORKOVER PROGRAM**

Number 50756B

Date 11/17/11

Page 2 of 3

17. Remove approx. 2,530 ft of 8-5/8", BT&C casing. Place casing on location for on-site cleaning, inspection, and re-doping threaded connections. Transport the rejected 8-5/8" casing off-site for repairs. Transport remainder of 8-5/8" casing to designated lay down area for future use.
18. Rig up wireline unit and run a density survey with CCL from the casing shoe to approx. 500 ft inside the casing.
Note: Have wireline company zero at bradenhead flange (BHF).
19. Rig up wireline unit and run a sonar survey. Rig down wireline unit.
Note: Have sonar company zero at bradenhead flange (BHF). Tie in the sonar tool with the casing shoe and CCL. Take sonar survey at 5 ft stations through the entire cavern interval and in the borehole to the cemented casing shoe. Tilt sonar tool and take thorough up shots of the cavern roof.
20. Rig up second wireline unit and run casing and cement evaluation logs (i.e. multi-finger caliper log (Profile Caliper), Vertilog and Segmented Bond Log) on the cemented casing. Rig down wireline unit.
21. Nipple down the 13-5/8" well control equipment.
22. Remove the wellhead B section. Remove the DSA w/pack-off. Nipple up new DSA w/pack-off. Nipple up wellhead B section air annulus casing spool. Activate and test the P-seals (2000-psi for 15 minutes) in the DSA.
23. Nipple up the 21-1/4" well control equipment (2M annular preventer).
24. Rig up a casing crew service and welders and run approx. 2,407' of type 316 stainless steel I PE casing.
25. Land casing liner hanger joint in wellhead B section hanger bowl.
26. Install wellhead C section DSA and master valve. (Ensure that Master Valve Remains Open). Install wellhead D Section.
27. Run in approx. 2,407 ft of 5-1/2", 17.5 lb/ft, J-55, LT&C casing. The 5-1/2" LT&C casing connections will be made up to the optimum torque. Externally pressure test (1,600 psi) the 5-1/2" casing and hold for 2 minutes as they are run in.
Note: A digital recorder **WILL** be run in conjunction with the external tester.
28. Land casing using a casing spear dressed for 5-1/2", 17.5 lb/ft casing. Screw in lock down screws located in the top flange of the wellhead D section.
29. Nipple down the 21-1/4" well control equipment and install the wellhead D section w/pack-off. Activate and test P-seals (1600-psi for 15 minutes).
30. Install the upper portion of the wellhead F section.
31. Rig down and move out the workover rig.
32. Rig up wireline unit and nitrogen injection unit.

PREPARED BY JMc	DATE 11/17/11	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
--------------------	------------------	------------	------	-------------	------	----------	------

NYSEG CAES CAVERNS
CONVERSION WORKOVER PROGRAM

Number 50756B

Date 11/17/11

Page 3 of 3

33. Perform nitrogen mechanical integrity test of the well. Warning, nitrogen must be injected simultaneously down the stainless steel nitrogen annulus and inside the stainless steel liner to prevent liner collapse.
34. Rig down MIT equipment, pipe wellhead, and begin dewatering operations.

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
JMc	11/17/11

NYSEG CAES CAVERNS SNUBBING PROGRAM

Number 50756B

Date 11/17/11

Page 1 of 2

This program presents the proposed steps for snubbing the 5-1/2" dewatering string out the NYSEG CAES caverns after dewatering and installing the final production wellhead. The caverns are located in Schuyler County New York near the town of Watkins Glen.

These steps are intended as a guideline for the snubbing operation. Actual conditions encountered during the work will dictate the appropriate steps to be taken. The basic steps involved in the operations are:

- Remove dewatering piping from wellhead and the logging valve assembly above the F section valve.
- Install two bridge plugs near the bottom of the casing.
- Rig up and snub 5-1/2" casing out.
- Close master valve and remove all wellhead components above the master valve.
- Install the final wellhead components.

SNUBBING PROGRAM

1. Snubbing supervisor will inspect the well to verify snubbing operations setup.
2. Install rig anchors, anchor blocks or beam for anchoring snubbing unit (if necessary).
3. Move in and rig up a wireline unit with pressure control equipment and run a gauge ring for running 5-1/2" bridge plugs. If gauge ring will not pass through the cavern interval run caliper log to determine casing deformation and clearances. If casing deformation is excessive the program will have to be revised to address these conditions.
4. Run in hole with wireline bridge plug and set within bottom 10' of last 5-1/2" joint.
5. Bleed off tubing pressure to verify plug is holding.
6. Fill 5-1/2" casing with water then run in and set second bridge plug approximately 5' above the first plug.
7. Move in rig assist snubbing unit, BOP stack, hydraulic cranes, and miscellaneous snubbing equipment.
8. Nipple up BOP stack on top of F section valve and rig up cranes and rig assist snubbing unit.
9. Test BOP's to 2000 psig.
10. Release hold down pins from wellhead D section.
11. Make up a spear for 5-1/2", 17.5 lb/ft casing and spear hanger joint.
12. Lift casing string up to work basket and lay down hanger joint.
13. Snub out 5-1/2" casing.
14. Close 20" Master valve. Verify that valve is holding.
15. Nipple down BOP's and snubbing unit.

PREPARED BY
JMc

DATE
11/17/11

CHECKED BY

DATE

APPROVED BY

DATE

REVISION

DATE

NYSEG CAES CAVERNS
SNUBBING PROGRAM

Number 50756B

Date 11/17/11

Page 2 of 2

16. Nipple down wellhead D section and install production wellhead.
17. Rig down and move out snubbing unit and associated equipment.
18. Turn over wellpad to NYSEG for well piping.

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
JMc	11/17/11

OPEN HOLE LOGGING

Number 50756B

NYSEG WATKINS GLEN CAES WELLS

Date 11/11

Page 1 of 2

OPEN HOLE LOGGING REQUIREMENT

Surface Hole:

17 1/2" Pilot Hole

1. Resistivity Log w/ SP and Gamma Ray
2. Compensated Neutron Log (Porosity)
3. Litho Density Log
4. Full Wave Sonic/Monopole sonic/Dipole Sonic Log.

After Opening Hole

1. Run a 60" (X-Y) Caliper Log. The 60" (X-Y) Caliper Log is to have a volume totalizer.

Production Hole:

17-1/2" Pilot Hole

1. Resistivity Log w/ SP and Gamma Ray.
2. Compensated Neutron Log (Porosity).
3. Litho Density Log.
4. Full Wave Sonic/Monopole Sonic Dipole Sonic Log

After Opening Up Hole

1. Run a 60" (X-Y) Caliper Log. The 60" (X-Y) Caliper Log is to have a volume totalizer.

PREPARED BY	DATE	CHECKED BY	DATE	APPROVED BY	DATE	REVISION	DATE
JMc	11/11					0

16285 Park Ten Place, Suite 400
Houston, Texas 77084

(281) 496-5590
Fax (281) 496-5865
www.pbenergy.com

December 13, 2011

James W. Rettberg, PE
Project Manager
NYSEG

Dear Mr. Rettberg;

Re: Dewatering Plan for NYSEG CAES Caverns

Introduction

Task 4.4.2.3 of the Technical Specification for the Cavern Development Consultant is to prepare a Preliminary Design for Cavern Dewatering System.

Cavern Description

NYSEG proposes to develop 3 storage caverns, each with a dewatered volume of approximately 970,000 bbl. The caverns are to be solution mined on property owned by Inergy near the U.S. Salt Refinery near Watkins Glen, NY. The caverns are designed to have a roof depth of approximately 2,402 ft below ground surface and a floor depth of approximately 2,527 ft. Brine string placement for dewatering is proposed to be at 2,525 ft.

Dewatering Plan

At the completion of solution mining a workover will take place to install the stainless steel cavern air injection string to a depth just below the cavern roof and a 5-1/2" dewatering string. Following the workover the cavern will undergo mechanical integrity testing at a nominal pressure of 1,500 psi (surface pressure). The mechanical integrity test will require that nitrogen be pumped down the inside and outside of the stainless steel air injection tubing to prevent collapse.

Following the mechanical integrity testing the cavern must be dewatered at a rate of approximately 350 gpm to Inergy. The wellhead configuration (provided in the Cavern Development Plan) will have a 20" isolation valve in place with a 5-1/2" tubing hanger positioned above the valve. The 20" valve must remain open until the dewatering string is snubbed from the cavern at the end of dewatering.

Due to the low dewatering rate portable diesel driven compressors will be used during the nominal 80 day dewatering period. A sketch of the proposed compressor arrangement for dewatering is provided in Figure 1. The maximum air pressure anticipated at the surface to dewater the cavern is 1,295 psia and the maximum air flow rate anticipated is approximately

3,750 scfm. A chart showing the surface air pressure and compressor volume flow rate is provided in Figure 2. Since the cavern interval is short (approximately 123 ft) very little dewatering pressure change will occur after the air / brine interface reaches the cavern roof.

As air is injected into the well the air / brine interface will fall as the pressure in the cavern increases and brine will be displaced. Figure 3 shows the interface and dewatered volume plotted change during the dewatering process.

Please do not hesitate to call or email if you have questions or suggestions.

Regards,

A handwritten signature in blue ink that reads "James M. McHenry". The signature is written in a cursive style with a large, stylized "M" and "H".

James M McHenry

Schematic Flow Diagram Compressed Air Manifold System

NYSEG CAES
Watkins Glen, NY
Figure 1 Dewatering Layout

Figure 2 Compressor Performance

Figure 3 Dewatering Time

CAVERN TESTING PROGRAM

CAES STORAGE CAVERN

Watkins Glen, NY

Prepared for

NYSEG

Binghamton, New York

Prepared by

PB ENERGY STORAGE SERVICES, INC.

Houston, TX

Project No. 50756B

November 2011

TABLE OF CONTENTS

SECTION	PAGE
1.0 INTRODUCTION	1
2.0 NITROGEN/BRINE INTERFACE METHOD	1
2.1 Minimum Detectable Leak Rate	2
2.2 Gas Volume Calculations	3
2.3 Calculated Leak Rate (CLR)	5
3.0 CASING INSPECTION	6
3.1 Digital Vertilog	6
3.2 Multi-Finger Imaging Caliper	7
3.3 Gyroscopic Survey	7

CAVERN TESTING PROGRAM WATKINS GLEN CAES FACILITY

1.0 INTRODUCTION

This document describes the required cavern integrity testing that must take place before the cavern can be dewatered. Mechanical integrity testing of a storage cavern consists of two distinct parts. The first part of the testing is a nitrogen test of the cavern to determine gross leakage. The second part of the testing is an inspection of the well casing.

Each of the NYSEG CAES caverns will undergo nitrogen mechanical integrity testing twice. The first test will take place after the completion of leaching, but prior to the start of the final configuration workover. This test will be performed to ascertain the integrity of the cavern prior to running the welded stainless steel liner. The test will be performed by bleeding off a portion of the nitrogen blanket and establishing an interface in the borehole below the casing shoe.

After the final configuration workover is completed, the stainless steel liner has been run, and the dewatering wellhead is in place the cavern will undergo its final nitrogen mechanical integrity testing. For this test of the cavern it will be necessary to inject nitrogen simultaneously down the inside of the stainless steel liner and down the annulus to prevent liner collapse.

2.0 NITROGEN/BRINE INTERFACE METHOD

The purpose of performing a mechanical integrity test is to determine if the cavern system has mechanical integrity, and is therefore suitable for storage. The detailed nitrogen/brine interface test procedure will be developed prior to testing. The procedure involves an initial injection of nitrogen into the well to check for wellhead and casing leaks. This initial injection is followed by continued injection of nitrogen into the storage well to a specified test pressure so that the nitrogen interface is below the last cemented casing. The nitrogen interface depth can be affected by pressure and temperature changes caused by temperature equilibration, cavern leaching, and salt creep effects. In order to distinguish between these effects, and nitrogen volume losses caused by leaks, the pressure and temperature changes (as they affect nitrogen volume) must be considered.

The nitrogen (annulus) and brine (tubing) pressure and interface depth are monitored during the test period. Evaluation of the test results involves calculating the volume of nitrogen to the interface at the start of the test and at the end of the test. The difference in calculated volumes over the test period yields an apparent volume change. The integrity of the well can be confirmed if the calculated nitrogen volume change (loss/gains) is within the accuracy limits of the test method. An annual leak rate can be determined by extrapolating (linearly) the calculated change in nitrogen volume during the defined interval of the test period (minimum 24 hours).

2.1 MINIMUM DETECTABLE LEAK RATE

The minimum detectable leak rate (MDLR) is the smallest volume of gas loss that can theoretically be measured considering the accuracy of the interface log and the configuration of the well. The actual accuracy achievable in the field may be slightly less than the MDLR, but is of the same order of magnitude, and therefore the MDLR gives a good indication of the test sensitivity. The MDLR can be calculated using the following relationship:

$$MDLR = \frac{V \bullet r \bullet 365}{T}$$

Where:

MDLR = Minimum Detectable Loss Rate (bbls/year)

V = Unit Volume of Borehole (bbls/ft)

r = Resolution of Interface Detection (ft)

T = Duration of Test (days)

The resolution of the interface detection tool is determined from the logging tool and the depth scale used to record the interface log. The borehole volume versus depth is calculated from the metered volume of nitrogen injected, combined with the corresponding interface location. The wellhead pressure and the nitrogen temperature are also used in the calculations.

2.2 GAS VOLUME CALCULATIONS

In addition to measured quantities, knowledge of the well casing and tubular sizes and the diameter of the wellbore from the casing shoe to the interface (from logs), allows the nitrogen volume to be estimated. The following P-V-T gas equation is used to calculate the volume of nitrogen (at standard temperature and pressure conditions) in the wellbore at the start and at the end of the test:

$$V_{N_2} = N_{SCF} \cdot \sum_i^N \left[\frac{(P_{WB})_i \cdot 144 \cdot (V_{WB})_i}{[(Z_{AVE})_i \cdot R \cdot (T_{AVE})_i]} \right]$$

Where:

V_{N_2} = Volume of nitrogen measured in the wellbore over a specific depth interval “ i ” (scf)

$(P_{WB})_i$ = Average calculated wellbore pressure over a specific depth interval “ i ” (psia)

$(V_{WB})_i$ = Volume of wellbore of a specific depth interval “ i ” (ft³)

NOTE: Determined by wellbore geometry, measured nitrogen volumes, and cavern sonar surveys

$(Z_{AVE})_i$ = Gas Compressibility Factor at a specific depth interval¹ “ i ” (dimensionless)

R = Specific Gas Constant $\left[55.16 \left(\frac{(ft \cdot lb_f)}{(lbmol \cdot ^\circ R)} \right) \right]$

$(T_{AVE})_i$ = Average wellbore temperature over a specific depth interval “ i ” (°R)

(N_{SCF}) = Gas Conversion for mass to volume at standard pressure and temperature conditions
(13.8 SCF_{N2} = 1 lb_{N2})

$i = 1, 2, \dots, N$, N = total number of depth intervals

¹Compressibility Factor (Z) research developed in NOWSCO Technical Manual, NOWSCO Services, 1980

The following equation is used to determine pressure at depth interval “*i*”:

$$P_i = P_{i-1} \left[1 + \frac{L}{RZ_i T_i} \right]$$

$$i = 1, 2, \dots, N$$

Where:

P_i = Calculated pressure at a specific depth “*i*” (psia)

P_1 = Measure wellhead pressure (psia)

L = Depth Interval (ft)

Z_i = Gas Compressibility Factor at a specific depth interval “*i*” (dimensionless)

$$R = \text{Specific Gas Constant} \left[55.16 \left(\frac{(ft \bullet lb_f)}{(lbmol \bullet ^\circ R)} \right) \right]$$

T_i = Measure wellbore temperature at a specific depth interval “*i*” (°R)

The volume calculation is performed for specific intervals throughout the wellbore from the surface to the interface. The total wellbore volume is determined by summing the specific volume for each regular interval.

The results of the volume and mass calculations (both “pre-test” and “post-test”) are tabulated. The difference between the initial and final volume calculation determines the volume change at standard conditions.

It is important to note that the measured volume of nitrogen may not be equal to the calculated volume of nitrogen in the wellbore. The accuracy of the metered nitrogen is based on the accuracy of the turbine and temperature measurement made during nitrogen injection. The calculated test volumes are based on downhole temperature logs, surface pressure recorders, calculated downhole pressures, and borehole dimensions determined by nitrogen strapping

calculations or sonar volumes. All measurements are subject to the accuracy of the instrumentation being used and the well conditions at the time of the measurements.

At average wellbore conditions (at the conclusion of the test), the nitrogen volume change can be stated as:

$$\Delta V_{TEST} = \left(\frac{[(Z_{AVE}) \cdot R \cdot (T_{AVE}) \cdot (\Delta V_{STP})]}{[(P_{WB})_{AVE} \cdot 144 \cdot N_{SCF}]} \right)$$

Where:

ΔV_{TEST} = nitrogen volume changes over the test period based on wellbore conditions (ft³)

$(P_{WB})_{AVE}$ = Average wellbore pressure over the test period (psia)

(ΔV_{STP}) = Nitrogen volume change (scf), based on standard conditions

(Z_{AVE}) = Average Gas Compressibility Factor over the test period

R = Specific Gas Constant $\left[55.16 \left(\frac{(ft \cdot lb_f)}{(lbmol \cdot ^\circ R)} \right) \right]$

(T_{AVE}) = Average wellbore temperature over the test period (°R)

(N_{SCF}) = Gas Conversion (13.8 SCF_{N2} = 1 lb_{N2})

2.3 CALCULATED LEAK RATE (CLR)

The equation below is used to calculate the annual calculated leak rate (CLR) from the volume change in nitrogen for the specified test period:

$$V_{CLR} = \frac{[(\Delta V_{TEST}) \cdot 24(hours / day) \cdot 365(days / year)]}{T_L}$$

Where:

$$V_{CLR} = \text{CLR (bbls/year)}$$

$$\Delta V_{TEST} = \text{Nitrogen volume change during the test period (bbls)}$$

$$T_L = \text{Test Duration (hours)}$$

A positive CLR indicates a calculated loss of nitrogen from the wellbore during the test period. A negative CLR indicates a calculated increase in nitrogen volume during the test period.

The evaluation of the MIT consists of comparing the CLR with the MDLR. The results are expressed in barrels of nitrogen per year. When the CLR is less than the MDLR, no leak has been detected by the test. If the CLR is greater than the MDLR, further investigation is required, as the CLR cannot be explained by the limitations of the test equipment.

3.0 CASING INSPECTION

While the suspended casing is out of the well casing evaluation logs should be run to establish a baseline. The baseline will allow comparisons of casing condition for compliance with future mandated inspection of the cemented casing. A digital Vertilog, a multifinger caliper survey, and a gyroscopic survey should be performed. Due to the size of the well for the first cavern the digital Vertilog will be run of only Caverns 2 and 3.

3.1 DIGITAL VERTILOG

This survey uses a tool that generates an electromagnetic field that permeates the casing walls as it is pulled up through the casing. Defects in the casing wall will cause a leakage in this electromagnetic field or “flux” that can be measured and quantified to determine percentage of metal loss in the body of the pipe.

The Vertilog Service uses magnetic flux leakage measurements to identify and quantify the extent and penetration depth of both internal and external corrosion defects. The combination of an overlapping array of flux leakage (FL) sensors and two discriminator (DIS) sensor arrays

provides full circumferential inspection of the tubing or casing string, allows for differentiating between metal loss (corrosion) and metal gain , and distinguishes between general corrosion and isolated pitting.

Defects in the casing wall as small as 3/8” in diameter can be identified using this technique. Casing sizes from 13-3/8 to 22 in. can be evaluated. Once a baseline is established, the technique can be used to detect corrosion and depth of penetration. The tool provides 360 degree identification and quantification of small, isolated casing defects in real-time or memory mode

3.2 MULTI-FINGER IMAGING CALIPER

This survey uses a multi-finger caliper to measure the ID of the last cemented casing. The multi-finger caliper tool mechanically measures the inside diameter of downhole casing. Two channels of information are recorded at the surface. One recording shows the minimum measured internal radius and the other shows the maximum measured internal radius. When the casing is relatively new, the Multi-Finger Caliper Log reveals the casing's minimum and maximum inside diameter. This information is useful for determining whether there is abnormal casing wear caused by the rubbing of drill pipe on the inside casing wall.

3.3 GYROSCOPIC SURVEY

This survey uses a logging tool with a gyroscopic compass and inclination sensor to measure the well deviation and direction of the deviation every 25 feet from the surface down to the bottom of the last cemented casing. This information is necessary to establish the location of the casing shoe and ultimately the location of the cavern walls in space.

CONSTRUCTION EXECUTION PLAN

CAES STORAGE CAVERN

Watkins Glen, NY

Prepared for

NYSEG

Binghamton, New York

Prepared by

PB ENERGY STORAGE SERVICES, INC.

Houston, TX

Project No. 50756B

November 2011

TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1.0 INTRODUCTION.....	1
2.0 CONSTRUCTION MANAGEMENT	1
3.0 CONSTRUCTION SCHEDULE.....	3
4.0 CONSTRUCTION TASK SEQUENCE.....	4
5.0 ENVIRONMENTAL SAFETY AND HEALTH.....	5
6.0 QUALITY ASSURANCE	6

CONSTRUCTION EXECUTION PLAN WATKINS GLEN CAES FACILITY

1.0 INTRODUCTION

NYSEG proposes to develop a compressed energy storage (CAES) project near Watkins Glen, NY which has a rated generating capacity of 180 MW. The storage chamber for the compressed air will consist of three nominal 970,000 barrel caverns developed in the F Salt Unit of the Salina Formation. The storage caverns are planned for development in the interval between 2,402 ft and 2,632 ft below ground surface and will be developed using solution mining methods. The total duration of the drilling and cavern development is estimated to be 7.4 years. The NYSEG CAES cavern development project is unique, and will require a high level of supervision and monitoring.

This construction execution plan describes the strategy to be employed for executing and managing activities required to build 3 storage caverns at the NYSEG Site near Watkins Glen, NY. Elements of this plan include:

- Construction Management
- Construction Schedule
- Construction Task Sequence
- Environmental Safety and Health
- Quality Assurance

2.0 CONSTRUCTION MANAGEMENT

The drilling, completion, cavern development monitoring, and testing required for construction of the NYSEG caverns will require the services of a specialty construction contractor. The Cavern Construction Manager will be responsible for all activities required to drill and complete the wells, solution mine the storage caverns, and prepare the storage caverns for CAES service. The contractor selected will require expertise in drilling and completion of large diameter gas storage wells in salt and the solution mining of storage caverns in salt.

The Construction Manager should be engaged as soon as possible after the decision has been made by NYSEG to proceed with the project. This early engagement will be required to locate, schedule, and place under contract, a drill rig capable of drilling the NYSEG wells. Acquisition of the drilling subcontractor is a critical path item in the cavern construction schedule.

The Construction Manager will be responsible for identifying available drill rigs which are capable of drilling the large diameter holes required by NYSEG and contracting with a drilling subcontractor for drilling all cavern storage wells. Based upon the drill rig capabilities the Construction Manager will provide drilling engineering services to prepare a final drilling program and specifications for major services required during drilling. The Construction Manager will solicit quotations from prequalified subcontractors, issue contracts with the various vendors to supply materials and services required for drilling and completing all storage wells, and coordinate all services.

Table 1 is a list of the major specifications for services required for drilling, which the Construction Manager will be required to prepare prior to drilling operations.

Table 1 - Required Major Services For Drilling NYSEG Wells

1. Final Casing Specifications
2. Casing Crew Services Specification
3. Cement Evaluation Logging Specification
4. Cementing Hardware Specification
5. Cementing Services Specification
6. Coring Services Specification
7. Double Jointing Services Specification
8. Drilling Bits Specification
9. Drilling Fluids Services Specification
10. Drilling Rig Services Specification
11. External Casing Testing Services Specification
12. Gyro Survey Services Specification
13. Hole Openers Specification
14. Lift Rings Specification
15. Miscellaneous Rentals Specification
16. Nitrogen Pumping Services Specification
17. Open Hole Logging Services Specification
18. Shock Subs Services Specification
19. Solids Control Equipment Services Specification
20. Solids Handling and Disposal Services Specification
21. Stabilizer Services Specification
22. Under-reamer Services Specification
23. Vertitrak Services Specification

24. Welding Services Specification

25. Wellpad Construction Services Specification

The Construction Manager will provide resident drilling supervision at the wellsite on a 24 hour per day basis during mobilization, drilling, completion, and demobilization. The drilling supervisor will be responsible for coordination of subcontractor activities, daily progress reporting, and wellsite safety. The drilling supervisors used by the Construction Manager shall be thoroughly experienced in the drilling and completion of large diameter gas storage wells in salt.

The Construction Manager will provide workover supervision services required to perform well workovers for the intermediate workovers, the conversion workovers, and during final wellhead installation.

The MIT, planning, execution, data interpretation, and report preparation.

The construction contractor will provide onsite workover supervision during all workovers and wireline operations. Workover supervisors will be thoroughly experienced in well workover and storage well field intervention operations.

Construction supervisor will provide cavern engineering services required to evaluate data collected by Inergy, monitor solution mining progress, evaluate wireline logging results, and perform solution mining modeling and solution mining program adjustments after sonar surveys and open hole logging.

3.0 CONSTRUCTION SCHEDULE

The schedule submitted by PB ESS for cavern development is based upon an assumed start date of 12/06/2013 for wellpad construction. The actual start of drilling is dependent on the availability of a drill rig of adequate capacity to drill Well No. 1 (24" cemented casing). The schedule assumes that the three wells will be drilled sequentially, one immediately following the other, to ensure that the availability of drill rigs will not impact development of Caverns 2 & 3. Due to high demand for drilling rigs in the Marcellus, PB ESS recommends that a firm commitment be made by NYSEG to a drilling subcontractor at the earliest possible date.

Wellhead components and stainless steel liners will require delivery times of approximately one year. Due to uncertainties in delivery and fabrication time these items should be considered long lead items and should be ordered at the earliest possible date. Tubulars should be welded

into 80 foot lengths prior to shipment to the drill site to decrease the rig time required to run the stainless steel liner. The fabrication of the bradenhead flanges should be considered as part of the critical path since they will be required prior to well completion.

The cavern development schedule will require monthly update and tracking once the drill rig mobilizes. Due to the geologic uncertainties associated with drilling of large diameter wells and the solution mining of storage caverns unplanned schedule delays can occur. Schedule variances will be reported to NYSEG on a monthly basis.

4.0 CONSTRUCTION TASK SEQUENCE

The overall construction sequence for building the NYSEG caverns is listed below as Table 2.

Table 2 - Construction Sequence

1. Order wellhead components and long lead stainless steel tubulars.
2. Subcontract drilling rig services.
3. Build drilling access road.
4. Subcontract required major drilling services.
5. Build wellpad.
6. Mobilize drilling rig and drill well.
7. Demobilize drilling rig to next hole or off site if all wells drilled.
8. Install wellpad piping and connect to Inergy piping.
9. Hydrotest wellpad piping.
10. Inject nitrogen blanket.
11. Perform data analysis on weekly basis to estimate cavern development progress.
12. Perform periodic blanket interface checks and adjust nitrogen volume as required.
13. Bleed nitrogen blanket, perform sonar survey, and perform workover to adjust tubing lengths.
14. Inject nitrogen blanket.
15. Leach cavern in reverse.
16. Perform blanket interface surveys as required.
17. Perform casing cuts as required.
18. Perform through pipe sonar surveys after each leaching stage and revise solution mining models as required.
19. At completion of leaching bleed nitrogen back to establish interface in borehole.
20. Perform preliminary MIT.

21. Bleed nitrogen from well and perform conversion workover.
22. Perform mechanical integrity test.
23. Connect temporary compressors and inject air, displacing brine from cavern.
24. Snub dewatering string from well.
25. Install remaining wellhead components
26. Solution mine remaining wells.

5.0 ENVIRONMENTAL SAFETY AND HEALTH

All drilling and construction personnel shall observe and enforce all applicable governmental safety regulations and all safety rules that have been or are established during performance of this agreement

Each subcontractor employee is required to complete Basic Orientation Plus® training, which is developed and administered through the Association of Reciprocal Safety Council's Inc. or an OSHA 10-Hour Construction Industry Outreach training course.

Subcontractor shall provide a Safety Meeting prior to beginning work. Additional "Tailgate Safety Meetings" shall be held on a weekly basis, covering work related safety topics. Subcontractor shall require that all personnel attend meetings and shall provide documentation of this attendance and meeting topics to the Construction Manager

On a daily basis, subcontractors shall develop Job Safety Analysis (JSA) forms for each major work activity. The JSA must list each step for the job, the hazards associated with each step and steps to mitigate each hazard. Any time that the scope of the job changes, the JSA must be revised or a new one must be written.

Subcontractor must notify the Construction Manager, as soon as is reasonably possible, of all injuries that occur during performance of and relative to work performed for NYSEG. A written report of each injury must be submitted to the Construction Manager within 24 hours of the injury.

If services to be performed requires subcontractor to bring chemicals or hazardous products onto the job site, subcontractor must post an inventory of and accurate material Safety Data Sheets for such materials at the job site. All materials brought onto the job site must be properly labeled, handled and stored to comply with OSHA Hazard Communication Standard.

6.0 QUALITY ASSURANCE

The Construction Manager shall have in place a quality assurance program that meets the standards set forth in ISO 9000. Subcontractors shall perform the work in a quality manner using qualified, efficient and careful workers; in accordance with NYSEG project management plans, quality plans, drawings, and specification; in compliance with all applicable quality, environmental and safety rules and regulations; in a manner to protect the work and NYSEG's property from damage, and the property and persons or others from injury or loss arising in conjunction with the contract and as not to interfere with operations of others on the premises.

NYSEG
CAES Project Schedule
Watkins Glen, NY

Project: 50756B NYSEG CAES
Date: Tue 6/5/12

Task

Milestone

Rolled Up Task

Rolled Up Progress

External Tasks

Group By Summary

Progress

Summary

Rolled Up Milestone

Split

Project Summary

Deadline

NYSEG
CAES Project Schedule
Watkins Glen, NY

Project: 50756B NYSEG CAES
Date: Tue 6/5/12

Task

Milestone

Rolled Up Task

Rolled Up Progress

External Tasks

Group By Summary

Progress

Summary

Rolled Up Milestone

Split

Project Summary

Deadline

NYSEG
CAES Project Schedule
Watkins Glen, NY

Project: 50756B NYSEG CAES
Date: Tue 6/5/12

Task

Milestone

Rolled Up Task

Rolled Up Progress

External Tasks

Group By Summary

Progress

Summary

Rolled Up Milestone

Split

Project Summary

Deadline

NYSEG
CAES Project Schedule
Watkins Glen, NY

Project: 50756B NYSEG CAES
Date: Tue 6/5/12

Task

Milestone

Rolled Up Task

Rolled Up Progress

External Tasks

Group By Summary

Progress

Summary

Rolled Up Milestone

Split

Project Summary

Deadline

NYSEG
CAES Project Schedule
Watkins Glen, NY

ID	Task Name	Duration	Start	2012				2013				2014				2015				2016				2017				2018				2019				2020				2021																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
				Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
235	Through Pipe Sonar	1 day	Fri 7/17/20

Project: 50756B NYSEG CAES
Date: Tue 6/5/12

Task

Milestone

Rolled Up Task

Rolled Up Progress

External Tasks

Group By Summary

Progress

Summary

Rolled Up Milestone

Split

Project Summary

Deadline

Cavern Construction Cost Estimate

NYSEG CAES - Watkins Glen NY

Description:	Overnight Cost	Cost Basis	Contract Date	Delivery / Completion Date	Duration (Days)
Material					
Stainless Steel Air Pipe and Wellheads	\$ 5,345,000	20-Oct-11	6-Jan-12	5-Jan-13	365
Total - Bulks	\$ 5,345,000				
Subcontract					
Wellpad 1	\$ 562,000	20-Nov-11	13-Dec-13	12-Jan-14	30
Drilling No. 1	\$ 7,771,000	20-Nov-11	19-Jan-14	4-Apr-14	75
Piping and Blanket No. 1	\$ 191,000	20-Nov-11	9-Apr-14	14-Apr-14	5
Intermediate W/O and Blanket No. 1	\$ 175,000	20-Nov-11	22-Aug-14	30-Aug-14	8
Sonar and Blanket No. 1	\$ 56,000	20-Nov-11	28-Jan-15	29-Jan-15	1
Sonar and Blanket No. 1	\$ 56,000	20-Nov-11	28-Jun-15	29-Jun-15	1
Sonar No. 1	\$ 25,000	20-Nov-11	26-Nov-15	27-Nov-15	1
Final Configuration W/O No. 1	\$ 1,178,000	20-Nov-11	5-Apr-16	10-May-16	35
Snub No. 1	\$ 194,000	20-Nov-11	9-Aug-16	13-Aug-16	4
Final Wellhead Install No. 1	\$ 61,980	20-Nov-11	13-Aug-16	18-Aug-16	5
Wellpad No. 2	\$ 562,000	20-Nov-11	12-Jan-14	11-Feb-14	30
Drilling No. 2	\$ 7,233,000	20-Nov-11	16-Apr-14	27-Jun-14	72
Piping and Blanket No. 2	\$ 191,000	20-Nov-11	2-Jul-14	7-Jul-14	5
Intermediate W/O and Blanket No. 2	\$ 175,000	20-Nov-11	17-Dec-16	26-Dec-16	9
Sonar and Blanket No. 2	\$ 56,000	20-Nov-11	25-May-17	26-May-17	1
Sonar and Blanket No. 2	\$ 56,000	20-Nov-11	23-Oct-17	24-Oct-17	1
Sonar No. 2	\$ 25,000	20-Nov-11	23-Mar-18	24-Mar-18	1
Final Configuration W/O No. 2	\$ 1,100,000	20-Nov-11	1-Aug-18	4-Sep-18	34
Snub No. 2	\$ 194,000	20-Nov-11	04-Dec-18	08-Dec-18	4
Final Wellhead Install No. 3	\$ 61,980	20-Nov-11	8-Dec-18	13-Dec-18	5
Wellpad No. 3	\$ 562,000	20-Nov-11	11-Feb-14	13-Mar-14	30
Drilling No. 3	\$ 7,067,000	20-Nov-11	9-Jul-14	13-Sep-14	66
Piping and Blanket No. 3	\$ 191,000	20-Nov-11	18-Sep-14	23-Sep-14	5
Intermediate W/O and Blanket No. 3	\$ 175,000	20-Nov-11	13-Apr-19	22-Apr-19	9
Sonar and Blanket No. 3	\$ 56,000	20-Nov-11	19-Sep-19	20-Sep-19	1
Sonar and Blanket No. 3	\$ 56,000	20-Nov-11	17-Feb-20	18-Feb-20	1
Sonar No. 3	\$ 25,000	20-Nov-11	17-Jul-20	18-Jul-20	1
Final Configuration W/O No. 3	\$ 1,100,000	20-Nov-11	25-Nov-20	28-Dec-20	33
Snub No. 3	\$ 194,000	20-Nov-11	29-Mar-21	2-Apr-21	4
Final Wellhead Install No. 3	\$ 61,980	20-Nov-11	2-Apr-21	4/7/2021	5
Subtotal - Services	\$ 29,412,000				
Operations and Maintenance					
Inergy Labor	\$ 999,000	20-Nov-11	14-Apr-14	25-Nov-20	2417
Engineering Labor	\$ 196,000	20-Nov-11	14-Apr-14	25-Nov-20	2417
Miscellaneous Maintenance	\$ 688,000	20-Nov-11	14-Apr-14	25-Nov-20	2417
Operations Total	\$ 1,883,000				
Total Estimate	\$ 36,640,000				
Total Estimate (Rounded)	\$ 36,640,000

10/31/2011

PB Energy Storage Services, Inc. Cost Estimate

TITLE NYSEG Seneca CAES Project				ESTIM TYPE	10 Percent	ESTIMATOR:		KS/Jm	REVIEWER:		JM	REV:		
				DISCIPLINE	All	DATE:		12/07/11	DATE:		12/07/11	DATE:		12/07/11
LINE NO	COVER SHEET Wellpad and Road	QTY	UNIT	UNIT MHRS	TOT MHRS	UNIT COST				TOTAL COST				TOTAL
						LABOR	MATL	EQUIP	SUBCON	LABOR	MATL	EQUIP	SUBCON	
1	DIVISION 1 - GENERAL REQUIREMENTS													
2	Labor & Services (1A-1)				2,016					60,896	-	-	5,000	65,896
3	Construction Plant (1A-1)									-	8,850	-	5,000	8,850
4	Construction Equipment (1B-1)				-					-	-	58,800	-	58,800
5														
6	DIVISION 2 - SITE WORK				8,654					258,308	212,338	284,639	-	774,784
7	DIVISION 3 - CONCRETE				-					-	-	-	-	-
8	DIVISION 5 - METALS				-					-	-	-	-	-
9	DIVISION 9 - FINISHES				-					-	-	-	-	-
10	DIVISION 13 - SPECIAL CONSTRUCTION				-					-	-	-	-	-
11	DIVISION 15 - MECHANICAL				-					-	-	-	-	-
12	DIVISION 16 - ELECTRICAL				-					-	-	-	-	-
13	DIVISION 100 - PROCESS EQUIPMENT				-					-	-	-	-	-
14														
15														
16														
17														
18	SUB-TOTAL				10,670					319,203	221,188	343,439	10,000	908,329
19														
20														
21	Benefits & Burdens	34%	(of Labor)											108,529
22	Sm. Tools & Consumables	2%	(of Div 2 - 16)											18,167
23	SUB-TOTAL													1,035,025
24														
25	Business Tax (4.166% Subtotal)	8.00%	(of Subtotal)											82,802
26	SUB-TOTAL													1,117,827
27														
28	Contractor's Overhead	10%	(of Contract)											143,311
29	SUB-TOTAL													1,261,138
30														
31	Contractor's Profit	10%	(of Contract)											143,311
32	SUB-TOTAL													1,404,450
33														
34	Bond	2%	(of Contract)											28,662
35	TOTAL CONSTRUCTION COST													1,433,112
36	Engineering, Design & Inspection	7%	(of Contract)											100,318
37	SUB-TOTAL													1,533,430
38	Contingency & Changes	10%	(of Subtotal)											153,343
39	TOTAL JOB COST													1,686,773
40	ROUNDED TO													1,686,800

NYSEG Cavern No. 1 Cost Estimate for MIT 2011 COST ESTIMATE		10/2/2011 Est By: JMc
ITEM	Budget Estimate	
01 MANAGEMENT COST		
01 LABOR - OFFICE	\$6,380	
02 LABOR - FIELD	\$0	
03 EXPENSES	\$2,125	
04 MISCELLANEOUS (PRESSURE RECORDERS)	\$3,000	
SUBTOTAL - 01 MANAGEMENT COST	\$11,505	
02 SERVICES AND RENTALS		
01 LOCATION	\$0	
02 MOBILIZATION/DEMOBILIZATION	\$0	
03 RIG	\$0	
04 FUEL	\$0	
05 WATER	\$0	
06 DRILLING FLUIDS	\$0	
07 BITS	\$0	
08 RENTAL TOOLS (LOGGING FLANGES)	\$1,500	
09 DIRECTIONAL DRILLING	\$0	
10 CEMENT, CEMENT SERVICES, HARDWARE	\$0	
11 LOGGING & WIRELINE SERVICES (1 TRIP)	\$31,250	
12 CORING & CORE ANALYSIS	\$0	
13 WORKOVER RIG	\$0	
14 PERFORATING	\$0	
15 STIMULATION, NITROGEN, PUMP TRUCKS	\$20,000	
16 CASING PULLING & RUNNING SERVICES	\$0	
17 WELDING	\$0	
18 WELLHEAD REPLACEMENT, TESTING, & REPAIR SERVICES	\$0	
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION	\$0	
20 MISCELLANEOUS MATERIALS & SUPPLIES	\$0	
21 MISCELLANEOUS SERVICES	\$3,750	
22 SITE COMMUNICATIONS	\$0	
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS	\$56,500	
03 MATERIALS		
01 CASING	\$0	
02 WELLHEAD EQUIPMENT	\$0	
03 DOWNHOLE WELL EQUIPMENT	\$0	
SUBTOTAL - 03 MATERIALS	\$0	
04 TAXES @ 7.25% OF CONSUMABLES, RENTALS & MATERIALS	\$109	
05 FEE @ 10% OF 02 + 04 AND 5% OF 03	\$5,661	
COST ESTIMATE W/OUT CONTINGENCY	\$73,775	
06 CONTINGENCY @ 0%	\$0	
TOTAL COST ESTIMATE WITH CONTINGENCY	\$73,775

NYSEG Wells 2 & 3 Nitrogen MIT Cost Each Well 2011 COST ESTIMATE		10/2/2011 Est By: JMc
ITEM	Budget Estimate	
01 MANAGEMENT COST		
01 LABOR - OFFICE	\$6,380	
02 LABOR - FIELD	\$0	
03 EXPENSES	\$2,125	
04 MISCELLANEOUS (PRESSURE RECORDERS)	\$3,000	
SUBTOTAL - 01 MANAGEMENT COST	\$11,505	
02 SERVICES AND RENTALS		
01 LOCATION	\$0	
02 MOBILIZATION/DEMOBILIZATION	\$0	
03 RIG	\$0	
04 FUEL	\$0	
05 WATER	\$0	
06 DRILLING FLUIDS	\$0	
07 BITS	\$0	
08 RENTAL TOOLS (LOGGING FLANGES)	\$1,500	
09 DIRECTIONAL DRILLING	\$0	
10 CEMENT, CEMENT SERVICES, HARDWARE	\$0	
11 LOGGING & WIRELINE SERVICES (1 TRIP)	\$31,250	
12 CORING & CORE ANALYSIS	\$0	
13 WORKOVER RIG	\$0	
14 PERFORATING	\$0	
15 STIMULATION, NITROGEN, PUMP TRUCKS	\$14,750	
16 CASING PULLING & RUNNING SERVICES	\$0	
17 WELDING	\$0	
18 WELLHEAD REPLACEMENT, TESTING, & REPAIR SERVICES	\$0	
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION	\$0	
20 MISCELLANEOUS MATERIALS & SUPPLIES	\$0	
21 MISCELLANEOUS SERVICES	\$3,750	
22 SITE COMMUNICATIONS	\$0	
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS	\$51,250	
03 MATERIALS		
01 CASING	\$0	
02 WELLHEAD EQUIPMENT	\$0	
03 DOWNHOLE WELL EQUIPMENT	\$0	
SUBTOTAL - 03 MATERIALS	\$0	
04 TAXES @ 7.25% OF CONSUMABLES, RENTALS & MATERIALS	\$109	
05 FEE @ 10% OF 02 + 04 AND 5% OF 03	\$5,136	
COST ESTIMATE W/OUT CONTINGENCY	\$68,000	
06 CONTINGENCY @ 0%	\$0	
TOTAL COST ESTIMATE WITH CONTINGENCY	\$68,000

AFE COST ESTIMATE
 Client: NYSEG
 Well: CAES Well No. 1
 Location: Watkins Glen, NY

October 2011
 Revision 1

Original

Phase	Cost Code	Description	Cost Estimate
01	LABOR		
		SUBTOTAL - 01 LABOR & EXP.	\$ 312,963
02	SUBCONTRACTORS, SERVICES, AND RENTALS		
	01	Location	\$ -
	02	Rig Mobilization/DeMobilization	\$ 150,000
	03	Drilling Rig	\$ 1,672,500
	04	Fuel	\$ 361,173
	05	Drilling Water	\$ 40,000
	06	Drilling Fluids & Solids Control	\$ 438,900
	07	Bits	\$ 415,900
	08	Rental & Fishing Tools & Services	\$ 261,013
	09	Directional Drilling	\$ 173,135
	10	Cement, Cement Services, Hardware & Rental Equipment	\$ 328,295
	11	Open Hole Logging & Wireline Services	\$ 63,094
	12	Coring & Core Analysis	\$ -
	13	Workover Rig	\$ -
	14	Perforating	\$ -
	15	Stimulation, Nitrogen, Pump Units	\$ -
	16	Casing Crews & Tools - External Testers - Spear Services	\$ 140,016
	17	Welding	\$ 484,058
	18	Testing, Inspection & Repair Services	\$ 40,600
	19	Transportation	\$ 116,750
	20	Hauling, Vacuum Trucks & Disposal	\$ 255,015
	21	Miscellaneous Materials & Supplies	\$ 7,500
	22	Miscellaneous Services	\$ 449,644
	23	Site Communications	\$ 37,200
	24	Special Activities	\$ -
		SUBTOTAL - 02 SUBCONTRACTORS, SERVICES & RENTALS	\$ 5,434,794
03	MATERIALS		
	01	Casing	\$ 702,927
	02	Wellhead Equipment	\$ -
	03	Downhole Well Equipment	\$ -
		SUBTOTAL - 03 MATERIALS	\$ 702,927
04	PROJECT MANAGEMENT FEES		
	01	Subs, Services, & Rentals 10%	\$ 543,479
	02	Materials 10%	\$ 70,293
		SUBTOTAL - 04 PROJECT MANAGEMENT FEES	\$ 613,772
		Contingency - 10%	\$ 706,446
		TOTAL COST ESTIMATE	\$ 7,771,000

AFE COST ESTIMATE
 Client: NYSEG
 Well: CAES Well No. 2
 Location: Watkins Glen, NY

October 2011
 Revision 1

Original

Phase	Cost Code	Description	Cost Estimate
01	LABOR		
		SUBTOTAL - 01 LABOR & EXP.	\$ 292,660
02	SUBCONTRACTORS, SERVICES, AND RENTALS		
	01	Location	\$ -
	02	Rig Mobilization/DeMobilization	\$ 150,000
	03	Drilling Rig	\$ 1,614,000
	04	Fuel	\$ 347,720
	05	Drilling Water	\$ 40,000
	06	Drilling Fluids & Solids Control	\$ 364,650
	07	Bits	\$ 373,900
	08	Rental & Fishing Tools & Services	\$ 232,778
	09	Directional Drilling	\$ 173,135
	10	Cement, Cement Services, Hardware & Rental Equipment	\$ 300,088
	11	Open Hole Logging & Wireline Services	\$ 63,094
	12	Coring & Core Analysis	\$ 40,135
	13	Workover Rig	\$ -
	14	Perforating	\$ -
	15	Stimulation, Nitrogen, Pump Units	\$ -
	16	Casing Crews & Tools - External Testers - Spear Services	\$ 140,016
	17	Welding	\$ 465,500
	18	Testing, Inspection & Repair Services	\$ 40,600
	19	Transportation	\$ 122,000
	20	Hauling, Vacuum Trucks & Disposal	\$ 225,834
	21	Miscellaneous Materials & Supplies	\$ 7,200
	22	Miscellaneous Services	\$ 418,570
	23	Site Communications	\$ 31,300
	24	Special Activities	\$ -
		SUBTOTAL - 02 SUBCONTRACTORS, SERVICES & RENTALS	\$ 5,150,520
03	MATERIALS		
	01	Casing	\$ 561,019
	02	Wellhead Equipment	\$ -
	03	Downhole Well Equipment	\$ -
		SUBTOTAL - 03 MATERIALS	\$ 561,019
04	PROJECT MANAGEMENT FEES		
	01	Subs, Services, & Rentals 10%	\$ 515,052
	02	Materials 10%	\$ 56,102
		SUBTOTAL - 04 PROJECT MANAGEMENT FEES	\$ 571,154
		Contingency - 10%	\$ 657,535
		TOTAL COST ESTIMATE	\$ 7,233,000

AFE COST ESTIMATE
 Client: NYSEG
 Well: CAES Well No. 3
 Location: Watkins Glen, NY

October 2011
 Revision 1

Original

Phase	Cost Code	Description	Cost Estimate
01	LABOR		
		SUBTOTAL - 01 LABOR & EXP.	\$ 283,305
02	SUBCONTRACTORS, SERVICES, AND RENTALS		
	01	Location	\$ -
	02	Rig Mobilization/DeMobilization	\$ 225,000
	03	Drilling Rig	\$ 1,497,000
	04	Fuel	\$ 320,813
	05	Drilling Water	\$ 40,000
	06	Drilling Fluids & Solids Control	\$ 364,650
	07	Bits	\$ 373,900
	08	Rental & Fishing Tools & Services	\$ 232,778
	09	Directional Drilling	\$ 173,135
	10	Cement, Cement Services, Hardware & Rental Equipment	\$ 300,088
	11	Open Hole Logging & Wireline Services	\$ 63,094
	12	Coring & Core Analysis	\$ -
	13	Workover Rig	\$ -
	14	Perforating	\$ -
	15	Stimulation, Nitrogen, Pump Units	\$ -
	16	Casing Crews & Tools - External Testers - Spear Services	\$ 140,016
	17	Welding	\$ 465,500
	18	Testing, Inspection & Repair Services	\$ 40,600
	19	Transportation	\$ 113,600
	20	Hauling, Vacuum Trucks & Disposal	\$ 225,834
	21	Miscellaneous Materials & Supplies	\$ 6,600
	22	Miscellaneous Services	\$ 405,807
	23	Site Communications	\$ 33,400
	24	Special Activities	\$ -
		SUBTOTAL - 02 SUBCONTRACTORS, SERVICES & RENTALS	\$ 5,021,816
03	MATERIALS		
	01	Casing	\$ 561,019
	02	Wellhead Equipment	\$ -
	03	Downhole Well Equipment	\$ -
		SUBTOTAL - 03 MATERIALS	\$ 561,019
04	PROJECT MANAGEMENT FEES		
	01	Subs, Services, & Rentals 10%	\$ 502,182
	02	Materials 10%	\$ 56,102
		SUBTOTAL - 04 PROJECT MANAGEMENT FEES	\$ 558,284
		Contingency - 10%	\$ 642,442
		TOTAL COST ESTIMATE	\$ 7,067,000

NYSEG INTERMEDIATE WORKOVER AND SONAR COST ESTIMATE - Per Well 2011 BUDGET COST ESTIMATE		DATE: 10/31/11 Job # 50756B Est By: JMc
ITEM	COST ESTIMATE	
01 MANAGEMENT COST		
01 LABOR - OFFICE		\$9,700
02 LABOR - FIELD		\$6,930
03 EXPENSES		\$2,550
04 MISCELLANEOUS		\$1,500
SUBTOTAL - 01 MANAGEMENT COST		\$20,680
02 SERVICES AND RENTALS		
01 LOCATION		\$1,500
02 MOBILIZATION/DEMOBILIZATION		\$0
03 RIG		\$0
04 FUEL		\$0
05 WATER		\$0
06 DRILLING FLUIDS		\$0
07 BITS		\$0
08 RENTAL TOOLS		\$2,750
09 DIRECTIONAL DRILLING		\$0
10 CEMENT, CEMENT SERVICES, HARDWARE		\$0
11 LOGGING & WIRELINE SERVICES		\$11,000
12 CORING & CORE ANALYSIS		\$0
13 WORKOVER RIG		\$42,500
14 PERFORATING		\$0
15 STIMULATION, NITROGEN, PUMP TRUCKS		\$0
16 CASING PULLING & RUNNING SERVICES		\$11,000
17 WELDING		\$250
18 WELLHEAD REPLACEMENT, TESTING, & REPAIR SERVICES		\$6,500
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION		\$1,500
20 MISCELLANEOUS MATERIALS & SUPPLIES		\$0
21 MISCELLANEOUS SERVICES		\$4,250
22 SITE COMMUNICATIONS		\$0
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS		\$81,250
03 MATERIALS		
01 CASING		\$966
02 WELLHEAD EQUIPMENT		\$0
03 DOWNHOLE WELL EQUIPMENT		\$0
SUBTOTAL - 03 MATERIALS		\$966
04 TAXES @ 7.25% OF CONSUMABLES, RENTALS & MATERIALS		\$269
05 FEE @ 6% OF 02 + 04 AND 5% OF 03		\$4,939
COST ESTIMATE W/OUT CONTINGENCY		\$108,105
06 CONTINGENCY @ 15%		\$16,216
TOTAL COST ESTIMATE WITH CONTINGENCY		\$124,320

NYSEG Caverns 1 WORKOVER ESTIMATE CONVERSION WORKOVER 2011 Budget Estimate		DATE:10/15/2011 Job # 50756B Est By: JMc
ITEM	COST ESTIMATE	
01 MANAGEMENT COST		
01 LABOR - OFFICE		\$20,870
02 LABOR - FIELD		\$33,000
03 EXPENSES		\$7,700
04 MISCELLANEOUS		\$1,500
SUBTOTAL - 01 MANAGEMENT COST		\$63,070
02 SERVICES AND RENTALS		
01 LOCATION		\$0
02 MOBILIZATION/DEMOBILIZATION		\$0
03 RIG		\$0
04 FUEL		\$0
05 WATER		\$0
06 DRILLING FLUIDS		\$0
07 BITS		\$0
08 RENTAL TOOLS		\$0
09 DIRECTIONAL DRILLING		\$0
10 CEMENT, CEMENT SERVICES, HARDWARE		\$0
11 LOGGING & WIRELINE SERVICES		\$73,950
12 CORING & CORE ANALYSIS		\$0
13 WORKOVER RIG		\$240,000
14 PERFORATING		\$0
15 STIMULATION, NITROGEN, PUMP TRUCKS		\$20,500
16 CASING PULLING & RUNNING SERVICES		\$35,000
17 WELDING		\$350,000
18 WELLHEAD REPLACEMENT, TESTING, & REPAIR SERVICES		\$3,000
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION		\$11,000
20 MISCELLANEOUS MATERIALS & SUPPLIES		\$2,500
21 MISCELLANEOUS SERVICES		\$28,000
22 SITE COMMUNICATIONS		\$0
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS		\$763,950
03 MATERIALS		
01 CASING		\$48,682
02 WELLHEAD EQUIPMENT		
03 DOWNHOLE WELL EQUIPMENT		
SUBTOTAL - 03 MATERIALS		\$48,682
04 TAXES @ 5.95% OF CONSUMABLES, RENTALS & MATERIALS		\$3,045
05 FEE @ 10% OF 02 + 04 AND 10% OF 03		\$81,568
COST ESTIMATE W/OUT CONTINGENCY		\$960,315
06 CONTINGENCY @ 15%		\$144,047
TOTAL COST ESTIMATE WITH CONTINGENCY		\$1,104,362

**NYSEG Caverns 2 & 3
WORKOVER ESTIMATE CONVERSION WORKOVER
2011 Budget Estimate**

**DATE:10/15/2011
Job # 50756B
Est By: JMc**

ITEM	COST ESTIMATE
01 MANAGEMENT COST	
01 LABOR - OFFICE	\$20,870
02 LABOR - FIELD	\$26,400
03 EXPENSES	\$6,800
04 MISCELLANEOUS	\$1,500
SUBTOTAL - 01 MANAGEMENT COST	\$55,570
02 SERVICES AND RENTALS	
01 LOCATION	\$0
02 MOBILIZATION/DEMOBILIZATION	\$0
03 RIG	\$0
04 FUEL	\$0
05 WATER	\$0
06 DRILLING FLUIDS	\$0
07 BITS	\$0
08 RENTAL TOOLS	\$0
09 DIRECTIONAL DRILLING	\$0
10 CEMENT, CEMENT SERVICES, HARDWARE	\$0
11 LOGGING & WIRELINE SERVICES	\$73,950
12 CORING & CORE ANALYSIS	\$0
13 WORKOVER RIG	\$195,000
14 PERFORATING	\$0
15 STIMULATION, NITROGEN, PUMP TRUCKS	\$14,750
16 CASING PULLING & RUNNING SERVICES	\$35,000
17 WELDING	\$350,000
18 WELLHEAD REPLACEMENT, TESTING, & REPAIR SERVICES	\$3,000
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION	\$11,000
20 MISCELLANEOUS MATERIALS & SUPPLIES	\$2,500
21 MISCELLANEOUS SERVICES	\$28,000
22 SITE COMMUNICATIONS	\$0
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS	\$713,200
03 MATERIALS	
01 CASING	\$48,682
02 WELLHEAD EQUIPMENT	\$0
03 DOWNHOLE WELL EQUIPMENT	\$0
SUBTOTAL - 03 MATERIALS	\$48,682
04 TAXES @ 5.95% OF CONSUMABLES, RENTALS & MATERIALS	\$3,045
05 FEE @ 10% OF 02 + 04 AND 10% OF 03	\$76,493
COST ESTIMATE W/OUT CONTINGENCY	\$896,990
06 CONTINGENCY @ 15%	\$134,549
TOTAL COST ESTIMATE WITH CONTINGENCY	\$1,031,539

NYSEG - Watkins Glen Well No. 1 Wellhead Installation Production BUDGET COST ESTIMATE		DATE: 10/31/11 Job # Est By: JMc
ITEM	COST ESTIMATE	
01 MANAGEMENT COST		
01 LABOR - OFFICE		\$3,490
02 LABOR - FIELD		\$3,300
03 EXPENSES		\$600
04 MISCELLANEOUS		\$0
SUBTOTAL - 01 MANAGEMENT COST		\$7,390
02 SERVICES AND RENTALS		
01 LOCATION		\$0
02 MOBILIZATION/DEMobilIZATION		\$0
03 RIG - DAYWORK		\$0
04 FUEL		\$0
05 WATER		\$0
06 DRILLING FLUIDS		\$0
07 BITS		\$0
08 RENTAL TOOLS - SNUBBING STACK		\$0
09 DIRECTIONAL DRILLING		\$0
10 CEMENT, CEMENT SERVICES, HARDWARE		\$0
11 LOGGING & WIRELINE SERVICES - CASING CUTS & BRIDGE PLUGS		\$0
12 CORING & CORE ANALYSIS		\$0
13 WORKOVER RIG		\$22,500
14 PERFORATING		\$0
15 STIMULATION, NITROGEN, PUMP TRUCKS		\$0
16 CASING PULLING & RUNNING SERVICES		\$0
17 WELDING		\$0
18 TESTING , INSPECTION, & REPAIR SERVICES		\$3,000
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION		\$1,500
20 MISCELLANEOUS MATERIALS & SUPPLIES		\$0
21 MISCELLANEOUS SERVICES		\$17,505
22 SITE COMMUNICATIONS		\$0
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS		\$44,505
03 MATERIALS		
01 CASING		
02 WELLHEAD EQUIPMENT		
03 DOWNHOLE WELL EQUIPMENT		
SUBTOTAL - 03 MATERIALS		\$0
04 TAXES @ 8% OF CONSUMABLES, RENTALS & MATERIALS	8.00%	\$0
05 FEE @ 10% OF 02 + 03 + 04	10%	\$4,451
COST ESTIMATE W/OUT CONTINGENCY		\$56,346
06 CONTINGENCY @ 10%	10%	\$5,635
TOTAL COST ESTIMATE WITH CONTINGENCY		\$61,980

NYSEG - Watkins Glen Wellhead Installation Production Wells 2 & 3 BUDGET COST ESTIMATE		DATE: 10/10/11 Job # Est By: JMc
ITEM	COST ESTIMATE	
01 MANAGEMENT COST		
01 LABOR - OFFICE		\$3,490
02 LABOR - FIELD		\$3,300
03 EXPENSES		\$600
04 MISCELLANEOUS		\$0
SUBTOTAL - 01 MANAGEMENT COST		\$7,390
02 SERVICES AND RENTALS		
01 LOCATION		\$0
02 MOBILIZATION/DEMOBILIZATION		\$0
03 RIG - DAYWORK		\$0
04 FUEL		\$0
05 WATER		\$0
06 DRILLING FLUIDS		\$0
07 BITS		\$0
08 RENTAL TOOLS - SNUBBING STACK		\$0
09 DIRECTIONAL DRILLING		\$0
10 CEMENT, CEMENT SERVICES, HARDWARE		\$0
11 LOGGING & WIRELINE SERVICES - CASING CUTS & BRIDGE PLUGS		\$0
12 CORING & CORE ANALYSIS		\$0
13 WORKOVER RIG		\$22,500
14 PERFORATING		\$0
15 STIMULATION, NITROGEN, PUMP TRUCKS		\$0
16 CASING PULLING & RUNNING SERVICES		\$0
17 WELDING		\$0
18 TESTING , INSPECTION, & REPAIR SERVICES		\$3,000
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION		\$1,500
20 MISCELLANEOUS MATERIALS & SUPPLIES		\$0
21 MISCELLANEOUS SERVICES		\$17,505
22 SITE COMMUNICATIONS		\$0
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS		\$44,505
03 MATERIALS		
01 CASING		
02 WELLHEAD EQUIPMENT		
03 DOWNHOLE WELL EQUIPMENT		
SUBTOTAL - 03 MATERIALS		
04 TAXES @ 8% OF CONSUMABLES, RENTALS & MATERIALS	8.00%	\$0
05 FEE @ 10% OF 02 + 03 + 04	10%	\$4,451
COST ESTIMATE W/OUT CONTINGENCY		\$56,346
06 CONTINGENCY @ 10%	10%	\$5,635
TOTAL COST ESTIMATE WITH CONTINGENCY		\$61,980

NYSEG Cavern No. 1 Cost Estimate for Setting Blanket 2011 COST ESTIMATE		10/2/2011 Est By: JMc
ITEM	Budget Estimate	
01 MANAGEMENT COST		
01 LABOR - OFFICE	\$2,960	
02 LABOR - FIELD	\$0	
03 EXPENSES	\$2,125	
04 MISCELLANEOUS (PRESSURE RECORDERS)	\$3,000	
SUBTOTAL - 01 MANAGEMENT COST	\$8,085	
02 SERVICES AND RENTALS		
01 LOCATION	\$0	
02 MOBILIZATION/DEMOBILIZATION	\$0	
03 RIG	\$0	
04 FUEL	\$0	
05 WATER	\$0	
06 DRILLING FLUIDS	\$0	
07 BITS	\$0	
08 RENTAL TOOLS (LOGGING FLANGES)	\$1,500	
09 DIRECTIONAL DRILLING	\$0	
10 CEMENT, CEMENT SERVICES, HARDWARE	\$0	
11 LOGGING & WIRELINE SERVICES (1 TRIP)	\$16,250	
12 CORING & CORE ANALYSIS	\$0	
13 WORKOVER RIG	\$0	
14 PERFORATING	\$0	
15 STIMULATION, NITROGEN, PUMP TRUCKS	\$20,000	
16 CASING PULLING & RUNNING SERVICES	\$0	
17 WELDING	\$0	
18 WELLHEAD REPLACEMENT, TESTING, & REPAIR SERVICES	\$0	
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION	\$0	
20 MISCELLANEOUS MATERIALS & SUPPLIES	\$0	
21 MISCELLANEOUS SERVICES	\$1,250	
22 SITE COMMUNICATIONS	\$0	
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS	\$39,000	
03 MATERIALS		
01 CASING	\$0	
02 WELLHEAD EQUIPMENT	\$0	
03 DOWNHOLE WELL EQUIPMENT	\$0	
SUBTOTAL - 03 MATERIALS	\$0	
04 TAXES @ 7.25% OF CONSUMABLES, RENTALS & MATERIALS	\$109	
05 FEE @ 10% OF 02 + 04 AND 5% OF 03	\$3,911	
COST ESTIMATE W/OUT CONTINGENCY	\$51,105	
06 CONTINGENCY @ 0%	\$0	
TOTAL COST ESTIMATE WITH CONTINGENCY	\$51,105

NYSEG Wells 2 & 3 Set Blanket Wells 2 & 3 2011 COST ESTIMATE		10/2/2011 Est By: JMc
ITEM	Budget Estimate	
01 MANAGEMENT COST		
01 LABOR - OFFICE	\$6,380	
02 LABOR - FIELD	\$0	
03 EXPENSES	\$2,125	
04 MISCELLANEOUS (PRESSURE RECORDERS)	\$3,000	
SUBTOTAL - 01 MANAGEMENT COST	\$11,505	
02 SERVICES AND RENTALS		
01 LOCATION	\$0	
02 MOBILIZATION/DEMOBILIZATION	\$0	
03 RIG	\$0	
04 FUEL	\$0	
05 WATER	\$0	
06 DRILLING FLUIDS	\$0	
07 BITS	\$0	
08 RENTAL TOOLS (LOGGING FLANGES)	\$1,500	
09 DIRECTIONAL DRILLING	\$0	
10 CEMENT, CEMENT SERVICES, HARDWARE	\$0	
11 LOGGING & WIRELINE SERVICES (1 TRIP)	\$16,250	
12 CORING & CORE ANALYSIS	\$0	
13 WORKOVER RIG	\$0	
14 PERFORATING	\$0	
15 STIMULATION, NITROGEN, PUMP TRUCKS	\$14,750	
16 CASING PULLING & RUNNING SERVICES	\$0	
17 WELDING	\$0	
18 WELLHEAD REPLACEMENT, TESTING, & REPAIR SERVICES	\$0	
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION	\$0	
20 MISCELLANEOUS MATERIALS & SUPPLIES	\$0	
21 MISCELLANEOUS SERVICES	\$1,250	
22 SITE COMMUNICATIONS	\$0	
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS	\$33,750	
03 MATERIALS		
01 CASING	\$0	
02 WELLHEAD EQUIPMENT	\$0	
03 DOWNHOLE WELL EQUIPMENT	\$0	
SUBTOTAL - 03 MATERIALS	\$0	
04 TAXES @ 7.25% OF CONSUMABLES, RENTALS & MATERIALS	\$109	
05 FEE @ 10% OF 02 + 04 AND 5% OF 03	\$3,386	
COST ESTIMATE W/OUT CONTINGENCY	\$48,750	
06 CONTINGENCY @ 0%	\$0	
TOTAL COST ESTIMATE WITH CONTINGENCY	\$48,750

NYSEG - Watkins Glen SNUB 5-1/2" CASING OUT - Per Well BUDGET COST ESTIMATE		DATE: 10/31/11 Job # Est By: JMc
ITEM	COST ESTIMATE	
01 MANAGEMENT COST		
01 LABOR - OFFICE		\$3,490
02 LABOR - FIELD		\$5,500
03 EXPENSES		\$2,200
04 MISCELLANEOUS		\$1,000
SUBTOTAL - 01 MANAGEMENT COST		\$12,190
02 SERVICES AND RENTALS		
01 LOCATION		\$2,000
02 MOBILIZATION/DEMOBILIZATION		\$0
03 RIG - DAYWORK		\$0
04 FUEL		\$0
05 WATER		\$0
06 DRILLING FLUIDS		\$0
07 BITS		\$0
08 RENTAL TOOLS - SNUBBING STACK		\$33,475
09 DIRECTIONAL DRILLING		\$0
10 CEMENT, CEMENT SERVICES, HARDWARE		\$0
11 LOGGING & WIRELINE SERVICES - CASING CUTS & BRIDGE PLUGS		\$26,525
12 CORING & CORE ANALYSIS		\$0
13 WORKOVER RIG - RIG ASSIST SNUBBING UNIT		\$64,600
14 PERFORATING		\$0
15 STIMULATION, NITROGEN, PUMP TRUCKS		\$0
16 CASING PULLING & RUNNING SERVICES		\$0
17 WELDING		\$0
18 TESTING , INSPECTION, & REPAIR SERVICES		\$0
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION		\$0
20 MISCELLANEOUS MATERIALS & SUPPLIES		\$0
21 MISCELLANEOUS SERVICES		\$19,705
22 SITE COMMUNICATIONS		\$0
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS		\$146,305
03 MATERIALS		
01 CASING		\$0
02 WELLHEAD EQUIPMENT		\$0
03 DOWNHOLE WELL EQUIPMENT		\$0
SUBTOTAL - 03 MATERIALS		\$0
04 TAXES @ 8% OF CONSUMABLES, RENTALS & MATERIALS	8.00%	\$2,678
05 FEE @ 10% OF 02 + 03 + 04	10%	\$14,898
COST ESTIMATE W/OUT CONTINGENCY		\$176,072
06 CONTINGENCY @ 10%	10%	\$17,607
TOTAL COST ESTIMATE WITH CONTINGENCY		\$193,679

NYSEG CAES Cavern Sonar Survey - Each Survey Cost Estimate		DATE: 10-11-11 Job # Est By: JMc
ITEM	COST ESTIMATE	
01 MANAGEMENT COST		
01 LABOR - OFFICE		\$4,840
02 LABOR - FIELD		\$0
03 EXPENSES		\$2,100
04 MISCELLANEOUS		\$0
SUBTOTAL - 01 MANAGEMENT COST		\$6,940
02 SERVICES AND RENTALS		
01 LOCATION		\$0
02 MOBILIZATION/DEMOBILIZATION		\$0
03 RIG		\$0
04 FUEL		\$0
05 WATER		\$0
06 DRILLING FLUIDS		\$0
07 BITS		\$0
08 RENTAL TOOLS		\$0
09 DIRECTIONAL DRILLING		\$0
10 CEMENT, CEMENT SERVICES, HARDWARE		\$0
11 LOGGING & WIRELINE SERVICES		\$11,500
12 CORING & CORE ANALYSIS		\$0
13 WORKOVER RIG		\$0
14 PERFORATING		\$0
15 STIMULATION, NITROGEN, PUMP TRUCKS		\$0
16 CASING PULLING & RUNNING SERVICES		\$0
17 WELDING		\$0
18 WELLHEAD REPLACEMENT, TESTING, & REPAIR SERVICES		\$0
19 VACUUM TRUCKS, HAULING, & TRANSPORTATION		\$0
20 MISCELLANEOUS MATERIALS & SUPPLIES		\$0
21 MISCELLANEOUS SERVICES		\$2,700
22 SITE COMMUNICATIONS		\$0
SUBTOTAL - 02 SUBCONTRACTS, SERVICES & RENTALS		\$14,200
03 MATERIALS		
01 CASING		\$0
02 WELLHEAD EQUIPMENT		\$0
03 DOWNHOLE WELL EQUIPMENT		\$0
SUBTOTAL - 03 MATERIALS		\$0
04 Taxes @ 8%		\$0
05 FEE @ 10%		\$1,420
COST ESTIMATE W/OUT CONTINGENCY		\$22,560
06 CONTINGENCY @ 10%		\$2,256
TOTAL COST ESTIMATE WITH CONTINGENCY		\$24,816

PB Energy Storage Services, Inc. Cost Estimate

TITLE NYSEG CAES Project				ESTIM TYPE 10%	ESTIMATOR: JMc	REVIEWER:	REV: 0							
				DISCIPLINE All	DATE: 10/10/2011	DATE:	DATE: 10/10/2011							
LINE NO	COVER SHEET Wellpad Piping	QTY	UNIT	UNIT MHRS	TOT MHRS	UNIT COST				TOTAL COST				TOTAL
						LABOR	MATL	EQUIP	SUBCON	LABOR	MATL	EQUIP	SUBCON	
1	DIVISION 1 - GENERAL REQUIREMENTS													
2	Labor & Services (1A-1)				57					3,213	-	-	-	3,213
3	Construction Plant (1A-1)				-					-	-	-	-	-
4	Construction Equipment (1B-1)				-					-	-	7,525	-	7,525
5	Cavern Development & Opns (1C-1)				-					-	-	-	-	-
6	DIVISION 2 - SITE WORK				-					-	-	-	-	-
7	DIVISION 3 - CONCRETE				28					1,198	386	8	-	1,592
8	DIVISION 5 - METALS				8					343	1,650	167	-	2,160
9	DIVISION 9 - FINISHES				-					-	-	-	119	119
10	DIVISION 13 - SPECIAL CONSTRUCTION				-					-	-	-	2,160	2,160
11	DIVISION 15 - MECHANICAL				260					11,636	49,462	-	528	61,626
12	DIVISION 16 - ELECTRICAL				-					-	-	-	7,315	7,315
13	DIVISION 100 - PROCESS EQUIPMENT				-					-	-	-	-	-
14	Labor competition * OT Factor									-				-
15														
16														
17														
18	SUB-TOTAL				354					16,391	51,498	7,699	10,121	85,709
19														
20														
21	Benefits & Burdens			(of Labor) (Included in Direct Cost)										-
22	Sm. Tools & Consumables	2%		(of Div 2 - 16)										1,714
23	SUB-TOTAL													87,423
24														
25	Sales Tax	8%		(of Subtotal)										6,994
26	SUB-TOTAL													94,417
27														
28	Contractor's Overhead	10%		(of Contract)										11,802
29	SUB-TOTAL													106,220
30														
31	Contractor's Profit	10%		(of Contract)										11,802
32	SUB-TOTAL													118,022
33														
34	Bond			(of Contract)										-
35	TOTAL CONSTRUCTION COST													118,022
36	Engineering, Design & Inspection	8%		(of Construction)										9,442
37	SUB-TOTAL													127,463
38	Contingency & Undefined Work	10%		(of Subtotal)										12,746
39	TOTAL JOB COST													140,210
40	ROUNDED TO													140,000

16285 Park Ten Place, Suite 400
Houston, Texas 77084

(281) 496-5590
Fax (281) 496-5865
www.pbenergy.com

August 11, 2011

Jim Rettberg
NYSEG
//via email//

Dear Mr. Rettberg:

Re: Seneca Lake CAES Project – Preliminary Cavern Criteria

Introduction

The PB Energy Storage Services (PB ESS) division of PB Americas was commissioned by NYSEG to determine the acceptability of the bedded salt at a site near Seneca Lake for compressed air energy storage (CAES) in accordance with the Technical Specification for the Cavern Development Consultant. Additionally, PB ESS tasking includes:

- Support a study by WorleyParsons (WP) to develop comprehensive cost estimates.
- Perform preliminary cavern design.
- Perform cavern thermodynamic modeling.
- Prepare a solution mining plan.
- Specify a program of inspections and tests to monitor cavern development.
- Prepare design specifications for wells and wellheads.
- Prepare a program to monitor the cavern during CAES operations.
- Prepare a mechanical integrity testing program.
- Prepare a list of procurement and construction specifications to develop and convert the cavern to storage operations.

This letter report was requested during our phone conversation of August 8, 2011. The purpose of the report is to provide cavern selection criteria for an existing cavern, which will meet the mission requirements of a maximum compression pressure of 1500 psi and the capability to generate electricity for 10 hours at an estimated mass flow rate of 550 lb/sec. Final thermomechanical models have not been run; however, based upon results to date the total cavern volume required is at least 3 MMbbls. Prior to using any cavern, the well(s) and cavern would need to be tested for integrity at pressures in excess of 1500 psi.

Criteria

The list of minimum requirements for consideration of an existing cavern for use by NYSEG is provided below.

1. De-waterable volume of at least 3.5 MMbbls.
2. Roof diameter or span of less than 260 ft.
3. Cavern roof at least 50 ft below top of salt (not leached to shale)
4. Proximity to other caverns of not less than 500 ft wall to wall
5. Never been used for LPG storage

Rationale

In establishing the criteria above, PB ESS has used the following rationale.

1. All of the preliminary thermomechanical modeling performed to date suggests that a cavern with a volume smaller than 3 MMbbls will exhibit tensile stress in the walls and/or roof. Since salt has a tensile strength of less than 300 psi, storage caverns are designed to have little or no tensile stress imposed during their operational life. At present, a volume of 3.5 MMbbls is believed to be adequate to meet this requirement.
2. Stable cavern roof diameter or roof span is established by assessment of the results of the thermomechanical modeling results. Typical storage industry practice limits cavern roof diameters to a range of 250 ft to 300 ft.
3. A review of available sonar surveys implies that cavern roof established within the shale present in the Camillus Formation has a significant potential for unraveling of the rock. The dolostones of the Bertie Formation are known to contain water. The presence of water implies that a cavern built with a roof in the Bertie Formation will not be pressure tight.
4. A 500 foot spacing is believed to be appropriate for preliminary design. This number is representative of intended cavern spacing at Watkins Glen.
5. Injection of air into a former LPG storage cavern will require initial purging of the cavern with an inert gas (e.g., nitrogen), which could prove difficult and costly.

Please do not hesitate to call or email if you have questions or suggestions.

Regards,

Jim McHenry

16285 Park Ten Place, Suite 400
Houston, Texas 77084

(281) 496-5590
Fax (281) 496-5865
www.pbenergy.com

December 15, 2011

James W. Rettberg, PE
Project Manager
NYSEG

Dear Mr. Rettberg;

Re: Input to U.S. DOE Environmental Questionnaire

The NYSEG Cavern Development Consultant Technical Specification deliverable 4.4.2.11 directs PB ESS to provide estimates of emissions generated by equipment, solid or hazardous waste that will be generated and disposed of, chemicals and hazardous or toxic materials that will be used in the cavern testing, well installation and cavern dewatering phases of the project. Specifically:

- III.A.8 Activities
- III.A.10 Materials and estimates of quantities used / produced
- III.D.6.e,f,g Atmospheric Air Quality
- III.D.7 Hydrologic / Water Quality
- III.D.8 Solid and Hazardous Waste
- III.D.9 Health and Safety Factors

III.A.8 – Activities

Summarize the objectives of the proposed work. List activities planned at the location as covered by this Environmental Questionnaire.

Objectives

NYSEG proposes to construct three storage caverns, to be used for Compressed Air Energy Storage, in the Salina Salt near Watkins Glen, NY. Each cavern will be solution mined to have a net volume of 970,000 barrels. The cavern development interval is expected to be from 2,402 – 2,632 feet below ground surface.

Activities

1. Build three 400 ft x 400 ft wellpads

2. Drill and Complete Well No. 1

- a. Mobilize drilling rig to Wellpad No. 1
- b. Drill a 48" diameter hole and cement in place a 42" conductor pipe to a depth of approximately 175 feet below ground level.
- c. Drill a 36" diameter hole inside the conductor pipe and cement in place a 30" surface casing to a depth of approximately 850 feet below ground level.
- d. Drill a 30" diameter hole inside the surface casing and cement in place a 24" diameter final cemented casing to a depth of approximately 2,360 feet below ground level.
- e. Drill a 24" diameter hole inside the final cemented casing to a depth of approximately 2,632 feet.
- f. Install a wellhead and two concentric leaching casings (8-5/8" diameter to 2,530 feet below ground level and 5-1/2" diameter to 2,630 feet below ground level).

3. Drill and Complete Well No. 2

- a. Move drilling rig to Wellpad No. 2
- b. Drill a 48" diameter hole and cement in place a 42" conductor pipe to a depth of approximately 175 feet below ground level.
- c. Drill a 36" diameter hole inside the conductor pipe and cement in place a 26" surface casing to a depth of approximately 850 feet below ground level.
- d. Drill a 26" diameter hole inside the surface casing and cement in place a 20" diameter final cemented casing to a depth of approximately 2,360 feet below ground level.
- e. Drill a 24" diameter hole inside the final cemented casing to a depth of approximately 2,632 feet.
- f. Install a wellhead and two concentric leaching casings (8-5/8" diameter to 2,530 feet below ground level and 5-1/2" diameter to 2,630 feet below ground level).
- g. Fill wellbore with nitrogen.

4. Drill and Complete Well No. 3

- a. Move drilling rig to Wellpad No. 3
- b. Drill a 48" diameter hole and cement in place a 42" conductor pipe to a depth of approximately 175 feet below ground level.

- c. Drill a 36" diameter hole inside the conductor pipe and cement in place a 26" surface casing to a depth of approximately 850 feet below ground level.
- d. Drill a 26" diameter hole inside the surface casing and cement in place a 20" diameter final cemented casing to a depth of approximately 2,360 feet below ground level.
- e. Drill a 24" diameter hole inside the final cemented casing to a depth of approximately 2,632 feet.
- f. Install a wellhead and two concentric leaching casings (8-5/8" diameter to 2,530 feet below ground level and 5-1/2" diameter to 2,630 feet below ground level).
- g. Demobilize drilling rig.
- h. Fill wellbore with nitrogen.

5. Solution Mine Cavern No. 1

- a. Run 4" diameter water and brine piping from edge of wellpad and connect to wellhead.
- b. Hydrotest wellpad piping.
- c. Inject nitrogen roof blanket to approximately 2,520 ft below ground surface.
- d. Begin water injection at 350 gpm down the inner string, brine will be displaced through the outer string and will flow to U.S. Salt. (Direct Injection)
- e. Continue direct injection for approximately 130 days.
- f. Stop water injection.
- g. Bleed nitrogen from wellbore.

h. Intermediate Workover Cavern No. 1

- i. Mobilize Workover Rig to wellpad
- ii. Remove approximately 100 ft of 5-1/2" diameter inner leach string and approximately 58 ft of 8-5/8" casing.
- iii. Demobilize workover rig.
- iv. Inject nitrogen blanket to 2,420 ft.
- v. Begin water injection at 350 gpm down 8-5/8" x 5-1/2" annulus, recovering brine up the 4-1/2" string. (Reverse Circulation)
- vi. Continue leaching in reverse for approximately 150 days.
- vii. Bleed nitrogen from wellbore and set interface at 2,410 feet below ground surface.
- viii. Continue leaching in reverse for approximately 150 days.
- ix. Bleed nitrogen from wellbore and set interface at 2,402 feet below ground surface.

- x. Continue leaching in reverse for approximately 280 days.
- xi. Stop water injection into well.
- xii. Perform mechanical integrity test of cavern.
- xiii. Bleed nitrogen from wellbore.

6. Conversion Workover Cavern No. 1

- a. Mobilize workover rig to well.
- b. Remove 5-1/2" and 8-5/8" casing from well.
- c. Run and weld 20" diameter stainless steel suspended liner to approximately 2,407 feet below ground level.
- d. Run new 5-1/2" dewatering string to approximately 2,407 ft below ground surface.
- e. Install dewatering wellhead.
- f. Perform mechanical integrity test of wellhead and wellbore.

7. Dewater Cavern No. 1

- a. Connect portable surface compressors to wellhead.
- b. Begin dewatering, injecting air at approximately 3,750 scfm and recovering brine through dewatering string at approximately 350 gpm.
- c. Continue dewatering for approximately 80 days.
- d. Stop air injection.

8. Final Configuration Workover – Cavern No. 1

- a. Mobilize workover rig to well.
- b. Snub 5-1/2" dewatering string from well.
- c. Install remaining wellhead components.

9. Cavern ready for service.

10. Solution Mine Cavern No. 2

- a. Run 4" diameter water and brine piping from edge of wellpad and connect to wellhead.
- b. Hydrotest wellpad piping.
- c. Bleed nitrogen from wellbore to set roof blanket to approximately 2,520 ft below ground surface.
- d. Begin water injection at 350 gpm down the inner string, brine will be displaced through the outer string and will flow to U.S. Salt. (Direct Injection)
- e. Continue direct injection for approximately 130 days.
- f. Stop water injection.
- g. Bleed nitrogen from wellbore.

h. Intermediate Workover Cavern No. 2

- i. Mobilize Workover Rig to wellpad.
- ii. Remove approximately 100 ft of 5-1/2" diameter inner leach string and approximately 58 ft of 8-5/8" casing.
- iii. Demobilize workover rig.
- i. Inject nitrogen blanket to 2,420 ft.
- j. Begin water injection at 350 gpm down 8-5/8" x 5-1/2" annulus, recovering brine up the 4-1/2" string. (Reverse Circulation)
- k. Continue leaching in reverse for approximately 150 days.
- l. Bleed nitrogen from wellbore and set interface at 2,410 feet below ground surface.
- m. Continue leaching in reverse for approximately 150 days.
- n. Bleed nitrogen from wellbore and set interface at 2,402 feet below ground surface.
- o. Continue leaching in reverse for approximately 280 days.
- p. Stop water injection into well.
- q. Perform mechanical integrity test of cavern.
- r. Bleed nitrogen from wellbore.

11. Conversion Workover Cavern No. 2

- a. Mobilize workover rig to well.
- b. Remove 5-1/2" and 8-5/8" casing from well.
- c. Run and weld 16" stainless steel suspended liner to approximately 2,407 feet below ground level.
- d. Run new 5-1/2" dewatering string to approximately 2,407 ft below ground surface.
- e. Install dewatering wellhead.
- f. Perform mechanical integrity test of wellhead and wellbore.

12. Dewater Cavern No. 2

- a. Connect portable surface compressors to wellhead.
- b. Begin dewatering, injecting air at approximately 3,750 scfm and recovering brine through dewatering string at approximately 350 gpm.
- c. Continue dewatering for approximately 80 days.
- d. Stop air injection.

13. Final Configuration Workover – Cavern No. 2

- a. Mobilize workover rig to well.

- b. Snub 5-1/2" dewatering string from well.
- c. Install remaining wellhead components.
- d. Demobilize workover rig

14. Cavern ready for service.

15. Solution Mine Cavern No. 3

- a. Run 4" diameter water and brine piping from edge of wellpad and connect to wellhead.
- b. Hydrotest wellpad piping.
- c. Bleed nitrogen from wellbore to set roof blanket to approximately 2,520 ft below ground surface.
- d. Begin water injection at 350 gpm down the inner string, brine will be displaced through the outer string and will flow to U.S. Salt. (Direct Injection)
- e. Continue direct injection for approximately 130 days.
- f. Stop water injection.
- g. Bleed nitrogen from wellbore.

h. Intermediate Workover Cavern No. 3

- i. Mobilize Workover Rig to wellpad.
- ii. Remove approximately 100 ft of 5-1/2" diameter inner leach string and approximately 58 ft of 8-5/8" casing.
- iii. Demobilize workover rig.
- i. Inject nitrogen blanket to 2,420 ft.
- j. Begin water injection at 350 gpm down 8-5/8" x 5-1/2" annulus, recovering brine up the 4-1/2" string. (Reverse Circulation)
- k. Continue leaching in reverse for approximately 150 days.
- l. Bleed nitrogen from wellbore and set interface at 2,410 feet below ground surface.
- m. Continue leaching in reverse for approximately 150 days.
- n. Bleed nitrogen from wellbore and set interface at 2,402 feet below ground surface.
- o. Continue leaching in reverse for approximately 280 days.
- p. Stop water injection into well.
- q. Perform mechanical integrity test of cavern.
- r. Bleed nitrogen from wellbore.

16. Conversion Workover Cavern No. 3

- a. Mobilize workover rig to well.

- b. Remove 5-1/2" and 8-5/8" casing from well.
- c. Run and weld 16" stainless steel suspended liner to approximately 2,407 feet below ground level.
- d. Run new 5-1/2" dewatering string to approximately 2,407 ft below ground surface.
- e. Install dewatering wellhead.
- f. Perform mechanical integrity test of wellhead and wellbore.

17. Dewater Cavern No. 3

- a. Connect portable surface compressors to wellhead.
- b. Begin dewatering, injecting air at approximately 3,750 scfm and recovering brine through dewatering string at approximately 350 gpm.
- c. Continue dewatering for approximately 80 days.
- d. Stop air injection.

18. Final Configuration Workover – Cavern No. 3

- a. Mobilize workover rig to well.
- b. Snub 5-1/2" dewatering string from well.
- c. Install remaining wellhead components.
- d. Demobilize workover rig

19. Cavern No. 3 ready for service.

III.A.10 - Materials and estimates of quantities used / produced

Identify major materials that would be used and produced by the project when the projects are larger than lab or bench scale.

Material Used	Estimated Quantity	Comments
Electricity	4,400,000 KWH	U.S. Salt power for injection pumps.
Water	1,071,000,000 gal	Supplied by U.S. Salt
Others - Diesel Fuel	920,000 gal	Drilling/Workover/Dewater

Material Produced	Estimated Quantity	Comments
Air Emissions	CO – 136,000 lbs NMHC -16,000 lbs NOX – 136,000 lbs PM – 5,200 lbs	Drilling Rig and Dewatering Compressors
Solid Waste	Mud – 12,800 bbl Cuttings – 8,300 bbl	Drill cuttings, drill mud, and cement waste
Brine	1,071,000,000 gal	Brine produced will not be waste product. Brine will be used by U.S. Salt

III.D.6.e - Materials and estimates of quantities used / produced

What types of air emissions, including fugitive emissions, would be anticipated from the proposed project, and what would be the maximum and minimum annual rate of emissions for the project?

Emitted	Maximum Annual Rate	Project Total
CO	46,000 lbs	136,000 lbs
NOx	46,000 lbs	136,000 lbs
PM	1,800 lbs	5,200 lbs

III.D.6.f- Materials and estimates of quantities used / produced

Would any types of emission control or particulate collection devices be used?
No.

III.D.6.g- Materials and estimates of quantities used / produced

If no control devices are used, how would emissions be vented?
Emissions would be from diesel equipment and vented to atmosphere.

III.D.7.a- Hydrologic Conditions / Water Quality

What is the closest body of water to the proposed project area and what is its distance from the project site?

Tributary 72 (Class C) to Seneca Lake is approximately 100 ft away from the closest well drilling site.

III.D.7.b- Hydrologic Conditions / Water Quality

What sources would supply potable water for the proposed project?

Water would be supplied by U.S. Salt from their intake structure on Seneca Lake.

III.D.7.c- Hydrologic Conditions / Water Quality

Quantify the annual amount of wastewater that would be generated by the proposed project.

None. All brine will be used piped to U.S. Salt to be used in their salt plant.

III.D.7.d- Hydrologic Conditions / Water Quality

What would be the major components of each type of wastewater?

No wastewater generated.

III.D.7.e- Hydrologic Conditions / Water Quality

Identify the local treatment facility that would receive wastewater from the proposed project.

No wastewater generated.

III.D.7.f- Hydrologic Conditions / Water Quality

Describe how wastewater would be collected and treated.

No wastewater generated.

III.D.7.g- Hydrologic Conditions / Water Quality

Would any runoff or leachates be produced from storage piles or waste disposal sites?

No.

III.D.7.h- Hydrologic Conditions / Water Quality

Would the project require issuance of new or modified water permits to perform project work or site development?

Yes, would require NPDES for storm water runoff from wellpads.

III.D.7.i- Hydrologic Conditions / Water Quality

Where would wastewater effluents from the proposed project be discharged?
Runoff water would be discharged to surface tributary to Seneca Lake.

III.D.7.j- Hydrologic Conditions / Water Quality

Would the proposed project be permitted to discharge effluents into an existing body of water?
Yes. No treatment of storm water required.

III.D.7.k- Hydrologic Conditions / Water Quality

Would a new or modified National Pollutant Discharge Elimination System (NPDES) permit be required?
Yes, required for surface runoff from wellpads.

III.D.7.l- Hydrologic Conditions / Water Quality

Would the proposed project adversely affect the quality or movement of groundwater?
No.

III.D.7.m- Hydrologic Conditions / Water Quality

Would the proposed project require issuance of an Underground Injection Control (UIC) permit?
Yes. A UIC permit is required to solution mine the cavern.

III.D.8.a- Solid and Hazardous Wastes

Identify and estimate major nonhazardous solid wastes that would be generated from the project.
Drilling mud and drill cuttings

Freshwater drilling mud	8,400 bbl
Saltwater drilling mud	4,500 bbl
Freshwater Drill Cuttings	4,700 bbl
Saltwater Drill Cuttings	3,700 bbl

III.D.8.b- Solid and Hazardous Wastes

Would the project require issuance of new or modified solid waste and / or hazardous waste related permits to perform project activities?
No.

III.D.8.c- Solid and Hazardous Wastes

How and where would solid waste disposal be accomplished?

Drilling mud and cuttings will be contained in a closed loop drilling system. Cuttings would be periodically (as required) transported to a NY State approved solid waste landfill for disposal. Drilling mud will be stabilized and transported to a NY State approved solid waste landfill at the end of freshwater drilling and at the end of drilling a well.

III.D.8.d- Solid and Hazardous Wastes

How would wastes be transported?

Wastes would be transported to landfill by truck.

III.D.8.e- Solid and Hazardous Wastes

Identify hazardous wastes that would be generated, used, or stored under this project.

None.

III.D.8.f- Solid and Hazardous Wastes

Would hazardous or toxic waste be collected and stored.

No.

III.D.8.g- Solid and Hazardous Wastes

If hazardous wastes would require off-site disposal, have arrangements been made with a certified TSD facility.

No hazardous wastes generated.

III.D.9.a- Health / Safety Factors

Identify hazardous or toxic materials that would be used in the proposed project.

Caustic soda may be used as part of the drilling fluids.

III.D.9.b- Health / Safety Factors

What would be the likely impacts of these project related hazardous materials on human health and the environment.

Caustic soda can cause severe chemical burns to unprotected skin.

III.D.9.c- Health / Safety Factors

Would there be any special physical hazards or health risks associated with the project?

No. Hazards typical of drilling, workover and construction will be present at the work site.

NYSEG health and safety programs will be supplemented by programs put in place by specialized contractors who are thoroughly knowledgeable in the construction and operation of underground storage facilities..

III.D.9.d- Health / Safety Factors

Does a worker safety program exist at the location of the proposed project?

No. NYSEG has in place a thorough over riding safety program. This program will be supplemented by a site safety program prior to the start of construction.

During construction all NYSEG Subcontractor Personnel will be adequately trained and qualified to perform their duties. Knowledgeable drilling and workover specialists will be assigned to monitor the job site to make sure that the percentage of inexperienced labor being used by any subcontractor is not so great as to pose a safety hazard to themselves or others working around them.

Operations that require highly skilled or technical expertise will be performed only by those individuals who by virtue of training, experience or education are capable of safely performing the task.

III.D.9.e- Health / Safety Factors

Would safety training be necessary for any laboratory, equipment, or process involved with the project.

Yes. Contractors would have in place a formal safety program for activities.

III.D.9.f- Health / Safety Factors

Describe any increases in ambient noise levels to the public from construction and operational activities.

The noise generating sources for this project are all intermittent. The drilling rig has not been selected at this time. The rig selection, workover rig selection, and compressor selection will be dependent upon availability, making definitive estimates of noise levels unwarranted. Each of the activities listed below is expected to take place at different times (i.e. the noise for each activity is independent of the other activities). No ambient noise measurement or noise modeling has been performed.

Construction activities to build three wellpads are expected to take approximately 4 months. Equipment for building the wellpads includes a backhoe/front end loader, a dozer, a roller compactor, and dump trucks. Activities will be limited to daylight hours.

Rig up and down will be accomplished over an aggregate 36 day period. At present a single 600 hp diesel engine is envisioned as the primary noise source. These activities will take place during daylight hours.

Drilling activities are anticipated to take place on a 24 hr per day basis for an aggregate of 213 days. During drilling two 600 hp diesel engines are envisioned as the primary noise source.

Intermediate workovers are expected to take place over a time period of approximately 15 days. During that time a 500 hp workover rig with a 318 hp mud pump is expected to be operating during daylight hours.

Final configuration workover as scheduled to take place for approximately 90 days. During these workovers a 500 hp workover rig with a 318 hp mud pump is expected to be operating during daylight hours.

The most significant noise impact during cavern construction will be during dewatering. During dewatering 4 – 600 hp diesel driven compressors are anticipated to be operating during an aggregate time period of 234 days (3 – 78 day periods separated from each other by approximately 2 years). Noise data for a CAT C18 driver indicates a $DB(A) = 89.1^1$ at 49.1 ft. for unenclosed engines. Using a chart provided by NYSDEC² the aggregate noise level from 4 compressors is calculated as 95.1 DB(A) at 49.1 feet. NYSEG wells have a 300' buffer to public or private property. Using the methodology set forth by the NYSDEC² an aggregate noise level of 83.1 DB(A) is predicted at a distance 100 ft inside public or private property.

III.D.9.g- Health / Safety Factors

Would project construction result in the removal of natural barriers that act as noise screens?
Yes.

Tree removal for wellpad and drilling road construction.

III.D.8.h- Solid and Hazardous Wastes

Would hearing protection be required for workers?

Yes. Hearing protection in the form of earplugs, ear muffs, or combinations, as recommended or approved by NIOSH is mandatory when the sound levels exceed the permissible noise exposures.

Please do not hesitate to call or email if you have questions or suggestions.

Regards,

¹ Milton Caterpillar. www.miltoncat.com

² New York State DEP. *Assessing and Mitigating Noise Impacts*. DEP-00-1. 2001.

A handwritten signature in blue ink that reads "James M. McHenry". The signature is written in a cursive style, with the first letters of each word being capitalized and prominent. The "M" in "McHenry" is particularly large and stylized.

James M McHenry

NYSEG - SENECA CAES PROJECT

ID	Task Name	Duration	Start	Finish																																																
					2012				2013				2014				2015				2016				2017				2018				2019				2020															
					Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4		
1	Seneca CAES Phase 2 & 3 Project Schedule	2268 days	Mon 11/28/11	Thu 8/6/20																																																
2	Project Milestones	2228 days	Mon 1/23/12	Thu 8/6/20																																																
3	Phase 2 NTP	0 hrs	Mon 1/23/12	Mon 1/23/12																																																
4	Start of Construction	0 hrs	Fri 7/18/14	Fri 7/18/14																																																
5	Complete Cavern 1 Development	0 hrs	Thu 4/21/16	Thu 4/21/16																																																
6	Complete Cavern 2 Development	0 hrs	Thu 6/14/18	Thu 6/14/18																																																
7	Complete Cavern 3 Development	0 hrs	Thu 8/6/20	Thu 8/6/20																																																
8	Complete Construction, Start-up & Commissioning	0 hrs	Tue 7/26/16	Tue 7/26/16																																																
9	Start of Cavern Development	0 hrs	Fri 1/29/16	Fri 1/29/16																																																
10	All Caverns Ready for Service	0 hrs	Thu 8/6/20	Thu 8/6/20																																																
11	Commercial Operations (COD)	0 hrs	Tue 6/28/16	Tue 6/28/16																																																
12	Phase 2 Activities	2268 days	Mon 11/28/11	Thu 8/6/20																																																
13	Management Review of Phase 1 Report	40 days	Mon 11/28/11	Mon 1/23/12																																																
14	Phase 1 Report Submitted to Management	0 hrs	Mon 11/28/11	Mon 11/28/11																																																
15	DOE Review & Notice to Proceed	160 hrs	Tue 11/29/11	Mon 12/26/11																																																
16	Management Review & Notice To Proceed	160 hrs	Tue 12/27/11	Mon 1/23/12																																																
17	Interconnection Agreement	401 days	Tue 1/24/12	Tue 8/6/13																																																
18	Submit Interconnection Request to NYISO	120 hrs	Tue 1/24/12	Mon 2/13/12																																																
19	SRIS Scope Developed & Approved by NYISO	400 hrs	Tue 2/14/12	Mon 4/23/12																																																
20	SRIS Conducted	480 hrs	Tue 4/24/12	Mon 7/16/12																																																
21	NYISO Provides Report to NYSEG	80 hrs	Tue 7/17/12	Mon 7/30/12																																																
22	Submit SRIS to TPAS	160 hrs	Tue 7/31/12	Mon 8/27/12																																																
23	Submit SRIS to Operating Committee	160 hrs	Tue 8/28/12	Mon 9/24/12																																																
24	Operating Committee Approves SRIS	8 hrs	Tue 9/25/12	Tue 9/25/12																																																
25	NYISO Provides Facility Study Agreement to NYSEG	80 hrs	Wed 9/26/12	Tue 10/9/12																																																
26	NYISO Provides Facility Study Cost Estimates to NYSEG	40 hrs	Wed 10/10/12	Tue 10/16/12																																																
27	NYSEG Signs FSA, Deposits \$100,000 with NYISO	160 hrs	Wed 10/17/12	Tue 11/13/12																																																

Task		Rolled Up Task		Split		Inactive Task		Manual Task		Start-only	
Critical Task		Rolled Up Critical Task		External Tasks		Inactive Task		Duration-only		Finish-only	
Milestone		Rolled Up Milestone		Project Summary		Inactive Milestone		Manual Summary Rollup		Progress	
Summary		Rolled Up Progress		Group By Summary		Inactive Summary		Manual Summary		Deadline	

Phase 2 & 3 Project Schedule, October 6, 2011, Rev #0.mpp

NYSEG - SENECA CAES PROJECT

ID	Task Name	Duration	Start	Finish
28	NYISO Conducts Class Year Study	720 hrs	Wed 9/26/12	Tue 1/29/13
29	Study Report Meeting with Class Year Developers	240 hrs	Wed 1/30/13	Tue 3/12/13
30	CAES Sign Engineering & Procurement Agreement	40 hrs	Wed 11/14/12	Tue 11/20/12
31	Interconnection Agreement Sent to NYSEG CAES	160 hrs	Wed 3/13/13	Tue 4/9/13
32	Draft Interconnection Agreement Approved by Developer	160 hrs	Wed 4/10/13	Tue 5/7/13
33	Provide Evidence of Continued Site Control	120 hrs	Wed 5/8/13	Tue 5/28/13
34	NYSEG CAES Executes Interconnection Agreement	320 hrs	Wed 5/29/13	Tue 7/23/13
35	NYISO File Interconnection Agreement with FERC	80 hrs	Wed 7/24/13	Tue 8/6/13
36	NYS Article X Permitting Process	569 days	Tue 1/24/12	Fri 3/28/14
37	Prepare Article X Pre-Application Preparation	912 hrs	Tue 1/24/12	Fri 6/29/12
38	Article X Scoping Statement Filed, Notice Published	0 hrs	Fri 6/29/12	Fri 6/29/12
39	Intervenor Fund Allocation	320 hrs	Mon 7/2/12	Fri 8/24/12
40	Scoping Consultations	160 hrs	Mon 8/27/12	Fri 9/21/12
41	Proposed Study Stipulations Comment Period	200 hrs	Mon 9/24/12	Fri 10/26/12
42	Study Stipulations Signed	32 hrs	Mon 10/29/12	Thu 11/1/12
43	Continue Studies & Application Preparation	880 hrs	Mon 7/2/12	Fri 11/30/12
44	Application Filed and Notice Published	0 hrs	Fri 11/30/12	Fri 11/30/12
45	Completeness Determination	352 hrs	Mon 12/3/12	Thu 1/31/13
46	Application Deemed Complete	0 hrs	Thu 1/31/13	Thu 1/31/13
47	Public Statement Hearings	0 hrs	Mon 3/4/13	Mon 3/4/13
48	Pre-Hearing Conference	16 hrs	Mon 3/4/13	Tue 3/5/13
49	Issues Ruling	0 hrs	Wed 3/27/13	Wed 3/27/13
50	Discovery	280 hrs	Wed 3/27/13	Tue 5/14/13
51	Direct Testimony Prepared & Filed	176 hrs	Wed 5/15/13	Thu 6/13/13
52	Rebuttal Testimony Prepared and Filed	80 hrs	Fri 6/14/13	Thu 6/27/13
53	Hearings	112 hrs	Tue 7/9/13	Fri 7/26/13
54	Briefs to ALJ's	248 hrs	Mon 7/29/13	Mon 9/9/13

Legend:

- Task: Blue box with dots (Rolled Up Task), Red box with dots (Rolled Up Critical Task), Black diamond (Rolled Up Milestone), Grey box (Inactive Task), White box (Manual Task), Green box (Start-only), Blue box (Finish-only), Grey box (Progress), Black box (Deadline).
- Critical Task: Red box with dots (Rolled Up Critical Task), Red box (External Tasks), Red box (Project Summary), Red box (Group By Summary).
- Milestone: Black diamond (Rolled Up Milestone), White diamond (Inactive Milestone), White diamond (Manual Summary Rollup), White diamond (Manual Summary).
- Summary: Grey box (Rolled Up Progress), Black box (Group By Summary), Grey box (Inactive Summary), Grey box (Manual Summary).

NYSEG - SENECA CAES PROJECT

ID	Task Name	Duration	Start	Finish
55	Recommended Decision	168 hrs	Tue 9/10/13	Tue 10/8/13
56	Briefs to Siting Board	168 hrs	Wed 10/9/13	Wed 11/6/13
57	DEC Permits Issued	80 hrs	Thu 11/7/13	Wed 11/20/13
58	Siting Board Decision	168 hrs	Thu 11/7/13	Thu 12/5/13
59	Appeal Period	648 hrs	Fri 12/6/13	Fri 3/28/14
60	CAES Final Design Engineering	725 days	Tue 1/24/12	Mon 11/3/14
61	Mobilze Engineering Resources	160 hrs	Tue 1/24/12	Mon 2/20/12
62	Complete Equipment Design & Specification	960 hrs	Tue 2/21/12	Mon 8/6/12
63	Surface Geotechnical Investigation	640 hrs	Tue 2/21/12	Mon 6/11/12
64	Preliminary/Final Site Plan	480 hrs	Tue 8/7/12	Mon 10/29/12
65	Foundation Design of CTG and Expanders	400 hrs	Tue 1/29/13	Mon 4/8/13
66	Prepare & Issue CTG & Expander Bldg Steel & Foundation Design	560 hrs	Tue 4/9/13	Mon 7/15/13
67	Foundation Design Compressors	200 hrs	Tue 1/29/13	Mon 3/4/13
68	Foundation Design BOP	400 hrs	Tue 2/26/13	Mon 5/6/13
69	Prepare/Issue Compressor Bldg Steel & Foundation Design	320 hrs	Tue 3/5/13	Mon 4/29/13
70	Admin/Control Room Bldg Steel	320 hrs	Tue 6/25/13	Mon 8/19/13
71	General Arrangement Drawings	320 hrs	Tue 10/30/12	Mon 12/24/12
72	Underground Piping Layouts	320 hrs	Tue 12/25/12	Mon 2/18/13
73	Prepare Final Mechanical Equipment Lists, Specifications	1200 hrs	Tue 12/25/12	Mon 7/22/13
74	Fuel Gas Piping Design	480 hrs	Tue 7/23/13	Mon 10/14/13
75	BOP Piping Design	960 hrs	Tue 10/15/13	Mon 3/31/14
76	Complete Control System Logic Design	480 hrs	Tue 7/15/14	Mon 10/6/14
77	Complete Final One Line Electrical Design	480 hrs	Tue 12/25/12	Mon 3/18/13
78	Final Electrical Equipment Lists, Specifications	1200 hrs	Tue 12/17/13	Mon 7/14/14
79	Complete Underground Electric Duct Bank Design	480 hrs	Tue 5/7/13	Mon 7/29/13
80	E & I Design BOP	640 hrs	Tue 7/15/14	Mon 11/3/14
81	Equipment Procurement	728 days	Tue 8/7/12	Thu 5/21/15

Legend:

- Task: Blue hatched bar
- Critical Task: Red hatched bar
- Milestone: Diamond symbol
- Summary: Thick black bar
- Rolled Up Task: Blue hatched bar with dots
- Rolled Up Critical Task: Red hatched bar with dots
- Rolled Up Milestone: Diamond symbol with dots
- Rolled Up Progress: Thick black bar with dots
- Split: Blue hatched bar with vertical lines
- External Tasks: Red hatched bar with vertical lines
- Project Summary: Diamond symbol with vertical lines
- Group By Summary: Thick black bar with vertical lines
- Inactive Task: Grey hatched bar
- Inactive Milestone: Diamond symbol with grey fill
- Inactive Summary: Thick grey bar
- Manual Task: Yellow bar
- Duration-only: Thin white bar
- Manual Summary Rollup: Thin white bar with dots
- Manual Summary: Thin white bar
- Start-only: Green bar
- Finish-only: Blue bar
- Progress: Blue bar with diagonal lines
- Deadline: Thick black bar with downward arrow

Phase 2 & 3 Project Schedule, October 6, 2011, Rev #0.mpp

NYSEG - SENECA CAES PROJECT																											
ID	Task Name	Duration	Start	Finish	2012		2013		2014		2015		2016		2017		2018		2019		2020						
					Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4					
82	CTG / Expanders	728 days	Tue 8/7/12	Thu 5/21/15																							
83	Complete Specification of CTG/Expanders	160 hrs	Tue 8/7/12	Mon 9/3/12																							
84	Bid, Evaluate CTG/Expanders	640 hrs	Tue 9/4/12	Mon 12/24/12																							
85	Award CTG/Expander Contract	40 hrs	Tue 12/25/12	Mon 12/31/12																							
86	Receive CTG/Expanders Loading & Foundation Info	160 hrs	Tue 1/1/13	Mon 1/28/13																							
87	Receive CTG/Expanders Vendor Drawings	240 hrs	Tue 1/1/13	Mon 2/11/13																							
88	Fabricate & Deliver CTG/Expanders	3040 hrs	Fri 12/6/13	Thu 5/21/15																							
89	Compressors	728 days	Tue 8/7/12	Thu 5/21/15																							
90	Complete Specification of Compressors	160 hrs	Tue 8/7/12	Mon 9/3/12																							
91	Bid, Evaluate Compressors	640 hrs	Tue 9/4/12	Mon 12/24/12																							
92	Award Compressor Contract	40 hrs	Tue 12/25/12	Mon 12/31/12																							
93	Fabricate & Deliver Compressors	3040 hrs	Fri 12/6/13	Thu 5/21/15																							
94	Receive Compressor Loading & Foundation Info	160 hrs	Tue 1/1/13	Mon 1/28/13																							
95	Control System	609 days	Tue 9/4/12	Fri 1/2/15																							
96	Complete Specification of Control System	160 hrs	Tue 9/4/12	Mon 10/1/12																							
97	Bid, Evaluate Control System	640 hrs	Tue 10/2/12	Mon 1/21/13																							
98	Award Controls Contract	40 hrs	Tue 1/22/13	Mon 1/28/13																							
99	Design, Manufacture, & Deliver Control System	1600 hrs	Mon 3/31/14	Fri 1/2/15																							
100	Cooling System (Cooling Tower)	644 days	Tue 8/7/12	Fri 1/23/15																							
101	Complete Specification of Cooling Systems	160 hrs	Tue 8/7/12	Mon 9/3/12																							
102	Bid, Evaluate Cooling System Equipment	640 hrs	Tue 9/4/12	Mon 12/24/12																							
103	Award Cooling System Contract	40 hrs	Tue 12/25/12	Mon 12/31/12																							
104	Fabricate & Deliver Cooling System	1720 hrs	Mon 3/31/14	Fri 1/23/15																							
105	Piping System	558 days	Tue 8/7/12	Thu 9/25/14																							
106	Complete Specification of Piping Systems	240 hrs	Tue 8/7/12	Mon 9/17/12																							
107	Bid, Evaluate Piping System Equipment	640 hrs	Tue 9/18/12	Mon 1/7/13																							
108	Award Piping System Contract	40 hrs																									

NYSEG - SENECA CAES PROJECT

ID	Task Name	Duration	Start	Finish	2012 Qtr 3Qtr 4Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2013 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2014 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2015 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2016 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2017 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2018 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2019 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2020 Qtr 1Qtr 2Qtr 3Qtr 4Qtr
109	Fabricate & Deliver Piping System	1032 hrs	Mon 3/31/14	Thu 9/25/14									
110	Pre-Engineered Buildings	453 days	Tue 1/1/13	Thu 9/25/14									
111	Complete Specification of Pre-Engineered Buildings	160 hrs	Tue 1/1/13	Mon 1/28/13									
112	Bid, Evaluate Pre-Engineered Buildings	480 hrs	Tue 1/29/13	Mon 4/22/13									
113	Award Pre-Engineered Buildings Contract	40 hrs	Tue 4/23/13	Mon 4/29/13									
114	Deliver Pre-Engineered Buildings	1032 hrs	Mon 3/31/14	Thu 9/25/14									
115	Structural Steel	309 days	Tue 8/20/13	Fri 10/24/14									
116	Complete Specification of Structural Steel	120 hrs	Tue 8/20/13	Mon 9/9/13									
117	Bid, Evaluate Structural Steel	640 hrs	Tue 9/10/13	Mon 12/30/13									
118	Award Structural Steel Contract	40 hrs	Tue 12/31/13	Mon 1/6/14									
119	Deliver CTG/Expander Building Steel	1200 hrs	Mon 3/31/14	Fri 10/24/14									
120	Deliver Compressor & Admin Area Steel	1200 hrs	Mon 3/31/14	Fri 10/24/14									
121	Generator Step-up Transformers	574 days	Tue 1/1/13	Fri 3/13/15									
122	Complete Specification of GSU Transformers	40 hrs	Tue 1/1/13	Mon 1/7/13									
123	Bid, Evaluate GSU Transformers	640 hrs	Tue 1/8/13	Mon 4/29/13									
124	Award GSU Transformers	40 hrs	Tue 4/30/13	Mon 5/6/13									
125	Deliver GSU Transformers	2000 hrs	Mon 3/31/14	Fri 3/13/15									
126	Aux Transformers	574 days	Tue 1/1/13	Fri 3/13/15									
127	Complete Specification of Aux Transformers	40 hrs	Tue 1/1/13	Mon 1/7/13									
128	Bid, Evaluate Aux Transformers	640 hrs	Tue 1/8/13	Mon 4/29/13									
129	Award Auxiliary Transformers	40 hrs	Tue 4/30/13	Mon 5/6/13									
130	Deliver Auxiliary Transformers	2000 hrs	Mon 3/31/14	Fri 3/13/15									
131	Power Distribution Centers	497 days	Tue 4/30/13	Wed 3/25/15									
132	Complete Specification of Power Distribution Centers	160 hrs	Tue 4/30/13	Mon 5/27/13									
133	Bid, Evaluate Power Distribution Centers	640 hrs	Tue 5/28/13	Mon 9/16/13									
134	Award Power Distribution Centers	40 hrs	Tue 9/17/13	Mon 9/23/13									
135	Deliver Power Distribution Centers	2064 hrs	Mon 3/31/14	Wed 3/25/15									

Task

Critical Task

Milestone

Summary

Rolled Up Task

Rolled Up Critical Task

Rolled Up Milestone

Rolled Up Progress

Split

External Tasks

Project Summary

Group By Summary

Inactive Task

Inactive Task

Inactive Milestone

Inactive Summary

Manual Task

Duration-only

Manual Summary Rollup

Manual Summary

Start-only

Finish-only

Progress

Deadline

NYSEG - SENECA CAES PROJECT																													
ID	Task Name	Duration	Start	Finish	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012	2012
136	Construction Contracts	402 days	Fri 12/6/13	Mon 6/22/15																									
137	Site Remediation	115 days	Fri 12/6/13	Thu 5/15/14																									
138	Develop RFP/Commercial Documents - Site Remediation	240 hrs	Fri 12/6/13	Thu 1/16/14																									
139	Solicit Proposals - Site Remediation	160 hrs	Fri 1/17/14	Thu 2/13/14																									
140	Review Proposals, Negotiate Contract - Site Remediation	480 hrs	Fri 2/14/14	Thu 5/8/14																									
141	Award Contract - Site Remediation	40 hrs	Fri 5/9/14	Thu 5/15/14																									
142	Civil Construction	145 days	Fri 12/6/13	Thu 6/26/14																									
143	Develop RFP/Commercial Documents - Civil Construction	320 hrs	Fri 12/6/13	Thu 1/30/14																									
144	Solicit Proposals - Civil Construction	320 hrs	Fri 1/31/14	Thu 3/27/14																									
145	Review Proposals, Negotiate Contract - Civil Construction	480 hrs	Fri 3/28/14	Thu 6/19/14																									
146	Award Contract - Civil Construction	40 hrs	Fri 6/20/14	Thu 6/26/14																									
147	Mechanical Construction	165 days	Tue 4/1/14	Mon 11/17/14																									
148	Develop RFP/Commercial Documents - Mech Construction	320 hrs	Tue 4/1/14	Mon 5/26/14																									
149	Solicit Proposals - Mechanical Construction	480 hrs	Tue 5/27/14	Mon 8/18/14																									
150	Review Proposals, Negotiate Contract - Mechanical Construction	480 hrs	Tue 8/19/14	Mon 11/10/14																									
151	Award Contract - Mechanical Construction	40 hrs	Tue 11/11/14	Mon 11/17/14																									
152	Electrical Construction	165 days	Tue 11/4/14	Mon 6/22/15																									
153	Develop RFP/Commercial Documents - Electrical Construction	320 hrs	Tue 11/4/14	Mon 12/29/14																									
154	Solicit Proposals - Electrical Construction	480 hrs	Tue 12/30/14	Mon 3/23/15																									
155	Review Proposals, Negotiate Contract - Electrical Construction	480 hrs	Tue 3/24/15	Mon 6/15/15																									
156	Award Contract - Electrical Construction	40 hrs	Tue 6/16/15	Mon 6/22/15																									
157	Switchyard Construction	165 days	Tue 11/4/14	Mon 6/22/15																									
158	Develop RFP/Commercial Documents - Switchyard Construction	320 hrs																											

ID	Task Name	Duration	Start	Finish	2012	2013	2014	2015	2016	2017	2018	2019	2020
163	Site Remediation	45 days	Fri 5/16/14	Thu 7/17/14									
164	Mobilization - Site Remediation	40 hrs	Fri 5/16/14	Thu 5/22/14									
165	Relocate Wetlands	320 hrs	Fri 5/23/14	Thu 7/17/14									
166	Civil Construction	145 days	Fri 7/18/14	Thu 2/5/15									
167	Pre-Engineered Building Foundation Construction (Pour&Cure)	320 hrs	Fri 10/17/14	Thu 12/11/14									
168	CTG & Expanders Foundation Construction (Pour&Cure)	320 hrs	Fri 8/22/14	Thu 10/16/14									
169	CTG/Expanders Building Foundation Construction (Pour&Cure)	320 hrs	Fri 9/19/14	Thu 11/13/14									
170	Compressor Foundation Construction (Pour&Cure)	320 hrs	Fri 9/19/14	Thu 11/13/14									
171	Cooling System Foundation Construction (Pour&Cure)	320 hrs	Fri 10/17/14	Thu 12/11/14									
172	Piping System Foundation Construction (Pour&Cure)	320 hrs	Fri 11/14/14	Thu 1/8/15									
173	Utility Bridge Foundation Construction (Pour&Cure)	320 hrs	Fri 11/14/14	Thu 1/8/15									
174	BOP Foundation Construction (Pour&Cure)	320 hrs	Fri 10/17/14	Thu 12/11/14									
175	Compressor Building Floor Slab Construction (Pour&Cure)	320 hrs	Fri 9/19/14	Thu 11/13/14									
176	CTG/Expanders Building Floor Slab Construction (Pour&Cure)	320 hrs	Fri 9/19/14	Thu 11/13/14									
177	Stack Foundation Construction (Pour&Cure)	320 hrs	Fri 9/19/14	Thu 11/13/14									
178	Transformer Foundation Construction (Pour&Cure)	320 hrs	Fri 9/19/14	Thu 11/13/14									
179	Main Electrical PDC Foundation Construction (Pour&Cure)	320 hrs	Tue 11/4/14	Mon 12/29/14									
180	Install Underground Electrical Ductbanks and Mechanical Piping	480 hrs	Fri 11/14/14	Thu 2/5/15									
181	Mobilization - Civil Contractor	40 hrs	Fri 7/18/14	Thu 7/24/14									
182	Site Preparation	160 hrs	Fri 7/25/14	Thu 8/21/14									
183	Retention Pond Construction	480 hrs	Fri 8/22/14	Thu 11/13/14									
184	Build Earthen Berm	320 hrs	Fri 11/14/14	Thu 1/8/15									
185	Mechanical Construction	293 days	Tue 11/18/14	Thu 12/31/15									
186	Erect Utility Bridge Steel	160 hrs	Fri 1/9/15	Thu 2/5/15									
187	Install Yard Piping	320 hrs	Fri 2/6/15	Thu 4/2/15									
188	Erect Stack	320 hrs	Tue 12/23/14	Mon 2/16/15									
189	Rig & Set CTG and Expanders	80 hrs	Fri 5/22/15	Thu 6/4/15									

Phase 2 & 3 Project Schedule, October 6, 2011, Rev #0.mpp

[illegible]

ID	Task Name	Duration	Start	Finish	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021
217	Construction	800 hrs	Fri 11/7/14	Thu 3/26/15										
218	Commissioning	160 hrs	Fri 3/27/15	Thu 4/23/15										
219	Commercial Operation	0 hrs	Thu 4/23/15	Thu 4/23/15										
220	Inergy Cavern Development	1740 days	Fri 12/6/13	Thu 8/6/20										
221	Cavern 1	620 days	Fri 12/6/13	Thu 4/21/16										
222	Solution Mining - Cavern 1	4160 hrs	Fri 1/31/14	Thu 1/28/16										
223	Drill Casing - Cavern 1	320 hrs	Fri 12/6/13	Thu 1/30/14										
224	Remove Brine - Cavern 1	480 hrs	Fri 1/29/16	Thu 4/21/16										
225	Cavern 2	620 days	Fri 1/29/16	Thu 6/14/18										
226	Solution Mining - Cavern 2	4160 hrs	Fri 3/25/16	Thu 3/22/18										
227	Drill Casing - Cavern 2	320 hrs	Fri 1/29/16	Thu 3/24/16										
228	Remove Brine - Cavern 2	480 hrs	Fri 3/23/18	Thu 6/14/18										
229	Cavern 3	620 days	Fri 3/23/18	Thu 8/6/20										
230	Solution Mining - Cavern 3	4160 hrs	Fri 5/18/18	Thu 5/14/20										
231	Drill Casing - Cavern 3	320 hrs	Fri 3/23/18	Thu 5/17/18										
232	Remove Brine - Cavern 3	480 hrs	Fri 5/15/20	Thu 8/6/20										
233	Construct Natural Gas Interconnection Facilities	360 days	Thu 2/27/14	Thu 7/16/15										
234	Notice to Proceed	0 hrs	Thu 2/27/14	Thu 2/27/14										
235	Develop Engineering Design	480 hrs	Fri 2/28/14	Thu 5/22/14										
236	Materials Procurement	1440 hrs	Fri 5/23/14	Thu 1/29/15										
237	Construction	800 hrs	Fri 1/30/15	Thu 6/18/15										
238	Commissioning	160 hrs	Fri 6/19/15	Thu 7/16/15										
239	Commercial Operation	0 hrs	Thu 7/16/15	Thu 7/16/15										
240	Negotiate Natural Gas Transportation Contracts	60 days	Thu 12/5/13	Thu 2/27/14										
241	Notice to Proceed with Contracting Efforts	0 hrs	Thu 12/5/13	Thu 12/5/13										
242	Negotiate Contracts with Transmission Providers	480 hrs	Fri 12/6/13	Thu 2/27/14										
243	Sign Contracts	0 hrs	Thu 2/27/14	Thu 2/27/14										

NYSEG - SENECA CAES PROJECT

ID	Task Name	Duration	Start	Finish	2012 Qtr 3Qtr 4Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2013 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2014 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2015 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2016 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2017 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2018 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2019 Qtr 1Qtr 2Qtr 3Qtr 4Qtr	2020 Qtr 1Qtr 2Qtr 3Qtr 4Qtr
244	Commissioning & Start-up	201 days	Tue 10/20/15	Tue 7/26/16									
245	CTG, Expanders, Compressor Pre-Commissioning	160 hrs	Tue 10/20/15	Mon 11/16/15									
246	CTG, Expanders, Compressor Lube Oil Flush	120 hrs	Tue 11/17/15	Mon 12/7/15									
247	BOP Commissioning	640 hrs	Tue 2/9/16	Mon 5/30/16									
248	First Firing	8 hrs	Tue 5/31/16	Tue 5/31/16									
249	CTG, Expanders, Compressor Commissioning	160 hrs	Wed 6/1/16	Tue 6/28/16									
250	Substantial Completion	0 hrs	Tue 6/28/16	Tue 6/28/16									
251	Reliability Run, Performance Testing	160 hrs	Wed 6/29/16	Tue 7/26/16									
252	Final Completion	0 hrs	Tue 7/26/16	Tue 7/26/16									
253	Phase 3: Monitoring & Testing	1556 days	Tue 8/7/12	Tue 7/24/18									
254	Plant Systems and Equipment Acceptance Testing	500 days	Tue 8/7/12	Mon 7/7/14									
255	Develop Detailed Equipment Acceptance Testing Plan	320 hrs	Tue 8/7/12	Mon 10/1/12									
256	Factory Acceptance Testing of Systems and Components	1040 hrs	Tue 1/7/14	Mon 7/7/14									
257	Operations & Maintenance Staff Training	1040 hrs	Tue 1/7/14	Mon 7/7/14									
258	Plant Monitoring System	365 days	Tue 8/7/12	Mon 12/30/13									
259	Develop Monitoring System Acceptance Testing Plan	320 hrs	Tue 8/7/12	Mon 10/1/12									
260	Factory Acceptance Testing of System	1920 hrs	Tue 1/29/13	Mon 12/30/13									
261	Operations & Maintenance Staff Training	1920 hrs	Tue 1/29/13	Mon 12/30/13									
262	Operations Data Collection Analysis	1556 days	Tue 8/7/12	Tue 7/24/18									
263	Develop Detailed Data Collection Plan	800 hrs	Tue 8/7/12	Mon 12/24/12									
264	Implement Collection Plan	4160 hrs	Wed 7/27/16	Tue 7/24/18									
265	Produce Required Reports and Analyses	4160 hrs	Wed 7/27/16	Tue 7/24/18									
266	Complete Testing Program	0 hrs	Tue 7/24/18	Tue 7/24/18									

Task

Critical Task

Milestone

Summary

Rolled Up Task

Rolled Up Critical Task

Rolled Up Milestone

Rolled Up Progress

Split

External Tasks

Project Summary

Group By Summary

Inactive Task

Inactive Task

Inactive Milestone

Inactive Summary

Manual Task

Duration-only

Manual Summary Rollup

Manual Summary

Start-only

Finish-only

Progress

Deadline

Phase 2 & 3 Project Schedule, October 6, 2011, Rev #0.mpp10

NEW YORK STATE ELECTIC AND GAS

SENECA COMPRESSED AIR ENERGY STORAGE PROJECT

CYCLE 1 POWER GENERATION EQUIPMENT

SCOPE OF WORK

Document: CAES-1-SW-RPG7

Revision: A

Date: June 2011

WorleyParsons International Inc.

2675 Morgantown Rd.

Reading, PA 19607

USA

Telephone: +1 610 855 2000

Facsimile:

www.worleyparsons.com

© Copyright 2011 WorleyParsons

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 1 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

SYNOPSIS

This document details the scope of work for a budgetary quotation of Cycle 1 Generation Cycle.

Disclaimer

This report has been prepared on behalf of and for the exclusive use of New York State Electric and Gas and is subject to and issued in accordance with the agreement between New York State Electric and Gas and WorleyParsons. WorleyParsons accepts no liability or responsibility whatsoever for it in respect of any use of or reliance upon this report by any third party.

Copying this report without the permission of New York State Electric and Gas or WorleyParsons is not permitted.

REV	DESCRIPTION	ORIG	REVIEW	WORLEY-PARSONS APPROVAL	DATE
A	Issued For Bid	Paul Phiam olis <small>Digitally signed by Paul Phiamolis DN: CN = Paul Phiamolis C = US O = WorleyParsons, OU = Mechanical Department Date: 2011.06.30 13:30:18 -0500</small>	Harry G. Eisenbise e <small>Digitally signed by Harry G. Eisenbise DN: CN = Harry G. Eisenbise C = US O = WorleyParsons, OU = Eastern Operations Date: 2011.06.30 13:31:07 -0500</small>	Harry G. Eisenbise e <small>Digitally signed by Harry G. Eisenbise DN: CN = Harry G. Eisenbise C = US O = WorleyParsons, OU = Eastern Operations Date: 2011.06.30 13:31:50 -0500</small>	June 2011

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 1 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

1.0 General Information

The Seller shall supply all the equipment within this Scope of Work document for a First Generation Compressed Air Energy Storage plant.

The equipment / system specified herein combined with the other equipment contained in the package shall be installed and operated in a First Generation Compressed Air Energy Storage plant located in Reading, NY. Site Specific Data which includes climate, structural, and utility supply data are displayed in Attachment A. English units shall be the system of units.

It is expected that the Seller shall read overall Attachment C – Seneca CAES Project Value Drivers and apply these items within the design of the cycle and equipment.

2.0 Scope of Supply

The equipment, material and services to be provided by the Seller shall include but not be limited to the following:

1. All thermodynamic and engineering cycle work within the requirements of this Scope document.
2. One (1) Gas Fired Air Turbine Generator package and auxiliaries as described per CAES-1-SP-RPG7, "Budgetary Quotation for Air Turbine Generator" and in Exhibit 1 – Air Turbine Generator Scope of Supply.
3. One (1) Recuperator package and auxiliaries as shown per CAES-1-SP-MQ01, "Budgetary Quotation for Recuperator" and in Exhibit 1 – Recuperator Scope of Supply.
4. Cavern air flow control valve to regulate air flow to the power generation equipment.
5. Gas Exit Stack for Recuperator
6. Interconnecting piping and ductwork design and material between all Seller provided equipment.
7. All necessary controls, instrumentation, and valves necessary for proper and safe operation of the complete cycle and plant.
8. Spare parts for erection, start-up and commissioning.
9. Two (2) years spare parts.
10. Special tools for erection, commissioning, operation, and maintenance.

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 1 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

3.0 Utility Supply Conditions

3.1 Site Conditions

See Attachment A.

3.2 Mechanical

See Attachment A for instrument air data, Attachment B for Water Quality, and Attachment D for Fuel Gas Analysis. Fuel gas supply pressure is in the range of 700-800 psig.

3.3 Electrical

See Attachment A for motor voltages.

4.0 Seller Technical Requirements

4.1 It is expected that the Seller shall engineer, design, supply, and guarantee the complete power generation process for a First Generation Compressed Air Energy Storage plant. The power generated during the generation cycle shall be maximized given the constraints of the process and the drivers shown in Attachment C – Seneca CAES Project Value Drivers.

4.2 Cavern and Electrical Constraints

Max Cavern Pressure, psig	1340
Min Cavern Pressure, psig	480
Cavern Air Temperature, °F	95
Cavern Size, ft ³	5,000,000
Line Capacity, MVA	200

4.3 The Seller shall design all equipment to meet the requirements listed within the attached Request for Budgetary Quotation documents.

4.4 All equipment and work not included within this Scope document and the attached Equipment Quotation Requests are assumed to be provided by Owner.

4.5 The Seller shall provide any cost saving solutions or options for improved performance not listed within this package.

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 1 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

5.0 Information and Data Requirements

- 5.1 Price summary and breakdown price schedule with Seller's Scope.
- 5.2 Exceptions and deviations against the Scope of Work and Equipment Requirements.
- 5.3 Seller's bid data for all equipment including:
 - a. Thermal Performance predictions including power output, exhaust pressures losses, exit temperatures, and equipment efficiencies.
 - b. Process flow diagrams detailing flow, temperature, and pressure values of gas, air, and water streams.
 - c. Emissions Data (NO_x, CO, VOC, CO₂).
 - d. Technical data sheets including all auxiliary equipment.
 - e. General Arrangement Drawings (plan, elevation, section).
 - f. Utility Consumption List (cooling water, instrument air, electricity, fuel gas requirements).
 - g. Equipment Weights.
 - h. Auxiliary load list including all auxiliary equipment.
- 5.4 P&I diagrams showing the terminal points for scope of supply.
- 5.5 Priced list for Maintenance spares and consumables.
- 5.6 Noise Data.
- 5.7 Control System overview with control philosophy.
- 5.8 Any additional requirements listed on the Budgetary Quotation documents.

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 1 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

6.0 Additional Documents

- 6.1 CAES-1-SP-MQ01, "Budgetary Quotation for Recuperator"
- 6.2 CAES-1-SP-RPG7, "Budgetary Quotation for Air Turbine Generator"
- 6.3 Attachment A – Site Specific Data
- 6.4 Attachment B – Water Analysis
- 6.5 Attachment C – Seneca CAES Project Value Drivers
- 6.6 Attachment D – Fuel Gas Composition

ATTACHMENT A

SITE SPECIFIC DATA

General:

Location:	Reading Center, New York
Elevation (feet above mean sea level)	1,000
Outdoor Ambient Temperature Range:	(-)2 to 87 °F
Outdoor Ambient Design Temperature for HVAC (ASHRAE 2009)	
Summer (1.0% cooling):	87° F DB, 71° F WB
Winter (99.6% heating):	(-) 2° F DB
Design Indoor Temperature Range (Control Room, DCS Room, Office Areas, Electrical Rooms):	70 to 75°F
Design Indoor RH Range (Control Room, DCS Room, Office Areas, Electrical Rooms):	40 to 60% RH
Design Indoor Temperature Range for Ventilated Areas	45 to 90° F

Structural Data:

Building Design Codes:	IBC 2006 ASCE 7-05
Wind Load	
Exposure Category (IBC 2006, Section 1609.4)	C
Basic Wind Speed, V (IBC 2006), mph	90
Occupancy Category of Buildings and Structures (IBC 2006, Table 1604.5)	III
Importance Factor, I (ASCE 7-05, Table 6-1)	1.15
Snow Load	
Ground Snow Load, p _g (IBC 2006, Figure 1608.2)	35 psf
Exposure Category (IBC 2006, Section 1609.4)	C
Exposure Factor C _e (ASCE 7-05, Table 7-2)	1.0
Occupancy Category of Buildings and Structures (IBC 2006, Table 1604.5)	III
Importance Factor, I (ASCE 7-05, Table 7-4)	1.1
Rainfall	
Annual Average, inches	36
10 yr, 24 hr, inches	3.9
25 yr, 24 hr inches	4.5
Earthquake Loads	
Site Class (IBC 2006 Table 1613.5.2)	C
Mapped Spectral Response Acceleration, short period, S _s (IBC 2006 Figure 1613.5(1))	0.162 g
Mapped Spectral Response Acceleration, 1 second period, S ₁ (IBC 2006 Figure 1613.5(2))	0.054g
Seismic Design Category (IBC 2006 Table 1613.5.6(1) & Table 1613.5.6(2))	A
Occupancy Category of Buildings and Structures (IBC 2006, Table 1604.5)	III
Importance Factor, I (ASCE 7-05, Table 11.5-1)	1.25

Electrical Data:

AC Power			
Medium Voltage	13.8 kV	3P, 3W	60 Hz
Low Voltage Power	480 V	3P, 3W	60 Hz
	208/120V	3P, 4W	60 Hz
Motors			
<= 1/3 hp motor (Except MOVs)	115 V	1P, 2W	60 Hz
> 1/3 hp but < 250 hp motor and MOVs	460 V	3P, 3W	60 Hz
>= 250 hp motor	13.2 kV	3P, 3W	60 Hz
Welding Receptacles	480 V	3P, 3W	60 Hz
Lighting	480 V	3P, 4W	60 Hz
DC Power			
Control Circuits	125 VDC	NA	NA
Instrument Power	120 VAC	1P, 2W	60 Hz

Mechanical Data:

Maximum Cooling Water Temperature, deg F	80
Site Air	
Instrument Air Maximum Pressure, psig	125
Instrument Air Dewpoint, °F	-40
Service Air Maximum Pressure, psig	125
Instrument / Service Air Maximum Temperature, °F	100
Noise Requirements	
Near Field (3 feet horizontally, 5 feet vertically from machine baseline)	90 dBA
Far Field (Plant equipment measured 400' from plant site)	45 dBA

Notes:

None

ATTACHMENT B

Water Analysis

Circulating Cooling Water

Cations	Concentration (mg/L)
Calcium (as CaCO ₃)	336.0
Magnesium (as CaCO ₃)	88.00
Sodium (as Na)	1072
Potassium (as K)	21.60
Total Hardness	424
Anions	
Chloride (as Cl)	1112
Sulfate (as SO ₄)	1052
Silica (as SiO ₂)	14.40
Phosphate (as PO ₄)	85.60
Nitrate	4.00
Total Alkalinity	46
Parameters	
pH	7.00
Max Supply Temperature	80 °F
Suspended Solids	12.00 mg/L

Raw Water

Cations	Concentration (mg/L)
Calcium (as CaCO ₃)	42.00
Magnesium (as CaCO ₃)	11.00
Sodium (as Na)	133.96
Potassium (as K)	2.70
Anions	
Chloride (as Cl)	139.0
Sulfate (as SO ₄)	38.00
Silica (as SiO ₂)	1.80
Phosphate (as PO ₄)	10.70
Nitrate	0.500
Total Alkalinity	106
Parameters	
Temperature	60 °F
Suspended Solids	1.50 mg/L

Data based on preliminary calculations.

ATTACHMENT C

SENECA CAES PROJECT VALUE DRIVERS

Purpose:

This document presents an overview on the different operating modes in which the Seneca CAES is anticipated to operate and the key parameters that will make such operation, and thus the project, successful.

Bidders should optimize these key parameters - moderated against the goals of producing a facility that is characterized by its safety, simplicity of operation, and reliability; and moderated by the incremental cost of further optimizing any particular key parameter.

Key Parameters:

Compression (Cavern Charging):

Minimum time required to charge 5 million cubic foot cavern from its minimum charge of 480 psig to 1,340 psig as measured at well head, limited by maximum available line capacity of 200 MVA with 0.85 power factor. Grade is approximately 1,000 feet above MSL and the top of the cavern is approximately 1,200 feet below MSL.

Turn down to allow compression at reduced available power down to 40 MVA.

Confirm whether compressor-motors can be de-coupled to operate in synchronous condenser mode. If feasible, provide "D" curves (leading and lagging), how much energy is required to spin them, and what is the maximum capacity.

Generation:

Minimum output value (meeting emissions limits).

Maximum output value (limited to same available line capacity as above.)

Heat rate and energy ratio – provide values for each 10% increase in output levels, starting at zero output.

Minimum start-up time – provide time to achieve each 10% increase in total output up to full load.

Confirm a minimum ramp rate of 8 MW/min, up and down, when operating above minimum load.

Minimum time to go from compression to generation. Minimum time to go from generation to compression. Target for both is 5 minutes or less.

ATTACHMENT C

SENECA CAES PROJECT VALUE DRIVERS

Minimum time to achieve synchronization.

Confirm whether expanders-generators can be de-coupled to operate in synchronous condenser mode. If feasible, provide “D” curves (leading and lagging), how much energy is required to spin them, and what is the maximum capacity.

Combined:

What is the breakpoint for energy ratio or heat input with respect to going from 480 psig to 1,340 psig?

Other:

Confirm that black start capability can be provided and provide option price for this feature.

Expected Revenue Opportunity Breakdown:

ATTACHMENT D

Fuel Gas Composition

Component	Typical Analysis (mole %)	Range (mole %)
Methane	94.9	87.0 - 96.0
Ethane	2.5	1.8 - 5.1
Propane	0.2	0.1 - 1.5
iso - Butane	0.03	0.01 - 0.3
n - Butane	0.03	0.01 - 0.3
iso - Pentane	0.01	Trace - 0.14
n - Pentane	0.01	Trace - 0.04
Hexanes+	0.01	Trace - 0.06
Nitrogen	1.6	1.3 - 5.6
Carbon Dioxide	0.7	0.1 - 1.0
Oxygen	0.02	0.01 - 0.1
Hydrogen	trace	Trace - 0.02
Specific Gravity	0.585	0.57 – 0.62
Lower Heating Value (Btu/scf), dry basis	960	914 - 1021

Data based on Russell Station Project.

WorleyParsons

resources & energy

EcoNomics™

NEW YORK STATE ELECTRIC AND GAS

SENECA COMPRESSED AIR ENERGY STORAGE PROJECT

CYCLE 2 POWER GENERATION EQUIPMENT

SCOPE OF WORK

Document: CAES-1-SW-RPG0

Revision: A

Date: September 2011

WorleyParsons International Inc.

2675 Morgantown Rd.

Reading, PA 19607

USA

Telephone: +1 610 855 2000

Facsimile:

www.worleyparsons.com

© Copyright 2011 WorleyParsons

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 2 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

SYNOPSIS

This document details the scope of work for a budgetary quotation of CAES 2 Generation Cycle.

Disclaimer

This report has been prepared on behalf of and for the exclusive use of New York State Electric and Gas and is subject to and issued in accordance with the agreement between New York State Electric and Gas and WorleyParsons. WorleyParsons accepts no liability or responsibility whatsoever for it in respect of any use of or reliance upon this report by any third party.

Copying this report without the permission of New York State Electric and Gas or WorleyParsons is not permitted.

REV	DESCRIPTION	ORIG	REVIEW	WORLEY-PARSONS APPROVAL	DATE
A	Issued For Bid	<small>Digitally signed by Paul Phiambolis DN: CN = Paul Phiambolis C = US O = WorleyParsons CO = Mechanical Department Date: 2011.09.28 13:10:13 -0500</small> P. Phiambolis	<small>Digitally signed by Harry G. Eisenbise DN: CN = Harry G. Eisenbise C = US O = WorleyParsons CO = Eastern Operations Date: 2011.09.28 13:01:03 -0500</small> Harry Eisenbise	<small>Digitally signed by Harry G. Eisenbise DN: CN = Harry G. Eisenbise C = US O = WorleyParsons CO = Eastern Operations Date: 2011.09.28 13:01:28 -0500</small> Harry Eisenbise	September 2011

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 2 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

1.0 General Information

The Seller shall supply all the equipment within this Scope of Work document for a Second Generation Compressed Air Energy Storage plant.

The equipment / system specified herein combined with the other equipment contained in the package shall be installed and operated in a Second Generation Compressed Air Energy Storage plant located in Reading, NY. Site Specific Data which includes climate, structural, and utility supply data are displayed in Attachment A. English units shall be the system of units.

2.0 Scope of Supply

The equipment, material and services to be provided by the Seller shall include but not be limited to the following:

1. All thermodynamic and engineering cycle work within the requirements of this Scope document.
2. Combustion Turbine Generator package and auxiliary options shown in CAES-1-SP-RPG0, "Budgetary Quotation for Combustion Turbine Generator".
3. One (1) Air Turbine Generator package and auxiliaries as described per CAES-1-SP-RPG8, "Budgetary Quotation for Air Turbine Generator" and in Exhibit 1 – Air Turbine Generator Scope of Supply.
4. One (1) Recuperator package and auxiliaries as shown per CAES-1-SP-MQ00, "Budgetary Quotation for Recuperator".
5. Stacks for Recuperator and Expander including a common stack option if deemed technically superior.
6. Interconnecting piping and ductwork design and material between all Seller provided equipment.
7. All necessary controls, instrumentation, and valves necessary for proper and safe operation of the complete cycle and plant.
8. Spare parts for erection, start-up and commissioning.
9. Two (2) years spare parts.
10. Special tools for erection, commissioning, operation, and maintenance.

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 2 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

3.0 Utility Supply Conditions

3.1 Site Conditions

See Attachment A.

3.2 Mechanical

See Attachment A for instrument air data, Attachment B for Water Quality, and Attachment D for Fuel Gas Analysis.

3.3 Electrical

See Attachment A for motor voltages.

5.0 Seller Technical Requirements

- 5.1 It is expected that the Seller shall engineer, design, supply, and guarantee the complete power generation process for a Second Generation Compressed Air Energy Storage plant. The power generated during the generation cycle shall be maximized given the constraints of the process.

5.2 Cavern and Electrical Constraints

The Supplier shall select compression / generation equipment with the following plant design parameters:

Max Cavern Pressure/Temperature, psig/deg F	1500 / 125
Min Cavern Pressure/Temperature, psig/deg F	1150 / 85
Total Usable Air Stored in Cavern, lbs	17,800,000
Maximum Compression Power Available, kW	170,000
Maximum Desired Net Plant Output, kW	210,000

- 5.3 The Seller shall design all equipment to meet the requirements listed within the attached Request for Budgetary Quotation documents.
- 5.4 All equipment and work not included within this Scope document and the attached Equipment Quotation Requests are assumed to be provided by Owner.

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 2 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

- 5.5 The Seller shall provide any cost saving solutions or options for improved performance not listed within this package.

6.0 Information and Data Requirements

- 6.1 Price summary and breakdown price schedule with Seller's Scope.
- 6.2 Exceptions and deviations against the Scope of Work and Equipment Requirements.
- 6.3 Seller's bid data for all equipment including:
- a. Thermal Performance predictions including power output, exhaust pressures losses, exit temperatures, and equipment efficiencies.
 - b. Process flow diagrams detailing flow, temperature, and pressure values of gas, air, and water streams.
 - c. Emissions Data (NOx, CO, VOC, CO2).
 - d. Technical data sheets including all auxiliary equipment.
 - e. General Arrangement Drawings (plan, elevation, section).
 - f. Utility Consumption List (cooling water, instrument air, electricity, water washing, fuel gas requirements).
 - g. Equipment Weights.
 - h. Auxiliary load list including all auxiliary equipment.
- 6.4 P&I diagrams showing the terminal points for scope of supply.
- 6.5 Priced list for Maintenance spares and consumables.
- 6.6 Noise Data.
- 6.7 Control System overview with control philosophy.
- 6.8 Any additional requirements listed on the Budgetary Quotation documents.

7.0 Additional Documents

- 7.1 CAES-1-SP-RPG0, "Budgetary Quotation for Combustion Turbine Generator"
- 7.2 CAES-1-SP-MQ00, "Budgetary Quotation for Recuperator"

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
CYCLE 2 POWER GENERATION EQUIPMENT
SCOPE OF WORK**

- 7.3 CAES-1-SP-RPG8, "Budgetary Quotation for Air Turbine Generator"
- 7.4 Attachment A – Site Specific Data
- 7.5 Attachment B – Water Analysis
- 7.6 Attachment C – Not Used
- 7.7 Attachment D – Fuel Gas Composition

ATTACHMENT A

SITE SPECIFIC DATA

General:

Location:	Reading Center, New York
Elevation (feet above mean sea level)	1,000
Outdoor Ambient Temperature Range:	(-)2 to 87 °F
Outdoor Ambient Design Temperature for HVAC (ASHRAE 2009)	
Summer (1.0% cooling):	87 °F DB, 71 °F WB
Winter (99.6% heating):	(-) 2 °F DB
Design Indoor Temperature Range (Control Room, DCS Room, Office Areas, Electrical Rooms):	70 to 75 °F
Design Indoor RH Range (Control Room, DCS Room, Office Areas, Electrical Rooms):	40 to 60% RH
Design Indoor Temperature Range for Ventilated Areas	45 to 90 °F

Structural Data:

Building Design Codes:	IBC 2006 ASCE 7-05
Wind Load	
Exposure Category (IBC 2006, Section 1609.4)	C
Basic Wind Speed, V (IBC 2006), mph	90
Occupancy Category of Buildings and Structures (IBC 2006, Table 1604.5)	III
Importance Factor, I (ASCE 7-05, Table 6-1)	1.15
Snow Load	
Ground Snow Load, p _g (IBC 2006, Figure 1608.2)	35 psf
Exposure Category (IBC 2006, Section 1609.4)	C
Exposure Factor C _e (ASCE 7-05, Table 7-2)	1.0
Occupancy Category of Buildings and Structures (IBC 2006, Table 1604.5)	III
Importance Factor, I (ASCE 7-05, Table 7-4)	1.1
Rainfall	
Annual Average, inches	36
10 yr, 24 hr, inches	3.9
25 yr, 24 hr inches	4.5
Earthquake Loads	
Site Class (IBC 2006 Table 1613.5.2)	C
Mapped Spectral Response Acceleration, short period, S _s (IBC 2006 Figure 1613.5(1))	0.162 g
Mapped Spectral Response Acceleration, 1 second period, S ₁ (IBC 2006 Figure 1613.5(2))	0.054g
Seismic Design Category (IBC 2006 Table 1613.5.6(1) & Table 1613.5.6(2))	A
Occupancy Category of Buildings and Structures (IBC 2006, Table 1604.5)	III
Importance Factor, I (ASCE 7-05, Table 11.5-1)	1.25

Electrical Data:

AC Power			
Medium Voltage	13.8 kV	3P, 3W	60 Hz
Low Voltage Power	480 V	3P, 3W	60 Hz
	208/120V	3P, 4W	60 Hz
Motors			
<= 1/3 hp motor (Except MOVs)	115 V	1P, 2W	60 Hz
> 1/3 hp but < 250 hp motor and MOVs	460 V	3P, 3W	60 Hz
>= 250 hp motor	13.2 kV	3P, 3W	60 Hz
Welding Receptacles	480 V	3P, 3W	60 Hz
Lighting	480 V	3P, 4W	60 Hz
DC Power			
Control Circuits	125 VDC	NA	NA
Instrument Power	120 VAC	1P, 2W	60 Hz

Mechanical Data:

Maximum Cooling Water Temperature, deg F	80
Site Air	
Instrument Air Maximum Pressure, psig	125
Instrument Air Dewpoint, °F	-40
Service Air Maximum Pressure, psig	125
Instrument / Service Air Maximum Temperature, °F	100
Noise Requirements	
Near Field (3 feet horizontally, 5 feet vertically from machine baseline)	90 dBA
Far Field (Plant equipment measured 400' from plant site)	45 dBA

Notes:

None

ATTACHMENT B

Water Analysis

Circulating Cooling Water

Cations	Concentration (mg/L)
Calcium (as CaCO ₃)	336.0
Magnesium (as CaCO ₃)	88.00
Sodium (as Na)	1072
Potassium (as K)	21.60
Total Hardness	424
Anions	
Chloride (as Cl)	1112
Sulfate (as SO ₄)	1052
Silica (as SiO ₂)	14.40
Phosphate (as PO ₄)	85.60
Nitrate	4.00
Total Alkalinity	46
Parameters	
pH	7.00
Max Supply Temperature	80 °F
Suspended Solids	12.00 mg/L

Raw Water

Cations	Concentration (mg/L)
Calcium (as CaCO ₃)	42.00
Magnesium (as CaCO ₃)	11.00
Sodium (as Na)	133.96
Potassium (as K)	2.70
Anions	
Chloride (as Cl)	139.0
Sulfate (as SO ₄)	38.00
Silica (as SiO ₂)	1.80
Phosphate (as PO ₄)	10.70
Nitrate	0.500
Total Alkalinity	106
Parameters	
Temperature	60 °F
Suspended Solids	1.50 mg/L

Data based on preliminary calculations.

ATTACHMENT D

Fuel Gas Composition

Component	Typical Analysis (mole %)	Range (mole %)
Methane	94.9	87.0 - 96.0
Ethane	2.5	1.8 - 5.1
Propane	0.2	0.1 - 1.5
iso - Butane	0.03	0.01 - 0.3
n - Butane	0.03	0.01 - 0.3
iso - Pentane	0.01	Trace - 0.14
n - Pentane	0.01	Trace - 0.04
Hexanes+	0.01	Trace - 0.06
Nitrogen	1.6	1.3 - 5.6
Carbon Dioxide	0.7	0.1 - 1.0
Oxygen	0.02	0.01 - 0.1
Hydrogen	trace	Trace - 0.02
Specific Gravity	0.585	0.57 – 0.62
Lower Heating Value (Btu/scf), dry basis	960	914 - 1021

Data based on Russell Station Project.

NEW YORK STATE ELECTIC AND GAS

SENECA COMPRESSED AIR ENERGY STORAGE PROJECT

PROCESS AIR COMPRESSOR

REQUEST FOR BUDGETARY QUOTATION

Document: CAES-1-SP-MFC1

Revision: B

Date: June 2011

WorleyParsons International Inc.

2675 Morgantown Rd.

Reading, PA 19607

USA

Telephone: +1 610 855 2000

Facsimile:

www.worleyparsons.com

© Copyright 2011 WorleyParsons

**NYSEG COMPRESSED AIR ENERGY STORAGE PROJECT
PROCESS AIR COMPRESSOR
REQUEST FOR BUDGETARY QUOTATION**

SYNOPSIS

This document presents the design criteria for the preparation of a budgetary quotation for an Air Compressor System.

Disclaimer

This report has been prepared on behalf of and for the exclusive use of New York State Electric and Gas and is subject to and issued in accordance with the agreement between New York State Electric and Gas and WorleyParsons. WorleyParsons accepts no liability or responsibility whatsoever for it in respect of any use of or reliance upon this report by any third party.

Copying this report without the permission of New York State Electric and Gas or WorleyParsons is not permitted.

REV	DESCRIPTION	ORIG	REVIEW	WORLEY-PARSONS APPROVAL	DATE
A	Issued For Review	Paul Phiambolis	Jay White	Harry G. Eisenbise	June 15, 2011
B	Issued For Bid	Paul Phiambolis	Jay White	Harry G. Eisenbise	June 22, 2011