Facsimile Price \$ 1.60
Microfilm Price \$.80

Available from the
Office of Technical Services
Department of Commerce
Washington 25, D. C.

BAW-1291, Ca-7
Joint U.S. -Euratom

NON-UNIFORM HEAT GENERATION
EXPERIMENTAL PROGRAM

Quarterly Progress Report No. 2

September - December 1963

FOR RESTRICTED INTERNAL
DISSEMINATION ONLY

To expedite dissemination of technical information to those persons requiring it, this report has been issued without the administrative review necessary to protect the interests of the U. S. Government, the European Atomic Energy Community (Euratom), and The Babcock & Wilcox Company. The recipient of this report agrees that it is passed to him in confidence and that he will maintain that confidence and make no disclosures or publication of the contents that would be detrimental to the interests of the U. S. Government, the European Atomic Energy Community (Euratom), and The Babcock & Wilcox Company.

AEC Contract No. AT(30-1)-3238
B&W Contract No. 59-3090

Submitted to
THE UNITED STATES ATOMIC ENERGY COMMISSION
by
THE BABCOCK & WILCOX COMPANY
Atomic Energy Division
Lynchburg, Virginia

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

LIST OF PRINCIPAL INVESTIGATORS

ATOMIC ENERGY DIVISION

D. F. Judd
Technical Manager

R. H. Wilson
Analytical Program

ALLIANCE RESEARCH CENTER

H. S. Swenson
R. A. Lee
J. W. Ackerman

Experimental Program

PREFACE

The Babcock & Wilcox Company and the United States Atomic Energy Commission acting for the Joint U.S. -Euratom Research and Development Board signed an agreement for a non-uniform heat generation experimental program.

The program includes experimental and analytical investigations to determine how non-uniformly distributed heat flux along lengths of tubular and annular channels affect the onset of burnout (departure from nucleate boiling). The experimental program is being conducted on the 1.8-MW heat transfer facility at B&W's Research Center, Alliance, Ohio. The analytical program is being conducted by the Atomic Energy Division, Lynchburg, Virginia.

The second calendar quarter of this program has been spent designing, procuring, fabricating, and modifying the heat transfer facility. Sufficient design work, procurement, and facility modification are expected to be completed in the third quarter so that test work can begin and experimental data can be obtained.

ABSTRACT

The Babcock & Wilcox Company, as part of the Joint U.S. -Euratom Research and Development Program, is conducting experimental and analytical investigations to determine the effects of irregular heat flow through reactor channels on the operating conditions that cause burnout (departure from nucleate boiling). This program seeks to improve design correlations that will be suitable for direct use by reactor designers. Tubular specimens having four axial power shapes and annular specimens having five power shapes will be used, and an effort to correlate the experimental data with empirical and analytical models will be made.

The second quarter of this program has been spent designing, procuring, fabricating, and formulating plans in preparation for the initial test work. The bus bars, loop piping, and Test Section No. 1 are complete and installed except for the final connections. The primary elements for the instrumentation and control modifications are ready for installation and will be installed when the loop is shut down to make the final connections for the test section.

Considerable effort has been expended to obtain a satisfactory supply source for the non-uniform test sections. It appears that the azimuthal variation of heat generation will be between $\pm 2\frac{1}{2}$ to 5%.

Procedures are being formulated for checking out the new equipment and loop modifications prior to test operations. Preliminary test runs will be made to substantiate the performance specifications or to establish new requirements before test data are taken.

CONTENTS

	Page
1. INTRODUCTION	1
2. PROGRAM	3
2.1. Test Facility Modifications	3
2.2. Test Sections	3
3. FACILITY CHECKOUT	9
4. PROGRAM SCHEDULE	10

List of Tables

Table

1. OD (in.) of Tubular Test Sections	5
2. Dimensions (in.) of Annular Test Sections	6

List of Figures

Figure

1. Schematic of Test Section in Loop	7
2. Photograph of Test Section No. 1	8
3. Schedule of Non-Uniform Heat Program	11

1. INTRODUCTION

Nuclear reactors and modern boilers require more and more knowledge about the limitations on the transfer rates of heat from channel walls to flowing liquids. Burnout (departure from nucleate boiling) is a very serious design problem still facing the reactor designer. The result of this phenomenon is that the heat transfer conductance is reduced considerably, causing the metal and fuel temperatures to rise and initiate failure of the fuel element. Although considerable attention has been given to this problem in recent years, the predictability of the occurrence of burnout conditions is quite uncertain. In fact, there is still much disagreement on the effect of the channel geometry and operating conditions upon burnout.

In an effort to clarify some of the areas of disagreement, Babcock & Wilcox (B&W), as part of the Joint U.S. -Euratom Research and Development Program, is conducting an experimental and analytical program to determine the effects of non-uniform heat generation rates in tubular and annular flow channels on the operating conditions causing burnout under experimental conditions representative of water reactor systems. The objective of the program is to seek improved design correlations suitable for direct use by reactor designers. The technical approach to the work emphasizes the development of an improved understanding of the physical phenomena involved and their relation to design variables.

The experimental program, which was discussed in the first quarterly report (BAW-1287)^{*}, will be conducted on a B&W heat transfer facility at its Research Center in Alliance, Ohio. The controlled variables

- - - - -
^{*}D. F. Judd et al, Non-Uniform Heat Generation Experimental Program, Quarterly Technical Report No. 1, The Babcock & Wilcox Company, BAW-1287, Lynchburg, Virginia, July - September 1963.

for the tests are pressure, inlet subcooling, and mass velocity. These variables will be investigated over the ranges of from 1000 to 2000 psia pressure, 0.5×10^6 to 2.5×10^6 lb/hr-ft² velocity, and 20 to 150 F subcooling. The tests will be performed in 6-foot-long tubular and annular test sections having both uniform and non-uniform axial heat flux distributions. The analytical program will then be conducted by the Atomic Energy Division in Lynchburg, Virginia.

The first quarter was spent planning, designing, and initiating procurement to begin the program. Work this quarter has been directed toward carrying out the plans of the first quarter, emphasizing the completion of test facility modifications so that testing can be started.

Troubles that developed in the d-c power supply set back the initiation of the test program. Parts of the power supply were removed and returned to the manufacturer for repairs. The full extent of the delay will be evaluated after the power supply has been returned and checked out.

2. PROGRAM

2.1. Test Facility Modifications

2.1.1. Instrumentation and Control

The power-measuring equipment has been completely installed except for final circuitry connections. The system flow, system pressure, and test section pressure-drop instrumentation is either at the facility or on order. The flow control system is ready for installation. Detailed plans and specifications have been completed for the installation of this equipment when the loop is shut down to make the final test section connections.

2.1.2. D-C Power Supply and Control Unit

The bus-bar system has been designed to accommodate either the tubular or annular test section. The material for the changes has been purchased and fabricated. The bus bars for the tubular test sections have been installed except for the final connection that will be made when the test section is connected into the loop. Modifications on the d-c power supply will be resumed when it is returned from the vendor.

2.1.3. Burnout Detector

Four fast-response voltage recorders to be used in conjunction with the burnout detector have been purchased and are being installed. High precision and response are desired so that the stability of the tube-metal temperatures can be observed.

2.2. Test Sections

2.2.1. Tubular Test Sections

The design work for all of the tubular test sections has been completed and the material has been ordered. Test Section No. 1

has been fabricated and installed in the loop except for final connection to the piping, power supply, and instrumentation. Figure 1 is a schematic of the test section installation. Figure 2 is a photograph of this test section attached to a support angle.

The wall thicknesses for the non-uniform test sections have been computed to obtain the desired axial heat generation shape and to limit the stresses at the thinnest section to an acceptable value. Table 1 presents the configurations of the four tubular test sections.

Fabrication of Test Sections 2, 3, and 4 will start as soon as a source to machine the wall variations has been selected. The specification on azimuthal heat generation is $\pm 5\%$ maximum. It appears that these test sections can be machined to $\pm 5\%$ on the wall thickness with approximately $\pm 2-1/2\%$ on concentricity.

2.2.2. Annular Test Sections

Preliminary design work for the annular test sections has been carried on in conjunction with the other design work so that loop modifications could accommodate both test sections as required. The dimensions established for the annular test sections are shown in Table 2.

Table 1. OD (in.) of Tubular Test Sections^(a)

Distance from inlet end of heated length, in.	Test section no.			
	1	2	3	4
0	0.6070	0.7750	0.7965	0.7965
2	.6070	.7171	.6804	.7965
4	.6070	.6688	.6197	.7965
6	.6070	.6316	.5884	.7938
8	.6070	.6080	.5671	.7858
10	.6070	.5922	.5534	.7832
12	.6070	.5773	.5447	.7832
14	.6070	.5668	.5392	.7712
16	.6070	.5593	.5355	.7600
18	.6070	.5557	.5351	.7496
20	.6070	.5467	.5355	.7395
22	.6070	.5425	.5384	.7219
24	.6070	.5395	.5411	.7143
26	.6070	.5370	.5470	.6926
28	.6070	.5340	.5534	.6804
30	.6070	.5324	.5626	.6587
32	.6070	.5307	.5771	.6454
34	.6070	.5307	.5929	.6299
36	.6070	.5300	.6107	.6107
38	.6070	.5307	.6299	.5929
40	.6070	.5307	.6454	.5771
42	.6070	.5324	.6587	.5626
44	.6070	.5340	.6804	.5534
46	.6070	.5370	.6926	.5470
48	.6070	.5395	.7143	.5411
50	.6070	.5425	.7219	.5384
52	.6070	.5467	.7396	.5355
54	.6070	.5557	.7496	.5351
56	.6070	.5593	.7600	.5355
58	.6070	.5668	.7712	.5392
60	.6070	.5773	.7832	.5447
62	.6070	.5922	.7832	.5534
64	.6070	.6080	.7858	.5671
66	.6070	.6316	.7938	.5884
68	.6070	.6688	.7965	.6197
70	.6070	.7171	.7965	.6804
72	0.6070	0.7750	0.7965	0.7965

^(a)ID = 0.446 in.

Table 2. Dimensions (in.) of Annular Test Sections

Distance from inlet end of heated length	Inner tube ^(a)		Outer tube ^(b)		Outer tube ^(c)	
	OD	ID	OD	ID	OD	ID
0	0.607	0.446	1.233	1.053	1.799	1.053
2	.607	.446	1.233	1.053	1.640	1.053
4	.607	.446	1.233	1.053	1.535	1.053
6	.607	.446	1.233	1.053	1.453	1.053
8	.607	.446	1.233	1.053	1.402	1.053
10	.607	.446	1.233	1.053	1.367	1.053
12	.607	.446	1.233	1.053	1.336	1.053
14	.607	.446	1.233	1.053	1.313	1.053
16	.607	.446	1.233	1.053	1.296	1.053
18	.607	.446	1.233	1.053	1.282	1.053
20	.607	.446	1.233	1.053	1.269	1.053
22	.607	.446	1.233	1.053	1.260	1.053
24	.607	.446	1.233	1.053	1.254	1.053
26	.607	.446	1.233	1.053	1.248	1.053
28	.607	.446	1.233	1.053	1.242	1.053
30	.607	.446	1.233	1.053	1.238	1.053
32	.607	.446	1.233	1.053	1.235	1.053
34	.607	.446	1.233	1.053	1.235	1.053
36	.607	.446	1.233	1.053	1.233	1.053
38	.607	.446	1.233	1.053	1.235	1.053
40	.607	.446	1.233	1.053	1.235	1.053
42	.607	.446	1.233	1.053	1.238	1.053
44	.607	.446	1.233	1.053	1.242	1.053
46	.607	.446	1.233	1.053	1.248	1.053
48	.607	.446	1.233	1.053	1.254	1.053
50	.607	.446	1.233	1.053	1.260	1.053
52	.607	.446	1.233	1.053	1.269	1.053
54	.607	.446	1.233	1.053	1.282	1.053
56	.607	.446	1.233	1.053	1.296	1.053
58	.607	.446	1.233	1.053	1.313	1.053
60	.607	.446	1.233	1.053	1.336	1.053
62	.607	.446	1.233	1.053	1.367	1.053
64	.607	.446	1.233	1.053	1.402	1.053
66	.607	.446	1.233	1.053	1.453	1.053
68	.607	.446	1.233	1.053	1.535	1.053
70	.607	.446	1.233	1.053	1.640	1.053
72	0.607	0.446	1.233	1.053	1.799	1.053

(a) Test Sections No. 5, 6, 7, 8, and 9.

(b) Test Sections No. 5, 6, and 7.

(c) Test Sections No. 8 and 9.

Figure 1. Schematic of Test Section in Loop

Figure 2. Photograph of Test Section No. 1

3. FACILITY CHECKOUT

Plans are being formulated to check out the new equipment being installed and the existing equipment operating under new conditions. The objective of this work is to make every reasonable effort for the equipment to meet our expectations and accomplish the test objectives.

4. PROGRAM SCHEDULE

The program schedule is very questionable at this time and cannot be stabilized until the power supply is corrected and operating satisfactorily. It is anticipated that the facility checkout can be completed, test work can be started, and some test data can be obtained during the next quarter. The schedule in Figure 3 indicates the work to be done during the next two quarters.

Figure 3. Schedule of Non-Uniform Heat Program

DISTRIBUTION

1. United States Atomic Energy Commission (27)
Contracts Division
New York Operations Office
376 Hudson Street
New York 14, New York
Attn: Technical Information Group

2. United States Atomic Energy Commission
New York Patents Office
Upton, Long Island, New York
Attn: Mr. Harmon S. Potter

3. United States Contractors (18)

Allis-Chalmers Mfg. Co.
Atomic Energy Division
Milwaukee 1, Wisconsin
Attn: K. F. Neusen

Argonne National Laboratory
Reactor Engineering Division
9700 South Cass Avenue
Argonne, Illinois
Attn: Dr. Paul Lottes

Argonne National Laboratory
Reactor Engineering Division
9700 South Cass Avenue
Argonne, Illinois
Attn: Dr. M. Petrick

Dartmouth College
Thayer School of Engineering
Hanover, New Hampshire
Attn: Dr. Graham B. Wallis

Dynatech Corporation
17 Tudor Street
Cambridge 39, Massachusetts
Attn: R. L. Mela

General Electric Company
Atomic Power Equipment Dept.
2151 South First Street
San Jose 12, California
Attn: Dr. S. Levy

General Electric Company
Atomic Power Equipment Dept.
2151 South First Street
San Jose 12, California
Attn: Dr. Frank Tippets

General Electric Company
Advanced Technology Laboratory
Schenectady, New York
Attn: Dr. Novak Zuber

General Electric Company
Hanford Atomic Products Operation
Richland, Washington
Attn: J. Batch

Geoscience Ltd.
8686 Dunaway Drive
La Jolla, California
Attn: Dr. H. F. Poppendiek

Massachusetts Institute of Tech.
Dept. of Mechanical Engineering
Cambridge 39, Massachusetts
Attn: Dr. W. M. Rohsenow

Massachusetts Institute of Tech.
Dept. of Mechanical Engineering
Cambridge 39, Massachusetts
Attn: Dr. P. Griffith

3. United States Contractors (Cont'd)

North Carolina State College
Dept. of Chemical Engineering
Raleigh, North Carolina
Attn: Dr. J. K. Ferrell

Oak Ridge National Laboratory
P. O. Box Y
Oak Ridge, Tennessee
Attn: Dr. H. W. Hoffman

National Aeronautics & Space
Administration (2)
Lewis Research Center
21000 Brookpark Road
Cleveland 35, Ohio
Attn: S. Weiss (SEPO)

United States Atomic Energy
Commission (2)
Division of Reactor Development
Washington 25, D. C.
Attn: R. M. Scroggins

4. European Contractors (15)

Centre d'Etudes Nucleaires
Chemin des Martyrs
Grenoble (Isere)
France
Attn: M. Mondin

CISE
Casella Postale 3986
Milano (Segrate)
Italy
Attn: Prof. M. Silvestri

MAN
Abhofach
Nurnberg 2
Germany
Attn: Dr. Mayinger

SNECMA
Division Atomique
22 quai Gallieni
Suresnes (Seine)
France
Attn: M. Foure

Technische Hogeschool
P. O. Box 313
Eindhoven
Netherlands
Attn: Prof. Bogaardt

Compagnie Francaise
Thomson-Houston
1 rue des Mathurins
Bagneux (Seine)
France
Attn: M. Lefranc

A.E.G.
AEG Hochhaus
6 Frankfurt (Main) S 10
Germany
Attn: M. Schuller

Alsthom
38 avenue Kleber
Paris 16e
France
Attn: M. P. Domenjoud

Centre d'Etudes Nucleaires
de Saclay
B.P. n° 2
Gif sur Yvette (Seine & Oise)
France
Attn: M. J. Horowitz

FIAT
Sezione Energia Nucleare
Via Settembrini 235
Torino
Italy
Attn: M. G. Cesoni

Reactor Centrum Nederland
112 Scheveningseweg
's Gravenhage
Netherlands
Attn: M. Pelser

CNEN
15 via Belisario
Roma
Italy
Attn: Prof. F. Ippolito

4. European Contractors (Cont'd)

EURATOM (2)
Direction Generale R & E
51 rue Belliard
Bruxelles
Belgium
Attn: Dr. P. Kruys

EURATOM
Casella Postale n° 1
Ispra (Varese)
Italy
Attn: M. R. Morin