1312

AI-AEC-12791 (VOL. III)

MASTER

1000 MWe

L M F B R

Liquid Metal Fast Breeder Reactor

FOLLOW-ON STUDY

ATOMICS INTERNATIONAL
TASK II REPORT

**Conceptual Systems Design
Descriptions
Volume III**

Prepared for ARGONNE NATIONAL LABORATORY

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

United States Atomic Energy Commission Division of Technical Information

DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency Thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

DISCLAIMER

Portions of this document may be illegible in electronic image products. Images are produced from the best available original document.

LEGAL NOTICE

This report was prepared as an account of Government sponsored work. Neither the United States, nor the Commission, nor any person acting on behalf of the Commission:

A. Makes any warranty or representation, expressed or implied, with respect to the accuracy, completeness, or usefulness of the information contained in this report, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately owned rights; or

B. Assumes any liabilities with respect to the use of, or for damages resulting from the use of any information, apparatus, method, or process disclosed in this report.

As used in the above, "person acting on behalf of the Commission" includes any employee or contractor of the Commission, or employee of such contractor, to the extent that such employee or contractor of the Commission, or employee of such contractor prepares, disseminates, or provides access to, any information pursuant to his employment or contract with the Commission, or his employment with such contractor.

This report has been reproduced directly from the best available copy.

Printed in USA. Price \$3.00. Available from the Clearinghouse for Federal Scientific and Technical Information, National Bureau of Standards, U. S. Department of Commerce, Springfield, Virginia 22151.

1000-Mwe LIQUID METAL FAST BREEDER REACTOR
FOLLOW-ON STUDY
CONCEPTUAL SYSTEM DESIGN DESCRIPTIONS
VOLUME III

LEGAL NOTICE

This report was prepared as an account of Government sponsored work. Neither the United States, nor the Commission, nor any person acting on behalf of the Commission:

A. Makes any warranty or representation, expressed or implied, with respect to the accuracy, completeness, or usefulness of the information contained in this report, or that the use of any information, apparatus, method, or process disclosed in this report may not infringe privately owned rights; or

B. Assumes any liabilities with respect to the use of, or for damages resulting from the use of any information, apparatus, method, or process disclosed in this report.

As used in the above, "person acting on behalf of the Commission" includes any employee or contractor of the Commission, or employee of such contractor, to the extent that such employee or contractor or the Commission, or employee of such contractor prepares, disseminates, or provides access to, any information pursuant to his employment or contract with the Commission, or his employment with such contractor.

ATOMICS INTERNATIONAL

A DIVISION OF NORTH AMERICAN ROCKWELL CORPORATION

CONTRACT: ANL 31-109-38-1996

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

CONTENTS

Tab

Auxiliary Systems Segment Conceptual System Design Description — 1000-Mwe LMFBR Follow-On Study	096-60-000
Reactor and Intermediate Coolant Supply and Treatment Conceptual System Design Description — 1000-Mwe LMFBR Follow-On Study	096-61-000
Startup, Shutdown, and Decay Heat Removal System Conceptual System Design Description — 1000-Mwe LMFBR Follow-On Study	096-64-100
Reactor Support Segment Conceptual System Design Description — 1000-Mwe LMFBR Follow-On Study	096-80-000
Subassembly Handling Conceptual System Design Description — 1000-Mwe LMFBR Follow-On Study	096-81-000
Land, Structures, and Conventional Systems Segment Conceptual System Design Description — 1000-Mwe LMFBR Follow-On Study	096-90-000

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	5
1.1 Functions/Functional Requirements	5
1.2 Summary Description	6
1.3 Requirements	7
1.3.1 Performance	7
1.3.2 Environmental	7
1.3.3 Operational	7
1.3.4 Safety	7
1.3.5 Design	8
2.0 DETAILED DESCRIPTION	11
2.1 Reactor and Intermediate Coolant Supply and Treatment System	11
2.1.1 Sodium Service System	11
2.1.2 Helium Supply System	11
2.1.3 Nitrogen Supply System	11
2.1.4 Helium Cover Gas Purification System	12
2.1.5 Miscellaneous Systems Features	12
2.2 Feedwater Supply and Treatment System	12
2.2.1 Raw Water Supply and Treatment System	12
2.2.2 Makeup Water Supply System	13
2.2.3 Steam Generator Feedwater Purification System	13
2.2.4 Feedwater Heater System	13
2.2.5 Feedwater Pumps and Drives	14
2.3 Radioactive Waste Treatment and Disposal System	14
2.3.1 Aqueous Waste System	14
2.3.2 Gaseous Waste System	14

TABLE OF CONTENTS (cont'd)

	<u>Page</u>
2.4 Auxiliary Cooling and Heating Systems	15
2.4.1 Startup and Shutdown Cooling System	15
2.4.2 Decay Heat Removal System	16
2.4.3 Kerosene Cooling System	17
2.4.4 Cooling Water System	17
2.4.5 NaK Cooling System	17
2.4.6 Auxiliary Steam System	18
2.4.7 Preheat System	18
2.4.8 Reactor Cavity Liner Cooling System	18
2.5 Steam Generator Rupture Relief System	19
3.0 PRINCIPLES OF OPERATION	20
3.1 Reactor and Intermediate Coolant	20
3.1.1 Sodium Service System	20
3.1.2 Helium Supply System	21
3.1.3 Nitrogen Supply System	21
3.1.4 Helium Cover Gas Purification System	21
3.2 Feedwater Supply and Treatment Systems	21
3.3 R/A Waste Treatment and Disposal Systems	21
3.3.1 Aqueous Waste System	22
3.3.2 Gaseous Waste System	22
3.4 Auxiliary Cooling and Heating Systems	22
3.4.1 Startup and Shutdown Cooling System	22
3.4.2 Decay Heat Removal System	23
3.4.3 Kerosene Cooling System	23
3.4.4 Water Cooling System	23
3.4.5 NaK Cooling System	23

TABLE OF CONTENTS (cont'd)

	<u>Page</u>
3.4.6 Auxiliary Steam System	24
3.4.7 Electric Preheat System	25
3.4.8 Post Incident Cooling System	25
3.5 Steam Generator Rupture Relief System	26
4.0 SAFETY PRECAUTIONS	27
5.0 MAINTENANCE	27
6.0 APPENDICES	29

AUXILIARY SYSTEMS SEGMENT CONCEPTUAL SYSTEM DESIGN DESCRIPTION

1.0 INTRODUCTION

The auxiliary systems are comprised of a number of service systems which perform necessary support and service functions in the plant. The following systems are included:

- a. Reactor and intermediate coolant supply and treatment.
- b. Feedwater supply and treatment.
- c. Radioactive waste treatment and disposal.
- d. Auxiliary cooling and heating systems.
- e. System vent and discharge handling.

1.1 Functions/Functional Requirements

The primary functions of the auxiliary systems are as follows:

- 1.1.1 Provide for the receipt, transfer, and storage of sodium in either tank car or drum lots.
- 1.1.2 Provide for the cleanup and chemical quality surveillance of the sodium coolant that is either circulating in the heat transfer systems or stored in the drain tanks.
- 1.1.3 Provide a sodium inventory available to the heat transfer systems for level control, makeup, or other purposes necessary for proper plant operation.
- 1.1.4 Provide inert gases for the various plant and process requirements such as heat transfer systems cover gas and equipment vault inert gas atmosphere.
- 1.1.5 Provide for the treatment of reactor system cover gas for radioactivity and sodium vapor removal.
- 1.1.6 Provide boiler feedwater of the required volume and quality to satisfy plant requirements.
- 1.1.7 Provide for the collection and safe disposal of radioactive gases and liquids.

1.1.8 Provide for the preheating of the various plant systems as appropriate.

1.1.9 Provide for dissipation of decay heat from the reactor for normal and emergency modes of plant operation.

1.1.10 Provide miscellaneous cooling systems, such as kerosene and water coolant systems for equipment cooling and servicing H&V systems.

1.1.11 Provide for the safe venting of reaction products resulting from a steam/water leak in the steam generator.

1.2 Summary Description

The auxiliary systems functions are satisfied by the following systems:

a. The reactor and intermediate coolant supply and treatment system consisting of:

The Sodium Service System

The Helium Supply System

The Nitrogen Supply System

The Helium Cover Gas Purification System

b. The feedwater supply and treatment system consisting of:

The Raw Water Supply and Treatment System

The Makeup Water Supply System

The Steam Generator Feedwater Purification System

The Feedwater Pump and Heater System

c. The radioactive waste treatment and disposal system consisting of:

The Aqueous Waste System

The Gaseous Waste System

The Solid Waste Disposal System

d. The auxiliary cooling and heating systems consisting of:

The Startup and Shutdown Cooling System

The Decay Heat Removal System

The Kerosene Cooling System

The Water Cooling System

The NaK Cooling System

The Auxiliary Steam System

The Electric Preheat System

The Post Incident Cooling System

e. The steam generator rupture relief system

1.3 Requirements

1.3.1 Performance

1.3.1.1 The auxiliary systems shall provide the support required to permit operation of the plant for the generation of the net full rated power of 1000 Mwe.

1.3.1.2 The auxiliary systems shall provide the support required for the safe and economical operation of the plant.

1.3.1.3 The auxiliary systems shall provide for the orderly and efficient startup and shutdown of the plant.

1.3.2 Environmental

The various systems comprising the auxiliary systems will be subject to a wide range of environmental conditions depending upon their location in the plant and their function. In general, the environmental conditions prevailing in the plant are expected to be as specified in SDD-096-90-000 section 1.3.2.

1.3.3 Operational

Operational requirements will vary, depending upon the system function and location. Manual, remote manual, and automatic control may be used as is appropriate with the requirements of the particular system and its relation to plant operation.

1.3.4 Safety

1.3.4.1 The systems shall be designed to include the necessary features to provide safe performance during all normal and emergency operating conditions.

1.3.5 Design

1.3.5.1 All vessels shall be designed in accordance with the ASME Boiler and Pressure Vessel Code, Section III. Vessels which are directly connected to the reactor during reactor operation above criticality shall be designed per Class A standards. Other vessels may be designed to Class C standards.

1.3.5.2 Piping shall be designed in accordance with the USA Standard Code for Pressure Piping, USAS B31.1, Section 1, Power Piping, except for kerosene systems, which shall be designed to B31.3, Petroleum Refinery Piping.

1.3.5.3 Heat exchangers shall be designed in accordance with TEMA Standards when within the scope thereof.

1.3.5.4 All piping, vessels, or equipment, including isolation valves, which are directly connected to the reactor during operation above criticality shall be designed to sustain transients predicted for the DBA without failure.

1.3.5.5 Equipment to be installed in primary sodium equipment vaults shall be suitable for operation in a bone dry nitrogen atmosphere at 150°F. Equipment to be installed outside (including helium and nitrogen supply facilities, and equipment connected to the steam generators) shall be suitable for use between 0°F and 100°F; for rain, snow, and 100% relative humidity up to 85°F wet bulb.

1.3.5.6 Transitions between sodium containing systems and gas systems shall be made with suitably designed freeze traps or vapor traps as applicable.

1.3.5.7 Design of vent systems shall prevent entry of moisture or water into sodium containing systems and vice-versa.

1.3.5.8 Equipment in inaccessible vaults shall be provided with remote means of operation. Critical equipment, failure of which would cause plant shutdown, shall have 100% installed spares.

1.3.5.9 The sodium in the heat transfer loops shall be continuously purified and monitored for purity.

1.3.5.10 The means to maintain a constant sodium level in the reactor vessel for all modes of operation shall be provided.

1.3.5.11 A system that will remove entrained and dissolved gas to at least the 800F saturation temperature shall be provided.

1.3.5.12 A system shall be provided to permit purging of and maintenance of, an inert gas atmosphere in the heat transfer loops.

1.3.5.13 Provisions shall be made for maintaining reactor cover gas activity below the level at which design leak rates will not result in activity levels above MPC in the plant.

1.3.5.14 Provide for the maintenance of a nitrogen atmosphere in the vaults containing sodium within the reactor building.

1.3.5.15 Provide a system to pump, treat, and store adequate quantities of water suitable as feedwater for the steam generator.

1.3.5.16 Provide a system for heating feedwater from the condenser not well temperature to the required boiler feedwater temperature utilizing turbine extraction steam as appropriate and delivering this water into the steam generator at required pressures.

1.3.5.17 Provide a supply of emergency feedwater to the steam generators in sufficient quantity to remove core decay heat until the decay heat level is equal to ambient losses from the reactor system piping and equipment. This emergency condition shall assume loss of normal power and main boiler feed pumps.

- 1.3.5.18 A system shall be provided to monitor potentially radioactive gases and dispose of them either by direct dispersal to the atmosphere through a stack, or to provide controlled release through compression and storage, such as to comply with 10 CFR, Part 20, Standards for Protection Against Radiation, filed September 6, 1960.
- 1.3.5.19 Vent systems shall be segregated to prevent water or moisture from entering vessels that contain sodium or vice-versa.
- 1.3.5.20 Vent streams containing hydrogen shall be segregated from vent streams containing oxygen in order to prevent hydrogen explosions.
- 1.3.5.21 Low activity level gases shall be isolated from potentially high level activity gases to facilitate release.
- 1.3.5.22 Provide a system to collect, store, and prepare for disposal of radioactive liquid waste generated in the operation of the plant in accordance with legal requirements.
- 1.3.5.23 Provide for the preheating of all sodium containing piping and equipment to a minimum of 350F prior to fill, and maintain this temperature irrespective of the operational status of the plant.
- 1.3.5.24 Provide a system to preheat the steam and power generation portion of the plant to the desired preheat temperatures. Included are the feedwater train, steam generation equipment, turbine, condenser, steam piping, and attendant equipment.
- 1.3.5.25 Provide a startup and steam dump system that will allow placing the steam generator and turbine into operation from a normal startup or a hot startup and protect the steam generator and turbine from thermal shocks and excess pressures.
- 1.3.5.26 Provide for the dissipation of reactor decay heat from the main heat transfer circuits without damage to equipment under all postulated emergency conditions, including at least the following:
- Loss of power
 - Loss of turbine
 - Loss of main boiler feed pumps
 - Loss of main sodium pumps
 - Loss of one main heat transfer circuit

1.3.5.27 Provide for cooling of the reactor core, or the residual fuel mass, after a postulated catastrophic failure such that fuel or excessive radioactivity will not be released from the secondary containment barriers in the plant.

1.3.5.28 Provide for the cooling of the various equipment in the plant where required.

2.0 DETAILED DESCRIPTION

2.1 Reactor and Intermediate Coolant Supply and Treatment System

This system consists of the following:

2.1.1 Sodium Service System (Dwg. NO9612011)

The sodium service system consists of piping, tanks, purification equipment, pumps, valves, and controls to receive and store sodium, fill and drain the various sodium filled loops, purify the sodium relative to deleterious contaminants, monitor chemical contamination, maintain proper level in the heat transfer loops, and provide for emergency refill in event of leakage.

2.1.2 Helium Supply System (Dwg. NO9612014)

The helium supply system consists of a source of helium (bottles or trailers), pressure control valving, and a piping distribution system to the various using units. The helium system maintains an inert cover gas over sodium to exclude deleterious contaminants, and serves as an inert gas to purge sodium filled equipment prior to fill. It acts as a carrier gas for purification and analysis equipment. It is used for sodium transfer by gas pressurizing. The helium cover gas provides the operating pressure maintained in the reactor coolant system.

2.1.3 Nitrogen Supply System (Dwg. NO9612014)

The nitrogen supply system consists of a source of nitrogen (LN_2 storage tank and vaporizer), a piping distribution system, and control valving. This supply of nitrogen is a general utility in the plant. It provides an inert gas blanket in primary sodium containing equipment cells as a fire retardant, and it acts as a heat transfer medium for cooling inert gas filled cells. The nitrogen supply system maintains

pressure control and assists in leakage control in radioactive material containment cells. It provides emergency backup to the instrument air system, and it supplies motive power to controls and tools in inert gas filled cells. Nitrogen serves as a diluent and carrier gas for sodium cleaning operations, and it is used to provide an inert cover gas in steam systems during standby periods.

2.1.4 Helium Cover Gas Purification System (No Dwg.)

The helium cover gas purification system consists of compressors, vapor traps, filters, adsorption beds, hold up tanks, and control devices, with the necessary piping and valves to remove a side stream of cover gas from the reactor, purify it with respect to deleterious chemical and radioactive species, and return it to the reactor. This system permits reactor operation with realistic top shield leak rates and controls radioactivity in occupied areas within acceptable limits. The system provides more economical use of helium, and minimizes storage requirements for radioactive gas decay.

2.1.5 Miscellaneous Systems Features

Miscellaneous interface requirements are satisfied by components in these systems. Vapor traps and freeze traps are provided in the various sodium containing systems to accommodate the interface between sodium containing systems and gas containing systems. Sampling equipment is provided in the various sodium, water, and gas containing systems to permit sampling or monitoring condition of the working fluids.

2.2 Feedwater Supply and Treatment System (Dwg. N09612016)

The system consists of the following:

2.2.1 Raw Water Supply and Treatment System

The raw water supply and treatment system consists of auxiliary pumps, storage vessels, and pre-treatment facilities such as screens, filters, sedimentation and precipitation equipment, and chemical feeders necessary to assure an adequate supply of a suitable feed water to the plant demineralizer system. The system pumps and screens raw water, stores a reasonable working level for emergency use (such as during power outage),

and pre-treats the water. Treatment may include sedimentation, settling, filtration, and pH adjustment. Partially treated water for auxiliary services is supplied as required. Examples are bearing cooling, fire protection, general yard usage, and similar functions.

2.2.2 Make-up Water Supply System

The makeup water supply system consists of pumps, deionizer units, deaerator units, regeneration and chemical addition equipment to service the units, filters, and storage vessels as necessary to convert the treated raw water into a water of quality satisfactory for boiler water make-up.

2.2.3 Steam Generator Feedwater Purification System

The steam generator feedwater purification system re-purifies condensate between the hot well and the feedwater heater train to remove corrosion products and contaminants that have been introduced in the steam and condenser sections. This system consists of a bank of mixed bed deionizers capable of polishing the full reactor feedwater flow. Regeneration equipment, filters, and standby units are included as required. The system is designed to reduce mineral content of the feedwater to an absolute minimum (~ 50 PPB). Volatile corrosion inhibitors are added as required. A means of sampling, analyzing, and monitoring the boiler feedwater is provided.

2.2.4 Feedwater Heater System

The feedwater heater system consists of a series of feedwater heaters designed to heat the feedwater from hotwell temperature to a suitable temperature for injection into the steam generators. There are 3 stages of low pressure feedwater heaters with 2 heaters per stage. There are 2 parallel deaerating feedwater heaters, and there are 3 stages of high pressure feedwater heaters with 2 heaters per stage. Appropriate piping, valves, and instrumentation are provided for proper functioning of the system.

2.2.5 Feedwater Pumps and Drives

Feedwater pumps and drives provide the motive power for forcing feedwater out of the condenser (at very low absolute pressures) into the boiler at steaming conditions. This system consists of four motor driven hotwell pumps (one being a spare) for pumping the water out of the hotwell through the low temperature and deaerating heaters, and two boiler feed pumps.

2.3 Radioactive Waste Treatment and Disposal System

The radioactive waste treatment and disposal system consist of three subsystems for handling aqueous, gaseous, and solid wastes contaminated with radioactive species.

2.3.1 Aqueous Waste System (Dwg. NO9612019)

The aqueous waste system consists of a collection piping network; a storage facility, pumps, sampling lines, and disposal piping and facilities. This system collects, segregates, and stores aqueous liquid waste in a manner that prevents contamination of sodium equipment with moisture and vice-versa, and segregates low-level activity from high to minimize cost of disposal. It holds up low-level, short-lived activity permitting decay so that the waste can be dispersed on site. It also holds and collects more highly contaminated waste for off-site shipment in tank cars. The system provides the necessary monitoring, transfer, loading, packaging, and shipment capability so that all aqueous waste may ultimately be dispersed or shipped off-site within existing safety requirements.

2.3.2 Gaseous Waste System (Dwg. NO9612015)

The gaseous waste system consists of a piping collection system; a series of storage tanks, compressors, filters, condensers, control devices, sampling equipment, and blowers for pressure control, collection, segregation, storage, decay, and regulated release of all gaseous waste generated in the plant. The system provides a sink at regulated back-pressures for collection of radioactive gaseous waste from all potential

sources within the building. It monitors these wastes and permits direct release (if activity level is low), or collects, stores, samples and allows decay of the waste if activity is high. It segregates wastes according to chemical nature, such that no hazard will arise due to potential chemical reaction. Waste gases are compressed for storage, thus minimizing cost of storage capacity. All potentially active gaseous waste are filtered through high efficiency filters prior to direct release to the atmosphere, thus minimizing release of active particulate material to the atmosphere. Active gaseous wastes are released in carefully measured and recorded quantities as required by existing regulations. Immediate stopping of release is provided in event of malfunction. Excess potentially radioactive liquid is condensed from the gaseous waste, thus minimizing the quantity of liquid borne activity released locally.

2.4 Auxiliary Cooling and Heating Systems (Dwg. N09612013)

The auxiliary cooling and heat systems are composed of several systems that perform a multitude of miscellaneous heating and cooling functions in the reactor complex. Brief descriptions of these systems follow:

2.4.1 Startup and Shutdown Cooling System (Dwg. N09612018)

The startup and shutdown cooling system consists of the main sodium heat transfer system in conjunction with the steam generator startup system. The steam generator startup system consists of an auxiliary flash tank, a turbine bypass, power relief valves, the high pressure feedwater heater, and a network of bypasses, drains, valves, controls and piping to permit heatup of the plant through sodium fill, rise to temperature, and rolling the turbine. The system accomplishes a number of interrelated functions as follows:

Beginning from a cold start, steam is admitted from the auxiliary boiler to preheat the flash tank, the steam generators, and high pressure feedwater heater in turn.

Condensing steam and/or heated feedwater provides clean-up of the water side of the steam generator, superheaters, reheaters, and feedwater drain, together with the attendant piping.

After sodium fill, steam and heated feedwater serve to maintain the systems at preheat temperature ($\sim 350^{\circ}\text{F}$) until nuclear heat becomes available, after which the heating load shifts to the main sodium heat transfer systems.

Steam is dumped through the turbine bypass to the main condensers during rise of system temperatures to satisfactory operating levels. It is estimated this requirement extends to about 15 percent of rated power, at which level the turbine may be rolled and loading started.

In event of sudden transients in the system (turbine trip, loss of load, reactor scram, and others), the turbine bypass is available to dump surplus steam (generated by decay heat in the core) to the main condenser.

As a backup to the turbine bypass, spring-loaded relief valves and power-relief valves are included in the system to dump steam to the atmosphere should the turbine bypass and condenser fail to dissipate heat for any reason.

2.4.2 Decay Heat Removal System (No Dwg.)

For emergency core cooling, the main sodium heat transfer systems are designed to remove decay heat from the core by the following means:

- Normal operation of the systems

- Operation of portion of the system on alternate or reserve power

- Natural convection sodium circulation

In any case, the ultimate heat rejection is the steam dump system described above.

2.4.3 Kerosene Cooling System (Dwg. NO9612013)

The kerosene cooling system provides an auxiliary cooling system for various applications in the reactor building. Kerosene was selected as an operating fluid in preference to water (or other aqueous media) primarily as a safety feature to minimize the quantity of water in the building and, in turn, the possibility of a sodium-water reaction.

The system consists of kerosene chillers, kerosene circulating pumps, a piping distribution system, and flow control devices on the various using units. The system is subdivided into a high temperature and a low temperature system. The high temperature system removes process heat from equipment that can be carried at elevated temperatures (120°F to 150°F and above). The low temperature system is refrigerated to cool working areas. The kerosene system's main function is to provide coolant to the equipment spaces for cooling within the Reactor Bldg. The system also provides cooling to other miscellaneous items such as the primary sodium pump variable speed coupling.

2.4.4 Cooling Water System (No Dwg.)

This system consists of the circulating water intake structure at the river and condenser circulating pumps and a closed loop water cooling system. Dual pumps and heat exchangers are provided to assure continuous availability of the loops. The closed loop water system takes its cooling water makeup from the demineralized water system.

The cooling water system supplies cooling to the kerosene cooling system, the H&V systems, the various compressors, and other equipment where cooling is required.

2.4.5 NaK Cooling System (No Dwg.)

The NaK cooling system provides cooling for the spent fuel storage pit. This system consists of cooling coils in the fuel storage pit, a circulating NaK system, a NaK pump, a NaK-to-kerosene heat exchanger, and the necessary piping and controls to cool the fuel storage pit.

2.4.6 Auxiliary Steam System (No Dwg.)

The auxiliary steam system was discussed generally under the startup and shutdown cooling system above. This system provides heat for a number of miscellaneous functions when nuclear heat is not available. The system consists of two half-capacity conventional boilers. The system supplies heat in the form of steam for the following purposes:

Building heating while the reactor is out of service

Preheat steam for preheating the steam generators

Process steam for miscellaneous services (such as cleaning)
while the reactor is off the line

Emergency steam for operating auxiliary turbines (such as
the emergency feed pump)

Process steam to miscellaneous areas to prevent freezing
of equipment

2.4.7 Preheat System (No Dwg.)

The preheat system employs electrical resistance heaters, for all sodium containing piping and equipment, except for the steam generator, which will be preheated by steam, and tank car sodium melting, which will use hot oil. Electrical tubular heaters are banded to the piping and equipment, wrapped with a reflector, and covered with thermal insulation. The system is provided with controls to avoid excessive hot spots and give a uniform 350F preheat temperature.

2.4.8 Reactor Cavity Liner Cooling System (DWg. N09612010)

In case of complete and catastrophic loss of cooling of the reactor core for any combination of events, the fuel mass will continue to generate afterglow heat. If this heat is not removed, theoretically the fuel mass could melt through a large amount of any material beneath it. The post incident cooling system provides sufficient cooling capability to cool the bottom portions of the reactor cavity, and thus prevent melting through of the cavity liner. By preventing loss of the cavity liner integrity, the fuel mass can be contained.

The post incident cooling system consists of cooling coils in the bottom and lower sides of the reactor cavity; a closed circuit pressurized water cooling system; circulating pumps; heat exchangers; and a supply of condenser cooling water for dissipation of this heat to the river. Normally, the kerosene cooled heat exchangers are used to remove heat during normal operation.

The system accomplishes the following functions:

- Removes sensible and gamma heat from the lower regions of the cavity during normal operation.

- Removes decay heat from fuel masses that may collect on the cavity bottom during an incident, thereby preventing meltdown of the cavity liner.

2.5 Steam Generator Rupture Relief System (No Dwg.)

In event of leakage in the steam generator, the leakage will, in all probability, be leakage of steam or water into sodium, due to the differential pressure. This leakage will result in sudden rise of sodium side pressure as a result of the sodium-water reaction, and resulting generation of heat and hydrogen gas. For large leaks, the pressure could approximate steam pressure in a matter of microseconds. Small leaks would probably propagate themselves rapidly. Thus, a means of pressure relief is required to prevent catastrophic failure, or the possibility of damage to primary systems.

The steam generator rupture relief system consists of the following:

- Rupture discs on each steam generator unit, and at other locations to relieve the initial pressure wave; a piping collection system to collect the products of the reaction, and direct them to a collection and disengagement tank; a disengagement tank to separate sodium and gases; a stack to dissipate the gases safely;

- Sodium dump tanks to permit rapid dumping of sodium from the affected loop;

- Cleanup capability to permit cleanup of the residual products and their safe disposal;

An alarm system to detect the failure as early as possible, and to identify the unit in which a failure has occurred, thus facilitating repair.

This system accomplishes the following:

Relieves excessive pressure on the sodium side of the steam generator as a result of a sodium-water reaction, and thus prevent damage to the IHX or primary sodium system;

Conducts and contains the products of the reaction, to permit gas relief without causing secondary damage;

Minimizes atmospheric contamination from sodium, sodium oxide, or sodium hydroxide release;

Release hydrogen gas in a manner that precludes a hydrogen explosion and resultant secondary damage;

Identifies the area of the initial leak to minimize downtime;

Provides facilities for analysis of the residual sodium mass, and for its appraisal, segregation, and disposal in the most expeditious, safe, and rapid means possible.

3.0 PRINCIPLES OF OPERATION

3.1 Reactor and Intermediate Coolant Supply and Treatment System

3.1.1 Sodium Service System

a. Operations shall be by manual means, primary sodium service operations are accomplished remotely.

b. Storage tanks are normally empty. With secondary tanks and some primary tankage on hot standby. Primary tankage is isolated from the reactor during reactor operation.

c. Oxide level is controlled by use of cold traps. Primary sodium and all secondary sodium is cold trapped continuously except for short periods for trap change-out. Normally, pressure for this operation is by main heat transfer system pumps.

d. Normal monitoring of oxide level is by automatic plugging meters. Periodic tab samples or sodium samples are removed on an as-required basis for determination of carbon or analysis for impurities.

e. Carbon content of primary sodium would be controlled by gettering on hot stainless steel foil on an as-required basis. Space for a hot trap in the building is provided.

f. Hydrogen content of sodium is controlled by cold traps.

3.1.2 Helium Supply System

Helium is supplied to all using units automatically on an as-required basis through automatic control valving. Re-supply is by manually changing-out of spent bottles or trailers.

3.1.3 Nitrogen Supply System

Nitrogen is supplied to all using units automatically on an as-required basis through automatic control valving. Re-supply is on a scheduled basis or as required, and is handled by the nitrogen vendor.

3.1.4 Helium Cover Gas Purification System

The helium cover gas purification system is a continuous operating unit in which a side stream of helium is passed through a carbon filled delay bed, which is operated saturated. Passage of Xe is delayed an average of about 35 days, by adsorption during which activity (due primarily to Xe^{133}) is reduced to about 1% of its initial value. This side stream is then returned to the reactor plenum. Two trains are provided, so that one may be maintained while the other is operating. When a unit is taken off the line, it may be purged to a decay tank for decay and subsequent release.

Operation of the unit is automatic, with switch-over to the standby unit being a manual operation.

3.2 Feedwater Supply and Treatment System

See Energy Conversion Segment, CSDD 096-40-000.

3.3 R/A Waste Treatment and Disposal System

3.3.1 Aqueous Waste System

Potentially radioactive liquid waste is drained into holding tanks by gravity under operator control. The waste is then sampled manually. Agitators are provided in the tanks to assure representative samples, depending on activity levels and radioactive species found. The material is pumped to one of the following sinks:

- a. The material is mixed with condenser cooling water effluent for disposal.
- b. The material is pumped into tank trailers per shipment to an R/A waste processing facility.
- c. The material is stored for eventual solidification; packaging in shielded shipping containers; and shipment for burial. Packaging is a semi-remote manual operation.

3.3.2 Gaseous Waste System

The gaseous waste system is, basically, an automatic operation. Potentially radioactive gases are released from the various vessels by automatic control valves under pressure control. Gases from the primary cover gas system are routed directly to hold-up tanks for monitoring, delay, and controlled release. Other gases are normally monitored and released directly to the atmosphere. However, automatic valves divert these gases to hold-up tanks in event of high activity. Release from decay tanks is manual under control of the plant health physicist.

3.4 Auxiliary Cooling and Heating Systems

3.4.1 Startup and Shutdown Cooling System

The startup and shutdown cooling system is not a separate system, but consists of proper use of components of a number of systems to effect startup and shutdown of the plant. These operations are manual operations under direct operator control until the plant reaches an operating level (~25% of full load) at which the plant control system can operate effectively as a fully automatic power plant.

After preheat, power level is increased slowly, and the plant is brought up to about 500-600°F isothermal. Small quantities of steam are dumped to the condenser. Power level is increased manually at a pre-determined rate, and steam temperature is increased slowly, while dumping to the condenser. When steam temperature and flow are satisfactory, the turbine is rolled and steam dumping is stopped. At this point, the automatic control system is placed into operation, and loading of the turbine is started.

For emergency shutdown, the turbine will trip automatically. The reactor will scram; and steam production will be diverted to the condenser. Power relief and spring loaded relief valves will open and relieve to the atmosphere if pressure exceeds set points. After trip, plant will be cooled manually at pre-determined rates by manual or automatic control of feedwater flow; sodium flow; and steam flow to the condenser.

3.4.2 Decay Heat Removal System

The decay heat removal system is not a separate system but consists of components of other systems utilized for removal of decay heat from the reactor.

Heat is removed from the core by the primary sodium systems and, in turn, by the secondary sodium systems. Two different sources of motive power are available to induce flow in these systems as follows:

Normal Power

Natural Convection Sodium Circulation

Flow in these systems is controlled by pump speed and/or control valves to maintain reasonably constant rates of temperature change, and avoid excessive thermal shock. Control may be automatically programmed or, in later stages, manual.

Ultimate heat rejection is to the steam system and finally to the main condenser. An emergency feed pump (or pumps) is provided, driven by both electricity and steam, to assure continuity of service. Reserve feedwater supply is available in the plant in event of outage of makeup equipment. The condenser is backed up by power relief valves, and finally spring loaded relief valves which discharge to the atmosphere.

3.4.3 Kerosene Cooling System

Main kerosene flow is constant. Supply temperature is maintained constant automatically by control of flow of cooling water, or compressor control, or both. Temperature control on each using unit is by bypass control of kerosene flow through the unit. Bypasses are thermostatically controlled from temperature signals in the using unit.

Most units are spared, and are alternated periodically to permit maintenance and equalize wear. The operation of starting up standby units is accomplished manually.

3.4.4 Water Cooling System

Water flow is continuous and reasonably constant. Standby pumps are provided to assure continuity of operation, even in event of equipment failure. Pumps are capable of operation on emergency power.

Temperature control is effected by valve control of flow to the various heat exchangers. Valves are automatically modulated based on temperature signals from the using equipment.

Standby units (pumps, heat exchangers) are placed in service periodically by operator action to release units for maintenance; and to permit equal wear on the various items of equipment.

3.4.5 NaK Cooling System

Heat load on this system is cyclic, being at maximum at the beginning of the storage period, and decaying in an exponential manner as the decay power of the stored fuel elements decreases. It is assumed that flow through the NaK system, and secondary coolant (kerosene) system, will be continuous. Flow in both circuits will be modulated depending on temperature. NaK flow will be automatically controlled by controlling pump operation. Interlocks will be provided to prevent hunting or excessive thermal gradients.

3.4.6 Auxiliary Steam System

The auxiliary steam system consists of two fully automatic boilers designed to produce steam at design temperature and pressure under varying load conditions. Fuel used in the boilers is oil. This boiler setup may be called on to raise steam under emergency conditions in event

of reactor outage and this fuel is readily adaptable to standby service.

Steam generation is fully automatic utilizing a conventional control system. Supply to all using units is controlled by thermostatically controlled valves, or pressure control valves, or both. Setpoints on supply to the steam generator warm-up and preheat system is under operator control.

3.4.7 Electric Preheat System

A fully automatic system will be employed for control of the sodium system heaters.

Scanner-controller units will be employed. Thermocouples will be installed on all tanks, vessels, pumps, valves, and other components, and at frequent intervals on the pipes, with leads extending into a central panel located in the control room and connected to the thermocouple scanners. The controllers have setpoints, continuously variable over the range of the instruments and contain pilot contacts which close when the sensed temperature is below the setpoint and open when the temperature is above the setpoint. By coupling the pilot contacts to the control coils of the mechanically held contactors in the heater circuit leads, the heaters will be turned on or off as necessary, depending upon whether the temperature of the system components under control is below or above the setpoint of the controller, as set by the operator. Mechanically held contactors are necessary to maintain the contact closed or open as required while the scanner controller is on other T/C positions during the scanning cycle.

3.4.8 Reactor Cavity Liner Cooling System

The post incident cooling system is divided into two basic loops, a small loop for removing normal sensible and γ heat gain from the reactor cavity walls; and a large cooling loop for removing afterglow heat after complete failure of the main primary containment. Each loop is subdivided with standby gear to permit maintenance during operation. Coils in the cavity liner are separately valved and spared to permit isolating one or more leaking coils.

In operation, one pump and heat exchanger in the normal heat removal system operate at all times. Units are alternated monthly for even wear.

The large units are normally started up and operated monthly to assure operability in event of emergency. After an incident, pumps start in the large loop automatically to assure cooling for the casualty case. These units operate at constant flow until afterglow heat generation has dropped to a low quantity, at which time, they are taken out of service by operator action.

3.5 Steam Generator Rupture Relief System

Rupture discs are installed and tested for leak tightness prior to system sodium fill. The entire relief collection, separation, and disposal system is then sealed and back-filled with nitrogen prior to introducing water into the steam generators. Thereafter, the system is on standby, and requires only a periodic check to assure purity of the nitrogen blanket.

In event of a rupture of a disc as evidenced by suitable signals, feedwater to the affected unit is stopped, and the water side is dumped by automatic valve action. Isolation valves at the building wall close automatically to isolate the steam generator from the IHX's; and the affected heat transfer loops are shut down automatically, operator action is then required to complete shutdown, draining, and securing the loop.

Rupture discs are inspected about every two years during steam generator outage. A representative sampling of discs is removed and destructively tested to attempt to predict disc life. Discs are changed out on a frequency that gives a high probability of not having disc failure due to normal degenerative effects such as corrosion, creep, or metallurgical changes.

If a sodium-H₂O reaction large enough to burst a rupture disc occurs, the pressure and reaction products are relieved by this system. The reaction products relieve into a blow-down tank. They are vented from the tank through a demister and stack to the atmosphere.

4.0

SAFETY PRECAUTIONS

- a. All primary sodium equipment is installed in nitrogen filled vaults to minimize the possibility of radioactive sodium fires.
- b. Two independent means of cover gas introduction are provided for the reactor to assure pressure control in event of malfunction.
- c. A reserve supply of helium is provided for emergency use in sodium transfer. A reserve supply of nitrogen is provided for fire protection and instrument air backup.
- d. The vault containing the helium purification system is designed to contain all adsorbed gases even in event of leakage and loss of pressure in the adsorption beds.
- e. All critical components have spares to assure operation even in event of equipment failure.
- f. All potentially radioactive gaseous waste is monitored, filtered, and recorded prior to disposal. Liquid waste is analyzed and recorded prior to disposal.
- g. At least two methods of decay heat removal are provided during reactor operation.
- h. Auxiliary cooling systems operate on emergency power if loss of cooling could result in secondary damage.
- i. All hydrogen bearing gases are segregated in inert gas filled systems such that combustible mixtures of hydrogen and oxygen cannot exist in confined spaces.

5.0

MAINTENANCE

- a. All critical equipment which must be spared shall be so installed and isolable that standby equipment may be isolated, approached, and maintained during plant operation.

b. Components containing primary sodium which must be maintained or changed out during plant operation shall be in separately shielded vaults isolatable from operating portions of the primary sodium system by at least two independent means including a frozen plug of sodium.

c. Design and installation of steam generator rupture discs shall be to facilitate removal, replacement, and leak test.

d. Where electrical heaters are installed in absolutely inaccessible vaults, they shall have 100% spares which can be wired into the system in event of failure.

e. Design of primary sodium cold traps and sodium samplers shall be such that these items can be removed and replaced remotely without waiting for sodium 24 decay.

f. All sodium equipment shall be completely drainable to permit maintenance with minimum delay.

6.0 APPENDICES

REVISIONS			
REV	DESCRIPTION	DATE	APPROVED
SDD-096-60-000			
Page 30

LEGEND

GENERAL

- AREA LIMIT
- WATCH LINE
- SPECIFICATION CHANGES
- ITEM SUPPLIED WITH EQUIPMENT

FITTINGS

- REDUCER
- WELDED CAP
- BEADED ON HOSE WELDED CAP

PIPING SPECIALTIES

- WATER TRAP
- PRESS. TELLER
- TELE. TRAP
- WIRE STRAINER
- ROSE CONNECTION
- FLUENT CONNECTION
- STRESS RELIEVING JOINT

CONTROL VALVES

- TEMPERATURE
- FLUX
- LEVEL
- PRESSURE
- RELIEF
- MANUAL
- DIAPHRAGM OPERATED

INSTRUMENTATION

- MODEL
- ORIFICE
- IN THE LINE
- RESTRICTING ORIFICE
- BOARD MOUNTED INSTR.
- LOCAL MOUNTED INSTR.
- LOCAL MOUNTED THERMOCUPLE
- BOARD MOUNTED TRANSMITTER

VALVES

- VALVE NO.
- DATE
- BLADE
- CHECK
- PLUG
- BUTTERFLY
- ANGLE
- THREE-WAY
- BELLOWS SEAL
- Y-POSTER
- NEEDLE VALVE
- NEEDLE VALVE
- LIQUID COOLED PRESS. SEAL
- SAR COOLED PRESS. SEAL
- NON-RETURN
- OFFSET BLOW
- MANUAL HANDLE OPERATED

SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
(Symbol)	WATER TRAP	(Symbol)	RESTRICTING ORIFICE	(Symbol)	BOARD MOUNTED INSTR.
(Symbol)	WELDED CAP	(Symbol)	LOCAL MOUNTED INSTR.	(Symbol)	LOCAL MOUNTED THERMOCUPLE
(Symbol)	BEADED ON HOSE WELDED CAP	(Symbol)	BOARD MOUNTED TRANSMITTER	(Symbol)	

ATOMIC INTERNATIONAL
10000 WILSON BLVD., SUITE 100, WILSON, N.C. 27157
TELEPHONE (704) 363-1111
FAX (704) 363-1112
E-MAIL: SALES@ATOMIC-INTL.COM
WWW.ATOMIC-INTL.COM

LEGEND

GENERAL

AREA LIMIT
WATCH LINE
SPECIFICATION CHANGES
ITEM SUPPLIED WITH EQUIPMENT

FITTINGS

REDUCER
WELDED CAP
SCREENED OR SOCKET WELDED CAP

PIPING SPECIALTIES

VAPOR TRAP
FREEZE TRAP
EXPANSION JOINT
WYE STRAINER
ROSE CONNECTION
FLEXIBLE CONNECTION
STRESS RELIEF JOINT

CONTROL VALVES

TEMPERATURE
PRESSURE
LEVEL
RELIEF
MANUAL
DIAPHRAGM OPERATED
SELF-CONTAINED REGULATING VALVES

INSTRUMENTATION

NOZZLE
ORIFICE
IN THE LINE
RESTRICTING ORIFICE
BOARD MOUNTED INSTR
LOCAL MOUNTED INSTR
THERMAL MOUNTED TRANSDUCER

VALVES

GATE
GLOBE
CHECK
BUTTERFLY
ANGLE
THREE-WAY
BELLWAS SEAL
VALVE NO.

FLOW ELEMENTS (TYPICAL)

LETTER	SYMBOL	DESCRIPTION	LETTER	SYMBOL	DESCRIPTION
A	[Symbol]	ORIFICE	F	[Symbol]	ORIFICE
B	[Symbol]	ORIFICE	G	[Symbol]	ORIFICE
C	[Symbol]	ORIFICE	H	[Symbol]	ORIFICE
D	[Symbol]	ORIFICE	I	[Symbol]	ORIFICE
E	[Symbol]	ORIFICE	J	[Symbol]	ORIFICE
F	[Symbol]	ORIFICE	K	[Symbol]	ORIFICE
G	[Symbol]	ORIFICE	L	[Symbol]	ORIFICE
H	[Symbol]	ORIFICE	M	[Symbol]	ORIFICE
I	[Symbol]	ORIFICE	N	[Symbol]	ORIFICE
J	[Symbol]	ORIFICE	O	[Symbol]	ORIFICE
K	[Symbol]	ORIFICE	P	[Symbol]	ORIFICE
L	[Symbol]	ORIFICE	Q	[Symbol]	ORIFICE
M	[Symbol]	ORIFICE	R	[Symbol]	ORIFICE
N	[Symbol]	ORIFICE	S	[Symbol]	ORIFICE
O	[Symbol]	ORIFICE	T	[Symbol]	ORIFICE
P	[Symbol]	ORIFICE	U	[Symbol]	ORIFICE
Q	[Symbol]	ORIFICE	V	[Symbol]	ORIFICE
R	[Symbol]	ORIFICE	W	[Symbol]	ORIFICE
S	[Symbol]	ORIFICE	X	[Symbol]	ORIFICE
T	[Symbol]	ORIFICE	Y	[Symbol]	ORIFICE
U	[Symbol]	ORIFICE	Z	[Symbol]	ORIFICE

NOTE: WHEN THE FOLLOWING SYMBOLS ARE USED IN A FIRST LETTER FOR PROCESS OR INSTRUMENT, THEY SHALL BE USED IN THE FOLLOWING MANNER: A, B, C, D, E, F, G, H, I, J, K, L, M, N, O, P, Q, R, S, T, U, V, W, X, Y, Z.

ATOMIC INTERNATIONAL
CORPORATION
1000 WILSON AVENUE
CHICAGO, ILL. 60642
TELEPHONE 312-346-1000
FAX 312-346-1001
CABLE ATOMIC
TELETYPE 312-346-1000
RADIO 312-346-1000
TELEVISION 312-346-1000
POSTAL 312-346-1000
AIR MAIL 312-346-1000
SEALED MAIL 312-346-1000
REGISTERED MAIL 312-346-1000
PRIORITY MAIL 312-346-1000
EXPRESS MAIL 312-346-1000
OVERNIGHT MAIL 312-346-1000
SAME DAY MAIL 312-346-1000
NEXT BUSINESS DAY MAIL 312-346-1000
TWO BUSINESS DAY MAIL 312-346-1000
THREE BUSINESS DAY MAIL 312-346-1000
FOUR BUSINESS DAY MAIL 312-346-1000
FIVE BUSINESS DAY MAIL 312-346-1000
SIX BUSINESS DAY MAIL 312-346-1000
SEVEN BUSINESS DAY MAIL 312-346-1000
EIGHT BUSINESS DAY MAIL 312-346-1000
NINE BUSINESS DAY MAIL 312-346-1000
TEN BUSINESS DAY MAIL 312-346-1000
ELEVEN BUSINESS DAY MAIL 312-346-1000
TWELVE BUSINESS DAY MAIL 312-346-1000
THIRTEEN BUSINESS DAY MAIL 312-346-1000
FOURTEEN BUSINESS DAY MAIL 312-346-1000
FIFTEEN BUSINESS DAY MAIL 312-346-1000
SIXTEEN BUSINESS DAY MAIL 312-346-1000
SEVENTEEN BUSINESS DAY MAIL 312-346-1000
EIGHTEEN BUSINESS DAY MAIL 312-346-1000
NINETEEN BUSINESS DAY MAIL 312-346-1000
TWENTY BUSINESS DAY MAIL 312-346-1000
TWENTY-ONE BUSINESS DAY MAIL 312-346-1000
TWENTY-TWO BUSINESS DAY MAIL 312-346-1000
TWENTY-THREE BUSINESS DAY MAIL 312-346-1000
TWENTY-FOUR BUSINESS DAY MAIL 312-346-1000
TWENTY-FIVE BUSINESS DAY MAIL 312-346-1000
TWENTY-SIX BUSINESS DAY MAIL 312-346-1000
TWENTY-SEVEN BUSINESS DAY MAIL 312-346-1000
TWENTY-EIGHT BUSINESS DAY MAIL 312-346-1000
TWENTY-NINE BUSINESS DAY MAIL 312-346-1000
THIRTY BUSINESS DAY MAIL 312-346-1000
THIRTY-ONE BUSINESS DAY MAIL 312-346-1000
THIRTY-TWO BUSINESS DAY MAIL 312-346-1000
THIRTY-THREE BUSINESS DAY MAIL 312-346-1000
THIRTY-FOUR BUSINESS DAY MAIL 312-346-1000
THIRTY-FIVE BUSINESS DAY MAIL 312-346-1000
THIRTY-SIX BUSINESS DAY MAIL 312-346-1000
THIRTY-SEVEN BUSINESS DAY MAIL 312-346-1000
THIRTY-EIGHT BUSINESS DAY MAIL 312-346-1000
THIRTY-NINE BUSINESS DAY MAIL 312-346-1000
FORTY BUSINESS DAY MAIL 312-346-1000
FORTY-ONE BUSINESS DAY MAIL 312-346-1000
FORTY-TWO BUSINESS DAY MAIL 312-346-1000
FORTY-THREE BUSINESS DAY MAIL 312-346-1000
FORTY-FOUR BUSINESS DAY MAIL 312-346-1000
FORTY-FIVE BUSINESS DAY MAIL 312-346-1000
FORTY-SIX BUSINESS DAY MAIL 312-346-1000
FORTY-SEVEN BUSINESS DAY MAIL 312-346-1000
FORTY-EIGHT BUSINESS DAY MAIL 312-346-1000
FORTY-NINE BUSINESS DAY MAIL 312-346-1000
FIFTY BUSINESS DAY MAIL 312-346-1000
FIFTY-ONE BUSINESS DAY MAIL 312-346-1000
FIFTY-TWO BUSINESS DAY MAIL 312-346-1000
FIFTY-THREE BUSINESS DAY MAIL 312-346-1000
FIFTY-FOUR BUSINESS DAY MAIL 312-346-1000
FIFTY-FIVE BUSINESS DAY MAIL 312-346-1000
FIFTY-SIX BUSINESS DAY MAIL 312-346-1000
FIFTY-SEVEN BUSINESS DAY MAIL 312-346-1000
FIFTY-EIGHT BUSINESS DAY MAIL 312-346-1000
FIFTY-NINE BUSINESS DAY MAIL 312-346-1000
SIXTY BUSINESS DAY MAIL 312-346-1000
SIXTY-ONE BUSINESS DAY MAIL 312-346-1000
SIXTY-TWO BUSINESS DAY MAIL 312-346-1000
SIXTY-THREE BUSINESS DAY MAIL 312-346-1000
SIXTY-FOUR BUSINESS DAY MAIL 312-346-1000
SIXTY-FIVE BUSINESS DAY MAIL 312-346-1000
SIXTY-SIX BUSINESS DAY MAIL 312-346-1000
SIXTY-SEVEN BUSINESS DAY MAIL 312-346-1000
SIXTY-EIGHT BUSINESS DAY MAIL 312-346-1000
SIXTY-NINE BUSINESS DAY MAIL 312-346-1000
SEVENTY BUSINESS DAY MAIL 312-346-1000
SEVENTY-ONE BUSINESS DAY MAIL 312-346-1000
SEVENTY-TWO BUSINESS DAY MAIL 312-346-1000
SEVENTY-THREE BUSINESS DAY MAIL 312-346-1000
SEVENTY-FOUR BUSINESS DAY MAIL 312-346-1000
SEVENTY-FIVE BUSINESS DAY MAIL 312-346-1000
SEVENTY-SIX BUSINESS DAY MAIL 312-346-1000
SEVENTY-SEVEN BUSINESS DAY MAIL 312-346-1000
SEVENTY-EIGHT BUSINESS DAY MAIL 312-346-1000
SEVENTY-NINE BUSINESS DAY MAIL 312-346-1000
EIGHTY BUSINESS DAY MAIL 312-346-1000
EIGHTY-ONE BUSINESS DAY MAIL 312-346-1000
EIGHTY-TWO BUSINESS DAY MAIL 312-346-1000
EIGHTY-THREE BUSINESS DAY MAIL 312-346-1000
EIGHTY-FOUR BUSINESS DAY MAIL 312-346-1000
EIGHTY-FIVE BUSINESS DAY MAIL 312-346-1000
EIGHTY-SIX BUSINESS DAY MAIL 312-346-1000
EIGHTY-SEVEN BUSINESS DAY MAIL 312-346-1000
EIGHTY-EIGHT BUSINESS DAY MAIL 312-346-1000
EIGHTY-NINE BUSINESS DAY MAIL 312-346-1000
NINETY BUSINESS DAY MAIL 312-346-1000
NINETY-ONE BUSINESS DAY MAIL 312-346-1000
NINETY-TWO BUSINESS DAY MAIL 312-346-1000
NINETY-THREE BUSINESS DAY MAIL 312-346-1000
NINETY-FOUR BUSINESS DAY MAIL 312-346-1000
NINETY-FIVE BUSINESS DAY MAIL 312-346-1000
NINETY-SIX BUSINESS DAY MAIL 312-346-1000
NINETY-SEVEN BUSINESS DAY MAIL 312-346-1000
NINETY-EIGHT BUSINESS DAY MAIL 312-346-1000
HUNDRED BUSINESS DAY MAIL 312-346-1000

ATOMIC INTERNATIONAL
CORPORATION
1000 WILSON AVENUE
CHICAGO, ILL. 60642
TELEPHONE 312-346-1000
FAX 312-346-1001
CABLE ATOMIC
TELETYPE 312-346-1000
RADIO 312-346-1000
TELEVISION 312-346-1000
POSTAL 312-346-1000
AIR MAIL 312-346-1000
SEALED MAIL 312-346-1000
REGISTERED MAIL 312-346-1000
PRIORITY MAIL 312-346-1000
EXPRESS MAIL 312-346-1000
OVERNIGHT MAIL 312-346-1000
SAME DAY MAIL 312-346-1000
NEXT BUSINESS DAY MAIL 312-346-1000
TWO BUSINESS DAY MAIL 312-346-1000
THREE BUSINESS DAY MAIL 312-346-1000
FOUR BUSINESS DAY MAIL 312-346-1000
FIVE BUSINESS DAY MAIL 312-346-1000
SIX BUSINESS DAY MAIL 312-346-1000
SEVEN BUSINESS DAY MAIL 312-346-1000
EIGHT BUSINESS DAY MAIL 312-346-1000
NINE BUSINESS DAY MAIL 312-346-1000
TEN BUSINESS DAY MAIL 312-346-1000
ELEVEN BUSINESS DAY MAIL 312-346-1000
TWELVE BUSINESS DAY MAIL 312-346-1000
THIRTEEN BUSINESS DAY MAIL 312-346-1000
FOURTEEN BUSINESS DAY MAIL 312-346-1000
FIFTEEN BUSINESS DAY MAIL 312-346-1000
SIXTEEN BUSINESS DAY MAIL 312-346-1000
SEVENTEEN BUSINESS DAY MAIL 312-346-1000
EIGHTEEN BUSINESS DAY MAIL 312-346-1000
NINETEEN BUSINESS DAY MAIL 312-346-1000
TWENTY BUSINESS DAY MAIL 312-346-1000
TWENTY-ONE BUSINESS DAY MAIL 312-346-1000
TWENTY-TWO BUSINESS DAY MAIL 312-346-1000
TWENTY-THREE BUSINESS DAY MAIL 312-346-1000
TWENTY-FOUR BUSINESS DAY MAIL 312-346-1000
TWENTY-FIVE BUSINESS DAY MAIL 312-346-1000
TWENTY-SIX BUSINESS DAY MAIL 312-346-1000
TWENTY-SEVEN BUSINESS DAY MAIL 312-346-1000
TWENTY-EIGHT BUSINESS DAY MAIL 312-346-1000
TWENTY-NINE BUSINESS DAY MAIL 312-346-1000
THIRTY BUSINESS DAY MAIL 312-346-1000
THIRTY-ONE BUSINESS DAY MAIL 312-346-1000
THIRTY-TWO BUSINESS DAY MAIL 312-346-1000
THIRTY-THREE BUSINESS DAY MAIL 312-346-1000
THIRTY-FOUR BUSINESS DAY MAIL 312-346-1000
THIRTY-FIVE BUSINESS DAY MAIL 312-346-1000
THIRTY-SIX BUSINESS DAY MAIL 312-346-1000
THIRTY-SEVEN BUSINESS DAY MAIL 312-346-1000
THIRTY-EIGHT BUSINESS DAY MAIL 312-346-1000
THIRTY-NINE BUSINESS DAY MAIL 312-346-1000
FORTY BUSINESS DAY MAIL 312-346-1000
FORTY-ONE BUSINESS DAY MAIL 312-346-1000
FORTY-TWO BUSINESS DAY MAIL 312-346-1000
FORTY-THREE BUSINESS DAY MAIL 312-346-1000
FORTY-FOUR BUSINESS DAY MAIL 312-346-1000
FORTY-FIVE BUSINESS DAY MAIL 312-346-1000
FORTY-SIX BUSINESS DAY MAIL 312-346-1000
FORTY-SEVEN BUSINESS DAY MAIL 312-346-1000
FORTY-EIGHT BUSINESS DAY MAIL 312-346-1000
FORTY-NINE BUSINESS DAY MAIL 312-346-1000
FIFTY BUSINESS DAY MAIL 312-346-1000
FIFTY-ONE BUSINESS DAY MAIL 312-346-1000
FIFTY-TWO BUSINESS DAY MAIL 312-346-1000
FIFTY-THREE BUSINESS DAY MAIL 312-346-1000
FIFTY-FOUR BUSINESS DAY MAIL 312-346-1000
FIFTY-FIVE BUSINESS DAY MAIL 312-346-1000
FIFTY-SIX BUSINESS DAY MAIL 312-346-1000
FIFTY-SEVEN BUSINESS DAY MAIL 312-346-1000
FIFTY-EIGHT BUSINESS DAY MAIL 312-346-1000
FIFTY-NINE BUSINESS DAY MAIL 312-346-1000
SIXTY BUSINESS DAY MAIL 312-346-1000
SIXTY-ONE BUSINESS DAY MAIL 312-346-1000
SIXTY-TWO BUSINESS DAY MAIL 312-346-1000
SIXTY-THREE BUSINESS DAY MAIL 312-346-1000
SIXTY-FOUR BUSINESS DAY MAIL 312-346-1000
SIXTY-FIVE BUSINESS DAY MAIL 312-346-1000
SIXTY-SIX BUSINESS DAY MAIL 312-346-1000
SIXTY-SEVEN BUSINESS DAY MAIL 312-346-1000
SIXTY-EIGHT BUSINESS DAY MAIL 312-346-1000
SIXTY-NINE BUSINESS DAY MAIL 312-346-1000
SEVENTY BUSINESS DAY MAIL 312-346-1000
SEVENTY-ONE BUSINESS DAY MAIL 312-346-1000
SEVENTY-TWO BUSINESS DAY MAIL 312-346-1000
SEVENTY-THREE BUSINESS DAY MAIL 312-346-1000
SEVENTY-FOUR BUSINESS DAY MAIL 312-346-1000
SEVENTY-FIVE BUSINESS DAY MAIL 312-346-1000
SEVENTY-SIX BUSINESS DAY MAIL 312-346-1000
SEVENTY-SEVEN BUSINESS DAY MAIL 312-346-1000
SEVENTY-EIGHT BUSINESS DAY MAIL 312-346-1000
SEVENTY-NINE BUSINESS DAY MAIL 312-346-1000
EIGHTY BUSINESS DAY MAIL 312-346-1000
EIGHTY-ONE BUSINESS DAY MAIL 312-346-1000
EIGHTY-TWO BUSINESS DAY MAIL 312-346-1000
EIGHTY-THREE BUSINESS DAY MAIL 312-346-1000
EIGHTY-FOUR BUSINESS DAY MAIL 312-346-1000
EIGHTY-FIVE BUSINESS DAY MAIL 312-346-1000
EIGHTY-SIX BUSINESS DAY MAIL 312-346-1000
EIGHTY-SEVEN BUSINESS DAY MAIL 312-346-1000
EIGHTY-EIGHT BUSINESS DAY MAIL 312-346-1000
EIGHTY-NINE BUSINESS DAY MAIL 312-346-1000
NINETY BUSINESS DAY MAIL 312-346-1000
NINETY-ONE BUSINESS DAY MAIL 312-346-1000
NINETY-TWO BUSINESS DAY MAIL 312-346-1000
NINETY-THREE BUSINESS DAY MAIL 312-346-1000
NINETY-FOUR BUSINESS DAY MAIL 312-346-1000
NINETY-FIVE BUSINESS DAY MAIL 312-346-1000
NINETY-SIX BUSINESS DAY MAIL 312-346-1000
NINETY-SEVEN BUSINESS DAY MAIL 312-346-1000
NINETY-EIGHT BUSINESS DAY MAIL 312-346-1000
HUNDRED BUSINESS DAY MAIL 312-346-1000

REVISIONS		
BY	DESCRIPTION	DATE APPROVED
		SDD-096-60-000
		Page 36

FOR LEGEND SEE DWG #N09612016

ATOMICS INTERNATIONAL A DIVISION OF NORTH AMERICAN AVIATION, INC. 8900 DEWITT AVENUE, CANBERRA PARK, CALIF.			
- P&I DIAGRAM RADIOACTIVE LIQUID WASTE SYSTEM 1000 MWE LMFBR - - ANI FOLLOW ON STUDY			
DRAWN CHECKED ENGINEER APPROVED	DATE SCALE	SHEET NO. OF	N09612019

EN09612019

ATOMICS INTERNATIONAL*A Division of North American Rockwell Corporation***SUPPORTING DOCUMENT****NUMBER**

SDD-096-61-000

REV

LTR A

DOCUMENT TYPE

System Design Description

PROGRAM TITLE

ANL 1000 Mwe Follow-on Study

KEY NOUNS

Coolant Supply and Treatment

DOCUMENT TITLEReactor and Intermediate Coolant Supply and
Treatment Conceptual System Design Description -
1000 Mwe LMFBR Follow-on Study**ORIGINAL**

ISSUE DATE August 15, 1968

GO NO.

7692

S/A NO.

13140

PAGE 1 OF**TOTAL PAGES 55****REL. DATE****ABSTRACT**The requirements and the description of the
sodium supply and treatment for the reactor
and intermediate coolant SDD are contained in
this description.**PREPARED BY****DATE****DEPT/GRP NO.**

H. O. Charnock

731-153

APPROVALS**DATE**

Supvsr: H. B. Holz

Proj. Eng: D. F. Casey

Program Office: R.E.Aronstein

SECURITY CLASSIFICATION**(CHECK ONE BOX ONLY)****AEC**☒**DOD**☐**UNCL.**☐**CONF.**☐**SECRET**☐**(CHECK ONE BOX ONLY)****RESTRICTED****DATA**☐**DEFENSE****INFO.**☐**AUTHORIZED
CLASSIFIER****DATE****DISTRIBUTION****REV****SUMMARY OF CHANGE****APPROVALS AND DATE**

★

NAME**LOC**

★ TITLE PAGE ONLY

TABLE OF CONTENTS

		<u>Page</u>
1.0	INTRODUCTION	3
1.1	Functions/Functional Requirements	3
1.2	Summary System Description	4
1.3	Requirements	6
1.3.1	Performance Requirements	6
1.3.2	Environmental Requirements	9
1.3.3	Operational Requirements	10
1.3.4	Safety Requirements	10
1.3.5	Design Requirements	11
2.0	DESCRIPTION OF SYSTEM	16
2.1	Components	16
2.1.1	Sodium Filter	16
2.1.2	Primary Sodium or Reactor Coolant Storage Tanks	17
2.1.3	Secondary Sodium or Intermediate Coolant Storage Tanks	18
2.1.4	Primary Sodium or Reactor Coolant System Degassifier Surge Tank	19
2.1.5	Primary Sodium or Reactor Coolant Fill and Drain Pumps	20
2.1.6	Secondary Sodium or Intermediate Coolant Fill and Drain Pump	21
2.1.7	Primary Sodium or Reactor Coolant System Level Control Fill Pump	22
2.1.8	Primary Sodium or Reactor Coolant System Cold Traps	24
2.1.9	Secondary Sodium or Intermediate Coolant System Cold Trap	26
2.1.10	Primary Cold Trap or Reactor Coolant Regenerative Heat Exchanger	27

TABLE OF CONTENTS, CONTINUED

		<u>Page</u>
2.1.11	Secondary Cold Trap or Intermediate Coolant Regenerative Heat Exchangers	28
2.1.12	Primary Sodium Hot Trap or Reactor Coolant Regenerative Heat Exchanger	29
2.1.13	Primary Sodium or Reactor Coolant System Sampler	31
2.1.14	Secondary Sodium or Intermediate Coolant System Sampler	32
2.1.15	Primary Sodium or Reactor Coolant System Plugging Meter	32
2.1.16	Secondary Sodium or Intermediate Coolant System Plugging Meters	33
2.1.17	Stainless Steel Hot Trap	33
2.1.18	Main Primary Sodium or Reactor Coolant System, Hot Trap Electric Heater	35
2.1.19	Reactor and Intermediate Coolant Supply and Treatment System Piping and Valves	36
2.1.20	Primary Sodium or Reactor Coolant Supply and Treatment System	37
2.1.21	Secondary Sodium or Intermediate Coolant Supply and Treatment System	37
2.1.22	Irradiated Fuel Storage Pots Sodium Clean-up System	38
2.1.23	Sodium Service or Reactor and Intermediate Coolant Supply and Treatment System Instruments	39
3.0	PRINCIPLES OF OPERATION	40
3.1	Startup	40
3.2	Normal Operation	41
3.3	Shutdown	41
3.4	Special or Infrequent Operation	41
3.5	Emergency	41

TABLE OF CONTENTS, CONTINUED

	<u>Page</u>
4.0 SAFETY PRECAUTIONS	43
4.1 Hazards	43
4.2 Precautions	43
5.0 MAINTENANCE	44
5.1 Preventive Maintenance	45
5.1.2 Vapor Traps	45
5.1.3 Plugging Meter	45
5.1.4 Cold Trap Blowers	45
5.1.5 Cold Traps	46
5.1.6 Valves	46
5.1.7 Hot Traps	47
5.1.8 Electric Heaters	47
5.2 Trouble-Shooting	47
5.2.1 Sodium Filter	47
5.2.2 Vapor Traps	48
5.2.3 Plugging Meter	48
5.2.4 Cold Trap and Cold Trap Blowers	49
5.2.5 Valves	49
5.2.6 Stainless Steel Packed Hot Traps	50
5.2.7 Heaters	50
5.2.8 E/M Pumps	51
6.0 APPENDICES	52
6.1 Drawings	52
6.2 References	52

1.0 INTRODUCTION

This System Design Description describes the sodium storage, handling, purification, and monitoring facilities for the 1000 MWe FBR. The facilities are shown diagrammatically on Drawing No. N 09612011, "P & I Diagram, Reactor and Intermediate Coolant Supply and Treatment System, 1000 MWe FBR". The system is divided into two basic systems, one for radioactive primary sodium, reactor coolant supply and treatment system, and one for non-radioactive secondary sodium, intermediate coolant supply and treatment system. In the text of this system description, the Reactor Coolant System shall be referred to as the main primary heat transfer system, primary radioactive sodium system, and the intermediate coolant system shall be referred to as the secondary sodium system. The nomenclature may be used interchangeably. Each system contains storage tanks, auxiliary transfer pumps, plugging meters, cold traps, and samplers. In addition, the reactor coolant system contains a hot trap for carbon removal. An overflow tank for level control, reserve primary sodium, and primary sodium degasification are included in the main heat transfer system. The latter equipment is shown on Drawing No. N 09612009, "Sodium Heat Transfer Diagram, 1000 MWe IMFBR-Follow-on Study", SDD-096-30-000.

1.1 Functions/Functional Requirements

The sodium receiving and processing system is designed to provide the following:

- 1) A means to receive, melt out, filter, and store reactor grade sodium in either tank car or drum lots.
- 2) A means to transfer clean "as received" sodium into the main primary heat transfer system, and the secondary sodium system, in a manner that prevents contamination of the clean sodium and clean sodium handling system."
- 3) Storage receptacles and transfer equipment for draining the main sodium heat transfer system and secondary sodium heat transfer systems.
- 4) A hot, standby source of sodium to make up deficiencies in event of containment failure in the main primary heat transfer system.

Inert gas pressure will be available for emergency injection of sodium into the main primary heat transfer system.

5) Preheat facilities on all equipment to ensure that the system can be maintained at preheat temperature ($\sim 350^{\circ}\text{F}$).

6) A means for continuously purifying and monitoring condition of the sodium in the various heat transfer loops; and occasional purification and monitoring of sodium in the fuel storage vessel.

7) A means for draining all sodium out of each component in a manner commensurate with safeguards requirements.

8) A means to maintain constant sodium level in the reactor during load changes; and to partially degasify the primary sodium.

1.2 Summary System Description

The reactor and intermediate coolant supply and treatment system consists of the necessary storage facilities, purification equipment, monitoring equipment, pumps, valves, and piping to perform the stated functional requirements. The division between the various systems is dictated by a necessity to control potential contamination of the systems. The general facilities breakdown is as follows:

- 1) "As received" sodium handling.
- 2) Intermediate coolant or secondary sodium storage and handling.
- 3) Reactor coolant or primary sodium storage and handling (including sodium in the fuel storage vessel).
- 4) Reactor overflow and level control.

Sodium storage tanks are carbon steel construction, designed specifically for sodium storage. All-welded construction is used. All sodium equipment is insulated and equipped with integral heaters to maintain the sodium in a molten state. All components, valves, and instrumentation are selected specifically for sodium service. All vessels include provisions for inert cover gas. Reactor coolant or primary sodium system

vessels are vented to a radioactive waste gas collection system. Sodium valves are of the freeze seal type. All components in radioactive sodium service are installed in shielded vaults, containing inert atmospheres. All operations on radioactive systems are performed remotely. In general, sodium handling, purification, and transfer functions are remote manual operations for maximum reliability.

The reactor coolant supply and treatment or primary sodium service system consists of storage tanks, transfer pumps, cold traps, carbon trap, and monitoring equipment. The storage tanks are inactive during normal operation. They are only utilized when one or more primary loops (or the reactor system) are drained. Four primary cold traps are available, with two normally operating to maintain oxygen level very low. A plugging meter is normally in use to monitor presence of oxide in the system.

The primary cold traps and plugging meters can be used periodically to repurify the sodium in the fuel storage pot.

Normally, the pressure required to induce flow in the cold traps is supplied by the main primary pumps. During low flow operation, the auxiliary pumps are available for this purpose.

The intermediate coolant supply and treatment or secondary sodium service system is divided into three more or less independent systems, one for each main secondary sodium loop. Each system consists of an auxiliary pump, a cold trap, two storage tanks, a sampling station, and a plugging meter. The cold trap and plugging meter are normally in service at all times. One reason is to keep hydrogen in the secondary systems at a low concentration, thus minimizing hydrogen diffusion to the primary sodium system. Normally, pressure for cold trap and plugging meter operation is derived from the main secondary sodium pumps. On low flow operation, the auxiliary pumps are utilized.

The reactor overflow system is shown on Drawing No. N-09612009. This system consists of a seal tank, an overflow and expansion tank, and a service pump.

1.3 Requirements

1.3.1 Performance Requirements

a) Sufficient storage shall be provided to contain all sodium in the plant. The reactor coolant or primary sodium system shall be absolutely separated from the intermediate coolant or secondary sodium system such that primary or radioactive sodium cannot enter the secondary system, even in event of maloperation.

b) Cold traps shall be provided capable of maintaining plugging temperature in the heat transfer systems below 260°F at all times during normal operation. If oxygen sensitive material is used in the control rods (i.e., tantalum) or for other sodium wetted applications in the system, then zirconium filled hot traps shall be provided to maintain oxygen content of the sodium below 1 ppm during power operation.

c) Installed plugging meters shall be provided to measure and record plugging temperatures in both the reactor coolant or primary sodium system and the intermediate or secondary sodium heat transfer systems.

d) A hot primary sodium tank shall be provided as a continuous overflow. This tank shall accommodate all sodium from expansion during temperature rise from 500°F isothermal to operating temperatures. This tank shall be operated to maintain reactor level constant at all times.

e) Primary sodium service pumps shall generate sufficient head to perform the following functions:

(1) Fill the system against system static head. The capacity shall be sufficient to fill a single primary loop in less than 12 hours.

(2) Circulate sodium from storage tanks through the purification system and discharge either to the primary systems under static conditions; or return to the tanks.

(3) Circulate sodium from the loops through the supply and treatment purification system and back to the main loops during static or low flow operation, with sufficient flow to meet purity requirements.

f) Secondary sodium system service pumps shall have the capability to perform the following functions:

(1) Secondary sodium service pump shall be capable of filling a single loop of the secondary sodium system in less than 12 hours against the hydrostatic head of sodium in the loop. This pump shall not be required to fill secondary loops against full loop pressure (including static gas pressure and main secondary circulating pump discharge).

(2) Fill a secondary sodium loop as outlined in f) (1) above in 24 hours by passing the sodium through the purification system; and then to the loop.

(3) Circulate sodium from a secondary sodium loop through the purification system and back to the loop such that plugging temperature in the loop can be reduced from 350°F to 250°F in less than 24 hours, without benefit of the main secondary sodium circulating pumps.

g) A pressurizing tank shall be provided for injecting sodium into an operating loop. This tank shall be capable of injecting small flows (110 ft³/hr or less) into an operating secondary sodium loop against full loop pressure. This corresponds to a temperature transient of -100°F/hr for the hot leg of the secondary loops.

h) A secondary loop shall be drainable in less than two hours by gravity under emergency conditions.

i) Each pair of primary system cold traps shall be capable of reducing oxide concentration of the sodium in the primary system or reactor coolant system as follows:

From 550°F plugging temperature to 250°F plugging temperature in less than 150 hours, assuming no concurrent oxide addition to the sodium phase (initial clean-up)

From 350°F plugging temperature to 250°F plugging temperature in less than 50 hours (after fuel change).

Capacity of the traps shall be not less than 550 lb sodium oxide. The traps shall be arranged for remote change-out into a suitable shipping cask, without disturbing cooling lines or pre-heat furnace installation. A minimum of four installed primary system cold traps shall be provided, such that two are operable while the others are decaying or being changed out. The traps shall be installed to be operated in parallel if desired.

j) A suitable regenerative heat exchanger shall be provided to reduce temperature of sodium entering the cold traps to 600°F from system operating temperature.

k) Secondary sodium system intermediate coolant system cold traps shall be capable of performing as follows:

(1) Reduce plugging temperature of one loop from 350°F to 250°F in less than 24 hours with no additional contamination.

(2) Permit continued operation of a secondary loop with water inleakage of up to 1 lb/day, and maintain plugging temperature in that loop at less than 280°F.

l) The main primary sodium system or reactor coolant system level control tank shall be sized to contain a volume of sodium corresponding to the expansion volume necessary in heating up from 500°F isothermal (fuel change temperature) to full power operating temperature, with an additional 15% allowance for freeboard and heel. Design will be based on holding this sodium at 800°F. The tank shall be designed for 200 psig (design base accident) at 800°F; and will not be operated above this temperature. The tank will receive sodium from an open overflow pipe in the reactor.

m) The primary sodium system level control pump shall have sufficient head and flow capability to transfer sodium from the level control tank to the main primary coolant system pump suctions, through the purification system, at a rate corresponding to a -100°F/hr temperature transient in the primary sodium hot leg, in addition to the normal running vent flow.

n) The tank car unloading station shall be capable of melting out a tank car in less than 48 hours at an ambient of 30°F. The unit shall be capable of transferring 75 gpm of sodium at 350°F, such that a tank car can be unloaded in approximately 3 hours, without exceeding tank car pressure ratings.

1.3.2 Environmental Requirements

a) All components of the primary sodium service system or reactor coolant supply and treatment system shall be installed in inert gas filled and shielded vaults designed to shield against the radiation in the sodium system; and to minimize possibility of a radioactive sodium fire in event of leakage. Vault ambient temperature shall not exceed 150°F. Vault humidity shall be very low (less than 20% RH); and no water or water bearing equipment shall be permitted in the vaults.

b) The secondary sodium service system or intermediate coolant supply and treatment system shall be installed in dry rooms or vaults except for those portions of the system in the steam generator area. Vaults shall be capable of being isolated and flooded with inert gas in event of leakage. Ambient temperature in vaults shall not exceed 150°F; and shall not exceed 110°F if the areas are accessible to personnel during plant operation. No water or water containing equipment shall be permitted in areas containing sodium, except for that portion of the secondary sodium system or intermediate coolant system in the steam generator area.

c) All components of the primary sodium purification systems or sodium supply and treatment system shall be designed for continuous service in a gamma radiation field of 10^5 R/hr; without appreciable degradation of physical properties. If this is not possible (for example, in the case of non-metallic components of the electrical or control equipment) then provision shall be made in the design for remote or contact replacement of all equipment subject to excessive radiation damage.

d) The reactor coolant or primary sodium cold traps shall be suitable for continuous operation in a gamma field of 1.6×10^5 R/hr. Basis: 0.1% of all cesium generated is released from the fuel; and this quantity is collected in the cold trap.

1.3.3 Operational Requirements

a) Operation of the primary sodium service system or reactor coolant supply and treatment system shall be by remote manual means. All valving shall be operable through extension stems, or by other remote means, from accessible shielded operating areas. Sufficient remote instrumentation shall be provided at operating stations to advise operators of significant operating parameters such as flow, temperature, pressure, power input, etc.

b) Where malfunction or mal-operation could endanger the plant, remote control instrumentation and operating gear shall be provided in the control room to permit the operator to override the mal-function and maintain the plant in-run until corrective action is taken.

c) Plugging temperature read-out shall be in the control room, with an alarm to sound in event plugging temperature exceeds a variable setpoint.

d) Flow through cold traps shall be recorded in the control room, with high and low flow alarms to warn the operator, should flow deviate widely from pre-determined set-points.

e) Cold trap temperatures shall be recorded in the control room, with high and low temperature alarms to signal deviation from pre-determined set-points.

1.3.4 Safety Requirements

a) All primary or radioactive sodium service operations are remote, and vaults containing primary sodium are inaccessible during operation.

b) Suitable safeguards shall be established to insure that, when primary service systems or reactor coolant supply and treatment systems are opened for entry, the following potential hazards are satisfied:

Vault atmosphere is suitable for breathing (or breathing equipment is utilized).

The vault has been monitored for radiation levels, and suitable exposure times have been established.

The chief operator is aware, at all times, which vaults are opened; and which are occupied.

All primary sodium piping entering an accessible vault is isolated from the operating system by at least two independent means, including a frozen sodium plug.

c) Whenever a sodium containing component is cut out or opened, the component shall be isolated, and shall be completely drained, or the sodium shall be in the frozen state. During plant run, any component so opened shall be isolated from operating portions of the plant by at least two means, one of which shall be a frozen section of pipe.

1.3.5 Design Requirements

a) All components containing sodium shall be provided with inert cover gas (helium or argon). All gas connections shall be provided with freeze traps or vapor traps as applicable.

b) All sodium-containing equipment shall be equipped with preheaters sized to heat up from ambient to 350°F at a rate commensurate with thermal stress limitations. All preheaters shall be thermostatically controlled. However, heaters shall be sized so that pipe and equipment temperatures will not exceed design, assuming controls fail in the "on" position. Control of preheaters shall be designed to permit uniform preheating both full and empty.

c) Four primary sodium storage tanks shall be provided capable of holding all sodium required in the primary sodium heat transfer

system with 15% allowance for heel and freeboard at pre-heat temperatures up to 600°F.

d) Six secondary sodium storage tanks shall be provided, two for each loop. Capacity of two tanks shall be sufficient to contain sodium from an entire secondary sodium loop at 500°F, with a 15% overage for heel and freeboard.

e) Where possible, all connections will be in top or sides of vessels so that, even in event of a complete break in piping, large vessels cannot drain from bottom connections.

f) Primary piping and equipment shall be designed for the design base accident conditions, except for storage tanks. The main storage tanks will be isolated by suitable double valving while the reactor is critical, and will not be required to sustain the design base accident. The level control tank will sustain DBA pressure, but need not be designed to DBA temperature.

g) The reactor coolant system or primary sodium system shall be isolated from the four primary sodium storage tanks by double valving while the reactor is critical. Double valving shall be suitable for resisting the design base accident. Since the main primary sodium storage tanks will not be utilized at high temperature; and will not be connected to the main primary heat transfer system during critical operation, carbon steel is a suitable material of construction for these tanks.

h) Primary sodium cold trap systems shall be designed to sustain the design base accident, such that, should the design base accident occur during cold trapping operations, no breach of the containment would occur. Secondary cold trap systems shall be designed to the maximum design pressure in the secondary sodium heat transfer systems.

i) Those portions of the secondary sodium service system which are installed in the steam generator area (primarily drain lines) shall be designed to operate at plant outdoor ambient conditions (air at 0°F to 100°F).

j) Freeze traps and vapor traps shall be designed for continuous service in the vault ambients specified, or cooling shall be provided as required.

(Note: Nitrogen at 120°F is available for cooling these items in the nitrogen filled vaults).

k) Equipment shall be designed, built, and inspected to the following codes:

(1) Primary sodium service system, exclusive of main storage tanks - ASME Boiler and Pressure Vessel Code, Section III, Class A.

(2) Main Primary Sodium Storage Tanks, ASME Boiler and Pressure Vessel Code, Section III, Class C.

(3) All heat exchange equipment: TEMA standards, when within the scope thereof. (Note: In case of discrepancies, the ASME Boiler and Pressure Vessel Codes shall govern).

(4) Secondary Sodium Service System: ASME Boiler and Pressure Vessel Code, Section III, Class C. (Note: Those components, such as cold traps, which are interchangeable with primary system components shall be designed, inspected, and built in accordance with Class A to permit such interchangeability).

All permanently installed equipment shall be designed for a 30-year useful life with normal maintenance.

1) The reliability objectives of the sodium supply and treatment or purification system components originate with the unavailability objective assigned to the system. The objective generates two initial premises: (1) failures within the sodium supply and treatment or purification system shall be limited so that any resulting unscheduled plant outage causes an energy availability loss less than 0.5%; and, (2) scheduled maintenance required for the sodium supply and treatment or purification system (including cold trap replacements) can be accomplished during the scheduled plant outages as defined in the above reference or during reactor operation.

The redundancy of components described in this system description for the sodium supply and treatment or purification system would, with few exceptions, require at least a double failure within the system before any unscheduled reactor outage would be necessitated. Considering this fact, the following reliability objectives result:

(1) Based on the design requirement for a minimum of one plugging temperature reading per hour in the range from 250°F to 500°F plugging temperature, all primary plugging system or reactor coolant system in-cell equipment shall be designed to operate for 20 days without maintenance with a failure free reliability of $> 93\%$. Since the above plugging system (flow meter, economizer, plugging meter, instrumentation, blower, and outlet valve) includes two plugging circuits, each shall have a 20-day failure free reliability of $> 96.5\% = (\sim 0.93)^{1/2}$. These objectives require a maintenance policy which dictates repair of a failed component within 20 days of such failure.

(2) Several valves can be significant to plant availability loss. They include valves interfacing the primary purification with the primary sodium system plus three purification system valves which cannot be isolated without complete isolation of the purification system. The critical failure mode is external leakage, since such an event could necessitate plant shutdown. These valves (at least 13 in number) shall be designed to operate one year without an external leakage failure with a reliability of $> 90\%$. Each of these valves (13) shall have a one-year non-leakage reliability of $> 99.1\% = (0.90)^{1/13}$. This goal has been accomplished with presently used freeze seal valves.

(3) The remaining portions of the in-cell primary purification system equipment (cold traps, economizers, valving and other associated components, service pumps, fill and drain tanks with associated valving and piping, sampling stations) shall have a 20-day failure free reliability of $> 90\%$. The ability to complete necessary repairs within a 20-day period following a primary purification system component failure

ATOMICS INTERNATIONAL

A Division of North American Rockwell Corporation

NO. SDD-096-61-000

DATE

PAGE 15 OF

is still assumed, since the loss of these systems for short periods of time (20 days) is not expected to be critical.

The above figure does not include any reliability consideration for the potential need of a capability to supply hot sodium to the core under postulated loss of sodium accidents.

(4) The ability to quickly repair the secondary purification system components, coupled with a non-critical duty cycle, again dictates a reliability goal based on the use of components similar to those used in the primary purification system where applicable. All secondary purification equipment shall be designed to operate for 20 days with a failure free reliability of $> 83\%$.

2.0 DESCRIPTION OF SYSTEM

2.1 Components2.1.1 Sodium Filter

A sodium filter will be provided to remove particulate matter which may have been picked up inadvertently in loading, shipping, and handling. This filter is similar to filters used at SRE, HNPF, and other installations. Design criteria are as follows:

Flow:	75 gpm
Operating pressure and temperature:	20 psig, 350°F
Design pressure and temperature:	150 psig, 500°F
Pressure drop:	5 psig maximum, clean 10 psig maximum, 60% clogged
Size:	To remove 97% of all particles 40 microns and larger

Special Requirements:

- (1) Provide one spare basket, nuts, bolts, and gaskets.
- (2) Baskets to be removable and cleanable.
- (3) Filter media to be porous sintered stainless steel, type 304 or 316 for liquid sodium service.
- (4) Vessel shall be designed and built of carbon steel, ASTM A-515, GR/60 or better, in accordance with Section III, Class C, ASME Boiler and Pressure Vessel Code. Code stamp required. 100% radiograph of all welded seams required.

Basis:

- (1) 75 gpm was selected to permit unloading a tank car in approximately 2-1/2 hr. This rate corresponds to maximum reasonable flow through a 2-in. valve, with which standard tank cars are equipped.
- (2) Ten (10) psig maximum pressure drop was selected to minimize pressure on tank car for unloading.

- (3) 40-micron size was selected as a compromise to remove offensive particulate material without unduly complicating the unloading operation due to excessive plugging of the filter.
- (4) 150-psi design was selected to conform to ASA flange standards with a reasonable margin of safety.
- (5) A 515, GR 60 is a code-accepted carbon steel, readily welded and obtained. It is satisfactory for use in sodium at temperatures below 600°F.

2.1.2 Primary Sodium or Reactor Coolant Storage Tanks

Four primary sodium storage tanks are provided with combined capacity to permit full drainage of the main primary sodium system.

Capacity:	Four 64,000 gal. tanks
Operating pressure and temperature:	Atmospheric to 25 psig, 350°F
Design pressure and temperature:	125 psig and full vacuum at 700°F
Material:	Carbon Steel, ASTM A-515, GRB or better

Codes: Vessels to be all-welded construction, per ASME Boiler and Pressure Vessel Code, Section III, Class C. Code stamping required.

Special Requirements:

- (1) All connections to be on top of tank
- (2) Manholes to be welded caps
- (3) All welds, both strength and attachment, in sodium service shall be designed to prevent entrapment of flux, moisture or other contaminants. Double welded butt joints shall be back-chipped to clean metal on the first pass.

Basis:

- (1) Capacity is sufficient to permit complete draining of the primary sodium system for maintenance purposes.
- (2) Maximum cold leg temperature is 780°F. All draining will be done from the cold leg. The system cannot be drained safely until essentially all afterglow heat is removed. Therefore, 700°F is an adequate design temperature.

- (3) Carbon steel was selected as satisfactory material for sodium service at 700°F. Expense of stainless steel is not recommended.
- (4) Four tanks were selected in preference to a lesser number for easy layout and shipping. The tanks are estimated at 13' $\emptyset$ x 68' overall length. This is approximately maximum size for rail shipment, and field assembly is not recommended.
- (5) 125 psig was selected to provide adequate margin above operating. Full vacuum design assures against tank collapse in event of mal-operation.
- (6) Section III, Class C, ASME Boiler and Pressure Vessel Code, requirement is selected since these tanks will only be connected to the reactor primary during non-critical operations.

2.1.3 Secondary Sodium or Intermediate Coolant Storage Tanks

Two each of these tanks are designed to receive and store sodium from one secondary sodium loop with 15% excess for heel and free-board. The vent is provided with a vapor trap to protect vent lines from sodium deposition. Requirements are as follows:

Capacity:	55,700 gal. each (estimated, 13' $\emptyset$ x 59' overall length)
Operating pressure and temperature:	atmospheric, 400°F
Design pressure and temperature:	100 psig and full vacuum, 700°F
Material:	Carbon steel, ASTM A-515, GR-60 or better
Codes:	Design and build in accordance with ASME Unfired Pressure Vessel Code, Section III, Class C (current issue) all- welded construction. Code stamp required.

Special Requirements:

- (1) All connections shall be in top of tank.
- (2) Manholes shall be welded caps.

- (3) All welds, both strength and attachment, in sodium service shall be designed to prevent entrapment of flux, moisture, or other contaminants. Double-welded butt joints shall be back-chipped to clean metal on the first pass.

- (4) 100% radiograph of weld seams required.

Basis:

- (1) Capacity was selected so that each pair of tanks will hold the sodium from one secondary loop. Thus, should one loop become contaminated, the sodium in the other loops will not also be contaminated.
- (2) Maximum secondary cold loop temperature is 670°F. Design is based on draining from the cold leg.
- (3) Carbon steel is a suitable material for the intended service. Stainless steel is not recommended, based on cost.
- (4) 75 psig and full vacuum exceed all anticipated service requirements.

2.1.4 Primary Sodium or Reactor Coolant System Degassifier Surge Tank

A separate primary or reactor coolant sodium storage tank is provided for maintaining constant sodium level in the reactor. This philosophy permits designing the main storage tanks to lower design pressures and temperatures; and minimizes control problems. Design requirements are as follows:

Capacity:	1700 cubic ft. operating capacity (~2100 ft. ³ gross)
Design pressure and temperature:	200 psig at 1160°F
Material:	Stainless steel, A-240, Type 304
Code:	Design and build per the ASME Boiler and Pressure Vessel Code, Section III, Class A. Code stamp required.

Special Requirements:

- (1) All connections shall be on top of tank
- (2) Manholes shall be welded caps
- (3) All welds, both strength and attachment, in sodium service shall be designed to prevent entrapment of flux, moisture, or

other contaminants behind welds. Double welded butt joints shall be back-chipped to clean metal on first pass.

Basis:

- (1) Capacity was estimated on the basis of containing overflow in heating from fuel change temperature of 500°F to operating, with an additional 15% for freeboard.
- (2) Design temperature of 1160°F is based on hot leg design temperature. 200-psig design is the design pressure of the reactor to resist the DBA.
- (3) Stainless steel was selected as material of construction primarily because of design temperature.
- (4) Since this tank will normally be connected to the reactor vessel, Code Section III Class A Design Criteria will apply.

2.1.5 Primary Sodium or Reactor Coolant Fill and Drain Pumps

The primary sodium or reactor coolant fill and drain pumps serve the following purposes in the system:

- (1) Transfer primary sodium between the fill tanks and the reactor coolant system.
- (2) Circulate sodium from the storage tank through the cold trap, hot traps, and monitoring facilities.
- (3) Circulate sodium from the reactor coolant system through the cold trap, hot traps, and monitoring facilities when the main primary coolant pumps are down or are operating at low flow (pressure).
- (4) Transfer sodium from the storage tanks to the reactor on an emergency basis in case of low level in the reactor.

Type:	AC induction electromagnetic pump
Flow:	250 gpm each
Discharge pressure:	100 psig
NPSH:	20 ft Na
Operating temperature:	350 to 1140°F
Design temperature:	1160°F

Control: 10 to 100% of rated flow by
excitation current

Material: Type 304 stainless steel throat
section

Throat Design: 200 psig at 1160°F

Basis:

- (1) 250 gpm was selected as a design flow to permit filling the reactor in a reasonable length of time, and to have capacity for emergency transfer of sodium in case of leakage. Two pumps are required for redundancy because of possible inaccessibility for maintenance.
- (2) 50 psig discharge pressure is adequate to overcome static head and cover gas pressure in the reactor system under fill conditions.
- (3) NPSH: The pump will be installed about 15 ft. above sodium level in tank to avoid bottom connections.
- (4) Hot leg temperature will not exceed about 1140°F. Therefore, 1160°F should be satisfactory as a design temperature.
- (5) Except during reactor fill and emergency transfer operations, these pumps will not operate at full rated flow. Normal cold trap and hot trap flow will be between 25 and 50 gpm. Therefore, control down to 25 gpm is a requirement.
- (6) Type 304 stainless steel was selected in preference to carbon steel to avoid possible unknown adverse effects such as cavitation; and to meet temperature requirements.

2.1.6 Secondary Sodium or Intermediate Coolant Fill and Drain Pump

The secondary sodium or intermediate coolant fill and drain pump is designed to:

- (1) Transfer sodium from the storage tank to the secondary sodium loops;
- (2) Circulate sodium from the tank through the cold trap and monitoring equipment;

- (3) Circulate sodium from either secondary or intermediate coolant sodium loop through the cold trap and monitoring equipment, and back to the loop.

This latter function is required when the main loop pumps are down or are operating at low flow and thus do not develop sufficient head to perform this function. Requirements are as follows:

Type:	AC induction electromagnetic pump
Flow:	100 gpm
Discharge pressure:	75 psig
NPSH:	20 ft. Na
Operating temperature:	350°F to 670°F
Design temperature:	750°F
Control:	10 to 100% rated flow by field excitation current
Material:	Type 304 stainless steel throat section
Throat Design:	200 psig at 800°F
Code:	All welding and fabrication on the pump body shall be in accordance with the ASME Boiler and Pressure Vessel Code, Section III

Basis:

- (1) 100 gpm will permit filling the secondary systems in approximately 9 hrs.
- (2) 75 psig was selected to overcome static head (estimated at 40 psi) plus pipe friction losses.
- (3) NPSH: The pump will be installed at the sodium level in the storage tanks, with a syphon to avoid bottom tank connections.
- (4) The pump is designed to operate at cold leg temperature (670°F maximum).

2.1.7 Primary Sodium or Reactor Coolant System Level Control Fill Pump

The primary sodium system or reactor coolant level control fill pump performs the following functions:

- (1) Transfer sodium from the level control tank to the primary or reactor coolant system on cool down.
- (2) Circulate sodium from the level control tank to the primary or reactor coolant system during fuel change operations.
- (3) Emergency fill of the primary sodium or reactor coolant system on emergency loss of flow.
- (4) Maintain continuous return of intermediate heat exchanger bleed to the reactor coolant system.

Design Requirements:

Type:	AC induction electromagnetic pump
Flow:	100 gpm
Discharge pressure:	355 ft TDH
NPSH:	20 ft Na
Operating temperature:	350 to 1140°F
Design temperature:	1160°F
Control:	10 to 100% of rated flow by excitation current
Material:	Type 304 stainless steel throat section
Throat Design:	200 psig at 1160°F

Code: All welding and fabrication on the pump throat shall be in accordance with the ASME Boiler and Pressure Vessel Code, Section III, Class A.

Basis:

- (1) Capacity: 80 gpm corresponds to a hot leg transient (average) of about -100°F/hr plus 50 gpm overflow and is considered adequate for design. A larger pump would be more costly, and would pose control problems at low flow. Overflow from each IHX is about 10 gpm.
- (2) 355 ft TDH is sufficient for cold leg injection.

(3) Cold leg temperature in the closed loop primary systems may reach 780°F; hot leg temperature is 1140°F. The pump is designed for full hot leg temperature at reactor design pressure.

(4) Control from 10 to 100% of rating is desired to facilitate level control, and to control low flow rates through purification and monitoring devices.

2.1.8 Primary Sodium or Reactor Coolant System Cold Traps

The primary sodium cold traps are required to remove oxides from the primary sodium system during initial fill and rise to power, after fuel change, and after system contamination during maintenance procedures or from other causes. Requirements are as follows:

Type:	Nitrogen-cooled removable cartridge, similar to the HNPF cold traps.
Flow:	125 gpm per trap (cleanup) or 50 gpm per trap (scavenging)
Design Pressure:	200 psig at 650°F
Pressure drop:	negligible clean; 20 psi at exhaustion
Material:	Carbon steel shell and attachments; stainless steel (type 304) mesh.
Control:	Nitrogen flow is automatically damper controlled to maintain trap temperature approximately 50°F below plugging temperature, or 250°F minimum. Sodium flow is manually controlled.
Capacity:	Trap shall contain a minimum of 550 lb Na ₂ O at exhaustion.
Code:	All welded construction. Design and build in accordance with the ASME Boiler and Pressure Vessel Code, Section III, Class A. Code stamp required.

Special Requirements:

- (1) Trap shall have a removable cartridge which can be disconnected remotely, and removed in a shielded shipping cask for disposal.
- (2) Trap shall be installed in an electrically preheated furnace, designed for accommodation of the cooling nitrogen flow. Furnace heaters shall be thermostatically controlled to maintain trap at preheat temperature (above about 240°F) to prevent trap freezing.
- (3) Vessel to have fins for nitrogen cooling; and an internal regenerative heat exchanger to avoid precipitation in the external parts of the system.

Basis:

- (1) The selected trap has operated satisfactorily at HNPF and SRE (5, 7, 9, 10, 11).
 - a) It is of a suitable size for shielding and transport.
 - b) Design is simple and economical, thus facilitating spare parts procurement.
- (2) Capacity was selected to facilitate standardization with other traps. 550 lb oxide capacity should be capable of reducing oxide content of the entire main primary system from 500°F to 250°F plugging temperature approximately 3 times before exhaustion. Three traps should serve the plant at least one year under normal conditions. (After initial cleanup).
- (3) A 250-gpm flow rate through two traps will permit reducing plugging temperature from 500 to 250°F in about 100 hr for emergency clean-up. This rate could be increased by operating two sets of traps in parallel.
- (4) Carbon steel is a suitable material for sodium service at the temperature of cold trap operation.
- (5) A separate cooling coil was selected in preference to direct liquid cooling to minimize cost of replacement traps, and to obviate the problem of disconnecting cooling lines during trap change-out.
- (6) Remote cold trap removal capability is a requirement to facilitate handling of radioactive spent traps.

2.1.9 Secondary Sodium or Intermediate Coolant System Cold Trap

The secondary sodium or intermediate coolant system cold trap is a stainless mesh filled vessel designed to remove oxide contaminants from secondary sodium by precipitation on the mesh.^(5, 6, 7, 8) This unit is used to purify secondary sodium prior to operation, as well as during normal operation. This cold trap will remove oxygen down to a plugging temperature of about 250°F, corresponding to less than 5 ppm O₂ as Na₂O. Design parameters are as follows:

Type:	Air cooled, stainless mesh filled forced convection cold trap
Capacity:	Minimum 550 lb Na ₂ O
Flow rate:	100 gpm cleanup 30 gpm normal
Operating pressure and temperature:	40 psig, 300°F
Design pressure and temperature:	200 psig, 650°F
Material:	Mesh: Type 304 stainless steel, Vessel and internals: Carbon steel, A-201, GR B or better.
Code:	Trap shall be all welded construction. Design and build in accordance with the ASME Boiler and Pressure Vessel Code, Section III, Class A. Code stamp required.

Special Requirements:

- (1) Vessel to be designed as a standard vessel similar to other cold traps in the plant, to facilitate spare trap warehousing. Class A code required for interchangeability.
- (2) A standardized pre-heat furnace will be built to accommodate this trap, similar to those in the primary system, to permit standardization.
- (3) Vessel to have fins for air cooling, and an internal regenerative heat exchanger to avoid precipitation in the external parts of the system.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 27 OF

Basis:

- (1) Size: The proposed trap is similar in size and design to the primary system trap, and is a reasonable size for handling. It is calculated that one trap this size should be capable of cold trapping the entire secondary charge of sodium twice from a plugging temperature of 550°F to 250°F plugging temperature in about 100 hours. Advantage of standardization to one trap size outweighs possible savings on smaller or larger traps.
- (2) Material: Carbon steel is a satisfactory material for this service. Stainless steel is not recommended at this temperature for a disposable unit.
- (3) Coolant: Air cooling is a simple, economical, and reliable method which obviates need for NaK or other chemically reactive coolants. This concept has been satisfactorily used at SRE and HNPF.⁽⁷⁾

2.1.10 Primary Cold Trap or Reactor Coolant Regenerative Heat Exchanger

The cold trap regenerative heat exchangers are provided to lower sodium temperature entering the cold traps and to heat the sodium leaving the cold traps, thus conserving heat and avoiding excessive temperature gradients in the system. Basic requirements are as follows:

Type:	Conventional shell and tube
Design pressure:	200 psi at 1160°F
Flow:	250 gpm (design)

	<u>Cold Side</u> <u>(°F)</u>	<u>Hot Side</u> <u>(°F)</u>
Inlet temperature thermal design:	562	1140
Outlet temperatures thermal design:	1120	600

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 28 OF

Material:	Stainless steel, Type 304
Heat transferred:	14.8×10^6 Btu/hr
Approximate surface:	375 ft ²
Pressure Drop:	10 psi maximum through both sides in series
Code:	Unit to be designed in accordance with TEMA standards while within the scope thereof. Unit to be designed in strict accordance with the ASME Boiler and Pressure Vessel Code, Section III, Class A. Code stamping required.

Special Requirements:

Unit to be all-welded construction. All welds, both strength and attachment, shall be designed to prevent the possibility of trapping weld flux, moisture, or other contaminants behind welds or in crevices.

Basis:

- (1) This unit is required to minimize size of internal regenerative heat exchangers. In the cold traps, a ΔT of 50°F was selected based on analogy with previous studies that have indicated ΔT 's of 40 to 75°F to be near optimum for this type heat exchanger.
- (2) Design conditions of 200 psig at 1160°F provides sufficient margin for control and instrument error without unduly complicating design.

2.1.11 Secondary Cold Trap or Intermediate Coolant Regenerative Heat Exchangers

The cold trap regenerative heat exchangers are provided to lower sodium temperature entering the cold traps and to heat the sodium leaving the cold traps, thus conserving heat and avoiding excessive temperature gradients in the system. The basic requirements are as follows:

Type:	Conventional shell and tube
Design pressure:	100 psi at 1070°F
Flow:	100 gpm (design)

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 29 OF

	Cold Side (°F)	Hot Side (°F)
Inlet temperature thermal design:	552	1070
Outlet temperatures thermal design:	1030	600
Material:	Stainless steel, Type 304	
Heat Transferred:	2.8×10^6 Btu/hr	
Approximate surface:	64 ft ²	
Pressure Drop:	10 psi maximum through both sides in series	
Code:	Unit to be designed in accordance with TEMA standards while within the scope thereof. Unit to be designed in strict accordance with ASME Boiler and Pressure Vessel Code, Section III, Class C. Code stamping required.	

Special Requirements:

Unit to be all-welded construction. All welds, both strength and attachment, shall be designed to prevent the possibility of trapping weld flux, moisture, or other contaminants behind welds or in crevices.

Basis:

- (1) This unit is required to minimize size of internal regenerative heat exchangers in the cold traps. A ΔT of 50°F was selected for conservatism.
- (2) Design conditions of 100 psig at 1090°F provides sufficient margin for control and instrument error without unduly complicating design.

2.1.12 Primary Sodium Hot Trap or Reactor Coolant Regenerative Heat Exchanger

A primary sodium system or reactor coolant hot trap regenerative heat exchanger is provided to: (1) raise sodium temperature entering the primary hot traps; and (2) cool sodium leaving the hot traps in order to conserve heat and avoid excessive thermal gradients in the system. Requirements are as follows:

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000
DATE _____
PAGE 30 OF _____

Type: Conventional shell and tube
Design pressure & temperature: 100 psi at 1300°F
Flow: 50 gpm

	<u>Cold End</u> <u>(°F)</u>	<u>Hot End</u> <u>(°F)</u>
Inlet temperature:		
Thermal design:	780	1210
Thermal operating:	780	1210
Outlet Temperature:		
Thermal design:	820	1250
Thermal operating:	820	1250
Material:	Stainless steel, Type 304	
Heat transferred (design):	3.77×10^6 Btu/hr	
Approximate heating surface:	87 ft ²	
Pressure drop:	10 psig maximum through both sides in series.	

Codes:

- (1) Unit to be designed in accordance with TEMA standards when within the scope thereof.
- (2) Unit to be designed and built in strict accordance with ASME Boiler and Pressure Vessel Code, Section III, Class A. Code stamp required.

Special Requirements:

Unit to be all-welded construction. All welds, both strength and attachment, shall be designed to prevent the possibility of trapping weld flux, moisture, or other contaminants behind welds or in crevices.

Basis:

- (1) This unit is required to conserve electrical energy and avoid severe thermal gradients in the system. A 40°F Δt was selected based on analogy with previous studies that have indicated delta T's on the order of 40 to 75°F are near optimum for this type exchanger. A similar design has proven satisfactory at HNPF.

- (2) Design conditions of 100 psig at 1300°F provides sufficient margin for control and instrument error without unduly complicating design.
- (3) Stainless steel is construction material and is the most economical available for sodium service at the design temperature.

2.1.13 Primary Sodium or Reactor Coolant System Sampler

A radioactive sodium sampling system will be required to permit drawing periodic samples of the sodium stream for the purpose of monitoring contamination. The data, in turn, will be utilized to ascertain possible effects of corrosion, contamination, mass transport, and fuel cladding failure. Requirements of the sampler or samplers are as follows:

- (1) The sampling system permits insertion and removal of metallurgical tab samples into the reactor plenum or in the hot leg piping for monitoring metallurgical changes due to effects of hot sodium.
- (2) The system permits insertion and removal of metallurgical samples into the cold leg of the primary sodium system.
- (3) The system permits periodic withdrawal of sodium metal samples from the primary sodium system. Samples can be withdrawn from either the hot or the cold leg of the system. The sampler shall be designed to permit rapid chilling to minimize possible segregation due to temperature gradients. The sampler shall preferably be arranged to permit remote handling of the sample, thus avoiding necessity for a decay period prior to analysis. Removal of sodium samples shall be possible during plant run without violating containment criteria.

Presently, there is no available design for a suitable sampler. The sampler will be developed and proof tested during the design phase of the plant.

2.1.14 Secondary Sodium or Intermediate Coolant System Sampler

The secondary sodium or intermediate coolant system sodium sampler consists of a piece of tubing connected with suitable disconnects (such as Swagelok fittings) to the sodium piping. It is equipped with a chiller so that sodium can be permitted to flow through the sampler for some period of time, after which flow stops and the sample is chilled. The piece of tubing is then removed, and the tube is crimped and removed to the laboratory for analysis.

This sampler has been used over an extended period of time at Atomics International on the fast reactor cladding program with satisfactory results.

2.1.15 Primary Sodium or Reactor Coolant System Plugging Meter

The primary sodium or reactor coolant system plugging meter consists of a regenerative heat exchanger, a gas-cooled subcooler, a plugging valve, a flow/temperature recorder, and the necessary controls and instruments to provide a periodic reading of the plugging temperature. The instrument is essentially continuous in operation, but readings are periodic. Sodium is cooled at a pre-determined rate (5°F/min) from a point well above the plugging temperature until flow suddenly breaks. The temperature corresponding to the flow break point is taken as the plugging temperature. Low flow triggers the re-set controls, and the cycle is repeated. Basic parameters are as follows:

Accuracy:	Within <u>±</u> 5°F of true plugging temperature
Flow Rate:	1 gpm
Coolant:	Ambient cell nitrogen
Cooling Rate:	5°F/min
Design coolant temperature:	ambient cell temperature (130 - 150°F)
Design coolant flow rate:	controlled to maintain set cooling rate
Material:	Type 304 stainless steel
Design Pressure/Temperature:	150 psig at 1160°F

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 33 OF

Basis:

- (1) The proposed plugging meter is similar to that which performed satisfactorily at HNPF.^(6,7) While a plugging meter is not considered an absolute analytical device, it is the only service-proved routine monitoring device known to be available.
- (2) Flow rate and coolant rate are based on data obtained from satisfactory operation at HNPF. Wide deviations from these criteria would necessitate a development and testing program.
- (3) The HNPF plugging meter is adaptable to all plugging meter requirements in the plant. As such, units can be standardized, facilitating maintenance and spare-parts procurement.
- (4) Plugging temperature is an operational parameter and can be related to O₂ concentration.⁽⁸⁾
- (5) Design pressure and temperature were selected above anticipated operating conditions as a safety factor. Type 304 is a suitable material of construction for this service.

2.1.16 Secondary Sodium or Intermediate Coolant System Plugging Meters

Secondary sodium or intermediate coolant system plugging meters are identical with primary sodium plugging meters described in paragraph 2.1.15 to facilitate stocking of spare parts. Coolant for the secondary plugging meters is ambient air, rather than nitrogen. One plugging meter is provided per loop for maximum detection capability of abnormality (i.e., steam generator leak). Since these meters are not radioactive, and may be approached during plant operation, installed standby equipment is not provided.

2.1.17 Stainless Steel Hot Trap

Sodium is available commercially at low carbon concentration (~10 to 15 ppm). Experience in sodium-cooled plants such as EFFBR, HNPF, and SRE has indicated that carbon contamination as high as 40 to 80 ppm may be picked up from the system during startup.^(6,7,12) Additional carbon contamination, such as with SRE, is a further possibility.⁽¹³⁾

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 34 OF

The consequences of carbon contamination are the embrittlement of clad and structural components beyond design conditions. Therefore, means must be provided to remove this carbon contamination. A stainless-steel-sheet-filled hot trap is provided for removing carbon from the main primary cooling system. The carbon trap for the primary system is similar to the HNPF carbon trap. Requirements are as follows:

Design pressure and temperature:	200 psig at 1300°F
Flow:	50 gpm (design)
Material:	Shell and internals: Type 304 stainless steel
Packing:	Stainless steel sheet 0.020 in. thick
Approximate Size:	36 in. O.D. x 12 ft. 6 in. long
Approximate capacity:	100 lb carbon
Approximate weight of packing:	8300 lb
Special requirements:	Design unit with a preheat furnace for remote removal from the furnace.

Basis:

- (1) A carbon hot trap provides for cleanup of the sodium system irrespective of the source of carbon. Thus, the design includes provision for a hot trap, even though it may not be required.
- (2) Sodium plants have shown initial sodium contamination with carbon far beyond the desirable level. The stainless steel hot trap provides the best available means of reducing the carbon to tolerable levels.
- (3) Size and general design were selected based on the HNPF carbon trap, since this is a proven unit of approximately the size required. This unit can reduce carbon concentration in the main primary system from about 80 to 20 ppm.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 35 OF

- (4) It is estimated that, with a flow rate of 50 gpm, carbon concentration can be reduced from 80 ppm to about 20 ppm in approximately 2000 hr.

2.1.18 Main Primary Sodium or Reactor Coolant System, Hot Trap Electric Heater

An electric heater is provided between the hot traps and the regenerative heat exchanger to boost temperature of sodium leaving the hot traps, and, in turn, the sodium entering the hot traps. This heater is installed downstream of the hot traps, rather than vice-versa, to protect the relatively thin heater sheaths from oxidation and carburization by exposing the sheaths only to purified sodium. Design requirements are as follows:

Type:	Electric resistance immersion type heater
Size:	120 kw
Material:	Heater elements: Stainless steel sheathed, magnesium oxide insulated.
Shell:	Stainless steel, Type 304
Design pressure and temperature:	200 psig at 1300°F
Operating temperature:	1210°F in.; 1265°F out
Flow:	50 gpm
Code:	ASME Boiler and Pressure Vessel Code, Section III, Class A. Code stamp required.

Special Requirements:

- (1) All welds shall be designed to prevent trapping weld flux, moisture, or other contaminants behind welds.
- (2) Flow shall be vertically upward through the unit.
- (3) Electric resistance heaters shall have cold ends through the wall of the unit, and for a distance of 6 in. from the outside wall of the heater to accommodate insulation. Heater ends shall terminate in a junction box at least 6 in. from the tube sheet.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 36 OF

- (4) Sheaths shall be seal welded to the inside face of the tube sheet to avoid possibility of crevices.

Basis:

- (1) The heater is of the same design as the HNPF hot trap heater, which performed satisfactorily in plant service.
- (2) 120 kw is based on a normal flow of 50 gpm, with about 5% overage for heat losses.
- (3) Design conditions of 200 psig at 1300°F is somewhat above operating conditions to provide for off-normal operation and instrument error.

2.1.19 Reactor and Intermediate Coolant Supply and Treatment System Piping and Valves

Piping in the fresh sodium system is carbon steel, ASTM-A-106. Piping in the remainder of the sodium service or reactor and intermediate coolant supply and treatment system is stainless steel, ASTM-A-312 Type 304-H seamless, or A-376 Type 304-H. Stainless steel was selected for this service due to high anticipated operating temperatures, and to avoid an excessive number of dissimilar weld connections.

Valves shall be butt-welded end valves of material to match adjacent piping (i.e., carbon steel in the fresh sodium system; stainless steel for the remainder of the system). Valves shall be wedge disc gate valves for shut-off service and modified plug disc globe valves for throttling service. Valves shall have extended stems with gas-cooled freeze seals, designed for the operating sodium temperatures and ambient temperatures involved. Valves shall have all seal-welded or strength-welded bonnets. Valves shall be back-seated with Stellite facings.

Freeze-seal stems shall have bellows seal backup to seal the inert atmospheres. Bellows shall be type 304 stainless steel.

Seats and discs shall be faced with dissimilar hard facings, Stellite No's 6 and 12 or approved equal.

Valves shall be designed for manual operation. Valves on non-radioactive service shall be direct handwheel operated. Valves in radioactive areas shall have line-shaft extension stems suitably supported on bearings or pillow blocks, with gas seals at penetrations. Provision is made in design for pipeline movement by including universal joints and/or slip joints in the operator shafting.

2.1.20 Primary Sodium or Reactor Coolant Supply and Treatment System

The piping in the primary sodium service or reactor coolant supply and treatment system is connected to provide maximum flexibility in operation of the system. Two primary sodium fill and drain pumps are required for redundancy in critical service. The two fill and drain pumps are connected in parallel so that either pump can pump from any one tank to any sodium loop through the service system or directly to the loops. It is also possible to pump from the loops through the service system and back to the loops utilizing the fill and drain pumps. The main sodium circulating pumps will be used to circulate a side stream of sodium through the purification system and back to the loops under normal plant operation. The reactor overflow tank will be maintained on standby at all times with heated lines to permit pumping from the overflow tank to the primary system in case of loss of sodium level in the reactor. Under normal operating conditions, it will be possible to continuously circulate, either by use of the auxiliary pumps or by the main pump through the sodium samplers and plugging meter, either in parallel with or independent of the purification equipment.

2.1.21 Secondary Sodium or Intermediate Coolant Supply and Treatment System

The secondary sodium piping is arranged so that sodium is pumped through the plugging meter, sodium sampler, or cold trap by the main secondary loop pumps during normal operation. This may also be

accomplished by use of the secondary sodium fill and drain pumps should the main secondary sodium loops be operating at low flow and thus not have sufficient head to drive the required flow through the purification system. No attempt has been made in the design of this system to provide for automatic transfer of sodium from the secondary sodium storage tanks to the loops. This will be a manual operation. There is sufficient expansion capacity available in the secondary loop expansion tank to provide for sodium expansion from approximately 350°F to maximum operating temperature. Thus, the problem of maintaining level in the secondary sodium loops is minimized. The sodium in the secondary sodium loops is purified without passing through the main secondary sodium storage tank. Thus, should some oxides or other deleterious material be residual in the secondary sodium storage tank, it will not be circulated through the cold trap while purifying the secondary loops. Also, the problem of possible transport of sodium from the loops to the storage tank or vice versa, thus complicating level control, is obviated.

2.1.22 Irradiated Fuel Storage Pots Sodium Clean-up System

The sodium in the irradiated fuel storage pots will be radioactive. Therefore, the cleanup system provided for the main primary system is used on a periodic interruptable basis for cleanup of the fuel storage pots. The sodium from storage pot may be circulated through the reactor coolant supply and treatment or primary sodium cleanup system and back to the fuel storage pot by means of the sodium service EM pumps. The cooling system for the fuel storage pots has not been designed at this time. However, it is shown on the drawing as a NaK system. It is considered inadvisable to interconnect the cooling function of the fuel storage pots to the main primary cooling system due to possible operational and control problems. It is conceivable that the present system could be modified to provide a parallel sodium cooling system for the fuel storage pots in lieu of the NaK system, after further detailed engineering evaluation.

2.1.23 Sodium Service or Reactor and Intermediate Coolant Supply and Treatment System Instruments

Plugging meters have been described previously. Other instruments are of a type compatible with sodium systems as follows:

Temperature: Thermocouples are used for all temperature measurement in this system. Iron-constantan is satisfactory for the service involved. Surface thermocouples are used for control of preheater operation. All welded thermocouple wells are utilized for process thermocouples. Wells are of the same material as piping and equipment.

Pressure: NaK filled transducers are utilized in sodium service.

Where possible, pressure readings are taken from the gas space over free sodium surfaces. In this case, conventional diaphragm or bourdon tube gages are utilized. Gages are protected from sodium frost by means of vapor traps.

Flow: Magnetic flow meters are utilized where specified, including the plugging meter circuits, to avoid penetrations into the sodium containing envelope.

Level: Induction coils are utilized for level measurement to avoid penetration of the envelope. The coils are installed in all welded thimbles to avoid penetrations into the sodium containing equipment. They may be single point indicators (for example, high or low level alarms); or they may be continuous reading over a given range, depending on duty required.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 40 OF

3.0 PRINCIPLES OF OPERATION

3.1 Startup

The sodium transfer and storage facilities are designed for manual operation. All valving and control is remote manual, (for example, reach rods are used for remote manual valve actuation under operator control). Startup procedure consists, basically, of the following steps:

- (1) After construction is complete, all instrumentation will be checked by means of synthetic signals to assure calibration and to assure that instruments are properly connected to the correct readout and primary sensor.
- (2) The entire system will be helium leak checked.
- (3) The entire system will be heated, dried, and purged with helium through purge connections provided. Effluent gas will be checked for residual oxygen. Residual oxygen shall not exceed 0.5% and dew point of effluent shall be less than 10°F before completion of purge. The system will be heated to about 350°F during purge to ensure that all moisture is removed and that surfaces are off-gassed.
- (4) The systems will be filled with sodium, starting with the sodium storage tanks. Prior to pumping sodium from the storage tanks to the loops, each tank will be cold trapped to less than 300°F plugging temperature.
- (5) The systems will be filled in turn from the various sodium storage tanks. Immediately on filling, each system will be circulated through the attendant cold trap to reduce plugging temperature to less than 300°F. On initial fill, sodium systems tend to pick up oxygen from the systems and plugging temperatures tend to rise, particularly on rise in system temperature until all "hide out" oxygen has been removed. Therefore, it is advisable to utilize the cold traps to maximum extent during initial fill and rise to temperature.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 41 OF

During the startup procedure, an adequate supply of cold traps should be kept on hand to insure that plant operations will not be delayed for want of cold traps. A minimum of one spare cold trap for each installed cold trap is recommended.

3.2 Normal Operation

In normal operation, storage tanks are valved out of the system. However, the primary sodium overflow tank is held on hot standby at all times, prepared to pump additional sodium into the reactor, should a leak occur and the sodium level fall below a safe level.

Should carbon contamination be detected or suspected, loop sodium temperature will be lowered to about 800°F and circulation initiated in the stainless steel packed hot trap until carbon content of the sodium is reduced below about 25 ppm. (25 ppm corresponds to ~ 0.8% surface carbon in stainless steel exposed to sodium at 1200°F.)

3.3 Shutdown

During initial phases of reactor shutdown, valves are opened and pumps turned on to perform transfer or circulation functions in the system. When these functions are completed, power to the pump is cutoff and valving is closed. On full plant shutdown, the storage tanks will normally contain the sodium inventory and it may be decided to allow the sodium to freeze in the tanks. For limited shutdown periods, all lines, piping, tanks, and equipment will be maintained in preheated condition.

3.4 Special or Infrequent Operation

All operations with the sodium transfer and storage system are based on intermittent operation on a random or pre-planned schedule. Therefore, all operations are to be considered in this category.

3.5 Emergency

Two emergencies are specifically planned for. In case the level in the reactor vessel falls below a safe level, a reserve of sodium, carried in the overflow tank at cold leg temperature, can be pumped into the main primary, or reactor coolant, system. The pumps and lines are maintained on hot standby at all times, permitting emergency fill of the reactor. Pumps are backed up by inert gas pressure, with a reserve of inert gas on immediate standby for this purpose.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 42 OF

Lines are kept on hot standby to permit rapid draining of all secondary sodium systems should a leak develop.

It is not anticipated that an emergency could develop that would necessitate draining of primary or reactor coolant systems. Such drainage would risk uncovering fuel and could be more serious than leakage of the system. Because of this potentiality, however, all primary sodium systems are doubly contained below core level to limit potential gross leakage to second-order failure conditions. A second-order failure is defined as two independent random failures of equipment occurring concurrently.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 43 OF

4.0 SAFETY PRECAUTIONS

4.1 Hazards

Primary sodium will be radioactive, necessitating shielding of primary or reactor coolant systems.

All sodium constitutes a potential fire hazard. Primary sodium would constitute both a fire and a radiological hazard, should a leak occur. Such a fire could, conceivably, disperse radioactive sodium oxide to the surroundings.

4.2 Precautions

All primary sodium-containing units are contained in vaults with inert atmospheres so that, should a leak occur, no radioactive sodium fire will ensue. All primary sodium heat transfer loops are doubly contained below core level to ensure against uncovering the core even in event of leakage. All connections to primary sodium heat transfer systems are doubly valved so that, should one valve tend to leak, the loop will not drain inadvertently.

Leak detectors are placed at strategic locations, throughout the sodium service systems. Fire protection supplies and equipment (calcium carbonate, Met-L-X fire extinguishers, protective clothing, etc.) are located throughout the plant for ready availability.

5.0

MAINTENANCE

Maintenance requirements in the design are as follows:

- (a) All primary sodium service system components which are reasonably subject to malfunction or failure, and whose failure could result in forcing plant shut-down, shall be redundant to permit routine maintenance. Such redundant equipment shall be installed in separately isolable and shielded vaults such that maintenance can be performed on standby equipment during plant run.
- (b) Where maintenance, as outlined in (a) above, is contemplated during plant operation, or where components (i.e., cold traps) will be changed out in run, freeze sections of piping shall be provided, such that isolation of a vault or working area is affected by at least two independent means (valve and frozen section of pipe), of which one is a frozen plug of solid sodium. Thus, certain items may be disconnected while the operating portions of the plant may continue to run, and the primary system could contain the design base accident.
- (c) Two primary sodium fill and drain pumps shall be provided. The pumps shall be installed in separately shielded compartments to permit maintenance on one pump while the other continues to run.
- (d) Either primary or secondary sodium cold traps shall be capable of change-out while the plant continues in normal operation, without violating containment criteria. It shall be possible to change-out a cold trap in less than 24 hours, assuming no plant shut-down and no appreciable radiological decay.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 45 OF

5.1 Preventive Maintenance

5.1.1 Sodium Filter

The sodium filter must be changed out whenever pressure drop becomes too high. Pressure gages are not provided, since these items themselves are maintenance items. Rather, the flow meter will be utilized to determine when the filter requires change-out. At a given tank car (nitrogen) pressure, when flow drops to 50% of flow through a clean filter, the filter element will be changed out. Gaskets will be changed with each change of filter element to ensure against gasket leakage.

5.1.2 Vapor Traps

Each tank is equipped with a vapor trap to remove sodium vapor from vent gasses. Vapor traps should be melted out periodically, thus removing solidified sodium and ensuring against plugging. The frequency at which this operation is required will depend on the operation, and cannot be predicted accurately. Whether or not a vapor trap is plugged can be determined by manual manipulation of helium and vent valving. All vapor traps will be checked monthly in this manner. Vapor traps will be melted out annually during maintenance shutdown as a precautionary measure.

5.1.3 Plugging Meter

Plugging meter operation can be observed by noting the plots of flow versus plugging temperature. Abnormalities in the charts should furnish current data on need for calibration or other maintenance. The plugging meter cooling fans require periodic lubrication. This will be accomplished each time the cell can be entered, but not less than once every 6 months.* Magnetic flux of flow meter magnets will be checked annually to ensure reliable flow meter calibration.

5.1.4 Cold Trap Blowers

Cold trap blowers and blower motors will be checked daily for bearing temperature. These units will be lubricated monthly. Blowers

*If scheduling is such that sealed cells will not be entered this frequently, means for bearing lubrication from outside the cells must be provided.

installed in radioactive areas are provided with remote lubrication fittings, and remote reading temperature indicators on the bearings to facilitate maintenance.

Motors should last for extended periods of time in the radiation fields predicted, based on experience at SRE. However, insulation should be checked annually to attempt to detect incipient radiation damage. Motors will be inspected annually for dirt, dust, and signs of radiation damage. Motor brushes will be inspected annually.

5.1.5 Cold Traps

Cold traps are changed out based on pressure drop measurements. Pressure gages and flow-meters are provided on pump discharge lines. When pressure drop through a cold trap increases 20 psi above pressure drop through a clean trap (at rated flow), the trap is considered exhausted and will be changed out. Radioactive traps are designed for remote removal. New gaskets are always provided with replacement traps.

5.1.6 Valves

Valve operator shafting is supported on bearings or pillow-blocks that require lubrication at approximately 6-month intervals. Where such bearings are installed in inaccessible areas, remote lubrication connections are supplied.

Valve stems in freeze seal valves occasionally become clogged with sodium oxide, since these areas constitute cold legs in the system. This effect can be detected by noting that valves become increasingly hard to turn with time. As a precautionary measure, all freeze seal valves, and all freeze seal vents, will be melted out and re-frozen annually during the maintenance shutdown. In event a valve becomes hard to turn, the freeze seal will be melted out and re-frozen at the first shutdown for fuel change.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 47 OF

Heaters are provided on all freeze seals and all valve freeze stems to facilitate this operation. In event one melting operation does not free a valve satisfactorily, the procedure will be repeated, and the valve operated until it turns freely.

Some valves are equipped with limit switches to indicate valve position. Adjustment of the limit switches will be checked at each maintenance shut-down when valves are accessible.

It is conceivable that bellows backup seals may fail and leak. This may be checked by manual manipulation of vent and inert gas valving. Leaking bellows seals will be changed out at the earliest opportunity, when the valves become accessible.

5.1.7 Hot Traps

Hot traps are changed out by cutting the connecting piping and removing the traps, after which new traps are installed. Prior to trap removal, sodium is blown from the traps to the maximum feasible extent, and the traps are cooled to room temperature. This minimizes possibility of spills or fire.

5.1.8 Electric Heaters

Annually, during maintenance shutdown, all electric heaters are checked for continuity and resistance to ground. Heaters showing evidence of failure are replaced. All relays and thermostatic controls are checked at this time, and cleaned or overhauled if required.

5.2 Trouble-Shooting

5.2.1 Sodium Filter

A major drop in flow of sodium through the filter, without a corresponding drop in driving force (nitrogen pressure), indicates possibility of filter plugging. In such an event, proceed as follows:

- (1) Check instruments to assure that it is, indeed, a drop in flow.
- (2) Check all valves between tank car and fresh sodium storage tank to assure that valves are open.
- (3) Check all preheaters on unloading line.

If all the above checks indicate satisfactory operation, the likelihood is that the filter is plugged. Cool down and change-out filter.

5.2.2 Vapor Traps

To check vapor traps, proceed as follows:

- 1) Check PIC for calibration, using a synthetic signal.
- 2) Close inlet helium valve and bleed down vent valve to atmosphere.
- 3) Open inlet helium valve. If set pressure is reached almost instantaneously, indications are the trap is plugged. Melt out trap and re-test.
- 4) If pressure rises slowly to set point on controller, indication is the trap is not plugged.

5.2.3 Plugging Meter

Plugging meter operation can usually be monitored simply by observing the chart. Possible indications of mal-operation are as follows:

- 1) Rate of temperature decay deviates widely from 5°F/min, prior to plugging. This is an indication of malfunction in the temperature control equipment.
- 2) Failure to re-heat after a plugging run. This could indicate failure of the solenoid to lift the valve off the seat, due to control malfunction or to burnout of the solenoid.
- 3) Failure to plug near the plugging temperature, coupled with high flow. This could indicate the plug has not re-seated after a plugging run, and may indicate control malfunction or burnout of solenoid.
- 4) Two or more breaks in the flow curve. This could indicate plugging caused by compounds other than sodium oxide (e.g., sodium hydride, sodium carbonate, or other material). Such erratic behavior would suggest need for chemical analysis to ascertain cause of the problem.

5.2.4 Cold Trap and Cold Trap Blowers

Possible indications of malfunctions and their meanings are as follows:

- 1) Premature plugging: experience has shown that cold traps will plug prematurely if excessive temperature difference is permitted between plugging temperature and cold trap set point. Cold trap set point should be not lower than 50°F below measured plugging temperature. If the cold trap has plugged prematurely, flow should be stopped and the trap heated to approximately 600°F for several hours. After soaking at the elevated temperature, the trap should be cooled below the system plugging temperature, and flow again started.
- 2) Failure of trap to cool below system temperature: this indication suggests lack of cooling. This could be caused by blower failure, or by malfunction of the temperature control equipment (thermocouple, damper, or positioner). It could also be caused by failure of coolant flow in the secondary (kerosene) heat removal system. These items can be checked out electrically.
- 3) Failure of trap to maintain predetermined operating temperature: this could indicate malfunction of control equipment (thermocouple, damper, or damper positioner). It could also indicate excessive sodium flow for the desired trap operating temperature. Check sodium flow-meter.

5.2.5 Valves

- 1) Valves Leak. Most valves in the system are duplicated. In general, leaking valves can be detected by closing one of two valves and observing results

2) Valves Difficult to Turn. This symptom probably indicates presence of excessive sodium oxide in the freeze seal area. This can usually be corrected by alternately heating and blowing out the seal, and re-freezing. In case of certain valves, this can only be done during shutdown. If this procedure does not free the valve, it may be necessary to open the valve. However, before opening the system, operating reach-rods should be checked carefully for freedom of motion to assure that the difficulty is not in the operating linkage.

5.2.6 Stainless Steel Packed Hot Traps

Stainless steel hot traps will remove carbon from sodium down to an equivalent of about 20 to 25 ppm when operated at 1200°F. This can be verified by checking surface carbon in stainless steel test tabs installed in the inlet and outlet of the carbon trap or elsewhere in the system. If carbon content of the sodium does not become lower after extended stainless steel hot trap operation, three possible conditions are indicated:

- 1) The stainless steel hot trap is not up to operating temperature.
- 2) The stainless steel hot trap is saturated with carbon and should be replaced.
- 3) A source of carbon contamination exists in the system and is replacing carbon as fast as the hot trap is removing it.

All three possibilities should be investigated in detail. In particular, if a test tab ahead of the hot trap is being carburized, and one downstream is not, items (1) and (2) can be eliminated. Conversely, if a test tab downstream of the hot trap is being carburized, items (1) or (2) or both are indicated.

5.2.7 Heaters

Performance of electric heaters and preheaters is monitored continuously by means of installed thermocouples. If indication of malfunction exists, the

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 51 OF

thermocouples should be checked for continuity, calibration, and ground. If thermocouples prove to be in operating condition, controllers and relays should be tested and inspected for such items as loose wiring, grounds, or sticking contacts. Finally, heaters themselves should be tested for continuity, resistance, and ground.

5.2.8 E/M Pumps

Possible malfunctions are as follows:

- 1) Failure to wet pump throat
- 2) Coil burnout
- 3) Control malfunction
- 4) Gas entrainment

Failure to wet pump throat will result in failure to pump. This can usually be corrected by priming the pump at an elevated temperature (500 to 600°F). The higher temperature can be attained by imposing a low voltage on the field coils.

Coil burnout can be checked out electrically. Control malfunction can be detected electrically. Gas entrainment can be observed by erratic flow meter behavior. This usually rectifies itself as temperature rises; if not, the entire system must be examined to determine source of gas.

ATOMICS INTERNATIONAL

A Division of North American Rockwell Corporation

NO. . SDD-096-61-000

PAGE . 52

6.0 APPENDICES

6.1 Drawings

6.2 References

1. NAA-SR-6502 (Special) - "HNPF Maintenance Manual, Vol. III, System Description"
2. U.S. Industrial Chemicals Co., Technical Pamphlet, "Handling Metallic Sodium on a Plant Scale," 3rd Edition, 1939
3. The Reactor Handbook, Vol. 2, Engineering. U.S.A.E.C., May, 1955, AECD-3646
4. Liquid Metals Handbook, Sodium-NaK Supplement, U.S.A.E.C./Dept. of the Navy, TID-5277, July 1, 1955
5. NAA-SR-3638, "Control of Oxygen Concentration in a Large Sodium System," R. B. Hinze, December 1959
6. NAA-SR-5445, Design and Thermal Analysis of Sodium Specialities Components for HNPF, Casey and Leonard
7. NAA-SR-9265, HNPF Reactor Operation Analysis Progress Report No. 2, March 1963 - August 1963
8. KAPL-1653, "Solubility of Sodium Monoxide in Liquid Sodium," Salmon, O.N., and Cashman, T.S., November 30, 1956
9. NAA-SR-4382, "HNPF Cold Trap Evaluation," R. Cygan, December 1959
10. NAA-SR-5348 (Rev.), "Design Modifications to the SRE During 1960," Staff, February 1961
11. NAA-SR-11396, "The Effects of Long Term Operation on SRE Sodium System Components," A.I., Hansen, August 1965
12. NAA-SR-6386, Removal of Carbon from Sodium Systems, W. J. Anderson
13. NAA-SR-4487, SRE Fuel Element Damage; staff
14. BNWL-CC-175, "Progress Report, Conceptual Design, Fast Flux Test Facility," Vol. 3, Design Analysis, Battelle, N.W., August 1965
15. NAA-SR-10850, AI Quarterly Progress Report, Section III, October to December 1964

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-61-000

DATE

PAGE 53 OF

16. BNWL-CC-400, "Progress Report, Fast Flux Test Facility, Interim Reference Concept"
17. ASME Boiler and Pressure Vessel Code, Section III, Nuclear Vessels (Latest Edition)
18. ASME Boiler and Pressure Vessel Code, Section VIII, Unfired Pressure Vessels (Latest Edition)
19. "The Reactor Handbook," Second Edition, Vol. 1, U.S. Atomic Energy Commission, 1960, Tipton, C. R., Editor.

ATOMICS INTERNATIONAL A DIVISION OF NORTH AMERICAN PARTITION, INC. 2700 BROADWAY AVENUE, CANADA PARK, CALIF.	
NAME <input type="text"/>	
FIRM <input type="text"/>	
ADDRESS <input type="text"/>	
CITY <input type="text"/>	
STATE <input type="text"/>	
ZIP <input type="text"/>	
PHONE <input type="text"/>	
FAX <input type="text"/>	
E-MAIL <input type="text"/>	
COMMENTS <input type="text"/>

ATOMICS INTERNATIONAL*A Division of North American Rockwell Corporation***SUPPORTING DOCUMENT**

NUMBER

SDD-096-64-100

REV
LTR

DOCUMENT TYPE

System Design Description

PROGRAM TITLE

ANL 1000 Mwe LMFBF Follow-On Study

KEY NOUNS

Auxiliary Systems

DOCUMENT TITLE

Startup, Shutdown and Decay Heat Removal
System CSDD - 1000 Mwe LMFBF Plant, ANL
Follow-on Study

ORIGINAL

ISSUE DATE January 2, 1969

GO NO.

7692

S/A NO.

13140

PAGE 1 OF

TOTAL PAGES 36

REL. DATE

ABSTRACT

The conceptual requirements and design of the
Startup, Shutdown and Decay Heat Removal
System for the 1000 Mwe LMFBF Plant are
contained in this document.

PREPARED BY

DATE

DEPT/GRP NO.

J. H. Campo

731-153

APPROVALS

DATE

Supvr: H. B. Holz

Proj. Engr: D. F. Casey

Prog. Off: R. E. Aronsteir

SECURITY CLASSIFICATION

(CHECK ONE BOX ONLY)

AEC

DOD

UNCL.

CONF.

SECRET

(CHECK ONE BOX ONLY)

RESTRICTED

DATA

DEFENSE

INFO.

AUTHORIZED
CLASSIFIER

DATE

DISTRIBUTION

REV

SUMMARY OF CHANGE

APPROVALS AND DATE

*

NAME

LOC

★ TITLE PAGE ONLY

TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION	4
1.1 Functions/Functional Requirements	4
1.2 Summary Description	5
1.3 Requirements	6
1.3.1 Performance	6
1.3.2 Environmental	10
1.3.3 Operational	11
1.3.4 Safety	12
1.3.5 Design	12
2.0 DESCRIPTION OF SYSTEM	15
2.1 Superheater Bypass	15
2.2 Main Steam Turbine Bypass	16
2.3 Reheat Steam Turbine Bypass	16
2.4 Flashtank	16
2.5 Decay Heat Pumps	17
2.6 Startup Auxiliary Boilers	18
2.7 Instrumentation	18
2.8 Piping	19
3.0 OPERATION	19
3.1 Cold Startup Sequence	19
3.2 Hot Restart (approx 3 hrs after tripout)	22
3.3 Hot Restart (within 1 hr after tripout)	23

TABLE OF CONTENTS (Cont'd)

	<u>page</u>
4.0 SAFETY CONSIDERATIONS	24
4.1 Hazards	24
4.2 Precautions	25
5.0 MAINTENANCE	26
6.0 APPENDICES	27
6.1 Design Data Tables	27
6.2 Figures	28
6.3 References	28

1.0 INTRODUCTION

The startup, shutdown and decay heat removal system is designed to provide for the coordinated startup and shutdown operation of the three once-through (modular) steam generator banks and the turbine, following a plant shutdown or a reactor or turbine tripout. The system functions during plant startup and shutdown, to remove the excess energy from the heat transfer system by dumping it to the main condenser; and to the atmosphere during certain emergency conditions.

The startup, shutdown and decay heat removal system contains the necessary equipment and controls used during plant startups, sudden load rejections, and during normal and emergency shutdowns. The system contains the following main subsystems and components.

- 1) Superheater bypass subsystem
- 2) Main steam turbine bypass subsystem
- 3) Reheat steam turbine bypass subsystem
- 4) Reactor decay heat rejection subsystem
- 5) Preheat steam and drain subsystem
- 6) Pegging and sealing steam subsystem
- 7) Flashtank steam dump and drain subsystem
- 8) Flashtank
- 9) Pressure reducing stations
- 10) Desuperheating and attemperating stations
- 11) Decay heat pumps and drives
- 12) Startup auxiliary boilers
- 13) Controls

1.1 Functiona/Functional Requirements

The steam dump and startup system provides the following main functions during startups and shutdown.

- 1) Preheat the steam generators, reheater, and the main steam lines by circulating water and steam.
- 2) Deaerate and heat the feedwater.
- 3) Regulate the pressure and temperature in the steam generator.
- 4) Act to relieve overpressure in the steam system.
- 5) Provide steam for sealing, preheating, and initial rolling of the turbine.
- 6) Reject decay heat from the reactor under all conditions when the turbine is not in operation.

The following are the functional requirements of the steam dump and startup system.

- 1) Protection of the steam generators, reheaters, and turbine from excessive temperatures, pressures, and thermal shocks.
- 2) An operating plant life of 30 years.

1.2 Summary Description

The flow diagram given in the appendix shows the main features of the Startup and Shutdown system, as follows:

Superheater bypass headers are provided from the three evaporator outlets to the corresponding pressure reducing valves. These valves are designed to reduce the water or steam pressure from evaporator outlet conditions to those existing in the flashtank. The pressure reducing valves from each of the evaporators exhaust through a common header to the flashtank. The pressure reducing stations are designed for a maximum flow capability of 360,000 lb/hr*, each, and for a maximum pressure drop from 2800 psig to 250 psig. The superheater bypass is used during the startup sequence, hot standby and during the decay heat operation.

Main steam turbine bypass headers are provided from the three superheater outlets to reduce the water (wet startup) or steam pressure from superheater outlet conditions to those existing in the flashtank. The pressure reducing valves from each of the superheaters exhaust to a common header which connects to the flashtank steam dump header. The pressure reducing stations are designed for a maximum steam flow capability of 360,000 lb/hr*, each, and for a maximum pressure drop from 2500 psig to 250 psig. An attemperating station in the turbine bypass header is used to reduce the steam temperature from approximately 900°F to approximately 400°F. The main steam turbine bypass is used during the startup sequence, hot standby, and during sudden load rejections and emergency shutdowns.

Reheat steam turbine bypass headers are provided from the three reheat outlets to the corresponding pressure reducing valves. These valves are designed to reduce the steam pressure from reheater outlet conditions, which is lower than flashtank pressure, to those existing in the common steam header leading to the condenser. The pressure reducing stations are designed for a maximum steam flow capability of 360,000 lb/hr*, each, and for a maximum

* 5% of turbine valve wide open flow.

pressure drop from 550 psig to 250 psig. An attenuating station in the reheat steam dump header is used to reduce the temperature from approximately 990°F to 400°F. The pressure and temperature are further reduced before admission to the condenser. The hot reheat steam turbine bypass is used during the startup sequence, hot standby, and during sudden load rejections and emergency shutdowns.

The flashtank, used as storage and source of intermediate pressure steam and water during the startup sequence, operates at pressures up to 600 psig and temperatures up to 500°F. It receives steam from the auxiliary boilers during the preheat cycle, from the evaporator outlet during the startup and decay heat operation, and from the evaporator and superheater outlets during the hot standby period. The flashtank provides steam or water for preheating, for deaerating and feedwater heating during the startup sequence and hot standby, and for warming, sealing and initial rolling of the main turbine. The flashtank pressure is reduced to approximately 250 psig during normal plant operation. The combined heat rejection capability from the three heat transfer circuits, during the steam dump operation, is approximately 30% of the rated thermal power.

The steam dump and startup system is provided with the following equipment which complements the operation of the above subsystems:

- 1) Two auxiliary startup boilers.
- 2) A decay heat feedwater pump, and a condensate pump, driven by electric motors.
- 3) Pressure, temperature, flow, and level controls tied to the plant startup and shutdown sequence control subsystem.

1.3 Requirements

1.3.1 Performance Requirements

1.3.1.1 Each of the three steam dump and startup system bypasses shall be designed with a flow capability of 15% of the turbine valve wide open flow, at the rated pressure and temperature conditions. This flow results in approximately 30% heat rejection capability from the three heat transfer circuits. The reactor shall be run down at its maximum rate to approximately 25% of rated power, following a turbine trip. Two-loop heat rejection is not expected to meet this requirement.

1.3.1.2 The system shall provide low pressure saturated steam at 30 psig to preheat the evaporator, superheater, and reheater modules and steam lines, from a cold start at less than 50°F to approximately 200°F in approximately 90 minutes.

1.3.1.3 The system shall provide low pressure saturated steam at 250 psig to preheat the evaporator, superheater and reheater modules from a warm start at approximately 90 minutes.

1.3.1.4 The system shall provide for drainage of the water accumulated in the evaporator, superheater and reheater modules, and steam lines during the preheating cycle.

1.3.1.5 The system shall provide a source of superheated steam to maintain the evaporator, superheater and reheater modules, steam lines, and the high and intermediate pressure turbine casings, at approximately 350°F during warm standby conditions.

1.3.1.6 The system shall provide for initial heating of the feed-water to approximately 350°F and circulation to the flashtank, condenser, and condensate polishing demineralizer prior to admission to the evaporator modules.

1.3.1.7 A superheater bypass subsystem shall provide for independent bypassing of each superheater bank. Each superheater bypass shall have a maximum flow capability of 360,000 lb/hr, and shall contain a pressure reducing station to decrease the water or steam pressure from evaporator outlet conditions to those existing in the flashtank, with a maximum pressure drop from 2800 psig to 250 psig. The evaporator outlet temperature during operation of the bypass shall be from 350°F to 715°F. The superheater bypass shall be used mainly during the startup sequence, hot standby, during the decay heat operation, and during normal and emergency shutdowns.

1.3.1.8 A main steam turbine bypass subsystem shall provide for bypassing the main steam flowing to the turbine from each superheater bank, and dumping it to the flashtank or the condenser. Each bypass shall have a maximum flow capability of 360,000 lb/hr, and shall contain a pressure reducing station to decrease the water (wet startup) or steam pressure from superheater outlet conditions to those existing in the flashtank, with a maximum pressure drop from 2500 psig to 250 psig. The superheater outlet temperature during operation of the bypass shall be from 350°F to 1005°F. An attenuating station shall be provided to reduce the steam temperature from 900°F to 410°F. The main steam turbine bypass is

used mainly during the startup sequence, hot standby, and during sudden load rejections and emergency shutdowns.

1.3.1.9 A reheat steam turbine bypass subsystem shall provide for bypassing the hot reheat steam flowing to the turbine from each reheater bank, and dumping it to the condenser. Each bypass shall have a maximum flow capability of 360,000 lb/hr, and shall contain a pressure reducing station to decrease the steam pressure from reheater outlet conditions to those existing in a common bypass header leading to the condenser, with a maximum pressure from 545 psig to 250 psig. Another pressure reducing station shall decrease the steam pressure from bypass header to approximately 85 psig before entering the condenser. An attenuating station in the bypass header shall reduce the steam temperature from 990°F to 400°F. Another attenuating station shall reduce the steam temperature, before entering the condenser, to approximately 150°F. The reheat steam turbine bypass is used during the startup sequence, hot standby, one loop shutdown and startup, and during sudden load rejections and emergency shutdowns.

1.3.1.10 The flashtank subsystem shall provide for flashing 1,080,000 lb/hr of incoming steam from the superheater bypass and shall operate at pressures up to 600 psig and temperatures up to 500°F. The flashtank shall be provided with an internal moisture separator with a maximum capability of 365,000 lb/hr of steam and a maximum exit moisture of 1%. The flashtank shall receive steam from the auxiliary boilers during the preheat cycle; from the superheater bypass during the startup and decay heat operation and sudden load rejections; and from the main steam turbine bypass during the hot standby period. The flashtank provides steam or water for preheating, for deaerating and feedwater heating and for warming, sealing and initial rolling of the main turbine. It also provides steam to the reheater during hot standby and one loop startup. The flashtank pressure shall be reduced to approximately 250 psig during normal plant operation.

1.3.1.11 The Startup and Shutdown system shall be provided with an auxiliary steam supply with a maximum flow capacity of 150,000 lb/hr at 250 psig and 600°F. The same steam supply shall provide a maximum saturated steam flow of 75,000 lb/hr at 250 psig during the preheating cycle. These flow capacities shall not be concurrent. The auxiliary steam supply is used during the preheating cycle, for operation of the feedwater pump turbine during startup, during hot standby operation, and for plant heating during outage of the nuclear steam supply.

1.3.1.12 The system shall provide for sequential control with manual overrides during preheating, startup, rolling of the turbine to speed, synchronization and initial loading sequence up to approximately 30% of rated steam flow. Shutdown control sequence shall be provided to minimize thermal stresses, to place the system on decay heat operation, and to prepare for subsequent plant startup.

1.3.1.13 During abnormal conditions (load rejections), the pressure at the turbine stop valves may exceed rated pressure briefly by as much as 30%; but the aggregate duration of such brief swings, beyond 105% of rated pressure, shall not exceed 12 hr per 12-month operating period.

1.3.1.14 During abnormal conditions (load rejections), the main steam temperature at each main line to the turbine stop valves shall not be in excess of rated temperature by more than 25°F for not more than 400 hr per 12-month operating period. The main steam temperature shall not exceed 50°F above rated temperature, for swings of 15 minutes duration or less, aggregating not more than 80 hr per 12 month period.

In maintaining the required temperatures during abnormal conditions, differences between the main steam lines, feeding a common valve casing or turbine shell, shall not exceed 75°F for periods aggregating not more than 400 hr per 12-month operating period.

1.3.1.15 During abnormal conditions (load rejections), the reheat temperature shall not exceed the rated value by more than 25°F for not more than 400 hr per 12-month operating period. The reheat temperature shall not exceed 50°F above the rated value for swings of 15 minutes duration or less, aggregating not more than 80 hr per 12-month operating period.

In maintaining the required temperatures during abnormal conditions, differences between the reheat steam lines, feeding a common valve casing or turbine shell, shall not exceed 75°F for periods aggregating not more than 400 hr per 12-month operating period.

1.3.1.16 The system shall provide a controlled steam dump, capable of releasing 5% of turbine valve wide open flow to the atmosphere, which shall be used if the condenser heat sink becomes unavailable to absorb the core decay heat, during reactor physics testing, operator license training, plant ready-hot standby training, and turbine maintenance. The combined half-capacity of the condensate storage and polished water storage tanks provides sufficient feed-water for three days of decay heat rejection to the atmosphere without makeup.

1.3.1.17 The system shall provide for rejection of up to approximately 120 Mwt of decay heat from the evaporator to the condenser, and the required pumps and controls to modulate the flow, temperature and pressure during removal of decay heat.

1.3.2 Environmental Requirements

1.3.2.1 The steam dump and startup system shall be located indoors within the Turbine-Generator Building as described in Reference 7.

1.3.2.2 The system shall be provided with a supply of water of the highest quality consistent with that required by the once-through steam generators and feedwater equipment as indicated in Section 1.3.5.7.

1.3.2.3 The system shall be subject to the operating pressures and temperatures stated in Section 1.3.1.

1.3.2.4 The system shall be subject to transient pressures, temperatures and flows produced by the following normal and emergency operating conditions.*

- 1) Startup preheat from approximately 50°F to 350°F.
- 2) Startup preheat from 350°F to 500°F and pressurization.
- 3) Starting and loading a cold turbine ($\approx 250^\circ\text{F}$).
- 4) Starting and loading a warm turbine ($\approx 400^\circ\text{F}$).
- 5) Starting and loading a hot turbine ($\approx 700^\circ\text{F}$).
- 6) Normal load changes at rates up to + 2% of rated load per minute, in the range from 25% load to the turbine valve wide open condition.
- 7) Refueling shutdowns
- 8) Maintenance shutdowns
- 9) Turbine generator tripouts followed by reactor rundown at maximum rate and operation at 25% of rated thermal power.
- 10) Turbine generator step load reductions
- 11) One loop shutdown and restart
- 12) Spurious reactor trip
- 13) Single control rod drop
- 14) Reactor trip without reduction of normal primary flow.
 - a. One loop abnormal
 - b. Two loops abnormal
- 15) Loss of primary and/or secondary flow
 - a. One primary loop of three
 - b. Three primary loops of three
 - c. Three secondary loops of three
 - d. All primary and secondary loops

*The expected number of cycles during the operating life of the plant is given in Reference 8

- 16) Control rod withdrawal
 - a. One rod, initially at rated power
 - b. One rod, cold restart
 - c. Bank of rods, initially at rated power
- 17) Loss of primary flow without flow rate action or first level of protection.
- 18) Loss of primary and secondary flows and simultaneous failure of setback or rate action.
- 19) Loss of three primary loops and failure of power/flow trip.
- 20) Control rod withdrawal and simultaneous failure of first level of protection (a., b., c. and d. same as item 16).
- 21) Spurious closure of the sodium control valve or valves.
- 22) Superheater, main steam or reheat steam bypass valve or valves fail to open.
- 23) Failure of attemperating stations.
- 24) Failure of flashtank pressure and level controls.
- 25) Spurious opening of the superheater, main steam or reheater bypass valve or valves.

1.3.3 Operational Requirements

1.3.3.1 The steam dump and startup system shall provide for local and remote operation. Remote operation shall be according to a programmed control sequence with manual overrides, and shall be from a central control room for both the nuclear and the steam-electric generation plants.

1.3.3.2 Operation of the system shall be according to the performance requirements in Section 1.3.1.

1.3.3.3 Operation of the system during cold and hot startups shall be according to the typical sequence shown in Figures 6.2.2 and 6.2.3, and according to other sequences to be investigated depending on the cause, nature, and duration of the shutdown.

1.3.3.4 Operation of the system following turbine trip shall permit reactor operation at approximately 25% of rated power.

1.3.3.5 During normal plant operation all the subsystems and components shall be on ready standby operation, that is, at nearly operating temperatures.

1.3.3.6 The system shall provide for periodic on-line operational checks of the main components during normal plant operation.

1.3.4 Safety Requirements

1.3.4.1 The design of the system shall include the necessary features to provide safe performance during all the normal and emergency operating conditions listed in Section 1.3.1, during the 30-year expected plant life. Safe performance shall consist of the prevention of injury to operating and maintenance personnel, the prevention of damage to the system components, and the prevention of harmful environment pollution.

1.3.4.2 The safety features shall include due consideration, but not be limited, by the following design practices.

1) Analytical investigations to determine the maximum pressures, temperatures, flows and loadings experienced during steady-state and transient plant operation. The system and component design conditions, and maximum number of cycles during the plant life, shall be selected accordingly.

2) Selection of materials, design factors of safety, welding procedures, heat treatment and testing procedures according to the applicable industrial Codes and Standards.

3) Determination of the pressure relief and dump system flow capacities, and setpoints, to prevent exceeding the component design conditions, thus ensuring the structural integrity of the system.

4) Determination of the ground conditions and seismic loads at the plant site, for design of the equipment and supports.

1.3.4.3 The steam dump and startup system shall provide for audio and visual alarms to indicate that an operating design parameter is being exceeded, and for the manual and/or automatic means to correct or isolate the fault and for the initiation of load reduction or shutdown.

1.3.4.4 The system shall provide for periodic on-line testing of those components which are used as protective devices, without affecting plant availability.

1.3.4.5 Provisions shall be made during plant construction, for regular inspection at point of manufacture, or at the plant site, of the architectural, electrical, mechanical and structural equipment and materials; in order to ensure their conformity with the applicable industrial Codes, Standards, and local regulations.

1.3.4.6 Capability for reactor decay heat removal shall be provided at all times from either of the three evaporator banks. Decay heat rejection shall be by means of the steam dump to the condenser under normal conditions. Controlled steam dump to the atmosphere or safety relief valve action shall be used if the steam dump system or the condenser heat sink become unavailable.

1.3.4.7 Pressurized feedwater shall be available at all times at the inlet to the evaporators for decay heat removal.

1.3.4.8 The safety design features shall include due consideration, but not be limited, to the following emergency conditions.

- 1) Superheater, main steam or reheat steam bypass valve or valves fail to open.
- 2) Spurious opening of the superheater, main steam or reheater bypass valve or valves.
- 3) Failure or maloperation of attenuating stations.
- 4) Failure or maloperation of the flashtank pressure and level controls.

1.3.4.9 All bypass lines connecting the steam generators and reheaters to the bypass valves shall be designed according to the ASME Code Section III, Class C; including the pressure reducing and blocking valves. The preheat connections shall also be included in this category.

1.3.5 Design Requirements

1.3.5.1 Applicable Codes and Standards

ASME	Boiler and Pressure Vessel Code Section II-Material Specifications Section III-Nuclear Vessels Section VIII-Unfired Pressure Vessels Section IX-Welding Qualifications Power Test Codes
USAS B.31.1 B.16.5	USA Standards Institute, Code for Pressure Piping
ASA C1	National Electric Code
NEMA	National Electrical Manufacturers Association
AWS	American Welding Society
ISA	Instrument Society of America
IEEE	Institute of Electrical and Electronic Engineers

NFPA	National Fire Protection Association
HEI	Heat Exchange Institute Standards
EEI	Edison Electric Institute
HI	Hydraulic Institute
NSC	National Safety Council

1.3.5.2 The structural and material design requirements of the system shall be according to the performance, environmental, availability, maintenance, operational and safety requirements described in the previous sections, and in agreement with the applicable Codes, Standards and local regulations.

1.3.5.3 In the design of the main equipment foundations, the recommendations of the manufacturer shall be followed for loading, deflection limitations, and allowable unit stresses. The manufacturer's recommendations shall also be followed for the thrust and moment limitations at the pipe connections.

1.3.5.4 The system piping design shall be based on engineering and economic considerations; some of which are as follows:

- 1) The ASME Boiler and Pressure Vessel Code and the USA Standards Institute Code for Pressure Piping B31.1.0 shall be followed for material, wall thickness, and general requirements.
- 2) The overall system shall be designed and the equipment located with the piping layout as one of the major major considerations.
- 3) Composite piping layouts shall be made during the early design phase.
- 4) Stress analysis of the main piping systems shall be made using electronic computers to ensure design within the allowable limits, and to obtain minimum piping usage.
- 5) Studies shall be made to establish the most economical fluid velocities, thus establishing the most economical pipe diameters.
- 6) Where possible, butt-welded joints shall be used in preference to flanged fittings, and socket-welded fittings in preference to screwed fittings.

1.3.5.5 Alternate design features, such as bypasses and the use of spares, shall be used whenever justified by engineering, operational and economic considerations.

1.3.5.6 The system design shall meet the overall plant design requirements given in Reference 9.

1.3.5.7 The system shall provide feedwater of the highest quality to the once-through steam generators and feedwater equipment during the startup cycle. Water treatment during startup shall be expected to result in the following feedwater quality.

- 1) Maximum iron concentration, 0.01 ppm,
- 2) Maximum copper concentration, 0.002 ppm,
- 3) Maximum water conductance, 0.5 micro-mho,
- 4) Maximum dissolved solids, 0.05 ppm,
- 5) Maximum dissolved oxygen, 0.007 ppm, and
- 6) Maximum silica content, 0.01 ppm.

2.0 DESCRIPTION OF SYSTEM

A summary description of the Startup and Shutdown system has been given in Section 1.2. The following is a more detailed, but by no means complete, description of the system and its main components. The flow diagram, Figure 6.2.1 shows the main features of the steam dump and startup system.

Each of the three steam dump and startup system bypasses are designed with a flow capability of 15% of the turbine valve wide open flow. This flow results in approximately 30% heat rejection capability from the three heat transfer loops.

2.1 Superheater Bypass

An 8-inch superheater bypass header is provided from each of the three evaporator outlets to the corresponding pressure reducing valves. The six 4 x 8 inch air-piston-operated angle valves are designed to reduce the water or steam pressure from evaporator outlet conditions to those existing in the flashtank. These valves exhaust through a 16-inch common header to the flashtank. A 10-ft straight pipe section with a target plate on a welded tee is used to connect each valve to the common header. A 4-inch bypass is provided around each pressure reducing station for warming the system and for maintaining the flashtank pressure at 250 psig during normal plant operation.

Design data for the superheater bypass subsystem are given in Table 6.1.1.

2.2 Main Steam Turbine Bypass

An 8-inch main steam turbine bypass header is provided from each of the three superheater outlets to the corresponding pressure reducing valves. The 4 x 10-inch air-piston-operated angle valves are designed to reduce the steam pressure from superheater outlet conditions to those existing in the flashtank steam dump header. These valves exhaust to a 20-inch common header which connects to the flashtank steam dump header. A desuperheating station, using feedwater, is designed to reduce the temperature of the steam in the turbine bypass from approximately 900°F to approximately 400°F. A 4-inch bypass is provided around each pressure reducing station for warming the lines during standby and normal plant operation.

Design data for the main steam turbine bypass subsystem are given in Table 6.1.2.

2.3 Reheat Steam Turbine Bypass

A 14-inch reheat steam turbine bypass header is provided from each of the three reheater outlets to the corresponding pressure reducing valves. The 8 x 12-inch air-piston-operated angle valves are designed to reduce the steam pressure from reheater outlet conditions to those existing in the 30-inch common steam header leading to the condenser. Another pressure reducing station with two 18-inch valves is designed to decrease the steam pressure from header to condenser conditions. A desuperheating station, using feedwater, is designed to reduce the temperature of the steam in the reheat steam turbine bypass header from approximately 990°F to 400°F. Another desuperheating station, using condensate water is designed to reduce the steam temperature to approximately 150°F before entering the condenser. Bypasses are provided around each pressure reducing station for warming the lines during standby and normal plant operation.

Design data for the reheat steam turbine bypass subsystem are given in Table 6.1.3.

2.4 Flashtank

The flashtank is a drum-type tank 30 ft long and 60 inches in diameter with 1-1/2 inch walls, designed for operation at 600 psig and 500°F. It contains a steam separator to provide dry steam for turbine startup and rolling. Six 6 x 8-inch safety valves are provided for overpressure protection. The tank is used as storage and source of intermediate pressure steam and water during the preheat, startup and standby operations.

A 10-inch line from the flashtank to the condenser is used as level control and drain. Two 10-inch valves are used for drain and one 2-inch valve is used for level control. A 10-inch line provides pegging water to the deaerator through two 8-inch control valves.

A 24-inch line from the flashtank is used as a steam dump header to the condenser. Two 16-inch pressure reducing valves are provided to decrease the steam pressure from flashtank steam header conditions to those existing in the condenser. A desuperheating station is provided to reduce the steam temperature from approximately 500°F to 150°F. A 20-inch line branches off from the flashtank steam dump header to provide feedwater heating steam to the deaerator and No. 6 headers. A 4-inch line branches off to provide sealing steam to the turbine. The main steam turbine bypass joins the flashtank header forming a common steam dump to the condenser.

A 16-inch line from the flashtank is used to provide steam to the evaporator, superheater and reheater modules during the preheating operation, and to provide steam through the superheaters for rolling the turbine.

The 16-inch superheater bypass line to the flashtank, described in Section 2.1, provides the steam-water mixture to the flashtank during the startup, rolling, decay heat and standby operations.

A 10-inch line provides saturated steam from the auxiliary boilers to the flashtank during the preheat, startup and standby operations.

A 6-inch line provides feedwater to the flashtank during the preheat and startup operations.

Design data for the flashtank subsystem are given in Table 6.1.4.

2.5 Decay Heat Pumps

A feedwater pump and a condensate pump are provided to supply these services during the decay heat operation of the plant. The pumps have sufficient flow capacity to remove 5% of maximum thermal power through the evaporators and are driven by induction motors operating from the vital service AC-power supply. One of the main hotwell pumps and feedwater pumps may be used with recirculation in case of failure of the decay heat pumps.

Design data for the pumps and motors are given in Table 6.1.5.

2.6 Startup Auxiliary Boilers

Two startup auxiliary boilers are provided to supply low pressure saturated steam to the flashtank during the preheat, initial startup, and standby operation of the plant. Steam is also provided from this source for operation of the main feed-water pump turbines and for sealing the main turbine during hot standby operation.

The startup auxiliary boilers are of the "package" design provided with integral fuel, draft and feedwater flow and level controls. Feedwater may be obtained from the main condenser, deaerator, from the demineralized water storage tank, or from the condensate storage tank.

Design data for the startup auxiliary boilers are given in Table 6.1.6.

2.7 Instrumentation (Requirements Only, Instrumentation is not part of this System)

2.7.1 Plant Control

2.7.1.1 Sequential control with manual overrides is provided during preheating, startup, rolling of the turbine to speed, synchronization, initial loading sequence up to approximately 30% of rated power; during standby operation, sudden load rejections and emergency and normal shutdowns. Shutdown control sequences is provided to minimize thermal stresses, to place the system on decay heat operation or hot standby, and to prepare for subsequent plant startup.

2.7.1.2 The control system provides for operation during cold and hot startups according to the typical sequences described in Section 3.0, and according to other sequences to be investigated which depend on the cause, nature, and duration of the shutdown.

2.7.1.3 Flow, pressure, temperature and level are monitored and controlled to obtain the desired heating, pressurization, depressurization, acceleration and loading rates to eliminate shocks or maloperation which may produce early failures of the equipment.

2.7.1.4 During normal plant operation the control system maintains the steam dump and startup system on ready standby operation, that is, at nearly operating temperatures.

2.7.1.5 The control system provides for periodic operational checks of the control loops during normal plant operation.

2.7.1.6 Operation of the control loops during startups, load rejections and tripouts shall be determined by transient analysis.

2.7.2 Plant Protection

2.7.2.1 Flow, pressure, temperature, position and level are monitored at all times to detect maloperation which may produce early failures of the equipment.

2.7.2.2 Audio and visual alarms are provided to indicate that an operating design parameter is being exceeded. Manual and/or automatic action are provided to correct or isolate the fault and for initiation of load reduction or shutdown if necessary.

2.7.2.3 Provisions are made for periodic on-line testing of those components with movable parts, particularly those used as protective devices, without affecting plant availability.

2.8 Piping

Pipe sizes were determined for steady-state conditions using steam velocities ranging from 100 to 150 ft/sec and water velocities ranging from 15 to 20 ft/sec. Thicknesses were determined according to the USASI Code for Pressure Piping.

Table 6.1.7 shows the design conditions and materials used in the piping.

3.0 OPERATION

Operation of the system during typical cold and hot startups is shown in Figures 6.2.2 and 6.2.3. The following sequences outline the operation of the steam dump and startup system during plant startups.

3.1 Cold Startup Sequence (Figure 6.2.2)

1) The auxiliary boilers are started and saturated steam is admitted to the flashtank. The flashtank pressure is held at 30 psig. Condenser vacuum pumps are started.

2) Saturated water at 270°F from the flashtank is admitted to the top of the evaporator modules, collected in the steam generator drains and returned to the main condenser. The superheater throttle valves are closed to prevent water circulation through the austenitic superheaters. Saturated steam from the flashtank is used to heat the steam lines, heaters, deaerators and turbine seals. Steam from the auxiliary boilers at approximately 300°F is circulated through the superheater, reheater modules and main steam lines and returned to the main condenser. The steam generator and main steam piping are thus heated at a constant rate, not exceeding 100°F/hr, from approximately 50°F to 200°F.

3) The main turbine and boiler feed pump turbines are on turning gear and are heated as above to 200°F.

4) The pressure in the flashtank is increased to 250 psig and water at 400°F is circulated through the evaporator modules. The temperature of the superheated steam circulating through the superheater and reheater modules is increased to approximately 450°F. The steam generator and main steam lines are thus heated from approximately 200°F to 350°F. Steam heating of the other lines and system components is continued.

5) The turbine high pressure casing is pressurized to 70 psig and the rotor is heated to approximately 310°F. The reheat portion of the rotor is warmed to approximately the same temperature by admitting steam to a packing in the center of the shaft span and to the seals at the end of the shaft. Prewarming of the turbine rotors with low-temperature steam while on turning gear reduces the mismatch between the metal and the main steam supply temperatures.

6) The deaerator is pegged at approximately 3 psig with steam and water from the flashtank. The No. 6 heaters are pegged at approximately 110 psig with flashtank steam. At the same time, 5% feedwater flow is circulated by means of the condensate and feedwater pumps from the main condenser through the heaters, through the evaporators, flashtank and back to the condenser. Saturated and superheated steam from the auxiliary boilers is used in the flashtank, superheater and reheater modules, main turbine seals, and for the feedwater pump turbines. Heating of the feedwater to 350°F, flushing the system, and condensate demineralization is thus obtained.

7) When the steam generator and feedwater reach 350°F the temperature is held for approximately 15 minutes to permit the steam generator shells to reach a steady state, thus avoiding thermal shocks. Sodium at 350°F is then admitted to the secondary side of steam generators. Condensate demineralization is continued to obtain the required water purity.

8) The superheater throttle valves are then closed and feedwater at approximately 350°F is admitted to the evaporator modules and pressurized to 2500 psig. Superheater bypass is opened to the flashtank.

NOTE: At this time the system condition is as follows:

- a. Feedwater at 350°F and 2500 psig circulating through the evaporators to the flashtank.
- b. Flashtank at approximately 400°F and 250 psig supplying pegging steam to the deaerator and No. 6 heaters, and to the main turbine seals. Drains flowing to condenser.
- c. Steam flowing through the superheaters, reheaters, and turbine bypasses, to the condenser.
- d. Steam lines and main turbine preheated to approximately 300°F.
- e. Sodium at 350°F circulating through the steam generators.
- f. Auxiliary boilers supplying steam to the superheater and reheater modules, flashtank and boiler feed pump turbine.

9) The sodium temperature is then increased at a constant rate not exceeding 100°F/hr and the flashtank is pressurized to 600 psig. The feedwater temperature is maintained at approximately 350°F.

10) When the flashtank temperature reaches 485°F, the reheaters are isolated from the auxiliary boiler and transferred to the turbine steam path. Dry steam from the flashtank is admitted to the superheater modules. The turbine stop-valve bypass and intercent valves are opened to start the turbine rolling from turning gear speed (full-arc admission).

11) The turbine is accelerated to synchronous speed according to the Turbine Startup Charts provided by the manufacturer; which establish the procedures that are to be followed from the time of rolling until initial load is applied. These procedures are based on the mismatch in temperature between the steam supply and the turbine metal prior to rolling. With the steam temperature at 485°F (600 psig) and the metal temperature at 300°F the acceleration rate is approximately 180 rpm/min, without 1000 rpm hold, and with a 20-min hold at 3600 rpm. After synchronization a load of 3% is applied and held for 30 minutes.

12) Before reaching 3600 rpm, the superheater throttle valves are partially opened and the flashtank steam supply is partially closed. The turbine throttle pressure is maintained slightly below the flashtank pressure by bypassing to the condenser if necessary.

13) During the 3% load hold the flashtank valve to the superheater is closed, with simultaneous opening of the superheater throttle valve. Throttle pressure is maintained at approximately 550 psig. The deaerator and No. 6 heaters are transferred to the plant cycle.

14) The superheater bypass is closed and the turbine throttle pressure is increased to 2400 psig, rated pressure, by closing the main steam turbine bypass. The pressure ramp is in accordance to the turbine loading requirements up to 25% load (approximately 1/2% per minute).

15) The startup system is then removed from service, and the plant is transferred to automatic load control.

3.2 Hot Restart (Figure 6.2.3)

(Approximately 3 hrs after tripout from rated load, reactor trip)

1) Prior to the hot restart the plant is placed on a hot standby operation. The turbine is on turning gear. The superheaters are depressurized to approximately 600 psig by means of the main turbine bypass and the superheater throttle valves. The superheater bypass valves to the flashtank are opened and the flashtank is pressurized to 600 psig. The reheaters and superheaters temperature is reduced to approximately 700°F. The feedwater flow is approximately 5% of rated. Steam from the flashtank is used in the deaerator and No. 6 heaters to maintain the feedwater at approximately 350°F, the rest flows to the superheater, reheater and steam lines to maintain the turbine throttle

temperature about 700°F, to the turbine seals and to the feed-water pump turbine. The excess steam and water is dumped to the condenser. The evaporator pressure is maintained at 2500 psig. At this time the reactor is producing approximately 1% thermal power of decay heat.

2) Before rolling the turbine, the reheaters are isolated from the flashtank and transferred to the turbine steam path. The turbine stop-valve bypass, control, and intercept valves are opened to start the turbine rolling from turning gear speed (full-arc admission).

3) The sodium temperature is increased at a constant rate not exceeding 100°F/hr.

4) The turbine is accelerated to synchronous speed according to the Turbine Startup Charts provided by the manufacturer; in a similar manner as that described in Item 11 of Section 3.1, depending on the mismatch in temperature between the steam supply and the turbine metal prior to rolling. With the steam temperature at 700°F and the metal temperature at about 550°F the acceleration is 180 rpm/min with a 15-minute hold at 3600 rpm. After synchronization a load of 3% is applied and held for 30 minutes.

After the initial loading the system operation is similar to that for the cold startup sequence.

3.3 Hot Restart (within approximately 1 hr after turbine trip from rated load)

1) Prior to hot restart the plant is on a hot standby operation, with the reactor generating approximately 25% of rated power. The superheater bypass valves to the flashtank are open and the flashtank is pressurized to approximately 600 psig. The reheater and superheater outlet temperatures are at approximately 890°F. The feedwater flow is approximately 25% of rated. Steam from the flashtank is used in the deaerator and No. 6 heaters to maintain the feedwater at approximately 350°F, the rest flows to the reheater, steam lines and turbine seals. Steam to the flashtank is supplied from the superheater and main steam turbine bypasses during this hot standby operation. Steam from the superheater outlets is supplied to the feedwater pump turbines. The pressure at the superheater outlets is maintained at approximately 2400 psig.

2) The pressure in the reheater is maintained at approximately 200 psig to prevent sodium leakage into the steam system. In order to maintain the superheater and reheater sodium outlet temperatures nearly the same, the turbine intercent valves and the reheater bypass valves are programmed to open and close simultaneously during the startup sequence.

3) The turbine stop-valve bypass, control, and intercent valves are opened to start the turbine rolling from turning gear speed (full-arc admission). The turbine is accelerated to synchronous speed according to the Turbine Startup Charts provided by the manufacturer; in a similar manner as that described in Item 11 of Section 3.1, depending on the mismatch in temperature between the steam supply and the turbine metal prior to rolling. With nearly zero mismatch between these temperatures the acceleration, hold period and initial load are as indicated in Item 4 of Section 3.2. The deaerator and No. 6 heaters are transferred to the plant cycle.

4) The turbine is then loaded in accordance to the turbine loading requirements up to 25% load (approximately 3% per minute). During these periods all the bypass valves are gradually closed as the turbine picks up load. The superheater and reheater outlet temperatures are reset to the rated value.

5) The startup system is then removed from service, and the plant is transferred to automatic load control.

NOTE: The cold and hot startup sequences described previously are typical and are not the only possible. Other startup sequences depend on the previous shutdown sequence, reason and duration of the shutdown, plant loading schedule, steam and metal temperatures before startup.

Investigation and evaluation of the emergency and normal shutdown sequences remain to be done. Steady-state and transient evaluations.

The above sequences need to be correlated with the reactor and heat transfer loop startup requirements to arrive at an overall plant startup program.

4.0 SAFETY CONSIDERATIONS

4.1 Hazards

4.1.1 The following hazardous conditions have been or will be considered in the design of the system and components:

- 1) Superheater, main steam or reheat steam bypass valve or valves fail to open during tripout or load rejection.
- 2) Spurious opening of the superheater, main steam or reheater bypass valve or valves.
- 3) Spurious closure of the superheater throttle valve or valves.
- 4) Failure or maloperation of attemperating stations.
- 5) Failure or maloperation of the flashtank pressure and level controls.
- 6) Failure or maloperation of the condenser steam dump sprays.
- 7) Failure of the decay heat feedwater and/or condensate pumps.
- 8) Flashtank failure
- 9) Bypass pipe failures
- 10) Loss of condenser heat sink.

4.2 Safety Precautions

4.2.1 The system and its components are designed according to the applicable industrial codes and standards, and consistent with practices used in the Electric Utility Industry.

4.2.2 The control and protective systems of the steam dump and startup system are closely integrated with those of the reactor, turbine generator and heat transfer segments, to prevent exceeding the structural limitations of the components during normal and emergency operation.

4.2.3 Audio and visual alarms will be provided to indicate that an operating design parameter is being exceeded. Manual and/or automatic means to correct or isolate the fault will be provided.

4.2.4 Controlled steam dump to the atmosphere and safety relief valve action are used as backup in case of failure of bypass valves.

4.2.5 Bypass valves will be sized so as to minimize the effects of spurious opening of the bypass valves.

4.2.6 Superheater throttle valves will be sized and selected so as to minimize the effects, or prevent, accidental closures.

4.2.7 Design redundancy will be provided to minimize the effects or prevent, failures or maloperation in the following functions:

- 1) Attemperation
- 2) Condenser steam dump cooling sprays
- 3) Flasket pressure and level

4.2.8 Capability for reactor decay heat removal is provided at all times from either of the three evaporator banks. Decay heat rejection is by means of the steam dump to the condenser under normal conditions. Controlled steam dump to the atmosphere or safety relief valve action is used if the steam dump system or the condenser heat sink become unavailable.

4.2.9 Either of the two main feedwater pumps may be used with recirculation in case of failure of the decay heat feedwater pump.

4.2.10 Either of the three main condensate hotwell pumps may be used with recirculation in case of failure of the decay heat feedwater pump.

4.2.11 Treated pressurized feedwater is available at all times at the inlet to the evaporators for decay heat removal.

4.2.12 Block valves are provided to isolate failed components.

4.2.13 Provisions will be made for on-line testing of those components used as protective devices, without affecting plant availability.

5.0 MAINTENANCE

5.1 The arrangement and design of the system is to minimize the time required for maintenance.

5.2 The equipment design features are to provide for minimum service and optimum maintenance time and cost.

5.3 The facilities provided at the plant site will meet the majority of the system maintenance requirements. Routine maintenance is expected to be performed by plant personnel. Overhauls and other major maintenance is expected to be performed by supplemental crews.

5.4 The required maintenance procedures are outlined in the component and subsystem descriptions, and are performed according to the manufacturer's recommendations.

5.5 Component maintenance is performed while the plant is in operation without affecting plant safety, with the backup provided by the controlled dump to the atmosphere and by safety relief valve action. Major maintenance is performed simultaneously with the scheduled maintenance of the major plant equipment. Continuous decay heat rejection capability is always maintained.

5.6 On-line testing of those components used as protective devices is provided to check for proper operation and repeatability at the preset levels. Preventive maintenance will be ascertained on this basis. The components judged to be in this category are the following:

- 1) The pressure reducing valves in the bypass subsystems, which are subject to severe pressure, temperature and flow transients.
- 2) The attenuating stations in the bypass subsystems.
- 3) The pressure relief valves in the auxiliary boilers, flashtank and bypass lines.
- 4) The decay heat feedwater and condensate pumps.

Preventive maintenance of the above equipment does not require plant or heat transfer circuit shutdown. It is performed during plant operation, during refueling or main plant equipment shutdown.

5.7 Maintenance of the auxiliary boilers may be performed during plant operation.

6.0 APPENDICES

6.1 Design Data Tables

- 6.1.1 Superheater Bypass Subsystem
- 6.1.2 Main Steam Turbine Bypass Subsystem
- 6.1.3 Reheat Steam Turbine Bypass Subsystem
- 6.1.4 Flashtank Subsystem
- 6.1.5 Decay Heat Pumps and Motors
- 6.1.6 Startup Auxiliary Boilers
- 6.1.7 Piping
- 6.2 Figures
 - 6.2.1 Startup and Shutdown System Flow Diagram
 - 6.2.2 Cold Startup History
 - 6.2.3 Hot Startup History
- 6.3 References

TABLE 6.1.1

SUPERHEATER BYPASS SUBSYSTEM DATA

Number of bypasses to common header	3
Maximum flow capability, lb/hr (each)	360,000*
Pressure reducing station range, nsig	2800 to 250**
Pressure reducing station inlet temperature range, °F	350 to 715**
Pressure reducing station maximum temperature rate, °F/hr	100**
Pressure reducing station maximum pressurization rate, psi/minute	200**
Maximum flow per valve, lb/hr	120,000*

TABLE 6.1.2

MAIN STEAM TURBINE BYPASS SUBSYSTEM DATA

Number of bypasses to common header	3
Maximum flow capability, lb/hr (each)	360,000*
Pressure reducing station range, nsig	2500 to 250**
Pressure reducing station inlet temperature range, °F	350 to 1005**
Pressure reducing station maximum temperature rate, °F/hr	100**
Pressure reducing station maximum pressurization rate, psi/minute	50**
Maximum flow per valve, lb/hr	90,000*
Desuperheating station temperature range, °F	900 to 410**
Desuperheating station heat load, Btu/hr	2.7×10^8 *

* performance requirement

** performance and environmental requirement

TABLE 6.1.3

REHEAT STEAM TURBINE BYPASS SUBSYSTEM DATA

Number of bypasses to common header	3
Maximum flow capability, lb/hr (each)	360,000*
No. 1 PRS range, psig	545 to 250**
No. 1 PRS inlet temperature range, °F	350 to 1005**
No. 1 PRS maximum temperature rate, °F/hr	~100**
No. 1 PRS maximum pressure rate, psi/min	~25**
No. 1 desuperheater station temperature range, °F	890 to 400**
No. 1 desuperheater station load, Btu/hr	3.4×10^8 *
No. 2 PRS range, psig	250 to 85**
No. 2 PRS inlet temperature range, °F	350 to 400**
No. 2 PRS maximum temperature rate, °F/hr	~100**
No. 2 PRS maximum pressure rate, psi/min	~25**
No. 2 desuperheater station temperature range, °F	400 to 330**
No. 2 desuperheater station load, Btu/hr	2.1×10^7 *

PRS = Pressure Reducing Station

TABLE 6.1.4

FLASH TANK SUBSYSTEM DATA

Flashtank type	drum
Flashtank length, ft	30
Flashtank ID, inch	60
Flashtank wall, inch	1.5
Operating pressure, psig	600**
Operating temperature, °F	490**
Steam separation effectiveness, %	85*
Maximum inflow capability, lb/hr	1,080,000*
Number of pipe connections	7
Number of safety valves (6" x 8")	6
Superheater bypass connection diameter, inch	16
Steam heating connection diameter, inch	16
Steam dump connection diameter, inch	14
Startup boiler connection diameter, inch	10
Feedwater connection diameter, inch	4
Drain connection diameter, inch	10
Drain flow capability, lb/hr (water)	1,080,000*
Steam dump flow capability, lb/hr	1,080,000*
Steam to deaerator, lb/hr	~300,000*
Steam to No. 6 heaters, lb/hr	~540,000*
Steam to turbine seals, lb/hr	~14,000*
Steam to roll turbine, lb/hr (600 psig, 500°F-2"Hg)	~350,000*
Steam dump header capability, lb/hr (after joining with turbine bypass)	1.5×10^6

*performance requirements

**performance and environmental requirements

TABLE 6.1.4 (Cont'd)

PRS range, nsig	600 to 85**
PRS inlet temperature range, °F	350 to 500**
PRS maximum temperature rate, °F/hr	~100**
PRS maximum pressurization rate, psi/min	----**
Desuperheater station temperature range, °F	500 to 330**
Desuperheater station heat load, Btu/hr	2.7x10 ⁷

PRS = Pressure Reducing Station

TABLE 6.1.5

DECAY HEAT PUMPS AND MOTORS DATA

Feedwater Pump

Capacity, lb/hr (gpm)	541,000 (1170)*
Total dynamic head, ft	6,950**
NPSH, ft	~100**
Pump efficiency, %	84
Speed, rpm	6,500
Water temperature, °F	~250**

Feedwater Pump Motor

Shaft horsepower	2,250
Speed, rpm	3,600**
Volts	4,160**

Condensate Pump

Capacity, lb/hr (gpm)	541,000 (1090)*
Total dynamic head, ft	460**
NPSH, ft	hotwell**
Pump efficiency, %	.80
Speed, rpm	1,200
Water temperature, °F	~115**

Condensate Pump Motor

Shaft horsepower	150
Speed, rpm	1,200**
Volts	480**

* performance requirement

** performance and environmental requirement

TABLE 6.1.6

STARTUP AUXILIARY BOILERS DATA

Number of auxiliary boilers	2
Design type	package
Outlet pressure, psig	250**
Outlet saturated steam temperature, °F	400**
Outlet reheated steam temperature, °F	600**
Flow capacity, lb/hr (each boiler)	75,000*
Feedwater temperature, °F	225**

* performance requirement

** performance and environmental requirement

TABLE 6.1.7

PIPING DATA

<u>Service</u>	<u>°F**</u>	<u>psig**</u>	<u>ASTM</u>	<u>Grade</u>
Superheater bypass	715	2800	A106	B
Main steam turbine bypass	1005	2500	A369	FP 22
Main steam turbine bypass	500	600	A106	B
Reheat steam turbine bypass	1005	600	A369	FP 22
Reheat steam turbine bypass	410	250	A106	B
Flashtank steam dump	500	600	A106	B
Flashtank drain	500	600	A106	B

** environmental requirement

6.3

References

1. Engineering Study for Large Steam-Electric Generating Units, Engineers and Constructors Inc., May 1, 1966.
2. Operating Experience at Morgan Creek No. 6 Confirms Once-Through Design, American Power Conference, by Pennebaker and Gorzegno, April 25, 1967.
3. Starting and Operating Once-Through Steam Generators, ASME 65-WA/PWR-11, by C. Stronemeyer, August 2, 1965.
4. Boiler-Turbine Coordination During Startup and Loading of Large Units, ASME 65-WA/PWR-9, by Hanzalck and Insen, August 16, 1965.
5. The Operation of Large Steam Turbines to Limit Cyclic Thermal Cracking, ASME 67-WA/PWR-4, by Timo and Sarney, August 11, 1967.
6. The Paradise Steam Plant, TVA Tech. Report No. 37.
7. Land, Structures and Conventional Systems Segment, SDD-096-90-000.
8. Heat Transfer Segment SDD-096-30-000.
9. Overall System SDD-096-10-000.
10. Control and Instrument Segment SDD-096-50-000.

1000 MWe FBR Plant

Cold Startup History of Pressure & Temperature (Typical)

Fig. 6.2.2

DATE
9/12/68

1000 MWe FBR Plant

Hot Startup History of Pressure & Temperature
(Approximately 3 hrs after tripout from rated load)

(Typical)

Fig. 6.2.3

JWC
6/13/68

ATOMICS INTERNATIONAL*A Division of North American Rockwell Corporation***SUPPORTING DOCUMENT**

NUMBER

SDD-096-80-000

REV
LTR

B

DOCUMENT TYPE

System Design Description

PROGRAM TITLE

ANL 1000 Mwe Follow-on Study

KEY NOUNS

Fuel Handling Support
Equipment

DOCUMENT TITLE

Reactor Support Segment Conceptual System Design
Description - 1000 Mwe LMFBR Follow-on Study

ORIGINAL

ISSUE DATE February 16, 1968

GO NO.

07692

S/A NO.

13120

PAGE 1 OF

TOTAL PAGES

38

REL. DATE

ABSTRACT

Brief Descriptions are given of the equipment, facilities, and operations involved in the receiving and storage of new core elements, in-plant transfers of both old and new core elements, and the preparation of old core elements for shipment. Time estimates are given for the in-plant transfer operations which are done while the reactor is shut down.

PREPARED BY

DATE

DEPT/GRP NO.

J. L. Hedgecock

731-152

APPROVALS

DATE

Suprv'r: J. E. Mahlmeister

Proj. Engr: D. F. Casey

Prog. Off: R. E. Aronstein

SECURITY CLASSIFICATION

(CHECK ONE BOX ONLY)

AEC

DOD

RESTRICTED

UNCL.

☒☐

DATA

☐

CONF.

☐☐

DEFENSE

☐

SECRET

☐☐

INFO.

☐AUTHORIZED
CLASSIFIER

DATE

DISTRIBUTION

REV

SUMMARY OF CHANGE

APPROVALS AND DATE

*

NAME

LOC

* TITLE PAGE ONLY

TABLE OF CONTENTS

	<u>Page</u>
1. INTRODUCTION	5
1.1 Functional Requirements	7
1.2 Summary Description	8
1.3 Requirements	8
1.3.1 Performance Requirements	8
1.3.1.1 Fuel Handling Equipment	8
1.3.1.2 Receiving, Storage, and Shipping Equipment and Facilities	8
1.3.2 Environmental and Endurance Requirements	9
1.3.2.1 External and Internal Environment	9
1.3.2.2 Shipping Cask Internal Environment	10
1.3.2.3 Seismic Conditions	10
1.3.2.4 Endurance Requirements	10
1.3.3 Reliability and Availability Requirements	10
1.3.4 Maintenance Requirements	11
1.3.4.1 Auxiliary Operating Devices	11
1.3.4.2 Parts Replacement	11
1.3.4.3 Decontamination	11
1.3.4.4 Maintenance Facility	11
1.3.5 Operational Interlock Requirements	11
1.3.5.1 Top Shield Rotation	12
1.3.5.2 Floor Valve Operation	12
1.3.5.3 Gantry Motion	12
1.3.5.4 Load Limit	12
1.3.5.5 Collisions	12
1.3.5.6 Grapple Actuation	12
1.3.6 Safety Requirements	12
1.3.6.1 Radiological Release	12
1.3.6.2 General Safety	13
1.3.6.3 Fuel Element Damage Prevention	13
1.3.7 Design Requirements	16
1.3.7.1 Applicable Codes	16
1.3.7.2 Seismic Loading	16
1.3.7.3 Materials	16
1.3.7.4 Flexibility	16
1.3.7.5 Seals	17
1.3.7.6 Package Limits	17
1.3.7.7 Radiation Levels	17
1.3.7.8 Physical Interfaces	17
2. DETAILED EQUIPMENT DESCRIPTIONS	19
2.1 Fuel Handling Equipment	19
2.2 Receiving, Storage, and Shipping Equipment and Facilities	19

Table of Contents (Continued)

	<u>Page</u>
2.2.1 New Fuel Shipping Cask	19
2.2.2 Shipping Cask Transfer Dolly	19
2.2.3 Shipping Cask Loading and Unloading Pit	19
2.2.4 Canister Loading Pit	20
2.2.5 Canister Welding Facility	20
2.2.6 Ex-Vessel Storage Tank	21
2.2.7 Spent Fuel Shipping Cask	21
3. PRINCIPLES OF OPERATION	21
4. SAFETY PRECAUTIONS	22
5. MAINTENANCE	22
6. APPENDICES	24
6.1 Design Data Sheets	25
6.2 Drawings	28

1. INTRODUCTION

The category of equipment and facilities known as the Support Equipment Segment includes a wide variety of systems, facilities, and equipment. For the most part, these systems, facilities, and equipment are involved in various aspects of the fuel handling processes. The following list describes briefly the major subcategories of the Support Equipment Segment:

Fuel Handling Equipment

This category includes the major equipment for handling reactor core elements and other radioactive components, limited purpose transport equipment and interlock systems, remote control equipment, and separate cooling and cleaning equipment.

Special Tools and Service Equipment

This category includes special purpose lifting and handling fixtures, adapting equipment such as shielded gate valves which enable the handling machines to operate at various facilities, special equipment for determining the status of other equipment in inaccessible location such as the reactor vessel, and other general purpose equipment such as portable purging units.

Storage, Cooling, Cleaning, and Inspection

This category includes the facilities and equipment required for the storage, cooling, and cleaning of radioactive core elements and other components outside the reactor vessel. It also includes inspection systems and equipment used for examination of radioactive components without regard for where they are used.

Reactor Plant Maintenance Equipment

This category includes decontamination equipment; equipment, tools, and fixtures used within hot cells; general purpose maintenance facilities and equipment; and special purpose equipment for maintenance operations on components outside the reactor vessel.

Reactor Plant Cranes and Shipping Casks

This category includes general purpose cranes and hoists within the reactor building and reusable shipping containers for core elements.

Miscellaneous Power Plant Equipment

This category includes general purpose cranes and hoists in the turbine plant, compressed air and vacuum systems, power plant furniture and fixtures, communication and alarm systems, fire extinguishing equipment, office furniture and equipment, maintenance

nance shop tools and equipment, scientific and weather instruments, and the turbine plant cooling water system.

Nuclear Fuel Processing and Fabrication Equipment

This category includes special equipment for the processing, fabrication, or reprocessing of fuel for a specific reactor, whether on or off the reactor site.

Scope of this Document

At the present stage of conceptual design only certain selected pieces of equipment and certain facilities have been included as part of the Support Equipment Segment. These are the equipment and facilities which are involved in the receiving, handling, storage, and preparation for shipment of new and spent core elements. It is felt appropriate to defer until a later time the descriptions of the more-or-less conventional equipment and facilities. The facilities and equipment discussed herein:

Fuel Handling Equipment

- a. In-Vessel Fuel Handling Machine
- b. Ex-Vessel Fuel Handling Machine
- c. Auxiliary Handling Machine.
- d. In-Vessel Machine Shielded Gate Valve
- e. Fuel Transfer Port Shielded Gate Valve
- f. Sweep Arm
- g. Canister

Receiving, Storage, and Shipping Equipment and Facilities

- h. New Fuel Shipping Cask
- i. Shipping Cask Transfer Dolly
- j. Shipping Cask Loading and Unloading Pit
- k. Canister Loading Pit
- l. Canister Welding Facility
- m. Ex-Vessel Storage Tank
- n. Spent Fuel Shipping Cask

These equipment and facilities constitute a loosely coupled system of essentially separate and independent entities which, at certain times, operate together with the specific grouping depending on the task to be done.

Items a through g are considered to be "fuel handling equipment" and are described in more detail in SDD-096-81-000, Subassembly Handling. Items h through n are not described further in any document prepared as part of this study, thus brief descriptions of them are included in this document.

In addition to the above mentioned facilities and equipment, important roles in the various fuel handling operations are played by the double rotating shield plugs above the reactor vessel and by the reactor building crane. These, however, have numerous other functions besides their roles in fuel handling and are not usually considered to be "fuel handling equipment" or "support equipment".

1.1 Functional Requirements

A diagram of the entire fuel flow process is given in Figure 1, page 28. This document is concerned with all fuel handling operations within the reactor plant, beginning and terminating at the shipping dock.

The Support Segment equipment and facilities must perform safely all of the core element receiving, handling, storage, and preparation-for-shipment functions from the time that new core elements leave the manufacturer's plant to the time that spent core elements are delivered to the reprocessing or disposal plant. These functions are as follows:

- a. Shipment of new core elements from the manufacturer's plant.
- b. Transfer of new core elements from the shipping vehicle into the reactor plant.
- c. Such inspection and preparation steps as are required to make new core elements ready for placement in the reactor.
- d. Exchanging new and spent core elements between the reactor and the new and spent element storage facility or facilities.
- e. Preparation of spent elements for shipment to the reprocessing plant and loading them into a suitable shipping cask.
- f. Transfer of spent core elements from the reactor plant to a shipping vehicle.
- g. Shipment of the spent core elements to a reprocessing and/or disposal plant or facility.

In addition to the above functions, the Support Segment equipment play important roles in determining the plant safety and availability. Thus, additional general functions include contributing to the plant safety by preventing the spread of radioactivity, preventing inadvertent criticality from developing at any stage in the handling process, and of contributing to a high plant availability by making possible the fast and reliable transfer of core elements.

1.2

Summary Description

The Support Equipment Segment includes all facilities and equipment for core component handling operations within the reactor plant. The operations will be discussed in their normal flow sequence.

The core component will be received in its unirradiated component shipping cask or container. The shipping cask or container will be transferred from the railroad car or motor truck to a cask dolly by a crane. The cask dolly will then be brought into the reactor building through an air lock. The shipping cask or container will be lifted to the vertical position and removed from the cask dolly using the building crane. The shipping cask or container will be lowered into the shipping cask pit.

The shipping cask or container cover will be removed and the core components will be removed individually. Each core component will be inspected and cleaned or tested as required. After the core component has been determined satisfactory for its function in the core it is placed in a canister in the canister loading station. The canister containing the core component is then transferred to the ex-vessel storage facility using the ex-vessel fuel handling machine. The canister is held partially inserted into the ex-vessel storage facility to preheat the core component before allowing sodium to fill the canister. This will minimize thermal shocking of the core component. The sodium in the ex-vessel storage facility will be held at about 350°F.

During reactor refueling periods the unirradiated core components in their canisters are transferred to transfer storage positions in the reactor vessel by the ex-vessel FHM. The unirradiated core components are removed from their canisters and transferred to empty core positions by the in-vessel FHM. Spent core components will be transferred from core positions to empty canisters in the in-vessel transfer storage positions. The canisters containing spent core components are transferred from the in-vessel transfer storage to the ex-vessel storage by the ex-vessel FHM.

The spent core components are held in ex-vessel storage until their decay heat generation rate has been reduced to a level which will allow preparation for shipment. The canisters containing spent core components are then transferred from ex-vessel storage facility to the canister welding station by the ex-vessel FHM. In the canister welding station the canister is capped and seal welded. The canister is then returned to the ex-vessel storage facility by the ex-vessel FHM to await loading into the spent core component shipping cask.

Upon arrival of the spent core component shipping cask it is brought into the reactor building and placed in the shipping cask pit in the same manner as the unirradiated core component shipping cask. The capped canisters containing spent core components are loaded into the shipping cask and solutions are pumped through the cask to remove the sodium from the external surfaces of the canisters. An alternate method of removing the sodium would be to route the canisters through the wash cell prior to loading them in

the shipping cask. The ex-vessel fuel handling machine is used for all canister handling operations between the ex-vessel storage facility and the shipping cask.

The shipping cask is closed and loaded on the cask dolly using the building crane. The external surfaces of the shipping cask are decontaminated and the cask and cask dolly are transferred out of the reactor building through the air lock. The outside crane will transfer the shipping cask from the cask dolly to the shipping conveyance.

The operations of the Support Segment fuel handling equipment and facilities are illustrated by the following operations sequence drawings:

Figure 7, page 34, New Fuel Receiving

Figure 8, page 35, In-Plant Handling

Figure 9, page 36, Spent Fuel Shipping Preparation

The captions on these drawings give a brief summary of the various handling operations that are done. It should be noted that the exchange of core elements between the reactor and the Ex-Vessel Storage Tank (Figure 8, Frames #6 and #7) is done with the reactor shut down or "off-line".

1.3 Requirements

1.3.1 Performance Requirements

The Support Segment equipment and facilities must be able to handle and process core elements at a rate which is commensurate with the reactor consumption rate. For this case, it is estimated that, on the average, about 161.5 core elements (137 fuel elements, 13-14 inner blanket elements, 10-11 outer blanket elements, and 1 control) will be received, exchanged, and prepared for shipment every year. In addition, an average of 23-24 blanket elements are rotated 180° every year during refueling shutdowns. (Control rod absorber columns will probably not be handled every year but the yearly average is used for estimating the number of annual handling operations)

1.3.1.1 Fuel Handling Equipment

Performance requirements for the Fuel Handling Equipment are given in SDD-096-81-000, Subassembly Handling.

1.3.1.2 Receiving, Storage, and Shipping Facilities and Equipment

1.3.1.2.1 New Fuel Shipping Cask

The New Fuel Shipping Cask must perform the function of transporting new core elements with safety to the general public and without damage to the elements themselves.

1.3.1.2.2 Shipping Cask Transfer Dolly

The Shipping Cask Transfer Dolly must perform the function of transporting shipping casks and other equipment between the reactor building and the transport loading and unloading facilities.

1.3.1.2.3 Shipping Cask Loading and Unloading Pit

The Shipping Cask Loading and Unloading Pit must perform the function of supporting the various shipping casks in a vertical position with their tops about flush with the reactor building floor.

1.3.1.2.4 Canister Loading Cell

The Canister Loading Cell performs the function of supporting new empty canisters vertically for loading with new core elements. It also performs the function of establishing an inert gas atmosphere in and around the canister prior to its being picked up by the Ex-vessel Fuel Handling Machine.

1.3.1.2.5 Canister Welding Facility

The Canister Welding Facility must perform the function of welding caps on canisters containing spent core elements prior to their shipment from the reactor plant. The welds must also be leak-checked before the canisters are removed from the Facility.

1.3.1.2.6 Ex-vessel Storage Tank

The Ex-vessel Storage Tank must perform the function of storing new core elements prior to their transfer into the reactor vessel and spent elements after their removal from the reactor vessel. The tank is sized to accommodate only the elements which are handled during the annual refuelings; it will not hold the entire reactor core loading. The coolant system is described in SDD-096-60-000, Auxiliary Systems.

1.3.1.2.7 Spent Fuel Shipping Cask

The Spent Fuel Shipping Cask must perform the function of transporting spent core elements between the reactor plant and the reprocessing plants with safety to the general public and without damage to the elements themselves.

1.3.2 Environmental and Endurance Requirements**1.3.2.1 External and Internal Environment**

With the exception of the shipping casks, all of the Support Segment equipment operates within the reactor building and the adjacent fuel handling and radioactive waste building. Most of the equipment has internal atmospheres of helium gas more or less saturated with sodium vapor and possibly containing appreciable amounts of fission gases released from the fuel elements. Internal pressures are substantially atmospheric. The Ex-vessel Fuel Handling Machine must operate satisfactorily with internal radiation levels of 10,000,000 R/hr or more and heat loads of as much as 60 Kw under normal operating conditions.

1.3.2.2 Shipping Cask External Environment

The shipping casks will be transported by either trucks or rail-road cars, possibly with no protection from the weather. These casks must, then, be designed to withstand sun, rain, snow, dust, etc., in addition to the usual handling and shipping loads and vibrations.

1.3.2.3 Seismic Conditions

All equipment and facilities shall be designed to meet the seismic criteria for Class IA as defined in SDD-096-10-000.

1.3.2.4 Endurance Requirements

In the course of the estimated 30-year life of the reactor, a total of about 5000 core elements will be handled. The initial loading is 412 elements and there will be 29 annual exchanges of about 162 elements each time (paragraph 1.3.1, page 8). On this basis, the number of operating cycles of the various pieces of equipment shall be determined.

1.3.3 Reliability and Availability Requirements

While no hard-and-fast requirements have been established for the fuel handling system, certain goals have been established for the plant unavailability which is attributable to the fuel handling equipment. The scheduled refueling time goal may be calculated from the "theoretical basis" time estimates given in Figure 10, For an average annual refueling shutdown, the time estimates are as follows:

Preparation and restoration steps	37.6 hours
161.5 Core element exchanges @ 1.37 hr	221
23.5 Blanket element rotations @ .3 hr	7.1
Total	265.7 hours

To account for various minor delays in the fuel handling process, an "efficiency" factor of 85% is applied to bring the total hours to $265.7/.85 = 312$; this is the goal for the average annual refueling time. Assuming an annual turbine maintenance period of two weeks (336 hours) the refueling time will not contribute to plant unavailability if this goal is met.

The goal for unscheduled unavailability attributable to failure of the fuel handling equipment is based on failure rate data for past similar equipment and estimates of the improvement that can be expected from future equipment. This goal is .81% plant unavailability. It should be noted that this figure does not include the additional unscheduled unavailability goal of .96% which is attributable to the reactor top shield.

1.3.4 Maintenance Requirements**1.3.4.1 Auxiliary Operating Devices**

To the greatest degree practicable, auxiliary operating means shall be provided for all Support System Segment equipment. Typically such means will consist of hand cranks, electrical overrides, ports in the equipment for the insertion of special tools, etc. These means are required in order that equipment operations can continue on an emergency basis until a convenient time for making the necessary repairs.

1.3.4.2 Parts Replacement

To the greatest extent practicable the equipment and facilities shall be designed for easy replacement of parts which are subject to wear or damage or which have an inherently low reliability. Electrical circuits shall be based largely on the use of plug-in components. Mechanical drives shall generally be located outside of radioactive areas. Access ports shall be provided for equipment that must be located inside radioactive areas. Dynamic seals shall be designed so that it is possible to make replacements without loss or contamination of the inert gas atmospheres inside the various pieces of equipment.

1.3.4.3 Decontamination

All Support Segment equipment and facilities shall be designed for easy cleaning and decontamination. Internal surfaces shall be sloped for good drainage of cleaning solutions. Internal spray nozzles may be used as needed for special requirements. Larger facilities which are subject to low-level contamination shall have man-access ports.

1.3.4.4 Maintenance Facility

A maintenance facility shall be provided which will permit men to work under the various pieces of Support Segment equipment. The facility shall have a deep pit which will permit grapples, tapes, etc., to be extended downward for inspection, cleaning, and repair. Special support structures shall be provided for equipment such as Shielded Gate Valves, the In-Vessel Fuel Handling Machine, the Sweep Arm, and other equipment as required.

1.3.5 Operational Requirements

While the other sections are concerned mainly with measures necessary to prevent damage to fuel elements and the release of radioactivity, this section is concerned mainly with the measures necessary to prevent damage to the fuel handling equipment. These measures consist mainly of various electrical interlocks which insure that the proper sequence of events is followed.

1.3.5.1 Top Shield Rotation

Rotation of the reactor top shield shall not be possible unless the control actuator rods have been separated from the neutron absorber rods and raised to an elevation permitting free motion of the Sweep Arm.

1.3.5.2 Floor Valve Operation

The floor mounted shielded gate valves and the lower end closure valves of the Ex-Vessel Fuel Handling Machine and the Auxiliary Handling Machine shall not be closeable unless the grapples are at a safe elevation with allowance made for items which may be hanging from the grapples.

1.3.5.3 Gantry Motion

The gantry mounted Ex-Vessel and Auxiliary Machines shall not be movable unless the floor-mounted shielded gate valves and the machine lower end closure valves are closed and separated from each other.

1.3.5.4 Load Limit

Variable load limit interlocks shall be provided so that excessive force cannot be applied inadvertently by the hoist mechanisms of any fuel handling machine.

1.3.5.5 Collisions

Interlocks shall be provided so that the gantry mounted equipment cannot collide with the reactor control rod drives or the In-Vessel Fuel Handling Machine.

1.3.5.6 Grapple Actuation

The In-Vessel Fuel Handling Machine grapples shall not be capable of being actuated for latching or releasing except at certain specified elevations where this is required.

1.3.6 Safety Requirements**1.3.6.1 Radiological Release**

The key Safety Requirements which are applicable at a Segment level are those pertaining to the prevention of excessive radiological release. These requirements are, essentially:

- a. Independent emergency backup cooling systems for all fuel handling equipment (and facilities).
- b. Adequate leak-tightness of all equipment and facilities.
- c. Instrumentation for monitoring the temperature of fuel elements to verify that the heat generation rate is within the rated capacities of the equipment.
- d. Double seals throughout.

1.3.6.2 General Safety

1.3.6.2.1 Means shall be provided for visual observation of the exterior of all new core elements before they are taken to the Ex-Vessel Storage Tank. The visual observation shall be for the purpose of checking for obvious shipping damage and for verification of part numbers. Means shall also be provided for conducting air flow tests on new elements to verify that there are no major obstructions to sodium flow through them.

1.3.6.2.2 Temperature controls shall be provided to limit the thermal shock to both new and spent core elements upon removal from or insertion into the large pools of sodium existing in the reactor vessel or the Ex-Vessel Storage Tank.

1.3.6.2.3 Shielding shall be provided on all equipment to limit the direct radiation exposure to safe levels.

1.3.6.2.4 Measures shall be taken to prevent inadvertent criticality from developing at all places where it is possible for fuel to be stored in greater quantities than a single element or for the fuel to attain a more compact configuration as the result of melting, compaction, etc. Criticality shall be prevented by means of suitable combination of neutron-absorbing materials and geometrical arrangement.

1.3.6.2.5 Interlocks and adequate mechanical strength shall be provided to insure that there is no disruption of the primary coolant system containment as a result of either operator error or equipment failure.

1.3.6.2.6 Interlocks shall be provided between the Sweep Arm and the reactor top shield to insure that the Sweep Arm has been rotated across the top of the reactor core thus verifying that all control actuator rods have been disconnected prior to rotation of the shields.

1.3.6.3 Fuel Element Damage Prevention

The Safety Requirements of this section are based primarily on the need to minimize the likelihood of fuel element damage and the release of fission products. Where appropriate, brief explanations are appended describing the way in which the requirement will be met. The absence of an explanation indicates that the requirement can be met in a straightforward manner and without any particular difficulty.

1.3.6.3.1 Requirement

Means shall be provided to clearly identify individual core assemblies, shims, absorbers, and instrumentation to assure that they are properly located within the core.

Method

The lower ends of core components are made with varying lower end diameters which fit into the lower grid plate. In addition the lower ends must simultaneously fit over pins of varying diameters. This arrangement of fits on both the outside and inside of the core elements insures that no element can be improperly placed without the error being detectable either by the In-Vessel Fuel Handling Machine or the Sweep Arm.

1.3.6.3.2 Requirement

Upon completion of core refueling or fuel relocation, capability shall be provided for an independent check to assure that proper placement has been achieved.

Method

The Sweep Arm provides an independent check on the placement of core assemblies. If the arm can be rotated without obstruction this will indicate that each assembly is properly placed, otherwise the assembly would stick up far enough to impede rotation.

1.3.6.3.3 Requirement

When handling of fuel requires that irradiated fuel be lifted out of the sodium coolant into an ex-core fuel handling machine, the fuel must be protected while in the ex-core machine against the effects of overheating by at least two independent means of cooling.

Method

Heat is transferred from the fuel element canister in the Ex-Vessel Fuel Handling Machine by means of combined conduction, convection, and radiation through the inert gas annulus between the canister and the inside "cold" wall of the machine. Forced convection of inert gas within the machine is not required. Two independent cooling systems will be built into the "cold wall" of the machine. Each system will have its own pump, heat exchanger, heater, etc. Two independent air blowers will be used to circulate air on the outside of the "cold" wall of the machine and transfer the heat generated in the shielding to the reactor building atmosphere.

1.3.6.3.4 Requirements

Cooling provisions must be incorporated which will remove the heat from the fuel while being loaded into the ex-core handling machine or being unloaded from the ex-core handling machine if the fuel were to become stuck in the procedure. Such provisions must prevent the release of radio-activity due to fuel overheating.

1.3.6.3.5 Requirement

Both the In-Vessel and Ex-Vessel Fuel Handling Machines must operate reliably at FBR temperature and sodium conditions, including vapor and impurity considerations.

1.3.6.3.6 Requirement

A positive mechanical design must be incorporated into the (in-core) fuel handling machine to eliminate the possibility of handling control rods during the fuel handling sequence.

Method

In order to pick up a control rod housing, the pick-up grapple must be driven lower than required for picking up a fuel element. A physical stop will be provided which will limit the downward travel of the grapple during normal fuel handling operations. The stop will be made so that it is reasonably difficult to remove to reduce the probability of its being accidentally or inadvertently removed.

1.3.6.3.7 Requirement

Design features must be incorporated to accurately and dependably determine the angular and elevation orientation of the fuel handling machine.

1.3.6.3.8 Requirement

The fuel handling machine must be capable of accurately indicating the latched and delatched motion of the grapple.

1.3.6.3.9 Requirement

The in-core fuel handling machine must incorporate an automatic reverse feature in case of a system malfunction, such as an approach to criticality during fuel insertion.

1.3.6.3.10 Requirement

The fuel handling machine must incorporate a rate-limited insertion of fuel elements into the core.

1.3.6.3.11 Requirement

Leak-tightness of the Ex-Vessel Fuel Handling Machine shall be equal to that of the loading face shield.

1.3.6.3.12 Requirement

Means shall be provided on the Ex-Vessel Fuel Handling Machine to permit determination of core element temperatures, either directly or by calibration.

1.3.6.3.13 Requirement

The leak-tightness of the Ex-Vessel Fuel Handling Machine shall consider the conditions of a stuck element and 10CFR20.

1.3.6.3.14 Requirement

The leak-tightness of the Ex-Vessel Fuel Handling Machine shall be based on the conditions involved in handling a ruptured fuel element.

1.3.7 Design Requirements

1.3.7.1 Applicable Codes

The Ex-Vessel Storage Tank shall meet the requirements of the ASME Boiler and Pressure Vessel Code, Section III (Nuclear Vessels), Class A. Other radioactivity-containing equipment shall meet the Class C requirements of the same Code.

1.3.7.2 Seismic Loading

All equipment and facilities shall be designed to meet the seismic criteria for Class IA as defined in SDD-096-10-000.

1.3.7.3 Materials

No hydrogenous or carbonaceous materials shall be used inside any piece of fuel handling equipment with the exception of elastomeric materials used for seals.

1.3.7.4 Flexibility

4

1.3.7.4.1 The Canister Welding Facility shall be designed with sufficient space allowed for the possible later installation of equipment for preparing spent core elements for shipment in an alternate cooling medium.

1.3.7.4.2 No special provisions shall be made to accommodate core elements of a different physical size or larger thermal power rating.

1.3.7.4.3 The Ex-Vessel and Auxiliary Handling Machines shall be designed for use only when the reactor is shut down.

1.3.7.4.4 All equipment and facilities involved in the handling of spent fuel elements shall be capable of handling vented elements.

1.3.7.5 Seals

All seals containing radioactive material shall have at least two sealing members with provisions for either pressurizing or evacuating the space(s) between sealing members.

1.3.7.6 Package Limits

Package limits for shipping have not yet been determined.

1.3.7.7 Radiation Levels

Personnel exposure will be in compliance with 10CFR20. Shielding for fuel handling equipment and facilities shall be based on a general radiation level of 100 mrem/hour at the surface of the shielding. For small local areas and under transient conditions, a level of 500 mrem/hour may be allowed. These figures are based on the relatively short-time exposures that will be incurred during fuel handling operations and the fact that operating personnel will normally be a few feet from most shielding surfaces.

1.3.8 Physical Interfaces

Table 1, page 14, indicates the cases where a physical compatibility must exist between the various pieces of equipment and the facilities. In most cases, the design work has not progressed far enough for the exact interface relationships to be defined in detail.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. . SDD-096-80-000

PAGE . 18

Table 1

Physical Interfaces

This Equipment →

↓
Interfaces with

	In-Vessel Fuel Handling Machine	Ex-Vessel Fuel Handling Machine	Auxiliary Handling Machine	In-Vessel Machine Shielded Gate Valve	Fuel Transfer Port Shielded Gate Valve	Sweep Arm	Canister	New Fuel Shipping Cask	Shipping Cask Transfer Dolly	Shipping Cask Loading and Unloading Pit	Canister Loading Cell	Canister Welding Facility	Ex-Vessel Storage Tank
In-Vessel Fuel Handling Machine			x	x		x							
Ex-Vessel Fuel Handling Machine					x		x				x	x	x
Auxiliary Handling Machine	x			x	x	x					x	x	x
In-Vessel Machine Gate Valve	x		x			x							
Fuel Transfer Port Gate Valve		x	x				x				x	x	x
Sweep Arm			x	x									
Canister		x			x						x	x	x
New Fuel Shipping Cask									x	x			
Shipping Cask Transfer Dolly								x					
Shipping Cask Loading.....Pit								x					
Canister Loading Cell		x	x		x		x						
Canister Welding Facility		x	x		x		x						
Ex-Vessel Storage Tank		x	x		x		x						
Spent Fuel Shipping Cask		x			x		x		x	x			
In-Vessel Machine Storage Area	x		x										
Sweep Arm Storage Area			x			x							
Small Shield Plug Storage Area			x										
Reactor Building Crane			x					x					
Reactor Building Air Lock								x	x				
Maintenance Pit	x	x	x	x	x	x							
Wash Cell	x	x	x	x	x	x							
Control Rod Drive		x	x	x									
Reactor Top Shield	x	x	x	x	x	x	x						
Fuel Element	x						x	x					
Control Rod	x						x	x					
Reactor In-Vessel Storage Rack							x						

(No. of separate and distinct interface pairs = 64)

2. DETAILED EQUIPMENT DESCRIPTIONS

2.1 Fuel Handling Equipment

Detailed descriptions of the various items of fuel handling equipment are given in SDD-096-81-000, Subassembly Handling.

2.2 Receiving, Storage, and Shipping Equipment and Facilities

Since they are not described elsewhere in this series of documents, brief descriptions of the fuel receiving, storage, and shipping facilities and equipment are included below.

2.2.1 New Fuel Shipping Cask

No detailed description of the New Fuel Shipping Cask is possible at the present time since no design work has yet been done. It is expected that the cask will be designed so that it may be stood on end in the Shipping Cask Loading and Unloading Pit with the elements vertical. The cover will be of a design that can be loosened manually and then lifted off remotely with the use of the building crane. An additional supplementary tool will permit the building crane to pick up individual fuel elements and lift them vertically into the reactor building. These operations are illustrated in Figure 7.

2.2.2 Shipping Cask Transfer Dolly

No detailed description of the transfer dolly is possible at the present time since no design work has yet been done. The dolly will have a load capacity of about 100 tons and will be electrically powered. Brakes or self-locking drives will be provided to prevent movement of the dolly during loading or unloading operations. The dolly will have provisions allowing the tilting of the shipping casks from horizontal to vertical and vice versa. The dolly is shown conceptually in Figures 7 and 9.

2.2.3 Shipping Cask Loading and Unloading Pit

No detailed description of the pit is possible at the present time since no design work has yet been done. The pit will be of a suitable depth so that the top end of either the Spent or New Fuel Shipping Casks will be at floor level. Since canisters containing spent fuel elements will be washed in the shipping cask after loading, the pit will have service connections for this purpose. These services will include steam, water, drain lines, dry air, helium, etc. A sketch of the pit is shown in Figures 7 and 9.

2.2.4**Canister Loading Pit**

No detailed description of the pit is possible at the present time since no design work has yet been done. The pit has facilities for evacuation and filling with helium. The upper end has provisions for mounting one of the Fuel Transfer Port Shielded Gate Valves. This valve has more shielding than is required but will serve to close the pit and is of the right height for the Ex-Vessel Fuel Handling Machine to couple to. A conceptual sketch of this pit is shown in Figure 7.

2.2.5**Canister Welding Facility**

The most recent conceptual design drawing of the Canister Welding Facility is shown in Figure 11, page 38. The facility contains two canister stations; one for a sodium-filled canister in which a fuel element is brought to the facility and one for welding caps on shipping canisters. No decision has yet been made regarding which heat transfer medium, sodium, lead, or helium, will be used for shipping spent fuel. The facility contains all the necessary tools and equipment for welding caps on canisters, removing caps from canisters and reworking the weld area, performing leak tests, performing gas flow tests through fuel elements, and external inspection of fuel elements.

An in-cell crane is provided for transferring elements from one canister to another and for general lifting and handling work. Special tools are provided for making and cutting the canister-to-cap weld and for rebuilding and remachining the weld area of a canister from which a cap has been removed. A positioned-manipulator tool is provided for positioning and removing the caps and special tools. A pair of lightweight manipulators is provided for light in-cell maintenance work and for manual assistance in certain in-cell lifting, steadying, and transfer operations. A transfer drawer and glove box is provided for the transfer of small components and tools into and out of the facility. A trash collection canister is provided within the facility; after this canister is full it can be capped and shipped to a solid waste disposal site. A viewing window, and in-cell TV cameras and microphones make it possible for an operator to see and hear what is going on inside the facility. Several sizes of removable plugs are provided in the roof of the facility; the largest plug covers the entire facility and its removal makes it possible to remove the largest piece of in-cell equipment. When the larger roof plugs are removed a high-velocity air ventilation system insures that no radioactive gases or particulate matter will leave the facility through the open ports. Provisions are made for steam cleaning the interior surfaces of the facility.

2.2.6 Ex-Vessel Storage Tank

Figure 5, page 32, shows the latest conceptual design of the Ex-Vessel Storage Tank. The top shield above the tank is stationary and the core elements in canisters are stored in a rotating internal rack (lazy susan). The core elements are stored in concentric circles in the storage rack and one port with a removable shield plug is provided above each of the circles. The internal storage rack is driven and supported by a center shaft which is removable for maintenance work on the seals or drive components. The tank is normally filled with sodium which is cooled and circulated to remove the afterglow heat of the core elements. The cover gas space above the free surface of the sodium is connected to the radioactive gas handling system of the plant. The sodium temperature in the tank may be raised to about 500°F in order to preheat new elements prior to their transfer into the reactor vessel.

2.2.7 Spent Fuel Shipping Cask

A conceptual sketch of the Spent Fuel Shipping Cask is shown in Figures 6 and 9, pages 33 and 36. The cask is made to hold six spent elements, each of which is individually contained in a sealed sodium-filled canister. The cask is loaded while standing vertically in the Cask Loading and Unloading Pit. Canisters are loaded into the cask by the Ex-Vessel Fuel Handling Machine through the rotating turret-type end shield of the cask. The cask incorporates all necessary external connections and internal plumbing for washing the outsides of the canisters after they have been loaded into the cask. During spent fuel shipment, the cask will have an internal helium atmosphere. Heat from the spent fuel elements totalling about 60 Kw is conducted to internal fins in the cask which wrap 240° around each canister, through the cask wall, and ultimately into the air outside the cask. External cooling fins will be used if necessary. The cask weighs about 100 tons.

3. PRINCIPLES OF OPERATION

For the purposes of describing the Principles of Operation, the various steps may be divided into three main groups:

- a. New fuel receiving and storage
- b. Inter-vessel transfers between the reactor and the Ex-Vessel Storage Tank.
- c. Spent fuel preparation for shipping

The basic steps in the operating procedures are described briefly by the captions on the following fuel handling sequence drawings in Appendix 6.2.

Figure 7, New fuel receiving

Figure 8, Inter-vessel transfers

Figure 9, Spent fuel preparation for shipment

A time estimate basis for the total reactor refueling downtime is given in Figure 11. For a semi-annual shutdown during which about 104 core elements are exchanged and about 18 blanket elements are rotated, the time estimate is about 200 hours as given in paragraph 1.3.3.

4. SAFETY PRECAUTIONS

4.1 Hazards

The principal hazards associated with the support equipment are:

- a) Sodium fires
- b) Radioactive gas leakage
- c) Radioactive materials spills

4.2 Precautions

Precautions which should be taken to guard against the above hazards are:

- a) Sodium fire fighting equipment should be located near the areas where sodium may be exposed to air and personnel should be trained and periodically tested in its use.
- b) The possibility of radioactive gas leakage into undesired areas can be minimized by regular replacement of gas seals and by maintenance of proper pressure differentials between operating areas.
- c) Radioactive material spills should be cleaned up immediately, to prevent contamination of wider area.

5. MAINTENANCE

5.1 Normal/Routine Maintenance

A regular maintenance program should be instituted and strictly adhered to. Mechanical equipment should be regularly inspected, especially for possible failures that could result in a difficult recovery problem. Careful checks should be made for accumulations of sodium or sodium "frost" that might cause binding or seizing of moving parts. Steel tapes should be regularly inspected for nicks and scratches that might be the source of a crack. Regular measurements of actuating force should be made so that incipient seizures can be detected and corrected. An especially important maintenance operation is the regular inspection of seals. All seals are made with two sealing members, such as O-rings, with provision for pressurizing the space between the sealing members. Regular checks should be made for any radioactivity leaking through the seals and regular measurements should be made of the gas flow resulting when the space between the sealing members is pressurized.

5.2**Unusual Maintenance**

The internal storage rack of the ex-vessel storage tank may have to be removed from the tank if it should become damaged. This can be accomplished as follows:

- a) Remove all fuel elements from the ex-vessel storage tank
- b) Drain sodium from the tank
- c) Fill tank with argon gas
- d) Lower turntable onto maintenance support surface and unlock turntable center shaft
- e) Remove turntable shaft and cover opening with a temporary cover
- f) Remove rotating shield plug into a plastic tent
- g) Remove turntable and cover ex-vessel storage tank with a temporary cover
- h) Replace turntable following reverse sequence.

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

NO. . SDD-096-80-000
PAGE . 24

6. APPENDICES

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

NO. .
PAGE .

SDD-096-80-000
25

6.1 Design Data Sheets

PREPARED BY: J. L. Hedgecock				APPROVED BY:		DESIGN DATA SHEET		TITLE: Fuel Handling Equipment - Support Equipment Segment	
LINE NO.	REVISION			ITEM	DESIGN POINT	REMARKS			
	NO.	DATE	NEW REV						
1.				Reactor condition during:					
2.				In-vessel fuel transfers	shutdown				
3.				Reactor-to-storage-tank transfers	shutdown				
4.				All other fuel handling operations	operating				
5.									
6.				Components handled annually (Average)					
7.				Fuel elements exchanged	137				
8.				Inner blanket elements exchanged	11.2				
9.				Outer blanket elements exchanged	10.3				
10.				Control rods exchanged	1				
11.				Total elements exchanged	159.5				
12.				Blanket elements rotated 180°	21.5				
13.									
14.				Equipment and facilities required					
15.				In-Vessel Fuel Handling Machine	1				
16.				Ex-Vessel Fuel Handling Machine	1				
17.				Auxiliary Handling Machine	1				
18.				In-Vessel Machine Shielded Gate Valve	4				
19.				Fuel Transfer Port Shielded Gate Valve	2				
20.				Sweep Arm	1				
21.				Canister (disposable)	160 per year				
22.				New Fuel Shipping Cask	to be determined				
23.				Shipping Cask Transfer Dolly	1				
24.				Shipping Cask Loading and Unloading Pit	1				
25.				Canister Loading Pit	1				
26.				Canister Welding Facility	1				
27.				Ex-Vessel Storage Tank	1				
28.				Spent Fuel Shipping Cask	to be determined				
29.									
30.				Unavailability goals (fuel handl. equip. only)		(Annual refueling period to			
31.				Scheduled refueling unavailability	0%	be masked by annual			
32.				Unscheduled unavailability	.81%	turbine maint.)			
33.				Total	.81%				
34.									
35.				Basic radiation levels at shield surface					
36.				Short time general exposures during handling	100 mrem/hour				
37.				Local & transient exposures during handling	500 mrem/hour				
38.				Long term exposure during storage	1.25 mrem/hour				

NUMBER

REVISION LETTER

PAGE 26

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

SDD-096-80-000

6.2**Drawings**

No single drawing can show the entire Support Equipment Segment. Thus, drawings have been included here which will show, conceptually at least, the principal features of each of the pieces of equipment and facilities referred to in this document. For more detailed drawings of the fuel handling equipment, please see Reference 1.

FIGURE 1

0 1 2 3 4 5 6
SCALE-FT

ATOMIC INTERNATIONAL			
A DIVISION OF ATOMIC INTERNATIONAL, INC.			
1000 HWY. 100, SUITE 100, FORT WORTH, TEXAS 76104			
GANTRY EQUIPMENT			
1000 MW LMFBR FOLLOW-ON STUDY			
DATE	2/20/82	FILE	CONFIDENTIAL
BY	J. SURE	DATE	2/20/82
REVISION		DATE

1

THE NEW FUEL SHIPPING CASK IS TRANSFERRED FROM THE RAILROAD CAR TO THE CASK DOLLY BY THE RAILYARD CRANE. IT THEN ENTERS THE BUILDING ON THE DOLLY THROUGH THE AIR LOCK.

2

THE SHIPPING CASK IS REMOVED FROM THE CASK DOLLY AND INSTALLED IN ITS PIT BY THE BUILDING CRANE. A FLOOR VALVE IS PLACED OVER THE CANISTER LOADING PIT AND A NEW CANISTER IS PLACED IN THE PIT BY THE BUILDING CRANE.

3

AS A NEW FUEL ELEMENT IS TRANSFERRED FROM THE SHIPPING CASK TO A CANISTER, IT IS VISUALLY INSPECTED. AFTER THE ELEMENT IS IN THE CANISTER, THE CANISTER LOADING PIT IS EVACUATED AND FILLED WITH HELIUM. AN INTERMEDIATE STATION WILL BE USED WHEN FLOW TESTING IS REQUIRED.

4

THE EX-VESSEL FUEL HANDLING MACHINE TRANSFERS THE CANISTERED FUEL INTO THE EX-VESSEL STORAGE TANK.

1
THE REACTOR SAFETY CAP IS REMOVED WITH THE BUILDING CRANE.

2
FLOOR VALVES ARE INSTALLED WITH THE BUILDING CRANE.

3
SHIELD PLUGS ARE REMOVED WITH THE AUXILIARY HANDLING MACHINE.

4
THE LOWER PART OF THE IN-VESSEL FUEL HANDLING MACHINE IS INSTALLED WITH THE AUXILIARY HANDLING MACHINE.

5
THE UPPER PART OF THE IN-VESSEL FUEL HANDLING MACHINE IS INSTALLED WITH THE BUILDING CRANE.

6
THE IN-VESSEL FUEL HANDLING MACHINE OPERATES WHILE THE EX-VESSEL FUEL HANDLING MACHINE IS AT THE EX-VESSEL STORAGE TANK.

7
THE IN-VESSEL FUEL HANDLING MACHINE IS IDLE WHILE THE EX-VESSEL FUEL HANDLING MACHINE IS AT THE REACTOR.

NOTES:

1. ALL FUEL TRANSFER OPERATIONS ARE DONE WHEN THE REACTOR IS SHUT DOWN.
2. FUEL TRANSFERS WITHIN THE REACTOR VESSEL ARE MADE WITH THE IN-VESSEL FUEL HANDLING MACHINE.
3. INTER-VESSEL FUEL TRANSFERS ARE MADE WITH THE EX-VESSEL FUEL HANDLING MACHINE.
4. ALL HANDLING OPERATIONS WITH THE EX-VESSEL MACHINE ARE DONE WITH ELEMENTS CONTAINED IN CANISTERS

RESUME
FULL POWER
OPERATION

REACTOR SHUTDOWN		PREPARATION STEPS TIME ESTIMATE: 11.9 HR.				BLANKET ELEMENT ROTATION TIME ESTIMATE: .3 HR./ELEM.	TRANSITION STEPS TIME EST.: .3 HR.	BASIC CYCLE TIME ESTIMATE: 1.37 HR./ELEMENT		BASIC CYCLE TIME ESTIMATE: 1.37 HR./ELEMENT		TRANSITION STEPS TIME ESTIMATE: .7 HR.		TERMINATION STEPS TIME ESTIMATE: 25.7 HR.				
REACTOR	COOL REACTOR TO 500°F (510°F @ 100°F/HR.) TIME = 5.6 HR.																	BRING REACTOR TO TEMP @ 25% POWER (510°F @ 100°F/HR.) - 5.6 HR. MEAS. POWER COEF. @ 25% 150% POWER - 17 HR. INCREASE POWER, 25% TO 100% - .7 HR. TIME = 8.0 HR.
CONTROL RODS & SWEEP ARM	PERFORM ROD DROP TESTS (15 @ 10 MIN.) 2.5 HR. DISCONNECT CONTROL RODS (15 @ 6 MIN.) 1.5 HR. ROTATE SWEEP ARM — TIME = 4.0 HR.													ROTATE SWEEP ARM — RE-CONNECT CONTROL RODS (15 @ 6 MIN.) 1.5 HR. PERFORM ROD DROP TESTS (15 @ 10 MIN.) 2.5 HR. TIME 4.0 HR.		INSTRUMENTATION CHECKOUT 8.0 HR.		BRING REACTOR TO CRITICALITY - 1.5 HR. PARTIALLY CALI- BRATE CONTROL ROD(S) - 1.0 HR. TIME = 2.5 HR.
BUILDING CRANE	REMOVE REACTOR CAP TIME = 4.0 HR.	SET 2 FLOOR VALVES IN PLACE AT REACTOR. TIME = 2.0 HR.		INSTALL TOP SECTION OF IN-VESEL FUEL HANDLING MACHINE. TIME 4.1 HR.									REMOVE TOP SECTION OF IN- VESEL FUEL HANDLING MACHINE. TIME 4.1 HR.		REMOVE 2 ROD VALVES FROM REACTOR TOP SHIELD TIME = 1.0 HR.	INSTALL REACTOR CAP. TIME = 8.3 HR.		
AUXILIARY HANDLING MACHINE			REMOVE SHIELD PLUG. INSTALL LOWER SECTION OF IN-VESEL FUEL HANDLING MACHINE. TIME = 1.8 HR.	REMOVE 3 INSTRU- MENTATION PORT SHIELD PLUGS. INSTALL 3 IN-VESEL INSTRUMENTS. REMOVE FUEL PORT SHIELD PLUG TIME = 4.1 HR.									REPLACE FUEL PORT SHIELD PLUG. REMOVE 3 IN-VESEL INSTRUMENTS. REPLACE 3 INSTRU- MENTATION PORT SHIELD PLUGS. TIME = 4.1 HR.	REMOVE LOWER SECTION OF IN- VESEL FUEL HANDLING MACHINE. REPLACE SHIELD PLUG. TIME = 1.8 HR.				
IN-VESEL FUEL HANDLING MACHINE					RAISE ELEMENT ROTATE ELEMENT LOWER ELEMENT TIME = 19 MIN./ELEM.	TRANSFER OLD FUEL FROM CORE TO STORAGE TIME = 18 MIN.	TRANSFER NEW FUEL FROM STORAGE TO CORE TRANSFER OLD FUEL FROM CORE TO STORAGE TIME = 40 MIN.	TRANSFER NEW FUEL FROM STORAGE TO CORE TRANSFER OLD FUEL FROM CORE TO STORAGE TIME = 40 MIN.	TRANSFER NEW FUEL FROM STORAGE TO CORE.									
EX-VESEL FUEL HANDLING MACHINE					AT STORAGE: — — PICK UP NEW FUEL TIME = 17 MIN.	AT REACTOR: PUT DOWN NEW FUEL RE-INDEX PICK UP OLD FUEL TIME = 42 MIN.	AT STORAGE: PUT DOWN OLD FUEL RE-INDEX PICK UP NEW FUEL TIME = 34 MIN.	AT REACTOR: PUT DOWN NEW FUEL RE-INDEX PICK UP OLD FUEL TIME = 42 MIN.	AT STORAGE: PUT DOWN OLD FUEL RE-INDEX PICK UP NEW FUEL TIME = 34 MIN.	AT REACTOR: PUT DOWN NEW FUEL TIME = 21 MIN.								
MAXIMUM OF OPERATION TIMES	4.0 HR.	2.0 HR.	1.8 HR.	4.1 HR.	19 MIN./ELEM.	18 MIN.	42 MIN./ELEM.	40 MIN./ELEM.	42 MIN./ELEM.	40 MIN./ELEM.	21 MIN.	22 MIN.	4.1 HR.	1.8 HR.	1.0 HR.	8.3 HR.	2.5 HR.	8.0 HR.

TIME SUMMARY

$$TIME = 31.6 + 1.37N_E + .3N_R + 11N_V \text{ (HOURS)}$$

WHERE:

N_E = NO. OF ELEMENTS EXCHANGED
 N_R = NO. OF ELEMENTS ROTATED
 N_V = NO. OF TIMES FLOOR VALVE
IS MOVED.

NOTES:

1. TIMES SHOWN DO NOT INCLUDE
AN ALLOWANCE FOR "CURING"
OR "SINTERING" NEW FUEL
ELEMENTS.

ATOMICS INTERNATIONAL*A Division of North American Rockwell Corporation***SUPPORTING DOCUMENT**

NUMBER

SDD-096-81-000

REV
LTR

DOCUMENT TYPE

System Design Description

PROGRAM TITLE

ANL 1000 Mwe Follow-on Study

KEY NOUNS

Fuel Handling

DOCUMENT TITLE

Subassembly Handling Conceptual System Design
Description - 1000 Mwe LMFBR Follow-on StudyORIGINAL
ISSUE DATE

Feb. 26, 1969

GO NO.

07692

S/A NO.

13140

PAGE 1 OF

TOTAL PAGES 56

REL. DATE

ABSTRACT

Brief descriptions are given of the equipment, facilities, and operations involved in the receiving and storage of new core subassemblies, in-plant transfers of both old and new core subassemblies, and the preparation of old core subassemblies for shipment. A time estimate is given for the annual in-plant transfer operations of 312 hours. The scheduled unavailability attributable to refueling is estimated at be 0.0% assuming that an annual turbine maintenance shutdown will mask out the refueling shutdown.

PREPARED BY

DATE

DEPT/GRP NO.

J. R. Faitel

731-152

APPROVALS

DATE

Superv: J. E. Mahlmeister

Proj. Engr: D. F. Casey

Prog. Off: R. E. Aronstein

SECURITY CLASSIFICATION

(CHECK ONE BOX ONLY)

(CHECK ONE BOX ONLY)

AEC

DOD

RESTRICTED

UNCL.

☒☐

DATA

☐

CONF.

☐☐

DEFENSE

☐

SECRET

☐☐

INFO.

☐AUTHORIZED
CLASSIFIER

DATE

DISTRIBUTION

REV

SUMMARY OF CHANGE

APPROVALS AND DATE

*

NAME

LOC

★ TITLE PAGE ONLY

TABLE OF CONTENTS

	<u>Page</u>
1. INTRODUCTION	4
1.1 Functional Requirements	4
1.1.1 Overall System	4
1.1.2 In-Vessel Fuel Handling Machine Functions	9
1.1.3 Ex-Vessel Fuel Handling Machine Functions	9
1.1.4 Auxiliary Handling Machine Functions	10
1.1.5 In-Vessel Machine Shielded Gate Valve Functions	10
1.1.6 Fuel Transfer Port Shielded Gate Valve Functions	11
1.1.7 Sweep Arm Functions	11
1.1.8 Canister Functions	11
1.2 Summary Description of the In-Plant Handling System	11
1.2.1 Handling Operations	11
1.2.2 Handling Time Estimate	11
1.3 Requirements	12
1.3.1 Performance Requirements	12
1.3.2 Environment Requirements	15
1.3.3 Reliability and Availability Requirements	18
1.3.4 Maintenance Requirements	18
1.3.5 Instrumentation Requirements	19
1.3.6 Safety Requirements	20
1.3.7 Design Requirements	21
1.3.8 Interface Requirements	24
2. DETAILED EQUIPMENT DESCRIPTION	25
2.1 In-Vessel Fuel Handling Machine	25
2.1.1 Design Drawing	25
2.1.2 Overall Configuration and Installation	25
2.1.3 Grapple and Grapple Actuator	25
2.1.4 Grapple Vertical Drive	26
2.1.5 Guide Tube Vertical and Rotation Drive	26
2.1.6 Fuel Element Orientation	27
2.1.7 Shielding	27
2.2 Ex-Vessel Fuel Handling Machine	27
2.2.1 Design Drawings	27
2.2.2 Overall Configuration	27
2.2.3 Gantry	27
2.2.4 Hoist Mechanism	28
2.2.5 Grapple	28
2.2.6 Grapple Tapes, Scrapers, and Seals	28
2.2.7 Cooling System	28

Table of Contents (Continued)

	<u>Page</u>
2.2.8 Lower End Closure Valve	29
2.2.9 Shielding	29
2.3 Auxiliary Handling Machine	29
2.4 Shielded Gate Valves	30
2.5 Sweep Arm	30
2.6 Canister	31
3. OPERATING PROCEDURES	31
3.1 Initial Preparation Steps	31
3.2 Initial Fuel Handling Transition Step	32
3.3 Basic Fuel Transfer Cycle	32
3.4 Blanket Element Rotation	32
3.5 Final Fuel Handling Transition Steps	32
3.6 Final Restoration Steps	33
3.7 Reactor Startup Operations	33
3.8 Shutdown Time Summary	33
4. SAFETY PRECAUTIONS	35
5. MAINTENANCE	36
6. APPENDICES	38
6.1 Design Data Sheets	39
6.2 Drawings	46

1. INTRODUCTION

This description of the in-plant fuel handling system is limited to the operations and equipment involved in the transfer of fuel elements and other core components between the reactor core and the ex-vessel storage tank. A conceptual flow diagram for the entire fuel cycle is shown in Figure 1, page 56. This document is concerned only with the first three fuel stations (rectangles) and the first two handling means (ovals) shown on this diagram.

The rotating top shields above the reactor and the ex-vessel storage tank play important parts in the fuel handling process. Nevertheless, they are not ordinarily included as part of the "fuel handling equipment", this term is reserved for items which are more portable or mobile. For the remainder of this document the term "fuel handling equipment" shall be defined as including only the following specific pieces of equipment:

1. In-vessel fuel handling machine
2. Ex-vessel fuel handling machine
3. Auxiliary handling machine
4. In-vessel machine shielded gate valve (2 required)
5. Fuel transfer port shielded gate valve (2 required)
6. Sweep arm
7. Canister

This list of equipment is probably not all-inclusive. Undoubtedly, as the design work progresses, additional items will be added. It is expected, however, that the additional items will be only relatively minor items such as lifting fixtures, alignment devices, special tools, etc.

1.1 Functional Requirements

1.1.1 Overall System

For the overall array of fuel handling equipment, the functional requirements are that they (the pieces of equipment) make possible the safe, reliable, and economical transfer of fuel elements and other core components within the reactor building. Table 1, pages 6, 7, 8, and 9 summarize some of the basic data about the items handled.

In addition, the fuel handling equipment may be called upon to perform certain maintenance and recovery-from-accident functions both within the reactor vessel and elsewhere should the need arise. Such possible functions are so varied and diverse that they cannot be defined at this time.

In the following paragraphs the main functional requirements of each specific piece of fuel handling equipment are briefly described.

Table 1. Items which may be handled by the Fuel Handling Equipment

ITEM HANDLED	APPROXIMATE OVERALL SIZE	WHEN HANDLED	HANDLING EQUIP.	THERMAL PWR, KW	RADIOACTIVITY
New empty canister	8 in. O.D.; 16 ft. long	During reactor operation	Building crane with pickup tool	none	none
New fuel element	6 $\frac{1}{2}$ in. O.D.; 15 ft. long	"	"	.16	At surface: gamma: 5.6 R/hr. neut.: .23 Rem/hr.
New blanket element	"	"	"	none	none
New control rod	"	"	"	none	none
New source element	"	"	to be determined	to be determined	
New canister with new fuel element	8 in. O.D. 16 ft. long	"	Ex-Vessel F.H.M.	.16	At surface: gamma: 2.8 R/hr. neut: .23 Rem/hr.
New canister with new blanket element	"	"	"	none	none
New canister with new control rod	"	"	"	none	none
New canister with new source element	"	"	"	to be determined

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

Table 1 (Continued)
Items which may be handled by the Fuel Handling Equipment

ITEM HANDLED	APPROXIMATE OVERALL SIZE	WHEN HANDLED	HANDLING EQUIP	THERMAL PWR, KW	RADIOACTIVITY
New canister with new fuel element and storage tank sodium	8 in. O.D.: 16 ft. long	During refueling shutdowns	Ex-Vessel F.H.M.	.16	At surface: gamma: 2.8 R/hr neut.: .23 Rem/hr.
New canister with new blanket element and storage tank sodium	"	"	"	none	none
New canister with new control rod and storage tank sodium	"	"	"	none	none
New canister with new source element and storage tank sodium	"	"	"	to be determined	
Old canister with old fuel element and reactor sodium	"	2 months after removal from core;	"	7.5 (ave)	At 4" from canister surface: 5.3×10^5 R/hr
Same as above.	"	6 hr. after shutdown	"	75 (ave)*	3,700,000 R/hr at 4" from element surface
Old canister with old blanket element and reactor sodium	"	"	"	25 max. (inner blanket)	At 4" from canister surface: 1,300,000 R/hr.
* Removal sequence will be established to limit decay heat generation to a maximum of 60 kw at time element is handled.

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

Table 1 (Continued)
Items which may be handled by the Fuel Handling Equipment

ITEM HANDLED	APPROXIMATE OVERALL SIZE	WHEN HANDLED	HANDLING EQUIP	THERMAL PWR, KW	RADIOACTIVITY
Old canister with old control rod and reactor sodium	8 in. O.D.; 16 ft. long	6 months after removal from core; 6 hr. after shutdown	Ex-Vessel F.H.M.	19	Ave. curies/ft. of Ta^{182} : 1,300,000
Old canister with old source element and reactor sodium	"	"	"	to be determined	
New fuel element	6 $\frac{1}{4}$ in. O.D.; 16 ft. long	During refueling shutdowns	In-Vessel F.H.M.	.16	At surface: gamma: 5.6 R/hr. neut: .23 Rem/hr.
New blanket element	"	"	"	none	none
New control rod	"	"	"	none	none
New source element	"	"	"	to be determined	
Old fuel element	"	6 hr. after shutdown	"	75 (ave)	At 4" from surface: 3,700,000 R/hr.
Old blanket element	"	"	"	25 max. (inner blanket)	At 4" from canister surface 1,300,000 R/Hr

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

NO. SDD-096-81-000
PAGE 7

Table 1 (Continued)
Items which may be handled by the fuel handling equipment

ITEM HANDLED	APPROXIMATE OVERALL SIZE	WHEN HANDLED	HANDLING EQUIP	THERMAL PWR, KW	RADIOACTIVITY
Old control rod	6 $\frac{1}{4}$ in. O.D.; 16 ft. long	6 hr. after shutdown	In-Vessel F.H.M.	58	Ave. curies/ft. of Ta ¹⁸² : 4,000,000
Old source element	"	"	"	to be determined	
Reactor top shield plugs	10 in. O.D.; 11 ft. long	Immediately after shutdown	Auxiliary H.M.	to be determined	
Reactor top shield plugs	"	After completion of refueling	"	to be determined	
In-Vessel F.H.M. (lower section)	10 in. O.D.; 36 ft. long	During refueling shutdowns	"	none	none
In-vessel F.H.M. (lower section)	"	After completion of refueling	"	to be determined	
Sweep arm	10 in. O.D.; 28 ft. long	Immediately after shutdown	"	to be determined	
Nuclear instrument	"	After completion of refueling	"	to be determined	
Old control rod actuator rod	"	Immediately after shutdown	"	to be determined

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

1.1.2 In-Vessel Fuel Handling Machine Functions

1.1.2.1 To raise core components from the reactor core into the sodium pool above, rotate them as required and lower them back into the same core position, or after horizontal motion resulting from the rotation of the reactor top shield plugs, lower them into another core position or into the canisters in the in-vessel transfer positions.

1.1.2.2 To raise core components from canisters in the in-vessel transfer positions into the sodium pool above, and, after horizontal motion resulting from the rotation of the reactor top shield plugs, lower them into another canister or into the reactor core.

1.1.2.3 To provide adequate shielding against radiation originating within the reactor vessel or from radioactive sodium, gases, fission products, or other material which may get up into the body of the machine.

1.1.2.4 To prevent contamination of and contain the reactor atmosphere under reactor-shutdown conditions.

1.1.2.5 To insure the proper placement of core components by means of an interlock system which will prevent release if the component is not properly installed.

1.1.3 Ex-Vessel Fuel Handling Machine Functions

1.1.3.1 To move fuel elements and other core components vertically in and out of itself and other facilities and ports. Such facilities and ports include at least the following:

1. Reactor in-vessel transfer positions
2. Ex-vessel storage tank
3. New fuel receiving facility
4. Spent fuel canister welding facility
5. Spent fuel shipping cask loading facility

1.1.3.2 To transport fuel elements and other core components among the various facilities and ports mentioned above.

1.1.3.3 To provide adequate cooling for core elements handled.

1.1.3.4 To contain and prevent contamination of the reactor vessel atmosphere under reactor-shutdown conditions.

1.1.3.5 To contain and prevent contamination of the atmospheres of all other facilities and ports at which the machine may be located.

1.1.3.6 To provide adequate shielding against radiation originating within itself, the reactor vessel, or any other facility or port at which the machine may be located.

1.1.4 Auxiliary Handling Machine Functions

1.1.4.1 To remove and replace various shield plugs including the following:

1. In-Vessel Fuel Handling Machine port plug
2. Reactor vessel fuel transfer port plugs
3. Spent fuel shipping cask loading port plug
4. Spent fuel canning facility port plug
5. Ex-vessel storage tank port plugs

1.1.4.2 To install and remove the reactor sweep arm assembly.

1.1.4.3 To remove and install a control rod drive extension assembly.

1.1.4.4 To install and remove the lower portion of the In-Vessel Fuel Handling Machine.

1.1.4.5 To provide adequate shielding against radiation originating within itself, the reactor vessel, or any other facility or port at which the machine may be located.

1.1.4.6 To contain and prevent contamination of the reactor vessel atmosphere when the reactor is shut down.

1.1.4.7 To contain and prevent contamination of the atmospheres of all other facilities and ports at which the machine may be located.

1.1.5 In-Vessel Machine Shielded Gate Valve Functions

1.1.5.1 To provide, when closed, adequate shielding against radiation within the reactor vessel during shutdown conditions or within the valve body.

1.1.5.2 To provide, when open, adequate shielding against radiation originating within the reactor vessel during shutdown conditions, within the valve body, within the Auxiliary Handling Machine when coupled to the valve, or from the In-Vessel Fuel Handling Machine when it passes through the valve.

1.1.5.3 To prevent contamination of and contain the reactor atmosphere during reactor shutdown conditions.

1.1.5.4 To provide physical support for the In-Vessel Fuel Handling Machine.

1.1.5.5 To support in-vessel nuclear instruments.

1.1.6 Fuel Transfer Port Shielded Gate Valve Functions

1.1.6.1 To provide, when closed, adequate shielding against radiation originating within the reactor vessel during shutdown conditions, within the ex-vessel storage tank, or within the valve body.

1.1.6.2 To provide, when open, adequate shielding against radiation originating within the reactor vessel during shutdown conditions, within the ex-vessel storage tank, within the valve body, or from fuel elements or other core components located within or passing through the valve.

1.1.6.3 To contain and prevent contamination of the reactor atmosphere.

1.1.7 Sweep Arm Functions

To detect and locate any obstructions which could interfere with the rotation of the reactor top shield or the proper operation of the fuel handling equipment. Such obstructions might consist of fuel elements sticking up above their normal position or control actuator rods which have not been disconnected from the neutron-absorber section.

1.1.8 Canister Functions

1.1.8.1 To serve as a vessel in which core components are carried while being moved into and out of the reactor vessel.

1.1.8.2 To serve as a vessel in which core components are stored.

1.1.8.3 To serve as a container in which spent fuel elements and other old core components can be shipped out of the reactor plant.

1.2 Summary Description of the In-Plant Fuel Handling System

1.2.1 Handling Operations

The principal steps in the in-plant fuel handling process are illustrated in Figure 8, page 54. The first five frames of this drawing illustrate the preparation steps between the time the reactor is shut down and the time actual fuel handling starts. Frames 6 and 7 illustrate the steps in the actual transfer of core elements between the reactor vessel and the Ex-Vessel storage tank. The final steps required to restore the reactor to operating condition are essentially the reverse of the first five frames and are not shown. The captions on the drawing describe briefly the operations shown. More detailed descriptions are given in Sections 4.1 to 4.6 of this document.

1.2.2 Handling Time Estimate

The current reference fuel handling scheme is based on refueling at one-year intervals.

The following time estimate for the refueling shutdown times is taken from Section 4.8 of this document:

a. Annual refueling shutdown: 312 hr/year.

1.3 Requirements

1.3.1 Performance Requirements

1.3.1.1 In-Vessel Fuel Handling Machine

1.3.1.1.1 Grapple upward force: 4000# (max) as limited by the drive train slip clutch.

1.3.1.1.2 Grapple downward force: 4000# + 2 (grapple weight) (max) as limited by the drive train slip clutch.

1.3.1.1.3 Grapple force measurement accuracy: $\pm$ 20 pounds.

1.3.1.1.4 Grapple Speed: must be capable of constant speed operation at any rate in the range 1 - 15 ft/min.

1.3.1.1.5 Grapple jogging: must be capable of being jogged in vertical motion increments of .040 inch or less.

1.3.1.1.6 Allowable leak rate: 45 cc/day per foot of seal, 450 cc/day total.

1.3.1.1.7 External radiation level

General: 100 mr/hr at surface of machine body and 10 mr/hr at surface of structure.

Local and Transient: 500 mr/hr.

Other: (to be determined).

1.3.1.1.8 Grapple must be capable of rotating core elements through 180°.

1.3.1.2 Ex-Vessel Fuel Handling Machine

1.3.1.2.1 Grapple upward force: 2000# (max) as limited by the drive train slip clutch.

1.3.1.2.2 Grapple downward force: = grapple weight.

1.3.1.2.3 Grapple force measurement accuracy: ± 10 lb.

1.3.1.2.4 Grapple speed: must be capable of constant speed operation at any rate in the range 1 - 15 ft/min.

1.3.1.2.5 Grapple jogging: must be capable of being jogged in vertical motion increments of .040 inch or less.

1.3.1.2.6 Allowable leak rate: 45 cc per day per foot of seal length, 4000 cc/day total.

1.3.1.2.7 External radiation level

General: 100 mr/hr at surface of the shielding.

10 mr/hr at operator's platform.

Local and Transient: 500 mr/hr.

Other: (to be determined).

1.3.1.2.8 Gantry longitudinal and transverse speed: must be capable of constant speed operation at any rate in the range 1 - 30 ft/min.

1.3.1.2.9 Gantry jogging: must be capable of being jogged in increments of longitudinal and transverse motion of .040 inch or less.

1.3.1.2.10 Cooling system capacity: 60 Kw (max) the fuel element removal sequence will be established to keep fuel element decay heat rate within the capability of the FHM.

1.3.1.2.11 Heating system capacity: sufficient to maintain an internal temperature of 500°F.

1.3.1.3 Auxiliary Handling Machine

1.3.1.3.1 Grapple upward force: 4000# (max) as limited by the drive train slip clutch.

1.3.1.3.2 Grapple downward force: 4000# + 2 (grapple weight) (max) as limited by the drive train slip clutch.

1.3.1.3.3 Grapple force measurement accuracy: ± 200 lb.

1.3.1.3.4 Grapple speed: must be capable of constant speed operation at any rate in the range 1 - 15 ft/min.

1.3.1.3.5 Grapple jogging: must be capable of being jogged in vertical motion increments of .040 inch or less.

1.3.1.3.6 Allowable leak rate: 45 cc per day per foot of seal length.

1.3.1.3.7 External radiation

General: 100 mr/hr

Local and Transient: 500 mr/hr.

Other: (to be determined).

1.3.1.3.8 Gantry: see Sections 1.3.1.2.8 and 1.3.1.2.9 above.

1.3.1.4 In-Vessel Machine Shielded Gate Valve

1.3.1.4.1 Opening or closing time: 1 min (nominal max).

1.3.1.4.2 Allowable leak rate: 45 cc per day per foot of seal length.

1.3.1.4.3 External radiation level

General: 100 mr/hr

Local and Transient: 500 mr/hr.

1.3.1.4.4 Equipment load on valve body

Direct compressive: (to be determined).

Moment: (to be determined).

1.3.1.5 Fuel Transfer Port Shielded Gate Valve

1.3.1.5.1 Allowable leak rate: 45 cc per day per foot of seal length.

1.3.1.5.2 External radiation level

General: 100 mr/hr

Local and Transient: 500 mr/hr

1.3.1.5.3 Equipment load on valve body

Direct compressive: (small)

Moment: none

1.3.1.5.4 Opening and closing time: 1 min (nominal max).

1.3.1.6 Sweep Arm

1.3.1.6.1 Arm extension: to be determined

1.3.1.6.2 Arm sag: 2 inches (max)

1.3.1.6.3 Rotation: unlimited manual rotation about the vertical axis.

1.3.1.6.4 Allowable leak rate: 45 cc per day per foot of seal length.

1.3.1.7 Canister

1.3.1.7.1 Allowable leakage: none detectable by mass spectrometer.

1.3.1.7.2 Weight: must be heavy enough to sink in liquid sodium when empty.

1.3.2 Environment Requirements

1.3.2.1 Operating Environment

At twelve-month intervals the reactor is shut down for refueling. During this period additional costs are being incurred at the rate of about \$2000 per hour. Because of this high cost, every effort will be made to reduce the downtime to a minimum and the operators will probably feel that they are under considerable pressure. The great emphasis on speed during this period makes it especially important that fuel handling equipment used be highly reliable and adequately interlocked to protect against improper operation by operators who are in a hurry.

1.3.2.2 Physical Environment

1.3.2.2.1 In-vessel Fuel Handling Machine

1.3.2.2.1.1 Grapple and holddown tube will be immersed in sodium at 500°F. In its penetration of the top shield it will be subjected to the thermal gradient and environmental conditions in the top shield. The components above the top shield will operate in the reactor building atmosphere.

1.3.2.2.1.2 Helium at 500°F containing appreciable but undetermined amounts of radioactive xenon and krypton and saturated with radioactive sodium vapor can get up into the body of the machine. Free circulation of these gases is restricted by the scraper rings at the lower end of the body, however.

about 1 psig.

1.3.2.2.1.3 Normal working pressure:

full vacuum.

1.3.2.2.1.4 Design pressure: 30 psig to

about 10 R/hr.

1.3.2.2.1.5 Internal radiation level:

1.3.2.2.2 Ex-vessel Fuel Handling Machine

1.3.2.2.2.1 The machine operates in the reactor building atmosphere. Helium at 500°F containing appreciable but undetermined amounts of radioactive xenon and krypton and saturated with radioactive sodium vapor can circulate freely up into the internal passages of the machine.

rate = 60 Kw (max).

1.3.2.2.2.2 Spent fuel heat generation

1250°F (max).

1.3.2.2.2.3 Fuel canister temperature -

about 1 psig.

1.3.2.2.2.4 Normal working pressure:

full vacuum.

1.3.2.2.2.5 Design pressure: 30 psig to

about 500,000 R/hr.

1.3.2.2.2.6 Internal radiation level:

1.3.2.2.3 Auxiliary Handling Machine

1.3.2.2.3.1 The machine operates in the reactor building atmosphere. Helium at 500°F containing appreciable but undetermined amounts of radioactive xenon and krypton and saturated with radioactive sodium vapor can circulate freely up into the internal passages of the machine.

about 1 psig.

1.3.2.2.3.2 Normal working pressure:

full vacuum.

1.3.2.2.3.3 Design pressure: 30 psig to

generation rate: (to be determined)

1.3.2.2.3.4 Control actuator rod heat

ture: (to be determined).

1.3.2.2.3.5 Control actuator rod tempera-

be determined).

1.3.2.2.3.6 Internal radiation level: (to

1.3.2.2.4 In-vessel Machine Shielded Gate Valve

1.3.2.2.4.1 The gate valve is located in the reactor building atmosphere above the reactor top shield. Helium at 500°F containing appreciable but undetermined amounts of radioactive xenon and krypton and saturated with radioactive sodium vapor can circulate up into the body of the valve.

1.3.2.2.4.2 Normal working pressure:
about 1 psig.

1.3.2.2.4.3 Design pressure: 30 psig to
full vacuum.

1.3.2.2.4.4 Internal radiation level:
to be determined.

1.3.2.2.5 Fuel Transfer Port Shielded Gate Valve

1.3.2.2.5.1 The gate valve is located in the reactor building atmosphere above the reactor top shield. Helium at 500°F contains appreciable but undetermined amounts of radioactive xenon and krypton and saturated with radioactive sodium vapor can circulate up into the body of the valve.

1.3.2.2.5.2 A fuel canister at 1250°F
(max) passes through the valve.

1.3.2.2.5.3 Normal working pressure:
about 1 psig.

1.3.2.2.5.4 Design pressure: 30 psig
to full vacuum.

1.3.2.2.5.5 Internal radiation level:
about 500,000 R/hr.

1.3.2.2.6 Sweep Arm

1.3.2.2.6.1 During reactor operation, the sweep arm is motionless in the reactor vessel in sodium and sodium-saturated-helium at 1140°F and in a high neutron and gamma ray flux.

1.3.2.2.6.2 During reactor shutdowns the sweep arm may be operated in the reactor vessel in sodium and sodium-saturated-helium at 500°F in a high gamma ray flux.

1.3.2.2.7 Canister

1.3.2.2.7.1 At certain times the canister is in the reactor vessel. The temperature may range from 500°F to 1140°F and the canister may be empty, contain a new fuel element, or contain a spent core element. It will be filled with Na during use.

1.3.2.2.7.2 At certain times the canister is stored in the ex-vessel storage tank. The temperature may range from 250°F to 500°F and the canister may contain either a new or spent core element.

1.3.2.2.7.3 Temperatures, pressures, and sealing requirements during handling and spent fuel shipping are to be determined.

1.3.3 Reliability and Availability Requirements

Two factors are the primary determinants of overall availability, the inherent reliability of the equipment and the way in which it is used. The reliability determines the unscheduled downtime and the operating procedures determine the scheduled downtime.

No hard-and-fast requirements have been or are likely to be established for either scheduled or unscheduled downtime. There are, however, certain goals that have been established. The goals have been established on the basis of off-line refueling and annual turbine maintenance shutdowns; they are:

Scheduled refueling unavailability (see p.34)	0.0
Unscheduled unavailability	<u>.81</u>
Total	0.81%

It should be noted that the values here are the additional unavailabilities over and above those that are attributable to turbine maintenance and that they also do not include the unavailability of .96% which is attributable to the reactor top shield.

1.3.4 Maintenance Requirements

1.3.4.1 All equipment shall be designed for easy steam or water cleaning. Internal surfaces shall be sloped for good drainage and drainage holes shall be provided as required. Internal spray nozzles may be used as needed to insure good cleaning.

1.3.4.2 Means shall be provided for sealing around the tapes of all handling machines which use them. The tape seals combined with adequate shielding shall permit access to the internal hoisting mechanism while the machine contains its most radioactive component.

1.3.4.3 To the greatest degree possible, auxiliary means of operating the fuel handling equipment shall be provided. Typically, such means will consist of hand cranks, electrical overrides, special ports in the equipment for the insertion of special tools. To the extent that needs can be foreseen, special tools shall be designed.

1.3.4.4 To the greatest extent practicable, operating equipment shall be located outside the equipment shielding and sealed housings of the various pieces of equipment.

1.3.4.5 A maintenance facility shall be provided which will permit men to work under the various pieces of fuel handling equipment.

A deep pit shall be provided in the floor of this facility which will permit grapples, special tools, etc, to be extended downward and out of the machines for inspection, cleaning, repair, etc. Special support structures shall be designed as required for the In-vessel Fuel Handling Machine, Shielded Gate Valves, and other equipment requiring them.

1.3.4.6 Parts subject to wear or damage shall be designed for easy replacement. Electrical circuits shall be designed with plug-in components to the greatest degree practicable.

1.3.4.7 Sufficient indicator lights and other instrumentation shall be provided as required to facilitate trouble-shooting and maintenance.

1.3.5 Instrumentation Requirements

1.3.5.1 Operation Sequence Controls and Instrumentation

1.3.5.1.1 An integrated control system for the In-vessel Fuel Handling Machine, Ex-vessel Fuel Handling Machine, Reactor Top Shield, and the Ex-vessel Storage Tank shall be provided to insure that the two machines can "call" at the various storage locations only in a safe sequence. These sequencing controls shall be based on a normal handling cycle. Provisions shall be made for bypassing these controls to permit operation in any desired sequence under proper administrative control.

1.3.5.1.2 Interlocks shall be provided which will insure that there are no mechanical interferences among the various pieces of handling equipment and other major plant equipment.

1.3.5.1.3 Physical stops shall be provided to prevent possible collisions of the gantry-mounted handling equipment with the reactor control rod drives. Interlocks shall be provided to prevent gantry movement unless the stops are in place.

1.3.5.2 Plant and Equipment Protection Instrumentation

1.3.5.2.1 Thermocouples shall be provided in the Ex-vessel Fuel Handling Machine which will indicate, either directly or by calibration, the outside surface temperature of fuel handling canisters.

1.3.5.2.2 Equipment and instrumentation shall be provided for measuring the radioactivity of the gas inside the Ex-vessel Fuel Handling Machine.

1.3.5.2.3 Equipment and instrumentation shall be provided for the purpose of measuring the gas flow pressure drop through new fuel elements before they are placed in canisters and taken to the Ex-vessel Storage Tank.

1.3.5.2.4 Instrumentation shall be provided to measure the rate of insertion of a new core element into the reactor core and to give an alarm if the rate is too fast to avoid damage to the element being handled or adjacent elements.

1.3.5.3 Performance Monitoring Instrumentation

1.3.5.3.1 The cooling system for the Ex-vessel Fuel Handling Machine "cold wall" shall be fully instrumented to measure coolant temperatures in and out of the machine, flow rates, and pressures. Alarms shall be provided in the event of abnormal values.

1.3.5.3.2 Temperature and flow measurements shall be made for the shield cooling system of the Ex-vessel FHM.

1.3.5.3.3 Instrumentation shall be provided for the measurement of purge gas flow rates for all seals. Alarms shall be given in the event of abnormally high flow rates.

1.3.5.3.4 Instrumentation shall be provided for measuring the actuating forces of all internal moving parts of the In-vessel, Ex-vessel, and Auxiliary Handling Machines and the shielded gate valves. Alarms shall be given in cases of abnormally high forces.

1.3.5.3.5 Instrumentation shall be provided to indicate the position of all major moving parts of the In-vessel, Ex-vessel, and Auxiliary Handling Machines and the shielded gate valves. Grapple heights shall have continuous reading instruments, most other indications can be either open or closed, up or down, engaged or disengaged, etc.

1.3.6 Safety Requirements

1.3.6.1 The reactor shall be in the shutdown condition with all control and safety rod absorber sections in their fully inserted position; nuclear flux detection and alarms shall be operative; and the building containment will be completely closed during all core component handling operations.

1.3.6.2 Reactor coolant temperature and level shall be monitored during all fuel handling operations. Suitable alarm points shall be established and operative.

1.3.6.3 The reactor cover gas shall be monitored for fission gas. Alarm points shall be established and operative.

1.3.6.4 No more than one control element shall be removed from the loaded core at any time and no fuel may be handled in the reactor while a control element is removed.

1.3.6.5 The temperature of core components being handled shall be monitored. An alarm system shall be provided.

1.3.6.6 During fuel handling operations cooling shall be provided to limit fuel cladding temperature to 1500°F under credible accident circumstances. Specific accidents to be considered include: loss of fuel handling equipment primary coolant systems, fuel element stuck in any position, a failure of the FHM's transporting device, and handling a fuel element with excessive power in the ex-vessel fuel handling machine.

1.3.6.7 The ex-vessel fuel handling machine shall be capable of handling ruptured fuel elements. Fission gas containment capability shall be based on compliance with 10CFR20 for short term exposure with a fission gas concentration within the ex-vessel machine based on the 100% release of fission gas from an element which ruptures within the FHM.

1.3.6.8 The ex-vessel FHM and associated equipment shall have sufficient remote control capability to achieve a steady-state safe condition in the event that personnel access to the manual control consoles is lost at any time a fuel element or other core component is being handled.

1.3.6.9 The fuel handling system shall maintain a current accountability, identification, and location of core components and must provide indication of correct location and seating of all core components within the core.

1.3.6.10 A method shall be provided to verify that the decay power of core components to be handled in the ex-vessel FHM is within the rated heat removal capability.

1.3.6.11 Provision shall be made to prevent inadvertent removal of a control element during in-vessel fuel transfer operations.

1.3.6.12 Provision shall be made to establish a removal sequence for core elements. The purpose of the removal sequence shall be to program the removal of core elements to coincide with the normal heat removal capabilities of the fuel handling equipment.

1.3.6.13 The fuel handling equipment shall be designed to accommodate seismic loadings as defined for Class IA per SDD-096-10-000.

1.3.6.14 The ex-vessel FHM transporter drive shall be provided with interlocks and safety stops to prevent collision with the in-vessel FHM drive, control rod drives, containment dome, or other equipment installed on the reactor loading face floor.

1.3.7 Design Requirements

1.3.7.1 Applicable Codes: ASME Unfired Pressure Vessel Code
ASME Nuclear Vessel Code

1.3.7.2 Seismic Loading: Fuel handling equipment shall be designed to withstand ground or equipment support accelerations of Class IA as defined in SDD-096-10-000.

1.3.7.3 Package limits for shipping: (to be determined).

1.3.7.4 All seals shall have at least two sealing members with provisions for either pressurizing or evacuating the space between the sealing members.

1.3.7.5 Materials

1.3.7.5.1 In general, metals in contact with sodium or the reactor atmosphere shall be type 304 stainless steels; other materials may be used where special circumstances require.

1.3.7.5.2 Other metals will, in general, be carbon steels. Exposed surfaces shall be painted for appearance and corrosion protection.

1.3.7.5.3 No hydrogenous or carbonaceous materials shall be used inside any piece of fuel handling equipment or in contact with the reactor atmosphere with the exception of elastomeric materials used for seals. The prescribed materials include oil, grease, water, graphite, etc.

1.3.7.6 Flexibility

1.3.7.6.1 The fuel handling equipment shall be designed so that fuel transfers into and out of the reactor vessel can be made only while the reactor is shut down.

1.3.7.6.2 No special design provisions need be made for fuel elements of a different size.

1.3.7.6.3 Provisions shall be made for handling damaged core elements.

1.3.7.7 Operating Lifetime and Number of Cycles

The assumed life of the reactor plant is 30 years. With annual refueling, there will be 30 cycles of fuel handling equipment use. The following estimates of numbers of operations are based on changing an average of 160 core components during each cycle. The approximate numbers of cycles given here are only for those operations involved in the transfer of core components between the reactor and the Spent Fuel Storage Vessel. Additional operations required for new fuel receiving and spent fuel shipping are not included.

1.3.7.7.1 In-Vessel Fuel Handling Machine

Installation and removal cycles	30
Hold down tube up-and-down cycles	19750
Grapple up-and-down cycles	19750

1.3.7.7.2 Ex-Vessel Fuel Handling Machine

Gantry travel cycles down-and-back	
Indexings	19750
Machine raising-and-lowering cycles	19750
Lower End Closure Valve opening-and-closing cycles	19750
Grapple long-stroke cycles	9875
Grapple short-stroke cycles	9875

1.3.7.7.3 Auxiliary Handling Machine

Sweep arm installation-and-removal cycles	1
In-vessel machine installation-and-removal cycles	30
Reactor fuel transfer port plug installation-and-removal cycles	60
Fuel storage port plug installation-and-removal cycles	

1.3.7.7.4 In-Vessel Machine Shielded Gate

Valve Installation-and-removal cycles	30
Opening-and-closing cycles	30

1.3.7.7.5 Fuel Transfer Port Shielded Gate Valve

Installation-and-removal cycles at reactor fuel transfer ports	30
Installation-and-removal cycles at spent fuel storage vessel	30
Opening-and-closing cycles at reactor fuel transfer ports	9875
Opening-and-closing cycles at spent fuel storage vessel	9875

1.3.7.7.6 Sweep Arm

Installation-and-removal cycles	1
Rotations	60
Arm extension-and-folding cycles	60

1.3.8 Interface Requirements

The following table summarizes the principal physical interfaces between fuel handling equipment and other plant equipment and facilities. In most cases, the design has not progressed far enough to permit a detailed description of the interface requirements.

<div style="text-align: center;"> This Equipment → Interfaces with ↓ </div>	In-Vessel Fuel Handling Machine	Ex-Vessel Fuel Handling Machine	Auxiliary Handling Machine	In-Vessel Machine Shielded Gate Valve	Fuel Transfer Port Shielded Gate Valve	Sweep Arm	Canister
In-Vessel Fuel Handling Machine			X	X		X	
Ex-Vessel Fuel Handling Machine					X		X
Auxiliary Handling Machine	X			X	X	X	
In-Vessel Machine Gate Valve	X		X			X	
Fuel Transfer Port Gate Valve		X	X				X
Sweep Arm			X	X			
Canister		X			X		
Canister Loading Cell		X	X		X		X
Canister Welding Facility		X	X		X		X
Ex-Vessel Storage Tank		X	X		X		X
Spent Fuel Shipping Cask		X			X		X
In-Vessel Machine Storage Area	X		X				
Sweep Arm Storage Area			X			X	
Small Shield Plug Storage Area			X				
Reactor Building Crane			X				
Maintenance Pit	X	X	X	X	X	X	
Wash Cell	X	X	X	X	X	X	
Control Rod Drives		X	X	X			
Reactor Top Shield	X	X	X	X	X	X	X
Fuel Element	(1)						X
Control Rod (Absorber Section)	(1)						X
Reactor In-Vessel Storage Rack							X

(1) The first drawing prepared in this series of interface control drawings is Figure 10.

2. DETAILED EQUIPMENT DESCRIPTION

2.1 In-vessel Fuel Handling Machine

2.1.1 Design Drawings

Three conceptual drawings are shown in Appendix 6.2 These are:

Figure 2 In-vessel FHM Schematic

Figure 3 In-vessel Fuel Handling Machine

Figure 4 In-vessel FHM Grapple

2.1.2 Overall Configuration and Installation

The reactor upper closure is a double-rotating top shield. The in-vessel FHM is installed through a port in the inner rotating shield plug. The in-vessel FHM is indexed to and traversed between core positions and canisters in transfer storage positions by rotation of the top shield plugs. The in-vessel FHM consists of a guide tube which is lowered to guide the grapple and hold down adjacent fuel elements, and, a grapple and grapple drive which picks up, raises, lowers, and releases the fuel element. A rotation drive on the grapple and guide tube assembly provides the capability for rotating blanket elements 180°.

The overall configuration of the machine is shown schematically in Figure 2 and to-scale in Figure 3. The machine is made in two main sections. The lower section passes through the reactor top shield and reaches down nearly to the top of the fuel elements. This section contains the grapple, the guide tube, and their actuators. This part of the machine is installed in the reactor top shield with the Auxiliary Handling Machine and the In-vessel Machine Shielded Gate Valve. The upper part of the machine consists mainly of the grapple and guide tube vertical drive equipment and the structural framework supporting them. The upper part is set in place after the lower part has been installed, at which time the drives are connected. The upper part of the machine is handled and installed by the overhead reactor building crane and is bolted to the shielded gate valve which was previously installed on the reactor top shield.

2.1.3 Grapple and Grapple Actuator

The grapple and its actuating system are shown in Figure 4. There are two grapple fingers which are actuated by a grapple actuator rod with pins at the lower end which operate in cam slots in the grapple fingers. Downward motion of the grapple actuator moves the fingers outward, in which position they will engage the internal lip of a fuel element or control rod housing.

The actuator rod is sealed to the grapple tube by means of a bellows at the lower end and an elastomeric seal at the top end. Relative motion between the actuator rod and the grapple tube is caused by an air cylinder mounted at the top end of the grapple tube.

2.1.4 Grapple Vertical Drive

The grapple rod is driven vertically by means of roller chains passing over upper and lower sprockets giving both push and pull capability. The lower sprockets are driven through a gear box by a variable speed dc motor. The upper sprockets are idlers. The vertical stroke of the grapple rod is about 4 inches greater than the overall length of the fuel element for a total of about 18 to 19 feet. Because of this long stroke, it is necessary to use elastomeric seals instead of bellows. The grapple tube moves relative to the guide tube and the guide tube is made long enough so that no portion of the grapple rod which is wetted by sodium passes through the seals at the upper end of the guide tube. To reduce the amount of sodium which is carried up into the region in and above the shield, scrapers are placed at the lower end of the guide tube. A plastic bellows covers the grapple rod as it is lifted vertically to keep off dust and minimize the spread of any condensed sodium from the grapple rod.

2.1.5 Guide Tube Vertical and Rotation Drive

The guide tube vertical and rotation drives are shown in Figure 3.

The guide tube serves the purposes of guiding the lower end of a fuel element into an empty core or storage position, of holding down surrounding elements as a given fuel element is removed from the core, and of rotationally driving the grapple assembly.

When the guide tube is fully down it bears lightly on the tops of the core elements and control rods surrounding the element which is to be removed. When the guide tube is fully up it clears the tops of the fuel elements by about eight inches leaving room for the horizontal blade of the Core Sweep Arm to pass underneath. The vertical motion of about 8 1/2 inches is provided by two motor-driven screw jacks which are mounted on the structural framework near the top end of the guide tube.

The guide tube rotation drive motor is mounted on a plate which is driven by the screw jacks mentioned above. A ball bearing between this plate and the guide tube proper allows both vertical and rotary motion of the guide tube.

Both the guide tube and the grapple are keyed together by means of a keyway in the lower end of the guide tube and keys built into the grapple assembly. Thus, as the guide tube is rotated by the rotation drive motor, the grapple is also forced to turn simultaneously. With both being driven there is no possibility of friction on the fuel element which would tend to cause the element to slip on the grapple jaws.

2.1.6 Fuel Element Orientation

Because the fuel elements are hexagonal-shaped and close packed in the core, it is necessary that they be oriented to be inserted in the core. To simplify the insertion procedure the fuel elements are designed in such a way as to be self-orienting. Special cam surfaces are built into the top end of each fuel element. As an element is lowered, a cam follower tab on the lower end of the element engages the cam surfaces on elements in place in the core causing the element being inserted to be rotated into proper orientation. The fuel element and control rod housings have no swivels but are free to rotate on the grapple as resistance to downward motion, if any, is encountered. This reduces the load on, and friction of, the grapple fingers and allows the element to rotate into proper orientation. The self-orientation system is required to work only when elements are inserted into the reactor core; normally this will be only twice in the lifetime of an element or control rod housing.

2.1.7 Shielding

Approximately two inches of lead are required to shield against the gamma rays from the sodium which adheres to the grapple rod. The shielding is not shown in any of the design drawings but would extend to slightly above the maximum elevation reached by the sodium wetted surfaces of the grapple drive rod.

2.2 Ex-vessel Fuel Handling Machine

2.2.1 Design Drawings

Two conceptual drawings are shown in Appendix 6.2. These are:

Figure 5 Gantry Mounted Handling Machines

Figure 6 Ex-vessel FHM Schematic

2.2.2 Overall Configuration

The ex-vessel FHM is a gantry-mounted shielded cask used for transporting core components in sodium filled canisters between the reactor, ex-vessel storage, canister welding station, wash cells, and shipping casks. The ex-vessel FHM has a grapple sized for the canister, a grapple drive, and heating and cooling systems which maintain the sodium in a liquid state and remove excess heat from irradiated components.

2.2.3 Gantry

Both the Ex-vessel Fuel Handling Machine and the Auxiliary Handling Machine are mounted side-by-side on a common gantry. An operator's platform is supported from the trolley of the gantry. The gantry and the approximate overall arrangement of the two machines on the gantry are shown in Figure 5.

2.2.4 Hoist Mechanism

The hoist mechanism consists of three tape drums, two for load-carrying tapes and one for the grapple-actuating tape. The drums are located inside a shielding housing, one side of which can be removed for access to the drums, tapes, etc. The drums are mounted on shafts which pass through and are sealed to the shielded housing. The load-carrying-tape drums are driven by dc electric motors driving through gear boxes and torque load cells. The characteristics of the dc motors are such that the total hoisting load is shared in nearly equal proportions. The grapple actuating tape is driven by a separate mechanism which functions as a "follower" holding the grapple tape in its proper position relative to the main load-carrying tapes.

2.2.5 Grapple

The grapple is not shown on any of the design drawings but is shown on the schematic diagram. It is basically similar to the grapple of the In-vessel Fuel Handling Machine, shown previously, in the way in which the gripping fingers are actuated. This grapple is made to grip only on the internal lip of a canister which will be described later; it will not grip a fuel element or a control rod housing. This is a safety feature to prevent the accidental picking up of a spent core element which would overheat if removed from the sodium-filled canister in which it is normally handled.

The grapple is made long enough so that it will reach through the sodium pool to the top of the fuel elements and control rod housings without immersing the steel tapes in the liquid sodium. This will greatly reduce the amount of sodium that is carried up into the hoist housing and onto the tape drums.

2.2.6 Grapple Tapes, Scrapers, and Seals

The grapple load-carrying tapes are made of steel 4 inches wide by .048 inch thick. The grapple actuating tape is 3/4 inch wide and of the same thickness. Before the tapes are wound onto the hoisting drums they pass through scrapers that will remove most of any sodium that may have condensed on the tapes. An inflatable seal arrangement permits the hoist housing to be sealed off from the rest of the machine so that access can be had to hoist housing even while a fuel element is within the main body of the machine.

2.2.7 Cooling System

The cooling system indicated in Figure 6 uses a separate NaK-cooled inner sleeve or "cold wall" within the main body of the machine. The coolant chosen must be compatible with the reactor coolant in the event of an internal leak. NaK was chosen to eliminate problems associated with freezing of the coolant, though sodium can be considered in combination with a suitable pre-heating system. The cooling system can also

function as a pre-heating system for initially warming up the inside of the machine to prevent freezing of condensed sodium. The cooling coil assembly is insulated on the outside and there is a small clearance between the outside of the insulation and the inner wall of the lead-shot-filled body. The cooling coil assembly is sealed to the main body at the lower end by means of a "piston ring" type seal that allows for differential thermal expansion between the cooling coil assembly and the main body while preventing any appreciable amount of sodium from getting into the clearance between them.

The main body of the machine is made with a double inner wall so that room air can be circulated on the outside of the inner wall and through the lead shot which comprises the shielding.

2.2.8 Lower End Closure Valve

The valve is essentially a gate valve in which the gate is heavily shielded with lead and the body of the valve is filled with lead shot. The gate travels horizontally on rollers and is driven by a lead screw and a standard commercial valve actuator (not shown). As the gate of the valve is driven to the closed position, a sealing plate is forced downward by a linkage arrangement to seal against the inside of the valve body. A drip pan is mounted atop the gate to catch any sodium which drips from a canister up in the machine or from the cooled inner sleeve. A heating coil built into the drip pan and a drain valve permit the drip pan to be emptied even if the sodium therein had previously solidified.

When the machine is positioned over a floor-mounted shielded gate valve, the entire machine is lowered a few inches until the seal is made. The lowering and subsequent raising are done by means of mechanical jacks on the gantry. The actual seal is made by means of a spring-loaded sliding sleeve within the valve body; sponge-rubber-backed lead blocks insure that there is no appreciable shielding crack at the interface. This arrangement of sealing and shielding members makes it unnecessary for the full weight of the ex-vessel machine to be lowered onto the floor valve in order that a suitable seal be made.

2.2.9 Shielding

The basic shielding requirement is about 13 inches of lead for spent fuel elements. In general, the shielding used in this machine is lead shot. Assuming an average apparent density of the shot of 61% of the density of solid lead, about 22 inches of shot are required.

2.3 Auxiliary Handling Machine

No design drawings of the Auxiliary Handling Machine exist at the present time. The approximate overall size and shape of the machine are shown in Figure 5, Appendix 6.2, in which it is shown mounted on a common gantry with the Ex-vessel Fuel Handling Machine.

In addition to sharing a mount with the Ex-vessel Machine, the Auxiliary Handling Machine shares many characteristics. The hoist mechanism

is currently envisioned as being identical, the grapple shorter but otherwise similar, and the lower end closure valve thinner but otherwise similar.

The primary differences between the two machines are that the shielding is considerably thinner because no highly radioactive sources are ever lifted up into the machine; there is no cooling system for the same reason; and a long vertical lift capability is required in order that the machine can be lifted clear of the lower part of the In-vessel Fuel Handling Machine after its installation is complete. At present, the bottom end of the machine must be lifted to about 13 feet above the reactor top shield plug to clear the top of the lower section of the In-vessel Fuel Handling Machine.

2.4 Shielded Gate Valves

In the present fuel handling concept there are four shielded gate valves. Two are used in conjunction with the In-vessel Fuel Handling Machine and two are used in conjunction with the Ex-vessel Fuel Handling Machine.

All four of the valves are similar in construction and design features. The valves used in conjunction with the In-vessel Fuel Handling Machine have less shielding than the valves through which fuel elements pass.

There are two main assemblies which make up each valve; these are the valve body assembly and the gate assembly. The valve bodies are rectangular in shape with a rectangular internal cavity in which the rectangular gate assembly moves. Each gate is driven by a standard commercial valve actuator and a stainless steel lead screw. The lead screw is mounted on bearings and is sealed where it passes through the valve body. The nut which is attached to the gate assembly has considerable freedom to accommodate lateral and angular wobble of the inboard end of the lead screw.

The gate assembly travels horizontally on rollers and is also guided laterally by rollers. On the top and bottom sides of the gate are two seal plates which seal against O-rings in the body. A combination of springs and links insures that the seal plates move only vertically as their seals with the top and bottom plates of the valve body are made and broken; there is no lateral component of motion to tend to scuff or twist the O-rings in their grooves.

2.5 Sweep Arm

The basic purpose of the sweep arm is to provide a horizontal blade which can be rotated about a vertical axis to satisfy the Safety Requirements of Section 1.3.6.

Two design approaches have been considered for the Sweep Arm. The first is a horizontal arm composed of specially-designed chain links which will bend in only one direction and may be extended and retracted as

desired. The second is a concept where the arm is a rigid member which may be folded up or down as required. In both designs, the Sweep Arm was to be removed and installed with the Auxiliary Handling Machine at the beginning and end of each in-vessel refueling cycle.

While no later designs have been made, it is believed that the requirement for insertion and removal at the beginning and end of the refueling cycles can be eliminated and that it is entirely practical to leave the Sweep Arm installed indefinitely. On this basis it may be possible to devise a simple system which would allow the arm to hang vertically down in the event that it should be necessary to remove the unit. During reactor operation, it will probably be necessary to support the tip end of the arm by means of a suitable bracket on the wall of the reactor vessel.

2.6 Canister

A conceptual design drawing of the fuel element canister is shown in Figure 7.

All core components are transferred into and out of the reactor vessel in canisters. Spent fuel elements are also shipped out of the plant in the canisters in which they were removed from the reactor vessel. Each canister is a plain piece of tubing, 8 inches in diameter, which is closed at the bottom end and which has a heavy ring welded to the top end. The ring section is machined with an internal pickup lip for the grapple of the Ex-vessel Fuel Handling Machine. The ring section also is made with internal passages which will siphon out the top few inches of sodium upon removal from a pool to reduce the likelihood of sloshing sodium out of the canister during handling operations. When the canister is to be used for shipping spent fuel elements or other components, a cap can be welded to the heavy ring section. The cap has identical pickup provisions so that the sealed canister can also be handled by the Ex-vessel Fuel Handling Machine.

3. OPERATING PROCEDURES

The basic refueling cycle is illustrated by Figure 8. This drawing shows the principal preparation steps and the transfer steps; the final steps involved in preparing the reactor for operation are essentially the reverse of the preparation steps and are not shown. The current time estimates for all of the operations which are done during a refueling shutdown are given in Figure 9.

3.1 Initial Preparation Steps

The first five frames of Figure 8 illustrate the installation of the fuel handling equipment which is done concurrently with the cooling down of the reactor primary loop and the disconnection of the control rod "poison" sections from the actuating rods. The reactor "safety dome" is

removed and set aside; the floor valves (tentatively 2 in number) are set in place on the reactor top shield; a shield plug in the reactor top shield is removed and the lower portion of the In-vessel Fuel Handling Machine is installed; and the top portion of the In-vessel Fuel Handling Machine is installed concurrently with the installation of the in-reactor-vessel instrument assemblies.

3.2 Initial Fuel Handling Transition Step

With the preparatory steps completed, fuel transfer operations by the In-vessel and Ex-vessel Fuel Handling Machines can begin. An initial transition step is necessary to get the cycle started; the first spent core element is removed from the core and placed in the in-reactor-vessel storage rack by the In-vessel Fuel Handling Machine and the first new element is picked up from the Ex-vessel Storage Tank by the Ex-vessel Fuel Handling Machine.

3.3 Basic Fuel Transfer Cycle

The basic fuel transfer cycle starts with the Ex-vessel Fuel Handling Machine traveling to the reactor where a new element in a canister is deposited into an empty position in the in-vessel transfer position. Both the Ex-vessel Fuel Handling Machine and the reactor top shield are re-positioned over a transfer position containing an element which has been removed from the core. This spent element in its canister is then picked up into the Ex-vessel Fuel Handling Machine. During the time that these operations have been taking place, the In-vessel Fuel Handling Machine has been idle.

In the second stage of the basic cycle, the In-vessel Fuel Handling Machine picks up the new element previously placed in the reactor vessel and takes it to the empty core position. Another spent element is then removed from the core and taken to the in-reactor-vessel storage rack. Concurrently with the operations of the In-vessel Fuel Handling Machine, the Ex-vessel Fuel Handling Machine takes its spent element to the Ex-vessel Storage Tank, re-positions, and picks up a new element from the Tank.

3.4 Blanket Element Rotation

At any convenient time blanket elements or fuel elements may be rotated; currently, both the inner and outer blanket elements are planned to be rotated. In this operation, the element is simply lifted up out of the core, rotated 180°, and lowered back into the core; this is done by the In-vessel Fuel Handling Machine.

3.5 Final Fuel Handling Transition Steps

The final transition steps complete the actual fuel transfer operations. In these steps the Ex-vessel Fuel Handling Machine brings its last new element to the reactor and deposits it, and the In-vessel Fuel Handling Machine transfers this element into the last empty space in the core.

3.6 Final Restoration Steps

The final restoration steps are essentially the reverse of the preparation steps. Instrument assemblies are removed concurrently with the removal of the top portion of the In-vessel Fuel Handling Machine; the lower portion of the In-vessel Fuel Handling Machine is removed and the shield plugs put back into the top shield; the floor valves are removed; and the reactor "safety dome" is secured in place over the reactor top shield.

3.7 Reactor Startup Operations

Following the installation of the reactor "safety dome" the reactor can be started up. The following steps are currently planned for as part of the startup sequence although some of them can possibly be eliminated by the use of sophisticated instrumentation, simulators, and on-line computers.

First the reactor is brought to criticality and at least a partial calibration of one control rod is made. If everything is satisfactory at this stage the reactor may be brought up to temperature and power.

3.8 Shutdown Time Summary

The "reference" refueling interval is every twelve months. The basic number of elements that are exchanged may be summarized as follows:

	<u>Annually</u>
Fuel elements exchanged	137
Inner row blanket elements exchanged	13.2
Outer row blanket elements exchanged	10.3
Control absorber rods exchanged	<u>1</u>
Total core elements exchanged	161.3
Total blanket elements rotated	23.5

The times estimates given in the following tabulations are all based on the times given in Figure 9 and do not include an allowance for times lost at the beginning and ends of shifts, coffee breaks, etc. These times, then, represent essentially a theoretical lower limit for a mature plant with a very well-trained crew and with enough relief operators and with overlapping work schedules arranged so as to minimize time losses. It is questionable whether such times can ever be realized in a real plant; thus, a "time efficiency" factor of about .85 has been applied as indicated to account for the small but probably unavoidable time losses.

Annual RefuelingOperationsTime

Preparation, transition and termination steps	37.6 hr
161.5 (avg) core elements exchanged @ 1.37 hr	221
23.5 blanket elements rotated @ .3 hr	<u>7.1</u>
Time (at 100% efficiency)	265.7 hr
Time (at 85% efficiency)	312
Unavailability attributable to refueling operations assuming turbine maintenance masks out refueling shutdown (Assumed turbine maintenance period is two weeks = 336 hr)	0.0 %

4. SAFETY PRECAUTIONS

4.1 Hazards

1. Loss of Cooling During Fuel Handling

a) Sticking of Canister

During removal from the reactor vessel or insertion into the storage vessel, the canistered fuel element can become stuck at any elevation. Sticking could be caused by misalignment of the movable and fixed parts of the plant and handling equipment, out-of-tolerance components, failure in the lifting equipment, or operation out of planned sequence. The effective inner containment barrier at this time is the combination of either the ex-vessel fuel handling machine, valve, and the reactor coolant pressure boundary, or the machine, valve and the fuel storage boundary.

b) Loss of Sodium from Canister

Sodium can be partially lost from a leaky canister during the transfer operation. The amount lost during a 15-min transfer can be limited to a few pounds through canister design and inspection before use, to eliminate large cracks and large inclusions.

c) Cooling System Failure

The fuel handling machine cooling system can fail through loss of power to the circulating pumps or mechanical damage to the NaK pipes. In this case, the fuel element is discharged to storage within 15 min, if power is available to move the machine, and 1- to 2-hr, if a new electrical power source or mechanical movement is required.

2. Handling an Overpower Fuel Element

A fuel element cooled for only about 8 hr could be picked up with the fuel handling machine. In this case, a radiation monitor will indicate excessive fission product activity, and automatic or operator action will lower the element back into the in-vessel storage area. If a second error occurs however, and the fuel handling machine is closed and moved, the fuel element will overheat.

3. Radioactive Gas Leakage

Excessive leakage of radioactive gas could occur through any of the numerous gas seals on the fuel handling equipment, resulting in potential overexposure of personnel.

4. Radioactive Material Spills

Drippage of reactor sodium from the ex-vessel handling equipment could occur, resulting in contamination of the working area and possible personnel exposure.

4.2 Precautions

Precautions which should be taken to minimize the consequences of loss of cooling or handling an overpower element are as follows:

- a) Fuel handling sequences should be planned so that the lower-powered blanket elements are moved from the core to transfer positions followed by low-powered fuel elements and then by high-powered fuel elements.
- b) Two independent gamma radiation detectors are mounted near the bottom of the fuel handling machine. An excessively overpowered element will activate a high-radiation alarm to alert the operator, lock the valve at the bottom of the machine open, and automatically lower the element back into the reactor.
- c) Spring-loaded thermocouples measuring canister surface temperature will give both rate of rise and high-temperature alarms.

Radioactive gas leakage hazards can be minimized by purging the reactor cover gas before initiating fuel handling operation, thorough leak testing of fuel handling and replacement of defective seals just prior to a refueling shutdown, and by having self-contained breathing equipment and radioactive gas monitors close at hand during fuel handling operations.

Radioactive material spills consisting of small quantities of sodium, possibly containing fission products and activated corrosion products should be immediately cleaned up to avoid spread of contamination.

5. MAINTENANCE

5.1 Normal/Routine Maintenance

The in-vessel machine will be removed from the reactor at the end of the refueling period, washed, placed in a maintenance facility, disassembled, checked and reworked as necessary to restore it to essentially "new" condition. The ex-vessel handling machine, the auxiliary handling machine, and the shielded gate valves will be similarly cleaned, inspected, and overhauled as necessary. The sweeparm will normally be left in the reactor but will be removed periodically (perhaps once every 2 years) for inspection and overhaul. Canisters will be inspected for defects when they enter the canister welding cell and will be replaced if necessary.

5.2 Unusual Maintenance

Unusual maintenance actions must be taken in various possible cases of in-plant fuel handling equipment malfunctions. These are briefly discussed below:

- a) Grapple cannot be released (In-vessel, ex-vessel, or auxiliary handling machine)

The action will be to utilize the independent backup grapple actuation mechanism to release the grapple. Since this may involve breakage of a "weak link", the affected machine will then have to be taken out of service to overhaul the mechanism.

- b) Grapple cannot be driven up or down (In-vessel machine)

If the jamming is in the drive mechanism of the machine, access can be gained to remove the cause. If the jamming is in the seal region around the grapple drive shaft, the seals are also accessible and can be removed to correct the cause of jamming. However, if the jamming occurs below the top shield, at the grapple rod scrapers or guides, the action will be to overpower the grapple drive. The scraper assembly and guide assembly will be designed to break away under the excess load.

- c) Grapple cannot be driven up or down (Ex-vessel or auxiliary handling machine)

Access can be gained to the drive mechanisms for each of these machines. If a fuel element is in the machine, special local shielding will have to be utilized to protect maintenance personnel.

6. APPENDICES

6.1 Design Data Sheets

PREPARED BY:				APPROVED BY:		DESIGN DATA SHEET		TITLE:	
J.L.Hedgecock								Fuel Handling Equipment In-Vessel Fuel Handling Machine	
LINE NO.	REVISION			ITEM	DESIGN POINT	REMARKS			
	NO.	DATE	NEW REV						
1.				Number required	1				
2.				Overall length, in-vessel portion, min.	about 40 ft				
3.				Overall length, ex-vessel portion	about 12 ft				
4.				Weight, in-vessel portion					
5.				Weight, ex-vessel portion					
6.				Transport means (in-plant)	{ Building crane (upper section) Auxiliary Handling Machine (lower Section)				
7.				Number of grapples	1				
8.				Grapple force upward, max	4000 lb.				
9.				Grapple weight	200 lb.	(estimated)			
10.				Grapple force downward, max.	4400 lb.				
11.				Grapple force measurement accuracy	± 20 lb.				
12.				Grapple speed range	1-15 ft/min				
13.				Maximum internal pressure	30 psig				
14.				Minimum internal pressure	full vacuum				
15.									
16.				Allowable leak rate @ 1 psig	{ 45 cc/day-ft 450 cc/day	(Tentative Values)			
17.									
18.				Basic external radiation at surface	100 mr/hr				
19.				Local and transient radiation at surface	500 mr/hr				
20.									
21.									
22.									
23.									
24.									
25.									
26.									
27.									
28.									
29.									
30.									
31.									
32.									
33.									
34.									
35.									
36.									
37.									
38.									

NUMBER

REVISION LETTER

PAGE 39

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

SDD-096-81-000

PREPARED BY: J.L.Hedgecock				APPROVED BY:		DESIGN DATA SHEET		TITLE: Fuel Handling Equipment Ex-Vessel Fuel Handling Machine	
LINE NO.	REVISION		NEW REV	ITEM	DESIGN POINT	REMARKS			
1.				Number required	1				
2.				Overall height from floor					
3.				Overall length x width					
4.				Weight					
5.				Transport means	Gantry				
6.				Number of grapples and internal chambers	1				
7.				Grapple force upward, max.	2000 lb.				
8.				Grapple weight	300 lb.				
9.				Grapple downward force, max.	300 lb.	(estimated)			
10.				Grapple force measurement accuracy	+ 10 lb.				
11.				Grapple speed	1-15 ft/min.				
12.									
13.				Gantry speed, longitudinally	1-30 ft/min				
14.				Gantry speed, transversely	1-30 ft/min				
15.				Gantry rail span, center-to-center	48 ft.				
16.				Gantry travel longitudinally	about 60 ft				
17.									
18.				Maximum internal pressure	30 psig				
19.				Minimum internal pressure	full vacuum				
20.				Allowable leak rate @ 1 psig	45 cc/day-ft	(Tentative Values)			
21.					4000 cc/day				
22.				Basic external radiation at surface	100 mr/hr				
23.				Local and transient radiation at surface	500 mr/hr				
24.									
25.									
26.									
27.									
28.									
29.									
30.									
31.									
32.									
33.									
34.									
35.									
36.									
37.									
38.									

NUMBER

REVISION LETTER

PAGE 40

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

SDD-096-81-000

PREPARED BY: J. Hedrecock				APPROVED BY:		DESIGN DATA SHEET		TITLE: Fuel Handling Equipment Auxilliary Handling Machine	
LINE NO.	REVISION			ITEM	DESIGN POINT	REMARKS			
	NO.	DATE	NEW REV						
1.									
2.				Number required	1				
3.				Overall height from floor, lowered					
4.				Overall height from floor, raised					
5.				Overall length x width					
6.				Weight					
7.				Transport means	Gantry				
8.				Number of grapples and internal chambers	1				
9.				Grapple force upward, max.	4000 lb				
10.				Grapple weight	100 lb	(estimate)			
11.				Grapple downward force, max.	100 lb				
12.				Grapple force measurement accuracy	± 20 lb				
13.				Grapple speed	1-15 ft/min				
14.									
15.				Gantry data: See previous page					
16.									
17.				Maximum internal pressure	30 psig				
18.				Minimum internal pressure	full vacuum				
19.				Allowable leak rate @ 1 psig	to be determined				
20.									
21.				Basic external radiation at surface	100 mr/hr				
22.				Local and transient radiation at surface	500 mr/hr				
23.									
24.									
25.									
26.									
27.									
28.									
29.									
30.									
31.									
32.									
33.									
34.									
35.									
36.									
37.									
38.									

NUMBER

REVISION LETTER

PAGE 41

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

SDD-096-81-000

PREPARED BY: J.L.Hedgecock				APPROVED BY:		DESIGN DATA SHEET		TITLE: Fuel Handling Equipment In-Vessel Machine Shielded Gate Valve	
LINE NO.	REVISION			ITEM	DESIGN POINT	REMARKS			
	NO.	DATE	NEW REV						
1.									
2.				Number required	1				
3.				Overall thickness	14.625 in.				
4.				Overall length x width	64 x 38 in.				
5.				Weight					
6.				Transport means	crane				
7.									
8.				Opening and closing time	1 min.				
9.									
10.				Basic external radiation at surface	100 mr/hr				
11.				Local and transient radiation at surface	500 mr/hr				
12.									
13.				Maximum internal pressure	30 psig				
14.				Minimum internal pressure	full vacuum				
15.				Allowable leakage rate @ 1 psig	Included in value given for In-Vessel FHM.				
16.									
17.									
18.									
19.									
20.									
21.									
22.									
23.									
24.									
25.									
26.									
27.									
28.									
29.									
30.									
31.									
32.									
33.									
34.									
35.									
36.									
37.									
38.									

NUMBER

REVISION LETTER

PAGE 42

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation
SDD-096-81-000

PREPARED BY: J.L.Hedgecock				APPROVED BY:		DESIGN DATA SHEET		TITLE: Fuel Handling Equipment Fuel Transfer Port Shielded Gate Valve	
LINE NO.	REVISION			ITEM	DESIGN POINT	REMARKS			
	NO.	DATE	NEW REV						
1.				Number required	2				
2.				Overall thickness	24 in.				
3.				Overall length x width	81 x 59 in				
4.				Weight					
5.				Transport means	crane				
6.									
7.				Opening and closing time	1 min				
8.									
9.				Basic external radiation at surface	100 mr/hr				
10.				Local and transient radiation at surface	500 mr/hr				
11.									
12.				Maximum internal pressure	30 psig				
13.				Minimum internal pressure	full vacuum				
14.				Allowable leakage rate @ 1 psig	Included in value given for Ex-Vessel FHM.				
15.									
16.				Compressive load on valve body	negligible				
17.				Moment load on valve body	negligible				
18.									
19.									
20.									
21.									
22.									
23.									
24.									
25.									
26.									
27.									
28.									
29.									
30.									
31.									
32.									
33.									
34.									
35.									
36.									
37.									
38.									

NUMBER

REVISION LETTER

PAGE 43

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

SDD-096-81-000

PREPARED BY: J L Hedgecock				APPROVED BY:		DESIGN DATA SHEET		TITLE: Fuel Handling Equipment Sweep Arm	
LINE NO.	REVISION			ITEM	DESIGN POINT	REMARKS			
	NO.	DATE	NEW REV						
1.				Number required	1				
2.				Arm extension	about 9½ ft.				
3.				Clear space for arm movement	4 in.				
4.									
5.									
6.									
7.									
8.									
9.									
10.									
11.									
12.									
13.									
14.									
15.									
16.									
17.									
18.									
19.									
20.									
21.									
22.									
23.									
24.									
25.									
26.									
27.									
28.									
29.									
30.									
31.									
32.									
33.									
34.									
35.									
36.									
37.									
38.									

NUMBER

REVISION LETTER

PAGE 44

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation
SDD-096-81-000

PREPARED BY: J.L. Hedgecock				APPROVED BY:		DESIGN DATA SHEET		TITLE: Fuel Handling Equipment Canister	
LINE NO.	REVISION			ITEM	DESIGN POINT	REMARKS			
	NO.	DATE	NEW REV						
1.				Number required	164/year				
2.				Outside diameter	8 inches				
3.				Overall length without cap	about 15 $\frac{1}{2}$ ft				
4.				Overall length with cap	about 16 ft				
5.				Weight	about 300 lb				
6.				Maximum internal pressure		(to be determined)			
7.				Maximum operating temperature	1250°F				
8.									
9.									
10.									
11.									
12.									
13.									
14.									
15.									
16.									
17.									
18.									
19.									
20.									
21.									
22.									
23.									
24.									
25.									
26.									
27.									
28.									
29.									
30.									
31.									
32.									
33.									
34.									
35.									
36.									
37.									
38.									

NUMBER

REVISION LETTER

PAGE 45

ATOMICS INTERNATIONAL
A Division of North American Rockwell Corporation

SDD-096-81-000

6.2 Drawings

The following drawings are a part of this System Design Description.

<u>Figure No.</u>	<u>Title</u>	<u>Page</u>
1	Fuel Flow Diagram 1000 Mwe LMFBF Follow-on Study	47
2	In-vessel FHM Schematic 1000 Mwe LMFBF Follow-on Study	48
3	In-vessel Fuel Handling Machine 1000 Mwe LMFBF Follow-on Study	49
4	In-vessel FHM Grapple 1000 Mwe LMFBF Follow-on Study	50
5	Gantry-mounted Handling Machines 1000 Mwe LMFBF Follow-on Study	51
6	Ex-vessel FHM Schematic 1000 Mwe LMFBF Follow-on Study	52
7	Fuel Transfer Canister 1000 Mwe LMFBF Follow-on Study	53
8	Fuel Handling Sequence 1000 Mwe LMFBF Follow-on Study	54
9	Refueling Cycle Times 1000 Mwe LMFBF Follow-on Study	55
10	In-vessel FHM - Core Element Interface 1000 Mwe LMFBF Follow-on Study	56

FIGURE 1

ALL SURFACES TO BE MACHINED TO SURFACES EXCEPT NOTED

NOTE: ALL FABRICATED PARTS TO BE MADE FROM 304 OR 316 ST. STL. PERIOD

ATOMICS INTERNATIONAL A DIVISION OF UNITED STATES ATOMICS, INC. 1000 MINE LAVER FOLLOW-ON STUDY	
DRAWN BY: CHECKED BY: DESIGNED BY: APPROVED BY:	FIGURE 4 DATE:

SDD-096-81-000
Page 51

*AUTOMATIC
SIPHON PASSAGES*

*CANISTER
CAP*

*WELDED FOR
SHIPMENT OF
SPENT FUEL*

SODIUM LEVEL

8 o.d.

REVISIONS			
BY	DESCRIPTION	DATE	APPROVED

SDD-096-81-000
Page 53

ATOMICS INTERNATIONAL <small>A DIVISION OF NORTH AMERICAN AVIATION, INC. 2500 BOULDER AVENUE, CANOGA PARK, CALIF.</small>			
CANISTER - FUEL TRANSFER 1000 MWe LMFBR FOLLOW-ON STUDY			
<small>DRAWN</small> HEDGECOCK	<small>CHECKED</small> HEDGECOCK	<small>DATE</small> D	<small>FIGURE</small> 7
<small>ENGINEER</small> HEDGECOCK	<small>SCALE</small> 1/1	<small>SHEET NO.</small> OF

1
THE REACTOR SAFETY CAP IS REMOVED WITH THE BUILDING CRANE.

2
FLOOR VALVES ARE INSTALLED WITH THE BUILDING CRANE.

3
SHIELD PLUGS ARE REMOVED WITH THE AUXILIARY HANDLING MACHINE.

4
THE LOWER PART OF THE IN-VESSEL FUEL HANDLING MACHINE IS INSTALLED WITH THE AUXILIARY HANDLING MACHINE.

5
THE UPPER PART OF THE IN-VESSEL FUEL HANDLING MACHINE IS INSTALLED WITH THE BUILDING CRANE.

6
THE IN-VESSEL FUEL HANDLING MACHINE OPERATES WHILE THE EX-VESSEL FUEL HANDLING MACHINE IS AT THE EX-VESSEL STORAGE TANK.

7
THE IN-VESSEL FUEL HANDLING MACHINE IS IDLE WHILE THE EX-VESSEL FUEL HANDLING MACHINE IS AT THE REACTOR.

NOTES:

1. ALL FUEL TRANSFER OPERATIONS ARE DONE WHEN THE REACTOR IS SHUT DOWN.
2. FUEL TRANSFERS WITHIN THE REACTOR VESSEL ARE MADE WITH THE IN-VESSEL FUEL HANDLING MACHINE.
3. INTER-VESSEL FUEL TRANSFERS ARE MADE WITH THE EX-VESSEL FUEL HANDLING MACHINE.
4. ALL HANDLING OPERATIONS WITH THE EX-VESSEL MACHINE ARE DONE WITH ELEMENTS CONTAINED IN CANISTERS

RESUME
FULL POWER
OPERATION

REACTOR SHUTDOWN		PREPARATION STEPS TIME ESTIMATE: 11.9 HR.				BLANKET ELEMENT ROTATION TIME ESTIMATE: .3 HR./ELEM.	TRANSITION STEPS TIME EST.: .3 HR.	BASIC CYCLE TIME ESTIMATE: 1.37 HR./ELEMENT		BASIC CYCLE TIME ESTIMATE: 1.37 HR./ELEMENT		TRANSITION STEPS TIME ESTIMATE: .7 HR.		TERMINATION STEPS TIME ESTIMATE: 25.7 HR.					
REACTOR	COOL REACTOR TO 500°F. (510°F @ 100°F/HR.) TIME = 5.6 HR.																	BRING REACTOR TO TEMP @25% POWER (SLOP @100°F/HR.) - 5.6 HR. MEAS. POWER COEF. @25% 150% POWER-1.0 HR. INCREASE POWER, 25% TO 100% - .7 HR. TIME = 8.0 HR.	
CONTROL RODS & SWEEP ARM	PERFORM ROD DROP TESTS (15@ 10 MIN.) 2.5 HR. DISCONNECT CONTROL RODS (15@ 6 MIN.) 1.5 HR. ROTATE SWEEP ARM. TIME = 4.0 HR.													ROTATE SWEEP ARM RE-CONNECT CONTROL RODS (15@ 6 MIN.) 1.5 HR. PERFORM ROD DROP TESTS (15@ 10 MIN.) 2.5 HR. TIME 4.0 HR.			INSTRUMENTATION CHECKOUT 8.0 HR.	BRING REACTOR TO CRITICALITY - 1.5 HR. PARTIALLY CALIBRATE CONTROL ROD(S) - 1.0 HR. TIME = 2.5 HR.	
BUILDING CRANE	REMOVE REACTOR CAP TIME = 40 HR.	SET 2 FLOOR VALVES IN PLACE AT REACTOR. TIME = 2.0 HR.		INSTALL TOP SECTION OF IN-VESSEL FUEL HANDLING MACHINE. TIME 4.1 HR.									REMOVE TOP SECTION OF IN-VESSEL FUEL HANDLING MACHINE. TIME < 4.1 HR.		REMOVE 2 ROD VALVES FROM REACTOR TOP SHIELD TIME = 1.0 HR.	INSTALL REACTOR CAP. TIME = 8.3 HR.			
AUXILIARY HANDLING MACHINE			REMOVE SHIELD PLUG. INSTALL LOWER SECTION OF IN-VESSEL FUEL HANDLING MACHINE. TIME = 1.8 HR.	REMOVE 3 INSTRUMENTATION PORT SHIELD PLUGS. INSTALL 3 IN-VESSEL INSTRUMENTS. REMOVE FUEL PORT SHIELD PLUG TIME = 4.1 HR.									REMOVE FUEL PORT SHIELD PLUG. REMOVE 3 IN-VESSEL INSTRUMENTS. REPLACE 3 INSTRUMENTATION PORT SHIELD PLUGS. TIME = 4.1 HR.	REMOVE LOWER SECTION OF IN-VESSEL FUEL HANDLING MACHINE. REPLACE SHIELD PLUG. TIME = 1.8 HR.					
IN-VESSEL FUEL HANDLING MACHINE					RAISE ELEMENT ROTATE ELEMENT LOWER ELEMENT TIME = 19 MIN./ELEM.	TRANSFER OLD FUEL FROM CORE TO STORAGE TIME = 18 MIN.	TRANSFER NEW FUEL FROM STORAGE TO CORE TRANSFER OLD FUEL FROM CORE TO STORAGE TIME = 40 MIN.		TRANSFER NEW FUEL FROM STORAGE TO CORE TRANSFER OLD FUEL FROM CORE TO STORAGE TIME = 40 MIN.		TRANSFER NEW FUEL FROM STORAGE TO CORE.								
EX-VESSEL FUEL HANDLING MACHINE						AT STORAGE: — — PICK UP NEW FUEL TIME = 17 MIN.	AT REACTOR: PUT DOWN NEW FUEL RE-INDEX PICK UP OLD FUEL TIME = 42 MIN.	AT STORAGE: PUT DOWN OLD FUEL RE-INDEX PICK UP NEW FUEL TIME = 34 MIN.	AT REACTOR: PUT DOWN NEW FUEL RE-INDEX PICK UP OLD FUEL TIME = 42 MIN.	AT STORAGE: PUT DOWN OLD FUEL RE-INDEX PICK UP NEW FUEL TIME = 34 MIN.	AT REACTOR: PUT DOWN NEW FUEL TIME = 21 MIN.								
MAXIMUM OF OPERATION TIMES	4.0 HR.	2.0 HR.	1.8 HR.	4.1 HR.	19 MIN./ELEM.	18 MIN.	42 MIN./ELEM.	40 MIN./ELEM.	42 MIN./ELEM.	40 MIN./ELEM.	21 MIN.	22 MIN.	4.1 HR.	1.8 HR.	1.0 HR.	8.3 HR.	2.5 HR.	8.0 HR.	

TIME SUMMARY

$$TIME = 57.6 + 1.37 N_E + .3 N_R + N_V \quad (\text{HOURS})$$

WHERE:

N_E = NO. OF ELEMENTS EXCHANGED
 N_R = NO. OF ELEMENTS ROTATED
 N_V = NO. OF TIMES FLOOR VALVE
IS MOVED.

NOTES:

1. TIMES SHOWN DO NOT INCLUDE
AN ALLOWANCE FOR "CURING"
OR "SINTERING" NEW FUEL
ELEMENTS.

ATOMICS INTERNATIONAL*A Division of North American Rockwell Corporation***SUPPORTING DOCUMENT**

NUMBER

SDD-096-90-000

REV

LTR B

DOCUMENT TYPE

System Design Description

PROGRAM TITLE

ANL 1000 Mwe IMFBR Follow-on Study

KEY NOUNS

Land and Structures

DOCUMENT TITLE

Land, Structures and Conventional Systems
Segment Conceptual System Design Description -
1000 Mwe Follow-on Study

ORIGINAL

ISSUE DATE October 24, 1967

GO NO.

7692

S/A NO.

13120

PAGE 1 OF

TOTAL PAGES 67

REL. DATE

ABSTRACT

This Conceptual SDD presents the design requirements for, and a brief description of, the Land, Structures and Conventional Systems Segment for the 1000 Mwe IMFBR Follow-On Study

PREPARED BY

DATE

DEPT/GRP NO.

C. V. DiPol

731-15

APPROVALS

DATE

Spvr: H. B. Holz

Proj. Engr: D. F. Casey

Prog. Off: R. E. Aronstein

SECURITY CLASSIFICATION

(CHECK ONE BOX ONLY)

(CHECK ONE BOX ONLY)

UNCL.

AEC

DOD

RESTRICTED

CONF.

☐☐

DATA

SECRET

☐☐

DEFENSE

INFO.

AUTHORIZED
CLASSIFIER

DATE

DISTRIBUTION

REV

SUMMARY OF CHANGE

APPROVALS AND DATE

*

NAME

LOC

* TITLE PAGE ONLY

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 2 OF

TABLE OF CONTENTS

	<u>Page</u>
1. INTRODUCTION	3
1.1 Functional Requirements	3
1.2 Summary Description	5
1.2.1 Site	5
1.2.2 General Plant Arrangement	6
1.3 Requirements	6
1.3.1 Performance	6
1.3.2 Environment	10
1.3.3 Reliability	13
1.3.4 Maintenance	13
1.3.5 Operation	14
1.3.6 Safety	14
1.3.7 Design Criteria	15
1.3.8 Interfaces	49
2. DETAILED DESCRIPTION	50
3. PRINCIPLES OF OPERATION	58
4. SAFETY PRECAUTIONS	58
4.1 Personnel Control	58
4.2 Radiation Shielding	59
4.3 Radiation Detection and Alarm System	59
4.4 Containment Structure	59
5. MAINTENANCE	60
5.1 Preventive Maintenance	60
5.2 Leak Rate Tests	60
6. APPENDIX	61
6.1 Drawings	61
6.2 References	61

CONCEPTUAL SYSTEM DESIGN DESCRIPTION
LAND, STRUCTURES, AND CONVENTIONAL SYSTEMS
SEGMENT

1. INTRODUCTION

1.1 Functional Requirements

The primary functions of the Land, Structures and Conventional Systems Segment are as follows:

- a) Provide a suitable environment for the reliable operation, and maintenance of the plant and the storage of equipment, and for the comfort and safety of personnel.
- b) Control the release, within acceptable limits, of any material or radiation that is injurious to the health and safety of the populace.

The reactor building has several subsidiary functions which must be achieved to meet the primary functions:

- (1) Capability to withstand peak transient pressures which could occur during the postulated accident.
- (2) Capability to maintain the functional integrity of the system indefinitely after the postulated accident.
- (3) Capability to withstand, without loss of function, the additional forces that might be imposed by natural phenomena such as earthquake, wind loadings, and other local site effects.
- (4) Protection of the system against credible missiles from internal or external sources which could directly or indirectly endanger the integrity of the containment.
- (5) Capability of limiting leakage during and following the postulated accident to values which are substantially less

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 4 OF

than leakage rates which would result in off-site doses approaching the reference doses in 10CFR100.

- (6) Capability of periodically conducting such leakage tests as may be appropriate to verify the integrity of the containment.
- (7) Capability for rapid closure or isolation of all pipes or ducts which penetrate the containment by means which provide a barrier as effective as is required to maintain leakage within permissible limits.

1.1.1 Items Included

This CSDD includes requirements for site & structures comprising the fixed installations, and the associated site utilities and building services. The major items included consist of

- a. Grading, paving, yard structures and utilities.
- b. All reinforced concrete and structural steel building structures, including the foundations, building shells, internal vault and cell structures, access locks and hatches, doors and windows, access stairways and ladders and facility equipment support structures.
- c. Containment liners.
- d. Penetration sleeves through containment barriers.
- e. Building cranes, manipulators, and supports.
- f. Heating, ventilating, and air conditioning systems, including containment recirculation system.
- g. Inert gas systems for the building areas.
- h. Plant and instrument air systems.
- i. Fire protection systems.

The design of the Site, Structures and Services must accommodate various systems and components of other plant segments, whose

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 5 OF

detailed requirements appear in other SDD's. The major items which must be accommodated, but are not included in this SDD, are as follows:

- a. Reactor segment items including the reactor structure and vessel, the loading face shield, and the reactor cavity liner.
- b. Support System Segment items including fuel handling and fuel storage systems.
- c. Heat Transfer Segment items including pumps, IHX, process equipment, piping, and piping and equipment supports.
- d. Auxiliary Systems Segment including process equipment, piping, and piping and equipment supports.
- e. Control and Instrumentation Segment items.
- f. Energy Conversion Segment items, including turbine generators, condensers and related equipment.

1.2 Summary Description

1.2.1 Site

An accurate description of the site cannot be provided until an actual site has been selected. However, in order to prepare a conceptual design of the plant, general site data has been assumed. These assumptions are used as criteria for the design of the applicable portions of the plant.

The assumed site lies along the bank of a navigable river. The land is relatively flat, clear of existing structures, and is above flood level. Good secondary roads and a railroad spur are available at the site boundary. The ground is easily excavated down to a depth of 100 feet: No blasting is required.

Site temperatures for design purposes range from 90° DB, summer to 0° DB, winter. Cooling water is available at 55°F, in a supply adequate for all plant cooling requirements, including main condenser cooling.

Seismic conditions at the site conform to seismic zone 1 conditions.

1.2.2 General Plant Arrangement

The overall plant and building arrangement is shown on Drawing No. NO9690008. The orientation of the plant on the site is representative of a typical plant layout. The actual relationship of the power plant to the river, railroad, and highway access will be dependent on the site selected.

The principal buildings comprising the plant are: The reactor building, secondary sodium and steam generator building, turbine generator building, reactor auxiliary, and water treatment. The arrangement and relationship of the buildings is established to maintain the natural flow pattern of the system from the reactor and primary sodium system, through the secondary sodium system and steam generator to the turbine generator. The arrangement is as close-coupled as practical to minimize piping runs and operating and construction costs. The arrangement also provides a natural separation of the fuel handling facilities from the sodium process portions of the plant.

The plant control area is centrally located, adjacent to both the reactor building and turbine-generator building. The close-in building housing the control room serves to minimize power and control wiring while still permitting full time occupancy during all normal or emergency conditions of the plant.

The basic plant arrangement is such that a second unit could be added at a later date with minimum cost and disturbance to the existing unit and with maximum use of existing facilities which could serve both units.

Railroad access will be provided to the turbine generator building, switchyard, sodium unloading area, and fuel handling building.

1.3 Requirements

1.3.1 Performance

1.3.1.1 Design Life All buildings, structures, and site service facilities shall be designed for a useful life of 30 years, assuming normal maintenance.

1.3.1.2 Functional Criteria

Normal Conditions: During normal operation of the plant, the site and all structures shall maintain a suitable operating environment and adequately resist all dead loads; operating loads; and commonly occurring natural phenomena without causing a loss of coolant accident; and to minimize plant shutdown; scram; or interruption of power generation.

Emergency Conditions: During, and subsequent to, abnormal or emergency conditions, the Reactor Building shall adequately resist all dead loads, operating loads, emergency (Containment Design Bases (CDB)) loads, and credibly occurring natural phenomena without resulting in the uncontrolled release of excessive amounts of radioactivity. During these conditions, the Reactor Building shall continue to function under all stresses imposed so that a safe, controlled plant shutdown can be made.

1.3.1.3 Reactor Building Containment Design Basis: A two-barrier containment concept shall be provided to adequately limit the release of radioactivity from the Reactor Building to the atmosphere during and subsequent to the Design Basis Accident (DBA), sodium fire accidents, and fuel handling accidents such that the integrated radiation doses at the exclusion and low population boundaries from all sources shall not exceed the allowable values given in the Code of Federal Regulations, Title 10, Part 100.

1.3.1.4 Leak Tightness

a. First Containment Barrier: The leakage rate of the first containment barrier (reactor cavity, primary heat transfer cells, drain tank cell and containment dome), including all penetrations, shall not exceed 10.0 percent by weight of the contained gas per 24 hours at an internal pressure of 20 psig. This leak rate shall be met under all emergency loading conditions, including earthquake.

b. Second Containment Barrier: The leakage rate of the second containment barrier (building envelope), including all penetrations, shall not exceed 0.5 percent by weight of the contained air per 24 hours at an internal pressure of 10 psig. This leak rate shall be met under all emergency loading conditions, including earthquake.

c. Leakage Rate Testing: Both barriers shall be designed so that containment can be leak tested to design pressure conditions after completion and installation of all penetrations, and the leakage rates measured over a suitable period to verify conformance with required performance. In addition, the design of the containment barriers shall permit later periodic leak rate tests at design or reduced pressures. The reduced pressures shall be determined by measuring leakage rate vs. pressure characteristics during the initial test program upon completion of construction. Leakage tests shall be conducted in accordance with ANS Standard 7.60, "Leakage Rate Testing of Containment Structures."

1.3.1.5 Thermal Pollution of Plant Cooling Water The design of the plant shall be such that, during all normal operating conditions, the plant cooling water source shall not be unacceptably thermally polluted. For conceptual design purposes, this cooling water source is assumed to be a river, large enough to provide all the required cooling capability without introducing a thermal pollution problem.

1.3.1.6 Design Margins

1.3.1.6.1 Structural Stress Margins

a) Class I Structures: Those systems, components or structures, or parts thereof, whose failure might cause or increase the severity of a loss of coolant flow accident or result in the uncontrolled release of excessive amounts of radioactivity; or which are vital to a proper shutdown of the plant and removal of decay heat.

1) Normal Conditions: The maximum stresses in structures shall be limited to code allowables as established by the ACI Building Code Requirements for Reinforced Concrete; the AISC Manual of Steel Construction; and the ASME Boiler and Pressure Vessel Code, under

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 9 OF

all conditions or normal loading, including earthquakes. For reinforced concrete structures, code allowable stresses are nominally 40% to 50% of yield stress, and for steel structures code allowables are nominally 60% of yield stress. Therefore, under these loadings, the structures will have a safety factor of 1.6 to 2.5 based on yield stresses. Both the ACI and AISC building codes permit a 33-1/3% increase in allowable stresses when earthquake loads are combined with other loads. By not utilizing this increase, an additional stress margin of 33%, when compared to code allowables will be realized under earthquake loading conditions.

2) **Emergency Conditions:** Due to the variety of possible loading combinations under emergency conditions, and the fact that some emergency loading conditions would be of short term duration and are only remotely possible, design stress margins shall be adjusted to suit the magnitude, duration, and probability of the loading conditions. The stress margin shall vary from the same value as for normal operating conditions to a minimum value of 5% of yield stress under the worst combination of loadings (dead loads, live loads, CDB Pressure loads, maximum hypothetical earthquake loads, and thermal stress loads). As an additional design margin under these loading conditions, materials used shall have a ductility sufficient to permit displacements 3.5 times yield point displacements without failure, and brittle materials shall not be used.

b) **Class II Structures:** All other portions of the plant not falling into Class I. Allowable stresses used in the design shall be those specified in the applicable codes and standards. This results in safety margins of between approximately 1.6 and 2.5 on minimum material yield stress.

1.3.1.6.2 Mechanical

Heating, Ventilating, and Air Conditioning:

Estimated heating and cooling loads: +10%.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 10 OF

1.3.2 Environment

1.3.2.1 External Environment Until an actual site has been selected, the following environmental conditions shall be considered design requirements:

1.3.2.1.1 Atmospheric Design Temperature

Summer: 90°F dry bulb; 78°F wet bulb,
5 mph wind

Winter: 0°F dry bulb, 15 mph wind

1.3.2.1.2 Geology

Soil conditions at the site will permit conventional excavation (no blasting) to a depth of 100 ft without requiring dewatering or sheet pilings. Allowable soil bearing values at 5 ft below grade or deeper shall be at least 6000 lb per sq. ft.

1.3.2.1.3 Seismology

The site is located in a seismic zone 1 as defined by the Uniform Building Code.

1.3.2.1.4 Hydrology

The plant is located above the flood zone. Ground water level is a minimum of 60 ft below grade.

1.3.2.1.5 Site Altitude

Site altitude of 1500 ft above sea level.

1.3.2.1.6 Meteorology and Climatology

Meteorological conditions for site dose: Pasquill Type F, 1 m/sec wind speed.

Wind Pressure: UBC 25 psf wind-pressure - map zone.

Snow Load: 15 psf on horizontal projection.

1.3.2.1.7 Population Data:

As indicated in AEC TID 7025, Vol. I, Section 110.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 11 OF

1.3.2.2 Internal Environment

1.3.2.2.1 Reactor Building

a) Normal Conditions

Air Atmosphere Areas: High bay, fuel encapsulating cell operating area, R/A waste room, personnel access locks.

Atmosphere: Air
Temperature: 100°F Max, 60°F Min.
Pressure: $-\frac{1}{4}$ " W.G. with respect to
outside atmosphere

Radiation Levels: Nominally 1.0 mr/hr in
normally occupied areas with
25 mr/hr maximum in
localized areas

Inert Gas Atmosphere Areas: Reactor cavity,
primary heat transfer cells, containment dome, drain tank cell, cold trap
cell, service pipe cell, EM pump cell and fuel encapsulating cell

Atmosphere: Nitrogen - 2% max. oxygen content
Temperature: 150°F Max
Pressure: Reactor cavity - $\frac{1}{2}$ " W.G.
Remaining areas - $\frac{1}{4}$ " W.G.

b) Emergency Conditions

Emergency environmental conditions can occur
throughout the building. Limiting cases will be set by either a nuclear
accident (DBA), a major sodium fire or a fuel handling accident, or
combinations thereof.

Post Nuclear DBA Environment

High Bay and Other Normally Accessible Areas:

Atmosphere: Air containing radioactive
fission product and gases
Temperature: Max of 100°F
Pressure: Max of 1.2 psig

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 12 OF

Reactor Cavity, Primary Cells, Containment Dome and Drain Tank Cells:

Atmosphere: Nitrogen containing radioactive sodium, fission products and gases, and possibly fuel or reactor structure particles or vapors

Temperature: Average peak gas temp. of 640°F in cavity and galleries, peak gas temp. of 1000°F in containment dome.

Pressure: Max of 20 psig in cavity and galleries
Max. of 25 psig in containment dome.

Post Sodium Fire Accident Environment

High Bay and Other Normally Accessible Areas:

Atmosphere: Air containing sodium vapor, sodium oxide, and smoke

Temperature: Max air temp. of 275°F

Pressure: Less than 10 psig.

Reactor Cavity, Primary Cells, and Drain Tank Cell:

Atmosphere: Nitrogen-containing sodium vapor, sodium oxide, and smoke

Temperature: Max. air temp. of 580°F

Pressure: Less than 10 psig.

1.3.2.2.2 R/A Waste Area in the Reactor Aux. Bldg.

This area will normally contain radioactively contaminated materials and/or equipment. For this reason the internal air atmosphere within the area shall be normally maintained at a pressure slightly lower than atmospheric to insure in-leakage rather than uncontrolled out-leakage.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 13 OF

1.3.2.2.3 Other Buildings With the exceptions noted in the previous paragraphs, the internal environment within all buildings throughout the plant may be considered 'normal' for an industrial plant. The internal environment will be controlled by standard industrial H&V and air conditioning equipment to provide environmental conditions suitable for the comfort of personnel and the service intended.

1.3.2.3 Design Loads Design loads are specified in the applicable paragraphs of the Design Criteria Requirements, Section 1.3.7 of this SDD.

1.3.3 Reliability/Availability

All structures, systems, and equipment of the Site, Structures and Services Segment shall be designed so that the unavailability shall be 0.3% for unscheduled equipment or system outages that could be the sole cause of cessation of generation of demand power.

1.3.3.1 Vital Supply Systems All vital supply systems such as inert gas supply, electrical power supply, etc., which must be operable during normal plant operation and during DBA conditions shall be located outside the Reactor Building.

1.3.3.2 Leakage Rate Tests Integrated leak rate tests on the containment barriers shall be scheduled to coincide with periods of normally scheduled plant shutdown.

1.3.4 Maintenance

Any structure, system or equipment that is essential to the generation of demand power shall be designed to be maintained or repaired while the plant is generating demand power. Equipment to be located inside the Reactor Building shall be held to a minimum. Any equipment that need not be located inside containment for proper operation shall be located outside of containment. If any equipment is inaccessible during normal plant operation, preventive maintenance or repair shall be accomplished during scheduled plant shutdown periods, and any such equipment shall be designed such that the frequency of preventive maintenance action is no greater than scheduled plant shutdown.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 14 OF

1.3.4.1 Procedures and Manuals Maintenance and operations procedures and manuals shall be prepared for all building systems and equipment.

1.3.5 Operational Requirements

Operational requirements are covered in other paragraphs of this SDD.

1.3.6 Safety

1.3.6.1 Industrial Safety All building, structures, and site service facilities shall be designed in accordance with all safety codes and standards applicable to the types of construction and plant operating procedures involved.

1.3.6.2 Radiation Safety

1.3.6.2.1 Containment: The Reactor Building, particularly the containment barriers, is one of the more important engineered safeguards for the entire plant. The containment barriers represent the last boundary preventing the uncontrolled release of radiation to the public. The containment structures shall provide a protective capability beyond the capability of the core and coolant boundary for accommodating the abnormal. The structures shall be designed to sustain the initial effects of gross equipment failures without loss of required integrity and, together with other engineered safeguards as may be necessary, to retain for as long as the situation requires the functional capability to protect the public.

1.3.6.2.2 Site Exclusion Area: The site exclusion boundary shall be established such that the combined radiation dose during the DBA from all sources (direct radiation plus leakage) does not exceed the allowable values given in the Code of Federal Regulations, Title 10, Part 100. For conceptual design purposes it shall be considered a design requirement that the site exclusion radius is a maximum of 0.4 miles.

The area within the site boundaries shall be considered a "restricted area" as defined by the U.S. Code of

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 15 OF

Federal Regulations, Title 10, Part 20.

1.3.6.2.3 Personnel Protection The design of all buildings or facilities containing radioactive material or subject to radioactive contamination shall be such that the radiation doses received by plant personnel during normal plant operation shall not exceed the allowable values given in the Code of Federal Regulations, Title 10, Part 20.

Shielding shall be provided as necessary to protect plant personnel in the event of the DBA. Such shielding shall be provided at all locations to which access is required during the course of the accident to maintain the plant in a safe condition.

1.3.6.2.4 Plant Effluents The design of the entire plant and all its systems and facilities shall be such that any plant effluent, gaseous, liquid or solid, shall conform to the requirements of the Code of Federal Regulations, Title 10, Parts 20 and 100.

1.3.7 Design Criteria Requirements

1.3.7.1 Applicable Codes and Standards The following documents, of the latest edition or revision, form a part of this SDD to the extent specified. In the event of conflict between any of the documents referred to here or between the documents and other detail content of this SDD, the more stringent requirement shall govern.

Specifications and Standards

Federal

U.S. Code of Federal Regulations Title 10, Part 20	"Protection Against Radiation"
---	-----------------------------------

U.S. Code of Federal Regulations Title 10, Part 50	"Licensing of Production & Utilization Facilities," including Proposed Appendix A, "General Design Criteria for Nuclear Power Plant Construction Permits"
---	--

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 16 OF

U.S. Code of Federal Regulations "Reactor Siting Criteria"
Title 10, Part 100

U.S. Public Health Service Manual of Recommended Water
Publication 525 Sanitation Practice

U.S. Weather Bureau Technical
Paper No. 25

Society

International Conference of Building Officials, Uniform
Building Code

American Association of State Highway Officials: Standard
Specification

American Railway Engineering Association: Manual of
Design and Practices

American Institute of Steel Construction: Specification for
the Design, Fabrication and Erection of Structural Steel
for Buildings

American Iron and Steel Institute: Light Gage Steel Design
Manual

Steel Joist Institute: Standard Specifications for Open Web
Steel Joist Construction

Research Council on Riveted and Bolted Structural Joints:
Specifications for Structural Joints Using ASTM 5325 Bolts

American Welding Society: Code for Welding in Building
Construction, AWS D1.0

National Electrical Manufacturer's Standards

Institute of Electrical and Electronic Engineers Standards

National Fire Protection Association

American Concrete Institute: Building Code Requirements
for Reinforced Concrete, ACI 318

American Concrete Institute: Manual of Standard Practice
of Detailing Reinforced Concrete Structures, ACI 315

National Bureau of Standards: American Standard Building
Code Requirements for Masonry

USA Standards: American Standard Building Code Require-
ments for Minimum Design Loads, Buildings and other
Structures, USA 58.1

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 17 OF

American Society for Testing Materials, Material Specification.

American Society of Heating, Refrigerating and Air Conditioning, ASHRAE Guide

Factory Insurance Association: Standards

U.S.A. Standards: Electrical Standards

U.S.A. Standards: Code for Pressure Piping, USA B31

American Society of Mechanical Engineers: Boiler and Pressure Vessel Code

American Nuclear Society: Proposed Standard 7.60, Leakage Rate Testing of Containment Structures

U.S.A. Standards: Safety Code for Cranes, Derricks and Hoists, USA B30.2

Electrical Overhead Crane Institute, Specification No. 49

Illuminating Engineering Society Design Handbook

National Electrical Code

Atomics International

SDD-096-10-000: Overall System Design Description for the 1000 Mwe LMFB

1.3.7.2 Siting and Arrangement Criteria

1.3.7.2.1 General The plant shall be arranged on the available site in the most economical and efficient manner, taking into consideration such factors as radiation safety, operations, economy, local topography, process relationships, personnel and material flow.

1.3.7.2.2 Future Expansion The plant shall be arranged on the site in such a manner as to permit orderly expansion by the addition of future plants of the same or larger capacity. Attention shall be given to arrangement of buildings to facilitate future expansion and common use of facilities by subsequent plants.

1.3.7.3 Civil Criteria

1.3.7.3.1 Subsurface Soil Information All necessary soil surveys shall be made to properly design a functional, safe, and economical facility. The surveys shall include necessary tests for the

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 18 OF

proper design of access areas, fill, buildings and equipment foundations, and subsurface structures.

1.3.7.3.2 Grading and Drainage All temporary grading, final grading, borrow pits and waste dumps shall be located and designed to avoid infringing upon or endangering neighboring property, or impair overall master plan development. All surface and subsurface drainage shall be directed into natural, existing or planned water courses. Sub-surface drainage, which may become contaminated or radioactive, shall be impounded and monitored prior to release to normal effluent systems. The facility shall be designed for a "once-in-ten-year" storm as defined by the U.S. Weather Bureau, Technical Paper No. 25. Evaluation shall be made of the possibility and magnitude of flooding at the plant site, and the consequences of any feasibly possible flooding shall be considered in plant design.

1.3.7.3.3 Roads and Access Areas Access roads to and within the facility, and storage parking and access areas shall be designed for American Association of State Highway Officials H20-S16 wheel loads, or for the mobile equipment to be used in connection with the facility, whichever is heavier. All such areas shall be paved with asphaltic concrete.

a) Road Widths Road widths shall be suitable for intended usage and traffic. Intra-plant roads shall be designed for a vehicular speed of 35 miles per hour.

b) Parking Paved parking areas shall be provided for plant operating personnel and for ten visitor vehicles. Parking for operating personnel shall be convenient to work locations. Parking for visitors shall be adjacent to the Administration Building.

c) Walks Paved walks shall be provided for pedestrian traffic between plant facilities as required. Walks shall be paved with either asphaltic concrete or portland cement concrete, whichever is more appropriate for anticipated traffic.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 19 OF

1.3.7.3.4 Railroad Spur A railroad spur shall be provided to the plant from the nearest point of connection of the serving railroad. The spur shall service the Fuel Handling Building, the Turbine Building, the Electrical Switchyard and Sodium Unloading Station.

Design of the railroad spur shall conform to the standards of the serving railroad for comparable tracks, supplemented as required by the Manual of Design and Practices of the American Railway Engineering Association.

1.3.7.3.5 Utilities

a) Domestic Water Supply Domestic water shall be supplied by the deep well system which also supplies plant feedwater. The raw water shall be suitably treated for human consumption in accordance with requirements of U.S. Public Health Service Publication 525, and shall be distributed to the plant buildings in the most economical manner consistent with topography.

b) Sewage Treatment All sewage shall receive primary and secondary treatment prior to release into natural existing, or planned water courses.

1.3.7.3.6 Exterior Fire Protection A fire protection water system shall be provided. This shall be a buried pipe loop system which distributes firewater to the plant buildings and fire hydrants. The system design shall conform to the applicable requirements and standards of the National Fire Protection Association.

1.3.7.3.7 Intake Structure and Canal The intake structure and canal shall serve to channel plant cooling water and to house the plant cooling and fire protection water pumping equipment.

The intake canal shall be sized for anticipated flows and supply water levels. The canal shall be lined with reinforced portland cement concrete, either cast-in-place or sprayed-in-place. Means shall be provided to prevent erosion of sidewall embankments.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 20 OF

The intake structure shall be constructed of reinforced concrete. The structure shall house the various pumps and equipment associated with the plant cooling and fire protection water systems. Structure size shall be sufficient to contain the equipment and normal facilities, with traveling screens, bar racks and stop logs to control and prevent the entrance of trash and other foreign matter into the pump suction area.

1.3.7.3.8 Cooling Water Discharge A below grade structure, tunnel and open canal shall be provided to discharge the plant cooling water.

The below grade structure and tunnel shall be constructed of reinforced concrete and shall serve to collect the cooling water discharge from the plant and route the discharge through the tunnel to the open canal. Structure and tunnel size shall handle anticipated volumes and flow rates.

The discharge canal shall route the discharge cooling water to the river. The canal shall be sized for anticipated volumes and flow rates, and shall be located and oriented with relation to the intake structure such that there is no possibility of "short-circuiting" flow of the plant cooling water. The canal shall be lined with reinforced portland cement concrete, either cast-in-place or sprayed-in-place, and shall be provided with a weir or other suitable feature to control discharge flow volume and rate into the river. Means shall be provided to prevent erosion of sidewall embankments.

1.3.7.3.9 Service Areas and Yard Structures
Service areas and yard structures shall be provided as required.

a) Service Areas Service areas shall be sized and located in accordance with intended use. Surfaces shall be paved, graveled or stabilized as required.

b) Yard Structures Yard structures such as gate houses, etc., shall be provided as required. The structures shall be suitable for intended use.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 21 OF

1.3.7.3.10 Fencing Fencing shall be provided at the plant exclusion boundary and around service or yard areas as required. Vehicular and pedestrian gates with locks shall be provided where required.

1.3.7.4 Architectural Criteria

1.3.7.4.1 Personnel Occupancy The plant will be operated on a 3 shift per day, 24 hour continuous basis. Estimated total operating staff is 80 people, broken down as follows:

Operational personnel	30
Maintenance personnel	16
Technical Staff	18
Administrative Services	16
Total Operating Staff:	80

Design of personnel service facilities such as toilets, lockers, parking, etc., shall be based upon a total of 100 operating personnel and a maximum of 20 visitors.

1.3.7.4.2 Training Facility Classroom instruction space shall be provided within, or near, the Administration Building, to be used primarily for personnel training. The space provided shall seat at least 35 people and shall be equipped to project visual aids.

1.3.7.4.3 Building Classification For purposes of design, the various buildings of the plant have the following "occupancy" classification, as defined by the Uniform Building Code. As a minimum requirement, all construction shall be Type IV (incombustible throughout), as defined by the Uniform Building Code.

Reactor Building	Not Applicable
Fuel Handling and R/A Waste Bldg	Not Applicable
Secondary Sodium and Steam Generator Bldg	Not Applicable
Turbine Generator Building	Occupancy Class G
Administration Building	Occupancy Class F

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10/24/67

PAGE 22 OF

Control Building	Occupancy Class F
Boiler Building	Occupancy Class G
Heating & Ventilating Bldg	Occupancy Class G
Service Building	Occupancy Class G

1.3.7.4.4 Building or Area Occupancy All buildings and structures inside the site boundary fence are in a "restricted area" as defined by 10CFR20. The various buildings and areas within buildings shall be capable of being occupied in accordance with the following requirements. Radiation exposure to operating personnel shall not exceed the limits established by 10CFR20.

a. Definition of Area Radiation Classifications:

All areas of the plant are classified according to radiation levels, as listed in this paragraph. The radiation levels assigned to each classification provide a basis for the design of the plant shielding. Generally, the names of the areas conform to those defined in 10CFR20; however, the allowable radiation levels are somewhat lower. The radiation levels established for design purposes are based on a maximum normal (non-accident situation) dose rate of 1 mr/hr for a 40 hour week, 50 week/yr schedule. This provides a safety factor of 2.5 with respect to the dose rate of 1-1/4 R/quarter permitted by 10CFR20.

Area Classification	Allowable Radiation Dose Rate	Description
1. Unrestricted Area	0.5 R/yr or 0.2mr/hr	Area outside the site boundaries
2. Restricted Area		Area within the site boundaries
a. Routine Access Area	1 mr/hr	Area accessible for routine work on a 40-hr week basis

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000DATE 10/24/67PAGE 23 OF

Area Classification	Allowable Radiation Dose Rate	Description
b. Radiation Area	1 mr/hr to 100 mr/hr	Area accessible only with H.P. permission and control. H.P. rep. not necessarily present during work in this area.
c. High Radiation Area	100 mr/hr to 3.6 R/hr	Area accessible only with H.P. permission and control. H.P. present during work in this area.
d. Inaccessible Area	> 3.6 R/hr	No entry permitted under any circumstances. Entry barred by physical barriers and administrative control.

b. Building Space Classifications: The various spaces within the plant shall conform to the area requirements defined above, in accordance with the following table:

Building/Area	Normal Plant Operation	Reactor Shutdown Periods	Emergency Conditions
REACTOR BLDG High Bay	Radiation Area	Radiation Area	High Radiation Area or Inaccessible
Fuel Encapsulating Cell Operation Area	Radiation Area	Radiation Area	High Radiation Area or Inaccessible
Containment Dome	Inaccessible	Radiation Area	Inaccessible
Reactor Cavity	Inaccessible	Inaccessible	Inaccessible
Primary Heat Transfer Cells	Inaccessible	Radiation Area	Inaccessible
Drain Tank Cell	Inaccessible	Radiation Area	Inaccessible
Service Pipe Cell	Inaccessible	Radiation Area	Inaccessible

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000DATE 10/24/67PAGE 24 OF

Building/Area	Normal Plant Operation	Reactor Shutdown Periods	Emergency Conditions
R/A Waste Room	Radiation Area	Radiation Area	High Radiation Area or Inaccessible
Cold Trap Cell	Inaccessible**	Radiation Area	"
EM Pump Cell	Inaccessible**	Radiation Area	"
CONTROL BLDG	Routine Access Area	Routine Access Area	Radiation Area
FUEL HANDLING & R/A WASTE BLDG			
Fuel Handling Areas	Routine Access	Routine Access	High Radiation Area or Inaccessible
R/A Waste Areas	Radiation Area	Radiation Area	High Radiation Area
H&V BLDG	Routine Access	Routine Access	High Radiation Area
ALL OTHER BLDGS	Routine Access	Routine Access	Radiation Area

**Individual cells shall be accessible as Radiation Areas during normal plant operation after isolation and suitable decay or drainage of the system.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 25 OF

c. Radiation Monitoring All accessible areas shall be provided with radiation monitors and alarms.

d. Personnel Traffic:
Traffic to "radiation areas" shall be physically channeled such that all entering and leaving personnel must be monitored and/or controlled by health physics procedures and equipment such as film badges, protective clothing, etc. Where emergency exits from radiation areas are required for safety, the exits shall be designed to be openable only from the inside and shall be automatically closed.

e. Outside Areas:
When "radiation areas" are outside of building enclosures, physical barriers such as fences and locked gates shall be used to prevent accidental personnel exposure. An example of such areas would be an outdoor storage yard for radioactive waste awaiting disposal, or areas within shielded enclosures surrounding major reactor building piping penetrations.

1.3.7.4.5 Building Dimensions All buildings and structures, and internal rooms and areas, shall be sized to contain all equipment and operation personnel, and to permit safe, efficient, and orderly installation, operation, maintenance, and repair of all systems and equipment.

1.3.7.4.6 Personnel and Equipment Access
Personnel and equipment access shall be provided to all buildings and areas. Equipment access openings shall be sized to handle the largest piece of equipment, plus conveyance, that may be removed or replaced during normal plant operation and maintenance. Sizes, location and number of personnel access shall be suitable for anticipated traffic, and, as a minimum shall comply with the requirements of the Uniform Building Code and NFPA.

The design of all buildings, particularly the Reactor Building, shall include provisions for installation of large items of equipment that would not normally be removed but which are installed within the buildings either during or after building construction.

a. Reactor Building Access

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 26 OF

(1) Personnel and Small Equipment

Access to the Reactor Building during reactor operation shall be via air locks which permit entrance and exit while remaining capable of withstanding the design overpressure and meeting the leakage rate requirements of the containment barrier being penetrated. Lock sizes shall be adequate to permit passage of personnel, equipment, fuel transfer cask, and conveyance vehicles such as a small fork lift or dolly.

(2) Large Equipment Access to the Reactor Building during plant construction and reactor shutdown periods shall be via a large equipment hatch that is normally closed and sealed during reactor operation. The hatch shall be designed to withstand the design overpressure and meet the leak rate requirements of the containment barrier being penetrated. The hatch size shall be adequate to permit passage of large equipment such as an IHX, reactor vessel, or fuel handling machine, plus a conveyance such as an AASHO-H2O-S16 truck.

(3) Manlift A manlift shall be provided to service the various working levels in the operating areas below the main operating floor.

b. Stairs and Ladders Stairs and ladders shall be provided as required to service all working levels, permit efficient traffic flow, and satisfy all fire and safety requirements.

1.3.7.4.7 Interior Finishes Interior finishes shall be suitable for intended area usage. Consideration shall be given to economy, appearance, serviceability and maintainability. Exposed construction shall be utilized wherever practicable.

Contaminated Areas Exposed interior surfaces in potentially contaminated areas shall be provided a radiation resistant finish capable of repeated decontamination.

1.3.7.4.8 Exterior Finishes Exposed exterior finishes shall be suitable for protection of the surface from the natural elements. Consideration shall be given to economy, appearance, serviceability and maintainability.

a. Ferrous Metal Exposed ferrous metal surfaces shall either be painted or shall have factory applied finishes or treatments to prevent corrosion.

b. Waterproofing All subsurface structures shall be waterproofed to prevent entrance of groundwater. Special attention shall be given to construction details to preclude any possibility of entrance of groundwater into subsurface areas.

1.3.7.5 Structural Criteria

1.3.7.5.1 General All structural designs shall conform to the applicable provisions of the Uniform Building Code, and shall also conform to the applicable provisions of the following codes and standards:

American Institute of Steel Construction: Specification for the Design, Fabrication and Erection of Structural Steel for Buildings

American Iron and Steel Institute: Light Gage Steel Design - Manual

Steel Joist Institute: Standard Specifications for Open Web Steel Joist Construction

Research Council on Riveted and Bolted Structural Joints: Specifications for Structural Joints Using ASTM A325 Bolts

American Welding Society: Code for Welding in Building Construction, AWS D1.0

American Concrete Institute: Building Code Requirements for Reinforced Concrete, ACI 318

American Concrete Institute: Manual of Standard Practice of Detailing Reinforced Concrete Structures, ACI 315

American Society of Mechanical Engineers: Boiler and Pressure Vessel Code

American Society for Testing Materials: Applicable Material Specifications

1.3.7.5.2 Design Loadings

a. Structural Design Loads

(1) External Loads Based on assumed site conditions, the following external loads shall be used for conceptual design purposes:

(a) Snow 15 lb/sq ft on horizontal projection.

(b) Wind Wind pressure loads as established by the Uniform Building Code for a 25 psf wind-pressure-map area.

(c) Seismic (Uniform Building Code Seismic Zone 1).

Design Earthquake (DEQ) A maximum probable horizontal ground acceleration of 0.05g. A maximum probable vertical ground acceleration of 0.03g.

Maximum Hypothetical Earthquake (MHEQ) A maximum hypothetical horizontal ground acceleration of 0.10g. A maximum hypothetical vertical ground acceleration of 0.06g.

(2) Internal Loads

(a) Dead Load Structure dead loads shall be determined on the basis of structure configuration, dimensions, and materials.

(b) Floor Live Loads Except as specified herein, design floor loads shall conform to the requirements of USA 58.1, "Minimum Design Loads for Buildings and Other Structures."

Reactor Building

Main Operating Floor The more severe of the following loading conditions: Fuel handling equipment loads; AASHO-H2)-S16 wheel loads; 1000 pounds per square foot uniform floor.

All Other Floors Equipment loads plus 100 lb per square foot uniform load.

Fuel Handling Bldg; Control Bldg and H&V Bldg Equipment loads or 100 lb per square foot uniform load, whichever is greater.

Turbine Building Equipment loads, or turbine generator component laydown loads, or 100 lbs per square foot uniform load, whichever is greater.

(c) Crane Loads Crane loads shall be determined on the basis of the rated capacity of the crane plus a 15% overload.

(3) Reactor Building Containment Design Basis Loads

First Containment Barrier

Reactor Cavity; Primary Heat Transfer Cells and Drain Tank Cell: 20 psig.

Containment Dome: 25 psig (wall temp. 650°F)

Second Containment Barrier 10 psig

(4) Seismic Loads Same as seismic loads under "External Loads."

1.3.7.5.3 Structure Classification All buildings and structures of the Site, Structures and Services Segment are Class II structures as defined by the overall System Design Description, SDD-096-10-000, except for the following buildings or structures which are Class IB.

Reactor Bldg and all internal structures

Control Bldg

Fuel Storage and Handling Facilities

Reactor Bldg Ventilation System, including the stack

Gallery Inert Gas System

Steam Generator Bldg

Emergency Electrical Power Facilities

1.3.7.5.4 Loading Combinations

a. Symbols The following symbol legend is used to simplify representation of loading and stress combinations:

DL = Dead Loads

DEQ = Design Earthquake

LL = Design Live Loads

MHEQ = Maximum Hypothetical Earthquake

SL = Snow Load

P = Containment Design Basis Over-pressure

WL = Wind Load

T = Containment Design Basis Thermal Stress

b. Loading Combinations

(1) Class II Structures All Class II structures shall be analyzed and stresses calculated in accordance with the requirements of the applicable building code.

(2) Class I Structures

Reactor Building The Reactor Building shell and all internal structural systems shall be analyzed and stresses calculated under each one of the following loading combinations:

- (a) DL + LL + DEQ
- (b) DL + LL + P
- (c) DL + LL + SL + WL
- (d) DL + LL + P + T
- (e) DL + LL + DEQ + P + T
- (f) DL + LL + MHEQ + P + T

All Other Class I Structures All Class I Structures other than the Reactor Building shall be analyzed and stresses calculated for the following loading combinations, in addition to the requirements of the applicable building code:

- (a) DL + LL + DEQ
- (b) DL + LL + MHEQ

1.3.7.5.5 Seismic Considerations

a. **Class II Structures** Seismic stresses shall be determined in accordance with the requirements of the applicable building code.

b. **Class I Structures**

(1) **Determination of Forces and Stresses**

Stresses resulting from seismic loadings for both the Design Earthquake and the Maximum Hypothetical Earthquake shall be determined for the more severe of the following methods of determining seismic forces:

(a) Static lateral seismic forces in conformance with the Uniform Building Code for the seismic zone established by the UBC for the plant location. Static vertical seismic forces that are $2/3$ of the lateral forces.

(b) Lateral seismic forces as determined by response spectra methods for the maximum estimated horizontal ground acceleration at the site. Vertical seismic forces as determined by response spectra methods for the maximum vertical ground acceleration.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 31 OF

(2) Damping Coefficients The following damping coefficients, expressed as percentage of critical damping, shall be used in response spectra calculations:

Welded Exposed Steel Structures: 1%

Riveted or Bolted Exposed Steel Structures: 2.5%

Reinforced Concrete Structures: 5%

(3) Combination of Stresses The stresses due to horizontal earthquake motions and those due to vertical earthquake motions shall be added directly (in terms of absolute values).

c. Seismic Instrumentation Strong motion accellographs shall be installed at the plant site as required to accurately measure and record the ground accelerations associated with a strong earthquake. This data will be used to assess possible hidden structural damage.

1.3.7.5.6 Allowable Stresses Combined stresses resulting from loading combinations previously defined in paragraph 1.3.7.5.3 shall conform to the following.

a. Class II Structures Allowable stresses as established by the applicable building code.

b. Class I Structures

(1) Reactor Building

$$\begin{array}{ll} \text{DL} + \text{LL} + \text{DEQ} & \leq F_W \\ \text{DL} + \text{LL} + \text{P} & \leq .50 F_y \text{ for re-} \\ & \text{inforcing} \\ & \text{steel} \\ & \leq .66 F_y \text{ for} \\ & \text{structural} \\ & \text{steel} \\ & \leq F_W \text{ for pres-} \\ & \text{sure vessels} \\ \text{DL} + \text{LL} + \text{SL/WL} & \leq 1.33 F_W \end{array}$$

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 32 OF

$DL + LL + P + T \leq 1.33 F_W$ for
reinforced
conc. & struc-
tural steel

$\leq 1.5 F_W$ for
pressure ves-
sels

$DL + LL + DEQ + P + T \leq .66 F_y$ for re-
forcing steel

$\leq .80 F_y$ for
structural
steel

$\leq 1.5 F_W$ for
pressure ves-
sels

$DL + LL + MHEQ + P + T \leq .95 F_y$ &
Material used
shall have
sufficient
ductility such
that rupture
strain is 3.5
times yield
strain.

(2) All Other Class I Structures

$DL + LL + DEQ \leq F_W$

$DL + LL + MHEQ \leq .95 F_y$ and
material used
shall have
sufficient
ductility such
that rupture
strain is 3.5
times yield
strain.

Where F_W = Code allowable stress

F_y = Specified min. tensile yield
stress for material

1.3.7.5.7 Radiation Shielding Radiation shield-
ing shall be provided throughout the plant as required to comply with the
provisions of 10CFR20 while permitting operating personnel access

previously specified in paragraph 1.3.7.4.4. Radiation shielding shall be provided around the reactor building shell such that during DBA conditions the total radiation dose from all sources (direct radiation plus leakage) at the site exclusion boundary does not exceed the allowable values given in 10CFR100.

Materials Shielding materials shall be suitable for intended use, and shall be economical and readily available. Wherever possible, a single material with both structural and shielding properties shall be utilized.

Cooling Wherever temperatures of shielding materials shall increase due to radiation attenuation to levels which impair the structural or shielding properties of the material, cooling shall be provided to reduce temperatures to acceptable levels.

1.3.7.5.8 Cranes Weight handling equipment such as cranes and monorails shall be provided for plant operation and maintenance. Capacities shall be adequate to lift the heaviest piece of equipment, equipment component, or shield block anticipated during normal plant operation, maintenance or repair. Coverage and hook height shall be adequate for the crane hooks to be positioned directly over and reach all such items, and lift such items clear of adjacent structures. Cranes and hoists shall comply with the applicable provisions of Specification No. 49 of the Electrical Overhead Crane Institute and the USA Safety Code for Cranes, Hoists and Derricks, USA B30.2. Cranes of 15-ton capacity and over shall be provided with low capacity auxiliary hoists.

1.3.7.5.9 Penetrations All access openings and penetrations through the containment barriers shall accommodate the appropriate internal design pressure, and leakage shall conform to the overall leak rates as specified in paragraph 1.3.1.4. All containment barrier penetrations subject to failure, such as resilient seals and expansion bellows, shall be designed and constructed so that leak tightness can be demonstrated at design pressure at any time through the operating life of the plant.

1.3.7.5.11 Missile Protection Provisions shall be taken to assure that the containment barriers are not pierced by internal or external missiles generated due to component or equipment failure.

These provisions may include features such as protection of the containment barrier or localized barriers around possible sources of such missiles.

1.3.7.5.12 Protection of Concrete In locations where concrete surfaces may be contacted by sodium as a result of equipment or component failure, the concrete shall be suitably protected to assure structural integrity and facilitate remedial cleanup and repair.

1.3.7.5.13 Entrapped Moisture Relief The design of all steel lined concrete structures shall include provisions for the collection and drainage or venting of any entrapped moisture or moisture vapor that may exist in the concrete due to either inleakage of groundwater or evaporation of free moisture in the concrete.

1.3.7.6 Mechanical Building Services Criteria

1.3.7.6.1 General This section provides guidance for the design of mechanical systems. Each system shall be evaluated for dependability, simplicity, and economy to provide adequate capacity and control to meet the requirements of the area being served. Equipment rooms shall be arranged for ready accessibility to equipment for repairs without requiring the movement of other equipment. All controls and valves shall be readily accessible. Particular attention shall be given to locating controls and valves associated with emergency and radioactive systems and procedures. Heating, ventilating and air conditioning design shall be in accordance with the requirements and instruction of the ASHRAE Guide. Boiler and pressure vessel design shall comply with the applicable sections of the ASME Boiler and Pressure Vessel Code. Pressure piping design shall comply with the USASI Code for Pressure Piping, USA B31.

1.3.7.6.2 Use of Water in the Areas Containing Sodium In areas containing radioactive sodium systems, the use of water shall not be permitted. Where auxiliary cooling fluids are required, other fluids, such as kerosene, which do not react to sodium, shall be used. Where primary (radioactive) sodium systems are located adjacent to an area normally containing water, a wall or other physical barrier shall be located so as to provide positive separation of the sodium and water.

In areas containing non-radioactive sodium, the use of water is permitted only where required by the system design, such as in the steam generator building. Wherever possible sodium and water shall not be located in the same building or area without the provision of two physical barriers between the fluids.

1.3.7.6.3 Heating, Ventilating and Air Conditioning (HV&AC)

a. General The heating, ventilating and air conditioning systems shall satisfy environmental requirements of equipment and provide for personnel comfort and safety, during normal and emergency plant conditions. Design temperatures and ventilation rates not covered herein shall be as recommended in the latest edition of the ASHRAE Guide.

b. Environmental Design Conditions

External The actual conditions will be determined upon selection of a site. For purposes of performing a conceptual design the following conditions shall be assumed:

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 36 OF

Summer: 90° Dry Bulb, 78° Wet Bulb,
5 MPH Wind

Winter: 0° Dry Bulb, 15 MPH Wind

Barometer: 29.92 in Hg

River Water: 55°F

Internal

Reactor Building

Inert Gas Atmosphere Areas - 150°F Max.

Preamplifier Room - 75°F and 50%
max. RH
year-round

All Other Areas - 100°F Max.
60°F Min.

Enclosed Equipment Buildings Heated and

Ventilated, 100°F Max., 65°F Minimum.

Administration & Control Buildings

Air-Conditioned Areas The control room,

visitors area, general office area, instrument repair room, and those areas housing complex instrumentation and/or control and computing equipment shall be air conditioned. 75°F $\pm$ 5°F dry bulb, 50% RH max.

c. Process Heat Loads Internal heat gains resulting from operations of process systems shall be determined. Other heat gains and losses shall be calculated in accordance with methods and recommendations of the latest ASHRAE Guide, using a site location of 40° north latitude.

d. General Air Flow Generally speaking, the plant is composed of areas containing no (radio) activity, low activity, and high activity. Where areas are connected by the H&V System, the system shall be such that air flow is always directed from an area of low activity to areas of a higher activity. In no case shall air flow be directed from a "controlled" area to an "uncontrolled" area.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 37 OF

e. Areas Normally Containing Radioactive Sodium

All areas or rooms which normally contain radioactive sodium shall be maintained under an inert gas atmosphere containing a maximum of 2% oxygen. Provisions shall be made for purging these areas with air for maintenance operations. Provisions shall be made to purge the atmosphere to the R/A Waste System for treatment and holdup, should this become necessary.

f. Areas Containing Non-Radioactive Sodium or NaK Where these areas depend on flow of

outside air for part, or all, of the required ventilation, proper signalling and control equipment shall be provided to shut down the system and isolate the area in the event of a fire.

g. Areas Containing Fuel or Radioactive Sources

This paragraph applies primarily to the H&V System for the Fuel Handling Building. The atmosphere shall be continuously monitored for activity. The system shall be isolated upon indication of high activity (as determined by Health Physics personnel) and the system shall be capable of purging the atmosphere to the R/A Waste System.

h. Detailed Requirements for the Reactor Bldg

The following paragraphs specify detailed requirements for the Reactor Building HV&AC System. A conceptual flow schematic for the Reactor Building is shown on Dwg. No. NO9696004.

(1) Air Atmosphere Areas Normal-operation recirculating units shall consist of filters, cooling coils, circulating fans, associated ductwork, and controls required to maintain minimum and maximum temperatures. Emergency operation recirculating units shall include high efficiency and halogen gas adsorbing filters, circulating fans, associated ductwork and controls to reduce the postaccident radioactive atmosphere to tolerable levels. The fresh air supply unit shall consist of filters, heating and cooling coils, circulating fans, dual

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 38 OF

building isolation valves, associated ductwork and controls to provide fresh air ventilation during normal and purge operating periods. Normal operation exhaust air unit shall consist of exhaust air blowers, dual building isolation valves, associated ductwork, and controls for both normal and purge air cycles of operation. Purge exhaust flow shall be filtered using a prefilter, high efficiency filters and halogen gas adsorbing filters. The recirculation, supply, and exhaust systems shall include standby equipment.

(2) Inert Gas Atmosphere Areas Cooling, high and low volume exhaust, nitrogen purge, and oxygen control systems shall be provided.

Cooling System Each cell shall be provided with a cooling system capable of handling inert gas. The equipment shall be physically protected and designed so that it may continue to function over a reasonable time period during the DBA. The system shall consist of both operating and standby kerosene-cooled coils, blowers, and associated ducting and controls. Components of the system located outside the containment boundary shall be considered as part of containment in the event of a DBA, and shall be designed to satisfy the same pressure and leak tightness requirements.

High Volume Exhaust System This system shall discharge to the high bay exhaust system. This system shall be capable of simultaneously maintaining 100 fpm face velocities across the access hatch openings from the high bay to the three heat transfer cells. The system shall consist of both operating and standby prefilters, high efficiency filters, blowers, and associated ductwork and controls. Air flow pattern shall be from the high bay to the heat transfer cells.

Low Volume Exhaust System This system shall be designed to permit independent or simultaneous operation of the separate cells. The system shall consist of both operating and standby

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 39 OF

prefilters, high efficiency filters, blowers, and associated ducting and controls. In addition to inleakage, the system shall be capable of permitting use of bleed type pneumatic instruments utilizing nitrogen gas, and shall incorporate provisions for automatic closure and isolation of each cell. This system shall discharge to the high bay system.

Radioactive Gas Exhaust System This system shall be designed to permit independent or simultaneous operation of the separate cells. The system shall consist of cell isolating valves, connecting ductwork and controls. The system shall incorporate provisions for automatic closure and isolation of each cell. The system shall be interconnected with the R/A vent holdup system.

Nitrogen Purge System This system shall be capable of providing a nitrogen atmosphere containing not more than 2% oxygen to any one cell within 48 hours of purging operation in conjunction with operation of the low volume exhaust system.

Oxygen Control System This system shall monitor oxygen content of each cell and maintain a 2% maximum oxygen content in each cell by introducing sufficient nitrogen to offset air inleakage.

(3) High Efficiency Filters All high efficiency filters shall be constructed entirely of non-combustible materials and shall have 99.97 percent retention efficiency of particles 0.3 micron and larger.

(4) Inspection & Testing: The air atmosphere emergency operation recirculating units and system shall satisfy the following inspection and testing requirements.

(a) Design provisions shall be made to facilitate physical inspection of all critical parts of the containment air cleanup system, such as ducts, filters, fans and dampers.

(b) Design provisions shall be made so that active components of the air cleanup system such as fans and

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 40 OF

dampers, can be tested periodically for operability and required functional performance.

(c) A capability shall be provided for in situ periodic testing and surveillance of the air cleanup system to ensure filter bypass paths have not developed and filter and trapping materials have not deteriorated beyond acceptable limits.

(d) A capability shall be provided to test under conditions as close to design as practicable the full operational sequence that would bring the air cleanup system into action, including the transfer to alternate power sources and the design air flow delivery capability.

i. Exhaust Vent An exhaust vent shall be provided for discharge of all gaseous effluents to the atmosphere. The vent shall be architecturally pleasing and shall be inconspicuous when the plant is viewed from outside the site boundary.

j. Radiation Monitoring All exhaust gas streams from potentially radioactive areas and the stack shall be provided with radiation monitors and alarms.

k. Special Requirements for Control Room The Control Room must be accessible to operating personnel at all times, including during and following the postulated DBA. Therefore, the ventilation and cooling system shall permit such occupancy during accident conditions. As a minimum during emergency conditions, the ventilation air supply shall be capable of being routed through a filter system which includes high efficiency and halogen filters, and the cooling system shall be capable of maintaining internal design conditions for a minimum of under 2 hours with the control room isolated from outside air supply.

1.3.7.6.4 Sodium Unloading Facilities Space and equipment shall be provided as required for sodium unloading and transfer to the proper process systems. Sodium for the initial plant charge will be transported to the site in railroad tank cars. Equipment shall be provided on the assumption that the sodium in the tank cars will be frozen when it arrives on-site. Sodium for replacement and makeup, after the initial charge will be received, frozen, in standard 55 gallon drums. Drum heating equipment shall be provided. All equipment shall be capable of heating the sodium to a minimum of 350°F.

1.3.7.6.5 Inert Gas Supply Provisions shall be made for an on-site supply of the inert gas required in the plant. The supply shall

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 41 OF

incorporate storage capacity for a minimum of 14 days normal plant operation, based on leakage or continuous usage, plus enough storage to completely purge the two largest rooms or areas which normally contain an inert gas atmosphere (main heat transfer loop cell, for example). The gas required to completely purge a given volume shall be considered to be a minimum of 5 times the volume. Provisions shall be made in the system for tank truck connections.

1.3.7.6.6 Plumbing All plumbing fixtures and equipment shall be standard, commercially available products. The system design shall be as is used in commercial practice, except for hot change areas where drainage shall flow to the R/A waste disposal system. Emergency shower and eyewash units shall be provided exterior to the various buildings as required to provide adequate coverage for operating personnel.

1.3.7.6.7 Plant and Instrument Air System
Two separate compressed air compressor stations (one standby) shall be provided to supply clean, dry air for controls and instrumentation and for general plant services. Cross connections shall be provided between both these compressor systems for emergency backup.

a. Instrument Air This system shall supply air at 125 psig to individual controllers and instruments. The system shall include after-cooler, moisture separator, regenerative air dryer and filters. Minimum capacity of the system is to be determined.

b. Plant Air This system shall apply air at 125 psig to the various buildings and areas for general plant service. The system shall include after-cooler and moisture separator. Minimum capacity of system is to be determined.

1.3.7.6.8 Isolation Valves All mechanical building services piping and ducting that penetrate either primary or secondary containments, such as ventilation supply and exhaust, plant and instrument air; etc., shall be provided with the appropriate quantity and type of isolation valves, as required by Table 1.3.7.6.8.

a. Design All isolation valves shall be designed to withstand the containment design pressures specified in paragraph 1.3.7.5.2. Closure time and leakage rates of the isolation valves shall be such that the total loss of containment atmosphere

Table 1.3.7.6.8

Piping or Ducting System Description	Inside	Outside
Normally operating outgoing lines connected to the reactor cooling system		
Normally operating incoming & outgoing lines connecting the containment environment directly to the outside		
Normally operating outgoing lines not connected to the reactor coolant system nor protected from missiles throughout their length.		
Normally operating incoming lines connected to open systems outside the containment.		
Incoming lines connected to closed systems outside the containment		
Normally operating incoming & outgoing lines connected to closed systems inside the containment & protected from missiles through their length		
Normally closed lines inside containment building		

Legend

- Normally open, Local Manual
 Normally closed, Local Manual
 Normally open, remotely operated manual
 Normally open, automatically tripped closed
 Check valve
 Blind Flange

through any lines and the containment barrier shall not exceed the allowable leakage rates specified in paragraph 1.3.1.4.

b. Testing The containment isolation valves and associated actuating equipment shall be designed to permit periodic tests; such as, leakage testing of the valve at containment design pressure; testing of the various automatic, manual and fail-safe modes of actuation and operation; checking set points of actuating sensors; and testing over the valve full stroke range.

1.3.7.6.9 Fire Protection All buildings and areas within the plant shall be provided with a fire protection system that shall conform to the standards of the NFPA.

a. Fire Detection and Alarm System An automatic fire detection and alarm system shall be provided for the entire plant. This shall provide both visual and audible alarm in the control room, and shall indicate the trouble area. The system shall incorporate heat actuating devices based on rate of rise and fixed temperature actuation, and smoke detection. Manual fire alarm boxes, tied into the fire detection system, shall be provided throughout the plant. All fire detectors located in areas that may become inaccessible due to contamination or high radiation level shall be designed so that they can be disconnected from outside these areas.

b. Special Provisions No water extinguishers, sprinklers or hose stations shall be used in the Reactor Building. Fire protection equipment shall consist of portable dry chemical or CO₂ extinguishers.

1.3.7.7 Electrical Building Services

1.3.7.7.1 General Design Features The electrical system shall distribute, control, and meter power to the facility and site, and to the interfaces with the plant auxiliary electrical subsystem, and shall include control, alarm, communications,

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 44 OF

lighting, grounding, cathodic protection, and necessary related systems. The electrical system shall provide electrical power for facility and site, and the reactor and turbine-generator plant startup from a cold start, or from normal shutdown conditions. In addition, the electrical system shall provide emergency power, uninterruptible, and uninterruptible transient-free power, as required. A conceptual single line schematic is shown on Dwg. No. NO9670003.

Classification of Loads Loads shall be classified as follows:

General Service May be shut down without loss of reduction of plant output.

Normal Service Required for normal plant operation, but may be shut down without causing a hazard to equipment or personnel.

Emergency Service May be shut down long enough for an emergency generator to be started and connected to the line.

Momentarily Interruptible Service May be shut down momentarily without plant shutdown or loss of required function of engineered safety features of the plant.

Uninterruptible and Transient-Free May not be shut down, even momentarily. Loads are electrically isolated to remove transients or other stray electrical noise which may cause accidental plant shutdown or loss of required function of engineered safety features of the plant.

1.3.7.7.2 Performance Characteristics The electrical distribution system shall supply power for the operation and control of the plant at the following voltage levels. Emergency, interruptible, and transient free power shall be provided as required.

4,160 volts, three phase, 60 cycles/second,
grounded wye

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 45 OF

277/480 volts, three phase, four wire, 60
cycles/second

120/208 volts, three phase, four wire, 60
cycles/second

125 volts, direct current

All voltages required for special equipment, devices or circuits.

1.3.7.7.3 Station Power Station power shall be furnished from two sources, namely the generator unit service transformer and a separate station service transformer. Normally, the generator unit service transformer will supply station power requirements when the plant is running. For startup and standby, the station service transformer shall provide station power. The separate station service transformer shall be fed from the high voltage distribution system. Both transformers shall have 4,160 volt secondaries, rated for 65°C temperature rise, OA/FA/FOA, with no-load tap changers and shall be equipped with standard accessories and protective devices.

1.3.7.7.4 Emergency Power Alternate power systems shall be provided and designed with adequate independency, redundancy, capacity and testability to permit the functioning required of the engineered safety features of the plant. As a minimum, the on-site power system and the off-site power system shall each, independently, provide this capacity assuming a failure of a single active component in each power system. The emergency systems shall provide power to all vital loads. Vital loads are defined as those loads which, upon loss of normal power, must be maintained or quickly re-energized in order to assure the safety of the plant and personnel. These loads shall be automatically reconnected in sequence in descending order of size to allow for starting current surges. The uninterruptible loads cannot tolerate even a momentary outage, or are sensitive to voltage transients which might scram the reactor. The uninterruptible loads shall be supplied from a dc bus which in turn shall be normally supplied from the

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 46 OF

emergency bus through static rectifiers. In addition, rechargeable storage batteries shall float on the bus to provide a non-interruptible source of power during the short time the emergency generator is started after a power failure. Alternating current for non-interruptible loads shall be provided by static inverters from the dc bus. The emergency generator rating and starting capability shall comply with the requirements for the overall availability of the plant. The storage batteries shall be rated to carry their particular load so long as necessary to provide safety to the personnel and equipment should there be a total power outage and the emergency generator fail to start.

1.3.7.7.5 Instrumentation Power Instrumentation power for the plant auxiliary electrical distribution subsystem circuits shall be voltage regulated to ± 1 percent, and frequency regulated to $\pm 1/2$ percent and shall be free from transients and electrical noise. Instrumentation power shall be derived from the non-interruptible dc bus through highly regulated and filtered static inverters.

1.3.7.7.6 Distribution System Voltages Distribution system voltages shall be as follows. The distribution voltages shall all be available on the emergency systems as required.

In-Plant Primary Distribution At 4,160 volts, three phase, shall serve motors 250 horsepower and larger, and distribution transformers for lesser secondary voltages.

Secondary Distribution At 277/480 volts, three phase, four wire for motors 200 horsepower and smaller, electric heaters, and fluorescent and mercury vapor lighting.

Incandescent Lighting and Convenience Receptacles

Incandescent lighting and convenience receptacles shall be served at 120/208 volts, three phase, four wire. Miscellaneous small loads, and motors 1/3 horsepower and less shall also be served from this system.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 47 OF

Direct Current, 125 Volts Served from the non-interruptible battery bus.

1.3.7.7.7 Switchgear and Motor Control Centers Switchgear and motor

control centers shall be metal-enclosed type in accordance with NEMA standards, and shall include relays, controls, and meters as required.

1.3.7.7.8 Motors Electric motors 250 horsepower and larger, shall be rated for operation on 4,160 volts. From 1/2 through 200 horsepower, motors shall be rated for 480 volts. Motors 1/3 horsepower and smaller shall be rated for operation on 120 volts. Outdoor motors shall be either weather protected or totally enclosed, fan cooled, with heaters which are automatically energized when the motor is de-energized. Indoor motors shall be of open, drip-proof construction, or explosion-proof depending on the requirements of the area. Motor insulation shall be rated for the ambient temperatures and nuclear radiation to be encountered in the various plant areas.

1.3.7.7.9 Lighting Lighting levels shall be in accordance with the latest recommendations of the Illuminating Engineers Society. Mercury vapor lights shall be used in high bay areas, and fluorescent lights shall be used in offices, laboratories and other work areas. Low bay process areas shall use incandescent lights. The control room shall have a glare-free luminous ceiling. Emergency lighting shall be included throughout the plant as required for safety and minimum operating conditions. Outside lighting shall be provided as required in accordance with the recommendations of the IES.

1.3.7.7.10 Intercommunications Intercommunications within the plant shall be provided by a combination two-way press-to-talk and paging system, and a separate sound powered phone. The two-way and paging system shall provide coverage over the entire plant. The sound powered system shall provide communication between the control room and the various process and equipment areas for use in making tests and adjustments.

1.3.7.7.11 Protective Systems The protective systems shall include lightning protection, fire detectors, smoke detectors, radiation detectors, annunciators, and audible alarm devices.

1.3.7.7.12 Grounding and Cathodic Protection
An effective grounding system shall be provided for the plant, with a separate, isolated grounding system for instrumentation. The two systems shall be electrically connected at only one point.

Cathodic Protection The design shall investigate possible electrolytic corrosion to any buried metal or containment liners resulting from failure of subsurface waterproofing and subsequent groundwater coming in contact with the metal. An incipient corrosion cell may exist because of a buried copper electrical grounding system, the groundwater, and any metal exposed to the groundwater. Should there be evidence that a problem may exist, suitable cathodic protection shall be provided to protect buried metal and containment liners which may come in contact with the groundwater.

1.3.7.7.13 Raceways and Wiring Wire and cables for power, lighting and instrumentation shall be protected in conduits, wireways, or cable trays as required. Wire and cable insulations shall be selected in accordance with operating voltage, temperature and nuclear radiation levels. Seals shall be provided where wires and cables penetrate the reactor building containment. The sealing methods shall prevent leakage both around conductors and through conductors.

Specifications, Standards & Codes

National Electrical Code The design shall comply with the requirements of the National Electrical Code unless superseded by a local code.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 49 OF

Equipment Equipment shall comply with the standards of the United States of America Standards Institute, National Electrical Manufacturer's Association and the Institute of Electrical and Electronic Engineers.

1.3.7.7.14 Electromagnetic Interfaces

Shielding and spacing shall be provided between instrumentation and power raceways and equipment. Grounding circuits shall avoid circulating currents through building structures, and all ground connections shall be made directly to the main electrical or instrumentation ground loops where practicable. Where grounded neutral circuits are powered from more than one source, the neutrals shall be switched with the power circuits. Common neutrals shall be avoided. Where fluorescent or mercury vapor lights are used, the fixtures shall be suitably shielded or provided with interference suppression devices in those areas where sensitive or critical instrumentation is used.

1.3.7.7.15 Materials and Processes

Electrical insulation for wire and cable, seals, motors, and other electrical equipment shall be selected with regard to conditions of voltage, temperature and nuclear radiation.

1.3.7.8 Materials

All materials used shall conform to the requirements of the Codes and Standards cited in the detailed design criteria.

1.3.7.9 Flexibility

Flexibility is applicable to the design of the overall plant only in that consideration shall be given to the possibility of the future installation of another unit.

1.3.7.10 Spares

Not applicable.

1.3.8 Interfaces

The design of the Site Structures and Services segment interfaces with the following segments of the plant:

Reactor Segment

Heat Transfer Segment

Control and Instrumentation Segment

Energy Conversion Segment

Auxiliary Systems Segment

Reactor Support System Segment

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 50 OF

2. DETAILED DESCRIPTION

2.1 Site

As previously noted, firm site data is not presently available. The conceptual design is based on assumed data described in Sections 1.2 and 1.3.

2.2 Plant Arrangement

The conceptual plant arrangement for the 1000 MWe Plant is shown on Dwg. No. NO9690008. The orientation of the plant is representative of a typical layout on a site suitable for a multi-unit plant.

The principal buildings comprising the plant are: Reactor, Secondary Sodium and Steam Generator, Turbine-Generator, Reactor Auxiliaries, and Water Treatment. The overall arrangement and relationship of the buildings is established to a) minimize structural costs, b) minimize lengths of piping and the electrical system, c) provide a central location for plant control, and d) permit the addition of a second, identical, 1000 MWe unit with a minimum of cost or additional facilities.

2.3 Provisions for Second Unit

The layout of the plant assumes the future addition of a second, 1000 MWe unit on the west side of the first unit. The second unit is a mirror image of the first, with the west wall of the turbine-generator and water treatment building being the interface. With the elimination of the common wall, existing handling equipment in both of these buildings would serve both units.

With the exception of the control room and electrical gear, the entire reactor auxiliary building serve both units with but minor modification. The tracks for the cask transfer car would be extended to the second reactor building; the transfer car and rail head would serve both units. The primary sodium storage tanks located below grade under the south end of the building are only required for complete primary system drainage, including the reactor vessel. Since it is extremely unlikely that complete drainage of both units would be required, these tanks could be used by either unit. The R/A gas system is sized to accommodate a second unit, with space provided for the addition of a third compressor. Gas decay tank capacity adequate for both units is installed with the initial unit in order to minimize disruption of first unit operation at a later date. Additional facilities for the second unit include a new control room, reactor building switchgear (located above the

existing switchgear) and additional H&V equipment.

2.4 Structures

2.4.1 Reactor Building

2.4.1.1 Building Structure

The reactor building contains the reactor, fuel handling system, all radioactive sodium systems, and the potentially higher activity portions of the liquid and gaseous waste systems. The reactor and radioactive sodium system components are enclosed in concrete vaults located below the main operating floor. The main operating floor is at grade. The reactor top shield and containment dome, the control rod drives, primary pump drives, main valve operators, and the fuel handling machine are located on the operating floor. The equipment arrangement is shown on Dwg. Nos. NO9696007 and NO9696008.

The building is a conventional reinforced concrete structure having a configuration of a right circular cylinder with a flat base and a hemispherical head. Nominal dimensions are 140 ft. inside diameter, 121 ft. inside height of the cylindrical section and overall inside height of 191 ft. The operating floor is at grade and the top of the base slab is 54 ft. below grade. The concrete structures serve both as pressure containers and biological shielding. The dome and cylinder section above grade are nominally 2 ft. thick. The cylinder section below grade ranges from 3 to 6 ft. thick depending on shielding and structural spans. The base slab ranges from approx. 4 ft. thick at the edge to approx. 14 ft. thick under the reactor. The operating floor slab over primary (radioactive) sodium components is nominally 6 ft. thick. Removable concrete plugs in the floor provide access to below grade equipment. All vaults containing primary sodium equipment within the building are separated by fire walls and are maintained under an inert (2% oxygen maximum) nitrogen atmosphere to inhibit fires in the event of a sodium leak and to reduce the consequences of the unprotected loss of flow accident.

The right cylindrical configuration for the building was selected as that most efficient for arrangement of the three primary heat transfer loops, particularly with respect to the elevated IHX requirement to assure natural convection. Conventional reinforced concrete is utilized as structural members throughout. The relatively low containment design pressures result in realistic member thicknesses and reinforcing, and the concrete itself

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 52 OF

doubles in function by acting as biological shielding. Crane coverage of the operating floor is provided by a 120 ton polar bridge crane, which is adequate to handle the spent fuel shipping cask.

2.4.1.2 Containment Barriers Containment of radioactive material that may be released from the fuel elements in the event of the DBA is accomplished by a double barrier containment concept. The inner barrier is a continuous steel plate membrane that encompasses the primary heat transfer vaults, drain tank vaults and the reactor cavity. In the vaults, the membrane is a 1/4-inch thick steel plate which is backed up by the reinforced concrete structure. Rupture discs located in common walls between vaults permit the entire enclosed volume to be used for containment of the energy released during a postulated DBA.

In the region of the reactor cavity, the membrane is a 3/4-inch thick steel containment dome over the top shield plus, under the current concept, a portion of the reactor cavity liner which is of varying thickness. The bottom plate of the cavity, which is the portion currently anticipated to be part of the inner barrier, will be cooled to assure liner integrity in the event molten fuel is dispersed over the bottom of the cavity.

The outer barrier is a continuous welded steel plate membrane over the inside surface of the building shell structure. This steel membrane will be 1/4-inch thick over the flat base slab and 3/8-inch to 1/2-inch thick on the inside surface of the cylinder and dome.

The containment barriers and penetrations are designed both to minimize outleakage and to satisfy testability requirements. The conceptual designs utilize seal welds and/or multiple barriers where practical and incorporate features which permit localized leak testing at design pressures. The inner containment barrier is designed for a maximum leak rate of 10% per day with a 20 psi overpressure in the vaults, cavities, and containment dome. The outer containment barrier is designed for a maximum leak rate of 0.5% per day with a 10 psi overpressure.

2.4.2 Secondary Sodium and Steam Generator Building

1. General

The secondary sodium and steam generator building and the general equipment arrangement within it are shown on Dwg. No. N09695001. The

ATOMICS INTERNATIONAL*A Division of North American Aviation, Inc.*

building contains the steam generators, secondary sodium pump/surge tanks, sodium purification and drain systems and equipment used for steam generator relief in the event of tube leakage and consequent sodium/water reactions. Three identical, independent, secondary sodium systems and steam generators are provided; one for each heat transfer circuit.

The building is located between the Reactor Building and the Turbine Building and shares a common wall with the Turbine Building.

2. Structural Features

Overall, the building is 200 ft. long and 114 ft. wide. The building extends approximately 120 ft. above grade and at its deepest part, 67 ft. below grade. Above grade, the building is an enclosed steel structure with uninsulated metal siding.

Internally, the building is divided into four bays extending across the width of the building. Three of the bays are 58 ft. long and each contains the secondary sodium system and steam generator for a single heat transfer loop. The fourth bay, 26 ft. long, is used for equipment and vehicular access. This bay does not extend below grade.

Each steam generator is individually isolated from the others to insure that a leak and/or fire does not prevent operation of the adjacent generator. Below grade, bay separation is provided by concrete walls extending up to grade. Above grade, each steam generator is enclosed on all four sides, either by the building wall or by fire retardent paneling such as "transite" which extends from grade up to the 180 ft. elevation. Intermediate platform levels are primarily open grating; thus, if a major break occurs, the sodium will fall to the bottom of the building and a major fire in the vicinity of the generator itself could not be sustained and spread to adjacent loops.

Access platforms are provided at those components requiring most frequent inspection and/or maintenance, particularly around the module rupture discs and the hydrogen detectors connected to the sodium outlet line from each module.

Equipment removal and replacement is accomplished by two bridge cranes which run the length of the building. Removable roof panels are provided over the steam generator modules. Module removal is accomplished by lifting them out of the building using hoisting equipment temporarily installed on the roof.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

The area between Cols. A and B is kept clear from grade up approx. 40 ft. in order to provide room for removal of the rupture disc separator tank. Permanent hoisting equipment is not provided for this equipment due to the infrequent use and high capacity requirements (>50 tons).

2.4.3 Reactor Auxiliary Building

The reactor auxiliary building is a multipurpose building located adjacent to the reactor building on the west side. The building provides the following facilities: cask handling, personnel control, reactor building switchgear, plant control, R/A waste gas and sodium storage tanks. With the exception of the plant control area, the building is a steel frame structure with insulated metal siding. The plant control area is of concrete construction in order to provide shielding for operators manning the control room during a DBA. Direct vehicular access is provided to the control room in order to minimize personnel exposure in the event an accident occurs which results in a higher than normal radiation dose immediately adjacent to the reactor building.

The shipping cask handling area is the area used to transfer fuel casks from the transfer car to a railroad car. The area is used to store and maintain the cask transfer car when not in use. The building is connected to the reactor building by the cask air lock. If a second unit were added to the station, the tracks would be extended to a similar air lock leading to the new reactor building. This area of the auxiliary building also serves as a storage area for fuel casks and new fuel during plant construction. A 120-ton bridge crane spanning the width of the building is provided for equipment handling. Overall height of this area of the building is approx. 45 ft.

The switchgear and personnel control areas are single story. The switchgear portion contains electrical gear for the reactor building equipment. A second story would be added to accommodate similar equipment for a second nuclear plant. The personnel control area contains a counting room, hot and cold change rooms, health physics offices and activity monitoring equipment.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 55 OF

The plant control area of the building is a three story structure. The control room is at the upper level with a cable spreading area immediately below it. The level at grade contains computer facilities, other auxiliary electrical hardware, and local air conditioning equipment. With the addition of a second unit, this portion of the building would be extended to the west, to double the area.

The building substructure consists of concrete vaults enclosing primary sodium storage tanks and the R/A waste gas system. Provisions are made to substitute nitrogen for the normal air atmosphere in the event primary sodium storage is required.

2.4.4 Turbine Generator Building

The turbine generator building adjoins the steam generator building on the north side. The building contains the turbine-generators, condensers, boiler feed pumps, feedwater heaters and associated turbine plant equipment. The turbine-generator axis runs east-west to permit extension of the building for the installation of a second unit.

The building is a steel frame structure with external walls of uninsulated metal siding. The turbine generator is set on a reinforced concrete structure with the turbine operating level approx. 40 ft. above grade. The main condensers are supported at grade and located directly beneath the low pressure turbines. Feedwater heaters are located between the turbine and steam generator.

2.4.5 H&V Building

The H&V building is a two-story steel structure located adjacent to the reactor building. The building contains the supply air units and exhaust fans which provide the outside air supply for the reactor building.

2.4.6 Administration Building

This building contains administrative office spaces and training areas. The building is a steel frame structure with insulated metal wall siding.

2.4.7 Intake Structure

A concrete river water intake structure is provided and is connected by an intake channel to the river. This structure houses the main condenser circulating water pumps, fire water pumps, screen wash pumps, handling equipment, and other associated hardware.

2.4.8 Auxiliary Facilities

Various service and auxiliary facilities are provided to support the power plant.

a) Service Building - The service building is located at grade adjacent to the turbine generator building. This building houses a machine shop, pipe shop, sheet metal shop, etc., and serves as a central area for material receiving and plant maintenance, repair and minor modification.

b) Turbine Plant Auxiliary Building - This building contains turbine feedwater makeup and treatment equipment and the auxiliary station boiler. It is located at grade north of the turbine building.

c) Sewage Treatment - Sewage treatment facilities are provided for primary and secondary treatment of sanitary sewage.

d) Inert Gas Area - The inert gas area provides space for inert gas storage tanks and associated equipment.

e) Cooling Water Discharge - A below grade concrete structure and tunnel collects the cooling water discharge from the turbine-condensers and dumps the discharge through a discharge canal and weir downstream from the intake structure.

2.5 Heating, Ventilating and Air Conditioning Systems

2.5.1 General

Multiple supply, recirculation, and exhaust gas (air or nitrogen) systems are provided. The supply gas systems are divided into four major categories; refrigerated air conditioning, water or kerosene-cooled, and ventilation air-cooled. The supply air systems include integral heaters where space heating is required. Supplementary room-type convection heaters are located within heated spaces not directly served by a supply air system. Exhaust gas systems are provided for general exhaust, purge exhaust, hood and equipment exhaust, toilet exhaust, and space pressure control.

2.5.2 Reactor Building

Multiple supply, recirculation and exhaust gas systems are provided to accommodate the various spaces within the reactor building. Process heat loads are removed by utilization of kerosene cooled, water cooled, or ventilation air cooled supply and recirculation air/gas systems. Space heaters are included in the supply air systems where required to maintain design

temperature conditions. Exhaust gas systems are provided for general exhaust, purge exhaust, and space pressure control. An air cleanup system is provided in the high bay area to accelerate fission product cleanup following certain accidents. Refer to Dwg. No. NO9696004 for a schematic of the system.

2.5.3 Control Room

During normal operation, the control room is provided with conditioned air by a supply air system similar to the administrative area. However, since the control room is capable of being occupied during any plant emergency, an emergency outside supply air filter system consisting of pre-filters, high efficiency filters, and halogen filters will also be provided. Under emergency conditions, all outside supply air coming into the control room can pass through this emergency filter train.

2.5.4 Cask Handling and R/A Waste Area

2.5.4.1 Supply Air System

The system is an all-outside-air supply system capable of cooling the spaces served while making up the air exhausted. The system consists of an outside air intake, an air-handling unit, and supply air distribution ductwork. The air-handling unit contains an outside air damper, fiberglass filter, cooling water coil, and ganged blowers with a common motor.

2.5.4.2 Exhaust Air System

The system consists of two half-capacity parallel subsystems. A failure of one will shut down the supply system so that the other can still hold the building negative with respect to atmosphere. Each subsystem includes a bagged prefilter, a bagged high efficiency filter, and exhaust fan and connecting ductwork. The system discharges to the facility exhaust vent.

3. PRINCIPLES OF OPERATION

Generally speaking, this section is not applicable for the Site, Structures and Services Segment. During normal plant operations all buildings, including the Reactor Building, are accessible to operating personnel. Upon appropriate signal of an emergency situation in the Reactor Building, (originating in the radiation detection and monitoring system, fire detection system, plant control system, or containment pressure detection system) the various process, service, and utility penetrations through the containment barriers will be automatically sealed and the building will be isolated. All intake and exhaust air ducts will be sealed, and the high bay cooling system will go into emergency mode of operation. Personnel inside the building will immediately evacuate through the air locks, and any subsequent reentry will be under strict control. The isolated condition will continue until it is determined safe to start exhausting building air through the stack and safe ambient conditions are again reached.

During the accident, all instruments and controls required to maintain the plant in a safe condition are operated either from the plant control room, or other suitably protected areas outside the Reactor Building.

4. SAFETY PRECAUTIONS

4.1 Personnel Control

All plant personnel are controlled by administrative and health physics procedures to prevent radiation exposures above allowable values.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 59 OF

Physical barriers, monitoring stations, and access locations, are designed and located specifically to prevent access to controlled areas by unauthorized personnel and to control and monitor all radiation exposure on a routine, continuing basis.

4.2 Radiation Shielding

Radiation shielding is provided around all sources of radioactivity, both actual and those postulated under accident conditions, so as to protect operating personnel and the general public from excessive radiation doses.

4.3 Radiation Detection and Alarm System

Radiation detectors and alarms are spotted throughout the plant. All plant effluents are continuously monitored for activity. In addition, periodic surveys are made throughout the site and the surrounding areas to insure the protection of the general public.

4.4 Containment Structure

In order for the Reactor Building to perform its primary function of protecting the public from uncontrolled release of radiation, certain precautions must be observed in the design construction and operation of the building.

4.4.1 Design Precautions

The containment structure, including penetrations, must be designed to accommodate or dissipate without failure the largest credible energy release from abnormal situations. It must also withstand, without loss of the capability to protect the public, the additional forces imposed by natural phenomena such as earthquakes, winds, flooding conditions, etc.

4.4.2 Construction Precautions

Strict quality control must be enforced during construction to insure the intent of the design is fulfilled. Commercially acceptable construction inspection procedures are not adequate, and

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000

DATE 10-24-67

PAGE 60 OF

greater attention must be paid to details of workmanship and adequacy of materials. Factory verification of materials properties, including sample testing, may be required to assure critical design parameters are satisfied.

4.4.3 Operational Precautions

Strict administrative control of plant operations must be established and enforced to assure the continuous integrity of the containment barriers. Access and egress must be controlled and monitored. Preventive maintenance procedures, including periodic inspection and test, must be established for all components of the containment system or any other engineered safeguards system to assure that these components and systems are capable of functioning under emergency conditions.

5. MAINTENANCE

5.1 Preventive Maintenance

To be determined.

5.2 Leak Rate Tests

The containment barriers and all penetrations are capable of being tested at appropriate pressures throughout the life of the plant to assure compliance with design leakage rates.

5.2.1 Penetration Tests

All penetrations through containment barriers that contain components subject to failure, such as resilient seals and expansion bellows, can be tested at design pressure at any time during plant operation.

5.2.1.1 Test Procedure To be determined.

5.2.2 Integrated Leak Rate Tests

Each containment envelope will be tested at appropriate pressure and at suitable intervals to assure that overall leakage rate requirements are met.

ATOMICS INTERNATIONAL

A Division of North American Aviation, Inc.

NO. SDD-096-90-000
DATE 10-24-67
PAGE 61 OF

5.2.2.1 Test Frequency: To be determined.

5.2.2.2 Test Procedure: In accordance with ANS Proposed

Standard 7.60.

6. APPENDICES

6.1 Drawings

- NO969008 - Plant Arrangement - ANL 1000 MWe Follow-on Study
- NO9696007 - Reactor Building Equip. Arrangement - Plans - ANL 1000 MWe Follow-on Study
- NO9696008 - Reactor Building Equip. Arrangement - Sections - ANL 1000 MWe Follow-on Study
- NO9695001 - Steam Generator Bldg Equip. Arrangement - ANL Follow-on Study
- NO9696004 - Reactor Bldg HV & AC Flow Diagram - 1000 MWe LMFBR Follow-on Study
- NO9670003 - Electrical Single Line Diagram - 1000 MWe LMFBR ANL Follow-on Study

6.2 References

- SDD-096-10-000 Overall Conceptual System Design Description, 1000 Mwe LMFBR Follow-on Study
- SDD-096-20-000 Reactor Segment CSDD - 1000 Mwe LMFBR Follow-on Study
- SDD-096-30-000 Heat Transfer Segment CSDD - 1000 Mwe LMFBR Follow-on Study
- SDD-096-40-000 Energy Conversion CSDD - 1000 Mwe LMFBR Follow-on Study
- SDD-096-60-000 Auxiliary Systems Segment CSDD - 1000 Mwe LMFBR Follow-on Study
- SDD-096-80-000 Reactor Support System CSDD - 1000 Mwe LMFBR Follow-on Study

REVISIONS		
NO.	DESCRIPTION	DATE
1	5DD-096-40-155	
2	V 62

ATOMIC INTERNATIONAL	
A DIVISION OF GEORGE WASHINGTON UNIVERSITY	
PLANT ARRANGEMENT	
AND 1000 MW FOLLOW-ON STUDY	
100690008	
100690008

PLAN A-A - ABOVE OPERATING FLOOR

CONTAINMENT BLDG.
STEEL LINER - 140' I.D.

PLAN B-B - BELOW OPERATING FLOOR

EQUIPMENT

1. REACTOR TOP SHIELD
2. REACTOR VESSEL
3. REACTOR VESSEL LINER
4. CAULTY LINER
5. REACTOR CONTAINMENT DOME
6. BRIT FUEL STORAGE VESSEL
7. FUEL EXHAUST ENCLOSURING CELL
8. REACTOR CONTAINMENT WASH CELL AND MISS. STORAGE PITS
9. SHIPPING CRANE
10. SHIPPING CRANE AIR LOCK - 8' X 10' CLEAR
11. FUEL HANDLING SANITARY
12. PUMP FOR BELOW-FLOOR MAINTENANCE OF FUEL HANDLING MACHINES
13. PROCESS EQUIP. WASH CELL - 8' DIA - SERVED BY PRL PUMP
14. VIEWING WINDOW
15. COOLING EQUIPMENT FOR SPENT FUEL STORAGE VESSEL
16. RECIRCULATING HEV UNITS
17. PRL-AMP ROOM
18. PRIMARY PUMP DRIVE
19. VALVE OPERATORS
20. ACCESS PLUGS FOR INK MAINTENANCE
21. COLD TRAP ACCESS PLUGS
22. INK ENCLOSURE
23. EQUIP. ACCESS HATCH (THROUGH TO BOTE LEVEL)
24. PRIMARY PUMP
25. INK
26. PRIMARY BLOCK VALVES
27. CHECK VALVE
28. THROTTLE VALVE
29. SECONDARY PUMP PENETRATION SEALS (DOUBLE BELLOW)
30. COLD TRAPS
31. HEV AND GEDSIE ORE CHASE
32. PRESSURE RELIEF PANELS FOR VAULT RELIEF TO DRAIN TANK BELOW (DBA RELIEF) - TYPICAL EACH VAULT
33. ATMO-SPIRATOR SEAL - TYPICAL
34. REACTOR OVERFLOW TANK
35. DEGASIFIER/BURGE TANK
36. DEGASIFIER RETURN PUMPS
37. PRIMARY NA SERVICE PUMPS
38. PRIMARY NA SERVICE PIPE CHASE
39. PRIMARY NA DRAIN TANK - 50,000 GAL
40. PRIMARY NA DRAIN TANK - 50,000 GAL
41. R/A LIQUID WASTE TANKS - DRAINS FROM WASH & ENCLOSURE CELLS
42. COARSE AIR PURIFICATION SYSTEM
43. POST DBA COOLING EQUIP. - USED DURING NORMAL OPERATION
44. EMERGENCY EQUIPMENT IS RUTHLESS BURNING
45. PRESSURE RELIEF AIR LOCK - 8' X 10' T. CLEAR - AT GARGE
46. LARGE EQUIPMENT ACCESS OPENING - 50' DIA. - WILL CLEAR REACTOR TOP SHIELD AND INK

FOR SECTIONS SEE DWG. NO. 10969008

PLAN C-C

REVISIONS
DATE APPROVED
SDD.096.90.000
PAGE 63

ATOMIC INTERNATIONAL	
REACTOR BLDG. EQUIP. ARRANGEMENT - PLANS -	
AHL 1000MM FOLLOW ON STUDY	
DATE	NO. 10969007
BY	DATE
CHECKED	DATE
APPROVED	DATE

REV	DATE	DESCRIPTION	APPROVED

SND 096 90.000
P. 64

SECTION D-D

SECTION E-E

SECTION H-H

SECTION F-F

SECTION G-G

EQUIPMENT

1. REACTOR TOP SHIELD
2. REACTOR VESSEL
3. REACTOR VESSEL LINER
4. CAVITY LINER
5. REACTOR CONTAINMENT DOME
6. SPENT FUEL STORAGE VESSEL
7. FUEL CHAMBER ENCAPSULATING CELL
8. SHIPPING CASE
9. SHIPPING CASE AIR LOCK
10. FUEL HANDLING ENTRY
11. PROCESS EQUIP WASH CELL
12. VIEWING WINDOW
13. COOLING EQUIPMENT FOR SPENT FUEL STORAGE VESSEL
14. RECIRCULATING HEAT EXCHANGERS
15. PRIMARY PUMP DRIVE
16. VALVE OPERATOR
17. ACCESS PLUG FOR DMX MAINTENANCE
18. THE ENCLOSURE
19. PRIMARY PUMP
20. DMX
21. PRIMARY BLOCK VALVE
22. CHECK VALVE
23. THROTTLE VALVE
24. SECONDARY PIPING PENETRATION SEAL
25. COLD TRAP
26. ATMOSPHERE SEAL
27. REACTOR OVERFLOW TANK
28. DEGASIFIER/AIRGAS TANK
29. DEGASIFIER RETURN PUMPS
30. PRIMARY NA SERVICE PUMP
31. PRIMARY NA TREAT TANK - 88,000 GAL
32. PRIMARY NA DRAIN TANK - 30,000 GAL
41. R/A LIQUID WASTE TANKS & PUMPS - DRAINS FROM WASH & ENCAPSUL CELL
42. COVER GAS PURIFICATION SYSTEM
43. PRIMARY FLOWMETER
44. BUILDING CRANE - 18.0 TON CAPACITY
45. EX-VESSSEL FUEL HANDLING MACHINE
46. TOP SHIELD HOLD-DOWN STRUCTURE

FOR PLAN VIEWS SEE -
DWG NO. N0969007

<p>ATOMIC INTERNATIONAL</p> <p>A DIVISION OF WESTINGHOUSE ELECTRIC CO.</p> <p>300 BROADWAY, CAMDEN, N.J. 08102</p>	
<p>REACTOR BLDG. EQUIP. ARRANGEMENT -</p> <p>100% - 100% - 100% - 100% - 100% - 100% - 100% - 100% - 100% - 100%</p>	
<p>DATE</p> <p>10/1/64</p>	<p>BY</p> <p>J. E. HARRIS</p>
<p>CHKD BY</p> <p>J. E. HARRIS</p>	<p>APP'D BY</p> <p>J. E. HARRIS</p>
<p>PROJECT NO. N0969000</p>

PLAN
ABOVE EL. 180' - COL. 1-7
ABOVE EL. 100' - COL. 7-15
ABOVE EL. 66' - COL. 15-18

SECTION B-B

SECTION A-A

ATOMIC INTERNATIONAL
A DIVISION OF NORTH AMERICAN UTILITIES, INC.
2000 WEST 10TH AVENUE, DENVER, COLO. 80202

STEAM GENERATOR BLDG. EQUIP. ATTACHMENT
ANL 1000MW FOLLOW-ON STUDY

PROJECT NO.	1000MW	DATE	10/1/77
DESIGN NO.	1000MW	DATE	10/1/77
REVISED NO.	1000MW	DATE	10/1/77
SHEET NO.	1000MW	DATE	10/1/77

NO. 000001

REVISIONS		
NO.	DESCRIPTION	DATE
1	REV. 11/10/60	11-10-60

SDD.096.90.000
P. 67

- LEGEND:**
- TRANSFORMER
 - DRAWN OUT CIRCUIT BREAKER
 - ELECTRICALLY OPERATED
 - MOLDED CASE CIRCUIT BREAKER
 - WOUND ROTOR MOTOR
 - SQUIRREL CAGE MOTOR
 - D.C. MOTOR
 - S.C.R. CONTROLLER
 - BATTERY
 - GROUND
 - TRANSFER SWITCH
 - REMOVABLE LINK
- ABBREVIATIONS:**
- AUX. AUXILIARY
 - Bldg. BUILDING
 - CIRC. CIRCULATION
 - COND. CONDENSATE
 - COND. CONDENSATE
 - DEMIN. DEMINERALIZER
 - EMERG. EMERGENCY
 - GEN. GENERATOR
 - HEAT. HEATER
 - H.P. HIGH PRESSURE
 - L.P. LOW PRESSURE
 - M.O. MOMENTARY ON
 - P.S. POWER SUPPLY
 - REGUL. REGULATIVE
 - SYNCH. SYNCHRONOUS
 - TRAMP. TRAMP
 - TREAT. TREATMENT
 - TURB. TURBINE
 - TYP. TYPICAL
 - VENT. VENTILATION
 - C.C. CONTROL CENTER
 - SWGR SWITCHGEAR
 - M.O. MOMENTARY OPEN
 - S. STANDBY USE
 - E. EMERGENCY USE

CONTROL ROD DRIVE C.C., NO PUMP SEAL OIL PUMPS & PANS, ESSENTIAL PLANT CONTROLS, NEUTRON DETECTOR DRIVES C.C.

SAFETY ROD DRIVES C.C., MOTOR OPERATED EMERG. VALVES C.C., IN-PLANT COMMUNICATIONS, INSTR. PANS & BLOWERS, RADIATION MONITORING INSTR. UNITS (5 KW)

NOTICE

THIS DRAWING IS THE PROPERTY OF ATOMICS INTERNATIONAL. IT IS TO BE USED ONLY FOR THE PROJECT AND PURPOSE SPECIFIED HEREIN. IT IS NOT TO BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF ATOMICS INTERNATIONAL.

ATOMICS INTERNATIONAL

1000 MVA LMFBR ANAL. FOLLOW-UP STUDY

N09670003