QA: N/A

**Civilian Radioactive Waste Management System
Management & Operating Contractor**

White Paper:

Waste Handling Building Conceptual Study

TDR-WHS-SE-000002 REV 00

October 2000

Prepared for:

**U.S. Department of Energy
Yucca Mountain Site Characterization Office
P.O. Box 30307
North Las Vegas, Nevada 89036-0307**

Prepared by:

**TRW Environmental Safety Systems Inc.
1261 Town Center Drive
Las Vegas, Nevada 89144**

**Under Contract Number
DE-AC08-91RW00134**

DISCLAIMER

This document was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

**Civilian Radioactive Waste Management System
Management & Operating Contractor**

**White Paper:
Waste Handling Building Conceptual Study**

TDR-WHS-SE-000002 REV 00

October 2000

Prepared by:

_____
G.W. Rowe
Systems Engineering Department

11-2-00
_____
Date

Checked by:

_____
F. A. Lane
Surface Facilities Department

11/6/00
_____
Date

Approved by:

_____
A.H. Falls, Manager
Requirements & Integration

11/6/00
_____
Date

INTENTIONALLY LEFT BLANK

EXECUTIVE SUMMARY

OBJECTIVE

The objective of the *Waste Handling Building Conceptual Study* is to develop proposed design requirements for the repository Waste Handling System in sufficient detail to allow the surface facility design to proceed to the License Application effort if the proposed requirements are approved by DOE. Proposed requirements were developed to further refine waste handling facility performance characteristics and design constraints with an emphasis on supporting modular construction, minimizing fuel inventory, and optimizing facility maintainability and dry handling operations.

To meet this objective, this study attempts to provide an alternative design to the Site Recommendation design that is flexible, simple, reliable, and can be constructed in phases. The design concept will be input to the "Modular Design/Construction and Operation Options Report", which will address the overall program objectives and direction, including options and issues associated with transportation, the subsurface facility, and Total System Life Cycle Cost. This study (herein) is limited to the Waste Handling System and associated fuel staging system.

SUMMARY OF RESULTS

New proposed requirements were developed and a conceptual Waste Handling System design was developed that meets those proposed requirements. The design utilizes a dry waste transfer system that can process both canistered and uncanistered fuel. This concept eliminates cask cool down prior to opening the cask and eliminates cask decontamination after removing the cask from the pool. The lines operate independently and therefore can be constructed in phases. Dry in-process staging for 432 assemblies is provided inside the Waste Handling Building to facilitate thermal blending and modular dry staging external to the Waste Handling Building is provided to accommodate variations in the staging requirements.

SCOPE

The U.S. Department of Energy requested the Management and Operating Contractor to evaluate the Waste Handling Building design and operations and develop proposed requirements that would lead to improvements to the present Site Recommendation design. Based on this request, the U.S. Department of Energy approved *Add Work Scope & Budget for Enhanced Surface Design Support for LA (M&O-00-048)* (CRWMS M&O 2000f) to perform these activities. The scope of the conceptual study was as follows:

- Develop proposed requirements that would lead to a modular Waste Handling Building that can be constructed in phases.
- Provide drawings, flow diagrams, and throughput predictions to confirm the recommendations.
- Develop a preliminary cost basis for each construction option.

REQUIREMENTS

The following is a summary of the proposed requirements contained in Appendix A.

- **Waste Handling Building Functions:** Further defined nine new and revised waste processing functions.
- **Blending Inventory:** Commercial Spent Nuclear Fuel inventory is limited to 5,000 metric tons of uranium, 400 assemblies inside the Waste Handling Building, and the remaining in modules external to the Waste Handling Building.
- **Transfer Lines:** Each waste transfer line is identical, operates in a dry environment, and is capable of processing both canistered and uncanistered fuel.
- **Modular Design:** Each waste transfer line is independent and can be constructed in phases. The staging is modular and can be constructed on an as-needed-basis.
- **Operational Radiation Exposure:** Disposal Container Handling Area will be designed and maintained to keep radiological conditions within the requirements for occupational radiation dose limits, and as practical, to keep personnel doses as low as is reasonably achievable (ALARA).

CONCEPTUAL DESIGN

Two design alternatives were developed, each based on a different Disposal Container welding (closure) approach. One alternative holds the Disposal Container stationary during closure, the second rotates the Disposal Container on a turntable. Cask unloading, waste transfer, and Disposal Container loading operations are identical in each option. Each transfer line handles canisters and bare fuel, and the fuel is handled in a dry environment. Modular design and phased construction is easily implemented with a common transfer line concept.

CONSTRUCTION OPTIONS

Two construction options were developed for each design alternative. The first option constructs one Waste Handling Building module in each of the three construction phases while the second option constructs two modules in the first phase and one module in the second phase.

COST ESTIMATES

The following table summarizes the capital costs for the design alternatives. Detail cost estimates are included in Appendix F.

Design Alternatives Capital Costs

Design Alternative	Construction Option	Total Capital Costs
Non-Rotating Waste Package	1 module per phase (three total)	\$554,000,000
	2 modules in first phase, one in second phase	\$545,000,000
Turntable (Rotating Waste Package)	1 module per phase (three total)	\$573,000,000
	2 modules in first phase, one in second phase	\$566,000,000
Fuel Staging Area (485 storage casks)	N/A	\$409,000,000

CONCLUSION

The recommendations in this document represent a Waste Handling System concept that is more flexible than the Site Recommendation design. It reduces the amount of liquid low-level waste, enhances modularity and supports phased construction, provides more flexibility in adapting to changes in the waste stream, and provides more flexibility in responding to changes in the repository design. Incorporating the proposed technical requirements in Appendix A would result in the following potential design improvements:

- The Assembly Transfer System and Canister Transfer Systems would be combined into one system that can process either individual assemblies or canisters. This simplifies the processing by reducing the types and amounts of equipment that are needed thus reducing construction and operating costs, the amount of spare parts necessary, the number of procedures required, and the amount of operator training required. This also increases the reliability because having one module out of service does not restrict the ability to process any type of incoming waste.
- The pools would be eliminated and all incoming waste would be handled in a dry environment. This would eliminate all of the water handling and processing systems associated with the pools and reduce the number of spent nuclear fuel waste processing steps required for each type of waste, thus eliminating many of the design basis events and increasing overall reliability of the facility.
- The cutting open of dual-purpose canisters would be moved out of the normal processing line. Since this task is very time consuming and represents one of the most unpredictable work tasks that must be performed in the Waste Handling Building, the overall system reliability and throughput would be increased.
- Shielding the disposal containers prior to loading would allow personnel access to the disposal container handling area. This would greatly simplify the equipment that is

needed to move the disposal containers/waste packages in the disposal container handling area thus reducing cost and increasing reliability. Shielding does not, however, mitigate the problem of decontaminating the waste package, if required.

- The Carrier Preparation Building would be eliminated and the function incorporated into the Waste Handling Building. This would reduce the capital cost, eliminate the possibility of a cask drop accident without impact limiters outside of a confinement area, and increase reliability.
- The addition of the transporter load bay would provide for the movement of loaded waste packages to the Fuel Staging Area. Also, storage casks could be loaded with hot assemblies for transport to the Fuel Staging Area. This would increase the flexibility of the facility.

The path forward is outlined in Section 3, which could be implemented in time to support the Fiscal Year 2001 plan.

CONTENTS

	Page
ACRONYMS AND ABBREVIATIONS	xvii
1. INTRODUCTION	1-1
1.1 OBJECTIVE	1-1
1.2 BACKGROUND	1-1
1.3 SCOPE	1-2
1.4 TECHNICAL APPROACH	1-3
1.4.1 Define Technical Requirements	1-3
1.4.2 Define Waste Handling Building Process	1-3
1.4.3 Develop Waste Handling Building Design/Layouts	1-3
1.4.4 Identify Design Basis Events	1-5
1.4.5 Determine Phased/Modular Construction Approach and Layouts	1-5
1.4.6 Define Receipt Scenarios, Milestone Schedule, and Funding Constraints	1-6
1.4.7 Prepare Cost Estimates and Throughput Analyses	1-7
1.4.8 Prepare Waste Handling Building Design Recommendations	1-7
1.4.9 DOE Review	1-7
1.4.10 Update FY2001 Technical Plan	1-7
2. DESIGN ANALYSIS	2-1
2.1 DESIGN GUIDANCE	2-1
2.1.1 Introduction	2-1
2.1.2 Basis for Recommendations	2-1
2.1.3 Summary	2-15
2.2 FACILITY DESCRIPTION	2-15
2.2.1 Non-Rotating Waste Package Design Alternative	2-16
2.2.2 Turntable Design Alternative	2-19
2.3 OPERATIONAL DESCRIPTION	2-20
2.3.1 Non-Rotating Waste Package Design Alternative	2-20
2.3.2 Turntable Design Alternative	2-25
2.4 DESIGN ALTERNATIVES EVALUATED	2-26
2.4.1 Waste Package Rotation Design Alternatives	2-27
2.4.2 Carrier Bay Design Alternative	2-28
2.4.3 Dual-Purpose Canister Cutting Alternatives	2-29
2.5 DESIGN BASIS EVENT ASSESSMENT	2-31
2.5.1 Introduction	2-31
2.5.2 Summary	2-31

Contents continued

2.6	PHASED CONSTRUCTION	2-33
2.7	COST ESTIMATE	2-34
2.8	THROUGHPUT ANALYSIS	2-36
2.8.1	Introduction	2-36
2.8.2	Scope	2-36
2.8.3	Approach	2-36
2.8.4	Basis and Assumptions	2-37
2.8.5	WITNESS Operational Simulation	2-38
2.8.6	Excel Spreadsheet Operational Simulation	2-38
2.8.7	Comparison of Results	2-38
2.8.8	Number of Weld Stations	2-39
2.9	PHASED CONSTRUCTION IMPLEMENTATION	2-39
3.	PATH FORWARD	3-1
3.1	INTRODUCTION	3-1
3.2	UPDATE OF PROJECT DOCUMENTS	3-1
3.3	ISSUES AND RECOMMENDATIONS	3-3
3.3.1	Maximum Throughput Requirements	3-3
3.3.2	Commercial Spent Nuclear Fuel Process Fuel Blending Inventory	3-3
3.3.3	CSNF Handling and Storage	3-4
3.3.4	Shipping Cask Drop Height	3-4
3.3.5	Inerting Requirements	3-5
3.3.6	Method to Determine Fuel Assembly Heat Output	3-5
3.3.7	Method to Determine Fuel Assembly Nuclear Reactivity	3-5
3.3.8	Waste Package Welding/Inspection Configuration and Operating Times	3-6
3.3.9	Cladding Performance in Dry Environment	3-6
3.3.10	Non-standard Fuel and Non-fuel Bearing Components	3-7
3.3.11	DPC Cutting and Contamination Control	3-7
3.4	DETAIL WASTE HANDLING BUILDING DESIGN SCHEDULE	3-8
4.	CONCLUSION	4-1
4.1	INTRODUCTION	4-1
4.2	DISCUSSION	4-1
5.	REFERENCES	5-1
5.1	DOCUMENTS CITED	5-1
5.2	CODES, STANDARDS, REGULATIONS, AND PROCEDURES	5-3

Contents continued

APPENDIXES:

Appendix A: Waste Handling Building Conceptual Design Guidance

Appendix B: Facility Layouts

Appendix C: Operational Flowcharts Non-Rotating WP Design Alternative

Appendix D: Throughput Analysis

Attachment D1: Operating Times and Sequence

Attachment D2: WITNESS Evaluation

Attachment D3: Excel Spreadsheet Evaluation

Attachment D4: Weld Station Calculation

Appendix E: Design Basis Event Assessment

Appendix F: Cost Estimate

INTENTIONALLY LEFT BLANK

FIGURES

	Page
Figure 1.4-1. WHB Conceptual Design Process	1-4
Figure 2.1-1. Flowchart.....	2-2
Figure 2.1-2. Maximum Blending Inventory, 11.8 kW Max WP Heat Output, No Co-Disposal	2-4
Figure 2.1-3. Maximum Blending Inventory, 11.8 kW Max WP Heat Output, Co-Disposal	2-5
Figure 2.1-4. Maximum Blending Inventory, 13.5 kW Max WP Heat Output, No Co-Disposal	2-6
Figure 2.9-1. Option NR-1A Cases 1 & 2 WHB and BOP Cost/Budget Profile	2-43
Figure 2.9-2. Option NR-1A Case 3 WHB and BOP Cost/Budget Profile.....	2-43
Figure 2.9-3. Option NR-1A Case 32 WHB and BOP Cost/Budget Profile.....	2-43
Figure 2.9-4. Option NR-1A Case 33 WHB and BOP Cost/Budget Profile.....	2-43
Figure 2.9-5. Option NR-1B Cases 1, 2, & 3 WHB and BOP Cost/Budget Profile.....	2-44
Figure 2.9-6. Option NR-1B Case 32 WHB and BOP Cost/Budget Profile.....	2-44
Figure 2.9-7. Option NR-1B Case 33 WHB and BOP Cost/Budget Profile.....	2-44
Figure 2.9-8. Option T-1A Cases 1 & 2 WHB and BOP Cost/Budget Profile	2-45
Figure 2.9-9. Option T-1A Case 3 WHB and BOP Cost/Budget Profile.....	2-45
Figure 2.9-10. Option T-1A Case 32 WHB and BOP Cost/Budget Profile.....	2-45
Figure 2.9-11. Option T-1A Case 33 WHB and BOP Cost/Budget Profile.....	2-45
Figure 2.9-12. Option T-1B Cases 1, 2, & 3 WHB and BOP Cost/Budget Profile.....	2-46
Figure 2.9-13. Option T-1B Case 32 WHB and BOP Cost/Budget Profile.....	2-46
Figure 2.9-14. Option T-1B Case 33 WHB and BOP Cost/Budget Profile.....	2-46
Figure 3.4-1. Concept Design Path Forward Schedule	3-9

INTENTIONALLY LEFT BLANK

TABLES

	Page
Table 1.4-1. Design Alternative Summary Description.....	1-6
Table 2.1-1. Peer Review: Comparison of Wet and Dry SNF Handling.....	2-9
Table 2.1-2. Estimated Weld Step Duration.....	2-14
Table 2.5-1. Comparison of Lifts	2-33
Table 2.5-2. Summary Comparison of WHB Conceptual Design with SR Design	2-33
Table 2.7-1. Construction Cost Estimate Options	2-34
Table 2.7-2. Capital Cost Estimate Summary	2-35
Table 2.8-1. Comparison of Results	2-38
Table 2.9-1. Startup Need Dates for Modules.....	2-39
Table 2.9-2. WHB Study Funding Profile (Non-Rotating Waste Package Alternative) (\$1,000s).....	2-41
Table 2.9-3. WHB Study Funding Profile (Turntable Alternative) (\$1,000s)	2-42
Table 3.2-1. Recommendations for Capturing Proposed Requirements.....	3-1
Table 4.2-1. Major Parameters Comparison	4-3

INTENTIONALLY LEFT BLANK

ACRONYMS AND ABBREVIATIONS

ALARA	as low as is reasonably achievable
ANSI	American National Standards Institute, Inc.
ANS	American Nuclear Society
anti-Cs	anti-contamination clothing
atm	atmosphere
ATS	Assembly Transfer System
BCP	baseline change proposal
BDBE	beyond design basis events
BOP	Balance of Plant
BWR	boiling water reactor
C	Celsius
CA	construction authorization
CFR	Code of Federal Regulations
CO	carbon monoxide
CO ₂	carbon dioxide
CPB	Carrier Preparation Building
CRWMS	Civilian Radioactive Waste Management System
CSNF	commercial spent nuclear fuel
CTS	Canister Transfer System
DBE	design basis event
DC	disposal container
DHLW	defense high-level waste
dia	diameter
DOE	U.S. Department of Energy
DPC	dual-purpose canister
ES&H	Environmental, Safety and Health
EM	Environmental Management
F	Fahrenheit
FY	fiscal year
H1	first half of fiscal year
H2	second half of fiscal year
HEPA	high efficiency particulate air
Hg	mercury
HLW	high-level waste
HP	Health Physics
hrs	hours
HVAC	heating, ventilation, and air-conditioning
IFC	indirect field cost

ACRONYMS AND ABBREVIATIONS (Continued)

INEEL	Idaho National Engineering and Environmental Laboratory
IP	immobilized plutonium
K	Kelvin
kg	kilogram
kW	kilowatt
LA	License Application
lb	pound
LWT	legal weight truck
M&O	Management and Operating Contractor
m	meter
MAR	material-at-risk
MCO	multi-canister overpack
MGR RD	Monitored Geologic Repository Requirements Document
min	minute
mm	millimeter
mrem	millirem
MTU	metric tons of uranium
N/A	not applicable
NPV	net present value
NR	non-rotating
NRC	Nuclear Regulatory Commission
O ₂	Oxygen
PDD	Project Description Document
PWR	pressurized water reactor
rem	roentgen equivalent man
SDD	System Description Document
SED	Systems Engineering Department
SFA	spent fuel assembly
SNF	spent nuclear fuel
SPC	single-purpose cask
SR	Site Recommendation
SRS	system requirements specification
T	turntable
TBD	to be determined
TBV	to be verified
TSAR	Topical Safety Analysis Report
TSLCC	total system life-cycle cost
TSPA	Total System Performance Assessment

ACRONYMS AND ABBREVIATIONS (Continued)

UO ₂	uranium dioxide
VA	Viability Assessment
WASRD	Waste Acceptance System Requirements Document
WHB	Waste Handling Building
wk	week
WP	waste package
WPDD	Waste Package Design Department
WTB	Waste Treatment Building
yr	year

INTENTIONALLY LEFT BLANK

1. INTRODUCTION

1.1 OBJECTIVE

The objective of the Waste Handling Building (WHB) Conceptual Study is to develop proposed requirements for the License Application (LA) design of the Waste Handling System in sufficient detail to allow the design to proceed as early as possible in Fiscal Year (FY) 2001.

To meet this objective, this study attempts to provide an alternative design to the present Site Recommendation (SR) design that is flexible, simple, reliable, and can be constructed in phases. This conceptual design will provide input to the ongoing *CRWMS Modular Design/Construction and Operation Options Report* (CRWMS M&O 1998), to develop the overall program objectives and direction. This study, herein, is limited to the Waste Handling System and associated fuel staging system. Items such as waste transportation options, phased construction of the subsurface facility, waste package (WP) loading sequence in the subsurface, and total system life cycle cost (TSLCC), are not included. These program level issues will be evaluated in the *CRWMS Modular Design/Construction and Operation Options Report* (CRWMS M&O 1998). That document will integrate all aspects of the repository operation (of which the WHB is only one part) and develop program level options and recommendations to optimize the overall operation of the repository.

The activities associated with the production of this document are not subject to the *Quality Assurance Requirements and Description* (QARD) (DOE 2000). This study has been prepared using the development plan submitted to the Records System, *Development Plan for White Paper: Waste Handling Building Conceptual Study* (CRWMS M&O 2000e), which was prepared in accordance with applicable portions of AP-2.21Q, *Quality Determinations and Planning for Scientific, Engineering, and Regulatory Compliance Activities*. Methods used to control the electronic management of data are as specified in the development plan.

1.2 BACKGROUND

The Viability Assessment (VA) and SR WHB designs separated the handling of canistered fuel and uncanistered fuel into two independent processing modules. The canisters were handled in a dry transfer line, while the uncanistered fuel was handled in a wet transfer line. Handling of the canisters was somewhat simpler than handling the uncanistered fuel, since contamination control was not a concern. Therefore, a simple dry transfer system was developed. Handling of the uncanistered fuel is much more complicated and the design was driven by two major factors:

- A standard design for incoming casks did not exist and therefore the method to unload the casks had to be flexible enough to accommodate various cask heights and diameters.
- The amount of fuel blending inventory required to perform the thermal blending was estimated to be 5,000 metric tons of uranium (MTU), or approximately 12,000 assemblies. It should be noted that blending was not included in the VA design.

Presently, there are about 30 different existing or potential shipping cask configurations which have various heights and diameters. The unloading portion of the WHB must accommodate all cask configurations. To accomplish this in the SR reference design, it was determined that the easiest method was to transfer the casks to a pool and unload them underwater. This approach allows the acceptance of any size cask but also requires that fuel assemblies be unloaded in a wet environment. This issue is addressed in Section 2.1.2.6.

The amount of fuel blending inventory included in the SR reference design was based on the limitation of the maximum heat output for each waste package at 11.8 kW. With the average heat output for a pressurized water reactor (PWR) WP at 11.3 kW, this results in a margin of only 4 percent between the average and maximum allowable heat output of the WP. The overall effect is that the PWR assemblies must be thermally blended. Since the incoming waste stream is not controlled to ensure that the thermal blending requirements can be met, the design of the WHB must be able to temporarily stage the assemblies that do not meet the required thermal limits. The initial estimation of the maximum number of assemblies that must be kept in fuel blending inventory at any time was approximately 12,000. With this large number of assemblies, previous studies found that it was impractical to utilize dry storage, and therefore pools were incorporated in the SR reference design. This issue is addressed in Section 2.1.2.4.

These requirements became drivers for a WHB design that resulted in the adoption of a wet system to handle and store bare fuel assemblies.

1.3 SCOPE

The scope of work for this study is as follows:

- Develop suggested recommendations that would lead the WHB to a flexible, simple, reliable, and modular design.
- Develop conceptual layout drawings, process flow diagrams, and throughput predictions to confirm that the recommendations can actually be implemented.
- Develop construction options that allow the WHB to be constructed in phases if necessary.
- Develop a preliminary cost basis for each construction option that can be used to establish the optimum overall program approach.

During the WHB Conceptual Study, the following major issues were addressed, with a recommended path forward:

- What could be done to minimize the impact of uncanistered fuel blending on the surface facility design and operation?
- Should the incoming uncanistered fuel be handled and stored using wet or dry methods?

1.4 TECHNICAL APPROACH

The technical approach used in this study followed the flowchart shown in Figure 1.4-1. The following steps were included:

- Define Technical Requirements
- Define WHB Process
- Develop WHB Design/Layouts
- Identify Design Basis Events (DBEs)
- Determine Phased/Modular Construction Approach and Layouts
- Prepare Cost Estimates and Throughput Analyses
- Prepare WHB Design Recommendations
- Obtain DOE Approval
- Develop Fiscal Year (FY)2001 Baseline Plan and Modified FY2001 Technical Plan
- Develop Final FY2001 Technical Plan.

1.4.1 Define Technical Requirements

A kickoff meeting was held on April 11 and 12, 2000 to define technical assumptions for the design of the WHB, including the Carrier Preparation Building (CPB) and the Waste Treatment Building (WTB). This brainstorming session, attended by various Management and Operating Contractor (M&O) design organizations, resulted in a first draft of the proposed technical requirements, later titled the "Waste Handling Building Conceptual Study Design Guidance" (WHB Conceptual Design Guidance), Appendix A of this document. The assumptions and proposed requirements were continuously reviewed during this study to evaluate impacts on the design. An iterative approach was used to refine the WHB Conceptual Design Guidance and layouts.

1.4.2 Define Waste Handling Building Process

During the kickoff meeting described above, the systems and processes used in the SR reference design for the WHB, CPB, and WTB were summarized in flowcharts. These flowcharts formed the basis for the layouts and designs for this study. As the conceptual design progressed, the flowcharts were updated; the updated versions are shown in Appendix C.

1.4.3 Develop Waste Handling Building Design/Layouts

During the brainstorming session mentioned above, several preliminary layouts were prepared that addressed issues such as wet versus dry handling of assemblies, modular design, and fuel blending inventory. These layouts were used to form the basis of several design concepts that were evaluated during this study. During weekly status meetings attended by various M&O design organizations, alternative layouts and concepts were reviewed and revised. Two primary design alternatives were developed:

DOE - U.S. Department of Energy; FY - Fiscal Year

Figure 1.4-1. WHB Conceptual Design Process

- Non-Rotating WP Design Alternative, in which the Disposal Container Handling System and weld stations are based on the WP remaining stationary, with the weld equipment rotating about the center of the WP.
- Turntable Design Alternative, in which the Disposal Container Handling System and weld stations are based on rotating a WP on a turntable during the welding process.

These two primary design alternatives were carried throughout this study. Other design alternatives were also evaluated, including a Carrier Bay configuration and two dual-purpose canister (DPC) cutting concepts, which are presented in Section 2.4 of this document.

1.4.4 Identify Design Basis Events

Using the conceptual layouts, a preliminary DBE analysis was performed. The results of this analysis were compared to the DBEs identified in the SR design (Section 2.5 and Appendix E).

1.4.5 Determine Phased/Modular Construction Approach and Layouts

Phased construction and modular design are secondary objectives of this study, and the layouts included modular concepts from the beginning. Ideas were solicited during the brainstorming session of April 11 and 12, and the layouts carried forward during this study included modular design. To ensure consistency in terminology, the following definitions were used:

- Modular – Designed with standardized units or dimensions to provide flexibility in how and when each unit is constructed.
- Phased – Constructed by planned phases, or in stages.

Four construction options were defined, using a modular design concept with three modules (Modules 1, 2, and 3). The definition of each module is provided in Section 2.6. The construction options were defined as follows:

- Construction Option Non-Rotating (NR)-1A – For the Non-Rotating WP Design Alternative, construct Module 1 during the first phase of construction (Phase 1), Module 2 during Phase 2, and Module 3 during Phase 3.
- Construction Option NR-1B – For the Non-Rotating WP Design Alternative, construct Modules 1 and 2 during Phase 1, and Module 3 during Phase 2.
- Construction Option Turntable (T)-1A – For the Turntable Design Alternative, construct Module 1 during Phase 1, Module 2 during Phase 2, and Module 3 during Phase 3.
- Construction Option T-1B – For the Turntable Design Alternative, construct Modules 1 and 2 during Phase 1, and Module 3 during Phase 2.

Table 1.4-1 summarizes the construction options, phases, modules, and waste receipt combinations for each of the two design alternatives described in Section 1.4.3.

Table 1.4-1. Design Alternative Summary Description

Design Alternative	Construction Option	Phase	Modules Included in Phase	Waste Receipt Case
Non-Rotating WP				
	NR-1A	1	Module 1	Cases 1, 2, 3, 32 & 33
		2	Module 2	Cases 1, 2, 3, 32 & 33
		3	Module 3	Cases 1, 2, 3, 32 & 33
	NR-1B	1	Modules 1 & 2	Cases 1, 2, 3, 32 & 33
		2	Module 3	Cases 1, 2, 3, 32 & 33
Turntable				
	T-1A	1	Module 1	Cases 1, 2, 3, 32 & 33
		2	Module 2	Cases 1, 2, 3, 32 & 33
		3	Module 3	Cases 1, 2, 3, 32 & 33
	T-1B	1	Modules 1 & 2	Cases 1, 2, 3, 32 & 33
		2	Module 3	Cases 1, 2, 3, 32 & 33

1.4.6 Define Receipt Scenarios, Milestone Schedule, and Funding Constraints

Baseline waste receipt scenarios were taken from the *Monitored Geologic Repository Project Description Document* (PDD) (CRWMS M&O 2000b) and were included in the WHB Conceptual Design Guidance (Appendix A). Additional scenarios were further defined by the ongoing *CRWMS Modular Design/Construction and Operation Options Report* (CRWMS M&O 1998) and are included in the WHB Conceptual Design Guidance. Five waste receipt cases for Commercial Spent Nuclear Fuel (CSNF) were used in this study:

- Case 1   Maximum Truck Casks – Rail available in 2010
- Case 2   Maximum Single Purpose Casks (SPC) Rail Casks – Rail available in 2010
- Case 3   Maximum DPC Rail Casks – Rail available in 2010
- Case 32   Initial 1,200 MTU, 2,400 MTU in 2015, 3,600 MTU in 2028 – Rail available in 2010
- Case 33   Initial 800 MTU (Legal-weight truck [LWT]), 2,400 MTU in 2014, 3,600 MTU in 2028 – Rail available in 2014

The CSNF cases described above were combined with the DOE/naval receipt rate for spent nuclear fuel (SNF) and high-level waste (HLW). The milestone schedule was taken from the current baseline schedule. Funding constraints were determined from the *CRWMS Modular Design/Construction and Operation Options Report* (CRWMS M&O 1998), and evaluated against the funding requirements determined from the cost estimates and throughput requirements in this study.

1.4.7 Prepare Cost Estimates and Throughput Analyses

For each design alternative and construction option identified in Table 1.4-1, capital cost estimates were prepared and are included in Appendix F. To determine the throughput capacity of the design, two types of analyses were performed. A "spreadsheet" analysis using operational sequences and estimated operational time durations was prepared. Also, a WITNESS (see Appendix D) analysis using the same sequences and time durations was developed. The results of the two analyses were compared and reconciled. Using these results, the required startup dates for each module were determined.

1.4.8 Prepare Waste Handling Building Design Recommendations

Design options were prepared, using the results of the evaluation and reviews of design alternative layouts and concepts, as well as the modular design and phased construction analysis. Conclusions are presented in Section 4 of this document and a recommended path forward is shown in Section 3.

1.4.9 DOE Review

This WHB Conceptual Study will be reviewed by DOE and M&O participants. Recommendations for proposed requirements in the LA version of the PDD (CRWMS M&O 2000b) and the SDDs are included in the WHB Conceptual Design Guidance, Appendix A of this document.

1.4.10 Update FY2001 Technical Plan

The present FY2001 baseline plan is based on the SR WHB conceptual design. If the recommendations in this report are considered viable, a Baseline Change Proposal (BCP) should be prepared using procedure AP-3.14Q to request approval by M&O Management and DOE. It may be necessary to prepare additional documentation to supplement this study in order to change the baseline.

INTENTIONALLY LEFT BLANK

2. DESIGN ANALYSIS

2.1 DESIGN GUIDANCE

2.1.1 Introduction

The primary objective of the WHB Conceptual Study is to develop proposed requirements for the LA version of the WHB design in sufficient detail to allow the design to proceed as early as possible in FY2001. The vehicle for capturing these proposed requirements is the "Waste Handling Building Conceptual Study Design Guidance" (WHB Conceptual Design Guidance), which is contained in Appendix A. Following is a discussion of the basis for each of these recommendations.

2.1.2 Basis for Recommendations

2.1.2.1 Types of Waste Forms and Required Function of the WHB Facility

The types of waste forms that must be processed by the WHB are defined in the PDD (CRWMS M&O 2000b) and are used as an assumption for this WHB Conceptual Study.

2.1.2.2 Processing Options

The actual incoming waste stream and the method of emplacement of the WPs are not known for certain. Because of this, it is imperative that the design of the WHB be as flexible as possible to accommodate future repository design options without having to make major modifications to the WHB. The required functions of the WHB facility were developed in an attempt to account for this uncertainty. The flowchart in Figure 2.1-1 defines those WHB functions that must be incorporated into the design.

2.1.2.3 Maximum Waste Throughput Requirements

For the purpose of this study, the CSNF and DOE throughput requirements are based on the latest version of the PDD (CRWMS M&O 2000b) with the exception of the naval canister arrival schedule. Naval Reactors issued a memorandum, "Comments on Waste Acceptance System Requirements Document Revision 4," (Mowbray 2000), with comments on the PDD (CRWMS M&O 2000b) requesting the naval waste stream be modified. The waste stream presented in Appendix A reflects this revised waste stream.

2.1.2.4 Process Fuel Blending Requirements for Commercial Spent Nuclear Fuel

During the 1999 evaluation of the wet versus dry options for CSNF handling (*Summary of Work in Progress for Reconfiguration of the Waste Handling Building* [1999 Wet/Dry Study], CRWMS M&O 1999), it was assumed that approximately 5,000 MTU of process fuel blending inventory was required and that this inventory would be staged in a wet pool for the wet option and in dry vaults for the dry option. This inventory and storage method resulted in a high initial capital cost and did not provide any margin for additional staging capacity that is limited by the PDD maximum of 5,000 MTUs.

Required Functions of the WHB Facility

Waste Package

Uncanistered CSNF

Canistered CSNF

DOE SNF/HLW/IP*

*Staging is not required for naval SNF, the fuel will be transferred directly from the shipping cask to a WP.

Figure 2.1-1. Flowchart

A major focus of the WHB Conceptual Study was to evaluate the level of blending inventory that is required, and the storage method used, in an attempt to develop engineering solutions that would increase the margin to the 5,000 MTU limit and reduce the capital costs of the staging system. The results of these evaluations are presented in the following sections.

2.1.2.4.1 Improved Blending Algorithm

The initial algorithm that was used to develop the 5,000 MTU fuel blending inventory level loaded assemblies into a WP whenever the sum of individual assembly heat outputs was less than 11.8 kW. This allowed WPs to sometimes be loaded with only cold assemblies and resulted in approximately 33 percent of the PWR WPs being loaded to less than 10.0 kW. The consequence of loading only cold assemblies into a WP is that they would not be available when needed to blend with the hot assemblies and therefore, the hot assemblies would have to be placed in blending inventory. This caused the blending inventory to increase to approximately 11,590 assemblies, with approximately 9,400 assemblies remaining in fuel blending inventory at the end of 2040.

A revised algorithm was developed that could "look ahead" to determine the heat output of the assemblies that would be arriving in the near future. If the upcoming waste stream is hot, the allowable minimum WP heat output would be increased, preventing the loading of only cold assemblies into a WP and thus making them available to blend with the hot assemblies. If the upcoming waste stream is cold, the allowable minimum WP heat output would be decreased, allowing loading the WP to a lower heat output. This change in the algorithm resulted in a peak blending inventory of approximately 3,750 assemblies. Figure 2.1-2 provides the profile of the number of assemblies in blending inventory and number of dry storage casks (less 432 assemblies in the Transfer Cells) as a function of emplacement year. This decrease in predicted blending inventory provides a margin of approximately 8,250 assemblies to the 12,000 maximum allowable inventory.

2.1.2.4.2 Co-Disposal of BWR and PWR Assemblies

The average BWR assembly has a heat output of approximately 160 watts and the average PWR assembly has a heat output of approximately 540 watts. One potential approach to reduce the blending inventory, and still maintain the total WP heat output less than the required 11.8kW, is to co-dispose in the same WP the colder BWR assemblies with the hotter PWR. Sensitivity analyses were run to determine the optimum number of BWR assemblies to co-dispose with PWR assemblies to reduce the blending inventory and at the same time minimize the number of additional waste packages required. It was determined, for the periods when the PWR waste stream is above the average, that mixing 5 cold BWR assemblies with 16 hot PWR assemblies in the same WP reduced the peak blending inventory to approximately 1,000 assemblies. Figure 2.1-3 profiles the peak number of blending inventory assemblies and the number of dry storage casks (less 432 assemblies in the Transfer Cells) required as a function of emplacement year.

Figure 2.1-2. Maximum Blending Inventory, 11.8 kW Max WP Heat Output, No Co-Disposal

This option increases the margin to the maximum blending inventory, reduces the number of dry storage casks required, and increases the flexibility to accommodate variations in the incoming waste stream. It does, however, increase the total number of WPs by approximately 300. In addition to the increased number of WPs, determination of the feasibility of this option will require 1) additional criticality analyses to verify that it is possible to co-dispose BWR assemblies with PWR assemblies, and 2) analyses to determine the structural integrity of a modified WP design that will accommodate loading assemblies with different dimensions into the same WP. Preliminary assessments indicate a significant cost increase for the WP basket may be required. Furthermore, it is questionable whether the integrity of the basket structure could be maintained during design basis events because the different dimensioned assemblies will necessitate plates which do not traverse the complete width of the WP.

Figure 2.1-3. Maximum Blending Inventory, 11.8 kW Max WP Heat Output, Co-Disposal

2.1.2.4.3 Increase the Maximum Allowable Waste Package Heat Output

The present PWR waste stream has an average assembly heat output of approximately 540 watts, which corresponds to an average 21-PWR WP heat output of 11.3 kW. The present maximum allowable WP heat output design solution of 11.8 kW provides approximately only 4 percent of margin to accommodate blending. Sensitivity analyses were run to determine the effect of increasing the maximum WP heat output above 11.8 kW on the blending inventory level. The results of this analysis indicated that increasing the maximum allowable WP heat output to 13.5 kW reduced the peak blending inventory to approximately 650 assemblies. Figure 2.1-4 profiles the peak number of blending inventory assemblies and the number of dry storage casks (less 432 assemblies in the Transfer Cells) required as a function of emplacement year.

This option increases the margin to the maximum blending inventory, reduces the number of dry storage casks required, and increases the flexibility to accommodate variations in the incoming waste stream. In addition, this option does not increase the total number of WPs, does not require additional criticality analysis, or require redesign of the WP. It does, however, require

significant effort to re-perform the thermal analyses of the WP to confirm that the waste form surface temperature limits are not violated and the thermal analyses of the emplacement drifts to ensure no thermal limits are exceeded. It should be noted that increasing the maximum allowable WP heat output does not change the average heat of the WPs or the total heat transferred to the surrounding rock. It is possible that some of these requirements would need to be modified in order for increased WP heat output to be a viable option.

Figure 2.1-4. Maximum Blending Inventory, 13.5 kW Max WP Heat Output, No Co-Disposal

2.1.2.4.4 Receiving Waste in Accordance with a Preferred Waste Stream

If it were possible to manage the incoming waste so that a preferred waste stream could be specified, the blending inventory could be reduced significantly. The objective of the preferred waste stream would be to have a relatively constant WHB throughput with the average heat output of each fuel type received in a three-month period as near the average of the entire inventory as possible. The commercial waste stream would consist of approximately 750 MTU per three-month period; with an approximate 4 to 3 ratio of BWR assemblies to PWR assemblies. Based on the present thermal goals, the average assembly heat output would have to

be approximately 540 watts per PWR assembly and 160 watts per BWR assembly during any three-month period (approximately 17-year-old fuel for both PWR and BWR assemblies).

This potential option would not require any changes to the present project requirements and is independent of the design solutions presented in Sections 2.1.2.4.2 and 2.1.2.4.3. Though no detailed blending analysis has been performed for this option, it is clear that the blending inventory would be reduced, which could lead to a reduction in the WHB cost. However, in order to be implemented, this option will require negotiation with the utilities that could result in changes to the standard contract and potentially additional costs to the overall program. Because of this, the M&O is not considering this option in the design of the WHB but rather that the waste stream is unconstrained. Should it be possible to receive the waste in accordance with a preferred waste stream, it would not change the design of the WHB concept presented in this study but could simplify the operations and potentially reduce the operating costs.

2.1.2.4.5 Blending Inventory Staging Options

The SR WHB design includes a large pool for staging 12,000 assemblies that cannot be loaded directly into WPs. This method for staging requires a large initial capital expenditure and limits the flexibility to adapt to variations in the amount of blending inventory required. If the actual staging requirements are less than predicted then the staging facility would be under utilized; if the actual staging requirements are greater than predicted then the staging facility could run out of capacity and potentially restrict the operation of the entire WHB.

Because of the uncertainty in the amount of blending inventory that will be required, it is important that the system developed be flexible enough to expand/contract as the blending inventory requirements change, and at the same time allow easy access to a portion of the assemblies to facilitate loading the WPs. Based on the sensitivity analyses performed to date, it appears that approximately 400 assemblies are required to facilitate the loading of the WPs and that they need to be located as near to the loading operation as possible. Any blending inventory in excess of these 400 assemblies, up to a maximum of 12,000 assemblies, may be located outside of the WHB but needs to be staged in modules that allow expansion/contraction of the inventory level and allow retrieval of small portions of the inventory when needed.

2.1.2.4.6 Summary

Because of the uncertainty associated with predicting the incoming waste stream, and thus the amount of blending inventory that will be required, it is important to provide as much flexibility as possible in the design of the WHB. The revised blending algorithm does not change the basic repository design basis but does provide acceptable margin to the maximum allowable staging level of 5,000 MTU. A relatively small amount of blending inventory inside the WHB will provide flexibility for blending and loading the WPs. Staging of assemblies in excess of the amount stored inside the WHB in modules external to the WHB will provide flexibility for variations in the total amount of blending inventory required and allow spreading the capital cost for the staging facility out over several years. In addition, there is a potential to increase the margin even further if future analyses confirm that either the WP maximum allowable heat output can be increased or if co-disposal of BWR and PWR assemblies can be adopted. These engineering options need to be evaluated further to confirm their validity.

2.1.2.5 Process Fuel Staging Requirements for DOE/Naval SNF

The DOE WPs, with the exception of the naval canisters, will generally contain 5 HLW glass logs and 1 SNF canister. Since these waste forms will be shipped separately, a small amount of canister staging inventory is necessary to accommodate co-disposal of the DOE waste forms. It was assumed that having the capability to store 25 canisters was sufficient to accomplish this co-disposal. There is a possibility that a much greater DOE canister storage capability will be required if it is determined that a central storage facility at Yucca Mountain is preferred over individual storage facilities at each of the DOE sites. If this does occur, the storage facility would probably be separate from the WHB and is beyond the scope of this study.

The naval SNF will be shipped to the repository in single canisters that will be transferred directly to a DC. Since this is a one-for-one transfer, no staging inventory capability is necessary for the naval SNF.

2.1.2.6 CSNF Handling and Storage

One of the major factors leading to adopting wet assembly handling for the VA and SR WHB designs was the flexibility that the pools provide for handling casks of different sizes. As part of the 1999 Wet/Dry Study (CRWMS M&O 1999), a dry design was developed that included adapters that allowed the various diameter casks to mate up with the unloading port. Also, the cask transporter cart was designed to elevate the cask to compensate for the various cask heights. These design solutions accounted for the unloading of dry casks of various sizes, and simplified the WHB design by eliminating the pools and all of the pool support facilities.

A peer review of the SR wet design and the dry design that incorporated the above design solutions was conducted on August 4 and 5 of 1999 (1999 Wet/Dry Study [CRWMS M&O 1999]). It should be noted that the present SR design for handling commercial uncanistered SNF assemblies is a hybrid design which combines both a wet pool for unloading the casks and a dry handling cell for drying the SNF and loading the DC. The members of the peer review team are listed below.

<u>Name</u>	<u>Company</u>	<u>Experience</u>
Pierre Saverot	Johnson Associates, Inc.	French SNF operational experience
Larry Waggoner	Fluor Daniel Hanford	Health physics and radiological controls
Kim Childs	Lockheed Martin	SNF operations at INEEL
Jim Linhart	Lockheed Martin	SNF operations at INEEL
Bob Kaestner	Bechtel, Bettis, Inc.	Naval SNF operations experience

The results from the peer review, published in the 1999 Wet/Dry Study (CRWMS M&O 1999) confirmed that either wet or dry handling is feasible and that both have advantages and

disadvantages. Table 2.1-1 provides a comparison of each option as determined by the review team.

Table 2.1-1. Peer Review: Comparison of Wet and Dry SNF Handling

Wet SNF Handling	Dry SNF Handling
<u>ADVANTAGES</u> 1. There is substantial experience in operating spent fuel pools. 2. There is substantial experience in NRC-licensing of fuel pool operations. 3. The pool water provides effective, flexible radiation shielding. 4. The pool water provides effective heat dissipation. 5. Accessibility to equipment and all operational areas in the pool is high. 6. Tooling required for operations is usually simple. 7. Pools provide greater flexibility in reacting to off-normal activities. <u>DISADVANTAGES</u> 1. Potential for pool liner leaks. • Leak detection is difficult • Leak repair is difficult • Pool liner becomes another vulnerability for accident analysis • Public perception of pool operations is poor 2. Pools cause equipment challenges. • Equipment is difficult to repair underwater • Preventive maintenance is difficult underwater • Special design required for work underwater • Equipment corrosion is enhanced underwater • Electrical Equipment is harder to use in a pool environment 3. Decontamination of equipment (previously) immersed in pools is difficult. Casks (that have been) immersed in pools have a tendency to "weep" contamination after decontamination has been completed. 4. Pools result in a number of additional water-treatment activities (cooling, filtration, sterilization, ion exchange) that require personnel and expense as well as cause additional hazards. 5. Pools result in a number of additional waste streams.	<u>ADVANTAGES</u> 1. No assembly drying is required before placement in the disposal container (DC). 2. No cask cooling is required before fuel assemblies are removed. (French experience is that fuel removal times are reduced by about 33%.) 3. Decontamination of casks is eliminated or at least greatly reduced. 4. Less personnel exposure. (French experience is a reduction by a factor of five.) 5. Potential for contamination spread is reduced. 6. Reduced amount of liquid radioactive waste. (French experience is that liquid wastes are reduced by 2/3.) 7. Increased throughput. <u>DISADVANTAGES</u> 1. Access inside the hot cell is limited. • May not be able to get to everything that is dropped • Access to react to a failure is limited 2. Access to repair equipment is limited 3. Complicated remote handling manipulators in hot cells can be a reliability and repair problem – redundancy is a significant requirement. 4. Movement of larger equipment into or out of a hot cell can be a problem. 5. Hot cell shielding is costly.

Wet SNF Handling	Dry SNF Handling
• Pool water • Ion exchange resins • Filter media 6. There is less productivity in working from the pool deck versus remotely in a hot cell. • Visibility for activities underwater is difficult due to water contamination, waves, and parallax • Work is exhausting in trying to manipulate long equipment • Anti-Cs are required on the pool deck • Frisking is required when exiting the pool deck 7. ALARA – while exposure rates are low, there is more exposure to those working on the pool deck versus those who work outside a hot cell. 8. Contamination control is required in the pool area. • Bathtub rings tend to collect radioactive particles which become airborne when the ring dries out • Smaller particles can become airborne due to the evaporation process • There is particle migration because after wetting surfaces, water evaporates off and air currents spread contamination • Over time, contamination collects in the bottom of the pool and can be stirred up by activities in the pool, whereas in the hot cell it can be vacuumed and discharged as solid waste 9. Increased requirements for criticality control. • Adds more accident scenarios 10. There are more safety challenges when working in a pool environment. • Heat exhaustion is a potential when working in anti-C clothing • There is the potential that workers could fall into the pools 11. Startup for a wet system presents more challenges and takes longer to complete. 12. Seismic requirements for a pool system are more challenging.	

Source: Derived from 1999 Wet/Dry Study, Attachment VIII (CRWMS M&O 1999).

The conclusion of the 1999 Wet/Dry Study (CRWMS M&O 1999) suggested that dry handling is preferable over wet handling both from an operational and maintenance point of view, and to

minimize waste streams created from the pool cooling and cleanup systems. It should be noted that eliminating the pools will put additional requirements on the HVAC system to remove additional heat and some of the contamination that would otherwise be handled by the pool water filtration system.

Even though the dry option was preferred from an operational and maintenance point of view, the wet option was selected over the dry option because of the dry option's greater fuel staging cost. As part of this WHB Conceptual Study, options were evaluated in an attempt to better manage the fuel staging assumed in the 1999 study, and the results are presented in Section 2.1.2.4. This evaluation showed that there is acceptable margin between the predicted maximum inventory of 3,750 assemblies and the maximum allowable staging inventory of 12,000 assemblies. The staging option presented in Section 2.1.2.4.5 provides flexibility for in-process blending and modular storage to accommodate a staging inventory of up to 12,000 assemblies, of which 432 would be staged inside the WHB. Utilizing a dry storage cask that can hold 24 assemblies would result in a need for approximately 485 casks $[(12,000-432)/24]$. The modular dry storage casks provide greater flexibility for staging and spreads out the staging costs over several years, thus reducing the initial capital expenditure. Therefore, because of the superior operational and maintenance performance of the dry option as indicated in the 1999 study, and the improved flexibility of the dry option developed in this study, it was determined that the dry option is the preferred method for handling and storing CSNF.

It should be noted that it might be possible to reduce the combined WP and storage cask cost by fabricating storage canisters that could also be used for disposal. This would reduce the cost of the WPs since the WP internals would be eliminated and should reduce the total WP/storage cask capital costs. This would also reduce the number of times the bare CSNF assemblies would have to be handled.

2.1.2.7 Transfer Lines

The present version of the SR WHB design utilizes separate processing lines for canistered fuel (Canister Transfer System) and uncanistered fuel (Assembly Transfer System). Each system operates independently of the other and has different equipment and processes. Though there are some advantages to separating these two processes, it makes the WHB less flexible (not able to handle variations in the incoming waste stream as easily), and does not support modular construction. With the decision to process uncanistered fuel in a dry environment, the ability now exists to combine these two processes into one and standardize the equipment and operation. Having a generic processing line for both canistered and uncanistered fuel also makes the design of discrete modules easier and phased construction more practical. The SR design and the conceptual design exhibit varying degrees of complexity. The SR design has more equipment and handling overall while the dry design has potentially more mechanical equipment and complex operations taking place within the Transfer Cell.

2.1.2.8 DC Handling Area Radiation Levels

The WHB design for the SR does not shield the disposal container (DC), but rather has five-foot thick concrete walls in the DC Handling Area to reduce the radiation levels outside of the WHB. This approach precludes personnel access to the DC Handling Area due to the very high

radiation levels from the unshielded DCs. Reducing the general area radiation level inside the DC Handling area has several advantages, which include:

- Allowing temporary personnel access to the DC Handling Area to facilitate movement of the DCs and to simplify recovery from any off-normal events.
- Reduce the reliance on remote handling equipment needed to move the DC/WP within the DC Handling Area.
- Reduction of the DC Handling Area wall thickness, thus reducing seismic loads, construction complexity, and costs.

Therefore, for the purpose of the WHB Conceptual Study, a design for DC temporary shielding was developed that reduces the dose rate from the DCs to levels that would allow personnel to access the DC handling area.

2.1.2.9 Canister and Cask Maximum Drop Height

The allowable DOE canister drop height is presently under evaluation and will be documented in the *Waste Acceptance System Requirements Document* (DOE 1999). The WHB will be designed to prevent exceeding the lift height specified in this document.

At the present there are no data available on cask drop height without impact limiters installed. This data either needs to be developed in-house or obtained from the cask vendors. Though these data are not mandatory, it would improve the DBE evaluation if credit could be taken for the shipping casks durability.

2.1.2.10 Fuel Staging

There is a possibility that the project will adopt a repository design that prevents heating the rock surrounding the emplacement drifts to above boiling. To accomplish this, it may be necessary to age some of the incoming fuel for a considerable period of time, to reduce the amount of heat generated. It is the object of this study to develop a flexible design that can accommodate future repository designs and therefore included the staging option as a proposed requirement for the WHB conceptual design.

2.1.2.11 Disposal Container/Waste Package Staging

Staging facilities are necessary for loaded WPs to prevent shutdown of the WHB should a problem occur that prevents emplacing WPs. Based on throughput projections for the WHB, it is anticipated that a peak volume of between 2 and 3 WPs per day will be processed. Therefore, providing staging for 20 welded WPs would allow approximately a one-week shutdown of the subsurface facility without affecting the operation of the WHB.

2.1.2.12 Preclosure Safety Strategy

The design of the WHB and the preclosure safety strategy needs to be closely integrated to ensure the final design of the WHB meets the requirements of the preclosure safety strategy. A member of the task force who is responsible for developing the preclosure safety strategy was included in the team for the WHB Conceptual Design Guidance to ensure that this integration occurs. The proposed requirements presented in Appendix A are based on the methodology being developed by the preclosure safety strategy task force and will be revised as necessary should the preclosure safety strategy methodology change.

2.1.2.13 Inerting Requirements

Each individual WP must be inerted to ensure that the oxygen level is low enough to minimize oxidation of the fuel and internal structures. There are presently no requirements in the PDD defining the acceptable levels of oxygen for long-term storage in the repository. However, *Standard Review Plan for Dry Cask Storage Systems: Final Report* (NRC 1997) provides guidance for dry cask storage systems. These requirements reduce the amount of oxidants below levels where any cladding degradation is expected and is used as the basis for the proposed requirement in Appendix A.

2.1.2.14 Method to Determine Waste Form Heat Output

The thermal output of each waste form is necessary in determining each WP heat output and thus the thermal response of the repository. Discussions are underway with the U.S. Nuclear Regulatory Commission (NRC) as to whether it is acceptable to use the records from the utilities as the basis for the waste form heat output or if it is necessary to measure the actual heat output. The results of these discussions could have a major impact on the design and throughput of the WHB. The type of equipment and process to be used has not been defined, therefore incorporating this function into the conceptual design of the WHB is extremely difficult at this time. It was decided not to include waste form measurement into the present conceptual design of the WHB. If, in the future, the decision is made that measurement is required, this function will need to be incorporated into the WHB design.

2.1.2.15 Method to Determine Waste Form Nuclear Reactivity

The nuclear reactivity of each individual waste form is necessary in determining the margin to criticality of each WP. Discussions are underway with the NRC as to whether it is acceptable to use the records as the basis for the waste form nuclear reactivity or if it is necessary to measure the actual nuclear reactivity. The results of these discussions could have a major impact on the design and throughput of the WHB. The type of equipment and process to be used has not been defined, therefore incorporating this function into the conceptual design of the WHB is extremely difficult at this time. It was decided not to include waste form measurement into the present conceptual design of the WHB. If, in the future, the decision is made that measurement is required, this function will need to be incorporated into the WHB design.

2.1.2.16 WP Welding/Inspection Configuration and Operating Times

It is beyond the scope of the WHB Conceptual Study to evaluate the DC welding and inspection process. The goal presented in Appendix A represents input from the Waste Package Design Department and is based on the present SR reference design and mock-up testing that has been performed to date (Table 2.1-2, Knapp 2000).

Table 2.1-2. Estimated Weld Step Duration

Step Description (Note)	Operation Duration (hrs) ⁽¹⁾	Setup Duration (hrs) ⁽¹⁾	Total Duration (hrs) ⁽¹⁾
Inner Closure Weld	15	10	25
Inner Closure Weld Inspection ⁽²⁾	10	5	15
Middle Closure Weld	5	5	10
Middle Closure Weld Inspection ⁽²⁾	5	5	10
Middle Closure Weld Stress Relief	5	5	10
Outer Closure Weld	10	5	15
Outer Closure Weld Inspection ⁽²⁾	5	5	10
Outer Closure Weld Stress Relief	5	5	10
Total	60	45	105

Notes: (1) Estimated time does not include time to move equipment or WPs into position.

(2) It is assumed that the average weld rejection rate of 9 WPs per year will occur. The resolution of the weld defects will be handled on a case by case basis; however, provisions must be provided to unload the WP.

It is estimated that movement and setup of the DCs and equipment will require an additional 30 hours. Therefore, the WHB should be sized assuming it requires 135 hours to complete the closure of one DC.

2.1.2.17 Cladding Performance in Dry Environment

The uncanistered CSNF will be handled and transferred in a dry non-inerted environment and therefore the concern with oxidation and subsequent failure of the cladding is increased. DOE submitted the *Dry Transfer System Topical Safety Analysis Report* (TSAR) (DOE 1996) to the NRC on September 30, 1996. As a result of the NRC's review, on February 29, 2000, the NRC submitted a preliminary draft assessment report regarding the dry transfer system, which was docketed by the DOE for review (Docket 71-1024 [NRC 2000]). The proposed dry storage requirements presented in Appendix A, Section 2.16, are based on the DOE recommendations.

2.1.2.18 Contamination Control and Decontamination

The most effective method of contamination control is to prevent contaminating components, and to limit the number of areas where there is a potential for contamination. This is the basic methodology that has been applied to the WHB conceptual design. The contamination areas, as defined in 10CFR 835.20, in the WHB must be limited to the Transfer Cells and the WP Remediation Cell. Dry decontamination methods shall be applied in these areas. Dry

decontamination methods are preferred because they do not introduce liquids into a dry environment or process. In addition, elimination of the wet pools, and subsequent reduction in the systems needed to process liquid radioactive waste, requires that the amount of liquid radioactive waste be minimized. By using dry decontamination, the amount of Low Level Liquid Waste is greatly reduced. Any time a component is moved out of one of these areas, it should be surveyed for contamination and decontaminated if necessary. This will limit the contamination areas and reduce the need to survey/decontaminate the DCs prior to loading onto the subsurface WP transporter.

2.1.2.19 Non-standard Fuel and Non-fuel Bearing Components

The requirements for receipt of non-standard fuel and non-fuel bearing components are still under negotiation and have not been defined. It is believed that these items will be placed into standard canisters that can be processed with the standard handling equipment. Until these requirements are defined, it is impossible to incorporate the handling of these items into the design of the WHB. Therefore, the WHB Conceptual Study did not address handling non-standard fuel and non-fuel bearing components.

2.1.3 Summary

Once the design recommendations have been reviewed and approved by project management, many of the recommendations contained in the WHB Conceptual Design Guidance (Appendix A) can be incorporated into existing project documents. However, the study identified several items that need further evaluation and specific recommendations to resolve the issue. These items are included in Section 3, Path Forward.

2.2 FACILITY DESCRIPTION

The following WHB conceptual designs are based on the proposed technical requirements and waste handling process developed during this WHB Conceptual Study. Two basic WP welding design alternatives were evaluated. The first, identified as the Non-Rotating WP Design Alternative, is based on the WP remaining stationary, with the weld equipment rotating about the center of the WP. The second, identified as the Turntable Design Alternative, is based on a WP that rotates on a turntable during the WP closure welding process.

The WHB receives rail and truck transportation casks, unloads uncanistered CSNF assemblies, canistered DOE SNF and HLW from the transportation casks, opens DPCs and unloads CSNF assemblies, loads CSNF assemblies and canistered DOE SNF and HLW into DCs, performs WP closure (closure weld, weld inspection, and stress relief), loads WPs into subsurface transporters, and prepares empty transportation casks and DPCs for off-site shipment.

The major waste handling components of the WHB consist of the Carrier Preparation Area, the Carrier Bay, the Cask Preparation Area, the Transfer Cell, the DC Load Cell, the DC Handling Area, the WP Weld Area, the Weld Maintenance Area, the WP Transporter Load Cell, the WP Remediation Cell, the Empty DC Preparation Area, and the Transporter Load Bay. WHB support areas include heating, ventilation, and air-conditioning (HVAC), electrical, Waste Treatment, Hot and Cold Support, and Operating Galleries and Transfer Corridors.

The empty waste container is identified as a DC until bare fuel assemblies or canisters are inserted and the closure welds are performed, inspected, and certified. At that point and for all subsequent waste container handling and processing in the WHB, the DC is identified as a WP. During all DC/WP handling operations in the WHB, the DC/WP is contained within a shielded overpack and shielded cover. The shielded overpack and cover allow manned access during loaded DC/WP operations in the DC Load Cell, DC Handling Area, and Transporter Load Bay.

2.2.1 Non-Rotating Waste Package Design Alternative

The WHB plan and section views for the Non-Rotating WP Design Alternative are shown in Figures B-2 through B-5 in Appendix B. The temporary shielded overpack and cover configuration for the Non-Rotating WP Design Alternative is shown in Figure B-6. Three diameters of overpacks are used to accommodate the various WP sizes. The overpacks consist of two segments, connected longitudinally along the WP centerline. The WPs are spaced and secured within an overpack by adapter rings. Trunnions are provided on the overpack to accommodate DC/WP lifting and tilting operations. Final design of the overpack will require additional analyses to ensure waste form surface temperature limits are not violated during WHB operations.

In the Empty DC Preparation Area, a shielded overpack is installed on each empty DC while it is in a horizontal position. The DC/overpack is lifted and placed vertically on a dedicated DC transfer cart. The DC/overpack remains on the dedicated cart throughout all DC/WP handling, loading, and closure operations within the WHB until the WP is lowered to a horizontal position prior to loading in the Subsurface Transporter. The DC/WP cart travels throughout the various WHB process areas on a network of rails. Rubber-tired prime movers are used to move the carts.

Two parallel recessed carrier lines, configured to receive rail and truck carriers delivered to the WHB by the Carrier/Cask Transport System, service the Carrier Preparation Area and the Carrier Bay. The Carrier Preparation Area is used to prepare the carriers for cask removal. These operations, which can be performed remotely or by contact, include personnel barrier removal, impact limiter removal, radiation survey, temperature measurement, contamination survey, and wipe-down decontamination as required. The preparation area is also used to prepare empty casks or empty DPC overpacks for off-site shipment. The Carrier Preparation Area is equipped with a bridge crane, a bridge-mounted manipulator, an access platform, and miscellaneous contact and remote tools. Isolation doors are provided where the carrier lines enter the Carrier Preparation Area.

The Carrier Bay is used to remove cask tie-downs, upright the casks, and install the casks vertically on cask transfer carts. These operations can be performed remotely or by contact. The Carrier Bay is equipped with a bridge crane, a bridge-mounted manipulator, a cask lifting yoke, miscellaneous remote and contact tools, cask adapters, cask spacers, DPC overpack adapters, and storage space for DPC overpacks. Isolation doors are provided where carrier lines enter the Carrier Bay.

A recessed Cask Transfer Area interconnects the Carrier Bay with the Cask Preparation Area and the Transfer Cell. The recessed area is equipped with three rail-mounted cask transfer carts. The

carts are used to transfer loaded and empty transportation casks and DPC overpacks. The cask transfer carts are capable of elevating the transportation casks and overpacks for engagement with the cask preparation ports and the cask/DPC unloading ports. Isolation doors isolate the Cask Transfer Corridors from the Carrier Bay.

The Cask Preparation Area is a single room located above the Cask Transfer Area. The preparation area is connected to the Cask Transfer Area by three cask preparation ports. The Cask Preparation Area is used to perform preparation operations on loaded and empty transportation casks and loaded and empty DPC overpacks. These operations, which can be performed remotely or by contact, include cask sampling and venting, lid bolt removal and installation, lid removal and installation, and shield plug lifting fixture attachment and removal. The Cask Preparation Area is also used to open DPCs positioned in the transportation casks. These operations, which can be performed remotely or by contact, include DPC lid weld removal, DPC outer lid removal, and DPC shield plug lifting fixture attachment and removal. Contact operations in this area will require an ALARA analysis. The center preparation port is primarily used for DPC opening, while the two outer preparation ports are used for cask/DPC overpack preparation. However, all three preparation ports are identical and can be used for either cask/DPC preparation or DPC opening. The Cask Preparation Area equipment includes an adjustable access platform for each port, a bridge crane, a bridge-mounted manipulator, DPC lid severing tools, bolt torque devices, and a variety of tools for remote and contact operations. The Cask Preparation Area also provides storage space for Cask and DPC overpack adapters and lid lifting fixtures.

The Transfer Cell is also located above the Cask Transfer Area. The Transfer Cell has three cask unloading ports connecting to the Cask Transfer Area and a DC loading port for each of two DC Load Cells located below the Transfer Cell. The Transfer Cell is used to unload SNF assemblies, DOE SNF/HLW canisters from transportation casks and either place the assemblies and canisters into in-cell blending inventory racks or load the assemblies and canisters into DCs. The transfer cell is also used to load assemblies and canisters into aging inventory storage casks and load empty DPCs into overpacks. The Transfer Cell is equipped with an assembly handling machine, a bridge crane with two hoists, a bridge-mounted manipulator with an auxiliary hoist, and a number of grapples and lifting fixtures for the variety of SNF assemblies and DOE canisters. Recessed storage racks are provided in the Transfer Cell floor for the in-process staging inventory of 144 PWR assemblies (or 288 BWR assemblies) and 25 DOE SNF canisters (with the exception of naval canisters). Lids and shield plugs are provided for each unloading/loading port and shield plugs are provided for each blending inventory rack. Recessed areas are provided in the cell floor for the storage of lids, lifting fixtures, grapples, and shield plugs. A maintenance bay is provided at the end of the cell for contact maintenance of the assembly transfer machine, bridge crane, and manipulator. The maintenance bay is separated from the Transfer Cell by a multi-segment isolation door.

The DC Load Cells are used to position the DCs for loading with SNF assemblies, DOE SNF/HLW canisters, and naval canisters. Each DC Load Cell is located below one of the Transfer Cell DC load ports. The DC Load Cells are equipped with embedded rails to allow the transfer of the DC carts between the load cells and the DC Handling Area. Prime movers are used to move the DCs. An extendable bellows mating device, mounted below each DC Loading

Port, provides an isolation barrier between the Transfer Cell and the DC Load Cell during DC loading operations. A DC shielded cover handling device is located in each DC Load Cell to remove and retain the cover during DC loading operations. An area is provided in the DC Loading area to survey, and decontaminate if necessary, the DC prior to moving out of the DC Loading Area. In addition, a shield door is provided between each DC Load Cell and the DC Handling Area.

The DC Handling Area provides the means of transferring DC/WP transfer carts on an embedded rail system between the DC Load Cells, the WP Weld Areas, the WP Transporter Load Cell, the Empty DC Preparation Area, the WP Remediation Cell, and the Transporter Load Bay. A transfer platform, capable of traveling along the entire length of DC Handling Area, is used to position the DC/WPs, the transfer carts, and the prime movers at rail positions servicing each process area and cell. The platform travels on a recessed rail system. The DC Handling Area also includes a number of rail positions for the staging of WPs on transfer carts.

A number of WP Weld Areas are located along one side of the DC Handling Area. The Weld Areas are used to perform the WP closure operations, which include WP lid welding, treatment, and inspection and also inerting of the WP. Each WP Weld Area consists of a shielded weld cell located above a weld station. The weld cell and weld station are connected by a weld port. The weld cell is equipped with a number of rail-mounted equipment modules. Each module is capable of deploying specialized equipment through the weld port for the performance of the closure operations. The weld cell also includes a WP closure lid and shield lid handling system and a bridge-mounted manipulator. The WP weld station includes embedded rails for transfer and positioning of the DC/WP at the weld port and an isolation door to isolate the weld station from the DC Handling Area.

A common Weld Maintenance Area services all the weld cells. The maintenance area is equipped with forklifts and miscellaneous tools for the transfer of lids and welding materials to the weld cells. Materials and equipment are delivered to the maintenance area by an elevator. Shield doors are provided between each weld cell and the maintenance area.

The WP Transporter Load Cell is used to remove the shielded overpack and lid from the WP and load the WP onto a subsurface WP transporter. The WP and cart are transferred on embedded rails from the DC Handling Area into the load cell by a prime mover. An additional rail system is used to transfer the WP transporter from the exterior of the WHB into the load cell. The load cell is equipped with a bridge crane and lifting yoke to remove the overpacked WP from the transfer cart and rotate WP to a horizontal position on a tilting fixture. The bridge crane is also used in conjunction with a horizontal lifting fixture to remove the shielded overpack segments from the WP and handle the unshielded WP horizontally. A grapple is provided to handle the WP shield cover. The WP Transporter Load Cell is also equipped with two wall-mounted manipulators, a shield door to shield the DC Handling Area from the WP Transporter Load Cell operations and an isolation door to isolate the load cell from the exterior of the WHB.

The Empty DC Preparation Area is used to receive empty DCs and DC lids on rail and truck carriers and prepares the empty DCs for waste loading. The preparation area is equipped with a rail system for the rail carriers and a rail system to transfer the empty DCs and transfer carts into

the DC Handling Cell. The Empty DC Preparation Area includes a bridge crane, a DC lifting fixture, a DC horizontal lifting beam, a tilting fixture, a horizontal DC/overpack support saddle system, a DC shield cover lifting adapter, a mobile access platform, and a forklift. The Empty DC Access Corridor connects the Empty DC Preparation Area with the DC Handling Area. Isolation doors are provided on both ends of the access corridor and on the entrance to the Empty DC Preparation Area from the outside rail system.

The Transporter Load Bay is used to transfer shielded WPs from the WHB to the Fuel Staging Area. A rail system allows transfer of a cart and WP/overpack into the load bay from the DC Handling Area. A motorized transporter is used to remove the WP/overpack from the transfer cart and transport the WP/overpack vertically to the inventory area. The Transporter Load Bay includes two isolation doors.

The WP Remediation Cell is used to remediate WPs as a result of rejected closure welds or other discrepancies that would prevent the WP from being certified for subsurface emplacement. The WP Remediation Cell can also be used for off-line remote repair and remediation of DCs, canisters, and other equipment. The remediation cell includes a bridge-mounted manipulator, a bridge-mounted cutting machine, a decontamination device, and a shield door.

The Fuel Staging Area is used to stage shielded WPs and storage casks for the purpose of incoming fuel aging, prior to subsurface emplacement. The inventory area is located near the WHB. The inventory area includes concrete pads for staging of WPs and storage casks. A motorized transporter is used to transfer the casks/WPs between the WHB and the Fuel Staging Area.

All remote WHB waste processing operations are controlled from operator consoles located in the operating galleries adjacent to each shielded cell and a centralized control center. Shield windows and close-circuit television systems support the remote operations. All cell equipment is designed to facilitate remote operation and remote maintenance. The equipment is also designed for safe and efficient recovery from failures and malfunctions. Access corridors are provided in the WHB for the efficient transfer of personnel and supplies. Maintenance and replacement of major equipment in the Transfer Cell has not been provided for and will require additional investigation.

2.2.2 Turntable Design Alternative

The WHB plan views and section views for the turntable design alternative are shown in Figures B-7 through B-10 in Appendix B. The shielded overpack and shielded lid configuration for the turntable design alternative is shown in Figure B-11. The configurations of WHB and the DC/WP and overpack for the turntable design alternative are identical to the non-rotating WP design alternative except as described in the following paragraphs.

In the Empty DC Preparation Area, a lifting collar is clamped on the DC upper collar sleeve, which varies in size to accommodate the different WP sizes. The lifting collar is equipped with trunnions to accommodate DC/WP lifting and tilting operations and a flange at the bottom to support the DC/WP on the welding turntable. The flange diameter is the same for all lifting collars so that it can mate with the welding turntable. The DC is uprighted and lowered into a

cylindrical one-piece shielded overpack. The lifting collar is attached to the top of the shielded overpack. A shielded lid is installed on top of the lifting collar. A specific lifting collar size is required for each WP diameter. Three diameters of overpack are used to accommodate the various WP sizes. The length of the overpacks are common for all WPs. The DC/overpack is lifted and installed vertically on a dedicated DC transfer cart.

In the DC Handling Area, an overhead bridge crane and lifting yoke are used to transfer a DC/WP between the DC Load Cells, the WP Weld Areas, the WP Transporter Load Cell, the Empty DC Preparation Area, the WP Remediation Cell, and the Transporter Load Bay in lieu of the embedded rail/transfer platform system utilized in the non-rotating WP design alternative. Transfer carts and prime movers are required to move the DC/WP between the DC Handling Area and DC Load Cells, the WP Transporter Load Cell, the Empty DC Preparation Area, the WP Remediation Cell, and the Transporter Load Bay. The transfer between the DC handling Area and the WP Weld Areas does not require a transfer cart/prime mover since the bridge crane coverage includes the turntable in the WP Weld Area.

Each weld area is equipped with a turntable to rotate the DC/WP during the closure welding process. After a DC is transferred by the bridge crane onto the turntable, the turntable and DC travel on rails to into the weld station. The turntable returns the DC to the DC Handling Area after closure. The turntable is designed to support and rotate the DC/WP at the handling collar, as opposed to the bottom of the overpack, to minimize the weld groove run-out at the weld head. The DC/WP is supported on the turntable by the collar flange and protrudes through the turntable below floor level. A trench is provided in the DC Handling Area floor, between the turntable rails, to clear the DC/WP during travel between the handling area and the weld station.

A pit is provided in the WP Transporter Load Cell for removal of the WP from the shielded overpack. The WP handling collar is remotely removed from the WP prior to loading the WP in the WP Transporter.

2.3 OPERATIONAL DESCRIPTION

The WHB must be capable of processing the following types of Waste Forms:

1. Uncanistered CSNF (BWR Assemblies/PWR Assemblies)
2. Canistered CSNF (DPCs/horizontal DPCs)
3. Canistered DOE SNF/HLW

2.3.1 Non-Rotating Waste Package Design Alternative

The WHB waste handling operations for the Non-Rotating WP Design Alternative are shown on the operational flowcharts in Appendix C. Figure C-1 is a high-level flowchart of the basic waste handling operations. Figures C-2 through C-8 in Appendix C are detailed flowcharts of the waste handling operations. The following is a detailed description of the waste handling operations.

2.3.1.1 Carrier Preparation/Carrier Bay Operations

Transportation casks on their carriers are moved into the Carrier Preparation Area and the personnel barriers and impact limiters are removed. The transportation casks are then surveyed for radiation level, measured for temperature, surveyed for contamination, and if required, decontaminated by surface wipe down. The transportation casks are moved into the Carrier Bay, the cask tie-downs are disconnected, and the casks are removed from their carriers and installed vertically on rail-mounted cask transfer carts. Shipping skids are kept with the carrier. Cask unloading port adapters are installed on the casks (if required) and the casks are moved on the carts and positioned at one of the three preparation stations below the Cask Preparation Area. A preparation port connects each preparation station with the Cask Preparation Area. The casks containing uncanistered CSNF assemblies, canistered DOE SNF are positioned at one of the two outer preparation stations. The casks containing canistered CSNF (DPCs/horizontal DPCs) are positioned at the center preparation station.

2.3.1.2 Cask Preparation Operations

The casks are raised by the carts through the preparation ports to an elevation that accommodates cask preparation operations in the Cask Preparation Area above. The preparation area access platforms are then adjusted for the cask diameters. The cask preparation activities are performed by a combination of remote and contact operations using the crane, manipulator, and associated tools.

The transportation casks that contain uncanistered CSNF assemblies and canistered DOE SNF/HLW with the exception of naval canisters, are equipped with an outer lid and an inner shield plug. The preparation operations for these casks consist of cask cavity sampling and venting, outer bolt and lid removal, inner shield plug bolt removal, and installation of the cask shield plug lifting fixture.

The transportation casks that contain canistered naval SNF (the tops of the canisters are shielded) are equipped with an outer lid only. The preparation operations for these casks consist of cask cavity sampling and venting, lid bolt removal, installation of a lid lifting fixture, lid removal, and installation of the naval canister lifting fixture.

The transportation casks that contain canistered commercial DPCs/horizontal DPCs (the tops of the DPCs are shielded) are also equipped with an outer lid only. The preparation operations for these casks consist of cask cavity sampling and venting, lid bolt removal, installation of a lid lifting fixture, and removal of the cask lid. Most of the DPCs contained in these casks are not disposable; therefore, the DPCs must be cut open in the transportation cask and the waste forms removed. DPC opening operations include outer lid weld cutting and lid removal, DPC sampling and venting, shield plug weld cutting, vacuuming of the inner lid, and installation of a shield plug lifting fixture.

After preparation operations are completed, the transportation casks for all these waste forms are lowered, transferred by the carts to the cask unloading stations, and raised by the carts to engage the Transfer Cell cask unloading ports.

2.3.1.3 Waste Unloading/Loading Operations

The Waste Unloading/Loading Operations are performed in the Transfer Cell. Prior to initiating these operations, an empty DC contained in a shielded overpack is transferred on a cart from the Empty DC Preparation Area through the DC Handling Area to the DC Load Cell. The DC is positioned at the DC Load Cell lid station and the shielded overpack lid is removed. The DC is then moved to the Transfer Cell DC loading port, and the port bellows mating device is extended to seal against the top of the DC overpack. The DC loading port lid and the DC inner lid are removed by the assembly handling machine and placed in an in-cell recessed storage area.

For the casks containing uncanistered CSNF assemblies or DOE SNF/HLW canisters, the cask unloading port lid is removed by the assembly handling machine and the cask shield plug is removed by the Transfer Cell crane. The port lid and the shield plug are placed in a recessed cell storage area. Fuel assemblies are removed from the transportation cask, one at a time, by the fuel handling machine. Depending on blending requirements, the fuel assemblies are placed in baskets and then in a recessed in-cell blending inventory rack or loaded directly into the DC. Canisters are removed from the transportation cask and depending on co-disposal requirements, placed in a recessed in-cell inventory rack or loaded directly into the DC. When the transportation cask is empty, the cask shield plug and cask unloading port lid are replaced. When a DC is filled to capacity with fuel assemblies or canisters, the DC inner lid and DC loading port lid are replaced.

For the casks containing naval SNF canisters, the cask unloading port lid is removed by the assembly handling machine and placed in a recessed cell storage area. The Transfer Cell crane is attached to the canister lifting fixture and the canister is removed from the cask and loaded directly into the DC. The lifting fixture is removed from the canister and returned to the cask preparation area by means of the cask unloading port and an empty cask transfer cart.

For the casks containing DPCs, an overpack is used to transfer the empty DPC out of the WHB. Prior to unloading the casks, an empty DPC overpack is transferred into the Carrier Bay, unloading port adapters are installed on the overpack (if required), and the overpack is transferred to the Cask Preparation Area. In the preparation area, the overpack lid is removed, and the overpack is transferred to the Cask unloading station and mated to the unloading port. To unload the DPC in the transportation cask, the unloading port lid is removed by the assembly handling machine and placed in a recessed cell storage area. The Transfer Cell crane is attached to the DPC shield plug lifting fixture and the shield plug is removed from the DPC and placed in a recessed cell storage area. Fuel assemblies are removed from the open DPC, one at a time, by the fuel handling machine. Depending on the blending requirements, the fuel assemblies are placed in the recessed blending inventory rack or loaded directly into the DC.

When the DPC is empty, the cask unloading port lid over the overpack is removed by the assembly handling machine. The Transfer Cell crane and a lifting device are then used to lift the empty DPC out of the transportation cask and place the DPC into the overpack. The DPC shield plug is then placed in the overpack and the loading port lid is replaced. The overpack is returned to the Cask Preparation Area, the overpack lid is replaced, and the DPC is transferred out of the WHB.

When a transportation cask is unloaded, the cask shield plug is replaced (if applicable) and the cask unloading port lid is replaced. The empty cask is returned to the Cask Preparation Area for lid replacement, and then returned to the Carrier Bay for loading on a carrier and transfer out of the WHB for off-site shipment.

When a DC is completely loaded, the DC inner lid is replaced, the top of the lid and overpack are vacuumed, and the DC loading port lid is replaced. The loading port bellows mating device is retracted, the DC is moved to the DC load cell lid station, the shielded overpack lid is replaced, and the DC is transferred by the DC transfer cart to the DC Handling Area.

2.3.1.4 Disposal Container Handling Area Operations

The DC Handling Area operations involve the movement of transfer carts containing empty DCs and loaded WPs on an embedded rail system between the Empty DC Preparation Area, the DC Load Cells, the WP Weld Areas, the WP Transporter Load Cell, the Transporter Load Bay, and the WP Remediation Cell. A transfer platform equipped with rails to position and support the DC/WP transfer cart, travels along the entire length of the DC Handling Area in a recessed corridor. The transfer platform aligns the carts with rails servicing each cell and area. Because the DCs/WPs are manned, prime movers are used to move the transfer carts. Initially, an empty DC is transferred out of the Empty DC Preparation Area and placed in one of the DC loading cells. When the DC is completely loaded with a waste form, the DC is transferred to one of the available Welding Areas and moved into the weld station. After weld closure (the DC is now identified as a WP), the WP is transferred to one of three areas: the Transporter Load Bay if the waste form requires aging; the WP staging area in the DC Handling Area if there is a delay in the Subsurface operations; or to the WP Transporter Load Cell if the WP is ready to be loaded into a WP transporter for transfer to the subsurface. In the event of a rejected closure weld or a damaged WP, the WP can be transferred by the prime mover and transfer bridge system to the WP Remediation Cell for off-line remediation.

2.3.1.5 Waste Package Welding Operations

When a DC is fully loaded and is ready for closure, the DC and transfer cart are moved by one of the DC Handling Area prime movers and positioned at an available weld station. The DC middle and outer lids and weld system supplies (weld wire, electrodes, etc.) are delivered by Weld Maintenance Area fork lifts and placed in the weld cell located above the weld station. Prior to overpack shield lid removal, the radiation levels are low enough to allow personnel to enter the weld cell for the handling and positioning of weld supplies and any adjustments to the weld equipment. Before remote welding operations are initiated, personnel must exit the weld cell. The WP remote welding operations are performed by the module-mounted equipment in the weld cell, deployed through the weld port above the DC. The remote weld operations consist of overpack shield lid removal; DC inner lid welding and inspection; DC inerting with an inert gas; DC middle lid placement, welding, inspection, and laser peening; DC outer lid placement, welding, inspection, and induction stress relieving; surveying of the top of the WP and spot decontamination (if required); and replacement of the overpack shield lid. The WP is then transferred back to the DC Handling Area.

2.3.1.6 Waste Package Transporter Loading Operations

When a welded WP is removed from a Weld Area, it is ready for transfer to the subsurface for emplacement. If the WP Transporter Loading Cell is not available as a result of a delay in WP emplacement operations, the WP cart will be moved by prime mover to a position at the end of the DC Handling Area for staging. If the WP Transporter Loading Cell is available, the WP will be transferred directly into the loading cell. The prime mover is removed from the loading cell and the cell bridge crane and a grapple are used to remove the WP overpack shield lid. The crane and a lifting yoke are then used to lift the WP from the transfer cart, place the WP into a tilting fixture, and rotate the WP to a horizontal position. The cell crane and a lifting fixture are used to remove the upper WP shielded overpack segment from the WP and place the segment on the cell floor. The crane and a WP lifting fixture are then used to lift the WP and place the WP horizontally on the WP transporter pallet. The WP and pallet are retracted into the transporter shielded enclosure and the transporter shield doors are closed. The WP transporter is then removed from the WP Transporter Loading Cell by the Transport Locomotive. The WP shielded overpack segments and the overpack shield lid are placed on a cart and returned to the Empty DC Preparation Area by a prime mover. It should be noted that operations in the WP Transporter Loading Cell are more complex than in the SR design due to the use of shielded overpacks.

2.3.1.7 Empty DC Preparation Process

New empty DCs are delivered to the Empty DC Preparation Area by truck or railcar. The DC lids are removed from the truck/railcar and placed on staging pallets. Prior to removing the DC from the truck/railcar, a DC shield overpack segment, fitted with the appropriately sized adapter rings, is lifted by the area bridge crane and a lifting fixture and placed horizontally on the support saddles of the tilting fixture. The DC is then lifted by the crane and lifting fixture and placed in the overpack segment. The remaining DC shield overpack segment, fitted with the adapter rings, is lifted by the crane and lifting fixture and placed over the horizontal DC. The overpack segments are then fastened together. Using the area crane and a lifting yoke, the DC is uprighted and installed vertically on a transfer cart. The crane and a grapple are then used to install the DC inner lid in the DC and the overpack shield lid on top of the overpack. The cart containing the DC and overpack is then transferred into the DC Handling Area by one of the prime movers. It should be noted that operations in the Empty DC Preparation Area are more complex than in the SR design due to the use of shielded overpacks.

2.3.1.8 Fuel Staging Process

For the purpose of reducing the waste form heat output prior to emplacement in the subsurface, some of the incoming waste forms may require aging. Aging will be accomplished by storing the waste forms at a Fuel Staging Area (FSA) adjacent to the WHB and returning the waste forms for processing when the heat outputs have reached the desired level.

When uncanistered CSNF that has been loaded in a WP or storage requires aging, the welded, shielded WP on a transfer cart is moved into the Transporter Load Bay by a prime mover. A motorized transporter is used to lift the WP from the transfer cart, transfer the WP in a vertical position out of the WHB to the FSA, and place the WP in a vertical position on the pad for aging.

When aging has been completed, the transporter will be used to return the WP to the Transporter Load Bay. The WP will then be transferred to the WP Transporter Load Cell for processing.

When canistered CSNF requires aging, the canister or individual assemblies can be loaded into a WP and then the welded and shielded WP is transported to the FSA in a similar manner.

When a canistered CSNF DPC requires aging, the transportation cask that contains the DPC and a storage cask are mated to the Transfer Cell cask unloading ports. The DPC is then transferred from the transportation cask to the storage cask. The storage cask is loaded on a carrier, transferred to the FSA. By means of a recessed ramp, the motorized transporter is used to remove the storage cask from the carrier and place it in a vertical position on the pad for aging. When aging has been completed, the storage cask is transferred back to the Carrier Bay by the carrier. The DPC will be positioned at the center preparation station and cut open and processed similar to the non-aging DPC process.

Similarly, uncanistered CSNF assemblies can be loaded into a storage cask and then the storage cask is transferred to the FSA.

2.3.2 Turntable Design Alternative

The WHB waste handling operations for the Turntable Design Alternative are identical to the operations the Non-Rotating WP Design alternative discussed in Section 2.3.1 and shown in the flowcharts in Appendix C, except as noted below.

2.3.2.1 Empty DC Preparation Process

In the Empty DC Preparation Area, a lifting collar is clamped on the DC upper collar sleeve while the DC is positioned horizontally on the support saddles of the tilting fixture. Using the bridge crane and a lifting yoke the DC is uprighted and lowered into the cylindrical overpack. The lifting collar is attached to the top of the overpack. The shielded lid is then installed on the top of the lifting collar. The DC and overpack are then lifted and installed vertically on the DC transfer cart. The transfer cart, with the DC and overpack, is then transferred to the DC Handling Area by a prime mover.

2.3.2.2 Disposal Container Handling Area Operations

The DC Handling Area operations for the Turntable design alternative are similar to those for the Non-Rotating WP Design Alternative. However, instead of using an embedded rail system, the DC Handling Area bridge crane is used to transfer the DC between the Empty DC Preparation Area, the DC load cells, the WP weld areas, the WP Transporter Load Cell, the Transporter Load Bay, and the WP Remediation Cell. The crane lifts the DC from a transfer cart adjacent to a cell/area and transfers the DC to the transfer cart at the next cell/area, with the exception of the WP Weld Areas. The DC and transfer cart are then moved by a prime mover into the area/cell. For the WP Weld Areas, the bridge crane transfers the DC directly into the turntable.

2.3.2.3 Waste Package Welding Operations

Using the DC Handling Area bridge crane and a lifting yoke, the DC/overpack is lowered into the turntable until the DC lifting collar flange rests on the turntable rotation ring. The crane and lifting yoke are removed and the turntable moves the DC into position at the welding station.

All DC/WP closure welding operations are similar to the non-rotating WP operations, except the DC/WP is rotated by the turntable during the welding, inspection, and treatment activities. After the shield lid is replaced on the WP, the turntable returns the WP to the DC Handling Area.

2.3.2.4 Waste Package Transporter Loading Operations

The WP and cart are transferred into the WP Transporter Load Cell by one of the prime movers. The WP and overpack is removed from the cart by the cell crane and a lifting yoke attached to the lifting collar trunnions and placed vertically into a pit. While in the pit, the shielded WP lid is removed and the WP lifting collar is disconnected from the overpack. Using the crane and yoke attached to the lifting collar trunnions, the WP is removed from the overpack, placed in the tilting fixture, and rotated to a horizontal position. The lifting collar is then removed from the WP. Using the cell crane and a lifting fixture, the WP is lifted from the tilting fixture and placed horizontally on the WP transporter pallet. The WP is then retracted into the transporter and removed from the cell for subsurface emplacement. The WP overpack and shield lid are placed on a cart and returned to the Empty DC Preparation Area.

2.4 DESIGN ALTERNATIVES EVALUATED

As part of the WHB Conceptual Study, several design alternatives were considered. Three key design areas were of concern:

1. Waste Package Rotation
2. Carrier Bay Arrangement
3. Dual-Purpose Canister Cutting.

For the first area, Waste Package Rotation, two alternatives were investigated. One alternative is based on a non-rotating WP during the WP closure welding process. The second alternative is based on a rotating WP during this process. Both alternatives are shown in Figures B-2 through B-11 in Appendix B. The evaluation of the Waste Package Rotation alternatives is in Section 2.4.1.

The second area of investigation, Carrier Bay Arrangement, includes one alternative to the design selected and presented in Figure B-12. The design selected is for the Carrier Preparation Areas and Carrier Bays to be parallel to the waste process lines. The alternative design is for these areas perpendicular to the process lines. The evaluation is summarized in Section 2.4.2.

The final set of alternatives evaluated is the DPC Cutting Alternatives. As described in Section 2.4.3, two alternatives to the selected design were investigated. The design selected and shown in Appendix B is with the DPC cutting operation at the center preparation port of the Cask Preparation Area. The first alternative is cutting open the DPC in the Transfer Cell. The second

alternative is to cut open the outer lid of the DPC at the Cask Preparation Area port and then moved to the Transfer Cell to complete the cutting operation.

2.4.1 Waste Package Rotation Design Alternatives

Two basic WP welding design alternatives were evaluated for this study. The first is based on a WP remaining stationary, and the weld equipment rotating about the center of the WP during the WP closure welding process. The WHB conceptual design associated with this alternative is shown on the Facility Layouts, Figures B-2 through B-5 in Appendix B. The WP shield overpack associated with the non-rotating WP design alternative is shown in Figure B-6. The facilities and waste handling operations required for this design alternative are described in Sections 2.2.1 and 2.3.1. The second design alternative evaluated for this study is based on a WP rotating on a turntable during the WP closure welding process. The WHB conceptual design associated with this design alternative is shown on the Facility Layouts, Figures B-7 through B-10 in Appendix B. The WP shielded overpack associated with the Turntable Design Alternative is shown on Figure B-11. The facilities and waste handling operations required for this design alternative are described in Sections 2.2.2 and 2.3.2.

The advantages of the Turntable Design alternative are as follows:

- The welding system manipulators, which deploy and position the weld head and inspection devices, require only a minimal x-y travel capability to track the WP lid weld groove runout as the WP rotates. In comparison, the manipulators for the non-rotating WP configuration require a greater x-y travel capability to traverse the stationary large diameter lid weld grooves while performing the lid welds and inspections. They also require unwinding of the cables or a turntable rotating in the opposite direction.
- Not rotating the weld head prevents twisting and wrapping of weld system cables, hoses, and weld wire and eliminates the need for cable/hose slip joints/rings.
- The wire delivery system can be remote and utilize larger spools.

The disadvantages of the Turntable Design alternative are as follows:

- Precise lateral and angular manufacturing tolerances are required for the DC/WP handling collar and the top section of the WP in order to minimize the weld groove runout during WP rotation.
- The turntable must be manufactured to very precise tolerances; in particular, the rotation system and the track-mounted travel system. The total cost of twenty-five precise turntables is high and the turntables would require constant maintenance and adjustment.
- Two additional WP lifts are required at each weld station to transfer the WP between the transfer cart and the turntable and the lift height of 23 feet exceeds the current WP design basis. One additional WP lift is required to remove the WP from the shield overpack. The WP drop potential is increased as a result of the additional WP lifts.

- A 200-ton bridge crane and lifting yoke must be added to the DC Handling Area to transfer DCs/WPs between the DC transfer carts and the turntables.
- The DC Handling Area must be wider to accommodate the turntables and the associated equipment.
- A trench and rail system must be provided at each weld station.
- In the WP Transporter Load Cell, the WP must be lifted vertically out of the overpack prior to loading on the transporter. To minimize the WP drop height during this operation and to minimize the load cell height, a pit must be provided to position the WP below floor level. The WP Transporter Load Cell must be longer to accommodate the pit.

It is not possible to make a selection between the Non-Rotating WP Design Alternative and the Turntable Design Alternative at this time since the selection is dependent upon the WP closure and inspection method.

2.4.2 Carrier Bay Design Alternative

The non-rotating WP design alternative configuration of the WHB described in Section 2.2.1 and shown in Figures B-2 through B-5, positions the Carrier Preparation Areas and the Carrier Bays parallel to the waste process lines. An alternative WHB configuration evaluated for this study positions the Carrier Preparation Area and Carrier Bay perpendicular to the waste process lines. This design alternative, identified as the Perpendicular Carrier Bay Design Alternative, is shown in Figure B-12.

This alternative provides two Carrier Preparation Areas, one at the entrance of the Carrier Bay and one at the exit. Two rail/truck carrier lines service the Carrier Preparation Areas and the Carrier Bay. Rail and truck carriers enter the first area for carrier preparation, travel into the Carrier Bay to remove empty casks and install empty casks, and then travel through the second preparation area to exit the WHB. When additional modules are added during later construction phases, the Carrier Bay will be extended to become one large common bay, serviced by two bridge cranes that travel in the direction of the rail/truck lines. As the Carrier Bay is extended, a new Carrier Preparation Area is provided at the Carrier Bay exit. If a carrier becomes disabled in the first preparation area and blocks incoming carriers, the second preparation area can be utilized for the incoming carriers.

The advantages of this alternative are as follows:

- As the carriers are prepared, unloaded, and loaded, they pass completely through the Carrier Preparation Areas and Carrier Bay. Incoming carriers do not have to wait until the processed carriers are retracted from the preparation area.
- When additional process modules are added during later WHB construction phases, three of the carrier positions (in the common Carrier Bay) can be utilized for loaded cask unloading (the other three carrier positions are used for loading empty casks on the

carriers). After removal from the carriers, the casks can be transferred to any of three cart positions, at each of the three waste process lines (nine positions), resulting in improved WHB operational flexibility.

- Two rail lines are required to transfer rail carriers through the common Carrier Bay as opposed to the parallel configuration where two rail lines service each of the three modules (six rail lines).

The disadvantage of this alternative is as follows:

- In the event of a major malfunction in the common Carrier Bay, such as carrier or crane malfunctions or a major contamination, the waste handling operations in all three process lines could be affected. For the parallel Carrier Bay configuration, the three Carrier Bay lines are independent.

The major reason that this alternative (Carrier Preparation Area and Carrier Bay perpendicular to the waste process lines) was not carried forward in this study, is the potential for a malfunction or contamination to completely halt WHB waste processing operations.

2.4.3 Dual-Purpose Canister Cutting Alternatives

The waste handling operations associated with the WHB configuration described in Section 2.2 and shown in Figures B-2 through B-5 include cutting open DPCs at the center preparation port of the Cask Preparation Area. The DPC remains in the transportation cask. The DPC opening operation includes cutting of the outer lid weld and lid removal, DPC sampling and venting, cutting of the shield plug weld, vacuuming of the shield plug, and installation of a shield plug lifting fixture.

The first DPC cutting alternative evaluated for this study involves cutting open the DPC in the Transfer Cell. The operation begins at the Cask Preparation Area preparation port by cutting holes in the DPC outer lid to access the connectors for sampling and venting. The DPC is then moved to the Transfer Cell center cask unloading port for removal of the DPC outer lid and shield plug (the DPC remains in the cask). After fuel assembly removal, the empty DPC is removed from the cask and the DPC and shield plug are placed in an empty DPC overpack positioned at another cask unloading port. Cutting holes to access the DPC sample/vent connectors in the preparation area can be performed using remote and contact operations. The balance of the DPC cutting operations in the Transfer Cell is performed remotely.

The advantages of this Transfer Cell DPC cutting alternative are as follows:

- In the event of a DPC contamination leak when the outer lid weld and shield plug weld are removed, the Transfer Cell contains the contamination. Cutting the welds in the Cask Preparation Area presents the potential for a contamination leak in a manned area.
- When the fuel has been removed from the DPC, the DPC, the shield plug, and the outer lids are placed in the overpack and the overpack lid is installed while the overpack is still positioned at the cask unloading port in the Transfer Cell. As a result, when the DPC is

returned to the Cask Preparation Area for overpack lid bolt installation, there is less potential for contamination.

The disadvantages of the Transfer Cell DPC cutting alternative are as follows:

- The DPC cutting operations in the Transfer Cell must be performed remotely. There is no capability to perform some of the cutting operations and equipment adjustments by contact methods. As a result, the operations are more difficult and time consuming and additional remote equipment is required in the Transfer Cell.
- The DPC shield plug lifting fixture must be installed remotely in the Transfer Cell after outer DPC lid removal.
- Performing the DPC lid cutting operations in the Transfer Cell may impact other waste handling operations in the cell, thereby affecting waste processing throughput.

A second alternative for cutting open the DPC was evaluated during this study. This alternative uses the same DPC cutting approach used for the WHB VA and SR design except the VA/SR DPC cutting was performed in a pool while this DPC cutting operation is performed dry. At the Cask Preparation Area preparation port, the DPC outer lid is cut to access the connectors, the DPC is sampled and vented, and a DPC lifting fixture is installed. The cask and DPC are then moved to the Transfer Cell cask unloading port. Using the cell bridge crane, the DPC is removed from the cask and placed in an in-cell cutting pit. The lifting fixture is removed, a cutting device is placed over the DPC, and the DPC is severed at the cylinder wall below the upper lid and shield plug. The severed top DPC section is removed and the bare fuel assemblies are unloaded.

The advantage of the VA/SR-type DPC cutting alternative is as follows:

- Removal of the complete top of the DPC in one operation reduces the number of steps as compared to cutting individual welds and handling individual lids and shield plugs.

The disadvantages of the VA/SR-type DPC cutting alternative are as follows:

- When the top of the DPC is severed at the cylinder wall below the shield plug, the original DPC internal lifting lugs (used to handle the empty DPC) are removed with the top section of the DPC. As a result, there are no features remaining to lift and handle the lower DPC cylindrical section.
- Moving the DPC from the cask unloading port in the Transfer Cell to the cutting pit and performing the cutting operations in the pit, may impact other waste handling operations in the cell, thereby affecting waste processing throughput.
- The DPC cutting operations in the Transfer Cell are performed remotely with no provisions to perform some of the cutting operations and equipment adjustments by contact methods. As a result, the operations are more difficult and additional remote equipment is required in the Transfer Cell.

The two alternatives discussed above were not carried forward in this study. The major reasons are 1) the need to perform the complete DPC cutting operations remotely and 2) the potential for impacting the waste processing throughput in the Transfer Cell.

In addition to evaluating the two alternatives discussed above, the issue of potential contamination of the transport cask during the DPC lid cutting operation was identified. Preliminary discussions with industry representatives determined that contamination of the transport cask can be prevented. However, further investigation is necessary to ensure that contamination is not possible. In addition, contact operations in the Cask Preparation Area will require an ALARA analysis.

2.5 DESIGN BASIS EVENT ASSESSMENT

2.5.1 Introduction

A preliminary DBE assessment was performed to identify the potential preclosure DBEs associated with the proposed WHB conceptual design. This analysis did not include the Fuel Staging Area nor the transportation of casks/WPs to and from the FSA. Appendix E presents an assessment of the initiating events and event frequencies, and mitigated event sequences related to the WHB Conceptual Design. This preliminary assessment also compared the results with those from *Design Basis Event Frequency and Dose Calculation for Site Recommendation (SR)* (CRWMS M&O 2000c). The potential DBEs identified for the WHB conceptual design were identified based on evaluation of the design drawings and operational concept. Implicit to this assessment is the assumption that the preclosure safety strategy is implemented.

Handling of DPCs and multipurpose canisters that contain commercial SNF was not considered in the DBE assessment. An analysis of the potential event sequences associated with these canisters will be performed at a later date.

2.5.2 Summary

From a preclosure safety perspective, the WHB conceptual design compares favorably with the SR design for the following reasons:

- Fewer overall lifts
- Fewer Category 1 events
- No spent fuel assemblies (SFA) basket events
- No Category 2 event sequences that result in a release to the public (for the Non-Rotating WP Design)
- No events involving unsealed DCs (for the Non-Rotating WP Design)
- Lower annual dose for Category 1 events
- Potential to downgrade HVAC system from QL-2 to QL-3

A Category 1 event is defined as an event having a frequency greater than 10^{-2} per year and a Category 2 event having a frequency not greater than 10^{-2} per year. Although both WHB designs are capable of meeting the dose limits for Category 1 and Category 2 DBEs, the WHB

conceptual design appears to provide additional safety margin by reducing both the number of potential DBEs and the bounding radiological consequences.

It should be noted that the proposed Turntable Design Alternative introduces four scenarios where the DC/WP could be potentially dropped from a height of 23 feet, which exceeds the current WP design basis. Two of these drops could occur at the weld station when the DC is lifted into the turntable and the sealed WP is subsequently removed from the turntable. The second two drops may occur when the WP is lifted in and out of the pit in the transporter loading area for the purpose of removing the WP shielded overpack. It is doubtful that the WP could be redesigned to structurally withstand such a drop without greatly increasing the fabrication costs for each of the 11,000 WPs.

Table 2.5-1 shows the number of individual lifts, estimated from the processes presented in Appendix C, and annual lifts, estimated from the throughput presented in Appendix A, assuming maximum throughput, for the WHB conceptual design compared to the SR design. In each design, the storage operation is included in the lift data. This is a conservative assumption that maximizes the number of lifts in both designs.

Table 2.5-2 compares the number of Category 1 and Category 2 DBEs, the maximum material-at-risk, and the DBE dose consequences associated with each design (see Appendix E for detail assessment). For the SR design, the bounding consequence Category 1 DBE is the breach of 8-PWR SFAs resulting from a SFA basket drop onto another basket in the ATS hot cell. The bounding consequence Category 2 DBE is a shipping cask drop into the Cask Preparation Pit, which results in the breach of 68-BWR SFAs. For the WHB conceptual design, the bounding consequence Category 1 DBE breaches only 2-PWR SFAs, a drop of one SFA onto another, because the SFA baskets are eliminated from the design. There are no Category 2 DBE consequences associated with the Non-Rotating WP Design because all potential cask, canister, and DC/WP drops that lead to a release are assumed to be prevented by design (i.e., become Beyond Design Basis Events [BDBE]). However, the Turntable Design has Category 2 DBEs that exceed the current WP design basis and could lead to significant radiological releases.

The annual Category 1 dose and the maximum individual Category 1 dose (used for classification purposes) for each design is shown in Table 2.5-2. The methodology for estimating the doses associated with the WHB conceptual design is consistent with the methodology used in the dose calculation for SR (CRWMS M&O 2000c). The annual cumulative Category 1 DBE dose (0.01 mrem/year) and the maximum individual Category 1 DBE dose (1.0 mrem/event) are slightly lower for the WHB conceptual design because there are fewer Category 1 DBEs and fewer SFAs involved in the accidents. The reduction in the individual Category 1 DBE dose from 5 mrem/event to 1.0 mrem/event is potentially significant because the classification process described in *Classification of Permanent Items* (QAP-2-3) uses a dose cutoff of 25 mrem/event to determine whether a system, structure or component is classified as QL-2 or QL-3. This could potentially allow the WHB HVAC system to be reclassified from QL-2 to QL-3, which would decrease the facility design and operational costs.

Table 2.5-1. Comparison of Lifts

Container	SR Design		Conceptual Design ⁽⁴⁾		Conceptual Design ⁽⁴⁾	
			(Non-Rotating WP Alternative)		(Turntable Alternative)	
	Individual Lifts	Total Lifts/Year	Individual Lifts	Total Lifts/Year	Individual Lifts ⁽³⁾	Total Lifts/Year
Casks	3	1,860	2	1,804	2	1,804
CSNF SFAs ⁽¹⁾	2	26,026	2	25,884	2	25,884
CSNF Baskets ⁽¹⁾	4	9,112	0	0	0	0
Canisters ⁽¹⁾	2	2,124	2	2,078	2	2,078
DCs (unsealed WPs)	2	1,200	0	0	1	600
WPs	3	1,800	3 ⁽²⁾	1,800	6	3,600
Totals:	16	42,122	9	31,566	13	33,966

⁽¹⁾ Includes in-process staging inventory operation.

⁽²⁾ Includes lift onto tilting fixture and two lifts associated with the Fuel Staging Area.

⁽³⁾ Same as Non-Rotating Design except for 4 additional lifts associated with Turntable Design.

⁽⁴⁾ The number of lifts are estimated from the processes presented in Appendix C and the annual lifts are estimated from the throughput presented in Appendix A.

Table 2.5-2. Summary Comparison of WHB Conceptual Design with SR Design

Measure	SR Design	Conceptual Design	
		(Non-Rotating WP)	(Turntable)
Category 1 Events	14	8	8
Category 2 Events	12	0	1
Max Cat. 1 Material-At-Risk	8-PWR	2-PWR	2-PWR
Max Cat. 2 Material-At-Risk	68-BWR	None	44-BWR
Annualized Cat. 1 Filtered Dose ⁽¹⁾	0.06 mrem/yr	0.01 mrem/yr	0.01 mrem/yr
Max. Individual Unfiltered Cat. 1 Dose ^{(1) (2)}	5 mrem/event	1.0 mrem/event	1.0 mrem/event
Max. Individual Unfiltered Cat. 2 Dose ⁽¹⁾	0.02 rem/event	None	1.4 rem/event
Meets Regulatory Dose Limits?	Yes	Yes	Yes

⁽¹⁾ Doses are off-site, not occupational

⁽²⁾ 25 mrem < Cat. 1 dose < 100 mrem → QL-2 HEPA filters, per QAP-2-3.

2.6 PHASED CONSTRUCTION

Phased construction is being considered for the surface facility during the LA design phase of the Monitored Geologic Repository. One of the primary objectives of this study is to develop a design that accommodates phased construction in order to provide the flexibility to allow construction as needed to meet waste receipt and emplacement requirements. The goal is to spread construction of the WHB over several years to reduce annual project costs and to provide a cost-effective design that supports waste emplacement starting in the year 2010.

For each design alternative (Non-Rotating WP and Turntable), the design includes the following construction modules:

Module 1 – One Carrier Preparation Area, one Carrier Bay, one Transfer Cell, WP Remediation Cell, Empty DC Preparation Area, DC Handling Area (including the building for all 25 weld stations, and equipment for only 16 weld stations), WP Transporter Cell, Waste Treatment Area, Waste Handling/Waste Treatment Support and Administration, Hot Support/Electrical, HVAC Areas, and associated Operating Galleries and Access Corridors.

Module 2 – One Carrier Preparation Area, one Carrier Bay, one Transfer Cell, associated Operating Galleries and Access Corridors, and equipment for 9 weld stations.

Module 3 - One Carrier Preparation Area, one Carrier Bay and one Transfer Cell, and associated Operating Galleries and Access Corridors.

The differences in the facility designs for the Non-Rotating WP and Turntable Alternatives are in the DC Handling Area, as described in Section 2.2.

Modules 2 and 3 are duplicates of Module 1 from the Carrier Preparation Area to the boundary between the Transfer Cell and the DC Handling Area. The entire portion of the building for the DC Handling Area is included in Module 1, even though only 11 of 17 weld stations are required in 2013, as shown in Table D4-1 (Appendix D). Equipment for each weld station is added as needed; that is, 11 in Module 1 and 6 more in Module 2. The entire building is constructed in Module 1 due to the difficulty in adding onto the DC Handling Area while continuing to operate.

The construction of subsequent phases will be difficult due to the continuous operation of the facility during construction. For example, the construction of the Transfer Cell in Modules 2 and 3 and the tie-in to the DC Handling Area will require special accommodations to separate construction from operations.

2.7 COST ESTIMATE

In order to compare the costs of the construction options for the design alternatives defined in previous sections of this document, the cost estimates are shown in Table 2.7-1:

Table 2.7-1. Construction Cost Estimate Options

Design Alternative/Construction Options	Description
Non-Rotating Waste Package/NR-1A	Module 1 in Phase 1, Module 2 in Phase 2, and Module 3 in Phase 3
Non-Rotating Waste Package NR-1B	Module 1 and 2 in Phase 1, Module 3 in Phase 2
Turntable/T-1A	Module 1 in Phase 1, Module 2 in Phase 2, and Module 3 in Phase 3
Turntable/T-1B	Module 1 and 2 in Phase 1, Module 3 in Phase 2

Appendix F includes the cost estimate basis/assumptions and detailed estimate for each construction option. For each design alternative, the estimate is composed of construction costs for each module. A separate line item estimate is also presented for the cost of storage casks which are used for fuel aging, on a per cask basis. A summary of the cost for each construction option is shown in Table 2.7-2.

The lowest cost construction option is NR-1B, where Modules 1 and 2 are constructed during Phase 1. The total capital cost is \$545 million. The primary reasons for the difference in cost include:

- 1) The cost of the Turntable Design Alternative weld station equipment is higher than the corresponding equipment for the Non-Rotating WP Design Alternative. Also, the space requirements for the Turntable Design Alternative are higher.
- 2) The cost of constructing Module 2 in Phase 2 for construction options NR-1A and T-1A is higher than in Phase 1 for construction options NR-1B and T-1B. This is due to the extra cost of construction adjacent to an operating facility, including higher costs for security, plant access, and congestion.

It should be noted that the WHB capital costs do not include provisions for handling non-standard fuel nor decontamination and surveying equipment and facilities.

The costs associated with storage casks which are used for fuel aging and/or fuel blending, are included in Table 2.7-2. The estimated number of casks required for fuel staging is 485, which is based on 12,000 assemblies (5,000 MTU), less 432 assemblies staged inside the Transfer Cells, and 24 PWR assemblies per storage cask.

Table 2.7-2. Capital Cost Estimate Summary

(\$Million)

Design Alternative	Construction Option	Phase	Total Direct Cost	Total Indirect Cost	Total Capital Cost
Non-Rotating WP					
Module 1	NR-1A	1	\$ 260	\$ 100	\$ 360
Module 2	NR-1A	2	\$ 93	\$ 35	\$ 128
Module 3	NR-1A	3	\$ 47	\$ 19	\$ 66
	Total-Option NR-1A		\$ 400	\$ 154	\$ 554
Modules 1 and 2	NR-1B	1	\$ 347	\$ 132	\$ 479
Module 3	NR-1B	2	\$ 47	\$ 19	\$ 66
	Total-Option NR-1B		\$ 394	\$ 151	\$ 545
Turntable					
Module 1	T-1A	1	\$ 273	\$ 104	\$ 377
Module 2	T-1A	2	\$ 94	\$ 36	\$ 129
Module 3	T-1A	3	\$ 47	\$ 19	\$ 66
	Total-Option T-1A		\$ 414	\$ 159	\$ 573
Modules 1 and 2	T-1B	1	\$ 362	\$ 137	\$ 500
Module 3	T-1B	2	\$ 47	\$ 19	\$ 66
	Total-Option T-1B		\$ 409	\$ 156	\$ 566

Design Alternative	Construction Option	Phase	Total Direct Cost	Total Indirect Cost	Total Capital Cost
Fuel Staging Area					
485 Storage Casks		NA	\$ 403	\$ 7	\$ 409

2.8 THROUGHPUT ANALYSIS

2.8.1 Introduction

A preliminary throughput analysis was performed to determine the approximate throughput rate of the proposed WHB. Because the WHB design is still in the conceptual stage, and detailed equipment design has not been performed, the analysis provides only a general idea of the actual throughput. It does, however, provide a basis for comparing the throughput of the proposed design with that of the SR design.

2.8.2 Scope

The scope of the operational throughput analysis begins at the WHB Carrier Preparation Area with the receipt of a SNF transportation system. The transportation cask is prepared for removal from the transportation carrier in the Carrier Preparation Area by removal of personnel barriers and impact limiters. From the Carrier Preparation Area, the SNF transportation system is moved to the Carrier Bay Area where the SNF transportation cask is unloaded from the carrier and placed onto a transport cart. From the Carrier Bay, the transportation cask and transport is moved into the Cask Preparation Area where the cask is prepared for unloading. After the transportation cask is prepared for unloading, the transportation cask is moved to the Cask Transfer Corridor and the transportation cask is mated with the Transfer Area. The SNF is then unloaded from the transportation cask and placed into a DC or into in-process blending inventory.

The scope of the throughput analysis did not include the closure of the DC in the DC Handling Area or loading of the WP in the WP Transportation Load Cell. Also, the analysis did not include the option of loading a storage cask for transport to the Fuel Staging Area.

2.8.3 Approach

Using the layout drawings of the WHB facility (Appendix B), operational sequences were developed (Appendix C). These operational sequences were based on SNF handling experience and information provided by the individuals developing the facility layout. Once the operational sequence was developed, operational times for the completion of each activity were determined (Appendix D, Attachment D1). The operational sequence and processing duration were developed for each type of SNF transportation system to be received at the WHB. The throughput was analyzed using two different and independent methods, the WITNESS program and an Excel spreadsheet. Sections 2.8.5 and 2.8.6 further describe these two methods.

It should be noted that since the detail facility design and handling equipment have not been finalized, it is difficult to establish the actual operational times for each task. The operational times presented in Appendix D, Attachment D-1, are estimates based on experience at commercial reactors for performing similar tasks. The design engineers should use these durations as guidance when performing the detail design and will be verified during mockup testing. The actual WHB throughput will be established based on the durations determined during mockup testing.

2.8.4 Basis and Assumptions

The basis and assumptions used for this throughput analysis are as follows:

- Five different cases were analyzed. The receipt rate for each case is provided in Appendix A.

Case 1:	Maximum Truck Casks - Rail Available 2010
Case 2:	Maximum SPC Rail Casks - Rail Available 2010
Case 3:	Maximum DPC Rail Casks - Rail Available 2010
Case 32:	Initial 1,200 MTU, 2,400 MTU in 2015, 3,600 MTU in 2028 – Rails available in 2010
Case 33	Initial 800 MTU (LWT), 2,400 MTU in 2014, 3,600 MTU in 2028 – Rails available in 2014
- Facility Operation: 3 shifts per day, 5 days per week, 50 weeks per year.
- A Productivity Factor of 77 percent has been included to account for shift changes, breaks, moving from station to station, personnel contamination protection, and other operator down time.
- A Maintenance Factor has been included to account for equipment breaking down during operations. The factor is 95 percent for the Carrier Preparation Area, Carrier Bay Area, and Cask Preparation Area, and 90 percent for the Transfer Cell Area.
- Routine maintenance is assumed to be scheduled for weekends and during the two weeks of annual down time.
- Cask decontamination, when required, does not impact critical path throughput activities.
- Change out of cask-specific adapters for equipment handling does not impact critical path throughput activities.

2.8.5 WITNESS Operational Simulation

WITNESS simulation software is a program used to facilitate the evaluation of designs and design alternatives. It uses a visual, interactive, and interpretative approach to simulation. By allowing users to make rapid changes to a model's logic and input data, the program can test many different operational scenarios in a short period of time. For these reasons, WITNESS was selected to test the operational and throughput capacity of the Non-Rotating WP Design Alternative, Construction Option NR-1B (Appendix B), based on the incoming waste streams described above. The results from these evaluations are contained in Appendix D, Attachment D2.

2.8.6 Excel Spreadsheet Operational Simulation

An Excel spreadsheet was developed to determine the total processing time required in each of the four major areas of the WHB (Carrier Preparation, Carrier Bay, Cask Preparation, and Transfer Area). From this Excel spreadsheet, the utilization of each of the four major areas of the WHB was derived. The utilization of each of the four major areas was then used to determine the number of modules required to process the required throughput for each year of operation. The spreadsheets used in the calculation as well as the results are contained in Appendix D, Attachment D3.

2.8.7 Comparison of Results

Table 2.8-1 presents a comparison of the results from the two evaluations. From these results it can be seen that the throughput from the WITNESS evaluation is consistently less than that from the Excel evaluation. This is due to the fact that the WITNESS model couples each individual step to the next step and will not allow the process to proceed until the preceding step is completed. The Excel model is much simpler and does not reflect the interaction between sequential steps. Therefore, the WITNESS results better predict the actual throughput of the proposed WHB.

Table 2.8-1. Comparison of Results

Year	Case 1			Case 2			Case 3			Case 32			Case 33		
	# Modules Required			# Modules Required			# Modules Required			# Modules Required			# Modules Required		
	Excel	WITNESS	Difference %	Excel	WITNESS	Difference %	Excel	WITNESS	Difference %	Excel	WITNESS	Difference %	Excel	WITNESS	Difference %
2010	0.33	0.39	15%	0.32	0.37	14%	0.27	0.35	22%	0.25	0.30	17%	0.94	1.08	13%
2011	0.48	0.56	14%	0.47	0.55	15%	0.39	0.49	20%	0.25	0.30	17%	0.94	1.08	13%
2012	0.90	1.06	15%	0.85	1.01	16%	0.72	0.91	21%	0.75	0.88	15%	1.82	2.10	13%
2013	1.36	1.45	6%	1.28	1.50	15%	1.06	1.33	20%	0.88	1.03	15%	2.18	2.51	13%
2014	2.09	2.43	14%	1.97	2.30	14%	1.63	2.02	19%	0.84	0.98	14%	1.44	1.70	15%
2015	2.25	2.62	14%	2.13	2.48	14%	1.78	2.21	20%	1.43	1.67	14%	1.41	1.64	14%
2020										1.37	1.62	15%	1.37	1.62	15%
2023	1.98	2.34	15%	1.86	2.19	15%	1.77	2.34	24%						
2025										1.34	1.59	16%	1.37	1.63	16%
2030										1.81	2.20	18%	1.81	2.20	18%
2034	1.87	2.32	19%	1.80	2.22	19%	1.61	2.55	37%						
2035										1.68	2.13	21%	1.73	2.18	21%
2040										1.70	1.88	10%	1.69	2.17	22%

Based on the waste streams evaluated, it can be seen that for the base cases (Case 1, 2, and 3) that two modules will be required starting in 2012 and three modules will be required starting in 2014. For Case 32 the second line is required in 2013 and the third line in 2030. For Case 33 the second line is required from the start of 2010 and the third line is required in 2012.

It should be noted that the basis for these predictions is a work schedule of 24 hours per day, 5 days per week, which is consistent with other WITNESS analyses done as part of previous studies. This may be overly conservative since it is very common for facilities with large capital investments to work 24 hours per day 7 days per week schedule to better utilize the facility.

2.8.8 Number of Weld Stations

As indicated above, the throughput analysis stopped after the WP was loaded. This is due to the fact that the actual DC closure process is still under development and not completely defined. A separate calculation was performed to determine the number of weld stations needed in order to determine the size of the WHB and allow a preliminary cost estimate to be performed. The calculation of the number of weld stations is contained in Appendix D, Attachment D4.

2.9 PHASED CONSTRUCTION IMPLEMENTATION

One of the primary objectives of this study is to develop a design that can be constructed in phases to provide the capacity as needed to meet waste receipt and emplacement requirements. The goal is to spread construction of the WHB over several years to reduce annual project costs and to provide a cost-effective design that supports waste emplacement starting in the year 2010. The throughput analysis described in Section 2.8 is used to determine when facilities must be constructed just in time to meet capacity requirements. Two different modular construction options are considered for each of the two design alternatives, the Non-Rotating Waste Package Alternative and the Turntable (Rotating Waste Package) Alternative. The construction options are summarized in Table 1.4-1.

It is not possible to make a selection between the Non-Rotating WP Design Alternative and the Turntable Design Alternative at this time since the selection is dependent upon the WP closure and inspection method.

Need dates for each module are established by the throughput analysis presented in Section 2.8. The need dates for each waste receipt case are summarized in Table 2.9-1 below.

Table 2.9-1. Startup Need Dates for Modules

Waste Receipt Case	Module 1	Module 2	Module 3
Case 1	2010	2012	2014
Case 2	2010	2012	2014
Case 3	2010	2013	2014
Case 32	2011	2013	2030
Case 33	2011	2011	2012

The entire portion of the building for the DC Handling Area is included in Module 1, even though only 11 weld stations are required in 2013. Equipment for each weld station is added as

needed; that is, 11 in Module 1 and 6 more in Module 2. The entire building is constructed in Module 1 due to the difficulty in adding onto the DC Handling Area while continuing to operate and since 15 weld stations are required in 2014.

Funding profiles for each design alternative, construction option, and waste receipt case are presented in Tables 2.9-2 and 2.9-3. The capital cost for each module is distributed over a four-year construction period that is completed the year prior to the need date shown in Table 2.9-2. The distribution of costs in that construction period are 20 percent in year 1, 33 percent in year 2, 28 percent in year 3, and 19 percent in year 4. The capital cost for horizontal storage casks and storage modules in the Fuel Staging Area are also shown, distributed evenly over ten years starting in 2010. In addition, the Net Present Value (NPV), based on the year 2000, is calculated for each case. The escalation and interest rates in the NPV calculation are taken from *Cost Escalation and Interest Rates for 2000* (CRWMS M&O 2000d). The NPV for the WHB varies from a low of \$375 million for Construction Option NR-1B, Case 32, to a high of \$420 million for Construction Option T-1B, Cases 1, 2, and 3.

WHB and Balance of Plant (BOP) Figures 2.9-1 through 2.9-14 present the funding requirements for each case as compared to the estimated funding available, as documented in the WHB Conceptual Design Guidance Table A8 in Appendix A. The estimated funding available is taken from the *CRWMS Modular Design/Construction and Operation Options Report* (CRWMS M&O 1998). In addition, cumulative capital cost for each case and the estimated funding is shown. The figures indicated that the funding requirements do not correlate to the funding anticipated. However, the results of this study will be used as input to the "Updating the CRWMS Modular Design/Construction and Operation Options Report" Study to establish new funding estimates.

Table 2.9-2. WHB Study Funding Profile (Non-Rotating Waste Package Alternative) (\$1,000s)

																								(Note 5)
Option NR-1A - Waste Receipt Case 1 & 2 (See Notes 1, 2, 3 and 4)																								NPV
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
WHB	\$0	\$0	\$72,023	\$118,838	\$126,395	\$110,600	\$49,007	\$46,097	\$18,508	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$554,026
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937
Totals	\$0	\$0	\$151,211	\$249,498	\$237,257	\$185,828	\$89,529	\$87,463	\$59,029	\$53,925	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,359,401
Option NR-1A - Waste Receipt Case 3 (See Notes 1, 2, 3 and 4)																								NPV
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
WHB	\$0	\$0	\$72,023	\$118,838	\$100,833	\$93,084	\$55,397	\$57,800	\$42,782	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$554,026
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937
Totals	\$0	\$0	\$151,211	\$249,498	\$211,695	\$169,212	\$95,919	\$98,968	\$83,313	\$53,925	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,359,401
Option NR-1A - Waste Receipt Case 32 (See Notes 1, 2, 3 and 4)																								NPV
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
WHB	\$0	\$0	\$0	\$72,023	\$118,838	\$126,395	\$110,600	\$35,787	\$24,284	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$13,220	\$21,813	\$18,508	\$12,559	\$554,026
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937
Totals	\$0	\$0	\$79,187	\$202,683	\$229,701	\$201,623	\$151,121	\$77,153	\$64,806	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$13,220	\$21,813	\$18,508	\$12,559	\$1,359,401
Option NR-1A - Waste Receipt Case 33 (See Notes 1, 2, 3 and 4)																								NPV
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
WHB	\$0	\$0	\$0	\$97,588	\$174,238	\$158,432	\$111,214	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$554,026
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937
Totals	\$0	\$0	\$79,187	\$228,245	\$285,098	\$233,660	\$151,736	\$53,925	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,359,401
Option NR-1B - Waste Receipt Case 1, 2 & 3 (See Notes 1, 2, 3 and 4)																								NPV
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
WHB	\$0	\$0	\$95,850	\$158,152	\$134,190	\$91,057	\$13,220	\$21,813	\$18,508	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$545,347
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937
Totals	\$0	\$0	\$175,037	\$288,811	\$245,052	\$166,285	\$53,741	\$63,178	\$59,029	\$53,925	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,359,722
Option NR-1B - Waste Receipt Case 32 (See Notes 1, 2, 3 and 4)																								NPV
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
WHB	\$0	\$0	\$0	\$95,850	\$158,152	\$134,190	\$91,057	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$13,220	\$21,813	\$18,508	\$12,559	\$545,347
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937
Totals	\$0	\$0	\$79,187	\$226,509	\$269,014	\$209,418	\$131,579	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$13,220	\$21,813	\$18,508	\$12,559	\$1,359,722
Option NR-1B - Waste Receipt Case 33 (See Notes 1, 2, 3 and 4)																								NPV
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
WHB	\$0	\$0	\$0	\$95,850	\$171,372	\$158,002	\$109,565	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$545,347
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937
Totals	\$0	\$0	\$79,187	\$226,509	\$282,234	\$231,230	\$150,088	\$53,925	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$40,522	\$41,368	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,359,722
Funding Limits (from Table A7 in Appendix A):																								NPV
Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
Annual Budget	\$61,000	\$0	\$0	\$278,000	\$274,000	\$283,000	\$0	\$0	\$262,000	\$272,000	\$0	\$0	\$135,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,565,000

Notes:

(1) Storage Cask positions added per year:

Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
Positions Added	0	0	0	0	0	0	48	49	48	49	48	49	48	49	48	49	0	0	0	0	0	0	0	485

(2) Capital Costs: Option NR-1A Option NR-1B

WHB Mod. 1 \$360,116 \$479,248

WHB Mod. 2 \$127,811 Included with Mod 1

WHB Mod. 3 \$68,099 \$68,099

Storage Casks \$844 \$844 per cask

BOP Surface \$395,937 \$395,937

Source of BOP Surface Facilities capital cost is 2000 TSLCC

(3) Spending profile for each module/BOP:

Year 1 - 20% Year 2 - 33% Year 3 - 28% Year 4 - 19%

(4) For startup need dates for each module, see Table 2.9-1

(5) Net Present Value (NPV) in year 2000 is calculated using escalation and interest rates from CWRMS-M&O Cost Escalation and Interest Rates for 2000, TDR-CRW-SE-000006 Rev 00, April 2000.

Table 2.9-3. WHB Study Funding Profile (Turntable Alternative) (\$1,000s)

Option T-1A - Waste Receipt Case 1 & 2 (See Notes 1, 2, 3 and 4)																											(Note 5)	
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total	NPV			
WHB	\$0	\$0	\$75,397	\$124,404	\$131,446	\$114,346	\$49,467	\$46,409	\$18,508	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$572,535	\$419,172			
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438	\$244,932			
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937	\$298,560			
Totals	\$0	\$0	\$154,584	\$255,064	\$242,308	\$189,574	\$89,988	\$87,775	\$59,029	\$53,925	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,377,910	\$962,664			
Option T-1A - Waste Receipt Case 3 (See Notes 1, 2, 3 and 4)																												
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total	NPV			
WHB	\$0	\$0	\$75,397	\$124,404	\$105,555	\$97,517	\$55,939	\$58,059	\$43,104	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$572,535	\$416,170			
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438	\$244,932			
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937	\$298,560			
Totals	\$0	\$0	\$154,584	\$255,064	\$216,418	\$172,745	\$96,461	\$99,425	\$83,625	\$53,925	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,377,910	\$959,662			
Option T-1A - Waste Receipt Case 32 (See Notes 1, 2, 3 and 4)																												
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total	NPV			
WHB	\$0	\$0	\$75,397	\$124,404	\$131,446	\$114,346	\$36,247	\$24,586	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$13,220	\$21,813	\$18,508	\$12,559	\$572,535	\$398,767			
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438	\$244,932			
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937	\$298,560			
Totals	\$0	\$0	\$79,187	\$206,058	\$235,267	\$208,674	\$154,868	\$77,613	\$65,118	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$13,220	\$21,813	\$18,508	\$12,559	\$1,377,910	\$932,250			
Option T-1A - Waste Receipt Case 33 (See Notes 1, 2, 3 and 4)																												
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total	NPV			
WHB	\$0	\$0	\$101,287	\$180,344	\$163,615	\$114,730	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$572,535	\$415,944			
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438	\$244,932			
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937	\$298,560			
Totals	\$0	\$0	\$79,187	\$231,946	\$291,206	\$238,843	\$155,252	\$53,925	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,377,910	\$959,436			
Option T-1B - Waste Receipt Case 1, 2 & 3 (See Notes 1, 2, 3 and 4)																												
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total	NPV			
WHB	\$0	\$0	\$99,948	\$164,914	\$130,927	\$94,950	\$13,220	\$21,813	\$18,508	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$595,837	\$420,435			
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438	\$244,932			
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937	\$298,560			
Totals	\$0	\$0	\$179,135	\$295,573	\$250,789	\$170,178	\$53,741	\$63,178	\$59,029	\$53,925	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,371,212	\$963,927			
Option T-1B - Waste Receipt Case 32 (See Notes 1, 2, 3 and 4)																												
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total	NPV			
WHB	\$0	\$0	\$99,948	\$164,914	\$130,927	\$94,950	\$13,220	\$21,813	\$18,508	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$13,220	\$21,813	\$18,508	\$12,559	\$595,837	\$389,979			
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438	\$244,932			
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937	\$298,560			
Totals	\$0	\$0	\$79,187	\$230,607	\$275,776	\$215,155	\$135,472	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$13,220	\$21,813	\$18,508	\$12,559	\$1,371,212	\$933,471			
Option T-1B - Waste Receipt Case 33 (See Notes 1, 2, 3 and 4)																												
Facility/Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total	NPV			
WHB	\$0	\$0	\$99,948	\$178,133	\$181,739	\$113,458	\$12,559	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$595,837	\$411,059			
Storage Casks	\$0	\$0	\$0	\$0	\$0	\$0	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$409,438	\$244,932			
BOP Surface	\$0	\$0	\$79,187	\$130,659	\$110,862	\$75,228	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$395,937	\$298,560			
Totals	\$0	\$0	\$79,187	\$230,607	\$288,996	\$238,967	\$153,960	\$53,925	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$40,522	\$41,366	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,371,212	\$954,552			
Funding Limits (from Table A7 in Appendix A):																												
Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total	NPV			
Annual Budget	\$61,000	\$0	\$0	\$278,000	\$274,000	\$283,000	\$0	\$0	\$262,000	\$272,000	\$0	\$0	\$135,000	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$0	\$1,565,000	\$1,088,174			

Notes:

(1) Storage Cask positions added per year:

Year	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022-25	2026	2027	2028	2029	Total
Positions Added	0	0	0	0	0	0	48	49	48	49	48	49	48	49	48	49	0	0	0	0	0	0	0	485

(2) Capital Costs: Option T-1A Option T-1B

WHB Mod. 1	\$376,983	\$499,738
WHB Mod. 2	\$129,453	Included with Mod. 1
WHB Mod. 3	\$88,099	\$88,099
Storage Casks	\$844	\$844 per cask
BOP Surface	\$395,937	\$395,937

Source of BOP Surface Facilities capital cost is 2000 TSLCC.

(3) Spending profile for each module/BOP:

Year 1 - 20% Year 2 - 33% Year 3 - 28% Year 4 - 19%

(4) For startup need dates for each module, see Table 2.9-1.

(5) Net Present Value in year 2000 is calculated using escalation and interest rates from CWRMS-M&O Cost Escalation and Interest Rates for 2000, TDR-CRW-SE-000006 Rev 00, April 2000.

**OFFICE OF CIVILIAN RADIOACTIVE WASTE MANAGEMENT
SPECIAL INSTRUCTION SHEET**

1. QA: N/A

Page: 1 of: 1

Complete Only Applicable Items

This is a placeholder page for records that cannot be scanned or microfilmed

2. Record Date 11/06/2000	3. Accession Number ATT-TO MOL.20001122.0004
4. Author Name(s) G.W. ROWE	5. Author Organization N/A
6. Title WHITE PAPER WASTE HANDLING BUILDING CONCEPTUAL STUDY	
7. Document Number(s) TDR-WHS-SE-000002	8. Version REV 00
9. Document Type REPORT	10. Medium OPTIC / PAPER
11. Access Control Code PUB	
12. Traceability Designator DC #26137	
13. Comments THE 4 PAGES OF ATTACHED TO ONE OF A KIND COLOR DOCUMENT CAN BE LOCATED THROUGH THE RECORDS PROCESSING CENTER	

Figure 2.9-1. Option NR-1A Cases 1 & 2
 WHB and BOP Cost/Budget Profile

Figure 2.9-2. Option NR-1A Case 3
 WHB and BOP Cost/Budget Profile

Figure 2.9-3. Option NR-1A Case 32
 WHB and BOP Cost/Budget Profile

Figure 2.9-4. Option NR-1A Case 33
 WHB and BOP Cost/Budget Profile

Figure 2.9-5. Option NR-1B Cases 1, 2, & 3
W/HB and BOP Cost/Budget Profile

Figure 2.9-6. Option NR-1B Case 32
W/HB and BOP Cost/Budget Profile

Figure 2.9-7. Option NR-1B Case 33
W/HB and BOP Cost/Budget Profile

Figure 2.9-8. Option T-1A Cases 1 & 2
WHB and BOP Cost/Budget Profile

Figure 2.9-9. Option T-1A Case 3
WHB and BOP Cost/Budget Profile

Figure 2.9-10. Option T-1A Case 32
WHB and BOP Cost/Budget Profile

Figure 2.9-11. Option T-1A Case 33
WHB and BOP Cost/Budget Profile

Figure 2.9-12. Option T-1B Cases 1, 2, & 3
WHB and BOP Cost/Budget Profile

Figure 2.9-13. Option T-1B Case 32
WHB and BOP Cost/Budget Profile

Figure 2.9-14. Option T-1B Case 33
WHB and BOP Cost/Budget Profile

3. PATH FORWARD

3.1 INTRODUCTION

As a result of the WHB Conceptual Study, several items were identified that could not be resolved as part of the study but need to be resolved before the LA design of the WHB can be finalized. These items are identified in the following sections with a recommendation for resolving each issue.

3.2 UPDATE OF PROJECT DOCUMENTS

Table 3.2-1 provides recommendations for incorporating the proposed requirements presented in Appendix A into project documents. If these recommendations are considered viable, a baseline change proposal (BCP) should be prepared using procedure AP-3.14Q to request approval by M&O Management and DOE. It may be necessary to prepare additional documentation to supplement this study in order to change the baseline. The SDD structure will be evaluated for changes by SED at a later date.

Table 3.2-1. Recommendations for Capturing Proposed Requirements

Included in BCP	Further Study	Description	Project Document (Note 1)	Comment	Need Date for LA (Note 2)
Study Section	Study Section				
2.1.1		Types of Waste Forms to Process	N/A	PDD already contains requirement for type of waste forms that will be accepted at the repository.	N/A
2.1.2		Processing Options	PDD	The PDD needs to be revised to incorporate the processing options that must be provided by the Waste Handling System.	TBD
2.1.3	3.3.1	Maximum HLW Throughput Requirements	PDD	The PDD needs to be revised to reflect the new naval waste stream.	TBD
2.1.4.1	3.3.2	CSNF Process Fuel Blending Inventory	PDD	PDD Section 5.2.14 needs to be revised to reflect the new blending inventory requirements.	TBD
2.1.4.2		DOE SNF Process Fuel Storage (with the exception of naval)	PDD	The PDD should be revised to reflect the required DOE SNF (with the exception of naval) process fuel storage requirements.	TBD
2.1.5	3.3.3	CSNF Handling and Storage	PDD/SDD	The PDD Section 2 and the applicable SDDs need to be revised to reflect dry CSNF handling and storage. An evaluation needs to be performed to determine if a small wet pool is necessary for off-normal events and/or non-standard fuel.	TBD

Table 3.2-1. Recommendations for Capturing Proposed Requirements (Continued)

Included in BCP	Further Study	Description	Project Document (Note 1)	Comment	Need Date for LA (Note 2)
Study Sect.	Study Sect.				
2.1.6		Transfer Lines	PDD/SDD	The PDD Section 2 and Table 2-1 and the applicable SDDs need to be revised to reflect the generic transfer line.	TBD
2.1.7		DC Handling Area Radiation Levels	PDD/SDD	The PDD and applicable SDDs need to be revised to reflect the proposed requirement for a maximum radiation level inside the DC Handling Area	TBD
2.1.8	3.3.4	Canister/Cask Maximum Drop Height	PDD/SDD	The PDD and applicable SDDs need to be revised to incorporate the maximum canister drop heights. An evaluation needs to be performed to determine if cask drop heights need to also be included.	TBD
2.1.9		Fuel Staging	PDD	The PDD needs to be revised to add the capability to allow for aging of the fuel.	TBD
2.1.10		WP Staging	PDD/SDD	The PDD and applicable SDDs need to be revised to add the capability to stage DC/WPs.	TBD
2.1.11		Pre-closure Safety Strategy	PDD	The proposed requirements should be included in Section 3.1 of the next revision of the PDD (CRWMS M&O 2000b)	TBD
2.1.12	3.3.5	Inerting Requirement	PDD/SDD	The proposed WP inerting requirements should be defined and included in the PDD and applicable SDD.	TBD
2.1.13	3.3.6	Method to Measure Waste Form Heat Output	PDD	The method to determine waste form heat output needs to be determined and the requirements included in the PDD.	TBD
2.1.14	3.3.7	Method to Measure Waste Form Nuclear Reactivity	PDD	The method to determine waste form nuclear reactivity needs to be determined and the proposed requirements included in the PDD.	TBD
2.1.15	3.3.8	WP Welding/Inspection Configuration and Operating Times	SDD	These values are estimates based on present tests performed by the Waste Package Design Department (WPDD) (Knapp 2000) and are for reference only. These methods/times need to be confirmed and the results included in the applicable SDDs.	TBD

Table 3.2-1. Recommendations for Capturing Proposed Requirements (Continued)

Included in BCP	Further Study	Description	Project Document (Note 1)	Comment	Need Date for LA (Note 2)
Study Sect.	Study Sect.				
2.1.16	3.3.9	Cladding Performance in Dry Environment	PDD/SDD	These proposed requirements should be included in the PDD and applicable SDD. In addition, the requirements for storing non-standard fuel in a dry environment need to be established and included in the applicable SDDs.	TBD
2.1.17		Contamination Control and Decontamination	SDD	The proposed requirements for contamination control should be included in the applicable SDDs.	TBD
2.1.18	3.3.10	Non-Standard Fuel and Non-Fuel Bearing Components	SDD	The receipt requirements for non-standard fuel need to be established and included in the applicable SDDs.	TBD
	3.3.11	DPC Cutting and Contamination Control	WHB Design	The method for cutting the DPCs needs to be developed and included in the design of the WHB.	TBD

Note 1: In lieu of revisions to PDD and SDDs, AP3-14Q transmittals may be used to provide preliminary revised requirements. (PDD = Monitored Geologic Repository Project Description Document, CRWMS M&O 2000b.)

Note 2: The need dates required to meet the LA design schedule are to be determined since the start of Surface Facility LA Design has been delayed until February 12, 2001.

3.3 ISSUES AND RECOMMENDATIONS

3.3.1 Maximum Throughput Requirements

The naval SNF arrival schedule specified in Section 2.3 of the WHB Conceptual Design Guidance (Appendix A) is different than the naval SNF arrival schedule defined in the PDD. The waste stream defined in Appendix A is based on a memorandum, "Comments on Waste Acceptance System Requirements Document Revision 4," (Mowbray 2000), requesting the arrival schedule be revised. The arrival schedule in Appendix A is based on this revised naval SNF arrival schedule.

Recommendation

Revise the PDD (CRWMS M&O 2000b) to reflect the naval SNF arrival schedule defined in Appendix A.

3.3.2 Commercial Spent Nuclear Fuel Process Fuel Blending Inventory

The recommended Waste Handling System configuration provides a margin of approximately 8,250 assemblies between the estimated required blending inventory and the maximum allowable blending inventory. Though this appears to be sufficient, the WHB Conceptual Study identified

various engineering solutions that will reduce the fuel blending inventory, increase the margin to the 12,000 maximum, and provide greater flexibility to account for variations in the incoming waste stream. These engineering solutions need to be studied further.

Recommendations

1. Perform a more detailed evaluation of the WP allowable maximum heat output in an attempt to increase it above the present 11.8 kW. The evaluation needs to consider the effects on cladding performance, local drift wall temperature, rock temperature profile, and the TSPA.
2. Perform an evaluation to determine if it is practical to co-dispose the BWR and PWR assemblies in the same WP. The evaluation needs to consider criticality issues as well as WP internal configuration.
3. Develop a flexible, modular dry storage facility that can adapt to variations in the level of blending inventory.

3.3.3 CSNF Handling and Storage

Handling of standard CSNF will take place in a dry environment. However, there are functions that may be handled more efficiently in a wet pool rather than dry area. These functions include recovery from certain off-normal events, temporary storage of assemblies with known cladding defects, and long term storage of high heat output assemblies.

Recommendation

Perform a more detailed evaluation of those functions that may be better performed in a wet pool environment and determine if it would be advantageous to add a small wet pool to the remediation cell to handle these functions.

3.3.4 Shipping Cask Drop Height

The WASRD identifies each type of DOE canister that will be shipped to the repository and the allowable drop height for each canister. No such evaluation has been performed for the shipping casks without the impact limiters installed. If the allowable drop height of the shipping casks is greater than the maximum lift height inside the WHB, and if credit could be taken for the shipping cask, the licensing basis for pre-closure safety would be improved.

Recommendation

Develop a list of casks that may be shipped to the repository and determine the maximum drop height for each cask. The maximum drop height evaluation could either be performed by the cask vendor or in house. The list of casks needs to be reviewed periodically and updated if new casks are developed. Document the results in the PDD and applicable SDD.

3.3.5 Inerting Requirements

Section 2.12 of the WHB Conceptual Design Guidance (Appendix A) presented recommendations for the allowable oxygen level inside the DC prior to final closure. These recommendations are based on requirements for short-term cask dry storage and have not been evaluated to determine if these oxygen levels/temperature profiles are acceptable for long-term storage prior to emplacement.

Recommendations

Perform an evaluation of the allowable oxygen levels inside the WP to determine what levels are acceptable for long term repository storage. Document the results in the appropriate SDD.

3.3.6 Method to Determine Fuel Assembly Heat Output

The WHB Conceptual Study did not include any provision for measuring the actual thermal output of individual SNF assemblies. If this becomes a routine requirement it could greatly affect the WHB configuration and throughput.

Recommendations

1. Evaluate the codes contained in Regulatory Guide 3.54, *Spent Fuel Heat Generation in an Independent Spent Fuel Storage Installation* and determine if they are adequate for repository thermal analyses.
2. Develop potential methods and/or processes that would allow measuring the actual thermal output of individual waste forms if benchmarking the computer codes were required.
3. Continue to work with the NRC to determine if it will be necessary to measure the actual thermal output of various waste forms.
4. Document the method of determining the heat output of various waste forms in the PDD (CRWMS M&O 2000b).

3.3.7 Method to Determine Fuel Assembly Nuclear Reactivity

The WHB Conceptual Study did not include any provision for measuring the actual nuclear reactivity of individual SNF assemblies. If this becomes a routine requirement, it could greatly affect the WHB configuration and throughput.

Recommendations

1. Develop potential methods and/or processes that would allow determining the actual burn-up of individual waste forms.
2. Continue to work with the NRC to determine if it will be necessary to measure the actual nuclear reactivity of the various waste forms.

3. Document the method of determining the nuclear reactivity of the various waste forms in the PDD (CRWMS M&O 2000b).

3.3.8 Waste Package Welding/Inspection Configuration and Operating Times

The present WP welding/inspection configuration causes several challenges to the design of the WHB. The present configuration necessitates that the DC be rotated during the welding/inspection/heat treatment processes. This requires additional lifts to move the DC from the transportation cart to the rotating device (which increases the DBE risk), increases the amount of large complex equipment that is required in the DC handling area (increased cost), and raises concerns as to how precise the rotating equipment must be (reliability and increased maintenance). In addition, the closure configuration utilizes 3 separate covers that are complicated and require over 4 days to install. With the estimated throughput of the WHB, it is estimated that at least 17 welding stations will be required (increases the size of the WHB and increases the cost due to the large amount of equipment that is required).

Recommendations

1. Evaluate the possibility of maintaining the DC stationary and rotating the weld/inspection/heat treatment equipment. (This option is continually being evaluated by the WPDD.)
2. Consider redesigning the inner lid to incorporate a mechanical closure similar to the naval design and eliminate the full penetration weld. (The inner lid design is currently under investigation and analysis by the WPDD.) The purpose of the inner lid is to provide structural strength to the WP in an accident condition and credit is not taken for this lid in the *Total System Performance Assessment (TSPA)- Site Recommendation Methods and Assumptions* (CRWMS M&O 2000a).
3. Evaluate combining the middle and outer barrier lids into a single system that incorporates mechanical as well as welded closure mechanisms.
4. Evaluate whether welding and inspection operations can be performed completely remote, or whether some manual assistance is required.

3.3.9 Cladding Performance in Dry Environment

The cladding performance for intact fuel assemblies is well understood and the requirements for handling these assemblies in a dry environment are already established. However, if there are any defects in the cladding that would permit oxygen to react with the uranium dioxide (UO₂) fuel pellets, fuel unzipping can occur. The requirements for handling and/or staging of failed fuel assemblies in a dry environment have not been established.

Another issue that requires investigation is the potential for elevated temperatures of the DC/WP internal CSNF and shell temperatures in a shielded overpack.

Recommendation

1. Perform an evaluation of fuel unzipping in a dry, un-inerted environment and establish requirements for the length of time that the fuel can be handled in this environment before unacceptable levels of fuel unzipping occur. Document these requirements in the PDD (CRWMS M&O 2000b).
2. Evaluate cladding temperatures for the shielded overpack configuration in the DC Handling Area.

3.3.10 Non-standard Fuel and Non-fuel Bearing Components

The conceptual design did not include consideration of non-standard fuel forms and non-fuel bearing components. This is due to the fact that the quantities, types, timing, and configuration for receipt of these components have not been defined and it is very difficult to design the facilities and equipment that are needed in the WHB to process these waste forms. Although these are a small percentage of the receipts, they must by contract be accommodated.

Recommendation

Determine quantities, types, configurations, and potential timing for receipt of non-standard fuel and non-fuel bearing components. Document results in the PDD and applicable SDD.

3.3.11 DPC Cutting and Contamination Control

The WHB Conceptual Study does not address specific tooling or methods for cutting open the DPCs. This is a significant task and could affect the throughput of the Waste Handling System. In addition, there is a potential that during the cutting operation the shipping cask could become contaminated.

Moving from a wet handling system to a dry handling system may make contamination control more challenging. The methods for monitoring and controlling the contamination need to be studied further during the LA design.

Recommendations

1. Several DPC cutting techniques need to be evaluated to determine the most reliable and efficient tooling and process to be employed. Consideration needs to be given to ensuring that the DPC shipping cask does not become contaminated during the cutting process. The method shall be documented in the applicable SDD.
2. For the dry handling design, the amount of contamination generated and the process/equipment necessary to control this contamination needs to be evaluated during the LA design.

3.4 DETAIL WASTE HANDLING BUILDING DESIGN SCHEDULE

As indicated in Section 1.4.3, two design alternatives were carried throughout this evaluation, the Non-Rotating WP Design Alternative and the Turntable Design Alternative. It was not possible as part of this study to select a single alternative because the selection is dependent on the method used to perform the WP closure and inspection. It is imperative that a decision whether to rotate the WP or not be made as soon as possible so that a single design alternative can be carried forward to LA detail design.

A Path Forward Schedule has been prepared (Figure 3.4-1). This schedule shows the review and approval schedule for the WHB Conceptual Study, as well as a proposed schedule for modifying the PDD (CRWMS M&O 2000b) and SDDs. The issues identified in Sections 3.2 and 3.3 above should be addressed at the beginning of FY2001 so that any changes to the baseline can be implemented in the LA design as soon as possible.

Figure 3.4-1. Concept Design Path Forward Schedule

INTENTIONALLY LEFT BLANK

4. CONCLUSION

4.1 INTRODUCTION

As stated in Section 1.1, the objective of the WHB Conceptual Study is to develop proposed requirements in sufficient detail to allow the surface facility design to proceed as early as possible in FY2001. These proposed requirements are presented in Appendix A and the recommendations for implementing these proposed requirements are presented in Section 3 of this study. As part of the process in developing these proposed requirements, layout drawings (Appendix B) and operational flowcharts (Appendix C) were developed to provide conceptual methods for implementing these requirements. In addition, a throughput analysis (Appendix D) and a cost estimate (Appendix F) were developed to assist with evaluating the feasibility of implementing the design recommendations and to evaluate the feasibility of a phased construction approach, Section 2.9.

It was **NOT** the intent of this study to provide a specific recommendation for the design layout and the construction schedule of the WHB since the final decision is dependent on factors that were outside the scope of this study (transportation, waste acceptance rate, sub-surface construction, etc.). It is the intent of this study to provide sufficient input to the revision of the *CRWMS Modular Design/Construction and Operations Options Report* (CRWMS M&O 1998) being performed by the Systems Cost & Schedule Section in the Washington DC office to allow evaluations of various options for optimizing overall CRWMS design and operations.

4.2 DISCUSSION

In developing the proposed requirements for the WHB, four major design objectives were considered:

Flexibility

Flexibility was a key factor in developing the proposed requirements. The design of the repository has not been finalized and therefore the design of the WHB needs to be able to accommodate various repository design alternatives. In addition, the actual incoming waste stream cannot be known with certainty. The design of the WHB needs to be flexible enough to account for repository design options and unknown variations in the incoming waste stream.

Simplicity

While flexibility is required for the design of the WHB, the design cannot be so complicated that it increases the cost to unrealistic levels. In developing the proposed requirements, realistic constraints were imposed on the incoming waste stream in an attempt to bound, and at the same time accommodate expected variations in, what will be received at the repository and what options are available to process each waste form.

Reliability

Since there will be specific requirements on the receipt rate of waste at the repository, reliability is important to ensure that the receipt rates can be met. The proposed requirements in Appendix A are intended to keep the design as simple as possible and provide adequate redundancy where needed to ensure that maximum reliability is achieved.

Modularity

Modularity and phased construction may be of great benefit in spreading out the capital cost profile thus increasing the viability of the overall program. Though it is beyond the scope of this study to evaluate the overall repository cost profile, an important result of this study is to provide options for the construction of the WHB that will support both modularity and phased construction.

Incorporating the proposed technical requirements in Appendix A and the design objectives discussed above have resulted in the following potential design improvements:

- The Assembly Transfer System (ATS) and Canister Transfer Systems (CTS) would be combined into one system that can process either individual assemblies or canisters. This simplifies the processing by reducing the types and amounts of equipment that are needed thus reducing construction and operating costs, the amount of spare parts necessary, the number of procedures required, and the amount of operator training required. This also increases the reliability because having one module out of service does not restrict the ability to process any type of incoming waste.
- The pools would be eliminated and all incoming waste would be handled in a dry environment. This would eliminate all of the water handling and processing systems associated with the pools and reduce the number of SNF waste processing steps required for each type of waste, thus eliminating many of the DBEs and increasing overall reliability of the facility.
- The cutting open of DPCs would be moved out of the normal processing line. Since this task is very time consuming and represents one of the most unpredictable work tasks that must be performed in the WHB, the overall system reliability and throughput would be increased.
- Shielding the DCs prior to loading would allow personnel access to the DC handling area. This would greatly simplify the equipment that is needed to move the DC/WPs in the DC handling area thus reducing cost and increasing reliability. Shielding does not, however, mitigate the problem of decontaminating the WP, if required.
- The Carrier Preparation Building would be eliminated and the function incorporated into the WHB. This would reduce the capital cost, eliminate the possibility of a cask drop accident without impact limiters outside of a confinement area, and increase reliability.

- The addition of the transporter load bay would provide for the movement of loaded WPs to the Fuel Staging Area. Also, storage casks could be loaded with hot assemblies for transport to the Fuel Staging Area. This would increase the flexibility of the facility.

A comparison of major parameters between the SR design and the Non-Rotating WP Alternative conceptual design is provided in the following table.

Table 4.2-1. Major Parameters Comparison

Parameter	SR Design	Conceptual Design
Building footprint (sq-ft)	747,670	839,400 ⁽¹⁾
Number of lifts per year	42,122	28,922
Number of Internal DBEs	26	8
Capital Cost	\$760M	\$954M ⁽¹⁾

⁽¹⁾ Includes WHB and FSA.

The recommendations presented in Section 3 of this report, if implemented, would lead to an improvement in the WHB design. It is important that these recommendations be baselined into project documents and that the items identified in Section 3 be resolved in a timely manner to prevent any delays in the WHB detail design to support the LA. It is also important that the modular construction and cost information be incorporated into the revision of the *CRWMS Modular Design/Construction and Operations Options Report* (CRWMS M&O 1998). This would allow that study to proceed in a timely manner so that an overall repository design approach may be developed.

INTENTIONALLY LEFT BLANK

5. REFERENCES

5.1 DOCUMENTS CITED

- Bechtel Nevada Corporation 1997   Bechtel Nevada Corporation 1997. *Project Labor Agreement for Tunnel and Tunnel-Shaft Construction between Bechtel Nevada Corporation and Laborers' International Union of North America, Local Union No. 872*. October 1, 1997-September 30, 2002. Las Vegas, Nevada: Bechtel Nevada Corporation. ACC: MOL.19980626.0070.
- CRWMS M&O 1998   CRWMS M&O 1998. *CRWMS Modular Design/Construction and Operation Options Report*. A00000000-01717-5700-00022 REV 02. Vienna, Virginia: CRWMS M&O. ACC: MOV.19981218.0001.
- CRWMS M&O 1999   CRWMS M&O 1999. *Summary of Work in Progress for Reconfiguration of the Waste Handling Building*. LV.SFO.GWG.9/99-070. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19991129.0452.
- CRWMS M&O 2000a   CRWMS M&O 2000. *Total System Performance Assessment-Site Recommendation Methods and Assumptions*. TDR-MGR-MD-000001 REV 00 ICN 02. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20000307.0384.
- CRWMS M&O 2000b   CRWMS M&O 2000. *Monitored Geologic Repository Project Description Document*. TDR-MGR-SE-000004 REV 02. Las Vegas, Nevada: CRWMS M&O. Submit to RPC URN-0624
- CRWMS M&O 2000c   CRWMS M&O 2000. *Design Basis Event Frequency and Dose Calculation for Site Recommendation*. CAL-WHS-SE-000001 REV 01. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20000627.0214.
- CRWMS M&O 2000d   CRWMS M&O 2000. *Cost Escalation and Interest Rates for 2000*. TDR-CRW-SE-000006 REV 00. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20000517.0452.
- CRWMS M&O 2000e   CRWMS M&O 2000. *White Paper: Waste Handling Building Conceptual Study*. Development Plan TDP-WHS-SE-000005 REV 00. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.20000811.0004.
- CRWMS M&O 2000f   CRWMS M&O 2000. *Add Work Scope & Budget for Enhanced Surface Design Support for LA (M&O-00-048)*. Las Vegas, Nevada: CRWMS M&O. URN-0533

DOE 1996	DOE (U.S. Department of Energy) 1996. <i>Dry Transfer System Topical Safety Analysis Report</i> . Rev. 0. Three volumes. Washington, D.C.: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: MOV.19980702.0006; MOV.19980702.0007; MOV.19980702.0008.
DOE 1999	DOE (U.S. Department of Energy) 1999. <i>Waste Acceptance System Requirements Document, Revision 03 (E00000000-00811-1708-00001)</i> . DOE/RW-0351. Washington, D.C.: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: HQO.19990226.0001.
DOE 2000	DOE (U.S. Department of Energy) 2000. <i>Quality Assurance Requirements and Description</i> . DOE/RW-0333P, Rev. 10. Washington, D.C.: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: MOL.20000427.0422.
Dyer 1999	Dyer, J.R. 1999. "Revised Interim Guidance Pending Issuance of New U.S. Nuclear Regulatory Commission (NRC) Regulations (Revision 01, July 22, 1999), for Yucca Mountain, Nevada." Letter from J.R. Dyer (DOE/YMSCO) to D.R. Wilkins (CRWMS M&O), September 3, 1999, OL&RC:SB-1714, with enclosure, "Interim Guidance Pending Issuance of New NRC Regulations for Yucca Mountain (Revision 01)." ACC: MOL.19990910.0079.
Knapp 2000	Knapp, M. 2000. "Revised Times." E-mail from M. Knapp to G. Rowe (CRWMS M&O), September 15, 2000. ACC: MOL.20000918.0524.
Mowbray 2000	Mowbray, G. 2000. "Comments on Waste Acceptance System Requirements Document Revision 4." Memorandum from G. Mowbray (DOE) to D. Shelor, March 8, 2000, with attachment. ACC: MOL.20000728.0538.
NRC 1997	NRC (U.S. Nuclear Regulatory Commission) 1997. <i>Standard Review Plan for Dry Cask Storage Systems: Final Report</i> . NUREG-1536. Washington, D.C.: U.S. Nuclear Regulatory Commission. TIC: 232373.
NRC 2000	NRC (U.S. Nuclear Regulatory Commission) 2000. <i>Preliminary Draft, Assessment Report, Docket 71-1024, Department of Energy's Dry Transfer System</i> . Washington, D.C.: U.S. Nuclear Regulatory Commission. TIC: 248976.
R.S. Means Company 1997a	R.S. Means Company 1997. <i>Heavy Construction Cost Data, 1998</i> . 12th Annual Edition. Kingston, Massachusetts: R.S. Means Company. TIC: 104089.

R.S. Means Company
1997b

R.S. Means Company 1997. *Building Construction Cost Data, 1998*. 56th Annual Edition. Kingston, Massachusetts: R.S. Means Company. TIC: 236392.

Richardson Engineering
Services 2000

Richardson Engineering Services 2000. *Process Plant Construction Estimating Standards*. 2000 Edition. Four volumes. Mesa, Arizona: Richardson Engineering Services. TIC: 247208.

5.2 CODES, STANDARDS, REGULATIONS, AND PROCEDURES

10 CFR 20. Energy: Standards for Protection Against Radiation. Readily available.

10 CFR 835. Energy: Occupational Radiation Protection. Readily available.

AP-2.21Q, Rev. 0, ICN 0. *Quality Determinations and Planning for Scientific, Engineering, and Regulatory Compliance Activities*. [Washington, D.C.]: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: MOL.20000802.0003.

AP-3.14Q, Rev. 0, ICN 1. *Transmittal of Input*. Washington, D.C.: U.S. Department of Energy, Office of Civilian Radioactive Waste Management. ACC: MOL.20000427.0419.

QAP-2-3, Rev. 10. *Classification of Permanent Items*. Las Vegas, Nevada: CRWMS M&O. ACC: MOL.19990316.0006.

Regulatory Guide 3.54, Rev. 0. 1984. *Spent Fuel Heat Generation in an Independent Spent Fuel Storage Installation*. Washington, D.C.: U.S. Nuclear Regulatory Commission. Readily available.

**White Paper:
Waste Handling Building Conceptual Study**

TDR-WHS-SE-000002 REV 00

APPENDIX A

Waste Handling Building Conceptual Design Guidance

INTENTIONALLY LEFT BLANK

Contents

1. INTRODUCTION	A-1
1.1 PURPOSE.....	A-1
1.2 FORMAT.....	A-1
2. TECHNICAL REQUIREMENTS	A-1
2.1 TYPES OF WASTE FORMS TO PROCESS	A-1
2.2 PROCESSING OPTIONS	A-1
2.3 MAXIMUM THROUGHPUT REQUIREMENTS	A-2
2.4 PROCESS FUEL BLENDING INVENTORY	A-2
2.4.1 Commercial Spent Nuclear Fuel.....	A-2
2.4.2 DOE/Naval SNF	A-2
2.5 COMMERCIAL SPENT NUCLEAR FUEL HANDLING AND STORAGE	A-2
2.6 TRANSFER LINES	A-3
2.7 DISPOSAL CONTAINER HANDLING AREA RADIATION LEVELS.....	A-3
2.8 CANISTER MAXIMUM DROP HEIGHT.....	A-3
2.9 DISPOSAL CONTAINERS/WASTE PACKAGES STAGING.....	A-3
2.10 PRE-CLOSURE SAFETY STRATEGY	A-3
2.11 INERTING REQUIREMENTS.....	A-3
2.12 METHOD TO DETERMINE WASTE FORM HEAT OUTPUT.....	A-3
2.13 METHOD TO DETERMINE WASTE FORM NUCLEAR REACTIVITY.....	A-3
2.14 WASTE PACKAGE WELDING/INSPECTION CONFIGURATION AND OPERATING TIMES	A-3
2.15 CLADDING PERFORMANCE IN DRY ENVIRONMENT	A-5
2.16 CONTAMINATION CONTROL AND DECONTAMINATION.....	A-5
2.17 NON-STANDARD FUEL AND NON-FUEL BEARING COMPONENTS	A-5
3. MILESTONE SCHEDULE.....	A-5

4. ALTERNATE RECEIPT SCENARIOS.....	A-6
4.1 CASE 32.....	A-6
4.2 CASE 33.....	A-8
5. FUNDING CONSTRAINTS.....	A-10

Tables

Table A-1. Naval SNF Arrival Schedule	A-2
Table A-2. Pre-closure Safety Strategy.....	A-4
Table A-3. Parametric Study Case 32 - Initial 1200 MTU Module, 3 modules at completion, 2400 MTU in 2015, 3600 MTU in 2028.....	A-7
Table A-4. Initial 1200 MTU Module, 3 modules at completion, 2600 MTU in 2015, 3600 MTU in 2028.....	A-8
Table A-5. Parametric Study Case 33 - Initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTU in 2014, 3600 MTU in 2028.....	A-9
Table A-6. Initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTU in 2014, 3600 MTU in 2028	A-10
Table A-7. Yearly Funding Projections	A-10

INTENTIONALLY LEFT BLANK

1. INTRODUCTION

1.1 PURPOSE

The DOE has requested the M&O to evaluate the Waste Handling Building (WHB) operations and make recommendations as to improvements that could be made to the present design. Based on this request, the M&O submitted, and the DOE approved, *Add Work Scope & Budget for Enhanced Surface Design Support for LA (M&O-00-048)* (CRWMS M&O 2000f) to develop proposed requirements in sufficient detail to allow the surface facility design to proceed once funding becomes available. The purpose of this appendix is to document these proposed requirements.

1.2 FORMAT

The design guidance used in the WHB Conceptual Study is broken down into four major categories. These categories are:

- Technical Requirements
- Milestone Schedule
- Alternate Receipt Scenarios
- Funding Constraints

The proposed technical requirements will be used to develop the actual conceptual design of the WHB facility. The milestone schedule, alternate receipt scenarios, and funding constraints will then be applied to the WHB design to determine if there are any options and/or benefits to constructing the WHB facility in a phased or modular approach.

2. TECHNICAL REQUIREMENTS

See Section 2.1 of WHB Conceptual Study for proposed requirement bases.

2.1 TYPES OF WASTE FORMS TO PROCESS

The WHB facility shall be capable of accepting and packaging the waste forms defined in the *Monitored Geologic Repository Project Description Document (PDD)* (CRWMS M&O 2000b), Section 2.3.

2.2 PROCESSING OPTIONS

The WHB shall be capable of the following processing options:

1. Load uncanistered CSNF into DC and emplace or transfer to the staging area
2. Load uncanistered CSNF into process blending inventory
3. Load uncanistered CSNF into dry storage cask and transfer to the staging area
4. Load CSNF canisters into dry storage cask and transfer to the staging area
5. Load CSNF canisters into DC and emplace or transfer to the staging area

6. Open CSNF canister, transfer individual assemblies to DC, and emplace or transfer to the staging area
7. Open CSNF canister, transfer individual assemblies to dry storage cask, and emplace or transfer to the staging area
8. Load canistered DOE SNF/HLW into DC and emplace or transfer to the staging area
9. Transfer canistered DOE SNF/HLW to temporary storage (with the exception of naval SNF)

2.3 MAXIMUM THROUGHPUT REQUIREMENTS

The WHB shall be capable of accepting and packaging the SNF waste stream defined in the PDD (CRWMS M&O 2000b), Tables 5-1 through 5-4 with the following exception:

Table A-1. Naval SNF Arrival Schedule

Year	Naval SNF	
	Casks	Canisters
2010	3	3
2011	3	3
2012	6	6
2013	6	6
2014	12	12
2015 until end of receipt	15	15

The number of WPs loaded shall be as defined in the PDD (CRWMS M&O 2000b), Table 5-5.

2.4 PROCESS FUEL BLENDING INVENTORY

2.4.1 Commercial Spent Nuclear Fuel

The WHB facility shall have the capability to maintain a maximum blending inventory of 5,000 MTU (approximately 12,000 assemblies) of CSNF. Of this inventory, at least 400 assemblies shall be located inside the WHB. The remaining inventory shall be staged in modular storage facilities external to the WHB.

2.4.2 DOE/Naval SNF

The WHB facility shall be capable of storing 25 DOE SNF/HLW canisters inside the WHB.

NOTE: No storage will be provided for naval canisters.

2.5 COMMERCIAL SPENT NUCLEAR FUEL HANDLING AND STORAGE

The WHB shall have the ability to handle and store all standard CSNF and DOE SNF/HLW in a dry environment.

2.6 TRANSFER LINES

Each Waste Transfer line inside the WHB shall be capable of handling both uncanistered waste and canistered waste.

The design shall be such that individual lines can be constructed in phases as necessary to provide the required throughput.

2.7 DISPOSAL CONTAINER HANDLING AREA RADIATION LEVELS

Radiation dose rates in the DC Handling Area shall be less than the High Radiation Area limits specified in 10CFR20.1003 to allow temporary access to this area. Normal access will be in accordance with project ALARA requirements.

2.8 CANISTER MAXIMUM DROP HEIGHT

The WHB facility operations should minimize the number of canister lifts and shall limit the height of the lifts to less than that specified in the current version of the WASRD.

2.9 DISPOSAL CONTAINERS/WASTE PACKAGES STAGING

The WHB facility shall be capable of staging 20 welded WPs inside the WHB.

2.10 PRE-CLOSURE SAFETY STRATEGY

The WHB shall support the pre-closure safety strategy defined in Table A-2.

2.11 INERTING REQUIREMENTS

The WHB shall have the capability to inert the WPs to a maximum quantity of oxidizing gasses (such as O₂, CO₂, and CO) of less than 1 gram-mole per cask.

2.12 METHOD TO DETERMINE WASTE FORM HEAT OUTPUT

The heat output of each waste form shall be calculated based on records provided by the utility, DOE-EM, or Navy Nuclear Propulsion Program (NNPP) before being loaded into a WP.

2.13 METHOD TO DETERMINE WASTE FORM NUCLEAR REACTIVITY

The reactivity of each waste form shall be calculated based on records provided by the utility, DOE-EM, or NNPP before being loaded into a WP.

2.14 WASTE PACKAGE WELDING/INSPECTION CONFIGURATION AND OPERATING TIMES

The WHB should be capable of completing closure (welding and inspection) of each DC within 135 hours.

Waste Handling Building Conceptual Study
Appendix A: Waste Handling Building Conceptual Design Guidance

Table A-2. Pre-closure Safety Strategy

Location	Functions	Canistered SNF		Uncanistered SNF	
		Safety Strategy	Major Safety Features	Safety Strategy	Major Safety Features
Carrier Prep Area	Survey Remove impact limiters Remove Personal barriers	Prevent events that could exceed shipping cask design basis (preclude breach)	Shipping Cask Canister	Prevent events that could exceed shipping cask design basis (preclude breach)	Shipping Cask
Carrier Bay Area	Remove hold downs Upright Cask Transfer cask to cart	Prevent events that could exceed shipping cask design basis (preclude breach)	Shipping Cask Canister	Prevent events that could exceed shipping cask design basis (preclude breach)	Shipping Cask
Cask Preparation Area	Vent/sample cask Unbolt cask cover Bolt cask cover	Prevent events that could exceed canister design basis (preclude breach)	Canister	Minimize the amount of radioactivity released to the environment during accident condition	Confinement HVAC
Cask Unloading Area	Remove cover Remove waste/SNF from cask Install cover	Prevent events that could exceed canister design basis (preclude breach) (Note 1)	Canister	Minimize the amount of radioactivity released to the environment during accident condition	Confinement HVAC
Canister co-disposal inventory Area	Store canistered waste	Prevent events that could exceed canister design basis (preclude breach) (Note 1)	Canister	N/A	N/A
Assembly Fuel blending inventory Area	Store SNF assemblies	N/A	N/A	Minimize the amount of radioactivity released to the environment during accident condition	Confinement HVAC
Cask Decontamination Area	Decontaminate cask (if necessary)	Minimize the amount of radioactivity released to the environment during accident condition	Confinement HVAC	Minimize the amount of radioactivity released to the environment during accident condition	Confinement HVAC
DC Loading Area	Remove DC cover Load DC Install DC cover Decontaminate DC	Prevent events that could exceed canister design basis (preclude breach) (Note 1)	Canister	Minimize the amount of radioactivity released to the environment during accident condition	Confinement HVAC
DC Welding Area	Weld DC Inspect DC welds Stress relief DC welds	Prevent events that could exceed canister design basis (preclude breach) (Note 1)	Canister	Minimize the amount of radioactivity released to the environment during accident condition	Confinement HVAC
WP Decontamination Area	Decontaminate WP (if necessary)	Prevent events that could exceed WP design basis (preclude breach)	WP	Prevent events that could exceed WP design basis (preclude breach)	WP
WP Staging Area	Store WP Transfer WP to underground transporter	Prevent events that could exceed WP design basis (preclude breach)	WP	Prevent events that could exceed WP design basis (preclude breach)	WP

Note 1: For Navy fuel and commercial canisters, credit can be taken for fuel assembly performance.

2.15 CLADDING PERFORMANCE IN DRY ENVIRONMENT

Under normal conditions (i.e., non-accident), the Waste Handling System shall maintain standard CSNF cladding temperature within the following limits:

- a) If the CSNF assembly is in an inerted environment, the cladding temperature shall be maintained less than 350 °C.
- b) If the CSNF assembly is in a non-inerted environment, the cladding accumulative time at temperature shall not exceed the following:
  - 464 °F (240 °C) for any 2-week period
  - 441 °F (227 °C) for any 1-month period
  - 347 °F (175 °C) for any 2-year period

2.16 CONTAMINATION CONTROL AND DECONTAMINATION

The WHB shall be designed to limit the spread of contamination through the use of differential pressure zones of the WHB Ventilation System; therefore, the only areas that shall be treated as contamination areas as defined in 10 CFR 835.20 are the Transfer Cells and the WP Remediation Cell. The Cask Loading Area, the DC Loading Areas, and Weld Areas shall be treated as potentially contaminated areas and all equipment that is moved out of these areas will be surveyed and decontaminated, if necessary, prior to moving. Provisions shall be provided in all other areas of the WHB to maintain the areas as non-contaminated. The decontamination shall be performed by either vacuuming the area or localized cleaning.

Provisions shall be provided to survey the top of the DC prior to welding the closure lids and decontaminate the top of the DC and overpack, if necessary, to prevent contaminating the DC Handling Area. In addition to the measures to decontaminate WPs before they are removed from the Weld Areas, it may be necessary to survey and decontaminate the WP in the WP Transporter Load Cell prior to loading the WP onto the transporter.

2.17 NON-STANDARD FUEL AND NON-FUEL BEARING COMPONENTS

The WHB shall be capable of handling and disposing of all non-standard fuel.

3. MILESTONE SCHEDULE

The following major milestones shall be used as the basis for this evaluation:

- LA December Submittal – December 2002
- CA and Construction Start – September 2005
- Emplacement Start – October 2010
- Emplacement Complete – December 2040

4. ALTERNATE RECEIPT SCENARIOS

4.1 CASE 32

This case assumes that each WHB module can process approximately 1,200 MTU of CSNF. One module will be available from 2010 through 2014, two modules will be available from 2015 through 2027, and three modules will be available from 2028 through end of emplacement. The actual commercial and DOE/naval waste streams are in Tables A-3 and A-4.

Waste Handling Building Conceptual Study
Appendix A: Waste Handling Building Conceptual Design Guidance

Table A-3. Parametric Study Case 32 - Initial 1200 MTU Module, 3 modules at completion, 2400 MTU in 2015, 3600 MTU in 2028

Fiscal Year	Cask Type	Average # of Assemblies per Cask	BWR		PWR		Total		
			Casks	Assemblies	Casks	Assemblies	Casks	Assemblies	MTU
2011	Truck	4	12	48	10	40	22	88	25.9
	SPC Rail	26	19	494	15	390	34	884	257.0
	DPC Rail	38	6	228	6	228	12	456	139.5
	Total		37	770	31	658	68	1,428	422.3
2012	Truck	4	35	140	27	108	62	248	71.7
	SPC Rail	26	78	2,028	60	1,560	138	3,588	1,037.2
	DPC Rail	38	12	456	9	342	21	798	229.4
	Total		125	2,624	96	2,010	221	4,634	1,338.3
2013	Truck	4	62	248	47	188	109	436	125.6
	SPC Rail	26	68	1,768	52	1,352	120	3,120	900.7
	DPC Rail	38	9	342	8	304	17	646	192.7
	Total		139	2,358	107	1,844	246	4,202	1,219.0
2014	Truck	4	32	128	24	96	56	224	64.4
	SPC Rail	26	73	1,898	55	1,430	128	3,328	957.7
	DPC Rail	38	11	418	9	342	20	760	222.7
	Total		116	2,444	88	1,868	204	4,312	1,244.7
2015	Truck	4	69	276	52	208	121	484	139.3
	SPC Rail	26	138	3,588	104	2,704	242	6,292	1,810.7
	DPC Rail	38	21	798	17	646	38	1,444	422.1
	Total		228	4,662	173	3,558	401	8,220	2,372.0
2020	Truck	4	20	80	16	64	36	144	42.0
	SPC Rail	26	106	2,756	80	2,080	186	4,836	1,392.1
	DPC Rail	38	38	1,444	30	1,140	68	2,584	751.2
	Total		164	4,280	126	3,284	290	7,564	2,185.3
2025	Truck	4	12	48	9	36	21	84	24.1
	SPC Rail	26	106	2,756	80	2,080	186	4,836	1,392.1
	DPC Rail	38	43	1,634	33	1,254	76	2,888	834.4
	Total		161	4,438	122	3,370	283	7,808	2,250.7
2030	Truck	4	0	0	0	0	0	0	0.0
	SPC Rail	26	144	3,744	108	2,808	252	6,552	1,883.5
	DPC Rail	38	93	3,534	71	2,698	164	6,232	1,798.5
	Total		237	7,278	179	5,506	416	12,784	3,682.0
2035	Truck	4	0	0	0	0	0	0	0.0
	SPC Rail	26	51	1,326	39	1,014	90	2,340	675.5
	DPC Rail	38	159	6,042	120	4,560	279	10,602	3,051.9
	Total		210	7,368	159	5,574	369	12,942	3,727.5
2040	Truck	4	0	0	0	0	0	0	0.0
	SPC Rail	26	19	494	15	390	34	884	257.0
	DPC Rail	38	177	6,726	133	5,054	310	11,780	3,387.8
	Total		196	7,220	148	5,444	344	12,664	3,644.8

Table A-4. Initial 1200 MTU Module, 3 modules at completion, 2600 MTU in 2015, 3600 MTU in 2028

Fiscal Year	DOE SNF		Naval SNF		DOE HLW		Immobilized Plutonium		Total	
	Casks	Cans.	Casks	Cans.	Casks	Cans.	Casks	Cans.	Casks	Cans.
2011	1	9	1	1	9	45	12	60	23	115
2012	3	27	1	1	47	235	12	60	63	323
2013	6	54	3	3	74	370	12	60	95	487
2014	8	72	6	6	92	460	12	60	118	598
2015	10	90	8	8	110	550	12	60	140	708
2020	16	144	15	15	164	820	12	60	207	1,039
2025	16	144	15	15	164	820	0	0	195	979
2030	16	144	15	15	162	810	0	0	193	969
2035	22	148	0	0	117	582	0	0	139	730
2040	22	123	0	0	141	705	0	0	163	828

Note: This case was for sensitivity evaluation only and original naval SNF receipt was used.

4.2 CASE 33

This case assumes that each WHB module can process approximately 1,200 MTU of CSNF but that rail transportation is not available until 2014. One module will be available from 2010 through 2014 but will be limited to 800 MTU of CSNF, two modules will be available from 2015 through 2027 to process 2,400 MTU of CSNF, and three modules will be available from 2028 through end of emplacement to process 3,600 MTU of CSNF. The actual commercial and DOE/naval waste streams are in Tables A-5 and A-6.

Waste Handling Building Conceptual Study
Appendix A: Waste Handling Building Conceptual Design Guidance

Table A-5. Parametric Study Case 33 - Initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTU in 2014, 3600 MTU in 2028

Fiscal Year	Cask Type	Average # of Assemblies per Cask	BWR		PWR		Total		
		PWR & BWR	Casks	Assemblies	Casks	Assemblies	Casks	Assemblies	MTU
2011	Truck	4	156	624	117	468	273	1,092	313.9
	SPC Rail	26	0	0	0	0	0	0	0.0
	DPC Rail	38	0	0	0	0	0	0	0.0
	Total		156	624	117	468	273	1,092	313.9
2012	Truck	4	304	1,216	228	912	532	2,128	611.7
	SPC Rail	26	0	0	0	0	0	0	0.0
	DPC Rail	38	0	0	0	0	0	0	0.0
	Total		304	1,216	228	912	532	2,128	611.7
2013	Truck	4	294	1,176	221	884	515	2,060	592.5
	SPC Rail	26	0	0	0	0	0	0	0.0
	DPC Rail	38	0	0	0	0	0	0	0.0
	Total		294	1,176	221	884	515	2,060	592.5
2014	Truck	4	77	308	59	236	136	544	157.1
	SPC Rail	26	124	3,224	94	2,444	218	5,668	1,633.2
	DPC Rail	38	40	1,520	30	1,140	70	2,660	764.7
	Total		241	5,052	183	3,820	424	8,872	2,555.0
2015	Truck	4	77	308	59	236	136	544	157.1
	SPC Rail	26	149	3,874	113	2,938	262	6,812	1,963.0
	DPC Rail	38	8	304	7	266	15	570	169.4
	Total		234	4,486	179	3,440	413	7,926	2,289.6
2020	Truck	4	20	80	16	64	36	144	42.0
	SPC Rail	26	108	2,808	81	2,106	189	4,914	1,412.6
	DPC Rail	38	38	1,444	29	1,102	67	2,546	734.7
	Total		166	4,332	126	3,272	292	7,604	2,189.3
2025	Truck	4	12	48	9	36	21	84	24.1
	SPC Rail	26	119	3,094	89	2,314	208	5,408	1,553.7
	DPC Rail	38	40	1,520	31	1,178	71	2,698	781.2
	Total		171	4,662	129	3,528	300	8,190	2,359.0
2030	Truck	4	0	0	0	0	0	0	0.0
	SPC Rail	26	136	3,536	103	2,678	239	6,214	1,790.2
	DPC Rail	38	97	3,686	74	2,812	171	6,498	1,875.0
	Total		233	7,222	177	5,490	410	12,712	3,665.1
2035	Truck	4	0	0	0	0	0	0	0.0
	SPC Rail	26	49	1,274	37	962	86	2,236	643.7
	DPC Rail	38	160	6,080	120	4,560	280	10,640	3,058.7
	Total		209	7,354	157	5,522	366	12,876	3,702.4
2040	Truck	4	0	0	0	0	0	0	0.0
	SPC Rail	26	16	416	13	338	29	754	220.6
	DPC Rail	38	179	6,802	134	5,092	313	11,894	3,417.8
	Total		195	7,218	147	5,430	342	12,648	3,638.3

Table A-6. Initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTU in 2014, 3600 MTU in 2028

Fiscal Year	DOE SNF		Naval SNF ⁽¹⁾		DOE HLW		Immobilized Plutonium		Total	
	Casks	Cans.	Casks	Cans.	Casks	Cans.	Casks	Cans.	Casks	Cans.
2011	9	9	1	1	45	45	60	60	115	115
2012	27	27	1	1	135	135	60	60	223	223
2013	54	54	3	3	270	270	60	60	387	387
2014	8	72	6	6	72	360	12	60	98	498
2015	10	90	8	8	110	550	12	60	140	708
2020	16	144	15	15	164	820	12	60	207	1,039
2025	16	144	15	15	164	820	0	0	195	979
2030	16	144	15	15	162	810	0	0	193	969
2035	22	148	0	0	137	682	0	0	159	830
2040	22	123	0	0	141	705	0	0	163	828

Note: (1) This case was for sensitivity evaluation only and original naval SNF receipt was used.

5. FUNDING CONSTRAINTS

Historically, Congress has limited total funding for the Yucca Mountain Project. In 1998 the M&O estimated funding projects for various scenarios (*CRWMS Modular Design/Construction and Operation Options Report*, CRWMS M&O 1998). Table A-7 summarizes the results for a modular surface facility with mostly rail receipt starting in 2010 and will be used as the basis for this evaluation.

Table A-7. Yearly Funding Projections

Year	Total Funding (Millions of Dollars)	Surface Construction (Millions of Dollars)
2004	464	61
2005	624	0
2006	898	0
2007	961	278
2008	1,102	274
2009	1,113	283
2010	769	0
2011	698	0
2012	1,243	262
2013	1,235	272
2014	1,049	0
2015	1,233	0
2016	1,437	135
2017	1,519	0
2018	1,434	0
2019	1,608	0
2020	1,623	0
Total	19,011	1,564

**White Paper:
Waste Handling Building Conceptual Study**

TDR-WHS-SE-000002 REV 00

APPENDIX B

Facility Layouts

INTENTIONALLY LEFT BLANK

Appendix B: Facility Layouts

- Figure B-1   Repository Site Plan
- Figure B-2   Waste Handling Building Non-rotating WP Design Alternative Construction Option NR-1A Plan
- Figure B-3   Waste Handling Building Non-rotating WP Design Alternative Construction Option NR-1B Plan
- Figure B-4   Waste Handling Building Non-rotating WP Design Alternative Construction Option NR-1A Sections
- Figure B-5   Waste Handling Building Non-rotating WP Design Alternative Construction Options NR-1A & NR-1B Sections
- Figure B-6   WP Shield Overpack Non-rotating WP Design Alternative
- Figure B-7   Waste Handling Building Turntable Design Alternative Construction Option T-1A Plan
- Figure B-8   Waste Handling Building Turntable Design Alternative Construction Option T-1B Plan
- Figure B-9   Waste Handling Building Turntable Design Alternative Construction Option T-1A Sections
- Figure B-10   Waste Handling Building Turntable Design Alternative Construction Options T-1A & T-1B Sections
- Figure B-11   WP Shield Overpack Turntable Design Alternative
- Figure B-12   Waste Handling Building Perpendicular Carrier Bay Alternative Plan

RADIOLOGICALLY CONTROLLED AREA FACILITIES

- 210 AIRLOCK BLDG (AB)
- 211 WASTE HANDLING BUILDING (WHB)
- 220-4C TRANSPORTER MAINTENANCE BUILDING (TMB)
- N120-1A RAIL PARKING
- N120-1B TRUCK PARKING
- N221-1 STANDBY GENERATORS
- 25-16 SUBSTATION (EXISTING)
- 5008 CHANGE HOUSE (EXISTING)
- 5010 SWITCHGEAR BUILDING (EXISTING)

BALANCE OF PLANT AREA FACILITIES

- 220-3A SECURITY STATION 1 (MAIN BOP PORTAL)
- 220-3B SECURITY STATION 2 (RCA/BOP PORTAL)
- 220-3C SECURITY STATION 3 (RCA TRUCK/RAIL PORTAL)
- 220-5A ADMINISTRATION BUILDING
- 220-5B FOOD SERVICE FACILITY
- 220-5C TRAINING AUDITORIUM
- 220-1B MEDICAL CENTER
- 220-2 FIRE STATION
- 220-22 COMPUTER CENTER
- 220-7 CENTRAL WAREHOUSE
- 220-4A CENTRAL SHOPS
- 220-4B MOTOR POOL AND FACILITY SERVICE STATION
- 220-6 MOCKUP BUILDING
- N120-1E COOLING TOWER
- N221-2 UTILITY BUILDING

SITE SERVICE FACILITIES

- N120-1C GENERAL PARKING
- N221-3 VISITOR CENTER

GRAPHIC SCALE

NOTE:
THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-1
REPOSITORY SITE PLAN

NOTE:
THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-2
WASTE HANDLING BUILDING
NON-ROTATING WP DESIGN ALTERNATIVE
CONSTRUCTION OPTION NR-1A
PLAN

NOTE:
THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-3
WASTE HANDLING BUILDING
NON-ROTATING WP DESIGN ALTERNATIVE
CONSTRUCTION OPTION NR-1B
PLAN

BUILDING SECTION - WTA / EMPTY DC PREP / TRANSFER CELL

A

BUILDING SECTION - COLD / HOT / WP LOAD / HVAC

B

NOTE:
 THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
 NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

**FIGURE B-4
 WASTE HANDLING BUILDING
 NON-ROTATING WP DESIGN ALTERNATIVE
 CONSTRUCTION OPTION NR-1A
 SECTIONS**

LONGITUDINAL BUILDING SECTION

C

LONGITUDINAL BUILDING SECTION

D

NOTE:
THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-5
WASTE HANDLING BUILDING
NON-ROTATING WP DESIGN ALTERNATIVE
CONSTRUCTION OPTIONS NR-1A & NR-1B
SECTIONS

FIGURE B-6
WP SHIELD OVERPACK
NON-ROTATING WP DESIGN
ALTERNATIVE

NOTE:
THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-7
WASTE HANDLING BUILDING
TURNTABLE DESIGN ALTERNATIVE
CONSTRUCTION OPTION T-1A
PLAN

NOTE:
 THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
 NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-8
 WASTE HANDLING BUILDING
 TURNTABLE DESIGN ALTERNATIVE
 CONSTRUCTION OPTION T-1B
 PLAN

BUILDING SECTION - WTA / EMPTY DC PREP / TRANSFER CELL

A

BUILDING SECTION - COLD / HOT / WP LOAD / HVAC

B

NOTE:
THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

**FIGURE B-9
WASTE HANDLING BUILDING
TURNTABLE DESIGN ALTERNATIVE
CONSTRUCTION OPTION T-1A
SECTIONS**

LONGITUDINAL BUILDING SECTION

C

LONGITUDINAL BUILDING SECTION

D

NOTE:
THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-10
WASTE HANDLING BUILDING
TURNTABLE DESIGN ALTERNATIVE
CONSTRUCTION OPTIONS T-1A & T-1B
SECTIONS

NOTE:
THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-11
WP SHIELD OVERPACK
TURNABLE DESIGN
ALTERNATIVE

NOTE:
 THIS SKETCH REFLECTS A CONCEPTUAL DESIGN ONLY AND IS
 NOT BASED ON THE SPACE REQUIREMENTS OF EQUIPMENT.

FIGURE B-12
 WASTE HANDLING BUILDING
 PERPENDICULAR
 CARRIER BAY ALTERNATIVE
 PLAN

**White Paper:
Waste Handling Building Conceptual Study**

TDR-WHS-SE-000002 REV 00

APPENDIX C

**Operational Flowcharts
Non-Rotating WP Design Alternative**

INTENTIONALLY LEFT BLANK

Appendix C: Operational Flowcharts

Figure C-1	WHB Waste Handling Operations Overview
Figure C-2	Carrier Preparation/Carrier Bay Process
Figure C-3	Cask Preparation Process
Figure C-4	Waste Unloading/Loading Process
Figure C-5	Waste Package (WP) Welding Process
Figure C-6	WP Transporter Loading Process
Figure C-7	Empty DC Preparation Process
Figure C-8	Fuel Staging Inventory Process

TDR-WHS-SE-000002 REV 00
WHB Ops Flow Chart-1.ppt
October 2000

WHB WASTE HANDLING OPERATIONS
Figure C-1: WHB Waste Handling Operations Overview
Non-Rotating WP Option NR-1
Page: C-1

Receipt, Inspection,
and Carrier
Washdown

OFFSITE

All waste forms received in
transportation casks on carriers

From Offsite

- Uncanistered commercial SNF
- Canistered commercial SNF (DPCs)
- Canistered DOE SNF/HLW/IP
- Canistered Navy SNF

To Cask
Preparation
Process

From Carrier
Preparation/
Carrier Bay
Process

WHB Waste Handling Operations
Figure C-3. Cask Preparation Process
Non-Rotating WP Design Alternative
Page: C-3

From Waste
Unloading/
Loading
Process

From WP
Welding
Process

OFFSITE

Receipt, Inspection,
and Carrier Washdown

Empty DC and lids on carrier

From WP
Transporter
Loading Process

Place overpack
segments and lid
in Staging Area
(near WHB)

From Waste
Unloading/Loading
Process

From Waste
Unloading/Loading
Process

To Carrier/
Preparation
Carrier Bay
Process

**White Paper:
Waste Handling Building Conceptual Study**

TDR-WHS-SE-000002 REV 00

APPENDIX D

Throughput Analysis

INTENTIONALLY LEFT BLANK

CONTENTS

	Page
Appendix D Throughput Analysis	D-1
Attachment D1 Operating Times and Sequence	D1-1
Attachment D2 WITNESS Evaluation.....	D2-1
Attachment D3 Excel Spreadsheet Evaluation	D3-1
Attachment D4 Weld Station Calculation	D4-1

INTENTIONALLY LEFT BLANK

TABLES

	Page
D1-1. Loaded Truck Cask into WHB & Remove Cask from Carrier (Common).....	D1-1
D1-2. Truck Cask Preparation Loaded Cask - Uncanistered Fuel.....	D1-2
D1-3. Transfer Area - Unload Truck Cask (PWR) Uncanistered SNF Unloaded.....	D1-3
D1-4. Truck Cask Preparation - Unloaded Transportation Cask.....	D1-4
D1-5. Unloaded Truck Transportation Cask from Carrier Bay to Exit Carrier Preparation.....	D1-5
D1-6. Loaded Rail Cask into WHB & Remove Cask from Carrier (Common).....	D1-6
D1-7. Rail Cask Preparation Loaded Cask - Uncanistered Fuel	D1-7
D1-8. Transfer Area - Unload Rail Cask Uncanistered SNF	D1-8
D1-9. Rail Cask Preparation - Unloaded Transportation Cask	D1-9
D1-10. Unloaded Rail Transportation Cask from Carrier Bay to Exit Carrier Prep	D1-10
D1-11. Loaded Dual Purpose Cask into WHB & Remove Cask from Carrier (Common) ..	D1-11
D1-12. Carrier Bay - Cask Preparation - Transportation Cask Loaded with DPC.....	D1-12
D1-13. Transfer Area - Cask Unload - DPC Unloading to a 44 BWR DC.....	D1-13
D1-14. Transfer Area - Empty DPC Transfer from Cask to DPC Overpack.....	D1-14
D1-15. Cask Preparation with Empty DPC Loaded in Cask.....	D1-15
D1-16. Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB (DPC)	D1-16
D1-17. Carrier Preparation Area - Move Empty Carrier into WHB (DPC)	D1-17
D1-18. Carrier Bay - Move Overpack Loaded with DPC out from the WHB.....	D1-18
D1-19. DOE SNF & HLW Loaded Cask Into WHB & Remove Cask From Carrier (Common).....	D1-19
D1-20. DOE SNF & HLW Cask Preparation Loaded Cask - Uncanistered Fuel	D1-20
D1-21. Transfer Area - Unload Uncanistered SNF	D1-21
D1-22. DOE SNF & HLW Cask Preparation - Unloaded Transportation Cask	D1-22
D1-23. DOE SNF & HLW Unloaded Transportation Cask from Carrier Bay to Exit.....	D1-23
D1-24. Loaded Cask into WHB & Remove Cask From Carrier (Common) Canistered Navy Fuel.....	D1-24
D1-25. Cask Preparation Loaded Cask - Canistered Navy Fuel	D1-25
D1-26. Transfer Area - Navy Canister Unloaded into a DC.....	D1-26
D1-27. Cask Preparation - Unloaded Transportation Cask (Canistered Navy Fuel).....	D1-27
D1-28. Unloaded Transportation Cask from Carrier Bay to Exit Carrier Preparation (Canistered Navy Fuel).....	D1-28
D2-1. WITNESS Results: Number of Modules Required	D2-2
D4-1. Weld Station Throughput Requirements.....	D4-1

INTENTIONALLY LEFT BLANK

Appendix D

Throughput Analysis

Using the layout drawings of the WHB facility (Appendix B), operational sequences were developed (Appendix C). These operational sequences were based on SNF handling experience and information provided by the individuals developing the facility layout. Once the operational sequence was developed, operational times for the completion of each activity were determined (Appendix D Attachment D1). The operational sequence and processing durations were developed for each type of SNF transportation system to be received at the WHB. The throughput was analyzed using two different and independent methods, the WITNESS program and an Excel spreadsheet.

Attachment D2 presents a description and the results of the analysis using the WITNESS program, and Attachment D3 presents the description and results for the Excel spreadsheet analysis. Supporting tables and charts are found in each attachment.

Section 2.8 of the main text of this document further describes each approach, and summarizes the results and a comparison of the two approaches.

Attachment D4 presents the annual WP throughput requirements and the calculated number of weld stations.

Attachment D1

Operating Times and Sequence

Table D1-1. Loaded Truck Cask into WHB & Remove Cask from Carrier (Common)

Loaded Truck Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Loaded Cask Into WHB & Remove Cask From Carrier (Common)			
Initial condition: carrier loaded with a transportation cask positioned outside of the Carrier Preparation Area.			
Cask Receipt and Preparation in Carrier Preparation Area			
Open Carrier Preparation Outer Door	10		
Move Cask/Carrier into Carrier Preparation.	15		
Close Carrier Preparation Outer Door	10		
Remove personnel barrier	36		
Health Physics (HP) survey	24		
Problem – Decontamination if required			60
Remove impact limiters	90		
HP impact limiters/TC interface	12		
Problem – Decontamination impact limiters/TC interface if required			60
Open Carrier Preparation Inner door	10		
Move Cask/Carrier into Carrier Bay	10		
Detach on-site mover and withdraw it from carrier bay	15		
Close carrier Preparation Inner door	10		
Remove tiedowns	48		
Engage cask yoke with crane	10		
Release trunnions or install trunnions	30		
Move crane in position over cask and rig yoke to cask	20		
Release lower trunnions and raise (upend) cask	30		
TIME SUBTOTAL	380		
TIME TOTAL (hrs.)		6.33	

Table D1-2. Truck Cask Preparation Loaded Cask - Uncanistered Fuel

Loaded Truck Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Cask Preparation Loaded Cask - Uncanistered Fuel			
Initial condition: is loaded cask is suspended from crane in Carrier Bay.			
Parallel activities for additional process lines not listed			
Stage cart (placement of spacers and cask tie-downs)	30		
Move cask from over Carrier to Transfer Cart	15		
Place Rail Cask on Cart, Secure Cask, and release Yoke	15		
Open the Cask Prep outer door	10		
Move Cask Cart into the Cask Preparation	10		
Close the Cask Preparation outer door	10		
Raise Cask into Preparation Station	10		
Sample/analyze cask atmosphere	85		
Detension and remove Cask lid bolts using Detensioner.	100		
Install Cask lid lift fixture	45		
Install Cask unloading port adaptor	20		
Install contamination control on Cask (Wrap cask in plastic?)	30		
Lower Cask from Preparation Station	10		
Open the Cask Unload area door	10		
Move Cart under cask unloading port	15		
Raise Cask to unloading port	15		
Close the Cask Unload area door	10		
TIME SUBTOTAL	440		
TIME TOTAL (hrs.)		7.33	

Table D1-3. Transfer Area - Unload Truck Cask (PWR) Uncanistered SNF Unloaded

Loaded Truck Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Transfer Area - Unload Truck Cask (PWR) Uncanistered SNF Unloaded			
Initial condition: is loaded cask (4 SNF Assemblies) mated to unload port.			
Remove Disposal Canister port cover	15		
Remove Disposal Canister temporary shield cover	20		
Remove Disposal Canister inner structural lid	20		
Remove Transportation cask unload port to hot cell cover	15		
Remove Transportation Cask lid (or radiation shield)	10		
Transfer SNF from open cask to Disposal Canister (4 @ 20 minutes each)	80		
Install Transportation Cask lid (or radiation shield)	10		
Install Transportation cask unload port to hot cell cover	15		
Install Disposal Canister inner structural lid	20		
Install Disposal Canister temporary shield cover	20		
Install Disposal Canister port cover	15		
TIME SUBTOTAL	240		
TIME TOTAL (hrs.)		4.00	

Table D1-4. Truck Cask Preparation - Unloaded Transportation Cask

Loaded Truck Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Cask Preparation - Unloaded Transportation Cask			
Initial condition: unloaded Transportation cask is at closed Transfer Area port.			
Open the Cask Unload area door	10		
Lower Cask from Unloading Port	10		
General HP survey	10		
Problem - Decontamination if required			60
Move Cart from under cask unloading port to Cask Preparation Area	15		
Close the Cask Unload area door	10		
Remove Cask unload port adaptor	20		
Raise Cask into Preparation station	10		
Remove contamination control (plastic) from Cask	20		
Install and tension Cask lid bolts using tensioner	100		
HP survey of Cask	30		
Problem - Decontamination if required			60
Lower cask from Preparation Station	10		
Open door from the Cask Preparation to Carrier Bay	10		
Move Cart to Carrier Bay	10		
Engage cask with crane and yoke	10		
Remove cart/cask tie-downs	15		
Transfer cask from cart to carrier, lower cask to horizontal position, disengage yoke, and secure cask to carrier	90		
TIME SUBTOTAL	380		
TIME TOTAL (hrs.)		6.33	

Table D1-5. Unloaded Truck Transportation Cask from Carrier Bay to Exit Carrier Preparation

Loaded Truck Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Preparation			
Initial condition: unloaded Transportation cask is on Carrier in Carrier Bay.			
Open carrier Preparation Inner door	10		
Move the prime mover into carrier Preparation and engage the carrier	15		
Move cask/carrier into carrier Preparation.	15		
Close carrier Preparation inner door	10		
HP survey	24		
Problem - Decontamination if required			60
Install impact limiters	90		
Install personnel barrier	36		
Open Carrier Preparation Outer Door	10		
Attach on-site mover and move cask/carrier out of carrier preparation.	15		
TIME SUBTOTAL	225		
TIME TOTAL (hrs.)		3.75	

Table D1-6. Loaded Rail Cask into WHB & Remove Cask from Carrier (Common)

Loaded Rail Cask at WHB DESCRIPTION OF OPERATIONAL STEP	WHB TIME (MIN.)	TOTAL TIME (HRS.)	Potential Time Additions
Loaded Cask Into WHB & Remove Cask From Carrier (Common)			
Initial condition: carrier loaded with a transportation cask positioned outside of the Carrier Preparation Area.			
Cask Receipt and Preparation in Carrier Prep Area			
Open Carrier Preparation Outer Door	10		
Move cask/carrier into carrier Preparation	15		
Close carrier Preparation Outer door	10		
Remove personnel barrier	36		
HP survey	24		
Problem – Decontamination if required			60
Remove impact limiters	90		
HP impact limiters/TC interface	12		
Problem – Decontamination impact limiters/TC interface if required			60
Open carrier Preparation Inner door	10		
Move cask/carrier into carrier bay	10		
Detach on-site mover and withdraw it from carrier bay	15		
Close carrier Preparation Inner door	10		
Remove tiedowns	48		
Engage cask yoke with crane	10		
Release trunnions or install trunnions	30		
Move crane in position over cask and rig yoke to cask	20		
Release lower trunnions and raise (upend) cask	30		
TIME SUBTOTAL	380		
TIME TOTAL (hrs.)		6.33	

Table D1-7. Rail Cask Preparation Loaded Cask - Uncanistered Fuel

Loaded Rail Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Cask Preparation Loaded Cask - Uncanistered Fuel			
Initial condition: loaded cask is suspended from crane in Carrier Bay			
Parallel activities for additional process lines not listed.			
Stage cart (placement of spacers and cask tie-downs)	30		
Move cask from over Carrier to Transfer Cart	15		
Place Rail Cask on Cart, Secure Cask, and release Yoke	15		
Open the Cask Preparation outer door	10		
Move Cask Cart into the Cask Preparation	10		
Close the Cask Preparation outer door	10		
Raise Cask into Preparation Station	10		
Sample/analyze cask atmosphere	85		
Detension and remove Cask lid bolts using Detensioner	100		
Install Cask lid lift fixture	45		
Install Cask unloading port adaptor	20		
Install contamination control on Cask (Wrap cask in plastic?)	30		
Lower Cask from Preparation Station	10		
Open the Cask Unload area door	10		
Move Cart under cask unloading port	15		
Raise Cask to unloading port	15		
Close the Cask Unload area door	10		
TIME SUBTOTAL	440		
TIME TOTAL (hrs.)		7.33	

Table D1-8. Transfer Area - Unload Rail Cask Uncanistered SNF

Loaded Rail Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Transfer Area - Unload Rail Cask Uncanistered SNF			
Initial condition: loaded cask (24 SNF Assemblies) mated to unload port.			
Remove Disposal Canister port cover	15		
Remove Disposal Canister temporary shield cover	20		
Remove Disposal Canister inner structural lid	20		
Remove Transportation cask unload port cover	15		
Remove Transportation Cask lid (or radiation shield)	10		
Transfer SNF from open cask to Disposal Canister (24 @ 20 minutes each)	480		
Install Transportation Cask lid (or radiation shield)	10		
Install Transportation cask unload port to hot cell cover	15		
Install Disposal Canister inner structural lid	20		
Install Disposal Canister temporary shield cover	20		
Install Disposal Canister port cover	15		
TIME SUBTOTAL	640		
TIME TOTAL (hrs.)		10.67	

Table D1-9. Rail Cask Preparation - Unloaded Transportation Cask

Loaded Rail Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Cask Preparation - Unloaded Transportation Cask			
Initial condition: unloaded Transportation cask is at closed Transfer Area port.			
Open the Cask Unload area door	10		
Lower Cask from Unloading Port	10		
General HP survey	10		
Problem - Decontamination if required			60
Move Cart from under cask unloading port to Cask Preparation Area	15		
Close the Cask Unload area door	10		
Remove Cask unload port adaptor	20		
Raise Cask into Preparation station	10		
Remove contamination control (plastic) from Cask	20		
Install and tension Cask lid bolts using tensioner	100		
HP survey of Cask	30		
Problem - Decontamination if required			60
Lower cask from Preparation Station	10		
Open door from the Cask Preparation to Carrier Bay	10		
Move Cart to Carrier Bay	10		
Engage cask with crane and yoke	10		
Remove cart/cask tie-downs	15		
Transfer cask from cart to carrier, lower cask to horizontal position, disengage yoke, and secure cask to carrier	90		
TIME SUBTOTAL	380		
TIME TOTAL (hrs.)		6.33	

Table D1-10. Unloaded Rail Transportation Cask from Carrier Bay to Exit Carrier Prep

Loaded Rail Cask at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Problem time estimates
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Preparation			
Initial condition: unloaded Transportation cask is on Carrier in Carrier Bay			
Open carrier Preparation Inner door	10		
Move the prime mover into carrier preparation and engage the carrier	15		
Move cask/carrier into carrier preparation	15		
Close carrier preparation inner door	10		
HP survey	24		
Problem – Decontamination if required			60
Install impact limiters	90		
Install personnel barrier	36		
Open Carrier Preparation Outer Door	10		
Attach on-site mover and move cask/carrier out of carrier preparation	15		
TIME SUBTOTAL	225		
TIME TOTAL (hrs.)		3.75	

Table D1-11. Loaded Dual Purpose Cask into WHB & Remove Cask from Carrier (Common)

DESCRIPTION OF OPERATIONAL STEPS FOR UNLOADING A DPC	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Loaded Cask Into WHB & Remove Cask From Carrier (Common)			
Pre-existing condition: a carrier loaded with a transportation cask positioned outside of the Carrier Preparation Area.			
Cask Receipt and Preparation in Carrier Preparation Area			
Open Carrier Preparation Outer Door	10		
Move cask/carrier into carrier preparation	15		
Close carrier prep. Outer door	10		
Remove personnel barrier	36		
HP survey	24		
Problem – Decontamination if required (60)			60
Remove impact limiters	90		
HP impact limiters/TC interface	12		
Problem – Decontamination impact limiters/TC interface if required (60)			60
Open carrier Preparation Inner door	10		
Move cask/carrier into carrier bay	10		
Detach on-site mover and withdraw it from carrier bay	15		
Close carrier preparation Inner door	10		
Remove tiedowns (Carrier Bay)	48		
Engage cask yoke with crane	10		
Release trunnions or install trunnions	30		
Move crane in position over cask and rig yoke to cask	20		
Release lower trunnions and upend cask	30		
SUBTOTAL (mins.)	380		
TOTAL (hrs.)		6.3	

Table D1-12. Carrier Bay - Cask Preparation - Transportation Cask Loaded with DPC

DESCRIPTION OF OPERATIONAL STEPS FOR UNLOADING A DPC	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Carrier Bay - Cask Preparation - Transportation Cask Loaded with DPC			
Pre-existing condition is: in the Carrier Bay Area, the Transportation Cask is positioned and supported by the crane in a vertical position above the carrier. The on-site prime mover is positioned in the Carrier Preparation Area. Parallel activities for additional process lines are not listed.			
Stage cart (placement of spacers and cask tie-downs)	30		
Move cask from over Carrier to Transfer Cart	15		
Place Rail Cask on Cart, Secure Cask, and release Yoke	15		
Open Cask Preparation outer door	10		
Move cart/cask to Cask Preparation Area	10		
Install cask unloading port adapter	20		
Raise cask into Preparation Station Port	10		
Detention and remove cask lid bolts using detentoner	100		
Install cask lid lifting fixture, remove cask lid, and store lid	45		
Install Contamination Control (Wrap cask in plastic?)	30		
Install DPC outer lid weld cutting machine, cut weld, and remove lid	90		
Sample/analyze DPC atmosphere	85		
Install DPC shield plug weld cutting machine, cut weld, and install shield plug lifting fixture	90		
Collect and remove weld chips	30		
Lower cart/cask	10		
Open Cask Unload Area door	10		
Move cart/cask under the Cask Unloading Port	15		
Raise cart/cask to engage unloading port (Transfer Area - Cask Unload)	15		
Close Cask Unload Area door	10		
SUBTOTAL (mins.)	640		
TOTAL (hrs.)		10.7	

Table D1-13. Transfer Area - Cask Unload - DPC Unloading to a 44 BWR DC

DESCRIPTION OF OPERATIONAL STEPS FOR UNLOADING A DPC	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Transfer Area - Cask Unload - DPC Unloading to a 44 BWR DC			
Remove cover from DC loading port	10		
Remove DC temporary shield cover	20		
Remove DC inner structural lid	20		
Remove cover from DPC unloading port	10		
Remove DPC shield plug	30		
Transfer SNFs from open DPC to DC (38SNFs @ 20 min. each)	760		
Replace cover in DC loading port	10		
Replace cover in DPC unloading port	10		
SUBTOTAL (mins.)	870		
TOTAL (hrs.)		14.5	

Table D1-14. Transfer Area - Empty DPC Transfer from Cask to DPC Overpack

DESCRIPTION OF OPERATIONAL STEPS FOR UNLOADING A DPC	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Transfer Area - Empty DPC Transfer from Cask to DPC Overpack			
Pre-existing conditions: under the Transfer Cell DPC unloading port (floor plug in), an empty DPC is placed inside a cask. An empty DPC overpack is under the Cask Unloading Port (floor plug in). These operations take place in the Transfer Cell.			
Remove Cask Unloading Port cover	10		
Remove DPC Unloading Port cover	10		
Attach sling and transfer empty DPC into overpack	30		
Replace DPC shield plug into DPC	30		
Replace Cask Unloading Port cover	10		
Replace DPC Unloading Port cover	10		
SUBTOTAL (mins.)	100		
TOTAL (hrs.)		1.7	

Table D1-15. Cask Preparation with Empty DPC Loaded in Cask

DESCRIPTION OF OPERATIONAL STEPS FOR UNLOADING A DPC	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Cask Preparation with Empty DPC Loaded in Cask			
Pre-existing condition: the empty cask has no lid installed in it.			
Replace Cask Unload Port lid	10		
Lower cask with empty DPC inside	10		
Open cask Transfer Corridor door	10		
Move cart/cask to Cask Preparation Station	10		
Close cask Transfer Corridor door	10		
Raise cask into Preparation Station port (Cask Preparation Area)	10		
Remove cask adapter (Carrier Bay)	10		
Replace cask lid	20		
Install and tension bolts using the tentioner	100		
Survey cask	30		
Open Cask Preparation Outer door	10		
Lower cask and transfer into Carrier Bay	15		
Close Cask Preparation Outer door	10		
Engage cask with crane and yoke	10		
Remove cart/cask tie-downs	15		
Transfer cask from cart to carrier, lower cask to horizontal position, disengage yoke, and secure cask to carrier	90		
SUBTOTAL (mins.)	370		
TOTAL (hrs.)		6.2	

Table D1-16. Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB (DPC)

DESCRIPTION OF OPERATIONAL STEPS FOR UNLOADING A DPC	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB			
Pre-existing conditions: a carrier is inside the carrier bay with the empty cask secured on it. The on-site mover is in the Carrier Preparation Area.			
Open Carrier Preparation Inner door	10		
Move on-site mover into Carrier Bay, attach to carrier, move carrier to Carrier Preparation.	30		
Close Carrier Preparation Inner door	10		
Prepare cask and carrier for road transportation (Carrier Preparation)	120		
Open Carrier Preparation Outer door	10		
Move Carrier out of Carrier Preparation Area	20		
Close Carrier Preparation outer door	10		
SUBTOTAL (mins.)	210		
TOTAL (hrs.)		3.5	

Table D1-17. Carrier Preparation Area - Move Empty Carrier into WHB (DPC)

DESCRIPTION OF OPERATIONAL STEPS FOR UNLOADING A DPC	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Carrier Preparation Area - Move Empty Carrier into WHB			
Pre-existing conditions: an empty carrier is located outside of the WHB.			
Attach on-site mover to empty carrier	0		
Open Carrier Preparation Outer door	10		
Move Onsite Mover with carrier into Carrier Preparation Area	15		
Close Carrier Preparation Outer door	10		
Open Carrier Preparation Inner door	10		
Move carrier into Carrier Bay Area	10		
Disconnect On-Site Mover from Carrier	15		
Move On-site Mover into Carrier Preparation Area	10		
Close Carrier Preparation Inner door	10		
SUBTOTAL (mins.)	90		
TOTAL (hrs.)		1.5	

Table D1-18. Carrier Bay - Move Overpack Loaded with DPC out from the WHB

DESCRIPTION OF OPERATIONAL STEPS FOR UNLOADING A DPC	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Carrier Bay - Move Overpack Loaded with DPC out from the WHB			
Pre-existing conditions: in the Carrier Bay, a loaded DPC overpack is secured on top of a carrier. On-site mover is in Carrier Preparation.			
Open Carrier Preparation Inner door	10		
Move on-site mover inside Carrier Bay and attach to carrier, and move carrier into Carrier Preparation	30		
Close Carrier Preparation Inner door	10		
Prepare carrier for road transportation (Carrier Preparation)	20		
Open Carrier Preparation Outer door	10		
Move carrier out from Carrier Preparation	20		
Close Carrier Preparation Outer door	10		
SUBTOTAL (mins.)	110		
TOTAL (hrs.)		1.8	

Table D1-19. DOE SNF & HLW Loaded Cask Into WHB & Remove Cask From Carrier (Common)

Loaded DOE SNF & HLW at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Potential Time Additions
Loaded Cask Into WHB & Remove Cask From Carrier (Common)			
Initial condition: carrier loaded with a transportation cask positioned outside of the Carrier Preparation Area.			
Cask Receipt and Preparation in Carrier Preparation Area			
Open Carrier Preparation Outer Door	10		
Move cask/carrier into carrier preparation	15		
Close carrier preparation outer door	10		
Remove personnel barrier	36		
HP survey	24		
Problem - Decontamination if required			60
Remove impact limiters	90		
HP impact limiters/TC interface	12		
Problem - Decontamination impact limiters/TC interface if required			60
Open carrier Preparation Inner door	10		
Move cask/carrier into carrier bay	10		
Detach on-site mover and withdraw it from carrier bay	15		
Close carrier preparation inner door	10		
Remove tiedowns	48		
Engage cask yoke with crane	10		
Release trunnions or install trunnions	30		
Move crane in position over cask and rig yoke to cask	20		
Release lower trunnions and raise (upend) cask	30		
TIME SUBTOTAL	380		
TIME TOTAL (hrs.)		6.33	

Table D1-20. DOE SNF & HLW Cask Preparation Loaded Cask - Uncanistered Fuel

Loaded DOE SNF & HLW at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Problem time estimates
Cask Preparation Loaded Cask - Uncanistered Fuel			
Initial condition: loaded cask is suspended from crane in Carrier Bay. Parallel activities for additional process lines not listed.			
Stage cart (placement of spacers and cask tie-downs)	30		
Move cask from over Carrier to Transfer Cart	15		
Place Rail Cask on Cart, Secure Cask, and release Yoke	15		
Open the Cask Preparation outer door	10		
Move Cask Cart into the Cask Preparation	10		
Close the Cask Preparation outer door	10		
Raise Cask into Preparation Station	10		
Sample/analyze cask atmosphere	85		
Detension and remove Cask lid bolts using Detensioner	100		
Install Cask lid lift fixture	45		
Install Cask unloading port adaptor	20		
Install contamination control on Cask (Wrap cask in plastic?)	30		
Lower Cask from Preparation Station	10		
Open the Cask Unload area door	10		
Move Cart under cask unloading port	15		
Raise Cask to unloading port	15		
Close the Cask Unload area door	10		
TIME SUBTOTAL	440		
TIME TOTAL (hrs.)		7.33	

Table D1-21. Transfer Area - Unload Uncanistered SNF

Loaded DOE SNF & HLW at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Problem time estimates
Transfer Area -- Unload Uncanistered SNF			
Initial condition: loaded cask (5 SNF Assemblies) mated to unload port.			
Remove Disposal Container port cover	15		
Remove Disposal Container temporary shield cover	20		
Remove Disposal Container inner structural lid	20		
Remove Transportation cask unload port cover	15		
Remove Transportation Cask lid (or radiation shield)	10		
Transfer SNF from open cask to Disposal Container (5 @ 20 minutes each)	100		
Install Transportation Cask lid (or radiation shield)	10		
Install Transportation cask unload port to hot cell cover	15		
Install Disposal Container inner structural lid	20		
Install Disposal Container temporary shield cover	20		
Install Disposal Container port cover	15		
TIME SUBTOTAL	260		
TIME TOTAL (hrs.)		4.33	

Table D1-22. DOE SNF & HLW Cask Preparation - Unloaded Transportation Cask

Loaded DOE SNF & HLW at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Problem time estimates
Cask Preparation - Unloaded Transportation Cask			
Initial condition: unloaded Transportation cask is at closed Transfer Area port.			
Open the Cask Unload area door	10		
Lower Cask from Unloading Port	10		
General HP survey	10		
Problem - Decontamination if required			60
Move Cart from under cask unloading port to Cask Preparation Area	15		
Close the Cask Unload area door	10		
Remove Cask unload port adaptor	20		
Raise Cask into Preparation station	10		
Remove contamination control (plastic) from Cask	20		
Install and tension Cask lid bolts using tensioner	100		
HP survey of Cask	30		
Problem - Decontamination if required			60
Lower cask from Preparation Station	10		
Open door from the Cask Preparation to Carrier Bay	10		
Move Cart to Carrier Bay	10		
Engage cask with crane and yoke	10		
Remove cart/cask tie-downs	15		
Transfer cask from cart to carrier, lower cask to horizontal position, disengage yoke, and secure cask to carrier	90		
TIME SUBTOTAL	380		
TIME TOTAL (hrs.)		6.33	

Table D1-23. DOE SNF & HLW Unloaded Transportation Cask from Carrier Bay to Exit

Loaded DOE SNF & HLW at WHB DESCRIPTION OF OPERATIONAL STEP	TIME (MIN.) WHB	TOTAL TIME (HRS.)	Problem time estimates
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Preparation			
Initial condition: unloaded Transportation cask is on Carrier in Carrier Bay.			
Open carrier Preparation Inner door	10		
Move the prime mover into carrier preparation and engage the carrier	15		
Move cask/carrier into carrier preparation	15		
Close carrier preparation Inner door	10		
HP survey	24		
Problem – Decontamination if required			60
Install impact limiters	90		
Install personnel barrier	36		
Open Carrier Preparation Outer Door	10		
Attach on-site mover and move cask/carrier out of carrier preparation	15		
TIME SUBTOTAL	225		
TIME TOTAL (hrs.)		3.75	

Table D1-24. Loaded Cask into WHB & Remove Cask From Carrier (Common) Canistered Navy Fuel

CASK LOADED WITH 1 NAVY CANISTER DESCRIPTION OF OPERATIONAL STEP	WHB TIME (MIN.)	TOTAL TIME (HRS)	Potential Time Additions
Loaded Cask Into WHB & Remove Cask From Carrier (Common)			
Initial condition: carrier loaded with a transportation cask positioned outside of the Carrier Preparation Area.			
Cask Receipt and Preparation in Carrier Preparation Area			
Open Carrier Preparation Outer Door	10		
Move cask/carrier into carrier preparation	15		
Close carrier preparation outer door	10		
Remove personnel barrier	36		
HP survey	24		
Problem – Decontamination if required			60
Remove impact limiters	90		
HP impact limiters/TC interface	12		
Problem – Decontamination impact limiters/TC interface if required			60
Open carrier Prep. Inner door	10		
Move cask/carrier into carrier bay	10		
Detach on-site mover and withdraw it from carrier bay	15		
Close carrier prep. inner door	10		
Remove tiedowns	48		
Engage cask yoke with crane	10		
Release trunnions or install trunnions	30		
Move crane in position over cask and rig yoke to cask	20		
Release lower trunnions and raise (upend) cask	30		
TIME SUBTOTAL	380		
TIME TOTAL (Hrs.)		6.33	

Table D1-25. Cask Preparation Loaded Cask - Canistered Navy Fuel

CASK LOADED WITH 1 NAVY CANISTER DESCRIPTION OF OPERATIONAL STEP	WHB TIME (MIN.)	TOTAL TIME (HRS.)	Potential Time Additions
Cask Preparation Loaded Cask - Canistered Navy Fuel			
Initial condition: in the Cask Preparation Area with the cask positioned and supported by the crane in a vertical position on the carrier. Parallel activities for additional process lines not listed.			
Stage cart (placement of spacers and cask tie-downs)	30		
Move cask from over Carrier to Transfer Cart	15		
Place Rail Cask on Cart, Secure Cask, and release Yoke	15		
Open the Cask Preparation outer door	10		
Move Cask Cart into the Cask Preparation	10		
Close the Cask Preparation outer door	10		
Raise Cask into Preparation Station Port	10		
Sample / analyze cask atmosphere	85		
Detension and remove Cask lid bolts using Detensioner.	100		
Install Cask lid lift fixture	45		
Install Cask unloading port adapter	20		
Install contamination control on Cask (Wrap cask in plastic?)	30		
Lower Cask from Preparation Station	10		
Open the Cask Unload area door	10		
Move Cart into cask unloading area	15		
Raise Cask to unloading port	15		
Close the Cask Unload area door	10		
TIME SUBTOTAL	440		
TIME TOTAL (hrs.)		7.33	

Table D1-26. Transfer Area - Navy Canister Unloaded into a DC

CASK LOADED WITH 1 NAVY CANISTER DESCRIPTION OF OPERATIONAL STEP	WHB TIME (MIN.)	TOTAL TIME (HRS.)	Potential Time Additions
Transfer Area - Navy Canister Unloaded into a DC			
Initial condition: is loaded cask w/(1 Navy Canister) placed under the cask unloading port (port cover in place). An empty DC is placed under one of the two DC loading ports (port cover in place).			
Remove Disposal Container port cover	15		
Remove Disposal Container temporary shield cover	20		
Remove Disposal Container inner structural lid	20		
Remove cask unload port cover	15		
Remove Transportation Cask lid (or radiation shield)	10		
Install canister lifting fixture	60		
Transfer Navy Canister from Transportation Cask to Disposal Container	15		
Replace Lid on Transportation cask	10		
Replace Cover in Cask Unloading Port	10		
Remove Lifting Fixture from Navy Canister	60		
Replace Inner Structural Lid in Disposal Container	20		
Replace Temporary Shield Cove in Disposal Container	20		
Install Disposal Container port cover	10		
TIME SUBTOTAL	285		
TIME TOTAL (hrs.)		4.75	

Table D1-27. Cask Preparation - Unloaded Transportation Cask (Canistered Navy Fuel)

CASK LOADED WITH 1 NAVY CANISTER DESCRIPTION OF OPERATIONAL STEP	WHB TIME (MIN.)	TOTAL TIME (HRS.)	Potential Time Additions
Cask Preparation – Unloaded Transportation Cask			
Initial condition: unloaded Transportation cask is at closed Transfer Area port.			
Open the Cask Unload area door	10		
Lower Cask from Unloading Port	10		
General HP survey	10		
Problem - Decontamination if required			60
Move Cart from under cask unloading port to Cask Preparation Area	15		
Close the Cask Unload area door	10		
Raise Cask into Preparation station	10		
Remove Cask unload port adaptor	20		
Remove contamination control (plastic) from Cask	20		
Install and tension Cask lid bolts using tensioner	100		
HP survey of Cask	30		
Problem - Decontamination if required			60
Lower cask from Preparation Station	10		
Open door from the Cask Preparation to Carrier Bay	10		
Move Cart to Carrier Bay	10		
Engage cask with crane and yoke (Carrier Bay)	10		
Remove cart/cask tie-downs	15		
Transfer cask from cart to carrier, lower cask to horizontal position, disengage yoke, and secure cask to carrier	90		
TIME SUBTOTAL	380		
TIME TOTAL (hrs.)		6.33	

Table D1-28. Unloaded Transportation Cask from Carrier Bay to Exit Carrier Preparation (Canistered Navy Fuel)

CASK LOADED WITH 1 NAVY CANISTER DESCRIPTION OF OPERATIONAL STEP	WHB TIME (MIN.)	TOTAL TIME (HRS.)	Potential Time Additions
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Preparation			
Initial condition: unloaded Transportation cask is on Carrier in Carrier Bay.			
Open carrier Preparation Inner door	10		
Move the on-site mover into carrier preparation and engage the carrier	15		
Move cask/carrier into carrier preparation	15		
Close carrier preparation inner door	10		
HP survey (Carrier Preparation Area)	24		
Problem - Decontamination if required			60
Install impact limiters	90		
Install personnel barrier	36		
Open Carrier Preparation Outer Door	10		
Move cask/carrier out of carrier preparation	15		
TIME SUBTOTAL	225		
TIME TOTAL (hrs.)		3.75	

Attachment D2

WITNESS Evaluation

Methodology

Modeling the Surface Facility design using WITNESS software involved first identifying each operational step associated with the design. These are the operational steps for processing each incoming cask, and are identified in Appendix D, Attachment D1. Using simulated machines, transporters, cranes, doors, and all other equipment and time-dependent functions of the Surface Facility throughput, the modeler created a representation of a working WHB and its functions. After inputting the expected time for each operational function, the WITNESS model simulated the total time necessary for processing any number of casks arriving.

Using the waste streams identified in Appendix A as inputs to the model, WITNESS outputs the total time needed to process the incoming waste for a given year. After converting this output into hours (from minutes), an efficiency factor of 73% was added. This number represents the total number of hours needed, with a 73% efficiency factor, to process the incoming waste stream. In order to determine the number of modules needed to process this waste stream, this number was then divided by 6000 hours (the total available working hours for one module in one year, assuming a 5-day, 3 shifts/day, 50-week work schedule). An example of this calculation, starting with the WITNESS output, is presented below.

Input Year:	2014
Input Case:	Case 1
WITNESS Output (minutes):	= 639, 076
WITNESS Output (hours):	= $639, 076 \div 60 = 10, 651$
Output with 73% efficiency:	= $10, 651 \div .73 = 14, 591$
Number of Modules needed in given year:	= $14, 591 \text{ hours} \div 6000 = 2.43$

Results

The results of this analysis are presented in Table D2-1.

Table D2-1. WITNESS Results: Number of Modules Required

Input Case	Minutes	Hours	73% Efficiency	# of Modules Needed (Based on 6000 Hours per Year Work Schedule)
Case 1				
2010 Case 1	103446	1724.1	2361.8	0.39
2011 Case 1	148366	2472.8	3387.4	0.56
2012 Case 1	278671	4644.5	6362.4	1.06
2013 Case 1	381006	6350.1	8698.8	1.45
2014 Case 1	639076	10651.3	14590.8	2.43
2015 Case 1	687736	11462.3	15701.7	2.62
2023 Case 1	614676	10244.6	14033.7	2.34
2034 Case 1	610111	10168.5	13929.5	2.32
Case 2				
2010 Case 2	98281	1638.0	2243.9	0.37
2011 Case 2	145236	2420.6	3315.9	0.55
2012 Case 2	264431	4407.2	6037.2	1.01
2013 Case 2	395506	6591.8	9029.8	1.50
2014 Case 2	603831	10063.9	13786.1	2.30
2015 Case 2	652336	10872.3	14893.5	2.48
2023 Case 2	574996	9583.3	13127.8	2.19
2034 Case 2	583956	9732.6	13332.3	2.22
Case 3				
2010 Case 3	91046	1517.4	2078.7	0.35
2011 Case 3	128851	2147.5	2941.8	0.49
2012 Case 3	239381	3989.7	5465.3	0.91
2013 Case 3	349371	5822.9	7976.5	1.33
2014 Case 3	530391	8839.9	12109.4	2.02
2015 Case 3	579496	9658.3	13230.5	2.21
2023 Case 3	614206	10236.8	14023.0	2.34
2034 Case 3	670471	11174.5	15307.6	2.55
Case 32				
2011 Case 32	78871	1314.5	1800.7	0.30
2012 Case 32	232071	3867.9	5298.4	0.88
2013 Case 32	269701	4495.0	6157.6	1.03
2014 Case 32	258736	4312.3	5907.2	0.98
2015 Case 32	439151	7319.2	10026.3	1.67
2020 Case 32	425481	7091.4	9714.2	1.62
2025 Case 32	417781	6963.0	9538.4	1.59
2030 Case 32	578676	9644.6	13211.8	2.20
2035 Case 32	558891	9314.9	12760.1	2.13
2040 Case 32	494556	8242.6	11291.2	1.88

Table D2-1. WITNESS Results: Number of Modules Required, continued

Case 33

2011 Case 33	284171	4736.2	6487.9	1.08
2012 Case 33	552061	9201.0	12604.1	2.10
2013 Case 33	659391	10989.9	15054.6	2.51
2014 Case 33	447111	7451.9	10208.0	1.70
2015 Case 33	431196	7186.6	9844.7	1.64
2020 Case 33	425656	7094.3	9718.2	1.62
2025 Case 33	427946	7132.4	9770.5	1.63
2030 Case 33	578341	9639.0	13204.1	2.20
2035 Case 33	573946	9565.8	13103.8	2.18
2040 Case 33	569726	9495.4	13007.4	2.17

Attachment D3

Excel Spreadsheet Evaluation

Methodology

The Excel Spreadsheet Evaluation involved first identifying each operational step and the proposed equipment to be used in defined areas to accomplish the required tasks for processing specific waste streams. The WHB process was then broken down into four major areas: the Carrier Preparation Area, the Carrier Bay, the Cask Preparation Area, and the Transfer Cell. The amount of time to process each waste form was calculated for each area by adding the times for the individual tasks in Appendix D Attachment D1. The total number of hours per year to process each waste form was calculated based on the number of casks entering the WHB each year. The area utilization was then calculated by dividing the total number of hours required to complete the tasks in each major area by the efficiency factor. The total area utilization was then calculated by adding each of the individual waste form utilization factors. The total area utilization represents the number of lines that are required to process the waste in any given year.

Results

The results for this analysis are presented on the sheets and graphs on the following pages.

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

Case 1 - Area Utilization

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

Case 2 - Area Utilization

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

Case 3 - Area Utilization

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

Case 32 - Area Utilization

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

Case 33 - Area Utilization

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 1, Maximum Truck Case, Rail 2010
LWT Truck Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Truck Cask Uncanistered SNF - Operation 13A	0.00	0.00	0.00	4.00	4.00
Total	7.78	5.39	10.59	4.00	27.76

Year	# TRUCK CASK		Truck Cask to DC													
	4 Assemblies/Cask	4 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required				
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	16	12	218	151	312	112	792	5%	3%	7%	3%	0.7	0.5	1.1	0.4	
2011	25	18	335	232	479	172	1218	8%	5%	11%	4%	1.1	0.8	1.6	0.6	
2012	49	37	669	464	962	344	2439	15%	11%	22%	8%	2.3	1.6	3.3	1.2	
2013	80	60	1089	755	1586	560	3989	25%	17%	36%	13%	3.7	2.6	5.4	2.0	
2014	131	99	1789	1240	2599	920	6548	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2015	131	99	1789	1240	2589	920	6538	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2016	131	99	1789	1240	2589	920	6538	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2017	131	99	1789	1240	2589	920	6538	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2018	131	99	1789	1240	2589	920	6538	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2019	131	99	1789	1240	2589	920	6538	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2020	131	99	1789	1240	2589	920	6538	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2021	131	99	1789	1240	2589	920	6538	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2022	131	99	1789	1240	2589	920	6538	41%	28%	59%	22%	6.1	4.2	8.9	3.3	
2023	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2024	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2025	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2026	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2027	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2028	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2029	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2030	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2031	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2032	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2033	51	39	700	485	1054	360	2599	16%	11%	24%	9%	2.4	1.7	3.6	1.3	
2034	23	17	311	216	511	160	1197	7%	5%	12%	4%	1.1	0.7	1.7	0.6	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 1, Maximum Truck Case, Rail 2010
SPC Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Rail Cask Uncanistered SNF - Operation 13B	0.00	0.00	0.00	10.67	10.67
Total	7.78	5.39	10.59	10.67	34.43

Year	# SPC RAIL CASKS		SPC Rail to DC												
	24 Assemblies/Cask	24 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	27	20	366	253	523	501	1644	8%	6%	12%	12%	1.3	0.9	1.8	1.8
2011	40	30	545	377	780	747	2449	12%	9%	18%	18%	1.9	1.3	2.7	2.7
2012	79	60	1081	749	1555	1483	4869	25%	17%	35%	36%	3.7	2.6	5.3	5.4
2013	130	98	1774	1229	2582	2433	8018	40%	28%	59%	59%	6.1	4.2	8.8	8.8
2014	215	162	2933	2032	4260	4023	13248	67%	46%	97%	97%	10.0	7.0	14.6	14.5
2015	215	162	2933	2032	4243	4023	13231	67%	46%	97%	97%	10.0	7.0	14.5	14.5
2016	215	162	2933	2032	4243	4023	13231	67%	46%	97%	97%	10.0	7.0	14.5	14.5
2017	215	162	2933	2032	4243	4023	13231	67%	46%	97%	97%	10.0	7.0	14.5	14.5
2018	215	162	2933	2032	4243	4023	13231	67%	46%	97%	97%	10.0	7.0	14.5	14.5
2019	215	162	2933	2032	4243	4023	13231	67%	46%	97%	97%	10.0	7.0	14.5	14.5
2020	215	162	2933	2032	4243	4023	13231	67%	46%	97%	97%	10.0	7.0	14.5	14.5
2021	215	162	2933	2032	4243	4023	13231	67%	46%	97%	97%	10.0	7.0	14.5	14.5
2022	215	162	2933	2032	4243	4023	13231	67%	46%	97%	97%	10.0	7.0	14.5	14.5
2023	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2024	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2025	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2026	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2027	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2028	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2029	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2030	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2031	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2032	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2033	185	139	2521	1746	3795	3457	11519	57%	40%	87%	83%	8.6	6.0	13.0	12.5
2034	47	35	638	442	1047	875	3002	15%	10%	24%	21%	2.2	1.5	3.6	3.2

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 1, Maximum Truck Case, Rail 2010
DPC Rail Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Prep. Area - Move Empty Carrier into WHB - Operation 3	1.50	0.00	0.00	0.00	1.50
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.67	0.83	0.00	0.00	3.50
Carrier Bay - Move Overpack Loaded with DPC out from the WHB - Operation 5	1.00	0.83	0.00	0.00	1.83
Carrier Bay - Cask Prep. - Transportation Cask Loaded with DPC - Operation 6A	0.00	1.33	9.34	0.00	10.67
Cask Preparation with Empty DPC Loaded in Cask - Operation 7.1	0.00	1.92	3.42	0.83	6.17
Transfer Area - Cask Unload - DPC Unloading to a 44 BWR DC - Operation 9C	0.00	0.00	0.00	14.50	14.50
Transfer Area - Empty DPC Transfer from Cask to DPC Overpack - Operation 10B	0.00	0.00	0.00	1.70	1.70
Total	9.20	7.21	12.76	17.03	46.20

Year	# DPC RAIL CASKS		DPC Rail to DC												
	38 Assemblies/Cask	38 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	3	2	46	36	67	85	234	1%	1%	2%	2%	0.2	0.1	0.2	0.3
2011	4	3	64	50	94	119	328	1%	1%	2%	3%	0.2	0.2	0.3	0.4
2012	9	6	138	108	202	255	704	3%	2%	5%	6%	0.5	0.4	0.7	0.9
2013	14	11	230	180	341	426	1177	5%	4%	8%	10%	0.8	0.6	1.2	1.5
2014	23	17	368	288	545	681	1882	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2015	23	17	368	288	542	681	1880	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2016	23	17	368	288	542	681	1880	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2017	23	17	368	288	542	681	1880	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2018	23	17	368	288	542	681	1880	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2019	23	17	368	288	542	681	1880	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2020	23	17	368	288	542	681	1880	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2021	23	17	368	288	542	681	1880	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2022	23	17	368	288	542	681	1880	8%	7%	12%	16%	1.3	1.0	1.9	2.5
2023	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2024	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2025	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2026	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2027	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2028	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2029	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2030	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2031	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2032	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2033	50	38	810	634	1242	1499	4185	18%	14%	28%	36%	2.8	2.2	4.2	5.4
2034	141	106	2272	1781	3799	4206	12059	52%	41%	87%	101%	7.8	6.1	13.0	15.2

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 1, Maximum Truck Case, Rail 2010
DOE SNF/HLW Immobilized Plutonium Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered DOE SNF/HLW Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Cask Canistered DOE SNF/HLW - Operation 13B	0.00	0.00	0.00	4.33	4.33
Total	6.95	6.22	10.59	4.33	28.09

Year	DOE SNF/HLW & Immobilized Pu			DOE SNF/HLW & Immobilized Pu Rail to DC															
	5/Cask	5/Cask	5/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required						
	DOE SNF	DOE HLW	Plutonium	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell			
2010	3	33	12	333.6	298.6	534.3	207.8	1374.3	8%	7%	12%	5%	1.1	1.0	1.8	0.8			
2011	6	48	12	458.7	410.5	735.6	285.8	1890.6	10%	9%	17%	7%	1.6	1.4	2.5	1.0			
2012	13	83	12	750.6	671.8	1208.4	467.6	3098.4	17%	15%	28%	11%	2.6	2.3	4.1	1.7			
2013	16	98	12	875.7	783.7	1427.1	545.6	3632.1	20%	18%	33%	13%	3.0	2.7	4.9	2.0			
2014	19	113	12	1000.8	895.7	1627.3	623.5	4147.3	23%	20%	37%	15%	3.4	3.1	5.6	2.3			
2015	30	168	12	1459.5	1306.2	2363.6	909.3	6038.6	33%	30%	54%	22%	5.0	4.5	8.1	3.3			
2016	30	168	12	1459.5	1306.2	2363.6	909.3	6038.6	33%	30%	54%	22%	5.0	4.5	8.1	3.3			
2017	30	168	12	1459.5	1306.2	2363.6	909.3	6038.6	33%	30%	54%	22%	5.0	4.5	8.1	3.3			
2018	30	168	12	1459.5	1306.2	2363.6	909.3	6038.6	33%	30%	54%	22%	5.0	4.5	8.1	3.3			
2019	30	168	12	1459.5	1306.2	2363.6	909.3	6038.6	33%	30%	54%	22%	5.0	4.5	8.1	3.3			
2020	30	168	12	1459.5	1306.2	2363.6	909.3	6038.6	33%	30%	54%	22%	5.0	4.5	8.1	3.3			
2021	30	168	12	1459.5	1306.2	2363.6	909.3	6038.6	33%	30%	54%	22%	5.0	4.5	8.1	3.3			
2022	30	168	12	1459.5	1306.2	2363.6	909.3	6038.6	33%	30%	54%	22%	5.0	4.5	8.1	3.3			
2023	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2024	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2025	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2026	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2027	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2028	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2029	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2030	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2031	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2032	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2033	30	168	12	1459.5	1306.2	2459.5	909.3	6134.5	33%	30%	56%	22%	5.0	4.5	8.4	3.3			
2034	30	168	12	1459.5	1306.2	2680.7	909.3	6355.7	33%	30%	61%	22%	5.0	4.5	9.2	3.3			

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 1, Maximum Truck Case, Rail 2010
Navy Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep
Percentage	50%	50%	50%
Hours/Yr	4385	4385	4385

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered Navy Fuel - Operation 12.1	0.00	1.50	5.83	0.00	7.33
Transfer Area - Navy Canistered Unloaded into a DC - Operation 13C	0.00	0.00	0.00	4.75	4.75
Total	6.95	6.55	10.25	4.75	28.50

Year	Navv Cans 1 / Cask	DOE SNF/HLW & Immobilized Pu Rail to DC													
		Hours of Operation / Year					Area Utilization				Shifts / Week Required				
		Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	3	21	20	32	14	87	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2011	3	21	20	32	14	87	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2012	3	21	20	32	14	87	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2013	3	21	20	33	14	88	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2014	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2015	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2016	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2017	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2018	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2019	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2020	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2021	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2022	12	83	79	131	57	350	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2023	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2024	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2025	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2026	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2027	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2028	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2029	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2030	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2031	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2032	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2033	12	83	79	136	57	355	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2034	12	83	79	148	57	367	2%	2%	3%	1%	0.3	0.3	0.5	0.2	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER PREP AREA																		
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required					
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	218	366	46	334	21	984	5%	8%	1%	8%	0%	22%	0.7	1.3	0.2	1.1	0.1	3.4
2011	335	545	64	459	21	1423	8%	12%	1%	10%	0%	32%	1.1	1.9	0.2	1.6	0.1	4.9
2012	669	1081	138	751	21	2660	15%	25%	3%	17%	0%	61%	2.3	3.7	0.5	2.6	0.1	9.1
2013	1089	1774	230	878	21	3990	25%	40%	5%	20%	0%	91%	3.7	6.1	0.8	3.0	0.1	13.6
2014	1789	2933	368	1001	83	6175	41%	67%	8%	23%	2%	141%	6.1	10.0	1.3	3.4	0.3	21.1
2015	1789	2933	368	1460	83	6633	41%	67%	8%	33%	2%	151%	6.1	10.0	1.3	5.0	0.3	22.7
2016	1789	2933	368	1460	83	6633	41%	67%	8%	33%	2%	151%	6.1	10.0	1.3	5.0	0.3	22.7
2017	1789	2933	368	1460	83	6633	41%	67%	8%	33%	2%	151%	6.1	10.0	1.3	5.0	0.3	22.7
2018	1789	2933	368	1460	83	6633	41%	67%	8%	33%	2%	151%	6.1	10.0	1.3	5.0	0.3	22.7
2019	1789	2933	368	1460	83	6633	41%	67%	8%	33%	2%	151%	6.1	10.0	1.3	5.0	0.3	22.7
2020	1789	2933	368	1460	83	6633	41%	67%	8%	33%	2%	151%	6.1	10.0	1.3	5.0	0.3	22.7
2021	1789	2933	368	1460	83	6633	41%	67%	8%	33%	2%	151%	6.1	10.0	1.3	5.0	0.3	22.7
2022	1789	2933	368	1460	83	6633	41%	67%	8%	33%	2%	151%	6.1	10.0	1.3	5.0	0.3	22.7
2023	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2024	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2025	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2026	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2027	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2028	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2029	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2030	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2031	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2032	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2033	700	2521	810	1460	83	5573	16%	57%	18%	33%	2%	127%	2.4	8.6	2.8	5.0	0.3	19.1
2034	311	638	2272	1460	83	4764	7%	15%	52%	33%	2%	109%	1.1	2.2	7.8	5.0	0.3	16.3

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER BAY AREA																				
Hour of Operation / Year							Area Utilization						Shifts / Week Required							
Year	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total		
2010	151	253	36	299	20	759	3%	6%	1%	7%	0%	17%	0.5	0.9	0.1	1.0	0.1	2.6		
2011	232	377	50	411	20	1090	5%	9%	1%	9%	0%	25%	0.8	1.3	0.2	1.4	0.1	3.7		
2012	464	749	108	672	20	2012	11%	17%	2%	15%	0%	46%	1.6	2.6	0.4	2.3	0.1	6.9		
2013	755	1229	180	784	20	2967	17%	28%	4%	18%	0%	68%	2.6	4.2	0.6	2.7	0.1	10.2		
2014	1240	2032	288	896	79	4534	28%	46%	7%	20%	2%	103%	4.2	7.0	1.0	3.1	0.3	15.5		
2015	1240	2032	288	1306	79	4945	28%	46%	7%	30%	2%	113%	4.2	7.0	1.0	4.5	0.3	16.9		
2016	1240	2032	288	1306	79	4945	28%	46%	7%	30%	2%	113%	4.2	7.0	1.0	4.5	0.3	16.9		
2017	1240	2032	288	1306	79	4945	28%	46%	7%	30%	2%	113%	4.2	7.0	1.0	4.5	0.3	16.9		
2018	1240	2032	288	1306	79	4945	28%	46%	7%	30%	2%	113%	4.2	7.0	1.0	4.5	0.3	16.9		
2019	1240	2032	288	1306	79	4945	28%	46%	7%	30%	2%	113%	4.2	7.0	1.0	4.5	0.3	16.9		
2020	1240	2032	288	1306	79	4945	28%	46%	7%	30%	2%	113%	4.2	7.0	1.0	4.5	0.3	16.9		
2021	1240	2032	288	1306	79	4945	28%	46%	7%	30%	2%	113%	4.2	7.0	1.0	4.5	0.3	16.9		
2022	1240	2032	288	1306	79	4945	28%	46%	7%	30%	2%	113%	4.2	7.0	1.0	4.5	0.3	16.9		
2023	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2024	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2025	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2026	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2027	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2028	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2029	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2030	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2031	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2032	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2033	485	1746	634	1306	79	4251	11%	40%	14%	30%	2%	97%	1.7	6.0	2.2	4.5	0.3	14.5		
2034	216	442	1781	1306	79	3823	5%	10%	41%	30%	2%	87%	0.7	1.5	6.1	4.5	0.3	13.1		

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CASK PREP AREA																		
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required					
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	312	523	67	534	32	1468	7%	12%	2%	12%	1%	33%	1.1	1.8	0.2	1.8	0.1	5.0
2011	479	780	94	736	32	2122	11%	18%	2%	17%	1%	48%	1.8	2.7	0.3	2.5	0.1	7.3
2012	962	1555	202	1208	32	3961	22%	35%	5%	28%	1%	90%	3.3	5.3	0.7	4.1	0.1	13.5
2013	1586	2582	341	1427	33	5969	36%	59%	8%	33%	1%	136%	5.4	8.8	1.2	4.9	0.1	20.4
2014	2599	4260	545	1627	131	9163	59%	97%	12%	37%	3%	209%	8.9	14.6	1.9	5.8	0.4	31.3
2015	2589	4243	542	2364	131	9869	59%	97%	12%	54%	3%	225%	8.9	14.5	1.9	8.1	0.4	33.8
2016	2589	4243	542	2364	131	9869	59%	97%	12%	54%	3%	225%	8.9	14.5	1.9	8.1	0.4	33.8
2017	2589	4243	542	2364	131	9869	59%	97%	12%	54%	3%	225%	8.9	14.5	1.9	8.1	0.4	33.8
2018	2589	4243	542	2364	131	9869	59%	97%	12%	54%	3%	225%	8.9	14.5	1.9	8.1	0.4	33.8
2019	2589	4243	542	2364	131	9869	59%	97%	12%	54%	3%	225%	8.9	14.5	1.9	8.1	0.4	33.8
2020	2589	4243	542	2364	131	9869	59%	97%	12%	54%	3%	225%	8.9	14.5	1.9	8.1	0.4	33.8
2021	2589	4243	542	2364	131	9869	59%	97%	12%	54%	3%	225%	8.9	14.5	1.9	8.1	0.4	33.8
2022	2589	4243	542	2364	131	9869	59%	97%	12%	54%	3%	225%	8.9	14.5	1.9	8.1	0.4	33.8
2023	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2024	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2025	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2026	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2027	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2028	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2029	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2030	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2031	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2032	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2033	1054	3795	1242	2460	136	8686	24%	87%	28%	56%	3%	198%	3.6	13.0	4.2	8.4	0.5	29.7
2034	511	1047	3799	2681	148	8185	12%	24%	87%	61%	3%	187%	1.7	3.6	13.0	9.2	0.5	28.0

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

TRANSFER AREA																			
Hour of Operation / Year							Area Utilization						Shifts / Week Required						
Year	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	
2010	112	501	85	208	14	921	3%	12%	2%	5%	0%	22%	0.4	1.8	0.3	0.8	0.1	3.3	
2011	172	747	119	286	14	1338	4%	18%	3%	7%	0%	32%	0.6	2.7	0.4	1.0	0.1	4.8	
2012	344	1483	255	468	14	2564	8%	36%	6%	11%	0%	62%	1.2	5.4	0.9	1.7	0.1	9.3	
2013	560	2433	426	546	14	3978	13%	59%	10%	13%	0%	96%	2.0	8.8	1.5	2.0	0.1	14.4	
2014	920	4023	681	624	57	6304	22%	97%	16%	15%	1%	152%	3.3	14.5	2.5	2.3	0.2	22.8	
2015	920	4023	681	909	57	6590	22%	97%	16%	22%	1%	159%	3.3	14.5	2.5	3.3	0.2	23.8	
2016	920	4023	681	909	57	6590	22%	97%	16%	22%	1%	159%	3.3	14.5	2.5	3.3	0.2	23.8	
2017	920	4023	681	909	57	6590	22%	97%	16%	22%	1%	159%	3.3	14.5	2.5	3.3	0.2	23.8	
2018	920	4023	681	909	57	6590	22%	97%	16%	22%	1%	159%	3.3	14.5	2.5	3.3	0.2	23.8	
2019	920	4023	681	909	57	6590	22%	97%	16%	22%	1%	159%	3.3	14.5	2.5	3.3	0.2	23.8	
2020	920	4023	681	909	57	6590	22%	97%	16%	22%	1%	159%	3.3	14.5	2.5	3.3	0.2	23.8	
2021	920	4023	681	909	57	6590	22%	97%	16%	22%	1%	159%	3.3	14.5	2.5	3.3	0.2	23.8	
2022	920	4023	681	909	57	6590	22%	97%	16%	22%	1%	159%	3.3	14.5	2.5	3.3	0.2	23.8	
2023	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2024	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2025	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2026	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2027	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2028	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2029	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2030	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2031	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2032	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2033	360	3457	1499	909	57	6282	9%	83%	36%	22%	1%	151%	1.3	12.5	5.4	3.3	0.2	22.7	
2034	160	875	4206	909	57	6208	4%	21%	101%	22%	1%	149%	0.6	3.2	15.2	3.3	0.2	22.4	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 2, Maximum SPC Rail Casks, Rail 2010
LWT Truck Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8738

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Truck Cask Uncanistered SNF - Operation 13A	0.00	0.00	0.00	4.00	4.00
Total	7.78	5.39	10.59	4.00	27.76

Year	# TRUCK CASK		Truck Cask to DC													
	4 Assemblies/Cask	4 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required				
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	12	9	163	113	236	42	554	4%	3%	5%	1%	0.6	0.4	0.8	0.2	
2011	18	14	249	172	360	64	845	6%	4%	8%	2%	0.9	0.6	1.2	0.2	
2012	36	27	490	340	708	126	1664	11%	8%	16%	3%	1.7	1.2	2.4	0.5	
2013	58	44	794	550	1156	204	2704	18%	13%	26%	5%	2.7	1.9	4.0	0.7	
2014	96	72	1307	906	1915	336	4464	30%	21%	44%	8%	4.5	3.1	6.6	1.2	
2015	96	72	1307	906	1904	336	4453	30%	21%	43%	8%	4.5	3.1	6.5	1.2	
2016	96	72	1307	906	1904	336	4453	30%	21%	43%	8%	4.5	3.1	6.5	1.2	
2017	96	72	1307	906	1904	336	4453	30%	21%	43%	8%	4.5	3.1	6.5	1.2	
2018	96	72	1307	906	1904	336	4453	30%	21%	43%	8%	4.5	3.1	6.5	1.2	
2019	96	72	1307	906	1904	336	4453	30%	21%	43%	8%	4.5	3.1	6.5	1.2	
2020	96	72	1307	906	1904	336	4453	30%	21%	43%	8%	4.5	3.1	6.5	1.2	
2021	96	72	1307	906	1904	336	4453	30%	21%	43%	8%	4.5	3.1	6.5	1.2	
2022	96	72	1307	906	1904	336	4453	30%	21%	43%	8%	4.5	3.1	6.5	1.2	
2023	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2024	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2025	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2026	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2027	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2028	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2029	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2030	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2031	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2032	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2033	18	14	249	172	373	64	858	6%	4%	8%	2%	0.9	0.6	1.3	0.2	
2034	3	2	39	27	63	10	139	1%	1%	1%	0%	0.1	0.1	0.2	0.0	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 2, Maximum SPC Rail Casks, Rail 2010
SPC Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4365	4365	4365	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Rail Cask Uncanistered SNF - Operation 13B	0.00	0.00	0.00	10.67	10.67
Total	7.78	5.39	10.59	10.67	34.43

		# SPC RAIL CASKS		SPC Rail to DC												
		24 Assemblies/Cask	24 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
Year	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	27	20	366	253	527	501	1648	8%	6%	12%	12%	1.3	0.9	1.8	1.8	
2011	41	31	560	388	809	768	2526	13%	9%	18%	18%	1.9	1.3	2.8	2.8	
2012	80	60	1089	755	1574	1494	4911	25%	17%	36%	36%	3.7	2.6	5.4	5.4	
2013	132	99	1797	1245	2619	2465	8126	41%	28%	60%	59%	6.1	4.3	9.0	8.9	
2014	217	163	2956	2048	4332	4055	13391	67%	47%	99%	98%	10.1	7.0	14.8	14.6	
2015	217	163	2956	2048	4307	4055	13366	67%	47%	98%	98%	10.1	7.0	14.7	14.6	
2016	217	163	2956	2048	4307	4055	13366	67%	47%	98%	98%	10.1	7.0	14.7	14.6	
2017	217	163	2956	2048	4307	4055	13366	67%	47%	98%	98%	10.1	7.0	14.7	14.6	
2018	217	163	2956	2048	4307	4055	13366	67%	47%	98%	98%	10.1	7.0	14.7	14.6	
2019	217	163	2956	2048	4307	4055	13366	67%	47%	98%	98%	10.1	7.0	14.7	14.6	
2020	217	163	2956	2048	4307	4055	13366	67%	47%	98%	98%	10.1	7.0	14.7	14.6	
2021	217	163	2956	2048	4307	4055	13366	67%	47%	98%	98%	10.1	7.0	14.7	14.6	
2022	217	163	2956	2048	4307	4055	13366	67%	47%	98%	98%	10.1	7.0	14.7	14.6	
2023	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2024	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2025	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2026	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2027	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2028	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2029	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2030	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2031	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2032	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2033	205	155	2801	1940	4192	3841	12774	64%	44%	96%	92%	9.6	6.6	14.3	13.9	
2034	80	60	1089	755	1773	1494	5111	25%	17%	40%	36%	3.7	2.6	6.1	5.4	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 2, Maximum SPC Rail Casks, Rail 2010
DPC Rail Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
Total Hours/Year			8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Prep. Area - Move Empty Carrier Into WHB - Operation 3	1.50	0.00	0.00	0.00	1.50
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.67	0.83	0.00	0.00	3.50
Carrier Bay - Move Overpack Loaded with DPC out from the WHB - Operation 5	1.00	0.83	0.00	0.00	1.83
Carrier Bay - Cask Prep. - Transportation Cask Loaded with DPC - Operation 6A	0.00	1.33	9.34	0.00	10.67
Cask Preparation with Empty DPC Loaded in Cask - Operation 7.1	0.00	1.92	3.42	0.83	6.17
Transfer Area - Cask Unload - DPC Unloading to a 44 BWR DC - Operation 9C	0.00	0.00	0.00	14.50	14.50
Transfer Area - Empty DPC Transfer from Cask to DPC Overpack - Operation 10B	0.00	0.00	0.00	1.70	1.70
Total	9.20	7.21	12.76	17.03	46.20

Year	# DPC RAIL CASKS		DPC Rail to DC												
	38 Assemblies/Cask	38 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	3	2	46	36	68	85	235	1%	1%	2%	2%	0.2	0.1	0.2	0.3
2011	5	4	83	65	122	153	423	2%	1%	3%	4%	0.3	0.2	0.4	0.6
2012	9	7	147	115	217	272	752	3%	3%	5%	7%	0.5	0.4	0.7	1.0
2013	16	12	258	202	382	477	1319	6%	5%	9%	11%	0.9	0.7	1.3	1.7
2014	26	19	414	324	618	766	2123	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2015	26	19	414	324	615	766	2119	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2016	26	19	414	324	615	766	2119	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2017	26	19	414	324	615	766	2119	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2018	26	19	414	324	615	766	2119	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2019	26	19	414	324	615	766	2119	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2020	26	19	414	324	615	766	2119	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2021	26	19	414	324	615	766	2119	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2022	26	19	414	324	615	766	2119	9%	7%	14%	18%	1.4	1.1	2.1	2.8
2023	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2024	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2025	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2026	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2027	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2028	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2029	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2030	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2031	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2032	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2033	41	31	662	519	1010	1226	3418	15%	12%	23%	30%	2.3	1.8	3.5	4.4
2034	122	92	1969	1543	3266	3644	10422	45%	35%	74%	88%	6.7	5.3	11.2	13.2

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 2, Maximum SPC Rail Casks, Rail 2010
DOE SNF/HLW Immobilized Plutonium Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered DOE SNF/HLW Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Cask Canistered DOE SNF/HLW - Operation 13B	0.00	0.00	0.00	4.33	4.33
Total	6.95	6.22	10.59	4.33	28.09

Year	DOE SNF/HLW & Immobilized Pu			DOE SNF/HLW & Immobilized Pu Rail to DC													
	5/Cask	5/Cask	5/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required				
	DOE SNF	DOE HLW	Plutonium	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	3	33	12	334	299	538	208	1378	8%	7%	12%	5%	1.1	1.0	1.8	0.8	
2011	6	48	12	459	411	742	286	1897	10%	9%	17%	7%	1.8	1.4	2.5	1.0	
2012	13	83	12	751	672	1214	468	3104	17%	15%	28%	11%	2.6	2.3	4.2	1.7	
2013	16	98	12	876	784	1428	546	3633	20%	18%	33%	13%	3.0	2.7	4.9	2.0	
2014	19	113	12	1001	896	1642	624	4162	23%	20%	37%	15%	3.4	3.1	5.6	2.3	
2015	30	168	12	1460	1306	2380	909	6055	33%	30%	54%	22%	5.0	4.5	8.1	3.3	
2016	30	168	12	1460	1306	2380	909	6055	33%	30%	54%	22%	5.0	4.5	8.1	3.3	
2017	30	168	12	1460	1306	2380	909	6055	33%	30%	54%	22%	5.0	4.5	8.1	3.3	
2018	30	168	12	1460	1306	2380	909	6055	33%	30%	54%	22%	5.0	4.5	8.1	3.3	
2019	30	168	12	1460	1306	2380	909	6055	33%	30%	54%	22%	5.0	4.5	8.1	3.3	
2020	30	168	12	1460	1306	2380	909	6055	33%	30%	54%	22%	5.0	4.5	8.1	3.3	
2021	30	168	12	1460	1306	2380	909	6055	33%	30%	54%	22%	5.0	4.5	8.1	3.3	
2022	30	168	12	1460	1306	2380	909	6055	33%	30%	54%	22%	5.0	4.5	8.1	3.3	
2023	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2024	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2025	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2026	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2027	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2028	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2029	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2030	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2031	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2032	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2033	30	168	12	1460	1306	2445	909	6120	33%	30%	56%	22%	5.0	4.5	8.4	3.3	
2034	30	168	12	1460	1306	2660	909	6335	33%	30%	61%	22%	5.0	4.5	9.1	3.3	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 2, Maximum SPC Rail Casks, Rail 2010
Navy Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep
Percentage	50%	50%	50%
Hours/Yr	4385	4385	4385

Critical Handling Times (WHB) (Hrs)

Operations

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered Navy Fuel - Operation 12.1	0.00	1.50	5.83	0.00	7.33
Transfer Area - Navy Canistered Unloaded into a DC - Operation 13C	0.00	0.00	0.00	4.75	4.75
Total	6.95	6.55	10.25	4.75	28.50

Year	Navy Cans 1 / Cask	DOE SNF/HLW & Immobilized Pu Rail to DC												
		Hours of Operation / Year					Area Utilization				Shifts / Week Required			
		Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	3	21	20	33	14	87	0%	0%	1%	0%	0.1	0.1	0.1	0.1
2011	3	21	20	33	14	87	0%	0%	1%	0%	0.1	0.1	0.1	0.1
2012	3	21	20	33	14	87	0%	0%	1%	0%	0.1	0.1	0.1	0.1
2013	3	21	20	33	14	88	0%	0%	1%	0%	0.1	0.1	0.1	0.1
2014	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2015	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2016	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2017	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2018	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2019	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2020	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2021	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2022	12	83	79	132	57	351	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2023	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2024	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2025	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2026	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2027	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2028	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2029	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2030	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2031	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2032	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2033	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2034	12	83	79	147	57	366	2%	2%	3%	1%	0.3	0.3	0.5	0.2

Appendix D - WHB Throughput
Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER PREP AREA																		
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required					
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	163	366	46	334	21	929	4%	8%	1%	8%	0%	21%	0.6	1.3	0.2	1.1	0.1	3.2
2011	249	560	46	459	21	1335	6%	13%	2%	10%	0%	31%	0.9	1.9	0.3	1.6	0.1	4.7
2012	490	1089	83	751	21	2434	11%	25%	3%	17%	0%	57%	1.7	3.7	0.5	2.6	0.1	6.5
2013	794	1797	147	876	21	3634	18%	41%	6%	20%	0%	85%	2.7	6.1	0.9	3.0	0.1	12.8
2014	1307	2956	258	1001	83	5605	30%	67%	9%	23%	2%	131%	4.5	10.1	1.4	3.4	0.3	19.7
2015	1307	2956	414	1460	83	6220	30%	67%	9%	33%	2%	142%	4.5	10.1	1.4	5.0	0.3	21.3
2016	1307	2956	414	1460	83	6220	30%	67%	9%	33%	2%	142%	4.5	10.1	1.4	5.0	0.3	21.3
2017	1307	2956	414	1460	83	6220	30%	67%	9%	33%	2%	142%	4.5	10.1	1.4	5.0	0.3	21.3
2018	1307	2956	414	1460	83	6220	30%	67%	9%	33%	2%	142%	4.5	10.1	1.4	5.0	0.3	21.3
2019	1307	2956	414	1460	83	6220	30%	67%	9%	33%	2%	142%	4.5	10.1	1.4	5.0	0.3	21.3
2020	1307	2956	414	1460	83	6220	30%	67%	9%	33%	2%	142%	4.5	10.1	1.4	5.0	0.3	21.3
2021	1307	2956	414	1460	83	6220	30%	67%	9%	33%	2%	142%	4.5	10.1	1.4	5.0	0.3	21.3
2022	1307	2956	414	1460	83	6220	30%	67%	9%	33%	2%	142%	4.5	10.1	1.4	5.0	0.3	21.3
2023	249	2801	414	1460	83	5007	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2024	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2025	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2026	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2027	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2028	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2029	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2030	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2031	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2032	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2033	249	2801	662	1460	83	5255	6%	64%	15%	33%	2%	120%	0.9	9.6	2.3	5.0	0.3	18.0
2034	39	1089	662	1460	83	3333	1%	25%	45%	33%	2%	106%	0.1	3.7	6.7	5.0	0.3	15.9

Appendix D - WHB Throughput
Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER BAY AREA																		
Hour of Operation / Year							Area Utilization						Shifts / Week Required					
Year	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	113	253	36	299	20	721	3%	6%	1%	7%	0%	16%	0.4	0.9	0.1	1.0	0.1	2.5
2011	172	388	65	411	20	1056	4%	9%	1%	9%	0%	24%	0.6	1.3	0.2	1.4	0.1	3.6
2012	340	755	115	872	20	1901	8%	17%	3%	15%	0%	43%	1.2	2.8	0.4	2.3	0.1	6.5
2013	550	1245	202	784	20	2800	13%	28%	5%	18%	0%	64%	1.9	4.3	0.7	2.7	0.1	9.8
2014	906	2048	324	896	79	4252	21%	47%	7%	20%	2%	97%	3.1	7.0	1.1	3.1	0.3	14.5
2015	906	2048	324	1306	79	4663	21%	47%	7%	30%	2%	106%	3.1	7.0	1.1	4.5	0.3	16.0
2016	906	2048	324	1306	79	4663	21%	47%	7%	30%	2%	106%	3.1	7.0	1.1	4.5	0.3	16.0
2017	906	2048	324	1306	79	4663	21%	47%	7%	30%	2%	106%	3.1	7.0	1.1	4.5	0.3	16.0
2018	906	2048	324	1306	79	4663	21%	47%	7%	30%	2%	106%	3.1	7.0	1.1	4.5	0.3	16.0
2019	906	2048	324	1306	79	4663	21%	47%	7%	30%	2%	106%	3.1	7.0	1.1	4.5	0.3	16.0
2020	906	2048	324	1306	79	4663	21%	47%	7%	30%	2%	106%	3.1	7.0	1.1	4.5	0.3	16.0
2021	906	2048	324	1306	79	4663	21%	47%	7%	30%	2%	106%	3.1	7.0	1.1	4.5	0.3	16.0
2022	906	2048	324	1306	79	4663	21%	47%	7%	30%	2%	106%	3.1	7.0	1.1	4.5	0.3	16.0
2023	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2024	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2025	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2026	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2027	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2028	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2029	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2030	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2031	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2032	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2033	172	1940	519	1306	79	4017	4%	44%	12%	30%	2%	92%	0.6	6.6	1.8	4.5	0.3	13.7
2034	27	755	1543	1306	79	3709	1%	17%	35%	30%	2%	85%	0.1	2.6	5.3	4.5	0.3	12.7

Appendix D - WHB Throughput
Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CASK PREP AREA																		
Hour of Operation / Year							Area Utilization						Shifts / Week Required					
Year	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	236	527	68	538	33	1401	5%	12%	2%	12%	1%	32%	0.8	1.8	0.2	1.8	0.1	4.8
2011	360	809	122	742	33	2065	8%	18%	3%	17%	1%	47%	1.2	2.8	0.4	2.5	0.1	7.1
2012	708	1574	217	1214	33	3745	16%	36%	5%	28%	1%	85%	2.4	5.4	0.7	4.2	0.1	12.8
2013	1156	2619	382	1428	33	5619	26%	60%	9%	33%	1%	128%	4.0	9.0	1.3	4.9	0.1	19.2
2014	1915	4332	618	1642	132	8639	44%	99%	14%	37%	3%	197%	6.6	14.8	2.1	5.6	0.5	29.6
2015	1904	4307	615	2380	132	9337	43%	98%	14%	54%	3%	213%	6.5	14.7	2.1	8.1	0.5	31.9
2016	1904	4307	615	2380	132	9337	43%	98%	14%	54%	3%	213%	6.5	14.7	2.1	8.1	0.5	31.9
2017	1904	4307	615	2380	132	9337	43%	98%	14%	54%	3%	213%	6.5	14.7	2.1	8.1	0.5	31.9
2018	1904	4307	615	2380	132	9337	43%	98%	14%	54%	3%	213%	6.5	14.7	2.1	8.1	0.5	31.9
2019	1904	4307	615	2380	132	9337	43%	98%	14%	54%	3%	213%	6.5	14.7	2.1	8.1	0.5	31.9
2020	1904	4307	615	2380	132	9337	43%	98%	14%	54%	3%	213%	6.5	14.7	2.1	8.1	0.5	31.9
2021	1904	4307	615	2380	132	9337	43%	98%	14%	54%	3%	213%	6.5	14.7	2.1	8.1	0.5	31.9
2022	1904	4307	615	2380	132	9337	43%	98%	14%	54%	3%	213%	6.5	14.7	2.1	8.1	0.5	31.9
2023	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2024	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2025	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2026	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2027	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2028	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2029	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2030	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2031	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2032	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2033	373	4192	1010	2445	135	8155	8%	96%	23%	56%	3%	186%	1.3	14.3	3.5	8.4	0.5	27.9
2034	63	1773	3266	2660	147	7910	1%	40%	74%	61%	3%	180%	0.2	6.1	11.2	9.1	0.5	27.1

Appendix D - WHB Throughput
Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

TRANSFER AREA																		
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required					
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	42	501	85	208	14	851	1%	12%	2%	5%	0%	20%	0.2	1.8	0.3	0.8	0.1	3.1
2011	64	768	153	286	14	1286	2%	18%	4%	7%	0%	31%	0.2	2.8	0.6	1.0	0.1	4.6
2012	126	1494	272	468	14	2374	3%	36%	7%	11%	0%	57%	0.5	5.4	1.0	1.7	0.1	8.6
2013	204	2465	477	546	14	3705	5%	59%	11%	13%	0%	89%	0.7	8.9	1.7	2.0	0.1	13.4
2014	336	4055	766	624	57	5837	8%	98%	18%	15%	1%	141%	1.2	14.6	2.8	2.3	0.2	21.1
2015	336	4055	766	909	57	6123	8%	98%	18%	22%	1%	147%	1.2	14.6	2.8	3.3	0.2	22.1
2016	336	4055	766	909	57	6123	8%	98%	18%	22%	1%	147%	1.2	14.6	2.8	3.3	0.2	22.1
2017	336	4055	766	909	57	6123	8%	98%	18%	22%	1%	147%	1.2	14.6	2.8	3.3	0.2	22.1
2018	336	4055	766	909	57	6123	8%	98%	18%	22%	1%	147%	1.2	14.6	2.8	3.3	0.2	22.1
2019	336	4055	766	909	57	6123	8%	98%	18%	22%	1%	147%	1.2	14.6	2.8	3.3	0.2	22.1
2020	336	4055	766	909	57	6123	8%	98%	18%	22%	1%	147%	1.2	14.6	2.8	3.3	0.2	22.1
2021	336	4055	766	909	57	6123	8%	98%	18%	22%	1%	147%	1.2	14.6	2.8	3.3	0.2	22.1
2022	336	4055	766	909	57	6123	8%	98%	18%	22%	1%	147%	1.2	14.6	2.8	3.3	0.2	22.1
2023	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2024	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2025	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2026	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2027	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2028	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2029	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2030	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2031	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2032	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2033	64	3841	1226	909	57	6098	2%	92%	30%	22%	1%	147%	0.2	13.9	4.4	3.3	0.2	22.0
2034	10	1494	3644	909	57	6115	0%	36%	88%	22%	1%	147%	0.0	5.4	13.2	3.3	0.2	22.1

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 3, Maximum DPC Rail Casks, Rail 2010
LWT Truck Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
Total Hours/Year			8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Truck Cask Uncanistered SNF - Operation 13A	0.00	0.00	0.00	4.00	4.00
Total	7.78	5.39	10.59	4.00	27.76

Year	# TRUCK CASK		Truck Cask to DC													
	4 Assemblies/Cask		Hours of Operation / Year					Area Utilization				Shifts / Week Required				
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	3	2	39	27	57	20	142	1%	1%	1%	0%	0.1	0.1	0.2	0.1	
2011	5	3	62	43	91	32	228	1%	1%	2%	1%	0.2	0.1	0.3	0.1	
2012	9	7	124	86	183	64	458	3%	2%	4%	2%	0.4	0.3	0.6	0.2	
2013	15	11	202	140	299	104	745	5%	3%	7%	3%	0.7	0.5	1.0	0.4	
2014	24	18	327	226	486	168	1208	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2015	24	18	327	226	483	168	1205	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2016	24	18	327	226	483	168	1205	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2017	24	18	327	226	483	168	1205	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2018	24	18	327	226	483	168	1205	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2019	24	18	327	226	483	168	1205	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2020	24	18	327	226	483	168	1205	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2021	24	18	327	226	483	168	1205	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2022	24	18	327	226	483	168	1205	7%	5%	11%	4%	1.1	0.8	1.7	0.6	
2023	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2024	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2025	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2026	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2027	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2028	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2029	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2030	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2031	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2032	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2033	45	34	615	426	938	316	2295	14%	10%	21%	8%	2.1	1.5	3.2	1.1	
2034	77	58	1050	728	1706	540	4024	24%	17%	39%	13%	3.6	2.5	5.8	2.0	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 3, Maximum DPC Rail Casks, Rail 2010
SPC Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Rail Cask Uncanistered SNF - Operation 13B	0.00	0.00	0.00	10.67	10.67
Total	7.78	5.39	10.59	10.67	34.43

Year	# SPC RAIL CASKS		SPC Rail to DC												
	24 Assemblies/Cask	24 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	28	21	381	264	555	523	1723	9%	6%	13%	13%	1.3	0.9	1.9	1.9
2011	42	32	576	399	839	790	2603	13%	9%	19%	19%	2.0	1.4	2.9	2.9
2012	83	63	1136	787	1668	1558	5149	26%	18%	38%	38%	3.9	2.7	5.7	5.6
2013	136	103	1859	1288	2747	2550	8445	42%	29%	63%	61%	6.4	4.4	9.4	9.2
2014	224	169	3058	2118	4551	4193	13921	70%	48%	104%	101%	10.5	7.2	15.6	15.1
2015	224	169	3058	2118	4523	4193	13892	70%	48%	103%	101%	10.5	7.2	15.5	15.1
2016	224	169	3058	2118	4523	4193	13892	70%	48%	103%	101%	10.5	7.2	15.5	15.1
2017	224	169	3058	2118	4523	4193	13892	70%	48%	103%	101%	10.5	7.2	15.5	15.1
2018	224	169	3058	2118	4523	4193	13892	70%	48%	103%	101%	10.5	7.2	15.5	15.1
2019	224	169	3058	2118	4523	4193	13892	70%	48%	103%	101%	10.5	7.2	15.5	15.1
2020	224	169	3058	2118	4523	4193	13892	70%	48%	103%	101%	10.5	7.2	15.5	15.1
2021	224	169	3058	2118	4523	4193	13892	70%	48%	103%	101%	10.5	7.2	15.5	15.1
2022	224	169	3058	2118	4523	4193	13892	70%	48%	103%	101%	10.5	7.2	15.5	15.1
2023	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2024	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2025	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2026	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2027	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2028	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2029	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2030	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2031	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2032	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2033	166	125	2264	1568	3456	3105	10393	52%	36%	79%	75%	7.7	5.4	11.8	11.2
2034	26	19	350	243	569	480	1641	8%	6%	13%	12%	1.2	0.8	1.9	1.7

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 3, Maximum DPC Rail Casks, Rail 2010
DPC Rail Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Prep. Area - Move Empty Carrier into WHB - Operation 3	1.50	0.00	0.00	0.00	1.50
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.67	0.83	0.00	0.00	3.50
Carrier Bay - Move Overpack Loaded with DPC out from the WHB - Operation 5	1.00	0.83	0.00	0.00	1.83
Carrier Bay - Cask Prep. - Transportation Cask Loaded with DPC - Operation 6A	0.00	1.33	9.34	0.00	10.67
Cask Preparation with Empty DPC Loaded in Cask - Operation 7.1	0.00	1.92	3.42	0.83	6.17
Transfer Area - Cask Unload - DPC Unloading to a 44 BWR DC - Operation 9C	0.00	0.00	0.00	14.50	14.50
Transfer Area - Empty DPC Transfer from Cask to DPC Overpack - Operation 10B	0.00	0.00	0.00	1.70	1.70
Total	9.20	7.21	12.76	17.03	46.20

Year	# DPC RAIL CASKS		DPC Rail to DC													
	38 Assemblies/Cask	38 Assemblies/Cask	Hours of Operation / Year						Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	4	3	64	50	96	119	330	1%	1%	2%	3%	0.2	0.2	0.3	0.4	
2011	5	4	83	65	123	153	424	2%	1%	3%	4%	0.3	0.2	0.4	0.6	
2012	11	8	175	137	262	324	897	4%	3%	6%	8%	0.6	0.5	0.9	1.2	
2013	17	13	276	216	415	511	1419	6%	5%	9%	12%	0.9	0.7	1.4	1.8	
2014	29	22	469	368	712	869	2417	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2015	29	22	469	368	707	869	2413	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2016	29	22	469	368	707	869	2413	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2017	29	22	469	368	707	869	2413	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2018	29	22	469	368	707	869	2413	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2019	29	22	469	368	707	869	2413	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2020	29	22	469	368	707	869	2413	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2021	29	22	469	368	707	869	2413	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2022	29	22	469	368	707	869	2413	11%	8%	16%	21%	1.6	1.3	2.4	3.1	
2023	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2024	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2025	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2026	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2027	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2028	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2029	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2030	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2031	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2032	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2033	63	47	1012	793	1574	1873	5252	23%	18%	36%	45%	3.5	2.7	5.4	6.8	
2034	148	112	2392	1875	3959	4428	12653	55%	43%	90%	107%	8.2	6.4	13.5	16.0	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 3, Maximum DPC Rail Casks, Rail 2010
DOE SNF/HLW Immobilized Plutonium Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
Total Hours/Year			8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered DOE SNF/HLW Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Cask Canistered DOE SNF/HLW - Operation 13B	0.00	0.00	0.00	4.33	4.33
Total	6.95	6.22	10.59	4.33	28.09

Year	DOE SNF/HLW & Immobilized Pu			DOE SNF/HLW & Immobilized Pu Rail to DC															
	5/Cask	5/Cask	5/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required						
	DOE SNF	DOE HLW	Plutonium	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Transfer Cell
2010	3	33	12	334	299	544	208	1384	8%	7%	12%	5%	1.1	1.0	1.9				0.8
2011	6	48	12	459	411	748	286	1903	10%	9%	17%	7%	1.6	1.4	2.6				1.0
2012	13	83	12	751	672	1234	468	3124	17%	15%	28%	11%	2.6	2.3	4.2				1.7
2013	16	98	12	876	784	1448	546	3653	20%	18%	33%	13%	3.0	2.7	5.0				2.0
2014	19	113	12	1001	896	1668	624	4188	23%	20%	38%	15%	3.4	3.1	5.7				2.3
2015	30	168	12	1460	1308	2417	909	6092	33%	30%	55%	22%	5.0	4.5	8.3				3.3
2016	30	168	12	1460	1308	2417	909	6092	33%	30%	55%	22%	5.0	4.5	8.3				3.3
2017	30	168	12	1460	1308	2417	909	6092	33%	30%	55%	22%	5.0	4.5	8.3				3.3
2018	30	168	12	1460	1308	2417	909	6092	33%	30%	55%	22%	5.0	4.5	8.3				3.3
2019	30	168	12	1460	1308	2417	909	6092	33%	30%	55%	22%	5.0	4.5	8.3				3.3
2020	30	168	12	1460	1308	2417	909	6092	33%	30%	55%	22%	5.0	4.5	8.3				3.3
2021	30	168	12	1460	1308	2417	909	6092	33%	30%	55%	22%	5.0	4.5	8.3				3.3
2022	30	168	12	1460	1308	2417	909	6092	33%	30%	55%	22%	5.0	4.5	8.3				3.3
2023	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2024	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2025	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2026	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2027	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2028	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2029	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2030	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2031	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2032	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2033	30	168	12	1460	1308	2494	909	6169	33%	30%	57%	22%	5.0	4.5	8.5				3.3
2034	30	168	12	1460	1308	2654	909	6329	33%	30%	61%	22%	5.0	4.5	9.1				3.3

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 3, Maximum DPC Rail Casks, Rail 2010
Navy Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep
Percentage	50%	50%	50%
Hours/Yr	4385	4385	4385

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered Navy Fuel - Operation 12.1	0.00	1.50	5.83	0.00	7.33
Transfer Area - Navy Canistered Unloaded into a DC - Operation 13C	0.00	0.00	0.00	4.75	4.75
Total	6.95	6.55	10.25	4.75	28.50

		DOE SNF/HLW & Immobilized Pu Rail to DC													
	Navy Cans	Hours of Operation / Year					Area Utilization				Shifts / Week Required				
Year	1 / Cask	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	3	21	20	33	14	88	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2011	3	21	20	33	14	88	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2012	3	21	20	33	14	88	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2013	3	21	20	33	14	88	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2014	12	83	79	135	57	354	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2015	12	83	79	134	57	353	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2016	12	83	79	134	57	353	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2017	12	83	79	134	57	353	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2018	12	83	79	134	57	353	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2019	12	83	79	134	57	353	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2020	12	83	79	134	57	353	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2021	12	83	79	134	57	353	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2022	12	83	79	134	57	353	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2023	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2024	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2025	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2026	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2027	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2028	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2029	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2030	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2031	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2032	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2033	12	83	79	138	57	357	2%	2%	3%	1%	0.3	0.3	0.5	0.2	
2034	12	83	79	147	57	366	2%	2%	3%	1%	0.3	0.3	0.5	0.2	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER PREP AREA																			
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required						
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	
2010	39	381	64	334	21	839	1%	9%	1%	8%	0%	19%	0.1	1.3	0.2	1.1	0.1	2.9	
2011	62	576	83	459	21	1200	1%	13%	2%	10%	0%	27%	0.2	2.0	0.3	1.6	0.1	4.1	
2012	124	1136	175	751	21	2207	3%	26%	4%	17%	0%	50%	0.4	3.9	0.6	2.6	0.1	7.5	
2013	202	1859	276	876	21	3234	5%	42%	6%	20%	0%	74%	0.7	6.4	0.9	3.0	0.1	11.1	
2014	327	3058	469	1001	83	4938	7%	70%	11%	23%	2%	113%	1.1	10.5	1.6	3.4	0.3	16.9	
2015	327	3058	469	1460	83	5396	7%	70%	11%	33%	2%	123%	1.1	10.5	1.6	5.0	0.3	18.5	
2016	327	3058	469	1460	83	5396	7%	70%	11%	33%	2%	123%	1.1	10.5	1.6	5.0	0.3	18.5	
2017	327	3058	469	1460	83	5396	7%	70%	11%	33%	2%	123%	1.1	10.5	1.6	5.0	0.3	18.5	
2018	327	3058	469	1460	83	5396	7%	70%	11%	33%	2%	123%	1.1	10.5	1.6	5.0	0.3	18.5	
2019	327	3058	469	1460	83	5396	7%	70%	11%	33%	2%	123%	1.1	10.5	1.6	5.0	0.3	18.5	
2020	327	3058	469	1460	83	5396	7%	70%	11%	33%	2%	123%	1.1	10.5	1.6	5.0	0.3	18.5	
2021	327	3058	469	1460	83	5396	7%	70%	11%	33%	2%	123%	1.1	10.5	1.6	5.0	0.3	18.5	
2022	327	3058	469	1460	83	5396	7%	70%	11%	33%	2%	123%	1.1	10.5	1.6	5.0	0.3	18.5	
2023	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2024	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2025	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2026	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2027	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2028	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2029	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2030	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2031	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2032	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2033	615	2264	1012	1460	83	5434	14%	52%	23%	33%	2%	124%	2.1	7.7	3.5	5.0	0.3	18.6	
2034	1050	350	2392	1460	83	5335	24%	8%	55%	33%	2%	122%	3.6	1.2	8.2	5.0	0.3	18.3	

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER BAY AREA																		
Hour of Operation / Year							Area Utilization						Shifts / Week Required					
Year	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	27	264	50	299	20	660	1%	6%	1%	7%	0%	15%	0.1	0.9	0.2	1.0	0.1	2.3
2011	43	399	65	411	20	937	1%	9%	1%	9%	0%	21%	0.1	1.4	0.2	1.4	0.1	3.2
2012	86	787	137	672	20	1702	2%	18%	3%	15%	0%	39%	0.3	2.7	0.5	2.3	0.1	5.8
2013	140	1288	216	784	20	2448	3%	29%	5%	18%	0%	56%	0.5	4.4	0.7	2.7	0.1	8.4
2014	226	2118	368	896	79	3687	5%	48%	8%	20%	2%	84%	0.8	7.2	1.3	3.1	0.3	12.6
2015	226	2118	368	1306	79	4097	5%	48%	8%	30%	2%	93%	0.8	7.2	1.3	4.5	0.3	14.0
2016	226	2118	368	1306	79	4097	5%	48%	8%	30%	2%	93%	0.8	7.2	1.3	4.5	0.3	14.0
2017	226	2118	368	1306	79	4097	5%	48%	8%	30%	2%	93%	0.8	7.2	1.3	4.5	0.3	14.0
2018	226	2118	368	1306	79	4097	5%	48%	8%	30%	2%	93%	0.8	7.2	1.3	4.5	0.3	14.0
2019	226	2118	368	1306	79	4097	5%	48%	8%	30%	2%	93%	0.8	7.2	1.3	4.5	0.3	14.0
2020	226	2118	368	1306	79	4097	5%	48%	8%	30%	2%	93%	0.8	7.2	1.3	4.5	0.3	14.0
2021	226	2118	368	1306	79	4097	5%	48%	8%	30%	2%	93%	0.8	7.2	1.3	4.5	0.3	14.0
2022	226	2118	368	1306	79	4097	5%	48%	8%	30%	2%	93%	0.8	7.2	1.3	4.5	0.3	14.0
2023	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2024	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2025	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2026	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2027	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2028	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2029	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2030	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2031	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2032	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2033	426	1568	793	1306	79	4172	10%	36%	18%	30%	2%	95%	1.5	5.4	2.7	4.5	0.3	14.3
2034	728	243	1875	1306	79	4230	17%	6%	43%	30%	2%	96%	2.5	0.8	6.4	4.5	0.3	14.5

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CASK PREP AREA																		
Hour of Operation / Year							Area Utilization						Shifts / Week Required					
Year	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	57	555	96	544	33	1284	1.3%	12.7%	2.2%	12.4%	0.7%	29.3%	0.2	1.9	0.3	1.9	0.1	4.4
2011	91	839	123	748	33	1833	2.1%	19.1%	2.8%	17.1%	0.8%	41.8%	0.3	2.9	0.4	2.6	0.1	6.3
2012	183	1668	262	1234	33	3380	4.2%	38.0%	6.0%	28.1%	0.8%	77.1%	0.6	5.7	0.9	4.2	0.1	11.6
2013	299	2747	415	1448	33	4943	6.8%	62.7%	9.5%	33.0%	0.8%	112.7%	1.0	9.4	1.4	5.0	0.1	16.9
2014	486	4551	712	1668	135	7552	11.1%	103.8%	16.2%	38.0%	3.1%	172.2%	1.7	15.6	2.4	5.7	0.5	25.8
2015	483	4523	707	2417	134	8265	11.0%	103.2%	16.1%	55.1%	3.0%	188.5%	1.7	15.5	2.4	8.3	0.5	28.3
2016	483	4523	707	2417	134	8265	11.0%	103.2%	16.1%	55.1%	3.0%	188.5%	1.7	15.5	2.4	8.3	0.5	28.3
2017	483	4523	707	2417	134	8265	11.0%	103.2%	16.1%	55.1%	3.0%	188.5%	1.7	15.5	2.4	8.3	0.5	28.3
2018	483	4523	707	2417	134	8265	11.0%	103.2%	16.1%	55.1%	3.0%	188.5%	1.7	15.5	2.4	8.3	0.5	28.3
2019	483	4523	707	2417	134	8265	11.0%	103.2%	16.1%	55.1%	3.0%	188.5%	1.7	15.5	2.4	8.3	0.5	28.3
2020	483	4523	707	2417	134	8265	11.0%	103.2%	16.1%	55.1%	3.0%	188.5%	1.7	15.5	2.4	8.3	0.5	28.3
2021	483	4523	707	2417	134	8265	11.0%	103.2%	16.1%	55.1%	3.0%	188.5%	1.7	15.5	2.4	8.3	0.5	28.3
2022	483	4523	707	2417	134	8265	11.0%	103.2%	16.1%	55.1%	3.0%	188.5%	1.7	15.5	2.4	8.3	0.5	28.3
2023	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2024	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2025	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2026	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2027	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2028	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2029	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2030	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2031	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2032	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2033	938	3456	1574	2494	138	8600	21.4%	78.8%	35.9%	56.9%	3.1%	196.1%	3.2	11.8	5.4	8.5	0.5	29.4
2034	1706	569	3959	2654	147	9034	38.9%	13.0%	90.3%	60.5%	3.3%	206.0%	5.8	1.9	13.5	9.1	0.5	30.9

Attachment D3 - Excel Spreadsheet Evaluation

TRANSFER AREA																		
Hour of Operation / Year							Area Utilization						Shifts / Week Required					
Year	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	20	523	119	208	14	884	0%	13%	3%	5%	0%	21%	0.1	1.9	0.4	0.8	0.1	3.2
2011	32	790	153	286	14	1275	1%	19%	4%	7%	0%	31%	0.1	2.9	0.8	1.0	0.1	4.8
2012	64	1558	324	468	14	2427	2%	38%	8%	11%	0%	58%	0.2	5.8	1.2	1.7	0.1	8.8
2013	104	2550	511	546	14	3725	3%	61%	12%	13%	0%	90%	0.4	9.2	1.8	2.0	0.1	13.5
2014	168	4193	869	624	57	5910	4%	101%	21%	15%	1%	142%	0.6	15.1	3.1	2.3	0.2	21.3
2015	168	4193	869	909	57	6196	4%	101%	21%	22%	1%	149%	0.6	15.1	3.1	3.3	0.2	22.4
2016	168	4193	869	909	57	6196	4%	101%	21%	22%	1%	149%	0.6	15.1	3.1	3.3	0.2	22.4
2017	168	4193	869	909	57	6196	4%	101%	21%	22%	1%	149%	0.6	15.1	3.1	3.3	0.2	22.4
2018	168	4193	869	909	57	6196	4%	101%	21%	22%	1%	149%	0.6	15.1	3.1	3.3	0.2	22.4
2019	168	4193	869	909	57	6196	4%	101%	21%	22%	1%	149%	0.6	15.1	3.1	3.3	0.2	22.4
2020	168	4193	869	909	57	6196	4%	101%	21%	22%	1%	149%	0.6	15.1	3.1	3.3	0.2	22.4
2021	168	4193	869	909	57	6196	4%	101%	21%	22%	1%	149%	0.6	15.1	3.1	3.3	0.2	22.4
2022	168	4193	869	909	57	6196	4%	101%	21%	22%	1%	149%	0.6	15.1	3.1	3.3	0.2	22.4
2023	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2024	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2025	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2026	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2027	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2028	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2029	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2030	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2031	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2032	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2033	316	3105	1873	909	57	6261	8%	75%	45%	22%	1%	151%	1.1	11.2	6.8	3.3	0.2	22.6
2034	540	480	4428	909	57	6414	13%	12%	107%	22%	1%	154%	2.0	1.7	16.0	3.3	0.2	23.2

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 32, Delta from TSLCC 2000, Utilize WHB Conceptual design Study Initial 1200 MTU Module, 3 modules at completion, 26000 MTHU in 2015, 3600 MTHU in 2028
LWT Truck Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Truck Cask Uncanistered SNF - Operation 13A	0.00	0.00	0.00	4.00	4.00
Total	7.78	5.39	10.59	4.00	27.76

Year	# TRUCK CASK		Truck Cask to DC												
	4 Assemblies/Cask	4 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010			0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2011	12	10	171	119	259	88	637	4%	3%	6%	2%	0.6	0.4	0.9	0.3
2012	35	27	482	334	711	248	1775	11%	8%	16%	6%	1.7	1.1	2.4	0.9
2013	62	47	848	588	1221	436	3093	19%	13%	28%	10%	2.9	2.0	4.2	1.6
2014	32	24	436	302	634	224	1596	10%	7%	14%	5%	1.5	1.0	2.2	0.8
2015	69	52	941	652	1381	484	3459	21%	15%	31%	12%	3.2	2.2	4.7	1.7
2016	55	42	755	523	1107	388	2773	17%	12%	25%	9%	2.6	1.8	3.8	1.4
2017	45	35	622	431	913	320	2287	14%	10%	21%	8%	2.1	1.5	3.1	1.2
2018	40	30	545	377	799	280	2001	12%	9%	18%	7%	1.9	1.3	2.7	1.0
2019	35	27	482	334	708	248	1772	11%	8%	16%	6%	1.7	1.1	2.4	0.9
2020	20	16	280	194	423	144	1041	6%	4%	10%	3%	1.0	0.7	1.4	0.5
2021	24	19	335	232	505	172	1243	8%	5%	12%	4%	1.1	0.8	1.7	0.6
2022	0	1	8	5	12	4	29	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2023	10	9	148	102	223	76	549	3%	2%	5%	2%	0.5	0.4	0.8	0.3
2024	12	9	163	113	247	84	607	4%	3%	6%	2%	0.6	0.4	0.8	0.3
2025	12	9	163	113	249	84	610	4%	3%	6%	2%	0.6	0.4	0.9	0.3
2026	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2027	14	11	195	135	297	100	726	4%	3%	7%	2%	0.7	0.5	1.0	0.4
2028	14	11	195	135	297	100	726	4%	3%	7%	2%	0.7	0.5	1.0	0.4
2029	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2030	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2031	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2032	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2033	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2034	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2035	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2036	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2037	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2038	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2039	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2040	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2041	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 32, Delta from TSLCC 2000, Utilize WHB Conceptual design Study Initial 1200 MTU Module, 3 modules at completion, 26000 MTHU in 2015, 3600 MTHU in 2028
SPC Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
Total Hours/Year			8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Rail Cask Uncanistered SNF - Operation 13B	0.00	0.00	0.00	10.67	10.67
Total	7.78	5.39	10.59	10.67	34.43

Year	# SPC RAIL CASKS		SPC Rail to DC												
	24 Assemblies/Cask	24 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010			0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2011	19	15	265	183	401	363	1211	6%	4%	9%	9%	0.9	0.6	1.4	1.3
2012	78	60	1074	744	1582	1472	4872	24%	17%	36%	35%	3.7	2.5	5.4	5.3
2013	68	52	934	647	1345	1280	4206	21%	15%	31%	31%	3.2	2.2	4.6	4.6
2014	73	55	996	690	1450	1366	4501	23%	16%	33%	33%	3.4	2.4	5.0	4.9
2015	138	104	1883	1304	2762	2582	8531	43%	30%	63%	62%	6.4	4.5	9.4	9.3
2016	137	104	1875	1299	2751	2571	8496	43%	30%	63%	62%	6.4	4.4	9.4	9.3
2017	130	98	1774	1229	2602	2433	8038	40%	28%	59%	59%	6.1	4.2	8.9	8.8
2018	119	89	1618	1121	2374	2219	7333	37%	26%	54%	53%	5.5	3.8	8.1	8.0
2019	113	85	1540	1067	2260	2113	6980	35%	24%	52%	51%	5.3	3.7	7.7	7.6
2020	106	80	1447	1003	2184	1985	6618	33%	23%	50%	48%	5.0	3.4	7.5	7.2
2021	99	75	1354	938	2043	1857	6191	31%	21%	47%	45%	4.6	3.2	7.0	6.7
2022	117	88	1595	1105	2407	2187	7294	36%	25%	55%	53%	5.5	3.8	8.2	7.9
2023	101	76	1377	954	2078	1889	6298	31%	22%	47%	45%	4.7	3.3	7.1	6.8
2024	115	86	1564	1083	2360	2145	7152	36%	25%	54%	52%	5.3	3.7	8.1	7.7
2025	106	80	1447	1003	2208	1985	6642	33%	23%	50%	48%	5.0	3.4	7.6	7.2
2026	119	89	1618	1121	2469	2219	7428	37%	26%	56%	53%	5.5	3.8	8.4	8.0
2027	87	66	1190	825	1816	1633	5464	27%	19%	41%	39%	4.1	2.8	6.2	5.9
2028	141	107	1929	1337	2944	2646	8857	44%	30%	67%	64%	6.6	4.6	10.1	9.6
2029	142	107	1937	1342	2956	2657	8892	44%	31%	67%	64%	6.6	4.6	10.1	9.6
2030	144	108	1961	1358	3121	2689	9129	45%	31%	71%	65%	6.7	4.6	10.7	9.7
2031	119	90	1626	1127	2588	2230	7571	37%	26%	59%	54%	5.6	3.9	8.9	8.1
2032	94	71	1284	889	2043	1761	5977	29%	20%	47%	42%	4.4	3.0	7.0	6.4
2033	71	54	973	674	1548	1334	4528	22%	15%	35%	32%	3.3	2.3	5.3	4.8
2034	68	52	934	647	1486	1280	4347	21%	15%	34%	31%	3.2	2.2	5.1	4.6
2035	51	39	700	485	1171	960	3316	16%	11%	27%	23%	2.4	1.7	4.0	3.5
2036	68	51	926	641	1548	1270	4385	21%	15%	35%	31%	3.2	2.2	5.3	4.8
2037	30	23	412	286	689	566	1953	9%	7%	16%	14%	1.4	1.0	2.4	2.0
2038	44	34	607	420	1015	832	2874	14%	10%	23%	20%	2.1	1.4	3.5	3.0
2039	33	26	459	318	767	630	2174	10%	7%	18%	15%	1.6	1.1	2.6	2.3
2040	19	15	265	183	443	363	1254	6%	4%	10%	9%	0.9	0.6	1.5	1.3
2041	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 32, Delta from TSLCC 2000, Utilize WHB Conceptual design Study Initial 1200 MTU Module, 3 modules at completion, 26000 MTHU in 2015, 3600 MTHU in 2028
DPC Rail Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Prep Area - Move Empty Carrier into WHB - Operation 3	1.50	0.00	0.00	0.00	1.50
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.67	0.83	0.00	0.00	3.50
Carrier Bay - Move Overpack Loaded with DPC out from the WHB - Operation 5	1.00	0.83	0.00	0.00	1.83
Carrier Bay - Cask Prep - Transportation Cask Loaded with DPC - Operation 6A	0.00	1.33	9.34	0.00	10.67
Cask Preparation with Empty DPC Loaded in Cask - Operation 7.1	0.00	1.92	3.42	0.83	6.17
Transfer Area - Cask Unload - DPC Unloading to a 44 BWR DC - Operation 9C	0.00	0.00	0.00	14.50	14.50
Transfer Area - Empty DPC Transfer from Cask to DPC Overpack - Operation 10B	0.00	0.00	0.00	1.70	1.70
Total	9.20	7.21	12.76	17.03	46.20

Year	# DPC RAIL CASKS		DPC Rail to DC												
	38 Assemblies/Cask	38 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2011	6	6	110	87	170	204	572	3%	2%	4%	5%	0.4	0.3	0.6	0.7
2012	12	9	193	151	290	358	992	4%	3%	7%	9%	0.7	0.5	1.0	1.3
2013	9	8	156	123	230	290	798	4%	3%	5%	7%	0.5	0.4	0.8	1.0
2014	11	9	184	144	273	341	942	4%	3%	6%	8%	0.6	0.5	0.9	1.2
2015	21	17	350	274	523	647	1793	8%	6%	12%	16%	1.2	0.9	1.8	2.3
2016	18	14	294	231	440	545	1510	7%	5%	10%	13%	1.0	0.8	1.5	2.0
2017	20	15	322	252	481	598	1652	7%	6%	11%	14%	1.1	0.9	1.6	2.2
2018	25	19	405	317	605	749	2076	9%	7%	14%	18%	1.4	1.1	2.1	2.7
2019	27	21	442	346	660	817	2265	10%	8%	15%	20%	1.5	1.2	2.3	3.0
2020	38	30	626	490	962	1158	3236	14%	11%	22%	28%	2.1	1.7	3.3	4.2
2021	33	25	534	418	820	988	2760	12%	10%	19%	24%	1.8	1.4	2.8	3.6
2022	32	25	524	411	806	971	2712	12%	9%	18%	23%	1.8	1.4	2.8	3.5
2023	44	34	718	562	1103	1328	3712	16%	13%	25%	32%	2.5	1.9	3.8	4.8
2024	36	28	589	461	905	1090	3046	13%	11%	21%	26%	2.0	1.6	3.1	3.9
2025	43	33	699	548	1087	1294	3629	16%	12%	25%	31%	2.4	1.9	3.7	4.7
2026	37	29	607	476	944	1124	3151	14%	11%	22%	27%	2.1	1.6	3.2	4.1
2027	57	44	929	728	1445	1720	4822	21%	17%	33%	41%	3.2	2.5	4.9	6.2
2028	72	54	1159	908	1802	2146	6016	26%	21%	41%	52%	4.0	3.1	6.2	7.7
2029	84	64	1362	1067	2117	2520	7066	31%	24%	48%	61%	4.7	3.7	7.2	9.1
2030	93	71	1509	1182	2447	2793	7931	34%	27%	56%	67%	5.2	4.0	8.4	10.1
2031	109	83	1766	1384	2865	3270	9286	40%	32%	65%	79%	6.0	4.7	9.8	11.8
2032	130	98	2098	1644	3402	3883	11027	48%	37%	78%	93%	7.2	5.6	11.6	14.0
2033	147	110	2364	1853	3835	4377	12429	54%	42%	87%	105%	8.1	6.3	13.1	15.8
2034	153	115	2466	1932	3999	4564	12961	56%	44%	91%	110%	8.4	6.6	13.7	16.5
2035	159	120	2567	2012	4373	4751	13703	59%	46%	100%	114%	8.8	6.9	15.0	17.2
2036	153	115	2466	1932	4201	4564	13162	56%	44%	96%	110%	8.4	6.6	14.4	16.5
2037	171	128	2751	2156	4686	5092	14685	63%	49%	107%	123%	9.4	7.4	16.0	18.4
2038	163	122	2622	2055	4467	4854	13997	60%	47%	102%	117%	9.0	7.0	15.3	17.5
2039	172	130	2778	2177	4733	5143	14832	63%	50%	108%	124%	9.5	7.4	16.2	18.6
2040	177	133	2852	2235	4867	5279	15234	65%	51%	111%	127%	9.8	7.6	16.7	19.1
2041	98	74	1582	1240	2701	2929	8452	36%	28%	62%	71%	5.4	4.2	9.2	10.6

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 32, Delta from TSLCC 2000, Utilize WHB Conceptual design Study Initial 1200 MTU Module, 3 modules at completion, 26000 MTHU in 2015, 3600 MTHU in 2028
DOE SNF/HLW Immobilized Plutonium Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
Total Hours/Year			8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered DOE SNF/HLW Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Cask Canistered DOE SNF/HLW - Operation 13B	0.00	0.00	0.00	4.33	4.33
Total	6.95	6.22	10.59	4.33	28.09

Year	DOE SNF/HLW & Immobilized Pu			DOE SNF/HLW & Immobilized Pu Rail to DC												
	5/Cask	5/Cask	5/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	DOE SNF	DOE HLW	Plutonium	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	0	0	0	0	0	0	0	0.0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2011	1	9	12	152.9	136.8	259.2	95.3	644.2	3%	3%	6%	2%	0.5	0.5	0.9	0.3
2012	3	47	12	430.9	385.6	710.6	268.5	1795.6	10%	9%	16%	6%	1.5	1.3	2.4	1.0
2013	6	74	12	639.4	572.2	1031.0	398.4	2641.0	15%	13%	24%	10%	2.2	2.0	3.5	1.4
2014	8	92	12	778.4	696.8	1268.7	485.0	3228.7	18%	16%	29%	12%	2.7	2.4	4.3	1.8
2015	10	110	12	917.4	821.0	1506.7	571.6	3816.7	21%	19%	34%	14%	3.1	2.8	5.2	2.1
2016	14	146	12	1195.4	1069.8	1963.2	744.8	4973.2	27%	24%	45%	18%	4.1	3.7	6.7	2.7
2017	14	146	12	1195.4	1069.8	1963.2	744.8	4973.2	27%	24%	45%	18%	4.1	3.7	6.7	2.7
2018	15	155	12	1264.9	1132.0	2077.4	788.1	5262.4	29%	26%	47%	19%	4.3	3.9	7.1	2.8
2019	15	155	12	1264.9	1132.0	2077.4	788.1	5262.4	29%	26%	47%	19%	4.3	3.9	7.1	2.8
2020	16	164	12	1334.4	1194.2	2254.2	831.4	5614.2	30%	27%	51%	20%	4.6	4.1	7.7	3.0
2021	16	164	7	1299.7	1163.1	2195.5	809.7	5468.0	30%	27%	50%	19%	4.4	4.0	7.5	2.9
2022	16	164	0	1251.0	1119.6	2113.3	779.4	5263.3	29%	26%	48%	19%	4.3	3.8	7.2	2.8
2023	16	164	0	1251.0	1119.6	2113.3	779.4	5263.3	29%	26%	48%	19%	4.3	3.8	7.2	2.8
2024	16	164	0	1251.0	1119.6	2113.3	779.4	5263.3	29%	26%	48%	19%	4.3	3.8	7.2	2.8
2025	16	164	0	1251.0	1119.6	2137.0	779.4	5287.0	29%	26%	49%	19%	4.3	3.8	7.3	2.8
2026	16	164	0	1251.0	1119.6	2137.0	779.4	5287.0	29%	26%	49%	19%	4.3	3.8	7.3	2.8
2027	16	164	0	1251.0	1119.6	2137.0	779.4	5287.0	29%	26%	49%	19%	4.3	3.8	7.3	2.8
2028	16	164	0	1251.0	1119.6	2137.0	779.4	5287.0	29%	26%	49%	19%	4.3	3.8	7.3	2.8
2029	16	164	0	1251.0	1119.6	2137.0	779.4	5287.0	29%	26%	49%	19%	4.3	3.8	7.3	2.8
2030	16	162	0	1237.1	1107.2	2204.4	770.7	5319.4	28%	25%	50%	19%	4.2	3.8	7.5	2.8
2031	16	154	0	1181.5	1057.4	2105.4	736.1	5080.4	27%	24%	48%	18%	4.0	3.6	7.2	2.7
2032	16	154	0	1181.5	1057.4	2105.4	736.1	5080.4	27%	24%	48%	18%	4.0	3.6	7.2	2.7
2033	19	130	0	1035.6	926.8	1845.3	645.2	4452.8	24%	21%	42%	16%	3.5	3.2	6.3	2.3
2034	22	116	0	959.1	858.4	1709.1	597.5	4124.1	22%	20%	39%	14%	3.3	2.9	5.8	2.2
2035	22	117	0	966.1	864.6	1808.1	601.9	4240.6	22%	20%	41%	14%	3.3	3.0	6.2	2.2
2036	21	165	0	1292.7	1156.9	2419.5	805.4	5674.5	29%	26%	55%	19%	4.4	4.0	8.3	2.9
2037	19	149	0	1167.6	1045.0	2185.4	727.4	5125.4	27%	24%	50%	18%	4.0	3.6	7.5	2.6
2038	21	165	0	1292.7	1156.9	2419.5	805.4	5674.5	29%	26%	55%	19%	4.4	4.0	8.3	2.9
2039	23	150	0	1202.4	1076.1	2250.4	749.1	5277.9	27%	25%	51%	18%	4.1	3.7	7.7	2.7
2040	22	141	0	1132.9	1013.9	2124.0	705.8	4976.5	26%	23%	48%	17%	3.9	3.5	7.3	2.5
2041	21	126	0	1021.7	914.3	1915.5	636.5	4488.0	23%	21%	44%	15%	3.5	3.1	6.6	2.3

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 32, Delta from TSLCC 2000, Utilize WHB Conceptual design Study initial 1200 MTU Module, 3 modules at completion, 26000 MTHU in 2015, 3600 MTHU in 2028
Navy Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep
Percentage	50%	50%	50%
Hours/Yr	4385	4385	4385

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered Navy Fuel - Operation 12.1	0.00	1.50	5.83	0.00	7.33
Transfer Area - Navy Canistered Unloaded into a DC - Operation 13C	0.00	0.00	0.00	4.75	4.75
Total	6.95	6.55	10.25	4.75	28.50

DOE SNF/HLW & Immobilized Pu Rail to DC														
Year	Navv Cans 1 / Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
		Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2011	1	7	7	11	5	30	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2012	1	7	7	11	5	29	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2013	3	21	20	33	14	87	0%	0%	1%	0%	0.1	0.1	0.1	0.1
2014	6	42	39	66	29	175	1%	1%	2%	1%	0.1	0.1	0.2	0.1
2015	8	56	52	88	38	234	1%	1%	2%	1%	0.2	0.2	0.3	0.1
2016	12	83	79	133	57	352	2%	2%	3%	1%	0.3	0.3	0.5	0.2
2017	14	97	92	155	67	410	2%	2%	4%	2%	0.3	0.3	0.5	0.2
2018	15	104	98	166	71	439	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2019	15	104	98	166	71	439	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2020	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2021	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2022	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2023	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2024	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2025	15	104	98	172	71	446	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2026	15	104	98	172	71	446	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2027	15	104	98	172	71	446	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2028	15	104	98	172	71	446	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2029	15	104	98	172	71	446	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2030	15	104	98	180	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2031	15	104	98	180	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2032	15	104	98	180	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2033	15	104	98	180	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2034	15	104	98	180	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3
2035	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2036	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2037	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2038	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2039	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2040	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2041	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER PREP AREA																		
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required					
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	0	0	0	0	0	0	0%	0%	0%	0%	0%	0%	0.0	0.0	0.0	0.0	0.0	0.0
2011	171	265	110	153	7	706	4%	6%	3%	3%	0%	16%	0.6	0.9	0.4	0.5	0.0	2.4
2012	482	1074	193	431	7	2187	11%	24%	4%	10%	0%	50%	1.7	3.7	0.7	1.5	0.0	7.5
2013	848	934	156	639	21	2598	19%	21%	4%	15%	0%	59%	2.9	3.2	0.5	2.2	0.1	8.9
2014	436	996	184	778	42	2436	10%	23%	4%	18%	1%	56%	1.5	3.4	0.6	2.7	0.1	8.3
2015	941	1883	350	917	56	4147	21%	43%	8%	21%	1%	95%	3.2	6.4	1.2	3.1	0.2	14.2
2016	755	1875	294	1195	83	4203	17%	43%	7%	27%	2%	96%	2.6	6.4	1.0	4.1	0.3	14.4
2017	622	1774	322	1195	97	4011	14%	40%	7%	27%	2%	91%	2.1	6.1	1.1	4.1	0.3	13.7
2018	545	1618	405	1265	104	3937	12%	37%	9%	29%	2%	90%	1.9	5.5	1.4	4.3	0.4	13.5
2019	482	1540	442	1265	104	3834	11%	35%	10%	29%	2%	87%	1.7	5.3	1.5	4.3	0.4	13.1
2020	280	1447	626	1334	104	3791	6%	33%	14%	30%	2%	86%	1.0	5.0	2.1	4.6	0.4	13.0
2021	335	1354	534	1300	104	3626	8%	31%	12%	30%	2%	83%	1.1	4.6	1.8	4.4	0.4	12.4
2022	8	1595	524	1251	104	3482	0%	36%	12%	29%	2%	79%	0.0	5.5	1.8	4.3	0.4	11.9
2023	148	1377	718	1251	104	3598	3%	31%	16%	29%	2%	82%	0.5	4.7	2.5	4.3	0.4	12.3
2024	163	1564	589	1251	104	3671	4%	36%	13%	29%	2%	84%	0.6	5.3	2.0	4.3	0.4	12.6
2025	163	1447	699	1251	104	3665	4%	33%	16%	29%	2%	84%	0.6	5.0	2.4	4.3	0.4	12.5
2026	0	1618	607	1251	104	3581	0%	37%	14%	29%	2%	82%	0.0	5.5	2.1	4.3	0.4	12.2
2027	195	1190	929	1251	104	3669	4%	27%	21%	29%	2%	84%	0.7	4.1	3.2	4.3	0.4	12.6
2028	195	1929	1159	1251	104	4638	4%	44%	26%	29%	2%	106%	0.7	6.6	4.0	4.3	0.4	15.9
2029	0	1937	1362	1251	104	4654	0%	44%	31%	29%	2%	108%	0.0	6.6	4.7	4.3	0.4	15.9
2030	0	1961	1509	1237	104	4811	0%	45%	34%	28%	2%	110%	0.0	6.7	5.2	4.2	0.4	16.5
2031	0	1626	1766	1182	104	4678	0%	37%	40%	27%	2%	107%	0.0	5.6	6.0	4.0	0.4	16.0
2032	0	1284	2098	1182	104	4667	0%	29%	48%	27%	2%	106%	0.0	4.4	7.2	4.0	0.4	16.0
2033	0	973	2364	1036	104	4477	0%	22%	54%	24%	2%	102%	0.0	3.3	8.1	3.5	0.4	15.3
2034	0	934	2466	959	104	4463	0%	21%	56%	22%	2%	102%	0.0	3.2	8.4	3.3	0.4	15.3
2035	0	700	2567	966	0	4233	0%	16%	59%	22%	0%	97%	0.0	2.4	8.8	3.3	0.0	14.5
2036	0	926	2466	1293	0	4684	0%	21%	56%	29%	0%	107%	0.0	3.2	8.4	4.4	0.0	16.0
2037	0	412	2751	1168	0	4331	0%	9%	63%	27%	0%	99%	0.0	1.4	9.4	4.0	0.0	14.8
2038	0	607	2622	1293	0	4522	0%	14%	60%	29%	0%	103%	0.0	2.1	9.0	4.4	0.0	15.5
2039	0	459	2778	1202	0	4440	0%	10%	63%	27%	0%	101%	0.0	1.6	9.5	4.1	0.0	15.2
2040	0	265	2852	1133	0	4249	0%	6%	65%	26%	0%	97%	0.0	0.9	9.8	3.9	0.0	14.5
2041	0	0	1582	1022	0	2604	0%	0%	36%	23%	0%	59%	0.0	0.0	5.4	3.5	0.0	8.9

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER BAY AREA																			
Hour of Operation / Year							Area Utilization						Shifts / Week Required						
Year	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	
2010	0	0	0	0	0	0	0%	0%	0%	0%	0%	0%	0.0	0.0	0.0	0.0	0.0	0.0	
2011	119	183	87	137	7	532	3%	4%	2%	3%	0%	12%	0.4	0.6	0.3	0.5	0.0	1.8	
2012	334	744	151	386	7	1622	8%	17%	3%	9%	0%	37%	1.1	2.5	0.5	1.3	0.0	5.5	
2013	588	647	123	572	20	1949	13%	15%	3%	13%	0%	44%	2.0	2.2	0.4	2.0	0.1	6.7	
2014	302	690	144	697	39	1872	7%	16%	3%	16%	1%	43%	1.0	2.4	0.5	2.4	0.1	6.4	
2015	652	1304	274	821	52	3104	15%	30%	6%	19%	1%	71%	2.2	4.5	0.9	2.8	0.2	10.6	
2016	523	1299	231	1070	79	3201	12%	30%	5%	24%	2%	73%	1.8	4.4	0.8	3.7	0.3	11.0	
2017	431	1229	252	1070	92	3074	10%	28%	6%	24%	2%	70%	1.5	4.2	0.9	3.7	0.3	10.5	
2018	377	1121	317	1132	98	3046	9%	26%	7%	26%	2%	69%	1.3	3.8	1.1	3.9	0.3	10.4	
2019	334	1067	346	1132	98	2978	8%	24%	8%	26%	2%	68%	1.1	3.7	1.2	3.9	0.3	10.2	
2020	194	1003	490	1194	98	2979	4%	23%	11%	27%	2%	68%	0.7	3.4	1.7	4.1	0.3	10.2	
2021	232	938	418	1163	98	2849	5%	21%	10%	27%	2%	65%	0.8	3.2	1.4	4.0	0.3	9.7	
2022	5	1105	411	1120	98	2739	0%	25%	9%	26%	2%	62%	0.0	3.8	1.4	3.8	0.3	9.4	
2023	102	954	562	1120	98	2837	2%	22%	13%	26%	2%	65%	0.4	3.3	1.9	3.8	0.3	9.7	
2024	113	1083	461	1120	98	2876	3%	25%	11%	26%	2%	66%	0.4	3.7	1.6	3.8	0.3	9.8	
2025	113	1003	548	1120	98	2882	3%	23%	12%	26%	2%	66%	0.4	3.4	1.9	3.8	0.3	9.9	
2026	0	1121	476	1120	98	2815	0%	26%	11%	26%	2%	64%	0.0	3.8	1.6	3.8	0.3	9.6	
2027	135	825	728	1120	98	2905	3%	19%	17%	26%	2%	66%	0.5	2.8	2.5	3.8	0.3	9.9	
2028	135	1337	908	1120	98	3598	3%	30%	21%	26%	2%	82%	0.5	4.6	3.1	3.8	0.3	12.3	
2029	0	1342	1067	1120	98	3627	0%	31%	24%	26%	2%	83%	0.0	4.6	3.7	3.8	0.3	12.4	
2030	0	1358	1182	1107	98	3746	0%	31%	27%	25%	2%	85%	0.0	4.6	4.0	3.8	0.3	12.8	
2031	0	1127	1384	1057	98	3666	0%	26%	32%	24%	2%	84%	0.0	3.9	4.7	3.6	0.3	12.5	
2032	0	889	1644	1057	98	3689	0%	20%	37%	24%	2%	84%	0.0	3.0	5.6	3.6	0.3	12.6	
2033	0	674	1853	927	98	3552	0%	15%	42%	21%	2%	81%	0.0	2.3	6.3	3.2	0.3	12.2	
2034	0	647	1932	858	98	3536	0%	15%	44%	20%	2%	81%	0.0	2.2	6.6	2.9	0.3	12.1	
2035	0	485	2012	865	0	3361	0%	11%	46%	20%	0%	77%	0.0	1.7	6.9	3.0	0.0	11.5	
2036	0	641	1932	1157	0	3731	0%	15%	44%	26%	0%	85%	0.0	2.2	6.6	4.0	0.0	12.8	
2037	0	286	2156	1045	0	3486	0%	7%	49%	24%	0%	80%	0.0	1.0	7.4	3.6	0.0	11.9	
2038	0	420	2055	1157	0	3632	0%	10%	47%	26%	0%	83%	0.0	1.4	7.0	4.0	0.0	12.4	
2039	0	318	2177	1076	0	3571	0%	7%	50%	25%	0%	81%	0.0	1.1	7.4	3.7	0.0	12.2	
2040	0	183	2235	1014	0	3432	0%	4%	51%	23%	0%	78%	0.0	0.6	7.6	3.5	0.0	11.7	
2041	0	0	1240	914	0	2154	0%	0%	28%	21%	0%	49%	0.0	0.0	4.2	3.1	0.0	7.4	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CASK PREP AREA																		
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required					
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	0	0	0	0	0	0	0%	0%	0%	0%	0%	0%	0.0	0.0	0.0	0.0	0.0	0.0
2011	259	401	170	259	11	1101	6%	9%	4%	6%	0%	25%	0.9	1.4	0.6	0.9	0.0	3.8
2012	711	1582	290	711	11	3304	16%	36%	7%	16%	0%	75%	2.4	5.4	1.0	2.4	0.0	11.3
2013	1221	1345	230	1031	33	3859	28%	31%	5%	24%	1%	88%	4.2	4.8	0.8	3.5	0.1	13.2
2014	634	1450	273	1269	66	3692	14%	33%	6%	29%	2%	84%	2.2	5.0	0.9	4.3	0.2	12.6
2015	1381	2762	523	1507	88	6261	31%	63%	12%	34%	2%	143%	4.7	9.4	1.8	5.2	0.3	21.4
2016	1107	2751	440	1963	133	6394	25%	63%	10%	45%	3%	146%	3.8	9.4	1.5	6.7	0.5	21.9
2017	913	2602	481	1963	155	6115	21%	59%	11%	45%	4%	139%	3.1	8.9	1.6	6.7	0.5	20.9
2018	799	2374	605	2077	166	6021	18%	54%	14%	47%	4%	137%	2.7	8.1	2.1	7.1	0.6	20.6
2019	708	2260	660	2077	166	5871	16%	52%	15%	47%	4%	134%	2.4	7.7	2.3	7.1	0.6	20.1
2020	423	2184	962	2254	170	5993	10%	50%	22%	51%	4%	137%	1.4	7.5	3.3	7.7	0.6	20.5
2021	505	2043	820	2195	170	5734	12%	47%	19%	50%	4%	131%	1.7	7.0	2.8	7.5	0.6	19.6
2022	12	2407	806	2113	170	5509	0%	55%	18%	48%	4%	126%	0.0	8.2	2.8	7.2	0.6	18.8
2023	223	2078	1103	2113	170	5688	5%	47%	25%	48%	4%	130%	0.8	7.1	3.8	7.2	0.6	19.5
2024	247	2360	905	2113	170	5796	6%	54%	21%	48%	4%	132%	0.8	8.1	3.1	7.2	0.6	19.8
2025	249	2208	1087	2137	172	5854	6%	50%	25%	49%	4%	134%	0.9	7.8	3.7	7.3	0.6	20.0
2026	0	2469	944	2137	172	5723	0%	56%	22%	49%	4%	131%	0.0	8.4	3.2	7.3	0.6	19.6
2027	297	1816	1445	2137	172	5867	7%	41%	33%	49%	4%	134%	1.0	6.2	4.9	7.3	0.6	20.1
2028	297	2944	1802	2137	172	7353	7%	67%	41%	49%	4%	168%	1.0	10.1	6.2	7.3	0.6	25.2
2029	0	2956	2117	2137	172	7383	0%	67%	48%	49%	4%	168%	0.0	10.1	7.2	7.3	0.6	25.3
2030	0	3121	2447	2204	180	7952	0%	71%	56%	50%	4%	181%	0.0	10.7	8.4	7.5	0.6	27.2
2031	0	2588	2865	2105	180	7739	0%	59%	65%	48%	4%	176%	0.0	8.9	9.8	7.2	0.6	26.5
2032	0	2043	3402	2105	180	7731	0%	47%	78%	48%	4%	176%	0.0	7.0	11.6	7.2	0.6	26.4
2033	0	1548	3835	1845	180	7408	0%	35%	87%	42%	4%	169%	0.0	5.3	13.1	6.3	0.6	25.3
2034	0	1486	3999	1709	180	7374	0%	34%	91%	39%	4%	168%	0.0	5.1	13.7	5.8	0.6	25.2
2035	0	1171	4373	1808	0	7352	0%	27%	100%	41%	0%	168%	0.0	4.0	15.0	6.2	0.0	25.2
2036	0	1548	4201	2420	0	8168	0%	35%	96%	55%	0%	186%	0.0	5.3	14.4	8.3	0.0	27.9
2037	0	689	4686	2185	0	7561	0%	16%	107%	50%	0%	172%	0.0	2.4	16.0	7.5	0.0	25.9
2038	0	1015	4467	2420	0	7901	0%	23%	102%	55%	0%	180%	0.0	3.5	15.3	8.3	0.0	27.0
2039	0	767	4733	2250	0	7751	0%	18%	108%	51%	0%	177%	0.0	2.8	16.2	7.7	0.0	26.5
2040	0	443	4667	2124	0	7434	0%	10%	111%	48%	0%	170%	0.0	1.5	16.7	7.3	0.0	25.4
2041	0	0	2701	1916	0	4616	0%	0%	62%	44%	0%	105%	0.0	0.0	9.2	6.6	0.0	15.8

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

TRANSFER AREA																				
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required							
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total		
2010	0	0	0	0	0	0	0%	0%	0%	0%	0%	0%	0.0	0.0	0.0	0.0	0.0	0.0		0.0
2011	88	363	204	95	5	755	2%	9%	5%	2%	0%	18%	0.3	1.3	0.7	0.3	0.0	0.0		2.7
2012	248	1472	358	268	5	2351	6%	35%	9%	6%	0%	57%	0.9	5.3	1.3	1.0	0.0	0.0		8.5
2013	436	1280	290	398	14	2419	10%	31%	7%	10%	0%	58%	1.6	4.6	1.0	1.4	0.1	0.1		8.7
2014	224	1366	341	485	29	2444	5%	33%	8%	12%	1%	59%	0.8	4.9	1.2	1.8	0.1	0.1		8.8
2015	484	2582	647	572	38	4323	12%	62%	16%	14%	1%	104%	1.7	9.3	2.3	2.1	0.1	0.1		15.6
2016	388	2571	545	745	57	4306	9%	62%	13%	18%	1%	104%	1.4	9.3	2.0	2.7	0.2	0.2		15.6
2017	320	2433	596	745	67	4160	8%	59%	14%	18%	2%	100%	1.2	8.8	2.2	2.7	0.2	0.2		15.0
2018	280	2219	749	788	71	4108	7%	53%	18%	19%	2%	99%	1.0	8.0	2.7	2.8	0.3	0.3		14.8
2019	248	2113	817	788	71	4037	6%	51%	20%	19%	2%	97%	0.9	7.6	3.0	2.8	0.3	0.3		14.6
2020	144	1985	1158	831	71	4189	3%	48%	28%	20%	2%	101%	0.5	7.2	4.2	3.0	0.3	0.3		15.1
2021	172	1857	988	810	71	3897	4%	45%	24%	19%	2%	94%	0.6	6.7	3.6	2.9	0.3	0.3		14.1
2022	4	2187	971	779	71	4013	0%	53%	23%	19%	2%	97%	0.0	7.9	3.5	2.8	0.3	0.3		14.5
2023	76	1889	1328	779	71	4144	2%	45%	32%	19%	2%	100%	0.3	6.8	4.8	2.8	0.3	0.3		15.0
2024	84	2145	1090	779	71	4169	2%	52%	26%	19%	2%	100%	0.3	7.7	3.9	2.8	0.3	0.3		15.1
2025	84	1985	1294	779	71	4214	2%	48%	31%	19%	2%	101%	0.3	7.2	4.7	2.8	0.3	0.3		15.2
2026	0	2219	1124	779	71	4194	0%	53%	27%	19%	2%	101%	0.0	8.0	4.1	2.8	0.3	0.3		15.1
2027	100	1633	1720	779	71	4303	2%	39%	41%	19%	2%	104%	0.4	5.9	6.2	2.8	0.3	0.3		15.5
2028	100	2646	2146	779	71	5743	2%	64%	52%	19%	2%	138%	0.4	9.6	7.7	2.8	0.3	0.3		20.7
2029	0	2657	2520	779	71	6028	0%	64%	61%	19%	2%	145%	0.0	9.6	9.1	2.8	0.3	0.3		21.8
2030	0	2689	2793	771	71	6324	0%	65%	67%	19%	2%	152%	0.0	9.7	10.1	2.8	0.3	0.3		22.8
2031	0	2230	3270	736	71	6307	0%	54%	79%	18%	2%	152%	0.0	8.1	11.8	2.7	0.3	0.3		22.8
2032	0	1761	3883	736	71	6451	0%	42%	93%	18%	2%	155%	0.0	6.4	14.0	2.7	0.3	0.3		23.3
2033	0	1334	4377	645	71	6427	0%	32%	105%	16%	2%	155%	0.0	4.8	15.8	2.3	0.3	0.3		23.2
2034	0	1280	4564	598	71	6513	0%	31%	110%	14%	2%	157%	0.0	4.6	16.5	2.2	0.3	0.3		23.5
2035	0	960	4751	602	0	6314	0%	23%	114%	14%	0%	152%	0.0	3.5	17.2	2.2	0.0	0.0		22.8
2036	0	1270	4564	805	0	6639	0%	31%	110%	19%	0%	160%	0.0	4.6	16.5	2.9	0.0	0.0		24.0
2037	0	568	5092	727	0	6385	0%	14%	123%	18%	0%	154%	0.0	2.0	18.4	2.6	0.0	0.0		23.1
2038	0	832	4854	805	0	6491	0%	20%	117%	19%	0%	156%	0.0	3.0	17.5	2.9	0.0	0.0		23.4
2039	0	630	5143	749	0	6522	0%	15%	124%	18%	0%	157%	0.0	2.3	18.6	2.7	0.0	0.0		23.6
2040	0	363	5279	706	0	6348	0%	9%	127%	17%	0%	153%	0.0	1.3	19.1	2.5	0.0	0.0		22.9
2041	0	0	2929	637	0	3566	0%	0%	71%	15%	0%	86%	0.0	0.0	10.6	2.3	0.0	0.0		12.9

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 33 - Delta from TSLCC 2000, Utilize WHB Conceptual Design Study Initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTHM in 2014, 3600 MTHM in 2028
LWT Truck Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability Factor

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Truck Cask Uncanistered SNF - Operation 13A	0.00	0.00	0.00	4.00	4.00
Total	7.78	5.39	10.59	4.00	27.76

# TRUCK CASK			Truck Cask to DC													
4 Assemblies/Cask		4 Assemblies/Cask		Hours of Operation / Year					Area Utilization				Shifts / Week Required			
Year	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2011	156	117	2124	1471	2891	1092	7578	48%	34%	66%	26%	7.3	5.0	9.9	3.9	
2012	304	228	4139	2867	5634	2128	14768	94%	65%	128%	51%	14.2	9.8	19.3	7.7	
2013	294	221	4007	2776	5454	2060	14296	91%	63%	124%	50%	13.7	9.5	18.7	7.4	
2014	77	59	1058	733	1599	544	3934	24%	17%	36%	13%	3.6	2.5	5.5	2.0	
2015	77	59	1058	733	1517	544	3852	24%	17%	35%	13%	3.6	2.5	5.2	2.0	
2016	76	57	1035	717	1483	532	3767	24%	16%	34%	13%	3.5	2.5	5.1	1.9	
2017	34	27	475	329	680	244	1728	11%	7%	16%	6%	1.6	1.1	2.3	0.9	
2018	30	24	420	291	602	216	1529	10%	7%	14%	5%	1.4	1.0	2.1	0.8	
2019	34	27	475	329	680	244	1728	11%	7%	16%	6%	1.6	1.1	2.3	0.9	
2020	20	16	280	194	422	144	1040	6%	4%	10%	3%	1.0	0.7	1.4	0.5	
2021	24	19	335	232	504	172	1242	8%	5%	11%	4%	1.1	0.8	1.7	0.6	
2022	24	19	335	232	504	172	1242	8%	5%	11%	4%	1.1	0.8	1.7	0.6	
2023	0	1	8	5	12	4	29	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2024	11	9	156	108	234	80	578	4%	2%	5%	2%	0.5	0.4	0.8	0.3	
2025	12	9	163	113	248	84	609	4%	3%	6%	2%	0.6	0.4	0.8	0.3	
2026	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2027	14	11	195	135	295	100	725	4%	3%	7%	2%	0.7	0.5	1.0	0.4	
2028	14	11	195	135	295	100	725	4%	3%	7%	2%	0.7	0.5	1.0	0.4	
2029	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2030	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2031	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2032	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2033	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2034	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2035	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2036	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2037	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2038	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2039	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2040	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2041	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 33 - Delta from TSLCC 2000, Utilize WHB Conceptual Design Study initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTHM in 2014, 3600 MTHM in 2028
SPC Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transportation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	3.75	0.00	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Uncanistered Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Rail Cask Uncanistered SNF - Operation 13B	0.00	0.00	0.00	10.67	10.67
Total	7.78	5.39	10.59	10.67	34.43

Year	# SPC RAIL CASKS		SPC Rail to DC													
	24 Assemblies/Cask	24 Assemblies/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required				
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2011	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2012	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2013	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2014	124	94	1696	1175	2564	2326	7761	39%	27%	58%	56%	5.8	4.0	8.8	8.4	
2015	149	113	2038	1412	2922	2796	9168	46%	32%	67%	67%	7.0	4.8	10.0	10.1	
2016	129	98	1766	1224	2532	2422	7943	40%	28%	58%	58%	6.0	4.2	8.7	8.7	
2017	140	106	1914	1326	2744	2625	8608	44%	30%	63%	63%	6.5	4.5	9.4	9.5	
2018	121	92	1657	1148	2376	2273	7454	38%	26%	54%	55%	5.7	3.9	8.1	8.2	
2019	115	87	1572	1089	2253	2155	7069	36%	25%	51%	52%	5.4	3.7	7.7	7.8	
2020	108	81	1470	1019	2213	2017	6719	34%	23%	50%	49%	5.0	3.5	7.6	7.3	
2021	109	82	1486	1029	2236	2038	6790	34%	23%	51%	49%	5.1	3.5	7.7	7.4	
2022	108	82	1478	1024	2225	2027	6754	34%	23%	51%	49%	5.1	3.5	7.6	7.3	
2023	107	81	1463	1013	2201	2006	6683	33%	23%	50%	48%	5.0	3.5	7.5	7.2	
2024	113	85	1540	1067	2318	2113	7039	35%	24%	53%	51%	5.3	3.7	7.9	7.6	
2025	119	89	1618	1121	2457	2219	7416	37%	26%	56%	53%	5.5	3.8	8.4	8.0	
2026	106	81	1455	1008	2209	1995	6667	33%	23%	50%	48%	5.0	3.4	7.6	7.2	
2027	86	66	1183	819	1796	1622	5419	27%	19%	41%	39%	4.0	2.8	6.1	5.9	
2028	152	115	2077	1439	3154	2849	9520	47%	33%	72%	69%	7.1	4.9	10.8	10.3	
2029	136	103	1859	1288	2824	2550	8521	42%	29%	64%	61%	6.4	4.4	9.7	9.2	
2030	136	103	1859	1288	2972	2550	8670	42%	29%	68%	61%	6.4	4.4	10.2	9.2	
2031	128	97	1751	1213	2798	2401	8162	40%	28%	64%	58%	6.0	4.1	9.6	8.7	
2032	90	68	1229	852	1965	1686	5732	28%	19%	45%	41%	4.2	2.9	6.7	6.1	
2033	72	54	980	679	1567	1344	4571	22%	15%	36%	32%	3.4	2.3	5.4	4.9	
2034	74	56	1011	701	1617	1387	4716	23%	16%	37%	33%	3.5	2.4	5.5	5.0	
2035	49	37	669	464	1120	918	3170	15%	11%	26%	22%	2.3	1.6	3.8	3.3	
2036	63	48	864	598	1445	1184	4092	20%	14%	33%	29%	3.0	2.0	4.9	4.3	
2037	28	21	381	264	638	523	1806	9%	6%	15%	13%	1.3	0.9	2.2	1.9	
2038	45	34	615	426	1029	843	2912	14%	10%	23%	20%	2.1	1.5	3.5	3.0	
2039	37	29	513	356	859	704	2433	12%	8%	20%	17%	1.8	1.2	2.9	2.5	
2040	16	13	226	156	377	309	1068	5%	4%	9%	7%	0.8	0.5	1.3	1.1	
2041	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 33 - Delta from TSLCC 2000, Utilize WHB Conceptual Design Study initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTHM in 2014, 3600 MTHM in 2028
DPC Rail Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Prep. Area - Move Empty Carrier into WHB - Operation 3	1.50	0.00	0.00	0.00	1.50
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.67	0.83	0.00	0.00	3.50
Carrier Bay - Move Overpack Loaded with DPC out from the WHB - Operation 5	1.00	0.83	0.00	0.00	1.83
Carrier Bay - Cask Prep. - Transportation Cask Loaded with DPC - Operation 6A	0.00	1.33	9.34	0.00	10.67
Cask Preparation with Empty DPC Loaded in Cask - Operation 7.1	0.00	1.92	3.42	0.83	6.17
Transfer Area - Cask Unload - DPC Unloading to a 44 BWR DC - Operation 9C	0.00	0.00	0.00	14.50	14.50
Transfer Area - Empty DPC Transfer from Cask to DPC Overpack - Operation 10B	0.00	0.00	0.00	1.70	1.70
Total	9.20	7.21	12.76	17.03	46.20

# DPC RAIL CASKS		DPC Rail to DC													
Year	36 Assemblies/Cask		Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	BWR	PWR	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2011	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2012	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2013	0	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2014	40	30	644	505	992	1192	3333	15%	12%	23%	29%	2.2	1.7	3.4	4.3
2015	8	7	138	108	202	255	703	3%	2%	5%	6%	0.5	0.4	0.7	0.9
2016	22	17	359	281	524	664	1828	8%	6%	12%	16%	1.2	1.0	1.8	2.4
2017	17	14	285	224	417	528	1453	7%	5%	10%	13%	1.0	0.8	1.4	1.9
2018	22	18	368	288	538	681	1875	8%	7%	12%	16%	1.3	1.0	1.8	2.5
2019	26	20	423	332	618	783	2156	10%	8%	14%	19%	1.4	1.1	2.1	2.8
2020	38	29	616	483	945	1141	3186	14%	11%	22%	27%	2.1	1.7	3.2	4.1
2021	32	24	515	404	790	954	2663	12%	9%	18%	23%	1.8	1.4	2.7	3.4
2022	37	28	598	469	917	1107	3091	14%	11%	21%	27%	2.0	1.6	3.1	4.0
2023	40	30	644	505	988	1192	3328	15%	12%	23%	29%	2.2	1.7	3.4	4.3
2024	33	26	543	425	832	1005	2805	12%	10%	19%	24%	1.9	1.5	2.8	3.6
2025	40	31	653	512	1011	1209	3385	15%	12%	23%	29%	2.2	1.8	3.5	4.4
2026	44	34	718	562	1110	1328	3719	16%	13%	25%	32%	2.5	1.9	3.8	4.8
2027	56	42	902	707	1395	1669	4672	21%	16%	32%	40%	3.1	2.4	4.8	6.0
2028	68	52	1104	865	1708	2044	5721	25%	20%	39%	49%	3.8	3.0	5.8	7.4
2029	89	68	1444	1132	2235	2674	7485	33%	26%	51%	64%	4.9	3.9	7.8	9.7
2030	97	74	1573	1233	2562	2912	8280	36%	28%	58%	70%	5.4	4.2	8.8	10.5
2031	98	75	1592	1247	2592	2946	8377	36%	28%	59%	71%	5.4	4.3	8.9	10.6
2032	135	101	2171	1702	3536	4019	11428	50%	39%	81%	97%	7.4	5.8	12.1	14.5
2033	147	110	2364	1853	3851	4377	12445	54%	42%	88%	105%	8.1	6.3	13.2	15.8
2034	151	114	2438	1911	3971	4513	12832	56%	44%	91%	109%	8.3	6.5	13.6	16.3
2035	160	120	2576	2019	4393	4768	13756	59%	46%	100%	115%	8.8	6.9	15.0	17.2
2036	156	117	2512	1968	4283	4649	13412	57%	45%	98%	112%	8.6	6.7	14.7	16.8
2037	173	130	2788	2185	4754	5160	14886	64%	50%	108%	124%	9.5	7.5	16.3	18.6
2038	164	124	2650	2076	4518	4905	14149	60%	47%	103%	118%	9.1	7.1	15.5	17.7
2039	168	127	2714	2127	4628	5024	14493	62%	49%	106%	121%	9.3	7.3	15.8	18.1
2040	179	134	2880	2257	4903	5330	15370	66%	51%	112%	128%	9.9	7.7	16.8	19.2
2041	76	58	1233	966	2099	2282	6580	28%	22%	48%	55%	4.2	3.3	7.2	8.2

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 33 - Delta from TSLCC 2000, Utilize WHB Conceptual Design Study Initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTHM in 2014, 3600 MTHM in 2028
DOE SNF/HLW Immobilized Plutonium Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
Percentage	50%	50%	50%	48%
Hours/Yr	4385	4385	4385	4154

Critical Handling Times (WHB) (Hrs)

Operations	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Unloaded Transporation Cask from Carrier Bay to Exit Carrier Prep - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transporation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered DOE SNF/HLW Fuel - Operation 12	0.00	1.17	6.17	0.00	7.34
Transfer Area - Unload Cask Canistered DOE SNF/HLW - Operation 13B	0.00	0.00	0.00	4.33	4.33
Total	6.95	6.22	10.59	4.33	28.09

Year	DOE SNF/HLW & Immobilized Pu			DOE SNF/HLW & Immobilized Pu Rail to DC												
	5/Cask	5/Cask	5/Cask	Hours of Operation / Year					Area Utilization				Shifts / Week Required			
	DOE SNF	DOE HLW	Plutonium	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
2010	0	0	0	0	0	0	0	0.0	0%	0%	0%	0%	0.0	0.0	0.0	0.0
2011	9	45	60	792.3	709.1	1207.3	493.6	3202.3	18%	16%	28%	12%	2.7	2.4	4.1	1.8
2012	27	135	60	1542.9	1380.8	2351.0	961.3	6236.0	35%	31%	54%	23%	5.3	4.7	8.0	3.5
2013	54	270	60	2668.8	2388.5	4066.6	1662.7	10786.6	61%	54%	93%	40%	9.1	8.2	13.9	6.0
2014	8	72	12	639.4	572.2	1081.9	398.4	2691.9	15%	13%	25%	10%	2.2	2.0	3.7	1.4
2015	10	110	12	917.4	821.0	1472.2	571.6	3782.2	21%	19%	34%	14%	3.1	2.8	5.0	2.1
2016	14	146	12	1195.4	1069.8	1918.4	744.8	4928.4	27%	24%	44%	18%	4.1	3.7	6.6	2.7
2017	14	146	12	1195.4	1069.8	1918.4	744.8	4928.4	27%	24%	44%	18%	4.1	3.7	6.6	2.7
2018	15	155	12	1264.9	1132.0	2029.9	788.1	5214.9	29%	26%	46%	19%	4.3	3.9	6.9	2.8
2019	15	155	12	1264.9	1132.0	2029.9	788.1	5214.9	29%	26%	46%	19%	4.3	3.9	6.9	2.8
2020	16	164	12	1334.4	1194.2	2248.2	831.4	5608.2	30%	27%	51%	20%	4.6	4.1	7.7	3.0
2021	16	164	7	1299.7	1163.1	2189.7	809.7	5462.2	30%	27%	50%	19%	4.4	4.0	7.5	2.9
2022	16	164	0	1251.0	1119.6	2107.7	779.4	5257.7	29%	26%	48%	19%	4.3	3.8	7.2	2.8
2023	16	164	0	1251.0	1119.6	2107.7	779.4	5257.7	29%	26%	48%	19%	4.3	3.8	7.2	2.8
2024	16	164	0	1251.0	1119.6	2107.7	779.4	5257.7	29%	26%	48%	19%	4.3	3.8	7.2	2.8
2025	16	164	0	1251.0	1119.6	2126.5	779.4	5276.5	29%	26%	48%	19%	4.3	3.8	7.3	2.8
2026	16	164	0	1251.0	1119.6	2126.5	779.4	5276.5	29%	26%	48%	19%	4.3	3.8	7.3	2.8
2027	16	164	0	1251.0	1119.6	2126.5	779.4	5276.5	29%	26%	48%	19%	4.3	3.8	7.3	2.8
2028	16	164	0	1251.0	1119.6	2126.5	779.4	5276.5	29%	26%	48%	19%	4.3	3.8	7.3	2.8
2029	16	164	0	1251.0	1119.6	2126.5	779.4	5276.5	29%	26%	48%	19%	4.3	3.8	7.3	2.8
2030	16	162	0	1237.1	1107.2	2213.5	770.7	5328.5	28%	25%	50%	19%	4.2	3.8	7.6	2.8
2031	16	154	0	1181.5	1057.4	2114.0	736.1	5089.0	27%	24%	48%	18%	4.0	3.6	7.2	2.7
2032	16	154	0	1181.5	1057.4	2114.0	736.1	5089.0	27%	24%	48%	18%	4.0	3.6	7.2	2.7
2033	19	150	0	1174.6	1051.2	2101.6	731.8	5059.1	27%	24%	48%	18%	4.0	3.6	7.2	2.6
2034	22	136	0	1098.1	982.8	1984.8	684.1	4729.8	25%	22%	45%	16%	3.8	3.4	6.7	2.5
2035	22	137	0	1105.1	989.0	2070.3	688.5	4852.8	25%	23%	47%	17%	3.8	3.4	7.1	2.5
2036	21	165	0	1292.7	1156.9	2421.9	805.4	5676.9	29%	26%	55%	19%	4.4	4.0	8.3	2.9
2037	19	149	0	1167.6	1045.0	2187.5	727.4	5127.5	27%	24%	50%	18%	4.0	3.6	7.5	2.6
2038	21	165	0	1292.7	1156.9	2421.9	805.4	5676.9	29%	26%	55%	19%	4.4	4.0	8.3	2.9
2039	23	150	0	1202.4	1076.1	2252.6	749.1	5280.1	27%	25%	51%	18%	4.1	3.7	7.7	2.7
2040	22	141	0	1132.9	1013.9	2119.0	705.8	4971.5	26%	23%	48%	17%	3.9	3.5	7.2	2.5
2041	21	126	0	1021.7	914.3	1911.0	636.5	4483.5	23%	21%	44%	15%	3.5	3.1	6.5	2.3

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

WHB - Case 33 - Delta from TSLCC 2000, Utilize WHB Conceptual Design Study initial 800 MTU (LWT) Module, 3 modules at completion, 2400 MTHM in 2014, 3600 MTHM in 2028
Navy Throughput

Operations Time Available/Yr

Shifts	3	Scaling Factor (%)	77%
Days/Wk	5	Operational Hours/Yr	4615
Shifts/Wk	15	Operational Weeks/Yr	50
		Total Hours/Year	8736

Maintenance Availability

Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell
95%	95%	95%	90%

Total Facility Availability Factor

	Carrier Prep	Carrier Bay	Cask Prep
Percentage	50%	50%	50%
Hours/Yr	4385	4385	4385

Critical Handling Times (WHB) (Hrs)

Operations

	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Totals
Loaded Cask Into WHB & Remove Cask From Carrier (Common) - Operation 1	4.03	2.30	0.00	0.00	6.33
Carrier Bay - Move Carrier Loaded with Empty Cask out of WHB - Operation 4	2.92	0.83	0.00	0.00	3.75
Cask Preparation - Unloaded Transportation Cask - Operation 7	0.00	1.92	4.42	0.00	6.34
Cask Preparation Loaded Cask - Canistered Navy Fuel - Operation 12.1	0.00	1.50	5.83	0.00	7.33
Transfer Area - Navy Canistered Unloaded into a DC - Operation 13C	0.00	0.00	0.00	4.75	4.75
Total	6.95	6.55	10.25	4.75	28.50

Year	Navv Cans 1 / Cask	DOE SNF/HLW & Immobilized Pu Rail to DC													
		Hours of Operation / Year					Area Utilization				Shifts / Week Required				
		Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Total	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	Carrier Prep	Carrier Bay	Cask Prep	Transfer Cell	
2010	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2011	1	7	7	10	5	29	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2012	1	7	7	10	5	29	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2013	3	21	20	31	14	86	0%	0%	1%	0%	0.1	0.1	0.1	0.1	
2014	6	42	39	68	29	178	1%	1%	2%	1%	0.1	0.1	0.2	0.1	
2015	8	56	52	86	38	232	1%	1%	2%	1%	0.2	0.2	0.3	0.1	
2016	12	83	79	130	57	349	2%	2%	3%	1%	0.3	0.3	0.4	0.2	
2017	14	97	92	151	67	407	2%	2%	3%	2%	0.3	0.3	0.5	0.2	
2018	15	104	98	162	71	436	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2019	15	104	98	162	71	436	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2020	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2021	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2022	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2023	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2024	15	104	98	170	71	444	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2025	15	104	98	172	71	445	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2026	15	104	98	172	71	445	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2027	15	104	98	172	71	445	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2028	15	104	98	172	71	445	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2029	15	104	98	172	71	445	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2030	15	104	98	181	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2031	15	104	98	181	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2032	15	104	98	181	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2033	15	104	98	181	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2034	15	104	98	181	71	454	2%	2%	4%	2%	0.4	0.3	0.6	0.3	
2035	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2036	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2037	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2038	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2039	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2040	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	
2041	0	0	0	0	0	0	0%	0%	0%	0%	0.0	0.0	0.0	0.0	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER PREP AREA																		
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required					
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	0	0	0	0	0	0	0%	0%	0%	0%	0%	0%	0.0	0.0	0.0	0.0	0.0	0.0
2011	2124	0	0	792	7	2923	48%	0%	0%	18%	0%	67%	7.3	0.0	0.0	2.7	0.0	10.0
2012	4139	0	0	1543	7	5689	94%	0%	0%	35%	0%	130%	14.2	0.0	0.0	5.3	0.0	19.5
2013	4007	0	0	2669	21	6696	91%	0%	0%	61%	0%	153%	13.7	0.0	0.0	9.1	0.1	22.9
2014	1058	1696	644	639	42	4079	24%	39%	15%	15%	1%	93%	3.6	5.8	2.2	2.2	0.1	14.0
2015	1058	2038	138	917	56	4207	24%	46%	3%	21%	1%	96%	3.6	7.0	0.5	3.1	0.2	14.4
2016	1035	1766	359	1195	83	4438	24%	40%	8%	27%	2%	101%	3.5	6.0	1.2	4.1	0.3	15.2
2017	475	1914	285	1195	97	3966	11%	44%	7%	27%	2%	90%	1.6	6.5	1.0	4.1	0.3	13.6
2018	420	1657	368	1265	104	3814	10%	38%	8%	29%	2%	87%	1.4	5.7	1.3	4.3	0.4	13.0
2019	475	1572	423	1265	104	3838	11%	36%	10%	29%	2%	88%	1.8	5.4	1.4	4.3	0.4	13.1
2020	280	1470	616	1334	104	3806	6%	34%	14%	30%	2%	87%	1.0	5.0	2.1	4.6	0.4	13.0
2021	335	1486	515	1300	104	3740	8%	34%	12%	30%	2%	85%	1.1	5.1	1.8	4.4	0.4	12.8
2022	335	1478	598	1251	104	3766	8%	34%	14%	29%	2%	86%	1.1	5.1	2.0	4.3	0.4	12.9
2023	8	1463	644	1251	104	3470	0%	33%	15%	29%	2%	79%	0.0	5.0	2.2	4.3	0.4	11.9
2024	156	1540	543	1251	104	3594	4%	35%	12%	29%	2%	82%	0.5	5.3	1.9	4.3	0.4	12.3
2025	163	1618	653	1251	104	3790	4%	37%	15%	29%	2%	86%	0.6	5.5	2.2	4.3	0.4	13.0
2026	0	1455	718	1251	104	3528	0%	33%	16%	29%	2%	80%	0.0	5.0	2.5	4.3	0.4	12.1
2027	195	1183	902	1251	104	3634	4%	27%	21%	29%	2%	83%	0.7	4.0	3.1	4.3	0.4	12.4
2028	195	2077	1104	1251	104	4731	4%	47%	25%	29%	2%	108%	0.7	7.1	3.8	4.3	0.4	16.2
2029	0	1859	1444	1251	104	4659	0%	42%	33%	29%	2%	106%	0.0	6.4	4.9	4.3	0.4	15.9
2030	0	1859	1573	1237	104	4774	0%	42%	36%	28%	2%	109%	0.0	6.4	5.4	4.2	0.4	16.3
2031	0	1751	1592	1182	104	4628	0%	40%	36%	27%	2%	106%	0.0	6.0	5.4	4.0	0.4	15.8
2032	0	1229	2171	1182	104	4686	0%	28%	50%	27%	2%	107%	0.0	4.2	7.4	4.0	0.4	16.0
2033	0	980	2364	1175	104	4623	0%	22%	54%	27%	2%	105%	0.0	3.4	8.1	4.0	0.4	15.8
2034	0	1011	2438	1098	104	4652	0%	23%	56%	25%	2%	106%	0.0	3.5	8.3	3.8	0.4	15.9
2035	0	669	2576	1105	0	4350	0%	15%	59%	25%	0%	99%	0.0	2.3	8.8	3.8	0.0	14.9
2036	0	864	2512	1293	0	4668	0%	20%	57%	29%	0%	106%	0.0	3.0	8.6	4.4	0.0	16.0
2037	0	381	2788	1168	0	4336	0%	9%	64%	27%	0%	99%	0.0	1.3	9.5	4.0	0.0	14.8
2038	0	615	2650	1293	0	4557	0%	14%	60%	29%	0%	104%	0.0	2.1	9.1	4.4	0.0	15.6
2039	0	513	2714	1202	0	4430	0%	12%	62%	27%	0%	101%	0.0	1.8	9.3	4.1	0.0	15.2
2040	0	226	2880	1133	0	4238	0%	5%	66%	26%	0%	97%	0.0	0.8	9.9	3.9	0.0	14.5
2041	0	0	1233	1022	0	2254	0%	0%	28%	23%	0%	51%	0.0	0.0	4.2	3.5	0.0	7.7

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CARRIER BAY AREA																			
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required						
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	
2010	0	0	0	0	0	0	0%	0%	0%	0%	0%	0%	0.0	0.0	0.0	0.0	0.0	0.0	0.0
2011	1471	0	0	709	7	2187	34%	0%	0%	16%	0%	50%	5.0	0.0	0.0	2.4	0.0	7.5	
2012	2867	0	0	1381	7	4255	65%	0%	0%	31%	0%	97%	9.8	0.0	0.0	4.7	0.0	14.6	
2013	2776	0	0	2388	20	5184	63%	0%	0%	54%	0%	118%	9.5	0.0	0.0	8.2	0.1	17.7	
2014	733	1175	505	572	39	3024	17%	27%	12%	13%	1%	69%	2.5	4.0	1.7	2.0	0.1	10.3	
2015	733	1412	108	821	52	3127	17%	32%	2%	19%	1%	71%	2.5	4.8	0.4	2.8	0.2	10.7	
2016	717	1224	281	1070	79	3370	16%	28%	6%	24%	2%	77%	2.5	4.2	1.0	3.7	0.3	11.5	
2017	329	1326	224	1070	92	3040	7%	30%	5%	24%	2%	69%	1.1	4.5	0.8	3.7	0.3	10.4	
2018	291	1148	288	1132	98	2958	7%	26%	7%	26%	2%	67%	1.0	3.9	1.0	3.9	0.3	10.1	
2019	329	1089	332	1132	98	2980	7%	25%	8%	26%	2%	68%	1.1	3.7	1.1	3.9	0.3	10.2	
2020	194	1019	483	1194	98	2988	4%	23%	11%	27%	2%	68%	0.7	3.5	1.7	4.1	0.3	10.2	
2021	232	1029	404	1163	98	2926	5%	23%	9%	27%	2%	67%	0.8	3.5	1.4	4.0	0.3	10.0	
2022	232	1024	469	1120	98	2942	5%	23%	11%	26%	2%	67%	0.8	3.5	1.6	3.8	0.3	10.1	
2023	5	1013	505	1120	98	2741	0%	23%	12%	26%	2%	63%	0.0	3.5	1.7	3.8	0.3	9.4	
2024	108	1067	425	1120	98	2818	2%	24%	10%	28%	2%	64%	0.4	3.7	1.5	3.8	0.3	9.8	
2025	113	1121	512	1120	98	2964	3%	26%	12%	26%	2%	68%	0.4	3.8	1.8	3.8	0.3	10.1	
2026	0	1008	562	1120	98	2788	0%	23%	13%	26%	2%	64%	0.0	3.4	1.9	3.8	0.3	9.5	
2027	135	819	707	1120	98	2878	3%	19%	16%	26%	2%	66%	0.5	2.8	2.4	3.8	0.3	9.8	
2028	135	1439	865	1120	98	3657	3%	33%	20%	26%	2%	83%	0.5	4.9	3.0	3.8	0.3	12.5	
2029	0	1288	1132	1120	98	3638	0%	29%	26%	26%	2%	83%	0.0	4.4	3.9	3.8	0.3	12.4	
2030	0	1288	1233	1107	98	3727	0%	29%	28%	25%	2%	85%	0.0	4.4	4.2	3.8	0.3	12.7	
2031	0	1213	1247	1057	98	3616	0%	28%	28%	24%	2%	82%	0.0	4.1	4.3	3.6	0.3	12.4	
2032	0	852	1702	1057	98	3709	0%	19%	39%	24%	2%	85%	0.0	2.9	5.8	3.6	0.3	12.7	
2033	0	679	1853	1051	98	3682	0%	15%	42%	24%	2%	84%	0.0	2.3	6.3	3.6	0.3	12.6	
2034	0	701	1911	983	98	3692	0%	16%	44%	22%	2%	84%	0.0	2.4	6.5	3.4	0.3	12.6	
2035	0	464	2019	989	0	3471	0%	11%	46%	23%	0%	79%	0.0	1.6	8.9	3.4	0.0	11.9	
2036	0	598	1968	1157	0	3724	0%	14%	45%	26%	0%	85%	0.0	2.0	6.7	4.0	0.0	12.7	
2037	0	264	2185	1045	0	3494	0%	6%	50%	24%	0%	80%	0.0	0.9	7.5	3.6	0.0	12.0	
2038	0	426	2076	1157	0	3659	0%	10%	47%	26%	0%	83%	0.0	1.5	7.1	4.0	0.0	12.5	
2039	0	356	2127	1076	0	3559	0%	8%	49%	25%	0%	81%	0.0	1.2	7.3	3.7	0.0	12.2	
2040	0	156	2257	1014	0	3427	0%	4%	51%	23%	0%	78%	0.0	0.5	7.7	3.5	0.0	11.7	
2041	0	0	966	914	0	1880	0%	0%	22%	21%	0%	43%	0.0	0.0	3.3	3.1	0.0	6.4	

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

CASK PREP AREA																			
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required						Total
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	
2010	0	0	0	0	0	0	0%	0%	0%	0%	0%	0%	0.0	0.0	0.0	0.0	0.0	0.0	0.0
2011	2891	0	0	1207	10	4109	66%	0%	0%	28%	0%	94%	9.9	0.0	0.0	4.1	0.0	0.0	14.1
2012	5634	0	0	2351	10	7995	128%	0%	0%	54%	0%	182%	19.3	0.0	0.0	8.0	0.0	0.0	27.4
2013	5454	0	0	4067	31	9551	124%	0%	0%	93%	1%	218%	18.7	0.0	0.0	13.9	0.1	0.0	32.7
2014	1599	2564	992	1082	68	6305	36%	58%	23%	25%	2%	144%	5.5	8.8	3.4	3.7	0.2	0.0	21.6
2015	1517	2922	202	1472	86	6199	35%	67%	5%	34%	2%	141%	5.2	10.0	0.7	5.0	0.3	0.0	21.2
2016	1483	2532	524	1918	130	6587	34%	58%	12%	44%	3%	150%	5.1	8.7	1.8	6.8	0.4	0.0	22.5
2017	680	2744	417	1918	151	5910	16%	63%	10%	44%	3%	135%	2.3	9.4	1.4	6.6	0.5	0.0	20.2
2018	602	2376	538	2030	162	5707	14%	54%	12%	46%	4%	130%	2.1	8.1	1.8	6.9	0.6	0.0	19.5
2019	680	2253	618	2030	162	5743	16%	51%	14%	46%	4%	131%	2.3	7.7	2.1	6.9	0.8	0.0	19.6
2020	422	2213	945	2248	170	5998	10%	50%	22%	51%	4%	137%	1.4	7.6	3.2	7.7	0.6	0.0	20.5
2021	504	2236	790	2190	170	5890	11%	51%	18%	50%	4%	134%	1.7	7.7	2.7	7.5	0.6	0.0	20.1
2022	504	2225	917	2108	170	5923	11%	51%	21%	48%	4%	135%	1.7	7.6	3.1	7.2	0.6	0.0	20.3
2023	12	2201	988	2108	170	5478	0%	50%	23%	48%	4%	125%	0.0	7.5	3.4	7.2	0.6	0.0	18.7
2024	234	2318	832	2108	170	5663	5%	53%	19%	48%	4%	129%	0.8	7.9	2.8	7.2	0.6	0.0	19.4
2025	248	2457	1011	2127	172	6014	6%	56%	23%	48%	4%	137%	0.8	8.4	3.5	7.3	0.6	0.0	20.6
2026	0	2209	1110	2127	172	5618	0%	50%	25%	48%	4%	128%	0.0	7.6	3.8	7.3	0.6	0.0	19.2
2027	295	1796	1395	2127	172	5784	7%	41%	32%	48%	4%	132%	1.0	6.1	4.8	7.3	0.6	0.0	19.8
2028	295	3154	1708	2127	172	7456	7%	72%	39%	48%	4%	170%	1.0	10.8	5.8	7.3	0.6	0.0	25.5
2029	0	2824	2235	2127	172	7356	0%	64%	51%	48%	4%	168%	0.0	9.7	7.6	7.3	0.6	0.0	25.2
2030	0	2972	2562	2214	181	7928	0%	68%	58%	50%	4%	181%	0.0	10.2	8.8	7.6	0.6	0.0	27.1
2031	0	2798	2592	2114	181	7685	0%	64%	59%	48%	4%	175%	0.0	9.6	8.9	7.2	0.6	0.0	26.3
2032	0	1965	3536	2114	181	7795	0%	45%	81%	48%	4%	178%	0.0	6.7	12.1	7.2	0.6	0.0	26.7
2033	0	1567	3851	2102	181	7700	0%	36%	88%	48%	4%	176%	0.0	5.4	13.2	7.2	0.6	0.0	26.3
2034	0	1617	3971	1965	181	7733	0%	37%	91%	45%	4%	176%	0.0	5.5	13.6	6.7	0.6	0.0	26.5
2035	0	1120	4393	2070	0	7583	0%	26%	100%	47%	0%	173%	0.0	3.8	15.0	7.1	0.0	0.0	25.9
2036	0	1445	4283	2422	0	8150	0%	33%	98%	55%	0%	186%	0.0	4.9	14.7	8.3	0.0	0.0	27.9
2037	0	638	4754	2188	0	7579	0%	15%	108%	50%	0%	173%	0.0	2.2	16.3	7.5	0.0	0.0	25.9
2038	0	1029	4518	2422	0	7969	0%	23%	103%	55%	0%	182%	0.0	3.5	15.5	8.3	0.0	0.0	27.3
2039	0	859	4628	2253	0	7740	0%	20%	106%	51%	0%	177%	0.0	2.9	15.8	7.7	0.0	0.0	26.5
2040	0	377	4903	2119	0	7399	0%	9%	112%	48%	0%	169%	0.0	1.3	16.8	7.2	0.0	0.0	25.3
2041	0	0	2099	1911	0	4010	0%	0%	48%	44%	0%	91%	0.0	0.0	7.2	6.5	0.0	0.0	13.7

Appendix D - WHB Throughput

Attachment D3 - Excel Spreadsheet Evaluation

TRANSFER AREA																		
Year	Hour of Operation / Year						Area Utilization						Shifts / Week Required					
	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total	Truck	SPC	DPC	DOE/HLW	Navy	Total
2010	0	0	0	0	0	0	0%	0%	0%	0%	0%	0%	0.0	0.0	0.0	0.0	0.0	0.0
2011	1092	0	0	494	5	1590	26%	0%	0%	12%	0%	38%	3.9	0.0	0.0	1.8	0.0	5.7
2012	2128	0	0	961	5	3094	51%	0%	0%	23%	0%	74%	7.7	0.0	0.0	3.5	0.0	11.2
2013	2060	0	0	1663	14	3737	50%	0%	0%	40%	0%	90%	7.4	0.0	0.0	6.0	0.1	13.5
2014	544	2326	1192	398	29	4489	13%	56%	29%	10%	1%	108%	2.0	8.4	4.3	1.4	0.1	16.2
2015	544	2796	255	572	38	4205	13%	67%	6%	14%	1%	101%	2.0	10.1	0.9	2.1	0.1	15.2
2016	532	2422	664	745	57	4420	13%	58%	16%	18%	1%	106%	1.9	8.7	2.4	2.7	0.2	16.0
2017	244	2825	528	745	67	4208	6%	63%	13%	18%	2%	101%	0.9	9.5	1.9	2.7	0.2	15.2
2018	216	2273	681	788	71	4029	5%	55%	16%	19%	2%	97%	0.8	8.2	2.5	2.8	0.3	14.5
2019	244	2155	783	788	71	4042	6%	52%	19%	19%	2%	97%	0.9	7.8	2.8	2.8	0.3	14.6
2020	144	2017	1141	831	71	4204	3%	49%	27%	20%	2%	101%	0.5	7.3	4.1	3.0	0.3	15.2
2021	172	2038	954	810	71	4045	4%	49%	23%	19%	2%	97%	0.6	7.4	3.4	2.9	0.3	14.6
2022	172	2027	1107	779	71	4157	4%	49%	27%	19%	2%	100%	0.6	7.3	4.0	2.8	0.3	15.0
2023	4	2006	1192	779	71	4053	0%	48%	29%	19%	2%	98%	0.0	7.2	4.3	2.8	0.3	14.6
2024	80	2113	1005	779	71	4048	2%	51%	24%	19%	2%	97%	0.3	7.6	3.6	2.8	0.3	14.6
2025	84	2219	1209	779	71	4363	2%	53%	29%	19%	2%	105%	0.3	8.0	4.4	2.8	0.3	15.8
2026	0	1995	1328	779	71	4174	0%	48%	32%	19%	2%	100%	0.0	7.2	4.8	2.8	0.3	15.1
2027	100	1622	1669	779	71	4241	2%	39%	40%	19%	2%	102%	0.4	5.9	6.0	2.8	0.3	15.3
2028	100	2849	2044	779	71	5843	2%	69%	49%	19%	2%	141%	0.4	10.3	7.4	2.8	0.3	21.1
2029	0	2550	2674	779	71	6074	0%	61%	64%	19%	2%	146%	0.0	9.2	9.7	2.8	0.3	21.9
2030	0	2550	2912	771	71	6304	0%	61%	70%	19%	2%	152%	0.0	9.2	10.5	2.8	0.3	22.8
2031	0	2401	2946	736	71	6154	0%	58%	71%	18%	2%	148%	0.0	8.7	10.6	2.7	0.3	22.2
2032	0	1686	4019	736	71	6512	0%	41%	97%	18%	2%	157%	0.0	6.1	14.5	2.7	0.3	23.5
2033	0	1344	4377	732	71	6524	0%	32%	105%	18%	2%	157%	0.0	4.9	15.8	2.6	0.3	23.6
2034	0	1387	4513	684	71	6655	0%	33%	109%	16%	2%	160%	0.0	5.0	16.3	2.5	0.3	24.0
2035	0	918	4768	688	0	6374	0%	22%	115%	17%	0%	153%	0.0	3.3	17.2	2.5	0.0	23.0
2036	0	1184	4649	805	0	6639	0%	29%	112%	19%	0%	160%	0.0	4.3	16.8	2.9	0.0	24.0
2037	0	523	5160	727	0	6410	0%	13%	124%	18%	0%	154%	0.0	1.9	18.6	2.6	0.0	23.1
2038	0	843	4905	805	0	6553	0%	20%	118%	19%	0%	158%	0.0	3.0	17.7	2.9	0.0	23.7
2039	0	704	5024	749	0	6477	0%	17%	121%	18%	0%	156%	0.0	2.5	18.1	2.7	0.0	23.4
2040	0	309	5330	706	0	6346	0%	7%	128%	17%	0%	153%	0.0	1.1	19.2	2.5	0.0	22.9
2041	0	0	2282	637	0	2919	0%	0%	55%	15%	0%	70%	0.0	0.0	8.2	2.3	0.0	10.5

Attachment D4

Weld Station Calculation

Table D4-1. Weld Station Throughput Requirements

Year	No. of Waste Packages	No. of Weld Stations ¹	Notes
2010	74	2.3	Module 1—11 Weld Stations
2011	150	4.6	
2012	242	7.4	Module 2—Add 6 Weld Stations
2013	338	10.4	
2014	461	14.2	
2015	507	15.6	
2016	512	15.7	
2017	508	15.6	
2018	522	16.1	
2019	496	15.3	
2020	532	16.4	
2021	539	16.6	
2022	542	16.7	
2023	540	16.6	
2024	537	16.5	
2025	545	16.8	Maximum Weld Stations Required = 17
2026	534	16.4	Maximum Weld Stations Required = 17
2027	545	16.8	
2028	526	16.2	
2029	539	16.6	
2030	528	16.2	
2031	529	16.3	
2032	438	13.5	
2033	500	15.4	
2034	469	14.4	
2035	520	16.0	
2036	513	15.8	
2037	534	16.4	
2038	531	16.3	
2039*	532	16.4	
2040*	486	14.9	
Total	14,769		Total 17 Weld Stations

¹ Weld Station Capacity is calculated as follows:

Hours available per year	= 6,000 hours (based on 5 days per week, 50 weeks per year)
Welding time	= 135 hours per Waste Package
Weld Station Capacity	= 6,000 hours / 135 hours per WP X 77% Productivity Scaling Factor
X 95% Maintenance Availability Factor	= 32.511 Waste Packages per Weld Station
Maximum No. of Weld Stations Required	= 545 WP/year (for 2025 & 2027) / 32.511 = 16.8

**White Paper:
Waste Handling Building Conceptual Study**

TDR-WHS-SE-000002 REV 00

APPENDIX E

Design Basis Event Assessment

INTENTIONALLY LEFT BLANK

CONTENTS

	Page
1. INTRODUCTION	E-1
2. IDENTIFICATION OF INITIATING EVENTS AND EVENT FREQUENCIES	E-1
3. MITIGATED EVENT SEQUENCES	E-1
4. SUMMARY OF RESULTS	E-2

INTENTIONALLY LEFT BLANK

TABLES

	Page
Table E-1. Initial Safety Evaluation of WHB Conceptual Design	E-5
Table E-2. Mitigated Event Sequences	E-7
Table E-3. Category 1 and Category 2 DBEs Associated with SR Design	E-8
Table E-4. Comparison of Lifts	E-9
Table E-5. Summary Comparison of WHB Conceptual Design with SR Design.....	E-9

INTENTIONALLY LEFT BLANK

Appendix E

Design Basis Event Assessment

1. INTRODUCTION

A preliminary design basis event (DBE) assessment was performed to identify the potential preclosure DBEs associated with the proposed Waste Handling Building (WHB) conceptual design. This analysis did not include the Fuel Staging Area nor transportation of casks/WPs to and from the FSA. This preliminary assessment also compared the results with *Design Basis Event Frequency and Dose Calculation for Site Recommendation* (SR) (CRWMS M&O 2000c). The potential DBEs identified for the WHB conceptual design were identified based on evaluation of the design drawings and operational concept. Implicit to this assessment is the assumption that the preclosure safety strategy (Table A-2) is implemented.

Handling of dual-purpose canisters (DPCs) and multi-purpose canisters (MPCs) that contain commercial SNF was not considered in the DBE assessment. An analysis of the potential event sequences associated with these canisters will be performed at a later date.

2. IDENTIFICATION OF INITIATING EVENTS AND EVENT FREQUENCIES

Upon review of the WHB conceptual design and the waste handling operational steps, a list of potential initiating events was developed. Initiating events are defined as those events that could potentially lead to a radiological release. The unmitigated initiating event frequency was estimated by multiplying the maximum annual throughput (e.g., handlings/year) by the estimated failure rate (e.g., drops/handling). The unmitigated initiating event frequency does not account for any design features that could potentially prevent a release or reduce the frequency of a release scenario. The unmitigated DBE category (Category 1 or Category 2) was then determined for each initiating event, based on the initiating event frequency and the DBE definitions in the "Revised Interim Guidance Pending Issuance of New U.S. Nuclear Regulatory Commission (NRC) Regulations (Revision 01, July 22, 1999), for Yucca Mountain, Nevada" (Revised Interim Guidance) (Dyer 1999). A Category 1 event is defined as an event having a frequency greater than 10^{-2} per year and a Category 2 event having a frequency not greater than 10^{-2} per year. Finally, the preclosure safety strategy was considered with respect to the initiating event and a judgement was made as to whether the design could prevent a radiological release from occurring. The evaluation described in this section is documented in tabular form in Table E-1 of this appendix.

3. MITIGATED EVENT SEQUENCES

DBE categories in the Revised Interim Guidance (Dyer 1999) are defined solely on the frequency of occurrence of a given event sequence and do not depend on the event consequence. However, for the purpose of this assessment and for consistency with the DBE analysis for Site Recommendation (SR), only event sequences that could potentially lead to a radiological release are considered.

Event sequences that begin with the initiating events identified above and end with a postulated radiological release were postulated and evaluated in Table E-2 of this appendix. The estimated frequencies of release identified in Table E-2 apply to the postulated event sequence with credit for the assumed design features present. This is the event sequence frequency that would be expected for a DBE analysis of the final design. Again, the design assumptions are consistent with the preclosure safety strategy (Table A-2). Also shown in Table E-2 are the DBE categories associated with the expected, mitigated event sequences and the material-at-risk (MAR) for the credible event sequences that result in a radiological release. The MAR refers to the maximum amount of radioactive material (e.g., spent fuel assemblies) that is potentially available for release during a given accident.

Table E-3 of this appendix contains the comparable list of Category 1 and Category 2 DBEs associated with the SR design.

4. SUMMARY OF RESULTS

From a preclosure safety perspective, the WHB conceptual design compares favorably with the SR design for the following reasons:

- Fewer overall lifts
- Fewer Category 1 events
- No SFA basket events
- No Category 2 event sequences that result in a release (for the Non-Rotating WP Design)
- No events involving unsealed DCs (for the Non-Rotating WP Design)
- Lower annual dose for Category 1 events
- Potential to downgrade HVAC system from QL-2 to QL-3

Although both WHB designs are capable of meeting the dose limits for Category 1 and Category 2 DBEs, the WHB conceptual design appears to provide additional safety margin by reducing both the number of potential DBEs and the bounding radiological consequences.

Table E-4 shows the number of individual lifts and annual lifts, assuming maximum throughput, for the WHB conceptual design compared to the SR design. In each design, the optional storage operation is included in the lift data. This is a conservative assumption that maximizes the number of lifts in both designs.

Table E-5 also compares the consequences for the bounding Category 1 and Category 1 DBEs associated with each design. For the SR design, the bounding consequence Category 1 DBE is the breach of 8-PWR spent fuel assemblies (SFAs) resulting from a SFA basket drop onto another basket in the Assembly Transfer System hot cell. The bounding consequence Category 2 DBE is a shipping cask drop into the Cask Preparation Pit, which results in the breach 68-BWR SFAs. For the WHB conceptual design, the bounding consequence Category 1 DBE breaches only 2-PWR SFAs, a drop of one SFA onto another, because the SFA baskets are eliminated from the design. There are no Category 2 DBE consequences associated with the Non-Rotating

WP Design because all potential cask, canister, and DC/WP drops that lead to a release are assumed to be prevented by design (i.e., become Beyond Design Basis Events [BDBEs]). However, the Turntable Design has Category 2 DBEs that exceed the current WP design basis and lead to significant radiological releases.

The annual Category 1 dose and the maximum individual Category 1 dose (used for classification purposes) for each design is shown in Table E-5. The methodology for estimating the doses associated with the WHB conceptual design is consistent with the methodology used in the dose calculation for *Design Basis Event Frequency and Dose Calculation for Site Recommendation* (SR) (DIRS 150276). The annual Category 1 DBE dose (0.01 mrem/year) and the maximum individual Category 1 DBE dose (1.0 mrem/event) are slightly lower for the WHB conceptual design because there are fewer Category 1 DBEs and fewer SFAs involved in the accidents. The reduction in the individual Category 1 DBE dose from 5.0 mrem/event to 1.0 mrem/event is potentially significant because the classification process (QAP-2-3, Rev. 10) uses a dose cutoff of 25 mrem/event to determine whether a system, structure or component is classified as QL-2 or QL-3. This could potentially allow the WHB HVAC system to be reclassified from QL-2 to QL-3, which would decrease the facility design and operational costs.

INTENTIONALLY LEFT BLANK

Table E-1. Initial Safety Evaluation of WHB Conceptual Design

Potential Initiating Events ⁽¹⁾	Maximum Throughput (operations/year)	Failure Rate (events/operation)	Unmitigated Initiating Event Frequency (events/year) ⁽²⁾	Unmitigated DBE Category ⁽³⁾	Can Release be Prevented by Design? ⁽⁴⁾	Assumptions
Cask (w/o impact limiter) Events:						Max. cask throughput based on Case 33, Year 2013
Fire/Explosion on rail car	902	TBD	TBD	TBD	Y	Probability of release expected to be incredible
Cask drop onto rail bed	902	1.4E-05	1.3E-02	1	Y	Impact < cask design basis
Cask drop into rail trench	902	1.4E-05	1.3E-02	1	Y	Design features to limit drop height to below cask DB.
Cask transporter collision with another transporter on rail	902	3.0E-06	2.7E-03	2	Y	Impact < cask design basis
Handling equipment drop onto cask	902	1.8E-07	1.6E-04	2	Y	Impact < cask design basis
Shield door closes on cask	902	1.0E-07	9.0E-05	2	Y	Impact < cask design basis
Cask drop onto floor during lift onto transfer cart	902	1.4E-05	1.3E-02	1	Y	Impact < cask design basis
Cask drop from 2-Block height	902	1.4E-07	1.3E-04	2	Y	Design to incorporate physical stops to prevent 2-block height from exceeding design basis.
Seismic tipover on transfer cart	902	N/A	1.0E-04	2	Y	Design to FC-2 DBEQ
Seismic tipover on jack screw	902	N/A	1.0E-04	2	Y	Design to FC-2 DBEQ
Cask drop during lowering in cask prep (cart on jack screw with lid unsealed)	902	TBD	TBD	TBD	Y	Probability of release expected to be incredible based on conceptual cart & jack screw design
Cask drop during cask lifting/lowering in transfer cell (cart on jack screw with lid unsealed)	902	TBD	TBD	TBD	Y	Probability of release expected to be incredible based on conceptual cart & jack screw design
SFA Events:						Max. SFA throughput based on Case 32, Year 2035
SFA drop into cask	12942	1.8E-05	2.3E-01	1	N	SFAs breach with any impact
SFA drop onto floor	12942	1.8E-05	2.3E-01	1	N	"
SFA drop into DC	12942	1.8E-05	2.3E-01	1	N	"
Inner DC lid drop onto SFA	12942	1.8E-05	2.3E-01	1	N	"
Shield plug drop onto SFA	12942	1.8E-05	2.3E-01	1	N	"
SFA drop into CSNF storage rack during lowering	12942	1.8E-05	2.3E-01	1	N	"
SFA drop into CSNF storage rack during lifting onto cart	12942	1.8E-05	2.3E-01	1	N	"
SFA collision with handling machine, crane or canister	12942	3.0E-06	3.9E-02	1	N	"
SFA cladding exceeds thermal limit in lag storage rack	12942	TBD	TBD	TBD	Y	Probability of release expected to be incredible based on maximum storage capacity (140 SFAs) and age of CSNF
Canister Events:⁽⁵⁾						Canister throughput based on Case 32, Year 2020
Canister drop into cask	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis
Canister drop onto floor	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis
Canister drop into DC	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis
Canister drop from 2-block height	1039	1.4E-07	1.5E-04	2	Y	Design to incorporate physical stops to prevent 2-block height from exceeding design basis.
Inner DC lid drop onto Canister	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis
Shield plug drop onto canister	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis
Canister drop onto SFAs in CSNF storage rack	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis.

Table E-1. Initial Safety Evaluation of WHB Conceptual Design, continued

Canister drop into lag storage area	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis.
Canister drop onto another canister in DC	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis
Defective canister drop from normal lift height	1039	TBD	TBD	TBD	Y	Probability of release scenario expected to be incredible
Heavy object drop onto canister	1039	1.4E-05	1.5E-02	1	Y	Impact < canister design basis.
Unsealed WP Events:						Maximum throughput of 600 WPs per year assumed
Unsealed WP tipover off transfer cart due to seismic event or random failure of cart/rail restraints during transfer to welding area (Non-Rotating WP Design Alternative only)	600	TBD	TBD	TBD	Y	Cart/Rail restraints designed to withstand Frequency Category-2 (1E-4/year) design basis earthquake.
Sealed WP Events:						
WP tipover off transfer cart due to seismic event or random failure of cart/rail restraints during transfer to Transporter Load Cell (Non-Rotating WP Design Alternative only)	600	TBD	TBD	TBD	Y	Cart/Rail restraints designed to withstand Frequency Category-2 (1E-4/year) design basis earthquake.
Sealed WP drop onto floor or tilting fixture during crane lift onto tilting fixture	600	1.4E-05	8.4E-03	2	Y	Potential impact does not exceed WP design basis
Transporter derailment and collision between WHB and North Portal	600	TBD	TBD	TBD	Y	Transporter design features ensure that impacts to the WP do not exceed WP design basis
Fire on electric prime mover breaches WP	TBD	TBD	TBD	TBD	Y	WP designed to withstand maximum credible fire
WP horizontal drop onto floor during lift onto Transporter pallet	600	1.4E-05	8.4E-03	2	Y	Potential impact does not exceed WP design basis
Defective WP drop from normal lift height breaches WP	600	1.4E-05	8.4E-03	2	Y	Probability of release scenario expected to be incredible
Additional Events Related to Turntable Design Alternative:						
Unsealed WP drop by DC handling crane from normal lift height (1-2') during transfer to welding area	600	TBD	TBD	TBD	Y	Administrative controls and/or crane design features (e.g., limit switches, yoke length, speed controls) ensure that drop does not result in a WP breach.
Unsealed WP drop during crane lift into weld station preparation area	600	1.4E-05	8.4E-03	2	N	Potential for 23' 6" drop. Design features and administrative controls unable to prevent a release.
Sealed WP drop during crane lift off weld turntable and out of weld station preparation area	600	1.4E-05	8.4E-03	2	Y	Potential for 23' 6" drop, which exceeds current WP design basis. Prevention would involve major redesign of WP.
Sealed WP drop during crane lift into pit in WP Transporter Load Cell	600	1.4E-05	8.4E-03	2	Y	Potential for 23' 6" drop, which exceeds current WP design basis. Prevention would involve major redesign of WP.
Sealed WP drop during crane lift out of pit in WP Transporter Load Cell and into WP tilting fixture	600	1.4E-05	8.4E-03	2	Y	Potential for 23' 6" drop, which exceeds current WP design basis. Prevention would involve major redesign of WP.
Notes:						
(1) Potential initiating events associated with pad storage (WP or cask) are not included.						
(2) Unmitigated event frequency is equal to maximum throughput multiplied by the estimated failure rate.						
(3) DBE category is based on unmitigated initiating event frequency; does not consider or credit preventive or mitigative design features.						
(4) Determination of whether an event can be prevented by design is based on the assumed implementation of the Preclosure Safety Strategy (Appendix A). An event sequence is considered prevented if the frequency is less than 10 ⁻⁶ per year (incredible).						
(5) This analysis is not applicable to naval canisters, dual-purpose canisters (DPCs), or multi-purpose canisters (MPCs). For naval fuel, credit is taken for the cladding integrity and off-site dose consequence of a potential canister breach is below regulatory limits. DPC and MPC event sequences will be analyzed at a later date.						
Legend:						
Shaded events are assumed to result in a radiological release.						

Table E-2. Mitigated Event Sequences

Potential Events	Estimated Frequency of Release	DBE Category	Material-At-Risk
Cask (w/o impact limiter) Events:			
Fire/Explosion on rail car	$< 10^{-6}/\text{yr}$	BDBE	N/A
Cask drop onto rail bed	$< 10^{-6}/\text{yr}$	BDBE	N/A
Cask drop into rail trench	$< 10^{-6}/\text{yr}$	BDBE	N/A
Cask transporter collision with another transporter on rail	$< 10^{-6}/\text{yr}$	BDBE	N/A
Handling equipment drop onto cask	$< 10^{-6}/\text{yr}$	BDBE	N/A
Shield door closes on cask	$< 10^{-6}/\text{yr}$	BDBE	N/A
Cask drop onto floor during lift onto transfer cart	$< 10^{-6}/\text{yr}$	BDBE	N/A
Cask drop from 2-Block height	$< 10^{-6}/\text{yr}$	BDBE	N/A
Seismic tipover on transfer cart	$< 10^{-6}/\text{yr}$	BDBE	N/A
Seismic tipover on jack screw	$< 10^{-6}/\text{yr}$	BDBE	N/A
Cask drop during lowering in cask prep (cart on jack screw with lid unsealed)	$< 10^{-6}/\text{yr}$	BDBE	N/A
Cask drop during cask lifting/lowering in transfer cell (cart on jack screw with lid unsealed)	$< 10^{-6}/\text{yr}$	BDBE	N/A
SFA Events:			
SFA drop into cask	$> 10^{-4}/\text{yr}$	1	1-2 assemblies
SFA drop onto floor	$> 10^{-4}/\text{yr}$	1	1 assembly
SFA drop into DC	$> 10^{-4}/\text{yr}$	1	1 assembly
Inner DC lid drop onto SFA	$> 10^{-4}/\text{yr}$	1	1 assembly
Shield plug drop onto SFA	$> 10^{-4}/\text{yr}$	1	1 assembly
SFA drop into CSNF storage rack during lowering	$> 10^{-4}/\text{yr}$	1	1-2 assemblies
SFA drop into CSNF storage rack during lifting onto cart	$> 10^{-4}/\text{yr}$	1	1-2 assemblies
SFA collision with handling machine, crane or canister	$> 10^{-4}/\text{yr}$	1	1 assembly
SFA cladding overheats in lag storage rack	$< 10^{-6}/\text{yr}$	BDBE	N/A
Canister Events:⁽¹⁾			
Canister drop into cask	$< 10^{-6}/\text{yr}$	BDBE	N/A
Canister drop onto floor	$< 10^{-6}/\text{yr}$	BDBE	N/A
Canister drop into DC	$< 10^{-6}/\text{yr}$	BDBE	N/A
Canister drop from 2-block height	$< 10^{-6}/\text{yr}$	BDBE	N/A
Inner DC lid drop onto Canister	$< 10^{-6}/\text{yr}$	BDBE	N/A
Shield plug drop onto canister	$< 10^{-6}/\text{yr}$	BDBE	N/A
Canister drop onto SFAs in CSNF storage rack	$< 10^{-6}/\text{yr}$	BDBE	N/A
Canister drop into lag storage area	$< 10^{-6}/\text{yr}$	BDBE	N/A
Canister drop onto another canister in DC	$< 10^{-6}/\text{yr}$	BDBE	N/A
Defective canister drop from normal lift height	$< 10^{-6}/\text{yr}$	BDBE	N/A
Heavy object drop onto canister	$< 10^{-6}/\text{yr}$	BDBE	N/A
Unsealed WP Events:			
Unsealed WP tipover off transfer cart due to seismic event or random failure of cart/rail restraints during transfer to welding area (Non-Rotating WP Design Alternative)	$< 10^{-6}/\text{yr}$	BDBE	N/A
Sealed WP Events:			
Sealed WP drop onto floor or tilting fixture during crane lift onto tilting fixture	$< 10^{-6}/\text{yr}$	BDBE	N/A
Transporter derailment and collision between WHB and North Portal or pad storage	$< 10^{-6}/\text{yr}$	BDBE	N/A
Fire on electric prime mover	$< 10^{-6}/\text{yr}$	BDBE	N/A
WP horizontal drop onto floor	$< 10^{-6}/\text{yr}$	BDBE	N/A
Defective WP drop from normal lift height	$< 10^{-6}/\text{yr}$	BDBE	N/A
Additional Events Related to Turntable Design Alternative:			
Unsealed WP drop by DC handling crane from normal lift height (1-2') during transfer to welding turntable	$< 10^{-6}/\text{yr}$	BDBE	N/A
Unsealed WP drop during crane lift into weld station preparation area	$> 10^{-6}/\text{yr}$	2	21-PWR or 44-BWR SFAs
Sealed WP drop during crane lift off weld turntable and out of weld station preparation area	$< 10^{-6}/\text{yr}$	BDBE	N/A
Sealed WP drop during crane lift into pit in WP Transporter Load Cell	$< 10^{-6}/\text{yr}$	BDBE	N/A
Sealed WP drop during crane lift out of pit in WP Transporter Load Cell and into WP tilting fixture	$< 10^{-6}/\text{yr}$	BDBE	N/A

Notes: (1) This analysis is not applicable to naval canisters, dual-purpose canisters (DPCs), or multi-purpose canisters (MPCs). For naval fuel, credit is taken for the cladding integrity and off-site dose consequence of a potential canister breach is below regulatory limits. DPC and MPC event sequences will be analyzed at a later date.

Table E-3. Category 1 and Category 2 DBEs Associated with SR Design

Category 1 Events*

Event #	Category 1 Events	Location	Material at Risk (# SFAs)		Sequence Frequency (per year)
			PWR	BWR	
1-01	SFA Drop Onto Another SFA in Cask	Cask Unloading Pool	2	2	2.34E-01
1-02	SFA Collision	ATS Pool	1	1	3.90E-02
1-03	SFA Drop Onto Empty Basket	ATS Pool	1	1	4.22E-02
1-04	SFA Drop Onto Another SFA in Basket Staging Rack (Lowering Into)	ATS Pool	2	2	1.92E-01
1-05	Basket Drop Onto Another Basket in Basket Staging Rack (Lifting Out)	ATS Pool	8	16	4.10E-02
1-06	Basket Drop Onto Another Basket in Pool (Transfer Into Pool Storage)	ATS Pool	8	16	4.10E-02
1-07	Basket Drop Onto Another Basket in Pool (Transfer Out of Pool Storage)	ATS Pool	8	16	4.10E-02
1-08	Basket Drop Onto Transfer Cart or Pool Floor	ATS Pool	4	8	4.10E-02
1-09	Basket Drop Back Into Pool	ATS Pool	4	8	4.10E-02
1-10	Basket Drop Onto ATS Hot Cell Floor	ATS Hot Cell	4	8	4.10E-02
1-11	Basket Drop Onto Another Basket in Dryer	ATS Hot Cell	8	16	4.10E-02
1-12	SFA Drop Onto Another SFA in Dryer	ATS Hot Cell	2	2	2.34E-01
1-13	SFA Drop Onto ATS Hot Cell Floor	ATS Hot Cell	1	1	2.34E-01
1-14	SFA Drop Onto Another SFA in DC	ATS Hot Cell	2	2	2.34E-01

Category 2 Events*

Event #	Category 2 Events	Location	Material at Risk (# SFAs)		Sequence Frequency (per year)
			PWR	BWR	
2-01	Basket Collision During Transfer to Pool Storage	ATS Pool	4	8	6.83E-03
2-02	Basket Collision During Transfer to Incline Transfer Canal	ATS Pool	4	8	6.83E-03
2-03	Uncontrolled Descent of Incline Transfer Cart	ATS Pool	4	8	6.83E-03
2-04	Handling Equipment Drop Onto SFA in Pool	ATS Pool	1	1	2.38E-03
2-05	Handling Equipment Drop Onto SFA in Hot Cell	ATS Hot Cell	1	1	2.38E-03
2-06	Handling Equipment Drop Onto SFA Basket in Pool	ATS Pool	4	8	1.74E-03
2-07	Handling Equipment Drop Onto SFA Basket in Hot Cell	ATS Hot Cell	4	8	6.95E-05
2-08	Unsealed DC Collision	DC Handling Cell	21	44	1.80E-03
2-09	Unsealed DC Drop and Slapdown	DC Handling Cell	21	44	8.40E-03
2-10	Handling Equipment Drop Onto Unsealed DC	DC Handling Cell	21	44	1.10E-04
2-11	Shipping Cask Drop Into Cask Preparation Pit	ATS Cask Preparation Pit	24	68	8.68E-03
2-12	Shipping Cask Drop Into Cask Unloading Pool	ATS Pool	24	68	8.68E-03

* Events Taken from *Design Basis Event Frequency and Dose Calculation for Site Recommendation* (CRWMS M&O 2000c)

Table E-4. Comparison of Lifts

Container	SR Design		Conceptual Design (Non-Rotating WP Alternative)		Conceptual Design (Turntable Alternative)	
	Individual Lifts	Total Lifts/Year	Individual Lifts	Total Lifts/Year	Individual Lifts***	Total Lifts/Year
Casks	3	1,860	2	1,804	2	1,804
CSNF SFAs*	2	26,026	2	25,884	2	25,884
CSNF Baskets*	4	9,112	0	0	0	0
Canisters*	2	2,124	2	2,078	2	2,078
DCs (unsealed WPs)	2	1,200	0	0	1	600
WPs	3	1,800	3**	1,800	6	3,600
Totals:	16	42,122	9	31,566	13	33,966

* Includes interim lag storage operation.

** Includes lift onto tilting fixture and two lifts associated with pad storage operation.

*** Same as Non-Rotating Design except for 4 additional lifts associated with Turntable Design.

Table E-5. Summary Comparison of WHB Conceptual Design with SR Design

Measure	SR Design	Conceptual Design	
		Non-Rotating WP	(Turntable)
Category 1 Events	14	8	8
Category 2 Events	12	0	1
Max Cat. 1 Material-At-Risk	8-PWR	2-PWR	2-PWR
Max Cat. 2 Material-At-Risk	68-BWR	None	44-BWR
Annualized Cat. 1 Filtered Dose (1)	0.06 mrem/yr	0.01 mrem/yr	0.01 mrem/yr
Max. Individual Unfiltered Cat. 1 Dose (1) (2)	5.0 mrem/event	1.0 mrem/event	1.0 mrem/event
Max. Individual Unfiltered Cat. 2 Dose (1)	0.02 rem/event	None	1.4 rem/event
Meets Regulatory Dose Limits?	Yes	Yes	Yes

(1) Doses are off-site, not occupational

(2) 25 mrem < Cat. 1 Dose < 100 mrem —> QL-2 HEPA filters, per QAP-2-3 Rev. 10.

**White Paper:
Waste Handling Building Conceptual Study**

TDR-WHS-SE-000002 REV 00

APPENDIX F

Cost Estimate

INTENTIONALLY LEFT BLANK

CONTENTS

1. INTRODUCTION.....	F-1
2. BASIS AND ASSUMPTIONS FOR COST ESTIMATE.....	F-1
3. COST ESTIMATE.....	F-4

Page

INTENTIONALLY LEFT BLANK

TABLES

	Page
F-1. Construction Cost Estimate Alternatives/Options.....	F-1
F-2. Construction Cost Summary	F-2
F-3. Construction Costs: Module 1, Construction Option NR-1A 17 Welders Non-rotating WP Design Alternative	F-5
F-4. Construction Costs: Module 2, Construction Option NR-1A 17 Welders Non-rotating WP Design Alternative	F-6
F-5. Construction Costs: Module 3, Construction Option NR-1A 17 Welders Non-rotating WP Design Alternative	F-7
F-6. Construction Costs: Modules 1 and 2, Construction Option NR-1B 17 Welders Non-rotating WP Design Alternative	F-8
F-7. Construction Costs: Module 3, Construction Option NR-1B 17 Welders Non-rotating WP Design Alternative	F-9
F-8. Construction Costs: Module 1, Construction Option T-1A 17 Welders Turntable Design Alternative.....	F-10
F-9. Construction Costs: Module 2, Construction Option T-1A 17 Welders Turntable Design Alternative.....	F-11
F-10. Construction Costs: Module 3, Construction Option T-1A 17 Welders Turntable Design Alternative.....	F-12
F-11. Construction Costs: Modules 1 and 2, Construction Option T-1B 17 Welders Turntable Design Alternative.....	F-13
F-12. Construction Costs: Module 3, Construction Option T-1B 17 Welders Turntable Design Alternative.....	F-14
F-13. Construction Costs: Fuel Staging Area.....	F-15
F-14. WHB Equipment List Non-rotating WP Design Alternative.....	F-16
F-15. WHB Equipment List Turntable Design Alternative	F-21

INTENTIONALLY LEFT BLANK

Appendix F

Cost Estimate

1. INTRODUCTION

This appendix includes the estimate basis and construction cost estimates for the following alternatives/options.

Table F-1. Construction Cost Estimate Alternatives/Options

Alternatives/Options	Description
Non-Rotating Waste Package Design Alternative, Construction Option NR-1A	Module 1 in Phase 1, Module 2 in Phase 2, and Module 3 in Phase 3
Non-Rotating Waste Package Design Alternative, Construction Option NR-1B	Module 1 and 2 in Phase 1, Module 3 in Phase 2
Turntable Design Alternative, Construction Option T-1A	Module 1 in Phase 1, Module 2 in Phase 2, and Module 3 in Phase 3
Turntable Design Alternative, Construction Option T-1B	Module 1 and 2 in Phase 1, Module 3 in Phase 2

A separate line item estimate is also presented for the cost of the Fuel Staging Area. A summary of the construction cost is shown in Table F-2.

2. BASIS AND ASSUMPTIONS FOR COST ESTIMATE

1. This estimate combines the Waste Handling Building, the Waste Treatment Building, and the Carrier Preparation Building into a single operating entity, as shown in the figures in Appendix B.
2. Modules 2 and 3 have a 25 percent adder to the installation labor due to security concerns, plant access, and congestion due to construction in an operating area.
3. The wage rates are based on *Project Labor Agreement for Tunnel and Tunnel-Shaft Construction between Bechtel Nevada Corporation and Laborers' International Union of North America, Local Union No. 872*. (DIRS 108532).
4. Material and equipment costs are in terms of 1998 dollars.
5. Escalation is based on the *Cost Escalation and Interest Rates for 2000* (DIRS 150784) is 4.7 percent.
6. All equipment includes 2.5 percent freight charge.

Table F-2. Construction Cost Summary

Design Alternative	Construction Option	Phase	Total Direct Cost	Total Indirect Cost	Total Capital Cost	Cost Estimate Reference Table
Non-Rotating WP Design Alternative						
	Option NR-1A					
Module 1		1	\$ 260,469,146	\$ 99,647,263	\$ 360,116,409	F-3
Module 2		2	\$ 92,648,077	\$ 35,163,050	\$ 127,811,127	F-4
Module 3		3	\$ 47,200,716	\$ 18,897,818	\$ 66,098,534	F-5
	Total-Option NR-1A		\$ 400,317,939	\$ 153,708,131	\$ 554,026,070	
	Option NR-1B					
Modules 1 and 2		1	\$ 347,039,204	\$ 132,209,184	\$ 479,248,388	F-6
Module 3		2	\$ 47,200,716	\$ 18,897,818	\$ 66,098,534	F-7
	Total-Option NR-1B		\$ 394,239,920	\$ 151,107,002	\$ 545,346,922	
Turntable Design Alternative						
	Option T-1A					
Module 1		1	\$ 272,880,414	\$ 104,102,324	\$ 376,982,738	F-8
Module 2		2	\$ 93,870,897	\$ 35,582,355	\$ 129,453,252	F-9
Module 3		3	\$ 47,200,716	\$ 18,897,818	\$ 66,098,534	F-10
	Total-Option T-1A		\$ 413,952,027	\$ 158,582,497	\$ 572,534,524	
	Option T-1B					
Modules 1 and 2		1	\$ 362,238,504	\$ 137,499,475	\$ 499,737,979	F-11
Module 3		2	\$ 47,200,716	\$ 18,897,818	\$ 66,098,534	F-12
	Total-Option T-1B		\$ 409,439,220	\$ 156,397,293	\$ 565,836,513	
Fuel Staging Area						
485 Storage Casks		NA	\$ 402,881,543	\$ 6,556,641	\$ 409,438,184	F-13

7. Bulk Materials, such as siding, roofing, concrete, steel, architectural finishes, conduit, and cable, were priced from *Heavy Construction Cost Data, 1998* (DIRS 100513).
8. Equipment installation hours were based on *Process Plant Construction Estimating Standards* (DIRS 151433), *Heavy Construction Cost Data, 1998* (DIRS 100513), in-house units, and similar DOE projects.
9. Bulk material installation units were from *Building Construction Cost Data, 1998* (DIRS 151437), *Process Plant Construction Estimating Standards* (DIRS 151433), and *Heavy Construction Cost Data, 1998* (DIRS 100513).
10. The installation of the equipment and material is done with a mixture of craft trades making up a crew, which includes part of a foreman's hours.
11. The civil account is mainly excavation, backfill, compaction, and hauling away excess excavation. All excavation is assumed to be suitable for backfill. The civil work is a take-off from the drawings.
12. The administration and cold support areas are all part of Module 1. Office furniture is added with the construction of each additional module.
13. The concrete account is a material take off from the drawings and consists of floor slabs, walls and elevated floors. There are two types of elevated floors: solid concrete floors and elevated floors on metal decking.
14. The steel account is a material take off from the building steel, stainless steel liner plate, HVAC stack, and other steel shapes.
15. The building account consists of HVAC equipment, HVAC ducting, duct supports, piping, controls, dampers, insulation, and duct accessories. The HVAC duct is based on pounds per square foot and the duct accessories, supports, dampers, insulation, and testing of the HVAC system as a percentage of the duct labor and material cost. Ducting material and installation are from *Building Construction Cost Data, 1998* (DIRS 151437). This account also includes numerous architectural furnishings and finishes including roofing materials, metal siding, doors, floor coverings, elevators, interior walls, and toilet fixtures. The fire protection system is in this account and is based on the building square footage. The interior furnishings and finishes are based on the total square footage of all three modules.
16. The equipment account contains all the Mechanical and Process equipment. The cranes and manipulators are tested in place to show that they perform properly. Also in this account are building of the prototype equipment, testing of this equipment, and testing of different equipment assemblies to verify performance.
17. The piping account consists of two categories. They are allowances for systems that are mentioned in the SR and systems that are factored from the process equipment. The

allowances are for systems such as helium, argon, utility piping, breathing, and compressed air. The factored piping is 20 percent of the process equipment cost, which is further split 50 percent labor and 50 percent material. The labor dollars are divided by the current labor rate to arrive at an hour total for that system. All piping is tested using the man-hours for that system times 5 percent.

18. The electrical account contains the power requirements for the building, lighting, electrical for instrumentation, ES&H instrumentation electrical, and all monitoring and control bulk electrical materials. This account also includes bulk material for the instruments that were factored from the process equipment. This cost is 5 percent of the instrument cost. This is further broken down into labor and material. Testing of all electrical cable is at 5 percent of the bulk material installation hours. A factor of 1 percent is added to the shield doors to allow for electrical bulks. The number of motor control centers was increased from 8 to 12 due to the increase in power requirements. Lighting is based on a square foot of floor space.
19. The instrument account includes instruments that were factored from the process equipment and ES&H instruments. The factored instruments are 35 percent of the equipment costs, reduced to direct hours and material costs. Testing for these instruments is 15 percent of the installation hours. The ES&H instruments installation for the plant operation is based on the requirements as directed in the SR, which includes manufacture's shop and field testing.
20. The painting account is a material take off from the coating of the concrete walls, painting of the building steel, doors, and stack. Painting of the piping is in two sections. These sections are for the piping allowances and the piping that was factored from the process equipment. The allowance for painting process piping was 2 percent of the process equipment cost, further reduced into labor and material.
21. The insulation account contains allowances for the piping system mentioned above, installed as a percent of the equipment costs. This cost is 6 percent of the process equipment cost, and is 40 percent labor and 60 percent material. The other cost is for the factored piping and this cost is 6 percent of the equipment, which is reduced to a labor and material cost.
22. The Fuel Staging Area was estimated on the basis of 485 standard storage casks. The cost includes only the excavation, backfill, crushed rock base, concrete pad, and cask. The estimate excludes all other costs such as roads, electrical, fencing, security, and monitoring. The standard storage cask has a capacity of 24 PWR assemblies or 52 BWR assemblies.

3. COST ESTIMATE

Cost estimate summaries are presented for each design alternative and construction option in Tables F-3 through F-12. The cost estimate for the Fuel Staging Area is shown in Table F-13. Priced equipment lists for the Non-Rotating WP Design Alternative and the Turntable Design Alternative are included in Tables F-14 and F-15, respectively.

Table F-3. Construction Costs: Module 1, Construction Option NR-1A
17 Welders
Non-rotating WP Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cont Ovhd	Subcont Fee	Cont Profit	Cont Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	9,604	\$37.95	364,477	116,089	-	-	480,566	228,624	709,189	34,571	128,809	-	32,202	13,525	4,806	14,611	228,624
10	Concrete	609,081	\$42.60	25,946,866	12,755,824	-	-	38,702,690	17,367,766	56,070,456	2,198,784	10,225,368	-	2,556,342	1,073,664	387,027	926,581	17,367,766
20	Structural Steel	83,724	\$52.00	4,353,649	11,147,496	-	-	15,501,145	5,938,020	21,439,165	302,244	3,950,847	-	987,712	414,839	155,011	127,367	5,938,020
30	Building	303,959	\$46.48	14,128,033	22,078,245	-	-	36,206,278	14,558,347	50,764,625	1,097,293	9,325,893	-	2,331,473	979,219	362,063	462,406	14,558,347
40	Equipment	40,643	\$46.60	1,893,964	-	134,644,924	-	136,538,888	47,876,189	184,415,077	146,721	34,171,402	-	8,542,851	3,587,997	1,365,389	61,829	47,876,189
50	Piping	46,093	\$47.15	2,173,263	1,784,018	-	-	3,957,281	1,672,981	5,630,262	166,394	1,030,919	-	257,730	108,246	39,573	70,119	1,672,981
60	Electrical	155,152	\$48.95	7,594,709	5,845,315	1,674,872	-	15,114,696	6,257,114	21,371,811	560,100	3,918,699	-	979,675	411,463	151,147	236,030	6,257,114
70	Instruments	104,142	\$49.30	5,134,220	7,130,941	-	-	12,265,161	4,939,213	17,204,374	375,954	3,160,279	-	790,070	331,829	122,652	158,429	4,939,213
80	Paint	31,704	\$40.10	1,271,345	218,775	-	-	1,490,120	721,134	2,211,254	114,453	401,143	-	100,286	42,120	14,901	48,231	721,134
85	Insulation	2,176	\$42.00	91,392	120,929	-	-	212,321	87,874	300,195	7,865	55,044	-	13,761	5,780	2,123	3,310	87,874
Total Cost		1,386,280	\$45.41	62,951,918	61,197,632	136,319,596	-	260,469,146	99,647,263	360,116,408	5,004,469	66,368,404	-	16,592,101	6,968,682	2,604,691	2,108,915	99,647,263

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-4. Construction Costs: Module 2, Construction Option NR-1A
17 Welders
Non-rotating WP Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cont Ovhd	Subcont Fee	Cont Profit	Cont Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	2,744	\$37.95	104,148	31,575	-	-	135,723	64,771	200,495	9,907	36,408	-	9,102	3,823	1,357	4,175	64,771
10	Concrete	284,811	\$42.60	12,132,959	4,383,930	-	-	16,516,889	7,570,002	24,086,891	1,028,169	4,386,264	-	1,096,566	460,558	165,169	433,277	7,570,002
20	Structural Steel	19,891	\$52.00	1,034,329	2,068,784	-	-	3,103,113	1,208,601	4,311,714	71,806	793,730	-	198,432	83,342	31,031	30,260	1,208,601
30	Building	54,533	\$46.48	2,534,713	2,428,027	-	-	4,962,740	2,077,270	7,040,010	196,866	1,289,901	-	322,475	135,440	49,627	62,960	2,077,270
40	Equipment	22,427	\$46.60	1,045,087	-	61,104,490	-	62,149,577	21,817,168	83,966,745	80,961	15,557,534	-	3,889,409	1,633,552	621,496	34,117	21,817,168
50	Piping	6,647	\$47.15	313,416	224,075	-	-	537,491	229,687	767,178	23,996	140,372	-	35,093	14,739	5,375	10,112	229,687
60	Electrical	28,106	\$48.95	1,375,789	838,800	337,579	-	2,552,168	1,068,659	3,620,826	101,463	663,408	-	165,852	69,658	25,522	42,757	1,068,659
70	Instruments	22,049	\$49.30	1,087,035	1,243,400	-	-	2,330,435	952,845	3,283,280	79,598	602,508	-	150,627	63,263	23,304	33,543	952,845
80	Paint	7,140	\$40.10	286,332	39,342	-	-	325,674	158,950	484,625	25,777	87,863	-	21,966	9,226	3,257	10,863	158,950
85	Insulation	495	\$42.00	20,791	13,476	-	-	34,267	15,096	49,363	1,787	9,014	-	2,253	946	343	753	15,096
Total Cost		448,845	\$44.41	19,934,599	11,271,409	61,442,069	-	92,648,077	35,163,050	127,811,127	1,620,330	23,567,182	-	5,891,775	2,474,546	926,481	682,817	35,163,050

Table F-5. Construction Costs: Module 3, Construction Option NR-1A
17 Welders
Non-rotating WP Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cent Ov'hd	Subcent Fee	Cent Profit	Cent Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	1,988	\$37.95	75,432	18,022	-	-	83,454	45,222	138,675	7,175	25,157	-	6,289	2,842	935	3,024	45,222
10	Concrete	249,413	\$42.60	10,624,973	3,985,713	-	-	14,810,686	6,880,285	21,290,971	900,379	3,877,768	-	989,442	407,185	146,107	379,425	6,680,285
20	Structural Steel	21,778	\$52.00	1,132,334	2,283,537	-	-	3,395,871	1,322,878	4,718,548	78,810	888,820	-	217,155	91,205	33,959	33,127	1,322,878
30	Building	54,532	\$48.48	2,534,870	2,153,973	-	-	4,888,843	1,981,873	6,870,316	198,862	1,221,378	-	305,344	128,245	48,888	82,859	1,981,873
40	Equipment	10,353	\$48.60	482,427	-	20,255,100	-	20,737,527	7,297,994	28,035,520	37,373	5,193,725	-	1,298,431	545,341	207,375	15,749	7,297,994
50	Piping	4,201	\$47.15	198,088	120,079	-	-	318,147	137,848	455,794	15,165	83,328	-	20,832	8,749	3,181	8,391	137,848
60	Electrical	22,928	\$48.95	1,122,312	881,487	71,304	-	1,875,103	799,828	2,874,731	82,769	489,488	-	122,387	51,394	18,751	34,879	799,828
70	Instruments	10,540	\$49.30	519,801	809,035	-	-	1,128,838	480,582	1,589,218	38,048	291,871	-	72,918	30,825	11,288	18,034	480,582
80	Paint	7,731	\$40.10	310,020	42,828	-	-	352,849	172,111	524,760	27,910	95,140	-	23,785	9,990	3,526	11,781	172,111
85	Insulation	-	\$42.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total Cost		383,480	\$44.33	16,999,837	9,874,476	20,326,404	-	47,200,716	18,897,818	66,098,533	1,384,291	12,148,262	-	3,038,663	1,276,368	472,007	583,349	18,897,818

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-6. Construction Costs: Modules 1 and 2, Construction Option NR-1B
17 Welders
Non-rotating WP Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cont Ov'hd	Subcont Fee	Cont Profit	Cont Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	10,390	\$37.95	394,301	155,919	-	-	550,220	257,909	808,129	37,508	148,932	-	36,733	15,428	5,502	15,808	257,909
10	Concrete	840,114	\$42.60	35,788,843	17,228,806	-	-	53,017,749	23,828,160	76,845,909	3,032,810	14,012,640	-	3,503,180	1,471,327	530,177	1,278,046	23,828,160
20	Structural Steel	99,913	\$52.00	5,195,470	13,303,987	-	-	18,499,457	7,088,549	25,588,006	360,696	4,715,036	-	1,178,759	495,079	184,895	151,995	7,088,549
30	Building	344,076	\$46.48	15,992,855	25,187,684	-	-	41,180,319	18,540,977	59,721,297	1,242,115	10,800,808	-	2,850,152	1,113,084	411,603	523,435	18,540,977
40	Equipment	65,838	\$46.60	3,068,051	-	192,142,444	-	195,210,495	68,498,006	263,708,500	237,675	48,862,042	-	12,215,511	5,130,514	1,852,105	100,158	68,498,006
50	Piping	52,947	\$47.15	2,496,451	2,080,150	-	-	4,576,601	1,932,524	6,509,125	191,139	1,191,935	-	297,884	125,153	45,766	80,547	1,932,524
60	Electrical	177,810	\$48.95	8,703,800	8,879,308	1,918,032	-	17,299,140	7,182,909	24,482,048	641,894	4,485,258	-	1,121,315	470,952	172,991	270,488	7,182,909
70	Instruments	128,163	\$48.30	6,218,838	8,407,105	-	-	14,625,941	5,802,806	20,528,747	455,449	3,770,587	-	942,648	395,913	148,268	181,928	5,802,806
80	Paint	38,533	\$40.10	1,585,288	270,399	-	-	1,855,685	888,371	2,754,056	142,715	489,600	-	124,800	52,458	18,557	60,141	888,371
85	Insulation	2,576	\$42.00	108,192	134,406	-	-	242,598	100,974	343,572	9,299	62,974	-	15,744	6,612	2,426	3,919	100,974
Total Cost		1,759,360	\$45.22	79,552,884	73,427,844	194,058,476	-	347,039,204	132,209,184	479,248,388	6,351,289	88,347,623	-	22,086,906	9,276,500	3,470,392	2,676,473	132,209,184

Table F-7. Construction Costs: Module 3, Construction Option NR-1B
17 Welders
Non-rotating WP Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cont Ov'hd	Subcont Fee	Cont Profit	Cont Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	1,988	\$37.95	75,432	18,022	-	-	93,454	45,222	138,675	7,175	25,157	-	6,289	2,642	935	3,024	45,222
10	Concrete	249,413	\$42.60	10,624,979	3,985,713	-	-	14,610,688	6,880,285	21,290,971	900,379	3,877,788	-	989,442	407,185	148,107	379,425	6,880,285
20	Structural Steel	21,776	\$52.00	1,132,334	2,283,537	-	-	3,395,871	1,322,878	4,718,548	78,810	888,820	-	217,155	91,205	33,958	33,127	1,322,878
30	Building	54,532	\$48.48	2,534,870	2,153,973	-	-	4,688,843	1,981,873	6,670,318	198,862	1,221,378	-	305,344	128,245	48,888	82,958	1,981,873
40	Equipment	10,353	\$46.60	482,427	-	20,255,100	-	20,737,527	7,287,994	28,035,520	37,373	5,193,725	-	1,298,431	545,341	207,375	15,749	7,287,994
50	Piping	4,201	\$47.15	198,088	120,079	-	-	318,147	137,848	455,784	15,185	83,328	-	20,832	8,748	3,181	8,391	137,848
60	Electrical	22,828	\$48.95	1,122,312	881,487	71,304	-	1,875,103	789,828	2,674,731	82,769	488,488	-	122,387	51,394	18,751	34,878	789,828
70	Instruments	10,540	\$49.30	519,801	609,035	-	-	1,128,836	480,582	1,589,218	38,048	291,871	-	72,918	30,825	11,288	18,034	480,582
80	Paint	7,731	\$40.10	310,020	42,829	-	-	352,849	172,111	524,780	27,910	95,140	-	23,785	9,990	3,526	11,781	172,111
85	Insulation	-	\$42.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total Cost		383,480	\$44.33	16,999,837	9,874,475	20,326,404	-	47,200,716	18,897,818	66,098,533	1,384,291	12,148,262	-	3,038,563	1,275,358	472,007	583,349	18,897,818

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-8. Construction Costs: Module 1, Construction Option T-1A
17 Welders
Turntable Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cont Ov'hd	Subcont Fee	Cont Profit	Cont Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	9,860	\$37.95	374,199	116,790	-	-	480,989	233,887	724,876	35,596	131,848	-	32,912	13,823	4,910	15,000	233,887
10	Concrete	611,801	\$42.60	26,082,709	12,833,241	-	-	38,915,950	17,452,445	56,368,395	2,208,800	10,278,138	-	2,589,034	1,079,994	388,980	930,718	17,452,445
20	Structural Steel	84,520	\$52.00	4,395,059	11,249,215	-	-	15,644,274	5,992,997	21,637,271	305,119	3,987,348	-	996,837	419,872	158,443	128,679	5,992,997
30	Building	308,572	\$46.48	14,342,419	22,478,874	-	-	36,821,293	14,802,142	51,623,434	1,113,844	8,483,808	-	2,370,852	985,800	388,213	489,423	14,802,142
40	Equipment	42,008	\$46.60	1,957,573	-	145,018,574	-	146,976,147	51,524,857	198,501,004	151,849	36,781,949	-	8,195,487	3,882,105	1,469,761	63,806	51,524,857
50	Piping	46,828	\$47.15	2,208,007	1,814,271	-	-	4,022,278	1,700,331	5,722,609	189,054	1,047,833	-	281,858	110,022	40,223	71,240	1,700,331
60	Electrical	157,489	\$48.95	7,708,122	5,938,439	1,674,872	-	15,321,233	6,343,866	21,665,099	568,464	3,972,424	-	993,106	417,105	153,212	239,554	6,343,866
70	Instruments	111,013	\$49.30	5,472,841	7,520,850	-	-	12,993,791	5,238,978	18,232,770	400,767	3,348,837	-	837,159	351,807	128,938	188,881	5,238,978
80	Paint	31,960	\$40.10	1,281,576	220,562	-	-	1,502,138	726,947	2,229,085	115,374	404,378	-	101,085	42,460	15,021	48,619	726,947
85	Insulation	2,176	\$42.00	91,392	120,828	-	-	212,321	87,874	300,195	7,955	55,044	-	13,781	5,780	2,123	3,310	87,874
Total Cost		1,408,208	\$45.44	63,893,897	62,293,171	146,693,246	-	272,860,414	104,102,324	376,962,738	5,078,412	68,489,207	-	17,372,302	7,286,367	2,728,804	2,139,232	104,102,324

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-9. Construction Costs: Module 2, Construction Option T-1A
17 Welders
Turntable Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cent Ov'hd	Subcont Fee	Cent Profit	Cent Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	2,744	\$37.95	104,148	31,575	-	-	135,723	84,771	200,495	9,807	38,408	-	9,102	3,823	1,357	4,175	84,771
10	Concrete	284,811	\$42.60	12,132,959	4,393,830	-	-	16,516,889	7,570,002	24,086,891	1,028,189	4,386,284	-	1,086,566	460,558	185,169	433,277	7,570,002
20	Structural Steel	19,891	\$52.00	1,034,329	2,068,784	-	-	3,103,113	1,208,801	4,311,914	71,806	783,730	-	198,432	83,342	31,031	30,260	1,208,801
30	Building	54,851	\$48.48	2,549,494	2,434,937	-	-	4,984,431	2,088,855	7,071,286	198,014	1,285,811	-	323,903	138,039	49,844	83,444	2,088,855
40	Equipment	20,750	\$46.60	966,862	-	62,367,080	-	63,334,052	22,219,601	85,553,653	74,800	15,852,240	-	3,963,060	1,664,485	633,341	31,567	22,219,601
50	Piping	6,647	\$47.15	313,416	224,075	-	-	537,491	229,687	767,178	23,996	140,372	-	35,093	14,739	5,376	10,112	229,687
60	Electrical	28,339	\$48.95	1,387,182	844,040	337,600	-	2,568,822	1,075,948	3,644,770	102,303	887,781	-	188,945	70,117	26,888	43,111	1,075,948
70	Instruments	22,048	\$48.30	1,087,035	1,243,400	-	-	2,330,435	852,845	3,283,280	78,598	802,508	-	150,827	63,283	23,304	33,543	852,845
80	Paint	7,140	\$40.10	286,332	39,342	-	-	325,674	168,850	494,525	25,777	87,883	-	21,866	9,228	3,257	10,883	168,850
85	Insulation	495	\$42.00	20,791	13,476	-	-	34,267	15,096	49,363	1,787	9,014	-	2,253	946	343	753	15,096
Total Cost		447,719	\$44.41	19,882,648	11,283,559	62,704,680	-	83,870,897	35,582,355	129,453,252	1,816,266	23,871,791	-	5,967,948	2,506,538	938,709	681,104	35,582,355

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-10. Construction Costs: Module 3, Construction Option T-1A
17 Welders
Turntable Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cont Ov'hd	Subcont Fee	Cont Profit	Cont Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	1,988	\$37.95	75,432	18,022	-	-	93,454	45,222	138,675	7,175	25,157	-	6,289	2,642	935	3,024	45,222
10	Concrete	249,413	\$42.60	10,624,973	3,985,713	-	-	14,610,686	6,680,285	21,290,971	900,379	3,877,766	-	969,442	407,165	146,107	379,425	8,680,285
20	Structural Steel	21,776	\$52.00	1,132,334	2,263,537	-	-	3,395,871	1,322,676	4,718,548	78,610	868,620	-	217,155	91,205	33,959	33,127	1,322,676
30	Building	54,532	\$46.48	2,534,670	2,153,973	-	-	4,688,643	1,981,673	6,670,316	196,862	1,221,376	-	305,344	128,245	46,886	82,959	1,981,673
40	Equipment	10,353	\$46.60	482,427	-	20,255,100	-	20,737,527	7,297,994	28,035,520	37,373	5,193,725	-	1,298,431	545,341	207,375	15,748	7,297,994
50	Piping	4,201	\$47.15	198,068	120,079	-	-	318,147	137,646	455,794	15,165	83,328	-	20,832	8,749	3,181	6,391	137,646
60	Electrical	22,928	\$48.95	1,122,312	681,487	71,304	-	1,875,103	799,628	2,674,731	82,769	469,468	-	122,367	51,394	18,751	34,879	799,628
70	Instruments	10,540	\$49.30	519,601	609,035	-	-	1,128,636	460,582	1,589,218	38,048	291,671	-	72,918	30,625	11,266	16,034	460,582
80	Paint	7,731	\$40.10	310,020	42,629	-	-	352,649	172,111	524,760	27,910	95,140	-	23,785	9,990	3,526	11,781	172,111
85	Insulation	-	\$42.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total Cost		383,460	\$44.33	16,999,837	9,874,475	20,326,404	-	47,200,716	18,897,818	66,098,533	1,384,291	12,146,252	-	3,036,563	1,275,356	472,007	583,349	18,897,818

Table F-11. Construction Costs: Modules 1 and 2, Construction Option T-1B
17 Welders
Turntable Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cent Ov'h'd	Subcent Fee	Cent Profit	Cent Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	10,324	\$37.95	391,798	155,289	-	-	547,085	258,398	803,481	37,270	148,089	-	38,522	15,339	5,471	15,708	258,398
10	Concrete	838,635	\$42.60	35,725,837	17,206,538	-	-	52,932,375	23,788,888	76,721,383	3,027,471	13,988,862	-	3,487,480	1,468,946	529,324	1,275,795	23,788,888
20	Structural Steel	99,926	\$52.00	5,196,146	13,307,618	-	-	18,503,764	7,088,133	25,591,897	360,732	4,716,124	-	1,179,031	495,193	185,038	152,015	7,088,133
30	Building	348,300	\$46.48	16,188,987	25,894,838	-	-	41,883,829	18,820,139	58,703,982	1,257,383	10,785,297	-	2,898,324	1,132,456	418,838	529,861	18,820,139
40	Equipment	53,468	\$46.60	2,481,608	-	208,382,345	-	208,853,954	73,177,581	282,031,515	183,018	52,261,743	-	13,065,436	5,487,483	2,088,540	81,340	73,177,581
50	Piping	53,900	\$47.15	2,541,385	2,114,618	-	-	4,656,003	1,966,270	6,622,273	194,579	1,212,646	-	303,161	127,328	46,560	81,997	1,966,270
60	Electrical	180,108	\$48.95	8,818,189	8,772,193	1,918,032	-	17,504,414	7,249,087	24,753,501	850,183	4,538,849	-	1,134,862	478,558	175,044	273,991	7,249,087
70	Instruments	132,762	\$49.30	6,545,187	8,788,924	-	-	15,342,091	8,184,146	21,538,238	478,271	3,855,340	-	988,835	415,311	153,421	201,888	8,184,146
80	Paint	37,716	\$40.10	1,512,424	259,974	-	-	1,772,398	857,780	2,630,178	138,156	477,139	-	119,285	50,100	17,724	57,377	857,780
85	Insulation	2,576	\$42.00	108,192	134,406	-	-	242,598	100,974	343,572	9,299	62,974	-	15,744	6,812	2,426	3,919	100,974
Total Cost		1,757,713	\$45.24	79,517,731	74,442,396	208,278,377	-	362,238,504	137,489,475	499,737,979	6,345,344	82,145,962	-	23,036,490	9,575,326	3,622,385	2,673,968	137,489,475

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-12. Construction Costs: Module 3, Construction Option T-1B
17 Welders
Turntable Design Alternative

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cont Ov'h'd	Subcont Fee	Cont Profit	Cont Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	1,988	\$37.95	75,432	18,022	-	-	93,454	45,222	138,676	7,175	25,157	-	6,289	2,642	935	3,024	45,222
10	Concrete	249,413	\$42.80	10,624,973	3,985,713	-	-	14,10,888	8,880,285	21,290,871	800,379	3,877,788	-	989,442	407,165	148,107	379,425	8,880,285
20	Structural Steel	21,776	\$52.00	1,132,334	2,263,537	-	-	3,395,871	1,322,676	4,718,548	78,810	668,620	-	217,155	91,205	33,959	33,127	1,322,676
30	Building	54,532	\$48.48	2,534,870	2,153,873	-	-	4,688,643	1,881,873	6,870,316	198,882	1,221,378	-	305,344	128,245	48,888	82,858	1,881,873
40	Equipment	10,353	\$46.60	482,427	-	20,255,100	-	20,737,527	7,297,994	28,035,520	37,373	5,193,725	-	1,298,431	545,341	207,375	15,749	7,297,994
50	Piping	4,201	\$47.15	198,088	120,078	-	-	318,147	137,848	455,794	15,165	83,328	-	20,832	8,748	3,181	8,381	137,848
60	Electrical	22,928	\$48.95	1,122,312	681,487	71,304	-	1,875,103	799,628	2,674,731	82,769	489,468	-	122,367	51,394	18,751	34,878	799,628
70	Instruments	10,540	\$49.30	518,801	608,035	-	-	1,126,836	460,582	1,588,218	38,049	281,871	-	72,818	30,825	11,288	18,034	460,582
80	Paint	7,731	\$40.10	310,020	42,628	-	-	352,648	172,111	524,760	27,910	95,140	-	23,785	9,990	3,526	11,761	172,111
85	Insulation	-	\$42.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total Cost		383,480	\$44.33	16,989,837	9,874,476	20,328,404	-	47,200,716	18,697,818	66,098,533	1,384,281	12,146,252	-	3,036,583	1,275,358	472,007	583,348	18,697,818

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-13. Construction Costs: Fuel Staging Area
485 Casks

Cost Account	Description	Labor Manhours	Labor Rate	Labor Dollars	Material Cost	Equipment Cost	Subcontract Cost	Direct Field Cost	Indirect Field Cost	Total Field Cost	Equip Rental	Cont Ov'hd	Subcont Fee	Cont Profit	Cont Bond	Temp Const	Bus Trans	Total IFC
00	Sitework	13,819	\$37.85	518,833	297,080	-	-	813,893	370,381	1,184,275	49,184	215,784	-	53,941	22,855	8,139	20,718	370,381
10	Concrete	201,468	\$42.60	8,582,579	5,485,070	-	-	14,067,649	8,186,280	20,253,909	727,303	3,698,738	-	824,885	380,368	140,876	306,490	6,186,280
20	Structural Steel	-	\$52.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
30	Building	-	\$48.48	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
40	Equipment	-	\$48.80	-	-	388,000,000	-	388,000,000	-	388,000,000	-	-	-	-	-	-	-	-
50	Piping	-	\$47.15	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
60	Electrical	-	\$48.85	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
70	Instruments	-	\$49.30	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
80	Paint	-	\$40.10	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
85	Insulation	-	\$42.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total Cost		215,088	\$42.31	9,089,413	5,782,130	388,000,000	-	402,861,543	6,556,641	409,438,184	776,487	3,914,502	-	878,626	411,023	148,815	327,208	6,556,641

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-14. WHB Equipment List
Non-rotating WP Design Alternative

CARRIER PREPARATION AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
CP-1	Bridge crane (56' span, 15 ton capacity)	1	ea.	\$350,000	\$350,000	1	\$350,000	1	\$350,000	CH-CN-100	
CP-2	Bridge mounted manipulator	1	ea.	\$800,000	\$800,000	1	\$800,000	1	\$800,000	PH-EM-100	
CP-3	Miscellaneous tools	1	ea.	\$10,000	\$10,000	1	\$10,000	1	\$10,000	Eng. Judgement	
CP-4	Access platform	1	lot	\$100,000	\$100,000	1	\$100,000	1	\$100,000	Eng. Judgement	4 platforms per set
CP-5	Isolation door (roll-up door) (20H x 15W)	4	ea.	\$6,000	\$24,000	4	\$24,000	4	\$24,000	PC-DO-111	
Sub Total					\$1,284,000	Sub Total		\$1,284,000	Sub Total		\$1,284,000
Total Cost Modules #1,2,3										\$3,852,000	
CARRIER BAY AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
CB-1	Bridge crane (76' span, 160 ton/10 ton)	2	ea.	\$2,000,000	\$4,000,000	0	\$0	0	\$0	PH-CN-100	
CB-2	Bridge mounted manipulator	1	ea.	\$800,000	\$800,000	0	\$0	0	\$0	CH-CN-101	
CB-3	Cask transfer cart with elevating platform (125 ton)	3	ea.	\$1,000,000	\$3,000,000	3	\$3,000,000	3	\$3,000,000	Eng. Judgement	
CB-4	Cask transfer cart spacer	2	ea.	\$20,000	\$40,000	2	\$40,000	2	\$40,000	Eng. Judgement	
CB-5	Cask adapter set (13 per set)	1	ea.	\$390,000	\$390,000	1	\$390,000	1	\$390,000	Eng. Judgement	
CB-6	Miscellaneous tools	1	lot	\$10,000	\$10,000	1	\$10,000	1	\$10,000	Eng. Judgement	
CB-7	Large DPC overpack	5	ea.	\$80,000	\$400,000	5	\$400,000	5	\$400,000	PU-CA-121	assume (2) DPC overpacks will accommodate all DPCs
CB-8	Small DPC overpack	5	ea.	\$70,000	\$350,000	5	\$350,000	5	\$350,000	PU-CA-122	
CB-9	Isolation door (steel roll-up door 13' W x 25' H)	6	ea.	\$6,000	\$36,000	6	\$36,000	6	\$36,000	PC-DO-111	
CB-10	Cask lifting yoke - adjustable (span 3'-6" to 9'-0", 160 tons)	1	ea.	\$175,000	\$175,000	1	\$175,000	1	\$175,000	PU-FX-100	
Sub Total					\$9,201,000	Sub Total		\$4,401,000	Sub Total		\$4,401,000
Total Cost Modules #1,2,3										\$18,003,000	
CASK PREPARATION AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
CPA-1	Bridge crane	1	ea.	\$350,000	\$350,000	1	\$350,000	1	\$350,000	CH-CN-100	
CPA-2	Bridge mounted manipulator	1	ea.	\$800,000	\$800,000	1	\$800,000	1	\$800,000	CH-CN-101	
CPA-3	DPC overpack adapter set	1	ea.	\$60,000	\$60,000	1	\$60,000	1	\$60,000	Eng. Judgement	2 adapters per set
CPA-4	Bolt torquing tool	2	ea.	\$90,000	\$180,000	2	\$180,000	2	\$180,000	Hanford procurement	
CPA-5	Cask lid lifting fixture set	1	ea.	\$20,000	\$20,000	1	\$20,000	1	\$20,000	PU-FX-110	(assume 3 fixtures per set and 4 casks per fixture)
CPA-6	DPC lid lifting fixture (large)	2	ea.	\$17,500	\$35,000	2	\$35,000	2	\$35,000	PU-FX-123	assume 3 fixtures per set and one fixture per 3 DPC
CPA-7	DPC lid lifting fixture (small)	2	ea.	\$12,500	\$25,000	2	\$25,000	2	\$25,000	PU-FX-124	assume 3 fixtures per set and one fixture per 3 DPC
CPA-8	Miscellaneous tools	1	lot	\$10,000	\$10,000	1	\$10,000	1	\$10,000	Eng. Judgement	
CPA-9	Large DPC lid severing machine	1	ea.	\$350,000	\$350,000	1	\$350,000	1	\$350,000	PU-ME-110	
CPA-10	Small DPC lid severing machine	1	ea.	\$350,000	\$350,000	1	\$350,000	1	\$350,000	PU-ME-112	
CPA-11	Access platform sets	3	ea.	\$100,000	\$300,000	3	\$300,000	3	\$300,000	Eng. Judgement	4 platforms per set
Sub Total					\$2,480,000	Sub Total		\$2,480,000	Sub Total		\$2,480,000
Total Cost Modules #1,2,3										\$7,440,000	

Table F-14. WHB Equipment List, continued
Non-rotating WP Design Alternative

TRANSFER CELL		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
TC-1	Cask unloading port lid	3	ea.	\$20,000	\$60,000	3	\$60,000	3	\$60,000	PU-DE-110 (similar)	Eng. Judgement
TC-2	Cask unloading port shield plug	3	ea.	\$35,000	\$105,000	3	\$105,000	3	\$105,000	PU-HA-112DC	
TC-3	Bridge crane (68' span, 75 tons/20tons)	1	ea.	\$2,000,000	\$2,000,000	1	\$2,000,000	1	\$2,000,000	PU-CN-110	
TC-4	Bridge mounted manipulator (68' span, 150 lbs arm, 8 ton hoist)	1	ea.	\$750,000	\$750,000	1	\$750,000	1	\$750,000	PU-EM-111	
TC-5	Assembly handling machine	1	ea.	\$1,300,000	\$1,300,000	1	\$1,300,000	1	\$1,300,000	PU-MA-115	Simplified machine
TC-6	Assembly storage rack	1	ea.	\$200,000	\$200,000	1	\$200,000	1	\$200,000	PU-SR-110 (similar)	
TC-7	Assembly storage rack shield plug	1	ea.	\$110,000	\$110,000	1	\$110,000	1	\$110,000		Eng. Judgement
TC-8	Canister storage rack	1	set	\$200,000	\$200,000	1	\$200,000	1	\$200,000	PC-SR-110	
TC-9	Canister storage rack shield plug	1	ea.	\$40,000	\$40,000	1	\$40,000	1	\$40,000		Eng. Judgement
TC-10	Assembly lifting grapple set	1	ea.	\$275,000	\$275,000	1	\$275,000	1	\$275,000	PU-FX-111	5 grapples per set
TC-11	DC lid lifting grapple	1	ea.	\$275,000	\$275,000	1	\$275,000	1	\$275,000	PU-DE-118	
TC-12	DOE DHLW canister lifting grapple	1	ea.	\$450,000	\$450,000	1	\$450,000	1	\$450,000		PC-FX-112 (similar)
TC-13	Empty DPC lifting fixtures	3	ea.	\$12,000	\$36,000	3	\$36,000	3	\$36,000		Eng. Judgement Not covered in SR
TC-14	Small canister lifting fixture (45 ton)	1	ea.	\$35,000	\$35,000	1	\$35,000	1	\$35,000	PC-FX-111A	
TC-15	Large canister lifting fixtures (75 ton)	1	ea.	\$44,000	\$44,000	1	\$44,000	1	\$44,000	PC-FX-111	
TC-16	Segmented environmental door (70' w x 50' h) with lifting drive & housing	1	ea.	\$120,000	\$120,000	1	\$120,000	1	\$120,000	PC-DO-112	Similar too but twice the size
TC-17	Steel shield door (1.5' l x 4' w x 8' h)	1	ea.	\$60,000	\$60,000	1	\$60,000	1	\$60,000		Eng. Judgement Not covered in SR
TC-19	Shield window (3' x 4' x 5')	9	ea.	\$325,000	\$2,925,000	9	\$2,925,000	9	\$2,925,000	PC-WO-111	
TC-20	MCO canister lifting grapple	1	ea.	\$450,000	\$450,000	1	\$450,000	1	\$450,000		Hanford procurement
TC-21	DC loading port lid	2	ea.	\$30,000	\$60,000	2	\$60,000	2	\$60,000	PU-HA-112	
TC-22	DC loading port shield plug	2	ea.	\$30,000	\$60,000	2	\$60,000	2	\$60,000	PU-HA-112	
TC-23	Large canister lifting grapple	1	ea.	\$450,000	\$450,000	1	\$450,000	1	\$450,000		Hanford procurement Not covered in SR
TC-24	Small canister lifting grapple	1	ea.	\$450,000	\$450,000	1	\$450,000	1	\$450,000		Hanford procurement Not covered in SR
TC-25	DC decontamination tool	1	ea.	\$10,000	\$10,000	1	\$10,000	1	\$10,000	PD-DC-100	
Sub Total					\$10,465,000	Sub Total		\$10,465,000	Sub Total		\$10,465,000

DC LOAD CELL		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
DC-1	Load port mating device	2	ea.	\$75,000	\$150,000	2	\$150,000	2	\$150,000	PU-DE-111DC	
DC-2	Shield door	2	ea.	\$80,000	\$160,000	2	\$160,000	2	\$160,000	PD-DO-101	
DC-3	DC shielded cover handling device	2	ea.	\$50,000	\$100,000	2	\$100,000	2	\$100,000		
Sub Total					\$410,000	Sub Total		\$410,000	Sub Total		\$410,000
						Total Cost Modules #1,2,3				\$1,230,000	

Table F-14. WHB Equipment List, continued
Non-rotating WP Design Alternative

DC HANDLING AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
DCH-1	DC transfer platform	2	ea.	\$420,000	\$840,000	0	\$0	0	\$0	PU-CR-113 (similar)	
DCH-2	DC prime mover	4	ea.	\$50,000	\$200,000	2	\$100,000	0	\$0	Eng. Judgement	
DCH-3	DC transfer cart	22	ea.	\$200,000	\$4,400,000	12	\$2,400,000	0	\$0	PU-CR-112	
DCH-4	Maintenance overhead crane (200 ton, 55' span)	1	ea.	\$2,000,000	\$2,000,000	0	\$0	0	\$0	PH-CN-100	
Sub Total					\$7,440,000	Sub Total		\$2,500,000	Sub Total		\$0
Total Cost Modules #1,2,3										\$9,940,000	
WELD AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
WA-1	Bridge mounted manipulator	11	ea.	\$2,000,000	\$22,000,000	6	\$12,000,000	0	\$0	PD-CN-100	
WA-2	Lid lifting system	11	ea.	\$300,000	\$3,300,000	6	\$1,800,000	0	\$0	PD-FX-102	
WA-3	Welding/treatment/inspection system	11	ea.	\$2,500,000	\$27,500,000	6	\$15,000,000	0	\$0	PD-ME-101A-H	
WA-4	Steel shield door (11' x 12' w x 12' h)	17	ea.	\$180,000	\$3,060,000	0	\$0	0	\$0	Eng. Judgement	
WA-5	Isolation door (16' x 24')	17	ea.	\$10,000	\$170,000	0	\$0	0	\$0	PC-DO-110	
WA-6	Retractable port shield plug	11	ea.	\$30,000	\$330,000	6	\$180,000	0	\$0	PU-HA-112	
WA-7	Swipe pass-through	17	ea.	\$12,000	\$204,000	0	\$0	0	\$0	PD-FT-100	
Sub Total					\$56,564,000	Sub Total		\$28,880,000	Sub Total		\$0
Total Cost Modules #1,2,3										\$85,544,000	
WELD MAINTENANCE AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
WMA-1	Miscellaneous tools (set)	3	lot	\$10,000	\$30,000	0	\$0	0	\$0	Eng. Judgement	
WMA-2	Forklift	3	ea.	\$45,000	\$135,000	0	\$0	0	\$0	Eng. Judgement	
Sub Total					\$165,000	Sub Total		\$0	Sub Total		\$0
Total Cost Modules #1,2,3										\$165,000	
WVP REMEDIATION CELL		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
WPR-1	Bridge mounted manipulator	1	ea.	\$800,000	\$800,000	0	\$0	0	\$0	PR-EM-100	w/ 6 ton hoist
WPR-2	Bridge mounted cutting machine	1	ea.	\$600,000	\$600,000	0	\$0	0	\$0	PR-ME-100	
WPR-3	Decontamination device	1	ea.	\$10,000	\$10,000	0	\$0	0	\$0	PR-DC-100	
WPR-4	Shield door (Z 1 x 13' w x 24h)	1	ea.	\$315,000	\$315,000	0	\$0	0	\$0	PR-DO-100	
WPR-5	Shield window	4	ea.	\$325,000	\$1,300,000	0	\$0	0	\$0	PC-WO-111 (similar)	
Sub Total					\$3,025,000	Sub Total		\$0	Sub Total		\$0
Total Cost Modules #1,2,3										\$3,025,000	

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-14. WHB Equipment List, continued
Non-rotating WP Design Alternative

WP TRANSPORTER LOAD CELL					Module #1		Module #2		Module #3			
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost	Reference	Notes	
WPC-1	Bridge crane (200 ton, 36' span)	1	ea.	\$2,000,000	\$2,000,000	0	\$0	0	\$0	PH-CN-100		
WPC-2	Waste package lifting yoke (adjustable)	1	ea.	\$175,000	\$175,000	0	\$0	0	\$0	PU-FX-100		
WPC-3	Waste package lifting fixture	1	ea.	\$50,000	\$50,000	0	\$0	0	\$0	PD-FX-103		
WPC-4	Waste package/overpack horizontal lifting fixture	1	ea.	\$1,100,000	\$1,100,000	0	\$0	0	\$0	PD-MA-100		
WPC-5	Wall-mounted manipulator	2	ea.	\$700,000	\$1,400,000	0	\$0	0	\$0	SR dry option		
WPC-6	Shield window	6	ea.	\$325,000	\$1,950,000	0	\$0	0	\$0	PC-WO-111		
WPC-7	Crane maintenance isolation door (36' x 20')	1	ea.	\$45,000	\$45,000	0	\$0	0	\$0	PC-DO-114		
WPC-8	Steel shield door (16' X 16' x 1')	1	ea.	\$320,000	\$320,000	0	\$0	0	\$0	Eng. Judgement		
WPC-9	Steel shield door (16' X 16' x 0.25')	1	ea.	\$80,000	\$80,000	0	\$0	0	\$0	Eng. Judgement		
WPC-10	Shield cover lifting grapple	1	ea.	\$275,000	\$275,000	0	\$0	0	\$0	PU-DE-116		
Sub Total					\$7,395,000	Sub Total		\$0	Sub Total		\$0	
Total Cost Modules #1,2,3										\$7,395,000		
EMPTY DC PREPARATION AREA												
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost	Reference	Notes	
EDP-1	Preparation bridge crane	1	ea.	\$1,200,000	\$1,200,000	0	\$0	0	\$0	PD-CN-104		
EDP-2	Lifting yoke	1	ea.	\$73,000	\$73,000	0	\$0	0	\$0	PD-FX-104		
EDP-3	Lifting beam	1	ea.	\$10,000	\$10,000	0	\$0	0	\$0	PD-FX-105		
EDP-4	Lifting fixture	1	ea.	\$10,000	\$10,000	0	\$0	0	\$0	PD-FX-106		
EDP-5	Support saddle system	1	ea.	\$5,000	\$5,000	0	\$0	0	\$0	PD-FX-102		
EDP-6	Shield cover lifting adapter	1	ea.	\$10,000	\$10,000	0	\$0	0	\$0	Eng. Judgement		
EDP-7	Forklift	1	ea.	\$45,000	\$45,000	0	\$0	0	\$0			
EDP-8	Mobile access platform	1	ea.	\$5,000	\$5,000	0	\$0	0	\$0	Eng. Judgement		
EDP-9	DC shielded overpack (3 sizes)	36	ea.	\$512,000	\$18,432,000	6	\$3,072,000	0	\$0		For use in WHB only. Doesn't include dry storage overpacks	
EDP-10	DC shielded overpack cover (3 sizes)	36	ea.	\$20,000	\$720,000	6	\$120,000	0	\$0		For use in WHB only. Doesn't include dry storage overpacks	
EDP-11	DC adapter ring (various sizes)	36	ea.	\$10,000	\$360,000	6	\$60,000	0	\$0	Eng. Judgement		
EDP-12	DC loading port adapter (2 sizes)	11	ea.	\$10,000	\$110,000	6	\$60,000	0	\$0	Eng. Judgement	WAS DCH-5	
Sub Total					\$20,680,000	Sub Total		\$3,312,000	Sub Total		\$0	
Total Cost Modules #1,2,3										\$24,292,000		
TRANSPORTER LOAD BAY												
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost	Reference	Notes	
TLB-1	Isolation door (20 H x 18 W)	2	ea.	\$6,000	\$12,000	0	\$0	0	\$0	PC-DO-111		
TLB-2	Motorized cask transporter (crawler) 150 ton	1	ea.	\$800,000	\$800,000	0	\$0	0	\$0	Vendor quote (4 Point Lift Syst. Inc)	Seismic design	
Sub Total					\$812,000	Sub Total		\$0	Sub Total		\$0	
Total Cost Modules #1,2,3										\$812,000		

Table F-14. WHB Equipment List, continued
Non-rotating WP Design Alternative

FUEL STAGING AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
FAI-1	Storage cask	48	ea.	\$800,000	\$38,400,000	49	\$39,200,000	388	\$310,400,000	D. Zabransky	Total of 485 casks
					\$ 38,400,000		\$ 39,200,000		\$ 310,400,000		
						Total Cost Modules #1,2,3			\$388,000,000		
						TOTAL			\$681,083,000		

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-15. WHB Equipment List
Turntable Design Alternative

CARRIER PREPARATION AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
CP-1	Bridge crane (56' span, 15 ton capacity)	1	ea.	\$350,000	\$350,000	1	\$350,000	1	\$350,000	CH-CN-100	
CP-2	Bridge mounted manipulator	1	ea.	\$800,000	\$800,000	1	\$800,000	1	\$800,000	PH-EM-100	
CP-3	Miscellaneous tools	1	ea.	\$10,000	\$10,000	1	\$10,000	1	\$10,000	Eng. Judgement	
CP-4	Access platform	1	lot	\$100,000	\$100,000	1	\$100,000	1	\$100,000	Eng. Judgement	4 platforms per set
CP-5	Isolation door (roll-up door) (20H x 15W)	4	ea.	\$6,000	\$24,000	4	\$24,000	4	\$24,000	PC-DO-111	
Sub Total					\$1,284,000	Sub Total		\$1,284,000	Sub Total		\$1,284,000
Total Cost Modules #1,2,3									\$3,852,000		
CARRIER BAY AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
CB-1	Bridge crane (76' span, 160 ton/10 ton)	2	ea.	\$2,000,000	\$4,000,000	0	\$0	0	\$0	PH-CN-100	
CB-2	Bridge mounted manipulator	1	ea.	\$800,000	\$800,000	0	\$0	0	\$0	CH-CN-101	
CB-3	Cask transfer cart with elevating platform (125 ton)	3	ea.	\$1,000,000	\$3,000,000	3	\$3,000,000	3	\$3,000,000	Eng. Judgement	
CB-4	Cask transfer cart spacer	2	ea.	\$20,000	\$40,000	2	\$40,000	2	\$40,000	Eng. Judgement	
CB-5	Cask adapter set (13 per set)	1	ea.	\$390,000	\$390,000	1	\$390,000	1	\$390,000	Eng. Judgement	
CB-6	Miscellaneous tools	1	lot	\$10,000	\$10,000	1	\$10,000	1	\$10,000	Eng. Judgement	
CB-7	Large DPC overpack	5	ea.	\$80,000	\$400,000	5	\$400,000	5	\$400,000	PU-CA-121	assume (2) DPC overpacks will accommodate all DPCs
CB-8	Small DPC overpack	5	ea.	\$70,000	\$350,000	5	\$350,000	5	\$350,000	PU-CA-122	
CB-9	Isolation door (steel roll-up door 13'W x 25' H)	8	ea.	\$8,000	\$68,000	8	\$68,000	8	\$68,000	PC-DO-111	
CB-10	Cask lifting yoke - adjustable (span 3'-6" to 9'-0", 160 tons)	1	ea.	\$175,000	\$175,000	1	\$175,000	1	\$175,000	PU-FX-100	
Sub Total					\$9,201,000	Sub Total		\$4,401,000	Sub Total		\$4,401,000
Total Cost Modules #1,2,3									\$18,003,000		
CASK PREPARATION AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
CPA-1	Bridge crane	1	ea.	\$350,000	\$350,000	1	\$350,000	1	\$350,000	CH-CN-100	
CPA-2	Bridge mounted manipulator	1	ea.	\$800,000	\$800,000	1	\$800,000	1	\$800,000	CH-CN-101	
CPA-3	DPC overpack adapter set	1	ea.	\$60,000	\$60,000	1	\$60,000	1	\$60,000	Eng. Judgement	2 adapters per set
CPA-4	Bolt torquing tool	2	ea.	\$90,000	\$180,000	2	\$180,000	2	\$180,000	Hanford procurement	
CPA-5	Cask lid lifting fixture set	1	ea.	\$20,000	\$20,000	1	\$20,000	1	\$20,000	PU-FX-110	assume 3 fixtures per set and 4 casks per fixture
CPA-6	DPC lid lifting fixture (large)	2	ea.	\$17,500	\$35,000	2	\$35,000	2	\$35,000	PU-FX-123	
CPA-7	DPC lid lifting fixture (small)	2	ea.	\$12,500	\$25,000	2	\$25,000	2	\$25,000	PU-FX-124	assume 3 fixtures per set and one fixture per 3 DPC
CPA-8	Miscellaneous tools	1	lot	\$10,000	\$10,000	1	\$10,000	1	\$10,000	Eng. Judgement	
CPA-9	Large DPC lid severing machine	1	ea.	\$350,000	\$350,000	1	\$350,000	1	\$350,000	PU-ME-110	
CPA-10	Small DPC lid severing machine	1	ea.	\$350,000	\$350,000	1	\$350,000	1	\$350,000	PU-ME-112	
CPA-11	Access platform sets	3	ea.	\$100,000	\$300,000	3	\$300,000	3	\$300,000	Eng. Judgement	4 platforms per set
Sub Total					\$2,480,000	Sub Total		\$2,480,000	Sub Total		\$2,480,000
Total Cost Modules #1,2,3									\$7,440,000		

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-15. WHB Equipment List, continued
Turntable Design Alternative

TRANSFER CELL		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
TC-1	Cask unloading port lid	3	ea.	\$20,000	\$60,000	3	\$60,000	3	\$60,000	PU-DE-110 (similar)	Eng. Judgement
TC-2	Cask unloading port shield plug	3	ea.	\$35,000	\$105,000	3	\$105,000	3	\$105,000	PU-HA-112DC	
TC-3	Bridge crane (68' span, 75 tons/20tons)	1	ea.	\$2,000,000	\$2,000,000	1	\$2,000,000	1	\$2,000,000	PU-CN-110	
TC-4	Bridge mounted manipulator (68' span, 150 lbs arm, 6 ton hoist)	1	ea.	\$750,000	\$750,000	1	\$750,000	1	\$750,000	PU-EM-111	
TC-5	Assembly handling machine	1	ea.	\$1,300,000	\$1,300,000	1	\$1,300,000	1	\$1,300,000	PU-MA-115	Simplified machine
TC-6	Assembly storage rack	1	ea.	\$200,000	\$200,000	1	\$200,000	1	\$200,000	PU-SR-110 (similar)	
TC-7	Assembly storage rack shield plug	1	ea.	\$110,000	\$110,000	1	\$110,000	1	\$110,000		Eng. Judgement
TC-8	Canister storage rack	1	set	\$200,000	\$200,000	1	\$200,000	1	\$200,000	PC-SR-110	
TC-9	Canister storage rack shield plug	1	ea.	\$40,000	\$40,000	1	\$40,000	1	\$40,000		Eng. Judgement
TC-10	Assembly lifting grapple set	1	ea.	\$275,000	\$275,000	1	\$275,000	1	\$275,000	PU-FX-111	5 grapples per set
TC-11	DC lid lifting grapple	1	ea.	\$275,000	\$275,000	1	\$275,000	1	\$275,000	PU-DE-116	
TC-12	DOE DHLW canister lifting grapple	1	ea.	\$450,000	\$450,000	1	\$450,000	1	\$450,000	PC-FX-112 (similar)	
TC-13	Empty DPC lifting fixtures	3	ea.	\$12,000	\$36,000	3	\$36,000	3	\$36,000		Eng. Judgement Not covered in SR
TC-14	Small canister lifting fixture (45 ton)	1	ea.	\$35,000	\$35,000	1	\$35,000	1	\$35,000	PC-FX-111A	
TC-15	Large canister lifting fixtures (75 ton)	1	ea.	\$44,000	\$44,000	1	\$44,000	1	\$44,000	PC-FX-111	
TC-16	Segmented environmental door (70' w x 50' h) with lifting drive & housing	1	ea.	\$120,000	\$120,000	1	\$120,000	1	\$120,000	PC-DO-112	Similar too but twice the size
TC-17	Steel shield door (15' l x 4' w x 8' h)	1	ea.	\$60,000	\$60,000	1	\$60,000	1	\$60,000		Eng. Judgement Not covered in SR
TC-18	Shield window (3' x 4' x 5')	8	ea.	\$325,000	\$2,625,000	8	\$2,625,000	8	\$2,625,000	PC-WO-111	
TC-20	MCO canister lifting grapple	1	ea.	\$450,000	\$450,000	1	\$450,000	1	\$450,000		Hanford procurement
TC-21	DC loading port lid	2	ea.	\$30,000	\$60,000	2	\$60,000	2	\$60,000	PU-HA-112	
TC-22	DC loading port shield plug	2	ea.	\$30,000	\$60,000	2	\$60,000	2	\$60,000	PU-HA-112	
TC-23	Large canister lifting grapple	1	ea.	\$450,000	\$450,000	1	\$450,000	1	\$450,000		Hanford procurement Not covered in SR
TC-24	Small canister lifting grapple	1	ea.	\$450,000	\$450,000	1	\$450,000	1	\$450,000		Hanford procurement Not covered in SR
TC-25	DC decontamination tool	1	ea.	\$10,000	\$10,000	1	\$10,000	1	\$10,000	PD-DC-100	
Sub Total					\$10,465,000	Sub Total		\$10,465,000	Sub Total		\$10,465,000
Total Cost Modules #1,2,3										\$31,395,000	

DC LOAD CELL		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
DC-1	Load port mating device	2	ea.	\$75,000	\$150,000	2	\$150,000	2	\$150,000	PU-DE-111DC	
DC-2	Shield door	2	ea.	\$80,000	\$160,000	2	\$160,000	2	\$160,000	PD-DO-101	
DC-3	DC shielded cover handling device	2	ea.	\$50,000	\$100,000	2	\$100,000	2	\$100,000		
Sub Total					\$410,000	Sub Total		\$410,000	Sub Total		\$410,000
Total Cost Modules #1,2,3										\$1,230,000	

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-15. WHB Equipment List, continued
Turntable Design Alternative

DC HANDLING AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
DCH-1	DC handling crane (55' span, 200 ton)	2	ea.	\$2,000,000	\$4,000,000	0	\$0	0	\$0	PH-CN-100	
DCH-2	Lifting yoke	1	ea.	\$200,000	\$200,000	0	\$0	0	\$0	PU-FX-100	
DCH-3	DC prime mover	2	ea.	\$50,000	\$100,000	0	\$0	0	\$0	Eng. Judgement	
DCH-4	DC transfer cart	15	ea.	\$200,000	\$3,000,000	7	\$1,400,000	0	\$0	PU-CR-112	
DCH-5	DC turntable/cart	11	ea.	\$900,000	\$9,900,000	6	\$5,400,000	0	\$0	PU-CR-112 & vendor estimate (Motion Index Drives Inc.)	
					Sub Total	\$17,200,000	Sub Total	\$6,800,000	Sub Total	\$0	
										Total Cost Modules #1,2,3	\$24,000,000

WELD AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
WA-1	Bridge mounted manipulator	11	ea.	\$2,000,000	\$22,000,000	6	\$12,000,000	0	\$0	PD-CN-100	
WA-2	Lid lifting system	11	ea.	\$300,000	\$3,300,000	6	\$1,800,000	0	\$0	PD-FX-102	
WA-3	Welding/treatment/inspection system	11	ea.	\$2,500,000	\$27,500,000	6	\$15,000,000	0	\$0	PD-ME-101A-H	
WA-4	Steel shield door (1' x 12' w x 12' h)	17	ea.	\$180,000	\$3,060,000	0	\$0	0	\$0	Eng. Judgement	
WA-5	Isolation door (16' x 24')	17	ea.	\$10,000	\$170,000	0	\$0	0	\$0	PC-DO-110	
WA-6	Retractable port shield plug	11	ea.	\$30,000	\$330,000	6	\$180,000	0	\$0	PU-HA-112	
WA-7	Swipe pass-through	17	ea.	\$12,000	\$204,000	0	\$0	0	\$0	PD-FT-100	
					Sub Total	\$56,564,000	Sub Total	\$28,980,000	Sub Total	\$0	
										Total Cost Modules #1,2,3	\$85,544,000

WELD MAINTENANCE AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
WMA-1	Miscellaneous tools (set)	2	lot	\$10,000	\$20,000	1	\$10,000	0	\$0	Eng. Judgement	
WMA-2	Forklift	2	ea.	\$45,000	\$90,000	1	\$45,000	0	\$0	Eng. Judgement	
					Sub Total	\$110,000	Sub Total	\$55,000	Sub Total	\$0	
										Total Cost Modules #1,2,3	\$165,000

WP REMEDIATION CELL		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
WPR-1	Bridge mounted manipulator	1	ea.	\$800,000	\$800,000	0	\$0	0	\$0	PR-EM-100	w/ 8 ton hoist
WPR-2	Bridge mounted cutting machine	1	ea.	\$800,000	\$800,000	0	\$0	0	\$0	PR-ME-100	
WPR-3	Decontamination device	1	ea.	\$10,000	\$10,000	0	\$0	0	\$0	PR-DC-100	
WPR-4	Shield door (2' l x 13' w x 24h)	1	ea.	\$315,000	\$315,000	0	\$0	0	\$0	PR-DO-100	
WPR-5	Shield window	4	ea.	\$325,000	\$1,300,000	0	\$0	0	\$0	PC-WO-111 (similar)	
					Sub Total	\$3,025,000	Sub Total	\$0	Sub Total	\$0	
										Total Cost Modules #1,2,3	\$3,025,000

Waste Handling Building Conceptual Study
Appendix F: Cost Estimate

Table F-15. WHB Equipment List, continued
Turntable Design Alternative

WP TRANSPORTER LOAD CELL		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
WPC-1	Bridge crane (200 ton, 36' span)	1	ea.	\$2,000,000	\$2,000,000	0	\$0	0	\$0	PH-CN-100	
WPC-2	Waste package lifting yoke (adjustable)	1	ea.	\$175,000	\$175,000	0	\$0	0	\$0	PU-FX-100	
WPC-3	Waste package lifting fixture	1	ea.	\$50,000	\$50,000	0	\$0	0	\$0	PD-FX-103	
WPC-4	Waste package/overpack horizontal lifting fixture	1	ea.	\$1,100,000	\$1,100,000	0	\$0	0	\$0	PD-MA-100	
WPC-5	Weld-mounted manipulator	2	ea.	\$700,000	\$1,400,000	0	\$0	0	\$0	SR dry option	
WPC-6	Shield window	6	ea.	\$325,000	\$1,950,000	0	\$0	0	\$0	PC-WO-111	
WPC-7	Crane maintenance isolation door (35' x 20')	1	ea.	\$45,000	\$45,000	0	\$0	0	\$0	PC-DO-114	
WPC-8	Steel shield door (15' X 16' x 1')	1	ea.	\$320,000	\$320,000	0	\$0	0	\$0	Eng. Judgement	
WPC-9	Steel shield door (16' X 16' x 0.25')	1	ea.	\$80,000	\$80,000	0	\$0	0	\$0	Eng. Judgement	
WPC-10	Shield cover lifting grapple	1	ea.	\$275,000	\$275,000	0	\$0	0	\$0	PU-DE-116	
				Sub Total	\$7,395,000	Sub Total	\$0	Sub Total	\$0		

EMPTY DC PREPARATION AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
EDP-1	Preparation bridge crane	1	ea.	\$1,200,000	\$1,200,000	0	\$0	0	\$0	PD-CN-104	
EDP-2	Lifting yoke	1	ea.	\$73,000	\$73,000	0	\$0	0	\$0	PD-FX-104	
EDP-3	Lifting beam	1	ea.	\$10,000	\$10,000	0	\$0	0	\$0	PD-FX-105	
EDP-4	Tilting fixture	1	ea.	\$10,000	\$10,000	0	\$0	0	\$0	PD-FX-106	
EDP-5	Support saddle system	1	ea.	\$5,000	\$5,000	0	\$0	0	\$0	PD-FX-102	
EDP-6	Shield cover lifting adapter	1	ea.	\$10,000	\$10,000	0	\$0	0	\$0	Eng. Judgement	
EDP-7	Forklift	1	ea.	\$45,000	\$45,000	0	\$0	0	\$0		
EDP-8	Mobile access platform	1	ea.	\$5,000	\$5,000	0	\$0	0	\$0	Eng. Judgement	
EDP-9	DC shielded overpack (3 sizes)	36	ea.	\$512,000	\$18,432,000	6	\$3,072,000	0	\$0		For use in WHB only. Doesn't include dry storage overpacks.
EDP-10	DC shielded overpack cover (3 sizes)	36	ea.	\$20,000	\$720,000	6	\$120,000	0	\$0		For use in WHB only. Doesn't
EDP-11	DC adapter ring (various sizes)	36	ea.	\$10,000	\$360,000	6	\$60,000	0	\$0	Eng. Judgement	
EDP-12	DC loading port adapter (2 sizes)	11	ea.	\$10,000	\$110,000	6	\$60,000	0	\$0		
				Sub Total	\$20,980,000	Sub Total	\$3,312,000	Sub Total	\$0		
							Total Cost Modules #1,2,3			\$24,292,000	

TRANSPORTER LOAD BAY		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
TLB-1	Isolation door (20 H x 18 W)	2	ea.	\$6,000	\$12,000	0	\$0	0	\$0	PC-DO-111	
TLB-2	Motorized cask transporter (crawler) 150 ton	1	ea.	\$800,000	\$800,000	0	\$0	0	\$0	Vendor quote (4 Point Lift Syst. Inc)	Seismic design
				Sub Total	\$812,000	Sub Total		\$0	Sub Total	\$0	
						Total Cost Modules #1,2,3			\$812,000		

FUEL STAGING AREA		Module #1				Module #2		Module #3		Reference	Notes
Equip. No.	Equipment Description	Qty	Unit	Unit Cost	Total Cost	Qty	Total Cost	Qty	Total Cost		
FAI-1	Storage cask	48	ea.	\$800,000	\$38,400,000	49	\$39,200,000	388	\$310,400,000	D. Zabransky	Total of 485 casks

Table F-15. WHB Equipment List, continued
Turntable Design Alternative

\$ 38,400,000	\$ 39,200,000	\$ 310,400,000
<u>Total Cost Modules #1,2,3</u>		<u>\$388,000,000</u>
<u>TOTAL</u>		<u>\$696,163,000</u>